

of America

Congressional Record

Proceedings and debates of the 111^{th} congress, first session

Vol. 155

WASHINGTON, FRIDAY, JUNE 26, 2009

No. 98

Senate

The Senate was not in session today. Its next meeting will be held on Monday, July 6, 2009, at 2 p.m.

House of Representatives

FRIDAY, JUNE 26, 2009

The House met at 9 a.m. and was called to order by the Speaker.

The Chaplain, the Reverend Daniel P. Coughlin, offered the following prayer:

Lord God, You hold all in good order

Lord God, You hold all in good order, yet You give us the freedom of choice in the realm of good conscience.

It seems You achieve Your own good purposes in and through Your people, whether or not they know Your guidance or wait to learn from their own mistakes.

Be with all Your people today in the decisions they make as a free people. Provide them with insight on how to use their many blessings.

Even though You guide them by Your Spirit, hold them accountable for their deeds before Your divine tribunal and in the realm of democratic forum and public opinion.

By personal integrity and right judgment, help all Americans to establish credence before other nations, so that seeing our good deeds may they glorify You, our God, as our protector and guide, now and forever. Amen.

THE JOURNAL

The SPEAKER. The Chair has examined the Journal of the last day's proceedings and announces to the House her approval thereof.

Pursuant to clause 1, rule I, the Journal stands approved.

Mr. MURPHY of Connecticut. Madam Speaker, pursuant to clause 1, rule I, I demand a vote on agreeing to the Speaker's approval of the Journal.

The SPEAKER. The question is on the Speaker's approval of the Journal.

The question was taken; and the Speaker announced that the ayes appeared to have it.

Mr. MURPHY of Connecticut. Madam Speaker, I object to the vote on the ground that a quorum is not present and make the point of order that a quorum is not present.

The SPEAKER. Pursuant to clause 8, rule XX, further proceedings on this question will be postponed.

The point of no quorum is considered withdrawn.

PLEDGE OF ALLEGIANCE

The SPEAKER. Will the gentle-woman from Hawaii (Ms. HIRONO) come forward and lead the House in the Pledge of Allegiance.

Ms. HIRONO led the Pledge of Allegiance as follows:

I pledge allegiance to the Flag of the United States of America, and to the Republic for which it stands, one nation under God, indivisible, with liberty and justice for all.

ANNOUNCEMENT BY THE SPEAKER

The SPEAKER. The Chair will entertain up to five requests for 1-minute speeches on each side of the aisle.

PROVIDING A TRUE DECLARATION OF ENERGY INDEPENDENCE

(Mr. KUCINICH asked and was given permission to address the House for 1 minute.)

Mr. KUCINICH. Millions of Americans have been and are under the threat of violent weather changes,

floods, droughts, scorching heat, extraordinary cold, and food insecurity. We are running out of time to craft practicable, workable solutions to moderate the effects of global climate change brought on by global greenhouse gasses.

We are past the tipping point, and instead of talking about saving ourselves, we are talking about saving the coal industry. Our first steps on the path to a clean energy future will leave footprints caked in coal, because under the bill, U.S. fossil fuel emissions aren't required to fall until 2030. The bill will facilitate the licensing of 25 new coal-fired plants with free permits to pollute. It guarantee coal's future by spending \$60 billion on an unproven, leaky technology where CO_2 is pumped into the ground.

We can still save ourselves and our planet, or we can save the coal industry. We can have a carbon-free and nuclear-free world which comes into harmony with nature's god through the creation of tens of millions of new wind and solar microtechnologies which will lower energy costs and make for a true declaration of energy independence. I will soon be introducing a bill to accomplish just that.


The American people are waiting to be inspired with a vision and a reality of a green future.

CAP-AND-TRADE TAXES AMERICAN FAMILIES

(Mr. WILSON of South Carolina asked and was given permission to address the House for 1 minute.)

 \Box This symbol represents the time of day during the House proceedings, e.g., \Box 1407 is 2:07 p.m.

Matter set in this typeface indicates words inserted or appended, rather than spoken, by a Member of the House on the floor.



Mr. WILSON of South Carolina. Madam Speaker, President Obama has stated that cap-and-trade would cause electric bills to skyrocket, which forces families to pay more. He also declared yesterday that cap-and-trade would only be paid for by polluters. The President seems to imply through his statements that American families and small businesses, those who will see their electric bills skyrocket, are the polluters who should pay for this legislation.

I disagree. Families, farmers, manufacturers and small businesses across America do not deserve this national energy tax. We do not need to threaten the financial well-being of American citizens or the competitiveness of American businesses in a global economy.

House Republicans have consistently offered an all-of-the-above energy plan that will invest in exploration, in new alternative energy resources, and promote conservation. Our strategy is built on the American spirit of ingenuity, not an oppressive policy of higher taxes and job losses.

In conclusion, God bless our troops, we will never forget September 11th in the global war on terrorism, and also I would like to extend my congratulations to Congresswoman ELLEN TAUSCHER on her confirmation yesterday evening to serve in the State Department of the United States.

RECOGNIZING NEDA AGHA-SOLTAN

(Ms. HIRONO asked and was given permission to address the House for 1 minute.)

Ms. HIRONO. Madam Speaker, today I would like to recognize Neda Agha-Soltan, this brave young woman who was shot and killed while en route to join the thousands of Iranians in Tehran who were demonstrating against the Presidential election result.

Neda, whose name means "the voice" in Farsi, was but one of the many women in Iran demanding that their voices be heard and that their votes be counted and their human rights respected.

Like many other Americans and people from around the world, I have been deeply moved by the images of Iranian women who have had the courage to speak their minds in defiance of a regime that seeks to suppress them.

I ask my colleagues to join me in honoring the memory of Neda and in supporting all of the courageous women in Iran who are raising their voices and fighting for the fundamental freedoms and human rights that we so often take for granted.

VOTE NO ON CAP-AND-TRADE BILL

(Mr. SHIMKUS asked and was given permission to address the House for 1 minute and to revise and extend his remarks.)

Mr. SHIMKUS. Madam Speaker, here it is, 1,090 pages. If we pass this bill, we

get this—unemployed miners. In fact, the last time, 35,000 miners lost their jobs. If we pass the Republican alternative we get jobs, offshore drilling, fuel from coal, wind and solar, renewable fuels.

I have an e-mail from eight rural electric co-ops in my district which I include for the RECORD. All say vote no.

I just got a voicemail from several Coops on one call. Jim Riddle, with Egyptian Electric Coop, Larry Level with Southern Illinois Electric Coop, Allen Waddle with Monroe County Coop, Ralph Cool with Clinton County Coop in Breeze, Scott Ramsey with Southern Illinois Power Coop in Marion, as well as Tri-County Coop in Mt. Vernon, Southeastern Coop in Eldorado, and Clay County Electric in Flora. They first wanted to thank you for your position on Climate Change and they all agree with you. Second they wanted to make sure you knew they are opposed that NRECA has taken "no position" on the bill and want to urge you to vote against the bill.

Do not believe the National Association.

VOTE NO ON CURRENT CAP-AND-TRADE BILL

(Mr. DEFAZIO asked and was given permission to address the House for 1 minute.)

Mr. DEFAZIO. Madam Speaker, unlike his predecessor, President Obama recognizes that greenhouse gasses and climate change are a real problem and must be dealt with, and in the tradition of the hugely successful Clean Water Act and Clean Air Act, he has ordered his Environmental Protection Agency to develop rules to cap and reduce greenhouse gasses.

This bill today actually prohibits the EPA from continuing to develop rules to regulate greenhouse gasses in the tradition of the Clean Water Act and the Clean Air Act. Instead, it turns to a market-based approach. Instead of a firm cap, regulating and reducing, this bill turns us to carbon offset derivative futures that will be insured by credit default swaps.

How quickly they forget Wall Street and AIG and the damage they wrought in the financial sector. This, Wall Street predicts, is the new \$1 trillion market. The market manipulators of Enron Corporation may have bankrupted their company, Ken Lay may be gone, but their spirit is fully embodied in this legislation.

HONORING MARTIN ROENIGK FOR HIS GENEROUS CONTRIBUTIONS TO THE COMMUNITY

(Mr. BOOZMAN asked and was given permission to address the House for 1 minute and to revise and extend his remarks.)

Mr. BOOZMAN. Madam Speaker, I rise today to honor the life of Martin Roenigk, a gracious contributor to the Third District of Arkansas, who unexpectedly passed away last week.

Marty was a philanthropist, a preservationist, and, above all else, a friend

to all who knew him. He spent the last 12 years as an Arkansan, and although he was a relatively new resident, you could never tell because of his compassion for the community.

Marty has been described as a visionary, and traveling in northwest Arkansas you can see that vision come alive. His love of historic preservation transformed Eureka Springs. In 1997, Marty and his wife bought the 1905 Basin Park Hotel and then the 1886 Crescent Hotel and Spa. The Roenigks restored these historic hotels and helped revitalize tourism to this town. The Roenigks then purchased the War Eagle Mill and were instrumental in preserving the War Eagle Bridge.

Madam Speaker, Marty will certainly be missed. However, his legacy will live on for generations to come because of his generosity. I ask my colleagues to keep Marty's family and friends in their thoughts and prayers during these difficult times.

ENERGY BILL FINE PRINT BETRAYS LAUDABLE PURPOSE

(Mr. DOGGETT asked and was given permission to address the House for 1 minute.)

Mr. DOGGETT. Madam Speaker, this energy bill's fine print betrays its laudable purpose. The real cap is on the public interest, and the trade is from the public to polluters. It is too weak to spur new technologies and green jobs.

An Administration analysis shows that doing nothing actually results in more new renewable energy electricity generation capacity than approving this bill.

Vital authority for the EPA is stripped, but two billion additional tons of pollution are authorized every year forever. Residential consumer protection is incredibly entrusted to the mercy of utility companies. Exempting 100 new coal plants and paying billions to Old King Coal does indeed leave him "a merry old soul."

This bill is 85 percent different from what President Obama proposed just a few months ago. No wonder that his Budget Director called this type of legislation "the largest corporate welfare program . . . in the history of the United States."

Until greatly improved, until families share in the billions this bill grants powerful lobbies, I cannot support it.

□ 0915

AGRICULTURE NEGATIVELY IMPACTED

(Mr. SMITH of Nebraska asked and was given permission to address the House for 1 minute and to revise and extend his remarks.)

Mr. SMITH of Nebraska. Madam Speaker, I rise in opposition to the capand-trade bill we will be taking up shortly.

Agriculture is one of the Nation's most energy-intensive industries and will be negatively impacted by this legislation. Even a small increase in operating costs could devastate rural farmers and ranchers, and this bill could prove to be a huge burden on our agricultural producers. U.S. farmers would also be at a severe disadvantage compared to farmers in nations which do not have cap-and-trade systems with the correspondingly high input costs.

Yesterday I offered an amendment which would have helped defray increased costs of production and declining prices resulting from increased imports or decreased exports.

It is simply not appropriate for allowances to be set aside for other industries heard by the cap-and-trade bill, but agriculture is left out.

PUBLIC HEALTH INSURANCE OPTION

(Mr. MURPHY of Connecticut asked and was given permission to address the House for 1 minute.)

Mr. MURPHY of Connecticut. Madam Speaker, I hope today we are going to pass a transformational climate bill that will not only grow jobs in this country but will make us truly energy independent.

And when we get back from our break, it is time to turn our attention to health care. There is a lot of controversy around these issues, but out in the American public, there is no controversy over their desire to see a public insurance option be part of health care reform: 69 percent support in a recent Kaiser Foundation poll; 72 percent in a CBS/New York Times poll; 76 percent by NBC and Wall Street Journal. And it is nonpartisan: 50 percent of Republicans support it, over 80 percent of Demograts

There might be a lot of controversy on the issue of energy or health care, but on the issue of whether or not Americans want a public option on their table as part of health care reform, the jury has decided.

DRIVING UP PRICES

(Mr. DUNCAN asked and was given permission to address the House for 1 minute and to revise and extend his remarks.)

Mr. DUNCAN. Madam Speaker, I have noticed that most environmental radicals come from very wealthy or very upper-income families. Perhaps they do not realize how much they have hurt the poor and the lower income and the working people by destroying jobs and driving up prices.

Now, those who seem to be the loudest in saying they are for the little guy are about to pass a bill that is going to hurt the little guy most of all. This cap-and-trade bill is going to drive up prices for gas, utilities, and especially costs for small businesses and farms. Businesses in China and India will probably jump for joy because this will give them even greater advantages.

And college graduates all over this country wonder why they cannot find good jobs and have to keep working as waiters and waitresses because this bill will drive even more jobs to other countries.

I hope everyone who is undecided on this bill will vote for the little guy instead of the big money environmental groups and the very big businesses which will benefit from this very costly bill.

RESIGNATION AS MEMBER OF COMMITTEE ON TRANSPORTATION AND INFRASTRUCTURE

The SPEAKER pro tempore (Ms. HIRONO) laid before the House the following resignation as a member of the Committee on Transportation and Infrastructure:

CONGRESS OF THE UNITED STATES, HOUSE OF REPRESENTATIVES, Washington, DC, June 26, 2009.

Hon. NANCY PELOSI.

Speaker of the House, U.S. Capitol, Washington, DC.

DEAR SPEAKER PELOSI: Given my nomination by the President as Undersecretary of State for Arms Control and International Security, this letter serves as my intent to resign from the Committee on Transportation and Infrastructure, effective today.

Sincerely.

ELLEN O. TAUSCHER,

Member of Congress.

The SPEAKER pro tempore. Without objection, the resignation is accepted. There was no objection.

PROVIDING FOR CONSIDERATION OF H.R. 2454, AMERICAN CLEAN ENERGY AND SECURITY ACT OF 2000

Ms. MATSUI. Madam Speaker, by direction of the Committee on Rules, I call up House Resolution 587 and ask for its immediate consideration.

The Clerk read the resolution, as follows:

H. RES. 587

Resolved, That upon the adoption of this resolution it shall be in order to consider in the House the bill (H.R. 2454) to create clean energy jobs, achieve energy independence. reduce global warming pollution and transition to a clean energy economy. All points of order against consideration of the bill are waived except those arising under clause 9 or 10 of rule XXI. In lieu of the amendment recommended by the Committee on Energy and Commerce now printed in the bill, an amendment in the nature of a substitute consisting of the text of H.R. 2998, modified by the amendment printed in part A of the report of the Committee on Rules accompanying this resolution, shall be considered as adopted. The bill, as amended, shall be considered as read. All points of order against provisions of the bill, as amended, are waived. The previous question shall be considered as ordered on the bill, as amended, and on any further amendment thereto, to final passage without intervening motion except: (1) three hours of debate, with two and one half hours equally divided and controlled by the chair and ranking minority member of the Committee on Energy and Commerce and 30 minutes equally divided and controlled by the chair and ranking minority member of the Committee on Ways and Means; (2) the further amendment in the nature of a substitute printed in part B of the report of the Committee on Rules, if offered by Representative Forbes of Virginia or his designee, which shall be in order without intervention of any point of order except those arising under clause 9 or 10 of rule XXI, shall be considered as read, and shall be separately debatable for 30 minutes equally divided and controlled by the proponent and an opponent; and (3) one motion to recommit with or without instructions.

The SPEAKER pro tempore (Mrs. TAUSCHER). The gentlewoman from California (Ms. MATSUI) is recognized for 1 hour.

Ms. MATSUI. For the purpose of debate only, I yield the customary 30 minutes to the gentleman from Texas (Mr. Sessions). All time yielded during consideration of the rule is for debate only.

GENERAL LEAVE

Ms. MATSUI. I ask unanimous consent that all Members may have 5 legislative days within which to revise and extend their remarks and to insert extraneous materials into the record.

The SPEAKER pro tempore. Is there objection to the request of the gentle-woman from California?

There was no objection.

Ms. MATSUI. Madam Speaker, before I begin my remarks, I would like to speak briefly about all that the Speaker has meant to this body.

Since coming to Congress, I have watched ELLEN TAUSCHER navigate the legislative and political waters of the House of Representatives. She has always done so with uncommon grace, skill and acumen which we would all be well served to emulate.

We will all miss her presence here in this Chamber, whether in the chair or on the floor. But we know that she will continue to serve our country well in her new capacity as Under Secretary for Arms Control and International Security at the State Department.

Madam Speaker, H. Res. 587 provides a structured rule for consideration of H.R. 2454, the American Clean Energy and Security Act. The resolution provides for 3 hours of general debate with 2½ hours controlled by the Committee on Energy and Commerce and 30 minutes controlled by the Committee on Ways and Means.

Madam Speaker, from coast to coast we are seeing the effects of our changing climate. Just last week, experts from 13 government agencies and several universities issued a new report on global climate change impacts in the United States. Their analysis was clear: global warming is caused by human-induced emissions.

It is also already having visible impacts in the United States. We are seeing these effects throughout our country, from increases in heavy storms to rising sea levels. From earlier snow melt to alterations in river flows. These experts concluded that negative effects of climate change will continue to worsen.

Climate change will combine with other air pollution, population growth, overuse of resources, and social, economic, and environmental stresses to create larger impacts that will be felt around the world and here at home. For my constituents, this threat is very real and very urgent.

California's Department of Water Resources projects that the Sierra Nevada snow pack will experience a 25 to 40 percent reduction by 2050. These are not empty numbers. As California's climate warms, more of the Sierra Nevada's watershed will continue to peak storm runoff. High-frequency flood events are projected to increase as a result. We have no choice but to adapt to these changing realities.

In Sacramento, we live at the confluence of two great rivers, the Sacramento and the American. As global warming intensifies, scientists predict greater storm intensity that could forever change these rivers' flow patterns. This means that my district will have to cope with more direct runoff and more flooding.

I want to thank Chairman WAXMAN and Chairman MARKEY for working with me to ensure that this bill addresses California's water needs in the context of climate change. Allowances are distributed to States for urgent projects to help fight extreme weather and flooding. These resources are vital as we work to adapt to changing climates and more intense weather patterns.

In order to deal with these issues and with others that confront us all, the Energy and Commerce Committee has held countless hearings on energy and climate change policy over the past 2½ years. This year alone we have convened over a dozen hearings and heard from numerous experts, as well as national and international leaders. In total, the committee has held over 40 days of hearings on energy and climate change policy over the past two Congresses. During these deliberations, over 300 witnesses testified, including 130 in this year alone.

Whether or not we all agree with Chairman WAXMAN and Chairman MARKEY on the issue of global warming, and I personally do, we should all applaud the work these two chairmen have done to get us here today.

This bill is not only an achievement for the American people but also for our children and our grandchildren. By spurring a new era of clean energy jobs, this bill puts our economy on a new trajectory. And because of this investment, our children and grandchildren will live in a country that is more sustainable, more economically viable, and more efficient than the country we live in today.

The legislation will create millions of new clean energy jobs, enhance America's energy independence, and protect the environment. Specifically, it requires electric utilities to meet 20 percent of the electricity demand through renewable and energy sources and energy efficiency by 2020.

It also invests in new clean energy technologies and energy efficiencies, including energy efficiency and renewable energy carbon capture and sequestration, and basic scientific research and development.

It mandates new energy-saving standards for buildings, appliances, and industry, and it reduces carbon emissions from major U.S. sources by 17 percent by 2020 and over 80 percent by 2050. These are the nationwide impacts of this groundbreaking legislation.

Part of the brilliance of this bill before us today, though, is that it also gives tools to local communities to fight climate change on their own. One of the ways this bill does so is through the transportation sector. Transportation accounts for 30 percent of the greenhouse gases emitted into the atmosphere each year. Therefore, effective climate change legislation must include a transportation component if we are going to achieve the emission reduction levels that scientists say are vital to saving our planet.

I appreciated working with the committee on section 222, which seeks to reduce greenhouse gas emissions through comprehensive transportation efficiency and land use planning. The way we plan our communities and transportation systems has a real effect on how well we reduce emissions from transportation. This legislation also protects consumers from energy price increases.

According to estimates from the EPA, the reductions in carbon pollution required by the legislation will cost American families only 22 to 30 cents per day. But fighting global warming is not just about preserving our current way of life; it is also about creating a cleaner, stronger economy that will power the United States toward a clean energy future.

EPA analysis shows that the Nation's gross domestic product would grow from \$13 trillion in 2008 to over \$22 trillion in 2030 while deploying clean energy technology and reducing global warming pollution. And consumption, an economic measure of a household's purchasing potential, would grow by 8 to 10 percent from 2010 to 2015, and 23 percent to 28 percent by 2030.

With the American Clean Energy and Security Act, we are making smart investments. We are giving entrepreneurs the tools they need to create clean energy jobs that demand American skills and that put our country in a strong position to compete internationally.

Madam Speaker, with the American Clean Energy and Security Act, we will show the rest of the world that America is back and we are ready to lead again.

I reserve the balance of my time.

□ 0930

Mr. SESSIONS. Madam Speaker, I would like to, on behalf of my Republican colleagues, congratulate you for your wonderful new responsibilities that you will have at the State Department, and congratulations on your Senate confirmation yesterday.

Mr. UPTON. Would the gentleman yield?

Mr. SESSIONS. I would yield to the gentleman.

Mr. UPTON. I, too, extend my congratulations, as I understand it, in charge of arms control. And I think this is a particularly worthy day that you have this job still, as a Member of Congress, until the end of the day, because you're going to need to repair a lot of arms on that side of the aisle after this vote is over.

Mr. SESSIONS. Reclaiming my time, and I thank the gentleman, but congratulations very much, Ellen.

At the very top, Madam Speaker, I would like to ask unanimous consent to the gentlewoman from California if we could extend the time of debate. I am inundated with the amount of requests and would like to ask that we extend it 30 minutes, extending both sides an additional 15 minutes.

The SPEAKER pro tempore. Is there objection to the request of the gentleman from Texas?

Ms. MATSUI. No, we will not agree to that. We object.

The SPEAKER pro tempore. The objection is heard.

Mr. SESSIONS. You do object. I would like to ask the gentlewoman if we could extend the time on both sides by 5 minutes then.

Ms. MATSUI. We object. There are 3 hours on the bill.

Mr. SESSIONS. I would like to see if we could extend by 1 minute this debate on both sides.

Ms. MATSUI. We object.

Mr. SESSIONS. You object. Okay.

Madam Speaker, good morning. I yield myself such time as I may consume. And I appreciate the gentlewoman extending me these few minutes that she has given us to debate this very important bill.

I rise in opposition to this lockdown rule and the underlying legislation which, if passed, The Wall Street Journal correctly notes will become the "biggest tax in American history."

After limited committee hearings and only one markup on this 1,200-plus page bill, the negotiations that have brought this bill to the floor have completely excluded Republicans and ignored our good ideas on how to stop the most economically devastating and job-killing parts of this bill.

For example, during the bill's brief deliberation in committee, Republicans offered three commonsense amendments, one to suspend the program if gas prices hit \$5 a gallon, one to suspend the program if electricity prices rise 10 percent over 2009, and one to suspend the program if unemployment rates hit 15 percent. But, unfortunately, the committee's Democrats defeated them all.

To make matters worse, for the past 2 weeks, despite numerous contrary promises to our Democrat colleagues and to the American people, Speaker Pelosi and her handpicked lieutenants on the Rules Committee have limited

open debate and, once again here on the floor, debate to talk about this unprecedented bill that is before the American people.

While this behavior is undemocratic and mildly irritating when dealing with bills like Federal Employees Paid Parental Leave Act of 2009, it is simply unacceptable when it comes to legislation of such great importance to the future of American jobs and families.

So once again, early this morning in the Rules Committee, after—and by the way, that was about 2–3:30 this morning—after being handed a brandnew 309-page revision of the bill, this unacceptable behavior continued.

My Republican colleagues and I offered numerous good ideas and improvements to this brand-new bill this morning, which not one Member has even read. As a matter of fact, we even joked about that as we walked in at 2 o'clock this morning about, sure everybody had a chance to read the bill. that's why we were up so late last night. This legislation that Republicans proposed would have provided commonsense relief for farmers and small businesses that drive our economy. Unsurprisingly, each of these good ideas was rejected by our Democrat colleagues along party lines.

Whether or not to impose the biggest tax increase in American history is a very serious issue, and one that affects every American family, legislation that the Heritage Foundation estimates will cost working families in the 32nd Congressional District of Texas, just one district which I happen to represent, some 4,178 jobs in 2012. We believe that this bill should actually be debated and openly read so that everyone doesn't just rush through this day but, rather, understands the true impact of what we're doing.

The rule being proposed here today is a grave mistake and an undemocratic embarrassment. And I, for one, think this body can do better. We owe it to the American people to allow Members, Members of this body on both sides, who have good ideas to be heard, especially the ideas to address the needs of rural and working class people who will see their incomes and choices slashed by this bill.

Instead of an inclusive debate on how to conserve our resources and provide clean, affordable energy for American businesses and families, the Democrats' answer to the worst recession in decades is a national energy tax, thinly disguised as a climate change bill.

Billions of dollars wasted on extra energy costs and millions of jobs lost is an extremely high price to pay for a bill that is estimated, at best, to slow the Earth's temperature rises by one-hundredth of a single degree by 2050, and no more than two-tenths of a degree by the end of this century.

Madam Speaker, the facts are clear: Nancy Pelosi's national energy tax will kill American jobs, it will raise prices on hardworking Americans, and do almost nothing to clean up our environment. But the American people watching today's debate don't need to take my word for it. President Obama and his senior administration officials, and many prominent Democrats, agree that cap-and-trade is actually cap-and-tax.

In January of 2008, President Obama told the San Francisco Chronicle that under his preferred cap-and-trade system electricity rates would necessarily skyrocket. Then on February 26, 2009, the President's own budget estimates that the climate revenue generated by this legislation to pay for Washington bureaucrat-run health care and a jobless stimulus package would cost American manufacturers and energy producers \$646 billion over 10 years. Three weeks later, the administration's top economic advisers disagreed with this lowball figure, suggesting that cap-and-trade could actually cost up to \$1.9 trillion over 10 years.

Next, former Energy and Commerce Committee Chairman, JOHN DINGELL, stated in a hearing on cap-and-trade: "Nobody in this country realizes that cap-and-trade is a tax, and it's a big one."

As recently as this week, Congressman Gene Green of Texas stated in an op-ed: "Instituting a cap on nationwide greenhouse emissions will raise the price of energy for consumers and businesses alike."

Madam Speaker, I'm confused. Why on this Earth would my friends on your side of the aisle create such a big tax on all American families and businesses during a time that a recession is so serious? Why are we rushing to do this with a \$1 trillion spending plan that will have such a large impact on the American people, killing jobs and making it more difficult for us to come out of this recession?

On June 15, I received a letter from the Texas Comptroller of Public Accounts stating that the current plan to implement mandatory mission caps would weigh far more heavily on Texas than any other region in the country. It goes on to note that "based on rising fuel prices as a result of the cap-and-trade provisions of this bill, Texas could see 135,000 to 277,000 fewer jobs in 2012, the first year of the bill."

Madam Speaker, Texas leads this country in jobs, and people are coming to Texas from all over the United States just to have jobs. Why would we go and diminish the opportunities for people to find those jobs that were available to help their families?

Madam Speaker, families all over Texas are already hurting; and with all the other troubles plaguing the economy, they simply cannot afford the additional and completely avoidable economic assault that the new Democrat majority is placing on the American people.

Perhaps worst of all, Madam Speaker, the economic damage created by this legislation actually favors foreign companies over American ones. China, the number one emitter of greenhouse gases, and India, who is set to expand

its emissions, will not be required to modify their behavior at all. That means that this new Democrat majority is taking the astonishing position of asking American small businesses and consumers to carry the global load for the world's carbon consumption because, as everyone understands, if only Americans tax their manufacturing and productions, then only Americans will be losing out while China, India and other countries gain an advantage over our domestic manufacturers, businesses, jobs and future.

Every Member of this Chamber understands that in an era of rising energy costs, Congress must and should be doing everything in its power to ensure that domestic production of clean energy is available at the cheapest price. However, I recently received a letter from the American Petroleum Institute expressing concern that this legislation could add as much as 77 cents to each gallon of gasoline.

Very simply, this legislation means that every American business and consumer will pay more to fuel their vehicles, heat their homes, and purchase everyday goods.

The facts are clear: NANCY PELOSI'S national energy tax will kill American jobs, will raise prices on hardworking Americans, and do little to clean up our environment.

I encourage a "no" vote on this lockdown rule and a "no" vote on the underlying legislation.

Madam Speaker, I reserve the balance of my time.

Ms. MATSUI. Madam Speaker, I yield 2 minutes to the gentleman from Massachusetts, a member of the Rules Committee, my colleague, Mr. McGov-ERN.

Mr. McGOVERN. I thank the gentlelady from California for yielding to me. Madam Speaker, I stand here today in support of this rule and in support of the underlying legislation.

I want to thank Speaker Pelosi, Leader Hoyer, Chairman Waxman, and my Massachusetts colleague, ED Mar-KEY, for crafting and shepherding through this tremendously important legislation.

This bill will reduce the release of greenhouse gases into our atmosphere, reduce global warming, and concurrently will spur the creation of millions of clean-energy jobs in the United States.

Specifically, I would like to thank the chairman for including funding for domestic and international adaptation and clean technology transfer. While I supported greater dedication for adaptation funding, this represents a necessary first step in U.S. commitment.

By dedicating a portion of the allowances to international adaptation financing, we can ensure that those poorest of countries who have already been and will continue to be disproportionately impacted by climate change will receive crucial funding to help them save their farmlands, sources of water, and oftentimes their homes.

As a co-Chair of the Congressional Hunger Caucus, I am particularly concerned with the impacts of climate change upon the hungriest in the world. By investing in sustaining agriculture technology and practices, adaptation financing will help in this fight to end hunger.

For many island nations and equatorial countries, the harmful impacts of climate change have already taken their toll. Sea level rise, caused by rising global temperature, has already fundamentally altered the geography of some nations.

Madam Speaker, to echo what Speaker Pelosi has emphasized consistently, there is a moral imperative to be good stewards of this Earth. And as we look toward the negotiations in Copenhagen this December, the world is looking for leadership from the United States for global solutions to this global problem. And by leading the way on clean-energy technology and services to help the poorest nations build resistance to climate change impacts, the U.S. will experience a boon in job creation and innovation. Solutions such as efficient water systems and irrigation technology can create jobs here while solving problems abroad.

The SPEAKER pro tempore. The gentleman's time has expired.

Ms. MATSUI. I yield the gentleman an additional 15 seconds.

Mr. McGOVERN. Devoting portions of revenues from a cap-and-trade system to investments in international adaptation to those countries most vulnerable is a clear signal to the world that the U.S. is ready to lead in combating global climate change.

I urge my colleagues to support the rule and the underlying legislation.

I would like to insert in the RECORD a column by Ken Hackett, the president of Catholic Relief Services, entitled, "Combat Hunger By Investing in Agricultural Development."

[From the Des Moines Register, May 29, 2009]

COMBAT HUNGER BY INVESTING IN AGRICULTURAL DEVELOPMENT

(By Ken Hackett)

The world is hungry.

The unprecedented global financial crisis is plummeting more people into poverty. Nearly 1 billion worldwide go hungry, according to the U.N. Food and Agriculture Organization. Our conscience tells us this is morally reprehensible; our intellect reminds us that hunger pangs can breed riots and civil unrest that jeopardize the peace for us all.

This human calamity—with far-reaching consequences—demands that we strategically and smartly retool our thinking on how to tackle the scourge of global hunger.

One place to begin is to increase our investment in all aspects of agricultural development, from seed to market. Despite the fact that the majority of poor people in the developing world live in rural areas and sustain themselves through farming, overall funding for agriculture has been declining for many years.

As clearly shown by the World Bank, agricultural productivity gains and innovation have been particularly low in Africa. This lack of investment has led to stagnating pro-

ductivity and missed opportunities to take advantage of improved technologies that enable farmers to grow more food, to process it and to sell it for the best price.

A modest investment in agriculture can pay major dividends, boosting the incomes of farm families and helping to lift them out of poverty. In Niger, where I just visited, Fatou Soumana for years sold her unprocessed sesame seeds for a pittance, barely making enough to feed her family. With some help provided by Catholic Relief Services, including training on how to save and invest and classes on how to process sesame seeds, she is now selling a refined oil for use in skincare products that is fetching top dollar.

Fatou has used her profits to buy a cell phone, six sheep and a refrigerator. The refrigerator helps her to store the ice cream she makes and sells on the side. Here is an example of the multiplier effect of this approach: awakening an entrepreneurial spirit.

We need to move toward more holistic approaches to rural development that reflect the needs of the poor themselves and build permanent solutions to end global hunger. These approaches are starting to take root among the world's poorest countries through the efforts of smart development-assistance programs.

The U.S. Government's Millennium Challenge Corp., for example, is investing in every facet of the agricultural value chain. Millennium Challenge grants are training farmers, including women who make up the majority of farmers throughout the developing world; building the roads and bridges they need to get their crops to market; and bolstering a sound policy environment that secures land rights for farmers or expands the financial services agribusinesses need to flourish. Innovative approaches like the sesame project in Niger are rather small, but Millennium Challenge grants can replicate them on a larger scale.

I applaud the Obama administration for the steps it has taken so far in the fight against global hunger and poverty, specifically in its commitment to increased funding for food security and for demonstrating its support of the Millennium Challenge Corp. in the proposed budget for the coming fiscal year. I urge the administration and Congress to continue America's commitment to assisting the world's poor in the face of fiscal stress and competing budget priorities.

To cure the malady of hunger, we must invest today in agriculture's long-term sustainability. We have smart models of development assistance that are working toward this goal for the world's poor. If we are truly committed to ending global hunger, we must deepen our support for the solutions these models are delivering.

Mr. SESSIONS. Madam Speaker, at this time, I would like to yield 3 minutes to the distinguished gentleman, the ranking member of Energy and Commerce from Ennis, Texas (Mr. BARTON).

(Mr. BARTON of Texas asked and was given permission to revise and extend his remarks.)

Mr. BARTON of Texas. I thank the distinguished member of the Rules Committee.

Madam Speaker, this is the most important economic bill before this House in the last 100 years, and we get, under this rule, 3½ hours of debate, equally divided. I can almost say we have debated ceremonial resolutions longer than this bill if this rule passes.

□ 0945

Let me give you just two or three reasons to vote against the rule. Four hundred pages of this bill have never been seen before. They were literally hot off the Xerox machine when they were handed into the Rules Committee at approximately sometime between 2 and 3 a.m. this morning. That's one reason to vote "no" on the rule.

Number two, there is a provision in this revised bill on derivatives that the chairman of the Ag Committee and the chairman of the Financial Services Committee have already said needs to be repealed. But they have agreed to let it be a part of today's package with the understanding that it will then be repealed later this summer. That's another reason to vote against the rule.

There are so many new provisions that have never been seen. Provisions that Chairman Peterson and Chairman Waxman negotiated on agriculture have never been the focus of a hearing or even a public debate. It is a debatable proposition whether the provisions that Chairman Peterson had negotiated have any value at all since the EPA Administrator still retains the ultimate authority under the bill to regulate any man-made greenhouse gas.

This bill needs to be pulled today. And if we vote against the rule, it will be. We need to go back, make sure that these new provisions are vetted in the committees and in public debate and then bring the revised bill to the floor sometime in July or September and have a week of debate on it with numerous amendments.

Two hundred amendments were presented to the Rules Committee last night. One was made in order, one of 224

This is a bad rule. It is a closed rule. This is a bad bill. It is the economic disaster bill for the United States of America if it were to pass.

The easiest thing to do is vote "no" on the rule and then let's do work together to come up with a more reasonable bill sometime this fall.

Ms. MATSUI. Madam Speaker, I yield 2 minutes to the gentlewoman from Nevada, a member of the Transportation and Infrastructure Committee and Education and Labor Committee (Ms. TITUS).

Ms. TITUS. Madam Speaker, I rise in strong support of the Titus-Giffords-Heinrich amendment, which the manager's amendment incorporates into the American Clean Energy and Security Act.

Our amendment will create clean-energy jobs, promote deployment of renewable energy technology, and put the Federal Government in a position to lead by example. Our amendment extends the limit for the Federal Government to 20 years on a contract for the acquisition of electricity generated from a renewable energy resource, often referred to as a power purchase agreement. This provision will encourage wide-scale deployment of renewable energy technology at Federal buildings, BLM land, and Superfund sites. Additionally, it will allow agencies to plan for more sustainable and

affordable energy use over an extended period of time. This small change will open the door to government investments in cleaner, more sustainable, and ultimately more cost-beneficial energy technologies.

Our amendment also establishes a Renewable Electricity Standard for Federal agencies. This RES will ensure that the Federal Government meets 20 percent of its electricity demands through renewable energy by 2020. It will drive demand for new, clean-energy technologies and help create new, clean-energy jobs. Indeed, we will be leading by example.

I'm proud to have joined my fellow members of the Sustainable Energy and Environment Coalition, chaired by JAY INSLEE and STEVE ISRAEL, on this provision. I would like to thank Chairman WAXMAN for his assistance on this important amendment.

I too will miss you, Madam Speaker. Mr. SESSIONS. Madam Speaker, I appreciate the gentlewoman's coming down and speaking this morning. There's an estimate that in her congressional district, there will be 5,334 jobs that will be lost in the first year of this bill.

Madam Speaker, at 3 o'clock, 2:30 this morning, we received the manager's amendment, 309 pages, brand new. And this is the text of the ideas that Chairman Barton was talking about that were completely ignored by the Democrat majority last night in the Rules Committee. The Members had come up to speak plainly about their ideas. Completely ignored. Completely ignored.

At this time I would like to yield 3 minutes to the ranking member of the Energy and Environment Subcommittee of the Energy and Commerce Committee, Mr. UPTON.

Mr. UPTON. Madam Speaker, this bill sure is an energy bill. This bill will turn out the lights on America.

You know, there was a chance that we were going to have a bipartisan bill. But that chance melted away when the subcommittee failed to mark up a bill and we went right to full committee. We thought we might have a chance on the House floor. And I can remember when Speaker Hastert was in your chair, Madam Speaker, because 4 years ago we had an energy bill on the floor and there were more than 50 amendments that were offered under Chairman DREIER and the Rules Committee, many of them Democratic amendments. We spent a number of days on this. And at the end of the day, both Mr. DINGELL, the former chairman, and JOE BARTON, the then-chairman of the Energy and Commerce Committee, were able to vote for a bill because, in fact, it was bipartisan.

Yesterday more than 200 amendments were filed up at the Rules Committee, many of them Republican, many of them bipartisan. Mr. HILL, Democrat from Indiana, and I offered a bipartisan amendment on nuclear. Nuclear is one issue that is absent from

this bill. Don't ask me why. There are no greenhouse gas emissions from nuclear. It really is a jobs bill. I've got two nuclear plants in my congressional district. When they were both brought online, 85 percent of the components were made in America. Today for a new nuclear plant, 85 percent is going to come from someplace else because we turned the light from green to red on nuclear the last 20, 25 years. Yet no amendment on nuclear in this bill and in this rule.

I woke up this morning and saw my friend and colleague Mr. INSLEE speaking on C-SPAN. He said this bill was going to cost only a postage stamp. I looked at the paper this morning and saw a full-page ad: gasoline costs will only go up 2 cents a gallon.

You know, I hope they're true. But I don't think that those statements are going to be true. We had amendments as a safety valve in case it does go up. The CBO and American Petroleum Institute say that gas prices are going to go up 77 cents a gallon, diesel prices 88 cents a gallon. Some energy costs could go up by 40 to 50 percent. We had amendments that said, hey, if gasoline goes up to 5 bucks a gallon, we're going to take off this cap-and-trade. If electricity prices go up more than 10 percent, we'll take off cap-and-trade. If unemployment reaches 15 percent, and it's almost there already in Michigan, we'll take off those job-killing provisions. Were those amendments allowed? No.

Then we've got the whole issue of India and China, jobs going someplace else. That consumed a couple of hours of debate, I think, in full committee. Yet no amendment at all allowed on the House floor.

Madam Speaker, my folks want to work and pay taxes. Yet they're going to find themselves laid off, and in Michigan a hundred thousand folks this year will run out of benefits. No amendments are allowed to help those folks. Not even a Republican substitute is allowed as part of this rule.

Madam Speaker, your side has an 80-vote margin. I would like to think that at least we could have the same cards to offer positive constructive amendments and debate it on the merits, not on the politics.

Ms. MATSUI. Madam Speaker, I yield 2 minutes to the gentlewoman from Florida, a member of the Energy and Commerce Committee (Ms. CASTOR).

Ms. CASTOR of Florida. I thank my good friend Congresswoman MATSUI from Florida for yielding and say that it is absolutely appropriate that Congresswoman Doris Matsui leads off the debate today on behalf of the Rules Committee because she has been one of America's most outspoken advocates for a new, clean-energy economy.

Madam Speaker, the American people's election of President Obama was a call for a change in the direction of the country, especially our energy policy.

America's energy policy is outdated. We rely too much on foreign oil, which

has serious economic and strategic risks. We have not invested in renewable energy or in cost-saving technologies as we should. Meanwhile, carbon pollution is changing our climate and destabilizing global markets. Unless carbon pollution is addressed, we face an uncertain future.

But thanks to the leadership of Speaker Pelosi, Chairman Waxman, Chairman Markey, and many of my colleagues and businesses and citizens all across America, we now have a golden opportunity to act and to modernize energy policy and to bolster science and research.

We are going to pass the American Clean Energy and Security Act, and none too soon. It comes at a critical time for our Nation and right on the heels of the Economic Recovery Act. Together the Clean Energy Act and the recovery plan provide a new foundation for economic recovery, new jobs, and clean-energy manufacturing. We are going to drive the development of new, clean-energy jobs that pay well and cannot be outsourced.

People are fed up with the wild swings in gas prices and tired of watching America's economy rise and fall along with the price of a barrel of oil. So we're going to commit ourselves to a new economic future.

The Clean Energy Act has special significance to my home State of Florida because alone in the continental United States, my State is surrounded on three sides by water. If we do not take action to address carbon pollution, it is possible that much of my State in future decades will no longer be habitable. We must act now.

The SPEAKER pro tempore. The time of the gentlewoman has expired.

Ms. MATSUI. I yield the gentlewoman an additional 30 seconds.

Ms. CASTOR of Florida. I thank my colleague.

Scientists tell us that if carbon pollution is not addressed, the seas could rise and the coasts could move inland. Florida has already seen increasing droughts and saltwater intrusion of our aquifers. What happens if we do not act? Property insurance rates are already out of sight. What if the scientists are right that warmer waters increase the intensity of hurricanes?

So for those that say that it's not time to build on a new energy economy or that environmental changes can be ignored, you are on the wrong side of history. We are going to make good on the promise to future generations of Americans and break our dependence on foreign oil and create the clean-energy jobs that will revitalize America's economy in the coming century.

Mr. SESSIONS. Madam Speaker, I appreciate the gentlewoman from Florida's coming down. A vote for this bill will lose 3,500 jobs in her congressional district in the year 2012, the first year of its implementation.

Madam Speaker, I would like to yield 2 minutes to the distinguished gentleman from the Fifth Congressional District of Texas (Mr. HENSARLING).

Mr. HENSARLING. Madam Speaker, since the Democrats have taken control of Congress, we have seen their idea to increase the deficit tenfold. We've seen their idea to triple the national debt in 10 years. We've seen their ideas to bail out AIG, GM, Fannie and Freddie, and the list goes on. And today's new idea, a new national energy tax costing every American family \$1,500 to \$3,000 a year, but only if they choose to turn on a light, cook a meal, or drive their children to school.

Don't take my word for it. Listen to the President of the United States, who said that under his plan, electricity rates would "necessarily skyrocket." That's from our President. Estimates are our gas prices will go up about 77 cents a gallon at the pump.

Now, all of this is due to global warming concerns, and, Madam Speaker, these are legitimate concerns. We have a right to be concerned, and manmade activity does contribute. But is this a smart policy? You know, if India and China don't participate, it is for naught. Even our own Federal Government estimates, at best over a course of a hundred years, this may impact global temperatures ½0 of 1 degree. Frankly, that variance occurs naturally every single year.

Think about the severe job loss, millions and millions of jobs lost due to the competitive disadvantage we have.

There are smarter ways to deal with global warming, but we hear nothing about clean coal from the other side. We hear nothing about nuclear from the other side.

Think about the huge loss of national wealth that could have been used to cure cancer, send a generation to college, help launch millions of small businesses.

Now, Madam Speaker, some call it "cap-and-trade." It will cap American opportunity. It will trade away American jobs. It's time to reject the new national energy tax.

□ 1000

Ms. MATSUI. Madam Speaker, I yield 2 minutes to the gentlewoman from Arizona (Ms. GIFFORDS).

Ms. GIFFORDS. Thank you, Ms. MATSUI.

I rise today in support of this legislation. I was pleased to join with my Southwestern colleagues DINA TITUS and MARTIN HEINRICH to offer amendments to this bill, which are now part of the manager's amendment.

With strong support from my colleagues and the Sustainable Energy and Environment Coalition, we cracked an amendment which will significantly expand the government's use of electricity from renewable sources, such as solar energy, in a couple of ways.

First, it extends the allowable period of time for which Federal agencies may sign public power agreements from 10 years to 20 years. This will allow renewable power providers to offer lower rates, making renewable power much more cost competitive. This is going to

promote the installation of renewable power projects on government buildings and military installations across the country.

In my district, southern Arizona, both Fort Huachuca and Davis-Monthan Air Force Base are looking at installing solar projects. This time expansion from 10 to 20 years, this provision is going to be a significant benefit to these projects and other projects across the country.

Second, the amendment will establish a target of 20 percent renewable electricity for all government agencies by 2020. Similar to the renewable electricity standard for utilities already crafted in this legislation, this provision simply ensures that our Federal Government is doing the same. We are creating a market for renewable power.

As an enormous consumer of energy, particularly the Department of Defense, the Federal Government can have a significant positive impact by modifying its procurement process to support emerging technologies in this way.

This bill, Madam Speaker, is not a perfect bill, but it's an important piece of legislation, and I urge my colleagues on both sides of the aisle to support it.

Mr. SESSIONS. Madam Speaker, at this time I would like to yield 3 minutes to the gentleman, the chairman of the Republican Conference, Mr. Pence.

(Mr. PENCE asked and was given permission to revise and extend his remarks.)

Mr. PENCE. Madam Speaker, this is a difficult time in the life of our Nation and the life of our Nation's economy and that of families and small businesses and family farms.

Remarkably, today, with an embarrassingly brief amount of debate and discussion and amendment, the Democrat majority is poised to bring to the floor of the Congress what amounts to the largest tax increase in American history under the guise of climate change legislation.

Now, there is a lot of debate about what this bill will cost the average American household from hundreds of dollars to thousands of dollars, but there actually is no debate over the fact that this legislation will cost millions of American jobs. On that point there is no discussion.

The bill, itself, actually includes a fund that would provide resources for Americans who lose their jobs if capand-trade becomes law, and there are news reports this morning, although I am yet to confirm them, that there may be new trade restrictions in this legislation, because the expectation, and it is reasonable, is, by raising the cost of energy for every American business, that we will see businesses flee overseas, taking jobs abroad in these difficult economic times. It is extraordinary, to say the least.

But the way that this bill is coming to the floor ought to be disturbing to every American, Republican, Democrat and Independent that's looking in. Last night, at 3:09 a.m., House Democrats filed a 309-page amendment and denied Republican and Democrat amendments to the tune of the 224 that were submitted.

Three hours of debate, one amendment filed at 3:09 in the morning that's 309 pages. And I would ask the Democrat majority and the Speaker respectfully, what's the hurry? What are we hiding here that we can't afford more time for the American people and their elected representatives to examine what's in this bill?

I mean, is there more corporate welfare, more deals for special interests. Were Members that were on the fence placated with special provisions for industries in their districts? We are hurrying to find out, and we have to hurry, because the majority just recently denied us one additional minute of debate.

You know, the term "Congress," Madam Speaker, actually is an ancient term. It means interaction. It means the intercourse between men and women in ideas and philosophies. This is not Congress. I don't know what this is; 3 o'clock in the morning, 300 pages, one amendment is a travesty.

Ms. MATSUI. Madam Speaker, I yield 1½ minutes to the gentleman from Vermont, a member of the Committee on Energy and Commerce, Mr. WELCH.

Mr. WELCH. I thank my colleague.

Madam Speaker, a confident nation acknowledges the challenges it faces. It doesn't ignore them. A confident people, when faced with the challenge, rolls up their sleeves and addresses the problems before them.

Madam Speaker, today, Congress has two questions. The first is will it acknowledge the challenge of global warming that it is real, that it is urgent, and that demands attention now.

And second, will Congress, by this first step of passing this legislation, unleash the power of America to take that step towards American energy independence; to unleash the brilliance of our scientists and engineers to develop alternative and renewable energy; to unleash the competitiveness of our entrepreneurs to bring to market energy-saving devices and to create jobs in America; the frugality and thriftiness of our homeowners and business owners who have buildings to be able to retrofit and make them more energy efficient and save money; the skills of our plumbers, masons, electricians and carpenters to go to work making our buildings more energy independent.

Madam Speaker, every generation faces its challenge, and what we have seen across America is that young people have taken this on, and our question is whether we are going to—

The SPEAKER pro tempore. The time of the gentleman has expired.

Ms. MATSUI. I yield the gentleman an additional 15 seconds.

Mr. WELCH. The question we face as Congress is simply this: Will we put to work those young Americans, those scientists, those entrepreneurs, and allow them to make America energy independent?

The questions we face can be solved. We have to give permission and authority for people to act.

Mr. SESSIONS. Madam Speaker, at this time I would like to yield 1½ minutes to the distinguished gentleman from Georgia, Dr. BROUN.

Mr. BROUN of Georgia. I want to give my personal congratulations to Congresswoman TAUSCHER, and I just look for great things out of you. Congratulations.

I rise to speak against this rule. This rule is blatantly unfair to the American people. It is quashed. It is. It has prevented good amendments to be introduced on this floor and to have the proper debate that we should have over something that is extremely important, as this bill is. We have just gotten this, but let me tell what you this bill is, America, Madam Speaker. This bill is going to kill millions of jobs in America. People are going to be put out of work because of this bill.

Now, we hear all the time about global warming. Actually, we have had flatline temperatures globally for the last 8 years. Scientists all over this world say that the idea of human-induced global climate change is one of the greatest hoaxes perpetrated out of the scientific community. It is a hoax. There is no scientific consensus.

But this is going to kill jobs. It's going to raise the cost of food. It's going to raise the cost of medicines. It's going to raise the cost of electricity and gasoline. Every good and service in this country is going to go up, and who is going to be hurt most? The poor, the people on limited income, the retirees, the elderly, the people who can least afford to have their energy taxes raised by, MIT says, over \$3.100 per family.

This rule must be defeated. This bill must be defeated. We need to be good stewards of our environment, but this is not it. It's a hoax.

I encourage people to vote against the rule and the bill.

Ms. MATSUI. Madam Speaker, I yield 3 minutes to the gentlewoman from Texas, Ms. Jackson-Lee.

Ms. JACKSON-LEE of Texas. I would like to thank the gentlelady from California, and I would like to express my recognition that this is heavy lifting.

This is for the courageous and the willing who want to see a new vision. I am well aware of the hard task that our friends on the Rules Committee had, so I am voting for the rule, and I come from the energy capital of the world. We are proud to say that. We have obviously lived in the clothing of the energy of this past century and what continues in the century to come.

But I realize it should be a seamless energy policy. I represent the city of Houston, hardworking Americans. And so it's important as we listen to our friends on the other side of the aisle, this is a challenging time. It is a time for heavy lifting, to be able to look at what happened in the past. We realize that under the Bush administration, the increase in what we pay for gasoline went from 2,000-plus to 4,000-plus. We also realize that in this legislation there is a great effort to ensure that the American people are addressed fairly.

So 40 percent of American households will face almost no cost as a result of this bill. Let's get the facts. We know that the CBO score of the bill that had been utilized by our friends on the other side of the aisle is incorrect because the increase on building our energy resources will wind up being \$770 per family. But there are issues that we should continue to be focused on, and, therefore, we should look to ensure that no American who may be displaced for any reason, new technology, is not, in essence, overlooked.

There are millions of dollars for green energy job training in this bill. I am looking to offer amendments that focus on making sure that any dip in job positions will be monitored by the Labor Department and, in fact, that resources be available for all Americans.

But what we are trying to do here is to build a new culture and work with what we have, to build the seamless resources that we have across the country and guide the carbons out of the air and make our quality of life better and at the same time give us a new vision for how we handle the energy needs of our Nation.

And so it is important that we recognize that there is a structure to capture that carbon. There is a response to those who are, in essence, impacted. There are credits that are going to be given.

At the same time, I was concerned about the labeling of different buildings, and we are working on language that would ensure that older buildings won't have to participate in the assessment of whether your building is energy efficient. It will be for new construction.

So we are making our way because, in fact, this is a beginning. We will be working with the Senate. We will be working with the President. We will be working on behalf of the American people.

We have to get started. We have to be innovative. We have to claim the 1.7 million jobs that this bill will create. I think America wants us to do that.

Mr. SESSIONS. Madam Speaker, could you please advise us how much time remains on both sides?

The SPEAKER pro tempore. The gentleman from Texas has 6 minutes remaining. The gentlewoman from California has 9¾ minutes remaining.

Mr. SESSIONS. Madam Speaker, at this time I would yield 1½ minutes to the distinguished gentleman from Georgia, Dr. GINGREY.

Mr. GINGREY of Georgia. Madam Speaker, I rise in opposition to this rule and to the underlying legislation.

I am just not sure to which I am more opposed. Americans are watching, as from Iran to North Korea, the forces of darkness are attempting to silence the voices of democracy and freedom.

The irony is, on this day, the democratic process and our Nation's economic freedom are under threat, not by some rogue state but in this very Chamber in which we stand. Good people may disagree on the impact of the merits of this bill, but no one can disagree with the fact that the Speaker and our Rules Committee have silenced the opposition of 224 amendments. Madam Speaker, one, and I repeat, one amendment was actually made in order.

Madam Speaker, I offered an amendment which was, of course, not made in order, that would have allowed a State to opt out of this legislation.

□ 1015

How can we not give them the ability to say that their citizens and their businesses simply cannot afford this Pelosi global warming tax? For some of them, this bill will be an economic death sentence.

And yet, Madam Speaker, this House will not have a chance to vote on this amendment or any of the other 222. They were banned from being debated and voted upon in this, the people's House.

I call upon every Member of this House, oppose and defeat this rule, not just for the sake of the democratic process, but for the sake of our Nation's economy.

Ms. MATSUI. Madam Speaker, I yield 2 minutes to a member of the Committee on Natural Resources, the gentleman from New Mexico (Mr. HEINRICH).

Mr. HEINRICH. Madam Speaker, I rise today in support of this rule, which includes an amendment I worked to draft with my colleagues, Ms. TITUS of Nevada and Ms. GIFFORDS of Arizona.

This amendment will make sure that the Federal Government leads by example on clean energy. In my district, Kirtland Air Force Base has tried for a number of years to contract with local clean-energy producers to purchase electricity to help power the base, but there are several Federal policies that stand in the way of these kinds of projects.

New Mexico is second in the Nation for solar energy potential, and we have a thriving clean-energy industry in Albuquerque, creating jobs today. So this is a natural partnership.

However, many Federal agencies have discovered that the 10-year limit on Federal power purchase agreements made these kinds of agreements uneconomical for their private sector partners in the solar industry.

Our amendment will extend the length of these contracts to 20 years, allowing more Federal agencies to sign agreements with clean-energy producers. This will put Americans to

work and ensure the Federal Government leads by example in the use of clean energy.

I urge my colleagues to support this rule, this legislation.

Mr. SESSIONS. Madam Speaker, if I can please ask my colleague, the gentlewoman from California, in an effort to get our time back to an even balance, if she could have one of her speakers up at this time.

I reserve the balance of my time.

Ms. MATSUI. I yield 2 minutes to the gentleman from California (Mr. Schiff).

Mr. SCHIFF. Madam Speaker, the bill today that Chairman WAXMAN has so carefully shepherded to the floor today is a landmark achievement for this body. For the first time as a Nation we are moving towards energy independence, creating millions of new clean jobs, and confronting the threat that global warming poses to the Earth

As parents, we all struggle to provide our children with a better life. Without the strong action embodied in this bill, the world that we bequeath to our children will be diminished by continued reliance on Middle Eastern oil, by exporting billions of hard-earned American dollars to petro dictatorships, and by a warming Earth.

America has been at her best during her greatest struggles and, as before, her industry and entrepreneurial spirit will prevail. Already, the green technology industry is booming across the country, with new factories built and new companies formed every day.

Unfortunately, the Federal Government itself has not been able to fully utilize renewable energy. Many renewable energy installations have large upfront costs, which then have to be recovered in the form of cheap energy over the course of many years. But the Federal Government has been restricted from signing long-term contracts for energy, so affordable renewable energy has been unavailable to thousands of government offices around the country.

The rule for this bill inserts an important provision that I authored as independent legislation earlier this year and that I worked with many colleagues to include. It loosens the restrictions on energy purchases by the government, and that will spur local green energy development in every State in the Nation.

I hope that we can support this measure, this rule, this bill and fulfill the promise that we have given to our constituents, that we will serve this country not only today and during this Congress, but for the long haul, that we will make not only the easy decisions, but the hard ones.

Mr. SESSIONS. At this time I yield 1 minute to the distinguished gentlewoman from Illinois (Mrs. BIGGERT).

Mrs. BIGGERT. I thank the gentleman for yielding. Madam Speaker, I rise today in opposition to this rule and the bill. I offered five bipartisan,

commonsense amendments to the bill with the support of other Members. Not one of these was made in order.

I offered an amendment to strike the section that mandates national building codes. Because my amendment was rejected, if State and local governments don't comply with these new national mandates, homeowners today who are struggling to make ends meet could be charged \$100 a day for not being in compliance. A new tax on American homeowners is the wrong direction.

I had another amendment to strike from this bill the new tax on all transactions cleared via any U.S. regulated derivatives clearing organization. This bill then will have very chilling consequences. It will punish those using U.S.-regulated clearing organizations, discourage the use of central clearing organizations, and reduce transparency and liquidity and encourage legitimate business activities to move to unregulated foreign markets.

Another amendment would revise the Nuclear Advanced Fuel Cycle Initiative to set a policy for clean, safe nuclear energy. I oppose this rule and the bill.

Ms. MATSUI. Madam Speaker, I yield 1½ minutes to the gentleman from Illinois (Mr. QUIGLEY).

Mr. QUIGLEY. It's interesting, earlier today someone asked me: How can you vote for this measure, because global warming is a hoax. My answer was: It's very simple. I remove the blinders there that exist with some of my colleagues who think that global warming is a hoax. I remind them that there are zero peer-reviewed scientific studies that say global warming is a hoax.

There are hundreds of peer-reviewed scientific studies that say global warming is real and that man's actions contribute greatly to that increase in temperature.

We are often asked: What is our legacy here? What really matters about what we do? And I'd like to think it's how our children and our grandchildren will react to what we did and what we left behind.

So let's face reality and do what is right for our children and our children's children.

Mr. SESSIONS. At this time I would yield a grand total of 30 seconds to the distinguished gentlewoman from Tennessee (Mrs. BLACKBURN).

Mrs. BLACKBURN. Thank you, Madam Speaker. I do rise to oppose this rule. Many of my constituents see this as a government regulation of the very air you breathe. They know that this is a liberal's dream, and that indeed many think that the Democrats have become the party of punishment. We are the party of "no." We want people to know what is in this bill.

I offered in committee an amendment that would require disclosure of what this legislation would cost consumers on their electric bills, at the gas pump, and on the products that they buy.

In Rules Committee, I offered an amendment to require every transaction that FERC makes on these allocations and offsets to be listed in a database that is searchable by the public so they will know what is in this. They were voted down.

I encourage all to oppose this rule and this bill.

The SPEAKER pro tempore. The gentlewoman from California has $5\frac{1}{2}$ minutes. The gentleman from Texas has 3 minutes remaining.

Ms. MATSUI. I reserve the balance of my time.

Mr. SESSIONS. If I could, Madam Speaker, is the gentlewoman through with her speakers now? We still have some disparity in the little bit of time that was given. I would like for there to be some parity.

Ms. MATSUI. I have additional speakers coming.

Mr. SESSIONS. If she has additional speakers, I will reserve the balance of my time.

Ms. MATSUI. Madam Speaker, I don't see my speakers present there, so I'm ready to close. I will use my remaining time to close.

Mr. SESSIONS. At this time I yield 1 minute to gentleman from Tennessee (Mr. ROE).

Mr. ROE of Tennessee. Madam Speaker, I rise in opposition to this rule and the underlying legislation. I've only been here 6 months, but this is the worst piece of legislation that has come out of the House yet.

It defies logic that at a time of economic recession we would impose a regressive national energy tax that many have predicted will result in a net job loss. Supporters of this legislation only want to talk about the so-called "green" jobs that will be created, but they conveniently ignore that some studies indicate that for every one job created, two are eliminated.

Worse, we are creating a costly, confusing program of carbon credits. Let me make one prediction: the only certainty under this bill is Wall Street traders sophisticated enough to understand how these credits are traded will make millions.

I offered an amendment yesterday at the Rules Committee stating that at least bring it to a level playing field between the U.S., China, and India. My feeling is that if Congress is going to pass this legislation, we should require India and China—two enormous and growing resources of greenhouse emissions—to abide by the same standards.

My amendment would have required the U.S. to come to agreement with these two countries on emission reductions before implementing any provision within this bill.

This rule is a sham. It pales in comparison to how awful the bill is. I urge the Members to demand a return to the democratic process and defeat this bill that will certainly exacerbate our economic recession.

Mr. SESSIONS. Madam Speaker, at this time I yield 30 seconds to the gentleman from Louisiana (Mr. SCALISE).

Mr. SCALISE. Thank you, Madam Speaker. I rise in opposition to this rule. This is a massive energy tax on the backs of the American people all across this country. All estimates show millions of jobs will be lost by this capand-trade energy tax.

Every household family will see an increase in their utility bills. And we brought amendments last night to protect American jobs. They ruled every one of those amendments out of order.

We brought amendments to protect American families having their utility bills increased. They ruled every one of those amendments out of order.

What is Speaker PELOSI and this liberal leadership trying to hide from the American people? We should have an open, honest debate on this bill. It's a bad bill and a bad rule. I urge rejection of the rule.

Ms. MATSUI. Madam Speaker, I yield 1 minute to the gentleman from New Mexico (Mr. Luján).

Mr. LUJÁN. Our country's dependence on foreign oils threatens our economy and security. We need to take bold steps to become energy independent by growing a new energy economy. Comprehensive energy reform will reduce our dependence on foreign oil, making us more secure as a Nation.

The energy bill we consider today will also create clean-energy jobs, inspiring a new economy. As a former utility commissioner, I saw firsthand the positive impact energy reform had on my State of New Mexico. We instituted a renewable energy standard that increased the generation of renewables. We encouraged energy efficiency to reduce costs for homes and businesses. And it's now time to see these steps at a national level.

For too long we have accepted the status quo on energy, and now, with the American Clean Energy and Security Act, we can put America on a path to energy independence, make America the global leader in energy technology, cut costly and harmful pollution, create new jobs, and save billions in the long run.

I support this rule and urge my colleagues to join us in supporting this rule and this legislation.

Mr. SESSIONS. At this time I yield 1½ minutes to the ranking member of the Rules Committee, the gentleman from California (Mr. DREIER).

Mr. DREIER. I thank my friend for his superb management. The American people are hurting. We know that very, very well. We hear it daily. Jobs are being lost, people are losing their businesses, people are losing their homes. They don't want to see another tax burden imposed on them, which is exactly what this bill is going to do. Everyone recognizes that there is going to be an increase in the burden on the American people.

Unfortunately, as we pursue green technology, we have not been given an opportunity to do that. My friend from Ohio has been very thoughtful on this issue. He had an idea—several ideas that I offered before the committee.

One of the things I believe we should do, Madam Speaker, is allow for the free flow of green technology globally. I'm working with my friend from Ohio in a bipartisan way on that.

Mr. KUCINICH. Would the gentleman yield?

Mr. DREIER. I'd be happy to yield to the gentleman.

□ 1030

Mr. KUCINICH. I believe the choices we are being offered in this bill are insufficient to address the immediate real threat of global warming. We can take market-based approaches that protect the planet, respect nature through incentivizing the mass production and worldwide distribution of American-made wind and solar microtechnologies, lowering our carbon footprint, lowering our energy costs, and rallying the American people to join in a great economic and social cause of creating a green future. We can do that. We can still do that.

I thank the gentleman.

Mr. DREIER. Madam Speaker, reclaiming my time. Let me say that I totally agree with the statement of my friend. Here is a demonstration of bipartisanship. It's not often that Mr. Kucinich and I work together on the exact same issue. We believe that the free flow of tremendous green technology around the world will, in fact, dramatically improve our economy and the standard of living and quality of life for the American people and for the rest of the world.

Defeat this rule, so that we can bring back some of the 224 brilliant ideas that were offered but totally denied by this majority.

I yield back the balance of my time.
Ms. MATSUI. Madam Speaker, I
vield myself the remainder of my time.

The SPEAKER pro tempore. The gentlewoman from California is recognized for 4½ minutes.

Ms. MATSUI. The rule before us today is a fair rule. It allows us to highlight our current energy policy challenges and a vision for a better tomorrow.

The bill contains expedited procedures for consideration of a joint resolution of approval related to an international reserve allowance program. Such procedures are within the jurisdiction of the Rules Committee, and it is the committee's understanding that the procedures are placeholder language that will be finalized as the legislation moves forward. The Rules Committee looks forward to working with the other committees of jurisdiction on this provision.

From water, to energy, to transportation, agriculture and public health, climate change is a defining environmental challenge of our time. The action we take today will impact our country in a positive way for generations.

Today, it is this Congress' responsibility to pass comprehensive energy policy that charts a new course towards a clean energy economy. The underlying bill, the American Clean Energy and Security Act, takes huge steps to create jobs, help end our dangerous dependence on foreign oil and fight global warming.

I urge my colleagues to recognize the urgent nature of the challenge before us today. If we do not act, we face disastrous consequences. Nearly every scientific society around the world has warned of the cost of inaction.

On the other hand, if we do act here today, we make our planet more sustainable, more economically viable and more efficient than the world we live in today. We will make a positive impact, not only on the billions of people who live on the Earth today, but for generations into the future.

Madam Speaker, I urge a "yes" vote on the previous question and on the rule.

Mr. MANZULLO. Madam Speaker, I rise in opposition to the Rule. I offered a commonsense amendment to strike the International Climate Change Adaptation program and the allocation of emission allowances to this program. We don't need to establish yet another foreign assistance program that is not only redundant but will actually hurt American manufacturers.

This legislation calls for the U.S. to transfer to developing nations a portion of America's emission allowances so that these nations can continue to pollute. By giving away additional allowances this legislation will put America's manufacturers at an even worse competitive footing than ever before. This is another incentive to encourage American manufacturers to leave this country.

And, this initiative will not reduce emissions. According to an article in yesterday's Washington Times, David Bookbinder, chief climate counsel to the Sierra Club, said, "emissions could actually stay the same or increase domestically because companies could choose to buy permits instead of investing in technology to make their operations cleaner." I ask unanimous consent to insert the full article into the RECORD.

Plus, this Rule prohibits a debate on some other commonsense amendments. My fellow Illinoisan, Representative JUDY BIGGERT, had a responsible amendment to strike the federalization of local building codes and replace it with positive incentives to encourage federal, state, and local governments to move towards green building codes. Even the liberal Washington Post editorialized against this provision in the bill. I ask unanimous consent to insert this editorial into the RECORD. This amendment was defeated 3 to 7 in the Rules Committee last night.

The Rule also prohibits a debate on an amendment offered by Representative DAVID ROE of Tennessee to waive this bill until the U.S. reaches an agreement with China and India on greenhouse gas reductions. Again, this sensible amendment was defeated by a vote of 3 to 7 in the Rules Committee last night. This is atrocious. We are only fooling ourselves if we think we're doing something to save the planet when all we're doing is transferring our manufacturing jobs and our pollution problems to China, India, and other developing nations. This bill will not lower global emissions of greenhouse gasses. The Roe

amendment would have prevented this mistake.

I urge my colleagues to vote "no" on the rule and "no" on the final "cap and tax" bill. [From the Washington Times, June 25, 2009]

CLIMATE BILL GIVES BILLIONS TO FOREIGN FOLIAGE

(By Amanda DeBard)

If a tree falls in Brazil, it will, in fact, be heard in the U.S.—at least if a little-noticed provision in the pending climate-change bill in Congress becomes law.

As part of the far-reaching climate bill, the House is set to vote Friday on a plan to pay companies billions of dollars not to chop down trees around the world, as a way to reduce global warming.

duce global warming.

The provision, called "offsets," has been attacked by both environmentalists and business groups as ineffective and poorly designed. Critics contend it would send scarce federal dollars overseas to plant trees when subsidies are needed at home, while the purported ecological benefits would be difficult to quantify.

The offsets "would be a transfer of wealth overseas," said William Kovacs, vice president for environmental affairs at the U.S. Chamber of Commerce

Chamber of Commerce.

The Congressional Budget Office (CBO), the official fiscal scorekeeper on Capitol Hill, has not offered an estimate on how much the offset plan would cost, but the liberal Center for American Progress says it will be pricey.

"The international offsets market is not a huge or cheap market," said Joseph Romm, a climate expert at the center. "By 2020, the U.S. could be spending \$4 billion on international offsets."

Supporters of the legislation counter that the plan recognizes the need to reduce greenhouse-gas emissions to curb global warming—in the United States and beyond. Supporting ways to keep trees alive or plant new trees, wherever those trees are located, helps the effort, they say.

Under the program, the government would reward domestic and international companies that perform approved "green" actions with certificates, called permits.

Those companies could, in turn, sell the permits to other companies that emit green-house gases. The permits would be, in effect, licenses to pollute—and potentially very valuable.

The heart of the climate plan would require major polluters to purchase the permits if they want to pollute above a certain level, controlling overall emissions through a market that is called "cap-and-trade."

Under the provision to be voted on in the House, the "green" companies could sell their offset permits to companies that need them because they are unable to, reduce their own emissions as fast as the government would like.

But critics from both the political left and right see problems.

"You have to ask yourself, what is the purpose of this provision? Because it won't actually reduce emissions," said David Bookbinder, chief climate counsel to the Sierra Club, the environmental advocacy group.

Mr. Bookbinder said emissions could actually stay the same or increase domestically because companies could choose to buy permits instead of invest in technology to make their operations cleaner.

Kenneth P. Green, a climate specialist at the conservative American Enterprise Institute for Public Policy Research, said keeping track of which projects would be eligible for inclusion is another flaw in the plan.

"Who is responsible if there's a fire that burns down a [green] project? Will those just be wasted offsets?" he asked. Mr. Green and others say the bill's offset provisions, are too vague and leave unanswered too many questions about which projects will qualify for the offsets and how many offsets would be offered for a given project.

"The key with offsets is ensuring that they generate credible emission reductions," said Evan Juska, North America senior policy manager for the Climate Group, which advises governments and business how to move to a low-carbon economy.

Mr. Juska said the bill, as written, "leaves much of it to be determined by the administrator after the program is enacted."

While tree stands are a large absorber of carbon dioxide and other greenhouse gases, they may not be the only projects that qualify for offsets. Companies that erect wind farms, install solar panels, invest in devices that trap the methane gas in landfills, use less fertilizer, or upgrade equipment at their refineries and power plants might also be eligible for offsets.

The bill would only allow 2 billion tons, or about 30 percent, of carbon-dioxide emissions to be offset a year through the so-called "green" actions.

Half of the qualifying projects must be domestic and half must be overseas, but the bill includes the option to award more offsets to international projects if not enough domestic projects are available.

The CBO projects that the thousands of firms subject to the cap-and-trade program would utilize 230 million tons of domestic offsets and 190 million tons of international offsets in 2012, the year the legislation is proposed to take effect, instead of reducing their emissions levels.

[From the Washington Post, June 7, 2009]

The running joke in Washington is that nobody has read the 900-plus-page energy bill sponsored by Reps. Henry A. Waxman (D-Calif.) and Edward J. Markey (D-Mass.). which the House will consider in coming weeks. What you hear from its backers is that its cap-and-trade provisions would create a market-based program to reduce greenhouse gas emissions—which should mean that a simple, systemwide incentive encourages polluters to make the easiest reductions in greenhouse gases first, keeping the costs of fighting global warming to a minimum. In fact, the bill also contains regulations on everything from light bulb standards to the specs on hot tubs, and it will reshape America's economy in dozens of ways that many don't realize.

Here is just one: The bill would give the federal government power over local building codes. It requires that by 2012 codes must require that new buildings be 30 percent more efficient than they would have been under current regulations. By 2016, that figure rises to 50 percent, with increases scheduled for years after that. With those targets in mind, the bill expects organizations that develop model codes for states and localities to fall in the details, creating a national code. If they don't, the bill commands the Energy Department to draft a national code itself.

States, meanwhile, would have to adopt the national code or one that achieves the same efficiency targets. Those that refuse will see their codes overwritten automatically, and they will be docked federal funds and carbon "allowances"—valuable securities created elsewhere in the bill that give the holder the right to pollute and can be sold. The Energy Department also could enforce its code itself. Among other things, the policy would demonstrate the new leverage of allocation of allowances as a sort of carbon currency—leverage this bill would be giving to Congress to direct state behavior.

According to the bill's advocates, America's buildings account for perhaps 40 percent of U.S. greenhouse emissions, and technology is available for builders to meet the targets in ways that are economical for building owners. Much of the problem is old buildings that waste huge amounts of energy, which wouldn't necessarily be touched by the new code. But it would be good if builders met these efficiency goals with new construction.

Is the best way to achieve that, though, to federalize what has long been a matter of local concern? And if the point of cap-and-trade is to change market incentives, why does Congress, and not the market, need to dictate these changes? Those are a few questions that emerge when you begin to read through the 900 pages.

Mr. GRAVES. Madam Speaker, I come to the floor today extremely disappointed with the Rule put before us.

Every day I hear the same message from my constituents—stop Washington's addiction to spending. Bailout after bailout, with no change in sight, the small business owners, farmers and hard working families in Missouri have grown weary and frustrated.

Instead of providing our taxpayers much needed relief, we are here today to ask for more of their money. H.R. 2454 is a thinly veiled attempt to address climate change, unsuccessfully I might add, while its actual goal is to direct more taxpayer dollars to the government coffers. The results are unacceptable:

an average tax increase of \$3100 for families:

additional regulatory and administrative costs on small businesses:

higher energy expenses for all—especially those in rural areas;

and significant job loss.

When will enough be enough?

I offered two common sense amendments to H.R. 2454-rejected by the Rules Committee-which struck the cap and tax provisions in the underlying bill should the unemployment rate reach 8 percent or higher. I have financially strapped companies in my district, who instead of laying off their employees have chosen to keep them on payroll at reduced hours. These business owners and employees are making serious sacrifices. Should this cap and tax provision be implemented while these companies continue to struggle to survive this economic downturn, their strategic and innovative efforts will become null and void and their employees will join the already overextended unemployment line.

Today I strongly urge my colleagues to stand with me. It is irresponsible of Congress to use taxation as an answer to our challenges. Voting against this rule and the underlying legislation will demonstrate your willingness to work together towards real energy solutions for our future and our children's future.

Ms. LEE of California. Madam Speaker, I rise in support of the rule.

President Obama, in commenting on the American Clean Energy and Security Act earlier this week, cited that this legislation "will open the door to a better future for this nation."

I strongly agree with President Obama, but I must also stress our responsibility to ensure all individuals will be provided the opportunity to participate in the new green economy.

That is why I offered the Lee Amendment to this legislation, which would have authorized legislation I have introduced in the House entitled the Metro Economies Green Act, or MEGA, in order to establish targeted grant programs to support green economic development, job training and creation.

Inclusion of the Lee Amendment to H.R. 2454 would have provided valuable opportunities for those who can benefit from good paying green collar jobs the most—urban youth of color, the unemployed, and those among our neighbors who have just faced incredible hardships in life.

Unfortunately the Lee Amendment was not made in order. However, I look forward to working with my colleagues in the future to expand access to high-paying, career-term green jobs that represent a much needed pathway out of poverty for millions of individuals across this country.

Mr. MATSUI. I yield back the balance of my time, and I move the previous question on the resolution.

The SPEAKER pro tempore. The question is on ordering the previous question.

The question was taken; and the Speaker pro tempore announced that the ayes appeared to have it.

Mr. SESSIONS. Madam Speaker, on that I demand the yeas and nays.

The yeas and nays were ordered.

The SPEAKER pro tempore. Pursuant to clause 8 of rule XX, further proceedings on this question will be postponed.

PROVIDING FOR A CONDITIONAL ADJOURNMENT OR RECESS OF THE SENATE, AND A CONDITIONAL ADJOURNMENT OF THE HOUSE OF REPRESENTATIVES

The SPEAKER pro tempore. The Chair laid before the House the following privileged concurrent resolution:

S. CON. RES. 31

Resolved by the Senate (the House of Representatives concurring), That when the Senate recesses or adjourns on any day from Thursday, June 25, 2009 through Sunday, June 28, 2009, on a motion offered pursuant to this concurrent resolution by its Majority Leader or his designee, it stand recessed or adjourned until noon on Monday, July 6, 2009, or such other time on that day as may be specified by its Majority Leader or his designee in the motion to recess or adjourn, or until the time of any reassembly pursuant to section 2 of this concurrent resolution, whichever occurs first: and that when the House adjourns on any legislative day from Thursday, June 25, 2009, through Sunday, June 28, 2009, on a motion offered pursuant to this concurrent resolution by its Majority Leader or his designee, it stand adjourned until 2:00 p.m. on Tuesday, July 7, 2009, or such other time on that day as may be specified in the motion to adjourn, or until the time of any reassembly pursuant to section 2 of this concurrent resolution, whichever occurs first.

SEC. 2. The Majority Leader of the Senate and the Speaker of the House, or their respective designees, acting jointly after consultation with the Minority Leader of the Senate and the Minority Leader of the House, shall notify the Members of the Senate and the House, respectively, to reassemble at such place and time as they may designate if, in their opinion, the public interest shall warrant it.

Foster

Frank (MA)

The SPEAKER pro tempore.

The question is on the concurrent Senate resolution.

The question was taken; and the Speaker pro tempore announced that the ayes appeared to have it.

Ms. MATSUI. Madam Speaker, on that I demand the yeas and nays.

The yeas and nays were ordered.

The SPEAKER pro tempore. Pursuant to clause 8 of rule XX, this 15-minute vote on adoption of S. Con. Res. 31 will be followed by 5-minute votes on ordering the previous question on H. Res. 587 and adoption of H. Res. 587, if ordered.

The vote was taken by electronic device, and there were—yeas 243, nays 180, not voting 10, as follows:

[Roll No. 464]

YEAS-243 Abercrombie Fudge Meek (FL) Andrews Giffords Meeks (NY) Baca Gohmert Melancon Baird Gonzalez Michaud Gordon (TN) Miller (NC) Baldwin Grayson Green, Al Barrow Miller, George Mollohan Bean Green, Gene Moore (KS) Becerra Berkley Grijalya. Moore (WI) Moran (VA) Berman Gutierrez Hall (NY) Murphy (CT) Berry Bishop (GA) Halvorson Murphy (NY) Murphy, Patrick Bishop (NY) Hare Blumenauer Harman Murtha Nadler (NY) Boccieri Heinrich Herseth Sandlin Napolitano Boren Boswell Higgins Neal (MA) Boucher Hill Nve Oberstar Boyd Himes Brady (PA) Hinchev Obey Bralev (IA) Hinoiosa Olver Brown, Corrine Hirono Ortiz Butterfield Hodes Pallone Capps Holden Pascrell Pastor (AZ) Capuano Holt Cardoza Honda Payne Perlmutter Carnahan Hoyer Carson (IN) Inslee Perriello Castor (FL) Israel Peters Jackson (IL) Chaffetz Peterson Chandler Jackson-Lee Pingree (ME) Clarke (TX) Polis (CO) Johnson (GA) Clay Pomeroy Cleaver Johnson, E. B. Price (NC) Clyburn Kagen Quigley Kanjorski Rahall Cohen Connolly (VA) Rangel Kaptur Convers Kildee Reves Cooper Kilpatrick (MI) Richardson Costa Kilroy Rodriguez Costello Kind Ross Courtney Kirkpatrick (AZ) Rothman (NJ) Crowley Kissell Roybal-Allard Klein (FL) Cuellar Ruppersberger Cummings Kosmas Rush Dahlkemper Kratovil Rvan (OH) Davis (AL) Kucinich Salazar Sánchez, Linda Davis (CA) Langevin Davis (IL) Larsen (WA) T. Sanchez, Loretta Larson (CT) Davis (TN) DeFazio Lee (CA) Sarbanes DeGette Levin Schakowsky Delahunt Lipinski Schauer DeLauro Loebsack Schiff Dicks Lofgren, Zoe Schrader Dingell Lowey Schwartz Doggett Luján Scott (GA) Donnelly (IN) Lynch Scott (VA) Maffei Doyle Serrano Driehaus Maloney Sestak Edwards (MD) Markey (CO) Shea-Porter Edwards (TX) Markey (MA) Sherman Ehlers Marshall Sires Skelton Ellison Massa. Matheson Ellsworth Slaughter Matsui Smith (WA) Engel McCarthy (NY) Eshoo Snyder Etheridge McCollum Space McDermott Speier Farr Fattah McGovern Spratt Filner McIntvre Stark

McMahon

McNerney

Stupak

Tanner

Tauscher Teague Thompson (CA) Thompson (MS) Tierney Titus Tonko Towns Tsongas Van Hollen Velázquez Visclosky Walz Wasserman Schultz Waters Watson Watt

Waxman Weiner Welch Wexler Wilson (OH) Woolsey Wu Yarmuth Young (FL)

NAYS-180

Aderholt Mitchell Foxx Franks (AZ) Moran (KS) Adler (NJ) Frelinghuysen Murphy, Tim Alexander Gallegly Myrick Garrett (NJ) Altmire Neugebauer Gerlach Arcuri Nunes Gingrey (GA) Austria Olson Bachmann Goodlatte Paul Granger Paulsen Bachus Barrett (SC) Graves Pence Bartlett Griffith Petri Barton (TX) Pitts Guthrie Biggert Harper Platts Bilbray Hastings (WA) Poe (TX) Heller Bilira.kis Posey Price (GA) Bishop (UT) Hensarling Blackburn Herger Putnam Blunt. Hoekstra. Radanovich Boehner Hunter Rehberg Bonner Inglis Reichert Bono Mack Tssa. Roe (TN) Jenkins Boozman Rogers (AL) Johnson (IL) Boustany Rogers (KY) Brady (TX) Johnson, Sam Rogers (MI) Bright Rohrabacher Jones Broun (GA) Jordan (OH) Rooney Ros-Lehtinen Brown (SC) King (IA) King (NY) Brown-Waite, Roskam Royce Ryan (WI) Ginny Kingston Buchanan Kirk Burgess Kline (MN) Scalise Burton (IN) Lamborn Schmidt Buver Lance Schock Latham Sensenbrenner Camp LaTourette Sessions Campbell Latta Shadegg Cantor Lee (NY) Shimkus Cao Lewis (CA) Shuler Capito Linder Shuster LoBiondo Carney Simpson Carter Lucas Smith (NE) Luetkemever Cassidy Smith (NJ) Castle Smith (TX) Lummis Childers Lungren, Daniel Souder Coble E. Stearns Coffman (CO) Mack Taylor Cole Manzullo Terry Conaway Marchant Thompson (PA) Crenshaw McCarthy (CA) Thornberry Davis (KY) McCaul Tia.hrt. Deal (GA) McClintock Tiberi Dent McCotter Turner Diaz-Balart, L. McHugh Upton Diaz-Balart, M. Walden McKeon Wamp Dreier McMorris Westmoreland Duncan Rodgers Mica Emerson Whitfield Miller (FL) Fallin Wilson (SC) Miller (MI) Wittman Fleming Forbes Miller, Garv Wolf Fortenberry Minnick Young (AK)

NOT VOTING-10

Ackerman Hastings (FL) Sullivan Culberson Kennedy Sutton Flake Lewis (GA) Hall (TX) McHenry

□ 1100

Messrs. SMITH of Texas, ALTMIRE, GERLACH, and Mrs. EMERSON changed their vote from "yea" to "nay."

Messrs. GOHMERT and DAVIS of Illinois changed their vote from "nay" to "yea."

So the concurrent resolution was agreed to.

The result of the vote was announced as above recorded.

A motion to reconsider was laid on the table.

□ 1100

MOMENT OF SILENCE IN TRIBUTE TO MICHAEL JACKSON

(Ms. WATSON asked and was given permission to address the House for 1 minute.)

Ms. WATSON. Madam Speaker, we rise to pay a 1-minute tribute to a star that shot high into the sky and now remains there. We would like all of those to join us who would like to take a moment to remember Michael Jackson, so Members may come and join us here at the mike.

I would just like to say to our House of Representatives, to the country and to the world, a young man has left Earth but now resides in the stars. He was a talented, multitalented person who entertained the world with his dynamic portrayals, the songs that he had written, and his style of dancing. We think that it is appropriate to say that we pay tribute to the culture that he has left behind, his legacy.

I would like now to ask my colleague, Mr. JACKSON, if he would close out, and all those who stand with us send our condolences, our heartfelt sorrow to his family, his friends, and to his millions of fans throughout the world.

Mr. JACKSON of Illinois. Madam Speaker, if there is a God, and I believe there is, and that God distributes grace and mercy and talent to all of his children, on August 29, 1958, he visited Gary, Indiana, and touched a young man with an abundance of his blessings. With that gift, Michael Joe Jackson would touch and change the world. His heart couldn't get any bigger, and yesterday, it arrested.

I come to the floor today on behalf of a generation to thank God for letting all of us live in his generation and in his era.

With that, Madam Speaker, we would ask Members to please stand for a moment of silence.

ANNOUNCEMENT BY THE SPEAKER PRO TEMPORE

The SPEAKER pro tempore. Without objection, 5-minute voting will continue.

There was no objection.

PROVIDING FOR CONSIDERATION OF H.R. 2454, AMERICAN CLEAN ENERGY AND SECURITY ACT OF 2009

The SPEAKER pro tempore. The unfinished business is the vote on ordering the previous question on House Resolution 587, on which the yeas and nays were ordered.

The Clerk read the title of the resolution.

The SPEAKER pro tempore. The question is on ordering the previous question.

This will be a 5-minute vote.

The vote was taken by electronic device, and there were—yeas 232, nays 189, not voting 12, as follows:

[Roll No. 465]

Abercrombie

Adler (NJ)

Andrews

Arcuri

Baird

Bean

Baldwin

Becerra

Berkley

Berman

Bishop (GA)

Bishop (NY)

Blumenauer

Boccieri

Boswell 8 |

Boucher

Brady (PA)

Braley (IA)

Butterfield

Brown, Corrine

Bovd

Bright

Capps

Capuano

Carnahan

Carson (IN)

Castor (FL)

Chandler

Clarke

Cleaver

Clyburn

Convers

Costello

Courtney

Crowley

Cummings

Dahlkemper

Davis (AL)

Davis (CA)

Davis (IL)

Davis (TN)

DeFazio

DeGette

Delahunt

DeLauro

Dingell

Doggett

Driehaus

Ellison

Engel

Eshoo

Farr

Fattah

Filner

Foster

Giffords

Gonzalez

Gravson

Green, Al

Aderholt

Alexander

Bachmann

Barrett (SC)

Barton (TX)

Bishop (UT)

Altmire

Austria

Bachus

Barrow

Bartlett

Biggert

Bilbray

Rilira kis

Akin

Frank (MA) Fudge

Gordon (TN)

Ellsworth

Etheridge

Dovle

Donnelly (IN)

Edwards (MD)

Edwards (TX)

Dicks

Cuellar

Cooper

Costa

Connolly (VA)

Cohen

Clay

Cardoza

Carney

Berry

YEAS-232

Green, Gene Olver Grijalva Ortiz Gutierrez Pallone Hall (NY) Pascrell Halvorson Pastor (AZ) Hare Payne Harman Perlmutter Heinrich Perriello Herseth Sandlin Peters Higgins Peterson Himes Pingree (ME) Hinchey Polis (CO) Hinojosa Pomeroy Hirono Price (NC) Hodes Quigley Holden Rahall Holt Rangel Honda Reves Inslee Richardson Israel Rodriguez Jackson (IL) Rothman (NJ) Jackson-Lee Roybal-Allard (TX) Ruppersberger Johnson (GA) Rush Johnson, E. B. Ryan (OH) Kagen Sánchez, Linda Kanjorski Т. Kaptur Sanchez, Loretta Kildee Sarbanes Kilpatrick (MI) Schakowsky Kilroy Schauer Kind Kirkpatrick (AZ) Schiff Kissell Schrader Klein (FL) Schwartz Scott (GA) Kosmas Kratovil Scott (VA) Langevin Serrano Larsen (WA) Sestak Larson (CT) Shea-Porter Lee (CA) Sherman Levin Sires Lipinski Skelton Loebsack Slaughter Lofgren, Zoe Smith (WA) Lowey Snyder Luján Space Lynch Speier Maffei Spratt Maloney Stark Markey (CO) Stupak Markey (MA) Sutton Marshall Tanner Massa Tauscher Matsui Teague McCarthy (NY) Thompson (CA) McCollum Thompson (MS) McDermott Tierney McGovern Titus McIntyre Tonko McMahon Towns McNerney Tsongas Meek (FL) Van Hollen Meeks (NY) Velázquez Michaud Miller (NC) Visclosky Walz Miller, George Wasserman Mollohan Schultz Moore (KS) Moore (WI) Waters Moran (VA) Watson Murphy (CT) Watt Murphy, Patrick Waxman Murtha Nadler (NY) Weiner Welch Napolitano Wexler Neal (MA) Wilson (OH) Oberstar Wu

NAYS—189

Burton (IN)

Obev

Blackburn Buyer Blunt Calvert Bonner Camp Campbell Bono Mack Boozman Cantor Boren Cao Boustany Capito Brady (TX) Carter Broun (GA) Cassidy Brown (SC) Castle Brown-Waite. Chaffetz Childers Ginny Buchanan Coble Coffman (CO) Burgess

Yarmuth

Cole

Conaway Crenshaw Davis (KY) Deal (GA) Dent Diaz-Balart, L. Diaz-Balart, M. Dreier Duncan Ehlers Emerson Fallin Fleming Forbes Fortenberry Foxx Franks (AZ) Frelinghuvsen Gallegly Garrett (NJ) Gerlach Gingrey (GA) Gohmert Goodlatte Granger Graves Griffith Guthrie Hall (TX) Harper Hastings (WA) Heller Hensarling Herger Hill Hoekstra Hunter Inglis Issa Jenkins Johnson (IL) Johnson, Sam Jones Jordan (OH) King (IA) King (NY) Kingston Kirk Kline (MN)

Kucinich Lamborn Lance Latham LaTourette Latta Lee (NY) Lewis (CA) Linder LoBiondo Lucas Luetkemever Lummis Lungren, Daniel \mathbf{E} Mack Manzullo Marchant Matheson McCarthy (CA) McCaul McClintock McCotter McHenry McHugh McKeon McMorris Rodgers Melancon Mica Miller (FL) Miller (MI) Miller, Garv Minnick Mitchell Moran (KS) Murphy, Tim Myrick Neugebauer Nunes Nve Olson Paulsen Pence Petri Pitts Platts Poe (TX)

Putnam Rehberg Reichert Roe (TN) Rogers (AL) Rogers (KY) Rogers (MI) Rohrabacher Rooney Ros-Lehtinen Roskam Ross Rovce Ryan (WI) Salazar Scalise Schmidt Schock Sensenbrenner Sessions Shadegg Shimkus Shuler Shuster Simpson Smith (NE) Smith (NJ) Smith (TX) Souder Stearns Taylor Terry Thompson (PA) Thornberry Tiahrt Tiberi Turner Upton Walden Wamp Westmoreland Whitfield Wilson (SC) Wittman Wolf Young (AK) Young (FL)

NOT VOTING-12

Ackerman Hastings (FL) Murphy (NY) Boehner Hoyer Radanovich Culberson Kennedy Sullivan Flake Lewis (GA) Woolsey

ANNOUNCEMENT BY THE SPEAKER PRO TEMPORE
The SPEAKER pro tempore (during the vote). Two minutes remain on this vote

Stated for:

Ms. WOOLSEY. Madam Speaker, on June 26, 2009, I was unavoidably detained and was not able to record my vote for rollcall No. 465.

Had I been present I would have voted: Rollcall No. 465—"yea"—On Ordering the Previous Question.

□ 1113

So the previous question was ordered. The result of the vote was announced as above recorded.

The SPEAKER pro tempore. The question is on the resolution.

The question was taken; and the Speaker pro tempore announced that the ayes appeared to have it.

RECORDED VOTE

Mr. SESSIONS. Madam Speaker, I demand a recorded vote.

A recorded vote was ordered.

The SPEAKER pro tempore. This will be a 5-minute vote.

The vote was taken by electronic device, and there were—ayes 217, noes 205, not voting 11, as follows:

[Roll No. 466]

AYES—217

Abercrombie Andrews Baca Adler (NJ) Arcuri Baldwin Lungren, Daniel Rogers (AL)

Gingrey (GA)

June 26, 26)09	C
Bean	Higgins	Pastor (AZ)
Becerra	Himes	Payne
Berkley	Hinchey	Perlmutter
Berman	Hinojosa	Perriello
Berry	Hirono	Peters
Bishop (GA)	Hodes	Peterson
Bishop (NY)	Holden	Pingree (ME)
Blumenauer	Honda	Polis (CO)
Boccieri	Hoyer	Pomeroy
Boswell	Inslee	Price (NC)
Boucher	Israel	Quigley
Boyd	Jackson (IL)	Rangel
Brady (PA)	Jackson-Lee	Reyes
Braley (IA)	(TX)	Richardson
Brown, Corrine Butterfield	Johnson (GA) Johnson, E. B.	Rodriguez
Capps	Kagen	Rothman (NJ)
Capuano	Kanjorski	Roybal-Allard
Cardoza	Kaptur	Ruppersberger
Carnahan	Kildee	Rush
Carson (IN)	Kilpatrick (MI)	Ryan (OH)
Castor (FL)	Kilroy	Sánchez, Linda
Chandler	Kind	Т.
Clarke	Kirkpatrick (AZ)	Sanchez, Loretta
Clay	Kissell	Sarbanes
Cleaver	Klein (FL)	Schakowsky
Clyburn	Kosmas	Schauer
Cohen	Kratovil	Schiff
Connolly (VA)	Langevin	Schrader
Conyers	Larsen (WA)	Schwartz
Cooper Costa	Larson (CT)	Scott (GA) Scott (VA)
Costello	Lee (CA) Levin	Serrano
Courtney	Lipinski	Sestak
Crowley	Loebsack	Shea-Porter
Cuellar	Lofgren, Zoe	Sherman
Cummings	Lowey	Sires
Davis (AL)	Luján	Skelton
Davis (CA)	Lynch	Slaughter
Davis (IL)	Maffei	Smith (WA)
DeGette	Markey (CO)	Snyder
Delahunt	Markey (MA)	Space
DeLauro	Massa	Speier
Dicks	Matsui	Spratt
Dingell	McCarthy (NY)	Stupak
Donnelly (IN)	McCollum	Sutton
Doyle Driehaus	McGovern	Tanner
Edwards (MD)	McIntyre	Tauscher
Edwards (TX)	McMahon	Teague
Ellison	McNerney	Thompson (CA)
Ellsworth	Meek (FL)	Thompson (MS)
Engel	Meeks (NY)	Tierney
Eshoo	Michaud	Titus
Etheridge	Miller (NC)	Tonko
Farr	Miller, George	Towns
Fattah	Moore (KS)	Tsongas Van Hollen
Filner	Moore (WI)	Vali Hollen Velázquez
Frank (MA)	Moran (VA)	Visclosky
Fudge	Murphy (CT)	Wasserman
Giffords Gonzalez	Murphy (NY) Murphy, Patrick	Schultz
Gordon (TN)	Murtha	Waters
Grayson	Nadler (NY)	Watson
Green, Al	Napolitano	Watt
Green, Gene	Neal (MA)	Weiner
Grijalva	Oberstar	Welch
Gutierrez	Obey	Wexler
Hall (NY)	Olver	Wilson (OH)
Hare	Ortiz	Woolsey
Heinrich	Pallone	Wu
Herseth Sandlin	Pascrell	Yarmuth

NOES-205

Aderholt	Bright	Crenshaw
Akin	Broun (GA)	Dahlkemper
Alexander	Brown (SC)	Davis (KY)
Altmire	Brown-Waite,	Davis (TN)
Austria	Ginny	Deal (GA)
Bachmann	Buchanan	DeFazio
Bachus	Burgess	Dent
Baird	Burton (IN)	Diaz-Balart, L.
Barrett (SC)	Buyer	Diaz-Balart, M
Barrow	Calvert	Doggett
Bartlett	Camp	Dreier
Barton (TX)	Campbell	Duncan
Biggert	Cantor	Ehlers
Bilbray	Cao	Emerson
Bilirakis	Capito	Fallin
Bishop (UT)	Carney	Fleming
Blackburn	Carter	Forbes
Blunt	Cassidy	Fortenberry
Boehner	Castle	Foster
Bonner	Chaffetz	Foxx
Bono Mack	Childers	Franks (AZ)
Boozman	Coble	Frelinghuysen
Boren	Coffman (CO)	Gallegly
Boustany	Cole	Garrett (NJ)
Brady (TX)	Conaway	Gerlach

dingrey (dri)	nungion, Damei	Trogers (TILL)
Gohmert	E.	Rogers (KY)
Goodlatte	Mack	Rogers (MI)
Granger	Manzullo	Rohrabacher
Graves	Marchant	Rooney
Griffith	Marshall	Ros-Lehtinen
Guthrie	Matheson	Roskam
Hall (TX)	McCarthy (CA)	Ross
Halvorson	McCaul	Royce
Harman	McClintock	Ryan (WI)
Harper	McCotter	Salazar
Hastings (WA)	McHenry	Scalise
Heller	McHugh	Schmidt
Hensarling	McKeon	Schock
Herger	McMorris	Sensenbrenner
Hill	Rodgers	Sessions
Hoekstra	Melancon	Shadegg
Holt	Mica	Shimkus
Hunter	Miller (FL)	Shuler
Inglis	Miller (MI)	Shuster
Issa	Miller, Gary	Simpson
Jenkins	Minnick	Smith (NE)
Johnson (IL)	Mitchell	Smith (NJ)
Johnson, Sam	Moran (KS)	Smith (TX)
Jones	Murphy, Tim	Souder
Jordan (OH)	Myrick	Stark
	Neugebauer	Stark
King (IA) King (NY)	Nunes	Taylor
	Nye	
Kingston	Olson	Terry
Kirk	Paul	Thompson (PA)
Kline (MN)	Paulsen	Thornberry
Kucinich	Pence	Tiahrt
Lamborn	Petri	Tiberi
Lance	Pitts	Turner
Latham	Platts	Upton
LaTourette	Poe (TX)	Walden
Latta	Posey	Wamp
Lee (NY)	Price (GA)	Westmoreland
Lewis (CA)	Putnam	Whitfield
Linder	Radanovich	Wilson (SC)
LoBiondo	Rahall	Wittman
Lucas	Rehberg	Wolf
Luetkemeyer	Reichert	Young (AK)
Lummis	Roe (TN)	Young (FL)
	NOT VOTING—	11

NOT VOTING-11

Ackerman	Kennedy	Sullivan
Culberson	Lewis (GA)	Walz
Flake Hastings (FL)	Maloney Mollohan	Waxman

ANNOUNCEMENT BY THE SPEAKER PRO TEMPORE

The SPEAKER pro tempore (during the vote). There are 2 minutes remaining on this vote.

□ 1122

So the resolution was agreed to.

The result of the vote was announced as above recorded.

A motion to reconsider was laid on the table.

Stated for:

Mr. WALZ. Madam Speaker, on rollcall No. 466, my intention to support the rule on 466 was not electronically recorded. Had I been present, I would have voted "aye."

DEPARTMENT OF THE INTERIOR, ENVIRONMENT, AND RELATED APPROPRIATIONS AGENCIES ACT. 2010

The SPEAKER pro tempore. Pursuant to House Resolution 578 and rule XVIII. the Chair declares the House in the Committee of the Whole House on the State of the Union for the further consideration of the bill, H.R. 2996.

\Box 1123

IN THE COMMITTEE OF THE WHOLE

Accordingly, the House resolved itself into the Committee of the Whole House on the State of the Union for the further consideration of the bill (H.R. 2996) making appropriations for the Department of the Interior, environment, and related agencies for the fiscal year ending September 30, 2010, and for other purposes, with Mr. LYNCH (Acting Chair) in the chair.

The Clerk read the title of the bill.

The Acting CHAIR. When the Committee of the Whole rose on Thursday, June 25, 2009, a request for a recorded vote on amendment No. 4 printed in part C of House Report 111-184 by the gentleman from California (Mr. CAMP-BELL) had been postponed and the bill had been read through page 119, line 22.

Pursuant to clause 6 of rule XVIII, proceedings will now resume on those amendments on which further proceedings were postponed, in the following order:

Amendment No. 1 printed in part A by Mr. Dicks of Washington.

Amendment No. 3 printed in part B by Mr. Heller of Nevada.

Amendment No. 4 printed in part B by Mr. JORDAN of Ohio.

Amendment No. 6 printed in part B by Mr. Stearns of Florida.

Amendment No. 1 printed in part C by Mr. Campbell of California.

Amendment No. 3 printed in part D by Mr. Campbell of California.

Amendment No. 3 printed in part C by Mr. Campbell of California.

Amendment No. 1 printed in part E by Mr. Campbell of California.

Amendment No. 4 printed in part C

by Mr. Campbell of California. The Chair will reduce to 2 minutes

the time for any electronic vote after the first vote in this series.

PART A AMENDMENT NO. 1 OFFERED BY MR. DICKS

The Acting CHAIR. The unfinished business is the demand for a recorded vote on the amendment offered by the gentleman from Washington DICKS) on which further proceedings were postponed and on which the ayes prevailed by voice vote.

The Clerk will redesignate amendment.

The text of the amendment is as follows:

Part A amendment No. 1 offered by Mr.

DICKS:

In the item relating to "Office of Surface Reclamation and Enforce-Abandoned Mine Reclamation Fund" (page 26, line 2), before the period at the end insert ": Provided further, That funds made available under title IV of Public Law 95-87 may be used for any required non-Federal share of the cost of projects funded by the Federal Government for the purpose of environmental restoration related to treatment or abatement of acid mine drainage from abandoned mines: Provided further, That such projects must be consistent with the purposes and priorities of the Surface Mining Control and Reclamation Act'

Page 18, line 11, after the dollar amount, insert "(increased by \$10,000,000)".

Page 18, line 13, after the dollar amount, insert "(increased by \$10,000,000)"

Page 46, line 2, after the dollar amount, insert "(reduced by \$10,000,000)"

Page 16, line 25, after the dollar amount, insert "(increased by \$1,000,000)"

Page 17, line 3, after the dollar amount, insert "(increased by \$1,000,000)"

Page 17, line 18, after the dollar amount, insert "(reduced by \$1,000,000)".

Mr. SIMPSON. Mr. Chairman, I withdraw my demand for a recorded vote on amendment No. 1.

The Acting CHAIR. The demand for a recorded vote is withdrawn.

Pursuant to the voice amendment is agreed to.

PART B AMENDMENT NO. 3 OFFERED BY MR. HELLER.

The Acting CHAIR. The unfinished business is the demand for a recorded vote on the amendment offered by the gentleman from Nevada (Mr. HELLER) on which further proceedings were postponed and on which the noes prevailed by voice vote.

Clerk will redesignate amendment

The text of the amendment is as follows:

Part B amendment No. 3 offered by Mr. HELLER:

Page 119, after line 22, insert the following: None of the funds made avail-SEC. able by this Act may be used to build a Carson Interagency Fire Facility on the approximately 15 acres of Federal land managed by the Bureau of Land Management and located east of the corner of South Edmonds Drive and Koontz Lane in Carson City, Neva.da.

RECORDED VOTE

The Acting CHAIR. A recorded vote has been demanded.

A recorded vote was ordered.

The vote was taken by electronic device, and there were—ayes 202, noes 225, not voting 12, as follows:

[Roll No. 467]

AYES-202

Aderholt Davis (KY) Kucinich Akin Deal (GA) Lamborn Alexander Dent Lance Diaz-Balart, M. Latham Altmire Arcuri Donnelly (IN) Latta Lee (NY) Austria Dreier Bachmann Duncan Lewis (CA) Bachus Ehlers Linder Barrett (SC) Ellsworth LoBiondo Bartlett Emerson Lucas Barton (TX) Fallin Luetkemeyer Bean Fleming Lummis Berkley Forbes Fortenberry Lungren, Daniel Biggert \mathbf{E} Mack Bilbray Foxx Bilirakis Franks (AZ) Manzullo Bishop (UT) Frelinghuvsen Marchant Blackburn Gallegly Marshall Massa Blunt Garrett (NJ) Boccieri Gerlach Matheson Boehner Giffords McCarthy (CA) Bonner Gingrey (GA) McCaul Bono Mack McClintock Gohmert Boozman Goodlatte McCotter Boren Granger McHenry Boustany McHugh Graves Griffith Brady (TX) McKeon Bright Guthrie McMahon Broun (GA) Hall (TX) McMorris Halvorson Brown (SC) Rodgers Brown-Waite, Harper Mica. Ginny Hastings (WA) Michaud Burgess Heinrich Miller (FL) Burton (IN) Heller Miller (MI) Hensarling Minnick Buyer Calvert Mitchell Herger Herseth Sandlin Moran (KS) Camp Campbell Hodes Murphy (NY) Murphy, Tim Cantor Hoekstra Cao Hunter Myrick Nadler (NY) Capito Inglis Carter Issa Jenkins Neugebauer Cassidy Nunes Johnson (IL) Castle Olson Chaffetz Johnson, Sam Paul Coble Jones Paulsen Coffman (CO) Jordan (OH) Pence Cole King (IA) Perriello Conaway King (NY) Petri Crenshaw Kingston Pitts Culberson Kirk Platts Klein (FL) Poe (TX) Cummings

Posey Price (GA) Putnam Radanovich Rehberg Reichert Reves Roe (TN) Rogers (AL) Rogers (KY) Rogers (MI) Rohrabacher Rooney Ros-Lehtinen Roskam Royce Ryan (WI)

Abercrombie

Ackerman

Adler (NJ)

Andrews

Baldwin

Barrow

Becerra

Berman

Bishop (GA)

Bishop (NY)

Blumenauer

Brady (PA)

Braley (IA)

Butterfield

Boucher

Boyd

Capps

Capuano

Cardoza

Carney

Carnahan

Carson (IN)

Castor (FL)

Christensen

Chandler

Childers

Clarke

Cleaver

Clyburn

Conyers

Costello

Courtney

Crowley

Cuellar

Dahlkemper

Davis (AL)

Davis (CA)

Davis (IL)

Davis (TN)

DeFazio

DeGette

Delahunt

DeLauro

Dicks

Doyle

Dingell

Doggett

Driehaus

Ellison

Engel

Eshoo

Farr

Fattah

Filner

Foster

Fudge

Gonzalez

Gravson

Green, Al

Bordallo

Buchanan

Etheridge

Faleomavaega

Frank (MA)

Gordon (TN)

Green, Gene

Edwards (MD)

Edwards (TX)

Cooper

Costa

Connolly (VA)

Cohen

Clay

Berry

Baca

Baird

Scalise Thornberry Schmidt Tiahrt Schock Tiberi Sensenbrenner Titus Sessions Turner Shadegg Unton Shimkus Walden Shuster Wamp Simpson Westmoreland Smith (NE) Whitfield Smith (NJ) Wilson (SC) Smith (TX) Wittman Souder Wolf Stearns Young (AK) Taylor Young (FL) Terry Thompson (PA)

NOES-225

Grijalva Pastor (AZ) Gutierrez Payne Hall (NY) Perlmutter Hare Peters Harman Peterson Higgins Pierluisi Pingree (ME) Hill Himes Polis (CO) Hinchey Pomeroy Hinojosa Price (NC) Hirono Quigley Holden Rahall Holt. Rangel Honda Richardson Hoyer Rodriguez Inslee Ross. Rothman (NJ) Israel Jackson (IL) Roybal-Allard Jackson-Lee Ruppersberger Brown, Corrine (TX) Rush Johnson (GA) Ryan (OH) Johnson, E. B. Sablan Salazar Kagen Sánchez, Linda Kanjorski Kaptur T. Kildee Sanchez, Loretta Kilroy Sarbanes Schakowsky Kind Kirkpatrick (AZ) Schauer Kissell Schiff Schrader Kosmas Kratovil Schwartz Langevin Scott (GA) Larsen (WA) Scott (VA) Larson (CT) Serrano LaTourette Sestak Shea-Porter Lee (CA) Levin Sherman Lipinski Shuler Loebsack Sires Lofgren, Zoe Skelton Lowey Slaughter Smith (WA) Luián Lynch Snyder Maffei Space Maloney Speier Markey (CO) Spratt Markey (MA) Stark Matsui Stupak McCarthy (NY) Sutton McCollum Tanner McDermott Tauscher Teague McGovernThompson (CA) McIntyre McNerney Thompson (MS) Meek (FL) Tierney Tonko Meeks (NY) Melancon Towns Miller (NC) Tsongas Van Hollen Miller, George Mollohan Velázquez Moore (KS) Moore (WI) Visclosky Walz Moran (VA) Wasserman Murphy (CT) Murphy, Patrick Schultz Waters Murtha Watson Napolitano Neal (MA) Watt Waxman Nye Weiner Oberstar Welch Obey Wexler Olver Wilson (OH) Ortiz Woolsey Pallone

NOT VOTING-12

Pascrell

Diaz-Balart, L Hastings (FL) Flake Kennedy

Yarmuth

Kilpatrick (MI) Lewis (GA) Norton Kline (MN) Miller, Gary Sullivan ANNOUNCEMENT BY THE ACTING CHAIR The Acting CHAIR (during the vote). Members have 2 minutes remaining.

\Box 1145

Mr. ADLER of New Jersey and Ms. SCHWARTZ changed their vote from "aye" to "no.

Messrs MASSA, TAYLOR, HALVORSON, Messrs. DONNELLY of Indiana and ARCURI changed their vote from "no" to "aye."

So the amendment was rejected. The result of the vote was announced

as above recorded.

Stated for:

Ms. BORDALLO. Mr. Chair, I was delayed in arriving to the Chamber earlier today to cast my vote in the Committee of the Whole House on the State of the Union on the question of adopting the amendment offered by Mr. HELL-ER of Nevada to H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act for Fiscal Year 2010. Had I been present and able to cast my vote, I would have voted "aye" in support of this amendment (rollcall vote 467).

\Box 1145

unanimous Mrs. (Bv consent. TAUSCHER was allowed to speak out of

CONFIRMATION OF CONGRESSWOMAN TAUSCHER BY U.S. SENATE AS UNDER SECRETARY OF

Mrs. TAUSCHER. Mr. Chairman and my colleagues, I rise to announce that I have been confirmed by the United States Senate as Under Secretary of State for Arms Control and International Security. I have informed my friend, the Speaker of the House, and the Governor of California that I will be resigning my seat at the end of votes today.

Madam Speaker, Mr. Chairman, I am deeply grateful for the trust that both President Obama and Secretary Clinton have placed in me. I am equally grateful and humbled by the honor and privilege to have represented California's 10th Congressional District for the last 13 years in the House of Representatives. It has been the deepest and greatest professional experience of my life, and I am deeply, deeply grateful for the opportunity and the trust that my constituents have placed in me.

In my seven terms in the Congress, I have tried to keep my promise of being an independent and effective moderate. I have worked hard, and I have worked with you. I look around the room; many Members I have served with for the entire time I have been here, and some of you I have flown on planes with and some of you I have taken codels with.

What I know is that we sit here and we do the people's work, and whether we agree or not doesn't always matter. What is most important is that we represent our constituents, that we honor the Constitution, and we keep faith with our conscience. Those are the

three Cs that I have tried for these years to maintain in balance. It's not always easy, but I have tried.

I look at all of you and I understand how difficult this world is and how troubling the lives of many Americans are now and how heavy the burden is on you.

What I pledge to you, as I leave the legislative branch in this great House that I have grown to love and all of you that I love, and my constituents that I love, what I promise you in my new capacity is to work with you to achieve what we all know is important, to make sure that we have the safety and the security of the American people always on the forefront of our minds.

I have been blessed to have, I think, some of the best staff in the world. I have always told people I represent the smartest people in the world. I have the two national nuclear labs in Livermore, California, and I have Travis Air Force Base and 600-some-odd thousand constituents who apparently, now, 100 percent of them have voted for me every time. There's nothing like leaving to become popular.

But I just want to thank the staff who have worked with me, both on the subcommittee and my personal staff and my district staff, that have been just absolutely fabulous.

I want to thank my friends in the House, my friends that started as friends and became family and who have sustained me and with whom I have learned so much.

I want to thank the Speaker for her indefatigable energy. I want to thank STENY HOYER. I want to thank my partner in my county, George Miller. I want to thank IKE SKELTON and JIM OBERSTAR, my chairmen, for being so generous and for helping me learn.

I want to thank, again, my constituents for the honor. I especially want to thank my family, my parents and my sisters and brothers and my friends who have been patient and understanding when I couldn't be at birthday parties and volleyball games.

I want to thank my daughter, who was raised in the House. She came here as a 5½-year-old. She is now going to college, and I am so thrilled that she is emancipated and happy and healthy and a smart young woman. And you should be as proud of her as I am, because you helped raise her.

And I want to thank, especially, my fiance, Jim Cieslak, who I will marry tomorrow. Thank you. It's hard to be a blushing bride at my age, but I will do my best.

Let me just close and say that no matter where I am serving in government, I will always remember those that sent me here, and I will always be grateful for your trust and support.

I just want to take a second and say that I have been honored to represent the Speaker on the podium. There's nothing like having the view from up there, because the view from up there is of all of you, and that's the best view I have had, I think, in my life. I will

take that in my heart as I go to the State Department.

I want to thank all the people behind the scenes who work so hard to make sure that we do the job that we do.

I am not saying goodbye, I am just saying farewell for the time being. I expect I will work with you all very well, but know that this has been the best experience of my life.

God bless you. God bless America.

ANNOUNCEMENT BY THE ACTING CHAIR

The Acting CHAIR. Without objection, 2-minute voting will continue.

PART B AMENDMENT NO. 4 OFFERED BY MR. JORDAN OF OHIO

The Acting CHAIR. The unfinished business is the demand for a recorded vote on the amendment offered by the gentleman from Ohio (Mr. JORDAN) on which further proceedings were postponed and on which the noes prevailed by voice vote.

The Clerk will redesignate amendment.

The text of the amendment is as fol-

Part B amendment No. 4 offered by Mr. JORDAN of Ohio:

At the end of the bill (before the short title), insert the following:

SEC. Appropriations made in this Act are hereby reduced in the amount of \$5,750,000,000.

RECORDED VOTE

The Acting CHAIR. A recorded vote has been demanded.

A recorded vote was ordered.

The Acting CHAIR. This will be a 2minute vote

The vote was taken by electronic device, and there were—ayes 169, noes 259, not voting 11, as follows:

[Roll No. 468]

AYES-169 Coble Aderholt Jones Adler (NJ) Coffman (CO) Jordan (OH) Akin Cole King (IA) Alexander Conaway King (NY) Altmire Crenshaw Kingston Kirkpatrick (AZ) Arcuri Culberson Davis (KY) Austria Kline (MN) Bachmann Deal (GA) Kosmas Bachus Dent Lamborn Diaz-Balart, L. Barrett (SC) Lance Bartlett Diaz-Balart, M. Latham Barton (TX) Dreier Latta Lee (NY) Bean Duncan Biggert Emerson Lewis (CA) Fallin Linder Bilbray Bilirakis Fleming Lucas Bishop (UT) Forbes Luetkemeyer Blackburn Foxx Lummis Franks (AZ) Lungren, Daniel Blunt Bonner Gallegly E. Garrett (NJ) Bono Mack Mack Boozman Giffords Manzullo Boustany Gingrey (GA) Marchant Brady (TX) McCarthy (CA) Gohmert Goodlatte Bright McCaul Broun (GA) McClintock Granger Brown (SC) Graves McCotter McHenry Brown-Waite Guthrie Hall (TX) Ginny McKeon Buchanan Harper McMahon Burgess Hastings (WA) McMorris Burton (IN) Heller Rodgers Buyer Hensarling Mica Miller (FI.) Calvert Herger Camp Himes Miller (MI) Campbell Hoekstra Miller, Garv Cantor Hunter Mitchell Moran (KS) Capito Inglis Carter Murphy, Patrick Cassidy Johnson (II.) Myrick Chaffetz Neugebauer Johnson, Sam

Rogers (MI) Rohrabacher Nve Rooney Pa.111 Ros-Lehtinen Paulsen Roskam Royce Rvan (WI) Petri Pitts Scalise Poe (TX) Schmidt Posey Price (GA) Schock Sensenbrenner Putnam Sessions Radanovich Shadegg Rehberg Shimkus Roe (TN) Shuster Rogers (AL) Simpson Rogers (KY) Smith (NE)

Smith (TX) Souder Stearns Taylor Terry Thompson (PA) Thornberry Tiahrt Tiberi Wamp Westmoreland Whitfield Wilson (SC) Wittman Wolf

NOES-259

Abercrombie Gerlach Ackerman Gonzalez Andrews Gordon (TN) Baca Grayson Green, Al Baird Green, Gene Baldwin Griffith Barrow Becerra Grijalva Berkley Gutierrez Berman Hall (NY) Berry Halvorson Bishop (GA) Bishop (NY) Harman Blumenauer Heinrich Herseth Sandlin Boccieri Bordallo Higgins Boren Hill Boswell Hinchey Boucher Hinoiosa Boyd Hirono Brady (PA) Hodes Braley (IA) Holden Butterfield Holt Cao Honda Capps Hover Capuano Inslee Cardoza Israel Jackson (IL) Carnahan Carney Jackson-Lee Carson (IN) (TX) Jenkins Castle Castor (FL) Johnson (GA) Chandler Johnson, E. B. Childers Kagen Kanjorski Christensen Clarke Kantur Clay Kildee Cleaver Kilroy Clyburn Kind Cohen Kirk Connolly (VA) Kissell Klein (FL) Convers Cooper Kratovil Costa Kucinich Costello Langevin Courtney Larsen (WA) Crowley Larson (CT) Cuellar LaTourette Cummings Lee (CA) Dahlkemper Levin Lipinski Davis (AL) Davis (CA) LoBiondo Davis (IL) Loebsack Lofgren, Zoe Davis (TN) DeFazio Lowey DeGette Luján Delahunt Lvnch DeLauro Maffei Dicks Maloney Dingell Markey (CO) Doggett Markey (MA) Donnelly (IN) Marshall Doyle Massa Driehaus Matheson Edwards (MD) Matsui McCarthy (NY) Edwards (TX) Ehlers McCollum McDermott Ellison Ellsworth McGovern Engel McHugh Eshoo McIntyre Etheridge McNerney Faleomavaega Meek (FL) Fattah Meeks (NY) Filner Melancon Fortenberry Michaud Miller (NC) Foster Frank (MA) Miller, George Frelinghuysen Mollohan

Moore (WI) Moran (VA) Murphy (CT) Murphy (NY) Murphy, Tim Murtha Nadler (NY) Napolitano Neal (MA) Oberstar Obey Olver Ortiz Pallone Pascrell Pastor (AZ) Payne Perlmutter Perriello Peters Peterson Pierluisi Pingree (ME) Platts Polis (CO) Pomeroy Price (NC) Quigley Rahall Rangel Reichert Reves Richardson Rodriguez Rothman (N.I) Roybal-Allard Ruppersberger Rush Ryan (OH) Sablan Salazar Sánchez, Linda Sanchez, Loretta Sarbanes Schakowsky Schauer Schiff Schrader Schwartz Scott (GA) Scott (VA) Serrano

Sestak

Sherman

Shuler

Skelton

Snyder

Space

Speier

Spratt

Stupak

Sutton

Tanner

Tauscher

Thompson (CA)

Thompson (MS)

Teague

Tierney Titus

Tonko

Towns Tsongas

Moore (KS)

Fudge

Stark

Slaughter

Smith (NJ) Smith (WA)

Sires

Shea-Porter

Turner Wasserman Wexler Schultz Wilson (OH) Upton Van Hollen Waters Woolsey Velázquez Watson Wu Watt Visclosky Yarmuth Waxman Walden Young (AK) Weiner Walz Young (FL) Welch

NOT VOTING-11

Hastings (FL) Minnick Boehner Brown, Corrine Kennedy Norton Kilpatrick (MI) Sullivan Flake Lewis (GA)

ANNOUNCEMENT BY THE ACTING CHAIR

The Acting CHAIR (during the vote). There is 1 minute remaining in this vote.

□ 1158

So the amendment was rejected. The result of the vote was announced as above recorded.

PART B AMENDMENT NO. 6 OFFERED BY MR. STEARNS

The Acting CHAIR. The unfinished business is the demand for a recorded vote on the amendment offered by the gentleman from Florida (Mr. STEARNS) on which further proceedings were postponed and on which the noes prevailed by voice vote.

The Clerk will redesignate amendment.

The text of the amendment is as fol-

Part B amendment No. 6 offered by Mr. STEARNS:

At the end of the bill (before the short title), insert the following:

. Each amount appropriated or otherwise made available by this Act for the Environmental Protection Agency that is not required to be appropriated or otherwise made available by a provision of law is hereby reduced by 38 percent.

RECORDED VOTE

The Acting CHAIR. A recorded vote has been demanded.

A recorded vote was ordered.

The Acting CHAIR. This is a minute vote.

The vote was taken by electronic device, and there were—ayes 170, noes 261, not voting 8, as follows:

[Roll No. 469]

AYES-170

Aderholt Buyer Foxx Akin Calvert Franks (AZ) Alexander Camp Frelinghuvsen Campbell Austria Gallegly Garrett (NJ) Bachmann Cantor Bachus Gingrev (GA) Cao Capito Barrett (SC) Gohmert Bartlett Carter Goodlatte Barton (TX) Cassidy Granger Biggert Castle Bilbray Chaffetz Guthrie Hall (TX) Bilirakis Childers Bishop (UT) Coble Harper Coffman (CO) Hastings (WA) Blackburn Cole Heller Blunt Boehner Conaway Hensarling Bonner Crenshaw Herger Bono Mack Culberson Hoekstra Boozman Davis (KY) Hunter Deal (GA) Boustany Inglis Brady (TX) Dent Issa Diaz-Balart, L Bright Jenkins Broun (GA) Johnson (IL) Diaz-Balart, M. Brown (SC) Dreier Johnson, Sam Brown-Waite Duncan Jones Jordan (OH) Ginny Emerson Buchanan Fallin King (IA) Fleming King (NY) Burgess Burton (IN) Forbes Kingston

Kirkpatrick (AZ) Miller (MI) Kline (MN) Miller, Gary Schock Kratovil Mitchell Lamborn Moran (KS) Myrick Latham Neugebauer Latta Lee (NY) Nunes Lewis (CA) Olson Linder Paul Lucas Pence Luetkemeyer Petri Souder Lummis Pitts Lungren, Daniel Poe (TX) Tanner E. Posey Taylor Price (GA) Mack Manzullo Putnam Marchant Radanovich Tia.hrt. Massa Rehberg Tiberi McCarthy (CA) Roe (TN) Upton McCaul Rogers (AL) McClintock Rogers (KY) Wamp McCotter Rogers (MI) McHenry Rohrabacher Rooney Ros-Lehtinen McHugh McKeon McMorris Roskam Rodgers Royce Wolf Ryan (WI) Mica Miller (FL) Scalise

NOES-261

Abercrombie

Ackerman

Adler (NJ)

Altmire

Andrews

Baldwin

Barrow

Becerra

Berkley

Berman

Bishop (GA)

Bishop (NY)

Blumenauer

Boccieri

Bordallo

Boren

Boswell

Boucher

Brady (PA)

Braley (IA)

Butterfield

Brown Corrine

Boyd

Capps Capuano

Cardoza

Carnev

Carnahan

Carson (IN)

Castor (FL)

Chandler

Clarke

Cleaver

Clyburn

Conyers

Costello

Courtney

Crowlev

Cuellar

Cummings

Dahlkemper

Davis (AL)

Davis (CA)

Davis (IL)

Davis (TN)

DeFazio

DeGette

Delahunt

DeLauro

Dingell

Doggett

Doyle

Ehlers

Driehaus

Donnelly (IN)

Edwards (MD)

Edwards (TX)

Loebsack

Dicks

Cooper

Costa

Connolly (VA)

Cohen

Clay

Berry

Bean

Arcuri

Ba.ca.

Baird

Ellison Ellsworth Lofgren, Zoe Lowey Luján Engel Eshoo Lynch Maffei Etheridge Faleomavaega Maloney Markey (CO) Markey (MA) Farr Fattah Filner Marshall Fortenberry Matheson Matsui Foster Frank (MA) McCarthy (NY) Fudge McCollum Gerlach McDermott Giffords McGovern Gonzalez McIntyre Gordon (TN) McMahon Grayson McNernev Green, Al Meek (FL) Green, Gene Meeks (NY) Griffith Melancon Grijalva Michaud Miller (NC) Gutierrez Hall (NY) Miller George Halvorson Minnick Hare Mollohan Harman Moore (KS) Moore (WI) Heinrich Herseth Sandlin Moran (VA) Higgins Murphy (CT) Murphy (NY) Hill Himes Murphy, Patrick Hinchev Murphy, Tim Hinojosa Murtha Nadler (NY) Hirono Hodes Napolitano Holden Neal (MA) Holt Nye Honda Oberstar Hoyer Obey Inslee Olver Ortiz Israel Jackson (IL) Pallone Jackson-Lee Pascrell Pastor (AZ) (TX) Johnson (GA) Paulsen Johnson, E. B. Payne Perlmutter Kagen Kanjorski Perriello Kaptur Peters Peterson Kildee Pierluisi Kilroy Pingree (ME) Kind Platts Kirk Kissell Polis (CO) Klein (FL) Pomerov Price (NC) Kosmas Kucinich Quigley Lance Rahall Langevin Rangel Larsen (WA) Reichert Larson (CT) Reves LaTourette Richardson Lee (CA) Rodriguez Levin Ross Lipinski Rothman (NJ) Roybal-Allard Ruppersberger LoBiondo

Schmidt Sensenbrenner Sessions Shadegg т Shimkus Shuster Simpson Smith (NE) Smith (TX) Schiff Stearns Thompson (PA) Thornberry Sestak Shuler Walden Westmoreland Whitfield Wilson (SC) Wittman Young (AK) Young (FL)

Towns Sires Ryan (OH) Skelton Tsongas Sablan Slaughter Turner Van Hollen Salazar Smith (NJ) Sánchez, Linda Smith (WA) Velázquez Snyder Visclosky Sanchez, Loretta Space Walz Wasserman Sarbanes Speier Schakowsky Spratt Schultz Waters Schauer Stark Stupak Watson Schrader Sutton Watt Waxman Schwartz Tauscher Scott (GA) Teague Weiner Scott (VA) Terry Welch Thompson (CA) Wexler Serrano Thompson (MS) Wilson (OH) Shea-Porter Tiernev Woolsey Sherman Titus Wu Tonko Yarmuth NOT VOTING-Kennedy Norton

Christensen Kilpatrick (MI) Flake Sullivan Hastings (FL) Lewis (GA)

ANNOUNCEMENT BY THE ACTING CHAIR The Acting CHAIR (during the vote). Members have 1 minute remaining.

\Box 1203

So the amendment was rejected. The result of the vote was announced as above recorded.

PERSONAL EXPLANATION

Ms. NORTON. Mr. Chair, on rollcall Nos. 467, 468 and 469 during the consideration of H.R. 2996, I was unavoidably detained. Had I been present, I would have voted "no."

PART C AMENDMENT NO. 1 OFFERED BY MR. CAMPBELL

The Acting CHAIR. The unfinished business is the demand for a recorded vote on the amendment offered by the gentleman from California (Mr. CAMP-BELL) on which further proceedings were postponed and on which the noes prevailed by voice vote.

The Clerk will redesignate amendment.

The text of the amendment is as fol-

Part C amendment No. 1 offered by Mr. CAMPBELL:

At the end of the bill (before the short title), insert the following:

. None of the funds provided in this Act under the heading "National Park Service-Construction" shall be available for the Restore Good Fellow Lodge project at Indiana Dunes National Lakeshore in Porter, Indiana, and the amount otherwise provided under such heading is hereby reduced by \$1,000,000.

Mr. CAMPBELL, Mr. Chairman, I ask unanimous consent to withdraw my demand for a recorded vote on all remaining amendments.

The Acting CHAIR. Is there objection to the request of the gentleman from California?

Mr. DICKS. Objection.

The Acting CHAIR. Objection is

Mr. CAMPBELL. Mr. Chairman, I withdraw my demand for a recorded vote on the next amendment. No. 1.

The Acting CHAIR. The demand for a recorded vote is withdrawn.

RECORDED VOTE

Mr. DICKS. Mr. Chairman, I demand a recorded vote.

Schwartz

Hoyer

The Acting CHAIR. A recorded vote has been demanded.

A recorded vote was ordered.

The Acting CHAIR. This will be a 2minute vote.

The vote was taken by electronic device, and there were—ayes 123, noes 305, not voting 11, as follows:

[Roll No. 470] AYES-123

Akin Fortenberry McMorris Alexander Foxx Rodgers Austria Franks (AZ) Miller (FL) Bachmann Gallegly Miller (MI) Garrett (NJ) Barrett (SC) Minnick Bartlett Gerlach Mitchell Bilbray Giffords Moran (KS) Gingrey (GA) Bilirakis Myrick Bishop (UT) Gohmert Neugebauer Goodlatte Blackburn Nunes Blunt Graves Olson Boehner Harper Paul Bono Mack Heller Paulsen Hensarling Boozman Pence Boustany Herger Petri Brady (TX) Hoekstra Pitts Bright Hunter Platts Broun (GA) Inglis Poe (TX) Brown (SC) Posev Issa Brown-Waite, Jenkins Price (GA) Johnson, Sam Ginny Putnam Radanovich Burgess Jones Burton (IN) Jordan (OH) Roe (TN) Rogers (MI) Buver King (IA) Rohrabacher Camp Kingston Campbell Kline (MN) Rooney Cantor Lamborn Royce Ryan (WI) ${\bf Carter}$ Lance Cassidy Latta Scalise Castle Linder Schauer Chaffetz Luetkemeyer Schmidt Coffman (CO) Lummis Sensenbrenner Lungren, Daniel Conaway Sessions Cooper Shadegg Davis (KY) Deal (GA) Mack Smith (NE) Manzullo Stearns McCarthy (CA) Dent Terry Duncan McCaul Thornberry McClintock Ehlers Tiahrt McCotter Westmoreland Fallin McHenry Fleming Wilson (SC) McKeon Wittman Forbes

NOES-305

Carson (IN) Abercrombie Ellison Castor (FL) Ackerman Ellsworth Aderholt Chandler Emerson Adler (N.I) Childers Engel Altmire Christensen Eshoo Andrews Clarke Etheridge Arcuri Clav Faleomavaega Baca Cleaver Farr Bachus Clyburn Fattah Baird Coble Filner Baldwin Cohen Foster Barrow Cole Frank (MA) Barton (TX) Connolly (VA) Frelinghuvsen Bean Conyers Fudge Becerra Costa Gonzalez Gordon (TN) Costello Berkley Berman Courtney Granger Berry Crenshaw Grayson Biggert Crowlev Green, Al Cuellar Green, Gene Bishop (GA) Bishop (NY) Culberson Griffith Cummings Grijalva Blumenauer Boccieri Dahlkemper Guthrie Bonner Davis (AL) Gutierrez Bordallo Davis (CA) Hall (NY) Davis (IL) Hall (TX) Boren Boswell Davis (TN) Halvorson Boucher DeFazio Hare Boyd DeGette Harman Brady (PA) Hastings (WA) Delahunt Braley (IA) DeLauro Heinrich Brown, Corrine Diaz-Balart, L Herseth Sandlin Diaz-Balart, M. Buchanan Higgins Butterfield Dicks Calvert Dingell Himes Cao Doggett Hinchey Capito Donnelly (IN) Hinojosa Doyle Hirono Capps Capuano Hodes Dreier Holden Cardoza Driehaus Edwards (MD) Carnahan Holt. Honda

Edwards (TX)

Carney

Miller, Gary Miller, George Inslee Scott (GA) Israel Mollohan Scott (VA) Jackson (IL) Moore (KS) Sestak Jackson-Lee Moore (WI) Shea-Porter (TX) Moran (VA) Sherman Johnson (GA) Murphy (CT) Shimkus Murphy (NY) Johnson (IL) Shuler Johnson, E. B. Murphy, Patrick Shuster Kagen Murphy, Tim Simpson Kanjorski Murtha Sires Nadler (NY) Kaptur Skelton Napolitano Kildee Slaughter Kilroy Neal (MA) Smith (NJ) King (NY) Norton Smith (TX) Kirk Nye Smith (WA) Kirkpatrick (AZ) Oberstar Snyder Kissell Obev Souder Klein (FL) Olver Space Kosmas Ortiz Speier Kratovil Pallone Spratt Kucinich Pascrell Stark Langevin Pastor (AZ) Stupak Larsen (WA) Payne Sutton Larson (CT) Perlmutter Tanner Latham Perriello Tauscher LaTourette Peters Taylor Lee (CA) Peterson Teague Lee (NY) Pierluisi Thompson (CA) Pingree (ME) Levin Thompson (MS) Lewis (CA) Polis (CO) Thompson (PA) Lipinski Pomeroy Tiberi Price (NC) LoBiondo Tiernev Loebsack Quigley Titus Lofgren, Zoe Rahall Tonko Lowey Rangel Towns Lucas Rehberg Tsongas Luján Reichert Turner Reves Lvnch Upton Maffei Richardson Van Hollen Maloney Rodriguez Rogers (AL) Velázquez Marchant Rogers (KY) Visclosky Markey (CO) Walden Marshall Ros-Lehtinen Walz Roskam Massa Matheson Wamp Ross Wasserman Rothman (NJ) Matsui McCarthy (NY) Schultz Roybal-Allard Waters Ruppersberger McCollum Watson McDermott Rush Watt McGovern Ryan (OH) Weiner McHugh Sablan Welch McIntyre Salazar McMahon Sánchez, Linda Whitfield Wilson (OH) McNerney T. Sanchez, Loretta Wolf Meek (FL) Meeks (NY) Sarbanes Woolsey Melancon Schakowsky Wıı Yarmuth Schiff Mica Young (AK) Michaud Schock Miller (NC) Schrader Young (FL)

NOT VOTING-11

Flake Kind Sullivan Hastings (FL) Lewis (GA) Waxman Markey (MA) Kennedy Wexler Kilpatrick (MI)

ANNOUNCEMENT BY THE ACTING CHAIR The Acting CHAIR (during the vote). There is 1 minute remaining.

□ 1208

So the amendment was rejected. The result of the vote was announced as above recorded

PART D AMENDMENT NO. 3 OFFERED BY MR. CAMPBELL

The Acting CHAIR. The unfinished business is the demand for a recorded vote on the amendment offered by the gentleman from California (Mr. CAMP-BELL) on which further proceedings were postponed and on which the noes prevailed by voice vote.

The Clerk will redesignate amendment.

The text of the amendment is as follows:

Part D amendment No. 3 offered by Mr. CAMPBELL:

At the end of the bill (before the short title), insert the following:

. None of the funds provided in this Act under the heading "National Park Service—Historic Preservation Fund" shall be available for the Village Park Historic Preservation project of the Traditional Arts in Upstate New York, Canton, New York, and the first, second, and fourth dollar amounts under such heading are each hereby reduced

Mr. CAMPBELL. Mr. Chairman, I withdraw my demand for a recorded vote on Campbell amendment No. 3.

The Acting CHAIR. The demand for a recorded vote is withdrawn.

RECORDED VOTE

Mr. DICKS. Mr. Chairman, I demand a recorded vote.

The Acting CHAIR. A recorded vote has been demanded.

A recorded vote was ordered.

The Acting CHAIR. This is a 2minute vote.

The vote was taken by electronic device, and there were—ayes 122, noes 309, not voting 8, as follows:

[Roll No. 471]

AYES-122

Gerlach Miller (MI) Adler (NJ) Gingrey (GA) Akin Minnick Alexander Gohmert Mitchell Austria Goodlatte Moran (KS) Bachmann Graves Myrick Hall (TX) Neugebauer Barrett (SC) Bartlett Harper Nunes Bean Heller Olson Bilbray Hensarling Paul Bishop (UT) Herger Paulsen Blackburn Hoekstra Pence Bono Mack Hunter Petri Boozman Inglis Pitts Boustany Poe (TX) Jenkins Brady (TX) Posey Price (GA) Johnson (IL) Bright Broun (GA) Johnson, Sam Radanovich Brown-Waite. Jordan (OH) Roe (TN) Ginny King (IA) Rohrabacher Burgess Kingston Roonev Burton (IN) Kirk Roskam Kline (MN) Buyer Royce Ryan (WI) Campbell Lamborn Cantor Latta Scalise Lee (NY) Cassidy Schauer Chaffetz Linder Schmidt Coble Luetkemever Sensenbrenner Coffman (CO) Lummis Sessions Lungren, Daniel Conaway Shadegg Cooper E. Davis (KY) Mack Shimkus Smith (NE) Deal (GA) Manzullo Marchant Stearns Duncan Ehlers McCarthy (CA) Terry Thornberry Fallin. McCaul Fleming McClintock Tiberi Forbes McCotter Tierney Fortenberry Upton McHenry Foster McMahon Wamp Foxx McMorris Westmoreland Franks (AZ) Wilson (SC) Rodgers Miller (FL) Garrett (NJ) Wittman

NOES-309

Abercrombie Ackerman Aderholt Altmire Andrews Arcuri Baca Bachus Baird Baldwin Barrow Barton (TX) Becerra Berkley Berman Berry Biggert

Bishop (GA) Calvert Bishop (NY) Camp Cao Blumenauer Capito Blunt Capps Capuano Boccieri Boehner Bonner Cardoza Bordallo Carnahan Boren Carney Boswell Carson (IN) Boucher Carter Boyd Castle Brady (PA) Castor (FL) Childers Bralev (IA) Brown (SC Christensen Brown, Corrine Clarke Buchanan Clay Butterfield Cleaver

Clyburn Kaptur Rahall Cohen Kildee Rangel Cole Kilpatrick (MI) Rehberg Connolly (VA) Kilroy Reichert Conyers Kind Reves King (NY) Richardson Costa Kirkpatrick (AZ) Costello Rodriguez Courtney Kissell Rogers (AL) Crenshaw Klein (FL) Rogers (KY) Crowley Kosmas Rogers (MI) Kratovil Cuellar Ros-Lehtinen Culberson Kucinich Ross Rothman (NJ) Cummings Lance Langevin Roybal-Allard Dahlkemper Davis (AL) Larsen (WA) Ruppersberger Davis (CA) Larson (CT) Rush Davis (IL) Latham Ryan (OH) Davis (TN) LaTourette Sablan DeFazio Lee (CA) Salazar DeGette Levin Sánchez, Linda Lewis (CA) Delahunt т Sanchez, Loretta DeLauro Lipinski LoBiondo Sarbanes Dent Diaz-Balart, L. Schakowsky Loebsack Diaz-Balart, M. Lofgren, Zoe Schiff Dicks Lowey Schock Dingell Lucas Schrader Luján Schwartz Doggett Donnelly (IN) Lynch Scott (GA) Scott (VA) Dovle Maffei Dreier Maloney Serrano Driehaus Markey (CO) Sestak Edwards (MD) Markey (MA) Shea-Porter Edwards (TX) Marshall Sherman Ellison Massa. Shuler Ellsworth Matheson Shuster Emerson Matsui Simpson McCarthy (NY) Engel Sires McCollum Skelton Eshoo Etheridge McDermott Slaughter Faleomavaega McGovern Smith (NJ) McHugh Smith (TX) Farr Fattah Smith (WA) McIntyre Filner McKeon Snyder Frank (MA) McNerney Souder Frelinghuysen Meek (FL) Space Fudge Meeks (NY) Speier Melancon Gallegly Spratt Giffords Mica Stark Michaud Gonzalez Stupak Miller (NC) Gordon (TN) Sutton Granger Miller, Gary Tanner Tauscher Gravson Miller, George Green, Al Mollohan Tavlor Green, Gene Moore (KS) Teague Thompson (CA) Griffith Moore (WI) Grijalva Moran (VA) Thompson (MS) Guthrie Murphy (CT) Thompson (PA) Murphy (NY) Gutierrez Tiahrt Murphy, Patrick Hall (NY) Titus Halvorson Murphy, Tim Tonko Towns Hare Murtha Harman Nadler (NY) Tsongas Hastings (WA) Napolitano Turner Van Hollen Neal (MA) Heinrich Velázquez Herseth Sandlin Norton Higgins Nye Visclosky Oberstar Walden Hill Himes Obey Walz Hinchey Olver Wasserman Hinojosa Ortiz Schultz Hirono Pallone Waters Hodes Pascrel1 Watson Pastor (AZ) Holden Watt Holt Payne Waxman Perlmutter Honda Weiner Perriello Welch Hoyer Inslee Peters Wexler Jackson (IL) Whitfield Peterson Jackson-Lee Wilson (OH) Pierluisi Pingree (ME) (TX) Wolf Johnson (GA) Woolsey

NOT VOTING-

Wu

Varmuth

Young (AK)

Young (FL)

Chandler Israel Platts Kennedy Sullivan Hastings (FL) Lewis (GA)

Polis (CO)

Price (NC)

Pomeroy

Putnam

Quigley

Johnson, E. B.

Jones

Kagen

Kanjorski

ANNOUNCEMENT BY THE ACTING CHAIR The Acting CHAIR (during the vote). There is 1 minute remaining.

\Box 1212

So the amendment was rejected.

The result of the vote was announced as above recorded.

PART C AMENDMENT NO. 3 OFFERED BY MR. CAMPBELL

The Acting CHAIR. The unfinished business is the demand for a recorded vote on the amendment offered by the gentleman from California (Mr. CAMP-BELL) on which further proceedings were postponed and on which the noes prevailed by voice vote.

Clerk will redesignate The amendment.

The text of the amendment is as follows:

Part C amendment No. 3 offered by Mr. CAMPBELL:

At the end of the bill (before the short title), insert the following:

None of the funds provided in SEC this Act under the heading "National Park Service—Historic Preservation Fund" shall be available for the Tarrytown Music Hall Restoration project of the Friends of the Musical Arts Conservatory, Mozartina Tarrytown, New York, and the first, second, and fourth dollar amounts under such heading are each hereby reduced by \$150,000.

Mr. CAMPBELL. Mr. Chairman, I withdraw my demand for a recorded vote on the Campbell-Flake amendment No. 3.

The Acting CHAIR. The demand for a recorded vote is withdrawn.

RECORDED VOTE

Mr. DICKS. Mr. Chairman, I demand a recorded vote.

The Acting CHAIR. A recorded vote has been demanded.

A recorded vote was ordered.

The Acting CHAIR. This is a minute vote.

The vote was taken by electronic device, and there were—ayes 122, noes 301, not voting 16, as follows:

[Roll No. 472]

AYES—122

Foxx McCotter Akin Alexander Franks (AZ) McHenry Gallegly Garrett (NJ) Austria McMahon Bachmann McMorris Barrett (SC) Goodlatte Rodgers Bartlett Graves Miller (FL) Bean Harper Miller (MI) Bilirakis Heller Miller, Gary Bishop (UT) Hensarling Minnick Mitchell Blackburn Herger Hoekstra Blunt Moran (KS) Boehner Hunter Myrick Bono Mack Neugebauer Inglis Boozman Issa Nunes Boustany Jenkins Olson Brady (TX) Johnson (IL) Paul Bright Johnson, Sam Paulsen Brown-Waite Jones Pence Ginny Jordan (OH) Petri Burgess King (IA) Pitts Burton (IN) Poe (TX) Kingston Posey Buyer Kirk Kline (MN) Radanovich Camp Campbell Lamborn Roe (TN) Rohrabacher Cantor Lance Cassidy Latta Rooney Chaffetz Lee (NY) Roskam Coble Linder Royce Ryan (WI) Coffman (CO) Luetkemeyer Conaway Lummis Scalise Cooper Lungren, Daniel Schauer Davis (KY) Schmidt \mathbf{E} Mack Sensenbrenner Deal (GA) Duncan Manzullo Sessions Ehlers Marchant Shadegg Matheson Shimkus Fallin McCarthy (CA) Smith (NE) Fleming Forbes McCaul Stearns Fortenberry McClintock Taylor

Terry Thornberry Tiahrt

Tiberi Wamp Westmoreland Wilson (SC) Wittman

NOES_301 Frank (MA) Abercrombie Moore (KS) Frelinghuvsen Ackerman Moore (WI) Aderholt Fudge Moran (VA) Adler (NJ) Gerlach Murphy (CT) Murphy (NY) Giffords Altmire Andrews Gingrey (GA) Murphy, Patrick Arcuri Gonzalez Murphy, Tim Gordon (TN) Baca Murtha Bachus Nadler (NY) Granger Baird Gravson Napolitano Baldwin Neal (MA) Green, Al Green, Gene Norton Barrow Barton (TX) Griffith Nve Grijalva Oberstar Becerra Berkley Guthrie Obey Berman Gutierrez Olver Berry Hall (NY) OrtizHall (TX) Pallone Biggert Bishop (NY) Pascrell Halvorson Blumenauer Hare Pastor (AZ) Payne Perlmutter Boccieri Harman Hastings (WA) Bonner Bordallo Heinrich Perriello Boren Herseth Sandlin ${\bf Peters}$ Boswell Higgins Peterson Pierluisi Boucher Hill Boyd Himes Pingree (ME) Brady (PA) Hinchey Polis (CO) Pomeroy Braley (IA) Hinojosa Brown (SC) Hirono Price (NC) Brown, Corrine Hodes Putnam Buchanan Holden Quigley Butterfield Holt Rahall Honda Calvert Rangel Rehberg Cao Hoyer Capito Inslee Reichert Capps Israel Reves Jackson (II.) Capuano Richardson Cardoza Jackson-Lee Rodriguez Carnahan (TX) Rogers (AL) Carney Johnson (GA) Rogers (KY) Carson (IN) Johnson, E. B. Rogers (MI) Carter Kagen Ross Kanjorski Castle Rothman (N.I) Castor (FL) Roybal-Allard Kaptur Chandler Kildee Ruppersberger Kilpatrick (MI) Childers Ryan (OH) Christensen Sablan Kilroy Clarke Kind Salazar King (NY) Clav Sánchez Linda Kirkpatrick (AZ) Cleaver T. Cohen Kissell Sanchez, Loretta Cole Kosmas Sarbanes Connolly (VA) Schakowsky Kratovil Conyers Kucinich Schiff Costa. Langevin Schock Costello Larsen (WA) Schrader Courtney Larson (CT) Schwartz Crenshaw Latham Scott (GA) Scott (VA) Cuellar LaTourette Culberson Lee (CA) Serrano Cummings Levin Sestak Lewis (CA) Dahlkemper Shea-Porter Davis (AL) Lipinski Sherman Davis (CA) LoBiondo Shuler Davis (IL) Loebsack Shuster Davis (TN) Lofgren, Zoe Simpson DeFazio Sires Lowey Skelton DeGette Lucas Delahunt Luján Slaughter DeLauro Smith (NJ) Lvnch Dent Maffei Smith (TX) Diaz-Balart, L. Maloney Smith (WA) Diaz-Balart, M. Markey (CO) Snyder Dicks Markey (MA) Souder Dingel1 Marshall Space Doggett Massa Speier Matsui Donnelly (IN) Spratt McCarthy (NY) Dovle Stark Dreier McCollum Stupak Driehaus McDermott Sutton Edwards (MD) McGovern Tanner Edwards (TX) McHugh Tauscher Teague Ellison McIntyre Ellsworth Thompson (CA) McKeon Emerson McNerney Thompson (MS) Meek (FL) Thompson (PA) Engel Eshoo Meeks (NY) Tierney Etheridge Melancon Titus Faleomavaega Mica Michaud Tonko Towns Farr

Fattah

Filner

Foster

Miller (NC)

Mollohan

Miller, George

Tsongas

Turner

Upton

Van Hollen	Watson	Wolf
Velázquez	Watt	Woolsey
Visclosky	Waxman	Wu
Walden	Weiner	Yarmuth
Walz	Welch	Young (AK)
Wasserman	Wexler	Young (FL)
Schultz	Whitfield	104118 (112)
Waters	Wilson (OH)	

NOT VOTING-16

Bilbrav Price (GA) Gohmert Bishop (GA) Hastings (FL) Ros-Lehtinen Broun (GA) Kennedy Rush Klein (FL) Clyburn Sullivan Crowley Lewis (GA) Flake Platts

ANNOUNCEMENT BY THE ACTING CHAIR The Acting CHAIR (during the vote). There is 1 minute remaining.

\sqcap 1216

So the amendment was rejected. The result of the vote was announced as above recorded.

PART E AMENDMENT NO. 1 OFFERED BY MR. CAMPBELL

The Acting CHAIR. The unfinished business is the demand for a recorded vote on the amendment offered by the gentleman from California (Mr. CAMP-BELL) on which further proceedings were postponed and on which the noes prevailed by voice vote.

The Clerk will redesignate amendment

The text of the amendment is as fol-

Part E amendment No. 1 offered by Mr. CAMPBELL:

At the end of the bill (before the short title), insert the following:

. None of the funds made available in this Act under the heading "National Park Service-Statutory or Contractual Aid" shall be available for the Angel Island State Park Immigration Station Hospital Rehabilitation project of the Angel Island Immigration Station Foundation, San Francisco, California, and the amount otherwise provided under such heading (and the portion of such amount specified for congressionally designated items) are hereby reduced by \$1,000,000.

RECORDED VOTE

The Acting CHAIR. A recorded vote has been demanded.

A recorded vote was ordered.

The Acting CHAIR. This is a 2minute vote.

The vote was taken by electronic device, and there were—ayes 131, noes 296, not voting 12, as follows:

[Roll No. 473]

AYES-131 Brown-Waite. Akin Forbes Ginnv Fortenberry Alexander Buchanan Foxx Austria Franks (AZ) Bachmann Burgess Burton (IN) Barrett (SC) Gallegly Garrett (NJ) Bartlett Campbell Gerlach Barton (TX) Cantor Gohmert Bean Cassidy Goodlatte Biggert Castle Graves Bilbray Hall (TX) Chaffetz Bilirakis Coble Harper Bishop (UT) Coffman (CO) Heller Blackburn Conaway Hensarling Blunt Cooper Davis (KY) Herger Boehner Hoekstra Bono Mack Deal (GA) Hunter Boozman Dent Inglis Boustany Duncan Issa Brady (TX) Jenkins Ehlers Johnson (IL) Johnson, Sam Bright. Fallin Broun (GA) Fleming

Jones Jordan (OH) King (IA) Kingston Kirk Kline (MN) Lamborn Lance Latta Lee (NY) Linder Luetkemever Lummis Mack Marchant Matheson McCarthy (CA) McCaul McClintock McCotter McHenry McKeon

Abercrombie

Ackerman

Adler (NJ)

Aderholt

Altmire

Andrews

Arcuri

Bachus

Baldwin

Barrow

Becerra

Berkley

Berman

Bishop (GA)

Bishop (NY)

Blumenauer

Boccieri

Bonner

Bordallo

Boucher

Brady (PA)

Braley (IA)

Brown (SC)

Butterfield

Calvert

Camp

Capito

Capps

Capuano

Cardoza Carnahan

Carnev

Carter

Carson (IN)

Castor (FL)

Christensen

Chandler

Childers

Clarke

Cleaver

Clyburn

Conyers

Costello

Courtney

Crenshaw

Crowley

Cuellar

Culberson

Cummings

Dahlkemper

Davis (AL)

Davis (CA)

Davis (IL)

Davis (TN

DeFazio

DeGette

Delahunt

DeLauro

Dicks

Dingell

Diaz-Balart, L.

Diaz-Balart, M.

Costa

Connolly (VA)

Cohen

Cole

Clay

Cao

Brown, Corrine

Boren

Boyd

Berry

Baird

Baca

McMorris Rohrabacher Rodgers Roonev Miller (FL) Roskam Miller (MI) Royce Ryan (WI) Minnick Mitchell Scalise Moran (KS) Schmidt Myrick Schock Neugebauer Sensenbrenner Nunes Sessions Shadegg Olson Paul Shimkus Smith (NE) Paulsen Stearns Pence Petri Terry Thornberry Pitts Poe (TX) Tiahrt Posey Tiberi Price (GA) Upton Radanovich Wamp Roe (TN) Westmoreland Rogers (KY) Whitfield Rogers (MI) Wilson (SC) NOES-296

Doggett Donnelly (IN) Larson (CT) Latham LaTourette Dovle Dreier Lee (CA) Driehaus Levin Lewis (CA) Edwards (MD) Edwards (TX) Lipinski LoBiondo Ellison Ellsworth Loebsack Emerson Lofgren, Zoe Engel Lowey Eshoo Lucas Etheridge Luján Faleomavaega Lungren, Daniel Farr E. Fattah Lynch Filner Maffei Foster Malonev Frank (MA) Manzullo Markey (CO) Frelinghuysen Fudge Markey (MA) Giffords Marshall Gingrey (GA) Massa Gonzalez Matsui Gordon (TN) McCarthy (NY) Granger McCollum Grayson McDermott McGovern Green, Al Green, Gene McHugh Griffith McIntvre McMahon Grijalva Guthrie McNerney Gutierrez Meek (FL) Hall (NY) Meeks (NY) Halvorson Melancon Hare Mica. Harman Michaud Hastings (WA) Miller (NC) Heinrich Miller, Garv Herseth Sandlin Miller, George Higgins Mollohan Moore (KS) Hill Himes Moore (WI) Hinchey Moran (VA) Murphy (CT) Hinojosa Murphy (NY) Hirono Hodes Murphy, Patrick Holden Murphy, Tim Holt Murtha Nadler (NY) Honda Napolitano Hover Inslee Neal (MA) Israel Norton Jackson (IL) Nve Jackson-Lee Oberstar (TX) Obey Johnson (GA) Olver Johnson, E. B. Ortiz Kagen Kanjorski Pascrell Kaptur Pastor (AZ) Kildee Pavne Kilpatrick (MI) Perlmutter Kilroy Perriello Kind Peters King (NY) Peterson Kirkpatrick (AZ) Pierluisi Pingree (ME) Kissell Klein (FL) Polis (CO) Kosmas Pomeroy Price (NC) Kratovil Kucinich Putnam Langevin Quigley Larsen (WA) Rahall

Titus Rangel Sestak Rehberg Shea-Porter Tonko Reichert Sherman Towns Reves Shuler Tsongas Richardson Shuster Turner Van Hollen Rodriguez Simpson Rogers (AL) Sires Velázquez Skelton Visclosky Ros-Lehtinen Ross Slaughter Walden Rothman (NJ) Smith (NJ) Walz Smith (WA) Wasserman Roybal-Allard Ruppersberger Snyder Schultz Waters Rvan (OH) Souder Sablan Space Watson Salazar Speier Watt Sánchez, Linda Waxman Spratt Stupak Weiner Sanchez Loretta Sutton Welch Sarbanes Tanner Wexler Schakowsky Tauscher Wilson (OH) Schauer Taylor Wolf Schiff Woolsey Teague Schrader Thompson (CA) Wu Varmuth Scott (GA) Thompson (MS) Scott (VA) Thompson (PA) Young (AK) Serrano Young (FL)

NOT VOTING-12

Lewis (GA) Smith (TX) Boswell 1 Flake Platts Stark Hastings (FL) Sullivan Rush Kennedy Schwartz Wittman

ANNOUNCEMENT BY THE ACTING CHAIR.

The Acting CHAIR (during the vote). There is 1 minute remaining in this vote.

□ 1221

So the amendment was rejected.

The result of the vote was announced as above recorded.

PART C AMENDMENT NO. 4 OFFERED BY MR. CAMPBELL

The Acting CHAIR. The unfinished business is the demand for a recorded vote on the amendment offered by the gentleman from California (Mr. CAMP-BELL) on which further proceedings were postponed and on which the noes prevailed by voice vote.

The Clerk will redesignate the amendment.

The text of the amendment is as fol-

Part C amendment No. 4 offered by Mr. CAMPBELL:

At the end of the bill (before the short title), insert the following:

None of the funds provided in SEC this Act under the heading "National Park Service-Historic Preservation Fund" shall be available for the Historic Fort Payne Coal and Iron Building Rehabilitation project of the city of Fort Payne, Alabama, and the first, second, and fourth dollar amounts under such heading are each hereby reduced by \$150,000.

Mr. CAMPBELL. Mr. Chairman, I withdraw my demand for a recorded vote on Campbell-Flake amendment No. 4.

The Acting CHAIR. The demand for a recorded vote is withdrawn.

RECORDED VOTE

Mr. DICKS. Mr. Speaker, I demand a recorded vote.

A recorded vote was ordered.

The SPEAKER pro tempore. This is a 2-minute vote.

The vote was taken by electronic device, and there were—ayes 114, noes 317, not voting 8, as follows:

Simpson

Pascrell

Levin

[Roll No. 474]

Akin Alexander Austria Bachmann Barrett (SC) Bartlett Barton (TX) Bean Blackburn Bono Mack Boozman Boustany Brady (TX) Bright Broun (GA) Brown-Waite. Ginny Burgess Burton (IN) Buyer Campbell Cassidy Castle Chaffetz Coble Coffman (CO) Conaway Cooper Davis (KY) Deal (GA) Duncan Ehlers Fallin Fleming Forbes Foster Foxx Franks (AZ) Garrett (NJ)

AYES-114 Gohmert Miller (MI) Goodlatte Minnick Graves Mitchell Hall (TX) Moran (KS) Heller Myrick Hensarling Herger Nunes Hoekstra Olson Hunter Inglis Paul Issa Jenkins Paulsen Pence Johnson (IL) Petri Pitts Johnson, Sam Jones Posey Jordan (OH) King (IA) Roe (TN) Kingston Kline (MN) Lamborn Rooney Roskam Lance Latta Lee (NY) Linder

Neugebauer Price (GA) Radanovich Rohrabacher Royce Ryan (WI) Scalise Schauer Schmidt Sensenbrenner Sessions Shadegg Smith (NE) Stearns Terry Thornberry Tiberi Tiernev Upton Westmoreland Wilson (SC) Wittman

Gordon (TN)

Granger

Gravson

Griffith

Guthrie

Gutierrez Hall (NY)

Green, Al

Green, Gene

NOES-317

Luetkemeyer

Lungren, Daniel

Lummis

Manzullo

Marchant

McClintock

McCaul

McCotter

McHenry

McMorris

Rodgers

Miller (FL)

E. Mack

Abercrombie Clay Ackerman Cleaver Clyburn Aderholt Adler (NJ) Cohen Altmire Cole Connolly (VA) Andrews Arcuri Conyers Baca Costa Bachus Costello Baird Courtney Baldwin Crenshaw Barrow Crowley Becerra Cuellar Berkley Culberson Berman Cummings Berry Biggert Bilbray Bilirakis Davis (IL) Bishop (GA) Davis (TN) Bishop (NY) DeFazio Bishop (UT) DeGette Blumenauer Delahunt Blunt DeLauro Boccieri Dent Boehner Bonner Bordallo Dicks Dingell Boren Boswell Doggett Boucher Dovle Bovd Brady (PA) Dreier Braley (IA) Driehaus Brown (SC) Brown, Corrine Buchanan Ellison Butterfield Ellsworth Emerson Calvert Camp Engel Eshoo Cantor Cao Etheridge Capito Capps Farr Capuano Fattah Cardoza Filner Carnahan Carney Carson (IN) Carter Fudge

Castor (FL)

Christensen

Gerlach

Giffords

Chandler

Childers

Clarke

Halvorson Hare Harman Harper Hastings (WA) Dahlkemper Heinrich Herseth Sandlin Davis (AL) Davis (CA) Higgins Hill Himes Hinchey Hinojosa Hirono Hodes Holden Diaz-Balart, L. Holt Honda Diaz-Balart, M. Hover Inslee Jackson (IL) Donnelly (IN) Jackson-Lee (TX) Johnson (GA) Johnson, E. B. Edwards (MD) Kagen Edwards (TX) Kanjorski Kaptur Kildee Kilpatrick (MI) Kilroy Kind King (NY) Faleomayaega Kirk Kirkpatrick (AZ) Kissell Klein (FL) Fortenberry Kosmas Frank (MA) Kratovil Frelinghuysen Kucinich Langevin Gallegly Larsen (WA) Larson (CT) Latham Gingrey (GA) LaTourette Lee (CA) Gonzalez

Lewis (CA) Pastor (AZ) Sires Lipinski Payne Skelton LoBiondo Perlmutter Slaughter Loebsack Perriello Smith (NJ) Lofgren, Zoe Peters Smith (TX) Smith (WA) Lowey Peterson Pierluisi Lucas Snyder Luján Pingree (ME) Souder Lynch Poe (TX) Space Maffei Polis (CO) Speier Pomeroy Malonev Spratt Markey (CO) Price (NC) Stark Markey (MA) Putnam Stupak Marshall Quigley Sutton Massa Rahall Tanner Matheson Rangel Tauscher Matsui Rehberg Taylor McCarthy (CA) Reichert Teague McCarthy (NY) Reyes Thompson (CA) Richardson McCollum Thompson (MS) McDermott Rodriguez Thompson (PA) McGovern Rogers (AL) Tiahrt Rogers (KY) McHugh Titus McIntyre Rogers (MI) Tonko McKeon Ros-Lehtinen Towns McNernev Ross Tsongas Meek (FL) Rothman (NJ) Turner Meeks (NY) Roybal-Allard Van Hollen Melancon Ruppersberger Velázquez Mica Rush Visclosky Michaud Ryan (OH) Walden Miller (NC) Sablan Walz Miller, Gary Salazar Wamp Miller, George Sánchez, Linda Wasserman Mollohan T. Sanchez, Loretta Schultz Moore (KS) Waters Moore (WI) Sarbanes Moran (VA) Schakowsky Watson Murphy (CT) Schiff Watt Waxman Murphy (NY) Schock Murphy, Patrick Weiner Schrader Murphy, Tim Welch Schwartz Wexler Murtha. Scott (GA) Whitfield Nadler (NY) Scott (VA) Napolitano Serrano Wilson (OH) Wolf Neal (MA) Sestak Norton Shea-Porter Woolsey Oberstar Sherman Wu Yarmuth Obev Shimkus Ortiz Young (AK) Shuler Pallone Young (FL) Shuster

NOT VOTING-

Flake Kennedy Platts Hastings (FL) Lewis (GA) Sullivan Olver Israel

ANNOUNCEMENT BY THE ACTING CHAIR

The Acting CHAIR (during the vote). Members have 1 minute remaining in this vote.

□ 1225

So the amendment was rejected.

The result of the vote was announced as above recorded.

Mr. DICKS. I move to strike the last word.

The Acting CHAIR. The gentleman from Washington is recognized for 5 minutes.

Mr. DICKS. I just want to commend everyone for their hard work and staying last night to work on this very important bill. I want to thank Mr. SIMP-SON, his staff and all the members of the committee. I think this is one of best Interior appropriation bills that I can ever remember. I want to thank Mr. Campbell for being so cooperative.

I think we ought to move ahead here and get to final passage, but again, thank you and I hope you will all vote for and support this bill.

The Acting CHAIR. The Clerk will read.

The Clerk read as follows:

This Act may be cited as the "Department of the Interior, Environment, and Related Agencies Appropriations Act. 2010"

The Acting CHAIR. Under the rule. the Committee rises.

Accordingly, the Committee rose; and the Speaker pro tempore (Mrs. TAUSCHER) having assumed the chair, Mr. LYNCH, Acting Chair of the Committee of the Whole House on the State of the Union, reported that that Committee, having had under consideration the bill (H.R. 2996) making appropriations for the Department of the Interior, environment, and related agencies for the fiscal year ending September 30, 2010, and for other purposes, pursuant to House Resolution 578, he reported the bill back to the House with sundry amendments adopted by the mittee of the Whole.

The SPEAKER pro tempore. Under the rule, the previous question is ordered.

Pursuant to House Resolution 578, the question on adoption of the amendments will be put en gros.

The question is on the amendments.

The amendments were agreed to.

The SPEAKER pro tempore. The question is on the engrossment and third reading of the bill.

The bill was ordered to be engrossed and read a third time, and was read the third time.

The SPEAKER pro tempore. The question is on the passage of the bill.

Under clause 10 of rule XX, the yeas and nays are ordered.

The vote was taken by electronic device, and there were—yeas 254, nays 173, not voting 6, as follows:

[Roll No. 475] YEAS-254

Abercrombie Conyers Grijalva Ackerman Cooper Gutierrez Hall (NY) Adler (NJ) Costa Altmire Costello Halvorson Andrews Courtney Hare Crowley Harman Arcuri Cuellar Heinrich Baird Cummings Heller Herseth Sandlin Baldwin Dahlkemper Barrow Davis (AL) Higgins Bean Davis (CA) Himes Becerra Davis (IL) Hinchey Berkley Davis (TN) Hinojosa DeFazio Berman Hirono Berry DeGette Hodes Bishop (GA) Delahunt Holden Bishop (NY) DeLauro Holt Honda Blumenauer Dicks Boccieri Dingell Hover Boren Doggett Inslee Boswell Doyle Israel Jackson (IL) Boucher Driehaus Boyd Edwards (MD) Jackson-Lee Brady (PA) Edwards (TX) (TX)Johnson (GA) Braley (IA) Ehlers Ellison Brown, Corrine Johnson, E. B. Ellsworth Butterfield Kagen Kaniorski Cao Engel Capps Kaptur Eshoo Capuano Etheridge Kildee Kilpatrick (MI) Cardoza Farr Fattah Carnahan Kilroy Carney Filner Kind Carson (IN) Foster Kirk Frank (MA) Castor (FL) Kirkpatrick (AZ) Fudge Giffords Kissell Klein (FL) Chandler Clarke Clay Gonzalez Kosmas Cleaver Gordon (TN) Kucinich Clyburn Grayson Lance Green, Al Langevin Cohen Green, Gene Larsen (WA) Cole Connolly (VA) Griffith Larson (CT)

Olver

Ortiz

Pallone

Pascrell

Payne

Peters

Peterson

Polis (CO)

Price (NC)

Pomeroy

Quigley

Reichert

Rodriguez

Rothman (NJ)

Roybal-Allard

Sánchez, Linda

Rahall

Reyes

Ross

Salazar

T. Sanchez, Loretta

Sarbanes

Schauer

Schwartz

Scott (GA)

Scott (VA)

Shea-Porter

Serrano

Sherman

Sestak

Schiff

Schakowsky

Pastor (AZ)

Perlmutter

LaTourette Lee (CA) Levin LoBiondo Loebsack Lofgren, Zoe Lowey Luján Lynch Pingree (ME) Maffei Maloney Markey (MA) Marshall Massa Matsui McCarthy (NY) Rangel McCollum McDermott Richardson McGovern McHugh McIntyre McMahon Ros-Lehtinen McNerney Meek (FL) Meeks (NY) Ruppersberger Michaud Miller (MI) Ryan (OH) Miller (NC) Miller, George Mollohan Moore (KS) Moore (WI) Moran (VA) Murphy (CT) Murphy (NY) Murphy, Patrick Murphy, Tim Schrader Murtha Nadler (NY) Napolitano Neal (MA) Oberstar Obev

Shuler Sires Skelton Slaughter Smith (NJ) Smith (WA) Snyder Space Speier Spratt Stark Stupak Sutton Tauscher Teague Thompson (CA) Thompson (MS) Tierney Titus Tonko Towns Tsongas Turner Van Hollen

Velázquez Visclosky Walden Walz Wasserman Schultz Waters Watson Watt Waxman Weiner Welch Wexler Wilson (OH) Woolsey Wıı Yarmuth Young (AK)

NAYS-173

Aderholt Fallin McCaul Fleming McClintock Akin Alexander Austria Fortenberry McHenry Bachmann McKeon Foxx Franks (AZ) McMorris Bachus Barrett (SC) Frelinghuvsen Rodgers Bartlett Gallegly Mica Barton (TX) Garrett (NJ) Miller (FL) Biggert Bilbray Gerlach Miller, Gary Gingrey (GA) Minnick Bilirakis Gohmert Mitchell Bishop (UT) Blackburn Goodlatte Moran (KS) Granger Myrick Neugebauer Blunt Boehner Guthrie Nunes Hall (TX) Bonner Nye Bono Mack Olson Hastings (WA) Boozman Paul Boustany Hensarling Paulsen Brady (TX) Herger Pence Perriello Bright Hill Hoekstra Broun (GA) Petri Pitts Brown (SC) Hunter Brown-Waite. Inglis Platts Ginny Poe (TX) Issa Buchanan Jenkins Posey Price (GA) Johnson (IL) Burgess Burton (IN) Johnson, Sam Putnam Radanovich Jones Jordan (OH) Buyer Calvert Rehberg King (IA) King (NY) Roe (TN) Camp Campbell Rogers (AL) Cantor Kingston Rogers (KY) Capito Kline (MN) Rogers (MI) Carter Kratovil Rohrabacher Lamborn Cassidy Rooney Castle Latham Roskam Chaffetz Latta Royce Lee (NY) Ryan (WI) Childers Scalise Schmidt Coble Lewis (CA) Coffman (CO) Linder Conaway Lipinski Schock Crenshaw Lucas Luetkemeyer Sensenbrenner Culberson Sessions Davis (KY) Lummis Shadegg Lungren, Daniel Deal (GA) Shimkus Dent Shuster Diaz-Balart, L. Mack Simpson Diaz-Balart, M. Donnelly (IN) Manzullo Smith (NE) Smith (TX) Marchant Markey (CO) Dreier Souder

Matheson

McCarthy (CA)

Stearns

Tanner

Duncan

Emerson

Tiberi Wilson (SC) Taylor Terry Upton Wittman Thompson (PA) Wamp Wolf Thornberry Westmoreland Young (FL) Tiahrt Whitfield

NOT VOTING-6

Flake Kennedy Melancon Hastings (FL) Lewis (GA) Sullivan

ANNOUNCEMENT BY THE SPEAKER PRO TEMPORE

The SPEAKER pro tempore (during the vote). There are 2 minutes remaining on this vote.

□ 1243

So the bill was passed.

The result of the vote was announced as above recorded.

A motion to reconsider was laid on the table.

□ 1245

AMERICAN CLEAN ENERGY AND SECURITY ACT OF 2009

Mr. WAXMAN. Madam Speaker, pursuant to H. Res. 587, I call up the bill (H.R. 2454) to create clean-energy jobs, achieve energy independence, reduce global warming pollution and transition to a clean-energy economy, and ask for its immediate consideration in the House

The Clerk read the title of the bill.

The SPEAKER pro tempore. Pursuant to House Resolution 587, in lieu of the amendment recommended by the Committee on Energy and Commerce printed in the bill, the amendment in the nature of a substitute consisting of the text of H.R. 2998, modified by the amendment printed in part A of House Report 111-185 is adopted and the bill, as amended, is considered read.

The text of the bill, as amended, is as follows:

H.R. 2998

Be it enacted by the Senate and House of Representatives of the United States of America in Congress assembled,

SECTION 1. SHORT TITLE; TABLE OF CONTENTS.

- (a) SHORT TITLE.—This Act may be cited as the "American Clean Energy and Security Act of 2009'
- (b) Table of Contents.—The table of contents for this Act is as follows:
- Sec. 1. Short title; table of contents.
- Sec. 2. Definitions
- Sec. 3. International participation.

TITLE I—CLEAN ENERGY

Subtitle A-Combined Efficiency and Renewable Electricity Standard

- Sec. 101. Combined efficiency and renewable electricity standard.
- Sec. 102. Clarifying State authority to adopt renewable energy incentives.
- Sec. 103. Federal renewable energy chases.

Subtitle B-Carbon Capture and Sequestration

- Sec. 111. National strategy.
- Sec. 112. Regulations for geologic sequestration sites.
 - "Sec. 813. Geologic sequestration sites.
- Sec. 113. Studies and reports.
- Sec. 114. Carbon capture and sequestration demonstration and early deployment program.
- Sec. 115. Commercial deployment of carbon capture and sequestration technologies.

- "Sec. 786. Commercial deployment carbon capture and sequestration technologies.
- Sec. 116. Performance standards for coalfueled power plants.
 - "Sec. 812. Performance standards new coal-fired power plants.

Subtitle C-Clean Transportation

- Sec. 121. Electric vehicle infrastructure.
- Sec. 122. Large-scale vehicle electrification program.
- Sec. 123. Plug-in electric drive vehicle manufacturing
- Sec. 124. Investment in clean vehicles.
- Sec. 125. Advanced technology vehicle manufacturing incentive loans.
- Sec. 126. Amendment to renewable standard.
- Sec. 127. Open fuel standard.
- Sec. 128. Diesel emissions reduction.
- Sec. 129. Loan guarantees for projects to construct renewable fuel pipelines
- Sec. 130. Fleet vehicles.
- Sec. 130A. Report on natural gas vehicle emissions reductions.
- Subtitle D-State Energy and Environment Development Accounts
- Sec. 131. Establishment of SEED Accounts. Sec. 132. Support of State renewable energy and energy efficiency programs.
- Sec. 133. Support of Indian renewable energy and energy efficiency programs.

Subtitle E—Smart Grid Advancement

- Sec. 141. Definitions.
- Assessment of Smart Grid cost ef-Sec. 142. fectiveness in products.
- Sec. 143. Inclusions of Smart Grid capability on appliance ENERGY GUIDE labels
- Sec. 144. Smart Grid peak demand reduction goals.
- Sec. 145. Reauthorization of energy efficiency public information program to include Smart Grid information.
- Sec. 146. Inclusion of Smart Grid features in appliance rebate program.

Subtitle F-Transmission Planning

- Sec. 151. Transmission planning and siting.
- Sec. 152. Net metering for Federal agencies.
- Sec. 153. Support for qualified advanced electric transmission manufacturing plants, qualified high efficiency transmission property, and qualified advanced electric transmission property.
- Subtitle G-Technical Corrections to Energy Laws
- Sec. 161. Technical corrections to Energy Independence and Security Act of 2007.
- Sec. 162. Technical corrections to Energy Policy Act of 2005.
- Subtitle H-Energy and Efficiency Centers and Research
- Sec. 171. Energy Innovation Hubs.
- Sec. 172. Advanced energy research.
- Sec. 173. Building Assessment Centers.
- Sec. 174. Centers for Energy and Environmental Knowledge and Outreach.

Subtitle I-Nuclear and Advanced Technologies

- Sec. 181. Revisions to loan guarantee program authority.
- Sec. 182. Purpose.
- Sec. 183. Definitions.
- Sec. 184. Clean energy investment fund.
- technology Sec. 185. Energy deployment goals.
- Sec. 186. Clean energy deployment administration.
- Sec. 187. Direct support.

- Sec. 188. Indirect support.
- Sec. 189. Federal credit authority.
- Sec. 190. General provisions.
- Sec. 191. Conforming amendments. Subtitle J-Miscellaneous
- Sec. 195. Increased hydroelectric generation at existing Federal facilities.
- Sec. 196. Clean technology business competition grant program.
- Sec. 197. National Bioenergy Partnership.
- Sec. 198. Office of Consumer Advocacy.
- Sec. 199. Development corporation for renewable power borrowing authority.
- Sec. 199A. Study.

TITLE II—ENERGY EFFICIENCY

Subtitle A—Building Energy Efficiency Programs

- Sec. 201. Greater energy efficiency in building codes.
- Sec. 202. Building retrofit program.
- Sec. 203. Energy efficient manufactured homes.
- Sec. 204. Building energy performance labeling program.
- Sec. 205. Tree planting programs.
- Sec. 206. Energy efficiency for data center buildings.
- Sec. 207. Community building code.
- Sec. 208. Solar energy systems building permit requirement for receipt of community development block grant funds.
- Subtitle B-Lighting and Appliance Energy Efficiency Programs
- Sec. 211. Lighting efficiency standards.
- Sec. 212. Other appliance efficiency standards.
- Sec. 213. Appliance efficiency determinations and procedures.
- Sec. 214. Best-in-Class Appliances Deployment Program.
- Sec. 215. WaterSense.
- Sec. 216. Federal procurement of water efficient products.
- Sec. 216A. Transmission planning.
- Sec. 216B. Siting and construction in the western interconnection.
- Sec. 217. Water efficient product rebate programs.
- Sec. 218. Certified stoves program.
- Sec. 219. Energy Star standards.

Subtitle C-Transportation Efficiency

- Sec. 221. Emissions standards.
 - "PART B-MOBILE SOURCES
 - "Sec. 821. Greenhouse gas emission standards for mobile sources.
- Sec. 222. Greenhouse gas emissions reductions through transportation efficiency.
 - "PART D-TRANSPORTATION EMISSIONS
 - "Sec. 841. Greenhouse gas emissions reductions through transportation efficiency.
- Sec. 223. SmartWay transportation ciency program.
- "Sec. 822. SmartWay transportation efficiency program.
- Sec. 224. State vehicle fleets.

Subtitle D—Industrial Energy Efficiency Programs

- Sec. 241. Industrial plant energy efficiency standards.
- Sec. 242. Electric and thermal waste energy recovery award program.
- Sec. 243. Clarifying election of waste heat recovery financial incentives.
- Sec. 244. Motor market assessment and commercial awareness program.
- Sec. 245. Motor efficiency rebate program.
- Subtitle E-Improvements in Energy Savings Performance Contracting
- Sec. 251. Energy savings performance contracts.

- Subtitle F-Public Institutions
- Sec. 261. Public institutions.
- Sec. 262. Community energy efficiency flexibility.
- Sec. 263. Small community joint participation.
- Sec. 264. Low income community energy efficiency program.
- Sec. 265. Consumer behavior research.

Subtitle G-Miscellaneous

- Sec. 271. Energy efficient information and communications technologies.
- Sec. 272. National energy efficiency goals.
- Sec. 273. Affiliated island energy independence team.
- Sec. 274. Product carbon disclosure program. TITLE III—REDUCING GLOBAL WARMING POLLUTION
- Sec. 301. Short title.

Subtitle A-Reducing Global Warming Pollution

Sec. 311. Reducing global warming pollution.

"TITLE VII—GLOBAL WARMING POLLUTION REDUCTION PROGRAM

- "PART A-GLOBAL WARMING POLLUTION REDUCTION GOALS AND TARGETS
- "Sec. 701. Findings and purpose
- "Sec. 702. Economy-wide reduction goals.
- "Sec. 703. Reduction targets for specified sources
- "Sec. 704. Supplemental pollution reductions.
- "Sec. 705. Review and program recommendations.
- "Sec. 706. National Academy review.
- "Sec. 707. Presidential response and recommendations.
- "PART B-DESIGNATION AND REGISTRATION OF GREENHOUSE GASES
 - "Sec. 711. Designation of greenhouse gases.
 - "Sec. 712. Carbon dioxide equivalent value of greenhouse gases.
 - "Sec. 713. Greenhouse gas registry.
 - "PART C-PROGRAM RULES
 - "Sec. 721. Emission allowances.
 - "Sec. 722. Prohibition of excess emissions.
 - "Sec. 723. Penalty for noncompliance.
 - "Sec. 724. Trading.
 - "Sec. 725. Banking and borrowing.
 - "Sec. 726. Strategic reserve.
 - "Sec. 727. Permits.
 - "Sec. 728. International emission allowances.

"PART D-OFFSETS

- "Sec. 731. Offsets Integrity Advisory Board.
- "Sec. 732. Establishment of offsets program.
- "Sec. 733. Eligible project types.
- "Sec. 734. Requirements for offset projects.
- "Sec. 735. Approval of offset projects. "Sec. 736. Verification of offset projects.
- "Sec. 737. Issuance of offset credits.
- "Sec. 738. Audits.
- "Sec. 739. Program review and revision.
- "Sec. 740. Early offset supply.
- "Sec. 741. Environmental considerations.
- "Sec. 742. Trading.
- "Sec. 743. International offset credits.
- "PART E—SUPPLEMENTAL EMISSIONS
- REDUCTIONS FROM REDUCED DEFORESTATION
- "Sec. 751. Definitions.
- "Sec. 752. Findings.
- "Sec. 753. Supplemental emissions reductions through reduced deforestation.
- "Sec. 754. Requirements for international deforestation reduction program.

- "Sec. 755. Reports and reviews.
- "Sec. 756. Legal effect of part.
- Sec. 312. Definitions.
 - "Sec. 700. Definitions.

Subtitle B—Disposition of Allowances

- Sec. 321. Disposition of allowances for global warming pollution reduction program.
 - "PART H—DISPOSITION OF ALLOWANCES
 - "Sec. 781. Allocation of allowances for supplemental reductions.
 - "Sec. 782. Allocation of emission allowances.
 - "Sec. 783. Electricity consumers.
 - "Sec. 784. Natural gas consumers.
 - "Sec. 785. Home heating oil, propane, and kerosene consumers.
 - "Sec. 787. Allocations to refineries.
 - "Sec. 788. [SECTION RESERVED].
 - "Sec. 789. Climate change consumer refunds.
 - "Sec. 790. Exchange for State-issued allowances.
 - "Sec. 791. Auction procedures.
 - "Sec. 792. Auctioning allowances for other entities.
 - "Sec. 793. Establishment of funds.
 - "Sec. 794. Oversight of allocations. Subtitle C-Additional Greenhouse Gas
- Standards
- Sec. 331. Greenhouse gas standards.
- "TITLE VIII—ADDITIONAL GREENHOUSE GAS STANDARDS
 - "Sec. 801. Definitions.
- "PART A—STATIONARY SOURCE STANDARDS
 - "Sec. 811. Standards of performance.
 - "PART C-EXEMPTIONS FROM OTHER PROGRAMS
 - "Sec. 831. Criteria pollutants.
 - "Sec. 832. International air pollution.
 - "Sec. 833. Hazardous air pollutants.
- "Sec. 834. New source review.
- "Sec. 835. Title V permits.
- Sec. 332. HFC Regulation. Sec. 333. Black carbon.
 - "PART E—BLACK CARBON
 - "Sec. 851. Black carbon.
- Sec. 334. States.
- Sec. 335. State programs.
 - "PART F-MISCELLANEOUS
 - "Sec. 861. State programs.
 - "Sec. 862. Grants for support of air pollution control programs.
- Sec. 336. Enforcement.
- Sec. 337. Conforming amendments.
- Sec. 338. Davis-Bacon compliance.
- Sec. 339. National strategy for domestic biological carbon sequestration.

- Subtitle D-Carbon Market Assurance
- Sec. 341. Carbon market assurance. Sec. 342. Carbon derivative markets.
- Subtitle E-Additional Market Assurance Sec. 351. Regulation of certain transactions in derivatives involving energy
- commodities. Sec. 352. No effect on authority of the Federal Energy Regulatory Com-
- mission. Sec. 353. Inspector General of the Commodity Futures Trading Com-
- mission. Sec. 354. Settlement and clearing through registered derivatives clearing
- organizations. Sec. 355. Limitation on eligibility to pur-
- chase a credit default swap. Sec. 356. Transaction fees.
- Sec. 357. No effect on antitrust law or authority of the Federal Trade
- Commission. Sec. 358. Effect of derivatives regulatory reform legislation.
- Sec. 359. Cease-and-desist authority.
- Sec. 360. Presidential review of regulations.

TITLE IV—TRANSITIONING TO A CLEAN ENERGY ECONOMY

Subtitle A—Ensuring Real Reductions in Industrial Emissions Sec. 401. Ensuring real reductions in indus-

trial emissions.
"PART F—ENSURING REAL REDUCTIONS IN

INDUSTRIAL EMISSIONS "Sec. 761. Purposes.

"Sec. 762. International negotiations.

"Sec. 763. Definitions.

"SUBPART 1—EMISSION ALLOWANCE REBATE PROGRAM

"Sec. 764. Eligible industrial sectors. "Sec. 765. Distribution of emission al-

lowance rebates.
"SUBPART 2—INTERNATIONAL RESERVE
ALLOWANCE PROGRAM

"Sec. 766. International reserve allowance program.

"SUBPART 3—PRESIDENTIAL DETERMINATION"Sec. 767. Presidential reports and determinations.

Subtitle B—Green Jobs and Worker Transition

PART 1—GREEN JOBS

Sec. 421. Clean energy curriculum development grants.

Sec. 422. Increased funding for energy worker training program.

PART 2—CLIMATE CHANGE WORKER ADJUSTMENT ASSISTANCE

Sec. 425. Petitions, eligibility requirements, and determinations.

Sec. 426. Program benefits.

Sec. 427. General provisions.

Subtitle C—Consumer Assistance

Sec. 431. Energy refund program.

Sec. 432. Modification of earned income credit amount for individuals with no qualifying children.

Sec. 433. Protection of Social Security and Medicare trust funds.

Subtitle D—Exporting Clean Technology

Sec. 441. Findings and purposes.

Sec. 442. Definitions.

Sec. 443. Governance.

Sec. 444. Determination of eligible countries.

Sec. 445. Qualifying activities.

Sec. 446. Assistance.

Subtitle E—Adapting to Climate Change PART 1—DOMESTIC ADAPTATION

SUBPART A—NATIONAL CLIMATE CHANGE ADAPTATION PROGRAM

Sec. 451. Global change research and data management.

Sec. 452. National Climate Service.

Sec. 453. State programs to build resilience to climate change impacts.

SUBPART B—PUBLIC HEALTH AND CLIMATE CHANGE

Sec. 461. Sense of Congress on public health and climate change.

Sec. 462. Relationship to other laws.

Sec. 463. National strategic action plan.

Sec. 464. Advisory board.

Sec. 465. Reports.

Sec. 466. Definitions.

Sec. 467. Climate Change Health Protection and Promotion Fund.

SUBPART C—NATURAL RESOURCE ADAPTATION

Sec. 471. Purposes.

Sec. 472. Natural resources climate change adaptation policy.

Sec. 473. Definitions.

Sec. 474. Council on Environmental Quality.

Sec. 475. Natural Resources Climate Change Adaptation Panel.

Sec. 476. Natural Resources Climate Change Adaptation Strategy. Sec. 477. Natural resources adaptation science and information.

Sec. 478. Federal natural resource agency adaptation plans.

Sec. 479. State natural resources adaptation plans.

Sec. 480. Natural Resources Climate Change Adaptation Fund.

Sec. 481. National Wildlife Habitat and Corridors Information Program.

Sec. 482. Additional provisions regarding Indian tribes.

PART 2—INTERNATIONAL CLIMATE CHANGE

Adaptation Program

Sec. 491. Findings and purposes.

Sec. 492. Definitions.

Sec. 493. International Climate Change Adaptation Program.

Sec. 494. Distribution of allowances.

Sec. 495. Bilateral assistance.

SEC. 2. DEFINITIONS.

For purposes of this Act:

(1) ADMINISTRATOR.—The term "Administrator" means the Administrator of the Environmental Protection Agency.

(2) STATE.—The term "State" has the meaning given that term in section 302 of the Clean Air Act.

SEC. 3. INTERNATIONAL PARTICIPATION.

The Administrator, in consultation with the Department of State and the United States Trade Representative, shall annually prepare and certify a report to the Congress regarding whether China and India have adopted greenhouse gas emissions standards at least as strict as those standards required under this Act. If the Administrator determines that China and India have not adopted greenhouse gas emissions standards at least as stringent as those set forth in this Act, the Administrator shall notify each Member of Congress of his determination, and shall release his determination to the media.

TITLE I—CLEAN ENERGY Subtitle A—Combined Efficiency and

Renewable Electricity Standard

SEC. 101. COMBINED EFFICIENCY AND RENEW-ABLE ELECTRICITY STANDARD.

(a) IN GENERAL.—Title VI of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2601 and following) is amended by adding at the end the following:

"SEC. 610. COMBINED EFFICIENCY AND RENEW-ABLE ELECTRICITY STANDARD.

"(a) DEFINITIONS.—For purposes of this section:

''(1) CHP SAVINGS.—The term 'CHP savings' means—

"(A) CHP system savings from a combined heat and power system that commences operation after the date of enactment of this section; and

"(B) the increase in CHP system savings from, at any time after the date of the enactment of this section, upgrading, replacing, expanding, or increasing the utilization of a combined heat and power system that commenced operation on or before the date of enactment of this section.

"(2) CHP SYSTEM SAVINGS.—The term 'CHP system savings' means the increment of electric output of a combined heat and power system that is attributable to the higher efficiency of the combined system (as compared to the efficiency of separate production of the electric and thermal outputs).

"(3) COMBINED HEAT AND POWER SYSTEM.— The term 'combined heat and power system' means a system that uses the same energy source both for the generation of electrical or mechanical power and the production of steam or another form of useful thermal energy, provided that—

"(A) the system meets such requirements relating to efficiency and other operating characteristics as the Commission may promulgate by regulation; and "(B) the net sales of electricity by the facility to customers not consuming the thermal output from that facility will not exceed 50 percent of total annual electric generation by the facility.

"(4) CUSTOMER FACILITY SAVINGS.—The term 'customer facility savings' means a reduction in end-use electricity consumption (including recycled energy savings) at a facility of an end-use consumer of electricity served by a retail electric supplier, as compared to—

"(A) in the case of a new facility, consumption at a reference facility of average efficiency;

"(B) in the case of an existing facility, consumption at such facility during a base period, except as provided in subparagraphs (C) and (D):

"(C) in the case of new equipment that replaces existing equipment with remaining useful life, the projected consumption of the existing equipment for the remaining useful life of such equipment, and thereafter, consumption of new equipment of average efficiency of the same equipment type; and

"(D) in the case of new equipment that replaces existing equipment at the end of the useful life of the existing equipment, consumption by new equipment of average efficiency of the same equipment type.

"(5) DISTRIBUTED RENEWABLE GENERATION FACILITY.—The term 'distributed renewable generation facility' means a facility that—

"(A) generates renewable electricity;
"(B) primarily serves 1 or more electricity
consumers at or near the facility site; and

"(C) is no greater than-

"(i) 2 megawatts in capacity; or

"(ii) 4 megawatts in capacity, in the case of a facility that is placed in service after the date of enactment of this section and generates electricity from a renewable energy resource other than by means of combustion.

"(6) ELECTRICITY SAVINGS.—The term 'electricity savings' means reductions in electricity consumption, relative to business-as-usual projections, achieved through measures implemented after the date of enactment of this section, limited to—

"(A) customer facility savings of electricity, adjusted to reflect any associated increase in fuel consumption at the facility;

"(B) reductions in distribution system losses of electricity achieved by a retail electricity distributor, as compared to losses attributable to new or replacement distribution system equipment of average efficiency;

"(C) CHP savings; and

"(D) fuel cell savings.

"(7) CENTRAL PROCUREMENT STATE.—The term 'central procurement State' means a State that, as of January 1, 2009, had adopted and implemented a legally enforceable mandate that, in lieu of requiring utilities to submit credits or certificates issued based on generation of electricity from (or to purchase or generate electricity from) resources defined by the State as renewable, requires retail electric suppliers to collect payments from electricity ratepayers within the State that are used for central procurement, by a State agency or a public benefit corporation established pursuant to State law, of credits or certificates issued based on generation of electricity from resources defined by the State as renewable.

"(8) FEDERAL RENEWABLE ELECTRICITY CREDIT.—The term 'Federal renewable electricity credit' means a credit, representing one megawatt hour of renewable electricity, issued pursuant to subsection (e).

"(9) FUEL CELL.—The term 'fuel cell' means a device that directly converts the chemical energy of a fuel and an oxidant into electricity by electrochemical processes occurring at separate electrodes in the device.

- "(10) FUEL CELL SAVINGS.—The term 'fuel cell savings' means the electricity saved by a fuel cell that is installed after the date of enactment of this section, or by upgrading a fuel cell that commenced operation on or before the date of enactment of this section, as a result of the greater efficiency with which the fuel cell transforms fuel into electricity as compared with sources of electricity delivered through the grid, provided that—
- "(A) the fuel cell meets such requirements relating to efficiency and other operating characteristics as the Commission may promulgate by regulation; and
- "(B) the net sales of electricity from the fuel cell to customers not consuming the thermal output from the fuel cell, if any, do not exceed 50 percent of the total annual electricity generation by the fuel cell.
- "(12) OTHER QUALIFYING ENERGY RE-SOURCE.—The term 'other qualifying energy resource' means any of the following:
 - "(A) Landfill gas.
 - "(B) Wastewater treatment gas.
- "(C) Coal mine methane used to generate electricity at or near the mine mouth.
- "(D) Qualified waste-to-energy.
- "(13) QUALIFIED HYDROPOWER.—The term qualified hydropower' means—
- "(A) energy produced from increased efficiency achieved, or additions of capacity made, on or after January 1, 1988, at a hydroelectric facility that was placed in service before that date and does not include additional energy generated as a result of operational changes not directly associated with efficiency improvements or capacity additions: or
- "(B) energy produced from generating capacity added to a dam on or after January 1, 1988, provided that the Commission certifies that—
- "(i) the dam was placed in service before the date of the enactment of this section and was operated for flood control, navigation, or water supply purposes and was not producing hydroelectric power prior to the addition of such capacity:
- "(ii) the hydroelectric project installed on the dam is licensed (or is exempt from licensing) by the Commission and is in compliance with the terms and conditions of the license or exemption, and with other applicable legal requirements for the protection of environmental quality, including applicable fish passage requirements; and
- "(iii) the hydroelectric project installed on the dam is operated so that the water surface elevation at any given location and time that would have occurred in the absence of the hydroelectric project is maintained, subject to any license or exemption requirements that require changes in water surface elevation for the purpose of improving the environmental quality of the affected waterway.
- "(14) QUALIFIED WASTE-TO-ENERGY.—The term 'qualified waste-to-energy' means energy from the combustion of municipal solid waste or construction, demolition, or disaster debris, or from the gasification or pyrolization of such waste or debris and the combustion of the resulting gas at the same facility, provided that—
- "(A) such term shall include only the energy derived from the non-fossil biogenic portion of such waste or debris;
- "(B) the Commission determines, with the concurrence of the Administrator of the Environmental Protection Agency, that the total lifecycle greenhouse gas emissions attributable to the generation of electricity from such waste or debris are lower than those attributable to the likely alternative method of disposing of such waste or debris; and
- "(C) the owner or operator of the facility generating electricity from such energy pro-

- vides to the Commission, on an annual basis—
- "(i) a certification that the facility is in compliance with all applicable State, tribal, and Federal environmental permits;
- "(ii) in the case of a facility that commenced operation before the date of enactment of this section, a certification that the facility meets emissions standards promulgated under sections 112 or 129 of the Clean Air Act (42 U.S.C. 7412 or 7429) that apply as of the date of enactment of this section to new facilities within the relevant source category; and
- "(iii) in the case of the combustion, pyrolization, or gasification of municipal solid waste, a certification that each local government unit from which such waste originates operates, participates in the operation of, contracts for, or otherwise provides for, recycling services for its residents.
- "(15) RECYCLED ENERGY SAVINGS.—The term 'recycled energy savings' means a reduction in electricity consumption that results from a modification of an industrial or commercial system that commenced operation before the date of enactment of this section, in order to recapture electrical, mechanical, or thermal energy that would otherwise be wasted.
- "(16) RENEWABLE BIOMASS.—The term 'renewable biomass' means any of the following:
- "(A) Materials, pre-commercial thinnings, or removed invasive species from National Forest System land and public lands (as defined in section 103 of the Federal Land Policy and Management Act of 1976 (43 U.S.C. 1702)), including those that are byproducts of preventive treatments (such as trees, wood, brush, thinnings, chips, and slash), that are removed as part of a federally recognized timber sale, or that are removed to reduce hazardous fuels, to reduce or contain disease or insect infestation, or to restore ecosystem health, and that are—
- "(i) not from components of the National Wilderness Preservation System, Wilderness Study Areas, Inventoried Roadless Areas, old growth stands, late-successional stands (except for dead, severely damaged, or badly infested trees), components of the National Landscape Conservation System, National Monuments, National Conservation Areas, Designated Primitive Areas, or Wild and Scenic Rivers corridors:
- "(ii) harvested in environmentally sustainable quantities, as determined by the appropriate Federal land manager; and
- "(iii) harvested in accordance with Federal and State law, and applicable land management plans.
- "(B) Any organic matter that is available on a renewable or recurring basis from non-Federal land or land belonging to an Indian or Indian tribe that is held in trust by the United States or subject to a restriction against alienation imposed by the United States, including—
 - "(i) renewable plant material, including—
 - "(I) feed grains;
- "(II) other agricultural commodities;
- "(III) other plants and trees; and
- "(IV) algae; and
- "(ii) waste material, including—
- "(I) crop residue;
- "(II) other vegetative waste material (including wood waste and wood residues);
- "(III) animal waste and byproducts (including fats, oils, greases, and manure);
- "(IV) construction waste; and
- ``(V) food waste and yard waste.
- $\mbox{``(C)}$ Residues and byproducts from wood, pulp, or paper products facilities.''.
- "(17) RENEWABLE ELECTRICITY.—The term 'renewable electricity' means electricity generated (including by means of a fuel cell)

- from a renewable energy resource or other qualifying energy resources.
- "(18) RENEWABLE ENERGY RESOURCE.—The term 'renewable energy resource' means each of the following:
 - "(A) Wind energy.
 - "(B) Solar energy.
 - "(C) Geothermal energy.
 - "(D) Renewable biomass.
- "(E) Biogas derived exclusively from renewable biomass.
- "(F) Biofuels derived exclusively from renewable biomass.
 - "(G) Qualified hydropower.
- "(H) Marine and hydrokinetic renewable energy, as that term is defined in section 632 of the Energy Independence and Security Act of 2007 (42 U.S.C. 17211).
 - "(19) RETAIL ELECTRIC SUPPLIER.—
- "(A) IN GENERAL.—The term 'retail electric supplier' means, for any given year, an electric utility that sold not less than 4,000,000 megawatt hours of electric energy to electric consumers for purposes other than resale during the preceding calendar year.
- "(B) INCLUSIONS AND LIMITATIONS.—For purposes of determining whether an electric utility qualifies as a retail electric supplier under subparagraph (A)—
- "(i) the sales of any affiliate of an electric utility to electric consumers, other than sales to the affiliate's lessees or tenants, for purposes other than resale shall be considered to be sales of such electric utility; and
- "(ii) sales by any electric utility to an affiliate, lessee, or tenant of such electric utility shall not be treated as sales to electric consumers.
- "(C) AFFILIATE.—For purposes of this paragraph, the term 'affiliate' when used in relation to a person, means another person that directly or indirectly owns or controls, is owned or controlled by, or is under common ownership or control with, such person, as determined under regulations promulgated by the Commission.
- "'(20) RETAIL ELECTRIC SUPPLIER'S BASE AMOUNT.—The term 'retail electric supplier's base amount' means the total amount of electric energy sold by the retail electric supplier, expressed in megawatt hours, to electric customers for purposes other than resale during the relevant calendar year, excluding—
- "(A) electricity generated by a hydroelectric facility that is not qualified hydropower;
- "(B) electricity generated by a nuclear generating unit placed in service after the date of enactment of this section; and
- "(C) the proportion of electricity generated by a fossil-fueled generating unit that is equal to the proportion of greenhouse gases produced by such unit that are captured and geologically sequestered.
- "(21) RETIRE AND RETIREMENT.—The terms 'retire' and 'retirement' with respect to a Federal renewable electricity credit, means to disqualify such credit for any subsequent use under this section, regardless of whether the use is a sale, transfer, exchange, or submission in satisfaction of a compliance obligation.
- "(22) THIRD-PARTY EFFICIENCY PROVIDER.— The term 'third-party efficiency provider' means any retailer, building owner, energy service company, financial institution or other commercial, industrial or nonprofit entity that is capable of providing electricity savings in accordance with the requirements of this section.
- "(23) TOTAL ANNUAL ELECTRICITY SAVINGS.— The term 'total annual electricity savings' means electricity savings during a specified calendar year from measures implemented since the date of the enactment of this section, taking into account verified measure lifetimes or verified annual savings attrition

rates, as determined in accordance with such regulations as the Commission may promulgate and measured in megawatt hours.

- "(b) ANNUAL COMPLIANCE OBLIGATION.-
- "(1) IN GENERAL.—For each of calendar years 2012 through 2039, not later than March 31 of the following calendar year, each retail electric supplier shall submit to the Commission an amount of Federal renewable electricity credits and demonstrated total annual electricity savings that, in the aggregate, is equal to such retail electric supplier's annual combined target as set forth in subsection (d), except as otherwise provided in subsection (h).
- "(2) DEMONSTRATION OF SAVINGS.—For purposes of this subsection, submission of demonstrated total annual electricity savings means submission of a report that demonstrates, in accordance with the requirements of subsection (f), the total annual electricity savings achieved by the retail electric supplier within the relevant compliance year
- "(3) RENEWABLE ELECTRICITY CREDITS PORTION.—Except as provided in paragraph (4), each retail electric supplier must submit Federal renewable electricity credits equal to at least three quarters of the retail electric supplier's annual combined target.
- "(4) STATE PETITION.—
- "(A) IN GENERAL.—Upon written request from the Governor of any State (including, for purposes of this paragraph, the Mayor of the District of Columbia), the Commission shall increase, to not more than two fifths, the proportion of the annual combined targets of retail electric suppliers located within such State that may be met through submission of demonstrated total annual electricity savings, provided that such increase shall be effective only with regard to the portion of a retail electric supplier's annual combined target that is attributable to electricity sales within such State.
- "(B) CONTENTS.—A Governor's request under this paragraph shall include an explanation of the Governor's rationale for determining, after consultation with the relevant State regulatory authority and other retail electricity ratemaking authorities within the State, to make such request. The request shall specify the maximum proportion of annual combined targets (not more than two fifths) that can be met through demonstrated total annual electricity savings, and the period for which such proportion shall be effective.
- "(C) REVISION.—The Governor of any State may, after consultation with the relevant State regulatory authority and other retail electricity ratemaking authorities within the State, submit a written request for revocation or revision of a previous request submitted under this paragraph. The Commission shall grant such request, provided that—
- "(i) any revocation or revision shall not apply to the combined annual target for any year that is any earlier than 2 calendar years after the calendar year in which such request is submitted, so as to provide retail electric suppliers with adequate notice of such change; and
- "(ii) any revision shall meet the requirements of subparagraph (A).
- "(c) ESTABLISHMENT OF PROGRAM.—Not later than 1 year after the date of enactment of this section, the Commission shall promulgate regulations to implement and enforce the requirements of this section. In promulgating such regulations, the Commission shall, to the extent practicable—
- "(1) preserve the integrity, and incorporate best practices, of existing State and tribal renewable electricity and energy efficiency programs:

- "(2) rely upon existing and emerging State, tribal, or regional tracking systems that issue and track non-Federal renewable electricity credits; and
- "(3) cooperate with the States and Indian tribes to facilitate coordination between State, tribal, and Federal renewable electricity and energy efficiency programs and to minimize administrative burdens and costs to retail electric suppliers.
- "(d) Annual Compliance Requirement.—
- "(1) ANNUAL COMBINED TARGETS.—For each of calendar years 2012 through 2039, a retail electric supplier's annual combined target shall be the product of—
- "(A) the required annual percentage for such year, as set forth in paragraph (2); and "(B) the retail electric supplier's base amount for such year.
- "(2) REQUIRED ANNUAL PERCENTAGE.—For each of calendar years 2012 through 2039, the required annual percentage shall be as follows:

"Calendar year	Required annual
	percentage
2012	6.0
2013	6.0
2014	9.5
2015	9.5
2016	13.0
2017	13.0
2018	16.5
2019	16.5
2020	20.0
2021 through 2039	20.0

- "(e) Federal Renewable Electricity Credits.—
- "(1) IN GENERAL.—The regulations promulgated under this section shall include provisions governing the issuance, tracking, and verification of Federal renewable electricity credits. Except as provided in paragraphs (2), (3), and (4) of this subsection, the Commission shall issue to each generator of renewable electricity, 1 Federal renewable electricity credit for each megawatt hour of renewable electricity generated by such generator after December 31, 2011. The Commission shall assign a unique serial number to each Federal renewable electricity credit.
- "(2) GENERATION FROM CERTAIN STATE RE-NEWABLE ELECTRICITY PROGRAMS.—"(A) Except as provided in subparagraph (B), where renewable electricity is generated with the support of payments from a retail electric supplier pursuant to a State renewable electricity program (whether through State alternative compliance payments or through payments to a State renewable electricity procurement fund or entity), the Commission shall issue Federal renewable electricity credits to such retail electric supplier for the proportion of the relevant renewable electricity generation that is attributable to the retail electric supplier's payments, as determined pursuant to regulations issued by the Commission. For any remaining portion of the relevant renewable electricity generation, the Commission shall issue Federal renewable electricity credits to the generator, as provided in paragraph (1), except that in no event shall more than 1 Federal renewable electricity credit be issued for the same megawatt hour of electricity. In determining how Federal renewable electricity credits will be apportioned among retail electric suppliers and generators in such circumstances, the Commission shall consider information and guidance furnished by the relevant State or States.
- "(B) In the case of a central procurement State that pursuant to subsection (g) has assumed responsibility for compliance with the requirements of subsection (b), the Commission shall issue directly to the State Federal renewable electricity credits for any renewable electricity for which the State, pursu-

- ant to a mandate described in subsection (a)(7), has centrally procured credits or certificates issued based on generation of such renewable electricity.
- "(3) CERTAIN POWER SALES CONTRACTS.—Except as otherwise provided in paragraph (2), when a generator has sold renewable electricity to a retail electric supplier under a contract for power from a facility placed in service before the date of enactment of this section, and the contract does not provide for the determination of ownership of the Federal renewable electricity credits associated with such generation, the Commission shall issue such Federal renewable electricity credits to the retail electric supplier for the duration of the contract.
- "
 (4) CREDIT MULTIPLIER FOR DISTRIBUTED RENEWABLE GENERATION.—
- "(A) IN GENERAL.—Except as provided in subparagraph (B), the Commission shall issue 3 Federal renewable electricity credits for each megawatt hour of renewable electricity generated by a distributed renewable generation facility.
- "(B) ADJUSTMENT.—Except as provided in subparagraph (C), not later than January 1, 2014, and not less frequently than every 4 years thereafter, the Commission shall review the effect of this paragraph and shall, as necessary, reduce the number of Federal renewable electricity credits per megawatt hour issued under this paragraph for any given energy source or technology, but not below 1, to ensure that such number is no higher than the Commission determines is necessary to make distributed renewable generation facilities using such source or technology cost competitive with other sources of renewable electricity generation.
- "(C) FACILITIES PLACED IN SERVICE AFTER ENACTMENT.—For any distributed renewable generation facility placed in service after the date of enactment of this section, subparagraph (B) shall not apply for the first 10 years after the date on which the facility is placed in service. For each year during such 10-year period, the Commission shall issue to the facility the same number of Federal renewable electricity credits per megawatt hour as are issued to that facility in the year in which such facility is placed in service. After such 10-year period, the Commission shall issue Federal renewable electricity credits to the facility in accordance with the current multiplier as determined pursuant to subparagraph (B).
- "(5) CREDITS BASED ON QUALIFIED HYDRO-POWER.—For purposes of this subsection, the number of Federal renewable electricity credits issued for qualified hydropower shall be calculated—
- "(A) based solely on the increase in average annual generation directly resulting from the efficiency improvements or capacity additions described in subsection (a)(13)(A); and
- "(B) using the same water flow information used to determine a historic average annual generation baseline for the hydroelectric facility, as certified by the Commission
- "(6) GENERATION FROM QUALIFIED WASTE-TO-ENERGY.—In the case of electricity generated from the combustion of any municipal solid waste or construction, demolition, or disaster debris that is included in the definition of renewable biomass, or from the gasification or pyrolization of such waste or debris and the combustion of the resulting gas at the same facility, the Commission shall issue Federal renewable electricity credits only for electricity generated from qualified waste-to-energy.
- "(7) GENERATION FROM MIXED RENEWABLE
 AND NONRENEWABLE RESOURCES.—If electricity is generated using both a renewable
 energy resource or other qualifying energy

resource and an energy source that is not a renewable energy resource or other qualifying energy resource (as, for example, in the case of co-firing of renewable biomass and fossil fuel), the Commission shall issue Federal renewable electricity credits based on the proportion of the electricity that is attributable to the renewable energy resource or other qualifying energy resource.

"(8) PROHIBITION AGAINST DOUBLE-COUNT-ING.—Except as provided in paragraph (4) of this subsection, the Commission shall ensure that no more than 1 Federal renewable electricity credit will be issued for any megawatt hour of renewable electricity and that no Federal renewable electricity credit will be used more than once for compliance with this section.

"(9) TRADING.—The lawful holder of a Federal renewable electricity credit may sell, exchange, transfer, submit for compliance in accordance with subsection (b), or submit such credit for retirement by the Commission

"(10) Banking.—A Federal renewable electricity credit may be submitted in satisfaction of the compliance obligation set forth in subsection (b) for the compliance year in which the credit was issued or for any of the 3 immediately subsequent compliance years. The Commission shall retire any Federal renewable electricity credit that has not been retired by April 2 of the calendar year that is 3 years after the calendar year in which the credit was issued.

"(11) RETIREMENT.—The Commission shall retire a Federal renewable electricity credit immediately upon submission by the lawful holder of such credit, whether in satisfaction of a compliance obligation under subsection (b) or on some other basis.

"(f) ELECTRICITY SAVINGS.—

"(1) STANDARDS FOR MEASUREMENT OF SAV-INGS.—As part of the regulations promulgated under this section, the Commission shall prescribe standards and protocols for defining and measuring electricity savings and total annual electricity savings that can be counted towards the compliance obligation set forth in subsection (b). Such protocols and standards shall, at minimum—

"(A) specify the types of energy efficiency and energy conservation measures that can be counted;

"(B) require that energy consumption estimates for customer facilities or portions of facilities in the applicable base and current years be adjusted, as appropriate, to account for changes in weather, level of production, and building area:

"(C) account for the useful life of measures;

"(D) include deemed savings values for specific, commonly used measures;

"(E) allow for savings from a program to be estimated based on extrapolation from a representative sample of participating customers;

"(F) include procedures for counting CHP savings, recycled energy savings, and fuel cell savings;

"(G) include procedures for documenting measurable and verifiable electricity savings achieved as a result of market transformation efforts;

"(H) include procedures for counting electricity savings achieved by solar water heating and solar light pipe technology that has the capability to provide measurable data on the amount of megawatt-hours displaced:

"(I) avoid double-counting of savings used for compliance with this section, including savings that are transferred pursuant to paragraph (3);

"(J) ensure that, except as provided in subparagraph (L), the retail electric supplier claiming the savings played a significant role in achieving the savings (including through the activities of a designated agent of the supplier or through the purchase of transferred savings);

"(K) include savings from programs administered by a retail electric supplier (or a retail electricity distributor that is not a retail electric supplier) that are funded by State, Federal, or other sources;

"(L) in any State in which the State regulatory authority has designated 1 or more entities to administer electric ratepayer-funded efficiency programs approved by such State regulatory authority, provide that electricity savings achieved through such programs shall be distributed equitably among retail electric suppliers in accordance with the direction of the relevant State regulatory authority; and

"(M) exclude savings achieved as a result of compliance with mandatory appliance and equipment efficiency standards or building codes

"(2) STANDARDS FOR THIRD-PARTY VERIFICATION OF SAVINGS.—The regulations promulgated under this section shall establish procedures and standards requiring third-party verification of all reported electricity savings, including requirements for accreditation of third-party verifiers to ensure that such verifiers are professionally qualified and have no conflicts of interest.

"(3) Transfers of Savings.—

"(A) BILATERAL CONTRACTS FOR SAVINGS TRANSFERS.—Subject to the limitations of this paragraph, a retail electric supplier may use electricity savings transferred, pursuant to a bilateral contract, from another retail electric supplier, an owner of an electric distribution facility that is not a retail electric supplier, a State, or a third-party efficiency provider to meet the applicable compliance obligation under subsection (b).

"(B) REQUIREMENTS.—Electricity savings transferred and used for compliance pursuant to this paragraph shall be—

"(i) measured and verified in accordance with the procedures specified under this subsection:

"(ii) reported in accordance with paragraph (4) of this subsection; and

"(iii) achieved within the same State as is served by the retail electric supplier.

"(C) REGULATORY APPROVAL.—Nothing in this paragraph shall limit or affect the authority of a State regulatory authority to require a retail electric supplier that is regulated by such authority to obtain such authority's authorization or approval of a contract for transfer of savings under this paragraph.

"(4) Reporting savings.—

"(A) REQUIREMENTS.—The regulations promulgated under this section shall establish requirements governing the submission of reports to demonstrate, in accordance with the protocols and standards for measurement and third-party verification established under this subsection, the total annual electricity savings achieved by a retail electric supplier within the relevant year.

"(B) REVIEW AND APPROVAL.—The Commission shall review each report submitted to the Commission by a retail electric supplier and shall exclude any electricity savings that have not been adequately demonstrated in accordance with the requirements of this subsection.

"(5) STATE ADMINISTRATION.—

"(A) DELEGATION OF AUTHORITY.—Upon receipt of an application from the Governor of a State (including, for purposes of this subsection, the Mayor of the District of Columbia), the Commission may delegate to the State the authority to review and verify reported electricity savings for purposes of determining demonstrated total annual electricity savings that may be counted towards a retail electric supplier's compliance obliga-

tion under subsection (b). The Commission shall make a substantive determination approving or disapproving a State application under this subparagraph, after notice and comment, within 180 days of receipt of a complete application.

"(B) ALTERNATIVE MEASUREMENT AND VERIFICATION PROCEDURES AND STANDARDS.—As part of an application submitted under subparagraph (A), a State may request to use alternative measurement and verification procedures and standards to those specified in paragraphs (1) and (2), provided the State demonstrates that such alternative procedures and standards provide a level of accuracy of measurement and verification at least equivalent to the Federal procedures and standards promulgated under paragraphs (1) and (2).

(C) REVIEW OF STATE IMPLEMENTATION.-The Commission shall, not less frequently than once every 4 years, review each State's implementation of delegated authority under this paragraph to ensure conformance with the requirements of this section. The Commission may, at any time, revoke the delegation of authority under this section upon a finding that the State is not implementing its delegated responsibilities in conformity with this paragraph. As a condition of maintaining its delegated authority under this paragraph, the Commission may require a State to submit a revised application under subparagraph (A) if the Commission has

"(i) promulgated new or substantially revised measurement and verification procedures and standards under this subsection; or "(ii) otherwise substantially revised the

"(ii) otherwise substantially revised program established under this section.

"(g) ALTERNATIVE COMPLIANCE PAY-MENTS.—

"(1) IN GENERAL.—A retail electric supplier ", or a central procurement State that, pursuant to subsection (g), has assumed responsibility for compliance with the requirements of subsection (b)," may satisfy the requirements of subsection (b) in whole or in part by submitting in accordance with this subsection, in lieu of each Federal renewable electricity credit or megawatt hour of demonstrated total annual electricity savings that would otherwise be due, a payment equal to \$25, adjusted for inflation on January 1 of each year following calendar year 2009, in accordance with such regulations as the Commission may promulgate.

(2) PAYMENT TO STATE FUNDS.—Except as otherwise provided in this paragraph and paragraph (4), payments made under this subsection shall be made directly to the State or States in which the retail electric supplier is located, in proportion to the portion of the retail electric supplier's base amount that is sold within each relevant State, provided that such payments are deposited directly into a fund in the State treasury established for this purpose and that the State uses such funds in accordance with paragraphs (3) and (5) and with paragraph (4) where applicable. If the Commission determines at any time that a State is in substantial noncompliance with paragraph (3) or (5), or with paragraph (4) where applicable, the Commission shall direct that any future alternative compliance payments that would otherwise be paid to such State under this subsection shall instead be paid to the Commission and deposited in the United States Treasury.

"(3) STATE USE OF FUNDS.—As a condition of continued receipt of alternative compliance payments pursuant to this subsection, a State shall use such payments exclusively for the purposes of—

"(A) deploying technologies that generate electricity from renewable energy resources; or

- "(B) implementing cost-effective energy efficiency programs to achieve electricity savings.
 - "(4) CENTRAL PROCUREMENT STATES.—
- "(A) In general.—A central procurement State that, pursuant to subsection (g), has assumed responsibility for compliance with the requirements of subsection (b) shall deposit any alternative compliance payments under this subsection in a unique fund in the State treasury created and used solely for this purpose.
- "(B) REQUIREMENTS.—As a precondition of making alternative compliance payments under this subsection, a central procurement State shall certify to the Commission, in accordance with such requirements as the Commission may prescribe, that—
- "(i) making such payments is the lowest cost alternative to meet the requirements of subsection (b); and
- "(ii) moneys used by the State to make such payments are in addition to any spending that the State, and any separate entity charged with administering the State central procurement requirement identified under subsection (a)(7), otherwise collectively would direct to the purposes identified in paragraph (3).
- "(C) USES.—A central procurement State that makes alternative compliance payments under this subsection shall certify to the Commission that, in using such payments in accordance with paragraph (3), it has, to the extent practicable, maximized the level of deployment of renewable electricity generation (measured in megawatt hours) and electricity savings per dollar that are achieved through such expenditures.
- "(5) REPORTING.—As a condition of continued receipt of alternative compliance payments pursuant to this subsection, a State shall, within 12 months of receipt of any such payments and at 12-month intervals thereafter until such payments are expended, provide a report to the Commission, in accordance with such regulations as the Commission may prescribe, giving a full accounting of the use of such payments, including a detailed description of the activities funded thereby and demonstrating compliance with the requirements of this subsection.
 - "(g) CENTRAL PROCUREMENT STATES.—
- "(1) IN GENERAL.—A central procurement State may, upon submission of a written request by the Governor of such State to the Commission, assume responsibility for compliance with the requirements of subsection (b) on behalf of retail electric suppliers located in such State, exclusively with regard to the portion of such retail electric suppliers' base amount that is sold within the State.
- "(2) DEMONSTRATION OF ELECTRICITY SAV-INGS.—If a central procurement State opts to meet any part of the requirements of subsection (b) based on the achievement of demonstrated total annual electricity savings, regardless of whether such State has received delegated authority pursuant to subsection (f)(5), such State shall submit such demonstrated total annual electricity savings to the Commission through an annual report in accordance with requirements prescribed by the Commission by regulation, which shall be of equivalent stringency to those applicable to retail electric suppliers under subsection (f).
- "(3) NONCOMPLIANCE.—If a central procurement State that pursuant to this subsection has assumed responsibility for compliance with the requirements of subsection (b), fails to satisfy the requirements of subsection (b) or (h) for any year, the State's assumption of responsibility under this subsection shall be discontinued immediately, and retail electric suppliers located in such State hence-

forth shall be directly subject to the requirements of this section.

"(h) INFORMATION COLLECTION.—The Com-

- "(h) Information Collection.—The Commission may require any retail electric supplier, renewable electricity generator, or such other entities as the Commission deems appropriate, to provide any information the Commission determines appropriate to carry out this section. Failure to submit such information or submission of false or misleading information under this subsection shall be a violation of this section.
- "(i) ENFORCEMENT AND JUDICIAL REVIEW.—
 "(1) FAILURE TO SUBMIT CREDITS OR DEMONSTRATE SAVINGS.—If any person ", other
 than any central procurement State that
 pursuant to subsection (g) has assumed responsibility for compliance with the requirements of subsection (b)," fails to comply
 with the requirements of subsection (b) or
 (h), such person shall be liable to pay to the
 Commission a civil penalty equal to the
 product of—
- "(A) double the alternative compliance payment calculated under subsection (h)(1), and
- "(B) the aggregate quantity of Federal renewable electricity credits, total annual electricity savings, or equivalent alternative compliance payments that the person failed to submit in violation of the requirements of subsections (b) and (h).
- "(2) ENFORCEMENT.—The Commission shall assess a civil penalty under paragraph (1) in accordance with the procedures described in section 31(d) of the Federal Power Act (16 U.S.C. 823b(d)).
- "(3) VIOLATION OF REQUIREMENT OF REGULATIONS OR ORDERS.—Any person ", other than any central procurement State that pursuant to subsection (g) has assumed responsibility for compliance with the requirements of subsection (b)," who violates, or fails or refuses to comply with, any requirement of a regulation promulgated or order issued under this section shall be subject to a civil penalty under section 316A(b) of the Federal Power Act (16 U.S.C. 8250-1). Such penalty shall be assessed by the Commission in the same manner as in the case of a violation referred to in section 316A(b) of such Act.
- "(j) JUDICIAL REVIEW.—Any person aggrieved by a final action taken by the Commission under this section, other than the assessment of a civil penalty under subsection (j), may use the procedures for review described in section 313 of the Federal Power Act (16 U.S.C. 8251). For purposes of this paragraph, references to an order in section 313 of such Act shall be deemed to refer also to all other final actions of the Commission under this section other than the assessment of a civil penalty under subsection (i).
- "(k) SAVINGS PROVISIONS.—Nothing in this section shall—
- "(1) diminish or qualify any authority of a State, a political subdivision of a State, or an Indian tribe to—
- "(A) adopt or enforce any law or regulation respecting renewable electricity or energy efficiency, including any law or regulation establishing requirements more stringent than those established by this section, provided that no such law or regulation may relieve any person of any requirement otherwise applicable under this section; or
- "(B) regulate the acquisition and disposition of Federal renewable electricity credits by retail electric suppliers within the jurisdiction of such State, political subdivision. or Indian tribe, including the authority to require such retail electric supplier to acquire and submit to the Secretary for retirement Federal renewable electricity credits in excess of those submitted under this section; or
- "(2) affect the application of, or the responsibility for compliance with, any other

- provision of law or regulation, including environmental and licensing requirements.
- "(1) SUNSET.—This section expires on December 31, 2040."
- (b) CONFORMING AMENDMENT.—The table of contents set forth in section 1(b) of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2601 and following) is amended by inserting after the item relating to section 609 the following:

"Sec. 610. Combined efficiency and renewable electricity standard.".

SEC. 102. CLARIFYING STATE AUTHORITY TO ADOPT RENEWABLE ENERGY INCENTIVES.

Section 210 of the Public Utility Regulatory Policies Act of 1978 is amended by adding at the end thereof:

(o) CLARIFICATION OF STATE AUTHORITY TO Adopt Renewable Energy Incentives. Notwithstanding any other provision of this Act or the Federal Power Act, a State legislature or regulatory authority may set the rates for a sale of electric energy by a facility generating electric energy from renewable energy sources pursuant to a State-approved production incentive program under which the facility voluntarily sells electric energy. For purposes of this subsection, 'State-approved production incentive program' means a requirement imposed pursuant to State law, or by a State regulatory authority acting within its authority under State law, that an electric utility purchase renewable energy (as defined in section 609 of this Act) at a specified rate.'

SEC. 103. FEDERAL RENEWABLE ENERGY PURCHASES.

(a) REQUIREMENT.—For each of calendar years 2012 through 2039, the President shall ensure that, of the total amount of electricity Federal agencies consume in the United States during each calendar year, the following percentage shall be renewable electricity:

Calendar year	Required annual per- centage
2012	6.0
2013	6.0
2014	9.5
2015	9.5
2016	13.0
2017	13.0
2018	16.5
2019	16.5
2020	20.0
2021 through 2039	

- (b) DEFINITIONS.—For purposes of this section:
- (1) RENEWABLE ELECTRICITY.—The term "renewable electricity" shall have the meaning given in section 610 of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2601 and following).
- (2) RENEWABLE ENERGY RESOURCE.—The term "renewable energy resource" shall have the meaning given in section 610 of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2601 and following).
- (c) Modification of Requirement.—If the President determines that the Federal Government cannot feasibly meet the requirement established in subsection (a) in a specific calendar year, the President may, by written order, reduce such requirement for such calendar year to a percentage the President determines the Federal Government can feasibly meet.
- (d) REPORTS.—Not later than April 1, 2013, and each year thereafter, the Secretary of Energy shall provide a report to Congress on the percentage of each Federal agency's electricity consumption in the United States that was renewable electricity in the previous calendar year.

- (e) CONTRACTS FOR RENEWABLE ENERGY.—
 (1) Notwithstanding section 501(b)(1)(B) of title 40, United States Code, a contract for the acquisition of electricity generated from a renewable energy resource for the Federal Government may be made for a period of not more than 20 years.
- (2) Not later than 90 days after the date of enactment of this subsection, the Secretary of Energy, through the Federal Energy Management Program, shall publish a standardized renewable energy purchase agreement, setting forth commercial terms and conditions, that Federal agencies may use to acquire electricity generated from a renewable energy resource.
- (3) The Secretary of Energy shall provide technical assistance to assist Federal agencies in implementing this subsection.

Subtitle B—Carbon Capture and Sequestration

SEC. 111. NATIONAL STRATEGY.

- (a) IN GENERAL.—Not later than 1 year after the date of enactment of this Act, the Administrator, in consultation with the Secretary of Energy, the Secretary of the Interior, and the heads of such other relevant Federal agencies as the President may designate, shall submit to Congress a report setting forth a unified and comprehensive strategy to address the key legal, regulatory and other barriers to the commercial-scale deployment of carbon capture and sequestration.
- (b) BARRIERS.— The report under this section shall—
- (1) identify those regulatory, legal, and other gaps and barriers that could be addressed by a Federal agency using existing statutory authority, those, if any, that require Federal legislation, and those that would be best addressed at the State, tribal, or regional level:
- (2) identify regulatory implementation challenges, including those related to approval of State and tribal programs and delegation of authority for permitting; and
- (3) recommend rulemakings, Federal legislation, or other actions that should be taken to further evaluate and address such barriers.

SEC. 112. REGULATIONS FOR GEOLOGIC SEQUESTRATION SITES.

(a) COORDINATED CERTIFICATION AND PERMITTING PROCESS.—Title VIII of the Clean Air Act, as added by section 331 of this Act, is amended by adding after section 812 (as added by section 116 of this Act) the following:

"SEC. 813. GEOLOGIC SEQUESTRATION SITES.

- "(a) COORDINATED PROCESS.—The Administrator shall establish a coordinated approach to certifying and permitting geologic sequestration, taking into consideration all relevant statutory authorities. In establishing such approach, the Administrator shall—
- "(1) take into account, and reduce redundancy with, the requirements of section 1421 of the Safe Drinking Water Act (42 U.S.C. 300h), as amended by section 112(b) of the American Clean Energy and Security Act of 2009, including the rulemaking for geologic sequestration wells described at 73 Fed. Reg. 43491–541 (July 25, 2008); and
- "(2) to the extent practicable, reduce the burden on certified entities and implementing authorities.
- "(b) REGULATIONS.—Not later than 2 years after the date of enactment of this title, the Administrator shall promulgate regulations to protect human health and the environment by minimizing the risk of escape to the atmosphere of carbon dioxide injected for purposes of geologic sequestration.
- "(c) REQUIREMENTS.—The regulations under subsection (b) shall include—

- "(1) a process to obtain certification for geologic sequestration under this section; and
 - "(2) requirements for—
- "(A) monitoring, record keeping, and reporting for emissions associated with injection into, and escape from, geologic sequestration sites, taking into account any requirements or protocols developed under section 713:
- "(B) public participation in the certification process that maximizes transparency;
- "(C) the sharing of data between States, Indian tribes, and the Environmental Protection Agency; and
- "(D) other elements or safeguards necessary to achieve the purpose set forth in subsection (b).
- "(d) REPORT.—Not later than 2 years after the promulgation of regulations under subsection (b), and at 3-year intervals therefier, the Administrator shall deliver to the Committee on Energy and Commerce of the House of Representatives and the Committee on Environment and Public Works of the Senate a report on geologic sequestration in the United States, and, to the extent relevant, other countries in North America. Such report shall include—
- "(1) data regarding injection, emissions to the atmosphere, if any, and performance of active and closed geologic sequestration sites, including those where enhanced hydrocarbon recovery operations occur:
- "(2) an evaluation of the performance of relevant Federal environmental regulations and programs in ensuring environmentally protective geologic sequestration practices;
- "(3) recommendations on how such programs and regulations should be improved or made more effective; and
- "(4) other relevant information."
- (b) SAFE DRINKING WATER ACT STANDARDS.—Section 1421 of the Safe Drinking Water Act (42 U.S.C. 300h) is amended by inserting after subsection (d) the following:
- "(e) CARBON DIOXIDE GEOLOGIC SEQUESTRATION WELLS.—
- "(1) IN GENERAL.—Not later than 1 year after the date of enactment of this subsection, the Administrator shall promulgate regulations under subsection (a) for carbon dioxide geologic sequestration wells.
- (2) FINANCIAL RESPONSIBILITY.—The regulations referred to in paragraph (1) shall include requirements for maintaining evidence of financial responsibility, including financial responsibility for emergency and remedial response, well plugging, site closure, and post-injection site care. Financial responsibility may be established for carbon dioxide geologic sequestration wells in accordance with regulations promulgated by the Administrator by any one, or any combination, of the following: insurance, guarantee, trust, standby trust, surety bond, letter of credit, qualification as a self-insurer, or any other method satisfactory to the Administrator.". SEC. 113. STUDIES AND REPORTS.
- (a) STUDY OF LEGAL FRAMEWORK FOR GEOLOGIC SEQUESTRATION SITES.—
- (1) ESTABLISHMENT OF TASK FORCE.—As soon as practicable, but not later than 6 months after the date of enactment of this Act, the Administrator shall establish a task force to be composed of an equal number of subject matter experts, nongovernmental organizations with expertise in environmental policy, academic experts with expertise in environmental law, State and tribal officials with environmental expertise, representatives of State and tribal Attorneys General, representatives from the Environmental Protection Agency, the Department of the Interior, the Department of Energy, the Department of Transportation, and other relevant Federal agencies, and members of the private sector, to conduct a study of-

- (A) existing Federal environmental statutes, State environmental statutes, and State common law that apply to geologic sequestration sites for carbon dioxide, including the ability of such laws to serve as risk management tools;
- (B) the existing statutory framework, including Federal and State laws, that apply to harm and damage to the environment or public health at closed sites where carbon dioxide injection has been used for enhanced hydrocarbon recovery;
- (C) the statutory framework, environmental health and safety considerations, implementation issues, and financial implications of potential models for Federal, State, or private sector assumption of liabilities and financial responsibilities with respect to closed geologic sequestration sites;
- (D) private sector mechanisms, including insurance and bonding, that may be available to manage environmental, health and safety risk from closed geologic sequestration sites; and
- (E) the subsurface mineral rights, water rights, or property rights issues associated with geologic sequestration of carbon dioxide, including issues specific to Federal lands.
- (2) REPORT.—Not later than 18 months after the date of enactment of this Act, the task force established under paragraph (1) shall submit to Congress a report describing the results of the study conducted under that paragraph including any consensus recommendations of the task force.
 - (b) Environmental Statutes.-
- (1) STUDY.—The Administrator shall conduct a study examining how, and under what circumstances, the environmental statutes for which the Environmental Protection Agency has responsibility would apply to carbon dioxide injection and geologic sequestration activities.
- (2) REPORT.—Not later than 1 year after the date of enactment of this Act, the Administrator shall submit to Congress a report describing the results of the study conducted under paragraph (1).

SEC. 114. CARBON CAPTURE AND SEQUESTRA-TION DEMONSTRATION AND EARLY DEPLOYMENT PROGRAM.

- (a) DEFINITIONS.—For purposes of this section:
- (1) SECRETARY.—The term "Secretary" means the Secretary of Energy.
- (2) DISTRIBUTION UTILITY.—The term "distribution utility" means an entity that distributes electricity directly to retail consumers under a legal, regulatory, or contractual obligation to do so.
- (3) ELECTRIC UTILITY.—The term "electric utility" has the meaning provided by section 3(22) of the Federal Power Act (16 U.S.C. 796(22)).
- (4) Fossil fuel-based electricity.—The term "fossil fuel-based electricity" means electricity that is produced from the combustion of fossil fuels.
- (5) FOSSIL FUEL.—The term "fossil fuel" means coal, petroleum, natural gas or any derivative of coal, petroleum, or natural gas.
- (6) CORPORATION.—The term "Corporation" means the Carbon Storage Research Corporation established in accordance with this section.
- (7) QUALIFIED INDUSTRY ORGANIZATION.— The term "qualified industry organization" means the Edison Electric Institute, the American Public Power Association, the National Rural Electric Cooperative Association, a successor organization of such organizations, or a group of owners or operators of distribution utilities delivering fossil fuel-based electricity who collectively represent at least 20 percent of the volume of fossil

fuel-based electricity delivered by distribution utilities to consumers in the United States.

- (8) RETAIL CONSUMER.—The term "retail consumer" means an end-user of electricity.
 (b) CARBON STORAGE RESEARCH CORPORA-
 - (1) Establishment.—
- (A) REFERENDUM.—Qualified industry organizations may conduct, at their own expense, a referendum among the owners or operators of distribution utilities delivering fossil fuelbased electricity for the creation of a Carbon Storage Research Corporation, Such referendum shall be conducted by an independent auditing firm agreed to by the qualified industry organizations. Voting rights in such referendum shall be based on the quantity of fossil fuel-based electricity delivered to consumers in the previous calendar year or other representative period as determined by the Secretary pursuant to subsection (f). Upon approval of those persons representing two-thirds of the total quantity of fossil fuel-based electricity delivered to retail consumers, the Corporation shall be established unless opposed by the State regulatory authorities pursuant to subparagraph (B). All distribution utilities voting in the referendum shall certify to the independent auditing firm the quantity of fossil fuel-based electricity represented by their vote.
- (B) STATE REGULATORY AUTHORITIES. its own motion or the petition of a qualified industry organization, each State regulatory authority shall consider its support or opposition to the creation of the Corporation under subparagraph (A). State regulatory authorities may notify the independent auditing firm referred to in subparagraph (A) of their views on the creation of the Corporation within 180 days after the date of enactment of this Act. If 40 percent or more of the State regulatory authorities submit to the independent auditing firm written notices of opposition, the Corporation shall not be established notwithstanding the approval of the qualified industry organizations as provided in subparagraph (A).
- (2) TERMINATION.—The Corporation shall be authorized to collect assessments and conduct operations pursuant to this section for a 10-year period from the date 6 months after the date of enactment of this Act. After such 10-year period, the Corporation is no longer authorized to collect assessments and shall be dissolved on the date 15 years after such date of enactment, unless the period is extended by an Act of Congress.
- (3) GOVERNANCE.—The Corporation shall operate as a division or affiliate of the Electric Power Research Institute (referred to in this section as "EPRI") and be managed by a Board of not more than 15 voting members responsible for its operations, including compliance with this section. EPRI, in consultation with the Edison Electric Institute, the American Public Power Association and the National Rural Electric Cooperative Association shall appoint the Board members under clauses (i), (ii), and (iii) of subparagraph (A) from among candidates recommended by those organizations. At least a majority of the Board members appointed by EPRI shall be representatives of distribution utilities subject to assessments under subsection (d).
- (A) MEMBERS.—The Board shall include at least one representative of each of the fol-
 - (i) Investor-owned utilities.
- (ii) Utilities owned by a State agency, a municipality, and an Indian tribe.
 - (iii) Rural electric cooperatives.
 - (iv) Fossil fuel producers.
- (v) Nonprofit environmental organizations. (vi) Independent generators or wholesale power providers.
 - (vii) Consumer groups.

- (B) NONVOTING MEMBERS.—The Board shall also include as additional nonvoting Members the Secretary of Energy or his designee and 2 representatives of State regulatory authorities as defined in section 3(17) of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2602(17)), each designated by the National Association of State Regulatory Utility Commissioners from States that are not within the same transmission interconnection.
- (4) COMPENSATION.—Corporation Board members shall receive no compensation for their services, nor shall Corporation Board members be reimbursed for expenses relating to their service.
- (5) TERMS.—Corporation Board members shall serve terms of 4 years and may serve not more than 2 full consecutive terms. Members filling unexpired terms may serve not more than a total of 8 consecutive years. Former members of the Corporation Board may be reappointed to the Corporation Board if they have not been members for a period of 2 years. Initial appointments to the Corporation Board shall be for terms of 1, 2, 3, and 4 years, staggered to provide for the selection of 3 members each year.
- (6) STATUS OF CORPORATION.—The Corporation shall not be considered to be an agency, department, or instrumentality of the United States, and no officer or director or employee of the Corporation shall be considered to be an officer or employee of the United States Government, for purposes of title 5 or title 31 of the United States Code, or for any other purpose, and no funds of the Corporation shall be treated as public money for purposes of chapter 33 of title 31, United States Code, or for any other purpose.
- (c) Functions and Administration of the Corporation.—
- (1) IN GENERAL.—The Corporation shall establish and administer a program to accelerate the commercial availability of carbon dioxide capture and storage technologies and methods, including technologies which capture and store, or capture and convert, carbon dioxide. Under such program competitively awarded grants, contracts, and financial assistance shall be provided and entered into with eligible entities. Except as provided in paragraph (8), the Corporation shall use all funds derived from assessments under subsection (d) to issue grants and contracts to eligible entities.
- (2) PURPOSE.—The purposes of the grants, contracts, and assistance under this subsection shall be to support commercial-scale demonstrations of carbon capture or storage technology projects capable of advancing the technologies to commercial readiness. Such projects should encompass a range of different coal and other fossil fuel varieties, be geographically diverse, involve diverse storage media, and employ capture or storage, or capture and conversion, technologies potentially suitable either for new or for retrofit applications. The Corporation shall seek, to the extent feasible, to support at least 5 commercial-scale demonstration projects integrating carbon capture and sequestration or conversion technologies.
- (3) ELIGIBLE ENTITIES.—Entities eligible for grants, contracts or assistance under this subsection may include distribution utilities, electric utilities and other private entities, academic institutions, national laboratories, Federal research agencies, State and tribal research agencies, nonprofit organizations, or consortiums of 2 or more entities. Pilot-scale and similar small-scale projects are not eligible for support by the Corporation. Owners or developers of projects supported by the Corporation shall, where appropriate, share in the costs of such projects.
- (4) GRANTS FOR EARLY MOVERS.—Fifty percent of the funds raised under this section

- shall be provided in the form of grants to electric utilities that had, prior to the award of any grant under this section, committed resources to deploy a large scale electricity generation unit with integrated carbon capture and sequestration or conversion applied to a substantial portion of the unit's carbon dioxide emissions. Grant funds shall be provided to defray costs incurred by such electricity utilities for at least 5 such electricity generation units.
- (5) ADMINISTRATION.—The members of the Board of Directors of the Corporation shall elect a Chairman and other officers as necessary, may establish committees and subcommittees of the Corporation, and shall adopt rules and bylaws for the conduct of business and the implementation of this section. The Board shall appoint an Executive Director and professional support staff who may be employees of the Electric Power Research Institute (EPRI). After consultation with the Technical Advisory Committee established under subsection (j), the Secretary, and the Director of the National Energy Technology Laboratory to obtain advice and recommendations on plans, programs, and project selection criteria, the Board shall establish priorities for grants, contracts, and assistance: publish requests for proposals for grants, contracts, and assistance; and award grants, contracts, and assistance competitively, on the basis of merit, after the establishment of procedures that provide for scientific peer review by the Technical Advisory Committee. The Board shall give preference to applications that reflect the best overall value and prospect for achieving the purposes of the section, such as those which demonstrate an integrated approach for capture and storage or capture and conversion technologies. The Board members shall not participate in making grants or awards to entities with whom they are affiliated.
- (6) USES OF GRANTS, CONTRACTS, AND ASSISTANCE.—A grant, contract, or other assistance provided under this subsection may be used to purchase carbon dioxide when needed to conduct tests of carbon dioxide storage sites, in the case of established projects that are storing carbon dioxide emissions, or for other purposes consistent with the purposes of this section. The Corporation shall make publicly available at no cost information learned as a result of projects which it supports financially.
- (7) INTELLECTUAL PROPERTY.—The Board shall establish policies regarding the ownership of intellectual property developed as a result of Corporation grants and other forms of technology support. Such policies shall encourage individual ingenuity and invention.
- (8) ADMINISTRATIVE EXPENSES.—Up to 5 percent of the funds collected in any fiscal year under subsection (d) may be used for the administrative expenses of operating the Corporation (not including costs incurred in the determination and collection of the assessments pursuant to subsection (d)).
- (9) Programs and Budget.—Before August 1 each year, the Corporation, after consulting with the Technical Advisory Committee and the Secretary and the Director of the Department's National Energy Technology Laboratory and other interested parties to obtain advice and recommendations, shall publish for public review and comment its proposed plans, programs, project selection criteria, and projects to be funded by the Corporation for the next calendar year. The Corporation shall also publish for public review and comment a budget plan for the next calendar year, including the probable costs of all programs, projects, and contracts and a recommended rate of assessment sufficient to cover such costs. The Secretary may

recommend programs and activities the Secretary considers appropriate. The Corporation shall include in the first publication it issues under this paragraph a strategic plan or roadmap for the achievement of the purposes of the Corporation, as set forth in paragraph (2).

- (10) RECORDS; AUDITS.—The Corporation shall keep minutes, books, and records that clearly reflect all of the acts and transactions of the Corporation and make public such information. The books of the Corporation shall be audited by a certified public accountant at least once each fiscal year and at such other times as the Corporation may designate. Copies of each audit shall be provided to the Congress, all Corporation board members, all qualified industry organizations, each State regulatory authority and, upon request, to other members of the industry. If the audit determines that the Corporation's practices fail to meet generally accepted accounting principles the assessment collection authority of the Corporation under subsection (d) shall be suspended until a certified public accountant renders a subsequent opinion that the failure has been corrected. The Corporation shall make its books and records available for review by the Secretary or the Comptroller General of the United States.
- (11) PUBLIC ACCESS.—The Corporation Board's meetings shall be open to the public and shall occur after at least 30 days advance public notice. Meetings of the Board of Directors may be closed to the public where the agenda of such meetings includes only confidential matters pertaining to project selection, the award of grants or contracts, personnel matters, or the receipt of legal advice. The minutes of all meetings of the Corporation shall be made available to and readily accessible by the public.
- (12) ANNUAL REPORT.—Each year the Corporation shall prepare and make publicly available a report which includes an identification and description of all programs and projects undertaken by the Corporation during the previous year. The report shall also detail the allocation or planned allocation of Corporation resources for each such program and project. The Corporation shall provide its annual report to the Congress, the Secretary, each State regulatory authority, and upon request to the public. The Secretary shall, not less than 60 days after receiving such report, provide to the President and Congress a report assessing the progress of the Corporation in meeting the objectives of this section.

(d) Assessments.—

(1) AMOUNT.—(A) In all calendar years following its establishment, the Corporation shall collect an assessment on distribution utilities for all fossil fuel-based electricity delivered directly to retail consumers (as determined under subsection (f)). The assessments shall reflect the relative carbon dioxide emission rates of different fossil fuel-based electricity, and initially shall be not less than the following amounts for coal, natural gas, and oil:

navurar gas, and on.	
Fuel type	Rate of
	assessment
	per kilowatt
	hour
Coal	\$0.00043
Natural Gas	\$0.00022
Oil	\$0.00032.

(B) The Corporation is authorized to adjust the assessments on fossil fuel-based electricity to reflect changes in the expected quantities of such electricity from different fuel types, such that the assessments generate not less than \$1.0 billion and not more than \$1.1 billion annually. The Corporation

is authorized to supplement assessments through additional financial commitments.

- (2) INVESTMENT OF FUNDS.—Pending disbursement pursuant to a program, plan, or project, the Corporation may invest funds collected through assessments under this subsection, and any other funds received by the Corporation, only in obligations of the United States or any agency thereof, in general obligations of any State or any political subdivision thereof, in any interest-bearing account or certificate of deposit of a bank that is a member of the Federal Reserve System, or in obligations fully guaranteed as to principal and interest by the United States.
- (3) REVERSION OF UNUSED FUNDS.—If the Corporation does not disburse, dedicate or assign 75 percent or more of the available proceeds of the assessed fees in any calendar year 7 or more years following its establishment, due to an absence of qualified projects or similar circumstances, it shall reimburse the remaining undedicated or unassigned balance of such fees, less administrative and other expenses authorized by this section, to the distribution utilities upon which such fees were assessed, in proportion to their collected assessments.
 - (e) ERCOT.—
- (1) ASSESSMENT, COLLECTION, AND REMITTANCE.—(A) Notwithstanding any other provision of this section, within ERCOT, the assessment provided for in subsection (d) shall be—
- (i) levied directly on qualified scheduling entities, or their successor entities;
- (ii) charged consistent with other charges imposed on qualified scheduling entities as a fee on energy used by the load-serving entities: and
- (iii) collected and remitted by ERCOT to the Corporation in the amounts and in the same manner as set forth in subsection (d).
- (B) The assessment amounts referred to in subparagraph (A) shall be—
- (i) determined by the amount and types of fossil fuel-based electricity delivered directly to all retail customers in the prior calendar year beginning with the year ending immediately prior to the period described in subsection (b)(2); and
- (ii) take into account the number of renewable energy credits retired by the load-serving entities represented by a qualified scheduling entity within the prior calendar year.
- (2) ADMINISTRATION EXPENSES.—Up to 1 percent of the funds collected in any fiscal year by ERCOT under the provisions of this subsection may be used for the administrative expenses incurred in the determination, collection and remittance of the assessments to the Corporation.
- (3) AUDIT.—ERCOT shall provide a copy of its annual audit pertaining to the administration of the provisions of this subsection to the Corporation.
- (4) DEFINITIONS.—For the purposes of this subsection:
- (A) The term ''ERCOT'' means the Electric Reliability Council of Texas.
- (B) The term "load-serving entities" has the meaning adopted by ERCOT Protocols and in effect on the date of enactment of this Act.
- (C) The term "qualified scheduling entities" has the meaning adopted by ERCOT Protocols and in effect on the date of enactment of this Act.
- (D) The term "renewable energy credit" has the meaning as promulgated and adopted by the Public Utility Commission of Texas pursuant to section 39.904(b) of the Public Utility Regulatory Act of 1999, and in effect on the date of enactment of this Act.
- (f) DETERMINATION OF FOSSIL FUEL-BASED ELECTRICITY DELIVERIES.—
- (1) FINDINGS.—The Congress finds that:

- (A) The assessments under subsection (d) are to be collected based on the amount of fossil fuel-based electricity delivered by each distribution utility.
- (B) Since many distribution utilities purchase all or part of their retail consumer's electricity needs from other entities, it may not be practical to determine the precise fuel mix for the power sold by each individual distribution utility.
- (C) It may be necessary to use average data, often on a regional basis with reference to Regional Transmission Organization ("RTO") or NERC regions, to make the determinations necessary for making assessments.
- (2) DOE PROPOSED RULE.—The Secretary, acting in close consultation with the Energy Information Administration, shall issue for notice and comment a proposed rule to determine the level of fossil fuel electricity delivered to retail customers by each distribution utility in the United States during the most recent calendar year or other period determined to be most appropriate. Such proposed rule shall balance the need to be efficient, reasonably precise, and timely, taking into account the nature and cost of data currently available and the nature of markets and regulation in effect in various regions of the country. Different methodologies may be applied in different regions if appropriate to obtain the best balance of such factors.
- (3) FINAL BULE —Within 6 months after the date of enactment of this Act, and after opportunity for comment, the Secretary shall issue a final rule under this subsection for determining the level and type of fossil fuelbased electricity delivered to retail customers by each distribution utility in the United States during the appropriate period. In issuing such rule, the Secretary may consider opportunities and costs to develop new data sources in the future and issue recommendations for the Energy Information Administration or other entities to collect such data. After notice and opportunity for comment the Secretary may, by rule, subsequently update and modify the methodology for making such determinations.
- (4) ANNUAL DETERMINATIONS.—Pursuant to the final rule issued under paragraph (3), the Secretary shall make annual determinations of the amounts and types for each such utility and publish such determinations in the Federal Register. Such determinations shall be used to conduct the referendum under subsection (b) and by the Corporation in applying any assessment under this subsection.
- (5) REHEARING AND JUDICIAL REVIEW.—The owner or operator of any distribution utility that believes that the Secretary has misapplied the methodology in the final rule in determining the amount and types of fossil fuel electricity delivered by such distribution utility may seek rehearing of such determination within 30 days of publication of the determination in the Federal Register. The Secretary shall decide such rehearing petitions within 30 days. The Secretary's determinations following rehearing shall be final and subject to judicial review in the United States Court of Appeals for the District of Columbia.
- (g) COMPLIANCE WITH CORPORATION ASSESS-MENTS.—The Corporation may bring an action in the appropriate court of the United States to compel compliance with an assessment levied by the Corporation under this section. A successful action for compliance under this subsection may also require payment by the defendant of the costs incurred by the Corporation in bringing such action.

- (h) MIDCOURSE REVIEW.—Not later than 5 years following establishment of the Corporation, the Comptroller General of the United States shall prepare an analysis, and report to Congress, assessing the Corporation's activities, including project selection and methods of disbursement of assessed fees, impacts on the prospects for commercialization of carbon capture and storage technologies, adequacy of funding, and administration of funds. The report shall also make such recommendations as may be appropriate in each of these areas. The Corporation shall reimburse the Government Accountability Office for the costs associated with performing this midcourse review.
- (i) RECOVERY OF COSTS.—

 (1) IN GENERAL.—A distribution utility whose transmission, delivery, or sales of electric energy are subject to any form of rate regulation shall not be denied the opportunity to recover the full amount of the prudently incurred costs associated with complying with this section, consistent with applicable State or Federal law.
- (2) RATEPAYER REBATES.—Regulatory authorities that approve cost recovery pursuant to paragraph (1) may order rebates to ratepayers to the extent that distribution utilities are reimbursed undedicated or unassigned balances pursuant to subsection (d)(3).
 - (j) TECHNICAL ADVISORY COMMITTEE.—
- (1) ESTABLISHMENT.—There is established an advisory committee, to be known as the "Technical Advisory Committee".
- (2) MEMBERSHIP.—The Technical Advisory Committee shall be comprised of not less than 7 members appointed by the Board from among academic institutions, national laboratories, independent research institutions, and other qualified institutions. No member of the Committee shall be affiliated with EPRI or with any organization having members serving on the Board. At least one member of the Committee shall be appointed from among officers or employees of the Department of Energy recommended to the Board by the Secretary of Energy.
- (3) CHAIRPERSON AND VICE CHAIRPERSON.— The Board shall designate one member of the Technical Advisory Committee to serve as Chairperson of the Committee and one to serve as Vice Chairperson of the Committee.
- (4) COMPENSATION.—The Board shall provide compensation to members of the Technical Advisory Committee for travel and other incidental expenses and such other compensation as the Board determines to be necessary.
- (5) PURPOSE.—The Technical Advisory Committee shall provide independent assessments and technical evaluations, as well as make non-binding recommendations to the Board, concerning Corporation activities, including but not limited to the following:
- (A) Reviewing and evaluating the Corporation's plans and budgets described in subsection (c)(9), as well as any other appropriate areas, which could include approaches to prioritizing technologies, appropriateness of engineering techniques, monitoring and verification technologies for storage, geological site selection, and cost control measures.
- (B) Making annual non-binding recommendations to the Board concerning any of the matters referred to in subparagraph (A), as well as what types of investments, scientific research, or engineering practices would best further the goals of the Corporation.
- (6) PUBLIC AVAILABILITY.—All reports, evaluations, and other materials of the Technical Advisory Committee shall be made available to the public by the Board, without charge, at time of receipt by the Board.
- (k) LOBBYING RESTRICTIONS.—No funds collected by the Corporation shall be used in

- any manner for influencing legislation or elections, except that the Corporation may recommend to the Secretary and the Congress changes in this section or other statutes that would further the purposes of this section.
- (1) DAVIS-BACON COMPLIANCE.—The Corporation shall ensure that entities receiving grants, contracts, or other financial support from the Corporation for the project activities authorized by this section are in compliance with the Davis-Bacon Act (40 U.S.C. 276a–276a–5).

SEC. 115. COMMERCIAL DEPLOYMENT OF CARBON CAPTURE AND SEQUESTRATION TECHNOLOGIES.

Part H of title VII of the Clean Air Act (as added by section 321 of this Act) is amended by adding the following new section after section 785:

"SEC. 786. COMMERCIAL DEPLOYMENT OF CAR-BON CAPTURE AND SEQUESTRATION TECHNOLOGIES.

- "(a) REGULATIONS.—Not later than 2 years after the date of enactment of this title, the Administrator shall promulgate regulations providing for the distribution of emission allowances allocated pursuant to section 782(f), pursuant to the requirements of this section, to support the commercial deployment of carbon capture and sequestration technologies in both electric power generation and industrial operations.
- "(b) ELIGIBILITY CRITERIA.—For an owner or operator of a project to be eligible to receive emission allowances under this section, the project must—
- "(1) implement carbon capture and sequestration technology—
- "(A) at an electric generating unit that—
 "(i) has a nameplate capacity of 200
- "(i) has a nameplate capacity of 200 megawatts or more;
 "(ii) in the case of a retrofit application,
- "(11) in the case of a retrofit application, applies the carbon capture and sequestration technology to the flue gas from at least 200 megawatts of the total nameplate generating capacity of the unit, provided that clause (i) shall apply without exception;
- "(iii) derives at least 50 percent of its annual fuel input from coal, petroleum coke, or any combination of these 2 fuels; and
- "(iv) upon implementation of capture and sequestration technology, will achieve an emission limit that is at least a 50 percent reduction in emissions of the carbon dioxide produced by—
- "(I) the unit, measured on an annual basis, determined in accordance with section 812(b)(2); or
- "(II) in the case of retrofit applications under clause (ii), the treated portion of flue gas from the unit, measured on an annual basis, determined in accordance with section 812(b)(2): or
 - "(B) at an industrial source that-
- "(i) absent carbon capture and sequestration, would emit greater than 50,000 tons per year of carbon dioxide;
- "(ii) upon implementation, will achieve an emission limit that is at least a 50 percent reduction in emissions of the carbon dioxide produced by the emission point, measured on an annual basis, determined in accordance with section 812(b)(2); and
- "(iii) does not produce a liquid transportation fuel from a solid fossil-based feedstock;
- "(2) geologically sequester carbon dioxide at a site that meets all applicable permitting and certification requirements for geologic sequestration, or, pursuant to such requirements as the Administrator may prescribe by regulation, convert captured carbon dioxide to a stable form that will safely and permanently sequester such carbon dioxide;
- "(3) meet all other applicable State, tribal, and Federal permitting requirements; and
 - "(4) be located in the United States.

- "(c) Phase I Distribution to Electric Generating Units.—
- "(1) APPLICATION.—This subsection shall apply only to projects at the first 6 gigawatts of electric generating units, measured in cumulative generating capacity of such units, that receive allowances under this section.
- "(2) DISTRIBUTION.—The Administrator shall distribute emission allowances allocated under section 782(f) to the owner or operator of each eligible project at an electric generating unit in a quantity equal to the quotient obtained by dividing—
- "(A) the product obtained by multiplying—
 "(i) the number of metric tons of carbon dioxide emissions avoided through capture and sequestration of emissions by the project, as determined pursuant to such methodology as the Administrator shall prescribe by regulation; and
- "(ii) a bonus allowance value, pursuant to paragraph (3); by
- "(B) the average fair market value of an emission allowance during the preceding year.
 - "(3) Bonus allowance values.—
- "(A) For a generating unit achieving the capture and sequestration of 85 percent or more of the carbon dioxide that otherwise would be emitted by such unit, the bonus allowance value shall be \$90 per ton.
- "(B) The Administrator shall by regulation establish a bonus allowance value for each rate of lower capture and sequestration achieved by a generating unit, from a minimum of \$50 per ton for a 50 percent rate and varying directly with increasing rates of capture and sequestration up to \$90 per ton for an 85 percent rate.
- "(C) For a generating unit that achieves the capture and sequestration of at least 50 percent of the carbon dioxide that otherwise would be emitted by such unit by not later than January 1, 2017, the otherwise applicable bonus allowance value under this paragraph shall be increased by \$10, provided that the owner of such unit notifies the Administrator by not later than January 1, 2012, of its intent to achieve such rate of capture and sequestration.
- (ID) For a carbon capture and sequestration project sequestering in a geological formation for purposes of enhanced hydrocarbon recovery, the Administrator shall, by regulation, reduce the applicable bonus allowance value under this paragraph to reflect the lower net cost of the project when compared to sequestration into geological formations solely for purposes of sequestration.
- "(E) The Administrator shall annually adjust for inflation the bonus allowance values established under this paragraph.
- "(d) Phase II Distribution to Electric Generating Units.—
- "(1) APPLICATION.—This subsection shall apply only to the distribution of emission allowances for carbon capture and sequestration projects at electric generating units after the capacity threshold identified in subsection (c)(1) is reached.
- "(2) REGULATIONS.—Not later than 2 years prior to the date on which the capacity threshold identified in subsection (c)(1) is projected to be reached, the Administrator shall promulgate regulations to govern the distribution of emission allowances to the owners or operators of eligible projects under this subsection.
 - "(3) REVERSE AUCTIONS.—
- "(A) IN GENERAL.—Except as provided in paragraph (4), the regulations promulgated under paragraph (2) shall provide for the distribution of emission allowances to the owners or operators of eligible projects under this subsection through reverse auctions, which shall be held no less frequently than

once each calendar year. The Administrator may establish a separate auction for each of no more than 5 different project categories, defined on the basis of coal type, capture technology, geological formation type, new unit versus retrofit application, such other factors as the Administrator may prescribe, or any combination thereof. The Administrator may establish appropriate minimum rates of capture and sequestration in implementing this paragraph.

"(B) AUCTION PROCESS.—At each reverse auction—

"(i) the Administrator shall solicit bids from eligible projects;

"(ii) eligible projects participating in the auction shall submit a bid including the desired level of carbon dioxide sequestration incentive per ton and the estimated quantity of carbon dioxide that the project will permanently sequester over 10 years; and

"(iii) the Administrator shall select bids, within each auction, for the sequestration amount submitted, beginning with the eligible project submitting the bid for the lowest level of sequestration incentive on a per ton basis and meeting such other requirements as the Administrator may specify, until the amount of funds available for the reverse auction is committed.

"(C) FORM OF DISTRIBUTION.—The Administrator shall distribute emission allowances to the owners or operators of eligible projects selected through a reverse auction under this paragraph pursuant to a formula equivalent to that described in subsection (c)(2), except that the bonus allowance value that is bid by the entity shall be substituted for the bonus allowance values set forth in subsection (c)(3).

"(4) ALTERNATIVE DISTRIBUTION METHOD.-

"(A) IN GENERAL.—If the Administrator determines that reverse auctions would not provide for efficient and cost-effective commercial deployment of carbon capture and sequestration technologies, the Administrator may instead, through regulations promulgated under paragraph (2) or (5), prescribe a schedule for the award of bonus allowances to the owners or operators of eligible projects under this subsection, in accordance with the requirements of this paragraph.

"(B) MULTIPLE TRANCHES.—The Administrator shall divide emission allowances available for distribution to the owners or operators of eligible projects into a series of tranches, each supporting the deployment of a specified quantity of cumulative electric generating capacity utilizing carbon capture and sequestration technology, each of which shall not be greater than 6 gigawatts.

"(C) METHOD OF DISTRIBUTION.—The Administrator shall distribute emission allowances within each tranche, on a first-come, first-served basis—

"(i) based on the date of full-scale operation of capture and sequestration technology; and

"(ii) pursuant to a formula, similar to that set forth in subsection (c)(2) (except that the Administrator shall prescribe bonus allowance values different than those set forth in subsection (c)(3)), establishing the number of allowances to be distributed per ton of carbon dioxide sequestered by the project.

"(D) REQUIREMENTS.—For each tranche established pursuant to subparagraph (B), the Administrator shall establish a schedule for distributing emission allowances that—

"(i) is based on a sliding scale that provides higher bonus allowance values for projects achieving higher rates of capture and sequestration;

"(ii) for each capture and sequestration rate, establishes a bonus allowance value that is lower than that established for such rate in the previous tranche (or, in the case of the first tranche, than that established for such rate under subsection (c)(3)); and

"(iii) may establish different bonus allowance levels for no more than 5 different project categories, defined by coal type, capture technology, geological formation type, new unit versus retrofit application, such other factors as the Administrator may prescribe, or any combination thereof.

"(E) CRITERIA FOR ESTABLISHING BONUS ALLOWANCE VALUES.—In setting bonus allowance values under this paragraph, the Administrator shall seek to cover no more than the reasonable incremental capital and operating costs of a project that are attributable to implementation of carbon capture, transportation, and sequestration technologies, taking into account—

"(i) the reduced cost of compliance with section 722 of this Act:

"(ii) the reduced cost associated with sequestering in a geological formation for purposes of enhanced hydrocarbon recovery when compared to sequestration into geological formations solely for purposes of sequestration;

"(iii) the relevant factors defining the project category; and

"(iv) such other factors as the Administrator determines are appropriate.

"(5) REVISION OF REGULATIONS.—The Administrator shall review, and as appropriate revise, the applicable regulations under this subsection no less frequently than every 8 years.

"(e) LIMITS FOR CERTAIN ELECTRIC GENERATING UNITS.—

"(1) DEFINITIONS.—For purposes of this subsection, the terms 'covered EGU' and 'initially permitted' shall have the meaning given those terms in section 812 of this Act.

"(2) COVERED EGUS INITIALLY PERMITTED FROM 2009 THROUGH 2014.—For a covered EGU that is initially permitted on or after January 1, 2009, and before January 1, 2015, the Administrator shall reduce the quantity of emission allowances that the owner or operator of such covered EGU would otherwise be eligible to receive under this section as follows:

"(A) In the case of a unit commencing operation on or before January 1, 2019, if the date in clause (ii)(I) is earlier than the date in clause (ii)(II), by the product of—

"(i) 20 percent; and

``(ii) the number of years, if any, that have elapsed between—

"(I) the earlier of January 1, 2020, or the date that is 5 years after the commencement of operation of such covered EGU; and

"(II) the first year that such covered EGU achieves (and thereafter maintains) an emission limit that is at least a 50 percent reduction in emissions of the carbon dioxide produced by the unit, measured on an annual basis, as determined in accordance with section 812(b)(2).

"(B) In the case of a unit commencing operation after January 1, 2019, by the product of—

"(i) 20 percent; and

"(ii) the number of years between-

"(I) the commencement of operation of such covered EGU; and

"(II) the first year that such covered EGU achieves (and thereafter maintains) an emission limit that is at least a 50 percent reduction in emissions of the carbon dioxide produced by the unit, measured on an annual basis, as determined in accordance with section 812(b)(2).

"(3) COVERED EGUS INITIALLY PERMITTED FROM 2015 THROUGH 2019.—The owner or operator of a covered EGU that is initially permitted on or after January 1, 2015, and before January 1, 2020, shall be ineligible to receive emission allowances pursuant to this section if such unit, upon commencement of oper-

ations (and thereafter), does not achieve and maintain an emission limit that is at least a 50 percent reduction in emissions of the carbon dioxide produced by the unit, measured on an annual basis, as determined in accordance with section 812(b)(2).

"(f) INDUSTRIAL SOURCES.—

"(1) ALLOWANCES.—The Administrator may distribute not more than 15 percent of the allowances allocated under section '782(f) for any vintage year to the owners or operators of eligible industrial sources to support the commercial-scale deployment of carbon capture and sequestration technologies at such sources.

"(2) DISTRIBUTION.—The Administrator shall, by regulation, prescribe requirements for the distribution of emission allowances to the owners or operators of industrial sources under this subsection, based on a bonus allowance formula that awards allowances to qualifying projects on the basis of tons of carbon dioxide captured and permanently sequestered. The Administrator may provide for the distribution of emission allowances pursuant to—

"(A) a reverse auction method, similar to that described under subsection (d)(3), including the use of separate auctions for different project categories; or

"(B) an incentive schedule, similar to that described under subsection (d)(4), which shall ensure that incentives are set so as to satisfy the requirement described in subsection (d)(4)(E).

"(3) REVISION OF REGULATIONS.—The Administrator shall review, and as appropriate revise, the applicable regulations under this subsection no less frequently than every 8

(g) LIMITATIONS.—Allowances may be distributed under this section only for tons of carbon dioxide emissions that have already been captured and sequestered. A qualifying project may receive annual emission allowances under this section only for the first 10 years of operation. No greater than 72 gigawatts of total cumulative generating capacity (including industrial applications. measured by such equivalent metric as the Administrator may designate) may receive emission allowances under this section. Upon reaching the limit described in the preceding sentence, any emission allowances that are allocated for carbon capture and sequestration deployment under section 782(f) and are not yet obligated under this section shall be treated as allowances not designated for distribution for purposes of section 782(r).

"(h) EXHAUSTION OF ACCOUNT AND ANNUAL ROLL-OVER OF SURPLUS ALLOWANCES.—

"(1) In distributing emission allowances under this section, the Administrator shall ensure that qualifying projects receiving allowances receive distributions for 10 years.

"(2) If the Administrator determines that the emission allowances allocated under section 782(f) with a vintage year that matches the year of distribution will be exhausted once the estimated full 10-year distributions will be provided to current eligible participants, the Administrator shall provide to new eligible projects allowances from vintage years after the year of the distribution.

"(i) RETROFIT APPLICATIONS.—(1) In calculating bonus allowance values for retrofit applications eligible under subsection (b)(1)(A)(ii) and (iv)(II), the Administrator shall apply the required capture rates with respect to the treated portion of flue gas

from the unit.

 $\lq\lq(2)$ No additional projects shall be eligible for allowances under subsection (b)(1)(A)(ii) and (iv)(II) as of such time as the Administrator reports, pursuant to section 812(d), that carbon capture and sequestration retrofit projects at electric generating units that are eligible for allowances under this

section have been applied, in the aggregate, to the flue gas generated by 1 gigawatt of total cumulative generating capacity. "The limitation in the preceding sentence shall not apply to projects that meet the eligibility criteria in subsection (b)(1)(A)(iv)(I)." after "generating capacity.".

"(j) DAVIS-BACON COMPLIANCE.—All laborers and mechanics employed on projects funded directly by or assisted in whole or in part by this section through the use of emission allowances shall be paid wages at rates not less than those prevailing on projects of a character similar in the locality as determined by the Secretary of Labor in accordance with subchapter IV, chapter 31, part A of subtitle II of title 40, United States Code. With respect to the labor standards specified in this subsection, the Secretary of Labor shall have the authority and functions set forth in Reorganization Plan Numbered 14 of 1950 (64 Stat. 1267: 5 U.S.C. App.) and section 3145 of title 40. United States Code."

SEC. 116. PERFORMANCE STANDARDS FOR COAL-FUELED POWER PLANTS.

(a) IN GENERAL.—Title VIII of the Clean Air Act (as added by section 331 of this Act) is amended by adding the following new section after section 811:

"SEC. 812. PERFORMANCE STANDARDS FOR NEW COAL-FIRED POWER PLANTS.

- "(a) DEFINITIONS.—For purposes of this section:
- "(1) COVERED EGU.—The term 'covered EGU' means a utility unit that is required to have a permit under section 503(a) and is authorized under state or federal law to derive at least 30 percent of its annual heat input from coal, petroleum coke, or any combination of these fuels.
- "(2) INITIALLY PERMITTED.—The term 'initially permitted' means that the owner or operator has received a Clean Air Act preconstruction approval or permit, for the covered EGU as a new (not a modified) source, but administrative review or appeal of such approval or permit has not been exhausted. A subsequent modification of any such approval or permits, ongoing administrative or court review, appeals, or challenges, or the existence or tolling of any time to pursue further review, appeals, or challenges shall not affect the date on which a covered EGU is considered to be initially permitted under this paragraph.

"(b) STANDARDS.—(1) A covered EGU that is initially permitted on or after January 1, 2020, shall achieve an emission limit that is a 65 percent reduction in emissions of the carbon dioxide produced by the unit, as measured on an annual basis, or meet such more stringent standard as the Administrator may establish pursuant to subsection

(c).

"(2) A covered EGU that is initially permitted after January 1, 2009, and before January 1, 2020, shall, by the applicable compliance date established under this paragraph, achieve an emission limit that is a 50 percent reduction in emissions of the carbon dioxide produced by the unit, as measured on an annual basis. Compliance with the requirement set forth in this paragraph shall be required by the earliest of the following:

"(A) Four years after the date the Administrator has published pursuant to subsection (d) a report that there are in commercial operation in the United States electric generating units or other stationary sources equipped with carbon capture and sequestration technology that, in the aggregate—

- "(i) have a total of at least 4 gigawatts of nameplate generating capacity of which—
- "(I) at least 3 gigawatts must be electric generating units; and
- "(II) up to 1 gigawatt may be industrial applications, for which capture and sequestra-

tion of 3 million tons of carbon dioxide per year on an aggregate annualized basis shall be considered equivalent to 1 gigawatt;

"(ii) include at least 2 electric generating units, each with a nameplate generating capacity of 250 megawatts or greater, that capture, inject, and sequester carbon dioxide into geologic formations other than oil and gas fields; and

"(iii) are capturing and sequestering in the aggregate at least 12 million tons of carbon dioxide per year, calculated on an aggregate annualized basis.

"(B) January 1, 2025.

"(3) If the deadline for compliance with paragraph (2) is January 1, 2025, the Administrator may extend the deadline for compliance by a covered EGU by up to 18 months if the Administrator makes a determination, based on a showing by the owner or operator of the unit, that it will be technically infeasible for the unit to meet the standard by the deadline. The owner or operator must submit a request for such an extension by no later than January 1, 2022, and the Administrator shall provide for public notice and comment on the extension request.

"(c) REVIEW AND REVISION OF STANDARDS.—Not later than 2025 and at 5-year intervals thereafter, the Administrator shall review the standards for new covered EGUs under this section and shall, by rule, reduce the maximum carbon dioxide emission rate for new covered EGUs to a rate which reflects the degree of emission limitation achievable through the application of the best system of emission reduction which (taking into account the cost of achieving such reduction and any nonair quality health and environmental impact and energy requirements) the Administrator determines has been adequately demonstrated.

"(d) REPORTS.-Not later than the date 18 months after the date of enactment of this title and semiannually thereafter, the Administrator shall publish a report on the nameplate capacity of units (determined pursuant to subsection (b)(2)(A)) in commercial operation in the United States equipped with carbon capture and sequestration technology, including the information described in subsection (b)(2)(A) (including the cumulative generating capacity to which carbon capture and sequestration retrofit projects meeting the criteria described in section 786(b)(1)(A)(ii) and (b)(1)(A)(iv)(II) has been applied and the quantities of carbon dioxide captured and sequestered by such projects).

"(e) REGULATIONS.—Not later than 2 years after the date of enactment of this title, the Administrator shall promulgate regulations to carry out the requirements of this section"

Subtitle C-Clean Transportation

SEC. 121. ELECTRIC VEHICLE INFRASTRUCTURE.

- (a) AMENDMENT OF PURPA.—Section 111(d) of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2621(d)) is amended by adding at the end the following:
- "(20) PLUG-IN ELECTRIC DRIVE VEHICLE INFRASTRUCTURE.—
- "(A) UTILITY PLAN FOR INFRASTRUCTURE.— Each electric utility shall develop a plan to support the use of plug-in electric drive vehicles, including heavy-duty hybrid electric vehicles. The plan may provide for deployment of electrical charging stations in public or private locations, including street parking, parking garages, parking lots, homes, gas stations, and highway rest stops. Any such plan may also include—
- "(i) battery exchange, fast charging infrastructure and other services;
- "(ii) triggers for infrastructure deployment based upon market penetration of plug-in electric drive vehicles; and

"(iii) such other elements as the State determines necessary to support plug-in electric drive vehicles.

Each plan under this paragraph shall provide for the deployment of the charging infrastructure or other infrastructure necessary to adequately support the use of plug-in electric drive vehicles.

- "(B) SUPPORT REQUIREMENTS.—Each State regulatory authority (in the case of each electric utility for which it has ratemaking authority) and each utility (in the case of a nonregulated utility) shall—
- "(i) require that charging infrastructure deployed is interoperable with products of all auto manufacturers to the extent possible: and
- "(ii) consider adopting minimum requirements for deployment of electrical charging infrastructure and other appropriate requirements necessary to support the use of plugin electric drive vehicles.
- "(C) COST RECOVERY.—Each State regulatory authority (in the case of each electric utility for which it has ratemaking authority) and each utility (in the case of a non-regulated utility) shall consider whether, and to what extent, to allow cost recovery for plans and implementation of plans.
- "(D) SMART GRID INTEGRATION.—The State regulatory authority (in the case of each electric utility for which it has ratemaking authority) and each utility (in the case of a nonregulated utility) shall, in accordance with regulations issued by the Federal Energy Regulatory Commission pursuant to section 1305(d) of the Energy Independence and Security Act of 2007—
- "(i) establish any appropriate protocols and standards for integrating plug-in electric drive vehicles into an electrical distribution system, including Smart Grid systems and devices as described in title XIII of the Energy Independence and Security Act of 2007;
- "(ii) include, to the extent feasible, the ability for each plug-in electric drive vehicle to be identified individually and to be associated with its owner's electric utility account, regardless of the location that the vehicle is plugged in, for purposes of appropriate billing for any electricity required to charge the vehicle's batteries as well as any crediting for electricity provided to the electric utility from the vehicle's batteries; and
- "(iii) review the determination made in response to section 1252 of the Energy Policy Act of 2005 in light of this section, including whether time-of-use pricing should be employed to enable the use of plug-in electric drive vehicles to contribute to meeting peakload and ancillary service power needs."
 - (b) COMPLIANCE.—
- (1) TIME LIMITATIONS.—Section 112(b) of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2622(b)) is amended by adding the following at the end thereof:
- "(7)(A) Not later than 3 years after the date of enactment of this paragraph, each State regulatory authority (with respect to each electric utility for which it has ratemaking authority) and each nonregulated utility shall commence the consideration referred to in section 111, or set a hearing date for consideration, with respect to the standard established by paragraph (20) of section 111(d).
- "(B) Not later than 4 years after the date of enactment of the this paragraph, each State regulatory authority (with respect to each electric utility for which it has rate-making authority), and each nonregulated electric utility, shall complete the consideration, and shall make the determination, referred to in section 111 with respect to the standard established by paragraph (20) of section 111(d)."
- (2) FAILURE TO COMPLY.—Section 112(c) of the Public Utility Regulatory Policies Act of

1978 (16 U.S.C. 2622(c)) is amended by adding the following at the end: "In the case of the standards established by paragraph (20) of section 111(d), the reference contained in this subsection to the date of enactment of this Act shall be deemed to be a reference to the date of enactment of such paragraph.".

(3) PRIOR STATE ACTIONS.—Section 112(d) of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2622(d)) is amended by striking "(19)" and inserting "(20)" before "of section 111(d)".

SEC. 122. LARGE-SCALE VEHICLE ELECTRIFICA-TION PROGRAM.

- (a) DEPLOYMENT PROGRAM.—The Secretary of Energy shall establish a program to deploy and integrate plug-in electric drive vehicles into the electricity grid in multiple regions. In carrying out the program, the Secretary may provide financial assistance described under subsection (d), consistent with the goals under subsection (b). The Secretary shall select regions based upon applications for assistance received pursuant to subsection (c)
- subsection (c).
 (b) GOALS.—The goals of the program established pursuant to subsection (a) shall be—
- (1) to demonstrate the viability of a vehicle-based transportation system that is not overly dependent on petroleum as a fuel and contributes to lower carbon emissions than a system based on conventional vehicles;
- (2) to facilitate the integration of advanced vehicle technologies into electricity distribution areas to improve system performance and reliability;
- (3) to demonstrate the potential benefits of coordinated investments in vehicle electrification on personal mobility and a regional grid:
- (4) to demonstrate protocols and standards that facilitate vehicle integration into the grid; and
- (5) to investigate differences in each region and regulatory environment regarding best practices in implementing vehicle electrification.
- (c) APPLICATIONS.—Any State, Indian tribe, or local government (or group of State, Indian tribe, or local governments) may apply to the Secretary of Energy for financial assistance in furthering the regional deployment and integration into the electricity grid of plug-in electric drive vehicles. Such applications may be jointly sponsored by electric utilities, automobile manufacturers, technology providers, car sharing companies or organizations, or other persons or entities.
- (d) USE OF FUNDS.—Pursuant to applications received under subsection (c), the Secretary may make financial assistance available to any applicant or joint sponsor of the application to be used for any of the following:
- (1) Assisting persons located in the regional deployment area, including fleet owners, in the purchase of new plug-in electric drive vehicles by offsetting in whole or in part the incremental cost of such vehicles above the cost of comparable conventionally fueled vehicles.
- (2) Supporting the use of plug-in electric drive vehicles by funding projects for the deployment of any of the following:
- (A) Electrical charging infrastructure for plug-in electric drive vehicles, including battery exchange, fast charging infrastructure, and other services, in public or private locations, including street parking, parking garages, parking lots, homes, gas stations, and highway rest stops.
- (B) Smart Grid equipment and infrastructure, as described in title XIII of the Energy Independence and Security Act of 2007, to facilitate the charging and integration of plugin electric drive vehicles.

- (3) Such other projects as the Secretary determines appropriate to support the large-scale deployment of plug-in electric drive vehicles in regional deployment areas.
- (e) PROGRAM REQUIREMENTS.—The Secretary, in consultation with the Administrator and the Secretary of Transportation, shall determine design elements and requirements of the program established pursuant to subsection (a), including—
- (1) the type of financial mechanism with which to provide financial assistance;
- (2) criteria for evaluating applications submitted under subsection (c), including the anticipated ability to promote deployment and market penetration of vehicles that are less dependent on petroleum as a fuel source;
- (3) reporting requirements for entities that receive financial assistance under this section, including a comprehensive set of performance data characterizing the results of the deployment program.
- (f) INFORMATION CLEARINGHOUSE.—The Secretary shall, as part of the program established pursuant to subsection (a), collect and make available to the public information regarding the cost, performance, and other technical data regarding the deployment and integration of plug-in electric drive vehicles.
- (g) AUTHORIZATION.—There are authorized to be appropriated to carry out this section such sums as may be necessary.

SEC. 123. PLUG-IN ELECTRIC DRIVE VEHICLE MANUFACTURING.

- (a) VEHICLE MANUFACTURING ASSISTANCE PROGRAM.—The Secretary of Energy shall establish a program to provide financial assistance to automobile manufacturers to facilitate the manufacture of plug-in electric drive vehicles, as defined in section 131(a)(5) of the Energy Independence and Security Act of 2007, that are developed and produced in the United States.
- (b) FINANCIAL ASSISTANCE.—The Secretary of Energy may provide financial assistance to an automobile manufacturer under the program established pursuant to "subsection (a) for the reconstruction or retooling of facilities for the manufacture of plug-in electric drive vehicles or batteries for such vehicles that are developed and produced in the United States."
- (c) COORDINATION WITH REGIONAL DEPLOY-MENT.—The Secretary may provide financial assistance under subsection (b) in conjunction with the award of financial assistance under the large scale vehicle electrification program established pursuant to section 122 of this Act.
- (d) PROGRAM REQUIREMENTS.—The Secretary shall determine design elements and requirements of the program established pursuant to subsection (a), including—
- (1) the type of financial mechanism with which to provide financial assistance;
- (2) criteria, in addition to the criteria described under subsection (e), for evaluating applications for financial assistance; and
- (3) reporting requirements for automobile manufacturers that receive financial assistance under this section.
- (e) Criteria.—In selecting recipients of financial assistance from among applicant automobile manufacturers, the Secretary shall give preference to proposals that—
- (1) are most likely to be successful; and
- (2) are located in local markets that have the greatest need for the facility.
- (f) REPORTS.—The Secretary shall annually submit to Congress a report on the program established pursuant to this section.
- (g) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated such sums as are necessary to carry out this section

SEC. 124. INVESTMENT IN CLEAN VEHICLES.

(a) DEFINITIONS.—In this section:

- (1) ADVANCED TECHNOLOGY VEHICLES AND QUALIFYING COMPONENTS.—The terms "advanced technology vehicles" and "qualifying components" shall have the definition of such terms in section 136 of the Energy Independence and Security Act of 2007, except that for purposes of this section, the average base year as described in such section 136(a)(1)(C) shall be the following:
- (A) In each of the years 2012 through 2016, model year 2009.
- (B) In 2017, the Administrator shall, notwithstanding such section 136(a)(1)(C), determine an appropriate baseline based on technological and economic feasibility.
- (2) PLUG-IN ELECTRIC DRIVE VEHICLE.—The term "plug-in electric drive vehicle" shall have the definition of such term in section 131 of the Energy Independence and Security Act of 2007.
- (b) DISTRIBUTION OF ALLOWANCES.—The Administrator shall, in accordance with this section, distribute emission allowances allocated pursuant to section 782(i) of the Clean Air Act not later than September 30 of 2012 and each calendar year thereafter through 2025
- (c) PLUG-IN ELECTRIC DRIVE VEHICLE MANUFACTURING AND DEPLOYMENT.—
- (1) IN GENERAL.—The Administrator shall, at the direction of the Secretary of Energy, provide emission allowances allocated pursuant to section 782(i) to applicants, joint sponsors and automobile manufacturers pursuant to sections 122 and 123 of this Act.
- (2) ANNUAL AMOUNT.—In each of the years 2012 through 2017, one-quarter of the portion of the emission allowances allocated pursuant to section 782(i) of the Clean Air Act shall be available to carry out paragraph (1) such that—
- (A) one-eighth of the portion shall be available to carry out section 122; and,
- (B) one-eighth of the portion shall be available to carry out section 123.
- (3) PREFERENCE.—In directing the provision of emission allowances under this subsection to carry out section 122, the Secretary shall give preference to applications under section 122(c) that are jointly sponsored by one or more automobile manufacturers.
- (4) MULTI-YEAR COMMITMENTS.—The Administrator shall commit to providing emission allowances to an applicant, joint sponsor, or automobile manufacturer for up to five consecutive years if—
- (A) an application under section 122 or 123 of this Act requests a multi-year commitment:
- (B) such application meets the criteria for support established by the Secretary of Energy under sections 122 or 123 of this Act;
- (C) the Administrator confirms to the Secretary that emission allowances will be available for a multi-year commitment;
- (D) the Secretary of Energy determines that a multi-year commitment for such application will advance the goals of section 122 or 123; and
- (E) the Secretary of Energy directs the Administrator to make a multi-year commitment.
- (5) INSUFFICIENT APPLICATIONS.—If, in any year, emission allowances available under paragraph (2) cannot be provided because of insufficient numbers of submitted applications that meet the criteria for support established by the Secretary of Energy under sections 122 or 123 of this Act, the remaining emission allowances shall be distributed according to subsection (d).
 - (d) ADVANCED TECHNOLOGY VEHICLES.—
- (1) IN GENERAL.—The Administrator shall, at the direction of the Secretary of Energy, provide any emission allowances allocated pursuant to section 782(i) of the Clean Air Act that are not provided under subsection

- (c) to automobile manufacturers and component suppliers to pay not more than 30 percent of the cost of—
- (A) reequipping, expanding, or establishing a manufacturing facility in the United States to produce—
- (i) qualifying advanced technology vehicles; or
 - (ii) qualifying components; and
- (B) engineering integration performed in the United States of qualifying vehicles and qualifying components.
- (2) PREFERENCE.—In directing the provision of emission allowances under this subsection during the years 2012 through 2017, the Secretary shall give preference to applications for projects that save the maximum number of gallons of fuel.

SEC. 125. ADVANCED TECHNOLOGY VEHICLE MANUFACTURING INCENTIVE LOANS.

Section 136(d)(1) of the Energy Independence and Security Act of 2007 (42 U.S.C. 17013(d)(1)) is amended by striking "\$25,000,000,000" and inserting "\$50,000,000,000".

SEC. 126. DEFINITION OF RENEWABLE BIOMASS.

- Section 211(o)(1)(I) of the Clean Air Act (42 U.S.C. 7545(o)(1)(I)) is amended to read as follows:
- "(I) RENEWABLE BIOMASS.—The term 'renewable biomass' means any of the following:
- "(i) Materials, pre-commercial thinnings, or removed invasive species from National Forest System land and public lands (as defined in section 103 of the Federal Land Policy and Management Act of 1976 (43 U.S.C. 1702)), including those that are byproducts of preventive treatments (such as trees, wood, brush, thinnings, chips, and slash), that are removed as part of a federally recognized timber sale, or that are removed to reduce hazardous fuels, to reduce or contain disease or insect infestation, or to restore ecosystem health, and that are—
- "(I) not from components of the National Wilderness Preservation System, Wilderness Study Areas, Inventoried Roadless Areas, old growth stands, late-successional stands (except for dead, severely damaged, or badly infested trees), components of the National Landscape Conservation System, National Monuments, National Conservation Areas, Designated Primitive Areas, or Wild and Scenic Rivers corridors:
- "(II) harvested in environmentally sustainable quantities, as determined by the appropriate Federal land manager; and
- "(III) harvested in accordance with Federal and State law, and applicable land management plans.
- "(ii) Any organic matter that is available on a renewable or recurring basis from non-Federal land or land belonging to an Indian or Indian tribe that is held in trust by the United States or subject to a restriction against alienation imposed by the United States, including—
 - "(I) renewable plant material, including—
 - "(aa) feed grains;
 - "(bb) other agricultural commodities;
 - "(cc) other plants and trees; and
 - "(dd) algae; and
 - "(II) waste material, including—
 - "(aa) crop residue;
- "(bb) other vegetative waste material (including wood waste and wood residues);
- "(cc) animal waste and byproducts (including fats, oils, greases, and manure);
 - "(dd) construction waste;
 - "(ee) food waste and yard waste; and
- "(ff) the non-fossil biogenic portion of municipal solid waste and construction, demolition, and disaster debris.
- "(iii) Residues and byproducts from wood, pulp, or paper products facilities.".

(c) REDUCTION.—The last sentence of section 211(0)(7)(D) of the Clean Air Act (42 U.S.C. 7545(0)(7)(D)) is amended to read as follows: "For any calendar year in which the Administrator makes such a reduction, the Administrator shall also reduce the applicable volume of renewable fuel and advanced biofuels requirement established under paragraph (2)(B) by the same volume."

SEC. 127. OPEN FUEL STANDARD.

- (a) FINDINGS.—The Congress finds that-
- (1) the status of oil as a strategic commodity, which derives from its domination of the transportation sector, presents a clear and present danger to the United States;
- (2) in a prior era, when salt was a strategic commodity, salt mines conferred national power and wars were fought over the control of such mines;
- (3) technology, in the form of electricity and refrigeration, decisively ended salt's monopoly of meat preservation and greatly reduced its strategic importance;
- (4) fuel competition and consumer choice would similarly serve to end oil's monopoly in the transportation sector and strip oil of its strategic status;
- (5) the current closed fuel market has allowed a cartel of petroleum exporting countries to inflate fuel prices, effectively imposing a harmful tax on the economy of the United States:
- (6) much of the inflated petroleum revenues the oil cartel earns at the expense of the people of the United States are used for purposes antithetical to the interests of the United States and its allies;
- (7) alcohol fuels, including ethanol and methanol, could potentially provide significant supplies of additional fuels that could be produced in the United States and in many other countries in the Western Hemisphere that are friendly to the United States:
- (8) alcohol fuels can only play a major role in securing the energy independence of the United States if a substantial portion of vehicles in the United States are capable of operating on such fuels:
- (9) it is not in the best interest of United States consumers or the United States Government to be constrained to depend solely upon petroleum resources for vehicle fuels if alcohol fuels are potentially available;
- (10) existing technology, in the form of flexible fuel vehicles, allows internal combustion engine cars and trucks to be produced at little or no additional cost, which are capable of operating on conventional gasoline, alcohol fuels, or any combination of such fuels, as availability or cost advantage dictates, providing a platform on which fuels can compete:
- (11) the necessary distribution system for such alcohol fuels will not be developed in the United States until a substantial fraction of the vehicles in the United States are capable of operating on such fuels;
- (12) the establishment of such a vehicle fleet and distribution system would provide a large market that would mobilize private resources to substantially advance the technology and expand the production of alcohol fuels in the United States and abroad;
- (13) the United States has an urgent national security interest to develop alcohol fuels technology, production, and distribution systems as rapidly as possible;
- (14) new cars sold in the United States that are equipped with an internal combustion engine should allow for fuel competition by being flexible fuel vehicles, and new diesel cars should be capable of operating on biodiesel; and
- (15) such an open fuel standard would help to protect the United States economy from high and volatile oil prices and from the

- threats caused by global instability, terrorism, and natural disaster.
- (b) OPEN FUEL STANDARD FOR TRANSPORTATION.—(1) Chapter 329 of title 49, United States Code, is amended by adding at the end the following:

"§ 32920. Open fuel standard for transportation

- "(a) DEFINITIONS.—In this section:
- "(1) E85.—The term 'E85' means a fuel mixture containing 85 percent ethanol and 15 percent gasoline by volume.
- "(2) FLEXIBLE FUEL AUTOMOBILE.—The term 'flexible fuel automobile' means an automobile that has been warranted by its manufacturer to operate on gasoline, E85, and M85.
- "(3) FUEL CHOICE-ENABLING AUTOMOBILE.— The term 'fuel choice-enabling automobile' means—
- "(A) a flexible fuel automobile; or
- "(B) an automobile that has been warranted by its manufacturer to operate on biodiesel.
- "(4) LIGHT-DUTY AUTOMOBILE.—The term 'light-duty automobile' means—
- "(A) a passenger automobile; or
- "(B) a non-passenger automobile.
- "(5) LIGHT-DUTY AUTOMOBILE MANUFAC-TURER'S ANNUAL COVERED INVENTORY.—The term 'light-duty automobile manufacturer's annual covered inventory' means the number of light-duty automobiles powered by an internal combustion engine that a manufacturer, during a given calendar year, manufactures in the United States or imports from outside of the United States for sale in the United States.
- ''(6) M85.—The term 'M85' means a fuel mixture containing 85 percent methanol and 15 percent gasoline by volume.
- (i) OPEN FUEL STANDARD FOR TRANSPORTATION —
- "(1) IN GENERAL.—The Secretary may promulgate regulations to require each lightduty automobile manufacturer's annual covered inventory to be comprised of a minimum percentage of fuel-choice enabling automobiles, with sufficient lead time, if the Secretary, in coordination with the Secretary of Energy and the Administrator of the Environmental Protection Agency, determines such requirement is a cost-effective way to achieve the Nation's energy independence and environmental objectives. The cost-effective determination shall consider the future availability of both alternative fuel supply and infrastructure to deliver the alternative fuel to the fuel-choice enabling vehicles
- "(2) TEMPORARY EXEMPTION FROM REQUIREMENTS.—
- "(A) APPLICATION.—A manufacturer may request an exemption from the requirement described in paragraph (1) by submitting an application to the Secretary, at such time, in such manner, and containing such information as the Secretary may require by regulation. Each such application shall specify the models, lines, and types of automobiles affected.
- "(B) EVALUATION.—After evaluating an application received from a manufacturer, the Secretary may at any time, under such terms and conditions, and to such extent as the Secretary considers appropriate, temporarily exempt, or renew the exemption of, a light-duty automobile from the requirement described in paragraph (1) if the Secretary determines that unavoidable events not under the control of the manufacturer prevent the manufacturer of such automobile from meeting its required production volume of fuel choice-enabling automobiles, including—
- "(i) a disruption in the supply of any component required for compliance with the regulations;

- "(ii) a disruption in the use and installation by the manufacturer of such component; or
- "(iii) application to plug-in electric drive vehicles causing such vehicles to fail to meet State air quality requirements.
- "(C) CONSOLIDATION.—The Secretary may consolidate applications received from multiple manufacturers under subparagraph (A) if they are of a similar nature.
- "(D) Conditions.—Any exemption granted under subparagraph (B) shall be conditioned upon the manufacturer's commitment to recall the exempted automobiles for installation of the omitted components within a reasonable time proposed by the manufacturer and approved by the Secretary after such components become available in sufficient quantities to satisfy both anticipated production and recall volume requirements.
- "(E) NOTICE.—The Secretary shall publish in the Federal Register—
- "(i) notice of each application received from a manufacturer:
- "(ii) notice of each decision to grant or deny a temporary exemption; and
- "(iii) the reasons for granting or denying such exemptions.".
- (2) The table of contents in chapter 329 of such title is amended by adding at the end the following:
- "32920. Open fuel standard for transportation.".

SEC. 128. DIESEL EMISSIONS REDUCTION.

Subtitle G of title VII of the Energy Policy Act of 2005 (42 U.S.C. 16131 et seq.) is amended— $\,$

- (1) in the matter preceding clause (i) in section 791(3)(B), by inserting "in any State" after "nonprofit organization or institution":
- (2) in section 791(9), by striking "The term 'State' includes the District of Columbia." and inserting "The term 'State' includes the District of Columbia, American Samoa, Guam, the Commonwealth of the Northern Mariana Islands, Puerto Rico, and the Virgin Islands.":
- (3) in section 793(c)—
- (A) in paragraph (2)(A), by striking "51 States" and inserting "56 States";
- (B) in paragraph (2)(A), by striking "1.96 percent" and inserting "1.785 percent";
- (C) in paragraph (2)(B), by striking "51 States" and inserting "56 States"; and
- (D) in paragraph (2)(B), by amending clause (ii) to read as follows:
- "(ii) the amount of funds remaining after each State described in paragraph (1) receives the 1.785-percent allocation under this paragraph."; and
- (4) in section 797, by striking "2011" and inserting "2016".

SEC. 129. LOAN GUARANTEES FOR PROJECTS TO CONSTRUCT RENEWABLE FUEL PIPELINES.

- (a) DEFINITIONS.—Section 1701 of the Energy Policy Act of 2005 (42 U.S.C. 16511) is amended by adding at the end the following:
- "(6) RENEWABLE FUEL.—The term 'renewable fuel' has the meaning given the term in section 211(o)(1) of the Clean Air Act (42 U.S.C. 7545(o)(1)), except that the term shall include all ethanol and biodiesel.
- "(7) RENEWABLE FUEL PIPELINE.—The term renewable fuel pipeline means a common carrier pipeline for transporting renewable fuel."
- (b) RENEWABLE FUEL PIPELINE ELIGIBILITY.—Section 1703(b) of the Energy Policy Act of 2005 (42 U.S.C. 16513) is amended by adding at the end the following:
- "(11) Renewable fuel pipelines.".

SEC. 130. FLEET VEHICLES.

Section 508 of the Energy Policy Act of 1992 (42 U.S.C. 13258) is amended as follows:

(1) By adding the following new paragraph at the end of subsection (a):

- "(6) REPOWERED OR CONVERTED ALTERNATIVE FUELED VEHICLES.—As used in this paragraph, the term 'repowered or converted alternative fueled vehicle' includes light, medium- or heavy-duty motor vehicles that have been modified with an EPA or CARB compliant engine or vehicle or aftermarket system so that the vehicle or engine is capable of operating on an alternative fuel."
- (2) By adding the following new paragraph at the end of subsection (b):
- "(3) Repowered or converted vehicles. Not later than January 1, 2010, the Secretary shall allocate credits to fleets that repower or convert an existing vehicle so that it is capable of operating on an alternative fuel. In the case of any medium- or heavy-duty vehicle that is repowered or converted so that it is capable of operating on an alternative fuel, the Secretary shall allocate additional credits for such vehicles if he determines that such vehicles displace more petroleum than light duty alternative fueled vehicles. Such rules shall also include a requirement. that such vehicles remain in the fleet for a period of no less than 2 years in order to continue to qualify for credit. The Secretary also shall extend the flexibility afforded in this paragraph to Federal fleets subject to the purchase provisions contained in section 303 of this Act.'

SEC. 130A. REPORT ON NATURAL GAS VEHICLE EMISSIONS REDUCTIONS.

Within 360 days after the date of enactment of this Act, the Administrator, in consultation with the Secretaries of Energy and Transportation, and the Administrator of the General Services Administration, and after an examination of available scientific studies or analysis, shall submit to the Congress a report on—

- (1) the contribution that light and heavy duty natural gas vehicles, by category and State, have made during the last decade to the reduction of greenhouse gases and criteria pollutants under the Clean Air Act, and the reduced consumption of petroleum-based fuels:
- (2) the contribution that light and heavy duty natural gas vehicles are expected to make from 2010 to 2020 in reducing greenhouse gas and criteria pollutants under the Clean Air Act based, among other things, on additional Federal incentives for the manufacture and deployment of natural gas vehicles provided in this Act, and other Federal legislation; and
- (3) additional Federal measures, including legislation, that could, if implemented, maximize the potential for natural gas used in both stationary and mobile sources to contribute to the reduction of greenhouse gases and criteria pollutants under the Clean Air Act.

Subtitle D—State Energy and Environment Development Accounts

SEC. 131. ESTABLISHMENT OF SEED ACCOUNTS.

- (a) DEFINITIONS.—In this section:
- (1) SEED ACCOUNT.—The term "SEED Account" means a State Energy and Environment Development Account established pursuant to this section.
- (2) STATE ENERGY OFFICE.—The term "State Energy Office" means a State entity eligible for grants under part D of title III of the Energy Policy and Conservation Act (42 U.S.C. 6321 et seq.).
- (b) ESTABLISHMENT OF PROGRAM.—The Administrator shall establish a program under which a State, through its State Energy Office or other State agency designated by the State, may operate a State Energy and Environment Development Account.
- (c) Purpose.—The purpose of each SEED Account is to serve as a common State-level repository for managing and accounting for emission allowances provided to States des-

ignated for renewable energy and energy efficiency purposes.

- (d) REGULATIONS.—Not later than one year after the date of enactment of this Act, the Administrator shall promulgate regulations to carry out this section, including regulations—
- (1) to ensure that each State operates its SEED Account and any subaccounts thereof efficiently and in accordance with this Act and applicable State and Federal laws;
 - (2) to prevent waste, fraud, and abuse;
- (3) to indicate the emission allowances that may be deposited in a State's SEED Account pending distribution or use;
- (4) to indicate the programs and objectives authorized by Federal law for which emission allowances in a SEED Account may be distributed or used;
- (5) to identify the forms of financial assistance and incentives that States may provide through distribution or use of SEED Accounts; and
- (6) to prescribe the form and content of reports that the States are required to submit under this section on the use of SEED Accounts.
 - (e) OPERATION.—
 - (1) Deposits.—
- (A) IN GENERAL.—In the allowance tracking system established pursuant to section 724(d) of the Clean Air Act, the Administrator shall establish a SEED Account for each State and place in it the allowances allocated pursuant to section 782(g) of the Clean Air Act to be distributed to States pursuant to sections 132 and 201 of this Act.
- (B) FINANCIAL ACCOUNT.—A State may create a financial account associated with its SEED Account to deposit, retain, and manage any proceeds of any sale of any allowance provided pursuant to this Act pending expenditure or disbursement of those proceeds for purposes permitted under this section. The funds in such an account shall not be commingled with other funds not derived from the sale of allowances provided to the State; however, loans made by the State from such funds pursuant to paragraph (2)(C)(i) may be repaid into such a financial account, including any interest charged.
 - (2) WITHDRAWALS.—
- (A) IN GENERAL.—All allowances distributed pursuant to sections 132 and 201, including the proceeds of any sale of such allowances, shall support renewable energy and energy efficiency programs authorized or approved by the Federal Government.
- (B) DEDICATED ALLOWANCES.—Allowances distributed pursuant to sections 132 and 201 that are required by law to be used for specific purposes for a specified period shall be used according to those requirements during that period.
- (C) UNDEDICATED ALLOWANCES.—To the extent that allowances distributed pursuant to sections 132 and 201 are not required by law to be used for specific purposes for a specified period as described in subparagraph (B), such allowances or the proceeds of their sale may be used for any of the following purposes:
- (i) LOANS.—Loans of allowances, or the proceeds from the sale of allowances, may be provided, interest on commercial loans may be subsidized at an interest rate as low as zero, and other credit support may be provided to support programs authorized to use SEED Account allowance value or any other renewable energy or energy efficiency purpose authorized or approved by the Federal Government.
- (ii) GRANTS.—Grants of allowances or the proceeds of their sale may be provided to support programs authorized to use SEED

Account allowance value or any other renewable energy or energy efficiency purpose authorized or approved by the Federal Government

- (iii) OTHER FORMS OF SUPPORT.—Allowances or the proceeds of the sale of allowances may be provided for other forms of support for programs authorized to use SEED Account allowance value or any other renewable energy or energy efficiency purpose authorized or approved by the Federal Government.
- (iv) ADMINISTRATIVE COSTS.—Except to the extent provided in Federal law authorizing or allocating allowances deposited in a SEED Account, not more than 5 percent of the allowance value in a SEED Account in any year may be used to cover administrative expenses of the SEED Account.
- (D) SUBACCOUNTS.—A State may request that the Administrator establish accounts for local governments that request such subaccounts to hold allowances distributed to local governments for renewable energy or energy efficiency programs authorized or approved by the Federal Government.
 - (E) INTENDED USE PLANS.—
- (i) IN GENERAL.—After providing for public review and comment, each State administering a SEED Account shall annually prepare a plan that identifies the intended uses of the allowances or proceeds from the sale of allowances in its SEED Account.
- (ii) CONTENTS.—An intended use plan shall include—
- (I) a list of the projects or programs for which withdrawals from the SEED Account are intended in the next fiscal year that begins after the date of the plan, including a description of each project;
- (II) the relationship of each of the projects or programs to an identified Federal purpose authorized by this Act, or any other Federal statute:
- (III) the expected terms of use of allowance value to provide assistance;
- (IV) the criteria and methods established for the distribution of allowances or allowance value;
- (V) a description of the equivalent financial value and status of the SEED Account; and
- (VI) a statement of the mid-term and long-term goals of the State for use of its SEED Account.
 - (3) ACCOUNTABILITY AND TRANSPARENCY.—
- (A) CONTROLS AND PROCEDURES.—Any State that has a SEED Account shall establish fiscal controls and recordkeeping and accounting procedures for the SEED Account sufficient to ensure proper accounting during appropriate accounting periods for distributions into the SEED Account, transfers from the SEED Account, and SEED Account balances, including any related financial accounts. Such controls and procedures shall conform to generally accepted government accounting principles. Any State that has a SEED Account shall retain records for a period of at least 5 years.
- (B) AUDITS.—Any State that has a SEED Account shall have an annual audit conducted of the SEED Account by an independent public accountant in accordance with generally accepted auditing standards, and shall transmit the results of that audit to the Administrator.
- (C) STATE REPORT.—Each State administering a SEED Account shall make publicly available and submit to the Administrator a report every 2 years on its activities related to its SEED Account.
 - (D) PUBLIC INFORMATION.—Any—
- (i) controls and procedures established under subparagraph (A); and
- (ii) information obtained through audits conducted under subparagraph (B), except to the extent that it would be protected from disclosure, if it were information held by the

- Federal Government, under section 552(b) of title 5, United States Code, shall be made publicly available.
- (E) OTHER PROTECTIONS.—The Administrator shall require such additional procedures and protections as are necessary to ensure that any State that has a SEED Account will operate the SEED Account in an accountable and transparent manner.
- (f) REQUIREMENTS FOR ELIGIBILITY.—A State's eligibility to receive allowances in its SEED Account shall depend on that State's compliance with the requirements of this Act (and the amendments made by this Act).
- (g) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to the Administrator such sums as may be necessary for SEED Account operations.

SEC. 132. SUPPORT OF STATE RENEWABLE ENERGY AND ENERGY EFFICIENCY PROGRAMS.

- (a) DEFINITIONS.—For purposes of this section:
- (1) ALLOWANCE.—The term "allowance" means an emission allowance established under section 721 of the Clean Air Act (as added by section 311 of this Act).
- (2) Cost-effective.—The term "cost-effective", with respect to an energy efficiency program, means that the program meets the Total Resource Cost Test, which requires that the net present value of economic benefits over the life of the program or measure, including avoided supply and delivery costs and deferred or avoided investments, is greater than the net present value of the economic costs over the life of the program, including program costs and incremental costs borne by the energy consumer.
- (3) RENEWABLE ENERGY RESOURCE.—The term "renewable energy resource" shall have the meaning given that term in section 610 of the Public Utility Regulatory Policies Act of 1978 (as added by section 101 of this Act).
- (4) VINTAGE YEAR.—The term "vintage year" shall the meaning given that term in section 700 of the Clean Air Act (as added by section 311 of this Act).
- DISTRIBUTION AMONG STATES.—Not later than September 30 of each calendar year from 2011 through 2049, the Administrator shall, in accordance with this section, distribute allowances allocated pursuant to section 782(g)(1) of the Clean Air Act (as added by section 311 of this Act) for the following vintage year. The Administrator shall distribute 0.5 percent of such allowances pursuant to section 133 of this Act. The Administrator shall distribute the remaining allowances to States for renewable energy and energy efficiency programs to be deposited in and administered through the State Environment Development Energy and Accounts established pursuant to section 131. The Administrator shall distribute allowances among the States under this section each year in accordance with the following formula:
- (1) One third of the allowances shall be divided equally among the States.
- (2) One third of the allowances shall be distributed ratably among the States based on the population of each State, as contained in the most recent reliable census data available from the Bureau of the Census, Department of Commerce, for all States at the time the Administrator calculates the formula for distribution.
- (3) One third of the allowances shall be distributed ratably among the States on the basis of the energy consumption of each State as contained in the most recent State Energy Data Report available from the Energy Information Administration (or such alternative reliable source as the Administrator may designate).
- (c) USES.—The allowances distributed to each State pursuant to this section shall be

- used exclusively in accordance with the following requirements:
- (1) Not less than 12.5 percent shall be distributed by the State to units of local government within such State to be used exclusively to support the energy efficiency and renewable energy purposes listed in paragraphs (2) and (3).
- (2) Not less than 20 percent shall be used exclusively for the following energy efficiency purposes, provided that not less than 1 percent shall be used for the purpose described in subparagraph (D) and not less than 5.5 percent shall be used for the purpose described in subparagraph (E):
- (A) Implementation and enforcement of building codes adopted in compliance with section 201.
- (B) Implementation of the energy efficient manufactured homes program established pursuant to section 203.
- (C) Implementation of the building energy performance labeling program established pursuant to section 204.
- (D) Low-income community energy efficiency programs that are consistent with the grant program established under section 264 of this Act.
- (E) Implementation of the Retrofit for Energy and Environmental Performance (REEP) program established pursuant to section 202.
- (3) Not less than 20 percent shall be used exclusively for capital grants, tax credits, production incentives, loans, loan guarantees, forgivable loans, direct provision of allowances, and interest rate buy-downs for—
- (A) re-equipping, expanding, or establishing a manufacturing facility that receives certification from the Secretary of Energy pursuant to section 1302 of the American Recovery and Reinvestment Act of 2009 for the production of—
- (i) property designed to be used to produce energy from renewable energy sources; and
 - (ii) electricity storage systems;
- (B) deployment of technologies to generate electricity from renewable energy sources; and
- (C) deployment of facilities or equipment, such as solar panels, to generate electricity or thermal energy from renewable energy resources in and on buildings in an urban environment.
- (4) The remaining 47.5 percent shall be used exclusively for any of the following purposes:
- (A) Energy efficiency purposes described in paragraph (2).
- (B) Renewable energy purposes described in paragraph (3)(B) and (C).
- (C) Cost-effective energy efficiency programs for end-use consumers of electricity, natural gas, home heating oil, or propane, including, where appropriate, programs or mechanisms administered by local governments and entities other than the State.
- (D) Enabling the development of a Smart Grid (as described in section 1301 of the Energy Independence and Security Act of 2007 (42 U.S.C. 17381)) for State, local government, and other public buildings and facilities, including integration of renewable energy resources and distributed generation, demand response, demand side management, and systems analysis.
- (E) Providing the non-Federal share of support for surface transportation capital projects under—
- (i) sections 5307, 5308, 5309, 5310, 5311 and 5319 of title 49, United States Code; and
- (ii) sections 142, 146, and 149 of title 23, United States Code,
- provided that not more than 10 percent of allowances distributed to each State pursuant to this section shall be used for such purpose.

- (5) For any allowances used for the purpose described in paragraph (4)(C), the State shall—
- (A) prioritize expansion of existing energy efficiency programs approved and overseen by the State or the appropriate State regulatory authority; and
- (B) demonstrate that such allowances have been used to supplement, and not to supplant, existing and otherwise available State, local, and ratepayer funding for such purpose.
- (d) REPORTING.—Each State receiving allowances under this section shall include in its biennial reports required under section 131, in accordance with such requirements as the Administrator may prescribe
- (1) a list of entities receiving allowances or allowance value under this section, including entities receiving such allowances or allowance value from units of local government pursuant to subsection (c)(1):
- (2) the amount and nature of allowances or allowance value received by each such recipient:
- (3) the specific purposes for which such allowances or allowance value was conveyed to each such recipient;
- (4) documentation of the amount of energy savings, emission reductions, renewable energy deployment, and new or retooled manufacturing capacity resulting from the use of such allowances or allowance value; and
- (5) for any energy efficiency program supported under subsection (c)(4)(C)—
- (A) an assessment demonstrating the cost-effectiveness of such program; and
- (B) a demonstration that the requirements set forth in subsection (c)(5) have been satisfied
- (e) ENFORCEMENT.—If the Administrator determines that a State is not in compliance with this section, the Administrator may withhold up to twice the number of allowances that the State failed to use in accordance with the requirements of this section, that such State would otherwise be eligible to receive under this section in later years. Allowances withheld pursuant to this subsection shall be distributed among the remaining States in accordance with the requirements of subsection (b).

SEC. 133. SUPPORT OF INDIAN RENEWABLE EN-ERGY AND ENERGY EFFICIENCY PROGRAMS.

- (a) Definitions.—For purposes of this section:
- (1) ALLOWANCE; COST-EFFECTIVE; RENEW-ABLE ENERGY RESOURCE.—The terms "allowance", "cost-effective", and "renewable energy resource" have the meaning given those terms in section 132 of this Act.
- (2) INDIAN TRIBE.—The term "Indian tribe" has the meaning given the term in section 4 of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450b).
- (3) SECRETARY.—The term "Secretary" means the Secretary of Energy.
- (b) ESTABLISHMENT.—Not later than 18 months after the date of enactment of this Act, the Secretary shall, in consultation with the Administrator and the Secretary of the Interior, promulgate regulations establishing a program to distribute allowances to Indian tribes on a competitive basis for the following purposes:
- (1) ENERGY EFFICIENCY.—Cost-effective energy efficiency programs for end-use consumers of electricity, natural gas, home heating oil, or propane.
- (2) RENEWABLE ENERGY.—Deployment of technologies to generate electricity from renewable energy resources.
- (c) REQUIREMENTS.—The regulations promulgated pursuant to subsection (b) shall prescribe design elements and requirements of the program established under this section, including—

- (1) objective criteria for evaluating proposals submitted by Indian tribes, and for selecting projects and programs to receive support, under this section;
- (2) reporting requirements for Indian tribes that receive allowances under this section; and
- (3) other appropriate elements and requirements.
- (d) DISTRIBUTION.—The Administrator shall, at the direction of the Secretary, distribute to Indian tribes allowances that are set aside, pursuant to section 132, for use under this section.

Subtitle E—Smart Grid Advancement SEC. 141. DEFINITIONS.

For purposes of this subtitle:

- (1) The term "applicable baseline" means the average of the highest three annual peak demands a load-serving entity has experienced during the 5 years immediately prior to the date of enactment of this Act.
- (2) The term "Commission" means Federal Energy Regulatory Commission.
- (3) The term "load-serving entity" means an entity that provides electricity directly to retail consumers with the responsibility to assure power quality and reliability, including such entities that are investorowned, publicly owned, owned by rural electric cooperatives, or other entities.
- (4) The term "peak demand" means the highest point of electricity demand, net of any distributed electricity generation or storage from sources on the load-serving entity's customers' premises, during any hour on the system of a load serving entity during a calendar year, expressed in Megawatts (MW), or more than one such high point as a function of seasonal demand changes.
- (5) The term "peak demand reduction" means the reduction in annual peak demand as compared to a previous baseline year or period, expressed in Megawatts (MW), whether accomplished by—
- (A) diminishing the end-use requirements for electricity;
- (B) use of locally stored energy or generated electricity to meet those requirements from distributed resources on the load-serving entity's customers' premises and without use of high-voltage transmission or
- (C) energy savings from efficient operation of the distribution grid resulting from the use of a Smart Grid.
- (6) The term "peak demand reduction plan" means a plan developed by or for a load-serving entity that it will implement to meet its peak demand reduction goals.
- (7) The term "peak period" means the time period on the system of a load-serving entity relative to peak demand that may warrant special measures or electricity resources to maintain system reliability while meeting peak demand.
- (8) The term "Secretary" means the Secretary of Energy.
- (9) The term "Smart Grid" has the meaning provided by section 1301 of the Energy Independence and Security Act of 2007 (15 U.S.C. 17381).

SEC. 142, ASSESSMENT OF SMART GRID COST EFFECTIVENESS IN PRODUCTS.

- (a) ASSESSMENT.—Within one year after the date of enactment of this Act, the Secretary and the Administrator shall each assess the potential for cost-effective integration of Smart Grid technologies and capabilities in all products that are reviewed by the Department of Energy and the Environmental Protection Agency, respectively, for potential designation as Energy Star products.
- (b) ANALYSIS.—(1) Within 2 years after the date of enactment of this Act, the Secretary and the Administrator shall each prepare an

- analysis of the potential energy savings, greenhouse gas emission reductions, and electricity cost savings that could accrue for each of the products identified by the assessment in subsection (a) in the following optimal circumstances:
- (A) The products possessed Smart Grid capability and interoperability that is tested and proven reliable.
- (B) The products were utilized in an electricity utility service area which had Smart Grid capability and offered customers rate or program incentives to use the products.
- (C) The utility's rates reflected national average costs, including average peak and valley seasonal and daily electricity costs.
- (D) Consumers using such products took full advantage of such capability.
- (E) The utility avoided incremental investments and rate increases related to such savings.
- (2) The analysis under paragraph (1) shall be considered the "best case" Smart Grid analysis. On the basis of such an analysis for each product, the Secretary and the Administrator shall determine whether the installation of Smart Grid capability for such a product would be cost effective. For purposes of this paragraph, the term "cost effective" means that the cumulative savings from using the product under the best case Smart Grid circumstances for a period of one-half of the product's expected useful life will be greater than the incremental cost of the Smart Grid features included in the product.
- (3) To the extent that including Smart Grid capability in any products analyzed under paragraph (2) is found to be cost effective in the best case, the Secretary and the Administrator shall, not later than 3 years after the date of enactment of this Act take each of the following actions:
- (A) Inform the manufacturer of such product of such finding of cost effectiveness.
- (B) Assess the potential contributions the development and use of products with Smart Grid technologies bring to reducing peak demand and promoting grid stability.
- (C) Assess the potential national energy savings and electricity cost savings that could be realized if Smart Grid potential were installed in the relevant products reviewed by the Energy Star program.
- (D) Assess and identify options for providing consumers information on products with Smart Grid capabilities, including the necessary conditions for cost-effective savings.
- (E) Submit a report to Congress summarizing the results of the assessment for each class of products, and presenting the potential energy and greenhouse gas savings that could result if Smart Grid capability were installed and utilized on such products.

SEC. 143. INCLUSIONS OF SMART GRID CAPA-BILITY ON APPLIANCE ENERGY GUIDE LABELS.

Section 324(a)(2) of the Energy Policy and Conservation Act (42 U.S.C. 6294(a)(2)) is amended by adding the following at the end:

- "(J)(i) Not later than 1 year after the date of enactment of this subparagraph, the Federal Trade Commission shall initiate a rule-making to consider making a special note in a prominent manner on any ENERGY GUIDE label for any product actually including Smart Grid capability that—
- "(I) Smart Grid capability is a feature of that product;
- "(II) the use and value of that feature depended on the Smart Grid capability of the utility system in which the product was installed and the active utilization of that feature by the customer; and
- "(III) on a utility system with Smart Grid capability, the use of the product's Smart Grid capability could reduce the customer's cost of the product's annual operation by an

estimated dollar amount range representing the result of incremental energy and electricity cost savings that would result from the customer taking full advantage of such Smart Grid capability.

"(ii) Not later than 3 years after the date of enactment of this subparagraph, the Commission shall complete the rulemaking initiated under clause (i)."

SEC. 144. SMART GRID PEAK DEMAND REDUCTION GOALS.

- (a) GOALS.—Not later than one year after the date of enactment of this section, each load-serving entity, or, at the option of the State, each State with respect to load-serving entities that the State regulates, shall determine and publish peak demand reduction goals for any load-serving entities that have an applicable baseline in excess of 250 megawatts.
- (b) Baselines.—(1) The Commission, in consultation with the Secretary and the Administrator, shall develop and publish, after an opportunity for public comment, but not later than 180 days after enactment of this section, a methodology to provide for adjustments or normalization to a load-serving entity's applicable baseline over time to reflect changes in the number of customers served, weather conditions, general economic conditions, and any other appropriate factors external to peak demand management, as determined by the Commission.

 (2) The Commission shall support load-
- (2) The Commission shall support load-serving entities (including any load-serving entities with an applicable baseline of less than 250 megawatts that volunteer to participate in achieving the purposes of this section) in determining their applicable baselines, and in developing their peak demand reduction goals.
- (3) The Secretary, in consultation with the Commission, the Administrator, and the North American Electric Reliability Corporation, shall develop a system and rules for measurement and verification of demand reductions.
- (c) PEAK DEMAND REDUCTION GOALS.—(1) Peak demand reduction goals may be established for an individual load-serving entity, or, at the determination of a State, tribal, or regional entity, by that State, tribal, or regional entity for a larger region that shares a common system peak demand and for which peak demand reduction measures would offer regional benefit.
- (2) A State or regional entity establishing peak demand reduction goals shall cooperate, as necessary and appropriate, with the Commission, the Secretary, State regulatory commissions, State energy offices, the North American Electric Reliability Corporation, and other relevant authorities.
- (3) In determining the applicable peak demand reduction goals—
- (A) States and other jurisdictional entities may utilize the results of the 2009 National Demand Response Potential Assessment, as authorized by section 571 of the National Energy Conservation Policy Act (42 U.S.C. 8279); and
- (B) the relative economics of peak demand reduction and generation required to meet peak demand shall be evaluated in a neutral and objective manner.
- (4) The applicable peak demand reduction goals shall provide that—
- (A) load-serving entities will reduce or mitigate peak demand by a minimum percentage amount from the applicable baseline to a lower peak demand during calendar year 2012:
- (B) load-serving entities will reduce or mitigate peak demand by a minimum percentage greater amount from the applicable baseline to a lower peak demand during calendar year 2015; and
- (C) the minimum percentage reductions established as peak demand reduction goals

- shall be the maximum reductions that are realistically achievable with an aggressive effort to deploy Smart Grid and peak demand reduction technologies and methods, including but not limited to those listed in subsection (d).
- (d) PLAN.—Each load-serving entity shall prepare a peak demand reduction plan that demonstrates its ability to meet each applicable goal by any or a combination of the following options:
- (1) Direct reduction in megawatts of peak demand through—
- (A) energy efficiency measures (including efficient transmission wire technologies which significantly reduce line loss compared to traditional wire technology) with reliable and continued application during peak demand periods; or
 - (B) use of a Smart Grid.
- (2) Demonstration that an amount of megawatts equal to a stated portion of the applicable goal is contractually committed to be available for peak reduction through one or more of the following:
- (A) Megawatts enrolled in demand response programs.
- (B) Megawatts subject to the ability of a load-serving entity to call on demand response programs, smart appliances, smart electricity or energy storage devices, distributed generation resources on the entity's customers' premises, or other measures directly capable of actively, controllably, reliably, and dynamically reducing peak demand ("dynamic peak management control").
- (C) Megawatts available from distributed dynamic electricity or energy storage under agreement with the owner of that storage.
- (D) Megawatts committed from dispatchable distributed generation demonstrated to be reliable under peak period conditions and in compliance with air quality regulations.
- (E) Megawatts available from smart appliances and equipment with Smart Grid capability available for direct control by the utility through agreement with the customer owning the appliances or equipment or with a third party pursuant to such agreements.
- (F) Megawatts from a demonstrated and assured minimum of distributed solar electric generation capacity in instances where peak period and peak demand conditions are directly related to solar radiation and accompanying heat.
- (3) If any of the methods listed in subparagraph (C), (D), or (E) of paragraph (2) are relied upon to meet its peak demand reduction goals, the load-serving entity must demonstrate this capability by operating a test during the applicable calendar year.
- (4) Nothing in this section shall require the publication in peak demand reduction goals or in any peak demand reduction plan of any information that is confidential for competitive or other reasons or that identifies individual customers.
- (e) EXISTING AUTHORITY AND REQUIRE-MENTS.—Nothing in this section diminishes or supersedes any authority of a State or political subdivision of a State to adopt or enforce any law or regulation respecting peak demand management, demand response, distributed energy storage, use of distributed generation, or the regulation of load-serving entities. The Commission, in consultation with States and Indian tribes having such peak management, demand response and distributed energy storage programs, shall to the maximum extent practicable, facilitate coordination between the Federal program and such State and tribal programs.
- (f) RELIEF.—The Commission may, for good cause, grant relief to load-serving entities from the requirements of this section.
- from the requirements of this section.
 (g) OTHER LAWS.—Except as provided in subsections (e) and (f), no law or regulation

- shall relieve any person of any requirement otherwise applicable under this section.
- (h) COMPLIANCE.—(1) The Commission shall within one year after the date of enactment of this Act establish a public website where the Commission will provide information and data demonstrating compliance by States, Indian tribes regional entities, and load-serving entities with this section, including the success of load-serving entities in meeting applicable peak demand reduction goals.
- (2) The Commission shall, by April 1 of each year beginning in 2012, provide a report to Congress on compliance with this section and success in meeting applicable peak demand reduction goals and, as appropriate, shall make recommendations as to how to increase peak demand reduction efforts.
- (3) The Commission shall note in each such report any State, political subdivision of a State, or load-serving entity that has failed to comply with this section, or is not a part of any region or group of load-serving entities serving a region that has complied with this section.
- (4) The Commission shall have and exercise the authority to take reasonable steps to modify the process of establishing peak demand reduction goals and to accept adjustments to them as appropriate when sought by load-serving entities.
 - (i) Assistance and Funding.—
- (1) ASSISTANCE TO STATES AND TRIBES.—Any costs incurred by States for activities undertaken pursuant to this section shall be supported by the use of emission allowances allocated to the States' SEED Accounts or to the tribes pursuant to section 132 of this Act. To the extent that a State provides allowances to local governments within the State to implement this program, that shall be deemed a distribution of such allowances to units of local government pursuant to subsection (c)(1) of that section.
- (2) FUNDING.—There are authorized to be appropriated such sums as may be necessary to the Commission, the Secretary, and the Administrator to carry out the provisions of this section.

SEC. 145. REAUTHORIZATION OF ENERGY EFFI-CIENCY PUBLIC INFORMATION PRO-GRAM TO INCLUDE SMART GRID IN-FORMATION.

- (a) IN GENERAL.—Section 134 of the Energy Policy Act of 2005 (42 U.S.C. 15832) is amended as follows:
- (1) By amending the section heading to read as follows: "ENERGY EFFICIENCY AND SMART GRID PUBLIC INFORMATION INITIATIVE".
- (2) In paragraph (1) of subsection (a) by striking "reduce energy consumption during the 4-year period beginning on the date of enactment of this Act" and inserting "increase energy efficiency and to adopt Smart Grid technology and practices".
- (3) In paragraph (2) of subsection (a) by striking "benefits to consumers of reducing" and inserting "economic and environmental benefits to consumers and the United States of optimizing".
- (4) In subsection (a) by inserting at the beginning of paragraph (3) "the effect of energy efficiency and Smart Grid capability in reducing energy and electricity prices throughout the economy, together with".
- (5) In subsection (a)(4) by redesignating subparagraph (D) as (E), by striking "and" at the end of subparagraph (C), and by inserting after subparagraph (C) the following:
- "(D) purchasing and utilizing equipment that includes Smart Grid features and capability; and".
- (6) In subsection (c), by striking "Not later than July 1, 2009," and inserting, "For each year when appropriations pursuant to the authorization in this section exceed \$10.000.000."

- (7) In subsection (d) by striking "2010" and inserting "2020".
- (8) In subsection (e) by striking "2010" and inserting "2020".
- (b) TABLE OF CONTENTS.—The item relating to section 134 in the table of contents for the Energy Policy Act of 2005 (42 U.S.C. 15801 and following) is amended to read as follows:
- "Sec. 134. Energy efficiency and Smart Grid public information initiative.".

SEC. 146. INCLUSION OF SMART GRID FEATURES IN APPLIANCE REBATE PROGRAM.

- (a) AMENDMENTS.—Section 124 of the Energy Policy Act of 2005 (42 U.S.C. 15821) is amended as follows:
- (1) By amending the section heading to read as follows: "ENERGY EFFICIENT AND SMART APPLIANCE REBATE PROGRAM.".
- (2) By redesignating paragraphs (4) and (5) of subsection (a) as paragraphs (5) and (6), respectively, and inserting after paragraph (3) the following:
- "(4) SMART APPLIANCE.—The term 'smart appliance' means a product that the Administrator of the Environmental Protection Agency or the Secretary of Energy has determined qualifies for such a designation in the Energy Star program pursuant to section 142 of the American Clean Energy and Security Act of 2009, or that the Secretary or the Administrator has separately determined includes the relevant Smart Grid capabilities listed in section 1301 of the Energy Independence and Security Act of 2007 (15 U.S.C. 17381)."
- (3) In subsection (b)(1) by inserting "and smart" after "efficient" and by inserting after "products" the first place it appears ", including products designated as being smart appliances".
- (4) In subsection (b)(3), by inserting "the administration of" after "carry out".
- (5) In subsection (d), by inserting "the administration of" after "carrying out" and by inserting ", and up to 100 percent of the value of the rebates provided pursuant to this section" before the period at the end.
- (6) In subsection (e)(3), by inserting ", with separate consideration as applicable if the product is also a smart appliance," after "Energy Star product" the first place it appears and by inserting "or smart appliance" before the period at the end.
- (7) In subsection (f), by striking "\$50,000,000" through the period at the end and inserting "\$100,000,000 for each fiscal year from 2010 through 2015.".
- (b) Table of Contents.—The item relating to section 124 in the table of contents for the Energy Policy Act of 2005 (42 U.S.C. 15801 and following) is amended to read as follows:
- "Sec. 124. Energy efficient and smart appliance rebate program.".

Subtitle F—Transmission Planning

SEC. 151. TRANSMISSION PLANNING AND SITING.

- (a) IN GENERAL.—Section 216 of the Federal Power Act (16 U.S.C. 824p) is amended as follows:
- (1) In subsection (b), in paragraph (5), by striking "; and" and inserting a semicolon, in paragraph (6) by striking the period and inserting "; and" and by adding the following at the end thereof:
- "(7) the facility is interstate in nature or is an intrastate segment integral to a proposed interstate facility;".
- (2) In subsection (k), by inserting at the end the following: "Subsections (a), (b), (c), and (h) of this section shall not apply in the Western interconnection."
- (3) In subsections (d) and (e), by striking "subsection (b)" in each place and inserting "subsection (b) or section 216B", and by striking "permit" and inserting "permit or certificate" in each place it appears.

 (b) NEW SECTIONS.—The Federal Power Act
- (b) New Sections.—The Federal Power Act (16 U.S.C. 824p) is amended by inserting the following new sections after section 216:

"SEC. 216A TRANSMISSION PLANNING.

- ''(a) Federal Policy for Transmission Planning.—
- "(1) OBJECTIVES.—It is the policy of the United States that regional electric grid planning should facilitate the deployment of renewable and other zero-carbon and low-carbon energy sources for generating electricity to reduce greenhouse gas emissions while ensuring reliability, reducing congestion, ensuring cyber-security, minimizing environmental harm, and providing for cost-effective electricity services throughout the United States, in addition to serving the objectives stated in section 217(b)(4).
- (2) OPTIONS.—In addition to the policy under paragraph (1), it is the policy of the United States that regional electric grid planning to meet these objectives should result from an open, inclusive and transparent process, taking into account all significant demand-side and supply-side options, including energy efficiency, distributed generation. renewable energy and zero-carbon electricity generation technologies, smart-grid technologies and practices, demand response, electricity storage, voltage regulation technologies, high capacity conductors with at least 25 percent greater efficiency than traditional ACSR (aluminum stranded conductors steel reinforced) conductors, superconductor technologies, underground transmission technologies, and new conventional electric transmission capacity and corridors. (b) Planning.—
- "(1) PLANNING PRINCIPLES.—Not later than 1 year after the date of enactment of this section, the Commission shall adopt, after notice and opportunity for comment, national electricity grid planning principles derived from the Federal policy established under subsection (a) to be applied in ongoing and future transmission planning that may implicate interstate transmission of electricity.
- REGIONAL PLANNING ENTITIES.—Not "(2) later than 3 months after the date of adoption by the Commission of national electricity grid planning principles pursuant to paragraph (1), entities that conduct or may conduct transmission planning pursuant to State, tribal, or Federal law or regulation, including States, Indian tribes, entities designated by States and Indian tribes, Federal Power Marketing Administrations, transmission providers, operators and owners, regional organizations, and electric utilities, and that are willing to incorporate the national electricity grid planning principles adopted by the Commission in their electric grid planning, shall identify themselves and the regions for which they propose to develop plans to the Commission.
- "(3) Coordination of regional planning ENTITIES.—The Commission shall encourage regional planning entities described under paragraph (2) to cooperate and coordinate across regions and to harmonize regional electric grid planning with planning in adjacent or overlapping jurisdictions to the maximum extent feasible. The Commission shall work with States, Indian tribes, Federal land management agencies, State energy, environment, natural resources, and land management agencies and commissions, Federal power marketing administrations, electric utilities, transmission providers, load-serving entities, transmission operators, regional transmission organizations, independent system operators, and other organizations to resolve any conflict or competition among proposed planning entities in order to build consensus and promote the Federal policy established under subsection (a). The Commission shall seek to ensure that planning that is consistent with the national electricity grid planning principles adopted pursuant to paragraph (1) is conducted in all regions of

- the United States and the territories, but in a manner that, to the extent feasible, avoids uncoordinated planning by more than one planning entity for the same area.
- "(4) RELATION TO EXISTING PLANNING POLICY.—In implementing the Federal policy established under subsection (a), the Commission shall
- "(A) incorporate and coordinate with any ongoing planning efforts undertaken pursuant to section 217 and Commission Order No. 890:
- "(B) coordinate with the Secretary of Energy in providing to the regional planning entities an annual summary of national energy policy priorities and goals;
- "(C) coordinate with corridor designation and planning functions carried out pursuant to section 216 by the Secretary of Energy, who shall provide financial support from available funds to support the purposes of this section: and
- "(D) coordinate with the Secretaries of the Interior and Agriculture and Indian tribes in carrying out the Secretaries' or tribal governments' existing responsibilities for the planning or siting of transmission facilities on Federal or tribal lands, consistent with law, policy, and regulations relating to the management of federal public lands.
 - "(5) ASSISTANCE.—
- "(A) IN GENERAL.—The Commission shall provide support to and may participate if invited to do so in the regional grid planning processes conducted by regional planning entities. The Secretary of Energy and the Commission may provide planning resources and assistance as required or as requested by regional planning entities, including system data, cost information, system analysis, technical expertise, modeling support, dispute resolution services, and other assistance to regional planning entities, as appropriate.
- "(B) AUTHORIZATION.—There are authorized to be appropriated such sums as may be necessary to carry out this paragraph.
- "(6) CONFLICT RESOLUTION.—In the event that regional grid plans conflict, the Commission shall assist the regional planning entities in resolving such conflicts in order to achieve the objectives of the Federal policy established under subsection (a).
- "(7) SUBMISSION OF PLANS.—The Commission shall require regional planning entities to submit initial regional electric grid plans to the Commission not later than 18 months after the date the Commission promulgates national electricity grid planning principles pursuant to paragraph (1), with updates to such plans not less than every 3 years thereafter. The Commission shall review such plans for consistency with the national grid planning principles and may return a plan to one or more planning entities for further consideration, along with the Commission's own recommendations for resolution of any conflict or for improvement.
- "(8) Integration of plans.—Regional electric grid plans should, in general, be developed from sub-regional requirements and plans, including planning input reflecting individual utility service areas. Regional plans may then in turn be combined into larger regional plans, up to interconnection-wide and national plans, as appropriate and necessary as determined by the Commission. In no case shall a multi-regional plan impose inclusion of a facility on a region that has submitted a valid plan that, after efforts to resolve the conflict, does not include such facility. To the extent practicable, all plans submitted to the Commission shall be public documents and available on the Commission's Web site.
- "(9) MULTI-REGIONAL MEETINGS.—As regional grid plans are submitted to the Commission, the Commission may convene multi-regional meetings to discuss regional

grid plan consistency and integration, including requirements for multi-regional projects, and to resolve any conflicts that emerge from such multi-regional projects. The Commission shall provide its recommendations for eliminating any inter-regional conflicts.

"(10) Report to congress.—Not later than 3 years after the date of enactment of this section and each 3 years thereafter, the Commission shall provide a report to Congress containing the results of the regional grid planning process, including summaries of the adopted regional plans and the extent to which the Federal policy objectives in subsection (a) have been successfully achieved. The Commission shall provide an electronic version of its report on its website with links to all regional and sub-regional plans taken into account. The Commission shall note and provide its recommended resolution for any conflicts not resolved during the planning process. The Commission shall make any recommendations to Congress on the appropriate Federal role or support required to address the needs of the electric grid, including recommendations for addressing any needs that are beyond the reach of existing State, tribal, and Federal authority.

"SEC. 216B. SITING AND CONSTRUCTION IN THE WESTERN INTERCONNECTION.

"(a) APPLICABILITY.—This section applies only to States located in the Western Interconnection and does not apply to States located in the Eastern Interconnection, to the States of Alaska or Hawaii, or to ERCOT.

"(b) CERTIFICATE OF PUBLIC CONVENIENCE AND NECESSITY.—The Commission may, after notice and opportunity for hearing, issue a certificate of public convenience and necessity for the construction or modification of a transmission facility if the Commission finds that—

"(1) the facility was identified and included in one or more relevant and final regional or interconnection-wide electric grid plans submitted to the Commission pursuant to subsection (b) of 216A:

"(2) any conflict among regional electric grid plans concerning the need for the facility was resolved;

"(3) such relevant regional electric grid plans are consistent with the national grid planning principles adopted by the Commission pursuant to subsection (b);

"(4) the facility was identified as needed in significant measure to meet demand for renewable energy in such plans;

"(5) the facility is a multistate facility;

"(6) the developer of such facility filed a complete application seeking approval for the siting of the facility with a state commission or other entity that has authority to approve the siting of the facility:

"(7) a State commission or other entity that has authority to approve the siting of the facility—

"(A) did not issue a decision on an application seeking approval for the siting of the facility within 1 year after the date the applicant submitted a completed application to the State;

``(B) denied a complete application seeking approval for the siting of the facility; or

"(C) authorized the siting of the facility subject to conditions that unreasonably interfere with the development of the facility; and

"(8) the siting of the facility can be accomplished in a manner consistent with the Federal policy established in subsection (a) of section 216A and the national grid planning principles adopted by the Commission pursuant to subsection (b) of section 216A.

"(c) STATE RECOMMENDATIONS ON RESOURCE PROTECTION.—In issuing a final certificate of public convenience and necessity pursuant to subsection (b), the Commission shall—

"(1) consider any siting constraints and mitigation measures based on habitat protection, health and safety considerations, environmental considerations, or cultural site protection identified by relevant State or local authorities; and

"(2) incorporate those identified siting constraints or mitigation measures, including recommendations related to project routing, as conditions in the final certificate of public convenience and necessity, or if the Commission determines that a recommended siting constraint or mitigation measure is infeasible, excessively costly, or inconsistent with the Federal policy established in subsection (a) of section 216A or the national grid planning principles adopted by the Commission pursuant to subsection (b) of section 216A—

"(A) consult with State regulatory agencies to seek to resolve the issue;

"(B) incorporate as conditions on the certificate such recommended siting constraints or mitigation measures as are determined to be appropriate by the Commission, based on consultation by the Commission with State regulatory agencies, the Federal policy established in subsection (a) of section 216A and the national grid planning principles adopted by the Commission pursuant to subsection (b) of section 216A, and the record before the Commission; and

"(C) if, after consultation, the Commission does not adopt in whole or in part a recommendation of an agency, publish a finding that the adoption of the recommendation is infeasible, not cost effective, or inconsistent with this section or other applicable provisions of law.

"(d) CERTIFICATE APPLICATIONS.—(1) An application for a preliminary or final certificate of public convenience and necessity under this subsection shall be made in writing to the Commission.

"(2) The Commission shall issue rules specifying—

"(A) the form of the application;

"(B) the information to be contained in the application; and

"(C) the manner of service of notice of the application on interested persons.

"(e) COORDINATION OF FEDERAL AUTHORIZATIONS FOR TRANSMISSION FACILITIES.—

"(1) In this subsection, the term 'Federal authorization' shall have the same meaning and include the same actions as in section 216(h)

"(2) The Federal Energy Regulatory Commission shall act as the lead agency for purposes of coordinating all applicable Federal authorizations and related environmental reviews of the facility, provided, however, that to the extent the facility is proposed to be sited on Federal lands, the Department of the Interior will assume such lead-agency duties as agreed between the Commission and the Department of Interior.

"(3) To the maximum extent practicable under applicable Federal law, the Commission, and to the extent agreed, the Secretary of Interior, shall coordinate the Federal authorization and review process under this subsection with any Indian tribes, multistate entities, and State agencies that are responsible for conducting any separate permitting and environmental reviews of the facility, to ensure timely and efficient review and permit decisions.

"(4)(A) As head of the lead agency, the Chairman of the Commission, in consultation with the Secretary of Interior and with those entities referred to in paragraph (3) that are willing to coordinate their own separate permitting and environmental reviews with the Federal authorization and environmental reviews, shall establish prompt and binding intermediate milestones and ultimate deadlines for the review of, and Federal

authorization decisions relating to, the proposed facility.

"(B) The Chairman of the Commission, or the Secretary of Interior, as agreed under paragraph (2), shall ensure that, once an application has been submitted with such data as the lead agency considers necessary, all permit decisions and related environmental reviews under all applicable Federal laws shall be completed—

"(i) within 1 year; or

"(ii) if a requirement of another provision of Federal law does not permit compliance with clause (i), as soon thereafter as is practicable.

"(C) The Commission shall provide an expeditious pre-application mechanism for prospective applicants to confer with the agencies involved to have each such agency determine and communicate to the prospective applicant not later than 60 days after the prospective applicant submits a request for such information concerning—

"(i) the likelihood of approval for a potential facility; and

"(ii) key issues of concern to the agencies and public.

"(5)(A) As lead agency head, the Chairman of the Commission, in consultation with the affected agencies, shall prepare a single environmental review document, which shall be used as the basis for all decisions on the proposed project under Federal law.

"(B) The Chairman of the Commission and the heads of other agencies shall streamline the review and permitting of transmission within corridors designated under section 503 of the Federal Land Policy and Management Act (43 U.S.C. 1763) by fully taking into account prior analyses and decisions relating to the corridors.

"(C) The document shall include consideration by the relevant agencies of any applicable criteria or other matters as required under applicable law.

"(6)(A) If any agency has denied a Federal authorization required for a transmission facility, or has failed to act by the deadline established by the Commission pursuant to this section for deciding whether to issue the authorization, the applicant or any State in which the facility would be located may file an appeal with the President, who shall, in consultation with the affected agency, review the denial or failure to take action on the pending application.

"(B) Based on the overall record and in consultation with the affected agency, the President may—

"(i) issue the necessary authorization with any appropriate conditions; or

"(ii) deny the application.

"(C) The President shall issue a decision not later than 90 days after the date of the filing of the appeal.

"(D) In making a decision under this paragraph, the President shall comply with applicable requirements of Federal law, including any requirements of—

"(i) the National Forest Management Act of 1976 (16 U.S.C. 472a et seq.);

"(ii) the Endangered Species Act of 1973 (16 U.S.C. 1531 et seq.);

"(iii) the Federal Water Pollution Control Act (33 U.S.C. 1251 et seq.);

"(iv) the National Environmental Policy Act of 1969 (42 U.S.C. 4321 et seq.); and

"(v) the Federal Land Policy and Management Act of 1976 (43 U.S.C. 1701 et seq.).

"(7)(A) Not later than 18 months after August 8, 2005, the Commission or, as requested, the Secretary or Interior, shall issue any regulations necessary to implement this subsection.

"(B)(i) Not later than 1 year after August 8, 2005, the Commission, the Secretary of Interior, and the heads of all Federal agencies

with authority to issue Federal authorizations shall enter into a memorandum of understanding to ensure the timely and coordinated review and permitting of electricity transmission facilities.

"(ii) Interested Indian tribes, multistate entities, and State agencies may enter the memorandum of understanding.

"(C) The head of each Federal agency with authority to issue a Federal authorization shall designate a senior official responsible for, and dedicate sufficient other staff and resources to ensure, full implementation of the regulations and memorandum required under this paragraph.

"(8)(A) Each Federal land use authorization for an electricity transmission facility shall be issued—

"(i) for a duration, as determined by the Secretary of Interior, commensurate with the anticipated use of the facility; and

"(ii) with appropriate authority to manage the right-of-way for reliability and environmental protection.

"(B) On the expiration of the authorization (including an authorization issued before August 8, 2005), the authorization shall be reviewed for renewal taking fully into account reliance on such electricity infrastructure, recognizing the importance of the authorization for public health, safety, and economic welfare and as a legitimate use of Federal land

"(9) In exercising the responsibilities under this section, the Commission shall consult regularly with—

(A) electric reliability organizations (including related regional entities) approved by the Commission; and

"(B) Transmission Organizations approved by the Commission.".

SEC. 152. NET METERING FOR FEDERAL AGENCIES.

(a) STANDARD.—Subsection (b) of section 113 of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2623) is amended by adding the following new paragraph at the end thereof:

"(6) NET METERING FOR FEDERAL AGEN-CIES.—Each electric utility shall offer to arrange (either directly or through a third party) to make interconnection and net metering available to Federal Government agencies, offices, or facilities in accordance with the requirements of section 115(j). The standard under this paragraph shall apply only to electric utilities that sold over 4,000,000 megawatt hours of electricity in the preceding year to the ultimate consumers thereof. In the case of a standard under this paragraph, a period of 1 year after the date of the enactment of this section shall be substituted for the 2-year period referred to in other provisions of this section.

(b) SPECIAL RULES.—Section 115 of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2625) is amended by adding the following new subsection at the end thereof:

"(j) NET METERING FOR FEDERAL AGENCIES.—(1) The standard under paragraph (6) of section 113(b) shall require that rates and charges and contract terms and conditions for the sale of electric energy to the Federal Government or agency shall be the same as the rates and charges and contract terms and conditions that would be applicable if the agency did not own or operate a qualified generation unit and use a net metering system.

"(2)(A) The standard under paragraph (6) of section 113(b) shall require that each electric utility shall arrange to provide to the Government office or agency that qualifies for net metering an electrical energy meter capable of net metering and measuring, to the maximum extent practicable, the flow of electricity to or from the customer, using a

single meter and single register, the cost of which shall be recovered from the customer.

"(B) In a case in which it is not practicable to provide a meter under subparagraph (A), the utility (either directly or through a third party) shall, at the expense of the utility install 1 or more of those electric energy meters

"(3)(A) The standard under paragraph (6) of section 113(b) shall require that each electric utility shall calculate the electric energy consumption for the Government office or agency using a net metering system that meets the requirements of this subsection and paragraph (6) of section 113(b) and shall measure the net electricity produced or consumed during the billing period using the metering installed in accordance with this paragraph.

"(B) If the electricity supplied by the retail electric supplier exceeds the electricity generated by the Government office or agency during the billing period, the Government office or agency shall be billed for the net electric energy supplied by the retail electric supplier in accordance with normal billing practices.

"(C) If electric energy generated by the Government office or agency exceeds the electric energy supplied by the retail electric supplier during the billing period, the Government office or agency shall be billed for the appropriate customer charges for that billing period and credited for the excess electric energy generated during the billing period, with the credit appearing as a kilowatt-hour credit on the bill for the following billing period.

"(D) Any kilowatt-hour credits provided to the Government office or agency as provided in this subsection shall be applied to the Government office or agency electric energy consumption on the following billing period bill (except for a billing period that ends in the next calendar year). At the beginning of each calendar year, any unused kilowatthour credits remaining from the preceding year will carry over to the new year.

"(4) The standard under paragraph (6) of section 113(b) shall require that each electric utility shall offer a meter and retail billing arrangement that has time-differentiated rates. The kilowatt-hour credit shall be based on the ratio representing the difference in retail rates for each time-of-use rate, or the credits shall be reflected on the bill of the Government office or agency as a monetary credit reflecting retail rates at the time of generation of the electric energy by the customer-generator.

"(5) The standard under paragraph (6) of section 113(b) shall require that the qualified generation unit, interconnection standards, and net metering system used by the Government office or agency shall meet all applicable safety and performance and reliability standards established by the National Electrical Code, the Institute of Electrical and Electronics Engineers, Underwriters Laboratories, and the American National Standards Institute.

"(6) The standard under paragraph (6) of section 113(b) shall require that electric utilities shall not make additional charges, including standby charges, for equipment or services for safety or performance that are in addition to those necessary to meet the other standards and requirements of this subsection and paragraph (6) of section 113(h)

"(7) For purposes of this subsection and paragraph (6) of section 113(b):

"(A) The term 'Government' means any office, facility, or agency of the Federal Government.

``(B) The term 'customer-generator' means the owner or operator of a electricity generation unit.

"(C) The term 'electric generation unit' means any renewable electric generation unit that is owned, operated, or sited on a Federal Government facility.

"(D) The term 'net metering' means the process of—

"(i) measuring the difference between the electricity supplied to a customer-generator and the electricity generated by the customer-generator that is delivered to a utility at the same point of interconnection during an applicable billing period; and

"(ii) providing an energy credit to the customer-generator in the form of a kilowatthour credit for each kilowatt-hour of electricity produced by the customer-generator from an electric generation unit."

(c) SAVINGS PROVISION.—If this section or a portion of this section is determined to be invalid or unenforceable, that shall not affect the validity or enforceability of any other provision of this Act.

SEC. 153. SUPPORT FOR QUALIFIED ADVANCED ELECTRIC TRANSMISSION MANU-FACTURING PLANTS, QUALIFIED HIGH EFFICIENCY TRANSMISSION PROPERTY, AND QUALIFIED ADVANCED ELECTRIC TRANSMISSION PROPERTY.

(a) LOAN GUARANTEES PRIOR TO SEPTEMBER 30, 2011.—Section 1705(a) of the Energy Policy Act of 2005 (42 U.S.C. 16515(a)), as added by section 406 of the American Recovery and Reinvestment Act of 2009 (Public Law 109-58; 119 Stat. 594) is amended by adding the following new paragraph at the end thereof:

"(5) The development, construction, acquisition, retrofitting, or engineering integration of a qualified advanced electric transmission manufacturing plant or the construction of a qualified high efficiency transmission property or a qualified advanced electric transmission property (whether by construction of new facilities or the modification of existing facilities). For purposes of this paragraph:

"(A) The term 'qualified advanced electric transmission property' means any high voltage electric transmission cable, related substation, converter station, or other integrated facility that—

"(i) utilizes advanced ultra low resistance superconductive material or other advanced technology that has been determined by the Secretary of Energy as—

"(I) reasonably likely to become commercially viable within 10 years after the date of enactment of this paragraph:

"(II) capable of reliably transmitting at least 5 gigawatts of high-voltage electric energy for distances greater than 300 miles with energy losses not exceeding 3 percent of the total power transported; and

``(III) not creating an electromagnetic field;

"(ii) has been determined by an appropriate energy regulatory body, upon application, to be in the public interest and thereby eligible for inclusion in regulated rates; and

"(iii) can be located safely and economically in a permanent underground right of way not to exceed 25 feet in width.

The term 'qualified advanced electric transmission property' shall not include any property placed in service after December 31, 2016.

"(B)(i) The term 'qualified high efficiency transmission property' means any high voltage overhead electric transmission line, related substation, or other integrated facility that—

"(I) utilizes advanced conductor core technology that—

"(aa) has been determined by the Secretary of Energy as reasonably likely to become commercially viable within 10 years after the date of enactment of this paragraph:

"(bb) is suitable for use on transmission lines up to 765kV; and

"(cc) exhibits power losses at least 30 percent lower than that of transmission lines using conventional 'ACSR' conductors;

"(II) has been determined by an appropriate energy regulatory body, upon application, to be in the public interest and thereby eligible for inclusion in regulated rates; and

"(III) can be located safely and economically in a right of way not to exceed that used by conventional 'ACSR' conductors; and

- "(ii) The term 'qualified high efficiency transmission property' shall not include any property placed in service after December 31, 2016
- "(C) The term 'qualified advanced electric transmission manufacturing plant' means any industrial facility located in the United States which can be equipped, re-equipped, expanded, or established to produce in whole or in part qualified advanced electric transmission property."
- (b) ADDITIONAL LOAN GUARANTEE AUTHOR-ITY.—Section 1703 of the Energy Policy Act of 2005 (42 U.S.C. 16513) is amended by adding the following new paragraph at the end of subsection (b):
- "(12) The development, construction, acquisition, retrofitting, or engineering integration of a qualified advanced electric transmission manufacturing plant or the construction of a qualified advanced electric transmission property (whether by construction of new facilities or the modification of existing facilities). For purposes of this paragraph, the terms 'qualified advanced electric transmission property' and 'qualified advanced electric transmission manufacturing plant' have the meanings provided by section 1705(a)(5)."
- (c) GRANTS.—The Secretary of Energy is authorized to provide grants for up to 50 percent of costs incurred in connection with the development, construction, acquisition of components for, or engineering of a qualified advanced electric transmission property defined in paragraph (5) of section 1705(a) of the Energy Policy Act of 2005 (42 U.S.C. 16515(a)). Such grants may only be made to the first project which qualifies under that paragraph. There are authorized to be appropriated for purposes of this subsection not more than \$100,000,000 for fiscal year 2010. The United States shall take no equity or other ownership interest in the qualified advanced electric transmission manufacturing plant or qualified advanced electric transmission property for which funding is provided under this subsection.

Subtitle G—Technical Corrections to Energy Laws

SEC. 161. TECHNICAL CORRECTIONS TO ENERGY INDEPENDENCE AND SECURITY ACT OF 2007.

- (a) TITLE III—ENERGY SAVINGS THROUGH IMPROVED STANDARDS FOR APPLIANCE AND LIGHTING.—(1) Section 325(u) of the Energy Policy and Conservation Act (42 U.S.C. 6295(u)) (as amended by section 301(c) of the Energy Independence and Security Act of 2007 (121 Stat. 1550)) is amended—
- (A) by redesignating paragraph (7) as paragraph (4); and
- (B) in paragraph (4) (as so redesignated), by striking "supplies is" and inserting "supply is"
- (2) Section 302 of the Energy Independence and Security Act of 2007 (121 Stat. 1551)) is amended—
- (A) in subsection (a), by striking "end of the paragraph" and inserting "end of subparagraph (A)"; and
- (B) in subsection (b), by striking "6313(a)" and inserting "6314(a)".
- (3) Section 343(a)(1) of the Energy Policy and Conservation Act (42 U.S.C. 6313(a)(1))

- (as amended by section 302(b) of the Energy Independence and Security Act of 2007 (121 Stat. 1551)) is amended—
- (A) by striking "Test procedures" and all that follows through "At least once" and inserting "Test procedures.—At least once"; and
- (B) by redesignating clauses (i) and (ii) as subparagraphs (A) and (B), respectively (and by moving the margins of such subparagraphs 2 ems to the left).
- (4) Section 342(a)(6) of the Energy Policy and Conservation Act (42 U.S.C. 6313(a)(6)) (as amended by section 305(b)(2) of the Energy Independence and Security Act of 2007 (121 Stat. 1554)) is amended—
 - (A) in subparagraph (B)-
- (i) by striking "If the Secretary" and inserting the following:
 - "(i) IN GENERAL.—If the Secretary";
- (ii) by striking "clause (ii)(II)" and inserting "subparagraph (A)(ii)(II)";
- (iii) by striking "clause (i)" and inserting "subparagraph (A)(i)"; and
- (iv) by adding at the end the following:
- "(ii) FACTORS.—In determining whether a standard is economically justified for the purposes of subparagraph (A)(ii)(II), the Secretary shall, after receiving views and comments furnished with respect to the proposed standard, determine whether the benefits of the standard exceed the burden of the proposed standard by, to the maximum extent practicable, considering—
- "(I) the economic impact of the standard on the manufacturers and on the consumers of the products subject to the standard;
- "(II) the savings in operating costs throughout the estimated average life of the product in the type (or class) compared to any increase in the price of, or in the initial charges for, or maintenance expenses of, the products that are likely to result from the imposition of the standard;
- (III) the total projected quantity of energy savings likely to result directly from the imposition of the standard;
- "(IV) any lessening of the utility or the performance of the products likely to result from the imposition of the standard;
- "(V) the impact of any lessening of competition, as determined in writing by the Attorney General, that is likely to result from the imposition of the standard;
- "(VI) the need for national energy conservation; and
- "(VII) other factors the Secretary considers relevant.
- "(iii) Administration.—
- "(I) ENERGY USE AND EFFICIENCY.—The Secretary may not prescribe any amended standard under this paragraph that increases the maximum allowable energy use, or decreases the minimum required energy efficiency, of a covered product.
 - "(II) UNAVAILABILITY.—
- "(aa) IN GENERAL.—The Secretary may not prescribe an amended standard under this subparagraph if the Secretary finds (and publishes the finding) that interested persons have established by a preponderance of the evidence that a standard is likely to result in the unavailability in the United States in any product type (or class) of performance characteristics (including reliability, features, sizes, capacities, and volumes) that are substantially the same as those generally available in the United States at the time of the finding of the Secretary.
- "(bb) OTHER TYPES OR CLASSES.—The failure of some types (or classes) to meet the criterion established under this subclause shall not affect the determination of the Secretary on whether to prescribe a standard for the other types or classes."; and
- (B) in subparagraph (C)(iv), by striking "An amendment prescribed under this subsection" and inserting "Notwithstanding

subparagraph (D), an amendment prescribed under this subparagraph''.

(5) Section 342(a)(6)(B)(iii) of the Energy Policy and Conservation Act (as added by section 306(c) of the Energy Independence and Security Act of 2007) is transferred and redesignated as clause (vi) of section 342(a)(6)(C) of the Energy Policy and Conservation Act (as amended by section 305(b)(2) of the Energy Independence and Security Act of 2007).

(6) Section 340 of the Energy Policy and Conservation Act (42 U.S.C. 6311) (as amended by sections 312(a)(2) and 314(a) of the Energy Independence and Security Act of 2007 (121 Stat. 1564, 1569)) is amended by redesignating paragraphs (22) and (23) (as added by section 314(a) of that Act) as paragraphs (23) and (24), respectively.

and (24), respectively.
(7) Section 345 of the Energy Policy and Conservation Act (42 U.S.C. 6316) (as amended by section 312(e) of the Energy Independence and Security Act of 2007 (121 Stat. 1567)) is amended—

is amended—

- (A) by striking "subparagraphs (B) through (G)" each place it appears and inserting "subparagraphs (B), (C), (D), (I), (J), and (K)":
- (B) by striking "part A" each place it appears and inserting "part B"; and
- (C) in subsection (h)(3), by striking "section 342(f)(3)" and inserting "section 342(f)(4)".
- (8) Section 340(13) of the Energy Policy and Conservation Act (42 U.S.C. 6311(13)) (as amended by section 313(a) of the Energy Independence and Security Act of 2007 (121 Stat. 1568)) is amended—
- (A) by striking subparagraphs (A) and (B) and inserting the following:
- "(A) IN GENERAL.—The term 'electric motor' means any motor that is—
- "(i) a general purpose T-frame, singlespeed, foot-mounting, polyphase squirrelcage induction motor of the National Electrical Manufacturers Association, Design A and B, continuous rated, operating on 230/460 volts and constant 60 Hertz line power as defined in NEMA Standards Publication MG1-1987; or
- "(ii) a motor incorporating the design elements described in clause (i), but is configured to incorporate one or more of the following variations—
 - "(I) U-frame motor;
 - "(II) NEMA Design C motor;
 - "(III) close-coupled pump motor;
 - ``(IV) footless motor;
- "(V) vertical solid shaft normal thrust motor (as tested in a horizontal configuration);
 - "(VI) 8-pole motor; or
- "(VII) poly-phase motor with a voltage rating of not more than 600 volts (other than 230 volts or 460 volts, or both, or can be operated on 230 volts or 460 volts, or both)."; and
- $(B)\;\; \mbox{by redesignating subparagraphs}\;\; (C)\; \mbox{through}\; (I)\; \mbox{as subparagraphs}\; (B)\; \mbox{through}\; (H),\; \mbox{respectively}.$
- (9)(A) Section 342(b) of the Energy Policy and Conservation Act (42 U.S.C. 6313(b)) is amended—
- (i) in paragraph (1), by striking "paragraph (2)" and inserting "paragraph (3)";
- (ii) by redesignating paragraphs (2) and (3) as paragraphs (3) and (4);
- (iii) by inserting after paragraph (1) the following:
- "(2) STANDARDS EFFECTIVE BEGINNING DE-CEMBER 19, 2010.—
- "(A) IN GENERAL.—Except for definite purpose motors, special purpose motors, and those motors exempted by the Secretary under paragraph (3) and except as provided for in subparagraphs (B), (C), and (D), each electric motor manufactured with power ratings from 1 to 200 horsepower (alone or as a component of another piece of equipment) on

or after December 19, 2010, shall have a nominal full load efficiency of not less than the nominal full load efficiency described in NEMA MG-1 (2006) Table 12-12.

"(B) FIRE PUMP ELECTRIC MOTORS.—Except for those motors exempted by the Secretary under paragraph (3), each fire pump electric motor manufactured with power ratings from 1 to 200 horsepower (alone or as a component of another piece of equipment) on or after December 19, 2010, shall have a nominal full load efficiency that is not less than the nominal full load efficiency described in NEMA MG-1 (2006) Table 12-11.

"(C) NEMA DESIGN B ELECTRIC MOTORS.— Except for those motors exempted by the Secretary under paragraph (3), each NEMA Design B electric motor with power ratings of more than 200 horsepower, but not greater than 500 horsepower, manufactured (alone or as a component of another piece of equipment) on or after December 19, 2010, shall have a nominal full load efficiency of not less than the nominal full load efficiency described in NEMA MG-1 (2006) Table 12-11.

"(D) Motors incorporating certain de-SIGN ELEMENTS.—Except for those motors exempted by the Secretary under paragraph (3), each electric motor described in section 340(13)(A)(ii) manufactured with power ratings from 1 to 200 horsepower (alone or as a

component of another piece of equipment) on or after December 19, 2010, shall have a nominal full load efficiency of not less than the nominal full load efficiency described in NEMA MG-1 (2006) Table 12-11.''; and

(iv) in paragraph (3) (as redesignated by clause (ii)), by striking "paragraph (1)" each place it appears in subparagraphs (A) and (D)

- and inserting "paragraphs (1) and (2)".
 (B) Section 313 of the Energy Independence and Security Act of 2007 (121 Stat. 1568) is repealed.
- (C) The amendments made by-
- (i) subparagraph (A) shall take effect on December 19, 2010; and
- (ii) subparagraph (B) shall take effect on December 19, 2007.
- (10) Section 321(30)(D)(i)(III) of the Energy Policy and Conservation Act (42 U.S.C. 6291(30)(D)(i)(III)) (as amended by section 321(a)(1)(A) of the Energy Independence and Security Act of 2007 (121 Stat. 1574)) is amended by inserting before the semicolon the following: "or, in the case of a modified spectrum lamp, not less than 232 lumens and not more than 1.950 lumens'
- (11) Section 321(30)(T) of the Energy Policy and Conservation Act (42 U.S.C. 6291(30)(T) (as amended by section 321(a)(1)(B) of the Energy Independence and Security Act of 2007 (121 Stat. 1574)) is amended-

- (A) in clause (i)-
- (i) by striking the comma after "household appliance" and inserting "and"; and
- (ii) by striking "and is sold at retail,"; and (B) in clause (ii), by inserting "when sold at retail," before "is designated"
- (12) Section 325 of the Energy Policy and Conservation Act (42 U.S.C. 6295) (as amended by sections 321(a)(3)(A) and 322(b) of the Energy Independence and Security Act of 2007 (121 Stat. 1577, 1588)) is amended by striking subsection (i) and inserting the fol-
- "(i) GENERAL SERVICE FLUORESCENT LAMPS, GENERAL SERVICE INCANDESCENT LAMPS, IN-TERMEDIATE BASE INCANDESCENT LAMPS, CAN-DELABRA BASE INCANDESCENT LAMPS, AND IN-CANDESCENT REFLECTOR LAMPS.-
 - "(1) ENERGY EFFICIENCY STANDARDS.
- "(A) IN GENERAL.—Each of the following general service fluorescent lamps, general service incandescent lamps, intermediate base incandescent lamps, candelabra base incandescent lamps, and incandescent reflector lamps manufactured after the effective date specified in the tables listed in this subparagraph shall meet or exceed the following lamp efficacy, new maximum wattage, and CRI standards:

"FLUORESCENT LAMPS

Lamp Type	Nominal Lamp Wattage	Minimum CRI	Minimum Average Lamp Efficacy (LPW)	Effective Date (Pe- riod of Months)
4-foot medium bi-pin	>35 W	69	75.0	36
	≤35 W	45	75.0	36
2-foot U-shaped	>35 W	69	68.0	36
-	≤35 W	45	64.0	36
8-foot slimline	65 W	69	80.0	18
	≤65 W	45	80.0	18
8-foot high output	>100 W	69	80.0	18
	≤100 W	45	80.0	18

"INCANDESCENT REFLECTOR "INCANDESCENT REFLECTOR "INCANDESCENT REFLECTOR LAMPS LAMPS—Continued LAMPS—Continued Effective Effective Effective Minimum Average Nominal Nominal Minimum Average Nominal Minimum Average Date (Pe-Date (Pe-Date (Pe-Lamp Efficacy Lamp Lamp Lamp Efficacy Lamp Lamp Efficacy riod of riod of riod of (LPW) (LPW) Wattage (LPW) Wattage Wattage Months) Months) Months) 116–155 67-85 12.5 14.5 36 40-50 10.5 36 156-205 15.0 36 86–115 51-66 11.0 36 14.0 36

"GENERAL SERVICE INCANDESCENT LAMPS

Rated Lumen Ranges	Maximum Rated Watt- age	Min- imum Rated Lifetime	Effective Date
1490–2600	72	1,000 hrs	1/1/2012
1050–1489	53	$1,000~\mathrm{hrs}$	1/1/2013
750–1049	43	1,000 hrs	1/1/2014
310–749	29	1,000 hrs	1/1/2014

"MODIFIED SPECTRUM GENERAL SERVICE INCANDESCENT LAMPS

Rated Lumen Ranges	Maximum Rated Watt- age	Min- imum Rated Lifetime	Effective Date
1118–1950	72	1,000 hrs	1/1/2012
788–1117	53	1,000 hrs	1/1/2013
563–787	43	1,000 hrs	1/1/2014
232–562	29	1,000 hrs	1/1/2014

⁽B) APPLICATION.—

[&]quot;(i) APPLICATION CRITERIA.—This subparagraph applies to each lamp that—

[&]quot;(I) is intended for a general service or general illumination application (whether screw base not defined in ANSI C81.61-2006; incandescent or not):

[&]quot;(II) has a medium screw base or any other

- "(III) is capable of being operated at a voltage at least partially within the range of 110 to 130 volts; and
- "(IV) is manufactured or imported after December 31, 2011.
- "(ii) REQUIREMENT.—For purposes of this paragraph, each lamp described in clause (i) shall have a color rendering index that is greater than or equal to—
- "(I) 80 for nonmodified spectrum lamps; or "(II) 75 for modified spectrum lamps.
- "(C) CANDELABRA INCANDESCENT LAMPS AND INTERMEDIATE BASE INCANDESCENT LAMPS.—
- "(i) CANDELABRA BASE INCANDESCENT LAMPS.—Effective beginning January 1, 2012, a candelabra base incandescent lamp shall not exceed 60 rated watts.
- "(ii) INTERMEDIATE BASE INCANDESCENT LAMPS.—Effective beginning January 1, 2012, an intermediate base incandescent lamp shall not exceed 40 rated watts.
 - "(D) Exemptions.—
- "(i) STATUTORY EXEMPTIONS.—The standards specified in subparagraph (A) shall not apply to the following types of incandescent reflector lamps:
- "(I) Lamps rated at 50 watts or less that are ER30, BR30, BR40, or ER40 lamps.
- "(II) Lamps rated at 65 watts that are BR30. BR40. or ER40 lamps.
- "(III) R20 incandescent reflector lamps rated 45 watts or less.
 - "(ii) Administrative exemptions.—
- "(I) PETITION.—Any person may petition the Secretary for an exemption for a type of general service lamp from the requirements of this subsection.
- "(II) CRITERIA.—The Secretary may grant an exemption under subclause (I) only to the extent that the Secretary finds, after a hearing and opportunity for public comment, that it is not technically feasible to serve a specialized lighting application (such as a military, medical, public safety, or certified historic lighting application) using a lamp that meets the requirements of this subsection
- "(III) ADDITIONAL CRITERION.—To grant an exemption for a product under this clause, the Secretary shall include, as an additional criterion, that the exempted product is unlikely to be used in a general service lighting application.
 - "(E) EXTENSION OF COVERAGE.—
- "(i) PETITION.—Any person may petition the Secretary to establish standards for lamp shapes or bases that are excluded from the definition of general service lamps.
- "(ii) INCREASED SALES OF EXEMPTED LAMPS.—The petition shall include evidence that the availability or sales of exempted incandescent lamps have increased significantly since the date on which the standards on general service incandescent lamps were established.
- "(iii) CRITERIA.—The Secretary shall grant a petition under clause (i) if the Secretary finds that—
- "(I) the petition presents evidence that demonstrates that commercial availability or sales of exempted incandescent lamp types have increased significantly since the standards on general service lamps were established and likely are being widely used in general lighting applications; and
- "(II) significant energy savings could be achieved by covering exempted products, as determined by the Secretary based in part on sales data provided to the Secretary from manufacturers and importers.
- "(iv) NO PRESUMPTION.—The grant of a petition under this subparagraph shall create no presumption with respect to the determination of the Secretary with respect to any criteria under a rulemaking conducted under this section.
- "(v) EXPEDITED PROCEEDING.—If the Secretary grants a petition for a lamp shape or

- base under this subparagraph, the Secretary shall—
- "(I) conduct a rulemaking to determine standards for the exempted lamp shape or base; and
- "(II) complete the rulemaking not later than 18 months after the date on which notice is provided granting the petition.
- "(F) EFFECTIVE DATES.-
- "(i) IN GENERAL.—In this paragraph, except as otherwise provided in a table contained in subparagraph (A) or in clause (ii), the term 'effective date' means the last day of the month specified in the table that follows October 24, 1992.
 - "(ii) SPECIAL EFFECTIVE DATES.—
- "(I) ER, BR, AND BPAR LAMPS.—The standards specified in subparagraph (A) shall apply with respect to ER incandescent reflector lamps, BR incandescent reflector lamps, BPAR incandescent reflector lamps, and similar bulb shapes on and after January 1, 2008, or the date that is 180 days after the date of enactment of the Energy Independence and Security Act of 2007.
- "(II) LAMPS BETWEEN 2.25–2.75 INCHES IN DI-AMETER.—The standards specified in subparagraph (A) shall apply with respect to incandescent reflector lamps with a diameter of more than 2.25 inches, but not more than 2.75 inches, on and after the later of January 1, 2008, or the date that is 180 days after the date of enactment of the Energy Independence and Security Act of 2007.
- "(2) COMPLIANCE WITH EXISTING LAW.—Notwithstanding section 332(a)(5) and section 332(b), it shall not be unlawful for a manufacturer to sell a lamp that is in compliance with the law at the time the lamp was manufactured.
- "(3) RULEMAKING BEFORE OCTOBER 24, 1995.—
 "(A) IN GENERAL.—Not later than 36
 months after October 24, 1992, the Secretary
 shall initiate a rulemaking procedure and
 shall publish a final rule not later than the
 end of the 54-month period beginning on October 24, 1992, to determine whether the
 standards established under paragraph (1)
 should be amended.
- "(B) ADMINISTRATION.—The rule shall contain the amendment, if any, and provide that the amendment shall apply to products manufactured on or after the 36-month period beginning on the date on which the final rule is published.
- "(4) RULEMAKING BEFORE OCTOBER 24, 2000.—
 "(A) IN GENERAL.—Not later than 8 years after October 24, 1992, the Secretary shall initiate a rulemaking procedure and shall publish a final rule not later than 9 years and 6 months after October 24, 1992, to determine whether the standards in effect for fluorescent lamps and incandescent lamps should be amended.
- "(B) ADMINISTRATION.—The rule shall contain the amendment, if any, and provide that the amendment shall apply to products manufactured on or after the 36-month period beginning on the date on which the final rule is published.
- "(5) RULEMAKING FOR ADDITIONAL GENERAL SERVICE FLUORESCENT LAMPS.—
- "(A) IN GENERAL.—Not later than the end of the 24-month period beginning on the date labeling requirements under section 324(a)(2)(C) become effective, the Secretary shall—
- "(i) initiate a rulemaking procedure to determine whether the standards in effect for fluorescent lamps and incandescent lamps should be amended so that the standards would be applicable to additional general service fluorescent lamps; and
- "(ii) publish, not later than 18 months after initiating the rulemaking, a final rule including the amended standards, if any.
- "(B) ADMINISTRATION.—The rule shall provide that the amendment shall apply to

- products manufactured after a date which is 36 months after the date on which the rule is published.
- "(6) STANDARDS FOR GENERAL SERVICE LAMPS.—
- "(A) RULEMAKING BEFORE JANUARY 1, 2014.—
 "(i) IN GENERAL.—Not later than January 1, 2014, the Secretary shall initiate a rulemaking procedure to determine whether—
- "(I) standards in effect for general service lamps should be amended; and
- "(II) the exclusions for certain incandescent lamps should be maintained or discontinued based, in part, on excluded lamp sales collected by the Secretary from manufacturers
 - "(ii) Scope.—The rulemaking—
- "(I) shall not be limited to incandescent lamp technologies; and
- "(II) shall include consideration of a minimum standard of 45 lumens per watt for general service lamps.
- "(iii) AMENDED STANDARDS.—If the Secretary determines that the standards in effect for general service lamps should be amended, the Secretary shall publish a final rule not later than January 1, 2017, with an effective date that is not earlier than 3 years after the date on which the final rule is published
- "(iv) Phased-in effective dates.—The Secretary shall consider phased-in effective dates under this subparagraph after considering—
- "(I) the impact of any amendment on manufacturers, retiring and repurposing existing equipment, stranded investments, labor contracts, workers, and raw materials; and
- "(II) the time needed to work with retailers and lighting designers to revise sales and marketing strategies.
- "(v) BACKSTOP REQUIREMENT.—If the Secretary fails to complete a rulemaking in accordance with clauses (i) through (iv) or if the final rule does not produce savings that are greater than or equal to the savings from a minimum efficacy standard of 45 lumens per watt, effective beginning January 1, 2020, the Secretary shall prohibit the manufacture of any general service lamp that does not meet a minimum efficacy standard of 45 lumens per watt.
- "(vi) STATE PREEMPTION.—Neither section 327(c) nor any other provision of law shall preclude California or Nevada from adopting, effective beginning on or after January 1, 2018—
- "(I) a final rule adopted by the Secretary in accordance with clauses (i) through (iv):
- "(II) if a final rule described in subclause (I) has not been adopted, the backstop requirement under clause (v); or
- "(III) in the case of California, if a final rule described in subclause (I) has not been adopted, any California regulations relating to these covered products adopted pursuant to State statute in effect as of the date of enactment of the Energy Independence and Security Act of 2007.
- "(B) RULEMAKING BEFORE JANUARY 1, 2020.—
 "(i) IN GENERAL.—Not later than January 1, 2020, the Secretary shall initiate a rulemaking procedure to determine whether—
- "(I) standards in effect for general service lamps should be amended; and
- "(II) the exclusions for certain incandescent lamps should be maintained or discontinued based, in part, on excluded lamp sales data collected by the Secretary from manufacturers
- "(ii) Scope.—The rulemaking shall not be limited to incandescent lamp technologies.
- "(iii) AMENDED STANDARDS.—If the Secretary determines that the standards in effect for general service lamps should be amended, the Secretary shall publish a final rule not later than January 1, 2022, with an effective date that is not earlier than 3 years

after the date on which the final rule is published.

- "(iv) Phased-in effective dates.—The Secretary shall consider phased-in effective dates under this subparagraph after consid-
- "(I) the impact of any amendment on manufacturers, retiring and repurposing existing equipment, stranded investments, labor contracts, workers, and raw materials; and
- "(II) the time needed to work with retailers and lighting designers to revise sales and marketing strategies.
 - "(7) FEDERAL ACTIONS.-
- "(A) COMMENTS OF SECRETARY.—
- "(i) IN GENERAL.—With respect to any lamp to which standards are applicable under this subsection or any lamp specified in section 346, the Secretary shall inform any Federal entity proposing actions that would adversely impact the energy consumption or energy efficiency of the lamp of the energy conservation consequences of the action.
- "(ii) CONSIDERATION.—The Federal entity shall carefully consider the comments of the Secretary.
- "(B) AMENDMENT OF STANDARDS.—Notwithstanding section 325(n)(1), the Secretary shall not be prohibited from amending any standard, by rule, to permit increased energy use or to decrease the minimum required energy efficiency of any lamp to which standards are applicable under this subsection if the action is warranted as a result of other Federal action (including restrictions on materials or processes) that would have the effect of either increasing the energy use or decreasing the energy efficiency of the product.
 - "(8) COMPLIANCE —
- "(A) IN GENERAL.—Not later than the date on which standards established pursuant to this subsection become effective, or, with respect to high-intensity discharge lamps covered under section 346, the effective date of standards established pursuant to that section, each manufacturer of a product to which the standards are applicable shall file with the Secretary a laboratory report certifying compliance with the applicable standard for each lamp type.
- "(B) CONTENTS.—The report shall include the lumen output and wattage consumption for each lamp type as an average of measurements taken over the preceding 12-month pe-
- "(C) OTHER LAMP TYPES.—With respect to lamp types that are not manufactured during the 12-month period preceding the date on which the standards become effective, the report shall-
- '(i) be filed with the Secretary not later than the date that is 12 months after the date on which manufacturing is commenced; and
- "(ii) include the lumen output and wattage consumption for each such lamp type as an average of measurements taken during the 12-month period.'
- (13) Section 325(1)(4)(A) of the Energy Poland Conservation Act (42 U.S.C. 6295(1)(4)(A)) amended by (as section 321(a)(3)(B) of the Energy Independence and Security Act of 2007 (121 Stat. 1581)) is amended by striking "only"
- (14) Section 327(b)(1)(B) of the Energy Poland Conservation Act (42 U.S.C. 6297(b)(1)(B)) (as amended by section 321(d)(3)of the Energy Independence and Security Act of 2007 (121 Stat. 1585)) is amended-
- (A) in clause (i), by inserting "and" after the semicolon at the end:
- (B) in clause (ii), by striking "; and" and inserting a period; and
 - (C) by striking clause (iii)
- (15) Section 321(e) of the Energy Independence and Security Act of 2007 (121 Stat. 1586) is amended-

- (A) in the matter preceding paragraph (1), by striking "is amended" and inserting "(as amended by section 306(b)) is amended"; and
- (B) by striking paragraphs (1) and (2) and inserting the following:
- "(1) in paragraph (5), by striking 'or' after the semicolon at the end;
- "(2) in paragraph (6), by striking the period at the end and inserting '; or'; and
- (16) Section 332(a) of the Energy Policy and Conservation Act (42 U.S.C. 6302(a)) (as amended by section 321(e) of the Energy Independence and Security Act of 2007 (121 Stat. 1586)) is amended by redesignating the second paragraph (6) as paragraph (7).
- (17) Section 321(30)(C)(ii) of the Energy Poland Conservation Act (42 U.S.C. 6291(30)(C)(ii)) (as amended by section 322(a)(1)(B) of the Energy Independence and Security Act of 2007 (121 Stat. 1587)) is amended by inserting a period after "40 watts or higher"
- (18) Section 322(b) of the Energy Independence and Security Act of 2007 (121 Stat. 1588)) is amended by striking "6995(i)" and inserting "6295(i)"
- (19) Section 327(c) of the Energy Policy and Conservation Act (42 U.S.C. 6297(c)) (as amended by sections 324(f) of the Energy Independence and Security Act of 2007 (121 Stat. 1594)) is amended-
- (A) in paragraph (6), by striking "or" after the semicolon at the end:
- (B) in paragraph (8)(B), by striking "and" after the semicolon at the end:
 - (C) in paragraph (9)—
- (i) by striking "except that—" and all that follows through "if the Secretary fails to issue" and inserting "except that if the Secretary fails to issue";
- (ii) by redesignating clauses (i) and (ii) as subparagraphs (A) and (B), respectively (and by moving the margins of such subparagraphs 2 ems to the left); and
- (iii) by striking the period at the end and inserting a semicolon; and
- (D) by adding at the end the following:
- "(10) is a regulation for general service lamps that conforms with Federal standards and effective dates;
- "(11) is an energy efficiency standard for general service lamps enacted into law by the State of Nevada prior to December 19, 2007, if the State has not adopted the Federal standards and effective dates pursuant to subsection (b)(1)(B)(ii); or"
- (20) Section 325(b) of the Energy Independence and Security Act of 2007 (121 Stat. 1596)) is amended by striking "6924(c)" and inserting "6294(c)"
- (b) TITLE IV-ENERGY SAVINGS IN BUILD-INGS AND INDUSTRY .- (1) Section 401 of the Energy Independence and Security Act of 2007 (42 U.S.C. 17061) is amended-
- (A) in paragraph (2), by striking "484" and inserting "494"; and
- (B) in paragraph (13), by striking "Agency" and inserting "Administration"
- (2) Section 422 of the Energy Conservation and Production Act (42 U.S.C. 6872) (as amended by section 411(a) of the Energy Independence and Security Act of 2007 (121 Stat. 1600)) is amended by striking 1 of the 2 periods at the end of paragraph (5).
- Section 305(a)(3)(D)(i) of the Energy Conservation and Production Act (42 U.S.C. 6834(a)(3)(D)(i)) (as amended by section 433(a)of the Energy Independence and Security Act of 2007 (121 Stat. 1612)) is amended-
 - (A) in subclause (I)-
- (i) by striking "in fiscal year 2003 (as measured by Commercial Buildings Energy Consumption Survey or Residential Energy Consumption Survey data from the Energy Information Agency" and inserting "as measured by the calendar year 2003 Commercial Buildings Energy Consumption Survey or the calendar year 2005 Residential Energy

- Consumption Survey data from the Energy Information Administration"; and
- (ii) in the table at the end, by striking "Fiscal Year" and inserting "Calendar Year"; and
 - (B) in subclause (II)—
- (i) by striking "(II) Upon petition" and inserting the following:
- "(II) Downward adjustment of numeric REQUIREMENT.-
 - "(aa) IN GENERAL.—On petition"; and
- (ii) by striking the last sentence and inserting the following:
- "(bb) Exceptions to requirement for con-
- CURRENCE OF SECRETARY.—
 "(AA) IN GENERAL.—The requirement to petition and obtain the concurrence of the Secretary under this subclause shall not apply to any Federal building with respect to which the Administrator of General Services is required to transmit a prospectus to Congress under section 3307 of title 40, United States Code, or to any other Federal building designed, constructed, or renovated by the Administrator if the Administrator certifies, in writing, that meeting the applicable numeric requirement under subclause (I) with respect to the Federal building would be technically impracticable in light of the specific functional needs for the building.
- '(BB) ADJUSTMENT.-In the case of a building described in subitem (AA), the Administrator may adjust the applicable numeric requirement of subclause (I) downward with respect to the building."
- (4) Section 436(c)(3) of the Energy Independence and Security Act of 2007 (42 U.S.C. 17092(c)(3)) is amended by striking "474" and inserting "494"
- (5) Section 440 of the Energy Independence and Security Act of 2007 (42 U.S.C. 17096) is amended by striking "and 482".
- (6) Section 373(c) of the Energy Policy and Conservation Act (42 U.S.C. 6343(c)) (as amended by section 451(a) of the Energy Independence and Security Act of 2007 (121 Stat. 1628)) is amended by striking "Administrator" and inserting "Secretary
- (c) DATE OF ENACTMENT.—Section 1302 of the Energy Independence and Security Act of 2007 (42 U.S.C. 17382) is amended in the first sentence by striking "enactment" and inserting "the date of enactment of this Act".
- (d) Reference.—Section 1306(c)(3) of the Energy Independence and Security Act of 2007 (42 U.S.C. 17386(c)(3)) is amended by striking "section 1307 (paragraph (17) of section 111(d) of the Public Utility Regulatory Policies Act of 1978)" and inserting "paragraph (19) of section 111(d) of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2621(d))'
- (e) EFFECTIVE DATE.—This section and the amendments made by this section take effect as if included in the Energy Independence and Security Act of 2007 (Public Law 110-140; 121 Stat. 1492).

SEC. 162. TECHNICAL CORRECTIONS TO ENERGY POLICY ACT OF 2005.

- (a) TITLE I—ENERGY EFFICIENCY.—Section 325(g)(8)(C)(ii) of the Energy Policy and Conservation Act (42 U.S.C. 6295(g)(8)(C)(ii)) (as added by section 135(c)(2)(B) of the Energy Policy Act of 2005) is amended by striking "20°F" and inserting "-20°F".
- (b) EFFECTIVE DATE.—This section and the amendments made by this section take effect as if included in the Energy Policy Act of 2005 (Public Law 109-58; 119 Stat. 594).

Subtitle H-Energy and Efficiency Centers and Research

SEC. 171. ENERGY INNOVATION HUBS.

(a) PURPOSE.—The Secretary shall carry out a program to establish Energy Innovation Hubs to enhance the Nation's economic, environmental, and energy security by promoting commercial application of clean, indigenous energy alternatives to oil and other

- fossil fuels, reducing greenhouse gas emissions, and ensuring that the United States maintains a technological lead in the development and commercial application of state-of-the-art energy technologies. To achieve these purposes the program shall—
- (1) leverage the expertise and resources of the university and private research communities, industry, venture capital, national laboratories, and other participants in energy innovation to support cross-disciplinary research and development in areas not being served by the private sector in order to develop and transfer innovative clean energy technologies into the marketplace:
- (2) expand the knowledge base and human capital necessary to transition to a low-carbon economy; and
- (3) promote regional economic development by cultivating clusters of clean energy technology firms, private research organizations, suppliers, and other complementary groups and businesses.
- (b) DEFINITIONS.—For purposes of this section:
- (1) ALLOWANCE.—The term "allowance" means an emission allowance established under section 721 of the Clean Air Act (as added by section 311 of this Act).
- (2) CLEAN ENERGY TECHNOLOGY.—The term "clean energy technology" means a technology that—
- (A) produces energy from solar, wind, geothermal, biomass, tidal, wave, ocean, and other renewable energy resources (as such term is defined in section 610 of the Public Utility Regulatory Policies Act of 1978);
- (B) more efficiently transmits, distributes, or stores energy;
- (C) enhances energy efficiency for buildings and industry, including combined heat and power:
- (D) enables the development of a Smart Grid (as described in section 1301 of the Energy Independence and Security Act of 2007 (42 U.S.C. 17381), including integration of renewable energy resources and distributed generation, demand response, demand side management, and systems analysis;
- (E) produces an advanced or sustainable material with energy or energy efficiency applications;
- (F) enhances water security through improved water management, conservation, distribution, and end use applications; or
- (G) improves energy efficiency for transportation, including electric vehicles.
- (3) CLUSTER.—The term "cluster" means a network of entities directly involved in the research, development, finance, and commercialization of clean energy technologies whose geographic proximity facilitates utilization and sharing of skilled human resources, infrastructure, research facilities, educational and training institutions, venture capital, and input suppliers.
- (4) HUB.—The term "Hub" means an Energy Innovation Hub established in accordance with this section.
- (5) PROJECT.—The term "project" means an activity with respect to which a Hub provides support under subsection (e).
- (6) QUALIFYING ENTITY.—The term "qualifying entity" means each of the following:
- (A) A research university.
- (B) A State or Federal institution with a focus on the advancement of clean energy technologies.
- (C) A nongovernmental organization with research or commercialization expertise in clean energy technology development.
- (7) SECRETARY.—The term "Secretary" means the Secretary of Energy.
- (8) TECHNOLOGY DEVELOPMENT FOCUS.—The term "technology development focus" means the unique technology development areas in which a Hub will specialize, and may include solar electricity, fuels from solar energy,

- batteries and energy storage, electricity grid systems and devices, energy efficient building systems and design, advanced materials, modeling and simulation, and other clean energy technology development areas designated by the Secretary.
- (9) TRANSLATIONAL RESEARCH.—The term "translational research" means coordination of basic or applied research with technical and commercial applications to enable promising discoveries or inventions to attract investment sufficient for market penetration and diffusion.
- (10) VINTAGE YEAR.—The term "vintage year" has the meaning given that term in section 700 of the Clean Air Act (as added by section 312 of this Act).
- (c) ROLE OF THE SECRETARY.—The Secretary shall—
- (1) have ultimate responsibility for, and oversight of, all aspects of the program under this section;
- (2) provide for the distribution of allowances allocated under section 782(h)(1) of the Clean Air Act (as added by section 321 of this Act) to support the establishment of 8 Hubs, each with a unique designated technology development focus, pursuant to this section;
- (3) coordinate the innovation activities of Hubs with those occurring through other Department of Energy entities, including the National Laboratories, the Advanced Research Projects Agency—Energy, and Energy Frontier Research Collaborations, and within industry, including by annually—
- (A) issuing guidance regarding national energy research and development priorities and strategic objectives; and
- (B) convening a conference of staff of the Department of Energy and representatives from such other entities to share research results, program plans, and opportunities for collaboration.
- (d) ENTITIES ELIGIBLE FOR SUPPORT.—A consortium shall be eligible to receive allowances to support the establishment of a Hub under this section if—
 - (1) it is composed of—
- (A) 2 research universities with a combined annual research budget of \$500,000,000; and
- (B) 1 or more additional qualifying entities:
- (2) its members have established a binding agreement that documents—
- (A) the structure of the partnership agreement;
- (B) a governance and management structure to enable cost-effective implementation of the program;
- (C) an intellectual property management policy:
- (D) a conflicts of interest policy consistent with subsection (e)(4);
- (E) an accounting structure that meets the requirements of the Department of Energy and can be audited under subsection (f)(5); and
- (F) that it has an Advisory Board consistent with subsection (e)(3):
- (3) it receives financial contributions from States, consortium participants, or other non-Federal sources, to be used to support project awards pursuant to subsection (e):
- (4) it is part of an existing cluster or demonstrates high potential to develop a new cluster; and
 - (5) it operates as a nonprofit organization.
- (e) ENERGY INNOVATION HUBS.-
- (1) Role.—Hubs receiving allowances under this section shall support translational research activities leading to commercial application of clean energy technologies, in accordance with the purposes of this section, through issuance of awards to projects managed by qualifying entities and other entities meeting the Hub's project criteria, including national laboratories. Each such Hub shall—

- (A) develop and publish for public review and comment proposed plans, programs, project selection criteria, and terms for individual project awards under this subsection:
- (B) submit an annual report to the Secretary summarizing the Hub's activities, organizational expenditures, and Board members, which shall include a certification of compliance with conflict of interest policies and a description of each project in the research portfolio:
 - (C) establish policies—
- (i) regarding intellectual property developed as a result of Hub awards and other forms of technology support that encourage individual ingenuity and invention while speeding technology transfer and facilitating the establishment of rapid commercialization pathways:
- (ii) to prevent resources provided to the Hub from being used to displace private sector investment otherwise likely to occur, including investment from private sector entities that are members of the consortium;
- (iii) to facilitate the participation of private investment firms or other private entities that invest in clean energy technologies to perform due diligence on award proposals, to participate in the award review process, and to provide guidance to projects supported by the Hub: and
- (iv) to facilitate the participation of entrepreneurs with a demonstrated history of developing and commercializing clean energy technologies:
- (D) oversee project solicitations, review proposed projects, and select projects for awards; and
 - (E) monitor project implementation.
- (2) DISTRIBUTION OF AWARDS BY HUBS.—A Hub shall distribute awards under this subsection to support clean energy technology projects conducting translational research and related activities, provided that at least 50 percent of such support shall be provided to projects related to the Hub's technology development focus.
 - (3) Advisory boards.—
- (A) IN GENERAL.—Each Hub shall establish an Advisory Board, the members of which shall have extensive and relevant scientific, technical, industry, financial, or research management expertise. The Advisory Board shall review the Hub's proposed plans, proselection criteria, and grams, project projects and shall ensure that projects selected for awards meet the conflict of interest policies of the Hub. Advisory Board members other than those representing consortium members shall serve for no more than 3 years, All Advisory Board members shall comply with the Hub's conflict of interest policies and procedures.
- (B) MEMBERS.—Each Advisory Board shall consist of—
- (i) 5 members selected by the consortium's research universities:
- (ii) 2 members selected by the consortium's other qualifying entities;
- (iii) 2 members selected at large by other Advisory Board members to represent the entrepreneur and venture capital communities; and
- (iv) 1 member appointed by the Secretary.
 (D) COMPENSATION.—Members of an Advisory Board may receive reimbursement for travel expenses and a reasonable stipend.
 - (4) Conflict of interest.—
- (A) PROCEDURES.—Hubs shall establish procedures to ensure that any employee or consortia designee for Hub activities who serves in a decisionmaking capacity shall—
- (i) disclose any financial interests in, or financial relationships with, applicants for or recipients of awards under this subsection, including those of his or her spouse or minor child, unless such relationships or interests

would be considered to be remote or inconsequential; and

- (ii) recuse himself or herself from any funding decision for projects in which he or she has a personal financial interest.
- (B) DISQUALIFICATION AND REVOCATION.— The Secretary may disqualify an application or revoke allowances distributed to the Hub or awards provided under this subsection, if cognizant officials of the Hub fail to comply with procedures required under subparagraph (A).

 (f) DISTRIBUTION OF ALLOWANCES TO EN-
- (f) DISTRIBUTION OF ALLOWANCES TO ENERGY INNOVATION HUBS.—
- (1) DISTRIBUTION OF ALLOWANCES.—Not later than September 30 of 2011 and each calendar year thereafter through 2049, the Secretary shall, in accordance with the requirements of this section, distribute to eligible consortia allowances allocated for the following vintage year under section 782(h)(1) of the Clean Air Act (as added by section 321 of this Act). Not less than 10 percent and not more than 30 percent of the allowances available for distribution in any given year shall be distributed to support any individual Hub under this section.
- (2) SELECTION AND SCHEDULE.—Allowances to support the establishment of a Hub shall be distributed to eligible consortia (as defined in subsection (d)) selected through a competitive process. Not later than 120 days after the date of enactment of this Act, the Secretary shall solicit proposals from eligible consortia to establish Hubs, which shall be submitted not later than 180 days after the date of enactment of this Act. The Secretary shall select the program consortia not later than 270 days after the date of enactment of this Act. For at least 3 awards to consortia under this section, the Secretary shall give special consideration to applications in which 1 or more of the institutions under subsection (d)(1)(A) are 1890 Land Grant Institutions (as defined in section 2 of the Agricultural Research, Extension, and Education Reform Act of 1998 (7 U.S.C. 7061)), Predominantly Black Institutions (as defined in section 318 of the Higher Education Act of 1965 (20 U.S.C. 1059e)), Tribal Colleges or Universities (as defined in section 316(b) of the Higher Education Act of 1965 (20 U.S.C. 1059c(b)), or Hispanic Serving Institutions (as defined in section 318 of the Higher Education Act of 1965 (20 U.S.C. 1059e)).
- (3) AMOUNT AND TERM OF AWARDS.—For each Hub selected to receive an award under this subsection, the Secretary shall define a quantity of allowances that shall be distributed to such Hub each year for an initial period not to exceed 5 years. The Secretary may extend the term of such award by up to 5 additional years, and a Hub may compete to receive an increase in the quantity of allowances per year that it shall receive during any such extension. A Hub shall be eligible to compete for a new award after the expiration of the term of any award, including any extension of such term, under this subsection
- (4) USE OF ALLOWANCES.—Allowances distributed under this section shall be used exclusively to support project awards pursuant to subsection (e)(1) and (2), provided that a Hub may use not more than 10 percent of the value of such allowances for its administrative expenses related to making such awards. Allowances distributed under this section shall not be used for construction of new buildings or facilities for Hubs, and construction of new buildings or facilities shall not be considered as part of the non-Federal share of a cost sharing agreement under this section.
- (5) AUDIT.—Each Hub shall conduct, in accordance with such requirements as the Secretary may prescribe, an annual audit to determine the extent to which allowances dis-

- tributed to the Hub under this subsection, and awards under subsection (e), have been utilized in a manner consistent with this section. The auditor shall transmit a report of the results of the audit to the Secretary and to the Government Accountability Office. The Secretary shall include such report in an annual report to Congress, along with a plan to remedy any deficiencies cited in the report. The Government Accountability Office may review such audits as appropriate and shall have full access to the books, records, and personnel of the Hub to ensure that allowances distributed to the Hub under this subsection, and awards made under subsection (e), have been utilized in a manner consistent with this section.
- (6) REVOCATION OF ALLOWANCES.—The Secretary shall have authority to review awards made under this subsection and to revoke such awards if the Secretary determines that a Hub has used the award in a manner not consistent with the requirements of this section.

SEC. 172. ADVANCED ENERGY RESEARCH.

- (a) Definitions.—For purposes of this section:
- (1) ALLOWANCE.—The term "allowance" means an emission allowance established under section 721 of the Clean Air Act (as added by section 311 of this Act).
- (2) DIRECTOR.—The term "Director" means Director of the Advanced Research Projects Agency-Energy.
- (b) IN GENERAL.—Not later than September 30 of 2011 and each calendar year thereafter through 2049, the Director shall distribute allowances allocated for the following vintage year under section 782(h)(2) of the Clean Air Act (as added by section 321 of this Act). Such allowances shall be distributed on a competitive basis to institutions of higher education, companies, research foundations, trade and industry research collaborations, or consortia of such entities, or other appropriate research and development entities to achieve the goals of the Advanced Research Projects Agency-Energy (as described in section 5012(c) of the America COMPETES Act) through targeted acceleration of-
- (1) novel early-stage energy research with possible technology applications;
- (2) development of techniques, processes, and technologies, and related testing and evaluation;
- (3) development of manufacturing processes for technologies; and
- (4) demonstration and coordination with nongovernmental entities for commercial applications of technologies and research applications
- (c) RESPONSIBILITIES.—The Director shall be responsible for assessing the success of programs and terminating programs carried out under this section that are not achieving the goals of the programs, consistent with 5012(e)(2) and (4) of the America COMPETES Act. The Director shall designate program managers whose responsibilities are consistent with 5012(f)(1)(B) of the America COMPETES Act. The Director's reporting and coordination requirements established through 5012(g) and (h) of the America COMPETES Act shall apply to activities funded through this section.
- (d) SUPPLEMENT NOT SUPPLANT.—Assistance provided under this section shall be used to supplement, and not to supplant, any other Federal resources available to carry out activities described in this section.

SEC. 173. BUILDING ASSESSMENT CENTERS.

(a) IN GENERAL.—The Secretary of Energy (in this section referred to as the "Secretary") shall provide funding to institutions of higher education for Building Assessment Centers to—

- (1) identify opportunities for optimizing energy efficiency and environmental performance in existing buildings;
- (2) promote high-efficiency building construction techniques and materials options;
- (3) promote applications of emerging concepts and technologies in commercial and institutional buildings;
- (4) train engineers, architects, building scientists, and building technicians in energy-efficient design and operation;
- (5) assist local community colleges, trade schools, registered apprenticeship programs and other accredited training programs in training building technicians;
- (6) promote research and development for the use of alternative energy sources to supply heat and power, for buildings, particularly energy-intensive buildings; and
- (7) coordinate with and assist State-accredited technical training centers and community colleges, while ensuring appropriate services to all regions of the United States.
- (b) COORDINATION WITH REGIONAL CENTERS FOR ENERGY AND ENVIRONMENTAL KNOWLEDGE AND OUTREACH.—A Building Assessment Center may serve as a Center for Energy and Environmental Knowledge and Outreach established pursuant to section 174
- (c) COORDINATION AND DUPLICATION.—The Secretary shall coordinate efforts under this section with other programs of the Department of Energy and other Federal agencies to avoid duplication of effort.
- (d) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to the Secretary to carry out this section \$50,000,000 for fiscal year 2010 and each fiscal year thereafter.

SEC. 174. CENTERS FOR ENERGY AND ENVIRON-MENTAL KNOWLEDGE AND OUT-REACH.

- (a) REGIONAL CENTERS FOR ENERGY AND ENVIRONMENTAL KNOWLEDGE AND OUTREACH.—
- (1) ESTABLISHMENT.—The Secretary shall establish not more than 10 regional Centers for Energy and Environmental Knowledge and Outreach at institutions of higher education to coordinate with and advise industrial research and assessment centers, Building Assessment Centers, and Clean Energy Application Centers located in the region of such Center for Energy and Environmental Knowledge and Outreach.
- (2) TECHNICAL ASSISTANCE PROGRAMS.— Each Center for Energy and Environmental Knowledge and Outreach shall consist of at least one, new or existing, high performing, of the following:
- $\left(A\right)$ An industrial research and assessment center.
- (B) A Clean Energy Application Center.
- (C) A Building Assessment Center.
- (3) SELECTION CRITERIA.—The Secretary shall select Centers for Energy and Environmental Knowledge and Outreach through a competitive process, based on the following:
- (A) Identification of the highest performing industrial research and assessment centers, Clean Energy Application Centers, and Building Assessment Centers.
- (B) The degree to which an institution of higher education maintains credibility among regional private sector organizations such as trade associations, engineering associations, and environmental organizations.
- (C) The degree to which an institution of higher education is providing or has provided technical assistance, academic leadership, and market leadership in the energy arena in a manner that is consistent with the areas of focus of industrial research and assessment centers, Clean Energy Application Centers, and Building Assessment Centers.
- (D) The presence of an additional industrial research and assessment center, Clean

Energy Application Center, or Building Assessment Center at the institution of higher education.

- (4) Geographic diversity.—In selecting Centers for Energy and Environmental Knowledge and Outreach under this subsection, the Secretary shall ensure such Centers are distributed geographically in a relatively uniform manner to ensure all regions of the Nation are represented.
- (5) REGIONAL LEADERSHIP.—Each Center for Energy and Environmental Knowledge and Outreach shall, to the extent possible, provide leadership to all other industrial research and assessment centers, Clean Energy Application Centers, and Building Assessment Centers located in the Center's geographic region, as determined by the Secretary, Such leadership shall include—
- (A) developing regional goals specific to the purview of the industrial research and assessment centers, Clean Energy Application Centers, and Building Assessment Centers programs:
- (B) developing regionally specific technical resources; and
- (C) outreach to interested parties in the region to inform them of the information, resources, and services available through the associated industrial research and assessment centers, Clean Energy Application Centers, and Building Assessment Centers.
- (6) FURTHER COORDINATION.—To increase the value and capabilities of the regionally associated industrial research and assessment centers, Clean Energy Application Centers, and Building Assessment Centers programs, Centers for Energy and Environmental Knowledge and Outreach shall—
- (A) coordinate with Manufacturing Extension Partnership Centers of the National Institute of Science and Technology;
- (B) coordinate with the relevant programs in the Department of Energy, including the Building Technology Program and Industrial Technologies Program:
- (C) increase partnerships with the National Laboratories of the Department of Energy to leverage the expertise and technologies of the National Laboratories to achieve the goals of the industrial research and assessment centers, Clean Energy Application Centers. and Building Assessment Centers:
- (D) work with relevant municipal, county, and State economic development entities to leverage relevant financial incentives for capital investment and other policy tools for the protection and growth of local business and industry:
- (E) partner with local professional and private trade associations and business development interests to leverage existing knowledge of local business challenges and opportunities:
- (F) work with energy utilities and other administrators of publicly funded energy programs to leverage existing energy efficiency and clean energy programs;
- (G) identify opportunities for reducing greenhouse gas emissions; and
- (H) promote sustainable business practices for those served by the industrial research and assessment centers, Clean Energy Application Centers, and Building Assessment Centers.
- (7) WORKFORCE TRAINING.—
- (A) IN GENERAL.—The Secretary shall require each Center for Energy and Environmental Knowledge and Outreach to establish or maintain an internship program for the region of such Center, designed to encourage students who perform energy assessments to continue working with a particular company, building, or facility to help implement the recommendations contained in any such assessment provided to such company, building, or facility. Each Center for Energy and Environmental Knowledge and Outreach

- shall act as internship coordinator to help match students to available opportunities.
- (B) FEDERAL SHARE.—The Federal share of the cost of carrying out internship programs described under subparagraph (A) shall be 50 percent.
- (C) FUNDING.—Subject to the availability of appropriations, of the funds made available to carry out this subsection, the Secretary shall use to carry out this paragraph not less than \$5,000,000 for fiscal year 2010 and each fiscal year thereafter.
- (8) SMALL BUSINESS LOANS.—The Administrator of the Small Business Administration shall, to the maximum practicable, expedite consideration of applications from eligible small business concerns for loans under the Small Business Act (15 U.S.C. 631 et seq.) for loans to implement recommendations of any industrial research and assessment center, Clean Energy Application Center, or Building Assessment Center.
 - (9) DEFINITIONS.—In this subsection:
- (A) INDUSTRIAL RESEARCH AND ASSESSMENT CENTER.—The term "industrial research and assessment center" means a center established or maintained pursuant to section 452(e) of the Energy Independence and Security Act of 2007 (42 U.S.C. 17111(e)).
- (B) CLEAN ENERGY APPLICATION CENTER.— The term "Clean Energy Application Center" means a center redesignated and described section under section 375 of the Energy Policy and Conservation Act (42 U.S.C. 6345)
- (C) BUILDING ASSESSMENT CENTER.—The term "Building Assessment Center" means an institution of higher education-based center established pursuant to section 173.
- (D) SECRETARY.—The term "Secretary" means the Secretary of Energy.
- (10) FUNDING.—There are authorized to be appropriated to the Secretary to carry out this subsection \$10,000,000 for fiscal year 2010 and each fiscal year thereafter. Subject to the availability of appropriations, of the funds made available to carry out this subsection, the Secretary shall provide to each Center for Energy and Environmental Knowledge and Outreach not less than \$500,000 for fiscal year 2010 and each fiscal year thereafter.
- (b) INTEGRATION OF OTHER TECHNICAL ASSISTANCE PROGRAMS.—
- (1) CLEAN ENERGY APPLICATION CENTERS.— Section 375 of the Energy Policy and Conservation Act (42 U.S.C. 6345) is amended—
- (A) by redesignating subsection (f) as subsection (g); and
- (B) by adding after subsection (e) the following new subsection:
- "(f) COORDINATION WITH CENTERS FOR ENERGY AND ENVIRONMENTAL KNOWLEDGE AND OUTREACH.—A Clean Energy Application Center may serve as a Center for Energy and Environmental Knowledge and Outreach established pursuant to section 174 of the American Clean Energy and Security Act of 2009"
- (2) INDUSTRIAL RESEARCH AND ASSESSMENT CENTERS.—Section 452(e) of the Energy Independence and Security Act of 2007 (42 U.S.C. 17111(e)) is amended—
- (A) by striking "The Secretary" and all that follows through "shall be—" and inserting the following:
- "(1) IN GENERAL.—The Secretary shall provide funding to institution of higher education-based industrial research and assessment centers, whose purposes shall be—";
- (B) by redesignating paragraphs (1) through (5) as subparagraphs (A) through (E), respectively (and by moving the margins of such subparagraphs 2 ems to the right); and
- (C) by adding at the end the following new paragraph:
- "(2) COORDINATION WITH CENTERS FOR ENERGY AND ENVIRONMENTAL KNOWLEDGE AND

- OUTREACH.—An industrial research and assessment center may serve as a Center for Energy and Environmental Knowledge and Outreach established pursuant to section 174 of the American Clean Energy and Security Act of 2009.".
- (c) ADDITIONAL FUNDING FOR CLEAN ENERGY APPLICATION CENTERS.—Subsection (g) of section 375 of the Energy Policy and Conservation Act (42 U.S.C. 6345(f)), as redesignated by subsection (b)(1) of this section, is amended by striking "\$10,000,000 for each of fiscal years 2008 through 2012" and inserting "\$30,000,000 for fiscal year 2010 and each fiscal year thereafter".

SEC. 175. HIGH EFFICIENCY GAS TURBINE RE-SEARCH, DEVELOPMENT, AND DEM-ONSTRATION.

- (a) IN GENERAL.—The Secretary of Energy shall carry out a multiyear, multiphase program of research, development, and technology demonstration to improve the efficiency of gas turbines used in combined cycle power generation systems and to identify the technologies that ultimately will lead to gas turbine combined cycle efficiency of 65 percent.
- (b) PROGRAM ELEMENTS.—The program under this section shall—
- (1) support first-of-a-kind engineering and detailed gas turbine design for utility-scale electric power generation, including—
- (A) high temperature materials, including superalloys, coatings, and ceramics;
 - (B) improved heat transfer capability;
- (C) manufacturing technology required to construct complex three-dimensional geometry parts with improved aerodynamic capability;
- (D) combustion technology to produce higher firing temperature while lowering nitrogen oxide and carbon monoxide emissions per unit of output;
- (E) advanced controls and systems integration:
- (F) advanced high performance compressor technology; and
- (G) validation facilities for the testing of components and subsystems;
- (2) include technology demonstration through component testing, subscale testing, and full scale testing in existing fleets;
- (3) include field demonstrations of the developed technology elements so as to demonstrate technical and economic feasibility; and
- (4) assess overall combined cycle system performance.
- (c) PROGRAM GOALS.—The goals of the multiphase program established under subsection (a) shall be—
 - (1) in phase I—
- (A) to develop the conceptual design of advanced high efficiency gas turbines that can achieve at least 62 percent combined cycle efficiency on a lower heating value basis; and
- (B) to develop and demonstrate the technology required for advanced high efficiency gas turbines that can achieve at least 62 percent combined cycle efficiency on a lower heating value basis; and
- (2) in phase II, to develop the conceptual design for advanced high efficiency gas turbines that can achieve at least 65 percent combined cycle efficiency on a lower heating value basis.

 (d) PROPOSALS.—Within 180 days after the
- date of enactment of this section, the Secretary shall solicit proposals for conducting activities under this section. In selecting proposals, the Secretary shall emphasize—
- (1) the extent to which the proposal will stimulate the creation or increased retention of jobs in the United States; and
- (2) the extent to which the proposal will promote and enhance United States technology leadership.
- (e) COST SHARING.—Section 988 of the Energy Policy Act of 2005 (42 U.S.C. 16352) shall

apply to an award of financial assistance made under this section.

- (f) LIMITS ON PARTICIPATION.—The limits on participation applicable under section 999E of the Energy Policy Act of 2005 (42 U.S.C. 16375) shall apply to financial assistance awarded under this section.
- (g) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to the Secretary for carrying out this section \$65,000,000 for each of fiscal years 2011 through 2014.

Subtitle I—Nuclear and Advanced Technologies

SEC. 181. REVISIONS TO LOAN GUARANTEE PROGRAM AUTHORITY.

- (a) DEFINITION OF CONDITIONAL COMMITMENT.—Section 1701 of the Energy Policy Act of 2005 (42 U.S.C. 16511), as amended by section 130(a) of this Act, is amended by adding after paragraph (7) the following:
- "(8) CONDITIONAL COMMITMENT.—The term 'conditional commitment' means a final term sheet negotiated between the Secretary and a project sponsor or sponsors, which term sheet shall be binding on both parties and become a final loan guarantee agreement if all conditions precedent established in the term sheet, which shall include the acquisition of all necessary permits and licenses, are satisfied."
- (b) SPECIFIC APPROPRIATION OR CONTRIBUTION.—Section 1702 of the Energy Policy Act of 2005 (42 U.S.C. 16512) is amended by striking subsection (b) and inserting the following:
- "(b) Specific Appropriation or Contribution.—
- "(1) IN GENERAL.—No guarantee shall be made unless—
- ``(A) an appropriation for the cost has been made:
- "(B) the Secretary has received from the borrower a payment in full for the cost of the obligation and deposited the payment into the Treasury; or
- "(C) a combination of appropriations or payments from the borrower has been made sufficient to cover the cost of the obligation.
- "(2) LIMITATION.—The source of payments received from a borrower under paragraph (1)(B) shall not be a loan or other debt obligation that is made or guaranteed by the Federal Government.".
- (c) FEES.—Section 1702(h) of the Energy Policy Act of 2005 (42 U.S.C. 16512(h)) is amended by striking paragraph (2) and inserting the following:
- "(2) AVAILABILITY.—Fees collected under this subsection shall—
- "(A) be deposited by the Secretary into a special fund in the Treasury to be known as the 'Incentives For Innovative Technologies Fund': and
- "(B) remain available to the Secretary for expenditure, without further appropriation or fiscal year limitation, for administrative expenses incurred in carrying out this title."
- (d) WAGE RATE REQUIREMENTS.—Section 1702 of the Energy Policy Act of 2005 (42 U.S.C. 16512) is amended by adding at the end the following new subsection:
- "(k) Wage Rate Requirements.—No loan guarantee shall be made under this title unless the borrower has provided to the Secretary reasonable assurances that all laborers and mechanics employed by contractors and subcontractors in the performance of construction work financed in whole or in part by the guaranteed loan will be paid wages at rates not less than those prevailing on projects of a character similar to the contract work in the civil subdivision of the State in which the contract work is to be performed as determined by the Secretary of Labor in accordance with subchapter IV of

chapter 31 of part A of subtitle II of title 40, United States Code. With respect to the labor standards specified in this subsection, the Secretary of Labor shall have the authority and functions set forth in Reorganization Plan Numbered 14 of 1950 (64 Stat. 1267; 5 U.S.C. App.) and section 3145 of title 40. United States Code."

(e) SUBROGATION.—Section 1702(g)(2) of the Energy Policy Act of 2005 (42 U.S.C. 16512(g)(2)) is amended by striking subparagraphs (B) and (C) and inserting the following:

"(B) SUPERIORITY OF RIGHTS.—Except as provided in subparagraph (C), the rights of the Secretary, with respect to any property acquired pursuant to a guarantee or related agreements, shall be superior to the rights of any other person with respect to the property.

"(C) TERMS AND CONDITIONS.—A guarantee agreement shall include such detailed terms and conditions as the Secretary determines appropriate to—

"(i) protect the financial interests of the United States in the case of default;

"(ii) have available all the patents and technology necessary for any person selected, including the Secretary, to complete and operate the project;

"(iii) provide for sharing the proceeds received from the sale of project assets with other creditors or control the disposition of project assets if necessary to protect the financial interests of the United States in the case of default; and

"(iv) provide such lien priority in project assets as necessary to protect the financial interests of the United States in the case of a default.".

SEC. 182, PURPOSE.

The purpose of sections 183 through 189 of this subtitle is to promote the domestic development and deployment of clean energy technologies required for the 21st century through the establishment of a self-sustaining Clean Energy Deployment Administration that will provide for an attractive investment environment through partnership with and support of the private capital market in order to promote access to affordable financing for accelerated and widespread deployment of—

- (1) clean energy technologies;
- (2) advanced or enabling energy infrastructure technologies;
- (3) energy efficiency technologies in residential, commercial, and industrial applications, including end-use efficiency in buildings; and
- (4) manufacturing technologies for any of the technologies or applications described in this section.

SEC. 183. DEFINITIONS.

- In this subtitle:
- (1) ADMINISTRATION.—The term "Administration" means the Clean Energy Deployment Administration established by section 186.
- (2) ADVISORY COUNCIL.—The term "Advisory Council" means the Energy Technology Advisory Council of the Administration.
- (3) Breakthrough technology.—The term "breakthrough technology" means a clean energy technology that—
- (A) presents a significant opportunity to advance the goals developed under section 185, as assessed under the methodology established by the Advisory Council; but
- (B) has generally not been considered a commercially ready technology as a result of high perceived technology risk or other similar factors.
- (4) CLEAN ENERGY TECHNOLOGY.—The term "clean energy technology" means a technology related to the production, use, transmission, storage, control, or conservation of energy—

- (A) that will contribute to a stabilization of atmospheric greenhouse gas concentrations thorough reduction, avoidance, or sequestration of energy-related emissions and—
- (i) reduce the need for additional energy supplies by using existing energy supplies with greater efficiency or by transmitting, distributing, or transporting energy with greater effectiveness through the infrastructure of the United States; or
- (ii) diversify the sources of energy supply of the United States to strengthen energy security and to increase supplies with a favorable balance of environmental effects if the entire technology system is considered; and
- (B) for which, as determined by the Administrator, insufficient commercial lending is available at affordable rates to allow for widespread deployment.
- (5) COST.—The term "cost" has the meaning given the term in section 502 of the Federal Credit Reform Act of 1990 (2 U.S.C. 661a).
- (6) DIRECT LOAN.—The term "direct loan" has the meaning given the term in section 502 of the Federal Credit Reform Act of 1990 (2 U.S.C. 661a).
- (7) FUND.—The term "Fund" means the Clean Energy Investment Fund established by section 184(a).
- (8) GREEN BONDS.—The term "Green Bonds" means bonds issued pursuant to section 184.
- (8) LOAN GUARANTEE.—The term "loan guarantee" has the meaning given the term in section 502 of the Federal Credit Reform Act of 1990 (2 U.S.C. 661a).
- (9) NATIONAL LABORATORY.—The term "National Laboratory" has the meaning given the term in section 2 of the Energy Policy Act of 2005 (42 U.S.C. 15801).
- (10) SECRETARY.—The term "Secretary" means the Secretary of Energy.
- (11) STATE.—The term "State" means—
- (A) a State;
- (B) the District of Columbia;
- (C) the Commonwealth of Puerto Rico; and (D) any other territory or possession of the United States.
- (12) TECHNOLOGY RISK.—The term "technology risk" means the risks during construction or operation associated with the design, development, and deployment of clean energy technologies (including the cost, schedule, performance, reliability and maintenance, and accounting for the perceived risk), from the perspective of commercial lenders, that may be increased as a result of the absence of adequate historical construction, operating, or performance data from commercial applications of the technology.

SEC. 184. CLEAN ENERGY INVESTMENT FUND.

- (a) ESTABLISHMENT.—There is established in the Treasury of the United States a revolving fund, to be known as the "Clean Energy Investment Fund", consisting of—
- (1) such amounts as are deposited in the Fund under this subtitle; and
- (2) such sums as may be appropriated to supplement the Fund.
- (b) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to the Fund such sums as are necessary to carry out this subtitle.
 - (c) EXPENDITURES FROM FUND.—
- (1) IN GENERAL.—Amounts in the Fund shall be available to the Administrator of the Administration for obligation without fiscal year limitation, to remain available until expended.
 - (2) ADMINISTRATIVE EXPENSES.—
- (A) FEES.—Fees collected for administrative expenses shall be available without limitation to cover applicable expenses.
- (B) FUND.—To the extent that administrative expenses are not reimbursed through

fees, an amount not to exceed 1.5 percent of the amounts in the Fund as of the beginning of each fiscal year shall be available to pay the administrative expenses for the fiscal year necessary to carry out this subtitle.

- (d) Transfers of Amounts.—
- (1) IN GENERAL.—The amounts required to be transferred to the Fund under this section shall be transferred at least monthly from the general fund of the Treasury to the Fund on the basis of estimates made by the Secretary of the Treasury.
- (2) ADJUSTMENTS.—Proper adjustment shall be made in amounts subsequently transferred to the extent prior estimates were in excess of or less than the amounts required to be transferred.
- (3) CASH FLOWS.—Cash flows associated with costs of the Fund described in section 502(5)(B) of the Federal Credit Reform Act of 1990 (2 U.S.C. 661a(5)(B)) shall be transferred to appropriate credit accounts.
 - (e) Green Bonds.-
- (1) INITIAL CAPITALIZATION.—The Secretary of the Treasury shall issue Green Bonds in the amount of \$7,500,000,000 on the credit of the United States to acquire capital stock of the Administration. Stock certificates evidencing ownership in the Administration shall be issued by the Administration to the Secretary of the Treasury, to the extent of payments made for the capital stock of the Administration.
- (2) DENOMINATIONS AND MATURITY.—Green Bonds shall be in such forms and denominations, and shall mature within such periods, as determined by the Secretary of the Treasury.
- (3) INTEREST.—Green Bonds shall bear interest at a rate not less than the current average yield on outstanding market obligations of the United States of comparable maturity during the month preceding the issuance of the obligation as determined by the Secretary of the Treasury.
- (4) LAWFUL INVESTMENTS.—Green Bonds shall be lawful investments, and may be accepted as security for all fiduciary, trust, and public funds, the investment or deposit of which shall be under the authority or control of the United States or any officer or officers thereof.

SEC. 185. ENERGY TECHNOLOGY DEPLOYMENT GOALS.

- (a) Goals.—Not later than 1 year after the date of enactment of this Act, the Secretary, after consultation with the Advisory Council, shall develop and publish for review and comment in the Federal Register recommended near-, medium-, and long-term goals (including numerical performance targets at appropriate intervals to measure progress toward those goals) for the deployment of clean energy technologies through the credit support programs established by section 187 to promote—
- (1) sufficient electric generating capacity using clean energy technologies to meet the energy needs of the United States;
- (2) clean energy technologies in vehicles and fuels that will substantially reduce the reliance of the United States on foreign sources of energy and insulate consumers from the volatility of world energy markets;
- (3) a domestic commercialization and manufacturing capacity that will establish the United States as a world leader in clean energy technologies across multiple sectors;
- (4) installation of sufficient infrastructure to allow for the cost-effective deployment of clean energy technologies appropriate to each region of the United States;
- (5) the transformation of the building stock of the United States to zero net energy consumption;
- (6) the recovery, use, and prevention of waste energy;

- (7) domestic manufacturing of clean energy technologies on a scale that is sufficient to achieve price parity with conventional energy sources:
- (8) domestic production of commodities and materials (such as steel, chemicals, polymers, and cement) using clean energy technologies so that the United States will become a world leader in environmentally sustainable production of the commodities and materials;
- (9) a robust, efficient, and interactive electricity transmission grid that will allow for the incorporation of clean energy technologies, distributed generation, and demand-response in each regional electric grid;
- (10) sufficient availability of financial products to allow owners and users of residential, retail, commercial, and industrial buildings to make energy efficiency and distributed generation technology investments with reasonable payback periods; and
- (11) sufficient availability of financial services and support to small businesses developing and deploying clean energy technologies through partnerships with private entities that have relevant creidt expertise; and
- (12) such other goals as the Secretary, in consultation with the Advisory Council, determines to be consistent with the purpose stated in section 182.
- (b) REVISIONS.—The Secretary shall revise the goals established under subsection (a), from time to time as appropriate, to account for advances in technology and changes in energy policy.

SEC. 186. CLEAN ENERGY DEPLOYMENT ADMINISTRATION.

- (a) ESTABLISHMENT.—
- (1) ESTABLISHMENT OF CORPORATION.—There is established a corporation to be known as the Clean Energy Deployment Administration that shall be wholly owned by the United States.
- (2) INDEPENDENT CORPORATION.—The Administration shall be an independent corporation. Neither the Administration nor any of its functions, powers, or duties shall be transferred to or consolidated with any other department, agency, or corporation of the Government unless the Congress provides otherwise.
- (3) Charter.—The Administration shall be chartered for 20 years from the date of enactment of this section.
- (4) Status.—
- (A) INSPECTOR GENERAL.—Section 12 of the Inspector General Act of 1978 (5 U.S.C. App.) is amended—
- (i) in paragraph (1), by inserting "the Administrator of the Clean Energy Deployment Administration;" after "Export-Import Bank:"; and
- (ii) in paragraph (2), by inserting "the Clean Energy Deployment Administration," after "Export-Import Bank,".
- (3) Offices.—
- (A) PRINCIPAL OFFICE.—The Administration shall— $\,$
- (i) maintain the principal office of the Administration in the national capital region; and
- (ii) for purposes of venue in civil actions, be considered to be a resident of the District of Columbia.
- (B) OTHER OFFICES.—The Administration may establish other offices in such other places as the Administration considers necessary or appropriate for the conduct of the business of the Administration.
 - (b) Administrator.—
- (1) In GENERAL.—The Administrator of the Administration shall be— $\,$
- (A) appointed by the President, with the advice and consent of the Senate, for a 5-year term; and

- (B) compensated at the prevailing rate for compensation for similar positions in industry
- (2) DUTIES.—The Administrator of the Administration shall—
- (A) serve as the Chief Executive Officer of the Administration and Chairman of the Board:
 - (B) ensure that-
- (i) the Administration operates in a safe and sound manner, including maintenance of adequate capital and internal controls (consistent with section 404 of the Sarbanes-Oxley Act of 2002 (15 U.S.C. 7262)):
- (ii) the operations and activities of the Administration foster liquid, efficient, competitive, and resilient energy and energy efficiency finance markets;
- (iii) the Administration carries out the purpose stated in section 182 only through activities that are authorized under and consistent with sections 182 through 189; and
- (iv) the activities of the Administration and the manner in which the Administration is operated are consistent with the public interest:
- (C) develop policies and procedures for the Administration that will— $\,$
- (i) promote a self-sustaining portfolio of investments that will maximize the value of investments to effectively promote clean energy technologies;
- (ii) promote transparency and openness in Administration operations;
- (iii) afford the Administration with sufficient flexibility to meet the purpose stated in section 182; and
- (iv) provide for the efficient processing of applications; and
- (D) with the concurrence of the Board, set expected loss reserves for the support provided by the Administration consistent with section 187(c).
 - (c) Board of Directors.—
- (1) IN GENERAL.—The Board of Directors of the Administration shall consist of—
- (A) the Secretary or the designee of the Secretary, who shall serve as an ex-officio member of the Board of Directors;
- (B) the Secretary of the Treasury or the designee of the Secretary, who shall serve as an ex-officio member of the Board of Directors;
- (C) the Secretary of the Interior or the designee of the Secretary, who shall serve as an ex-officio member of the Board of Directors;
- (D) the Secretary of Agriculture or the designee of the Secretary, who shall serve as an ex officio member of the Board of Directors:
- (E) the Administrator of the Administration, who shall serve as the Chairman of the Board of Directors: and
 - (F) 4 additional members who shall—
- (i) be appointed by the President, with the advice and consent of the Senate, for staggered 5-year terms; and
- (ii) have experience in banking, financial services, technology assessment, energy regulation, or risk management, including individuals with substantial experience in the development of energy projects, the electricity generation sector, the transportation sector, the manufacturing sector, and the energy efficiency sector.
- (2) DUTIES.—The Board of Directors shall—(A) oversee the operations of the Administration and ensure industry best practices are followed in all financial transactions involving the Administration:
- (B) consult with the Administrator of the Administration on the general policies and procedures of the Administration to ensure the interests of the taxpayers are protected;
- (C) ensure the portfolio of investments are consistent with purpose stated in section 182 and with the long-term financial stability of the Administration;

- (D) ensure that the operations and activities of the Administration are consistent with the development of a robust private sector that can provide commercial loans or financing products; and
- (E) not serve on a full-time basis, except that the Board of Directors shall meet at least quarterly to review, as appropriate, applications for credit support and set policies and procedures as necessary.
- (3) REMOVAL.—An appointed member of the Board of Directors may be removed from office by the President for good cause.
- (4) VACANCIES.—An appointed seat on the Board of Directors that becomes vacant shall be filled by appointment by the President, but only for the unexpired portion of the term of the vacating member.
- (5) COMPENSATION OF MEMBERS.—An appointed member of the Board of Directors shall be compensated at the prevailing rate for compensation for similar positions in industry.
- (d) Energy Technology Advisory Council.—
- (1) IN GENERAL.—The Administration shall have an Energy Technology Advisory Council consisting of 8 members selected by the Board of Directors of the Administration.
- (2) QUALIFICATIONS.—The members of the Advisory Council shall—
- (A) have clean energy project development, clean energy finance, commercial, and/or relevant scientific expertise; and
 - (B) include representatives of
 - (i) the academic community;
 - (ii) the private research community:
 - (iii) National Laboratories:
- (iv) the technology or project development community; and
- (v) the commercial energy financing and operations sector.
 - (3) DUTIES.—The Advisory Council shall—
- (A) develop and publish for comment in the Federal Register a methodology for assessment of clean energy technologies that will allow the Administration to evaluate projects based on the progress likely to be achieved per-dollar invested in maximizing the attributes of the definition of clean energy technology, taking into account the extent to which support for a clean energy technology is likely to accrue subsequent benefits that are attributable to a commercial scale deployment taking place earlier than that which otherwise would have occurred without the support; and
- (B) advise on the technological approaches that should be supported by the Administration to meet the technology deployment goals established by the Secretary pursuant to section 185.
- (4) TERM.—
- (A) IN GENERAL.—Members of the Advisory Council shall have 5-year staggered terms, as determined by the Administrator of the Administration.
- (B) REAPPOINTMENT.—A member of the Advisory Council may be reappointed.
- (5) COMPENSATION.—A member of the Advisory Council, who is not otherwise compensated as a Federal employee, shall be compensated at a rate equal to the daily equivalent of the annual rate of basic pay prescribed for level IV of the Executive Schedule under section 5315 of title 5, United States Code, for each day (including travel time) during which the member is engaged in the performance of the duties of the Advisory Council.
 - (e) STAFF.—
- (1) IN GENERAL.—The Administrator of the Administration, in consultation with the Board of Directors, may—
- (A) appoint and terminate such officers, attorneys, employees, and agents as are necessary to carry out this subtitle; and

- (B) vest those personnel with such powers and duties as the Administrator of the Administration may determine.
- (f) CONFLICTS OF INTEREST.—No director, officer, attorney, agent, or employee of the Administration shall in any manner, directly or indirectly, participate in the deliberation upon, or the determination of, any question affecting such individual's personal interests, or the interests of any corporation, partnership, or association in which such individual is directly or indirectly personally interested.
 - (g) Sunset.-
- (1) EXPIRATION OF CHARTER.—The Administration shall continue to exercise its functions until all obligations and commitments of the Administration are discharged, even after its charter has expired.
- (2) PRIOR OBLIGATIONS.—No provisions of this subsection shall be construed as preventing the Administration from—
- (A) undertaking obligations prior to the date of the expiration of its charter which mature subsequent to such date;
- (B) assuming, prior to the date of the expiration of its charter, liability as guarantor, endorser, or acceptor of obligations which mature subsequent to such date; or
- (C) continuing as a corporation and exercising any of its functions subsequent to the date of the expiration of its charter for purposes of orderly liquidation, including the administration of its assets and the collection of any obligations held by the Administration.

SEC. 187. DIRECT SUPPORT.

- (a) IN GENERAL.—The Administration may issue direct loans, letters of credit, and loan guarantees to deploy clean energy technologies if the Administrator of the Administration has determined that deployment of the technologies would benefit or be accelerated by the support.
- (b) ELIGIBLITY CRITERIA.—In carrying out this section and awarding credit support to projects, the Administrator of the Administration shall account for—
- (1) how the technology rates based on an evaluation methodology established by the Advisory Council;
- (2) how the project fits with the goals established under section 185; and
- (3) the potential for the applicant to successfully complete the project.
 - (c) RISK.—
- (1) EXPECTED LOAN LOSS RESERVE.—The Administrator of the Administration shall establish an expected loan loss reserve to account for estimated losses attributable to activities under this section that is consistent with the purposes of—
- (A) developing breakthrough technologies to the point at which technology risk is largely mitigated;
- (B) achieving widespread deployment and advancing the commercial viability of clean energy technologies; and
- (C) advancing the goals established under section 185.
- (2) INITIAL EXPECTED LOAN LOSS RESERVE.— Until such time as the Administrator of the Administration determines sufficient data exist to establish an expected loan loss reserve that is appropriate, the Administrator of the Administration shall consider establishing an initial rate of 10 percent for the portfolio of investments under this subtitle.
- (3) PORTFOLIO INVESTMENT APPROACH.—The Administration shall—
- (A) use a portfolio investment approach to mitigate risk and diversify investments across technologies and ensure that no particular technology is provided more than 30 percent of the financial support available;
- (B) to the maximum extent practicable and consistent with long-term self-sufficiency,

- weigh the portfolio of investments in projects to advance the goals established under section 185;
- (C) consistent with the expected loan loss reserve established under this subsection, the purpose stated in section 182, and section 186(b)(2)(B), provide the maximum practicable percentage of support to promote breakthrough technologies; and
- (D) give the highest priority to investments that promote technologies that will achieve the maximum greenhouse gas emission reductions within a reasonable period of time per dollar invested and the earliest reductions in greenhouse gas emissions.
 - (4) Loss rate review.—
- (A) IN GENERAL.—The Board of Directors shall review on an annual basis the loss rates of the portfolio to determine the adequacy of the reserves.
- (B) REPORT.—Not later than 90 days after the date of the initiation of the review, the Administrator of the Administration shall submit to the Committee on Energy and Natural Resources and the Committee on Finance of the Senate, and the Committee on Energy and Commerce and the Committee on Ways and Means of the House of Representatives a report describing the results of the review and any recommended policy changes.
- (5) FEDERAL COST SHARE.—Direct loans, letters of credit and loan guarantees by the Administration shall not exceed an amount equal to 80 percent of the project cost of the facility that is the subject of the loan, letter of credit or loan guarantee, as estimated at the time at which the loan, letter of credit or loan guarantee is issued.
 - (d) APPLICATION REVIEW.—
- (1) IN GENERAL.—To the maximum extent practicable and consistent with sound business practices, the Administration shall seek to consolidate reviews of applications for credit support under this subtitle such that final decisions on applications can generally be issued not later than 180 days after the date of submission of a completed application.
- (2) Environmental review.—In carrying out this subtitle, the Administration shall, to the maximum extent practicable—
- (A) avoid duplicating efforts that have already been undertaken by other agencies (including State agencies acting under Federal programs); and
- (B) with the advice of the Council on Environmental Quality and any other applicable agencies, use the administrative records of similar reviews conducted throughout the executive branch to develop the most expeditious review process practicable.
 - (e) WAGE RATE REQUIREMENTS.-
- (1) IN GENERAL.—No credit support shall be issued under this section unless the borrower has provided to the Administrator of the Administration reasonable assurances that all laborers and mechanics employed by contractors and subcontractors in the performance of construction work financed in whole or in part by the Administration will be paid wages at rates not less than those prevailing on projects of a character similar to the contract work in the civil subdivision of the State in which the contract work is to be performed as determined by the Secretary of Labor in accordance with subchapter IV of chapter 31 of part A of subtitle II of title 40. United States Code.
- (2) LABOR STANDARDS.—With respect to the labor standards specified in this subsection, the Secretary of Labor shall have the authority and functions set forth in Reorganization Plan Numbered 14 of 1950 (64 Stat. 1267; 5 U.S.C. App.) and section 3145 of title 40, United States Code.
- (f) LIMITATIONS.—(1) The Administration shall not provide direct support as defined

under this section or indirect support as defined under section 188 to an individual clean energy technology project that obtained a loan guarantee under title XVII of the Energy Policy Act of 2005.

(2) No direct or indirect support provided by the Administration may be used to pay any part of the cost of an obligation or a loan guarantee under Title XVII of the Energy Policy Act of 2005.

SEC. 188. INDIRECT SUPPORT.

- (a) IN GENERAL.—For the purpose of enhancing the availability of private financing for clean energy technology deployment, the Administration may—
- (1) provide credit support to portfolios of taxable debt obligations originated by state, local, and private sector entities that enable owners and users of buildings and industrial facilities to—
- (A) significantly increase the energy efficiency of such buildings or facilities; or
- (B) install systems that individually generate electricity from renewable energy resources and have a capacity of no more than 2 megawatts:
- (2) facilitate financing transactions in tax equity markets and long-term purchasing of clean energy by state, local, and non-governmental not-for-profit entities, to the degree and extent that the Administration determines such financing activity is appropriate and consistent with carrying out the purposes described in Section 182 of this Act; and
- (3) provide credit support to portfolios of taxable debt obligations originated by state, local, and private sector entities that enable the deployment of energy storage applications for electric drive vehicles, stationary applications, and electricity transmission and distribution.
- (b) DEFINITIONS.—For purposes of the section:
- (1) CREDIT SUPPORT.—The term "credit support" means—
- (A) direct loans, letters of credit, loan guarantees, and insurance products; and
- (B) the purchase or commitment to purchase, or the sale or commitment to sell, debt instruments (including subordinated securities).
- (2) RENEWABLE ENERGY RESOURCE.—The term "renewable energy resource" shall have the meaning given that term in section 610 of the Public Utility Regulatory Policies Act of 1978 (as added by section 101 of this Act).
- (c) Transparency.—The Administration shall seek to foster through its credit support activities—
- (1) the development and consistent application of standard contractual terms, transparent underwriting standards and consistent measurement and verification protocols, as applicable: and
- (2) the creation of performance data that promotes effective underwriting and risk management to support lending markets and stimulate the development of private investment markets.
- (d) EXEMPT SECURITIES.—All securities insured or guaranteed by the Administration shall, to the same extent as securities that are direct obligations of or obligations guaranteed as to the principal or interest by the United States, be considered to be exempt securities within the meaning of the laws administered by the Securities and Exchange Commission

SEC. 189. FEDERAL CREDIT AUTHORITY.

- (a) PAYMENTS OF LIABILITIES.
- (1) IN GENERAL.—Any payment made to discharge liabilities arising from agreements under this subtitle shall be paid exclusively out of the Fund or the associated credit account, as appropriate.
- (2) SECURITY.—Subject to paragraph (1), the full faith and credit of the United States

- is pledged to the payment of all obligations entered into by the Administration pursuant to this subtitle.
 - (b) FEES.—
- (1) IN GENERAL.—Consistent with achieving the purpose stated in section 182, the Administrator of the Administration shall charge fees or collect compensation generally in accordance with commercial rates.
- (2) AVAILABILITY OF FEES.—All fees collected by the Administration may be retained by the Administration and placed in the Fund and may remain available to the Administration, without further appropriation or fiscal year limitation, for use in carrying out the purpose stated in section 182.
- (3) BREAKTHROUGH TECHNOLOGIES.—The Administration shall charge the minimum amount in fees or compensation practicable for breakthrough technologies, consistent with the long-term viability of the Administration, unless the Administration first determines that a higher charge will not impede the development of the technology.
- (4) ALTERNATIVE FEE ARRANGEMENTS.—The Administration may use such alternative arrangements (such as profit participation, contingent fees, and other valuable contingent interests) as the Administration considers appropriate to compensate the Administration for the expenses of the Administration and the risk inherent in the support of the Administration.
- (c) COST TRANSFER AUTHORITY.—Amounts collected by the Administration for the cost of a loan or loan guarantee shall be transferred by the Administration to the respective credit accounts.

SEC. 190. GENERAL PROVISIONS.

- (a) IMMUNITY FROM IMPAIRMENT, LIMITATION, OR RESTRICTION.—
- (1) In GENERAL.—All rights and remedies of the Administration (including any rights and remedies of the Administration on, under, or with respect to any mortgage or any obligation secured by a mortgage) shall be immune from impairment, limitation, or restriction by or under—
- (A) any law (other than a law enacted by Congress expressly in limitation of this paragraph) that becomes effective after the acquisition by the Administration of the subject or property on, under, or with respect to which the right or remedy arises or exists or would so arise or exist in the absence of the law; or
- (B) any administrative or other action that becomes effective after the acquisition.
- (2) STATE LAW.—The Administrator of the Administration may conduct the business of the Administration without regard to any qualification or law of any State relating to incorporation.
- (b) USE OF OTHER AGENCIES.—With the consent of a department, establishment, or instrumentality (including any field office), the Administration may—
- (1) use and act through any department, establishment, or instrumentality; and
- (2) use, and pay compensation for, information, services, facilities, and personnel of the department, establishment, or instrumentality.
 - (c) FINANCIAL MATTERS.—
- (1) INVESTMENTS.—Funds of the Administration may be invested in such investments as the Board of Directors may prescribe. Earnings from such funds, other than fees collected under section 189, may be spent by the Administration only to such extent or in such amounts as are provided in advance by appropriation Acts.
- (2) FISCAL AGENTS.—Any Federal Reserve bank or any bank as to which at the time of the designation of the bank by the Administrator of the Administration there is outstanding a designation by the Secretary of

- the Treasury as a general or other depository of public money, may be designated by the Administrator of the Administration as a depositary or custodian or as a fiscal or other agent of the Administration.
- (d) PERIODIC REPORTS.—Not later than 1 year after commencement of operation of the Administration and at least biannually thereafter, the Administrator of the Administration shall submit to the Committee on Energy and Natural Resources and the Committee on Finance of the Senate and the Committee on Energy and Commerce and the Committee on Ways and Means of the House of Representatives a report that includes a description of—
- (1) the technologies supported by activities of the Administration and how the activities advance the purpose stated in section 182; and
- (2) the performance of the Administration on meeting the goals established under section 185.
- (g) Audits by the Comptroller General.—
- (1) IN GENERAL.—The programs, activities, receipts, expenditures, and financial transactions of the Administration shall be subject to audit by the Comptroller General of the United States under such rules and regulations as may be prescribed by the Comptroller General.
- (2) Access.—The representatives of the Government Accountability Office shall—
- (A) have access to the personnel and to all books, accounts, documents, records (including electronic records), reports, files, and all other papers, automated data, things, or property belonging to, under the control of, or in use by the Administration, or any agent, representative, attorney, advisor, or consultant retained by the Administration, and necessary to facilitate the audit:
- (B) be afforded full facilities for verifying transactions with the balances or securities held by depositories, fiscal agents, and custodians;
- (C) be authorized to obtain and duplicate any such books, accounts, documents, records, working papers, automated data and files, or other information relevant to the audit without cost to the Comptroller General; and
- (D) have the right of access of the Comptroller General to such information pursuant to section 716(c) of title 31, United States
 - (3) ASSISTANCE AND COST.—
- (A) IN GENERAL.—For the purpose of conducting an audit under this subsection, the Comptroller General may, in the discretion of the Comptroller General, employ by contract, without regard to section 3709 of the Revised Statutes (41 U.S.C. 5), professional services of firms and organizations of certified public accountants for temporary periods or for special purposes.
 - (B) REIMBURSEMENT.—
- (i) IN GENERAL.—On the request of the Comptroller General, the Administration shall reimburse the Government Accountability Office for the full cost of any audit conducted by the Comptroller General under this subsection.
- (ii) Crediting.—Such reimbursements shall—
- (I) be credited to the appropriation account entitled "Salaries and Expenses, Government Accountability Office" at the time at which the payment is received; and
 - (II) remain available until expended.
 - (h) ANNUAL INDEPENDENT AUDITS.—
- (1) IN GENERAL.—The Administrator of the Administration shall— $\,$
- (A) have an annual independent audit made of the financial statements of the Administration by an independent public accountant

in accordance with generally accepted auditing standards; and

- (B) submit to the Secretary and to the Committee on Energy and Natural Resources and the Committee on Finance of the Senate and the Committee on Energy and Commerce and the Committee on Ways and Means of the House the results of the audit.
- (2) CONTENT.—In conducting an audit under this subsection, the independent public accountant shall determine and report on whether the financial statements of the Administration—
- (A) are presented fairly in accordance with generally accepted accounting principles; and
- (B) comply with any disclosure requirements imposed under this subtitle.
 - Financial Reports.—
- (1) In GENERAL.—The Administrator of the Administration shall submit to the Secretary and to the Committee on Energy and Natural Resources and the Committee on Finance of the Senate and the Committee on Energy and Commerce and the Committee on Ways and Means of the House annual and quarterly reports of the financial condition and operations of the Administration, which shall be in such form, contain such information, and be submitted on such dates as the Secretary shall require.
- (2) CONTENTS OF ANNUAL REPORTS.—Each annual report shall include—
- (A) financial statements prepared in accordance with generally accepted accounting principles;
- (B) any supplemental information or alternative presentation that the Secretary may require; and
- (C) an assessment (as of the end of the most recent fiscal year of the Administration), signed by the chief executive officer and chief accounting or financial officer of the Administration, of—
- (i) the effectiveness of the internal control structure and procedures of the Administration; and
- (ii) the compliance of the Administration with applicable safety and soundness laws.
- (3) SPECIAL REPORTS.—The Secretary may require the Administrator of the Administration to submit other reports on the condition (including financial condition), management, activities, or operations of the Administration, as the Secretary considers appropriate.
- (4) ACCURACY.—Each report of financial condition shall contain a declaration by the Administrator of the Administration or any other officer designated by the Board of Directors of the Administration to make the declaration, that the report is true and correct to the best of the knowledge and belief of the officer.
- (5) AVAILABILITY OF REPORTS.—Reports required under this section shall be published and made publicly available as soon as is practicable after receipt by the Secretary.
- (j) SPENDING SAFEGUARDS AND REPORTING.—
 - (1) IN GENERAL.—The Administrator—
- (A) shall require any entity receiving financing support from the Administration to report quarterly, in a format specified by the Administrator, on such entity's use of such support and its progress fulfilling the objectives for which such support was granted, and the Administrator shall make these reports available to the public;
- (B) may establish additional reporting and information requirements for any recipient of financing support from the Administration;
- (C) shall establish appropriate mechanisms to ensure appropriate use and compliance with all terms of any financing support from the Administration;
- (D) shall create and maintain a fully searchable database, accessible on the Inter-

- net (or successor protocol) at no cost to the public, that contains at least—
- (i) a list of each entity that has applied for financing support;
- (ii) a description of each application;
- (iii) the status of each such application;
- (iv) the name of each entity receiving financing support;
- (v) the purpose for which such entity is receiving such financing support;
- (vi) each quarterly report submitted by the entity pursuant to this section; and
- (vii) such other information sufficient to allow the public to understand and monitor the financial support provided by the Administration:
- (E) shall make all financing transactions available for public inspection, including formal annual reviews by both a private auditor and the Comptroller General; and
- (F) shall at all times be available to receive public comment in writing on the activities of the Administration.
- (2) PROTECTION OF CONFIDENTIAL BUSINESS INFORMATION.—To the extent necessary and appropriate, the Administrator may redact any information regarding applicants and borrowers to protect confidential business information.

SEC. 191. CONFORMING AMENDMENTS.

- (a) TAX EXEMPT STATUS.—Subsection (1) of section 501 of the Internal Revenue Code of 1986 is amended by adding at the end the following:
- "(4) The Clean Energy Deployment Administration established under section 186 of the American Clean Energy and Security Act of 2009"
- (b) WHOLLY OWNED GOVERNMENT CORPORA-TION.—Paragraph (3) of section 9101 of title 31, United States Code, is amended by adding at the end the following:
- "(S) the Clean Energy Deployment Administration.".

Subtitle J-Miscellaneous

SEC. 195. INCREASED HYDROELECTRIC GENERATION AT EXISTING FEDERAL FACILITIES

- (a) IN GENERAL.—The Secretary of the Interior, the Secretary of Energy, and the Secretary of the Army shall jointly update the study of the potential for increasing electric power production capability at federally owned or operated water regulation, storage, and conveyance facilities required in section 1834 of the Energy Policy Act of 2005.
- (b) CONTENT.—The update under this section shall include identification and description in detail of each facility that is capable, with or without modification, of producing additional hydroelectric power, including estimation of the existing potential for the facility to generate hydroelectric power.
- (c) REPORT.—The Secretaries shall submit to the Committees on Energy and Commerce, Natural Resources, and Transportation and Infrastructure of the House of Representatives and the Committee on Energy and Natural Resources of the Senate a report on the findings, conclusions, and recommendations of the update of the study under this section by not later than 12 months after the date of enactment of this Act. The report shall include each of the following:
- (1) The identifications, descriptions, and estimations referred to in subsection (b).
- (2) A description of activities currently conducted or considered, or that could be considered, to produce additional hydroelectric power from each identified facility.
- (3) A summary of prior actions taken by the Secretaries to produce additional hydroelectric power from each identified facility.
- (4) The costs to install, upgrade, or modify equipment or take other actions to produce additional hydroelectric power from each

identified facility, and the level of Federal power customer involvement in the determination of such costs.

- (5) The benefits that would be achieved by such installation, upgrade, modification, or other action, including quantified estimates of any additional energy or capacity from each facility identified under subsection (b).
- (6) A description of actions that are planned, underway, or might reasonably be considered to increase hydroelectric power production by replacing turbine runners, by performing generator upgrades or rewinds, or by construction of pumped storage facilities.
- (7) The impact of increased hydroelectric power production on irrigation, water supply, fish, wildlife, Indian tribes, river health, water quality, navigation, recreation, fishing, and flood control.
- (8) Any additional recommendations to increase hydroelectric power production from, and reduce costs and improve efficiency at, federally owned or operated water regulation, storage, and conveyance facilities.

SEC. 196. CLEAN TECHNOLOGY BUSINESS COM-PETITION GRANT PROGRAM.

- (a) IN GENERAL.—The Secretary of Energy is authorized to provide grants to organizations to conduct business competitions that provide incentives, training, and mentorship to entrepreneurs including minority-owned and woman-owned and early stage start-up companies throughout the United States to meet high priority economic, environmental. and energy security goals in areas to include energy efficiency, renewable energy, air quality, water quality and conservation, transportation, smart grid, green building, and waste management. Such competitions shall have the purpose of accelerating the development and deployment of clean technology businesses and green jobs; stimulating green economic development; providing business training and mentoring to early stage clean technology companies; and strengthening the competitiveness of United States clean technology industry in world trade markets. Priority shall be given to business competitions that are private sector led, encourage regional and interregional cooperation, and can demonstrate market-driven practices and show the creation of cost-effective green jobs through an annual publication of competition activities and directory of companies.
- (b) ELIGIBILITY.—An organization eligible for a grant under subsection (a) is—
- (1) any organization described in section 501(c)(3) of the Internal Revenue Code of 1986 and exempt from tax under section 501(a) of such Code; and
- (2) any sponsored entity of an organization described in paragraph (1) that is operated as a nonprofit entity.
- (c) PRIORITY.—In making grants under this section, the Secretary shall give priority to those organizations that can demonstrate broad funding support from private and other non-Federal funding sources to leverage Federal investment.
- (d) AUTHORIZATION OF APPROPRIATIONS.— For the purpose of carrying out this section, there are authorized to be appropriated \$20,000,000.

SEC. 197. NATIONAL BIOENERGY PARTNERSHIP.

- (a) IN GENERAL.—The Secretary of Energy shall establish a National Bioenergy Partnership to provide coordination among programs of State governments, the Federal Government, and the private sector that support the institutional and physical infrastructure necessary to promote the deployment of sustainable biomass fuels and bioenergy technologies for the United States.
- (b) PROGRAM.—The National Bioenergy Partnership shall consist of five regions, to be administered by the CONEG Policy Research Center, the Council of Great Lakes

Governors, the Southern States Energy Board, the Western Governors Association, and the Pacific Regional Biomass Energy Partnership led by the Washington State University Energy Program.

(c) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated for each of fiscal years 2010 through 2014 to carry out this section—

(1) \$5,000,000, to be allocated among the 5 regions described in subsection (b) on the basis of the number of States in each region, for distribution among the member States of that region based on procedures developed by the member States of the region; and

(2) \$2,500,000, to be allocated equally among the 5 regions described in subsection (b) for region-wide activities, including technical assistance and regional studies and coordination.

SEC. 198. OFFICE OF CONSUMER ADVOCACY.

Section 319 of the Federal Power Act is amended to read as follows:

"SEC. 319. OFFICE OF CONSUMER ADVOCACY.

"(a) Office.-

"(1) ESTABLISHMENT.—There is established within the Commission an Office of Consumer Advocacy to serve as an advocate for the public interest. The Office of Administrative Litigation within the Commission shall be incorporated into the Office of Consumer Advocacy.

"(2) DIRECTOR.—The Office shall be headed by a Director to be appointed by the President by and with the advice and consent of the Senate from among individuals who are licensed attorneys admitted to the Bar of any State or of the District of Columbia and who have experience in public utility proceedings.

"(3) DUTIES.—The Office may—

"(A) represent the interests of energy cus-

"(i) on matters before the Commission concerning rates or service of public utilities and natural gas companies under the jurisdiction of the Commission:

"(ii) as amicus curiae, in the review in the courts of the United States of rulings by the Commission in such matters; and

"(iii) as amicus, in hearings and proceedings in other Federal regulatory agencies and commissions related to such matters."

"(B) monitor and review energy customer complaints and grievances on matters concerning rates or service of public utilities and natural gas companies under the jurisdiction of the Commission;

"(C) investigate independently, or within the context of formal proceedings, the services provided by, the rates charged by, and the valuation of the properties of, public utilities and natural gas companies under the jurisdiction of the Commission:

"(D) develop means, such as public dissemination of information, consultative services, and technical assistance, to ensure, to the maximum extent practicable, that the interests of energy consumers are adequately represented in the course of any hearing or proceeding described in subparagraph (A);

"(E) collect data concerning rates or service of public utilities and natural gas companies under the jurisdiction of the Commission; and

 $\lq\lq(F)$ prepare and issue reports and recommendations.

"(4) COMPENSATION AND POWERS.—The Director shall be compensated at Level IV of the Executive Schedule. The Director may—

"(A) employ not more than 25 full-time professional employees at appropriate levels in the GS Scale and such additional support personnel as required; and

 $\mbox{``(B)}$ procure temporary and intermittent services as needed.

"(5) Information from other federal agencies.—The Director may request, from any department, agency, or instrumentality of the United States such information as he deems necessary to carry out his functions under this section. Upon such request, the head of the department, agency, or instrumentality concerned shall, to the extent practicable and authorized by law, provide such information to the Office.

"(b) Consumer Advocacy Advisory Committee.—

"(1) ESTABLISHMENT.—The Director shall establish an advisory committee to be known as Consumer Advocacy Advisory Committee (in this section referred to as the 'Advisory Committee') to review rates, services, and disputes and to make recommendations to the Director.

"(2) Composition.—The Director shall appoint 5 members to the Advisory Committee including—

"(A) 2 individuals representing State utility consumer advocates; and

"(B) 1 individual, from a nongovernmental organization representing consumers.

(3) MEETINGS.—The Advisory Committee shall meet at such frequency as may be required to carry out its duties.

"(4) REPORTS.—The Director shall provide for the publication of recommendations of the Advisory Committee on the public website established for the Office.

"(5) DURATION.—Notwithstanding any other provision of law, the Advisory Committee shall continue in operation during the period for which the Office exists.

"(c) Definitions.—

"(1) ENERGY CUSTOMER.—The term 'energy customer' means a residential customer or a small commercial customer that receives products or services directly or indirectly from a public utility or natural gas company under the jurisdiction of the Commission.

"(2) NATURAL GAS COMPANY.—The term 'natural gas company' has the meaning given the term in section 2 of the Natural Gas Act (15 U.S.C. 717a), as modified by section 601(a) of the Natural Gas Policy Act of 1978 (15 U.S.C. 3431(a)).

"(3) OFFICE.—The term 'Office' means the Office of Consumer Advocacy established under this section.

"(4) PUBLIC UTILITY.—The term 'public utility' has the meaning given the term in section 201(e) of this Act.

"(5) SMALL COMMERCIAL CUSTOMER.—The term 'small commercial customer' means a commercial customer that has a peak demand of not more than 1,000 kilowatts per hour.

"(d) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated such sums as necessary to carry out this section.

"(e) SAVINGS CLAUSE.—Nothing in this section affects the rights or obligations of any State utility consumer advocate.".

SEC. 199. DEVELOPMENT CORPORATION FOR RENEWABLE POWER BORROWING AUTHORITY

(a) DETERMINATION.—No later than 6 months after the date of enactment of this Act, the Secretary of Energy, in coordination with the Secretary of Commerce, shall—

(1) determine any geographic area within the contiguous United States that lacks a Federal power marketing agency;

(2) develop a plan or criteria for the geographic areas identified in paragraph (1) regarding investment in renewable energy and associated infrastructure within an area identified in paragraph (1); and

(3) identify any Federal agency within an area in paragraph (1) that has, or could develop, the ability to facilitate the investment in paragraph (2).

(b) REPORT.—The Secretary of Energy, in coordination with the Secretary of Com-

merce, shall provide the determinations made under subsection (a) to the Committee on Energy and Commerce of the House of Representatives.

(c) ESTABLISHMENT.—Based upon the determinations made pursuant to subsection (a), the Secretary of Energy, in coordination with the Secretary of Commerce, shall recommend to the Committee on Energy and Commerce of the House of Representatives the establishment of any new Federal lending authority, including authorization of additional lending authority for existing Federal agencies, not to exceed \$3,500,000,000 per geographic area identified in subsection (a)(1).

(d) Authorization.—\$25,000,000 is authorized to be appropriated for fiscal year 2010 to carry out the provisions of this section.

SEC. 199A. STUDY.

Not later than February 1, 2011, the Secretary of Energy shall transmit to the Congress a report showing the results of a study on the use of thorium-fueled nuclear reactors for national energy needs. Such report shall include a response to the International Atomic Energy Agency study entitled "Thorium fuel cycle - Potential benefits and challenges" (IAEA-TECDOC-1450).

TITLE II—ENERGY EFFICIENCY Subtitle A—Building Energy Efficiency Programs

SEC. 201. GREATER ENERGY EFFICIENCY IN BUILDING CODES.

Section 304 of the Energy Conservation and Production Act (42 U.S.C. 6833) is amended to read as follows:

"SEC. 304. GREATER ENERGY EFFICIENCY IN BUILDING CODES.

"(a) ENERGY EFFICIENCY TARGETS.—

"(1) IN GENERAL.—Except as provided in paragraph (2) or (3), the national building code energy efficiency target for the national average percentage improvement of a building's energy performance when built to a code meeting the target shall be—

"(A) effective on the date of enactment of the American Clean Energy and Security Act of 2009, 30 percent reduction in energy use relative to a comparable building constructed in compliance with the baseline code:

"(B) effective January 1, 2014, for residential buildings, and January 1, 2015, for commercial buildings, 50 percent reduction in energy use relative to the baseline code; and

"(C) effective January 1, 2017, for residential buildings, and January 1, 2018, for commercial buildings, and every 3 years thereafter, respectively, through January 1, 2029, and January 1, 2030, 5 percent additional reduction in energy use relative to the baseline code.

"(2) CONSENSUS-BASED CODES.—If on any effective date specified in paragraph (1)(A), (B), or (C) a successor code to the baseline codes provides for greater reduction in energy use than is required under paragraph (1), the overall percentage reduction in energy use provided by that successor code shall be the national building code energy efficiency target.

"(3) TARGETS ESTABLISHED BY SECRETARY.—
The Secretary may by rule establish a national building code energy efficiency target for residential or commercial buildings achieving greater reductions in energy use than the targets prescribed in paragraph (1) or (2) if the Secretary determines that such greater reductions in energy use can be achieved with a code that is life cycle costjustified and technically feasible. The Secretary may by rule establish a national building code energy efficiency target for residential or commercial buildings achieving a reduction in energy use that is greater

than zero but less than the targets prescribed in paragraph (1) or (2) if the Secretary determines that such lesser target is the maximum reduction in energy use that can be achieved through a code that is life cycle cost-justified and technically feasible.

"(4) ADDITIONAL REDUCTIONS IN ENERGY USE.—Effective on January 1, 2033, and once every 3 years thereafter, the Secretary shall determine, after notice and opportunity for comment, whether further energy efficiency building code improvements for residential or commercial buildings, respectively, are life cycle cost-justified and technically feasible, and shall establish updated national building code energy efficiency targets that meet such criteria.

"(5) ZERO-NET-ENERGY BUILDINGS.—In setting targets under this subsection, the Secretary shall consider ways to support the deployment of distributed renewable energy technology, and shall seek to achieve the goal of zero-net-energy commercial buildings established in section 422 of the Energy Independence and Security Act of 2007 (42 U.S.C. 17082).

``(6) Baseline code.—For purposes of this section, the term 'baseline code' means—

"(A) for residential buildings, the 2006 International Energy Conservation Code (IECC) published by the International Code Council (ICC); and

"(B) for commercial buildings, the code published in ASHRAE Standard 90.1-2004.

"(7) CONSULTATION.—In establishing the targets required by this section, the Secretary shall consult with the Director of the National Institute of Standards and Technology.

"(b) NATIONAL ENERGY EFFICIENCY BUILDING CODES.—

"(1) REQUIREMENT.—

"(A) IN GENERAL.—There shall be established national energy efficiency building codes under this subsection, for residential and commercial buildings, sufficient to meet each of the national building code energy efficiency targets established under subsection (a), not later than the date that is one year after the deadline for establishment of each such target, except that the national energy efficiency building code established to meet the target described in subsection (a)(1)(A) shall be established by not later than 15 months after the effective date of that target.

"(B) EXISTING CODE.—If the Secretary finds prior to the date provided in subparagraph (A) for establishing a national code for any target that one or more energy efficiency building codes published by a recognized developer of national energy codes and standards meet or exceed the established target, the Secretary shall select the code that meets the target with the highest efficiency in the most cost-effective manner, and such code shall be the national energy efficiency building code.

"(C) REQUIREMENT TO ESTABLISH CODE.—If the Secretary does not make a finding under subparagraph (B), the national energy efficiency building code shall be established by rule by the Secretary under paragraph (2).

"(2) ESTABLISHMENT BY SECRETARY.—

"(A) PROCEDURE.—In order to establish a national energy efficiency building code as required under paragraph (1)(C), the Secretary shall—

"(i) not later than six months prior to the effective date for each target, review existing and proposed codes published or under review by recognized developers of national energy codes and standards;

"(ii) determine the percentage of energy efficiency improvements that are or would be achieved in such published or proposed code versions relative to the target;

"(iii) propose improvements to such published or proposed code versions sufficient to meet or exceed the target; and

"(iv) unless a finding is made under paragraph (1)(B) with respect to a code published by a recognized developer of national energy codes and standards, adopt a code that meets or exceeds the relevant national building code energy efficiency target by not later than one year after the effective date of each such target, and by not later than 15 months after the target is established under subsection (a)(1)(A).

"(B) CALCULATIONS.—Each national energy efficiency building code established by the Secretary under this paragraph shall be set at the maximum level the Secretary determines is life cycle cost-justified and technically feasible, in accordance with the following:

"(i) SAVINGS CALCULATIONS.—Calculations of energy savings shall take into account the typical lifetimes of different products, measures, and system configurations.

"(ii) Cost-effectiveness calculations of life cycle cost-effectiveness shall be based on life cycle cost methods and procedures under section 544 of the National Energy Conservation Policy Act (42 U.S.C. 8254), but shall incorporate to the extent feasible externalities such as impacts on climate change and on peak energy demand that are not already incorporated in assumed energy costs.

"(C) CONSIDERATIONS.—In developing a national energy efficiency building code under this paragraph, the Secretary shall consider—

"(i) for residential national energy efficiency building codes—

"(I) residential building standards published or proposed by ASHRAE;

"(II) building codes published or proposed by the International Code Council (ICC);

"(III) data from the Residential Energy Services Network (RESNET) on compliance measures utilized by consumers to qualify for the residential energy efficiency tax credits established under the Energy Policy Act of 2005:

"(IV) data and information from the Department of Energy's Building America Program:

"(V) data and information from the Energy Star New Homes program;

"(VI) data and information from the New Building Institute and similar organizations;

"(VII) standards for practices and materials to achieve cool roofs in residential buildings, taking into consideration reduced air conditioning energy use as a function of cool roofs, the potential reduction in global warming from increased solar reflectance from buildings, and cool roofs criteria in State and local building codes and in national and local voluntary programs, without reduction of otherwise applicable ceiling insulation standards; and

"(ii) for commercial national energy efficiency building codes—

"(I) commercial building standards proposed by ASHRAE;

"(II) building codes proposed by the International Code Council (ICC);

"(III) the Core Performance Criteria published by the New Buildings Institute;

"(IV) data and information developed by the Director of the Commercial High-Performance Green Building Office of the Department of Energy and any public-private partnerships established under that Office;

"(V) data and information from the Energy Star for Buildings program;

"(VI) data and information from the New Building Institute, RESNET, and similar organizations; and "(VII) standards for practices and materials to achieve cool roofs in commercial buildings, taking into consideration reduced air conditioning energy use as a function of cool roofs, the potential reduction in global warming from increased solar reflectance from buildings, and cool roofs criteria in State and local building codes and in national and local voluntary programs, without reduction of otherwise applicable ceiling insulation standards.

"(D) CONSULTATION.—In establishing any national energy efficiency building code required by this section, the Secretary shall consult with the Director of the National Institute of Standards and Technology.

"(3) Consensus standard assistance.—(A) To support the development of consensus standards that may provide the basis for national energy efficiency building codes, miniduplication of effort, mize encourage progress through consensus, and facilitate the development of greater building efficiency, the Secretary shall provide assistance to recognized developers of national energy codes and standards to develop, and where the relevant code has been adopted as the national code, disseminate consensus based energy efficiency building codes as provided in this paragraph.

"(B) Upon a finding by the Secretary that a code developed by such a developer meets a target established under subsection (a), the Secretary shall—

"(i) send notice of the Secretary's finding to all duly authorized or appointed State, tribal, and local code agencies; and

"(ii) provide sufficient support to such a developer to make the code available on the Internet, or to accomplish distribution of such code to all such State, tribal, and local code agencies at no cost to the State, tribal, and local code agencies

"(C) The Secretary may contract with such a developer and with other organizations with expertise on codes to provide training for State, tribal, and local code officials and building inspectors in the implementation and enforcement of such code.

"(D) The Secretary may provide grants and other support to such a developer to—

"(i) develop appropriate refinements to such code: and

"(ii) support analysis of options for improvements in the code to meet the next scheduled target.

"(4) CODE DEVELOPED BY SECRETARY.—If the Secretary establishes a national energy efficiency building code under paragraph (2), the Secretary shall—

"(A) to the extent that such code is based on a prior code developed by a recognized developer of national energy codes and standards, negotiate and provide appropriate compensation to such developer for the use of the code materials that remain in the code established by the Secretary; and

"(B) disseminate the national energy efficiency building codes to State, tribal, and local code officials, and support training and provide guidance and technical assistance to such officials as appropriate.

"(c) STATE ADOPTION OF ENERGY EFFI-CIENCY BUILDING CODES.—

"(1) REQUIREMENT.—Not later than 1 year after a national energy efficiency building code for residential or commercial buildings is established or revised under subsection (b), each State—

"(A) shall—

"(i) review and update the provisions of its building code regarding energy efficiency to meet or exceed the target met in the new national energy efficiency building code, to achieve equivalent or greater energy savings;

"(ii) document, where local governments establish building codes, that local governments representing not less than 80 percent of the State's urban population have adopted the new national code, or have adopted local codes that meet or exceed the target met in the new national code to achieve equivalent or greater energy savings; or

'(iii) adopt the new national code; and

"(B) shall provide a certification to the Secretary demonstrating that energy efficiency building code provisions that apply pursuant to subparagraph (A) in that State meet or exceed the target met by the new national code, to achieve equivalent or greater energy savings.

(2) Confirmation.

"(A) REQUIREMENT.—Not later than 90 days after a State certification is provided under paragraph (1)(B), the Secretary shall determine whether the State's energy efficiency building code provisions meet the requirements of this subsection.

"(B) ACCEPTANCE BY SECRETARY.—If the Secretary determines under subparagraph (A) that the State's energy efficiency building code or codes meet the requirements of this subsection, the Secretary shall accept the certification.

"(C) Deficiency Notice.—If the Secretary determines under subparagraph (A) that the State's building code or codes do not meet the requirements of this subsection, the Secretary shall identify the deficiency in meeting the national building code energy efficiency target, and, to the extent possible, indicate areas where further improvement in the State's code provisions would allow the deficiency to be eliminated.

"(D) REVISION OF CODE AND RECERTIFI-CATION.—A State may revise its code or codes and submit a recertification under paragraph (1)(B) to the Secretary at any time.

"(3) COMPLIANT CODE.—For the purposes of meeting the target described in subsection (a)(1)(A) for residential buildings, a State that adopts the code represented in California's Title 24-2009 by the date 27 months after the date of enactment of the American Clean Energy and Security Act of 2009 shall be considered to have met the requirements of this subsection for the applicable period.

'(d) APPLICATION OF NATIONAL CODE TO STATE AND LOCAL JURISDICTIONS.-

(1) IN GENERAL.—Upon the expiration of 18 months after a national energy efficiency building code is established under subsection (b), in any jurisdiction where the State has not had a certification relating to that code accepted by the Secretary under subsection (c)(2)(B), and the local government has not had a certification relating to that code accepted by the Secretary under subsection (e)(5), the national energy efficiency building code shall become the applicable energy efficiency building code for such jurisdiction.

"(2) CONFLICTS.—In the event of a conflict between a provision of the national energy efficiency building code and a provision of other applicable energy codes, the national energy efficiency building code shall apply. If there is a conflict between a provision of the national energy efficiency building code and a provision of any applicable fire code, life safety code, egress code, or accessibility code, the Secretary shall take appropriate actions to resolve such conflict in a manner that does not compromise the objectives of such codes.

"(3) STATE LEGISLATIVE ADOPTION.—In a State in which the relevant building energy code is adopted legislatively, the deadline in paragraph (1) shall not be earlier than 1 year after the first day that the legislature meets following establishment of a national energy efficiency building code.

"(4) NOTICE OF INTENT TO ENFORCE.—A State or locality that enforces building codes may assume responsibility for enforcing the national energy efficiency building code by notifying the Secretary to that effect not later than three months after the date established under paragraph (1).

"(5) VIOLATIONS.—Violations of this section shall be defined as follows:

"(A) If the building is subject to the requirements of a State energy efficiency building code with respect to which a certification has been accepted by the Secretary under subsection (c)(2)(B) or a local energy efficiency building code with respect to which a certification has been accepted by the Secretary pursuant to subsection (e)(5), or the requirements of the national energy efficiency building code in a State where the State or locality has notified the Secretary of its intent to enforce the provisions of the national energy efficiency building code, a violation shall be determined pursuant to the relevant provisions of State or local law.

"(B) If the building is subject to the requirements of a national energy efficiency building code made applicable under paragraph (1) of this subsection, except as provided in subparagraph (A), a violation shall be defined by the Secretary pursuant to subsection (g).

'(e) STATE ENFORCEMENT OF ENERGY EFFI-CIENCY BUILDING CODES .-

'(1) IN GENERAL.—Each State, or where applicable under State law each local government, shall implement and enforce applicable State or local codes with respect to which a certification was accepted by the Secretary under subsection (c)(2)(B) or paragraph (5) of this subsection, or the national energy efficiency building codes, as provided in this subsection.

(2) STATE CERTIFICATION.—Not later than 2 years after the date of a certification under subsection (c)(1) or the application of a national energy efficiency building code under subsection (d)(1), each State shall certify that it has-

"(A) achieved compliance with-

"(i) State codes, or, as provided under State law, local codes, with respect to which a certification was accepted by the Secretary under subsection (c)(2)(B); or

"(ii) the national energy efficiency building code, as applicable; or

(B) for any certification submitted within years after the date of enactment of the American Clean Energy and Security Act of 2009, made significant progress achieving such compliance.

"(3) ACHIEVING COMPLIANCE.—A State shall be considered to achieve compliance with a code described in paragraph (2)(A) if at least 90 percent of new and substantially ren-ovated building space in that State in the preceding year upon inspection meets the requirements of the code. A certification under paragraph (2) shall include documentation of the rate of compliance based on-

(A) independent inspections of a random sample of the new and substantially renovated buildings covered by the code in the preceding year; or

"(B) an alternative method that yields an accurate measure of compliance as determined by the Secretary.

"(4) SIGNIFICANT PROGRESS.—A State shall be considered to have made significant progress toward achieving compliance with a code described in paragraph (2)(A) if-

"(A) the State has developed a plan, including for hiring enforcement staff, protraining, providing manuals and checklists, and instituting enforcement programs, designed to achieve full compliance within 5 years after the date of the adoption of the code:

"(B) the State is taking significant, timely, and measurable action to implement that plan;

"(C) the State has not reduced its expenditures for code enforcement; and

"(D) at least 50 percent of new and substantially renovated building space in the State in the preceding year upon inspection meets the requirements of the code.

SECRETARY'S DETERMINATION. later than 90 days after a State certification under paragraph (2), the Secretary shall determine whether the State has demonstrated that it has complied with the requirements of this subsection, including accurate measurement of compliance, or that it has made significant progress toward compliance. If such determination is positive, the Secretary shall accept the certification. If the determination is negative, the Secretary shall identify the areas of deficiency.

(6) OUT OF COMPLIANCE.

"(A) IN GENERAL.—Any State for which the Secretary has not accepted a certification under paragraph (5) by the dates specified in paragraph (2) is out of compliance with this section.

"(B) LOCAL COMPLIANCE.—In any State that is out of compliance with this section as provided in subparagraph (A), a local government may be in compliance with this section by meeting all certification requirements of this subsection.

"(C) NONCOMPLIANCE.—Any State that is not in compliance with this section, as provided in subparagraph (A), shall, until the State regains such compliance, be ineligible to receive-

"(i) emission allowances pursuant to subsection (h)(1);

"(ii) Federal funding in excess of that State's share (calculated according to the allocation formula in section 363 of the Energy Policy and Conservation Act (42 U.S.C. 6323)) of \$125,000,000 each year; and

"(iii) for-

"(I) the first year for which the State is out of compliance, 25 percent of any additional funding or other items of monetary value otherwise provided under the American Clean Energy and Security Act of 2009;

"(II) the second year for which the State is out of compliance, 50 percent of any additional funding or other items of monetary value otherwise provided under the American Clean Energy and Security Act of 2009:

"(III) the third year for which the State is out of compliance, 75 percent of any additional funding or other items of monetary value otherwise provided under the American Clean Energy and Security Act of 2009; and

"(IV) the fourth and subsequent years for which the State is out of compliance, 100 percent of any additional funding or other items of monetary value otherwise provided under the American Clean Energy and Security Act of 2009

"(f) FEDERAL ENFORCEMENT AND TRAIN-ING —Where a State fails and local governments in that State also fail to enforce the applicable State or national energy efficiency building codes, the Secretary shall enforce such codes, as follows:

"(1) The Secretary shall establish, by rule, within 2 years after the date of enactment of the American Clean Energy and Security Act of 2009, an energy efficiency building code enforcement capability.

"(2) Such enforcement capability shall be designed to achieve 90 percent compliance with such code in any State within 1 year after the date of the Secretary's determination that such State is out of compliance with this section.

"(3) The Secretary may set and collect reasonable inspection fees to cover the costs of inspections required for such enforcement. Revenue from fees collected shall be available to the Secretary to carry out the requirements of this section upon appropriation.

- "(4) In any jurisdiction to which this subsection applies, the Secretary shall coordinate enforcement of the national energy efficiency building code with State and local code enforcement of other building codes.
- "(5) In any jurisdiction to which this subsection applies, the Secretary shall enhance compliance by conducting training and education of builders and other professionals in the jurisdiction concerning the national energy efficiency building code.
- "(6) The Secretary shall coordinate with professional organizations representing code officials, architects, engineers, builders, and other experts to develop training curricula concerning the national energy efficiency building code.
- "(7) If the Secretary enforces such codes under this subsection, the Secretary may, as appropriate, redefine violations of such codes.
- "(g) Enforcement Procedures.—The Secretary shall propose and, not later than three years after the date of enactment of the American Clean Energy and Security Act of 2009, shall define by rule violations of the energy efficiency building codes to be enforced by the Secretary pursuant to this section, and the penalties that shall apply to violators, in any jurisdiction in which the national energy efficiency building code has been made applicable under subsection (d)(1). To the extent that the Secretary determines that the authority to adopt and impose such violations and penalties by rule requires further statutory authority, the Secretary shall report such determination to Congress as soon as such determination is made, but not later than one year after the enactment of the American Clean Energy and Security Act
- "(h) FEDERAL SUPPORT.—
- "(1) ALLOWANCE ALLOCATION FOR STATE COMPLIANCE.—For each vintage year from 2012 through 2050, the Administrator shall distribute allowances allocated pursuant to section 782(g)(2) of the Clean Air Act to the SEED Account for each State. Such allowances shall be distributed according to a formula established by the Secretary as follows:
- ``(A) One-fifth in an equal amount to each of the 50 States and United States territories.
- "(B) Two-fifths as a function of the relative energy use in all buildings in each State in the most recent year for which data is available.
- "(C) Two-fifths based on the number of building construction starts recorded in each State, the number of new building permits applied for in each State, or other relevant available data indicating building activity in each State, in the judgment of the Secretary, for the year prior to the year of the distribution.
- "(2) ALLOWANCE ALLOCATION TO LOCAL GOVERNMENTS.—In the instance that the Secretary certifies that one or more local governments are in compliance with this section pursuant to subsection (e)(6)(B), the Administrator shall provide to each such local government the portion of the emission allowances that would have been provided to that State as a function of the population of that State as a whole.
- "(3) UNALLOCATED ALLOWANCES.—To the extent that allowances are not provided to State or local governments for lack of certification in any year, those allowances shall be added to the amount provided to those States and local governments that are certified as eligible in that year.
- "(4) USE OF ALLOWANCES.—Each State or each local government shall use such emission allowances as it receives pursuant to this section exclusively for the purposes of this section, including covering a reasonable

- portion of the costs of the development. adoption, implementation, and enforcement of a State or local energy efficiency building code that meets the national building code energy efficiency targets, or the national energy efficiency building code. In a State where local governments provide substantially all building code enforcement, a minimum of 50 percent of the allowance value received pursuant to this section shall be distributed to local governments as a function of the relative populations of such localities. In a State where local and State governments share building code enforcement duties, the State and local shares of allowance value required for enforcement shall be allocated in proportion to the number of building inspections performed by each level of government, and the share for local governments shall be distributed as a function of the relative populations of such localities. States shall further ensure that the allowance value made available pursuant to section 782 of the Clean Air Act and section 132 of the American Clean Energy and Security Act of 2009 is provided to the applicable State or local governmental entities as necessary to adopt and implement energy efficiency building codes, provide training for inspectors, ensure compliance, and provide such other functions as necessary. Actions taken by local authorities pursuant to this section shall constitute an acceptable use of funds authorized pursuant to the Energy Efficiency and Conservation Block Grant program under section 544 of the Energy Independence and Security Act of 2007 (42 U.S.C. 17154).
- "(i) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to the Secretary of Energy \$25,000,000, and such additional sums as may be necessary to provide enforcement of a national energy efficiency building code, for each of fiscal years 2010 through 2020, and such sums thereafter as may be necessary to support the purposes of this section.
- "(j) Annual Reports by Secretary.—The Secretary shall annually submit to Congress, and publish in the Federal Register, a report on—
- "(1) the status of national energy efficiency building codes:
- "(2) the status of energy efficiency building code adoption and compliance in the States:
- "(3) the implementation of this section;
- "(4) the status of Federal enforcement of building codes, including coordination with State and local enforcement, and the extent and resolution of any conflicts between the national energy efficiency building code and other residential and commercial building codes in force in the same jurisdictions; and
- "(5) impacts of past action under this section, and potential impacts of further action, on lifetime energy use by buildings, including resulting energy and cost savings.".

SEC. 202. BUILDING RETROFIT PROGRAM.

- (a) DEFINITIONS.—For purposes of this section:
- (1) ASSISTED HOUSING.—The term "assisted housing" means those properties receiving project-based assistance pursuant to section 202 of the Housing Act of 1959 (12 U.S.C. 1701q), section 811 of the Cranston-Gonzalez National Affordable Housing Act (42 U.S.C. 8013), section 8 of the United States Housing Act of 1937 (42 U.S.C. 1437f), or similar programs.
- (2) Nonresidential building. The term "nonresidential building" means a building with a primary use or purpose other than residential housing, including any building used for commercial offices, schools, academic and other public and private institutions, nonprofit organizations including

- faith-based organizations, hospitals, hotels, and other nonresidential purposes. Such buildings shall include mixed-use properties used for both residential and nonresidential purposes in which more than half of building floor space is nonresidential.
- (3) PERFORMANCE-BASED BUILDING RETROFIT PROGRAM.—The term "performance-based building retrofit program" means a program that determines building energy efficiency success based on actual measured savings after a retrofit is complete, as evidenced by energy invoices or evaluation protocols.
- (4) PRESCRIPTIVE BUILDING RETROFIT PROGRAM.—The term "prescriptive building retrofit program" means a program that projects building retrofit energy efficiency success based on the known effectiveness of measures prescribed to be included in a retrofit.
- (5) PUBLIC HOUSING.—The term "public housing" means properties receiving assistance under section 9 of the United States Housing Act of 1937 (42 U.S.C. 1437g).
- (6) RECOMMISSIONING; RETROCOMMISSIONING; The terms "recommissioning" and "retrocommissioning" have the meaning given those terms in section 543(f)(1) of the National Energy Conservation Policy Act (42 U.S.C. 8253(f)(1)).
- (7) RESIDENTIAL BUILDING.—The term "residential building" means a building whose primary use is residential. Such buildings shall include single-family homes (both attached and detached), owner-occupied units in larger buildings with their own dedicated space-conditioning systems, apartment buildings, multi-unit condominium buildings, public housing, assisted housing, and buildings used for both residential and non-residential purposes in which more than half of building floor space is residential.
- (8) STATE ENERGY PROGRAM.—The term "State Energy Program" means the program under part D of title III of the Energy Policy and Conservation Act (42 U.S.C. 6321 et seq.).
- (b) ESTABLISHMENT.—The Administrator shall develop and implement, in consultation with the Secretary of Energy, standards for a national energy and environmental building retrofit policy for single-family and multifamily residences. The Administrator shall develop and implement, in consultation with the Secretary of Energy and the Director of Commercial High-Performance Green Buildings, standards for a national energy and environmental building retrofit policy for nonresidential buildings. The programs to implement the residential and nonresidential policies based on the standards developed under this section shall together be known as the Retrofit for Energy and Environmental Performance (REEP) program.
- (c) PURPOSE.—The purpose of the REEP program is to facilitate the retrofitting of existing buildings across the United States to achieve maximum cost-effective energy efficiency improvements and significant improvements in water use and other environmental attributes.
 - (d) Federal Administration.—
- (1) EXISTING PROGRAMS.—In creating and operating the REEP program—
- (A) the Administrator shall make appropriate use of existing programs, including the Energy Star program and in particular the Environmental Protection Agency Energy Star for Buildings program; and
- (B) the Secretary of Energy shall make appropriate use of existing programs, including delegating authority to the Director of Commercial High-Performance Green Buildings appointed under section 421 of the Energy Independence and Security Act of 2007 (42 U.S.C. 17081), who shall designate and provide funding to support a high-performance

green building partnership consortium pursuant to subsection (f) of such section to support efforts under this section.

- (2) CONSULTATION AND COORDINATION.—The Administrator and the Secretary of Energy shall consult with and coordinate with the Secretary of Housing and Urban Development in carrying out the REEP program with regard to retrofitting of public housing and assisted housing. As a result of such consultation, the Administrator shall establish standards to ensure that retrofits of public housing and assisted housing funded pursuant to this section are cost-effective, including opportunities to address the potential coperformance of repair and replacement needs that may be supported with other forms of Federal assistance. "Owners of public housing or assited housing receiving funding through the REEP program shall agree to continue to provide affordable housing consistent with the provisions of the authorizing legislation governing each program for an additional period commensurate with the funding received, as determined in accordance with guidelines established by the Secretary of Housing and Urban Development."
- (3) ASSISTANCE.—The Administrator and the Secretary of Energy shall provide consultation and assistance to State and local agencies for the establishment of revolving loan funds, loan guarantees, or other forms of financial assistance under this section.
 - (e) STATE AND LOCAL ADMINISTRATION.—
- (1) Designation and Delegation.—A State may designate one or more agencies or entities, including those regulated by the State, to carry out the purposes of this section, but shall designate one entity or individual as the principal point of contact for the Administrator regarding the REEP Program. The designated State agency, agencies, or entities may delegate performance of appropriate elements of the REEP program, upon their request and subject to State law, to counties, municipalities, appropriate public agencies, and other divisions of local government, as well as to entities regulated by the State. In making any such designation or delegation, a State shall give priority to entities that administer existing comprehensive retrofit programs, including those under the supervision of State utility regulators. States shall maintain responsibility for meeting the standards and requirements of the REEP program. In any State that elects not to administer the REEP program, a unit of local government may propose to do so within its jurisdiction, and if the Administrator finds that such local government is capable of administering the program, the Administrator may provide allowances to that local government, prorated according to the population of the local jurisdiction relative to the population of the State, for purposes of the REEP program.
- (2) EMPLOYMENT.—States and local government entities may administer a REEP program in a manner that authorizes public or regulated investor-owned utilities, building auditors and inspectors, contractors, nonprofit organizations, for-profit companies, and other entities to perform audits and retrofit services under this section. A State may provide incentives for retrofits without direct participation by the State or its agents, so long as the resulting savings are measured and verified. A State or local administrator of a REEP program shall seek to ensure that sufficient qualified entities are available to support retrofit activities so that building owners have a competitive choice among qualified auditors, raters, contractors, and providers of services related to retrofits. Nothing in this section is intended to deny the right of a building owner to choose the specific providers of retrofit serv-

ices to engage for a retrofit project in that owner's building.

- (3) EQUAL INCENTIVES FOR EQUAL IMPROVE-MENT.—In general, the States should strive to offer the same levels of incentives for retrofits that meet the same efficiency improvement goals, regardless of whether the State, its agency or entity, or the building owner has conducted the retrofit achieving the improvement, provided the improvement is measured and verified.
- (f) ELEMENTS OF REEP PROGRAM.—The Administrator, in consultation with the Secretary of Energy, shall establish goals, guidelines, practices, and standards for accomplishing the purpose stated in subsection (c), and shall annually review and, as appropriate, revise such goals, guidelines, practices, and standards. The program under this section shall include the following:
- (1) Residential Energy Services Network (RESNET) or Building Performance Institute (BPI) analyst certification of residential building energy and environment auditors, inspectors, and raters, or an equivalent certification system as determined by the Administrator.
- (2) BPI certification or licensing by States of residential building energy and environmental retrofit contractors, or an equivalent certification or licensing system as determined by the Administrator.
- (3) Provision of BPI, RESNET, or other appropriate information on equipment and procedures, as determined by the Administrator, that contractors can use to test the energy and environmental efficiency of buildings effectively (such as infrared photography and pressurized testing, and tests for water use and indoor air quality).
- (4) Provision of clear and effective materials to describe the testing and retrofit processes for typical buildings.
- (5) Guidelines for offering and managing prescriptive building retrofit programs and performance-based building retrofit programs for residential and nonresidential buildings.
- (6) Guidelines for applying recommissioning and retrocommissioning principles to improve a building's operations and maintenance procedures.
- (7) A requirement that building retrofits conducted pursuant to a REEP program utilize, especially in all air-conditioned buildings, roofing materials with high solar energy reflectance, unless inappropriate due to green roof management, solar energy production, or for other reasons identified by the Administrator, in order to reduce energy consumption within the building, increase the albedo of the building's roof, and decrease the heat island effect in the area of the building, without reduction of otherwise applicable ceiling insulation standards.
- (8) Determination of energy savings in a performance-based building retrofit program through—
- (A) for residential buildings, comparison of before and after retrofit scores on the Home Energy Rating System (HERS) Index, where the final score is produced by an objective third party;
- (B) for nonresidential buildings, Environmental Protection Agency Portfolio Manager benchmarks; or
- (C) for either residential or nonresidential buildings, use of an Administrator-approved simulation program by a contractor with the appropriate certification, subject to appropriate software standards and verification of at least 15 percent of all work done, or such other percentage as the Administrator may determine.
- (9) Guidelines for utilizing the Energy Star Portfolio Manager, the Home Energy Rating System (HERS) rating system, Home Performance with Energy Star program approv-

- als, and any other tools associated with the retrofit program.
- (10) Requirements and guidelines for postretrofit inspection and confirmation of work and energy savings.
- (11) Detailed descriptions of funding options for the benefit of State and local governments, along with model forms, accounting aids, agreements, and guides to best practices.
 - (12) Guidance on opportunities for-
- (A) rating or certifying retrofitted buildings as Energy Star buildings, or as green buildings under a recognized green building rating system:
- (B) assigning Home Energy Rating System (HERS) or similar ratings; and
- (C) completing any applicable building performance labels.
- (13) Sample materials for publicizing the program to building owners, including public service announcements and advertisements.
- (14) Processes for tracking the numbers and locations of buildings retrofitted under the REEP program, with information on projected and actual savings of energy and its value over time.
- (g) REQUIREMENTS.—As a condition of receiving allowances for the REEP program pursuant to this Act, a State or qualifying local government shall—
- (1) adopt the standards for training, certification of contractors, certification of buildings, and post-retrofit inspection as developed by the Administrator for residential and nonresidential buildings, respectively, except as necessary to match local conditions, needs, efficiency opportunities, or other local factors, or to accord with State laws or regulations, and then only after the Administrator approves such a variance;
- (2) establish fiscal controls and accounting procedures (which conform to generally accepted government accounting principles) sufficient to ensure proper accounting during appropriate accounting periods for payments received and disbursements, and for fund balances; and
- (3) agree to make not less than 10 percent of allowance value received pursuant to section 132(c)(2) for dedicated funding of its REEP program available on a preferential basis for retrofit projects proposed for public housing and assisted housing, provided that—
- (A) none of such funds shall be used for demolition of such housing;
- (B) such retrofits shall not be used to justify any increase in rents charged to residents of such housing; and
- (C) owners of such housing shall agree to continue to provide affordable housing consistent with the provisions of the authorizing legislation governing each program for an additional period commensurate with the funding received.
- The Administrator shall conduct or require each State to have such independent financial audits of REEP-related funding as the Administrator considers necessary or appropriate to carry out the purposes of this section.
- (h) OPTIONS TO SUPPORT REEP PROGRAM.— The emission allowances provided pursuant to this Act to the States SEED Accounts shall support the implementation through State REEP programs of alternate means of creating incentives for, or reducing financial barriers to, improved energy and environmental performance in buildings, consistent with this section, including—
- (1) implementing prescriptive building retrofit programs and performance-based building retrofit programs;
- (2) providing credit enhancement, interest rate subsidies, loan guarantees, or other credit support;

- (3) providing initial capital for public revolving fund financing of retrofits, with repayments by beneficiary building owners over time through their tax payments, calibrated to create net positive cash flow to the building owner:
- (4) providing funds to support utility-operated retrofit programs with repayments over time through utility rates, calibrated to create net positive cash flow to the building owner, and transferable from one building owner to the next with the building's utility services:
- (5) providing funds to local government programs to provide REEP services and financial assistance; and
- (6) other means proposed by State and local agencies, subject to the approval of the Administrator.
 - (i) SUPPORT FOR PROGRAM.—
- (1) USE OF ALLOWANCES.—Direct Federal support for the REEP program is provided through the emission allowances allocated to the States' SEED Accounts pursuant to section 132 of this Act. To the extent that a State provides allowances to local governments within the State to implement elements of the REEP Program, that shall be deemed a distribution of such allowances to units of local government pursuant to subsection (c)(1) of that section.
- (2) INITIAL AWARD LIMITS.—Except as provided in paragraph (3), State and local REEP programs may make per-building direct expenditures for retrofit improvements, or their equivalent in indirect or other forms of financial support, from funds derived from the sale of allowances received directly from the Administrator in amounts not to exceed the following amounts per unit:
- (A) RESIDENTIAL BUILDING PROGRAM.—
- (i) AWARDS.—For residential buildings-
- (I) support for a free or low-cost detailed building energy audit that prescribes measures sufficient to achieve at least a 20 percent reduction in energy use, by providing an incentive equal to the documented cost of such audit, but not more than \$200, in addition to any earned by achieving a 20 percent or greater efficiency improvement;
- (II) a total of \$1,000 for a combination of measures, prescribed in an audit conducted under subclause (I), designed to reduce energy consumption by more than 10 percent, and \$2,000 for a combination of measures prescribed in such an audit, designed to reduce energy consumption by more than 20 percent;
- (III) \$3,000 for demonstrated savings of 20 percent, pursuant to a performance-based building retrofit program; and
- (IV) \$1,000 for each additional 5 percentage points of energy savings achieved beyond savings for which funding is provided under subclause (II) or (III).
- Funding shall not be provided under clauses (II) and (III) for the same energy savings.
- (ii) MAXIMUM PERCENTAGE.—Awards under clause (i) shall not exceed 50 percent of retrofit costs for each building. For buildings with multiple residential units, awards under clause (i) shall not be greater than 50 percent of the total cost of retrofitting the building, prorated among individual residential units on the basis of relative costs of the retrofit. In the case of public housing and assisted housing, the 50 percent contribution matching the contribution from REEP program funds may come from any other source, including other Federal funds.
- (iii) ADDITIONAL AWARDS.—Additional awards may be provided for purposes of increasing energy efficiency, for buildings achieving at least 20 percent energy savings using funding provided under clause (i), in the form of grants of not more than \$600 for measures projected or measured (using an appropriate method approved by the Admin-

- istrator) to achieve at least 35 percent potable water savings through equipment or systems with an estimated service life of not less than seven years, and not more than an additional \$20 may be provided for each additional one percent of such savings, up to a maximum total grant of \$1,200.
- (B) NONRESIDENTIAL BUILDING PROGRAM.—
- (i) AWARDS.—For nonresidential buildings—
- (I) support for a free or low-cost detailed building energy audit that prescribes, as part of a energy-reducing measures sufficient to achieve at least a 20 percent reduction in energy use, by providing an incentive equal to the documented cost of such audit, but not more than \$500, in addition to any award earned by achieving a 20 percent or greater efficiency improvement;
- (II) \$0.15 per square foot of retrofit area for demonstrated energy use reductions from 20 percent to 30 percent;
- (III) \$0.75 per square foot for demonstrated energy use reductions from 30 percent to 40 percent;
- (IV) \$1.60 per square foot for demonstrated energy use reductions from 40 percent to 50 percent; and
- (V) \$2.50 per square foot for demonstrated energy use reductions exceeding 50 percent.
- (ii) MAXIMUM PERCENTAGE.—Amounts provided under subclauses (II) through (V) of clause (i) combined shall not exceed 50 percent of the total retrofit cost of a building. In nonresidential buildings with multiple units, such awards shall be prorated among individual units on the basis of relative costs of the retrofit.
- (iii) ADDITIONAL AWARDS.—Additional awards may be provided, for buildings achieving at least 20 percent energy savings using funding provided under clause (i), as follows:
- (I) WATER.—For purposes of increasing energy efficiency, grants may be made for whole building potable water use reduction (using an appropriate method approved by the Administrator) for up to 50 percent of the total retrofit cost, including amounts up
- (aa) \$24.00 per thousand gallons per year of potable water savings of 40 percent or more; (bb) \$27.00 per thousand gallons per year of potable water savings of 50 percent or more; and
- (cc) \$30.00 per thousand gallons per year of potable water sayings of 60 percent or more.
- (II) ENVIRONMENTAL IMPROVEMENTS.—Additional awards of up to \$1,000 may be granted for the inclusion of other environmental attributes that the Administrator, in consultation with the Secretary, identifies as contributing to energy efficiency. Such attributes may include, but are not limited to waste diversion and the use of environmentally preferable materials (including salvaged, renewable, or recycled materials, and materials with no or low-VOC content). The Administrator may recommend that States develop such standards as are necessary to account for local or regional conditions that may affect the feasibility or availability of identified resources and attributes.
- (iv) INDOOR AIR QUALITY MINIMUM.—Nonresidential buildings receiving incentives under this section must satisfy at a minimum the most recent version of ASHRAE Standard 62.1 for ventilation, or the equivalent as determined by the Administrator. A State may issue a waiver from this requirement to a building project on a showing that such compliance is infeasible due to the physical constraints of the building's existing ventilation system, or such other limitations as may be specified by the Administrator.
- (C) DISASTER DAMAGED BUILDINGS.—Any source of funds, including Federal funds provided through the Robert T. Stafford Dis-

- aster Relief and Emergency Assistance Act, shall qualify as the building owner's 50 percent contribution, in order to match the contribution of REEP funds, so long as the REEP funds are only used to improve the energy efficiency of the buildings being reconstructed. In addition, the appropriate Federal agencies providing assistance to building owners through the Robert T. Stafford Disaster Relief and Emergency Assistance Act shall make information available, following a disaster, to building owners rebuilding disaster damaged buildings with assistance from the Act, that REEP funds may be used for energy efficiency improvements.
- (D) HISTORIC BUILDINGS.—Notwithstanding subparagraphs (A) and (B), a building in or eligible for the National Register of Historic Places shall be eligible for awards under this paragraph in amounts up to 120 percent of the amounts set forth in subparagraphs (A) and (B).
- (E) SUPPLEMENTAL SUPPORT.—State and local governments may supplement the perbuilding expenditures under this paragraph with funding from other sources.
- (3) ADJUSTMENT.—The Administrator may adjust the specific dollar limits funded by the sale of allowances pursuant to paragraph (2) in years subsequent to the second year after the date of enactment of this Act, and every 2 years thereafter, as the Administrator determines necessary to achieve optimum cost-effectiveness and to maximize incentives to achieve energy efficiency within the total building award amounts provided in that paragraph, and shall publish and hold constant such revised limits for at least 2 years
- (j) REPORT TO CONGRESS.—The Administrator shall conduct an annual assessment of the achievements of the REEP program in each State, shall prepare an annual report of such achievements and any recommendations for program modifications, and shall provide such report to Congress at the end of each fiscal year during which funding or other resources were made available to the States for the REEP Program.
- (k) OTHER SOURCES OF FEDERAL SUPPORT.—
 (1) ADDITIONAL STATE ENERGY PROGRAM FUNDS.—Any Federal funding provided to a State Energy Program that is not required to be expended for a different federally designated purpose may be used to support a REEP program.
- (2) PROGRAM ADMINISTRATION.—State Energy Offices or designated State agencies may expend up to 10 percent of available allowance value provided under this section for program administration.
- (3) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated for the purposes of this section, for each of fiscal years 2010, 2011, 2012, and 2013—
- (A) \$50,000,000 to the Administrator for program administration costs; and
- (B) \$20,000,000 to the Secretary of Energy for program administration costs.

SEC. 203. ENERGY EFFICIENT MANUFACTURED HOMES.

- (a) DEFINITIONS.—In this section:
- (1) MANUFACTURED HOME.—The term "manufactured home" has the meaning given such term in section 603 of the National Manufactured Housing Construction and Safety Standards Act of 1974 (42 U.S.C. 5402).
- (2) ENERGY STAR QUALIFIED MANUFACTURED HOME.—The term "Energy Star qualified manufactured home" means a manufactured home that has been designed, produced, and installed in accordance with Energy Star's guidelines by an Energy Star certified plant.

 (b) PURPOSE.—The purpose of this section
- (b) FORPOSE.—The purpose of this section is to assist low-income households residing in manufactured homes constructed prior to 1976 to save energy and energy expenditures by providing support toward the purchase of

new Energy Star qualified manufactured homes.

- (c) STATE IMPLEMENTATION OF PROGRAM.—
- (1) Manufactured home replacement pro-GRAM.—Any State may provide to the owner of a manufactured home constructed prior to 1976 a rebate to use toward the purchase of a new Energy Star qualified manufactured home pursuant to this section.
- (2) Use of allowances.—Direct Federal support for the program established in this section is provided through the emission allowances allocated to the States' SEED Accounts pursuant to section 132 of this Act. To the extent that a State provides allowances to local governments within the State to implement this program, that shall be deemed a distribution of such allowances to units of local government pursuant to subsection (c)(1) of that section.
 - (3) Rebates.
- (A) PRIMARY RESIDENCE REQUIREMENT.—A rebate described under paragraph (1) may only be made to an owner of a manufactured home constructed prior to 1976 that is used on a year-round basis as a primary residence.
- (B) DISMANTLING AND REPLACEMENT.—A rebate described under paragraph (1) may be made only if the manufactured home constructed prior to 1976 will be-
- (i) rendered unusable for human habitation (including appropriate recycling); and
- (ii) replaced, in the same general location, as determined by the applicable State agency, with an Energy Star qualified manufactured home.
- (C) SINGLE REBATE.—A rebate described under paragraph (1) may not be provided to any owner of a manufactured home constructed prior to 1976 that was or is a member of a household for which any other member of the household was provided a rebate pursuant to this section.
- (D) ELIGIBLE HOUSEHOLDS.—To be eligible to receive a rebate described under paragraph (1), an owner of a manufactured home constructed prior to 1976 shall demonstrate to the applicable State agency that the total income of all members the owner's household does not exceed 200 percent of the Federal poverty level for income in the applicable area.
- (E) ADVANCE AVAILABILITY.—A rebate may be provided under this section in a manner to facilitate the purchase of a new Energy Star qualified manufactured home.
- (4) REBATE LIMITATION.—Rebates provided by States under this section shall not exceed \$7.500 per manufactured home from any value derived from the use of emission allowances provided to the State pursuant to section 132.
- (5) Use of state funds.—A State providing rebates under this section may supplement the amount of such rebates under paragraph (4) by any additional amount is from State funds and other sources, including private donations or grants from charitable organizations.
- (6) COORDINATION WITH SIMILAR PRO-GRAMS.
- (A) STATE PROGRAMS.—A State conducting an existing program that has the purpose of replacing manufactured homes constructed prior to 1976 with Energy Star qualified manufactured homes, may use allowance value provided under section 782 of the Clean Air Act to support such a program, provided such funding does not exceed the rebate limitation amount under paragraph (4).
- (B) FEDERAL PROGRAMS.—The Secretary of Energy shall coordinate with and seek to achieve the purpose of this section through similar Federal programs including-
- (i) the Weatherization Assistance Program under part A of title IV of the Energy Conservation and Production Act (42 U.S.C. 6861 et seq.); and

- (ii) the program under part D of title III of the Energy Policy and Conservation Act (42 U.S.C. 6321 et seq.).
- (C) COORDINATION WITH OTHER STATE AGEN-CIES.—A State agency using allowance value to administer the program under this section may coordinate its efforts, and share funds for administration, with other State agencies involved in low-income housing programs.
- (7) ADMINISTRATIVE EXPENSES.—A State using allowance value under this section may expend not more than 10 percent of such value for administrative expenses related to this program.

SEC. 204. BUILDING ENERGY PERFORMANCE LA-BELING PROGRAM.

- (a) Establishment.
- (1) PURPOSE.—The Administrator shall establish a building energy performance labeling program with broad applicability to the residential and commercial markets to enable and encourage knowledge about building energy performance by owners and occupants and to inform efforts to reduce energy consumption nationwide.
- (2) COMPONENTS.—In developing such program, the Administrator shall-
- (A) consider existing programs, such as Environmental Protection Agency's Energy Star program, the Home Energy Rating System (HERS) Index, and programs at the Department of Energy;
- (B) support the development of model performance labels for residential and commercial buildings; and
- (C) utilize incentives and other means to spur use of energy performance labeling of public and private sector buildings nationwide.
- (b) DATA ASSESSMENT FOR BUILDING EN-ERGY PERFORMANCE.-
- (1) INITIAL REPORT.—Not later than 90 days after the date of enactment of this Act, the Administrator shall provide to Congress, as well as to the Secretary of Energy and the Office of Management and Budget, a report identifying-
- (A) all principal building types for which statistically significant energy performance data exists to serve as the basis of measurement protocols and labeling requirements for achieved building energy performance; and
- (B) those building types for which additional data are required to enable the development of such protocols and requirements.
- (2) ADDITIONAL REPORTS.—Additional updated reports shall be provided under this subsection as often as The Administrator considers practicable, but not less than every 2 years
 - (c) Building Data Acquisition.—
- (1) RESOURCE REQUIREMENTS.—For all principal building types identified under subsection (b), the Secretary of Energy, not later than 90 days after a report by the Administrator under subsection (b), shall provide to Congress, the Administrator, and the Office of Management and Budget a statement of additional resources needed, if any, to fully develop the relevant data, as well as the anticipated timeline for data develop-
- (2) CONSULTATION.—The Secretary of Energy shall consult with the Administrator concerning the Administrator's ability to use data series for these additional building types to support the achieved performance component in the labeling program.
- (3) Improvements to building energy con-SUMPTION DATABASES .-
- (A) COMMERCIAL DATABASE.—The Secretary of Energy shall support improvements to the Commercial Buildings Energy Consumption Survey (CBECS) as authorized by section 205(k) of the Department of Energy Organization Act (42 U.S.C. 7135(k))-

- (i) to enable complete and robust data for the actual energy performance of principal building types currently covered by survey;
- (ii) to cover additional building types as identified by the Administrator under subsection (b)(1)(B), to enable the development of achieved performance measurement protocols are developed for at least 90 percent of all major commercial building types within 5 years after the date of enactment of this Act: and
- (iii) to include third-party audits of random data samplings to ensure the quality and accuracy of survey information.
- (B) RESIDENTIAL DATABASES.—The Administrator, in consultation with the Energy Information Administration and the Secretary of Energy, shall support improvements to the Residential Energy Consumption Survey (RECS) as authorized by section 205(k) of the Department of Energy Organization Act (42 U.S.C. 7135(k)), or such other residential energy performance databases as the Administrator considers appropriate, to aid the development of achieved performance measurement protocols for residential building energy use for at least 90 percent of the residential market within 5 years after the date of enactment of this Act.
- (C) CONSULTATION.—The Secretary of Energy and the Administrator shall consult with public, private, and nonprofit sector representatives from the building industry and real estate industry to assist in the evaluation and improvement of building energy performance databases and labeling pro-
- (d) Identification of Measurement Pro-TOCOLS FOR ACHIEVED PERFORMANCE.
- (1) PROPOSED PROTOCOLS AND REQUIRE-MENTS.—At the earliest practicable date, but not later than 1 year after identifying a building type under subsection (b)(1)(A), the Administrator shall propose a measurement protocol for that building type and a requirement detailing how to use that protocol in completing applicable commercial or residential performance labels created pursuant to this section.
- (2) FINAL RULE.—After providing for notice and comment, the Administrator shall publish a final rule containing a measurement protocol and the corresponding requirements for applying that protocol. Such a rule-
- (A) shall define the minimum period for measurement of energy use by buildings of that type and other details for determining achieved performance, to include leased buildings or parts thereof;
- (B) shall identify necessary data collection and record retention requirements; and
- (C) may specify transition rules and exemptions for classes of buildings within the building type.
- (e) PROCEDURES FOR EVALUATING DESIGNED PERFORMANCE.—The Administrator shall develop protocols for evaluating the designed performance of individual building types. The Administrator may conduct such feasibility studies and demonstration projects as are necessary to evaluate the sufficiency of proposed protocols for designed performance.
- (f) CREATION OF BUILDING ENERGY PER-FORMANCE LABELING PROGRAM.
- (1) Model label.—Not later than 1 year after the date of enactment of this Act, the Administrator shall propose a model building energy label that provides a format-
- (A) to display achieved performance and designed performance data:
- (B) that may be tailored for residential and commercial buildings, and for single-occupancy and multitenanted buildings; and
- (C) to display other appropriate elements identified during the development of measurement protocols under subsections (d) and

- (2) INCLUSIONS.—Nothing in this section shall require the inclusion on such a label of designed performance data where impracticable or not cost effective, or to preclude the display of both achieved performance and designed performance data for a particular building where both such measures are available, practicable, and cost effective.
- (3) EXISTING PROGRAMS.—In developing the model label, the Administrator shall consider existing programs, including—
- (A) the Environmental Protection Agency's Energy Star Portfolio Manager program and the California HERS II Program Custom Approach for the achieved performance component of the label;
- (B) the Home Energy Rating System (HERS) Index system for the designed performance component of the label; and
- (C) other Federal and State programs, including the Department of Energy's related programs on building technologies and those of the Federal Energy Management Program.
- (4) FINAL RULE.—After providing for notice and comment, the Administrator shall publish a final rule containing the label applicable to covered building types.
- (g) DEMONSTRATION PROJECTS FOR LABELING PROGRAM.—
- (1) IN GENERAL.—The Administrator shall conduct building energy performance labeling demonstration projects for different building types—
- (A) to ensure the sufficiency of the current Commercial Buildings Energy Consumption Survey and other data to serve as the basis for new measurement protocols for the achieved performance component of the building energy performance labeling program;
- (B) to inform the development of measurement protocols for building types not currently covered by the Commercial Buildings Energy Consumption Survey; and
- (C) to identify any additional information that needs to be developed to ensure effective use of the model label.
- (2) PARTICIPATION.—Such demonstration
- projects shall include participation of—
 (A) buildings from diverse geographical and climate regions:
- (B) buildings in both urban and rural areas:
- (C) single-family residential buildings:
- (D) multihousing residential buildings with more than 50 units, including at least one project that provides affordable housing to individuals of diverse incomes;
- (E) single-occupant commercial buildings larger than 30,000 square feet;
- (F) multitenanted commercial buildings larger than 50,000 square feet; and
- (G) buildings from both the public and private sectors.
- (3) PRIORITY.—Priority in the selection of demonstration projects shall be given to projects that facilitate large-scale implementation of the labeling program for samples of buildings across neighborhoods, geographic regions, cities, or States.
- (4) FINDINGS.—The Administrator shall report any findings from demonstration projects under this subsection, including an identification of any areas of needed data improvement, to the Department of Energy's Energy Information Administration and Building Technologies Program.
- (5) COORDINATION.—The Administrator and the Secretary of Energy shall coordinate demonstration projects undertaken pursuant to this subsection with those undertaken as part of the Zero-Net-Energy Commercial Buildings Initiative adopted under section 422 of the Energy Independence and Security Act of 2007 (42 U.S.C. 17082).
- (h) IMPLEMENTATION OF LABELING PROGRAM.—
- (1) IN GENERAL.—The Administrator, in consultation with the Secretary of Energy,

- shall work with all State Energy Offices established pursuant to part D of title III of the Energy Policy and Conservation Act (42 U.S.C. 6321 et seq.) or other State authorities as necessary for the purpose of implementing the labeling program established under this section for commercial and residential buildings.
- (2) Outreach to local authorities.—The Administrator shall, acting in consultation and coordination with the respective States, encourage use of the labeling program by counties and other localities to broaden access to information about building energy use, for example, through disclosure of building label contents in tax, title, and other records those localities maintain. For this purpose, the Administrator shall develop an electronic version of the label and information that can be readily transmitted and read in widely-available computer programs but is protected from unauthorized manipulation.
- (3) MEANS OF IMPLEMENTATION.—In adopting the model labeling program established under this section, a State shall seek to ensure that labeled information be made accessible to the public in a manner so that owners, lenders, tenants, occupants, or other relevant parties can utilize it. Such accessibility may be accomplished through—
- (A) preparation, and public disclosure of the label through filing with tax and title records at the time of—
- (i) a building audit conducted with support from Federal or State funds;
- (ii) a building energy-efficiency retrofit conducted in response to such an audit;
- (iii) a final inspection of major renovations or additions made to a building in accordance with a building permit issued by a local government entity:
- (iv) a sale that is recorded for title and tax purposes consistent with paragraph (8);
- (v) a new lien recorded on the property for more than a set percentage of the assessed value of the property, if that lien reflects public financial assistance for energy-related improvements to that building; or
- (vi) a change in ownership or operation of the building for purposes of utility billing; or
- (B) other appropriate means.
- (4) STATE IMPLEMENTATION OF PROGRAM.—
- (A) ELIGIBILITY.—A State may become eligible to utilize allowance value to implement this program by—
- (i) adopting by statute or regulation a requirement that buildings be assessed and labeled, consistent with the labeling requirements of the program established under this section: or
- (ii) adopting a plan to implement a model labeling program consistent with this section within one year of enactment of this Act, including the establishment of that program within 3 years after the date of enactment of this Act, and demonstrating continuous progress under that plan.
- (B) USE OF ALLOWANCES.—Direct Federal support for the program established in this section is provided through the emission allowances allocated to the States' SEED Accounts pursuant to section 132 of this Act. To the extent that a State provides allowances to local governments within the State to implement this program, that shall be deemed a distribution of such allowances to units of local government pursuant to subsection (c)(1) of that section.
- (5) GUIDANCE.—The Administrator may create or identify model programs and resources to provide guidance to offer to States and localities for creating labeling programs consistent with the model program established under this section.
- (6) PROGRESS REPORT.—The Administrator, in consultation with the Secretary of Energy, shall provide a progress report to Con-

- gress not later than 3 years after the date of enactment of this Act that—
- (A) evaluates the effectiveness of efforts to advance use of the model labeling program by States and localities;
- (B) recommends any legislative changes necessary to broaden the use of the model labeling program; and
- (C) identifies any changes to broaden the use of the model labeling program that the Administrator has made or intends to make that do not require additional legislative authority.
- (7) STATE INFORMATION.—The Administrator may require States to report to the Administrator information that the Administrator requires to provide the report required under paragraph (6).
- (8) PREVENTION OF DISRUPTION OF SALES TRANSACTIONS.—No State shall implement a new labeling program pursuant to this section in a manner that requires the labeling of a building to occur after a contract has been executed for the sale of that building and before the sales transaction is completed.
- (i) IMPLEMENTATION OF LABELING PROGRAM IN FEDERAL BUILDINGS.—
- (1) USE OF LABELING PROGRAM.—The Secretary of Energy and the Administrator shall use the labeling program established under this section to evaluate energy performance in the facilities of the Department of Energy and the Environmental Protection Agency, respectively, to the extent practicable, and shall encourage and support implementation efforts in other Federal agencies.
- (2) ANNUAL PROGRESS REPORT.—The Secretary of Energy and Administrator shall provide an annual progress report to Congress and the Office of Management and Budget detailing efforts to implement this subsection, as well as any best practices or needed resources identified as a result of such efforts.
- (j) PUBLIC OUTREACH.—The Secretary of Energy and the Administrator, in consultation with nonprofit and industry stakeholders with specialized expertise, and in conjunction with other energy efficiency public awareness efforts, shall establish a business and consumer education program to increase awareness about the importance of building energy efficiency and to facilitate widespread use of the labeling program established under this section.
 - (\ensuremath{k}) Definitions.—In this section:
- (1) BUILDING TYPE.—The term "building type" means a grouping of buildings as identified by their principal building activities, or as grouped by their use, including office buildings, laboratories, libraries, data centers, retail establishments, hotels, warehouses, and educational buildings.
- (2) MEASUREMENT PROTOCOL.—The term "measurement protocol" means the methodology, prescribed by the Administrator, for defining a benchmark for building energy performance for a specific building type and for measuring that performance against the benchmark.
- (3) ACHIEVED PERFORMANCE.—The term "achieved performance" means the actual energy consumption of a building as compared to a baseline building of the same type and size, determined by actual consumption data normalized for appropriate variables.
- (4) DESIGNED PERFORMANCE.—The term "designed performance" means the energy consumption performance a building would achieve if operated consistent with its design intent for building energy use, utilizing a standardized set of operational conditions informed by data collected or confirmed during an energy audit.
- (1) AUTHORIZATION OF APPROPRIATIONS.—There are authorized to be appropriated—

- (1) to the Administrator \$50,000,000 for implementation of this section for each fiscal year from 2010 through 2020; and
- (2) to the Secretary of Energy \$20,000,000 for implementation of this section for fiscal year 2010 and \$10,000,000 for fiscal years 2011 through 2020.
- (m) NEW CONSTRUCTION.—This section shall apply only to construction beginning after the date of enactment of this Act.

SEC. 205. TREE PLANTING PROGRAMS.

- (a) FINDINGS.—The Congress finds that-
- (1) the utility sector is the largest single source of greenhouse gas emissions in the United States today, producing approximately one-third of the country's emissions;
- (2) heating and cooling homes accounts for nearly 60 percent of residential electricity usage in the United States;
- (3) shade trees planted in strategic locations can reduce residential cooling costs by as much as 30 percent;
- (4) shade trees have significant clean-air benefits associated with them;
- (5) every 100 healthy large trees removes about 300 pounds of air pollution (including particulate matter and ozone) and about 15 tons of carbon dioxide from the air each year:
- (6) tree cover on private property and on newly-developed land has declined since the 1970s, even while emissions from transportation and industry have been rising; and
- (7) in over a dozen test cities across the United States, increasing urban tree cover has generated between two and five dollars in savings for every dollar invested in such tree planting.
 - (b) DEFINITIONS.—As used in this section:
- (1) The term "Secretary" refers to the Secretary of Energy.
- (2) The term "retail power provider" means any entity authorized under applicable State or Federal law to generate, distribute, or provide retail electricity, natural gas, or fuel oil service.
- (3) The term "tree-planting organization" means any nonprofit or not-for-profit group which exists, in whole or in part, to—
- (A) expand urban and residential tree cover:
 - (B) distribute trees for planting;
- (C) increase awareness of the environmental and energy-related benefits of trees;
- (D) educate the public about proper tree planting, care, and maintenance strategies; or
- (E) carry out any combination of the foregoing activities.
- (4) The term "tree-siting guidelines" means a comprehensive list of science-based measurements outlining the species and minimum distance required between trees planted pursuant to this section, in addition to the minimum required distance to be maintained between such trees and—
 - (A) building foundations;
- (B) air conditioning units;
- (C) driveways and walkways;
- (D) property fences:
- (E) preexisting utility infrastructure;
- (F) septic systems;
- (G) swimming pools; and
- (H) other infrastructure as deemed appropriate.
- (5) The terms "small office", "small office buildings", and "small office settings" means nonresidential buildings or structures zoned for business purposes that are 20,000 square feet or less in total area.
- (c) Purposes.—The purpose of this section is to establish a grant program to assist retail power providers with the establishment and operation of targeted tree-planting programs in residential and small office settings, for the following purposes:
- (1) Reducing the peak-load demand for electricity from residences and small office

- buildings during the summer months through direct shading of buildings provided by strategically planted trees.
- (2) Reducing wintertime demand for energy from residences and small office buildings by blocking cold winds from reaching such structures, which lowers interior temperatures and drives heating demand.
- (3) Protecting public health by removing harmful pollution from the air.
- (4) Utilizing the natural photosynthetic and transpiration process of trees to lower ambient temperatures and absorb carbon dioxide, thus mitigating the effects of climate change.
- (5) Lowering electric bills for residential and small office ratepayers by limiting electricity consumption without reducing benefits
- (6) Relieving financial and demand pressure on retail power providers that stems from large peak-load energy demand.
- (7) Protecting water quality and public health by reducing stormwater runoff and keeping harmful pollutants from entering waterways.
- (8) Ensuring that trees are planted in locations that limit the amount of public money needed to maintain public and electric infrastructure.
 - (d) GENERAL AUTHORITY.-
- (1) Assistance.—The Secretary is authorized to provide financial, technical, and related assistance to retail power providers to assist with the establishment of new, or continued operation of existing, targeted treeplanting programs for residences and small office buildings.
- (2) PUBLIC RECOGNITION INITIATIVE.—In carrying out the authority provided under this section, the Secretary shall also create a national public recognition initiative to encourage participation in tree-planting programs by retail power providers.
- (3) ELIGIBILITY.—Only those programs which utilize targeted, strategic tree-siting guidelines to plant trees in relation to building location, sunlight, and prevailing wind direction shall be eligible for assistance under this section.
- (4) REQUIREMENTS.—In order to qualify for assistance under this section, a tree-planting program shall meet each of the following requirements:
- (A) The program shall provide free or discounted shade-providing or wind-reducing trees to residential and small office consumers interested in lowering their home energy costs.
- (B) The program shall optimize the electricity-consumption reduction benefit of each tree by planting in strategic locations around a given residence or small office.
 - (C) The program shall either—
- (i) provide maximum amounts of shade during summer intervals when residences and small offices are exposed to the most sun intensity; or
- (ii) provide maximum amounts of wind protection during fall and winter intervals when residences and small offices are exposed to the most wind intensity.
- (D) The program shall use the best available science to create tree siting guidelines which dictate where the optimum tree species are best planted in locations that achieve maximum reductions in consumer energy demand while causing the least disruption to public infrastructure, considering overhead and underground facilities.
- (E) The program shall receive certification from the Secretary that it is designed to achieve the goals set forth in subparagraphs (A) through (D). In designating criteria for such certification, the Secretary shall collaborate with the United States Forest Service's Urban and Community Forestry Pro-

- gram to ensure that certification requirements are consistent with such above goals.
- (5) NEW PROGRAM FUNDING SHARE.—The Secretary shall ensure that no less than 30 percent of the funds made available under this section are distributed to retail power providers which—
- (A) have not previously established or operated qualified tree-planting programs; or
- (B) are operating qualified tree-planting programs which were established no more than three years prior to the date of enactment of this section.
- (e) AGREEMENTS BETWEEN ELECTRICITY PROVIDERS AND TREE-PLANTING ORGANIZATIONS —
- (1) Grant authorization.—In providing assistance under this section, the Secretary is authorized to award grants only to retail power providers that have entered into binding legal agreements with nonprofit tree-planting organizations.
- (2) CONDITIONS OF AGREEMENT.—Those agreements between retail power providers and tree-planting organizations shall set forth conditions under which nonprofit tree-planting organizations shall provide targeted tree-planting programs which may require these organizations to—
- (A) participate in local technical advisory committees responsible for drafting general tree-siting guidelines and choosing the most effective species of trees to plant in given locations:
- (B) coordinate volunteer recruitment to assist with the physical act of planting trees in residential locations;
- (C) undertake public awareness campaigns to educate local residents about the benefits, cost savings, and availability of free shade trees:
- (D) establish education and information campaigns to encourage recipients to maintain their shade trees over the long term;
- (E) serve as the point of contact for existing and potential residential participants who have questions or concerns regarding the tree-planting program;
- (F) require tree recipients to sign agreements committing to voluntary stewardship and care of provided trees;
- (G) monitor and report on the survival, growth, overall health, and estimated energy savings of provided trees up until the end of their establishment period which shall be no less than five years; and
- (H) ensure that trees planted near existing power lines will not interfere with energized electricity distribution lines when mature, and that no new trees will be planted under or adjacent to high-voltage electric transmission lines without prior consultation with the applicable retail power provider receiving assistance under this section.
- (3) LACK OF NONPROFIT ORGANIZATION.—If qualified nonprofit or not-for-profit tree planting organizations do not exist or operate within areas served by retail power providers applying for assistance under this section, the requirements of this section shall apply to binding legal agreements entered into by such retail power providers and one of the following entities:
- (A) Local municipal governments with jurisdiction over the urban or suburban forest.
- (B) The State Forester for the State in which the tree planting program will operate
- (C) The United States Forest Service's Urban and Community Forestry representative for the State in which the tree-planting program will operate.
- (D) A landscaping services company that is—
- (i) identified in consultation with a national or State nonprofit or not-for-profit tree-planting organization;

- (ii) licensed to operate in the State in which the tree-planting program will operate: and
- (iii) a business as defined by the United States Census Bureau's 2007 North American Industry Classification System Code 561730.
 - (f) TECHNICAL ADVISORY COMMITTEES.—
- (1) DESCRIPTION.—In order to qualify for assistance under this section, the retail power provider shall establish and consult with a local technical advisory committee which shall provide advice and consultation to the program, and may—
- (A) design and adopt an approved plant list that emphasizes the use of hardy, noninvasive tree species and, where geographically appropriate, the use of native, or site-adapted or low water-use shade trees:
- (B) design and adopt planting, installation, and maintenance specifications and create a process for inspection and quality control;
- (C) ensure that tree recipients are educated to care for and maintain their trees over the long term;
- (D) help the public become more engaged and educated in the planting and care of shade trees;
- (E) prioritize which sites receive trees, giving preference to locations with the most potential for energy conservation and secondary preference to areas where the average annual income is below the regional median; and
- (F) assist with monitoring and collection of data on tree health, tree survival, and energy conservation benefits generated under this section.
- (2) COMPENSATION.—Individuals serving on local technical advisory committees shall not receive compensation for their service.
- (3) COMPOSITION.—Local technical advisory committees shall be composed of representatives from public, private, and nongovernmental agencies with expertise in demandside energy efficiency management, urban forestry, or arboriculture, and shall be composed of the following:
- (A) Up to 4 persons, but no less than one person, representing the retail power provider receiving assistance under this section.
- (B) Up to 4 persons, but no less than one person, representing the local tree-planting organization which will partner with the retail power provider to carry out this section.
- (C) Up to 3 persons representing local nonprofit conservation or environmental organizations. Preference shall be given to those entities which are organized under section 501(c)(3) of the Internal Revenue Code of 1986, and which have demonstrated expertise engaging the public in energy conservation, energy efficiency, or green building practices or a combination thereof, such that no single organization is represented by more than one individual under this paragraph.
- (D) Up to 2 persons representing a local affordable housing agency, affordable housing builder, or community development corporation
- (E) Up to 3, but no less than one, persons representing local city or county government for each municipality where a shade tree-planting program will take place; at least one of these representatives shall be the city or county forester, city or county arborist, or functional equivalent.
- (F) Up to one person representing the local government agency responsible for management of roads, sewers, and infrastructure, including but not limited to public works departments, transportation agencies, or equivalents
- (G) Up to 3 persons representing the nursery and landscaping industry.
- (H) Up to 3 persons representing the research community or academia with expertise in natural resources or energy management issues.

- (4) CHAIRPERSON.—Each local technical advisory committee shall elect a chairperson to preside over Committee meetings, act as a liaison to governmental and other outside entities, and direct the general operation of the committee; only committee representatives from paragraph (3)(A) or paragraph (3)(B) of this subsection shall be eligible to act as local technical advisory committee chairpersons.
- (5) CREDENTIALS.—At least one of the members of each local technical advisory committee shall be certified with one or more of the following credentials: International Society of Arboriculture; Certified Arborist, ISA; Certified Arborist Municipal Specialist, ISA; Certified Arborist Utility Specialist, ISA; Board Certified Master Arborist; or Registered Landscape Architect recommended by the American Society of Landscape Architects.
 - (g) Cost-share Program.—
- (1) FEDERAL SHARE.—The Federal share of support for projects funded under this section shall not exceed 50 percent of the cost of such project and shall be provided on a matching basis.
- (2) NON-FEDERAL SHARE.—The non-Federal share of such costs may be paid or contributed by any governmental or nongovernmental entity other than from funds derived directly or indirectly from an agency or instrumentality of the United States.
 - (h) RULEMAKING.—
- (1) RULEMAKING PERIOD.—The Secretary shall be authorized to solicit comments and initiate a rulemaking period that shall last no more than 6 months after the date of enactment of this section.
- (2) COMPETITIVE GRANT RULE.—At the conclusion of the rulemaking period under paragraph (1), the Secretary shall promulgate a rule governing a public, competitive grants process through which retail power providers may apply for Federal support under this section.
- (i) NONDUPLICITY.—Nothing in this section shall be construed to supersede, duplicate, cancel, or negate the programs or authorities provided under section 9 of the Cooperative Forestry Assistance Act of 1978 (92 Stat. 369: Public Law 95-313: 16 U.S.C. 2105).
- (j) AUTHORIZATION OF APPROPRIATIONS.— There are hereby authorized to be appropriated such sums as may be necessary for the implementation of this section.

SEC. 206. ENERGY EFFICIENCY FOR DATA CENTER BUILDINGS.

Section 453(c)(1) of the Energy Independence and Security Act of 2007 (42 U.S.C. 17112(c)(1)) is amended by inserting "but not later than 2 years after the date of enactment of this Act" after "described in subsection (b)".

SEC. 207. COMMUNITY BUILDING CODE ADMINISTRATION GRANTS.

- (a) Grant Program Authorized.—
- (1) Grant authorization.—The Secretary of Housing and Urban Development shall to the extent amounts are made available for grants under this section provide grants to local building code enforcement departments.
- (2) COMPETITIVE AWARDS.—The Secretary shall award grants under paragraph (1) on a competitive basis taking into consideration the following:
- (A) The financial need of each building code enforcement department.
- (B) The benefit to the jurisdiction of having an adequately funded building code enforcement department.
- (C) The demonstrated ability of each building code enforcement department to work cooperatively with other local code enforcement offices, health departments, and local prosecutorial agencies.

- (3) MAXIMUM AMOUNT.—The maximum amount of any grant awarded under this subsection shall not exceed \$1,000,000.
- (4) COORDINATION.—The Secretary of Housing and Urban Development shall coordinate with the Secretary of Energy to ensure that any unnecessarily duplicative funding through grants under this section of activities otherwise funded through the Department of Energy is minimized or eliminated (b) REQUIRED ELEMENTS IN GRANT PRO-
- (b) REQUIRED ELEMENTS IN GRANT PROPOSALS.—In order to be eligible for a grant under subsection (a), a building code enforcement department of a jurisdiction shall submit to the Secretary the following:
- (1) A demonstration of the jurisdiction's needs in executing building code enforcement administration.
- (2) A plan for the use of any funds received from a grant under this section that addresses the needs discussed in paragraph (1) and that is consistent with the authorized uses established in subsection (c).
- (3) A plan for local governmental actions to be taken to establish and sustain local building code enforcement administration functions, without continuing Federal support, at a level at least equivalent to that proposed in the grant application.
- (4) A plan to create and maintain a program of public outreach that includes a regularly updated and readily accessible means of public communication, interaction, and reporting regarding the services and work of the building code enforcement department to be supported by the grant.
- (5) A plan for ensuring the timely and effective administrative enforcement of building safety and fire prevention violations.
 - (c) Use of Funds; Matching Funds.—
- (1) AUTHORIZED USES.—Amounts grants awarded under subsection (a) may be used by the grant recipient to supplement existing State or local funding for administration of building code enforcement, or to supplement allowance value received pursuant to this Act for implementation and enforcement of energy efficiency building codes. Such amounts may be used to increase staffing, provide staff training, increase staff competence and professional qualifications, or support individual certification or departmental accreditation, or for capital expenditures specifically dedicated to the administration of the building code enforcement department.
- (2) ADDITIONAL REQUIREMENT.—Each building code enforcement department receiving a grant under subsection (a) shall empanel a code administration and enforcement team consisting of at least 1 full-time building code enforcement officer, a city planner, and a health planner or similar officer.
 - (3) MATCHING FUNDS REQUIRED.—
- (A) IN GENERAL.—To be eligible to receive a grant under this section, a building code enforcement department shall provide matching, non-Federal funds in the following amount:
- (i) In the case of a building code enforcement department serving an area with a population of more than 50,000, an amount equal to not less than 50 percent of the total amount of any grant to be awarded under this section.
- (ii) In the case of a building code enforcement department serving an area with a population of between 20,001 and 50,000, an amount equal to not less than 25 percent of the total amount of any grant to be awarded under this section.
- (iii) In the case of a building code enforcement department serving an area with a population of less than 20,000, an amount equal to not less than 12.5 percent of the total amount of any grant to be awarded under this section.
- (B) ECONOMIC DISTRESS.—

- (i) IN GENERAL.—The Secretary may waive the matching fund requirements under subparagraph (A), and institute, by regulation, new matching fund requirements based upon the level of economic distress of the jurisdiction in which the local building code enforcement department seeking such grant is located.
- (ii) CONTENT OF REGULATIONS.—Any regulations instituted under clause (i) shall include—
- (I) a method that allows for a comparison of the degree of economic distress among the local jurisdictions of grant applicants, as measured by the differences in the extent of growth lag, the extent of poverty, and the adjusted age of housing in such jurisdiction; and
- (II) any other factor determined to be relevant by the Secretary in assessing the comparative degree of economic distress among such jurisdictions.
- (4) IN-KIND CONTRIBUTIONS.—In determining the non-Federal share required to be provided under paragraph (3), the Secretary shall consider in-kind contributions, not to exceed 50 percent of the amount that the department contributes in non-Federal funds.
- (5) WAIVER OF MATCHING REQUIREMENT.— The Secretary shall waive the matching fund requirements under paragraph (3) for any recipient jurisdiction that has dedicated all building code permitting fees to the conduct of local building code enforcement.
 - (d) Evaluation and Report.—
- (1) IN GENERAL.—Grant recipients under this section shall—
- (A) be obligated to fully account and report for the use of all grants funds; and
- (B) provide a report to the Secretary on the effectiveness of the program undertaken by the grantee and any other criteria requested by the Secretary for the purpose of indicating the effectiveness of, and ideas for, refinement of the grant program.
- (2) REPORT.—The report required under paragraph (1)(B) shall include a discussion of—
- (A) the specific capabilities and functions in local building code enforcement administration that were addressed using funds received under this section;
- (B) the lessons learned in carrying out the plans supported by the grant; and
- (C) the manner in which the programs supported by the grant are to be maintained by the grantee.
- (3) CONTENT OF REPORTS.—The Secretary shall—
- (A) require each recipient of a grant under this section to file interim and final reports under paragraph (2) to ensure that grant funds are being used as intended and to measure the effectiveness and benefits of the grant program; and
- (B) develop and maintain a means whereby the public can access such reports, at no cost, via the Internet.
- (e) DEFINITIONS.—For purposes of this section, the following definitions shall apply:
- (1) BUILDING CODE ENFORCEMENT.—The term "building code enforcement" means the enforcement of any code, adopted by a State or local government, that regulates the construction of buildings and facilities to mitigate hazards to life or property. Such term includes building codes, electrical codes, energy codes, fire codes, fuel gas codes, mechanical codes, and plumbing codes.
- (2) BUILDING CODE ENFORCEMENT DEPARTMENT.—The term "building code enforcement department" means an inspection or enforcement agency of a jurisdiction that is responsible for conducting building code enforcement.
- (3) JURISDICTION.—The term "jurisdiction" means a city, county, parish, city and county authority, or city and parish authority having local authority to enforce building

- codes and regulations and to collect fees for building permits.
- (4) SECRETARY.—The term "Secretary" means the Secretary of Housing and Urban Development.
- (f) AUTHORIZATION OF APPROPRIATIONS.—
- (1) IN GENERAL.—There are authorized to be appropriated \$20,000,000 for each of fiscal years 2010 through 2014 to the Secretary of Housing and Urban Development to carry out the provisions of this section.
- (2) RESERVATION.—From the amount made available under paragraph (1), the Secretary may reserve not more than 5 percent for administrative costs.
- (3) AVAILABILITY.—Any funds appropriated pursuant to paragraph (1) shall remain available until expended.

SEC. 208. SOLAR ENERGY SYSTEMS BUILDING PERMIT REQUIREMENTS FOR RECEIPT OF COMMUNITY DEVELOPMENT BLOCK GRANT FUNDS.

Section 104 of the Housing and Community Development Act of 1974 (42 U.S.C. 5304) is amended by adding at the end the following new subsection:

"(n) REQUIREMENTS FOR BUILDING PERMITS REGARDING SOLAR ENERGY SYSTEMS.—

"(1) IN GENERAL.—A grant under section 106 for a fiscal year may be made only if the grantee certifies to the Secretary that—

- "(A) in the case of a grant under section 106(a) for any Indian tribe or insular area, during such fiscal year the cost of any permit or license, for construction or installation of any solar energy system for any structure, that is required by the tribe or insular area or by any other unit of general local government or other political subdivision of such tribe or insular area, complies with paragraph (2):
- "(B) in the case of a grant under section 106(b) for any metropolitan city or urban county, during such fiscal year the cost of any permit or license, for construction or installation of any solar energy system for any structure, that is required by the metropolitan city or urban county, or by any other political subdivision of such city or county, complies with paragraph (2); and
- "(C) in the case of a grant under section 106(d) for any State, during such fiscal year the cost of any permit or license, for construction or installation of any solar energy system for any structure, that is required by the State, or by any other unit of general local government within any nonentitlement area of such State, or other political subdivision within any nonentitlement area of such State or such a unit of general local government, complies with paragraph (2).
- "(2) LIMITATION ON COST.—The cost of permit or license for construction or installation of any solar energy system complies with this paragraph only if such cost does not exceed the following amount:
- "(A) RESIDENTIAL STRUCTURES.—In the case of a structure primarily for residential use, \$500
- "(B) NONRESIDENTIAL STRUCTURES.—In the case of a structure primarily for nonresidential use, 1.0 percent of the total cost of the installation or construction of the solar energy system, but not in excess of \$10,000.
- "(3) NONCOMPLIANCE.—If the Secretary determines that a grantee of a grant made under section 106 is not in compliance with a certification under paragraph (1)—
- $\mbox{``(A)}$ the Secretary shall notify the grantee of such determination; and
- "(B) if the grantee has not corrected such noncompliance before the expiration of the 6-month period beginning upon notification under subparagraph (A), such grantee shall not be eligible for 5 percent of any amounts awarded under a grant under section 106 for the first fiscal year that commences after the expiration of such 6-month period.
- "(4) SOLAR ENERGY SYSTEM.—For purposes of this subsection, the term 'solar energy

system' means, with respect to a structure, equipment that uses solar energy to generate electricity for, or to heat or cool (or provide hot water for use in), such structure."

SEC. 209. PROHIBITION OF RESTRICTIONS ON RESIDENTIAL INSTALLATION OF SOLAR ENERGY SYSTEM.

- (a) REGULATIONS.—Within 180 days after the enactment of this Act, the Secretary of Housing and Urban Development, in consultation with the Secretary of Energy, shall issue regulations—
- (1) to prohibit any private covenant, contract provision, lease provision, homeowners' association rule or bylaw, or similar restriction, that impairs the ability of the owner or lessee of any residential structure designed for occupancy by 1 family to install, construct, maintain, or use a solar energy system on such residential property; and
- (2) to require that whenever any such covenant, provision, rule or bylaw, or restriction requires approval for the installation or use of a solar energy system, the application for approval shall be processed and approved by the appropriate approving entity in the same manner as an application for approval of an architectural modification to the property, and shall not be willfully avoided or delayed.
- (b) CONTENTS.—The regulations required under subsection (a) shall provide that—
- (1) such a covenant, provision, rule or bylaw, or restriction impairs the installation, construction, maintenance, or use of a solar energy system if it—
- (A) unreasonably delays or prevents installation, maintenance, or use;
- (B) unreasonably increases the cost of installation, maintenance, or use; or
 - (C) precludes use of such a system; and
- (2) any fee or cost imposed on the owner or lessee of such a residential structure by such a covenant, provision, rule or bylaw, or restriction shall be considered unreasonable if—
- (A) such fee or cost is not reasonable in comparison to the cost of the solar energy system or the value of its use; or
- (B) treatment of solar energy systems by the covenant, provision, rule or bylaw, or restriction is not reasonable in comparison with treatment of comparable systems by the same covenant, provision, rule or bylaw, or restriction.
- (c) SOLAR ENERGY SYSTEM.—For purposes of this section, the term "solar energy system" means, with respect to a structure, equipment that uses solar energy to generate electricity for, or to heat or cool (or provide hot water for use in), such structure.

Subtitle B—Lighting and Appliance Energy Efficiency Programs

SEC. 211. LIGHTING EFFICIENCY STANDARDS.

- (a) OUTDOOR LIGHTING.-
- (1) Definitions.—
- (A) Section 340(1) of the Energy Policy and Conservation Act (42 U.S.C. 6311(1)) is amended by striking subparagraph (L) and inserting the following:
 - '(L) Outdoor luminaires.
 - "(M) Outdoor high light output lamps.
- $\lq\lq(N)$ Any other type of industrial equipment which the Secretary classifies as covered equipment under section 341(b). $\lq\lq$.
- (B) Section 340 of the Energy Policy and Conservation Act (42 U.S.C. 6311) is amended as adding at the end the following:
- "(25) The term 'luminaire' means a complete lighting unit consisting of one or more light sources and ballast(s), together with parts designed to distribute the light, to position and protect such lamps, and to connect such light sources to the power supply.
- "(26) The term 'outdoor luminaire' means a luminaire that is listed as suitable for wet locations pursuant to Underwriters Laboratories Inc. standard UL 1598 and is labeled as

'Suitable for Wet Locations' consistent with section 410.4(A) of the National Electrical Code 2005, or is designed for roadway illumination and meets the requirements of Addendum A for IESNA TM-15-07: Backlight, Uplight, and Glare (BUG) Ratings, except for—

- "(A) luminaires designed for outdoor video display images that cannot be used in general lighting applications;
- "(B) portable luminaires designed for use at construction sites:
- "(C) luminaires designed for continuous immersion in swimming pools and other water features;
- "(D) seasonal luminaires incorporating solely individual lamps rated at 10 watts or less:
- "(E) luminaires designed to be used in emergency conditions that incorporate a means of charging a battery and a device to switch the power supply to emergency lighting loads automatically upon failure of the normal power supply:
- "(F) components used for repair of installed luminaries and that meet the requirements of section 342(h):
- "(G) a luminaire utilizing an electrode-less fluorescent lamp as the light source;
 - "(H) decorative gas lighting systems;
- "(I) luminaires designed explicitly for lighting for theatrical purposes, including performance, stage, film production, and video production;
- "(J) luminaires designed as theme elements in theme/amusement parks and that cannot be used in most general lighting applications;
- "(K) luminaires designed explicitly for vehicular roadway tunnels designed to comply with ANSI/IESNA RP-22-05:
- "(L) luminaires designed explicitly for hazardous locations meeting UL Standard 844;
 - "(M) searchlights;
- "(N) luminaires that are designed to be recessed into a building, and that cannot be used in most general lighting applications;
- "(O) a luminaire rated only for residential applications utilizing a light source or sources regulated under the amendments made by section 321 of the Energy Independence and Security Act of 2007 and with a light output no greater than 2,600 lumens;
- "(P) a residential pole-mounted luminaire that is not rated for commercial use utilizing a light source or sources meeting the efficiency requirements of section 231 of the Energy Independence and Security Act of 2007 and mounted on a post or pole not taller than 10.5 feet above ground and with a light output not greater than 2.600 lumens:
- "(Q) a residential fixture with E12 (Candelabra) bases that is rated for not more than 300 watts total: or
- $\ensuremath{^{\prime\prime}}(R)$ a residential fixture with medium screw bases that is rated for not more than 145 watts.
- "(27) The term 'outdoor high light outputlamp' means a lamp that—
- "(A) has a rated lumen output not less than 2601 lumens;
- "(B) is capable of being operated at a voltage not less than 110 volts and not greater than 300 volts, or driven at a constant current of 6.6 amperes;
- "(C) is not a Parabolic Aluminized Reflector lamp; and
- "(D) is not a J-type double-ended (T-3) halogen quartz lamp, utilizing R-7S bases, that is manufactured before January 1, 2015.
- "(28) The term 'outdoor lighting control' means a device incorporated in a luminaire that receives a signal, from either a sensor (such as an occupancy sensor, motion sensor, or daylight sensor) or an input signal (including analog or digital signals communicated through wired or wireless tech-

- nology), and can adjust the light level according to the signal.".
- (2) STANDARDS.— Section 342 of the Energy Policy and Conservation Act (42 U.S.C. 6313) is amended by adding at the end the following:
 - "(g) OUTDOOR LUMINAIRES.—
- "(1) Each outdoor luminaire manufactured on or after January 1, 2011, shall—
- "(A) have an initial luminaire efficacy of at least 50 lumens per watt; and
- "(B) be designed to use a light source with a lumen maintenance, calculated as mean rated lumens divided by initial lumens, of at least 0.6.
- "(2) Each outdoor luminaire manufactured on or after January 1, 2018, shall—
- "(A) have an initial luminaire efficacy of at least 70 lumens per watt; and
- "(B) be designed to use a light source with a lumen maintenance, calculated as mean rated lumens divided by initial lumens, of at least 0.6.
- "(3) In addition to the requirements of paragraphs (1) through (3), each outdoor luminaire manufactured on or after January 1, 2016, shall have the capability of producing at least two different light levels, including 100 percent and 60 percent of full lamp output as tested with the maximum rated lamp per UL1598 or the manufacturer's maximum specified for the luminaire under test, outdoor luminaires used for roadway lighting applications shall be exempt from the 2 light level requirements.
- "(4)(A) Not later than January 1, 2022, the Secretary shall issue a final rule amending the applicable standards established in paragraph (3) if technologically feasible and economically justified.
- "(B) A final rule issued under subparagraph (A) shall establish efficiency standards at the maximum level that is technically feasible and economically justified, as provided in subsections (o) and (p) of section 325. The Secretary may also, in such rulemaking, amend or discontinue the product exclusions listed in section 340(26)(A) through (P), or amend the lumen maintenance requirements in paragraph (2) if the Secretary determines that such amendments are consistent with the purposes of this Act.
- "(C) If the Secretary issues a final rule under subparagraph (A) establishing amended standards, the final rule shall provide that the amended standards apply to products manufactured on or after January 1, 2025, or one year after the date on which the final amended standard is published, whichever is later.
- "(h) OUTDOOR HIGH LIGHT OUTPUT LAMPS.— Each outdoor high light output lamp manufactured on or after January 1, 2017, shall have a lighting efficiency of at least 45 lumens per watt."
- (3) Test procedures.— Section 343(a) of the Energy Policy and Conservation Act (42 U.S.C. 6314(a)) is amended by adding at the end the following:
 - "(10) OUTDOOR LIGHTING.—
- "(A) With respect to outdoor luminaires and outdoor high light output lamps, the test procedures shall be based upon the test procedures specified in illuminating engineering society procedures LM-79 as of March 1, 2009, and LM-31, and/or other appropriate consensus test procedures developed by the Illuminating Engineering Society or other appropriate consensus standards bodies
- "(B) If illuminating engineering society procedure LM—79 is amended, the Secretary shall amend the test procedures established in subparagraph (A) as necessary to be consistent with the amended LM—79 test procedure, unless the Secretary determines, by rule, published in the Federal Register and supported by clear and convincing evidence,

- that to do so would not meet the requirements for test procedures under paragraph
- "(C) The Secretary may revise the test procedures for outdoor luminaires or outdoor high light output lamps by rule consistent with paragraph (2), and may incorporate as appropriate consensus test procedures developed by the Illuminating Engineering Society or other appropriate consensus standards bodies."
- (4) PREEMPTION.— Section 345 of the Energy Policy and Conservation Act (42 U.S.C. 6316) is amended by adding at the end the following:
- "(i)(1) Except as provided in paragraph (2), section 327 shall apply to outdoor luminaires to the same extent and in the same manner as the section applies under part B.
- "(2) Any State standard that is adopted on or before January 1, 2015, pursuant to a statutory requirement to adopt efficiency standards for reducing outdoor lighting energy use enacted prior to January 31, 2008, shall not be preempted.".
- (5) Energy efficiency standards for cer-TAIN LUMINAIRES.—Not later than 1 year after the date of enactment of this Act, the Secretary of Energy shall, in consultation with the National Electrical Manufacturers Association, collect data for United States sales of luminaires described in section 340(26)(H) and (M) of the Energy Policy and Conservation Act, to determine the historical growth rate. If the Secretary finds that growth in market share of such the luminaires exceeds twice the year to year rate of the average of the previous three years, then the Secretary shall within 12 months initiate a rulemaking to determine if such exclusion should be eliminated, if substitute products exist that perform more efficiently and fulfill the performance functions of these luminaires.
 - (b) PORTABLE LIGHTING.—
 - (1) PORTABLE LIGHT FIXTURES.—
- (A) DEFINITIONS.—Section 321 of the Energy Policy and Conservation Act (42 U.S.C. 6291) is amended by adding at the end the following:
- "(67) ART WORK LIGHT FIXTURE.—The term 'art work light fixture' means a light fixture designed only to be mounted directly to an art work and for the purpose of illuminating that art work.
- "(68) LED LIGHT ENGINE.—The term 'LED light engine' or 'LED light engine with integral heat sink' means a subsystem of an LED light fixture that—
- "(A) includes 1 or more LED components, including—
- "(i) an LED driver power source with electrical and mechanical interfaces; and
- "(ii) an integral heat sink to provide thermal dissipation; and
- "(B) may be designed to accept additional components that provide aesthetic, optical, and environmental control.
- "(69) LED LIGHT FIXTURE.—The term 'LED light fixture' means a complete lighting unit consisting of—
- "(A) an LED light source with 1 or more LED lamps or LED light engines; and
 - "(B) parts—
 - "(i) to distribute the light;
- "(ii) to position and protect the light source; and
- "(iii) to connect the light source to electrical power.
- "(70) LIGHT FIXTURE.—The term 'light fixture' means a product designed to provide light that includes—
 - "(A) at least 1 lamp socket; and
 - "(B) parts-
- "(i) to distribute the light;
- "(ii) position and protect 1 or more lamps; and

- "(iii) to connect 1 or more lamps to a power supply.
 - "(71) PORTABLE LIGHT FIXTURE.—
- "(A) IN GENERAL.—The term 'portable light fixture' means a light fixture that has a flexible cord and an attachment plug for connection to a nominal 120-volt circuit that—
- "(i) allows the user to relocate the product without any rewiring; and
- "(ii) typically can be controlled with a switch located on the product or the power cord of the product.
- "(B) EXCLUSIONS.—The term 'portable light fixture' does not include—
- "(i) direct plug-in night lights, sun or heat lamps, medical or dental lights, portable electric hand lamps, signs or commercial advertising displays, photographic lamps, germicidal lamps, or light fixtures for marine use or for use in hazardous locations (as those terms are defined in ANSI/NFPA 70 of the National Electrical Code): or
- "(ii) decorative lighting strings, decorative lighting outfits, or electric candles or candelabra without lamp shades that are covered by Underwriter Laboratories (UL) standard 588, 'Seasonal and Holiday Decorative Products'."
- (B) COVERAGE.—
- (i) IN GENERAL.—Section 322(a) of the Energy Policy and Conservation Act (42 U.S.C. 6292(a)) is amended—
- (I) by redesignating paragraph (20) as paragraph (24); and
- (II) by inserting after paragraph (19) the following:
- "(20) Portable light fixtures.".
- (ii) CONFORMING AMENDMENTS.—Section 325(1) of the Energy Policy and Conservation Act (42 U.S.C. 6295(1)) is amended by striking "paragraph (19)" each place it appears in paragraphs (1) and (2) and inserting "paragraph (24)".
- (C) TEST PROCEDURES.—Section 323(b) of the Energy Policy and Conservation Act (42 U.S.C. 6293(b)) is amended by adding at the end the following:
- "(19) LED FIXTURES AND LED LIGHT ENGINES.—Test procedures for LED fixtures and LED light engines shall be based on Illuminating Engineering Society of North America (IESNA) test procedure LM-79, Approved Method for Electrical and Photometric Testing of Solid-State Lighting Devices, and IESNA-approved test procedure for testing LED light engines."
- (D) STANDARDS.—Section 325 of the Energy Policy and Conservation Act (42 U.S.C. 6295) is amended—
- (i) by redesignating subsection (ii) as subsection (oo);
- (ii) in subsection (oo)(2), as redesignated in clause (i) of this subparagraph, by striking "(hh)" each place it appears and inserting "(mm)": and
- (iii) by inserting after subsection (hh) the following:
- "(ii) PORTABLE LIGHT FIXTURES.—
- "(1) IN GENERAL.—Subject to paragraphs (2) and (3), portable light fixtures manufactured on or after January 1, 2012, shall meet 1 or more of the following requirements:
- "(A) Be a fluorescent light fixture that meets the requirements of the Energy Star Program for Residential Light Fixtures, Version 4.2.
- "(B) Be equipped with only 1 or more GU-24 line-voltage sockets, not be rated for use with incandescent lamps of any type (as defined in ANSI standards), and meet the requirements of version 4.2 of the Energy Star program for residential light fixtures.
- "(C) Be an LED light fixture or a light fixture with an LED light engine and comply with the following minimum requirements:
- ``(i) Minimum light output: 200 lumens (initial).

- "(ii) Minimum LED light engine efficacy: 40 lumens/watt installed in fixtures that meet the minimum light fixture efficacy of 29 lumens/watt or, alternatively, a minimum LED light engine efficacy of 60 lumens/watt for fixtures that do not meet the minimum light fixture efficacy of 29 lumens/watt.
- "(iii) All portable fixtures shall have a minimum LED light fixture efficacy of 29 lumens/watt and a minimum LED light engine efficacy of 60 lumens/watt by January 1, 2016.
- "(iv) Color Correlated Temperature (CCT): 2700K through 4000K.
- ``(v) Minimum Color Rendering Index (CRI): 75.
- $\lq\lq(vi)$ Power factor equal to or greater than 0.70.
- "(vii) Portable luminaries that have internal power supplies shall have zero standby power when the luminaire is turned off.
- "(viii) LED light sources shall deliver at least 70 percent of initial lumens for at least 25,000 hours.
- "(D)(i) Be equipped with an ANSI-designated E12, E17, or E26 screw-based socket and be prepackaged and sold together with 1 screw-based compact fluorescent lamp or screw-based LED lamp for each screw-based socket on the portable light fixture.
- "(ii) The compact fluorescent or LED lamps prepackaged with the light fixture shall be fully compatible with any light fixture controls incorporated into the light fixture (for example, light fixtures with dimmers shall be packed with dimmable lamps).
- "(iii) Compact fluorescent lamps prepackaged with light fixtures shall meet the requirements of the Energy Star Program for CFLs Version 4.0.
- "(iv) Screw-based LED lamps shall comply with the minimum requirements described in subparagraph (C).
- "(E) Be equipped with 1 or more singleended, non-screw based halogen lamp sockets (line or low voltage), a dimmer control or high-low control, and be rated for a maximum of 100 watts.
- "(2) Review.—
- "(A) REVIEW.—The Secretary shall review the criteria and standards established under paragraph (1) to determine if revised standards are technologically feasible and economically justified.
- $\begin{tabular}{ll} ``(B) & COMPONENTS.— The review shall include consideration of— \\ \end{tabular}$
- "(i) whether a separate compliance procedure is still needed for halogen fixtures described in subparagraph (E) and, if necessary, what an appropriate standard for halogen fixtures shall be;
- "(ii) whether the specific technical criteria described in subparagraphs (A), (C), and (D)(iii) should be modified; and
- "(iii) which fixtures should be exempted from the light fixture efficacy standard as of January 1, 2016, because the fixtures are primarily decorative in nature (as defined by the Secretary) and, even if exempted, are likely to be sold in limited quantities.
- "(C) TIMING.-
- "(i) DETERMINATION.—Not later than January 1, 2014, the Secretary shall publish amended standards, or a determination that no amended standards are justified, under this subsection.
- "(ii) STANDARDS.—Any standards under this paragraph shall take effect on January 1, 2016.
- "(3) ART WORK LIGHT FIXTURES.—Art work light fixtures manufactured on or after January 1, 2012, shall—
- "(A) comply with paragraph (1); or
- "(B)(i) contain only ANSI-designated E12 screw-based line-voltage sockets;
 - "(ii) have not more than 3 sockets;

- "(iii) be controlled with an integral high/ low switch;
- "(iv) be rated for not more than 25 watts if fitted with 1 socket; and
- "(v) be rated for not more than 15 watts per socket if fitted with 2 or 3 sockets.
- "(4) EXCEPTION FROM PREEMPTION.—Notwithstanding section 327, Federal preemption shall not apply to a regulation concerning portable light fixtures adopted by the California Energy Commission on or before January 1, 2014."
 - (2) GU-24 BASE LAMPS.-
- (A) DEFINITIONS.—Section 321 of the Energy Policy and Conservation Act (42 U.S.C. 6291) (as amended by paragraph (1)(A)) is amended by adding at the end the following:
- "(72) GU-24.—The term 'GU-24 means the designation of a lamp socket, based on a coding system by the International Electrotechnical Commission, under which—
- "(A) 'G' indicates a holder and socket type with 2 or more projecting contacts, such as pins or posts;
- "(B) 'U' distinguishes between lamp and holder designs of similar type that are not interchangeable due to electrical or mechanical requirements; and
- "(C) 24 indicates the distance in millimeters between the electrical contact posts.
 - "(73) GU-24 ADAPTOR.—
- "(A) IN GENERAL.—The term 'GU-24 Adaptor' means a 1-piece device, pig-tail, wiring harness, or other such socket or base attachment that...
- "(i) connects to a GU-24 socket on 1 end and provides a different type of socket or connection on the other end; and
 - "(ii) does not alter the voltage.
- "(B) EXCLUSION.—The term 'GU-24 Adaptor' does not include a fluorescent ballast with a GU-24 base.
- "(74) GU-24 BASE LAMP.—'GU-24 base lamp' means a light bulb designed to fit in a GU-24 socket.".
- (B) STANDARDS.—Section 325 of the Energy Policy and Conservation Act (42 U.S.C. 6295) (as amended by paragraph (1)(D)) is amended by inserting after subsection (ii) the following:
 - "(jj) GU-24 BASE LAMPS.—
- "(1) IN GENERAL.—A GU-24 base lamp shall not be an incandescent lamp as defined by ANSI.
- "(2) GU-24 ADAPTORS.—GU-24 adaptors shall not adapt a GU-24 socket to any other line voltage socket.".
- (3) STANDARDS FOR CERTAIN INCANDESCENT REFLECTOR LAMPS.—Section 325(i) of the Energy Policy and Conservation Act (42 U.S.C. 6295(i)), as amended by section 161(a)(12) of this Act, is amended by adding at the end the following:
- "(9) CERTAIN INCANDESCENT REFLECTOR LAMPS.—(A) No later than 12 months after enactment of this paragraph, the Secretary shall publish a final rule establishing standards for incandescent reflector lamp types described in paragraph (1)(D). Such standards shall be effective on July 1, 2013.
- "(B) Any rulemaking for incandescent reflector lamps completed after enactment of this section shall consider standards for all incandescent reflector lamps, inclusive of those specified in paragraph (1)(C).
- "(10) REFLECTOR LAMPS.—No later than January 1, 2015, the Secretary shall publish a final rule establishing and amending standards for reflector lamps, including incandescent reflector lamps. Such standards shall be effective no sooner than three years after publication of the final rule. Such rule-making shall consider incandescent and non-incandescent technologies. Such rulemaking shall consider a new metric other than lumens-per-watt based on the photometric distribution of light from such lamps.".

SEC. 212. OTHER APPLIANCE EFFICIENCY STANDARDS.

- (a) STANDARDS FOR WATER DISPENSERS, HOT FOOD HOLDING CABINETS, AND PORTABLE ELECTRIC SPAS.—
- (1) DEFINITIONS.—Section 321 of the Energy Policy and Conservation Act (42 U.S.C. 6291), as amended by section 211 of this Act, is further amended by adding at the end the following:
- "(75) The term 'water dispenser' means a factory-made assembly that mechanically cools and heats potable water and that dispenses the cooled or heated water by integral or remote means.
- "(76) The term 'bottle-type water dispenser' means a drinking water dispenser designed for dispensing both hot and cold water that uses a removable bottle or container as the source of potable water.
- "(77) The term 'commercial hot food holding cabinet' means a heated, fully-enclosed compartment with one or more solid or glass doors that is designed to maintain the temperature of hot food that has been cooked in a separate appliance. Such term does not include heated glass merchandizing cabinets, drawer warmers, commercial hot food holding cabinets with interior volumes of less than 8 cubic feet, or cook-and-hold appliances.
- "(78) The term 'portable electric spa' means a factory-built electric spa or hot tub, supplied with equipment for heating and circulating water.".
- (2) COVERAGE.—Section 322(a) of the Energy Policy and Conservation Act (42 U.S.C. 6292(a)), as amended by section 211(b)(1)(B) of this Act, is further amended by inserting after paragraph (20) the following new paragraphs:
 - "(21) Bottle type water dispensers.
- "(22) Commercial hot food holding cabinets.
- "(23) Portable electric spas."
- (3) TEST PROCEDURES.—Section 323(b) of the Energy Policy and Conservation Act (42 U.S.C. 6293(b)), as amended by section 211(b)(1)(C) of this Act, is further amended by adding at the end the following:
- "(20) BOTTLE TYPE WATER DISPENSERS.— Test procedures for bottle type water dispensers shall be based on 'Energy Star Program Requirements for Bottled Water Coolers version 1.1' published by the Environmental Protection Agency. Units with an integral, automatic timer shall not be tested using section 4D, 'Timer Usage,' of the test criteria.
- "(21) COMMERCIAL HOT FOOD HOLDING CABINETS.—Test procedures for commercial hot food holding cabinets shall be based on the test procedures described in ANSI/ASTM F2140-01 (Test for idle energy rate-dry test). Interior volume shall be based on the method shown in the Environmental Protection Agency's 'Energy Star Program Requirements for Commercial Hot Food Holding Cabinets' as in effect on August 15, 2003.
- "(22) PORTABLE ELECTRIC SPAS.—Test procedures for portable electric spas shall be based on the test method for portable electric spas contained in section 1604, title 20, California Code of Regulations as amended on December 3, 2008. When the American National Standards Institute publishes a test procedure for portable electric spas, the Secretary shall revise the Department of Energy's procedure."
- (4) STANDARDS.—Section 325 of the Energy Policy and Conservation Act (42 U.S.C. 6295), as amended by section 211 of this Act, is further amended by adding after subsection (jj) the following:
- "(kk) BOTTLE TYPE WATER DISPENSERS.— Effective January 1, 2012, bottle-type water dispensers designed for dispensing both hot and cold water shall not have standby energy

- consumption greater than 1.2 kilowatt-hours per day.
- "(11) COMMERCIAL HOT FOOD HOLDING CABINETS.—Effective January 1, 2012, commercial hot food holding cabinets with interior volumes of 8 cubic feet or greater shall have a maximum idle energy rate of 40 watts per cubic foot of interior volume.
- "(mm) PORTABLE ELECTRIC SPAS.—Effective January 1, 2012, portable electric spas shall not have a normalized standby power greater than 5(V2\%) Watts where V=the fill volume in gallons.
- "(nn) REVISIONS.—The Secretary of Energy shall consider revisions to the standards in subsections (kk), (ll), and (mm) in accordance with subsection (o) and publish a final rule no later than January 1, 2013 establishing such revised standards, or make a finding that no revisions are technically feasible and economically justified. Any such revised standards shall take effect January 1, 2016."
- (b) COMMERCIAL FURNACE EFFICIENCY STANDARDS.—Section 342(a) of the Energy Policy and Conservation Act (42 U.S.C. 6312(a)) is amended by inserting after paragraph (10) the following new paragraph:
- "(11) WARM AIR FURNACES.—Each warm air furnace with an input rating of 225,000 Btu per hour or more and manufactured after January 1, 2011, shall meet the following standard levels:
 - "(A) GAS-FIRED UNITS.-
- "(i) Minimum thermal efficiency of 80 percent.
- "(ii) Include an interrupted or intermittent ignition device.
- "(iii) Have jacket losses not exceeding 0.75 percent of the input rating.
- "(iv) Have either power venting or a flue damper.
- "(B) OIL-FIRED UNITS.—
- "(i) Minimum thermal efficiency of 81 percent.
- "(ii) Have jacket losses not exceeding 0.75 percent of the input rating.
- "(iii) Have either power venting or a flue damper.".

SEC. 213. APPLIANCE EFFICIENCY DETERMINATIONS AND PROCEDURES.

- (a) Definition of Energy Conservation STANDARD.—Section 321(6) of the Energy Policy and Conservation Act (42 U.S.C. 6291(6)) is amended to read as follows:
- "(6) Energy conservation standard.
- "(A) IN GENERAL.—The term 'energy conservation standard' means 1 or more performance standards that—
- "(i) for covered products (excluding clothes washers, dishwashers, showerheads, faucets, water closets, and urinals), prescribe a minimum level of energy efficiency or a maximum quantity of energy use, determined in accordance with test procedures prescribed under section 323;
- "(ii) for showerheads, faucets, water closets, and urinals, prescribe a minimum level of water efficiency or a maximum quantity of water use, determined in accordance with test procedures prescribed under section 323; and
- "(iii) for clothes washers and dishwashers—
- "(I) prescribe a minimum level of energy efficiency or a maximum quantity of energy use, determined in accordance with test procedures prescribed under section 323; and
- "(II) may include a minimum level of water efficiency or a maximum quantity of water use, determined in accordance with those test procedures.
- "(B) INCLUSIONS.—The term 'energy conservation standard' includes—
- "(i) 1 or more design requirements, if the requirements were established—
- "(I) on or before the date of enactment of this subclause;

- "(II) as part of a direct final rule under section 325(p)(4); or
- "(III) as part of a final rule published on or after January 1, 2012, and
- "(ii) any other requirements that the Secretary may prescribe under section 325(r).
- "(C) EXCLUSION.—The term 'energy conservation standard' does not include a performance standard for a component of a finished covered product, unless regulation of the component is specifically authorized or established pursuant to this title."

 (b) ADOPTING CONSENSUS TEST PROCEDURES
- (b) ADOPTING CONSENSUS TEST PROCEDURES AND TEST PROCEDURES IN USE ELSEWHERE.—Section 323(b) of the Energy Policy and Conservation Act (42 U.S.C. 6293(b)), as amended by sections 211 and 212 of this Act, is further amended by adding the following new paragraph after paragraph (22):
- ``(23) Consensus and alternate test procedures.—
- "(A) RECEIPT OF JOINT RECOMMENDATION OR ALTERNATE TESTING PROCEDURE.—On receipt of—
- "(i) a statement that is submitted jointly by interested persons that are fairly representative of relevant points of view (including representatives of manufacturers of covered products, States, and efficiency advocates), as determined by the Secretary, and contains recommendations with respect to the testing procedure for a covered product: or
- "(ii) a submission of a testing procedure currently in use for a covered product by a State, nation, or group of nations—
- "(I) if the Secretary determines that the recommended testing procedure contained in the statement or submission is in accordance with subsection (b)(3), the Secretary may issue a final rule that establishes an energy or water conservation testing procedure that is published simultaneously with a notice of proposed rulemaking that proposes a new or amended energy or water conservation testing procedure that is identical to the testing procedure established in the final rule to establish the recommended testing procedure (referred to in this paragraph as a 'direct final rule'): or
- "(II) if the Secretary determines that a direct final rule cannot be issued based on the statement or submission, the Secretary shall publish a notice of the determination, together with an explanation of the reasons for the determination.
- "(B) PUBLIC COMMENT.—The Secretary shall solicit public comment for a period of at least 110 days with respect to each direct final rule issued by the Secretary under subparagraph (A)(ii)(I).
- "(C) WITHDRAWAL OF DIRECT FINAL RULES.—
 "(i) IN GENERAL.—Not later than 120 days
- after the date on which a direct final rule issued under subparagraph (A)(ii)(I) is published in the Federal Register, the Secretary shall withdraw the direct final rule if—
- "(I) the Secretary receives 1 or more adverse public comments relating to the direct final rule under subparagraph (B)or any alternative joint recommendation; and
- "(II) based on the rulemaking record relating to the direct final rule, the Secretary determines that such adverse public comments or alternative joint recommendation may provide a reasonable basis for withdrawing the direct final rule under paragraph (3) or any other applicable law.
- (ii) ACTION ON WITHDRAWAL.—On withdrawal of a direct final rule under clause (i), the Secretary shall—
- "(I) proceed with the notice of proposed rulemaking published simultaneously with the direct final rule as described in subparagraph (A)(ii)(I); and
- "(II) publish in the Federal Register the reasons why the direct final rule was withdrawn.

- "(iii) TREATMENT OF WITHDRAWN DIRECT FINAL RULES.—A direct final rule that is withdrawn under clause (i) shall not be considered to be a final rule for purposes of subsection (b).
- "(D) EFFECT OF PARAGRAPH.—Nothing in this paragraph authorizes the Secretary to issue a direct final rule based solely on receipt of more than 1 statement containing recommended test procedures relating to the direct final rule."
- (c) UPDATING TELEVISION TEST METHODS.— Section 323(b) of the Energy Policy and Conservation Act (42 U.S.C. 6293(b)), as amended by sections 211 and 212 of this Act, and subsection (b) of this section, is further amended by adding at the end the following new paragraph:
- "(24) TELEVISIONS.—(A) On the date of enactment of this paragraph, Appendix H to Subpart B of Part 430 of the United States Code of Federal Regulations, 'Uniform Test Method for Measuring the Energy Consumption of Television Sets', is repealed.
- "(B) No later than 12 months after the date of enactment of this paragraph the Secretary shall publish in the Federal Register a final rule prescribing a new test method for televisions.".
- (d) CRITERIA FOR PRESCRIBING NEW OR AMENDED STANDARDS.—(1) Section 325(0)(2)(B)(i) of the Energy Policy and Conservation Act (42 U.S.C. 6295(0)(2)(B)(i)) is amended as follows:
- (A) By striking "and" at the end of subclause (VI).
- (B) By redesignating subclause (VII) as subclause (XI).
- (C) By inserting the following new subclauses after subclause (VI):
- "(VII) the estimated value of the carbon dioxide and other emission reductions that will be achieved by virtue of the higher energy efficiency of the covered products resulting from the imposition of the standard:
- "(VIII) the estimated impact of standards for a particular product on average consumer energy prices;
- "(IX) the increased energy efficiency that may be attributable to the installation of Smart Grid technologies or capabilities in the covered products, if applicable in the determination of the Secretary:
- "(X) the availability in the United States or in other nations of examples or prototypes of covered products that achieve significantly higher efficiency standards for energy or for water: and".
- (2) Section 325(o)(2)(B)(iii) of such Act is amended as follows:
- (A) By striking "three" and inserting "5".
- (B) By inserting after the first sentence the following "For products with an average expected useful life of less than 5 years, such rebuttable presumption shall be determined utilizing 75 percent of the product's average expected useful life as a multiplier instead of 5.".
- (C) By striking the last sentence and inserting the following: "Such a presumption may be rebutted only if the Secretary finds, based on clear, convincing, and reliable evidence, that—
- "(I) such standard level would cause serious and unavoidable hardship to the average consumer of the product, or to manufacturers supplying a significant portion of the market for the product, that substantially outweighs the standard level's benefits;
- "(II) the standard and implementing regulations cannot be designed to avoid or mitigate the hardship identified under subclause (I), through the adoption of regional standards consistent with paragraph (6) of this subsection, or other reasonable means consistent with this part;
- "(III) the same or substantially similar hardship would not occur under a standard

- adopted in the absence of the presumption, but that otherwise meets the requirements of this section; and
- "(IV) the hardship cannot be avoided or mitigated pursuant the procedures specified in section 504 of the Department of Energy Organization Act (42 U.S.C. 7194).
- A determination by the Secretary that the criteria triggering such presumption are not met, or that the criterion for rebutting the presumption are met shall not be taken into consideration in the Secretary's determination of whether a standard is economically justified."
- (e) OBTAINING APPLIANCE INFORMATION FROM MANUFACTURERS.—Section 326(d) of the Energy Policy and Conservation Act (42 U.S.C. 6295(d)) is amended to read as follows:
- "'(d) INFORMATION REQUIREMENTS.—(1) For purposes of carrying out this part, the Secretary shall publish proposed regulations not later than one year after the date of enactment of the American Clean Energy and Security Act of 2009, and after receiving public comment, final regulations not later than 18 months from such date of enactment under this part or other provision of law administered by the Secretary, which shall require each manufacturer of a covered product to submit information or reports to the Secretary on an annual basis in a form adopted by the Secretary. Such reports shall include information or data with respect to—
- "(A) the manufacturers' compliance with all requirements applicable pursuant to this part:
- "(B) the economic impact of any proposed energy conservation standard;
- "(C) the manufacturers' annual shipments of each class or category of covered products, organized, to the maximum extent practicable by—
- "(i) energy efficiency, energy use, and, if applicable, water use;
- "(ii) the presence or absence of such efficiency related or energy consuming operational characteristics or components as the Secretary determines are relevant for the purposes of carrying out this part; and
- "(iii) the State or regional location of sale, for covered products for which the Secretary may adopt regional standards; and
- "(D) such other categories of information as the Secretary deems relevant to carry out this part, including such other information as may be necessary to establish and revise test procedures, labeling rules, and energy conservation standards and to insure compliance with the requirements of this part.
- "(2) In adopting regulations under this subsection, the Secretary shall consider existing public sources of information, including nationally recognized certification programs of trade associations.
- "(3) The Secretary shall exercise authority under this section in a manner designed to minimize unnecessary burdens on manufacturers of covered products.
- "(4) To the extent that they do not conflict with the duties of the Secretary in carrying out this part, the provisions of section 11(d) of the Energy Supply and Environmental Coordination Act of 1974 (15 U.S.C. 796(d)) shall apply with respect to information obtained under this subsection to the same extent and in the same manner as they apply with respect to other energy information obtained under such section."
- (f) STATE WAIVER.—Section 327(c) of the Energy Policy and Conservation Act (42 U.S.C. 6297(c)), as amended by section 161(a)(19) of this Act, is further amended by adding at the end the following:
- "(12) is a regulation concerning standards for hot food holding cabinets, drinking water dispensers and portable electric spas adopted by the California Energy Commission on or before January 1, 2013.".

- (g) WAIVER OF FEDERAL PREEMPTION.— Paragraph (1) of section 327(d) of the Energy Policy and Conservation Act (42 U.S.C. 6297(d)) is amended as follows:
- (1) In subparagraph (A) by striking "State regulation" each place it appears and inserting "State statute or regulation".
- (2) In subparagraph (B) by adding at the end the following new sentence: "In making such a finding, the Secretary may not reject a petition for failure of the petitioning State or river basin commission to produce confidential information maintained by any manufacturer or distributor, or group or association of manufacturers or distributors, and which the petitioning party does not have the legal right to obtain."
- (3) In clause (ii) of subparagraph (C) by striking "costs" each place it appears and inserting "estimated costs".
- (4) In subparagraph (C) by striking "within the context of the State's energy plan and forecast, and,".
- (h) INCLUSION OF CARBON OUTPUT ON APPLIANCE "ENERGYGUIDE" LABELS.—(1) Section 324(a)(2) of the Energy Policy and Conservation Act (42 U.S.C. 6294(a)(2)) is amended by adding the following at the end:
- "(I)(i) Not later than 90 days after the date of enactment of this subparagraph, the Commission shall initiate a rulemaking to implement the additional labeling requirements specified in subsection (c)(1)(C) of this section with an effective date for the revised labeling requirement not later than 12 months from issuance of the final rule.
- "(ii) Not later than 24 months after the date of enactment of this subparagraph, the Commission shall complete the rulemaking initiated under clause (i).
- "(iii) Not later than 90 days after issuance of the final rule as provided in this subparagraph, the Secretary shall issue calculation methods required to effectuate the labeling requirements specified in subsection (c)(1)(C) of this section "
- (2) Section 324(c)(1) of the Energy Policy and Conservation Act (42 U.S.C. 6294(c)(1)) is amended—
- (A) by striking "and" at the end of sub-paragraph (A);
- (B) by striking the period at the end of subparagraph (B) and inserting a semicolon; and
- (C) by adding at the end the following new subparagraphs:
- "(C) for products or groups of products providing a comparable function (including the group of products comprising the heating function of heat pumps and furnaces) among covered products listed in paragraphs (3), (4), (5), (8), (9), (10), and (11) of section 322(a) of this part, and others designated by the Secretary, the estimated total annual atmospheric carbon dioxide emissions (or their equivalent in other greenhouse gases) associated with, or caused by, the product, calculated utilizing—
- "(i) national average energy use for the product including energy consumed at the point of end use based on test procedures developed under section 323 of this part;
- "(ii) national average energy consumed or lost in the production, generation, transportation, storage, and distribution of energy to the point of end use; and
- "(iii) any direct emissions of greenhouse gases from the product during normal use;
- "(D) in determining the national average energy consumption and total annual atmospheric carbon dioxide emissions, the Secretary shall utilize Federal Government sources, including the Energy Information Administration Annual Energy Review, the Environmental Protection Agency eGRID data base, Environmental Protection Agency AP-42 Emission Factors as amended, and other sources determined to be appropriate by the Secretary; and

- "(E) information presenting, for each product (or group of products providing the comparable function) identified in section (c)(1)(C) of this section, the estimated annual carbon dioxide emissions calculated within the range of emissions calculated for all models of the product or group according to its function, including those models consuming fuels and those models not consuming fuels."
- (i) PERMITTING STATES TO SEEK INJUNCTIVE ENFORCEMENT.—(1) Section 334 of the Energy Policy and Conservation Act (42 U.S.C. 6304) is amended to read as follows:

"SEC. 334. JURISDICTION AND VENUE.

- "(a) JURISDICTION.—The United States district courts shall have jurisdiction to restrain—
 - "(1) any violation of section 332; and
- "(2) any person from distributing in commerce any covered product which does not comply with an applicable rule under section 324 or 325.
- "(b) AUTHORITY.—Any action referred to in subsection (a) shall be brought by the Commission or by the attorney general of a State in the name of the State, except that.—
- "(1) any such action to restrain any violation of section 332(a)(3) which relates to requirements prescribed by the Secretary or any violation of section 332(a)(4) which relates to request of the Secretary under section 326(b)(2) shall be brought by the Secretary; and
- "(2) any violation of section 332(a)(5) or 332(a)(7) shall be brought by the Secretary or by the attorney general of a State in the name of the State.
- "(c) VENUE AND SERVICE OF PROCESS.—Any such action may be brought in the United States district court for a district wherein any act, omission, or transaction constituting the violation occurred, or in such court of the district wherein the defendant is found or transacts business. In any action under this section, process may be served on a defendant in any other district in which the defendant resides or may be found.".
- (2) The item relating to section 334 in the table of contents for such Act is amended to read as follows:
- "Sec. 334. Jurisdiction and venue.".
- (j) TREATMENT OF APPLIANCES WITHIN BUILDING CODES.—(1) Section 327(f)(3) of the Energy Policy and Conservation Act (42 U.S.C. 6297(f)(3)) is amended by striking subparagraphs (B) through (G) and inserting the following:
- "(B) The code meets at least one of the following requirements:
- "(i) The code does not require that the covered product have an energy efficiency exceeding—
- "(I) the applicable energy conservation standard established in or prescribed under section 325;
- "(II) the level required by a regulation of that State for which the Secretary has issued a rule granting a waiver under subsection (d) of this section; or
- "(III) the required level established in the International Energy Conservation Code or in a standard of the American Society of Heating, Refrigerating and Air-Conditioning Engineers, or by the Secretary pursuant to section 304 of the Energy Conservation and Production Act.
- "(ii) If the code uses one or more baseline building designs against which all submitted building designs are to be evaluated and such baseline building designs contain a covered product subject to an energy conservation standard established in or prescribed under section 325, the baseline building designs are based on an efficiency level for such covered product which meets but does not exceed one of the levels specified in clause (i).

- "(iii) If the code sets forth one or more optional combinations of items which meet the energy consumption or conservation objective, in at least one combination that the State has found to be reasonably achievable using commercially available technologies the efficiency of the covered product meets but does not exceed one of the levels specified in clause (i).
- "(C) The credit to the energy consumption or conservation objective allowed by the code for installing covered products having energy efficiencies exceeding one of the levels specified in subparagraph (B)(i) is on a one-for-one equivalent energy use or equivalent energy cost basis, taking into account the typical lifetime of the product.
- "(D) The energy consumption or conservation objective is specified in terms of an estimated total consumption of energy (which may be calculated from energy loss- or gainbased codes) utilizing an equivalent amount of energy (which may be specified in units of energy or its equivalent cost) and equivalent lifetimes.
- "(E) The estimated energy use of any covered product permitted or required in the code, or used in calculating the objective, is determined using the applicable test procedures prescribed under section 323, except that the State may permit the estimated energy use calculation to be adjusted to reflect the conditions of the areas where the code is being applied if such adjustment is based on the use of the applicable test procedures prescribed under section 323 or other technically accurate documented procedure."
- (2) Section 327(f)(4)(B) of the Energy Policy and Conservation Act (42 U.S.C. 6297(f)(4)(B)) is amended to read as follows:
- "(B) If a building code requires the installation of covered products with efficiencies exceeding the levels and requirements specified in paragraph (3)(B), such requirement of the building code shall not be applicable unless the Secretary has granted a waiver for such requirement under subsection (d) of this section"

SEC. 214. BEST-IN-CLASS APPLIANCES DEPLOY-MENT PROGRAM.

- (a) IN GENERAL.—Not later than 1 year after the date of enactment of this Act, the Secretary of Energy, in consultation with the Administrator, shall establish a program to be known as the "Best-in-Class Appliances Deployment Program" to—
- (1) provide bonus payments to retailers or distributors under subsection (c) for sales of best-in-class high-efficiency household appliance models, high-efficiency installed building equipment, and high-efficiency consumer electronics, with the goal of reducing lifecycle costs for consumers, encouraging innovation, and maximizing energy savings and public benefit;
- (2) provide bounties under subsection (d) to retailers and manufacturers for the replacement, retirement, and recycling of old, inefficient, and environmentally harmful products; and
- (3) provide premium awards under subsection (e) to manufacturers for developing and producing new Superefficient Best-in-Class Products.
- (b) DESIGNATION OF BEST-IN-CLASS PRODUCT MODELS.—
- (1) IN GENERAL.—The Secretary of Energy shall designate product models of appliances, equipment, or electronics as Best-in-Class Product models. The Secretary shall publicly announce the Best-in-Class Product models designated under this subsection. The Secretary shall define product classes broadly and, except as provided in paragraph (2), shall designate as Best-in-Class Product models no more than the most efficient 10 percent of the commercially available product models in a class that demonstrate, as a

- group, a distinctly greater energy efficiency than the average energy efficiency of that class of appliances, equipment, or electronics. In designating models, the Secretary shall—
- (A) identify commercially available models in the relevant class of products;
- (B) identify the subgroup of those models that share the distinctly higher energy-efficiency characteristics that warrant designation as best-in-class; and
- (C) add other models in that class to the list of Best-in-Class Product models as they demonstrate their ability to meet the higher-efficiency characteristics on which the designation was made.
- (2) PERCENTAGE EXCEPTION.—If there are fewer than 10 product models in a class of products, the Secretary may designate one or more of such models as Best-in-Class Products
- (3) REVIEW OF BEST-IN-CLASS STANDARDS.— The Secretary shall review annually the product-specific criteria for designating, and the product models that qualify as, Best-in-Class Products and, after notice and a 30-day comment period, make upwards adjustments in the efficiency criteria as necessary to maintain an appropriate ratio of such product models to the total number of product models in the product class.
- (4) SMART GRID ENERGY EFFICIENCY SAVINGS.—The Secretary shall include energy efficiency savings achieved by a commercially available product having smart grid capability in determining the efficiency level of a product for purposes of a Best-In-Class Product designation pursuant to this subsection. In measuring energy efficiency savings achieved by smart grid capability, the Secretary shall use a metric that—
- (A) is based on the time-differentiated value and amount of energy consumption;
- (B) accounts for the capability of the product to respond to a smart grid in which the physical capability of the product to save or delay energy because of a smart grid feature is weighted by the likelihood that the feature will be used;
- (C) is based on the value of a unit of electric or gas consumption as a function of time of day and season; and
- (D) includes a test method by which the manufacturer shall determine the energy efficiency of smart grid capable products.
- (c) Bonuses for Sales of Best-in-Class Products.—
- (1) IN GENERAL.—The Secretary of Energy shall make bonus payments to retailers or, as provided in paragraph (5)(B), distributors for the sale of Best-in-Class Products.
- (2) BONUS PROGRAM.—The Secretary shall—(A) publicly announce the availability and amount of the bonus to be paid for each sale of a Best-in-Class Product of a model designated under subsection (b); and
- (B) make bonus payments in at least that amount for each Best-in-Class Product of that model sold during the 3-year period beginning on the date the model is designated under subsection (b).
- (3) UPGRADE OF BEST-IN-CLASS PRODUCT ELI-GIBILITY.—In conducting a review under subsection (b)(3), the Secretary shall—
- (A) consider designating as a Best-in-Class Product model a Superefficient Best-in-Class Product model that has been designated pursuant to subsection (e);
- (B) announce any change in the bonus payment as necessary to increase the market share of Best-in-Class Product models;
- (C) list models that will be eligible for bonuses in the new amount; and
- (D) continue paying bonus payments at the original level, for the sale of any models that previously qualified as Best-in-Class Products but do not qualify at the new level, for

the remainder of the 3-year period announced with the original designation.

- (4) SIZE OF INDIVIDUAL BONUS PAYMENTS.—
 (A) The size of each bonus payment under this subsection shall be the product of—
- (i) an amount determined by the Secretary; and
- (ii) the difference in energy consumption between the Best-in-Class Product and the average product in the product class.
- (B) The Secretary shall determine the amount under subparagraph (A)(i) for each product type, in consultation with State and utility efficiency program administrators as well as the Administrator, based on estimates of the amount of bonus payment that would provide significant incentive to increase the market share of Best-in-Class Products.
- (5) ELIGIBLE BONUS RECIPIENT.—(A) The Secretary shall ensure that not more than 1 bonus payment is provided under this subsection for each Best-in-Class Product.
- (B) The Secretary may make distributors eligible to receive bonus payments under this subsection for sales that are not to the final end-user, to the extent that the Secretary determines that for a particular product category distributors are well situated to increase sales of Best-in-Class Products.
- (d) BOUNTIES FOR REPLACEMENT, RETIRE-MENT, AND RECYCLING OF EXISTING LOW-EFFI-CIENCY PRODUCTS.—
- (1) IN GENERAL.—The Secretary of Energy shall make bounty payments to—
- (A) retailers for the replacement, retirement, and recycling of older operating low-efficiency products that might otherwise continue in operation; and
- (B) manufacturers of Superefficient Bestin-Class Products for the retirement and recycling of older operating low-efficiency products that perform the same function and which might otherwise continue in operation
- (2) BOUNTIES.—Bounties shall be payable—(A) to a retailer upon documentation that
- (A) to a retailer upon documentation that the sale of a Best-in-Class Product was accompanied by the replacement, retirement, and recycling of—
- (i) an inefficient but still-functioning product; or
- (ii) a nonfunctioning product containing a refrigerant, by the consumer to whom the Best-in-Class Product was sold; and
- (B) to a manufacturer upon documentation of the retirement and recycling of— $\,$
- (i) an inefficient but still-functioning product from a consumer to whom a Superefficient Best-in-Class Product was delivered; or
- (ii) a nonfunctioning product containing a refrigerant from a consumer to whom a Superefficient Best-in-Class Product was delivered.
 - (3) AMOUNT.—
- (A) FUNCTIONING PRODUCTS.—The bounty payment payable under this subsection for a product described in paragraphs (2)(A)(i) and (2)(B)(i) shall be based on the difference between the estimated energy use of the product replaced and the energy use of an average new product in the product class, over the estimated remaining lifetime of the product that was replaced.
- (B) NONFUNCTIONING PRODUCTS CONTAINING REFRIGERANTS.—The bounty payment payable under this subsection for a product described in paragraphs (2)(A)(ii) and (2)(B)(ii) shall be in the amount that the Secretary of Energy, in consultation with the Administrator, determines is sufficient to promote the recycling of such products, up to the amount of bounty for a comparable product described in paragraphs (2)(A) and (2)(B).
- (4) RETIREMENT.—The Secretary shall ensure that no product for which a bounty is paid under this subsection is returned to ac-

tive service, but that it is instead destroyed, and recycled to the extent feasible.

- (5) RECYCLING APPLIANCES CONTAINING RE-FRIGERANTS.—Exclusively for the purpose of implementing the bounty payment program for products containing a refrigerant under this section, the Administrator shall establish standards for environmentally responsible methods of recycling and disposal of refrigerant-containing appliances that, at a minimum, meet the requirements set by the Responsible Appliance Disposal (RAD) Program for refrigerant disposal. The Secretary shall ensure that such standards are met before a bounty payment is made under this subsection for a product containing a refrigerant. Nothing in this section shall be interpreted to alter the requirements of section 608 of the Clean Air Act or to relieve any person from complying with those require-
- ments.
 (e) Premium Awards for Development and Production of Superefficient Best-in-Class Products.—
- (1) In GENERAL.—(A) The Secretary of Energy shall provide premium awards to manufacturers for the development and production of Superefficient Best-in-Class Products. The Secretary shall set and periodically revise standards for eligibility of products for designation as a Superefficient Best-in-Class Product.
- (B) The Secretary may establish a standard for a Superefficient Best-in-Class Product even if no product meeting that standard exists, if the Secretary has reasonable grounds to conclude that a mass-producible product could be made to meet that standard.
- (C) The Secretary may also establish a Superefficient Best-in-Class Product standard that is met by one or more existing Bestin-Class Product models, if those product models have distinct energy efficiency attributes and performance characteristics that make them significantly better than other product models qualifying as best-in-The Secretary may not designate as class. Superefficient Best-in-Class Products under this subparagraph models that represent more than 10 percent of the currently qualifying Best-in-Class Product models. subparagraph shall not apply to products designated pursuant to paragraph (4)(A).
- (D) In making its finding on the efficiency level a product can achieve for purposes of a Superefficient Best-In-Class Product designation pursuant to this paragraph, the Secretary shall include energy efficiency savings that would be achieved by a product as a result of smart grid capability when a product having such capability can be produced and sold commercially to mass market consumers. In measuring energy efficiency savings achieved by smart grid capability, the Secretary shall use a metric that—
- (i) is based on the time-differentiated value and amount of energy consumption;
- (ii) accounts for the capability of the product to respond to a smart grid in which the physical capability of the product to save or delay energy because of a smart grid feature is weighted by the likelihood that the feature will be used;
- (iii) is based on the value of a unit of electric or gas consumption as a function of time of day and season; and
- (iv) includes a test method by which the manufacturer shall determine the energy efficiency of smart grid capable products.
- (2) PREMIUM AWARDS.—(A) The premium award payment provided to a manufacturer under this subsection shall be in addition to any bonus payments made under subsection (c)
- (B) The amount of the premium award paid per unit of Superefficient Best-in-Class Products sold to retailers or distributors shall,

- except as provided by subparagraph (F), be the product of—
- (i) an amount determined by the Secretary; and
- (ii) the difference in energy consumption between the Superefficient Best-in-Class Product and the average product in the product class.
- (C) The Secretary shall determine the amount under subparagraph (B)(i) for each product type, in consultation with State and utility efficiency program administrators as well as the Administrator, based on consideration of the present value to the Nation of the energy (and water or other resources or inputs) saved over the useful life of the product. The Secretary may also take into consideration the methods used to increase sales of qualifying products in determining such amount.
- (D) The Secretary may adjust the value described in subparagraph (C) upward or downward as appropriate, including based on the effect of the premium awards on the sales of products in different classes that may be affected by the program under this subsection.
- (E) Premium award payments shall be applied to sales of any Superefficient Best-in-Class Product for the first 3 years after designation as a Superefficient Best-in-Class Product.
- (F) For years 2011 through 2013, the Secretary shall make bonus payments to manufacturers of the products designated in paragraph (4)(A) for each product produced in the following amounts:
 - (i) \$75 for each dishwasher.
 - (ii) \$250 for each clothes washer.
- (iii) \$200 for each refrigerator or refrigerator-freezer.
 - (iv) \$250 for each clothes dryer.
 - (v) \$200 for each cooking product.
- (vi) \$300 for each water heater.
- (3) COORDINATION OF INCENTIVES.—No product for which Federal tax credit is received under section 45M of the Internal Revenue Code of 1986 shall be eligible to receive premium award payments pursuant to this subsection.
 - (4) Designations.—
- (A) INITIAL DESIGNATIONS.—Notwithstanding any other provisions of this section, the products the Secretary shall designate as a Superefficient Best-In-Class Product include, but are not limited to, the following products manufactured in 2011 through 2013:
- (i) A dishwasher, clothes washer, refrigerator, or refrigerator-freezer that meets the highest efficiency performance standards in its product category as provided in Section 305(b) of the Emergency Economic Stabilization Act of 2008 and has the smart grid capability specified in paragraph (5).
- (ii) A water heater that meets an efficiency standard that is the same or equivalent to the standard provided in Section 1333 of the Energy Policy Act of 2005 and has the smart grid capability specified in paragraph (5).
- (iii) A clothes dryer or cooking product that the Secretary determines meets the standards specified in subsection (j)(3), which the Secretary shall promulgate no later than one year after the date of enactment, and has the smart grid capability specified in paragraph (5).
- (B) EXTENSION OF INITIAL DESIGNATIONS.—
- (i) GENERAL.—The Secretary shall in 2013 extend the Superefficient Best-In-Class Product designation of each product specified in subparagraph (A)(i) through (iii) through 2017, provided that for each product designation extended—
- (1) the extension will result in significant energy efficiency savings;
- (II) the product meets the Superefficient Best-In-Class Product criteria specified in paragraph (1);

- (III) the eligibility standards of the product include the smart grid capability specified in paragraph (5); and
- (IV) the Secretary makes appropriate revisions to the eligibility standards of the product as provided by paragraph (1).
- (ii) AWARDS.—If a Superefficient Best-In-Class Product designation for a product is extended pursuant to this subparagraph, the premium award for the product shall be determined in accordance with paragraph (2).
 - (5) SMART GRID CAPABILITY.-
- (A) Until the Secretary promulgates criteria under subparagraph (B), the term 'smart grid capability" means capability of receiving and interpreting time-of-use pricing and peak-load-shed signals from a utility and-
- (i) in the case of a cooking product, reducing a minimum of 20 percent during peak demand as measured by the tested average wattage over the course of a typical operating cycle of the product; or
- (ii) in the case of a clothes washer, a refrigerator, a dishwasher, a dryer and a water heater, reducing a minimum of 50 percent during peak demand as measured by the tested average wattage over the course of a typical operating cycle of the product, provided that the typical operating cycle of a refrigerator and a water heater shall be a 24-hour period.
- (B) After completion of the analysis required under section 142(b) of this Act, the Secretary shall expeditiously promulgate, after notice and a 30-day public comment period, criteria for what constitutes "smart grid capability."
- (f) REPORTING.—The Secretary of Energy shall require, as a condition of receiving a bonus, bounty, or premium award under this section, that a report containing the following documentation be provided:
- (1) For retailers and distributors, the number of units sold within each product type, and model-specific wholesale purchase prices and retail sale prices, on a monthly basis.
- (2) For manufacturers, model-specific energy efficiency and consumption data.
- (3) For manufacturers, on an immediate basis, information concerning any product design or function changes that affect the energy consumption of the unit.
- (4) The methods used to increase the sales
- of qualifying products.

 (g) MONITORING AND VERIFICATION PROTO-COLS.—The Secretary of Energy shall establish monitoring and verification protocols for energy consumption tests for each product model and for sales of energy-efficient models. The Secretary shall estimate actual savings of energy from the use of Smart Grid capability in appliances for which premium award payments are made pursuant to subsection (e) as a function of utility and consumer readiness to utilize such capability.
- (h) DISCLOSURE.—The Secretary of Energy may require that manufacturers, retailers and distributors disclose publicly and to consumers their participation in the program under this section.
 - (i) Cost-Effectiveness Requirement -
- (1) REQUIREMENT.—The Secretary of Energy shall make cost-effectiveness a top priority in designing the program under, and administering, this section, except that the cost-effectiveness of providing premium awards to manufacturers under subsection (e), in aggregate, may be lower by this measure than that of the bonuses and bounties to retailers and distributors under subsections
 - (2) DEFINITIONS.—In this subsection:
- (A) Cost-effectiveness.—The term "costeffectiveness" means a measure of aggregate savings in the cost of energy over the lifetime of a product in relation to the cost to the Secretary of the bonuses, bounties, and

- premium awards provided under this section for a product.
- (B) SAVINGS.—The term "savings" means the cumulative megawatt-hours of electricity or million British thermal units of other fuels saved by a product during the projected useful life of the product, in comparison to projected energy consumption of the average product in the same class, taking into consideration the impact of any documented measures to replace, retire, and recycle low-efficiency products at the time of purchase of highly-efficient substitutes.
- (j) DEFINITIONS.—In this section-
- (1) the term "distributor" mean an individual, organization, or company that sells products in multiple lots and not directly to end-users;
- (2) the term "retailer" means an individual, organization, or company that sells products directly to end-users;
- (3) the term "manufacturer" means an individual, organization, or company that transforms raw materials into mass-producible finished goods; and
- (4) the term "Superefficient Best-in-Class Product" means a product that-
- (A) can be mass produced; and
- (B) achieves the highest level of efficiency that the Secretary of Energy finds can, given the current state of technology, be produced and sold commercially to mass-market consumers
- (k) AUTHORIZATION OF APPROPRIATIONS.-There are authorized to be appropriated \$600,000,000 for each of the fiscal years 2011 through 2013 to the Secretary of Energy for purposes of this section, and such sums as may be necessary for subsequent fiscal years. Of funds appropriated, not more than 10 percent for any fiscal year may be expended on program administration, and not less than 40 percent of any funds appropriated during fiscal years 2011 through 2013 shall be for purposes of subsection (e).

SEC. 215. WATERSENSE.

- (a) IN GENERAL.—There is established within the Environmental Protection Agency a WaterSense program to identify and promote water efficient products, buildings and landscapes, and services in order-
 - (1) to reduce water use;
- (2) to reduce the strain on water, wastewater, and stormwater infrastructure;
- (3) to conserve energy used to pump, heat, transport, and treat water; and
- (4) to preserve water resources for future generations,
- through voluntary labeling of, or other forms of communications about, products, buildings and landscapes, and services that meet the highest water efficiency and performance standards.
- (b) DUTIES.—The Administrator shall-
- (1) promote WaterSense labeled products. buildings and landscapes, and services in the market place as the preferred technologies and services for-
- (A) reducing water use; and
- (B) ensuring product and service performance;
- (2) work to enhance public awareness of the WaterSense label through public outreach, education, and other means;
- (3) establish and maintain performance standards so that products, buildings and landscapes, and services labeled with the WaterSense label perform as well or better than their less efficient counterparts;
- (4) publicize the need for proper installation and maintenance of WaterSense products by a licensed, and where certification guidelines exist, WaterSense-certified professional to ensure optimal performance;
- preserve the integrity WaterSense label;
- (6) regularly review and, when appropriate, update WaterSense criteria for categories of

- products, buildings and landscapes, and services, at least once every four years;
- (7) to the extent practical, regularly estimate and make available to the public the production and relative market shares of WaterSense labeled products, buildings and landscapes, and services, at least annually;
- (8) to the extent practical, regularly estimate and make available to the public the water and energy savings attributable to the use of WaterSense labeled products, buildings and landscapes, and services, at least annually:
- (9) solicit comments from interested parties and the public prior to establishing or revising a WaterSense category, specification, installation criterion, or other criterion (or prior to effective dates for any such category, specification, installation criterion, or other criterion):
- (10) provide reasonable notice to interested parties and the public of any changes (including effective dates), on the adoption of a new or revised category, specification, installation criterion, or other criterion, along with-
- (A) an explanation of changes; and
- (B) as appropriate, responses to comments submitted by interested parties;
- (11) provide appropriate lead time (as determined by the Administrator) prior to the applicable effective date for a new or significant revision to a category, specification, installation criterion, or other criterion, taking into account the timing requirements of the manufacturing, marketing, training, and distribution process for the specific product, building and landscape, or service category addressed: and
- (12) identify and, where appropriate, implement other voluntary approaches in commercial, institutional, residential, municipal, and industrial sectors to encourage reuse and recycling technologies, improve water efficiency, or lower water use while meeting, where applicable, the performance standards established under paragraph (3).
- (c) AUTHORIZATION OF APPROPRIATIONS There are authorized to be appropriated \$7,500,000 for fiscal year 2010, \$10,000,000 for fiscal year 2011, \$20,000,000 for fiscal year 2012, and \$50,000,000 for fiscal year 2013 and each year thereafter, adjusted for inflation, to carry out this section.

SEC. 216. FEDERAL PROCUREMENT OF WATER EFFICIENT PRODUCTS.

- (a) Definitions.—In this section:
- (1) AGENCY.—The term "agency" has the meaning given that term in section 7902(a) of title 5, United States Code.
- (2) Watersense product or service.—The term "WaterSense product or service" means a product or service that is rated for water efficiency under the WaterSense program.
- WATERSENSE PROGRAM.—The "WaterSense program" means the program established by section 215 of this Act.
- (4) FEMP DESIGNATED PRODUCT.—The term "FEMP designated product" means a product that is designated under the Federal Energy Management Program of the Department of Energy as being among the highest 25 percent of equivalent products for efficiency.
- (5) PRODUCT AND SERVICE.—The terms "product" and "service" do not include any water consuming product or service designed or procured for combat or combat-related missions. The terms also exclude products or services already covered by the Federal procurement regulations established under section 553 of the National Energy Conservation Policy Act (42 U.S.C. 8259b).
- (b) PROCUREMENT OF WATER EFFICIENT PRODUCTS.-
- (1) REQUIREMENT.—To meet the requirements of an agency for a water consuming product or service, the head of the agency

mal performance.

- shall, except as provided in paragraph (2), procure—
- (A) a WaterSense product or service; or(B) a FEMP designated product.
- A WaterSense plumbing product should preferably, when possible, be installed by a licensed and, when WaterSense certification guidelines exist, WaterSense-certified plumber or mechanical contractor, and a WaterSense irrigation system should preferably, when possible, be installed, maintained, and audited by a WaterSense-certified irrigation professional to ensure opti-
- (2) EXCEPTIONS.—The head of an agency is not required to procure a WaterSense product or service or FEMP designated product under paragraph (1) if the head of the agency finds in writing that—
- (A) a WaterSense product or service or FEMP designated product is not cost-effective over the life of the product, taking energy and water cost savings into account: or
- (B) no WaterSense product or service or FEMP designated product is reasonably available that meets the functional requirements of the agency.
- (3) PROCUREMENT PLANNING.—The head of an agency shall incorporate into the specifications for all procurements involving water consuming products and systems, including guide specifications, project specifications, and construction, renovation, and services contracts that include provision of water consuming products and systems, and into the factors for the evaluation of offers received for the procurement, criteria used for rating WaterSense products and services and FEMP designated products. The head of an agency shall consider, to the maximum extent practicable, additional measures for reducing agency water consumption, including water reuse technologies, leak detection and repair, and use of waterless products that perform similar functions to existing water-consuming products.
- (c) REGULATIONS.—Not later than 180 days after the date of enactment of this Act, the Secretary of Energy, working in coordination with the Administrator, shall issue guidelines to carry out this section.

SEC. 217. EARLY ADOPTER WATER EFFICIENT PRODUCT INCENTIVE PROGRAMS.

- (a) DEFINITIONS.—In this section:
- (1) ELIGIBLE STATE.—The term "eligible entity" means a State government, local or county government, tribal government, wastewater or sewerage utility, municipal water authority, energy utility, water utility, or nonprofit organization that meets the requirements of subsection (b).
- (2) INCENTIVE PROGRAM.—The term "incentive program" means a program for administering financial incentives for consumer purchase and installation of residential water efficient products and services as described in subsection (b)(1).
- (3) RESIDENTIAL WATER EFFICIENT PRODUCT OR SERVICE.—The term "residential water efficient product or service" means a product or service for a single-family or multifamily residence or its landscape that is rated for water efficiency and performance—
 - (A) by the WaterSense program; or
- (B) where a WaterSense specification does not exist; by an incentive program.
- Categories of water efficient products and services may include faucets, irrigation technologies and services, point-of-use water treatment devices, reuse and recycling technologies, toilets, and showerheads.
- (4) WATERSENSE PROGRAM.—The term "WaterSense program" means the program established by section 215 of this Act.
- (b) ELIGIBLE ENTITIES..—An entity shall be eligible to receive an allocation under subsection (c) if the entity—

- (1) establishes (or has established) an incentive program to provide rebates, vouchers, other financial incentives, or direct installs to consumers for the purchase of residential water efficient products or services;
- (2) submits an application for the allocation at such time, in such form, and containing such information as the Administrator may require; and
- (3) provides assurances satisfactory to the Administrator that the entity will use the allocation to supplement, but not supplant, funds made available to carry out the incentive program.
- (c) AMOUNT OF ALLOCATIONS.—For each fiscal year, the Administrator shall determine the amount to allocate to each eligible entity to carry out subsection (d) taking into consideration—
- (1) the population served by the eligible entity in the most recent calendar year for which data are available:
- (2) the targeted population of the eligible entity's incentive program, such as general households, low-income households, or first-time homeowners, and the probable effectiveness of the incentive program for that population;
- (3) for existing programs, the effectiveness of the incentive program in encouraging the adoption of water efficient products and services: and
- (4) any prior year's allocation to the eligible entity that remains unused.
- (d) USE OF ALLOCATED FUNDS.—Funds allocated to an entity under subsection (c) may be used to pay up to 50 percent of the cost of establishing and carrying out an incentive program.
- (e) FIXTURE RECYCLING.—Entities are encouraged to promote or implement fixture recycling programs to manage the disposal of older fixtures replaced due to the incentive program under this section.
- (f) ISSUANCE OF INCENTIVES.—Financial incentives may be provided to consumers that meet the requirements of the incentive program. The entity may issue all financial incentives directly to consumers or, with approval of the Administrator, delegate some or all financial incentive administration to other organizations including, but not limited to local governments, municipal water authorities, and water utilities. The amount of a financial incentive shall be determined by the entity, taking into consideration—
- (1) the amount of the allocation to the entity under subsection (c):
- (2) the amount of any Federal, State, or other organization's tax or financial incentive available for the purchase of the residential water efficient product or service;
- (3) the amount necessary to change consumer behavior to purchase water efficient products and services; and
- (4) the consumer expenditures for onsite preparation, assembly, and original installation of the product.
- (g) AUTHORIZATION OF APPROPRIATIONS.—There are authorized to be appropriated to the Administrator to carry out this section \$50,000,000 for fiscal years 2010, \$100,000,000 for fiscal year 2011, \$150,000,000 for fiscal year 2012, \$100,000,000 for fiscal year 2013, and \$50,000,000 for fiscal year 2014.

SEC. 218. CERTIFIED STOVES PROGRAM.

- (a) DEFINITIONS.—In this section:
- (1) AGENCY.—The term "Agency" means the Environmental Protection Agency.
- (2) WOOD STOVE OR PELLET STOVE.—The term "wood stove or pellet stove" means a wood stove, pellet stove, or fireplace insert that uses wood or pellets for fuel.
- (3) CERTIFIED STOVE.—The term "certified stove" means a wood stove or pellet stove that meets the standards of performance for new residential wood heaters under subpart

- AAA of part 60 of subchapter C of chapter I of title 40, Code of Federal Regulations (or successor regulations), as certified by the Administrator. Pellet stoves and fireplace inserts using pellets for fuel that are exempt from testing by the Administrator but meet the same standards of performance as wood stoves are considered certified for the purposes of this section.
- (4) ELIGIBLE ENTITY.—The term "eligible entity" means—
- (A) a State, a local government, or a federally recognized Indian tribe;
- (B) Alaskan Native villages or regional or village corporations (as defined in, or established under, the Alaskan Native Claims Settlement Act (43 U.S.C. 1601 et seq.)); and
- (C) a nonprofit organization or institution that—
- (i) represents or provides pollution reduction or educational services relating to wood smoke minimization to persons, organizations, or communities; or
- (ii) has, as its principal purpose, the promotion of air quality or energy efficiency.
- (b) ESTABLISHMENT.—The Administrator shall establish and carry out a program to assist in the replacement of wood stoves or pellet stoves that do not meet the standards of performance referred to in subsection (a)(4) by—
- (1) requiring that each wood stove or pellet stove sold in the United States on and after the date of enactment of this Act meet the standards of performance referred to in subsection (a)(4):
- (2) requiring that no wood stove or pellet stove replaced under this program is sold or returned to active service, but that it is instead destroyed and recycled to the maximum extent feasible:
- (3) providing funds to an eligible entity to replace a wood stove or pellet stove that does not meet the standards of performance in subsection (a)(4) with a certified stove, including funds to pay for—
- (A) installation of a replacement certified stove; and
- (B) necessary replacement of or repairs to ventilation, flues, chimneys, or other relevant items necessary for safe installation of a replacement certified stove;
- (4) in addition to any funds that may be appropriated for the program under this subsection, using existing Federal, State, and local programs and incentives, to the greatest extent practicable;
- (5) prioritizing the replacement of wood stoves or pellet stoves manufactured before July 1, 1990; and
- (6) carrying out such other activities as the Administrator determines appropriate to facilitate the replacement of wood stoves or pellet stoves that do not meet the standards of performance referred to in subsection (a)(3).
- (c) REGULATIONS.—The Administrator may promulgate such regulations as are necessary to carry out the program established under subsection (b).
 - (d) FUNDING.—
- (1) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to carry out the program under this section \$20,000,000 for the period of fiscal years 2010 through 2014.
- (2) DESIGNATED USE.—Of amounts appropriated pursuant to this subsection—
- (A) 25 percent shall be designated for use to carry out the program under this section on lands held in trust for the benefit of a federally recognized Indian tribe;
- (B) 3 percent shall be designated for use to carry out the program under this section in Alaskan Native villages or regional or village corporations (as defined in, or established under, the Alaskan Native Claims Settlement Act (43 U.S.C. 1601 et seq.)); and

- (C) 72 percent shall be designated for use to carry out the program under this section nationwide.
 - (3) REGULATORY PROGRAMS.—
- (A) IN GENERAL.—No grant or loan provided under this section shall be used to fund the costs of emissions reductions that are mandated under Federal, State, or local law.
- (B) MANDATED.—For purposes of subparagraph (A), voluntary or elective emission reduction measures shall not be considered "mandated", regardless of whether the reductions are included in the implementation plan of a State.
- (e) EPA AUTHORITY TO ACCEPT WOOD STOVE OR PELLET STOVE REPLACEMENT SUPPLEMENTAL ENVIRONMENTAL PROJECTS.—
- (1) IN GENERAL.—The Administrator may accept (notwithstanding sections 3302 and 1301 of title 31, United States Code) wood stove or pellet stove replacement Supplemental Environmental Projects if such projects, as part of a settlement of any alleged violation of environmental law—
- (A) protect human health or the environment:
- (B) are related to the underlying alleged violation;
- (C) do not constitute activities that the defendant would otherwise be legally required to perform; and
- (D) do not provide funds for the staff of the Agency or for contractors to carry out the Agency's internal operations.
- (2) CERTIFICATION.—In any settlement agreement regarding an alleged violation of environmental law in which a defendant agrees to perform a wood stove or pellet stove replacement Supplemental Environmental Project, the Administrator shall require the defendant to include in the settlement documents a certification under penalty of law that the defendant would have agreed to perform a comparably valued, alternative project other than a wood stove or pellet stove replacement Supplemental Environmental Project if the Administrator were precluded by law from accepting a wood stove or pellet stove replacement Supplemental Environmental Project. A failure by the Administrator to include this language in such a settlement agreement shall not create a cause of action against the United States under the Clean Air Act or any other law or create a basis for overturning a settlement agreement entered into by the United States.

SEC. 219. ENERGY STAR STANDARDS.

- (a) Energy Star.—Section 324A(c) of the Energy Policy and Conservation Act is amended—
- (1) in paragraph (6)(B), by striking "and" after the semicolon at the end:
- (2) in paragraph (7), by striking the period at the end and inserting a semicolon; and
- (3) by adding at the end the following:
- "(8) not later than 18 months after the date of enactment of this paragraph, establish and implement a rating system for products identified as Energy Star products pursuant to this section to provide consumers with the most helpful information on the relative energy efficiency, including cost effectiveness from the consumer's perspective, and relative length of time for consumers to recover costs attributable to the energy efficient features, of those products, unless the Administrator and the Secretary communicate to Congress that establishing such a system would diminish the value of the Energy Star brand to consumers;
- "(9)(A) review the Energy Star product criteria for the 10 product models in each product category with the greatest energy consumption at least once every 3 years; and
- "(B) based on the review, update and publish the Energy Star product criteria for each such category, as necessary; and

- "(10) require periodic verification of compliance with the Energy Star product criteria by products identified as Energy Star products pursuant to this section, including—
- "(A) purchase and testing of products from the market; or
- "(B) other appropriate testing and compliance approaches.".
- (b) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to carry out the amendments made by this section \$5,000,000 for fiscal year 2010 and for each fiscal year thereafter.

Subtitle C—Transportation Efficiency SEC. 221. EMISSIONS STANDARDS.

Title VIII of the Clean Air Act, as added by section 331 of this Act, is amended by inserting after part A the following new part:

"PART B-MOBILE SOURCES

"SEC. 821. GREENHOUSE GAS EMISSION STAND-ARDS FOR MOBILE SOURCES.

- "(a) NEW MOTOR VEHICLES AND NEW MOTOR VEHICLE ENGINES.—(1) Pursuant to section 202(a)(1), by December 31, 2010, the Administrator shall promulgate standards applicable to emissions of greenhouse gases from new heavy-duty motor vehicles or new heavy-duty motor vehicle engines, excluding such motor vehicles covered by the Tier II standards (as established by the Administrator as of the date of the enactment of this section). The Administrator may revise these standards from time to time.
- (2) Regulations issued under section 202(a)(1) applicable to emissions of greenhouse gases from new heavy-duty motor vehicles or new heavy-duty motor vehicle engines, excluding such motor vehicles covered by the Tier II standards (as established by the Administrator as of the date of the enactment of this section), shall contain standards that reflect the greatest degree of emissions reduction achievable through the application of technology which the Administrator determines will be available for the model year to which such standards apply, giving appropriate consideration to cost, energy, and safety factors associated with the application of such technology. Any such regulations shall take effect after such period as the Administrator finds necessary to permit the development and application of the requisite technology, and, at a minimum, shall apply for a period no less than 3 model years beginning no earlier than the model year commencing 4 years after such regulations are promulgated.
- "(3) Regulations issued under section 202(a)(1) applicable to emissions of greenhouse gases from new heavy-duty motor vehicles or new heavy-duty motor vehicle engines, excluding such motor vehicles covered by the Tier II standards (as established by the Administrator as of the date of the enactment of this section), shall supersede and satisfy any and all of the rulemaking and compliance requirements of section 32902(k) of title 49, United States Code.
- "(4) Other than as specifically set forth in paragraph (3) of this subsection, nothing in this section shall affect or otherwise increase or diminish the authority of the Secretary of Transportation to adopt regulations to improve the overall fuel efficiency of the commercial goods movement system.
- "(b) Nonroad Vehicles and Engines.—(1) Pursuant to section 213(a)(4) and (5), the Administrator shall identify those classes or categories of new nonroad vehicles or engines, or combinations of such classes or categories, that, in the judgment of the Administrator, both contribute significantly to the total emissions of greenhouse gases from nonroad engines and vehicles, and provide the greatest potential for significant and cost-effective reductions in emissions of

- greenhouse gases. The Administrator shall promulgate standards applicable to emissions of greenhouse gases from these new nonroad engines or vehicles by December 31, 2012. The Administrator shall also promulgate standards applicable to emissions of greenhouse gases for such other classes and categories of new nonroad vehicles and engines as the Administrator determines appropriate and in the timeframe the Administrator determines appropriate. The Administrator shall base such determination, among other factors, on the relative contribution of greenhouse gas emissions, and the costs for achieving reductions, from such classes or categories of new nonroad engines and vehicles. The Administrator may revise these standards from time to time.
- "(2) Standards under section 213(a)(4) and (5) applicable to emissions of greenhouse gases from those classes or categories of new nonroad engines or vehicles identified in the first sentence of paragraph (1) of this subsection, shall achieve the greatest degree of emissions reduction achievable based on the application of technology which the Administrator determines will be available at the time such standards take effect, taking into consideration cost, energy, and safety factors associated with the application of such technology. Any such regulations shall take effect at the earliest possible date after such period as the Administrator finds necessary to permit the development and application of the requisite technology, giving appropriate consideration to the cost of compliance within such period, the applicable compliance dates for other standards, and other appropriate factors, including the period of time appropriate for the transfer of applicable technology from other applications, including motor vehicles, and the period of time in which previously promulgated regulations have been in effect.
- "(3) For purposes of this section and standards under section 213(a)(4) or (5) applicable to emissions of greenhouse gases, the term 'nonroad engines and vehicles' shall include non-internal combustion engines and the vehicles these engines power (such as electric engines and electric vehicles), for those non-internal combustion engines and vehicles which would be in the same category and have the same uses as nonroad engines and vehicles that are powered by internal combustion engines.
- "(c) AVERAGING, BANKING, AND TRADING OF EMISSIONS CREDITS.—In establishing standards applicable to emissions of greenhouse gases pursuant to this section and sections 202(a), 213(a)(4) and (5), and 231(a), the Administrator may establish provisions for averaging, banking, and trading of greenhouse gas emissions credits within or across classes or categories of motor vehicles and motor vehicle engines, nonroad vehicles and engines (including marine vessels), and aircraft and aircraft engines, to the extent the Administrator determines appropriate and considering the factors appropriate in setting standards under those sections. Such provisions may include reasonable and appropriate provisions concerning generation, banking, trading, duration, and use of credits.
- "(d) REPORTS.—The Administrator shall, from time to time, submit a report to Congress that projects the amount of greenhouse gas emissions from the transportation sector, including transportation fuels, for the years 2030 and 2050, based on the standards adopted under this section.
- "(e) Greenhouse Gases.—Notwithstanding the provisions of section 711, hydrofluorocarbons shall be considered a greenhouse gas for purposes of this section.".

SEC. 222. GREENHOUSE GAS EMISSIONS REDUC-TIONS THROUGH TRANSPORTATION EFFICIENCY.

(a) ENVIRONMENTAL PROTECTION AGENCY.— Title VIII of the Clean Air Act, as added by section 331 of this Act, is further amended by inserting after part C the following new part:

"PART D—TRANSPORTATION EMISSIONS "SEC. 841. GREENHOUSE GAS EMISSIONS REDUCTIONS THROUGH TRANSPORTATION EFFICIENCY.

- "(a) IN GENERAL.—The Administrator, in consultation with the Secretary of Transportation, shall promulgate, and update from time to time, regulations to establish national transportation-related greenhouse gas emissions reduction goals, standardized models and methodologies for use in developing surface transportation-related greenhouse gas emissions reduction targets pursuant to sections 134 and 135 of title 23 of the United States Code and methods for collection of data on transportation-related greenhouse gas emissions. Such goals shall be commensurate with the emissions reductions goals established under the American Clean Energy and Security Act of 2009. In establishing such goals, models, and methodologies, the Administrator shall consult with States and metropolitan planning organizations and may utilize existing models and methodolo-
- "(b) TIMING.—The Administrator shall-
- "(1) publish proposed regulations under subsection (a) not later than 12 months after the date of enactment of this section; and
- "(2) promulgate final regulations under subsection (a) not later than 18 months after the date of enactment of this section.
- "(c) ASSESSMENT.—At least every 6 years after promulgating final regulations under subsection (a), the Administrator, jointly with the Secretary of Transportation, shall assess current and projected progress in reducing national transportation-related greenhouse gas emissions. The assessment shall examine the contributions to emissions reductions attributable to improvements in vehicle efficiency, greenhouse gas performance of transportation fuels, increased efficiency in utilizing transportation systems and the effects of local and State planning."
- (b) METROPOLITAN PLANNING ORGANIZA-TIONS.—Section 134 of title 23 of the United States Code is amended as follows:
- (1) In subsection (a)(1)—
- (A) by striking "minimizing" and inserting "reducing"; and
- (B) by inserting ", reliance on oil, impacts on the environment, transportation-related greenhouse gas emissions" after "consumption".
- (2) In subsection (h)(1)(E)—
- (A) by inserting "sustainability and livability, reduce surface transportation-related greenhouse gas emissions and reliance on oil, adapt to the effects of climate change," after "energy conservation";
- (B) by inserting "and public health" after "quality of life"; and
- (C) by inserting ", including housing and land use patterns" after "development patterns".
- (3) In subsection (i)(4)(A) by inserting "air quality, public health, housing, transportation," after "conservation,".
- (4) In subsection (k) by inserting at the end the following new paragraph:
- "(6) Emissions reduction process.—
- "(A) IN GENERAL.—Within a metropolitan planning area serving a transportation management area, the transportation planning process under this section shall address transportation-related greenhouse gas emissions by including emission reduction targets and strategies.
- "(B) ESTABLISHMENT OF EMISSIONS REDUCTION TARGETS AND STRATEGIES.—

- "(i) IN GENERAL.—Not later than one year after the promulgation of the final regulations required under section 841 of the Clean Air Act, each metropolitan planning organization shall develop surface transportationrelated greenhouse gas emission reduction targets, as well as strategies to meet such targets, as part of the transportation planning process under this section. If more than one metropolitan planning organization has been designated within a metropolitan planning area serving a transportation management area, each such metropolitan planning organization shall work cooperatively with other such organization to develop the surface transportation-related greenhouse gas emission reduction targets required under this subparagraph.
- "(ii) MINIMUM REQUIREMENTS.—Each metropolitan planning organization that develops targets and strategies required under clause (i) shall demonstrate progress in stabilizing and reducing transportation-related greenhouse gas emissions in each metropolitan planning area serving a surface transportation management area. The targets and strategies shall, at a minimum—
- "(I) be based on the models and methodologies established in the final regulations required under section 841 of the Clean Air Act:
- "(II) address sources of surface transportation-related greenhouse gas emissions and contribute to achievement of the national transportation-related greenhouse gas emissions reduction goals;
- "(III) include efforts to increase public transportation ridership; and
- "(IV) include efforts to increase walking, bicycling, and other forms of nonmotorized transportation.
- "(C) PUBLIC NOTICE.—Each metropolitan planning organization shall make its emission reduction targets and strategies, and an analysis of the anticipated effects thereof, available to the public through its Web site.
- "(D) ENFORCEMENT.—If the Secretary finds that a metropolitan planning organization has failed to develop, submit or publish its emission reduction targets and strategies, the Secretary shall not certify that the requirements of this section are met with respect to the metropolitan planning process of such organization."
- (c) STATES.—Section 135 of title 23 of the United States Code is amended as follows:
- (1) In subsection (d)(1)(E)—
- (A) by inserting "sustainability and livability, reduce surface transportation-related greenhouse gas emissions and reliance on oil, adapt to the effects of climate change," after "energy conservation":
- (B) by inserting "and public health" after "quality of life"; and
- (C) by inserting ", including housing and land use patterns" after "development patterns".
- (2) In subsection (f)(2)(D)(i) by inserting "air quality, public health, housing, transportation," after "conservation,".
- (3) In subsection (f) by inserting at the end the following new paragraph:
 - "(9) Emissions reduction process.—
- "(A) IN GENERAL.—Within a State, the transportation planning process under this section shall address transportation-related greenhouse gas emissions by including emission reduction targets and strategies.
- "(B) ESTABLISHMENT OF EMISSIONS REDUCTION TARGETS AND STRATEGIES.—
- "(i) IN GENERAL.—Not later than one year after the promulgation of the final regulations required under section 841 of the Clean Air Act, each State shall develop surface transportation-related greenhouse gas emission reduction targets, as well as strategies to meet such targets, as part of the transportation planning process under this section.

- "(ii) MINIMUM REQUIREMENTS.—Each State that develops targets and strategies required under clause (i) shall demonstrate progress in stabilizing and reducing transportation-related greenhouse gas emissions in such State. The targets and strategies shall, at a minimum.
- "(I) be based on the models and methodologies established in the final regulations required under section 841 of the Clean Air Act;
- "(II) address sources of surface transportation-related greenhouse gas emissions and contribute to achievement of the national transportation-related greenhouse gas emissions reduction goals:
- "(III) include efforts to increase public transportation ridership; and
- "(IV) include efforts to increase walking, bicycling, and other forms of nonmotorized transportation.
- "(D) PUBLIC NOTICE.—Each State shall make its emission reduction targets and strategies, and an analysis of the anticipated effects thereof, available to the public through its Web site.
- "(E) ENFORCEMENT.—If the Secretary finds that a State has failed to develop, submit or publish its emission reduction targets and strategies, the Secretary shall not certify that the requirements of this section are met with respect to the statewide planning process of such State."
- (d) DEPARTMENT OF TRANSPORTATION.—The Secretary of Transportation shall establish appropriate requirements, including performance measures, to ensure that transportation plans developed under sections 134 and 135 of title 23 of the United States Code sufficiently meet the requirements of this section, including achieving progress towards national transportation-related greenhouse gas emissions reduction goals.

SEC. 223. SMARTWAY TRANSPORTATION EFFI-CIENCY PROGRAM.

Part B of title VIII of the Clean Air Act, as added by section 221 of this Act is amended by adding after section 821 the following section:

"SEC. 822. SMARTWAY TRANSPORTATION EFFI-CIENCY PROGRAM.

- "(a) IN GENERAL.—There is established within the Environmental Protection Agency a SmartWay Transport Program to quantify, demonstrate, and promote the benefits of technologies, products, fuels, and operational strategies that reduce petroleum consumption, air pollution, and greenhouse gas emissions from the mobile source sector.
- "(b) GENERAL DUTIES.—Under the program established under this section, the Administrator shall carry out each of the following:
- "(1) Development of measurement protocols to evaluate the energy consumption and greenhouse gas impacts from technologies and strategies in the mobile source sector, including those for passenger transport and goods movement.
- "(2) Development of qualifying thresholds for certifying, verifying, or designating energy-efficient, low-greenhouse gas SmartWay technologies and strategies for each mode of passenger transportation and goods movement.
- "(3) Development of partnership and recognition programs to promote best practices and drive demand for energy-efficient, low-greenhouse gas transportation performance.
- "(4) Promotion of the availability of, and encouragement of the adoption of, SmartWay certified or verified technologies and strategies, and publication of the availability of financial incentives, such as assistance from loan programs and other Federal and State incentives.
- "(c) SMARTWAY TRANSPORT FREIGHT PART-NERSHIP.—The Administrator shall establish a SmartWay Transport Freight Partnership

program with shippers and carriers of goods to promote energy-efficient, low-greenhouse gas transportation. In carrying out such partnership, the Administrator shall undertake each of the following:

- "(1) Certification of the energy and greenhouse gas performance of participating freight carriers, including those operating rail, trucking, marine, and other goods movement operations.
- "(2) Publication of a comprehensive energy and greenhouse gas performance index of freight modes (including rail, trucking, marine, and other modes of transporting goods) and individual freight companies so that shippers can choose to deliver their goods more efficiently.
- "(3) Development of tools for-
- "(A) carriers to calculate their energy and greenhouse gas performance; and
- "(B) shippers to calculate the energy and greenhouse gas impacts of moving their products and to evaluate the relative impacts from transporting their goods by different modes and corporate carriers.
- "(4) Provision of recognition opportunities for participating shipper and carrier companies demonstrating advanced practices and achieving superior levels of greenhouse gas performance.
- "(d) IMPROVING FREIGHT GREENHOUSE GAS PERFORMANCE DATABASES.—The Administrator shall, in coordination with other appropriate agencies, define and collect data on the physical and operational characteristics of the Nation's truck population, with special emphasis on data related to energy efficiency and greenhouse gas performance to inform the performance index published under subsection (c)(2) of this section, and other means of goods transport as necessary, at least every 5 years.
- "(e) ESTABLISHMENT OF FINANCING PROGRAM.—The Administrator shall establish a SmartWay Financing Program to competitively award funding to eligible entities identified by the Administrator in accordance with the program requirements in subsection (g).
- "(f) PURPOSE.—Under the SmartWay Financing Program, eligible entities shall—
- "(1) use funds awarded by the Administrator to provide flexible loan and lease terms that increase approval rates or lower the costs of loans and leases in accordance with guidance developed by the Administrator; and
- "(2) make such loans and leases available to public and private entities for the purpose of adopting low-greenhouse gas technologies or strategies for the mobile source sector that are designated by the Administrator.
- "(g) Program Requirements.—The Administrator shall determine program design elements and requirements, including—
- "(1) the type of financial mechanism with which to award funding, in the form of grants or contracts;
- "(2) the designation of eligible entities to receive funding, including State, tribal, and local governments, regional organizations comprised of governmental units, nonprofit organizations, or for-profit companies;
- "(3) criteria for evaluating applications from eligible entities, including anticipated—
- "(A) cost-effectiveness of loan or lease program on a metric-ton-of-greenhouse gas-saved-per-dollar basis;
- "(B) ability to promote the loan or lease program and associated technologies and strategies to the target audience; and
- "(4) reporting requirements for entities that receive awards, including—
- "(A) actual cost-effectiveness and greenhouse gas savings from the loan or lease program based on a methodology designated by the Administrator;

- "(B) the total number of applications and number of approved applications; and
- "(C) terms granted to loan and lease recipients compared to prevailing market practices.
- "(h) AUTHORIZATION OF APPROPRIATIONS.— Such sums as necessary are authorized to be appropriated to the Administrator to carry out this section."

SEC. 224. STATE VEHICLE FLEETS.

Section 507(o) of the Energy Policy Act of 1992 (42 U.S.C. 13257) is amended by adding the following new paragraph at the end thereof:

"(3) The Secretary shall revise the rules under this subsection with respect to the types of alternative fueled vehicles required for compliance with this subsection to ensure those rules are consistent with any guidance issued pursuant to section 303 of this Act."

Subtitle D—Industrial Energy Efficiency Programs

SEC. 241. INDUSTRIAL PLANT ENERGY EFFI-CIENCY STANDARDS.

The Secretary of Energy shall continue to support the development of the American National Standards Institute (ANSI) voluntary industrial plant energy efficiency certification program, pending International Standards Organization (ISO) consensus standard 50001, and other related ANSI/ISO standards. In addition, the Department shall undertake complementary activities through the Department of Energy's Industry Technologies Program that support the voluntary implementation of such standards by manufacturing firms. There are authorized to be appropriated to the Secretary such sums as are necessary to carry out these activities. The Secretary shall report to Congress on the status of standards development and plans for further standards development pursuant to this section by not later than 18 months after the date of enactment of this Act, and shall prepare a second such report 18 months thereafter.

SEC. 242. ELECTRIC AND THERMAL WASTE ENERGY RECOVERY AWARD PROGRAM.

- (a) ELECTRIC AND THERMAL WASTE ENERGY RECOVERY AWARDS.—The Secretary of Energy shall establish a program to make monetary awards to the owners and operators of new and existing electric energy generation facilities or thermal energy production facilities using fossil or nuclear fuel, to encourage them to use innovative means of recovering any thermal energy that is a potentially useful byproduct of electric power generation or other processes to—
- (1) generate additional electric energy; or
- (2) make sales of thermal energy not used for electric generation, in the form of steam, hot water, chilled water, or desiccant regeneration, or for other commercially valid purnoses
- (b) Amount of Awards.—
- (1) ELIGIBILITY.—Awards shall be made under subsection (a) only for the use of innovative means that achieve net energy efficiency at the facility concerned significantly greater than the current standard technology in use at similar facilities.
- (2) AMOUNT.—The amount of an award made under subsection (a) shall equal an amount up to the value of 25 percent of the energy projected to be recovered or generated during the first 5 years of operation of the facility using the innovative energy recovery method, or such lesser amount that the Secretary determines to be the minimum amount that can cost-effectively stimulate such innovation.
- (3) LIMITATION.—No person may receive an award under this section if a grant under the waste energy incentive grant program under section 373 of the Energy Policy and Con-

- servation Act (42 U.S.C. 6343) is made for the same energy savings resulting from the same innovative method.
- (c) REGULATORY STATUS.—The Secretary of Energy shall—
- (1) assist State regulatory commissions to identify and make changes in State regulatory programs for electric utilities to provide appropriate regulatory status for thermal energy byproduct businesses of regulated electric utilities to encourage those utilities to enter businesses making the sales referred to in subsection (a)(2); and
- (2) encourage self-regulated utilities to enter businesses making the sales referred to in subsection (a)(2).
- (d) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to the Secretary of Energy such sums as are necessary for the purposes of this section.

SEC. 243. CLARIFYING ELECTION OF WASTE HEAT RECOVERY FINANCIAL INCENTIVES.

Section 373(e) of the Energy Policy and Conservation Act (42 U.S.C. 6343(e)) is amended—

- (1) by striking "that qualifies for" and inserting "who elects to claim"; and
- (2) by inserting "from that project" after "for waste heat recovery".

SEC. 244. MOTOR MARKET ASSESSMENT AND COMMERCIAL AWARENESS PROGRAM.

- (a) FINDINGS.—Congress finds that—
- (1) electric motor systems account for about half of the electricity used in the United States;
- (2) electric motor energy use is determined by both the efficiency of the motor and the system in which the motor operates;
- (3) Federal Government research on motor end use and efficiency opportunities is more than a decade old; and
- (4) the Census Bureau has discontinued collection of data on motor and generator importation, manufacture, shipment, and sales.
 - (b) DEFINITIONS.—In this section:
- (1) DEPARTMENT.—The term "Department" means the Department of Energy.
- (2) INTERESTED PARTIES.—The term "interested parties" includes—
 - (A) trade associations;
 - (B) motor manufacturers;
 - (C) motor end users;
 - (D) electric utilities; and
- (E) individuals and entities that conduct energy efficiency programs.
- (3) SECRETARY.—The term "Secretary" means the Secretary of Energy, in consultation with interested parties.
- (c) ASSESSMENT.—The Secretary shall conduct an assessment of electric motors and the electric motor market in the United States that shall—
- (1) include important subsectors of the industrial and commercial electric motor market (as determined by the Secretary), including—
- (A) the stock of motors and motor-driven equipment;
- (B) efficiency categories of the motor population; and
- (C) motor systems that use drives, servos, and other control technologies;
- (2) characterize and estimate the opportunities for improvement in the energy efficiency of motor systems by market segment, including opportunities for—
- (A) expanded use of drives, servos, and other control technologies;
- (B) expanded use of process control, pumps, compressors, fans or blowers, and material handling components; and
- (C) substitution of existing motor designs with existing and future advanced motor designs, including electronically commutated permanent magnet, interior permanent magnet, and switched reluctance motors; and

- (3) develop an updated profile of motor system purchase and maintenance practices, including surveying the number of companies that have motor purchase and repair specifications, by company size, number of employees, and sales.
- (d) RECOMMENDATIONS; UPDATE.—Based on the assessment conducted under subsection (c), the Secretary shall—
 - (1) develop-
- (A) recommendations to update the detailed motor profile on a periodic basis;
- (B) methods to estimate the energy savings and market penetration that is attributable to the Save Energy Now Program of the Department; and
- (C) recommendations for the Director of the Census Bureau on market surveys that should be undertaken in support of the motor system activities of the Department; and
- (2) prepare an update to the Motor Master+program of the Department.
- (e) PROGRAM.—Based on the assessment, recommendations, and update required under subsections (c) and (d), the Secretary shall establish a proactive, national program targeted at motor end-users and delivered in cooperation with interested parties to increase awareness of—
- (1) the energy and cost-saving opportunities in commercial and industrial facilities using higher efficiency electric motors;
- (2) improvements in motor system procurement and management procedures in the selection of higher efficiency electric motors and motor-system components, including drives, controls, and driven equipment; and
- (3) criteria for making decisions for new, replacement, or repair motor and motor system components.

SEC. 245. MOTOR EFFICIENCY REBATE PROGRAM.

(a) IN GENERAL.—Part C of title III of the Energy Policy and Conservation Act (42 U.S.C. 6311 et seq.) is amended by adding at the end the following:

"SEC. 347. MOTOR EFFICIENCY REBATE PROGRAM.

- "(a) ESTABLISHMENT.—Not later than January 1, 2010, in accordance with subsection (b), the Secretary shall establish a program to provide rebates for expenditures made by entities—
- "(1) for the purchase and installation of a new electric motor that has a nominal full load efficiency that is not less than the nominal full load efficiency as defined in—
- "(A) table 12-12 of NEMA Standards Publication MG 1-2006 for random wound motors rated 600 volts or lower; or
- "(B) table 12-13 of NEMA Standards Publication MG 1-2006 for form wound motors rated 5000 volts or lower; and
- "(2) to replace an installed motor of the entity the specifications of which are established by the Secretary by a date that is not later than 90 days after the date of enactment of this section.
 - "(b) Requirements.—
- "(1) APPLICATION.—To be eligible to receive a rebate under this section, an entity shall submit to the Secretary an application in such form, at such time, and containing such information as the Secretary may require, including—
- "(A) demonstrated evidence that the entity purchased an electric motor described in subsection (a)(1) to replace an installed motor described in subsection (a)(2);
- "(B) demonstrated evidence that the enti-
- "(i) removed the installed motor of the entity from service; and
- "(ii) properly disposed the installed motor of the entity; and
- "(C) the physical nameplate of the installed motor of the entity.

- "(2) AUTHORIZED AMOUNT OF REBATE.—The Secretary may provide to an entity that meets each requirement under paragraph (1) a rebate the amount of which shall be equal to the product obtained by multiplying—
- "(A) the nameplate horsepower of the electric motor purchased by the entity in accordance with subsection (a)(1); and
 - "(B) \$25.00.
- "(3) PAYMENTS TO DISTRIBUTORS OF QUALIFYING ELECTRIC MOTORS.—To assist in the payment for expenses relating to processing and motor core disposal costs, the Secretary shall provide to the distributor of an electric motor described in subsection (a)(1), the purchaser of which received a rebate under this section, an amount equal to the product obtained by multiplying—
- "(A) the nameplate horsepower of the electric motor; and
 - "(B) \$5.00.
- "(c) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to carry out this section, to remain available until expended—
 - "(1) \$80,000,000 for fiscal year 2011;
 - "(2) \$75,000,000 for fiscal year 2012;
 - "(3) \$70,000,000 for fiscal year 2013;
 - "(4) \$65,000,000 for fiscal year 2014; and "(5) \$60,000,000 for fiscal year 2015.".
- (b) Table of Contents.—The table of contents of the Energy Policy and Conservation Act (42 U.S.C. prec. 6201) is amended by add-
- ing at the end of the items relating to part C of title III the following:
 "Sec. 347. Motor efficiency rebate program.".

SEC. 246. CLEAN ENERGY MANUFACTURING RE-VOLVING LOAN FUND PROGRAM.

The National Institute of Standards and Technology Act (15 U.S.C. 271 et seq.) is amended by inserting after section 26 the following:

"SEC. 27. CLEAN ENERGY MANUFACTURING RE-VOLVING LOAN FUND PROGRAM.

- "(a) PURPOSES.—The purposes of this section are as follows:
- "(1) To develop the long-term manufacturing capacity of the United States.
- "(2) To create jobs through the retooling and expansion of manufacturing facilities to produce clean energy technology products and energy efficient products.
- "(3) To improve the long-term competitiveness of domestic manufacturing by increasing the energy efficiency of manufacturing facilities.
- "(4) To assist small and medium-sized manufacturers diversify operations to respond to emerging clean energy technology product markets.
- "(b) Definitions.—In this section:
- "(1) CLEAN ENERGY TECHNOLOGY PRODUCT.— The term 'clean energy technology product' means technology products relating to the following:
 - "(A) Wind turbines.
 - "(B) Solar energy.
 - "(C) Fuel cells.
- ``(D) Advanced batteries, battery systems, or storage devices.
 - "(E) Biomass equipment.
- "(F) Geothermal equipment.
- "(G) Advanced biofuels.
- ``(H) Ocean energy equipment.
- "(I) Carbon capture and storage.
- "(J) Such other products as the Secretary determines—
- "(i) relate to the production, use, transmission, storage, control, or conservation of energy;
- "(ii) reduce greenhouse gas concentrations; "(iii) achieve the earliest and maximum emission reductions within a reasonable period per dollar invested;
- "(iv) result in the fewest non-greenhouse gas environmental impacts; and

- "(v) either—
- "(I) reduce the need for additional energy supplies by—
- "(aa) using existing energy supplies with greater efficiency; or
- "(bb) by transmitting, distributing, or transporting energy with greater effectiveness through the infrastructure of the United States; or
- "(II) diversity the sources of energy supply of the United States—
- "(aa) to strengthen energy security; and
- "(bb) to increase supplies with a favorable balance of environmental effects if the entire technology system is considered.
- "(2) ENERGY EFFICIENT PRODUCT.—The term 'energy efficient product' means a product that, as determined by the Secretary in consultation with the Secretary of Energy—
- "(A) consumes significantly less energy than the average amount that all similar products consumed on the day before the date of the enactment of this Act; or
- "(B) is a component, system, or group of subsystems that is designed, developed, and validated to optimize the energy efficiency of a product.
- "(3) HOLLINGS MANUFACTURING EXTENSION CENTER.—The term 'Hollings Manufacturing Extension Center' means a center established under section 25.
- "(4) HOLLINGS MANUFACTURING PARTNER-SHIP PROGRAM.—The term 'Hollings Manufacturing Partnership Program' means the program established under sections 25 and 26.
- "(5) PROGRAM.—The term 'Program' means the grant program established pursuant to subsection (c)(1).
- "(6) REVOLVING LOAN FUND.—The term 'revolving loan fund' means a revolving loan fund described in subsection (d).
- "(7) SECRETARY.—Except as otherwise provided, the term 'Secretary' means the Secretary of Commerce.
- "(8) SMALL OR MEDIUM-SIZED MANUFAC-TURER.—The term 'small or medium-sized manufacturer' means a manufacturer that employees at a manufacturing facility that is not owned or controlled by an automobile manufacturer.
 - "(c) GRANT PROGRAM.—
- "(1) ESTABLISHMENT.—Not later than 120 days after the date of the enactment of this section, the Secretary shall establish a program under which the Secretary shall award grants to States to establish revolving loan funds to provide loans to small and medium-sized manufacturers to finance the cost of—
- "(A) reequipping, expanding, or establishing (including applicable engineering costs) a manufacturing facility in the United States to produce—
 - "(i) clean energy technology products;
 - "(ii) energy efficient products; or
- "(iii) integral component parts of clean energy technology products or energy efficient products; or
- "(B) reducing the energy intensity or greenhouse gas production of a manufacturing facility in the United States, including using energy intensive feedstocks.
- "(2) MAXIMUM AMOUNT.—The Secretary may not award a grant under the Program in an amount that exceeds \$500,000,000 in any fiscal year.
 - "(d) CRITERIA FOR AWARDING GRANTS.—
- "(1) MATCHING FUNDS.—The Secretary may make a grant to a State under the Program only if the State agrees to ensure that for each loan provided by the State under the Program, not less than 20 percent of the amount of each loan will come from a non-Federal source.
- "(2) ADMINISTRATIVE COSTS.—A State receiving a grant under the Program may only use such amount of the grant for the costs of

administering the revolving loan fund as the Secretary shall provide in regulations.

- "(3) APPLICATION.—Each State seeking a grant under the Program shall submit to the Secretary an application therefor in such form and in such manner as the Secretary considers appropriate.
- "(4) EVALUATION.—The Secretary shall evaluate and prioritize an application submitted by a State for a grant under the Program on the basis of—
- "(A) the description of the revolving loan fund to be established with the grant and how such revolving loan fund will achieve the purposes described in subsection (a);
- "(B) whether the State will be able to provide loans from the revolving loan fund to small or medium-sized manufacturers before the date that is 120 days after the date on which the State receives the grant:
- "(C) a description of how the State will administer the revolving loan fund in coordination with other State and Federal programs, including programs administered by the Assistant Secretary for Economic Development;
- "(D) a description of the actual or potential clean energy manufacturing supply chains, including significant component parts, in the region served by the revolving loan fund;
- "(E) how the State will target the provision of loans under the Program to manufacturers located in regions characterized by high unemployment and sudden and severe economic dislocation, in particular where mass layoffs have resulted in a precipitous increase in unemployment;
- "(F) the availability of a skilled manufacturing workforce in the region served by the revolving loan fund and the capacity of the region's workforce and education systems to provide pathways for unemployed or low-income workers into skilled manufacturing employment:
- "(G) a description of how the State will target loans to small or medium-sized manufacturers who are—
- "(i) manufacturers of automobile components; and
 - "(ii) either—
- "(I) increasing the energy efficiency of their manufacturing facilities: or
- "(II) retooling to manufacture clean energy products or energy efficient products, including manufacturing components to improve the compliance of an automobile with fuel economy standards prescribed under section 32902 of title 49. United States Code:
- "(H) a description of how the State will use the loan fund to achieve the earliest and maximum greenhouse gas emission reductions within a reasonable period of time per dollar invested and with the fewest nongreenhouse gas environmental impacts; and
- "(I) such other factors as the Secretary considers appropriate to ensure that grants awarded under the Program effectively and efficiently achieve the purposes described in subsection (a).
- "(e) REVOLVING LOAN FUNDS.—
- "(1) IN GENERAL.—A State receiving a grant under the Program shall establish, maintain, and administer a revolving loan fund in accordance with this subsection.
- "(2) DEPOSITS.—A revolving loan fund shall consist of the following:
- "(A) Amounts from grants awarded under this section.
- "(B) All amounts held or received by the State incident to the provision of loans described in subsection (f), including all collections of principal and interest.
- "(3) EXPENDITURES.—Amounts in the revolving loan fund shall be available for the provision and administration of loans in accordance with subsection (f).

- "(4) LIMITATION.—No funds provided pursuant to this section may be leveraged through use of tax-exempt bonding authority by a State or a political subdivision of a State.
- "(f) LOANS.—
- "(1) IN GENERAL.—A State receiving a grant under this section shall use the amount in the revolving loan fund to provide loans to small and medium-sized manufacturers as described in subsection (c)(1).
- "(2) LOAN TERMS AND CONDITIONS.—The following shall apply with respect to loans provided under paragraph (1):
- "(A) TERMS.—Loans shall have a term determined by the State receiving the grant as follows:
- "(i) For fixed assets, the term of the loan shall not exceed the useful life of the asset and shall be less than 15 years.
- "(ii) For working capital, the term of the loan shall not exceed 36 months.
- "(B) INTEREST RATES.—Loans shall bear an interest rate determined by the State receiving the grant as follows:
- "(i) The interest rate shall enable the loan recipient to accomplish the activities described in subparagraphs (A) and (B) of subsection (c)(1).
- "(ii) The interest rate may be set belowmarket interest rates.
- "(iii) The interest rate may not be less than zero percent.
- ''(iv) The interest rate may not exceed the current prime rate plus 500 basis points.
- "(C) DESCRIPTION AND BUDGET FOR USE OF LOAN FUNDS.—Each recipient of a loan from a State under the Program shall develop and submit to the State and the Secretary a description and budget for the use of loan amounts, including a description of the following:
- "(i) Any new business expected to be developed with the loan.
- "(ii) Any improvements to manufacturing operations to be developed with the loan.
- "(iii) Any technology expected to be commercialized with the loan.
- "(D) PRIORITY IN REVIEW AND PREFERENCE IN SELECTION FOR CERTAIN LOAN APPLI-CANTS.—
- "(i) REVIEW.—In reviewing applications submitted by small or medium-sized manufacturers for a loan, a recipient of a grant under the Program shall give priority to small or medium-sized manufacturers described in clause (iii).
- "(ii) SELECTION.—In selecting small or medium-sized manufacturers to receive a loan, a recipient of a grant under the Program shall give preference to small or medium-sized manufacturers described in clause (iii).
- "(iii) PRIORITY AND PREFERRED SMALL OR MEDIUM-SIZED MANUFACTURERS.—A small or medium-sized manufacturer described in this clause is a manufacturer that—
- "(I) is certified by a Hollings Manufacturing Extension Center or a manufacturing-related local intermediary designated by the Secretary for purposes of providing such certification; or
- "(II) provides individuals employed at the manufacturing facilities of the manufacturer
- "(aa) pay in amounts that are, on average, equal to or more than the average wage of an individual working in a manufacturing facility in the State; and
- "(bb) health benefits.
- "(iv) CERTIFICATION BY HOLLINGS MANUFACTURING EXTENSION CENTER.—A Hollings Manufacturing Extension Center or other entity designated by the Secretary for purposes of providing certification under clause (iii)(I) shall only certify applications for a loan after carrying out a qualitative and quantitative review of the applicant's business strategy, manufacturing operations, and

- technological ability to contribute to the purposes described in subsection (a).
- "(E) REPAYMENT UPON RELOCATION OUTSIDE UNITED STATES.—
- "(i) IN GENERAL.—If a person receives a loan under paragraph (1) to finance the cost of reequipping, expanding, or establishing a manufacturing facility as described in subsection (c)(1)(A) or to reduce the energy intensity of a manufacturing facility and such person relocates the production activities of such manufacturing facility outside the United States during the term of the loan, the recipient shall repay such loan in full with interest as described in clause (ii) and for a duration described in clause (iii).
- "(ii) PAYMENT OF INTEREST.—Any amount owed by the recipient of a loan under paragraph (1) who is required to repay the loan under clause (i) shall bear interest at a penalty rate determined by the Secretary to deter recipients of loans under paragraph (1) from relocating production activities as described in clause (i).
- "(iii) PERIOD OF REPAYMENT.—Repayment of a loan under clause (i) shall be for a duration determined by the Secretary.
- "(F) COMPLIANCE WITH WAGE RATE REQUIRE-MENTS.—Each recipient of a loan shall undertake and agree to incorporate or cause to be incorporated into all contracts for construction, alteration or repair, which are paid for in whole or in part with funds obtained pursuant to such loan, a requirement that all laborers and mechanics employed by contractors and subcontractors performing construction, alteration or repair shall be paid wages at rates not less than those determined by the Secretary of Labor, in accordance with subchapter IV of chapter 31 of title 40, United States Code (known as the 'Davis-Bacon Act'), to be prevailing for the corresponding classes of laborers and mechanics employed on projects of a character similar to the contract work in the same locality in which the work is to be performed. The Secretary of Labor shall have, with respect to the labor standards specified in this subparagraph, the authority and functions set forth in Reorganization Plan Numbered 14 of 1950 (15 F.R. 3176: 64 Stat. 1267) and section 3145 of title 40. United States Code.
- "(G) ANNUAL REPORTS BY LOAN RECIPIENTS.—Each recipient of a loan issued by a State under paragraph (1) shall, not less frequently than once each year during the term of the loan, submit to such State a report containing such information as the Secretary may specify for purposes of the Program, including information that the Secretary can use to determine whether a recipient of a loan is required to repay the loan under subparagraph (E).
- "(3) ANNUAL REPORTS BY GRANT RECIPIENTS.—Each recipient of a grant under the Program shall, not less frequently than once each year, submit to the Secretary a report on the impact of each loan issued by the State under the Program and the aggregate impact of all loans so issued, including the following:
 - "(A) The sales increased or retained.
- "(B) Cost savings or costs avoided.
- "(C) Additional investment encouraged.
- "(D) Jobs created or retained.
- "(g) AUTHORIZATION OF APPROPRIATIONS.— There is authorized to be appropriated to carry out this section \$15,000,000,000 for each of fiscal years 2010 and 2011.".

SEC. 247. CLEAN ENERGY AND EFFICIENCY MAN-UFACTURING PARTNERSHIPS.

- (a) HOLLINGS MANUFACTURING PARTNERSHIP PROGRAM.—Section 25(b) of the National Institute of Standards and Technology Act (15 U.S.C. 278k(b)) is amended—
- (1) in paragraph (2), by striking "and" at the end;

- (2) in paragraph (3), by striking the period at the end and inserting "; and"; and
- (3) by adding at the end the following:
- "(4) the establishment of a clean energy manufacturing supply chain initiative—
- "(A) to support manufacturers in their identification of and diversification to new markets, including support for manufacturers transitioning to the use of clean energy supply chains;
- "(B) to assist manufacturers improve their competitiveness by reducing energy intensity and greenhouse gas production, including the use of energy intensive feedstocks;
- "(C) to increase adoption and implementation of innovative manufacturing technologies:
- "(D) to coordinate and leverage the expertise of the National Laboratories and Technology Centers and the Industrial Assessment Centers of the Department of Energy to meet the needs of manufacturers; and
- "(E) to identify, assist, and certify manufacturers seeking loans under section 27(e)(1).".
- (b) REDUCTION IN COST SHARE REQUIRE-MENTS.—Section 25(c) of such Act (15 U.S.C. 278k(c)) is amended—
- (1) in paragraph (1), by inserting "or as provided in paragraph (5)" after "not to exceed six years";
- (2) in paragraph (3)(B), by striking "not less than 50 percent of the costs incurred for the first 3 years and an increasing share for each of the last 3 years" and inserting "50 percent of the costs incurred or such lesser percentage of the costs incurred as determined appropriate by the Secretary by rule"; and
 - (3) in paragraph (5)—
 - (A) by striking "at declining levels";
- (B) by striking "one third" and inserting "50 percent"; and
- (C) by inserting ", or such lesser percentage as determined appropriate by the Secretary by rule," after "maintenance costs".
- (c) AUTHORIZATION OF APPROPRIATIONS.—There are authorized to be appropriated to the Secretary of Commerce for the Hollings Manufacturing Partnership Program authorized under sections 25 of the National Institute of Standards and Technology Act (15 U.S.C. 278k) and for the provision of assistance under section 26 of such Act (15 U.S.C. 278l)—
 - (1) \$200,000,000 for fiscal year 2010;
 - (2) \$250,000,000 for fiscal year 2011;
 - (3) \$300,000,000 for fiscal year 2012;
 - (4) \$350,000,000 for fiscal year 2013; and
 - (5) \$400,000,000 for fiscal year 2014.

SEC. 248. TECHNICAL AMENDMENTS.

- (a) AMENDMENT TO NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY ACT.—Section 25 of the National Institute of Standards and Technology Act (15 U.S.C. 278k(b)) is amended—
- (1) in subsection (a), by striking "(hereafter in this Act referred to as the 'Centers')"; and
 - (2) by adding at the end the following:
 - "(g) Designation.-
- "(1) HOLLINGS MANUFACTURING PARTNER-SHIP PROGRAM.—The program under this section shall be known as the 'Hollings Manufacturing Partnership Program'.
- "(2) HOLLINGS MANUFACTURING EXTENSION CENTERS.—The Regional Centers for the Transfer of Manufacturing Technology created and supported under subsection (a) shall be known as the 'Hollings Manufacturing Extension Centers' (in this Act referred to as the 'Centers')."
- (b) AMENDMENT TO CONSOLIDATED APPROPRIATIONS ACT, 2005.—Division B of title II of the Consolidated Appropriations Act, 2005 (Public Law 108-09447; 118 Stat. 2879; 15 U.S.C. 278k note) is amended under the heading "IN-

DUSTRIAL TECHNOLOGY SERVICES" by striking "2007: Provided further, That" and all that follows through "Extension Centers." and inserting "2007.".

Subtitle E—Improvements in Energy Savings Performance Contracting

SEC. 251. ENERGY SAVINGS PERFORMANCE CONTRACTS.

- (a) COMPETITION REQUIREMENTS FOR TASK OR DELIVERY ORDERS UNDER ENERGY SAVINGS PERFORMANCE CONTRACTS.—
- (1) COMPETITION REQUIREMENTS.—Subsection (a) of section 801 of the National Energy Conservation Policy Act (42 U.S.C. 8287(a)) is amended by adding at the end the following paragraph:

"(3)(A) The head of a Federal agency may issue a task or delivery order under an energy savings performance contract by—

"(i) notifying all contractors that have received an award under such contract that the agency proposes to discuss energy savings performance services for some or all of its facilities and, following a reasonable period of time to provide a proposal in response to the notice, soliciting an expression of interest in performing site surveys or investigations and feasibility designs and studies and the submission of qualifications from such contractors, and including in such notice summary information concerning energy use for any facilities that the agency has specific interest in including in such contract;

"(ii) reviewing all expressions of interest and qualifications submitted pursuant to the notice under clause (i);

"(iii) selecting two or more contractors (from among those reviewed under clause (ii)) to conduct discussions concerning the contractors' respective qualifications to implement potential energy conservation measures, including requesting references demonstrating experience on similar efforts and the resulting energy savings of such similar efforts, and providing an opportunity for a post-award debriefing to all contractors that submitted expressions of interest and qualifications under clause (ii) pursuant to the notice;

"(iv) selecting and authorizing-

"(I) more than one contractor (from among those selected under clause (iii)) to conduct site surveys, investigations, feasibility designs and studies or similar assessments for the energy savings performance contract services (or for discrete portions of such services), for the purpose of allowing each such contractor to submit a firm, fixed-price proposal to implement specific energy conservation measures; or

"(II) one contractor (from among those selected under clause (iii)) to conduct a site survey, investigation, a feasibility design and study or similar for the purpose of allowing the contractor to submit a firm, fixed-price proposal to implement specific energy conservation measures:

"(v) negotiating a task or delivery order for energy savings performance contracting services with the contractor or contractors selected under clause (iv) based on the energy conservation measures identified; and

"(vi) issuing a task or delivery order for energy savings performance contracting services to such contractor or contractors.

- "(B) The issuance of a task or delivery order for energy savings performance contracting services pursuant to subparagraph (A) is deemed to satisfy the task and delivery order competition requirements in section 2304c(d) of title 10, United States Code, and section 303J(d) of the Federal Property and Administrative Services Act of 1949 (41 U.S.C. 253j(d)).
 "(C) The Secretary may issue guidance as
- "(C) The Secretary may issue guidance as necessary to agencies issuing task or delivery orders pursuant to subparagraph (A).".

- (2) EFFECTIVE DATE.—The amendment made by paragraph (1) is inapplicable to task or delivery orders issued before the date of enactment of this section.
- (b) INCLUSION OF THERMAL RENEWABLE ENERGY.—Section 203 of the Energy Policy Act of 2005 (42 U.S.C. 15852) is amended—
- (1) in subsection (a), by striking "electric"; and
- (2) in subsection (b)(2), by inserting "or thermal" after "means electric".
- (c) CREDIT FOR RENEWABLE ENERGY PRODUCED AND USED ON SITE.—Subsection (c) of section 203 of the Energy Policy Act of 2005 (42 U.S.C. 15852) is amended to read as follows:
- "(c) CALCULATION.—Renewable energy produced at a Federal facility, on Federal lands, or on Indian lands (as defined in title XXVI of the Energy Policy Act of 1992 (25 U.S.C. 3501 et seq.)) shall be calculated separately from renewable energy consumed at a Federal facility, and each may be used to comply with the consumption requirement under subsection (a)."
- (d) FINANCING FLEXIBILITY.—Section 801(a)(2)(E) of the National Energy Conservation Policy Act (42 U.S.C. 8287(a)(2)(E)) is amended by striking "In" and inserting "Notwithstanding any other provision of law, in".

Subtitle F-Public Institutions

SEC. 261. PUBLIC INSTITUTIONS.

Section 399A of the Energy Policy and Conservation Act (42 U.S.C. 6371h-1) is amended...

- (1) in subsection (a)(5), by striking "or a designee" and inserting "an Indian tribe, a not-for-profit hospital or not-for-profit inpatient health care facility, or a designated agent":
- (2) in subsection (c)(1), by striking subparagraph (C);
- (3) in subsection (f)(3)(A), by striking "\$1,000,000" and inserting "\$2,500,000"; and
- (4) in subsection (i)(1), by striking "\$250,000,000 for each of fiscal years 2009 through 2013" and inserting "\$250,000,000 for each of fiscal years 2010 through 2015".

SEC. 262. COMMUNITY ENERGY EFFICIENCY FLEXIBILITY.

Section 545(b)(3) of the Energy Independence and Security Act of 2007 (42 U.S.C. 17155(b)(3)) is amended—

- (1) by striking "Indian tribe may use" and all that follows through "for administrative expenses" and inserting "Indian tribe may use for administrative expenses";
 - (2) by striking subparagraphs (B) and (C);
- (3) by redesignating the remaining clauses (i) and (ii) as subparagraphs (A) and (B), respectively and adjusting the margin of those subparagraphs accordingly; and
- (4) by striking the semicolon at the end and inserting a period.

SEC. 263. SMALL COMMUNITY JOINT PARTICIPATION.

- (a) Section 541(3)(A) of the Energy Independence and Security Act of 2007 is amended in clause (i) by striking "and" at the end of subclause (II), in clause (ii) by striking the period at the end of subclause (II) and inserting "; or", and by inserting the following new clause (iii):
- "(iii) a group of adjacent, contiguous, or geographically proximate units of local government that reach agreement to act jointly for purposes of this section and that represent a combined population of not less than 35,000."
- (b) Section 541(3)(B) of the Energy Independence and Security Act of 2007 is amended in clause (i) by striking "or", in clause (ii) by striking the period at the end and inserting "; or", and by inserting the following new clause (iii):

"(iii) a group of adjacent, contiguous, or geographically proximate units of local government that reach agreement to act jointly for purposes of this section and that represent a combined population of not less than 50,000."

SEC. 264. LOW INCOME COMMUNITY ENERGY EF-FICIENCY PROGRAM.

- (a) IN GENERAL.—The Secretary of Energy is authorized to make grants to private, nonprofit, mission-driven community development organizations including community development corporations and community development financial institutions to provide financing to businesses and projects that improve energy efficiency; identify and develop alternative, renewable, and distributed energy supplies; provide technical assistance and promote job and business opportunities for low-income residents; and increase energy conservation in low income rural and urban communities
- (b) Grants.—The purpose of such grants is to increase the flow of capital and benefits to low income communities, minority-owned and woman-owned businesses and entrepreneurs and other projects and activities located in low income communities in order to reduce environmental degradation, foster energy conservation and efficiency and create job and business opportunities for local residents. The Secretary may make grants on a competitive basis for—
- (1) investments that develop alternative, renewable, and distributed energy supplies;
- (2) capitalizing loan funds that lend to energy efficiency projects and energy conservation programs:
- (3) technical assistance to plan, develop, and manage an energy efficiency financing program; and
- (4) technical and financial assistance to assist small-scale businesses and private entities develop new renewable and distributed sources of power or combined heat and power generation.
- (c) AUTHORIZATION OF APPROPRIATIONS.—For the purposes of this section there is authorized to be appropriated \$50,000,000 for each of the fiscal years 2010 through 2015.

SEC. 265. CONSUMER BEHAVIOR RESEARCH.

- (a) IN GENERAL.—The Secretary of Energy is authorized to establish a research program to identify the factors affecting consumer actions to conserve energy and make improvements in energy efficiency. Through the program the Secretary will make grants to public and private institutions of higher education to study the effects of consumer behavior on total energy use; potential energy savings from changes in consumption habits; the ability to reduce greenhouse gas emissions through changes in energy consumption habits; increase public awareness of Federal climate adaptation and mitigation programs; and the potential for alterations in consumer behavior to further American energy independence. Grants may also fund projects that evaluate or inform public knowledge of the effects of energy consumption habits on these topics.
- (b) Grants.—The purpose of the program is to provide grants to public and private institutions of higher education to carry out projects which will improve understanding of the effects of consumer behavior on energy consumption and conservation. The Secretary shall make grants on a competitive basis for—
- (1) studies of the effects of consumer habits on energy consumption and conservation;
- (2) development of strategies that communicate the importance of energy efficiency and conservation to consumers;
- (3) identification of best practices to improve consumer energy use habits;
- (4) education programs that inform consumers about the implications of consump-

- tion habits on energy use and climate change;
- (5) evaluation of the effectiveness of programs designed to promote public awareness of Federal Government climate adaptation and mitigation activities; and
- (6) other projects that advance the mission of the program.
- (c) REPORT.—The Secretary of Energy shall provide Congress with a report on progress towards establishing the program within 120 days after the date of enactment of this Act.
- (d) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated such sums as may be necessary to carry out this section.

Subtitle G-Miscellaneous

SEC. 271. ENERGY EFFICIENT INFORMATION AND COMMUNICATIONS TECHNOLOGIES.

Section 543 of the National Energy Conservation Policy Act (42 U.S.C. 8253) is amended to read as follows:

"SEC. 543. ENERGY EFFICIENT INFORMATION AND COMMUNICATIONS TECH-NOLOGIES.

- "(a) IN GENERAL.—Not later than 1 year after the date of enactment of the American Clean Energy and Security Act of 2009, each Federal agency shall collaborate with the Director of the Office of Management and Budget (referred to in this section as the 'Director') to create an implementation strategy, including best practices and measurement and verification techniques, for the purchase and use of energy efficient information and communications technologies and practices. Wherever possible, existing standards, specifications, performance metrics, and best management practices that have been or are being developed in open collaboration and with broad stakeholder input and review should be incorporated. In addition, agency strategies shall be flexible, cost-effective, and based on the specific operating requirements and statutory mission of each
- "(b) ENERGY EFFICIENT INFORMATION AND COMMUNICATIONS TECHNOLOGIES.—In developing an implementation strategy, each agency shall—
- "(1) consider information and communications technologies and infrastructure, including, but not limited to, advanced metering infrastructure, information and communications technology services and products, efficient data center strategies, applications modernization and rationalization, building systems energy efficiency, and telework; and
- "(2) ensure that agencies are eligible to realize the savings and rewards brought about through increased efficiencies.
- "(c) PERFORMANCE GOALS.—Not later than 6 months after the date of enactment of the American Clean Energy and Security Act of 2009, the Director shall establish performance goals for evaluating the efforts of the agencies in improving the maintenance, purchase and use of energy efficiency of information and communications technology systems. These performance goals should measure information technology costs over a specific time horizon (3 to 5 years), providing a complete picture of all costs, including energy.
- "(d) REPORT.—Not later than 18 months after the date of enactment of the American Clean Energy and Security Act of 2009, and annually thereafter, the Director shall submit a report to Congress on—
- "(1) the progress of each agency in reducing energy use through its implementation strategy; and
- "(2) new and emerging technologies that would help achieve increased energy efficiency.".

SEC. 272. NATIONAL ENERGY EFFICIENCY GOALS.

(a) GOALS.—The energy efficiency goals of the United States are—

- (1) to achieve an improvement in the overall energy productivity of the United States (measured in gross domestic product per unit of energy input) of at least 2.5 percent per year by the year 2012; and
- (2) to maintain that annual rate of improvement each year through 2030.
 - (b) STRATEGIC PLAN.-
- (1) IN GENERAL.—Not later than 1 year after the date of enactment of this Act, the Secretary of Energy (referred to in this section as the "Secretary"), in cooperation with the Administrator and the heads of other appropriate Federal agencies, shall develop a strategic plan to achieve the national goals for improvement in energy productivity established under subsection (a).
- (2) PUBLIC INPUT AND COMMENT.—The Secretary shall develop the plan in a manner that provides appropriate opportunities for public input and comment.
- (c) PLAN CONTENTS.—The strategic plan shall—
- (1) identify future regulatory, funding, and policy priorities that would assist the United States in meeting the national goals;
- (2) include energy savings estimates for each sector; and
- (3) include data collection methodologies and compilations used to establish baseline and energy savings data.
 - (d) PLAN UPDATES.—
 - (1) IN GENERAL.—The Secretary shall—
- (A) update the strategic plan biennially; and
- (B) include the updated strategic plan in the national energy policy plan required by section 801 of the Department of Energy Organization Act (42 U.S.C. 7321).
- (2) CONTENTS.—In updating the plan, the Secretary shall—
- (A) report on progress made toward implementing efficiency policies to achieve the national goals established under subsection (a); and
- (B) verify, to the maximum extent practicable, energy savings resulting from the policies.
- (e) REPORT TO CONGRESS AND THE PUBLIC.— The Secretary shall submit to Congress, and make available to the public, the initial strategic plan developed under subsection (b) and each updated plan.

SEC. 273. AFFILIATED ISLAND ENERGY INDE-PENDENCE TEAM.

- (a) DEFINITIONS.—In this section:
- (1) AFFILIATED ISLAND.—The term "affiliated island" means—
- (A) the Commonwealth of Puerto Rico;
- (B) Guam;
- (C) American Samoa;
- (D) the Commonwealth of the Northern Mariana Islands;
- (E) the Federated States of Micronesia;
- (F) the Republic of the Marshall Islands;(G) the Republic of Palau; and
- (H) the United States Virgin Islands.
- (2) SECRETARY.—The term "Secretary" means the Secretary of Energy (acting through the Assistant Secretary of Energy Efficiency and Renewable Energy), in consultation with the Secretary of the Interior and the Secretary of State.
- (3) TEAM.—The term "team" means the team established by the Secretary under subsection (b).
- (b) ESTABLISHMENT.—As soon as practicable after the date of enactment of this Act, the Secretary shall assemble a team of technical, policy, and financial experts to address the energy needs of each affiliated island—
- (1) to reduce the reliance and expenditure of each affiliated island on imported fossil fuels;
- (2) to increase the use by each affiliated island of indigenous, nonfossil fuel energy sources;

- (3) to improve the performance of the energy infrastructure of the affiliated island through projects—
- (A) to improve the energy efficiency of power generation, transmission, and distribution; and
 - (B) to increase consumer energy efficiency;
- (4) to improve the performance of the energy infrastructure of each affiliated island through enhanced planning, education, and training:
- (5) to adopt research-based and public-private partnership-based approaches as appropriate;
- (6) to stimulate economic development and job creation; and
- (7) to enhance the engagement by the Federal Government in international efforts to address island energy needs.
 - (c) Duties of Team.—
 - (1) Energy action plans.—
- (A) IN GENERAL.—In accordance with subparagraph (B), the team shall provide technical, programmatic, and financial assistance to each utility of each affiliated island, and the government of each affiliated island, as appropriate, to develop and implement an energy Action Plan for each affiliated island to reduce the reliance of each affiliated island on imported fossil fuels through increased efficiency and use of indigenous clean-energy resources.
- (B) REQUIREMENTS.—Each Action Plan described in subparagraph (A) for each affiliated island shall require and provide for—
- (i) the conduct of 1 or more studies to assess opportunities to reduce fossil fuel use through—
- (I) the improvement of the energy efficiency of the affiliated island; and
- (II) the increased use by the affiliated island of indigenous clean-energy resources;
- (ii) the identification and implementation of the most cost-effective strategies and projects to reduce the dependence of the affiliated island on fossil fuels:
- (iii) the promotion of education and training activities to improve the capacity of the local utilities of the affiliated island, and the government of the affiliated island, as appropriate, to plan for, maintain, and operate the energy infrastructure of the affiliated island through the use of local or regional institutions, as appropriate;
- (iv) the coordination of the activities described in clause (iii) to leverage the expertise and resources of international entities, the Department of Energy, the Department of the Interior, and the regional utilities of the affiliated island;
- (v) the identification, and development, as appropriate, of research-based and private-public, partnership approaches to implement the Action Plan; and
- (vi) any other component that the Secretary determines to be necessary to reduce successfully the use by each affiliated island of fossil fuels.
- (2) REPORTS TO SECRETARY.—Not later than 1 year after the date on which the Secretary establishes the team and biennially thereafter, the team shall submit to the Secretary a report that contains a description of the progress of each affiliated island in—
- (A) implementing the Action Plan of the affiliated island developed under paragraph (1)(A); and
- (B) reducing the reliance of the affiliated island on fossil fuels
- (d) USE OF REGIONAL UTILITY ORGANIZATIONS.—To provide expertise to affiliated islands to assist the affiliated islands in meeting the purposes of this section, the Secretary shall consider—
- (1) including regional utility organizations in the establishment of the team; and
- (2) providing assistance through regional utility organizations.

- (e) ANNUAL REPORTS TO CONGRESS.—Not later than 30 days after the date on which the Secretary receives a report submitted by the team under subsection (c)(2), the Secretary shall submit to the appropriate committees of Congress a report that contains a summary of the report of the team.
- (f) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated such sums as are necessary to carry out this section.

SEC. 274. PRODUCT CARBON DISCLOSURE PRO-GRAM.

- (a) EPA STUDY.—The Administrator shall conduct a study to determine the feasibility of establishing a national program for measuring, reporting, publicly disclosing, and labeling products or materials sold in the United States for their carbon content, and shall, not later than 18 months after the date of enactment of this Act, transmit a report to Congress which shall include the following:
- (1) A determination of whether a national product carbon disclosure program and labeling program would be effective in achieving the intended goals of achieving greenhouse gas reductions and an examination of existing programs globally and their strengths and weaknesses.
- (2) Criteria for identifying and prioritizing sectors and products and processes that should be covered in such program or programs.
- (3) An identification of products, processes, or sectors whose inclusion could have a substantial carbon impact (prioritizing industrial products such as iron and steel, aluminum, cement, chemicals, and paper products, and also including food, beverage, hygiene, cleaning, household cleaners, construction, metals, clothing, semiconductor, and consumer electronics).
- (4) Suggested methodology and protocols for measuring the carbon content of the products across the entire carbon lifecycle of such products for use in a carbon disclosure program and labeling program.
- (5) A review of existing greenhouse gas product accounting standards, methodologies, and practices including the Greenhouse Gas Protocol, ISO 14040/44, ISO 14067, and Publically Available Specification 2050, and including a review of the strengths and weaknesses of each.
- (6) A survey of secondary databases including the Manufacturing Energy Consumption Survey and evaluate the quality of data for use in a product carbon disclosure program and product carbon labeling program and an identification of gaps in the data relative to the potential purposes of a national product carbon disclosure program and product carbon labeling program and development of recommendations for addressing these data gaps.
- (7) An assessment of the utility of comparing products and the appropriateness of product carbon standards.
- (8) An evaluation of the information needed on a label for clear and accurate communication, including what pieces of quantitative and qualitative information needs to be disclosed.
- (9) An evaluation of the appropriate boundaries of the carbon lifecycle analysis for different sectors and products.
- (10) An analysis of whether default values should be developed for products whose producer does not participate in the program or does not have data to support a disclosure or label and determine best ways to develop such default values.
- (11) A recommendation of certification and verification options necessary to assure the quality of the information and avoid greenwashing or the use of insubstantial or

- meaningless environmental claims to promote a product.
- (12) An assessment of options for educating consumers about product carbon content and the product carbon disclosure program and product carbon labeling program.
- (13) An analysis of the costs and timelines associated with establishing a national product carbon disclosure program and product carbon labeling program, including options for a phased approach. Costs should include those for businesses associated with the measurement of carbon footprints and those associated with creating a product carbon label and managing and operating a product carbon labeling program, and options for minimizing these costs.
- (14) An evaluation of incentives (such as financial incentives, brand reputation, and brand loyalty) to determine whether reductions in emissions can be accelerated through encouraging more efficient manufacturing or by encouraging preferences for lower-emissions products to substitute for higher-emissions products whose level of performance is no better
- (b) DEVELOPMENT OF NATIONAL CARBON DISCLOSURE PROGRAM.—Upon conclusion of the study, and not more than 36 months after the date of enactment of this Act, the Administrator shall establish a national product carbon disclosure program, participation in which shall be voluntary, and which may involve a product carbon label with broad applicability to the wholesale and consumer markets to enable and encourage knowledge about carbon content by producers and consumers and to inform efforts to reduce energy consumption (carbon dioxide equivalent emissions) nationwide. In developing such a program, the Administrator shall—
- (1) consider the results of the study conducted under subsection (a);
- (2) consider existing and planned programs and proposals and measurement standards (including the Publicly Available Specification 2050, standards to be developed by the World Resource Institute/World Business Council for Sustainable Development, the International Standards Organization, and the bill AB19 pending in the California legislature);
- (3) consider the compatibility of a national product carbon disclosure program with existing programs;
- (4) utilize incentives and other means to spur the adoption of product carbon disclosure and product carbon labeling;
- (5) develop protocols and parameters for a product carbon disclosure program, including a methodology and formula for assessing, verifying, and potentially labeling a product's greenhouse gas content, and for data quality requirements to allow for product comparison:
 - (6) create a means to—
 - (A) document best practices;
 - (B) ensure clarity and consistency;
- (C) work with suppliers, manufacturers, and retailers to encourage participation;
- (D) ensure that protocols are consistent and comparable across like products; and
- (E) evaluate the effectiveness of the program;
- (7) make publicly available information on product carbon content to ensure transparency;
- (8) provide for public outreach, including a consumer education program to increase awareness:
- (9) develop training and education programs to help businesses learn how to measure and communicate their carbon footprint and easy tools and templates for businesses to use to reduce cost and time to measure their products' carbon lifecycle;
- (10) consult with the Secretary of Energy, the Secretary of Commerce, the Federal

Trade Commission, and other Federal agencies, as necessary;

- (11) gather input from stakeholders through consultations, public workshops or hearings with representatives of consumer product manufacturers, consumer groups, and environmental groups;
- (12) utilize systems for verification and product certification that will ensure that claims manufacturers make about their products are valid;
- (13) create a process for reviewing the accuracy of product carbon label information and protecting the product carbon label in the case of a change in the product's energy source, supply chain, ingredients, or other factors, and specify the frequency to which data should be updated; and
- (14) develop a standardized, easily understandable carbon label, if appropriate, and create a process for responding to inaccuracies and misuses of such a label.
- (c) REPORT TO CONGRESS.—Not later than 5 years after the program is established pursuant to subsection (b), the Administrator shall report to Congress on the effectiveness and impact of the program, the level of voluntary participation, and any recommendations for additional measures.
- (d) DEFINITIONS.—As used in this section—(1) the term "carbon content" means the
- amount of greenhouse gas emissions and their warming impact on the atmosphere expressed in carbon dioxide equivalent associated with a product's value chain;
- (2) the term "carbon footprint" means the level of greenhouse gas emissions produced by a particular activity, service, or entity; and
- (3) the term "carbon lifecycle" means the greenhouse gas emissions that are released as part of the processes of creating, producing, processing or manufacturing, modifying, transporting, distributing, storing, using, recycling, or disposing of goods and services.
- (e) AUTHORIZATION OF APPROPRIATIONS.— There is authorized to be appropriated to the Administrator \$5,000,000 for the study required by subsection (a) and \$25,000,000 for each of fiscal years 2010 through 2025 for the program required under subsection (b).

SEC. 275. INDUSTRIAL ENERGY EFFICIENCY EDU-CATION AND TRAINING INITIATIVE.

- (a) IN GENERAL.—The Secretary of Energy shall carry out a national education and awareness program for the purpose of informing building, facility, and industrial plant owners and managers and decision-makers, government leaders, and industry leaders about the large energy-saving potential of greater use of mechanical insulation, and other benefits.
- (b) PURPOSE AND GOALS.—
- (1) PURPOSE.—The purpose of the initiative shall be to increase the energy efficiency of the commercial and industrial sectors through an ongoing program that will include—
- (A) education and training sessions;
- (B) Web-based information; and
- (C) advertising.
- (2) Goals.—The goals of the initiative shall be to— $\,$
- (A) educate and motivate commercial building owners and industrial facility managers to utilize mechanical insulation in new and existing facilities;
- (B) preserve and create jobs while reducing energy and greenhouse gas emissions;
- (C) create a safer working environment and make businesses more competitive in a global economy; and
- (D) motivate and empower the industry to make better use of mechanical insulation through awareness, education, and training.
- through awareness, education, and training. (c) REPORT.—Not later than July 1, 2013, the Secretary shall submit to Congress a re-

- port describing the extent by which the initiative has been enacted and the actual and projected effectiveness of the program under this section, including the energy efficiency, greenhouse gas emissions reductions, cost savings, and safety benefits at manufacturing facilities, power plants, refineries, hospitals, universities, government buildings, and other commercial and industrial locations.
- (d) AUTHORIZATION OF APPROPRIATIONS.—There are authorized to be appropriated \$3,500,000 for each of fiscal years 2010 through 2014 to carry out this section. The Secretary may enter into a cooperative agreement, including grant funding, with an industry association and union working collaboratively and having expertise on the installation, maintenance, measure of efficiencies and standards, and certification of mechanical insulation in buildings and facilities.
- (e) TERMINATION OF AUTHORITY.—The program carried out under this section shall terminate on December 31, 2014.

SEC. 276. SENSE OF CONGRESS.

- It is the sense of Congress that the United States should—
- (1) continue to actively promote, within the International Civil Aviation Organization, the development of a global framework for the regulation of greenhouse gas emissions from civil aircraft that recognizes the uniquely international nature of the industry and treats commercial aviation industries in all countries fairly; and
- (2) work with foreign governments towards a global agreement that reconciles foreign carbon emissions reduction programs to minimize duplicative requirements and avoids unnecessary complication for the aviation industry, while still achieving the environmental goals.

Subtitle H—Green Resources for Energy Efficient Neighborhoods

SEC. 281. SHORT TITLE.

This subtitle may be cited as the "Green Resources for Energy Efficient Neighborhoods Act of 2009" or the "GREEN Act of 2009".

SEC. 282. DEFINITIONS.

For purposes of this subtitle, the following definitions shall apply:

- (1) Green building standards.—The term "green building standards" means standards to require use of sustainable design principles to reduce the use of nonrenewable resources, encourage energy-efficient construction and rehabilitation and the use of renewable energy resources, minimize the impact of development on the environment, and improve indoor air quality.
- (2) HUD.—The term "HUD" means the Department of Housing and Urban Development.
- (3) HUD ASSISTANCE.—The term "HUD assistance" means financial assistance that is awarded, competitively or noncompetitively, allocated by formula, or provided by HUD through loan insurance or guarantee.
- (4) Nonresidential structures" means only nonresidential structures that are appurtenant to single-family or multifamily housing residential structures, or those that are funded by the Secretary of Housing and Urban Development through the HUD Community Development Block Grant program.
- (5) SECRETARY.—The term "Secretary", unless otherwise specified, means the Secretary of Housing and Urban Development.

SEC. 283. IMPLEMENTATION OF ENERGY EFFI-CIENCY PARTICIPATION INCEN-TIVES FOR HUD PROGRAMS.

(a) IN GENERAL.—Not later than 180 days after the date of the enactment of this Act, the Secretary shall issue such regulations as

may be necessary to establish annual energy efficiency participation incentives to encourage participants in programs administered by the Secretary, including recipients under programs for which HUD assistance is provided, to achieve substantial improvements in energy efficiency.

(b) REQUIREMENT FOR APPROPRIATION OF FUNDS.—The requirement under subsection (a) for the Secretary to provide annual energy efficiency participation incentives pursuant to the provisions of this subtitle shall be subject to the annual appropriation of necessary funds.

SEC. 284. BASIC HUD ENERGY EFFICIENCY STANDARDS AND STANDARDS FOR ADDITIONAL CREDIT.

- (a) BASIC HUD STANDARD.-
- (1) RESIDENTIAL STRUCTURES.—A residential single-family or multifamily structure shall be considered to comply with the energy efficiency standards under this subsection if—
- (A) the structure complies with an energy efficiency building code that has been certified as in compliance with section 304 of the Energy Conservation and Production Act (42 U.S.C. 6833) as amended by section 201 of this Act, or a national energy efficiency building code adopted pursuant to that section:
- (B) the structure complies with the applicable provisions of the American Society of Heating, Refrigerating, and Air-Conditioning Engineers Standard 90.1–2007, as such standard or successor standard is in effect for purposes of this section pursuant subsection (c);
- (C) the structure complies with the applicable provisions of the 2009 International Energy Conservation Code, as such standard or successor standard is in effect for purposes of this section pursuant subsection (c);
- (D) in the case only of an existing structure, where determined cost effective, the structure has undergone rehabilitation or improvements, completed after the date of the enactment of this Act, and the energy consumption for the structure has been reduced by at least 20 percent from the previous level of consumption, as determined in accordance with energy audits performed both before and after any rehabilitation or improvements undertaken to reduce such consumption; or
- (E) the structure complies with the applicable provisions of such other energy efficiency requirements, standards, checklists, or ratings systems as the Secretary may adopt and apply by regulation, as may be necessary, for purposes of this section for specific types of residential single-family or multifamily structures or otherwise, except that the Secretary shall make a determination regarding whether to adopt and apply any such requirements, standards, checklists, or rating system for purposes of this section not later than the expiration of the 180-day period beginning upon the date of receipt of any written request, made in such form as the Secretary shall provide, for such adoption and application.

In addition to compliance with any of subparagraphs (A) through (E), the Secretary shall by regulation require, for any newly constructed residential single-family or multifamily structure to be considered to comply with the energy efficiency standards under this subsection, that the structure have appropriate electrical outlets with the facility and capacity to recharge a standard electric passenger vehicle, including an electric hybrid vehicle, where such vehicle would normally be parked.

(2) NONRESIDENTIAL STRUCTURES.—For purposes of this section, the Secretary shall identify and adopt by regulation, as may be necessary, energy efficiency requirements,

standards, checklists, or rating systems applicable to nonresidential structures that are constructed or rehabilitated with HUD assistance. A nonresidential structure shall be considered to comply with the energy efficiency standards under this subsection if the structure complies with the applicable provisions of any such energy efficiency requirements, standards, checklist, or rating systems identified and adopted by the Secretary pursuant to this paragraph, as such standards are in effect for purposes of this section pursuant to subsection (c).

- (3) EFFECT.—Nothing in this subsection may be construed to require any structure to comply with any standard established or adopted pursuant to this subsection, or identified in this subsection, or to provide any benefit or credit under any Federal program for any structure that complies with any such standard, except to the extent that—
- (A) any provision of law other than this subsection provides a benefit or credit under a Federal program for compliance with a standard established or adopted pursuant to this subsection, or identified in this subsection; or
- (B) the Secretary specifically provides pursuant to subsection (c) for the applicability of such standard.
- (b) ENHANCED ENERGY EFFICIENCY STANDARDS FOR PURPOSES OF PROVIDING ADDITIONAL CREDIT UNDER CERTAIN FEDERALLY ASSISTED HOUSING PROGRAMS.—
 - (1) Purpose and effect.—
- (A) PURPOSE.—The purpose of this subsection is to establish energy efficiency and conservation standards and green building standards that—
- (i) provide for greater energy efficiency and conservation in structures than is required for compliance with the energy efficiency standards under subsection (a) and then in effect:
- (ii) provide for green and sustainable building standards not required by such standards and
- (iii) can be used in connection with Federal housing, housing finance, and development programs to provide incentives for greater energy efficiency and conservation and for green and sustainable building methods, elements, practices, and materials.
- (B) EFFECT.—Nothing in this subsection may be construed to require any structure to comply with any standard established pursuant to this subsection or to provide any benefit or credit under any Federal program for any structure, except to the extent that any provision of law other than this subsection provides a benefit or credit under a Federal program for compliance with a standard established pursuant to this subsection.
- (2) COMPLIANCE.—A residential or nonresidential structure shall be considered to comply with the enhanced energy efficiency and conservation standards or the green building standards under this subsection, to the extent that such structure complies with the applicable provisions of the standards under paragraph (3) or (4), respectively (as such standards are in effect for purposes of this section, pursuant to paragraph (7)), in a manner that is not required for compliance with the energy efficiency standards under subsection (a) then in effect and subject to the Secretary's determination of which standards are applicable to which structures.
- (3) ENERGY EFFICIENCY AND CONSERVATION STANDARDS.—The energy efficiency and conservation standards under this paragraph are as follows:
- (A) RESIDENTIAL STRUCTURES.—With respect to residential structures:
- (i) NEW CONSTRUCTION.—For new construction, the Energy Star standards established by the Environmental Protection Agency, as

- such standards are in effect for purposes of this subsection pursuant to paragraph (7);
- (ii) EXISTING STRUCTURES.—For existing structures, a reduction in energy consumption from the previous level of consumption for the structure, as determined in accordance with energy audits performed both before and after any rehabilitation or improvements undertaken to reduce such consumption, that exceeds the reduction necessary for compliance with the energy efficiency standards under subsection (a) then in effect and applicable to existing structures.
- (B) NONRESIDENTIAL STRUCTURES.—With respect to nonresidential structures, such energy efficiency and conservation requirements, standards, checklists, or rating systems for nonresidential structures as the Secretary shall identify and adopt by regulation, as may be necessary, for purposes of this paragraph.
- (4) GREEN BUILDING STANDARDS.—The green building standards under this paragraph are as follows:
- (A) The national Green Communities criteria checklist for residential construction that provides criteria for the design, development, and operation of affordable housing, as such checklist or successor checklist is in effect for purposes of this section pursuant to paragraph (7).
- (B) The gold certification level for the LEED for New Construction rating system, the LEED for Homes rating system, the LEED for Core and Shell rating system, as applicable, as such systems or successor systems are in effect for purposes of this section pursuant to paragraph (7).
- (C) The Green Globes assessment and rating system of the Green Buildings Initiative.
- (D) For manufactured housing, energy star rating with respect to fixtures, appliances, and equipment in such housing, as such standard or successor standard is in effect for purposes of this section pursuant to paragraph (7).
- (E) The National Green Building Standard.
- (F) Any other requirements, standards, checklists, or rating systems for green building or sustainability as the Secretary may identify and adopt by regulation, as may be necessary for purposes of this paragraph, except that the Secretary shall make a determination regarding whether to adopt and apply any such requirements, standards, checklist, or rating system for purposes of this section not later than the expiration of the 180-day period beginning upon date of receipt of any written request, made in such form as the Secretary shall provide, for such adoption and application.
- (5) GREEN BUILDING.—For purposes of this subsection, the term "green building" means, with respect to standards for structures, standards to require use of sustainable design principles to reduce the use of non-renewable resources, minimize the impact of development on the environment, and to improve indoor air quality.
- prove indoor air quality.
 (6) ENERGY AUDITS.—The Secretary shall establish standards and requirements for energy audits for purposes of paragraph (3)(A)(ii) and, in establishing such standards, may consult with any advisory committees established pursuant to section 285(c)(2) of this subtitle.
- (7) APPLICABILITY AND UPDATING OF STANDARDS —
- (A) APPLICABILITY.—Except as provided in subparagraph (B), the requirements, standards, checklists, and rating systems referred to in this subsection that are in effect for purposes of this subsection are such requirements, standards, checklists, and systems are as in existence upon the date of the enactment of this Act.
- (B) UPDATING.—For purposes of this section, the Secretary may adopt and apply by

- regulation, as may be necessary, future amendments and supplements to, and editions of, the requirements, standards, checklists, and rating systems referred to in this subsection, including applicable energy efficiency building codes that are certified as in compliance with section 304 of the Energy Conservation and Production Act (42 U.S.C. 6833) as amended by section 201 of this Act, or national energy efficiency building codes adopted pursuant to that section.
- (c) AUTHORITY OF SECRETARY TO APPLY STANDARDS TO FEDERALLY ASSISTED HOUSING AND PROGRAMS.—
- (1) HUD HOUSING AND PROGRAMS.—The Secretary of Housing and Urban Development may, by regulation, provide for the applicability of the energy efficiency standards under subsection (a) or the enhanced energy efficiency and conservation standards and green building standards under subsection (b), or both, with respect to any covered federally assisted housing described in paragraph (3)(A) or any HUD assistance, subject to minimum Federal codes or standards then in effect.
- (2) RURAL HOUSING.—The Secretary of Agriculture may, by regulation, provide for the applicability of the energy efficiency standards under subsection (a) or the enhanced energy efficiency and conservation standards and green building standards under subsection (b), or both, with respect to any covered federally assisted housing described in paragraph (3)(B) or any assistance provided with respect to rural housing by the Rural Housing Service of the Department of Agriculture, subject to minimum Federal codes or standards then in effect.
- (3) COVERED FEDERALLY ASSISTED HOUSING.—For purposes of this subsection, the term "covered federally assisted housing" means—
- (A) any residential or nonresidential structure for which any HUD assistance is provided; and
- (B) any new construction of single-family housing (other than manufactured homes) subject to mortgages insured, guaranteed, or made by the Secretary of Agriculture under title V of the Housing Act of 1949 (42 U.S.C. 1471 et seq.).
- SEC. 285. ENERGY EFFICIENCY AND CONSERVATION DEMONSTRATION PROGRAM FOR MULTIFAMILY HOUSING PROJECTS ASSISTED WITH PROJECT-BASED RENTAL ASSISTANCE.
- (a) AUTHORITY.—For multifamily housing projects for which project-based rental assistance is provided under a covered multifamily assistance program, the Secretary shall, subject to the availability of amounts provided in advance in appropriation Acts, carry out a program to demonstrate the effectiveness of funding a portion of the costs of meeting the enhanced energy efficiency standards under section 284(b). At the discretion of the Secretary, the demonstration program may include incentives for housing that is assisted with Indian housing block grants provided pursuant to the Native American Housing Assistance and Self-Determination Act of 1996, but only to the extent that such inclusion does not violate such Act, its regulations, and the goal of such Act of tribal self-determination.
- (b) GOALS.—The demonstration program under this section shall be carried out in a manner that—
- (1) protects the financial interests of the Federal Government:
- (2) reduces the proportion of funds provided by the Federal Government and by owners and residents of multifamily housing projects that are used for costs of utilities for the projects:

- (3) encourages energy efficiency and conservation by owners and residents of multifamily housing projects and installation of renewable energy improvements, such as improvements providing for use of solar, wind, geothermal, or biomass energy sources;
- (4) creates incentives for project owners to carry out such energy efficiency renovations and improvements by allowing a portion of the savings in operating costs resulting from such renovations and improvements to be retained by the project owner, notwithstanding otherwise applicable limitations on dividends;
- (5) promotes the installation, in existing residential buildings, of energy-efficient and cost-effective improvements and renewable energy improvements, such as improvements providing for use of solar, wind, geothermal, or biomass energy sources;
- (6) tests the efficacy of a variety of energy efficiency measures for multifamily housing projects of various sizes and in various geographic locations;
- (7) tests methods for addressing the various, and often competing, incentives that impede owners and residents of multifamily housing projects from working together to achieve energy efficiency or conservation; and
- (8) creates a database of energy efficiency and conservation, and renewable energy, techniques, energy-savings management practices, and energy efficiency and conservation financing vehicles.
- (c) APPROACHES.—In carrying out the demonstration program under this section, the Secretary may—
- (1) enter into agreements with the Building America Program of the Department of Energy and other consensus committees under which such programs, partnerships, or committees assume some or all of the functions, obligations, and benefits of the Secretary with respect to energy savings;
- (2) establish advisory committees to advise the Secretary and any such third-party partners on technological and other developments in the area of energy efficiency and the creation of an energy efficiency and conservation credit facility and other financing opportunities, which committees shall include representatives of homebuilders, realtors, architects, nonprofit housing organizations, environmental protection organizations, renewable energy organizations, and advocacy organizations for the elderly and persons with disabilities; any advisory committees established pursuant to this paragraph shall not be subject to the Federal Advisory Committee Act (5 U.S.C. App.):
- (3) approve, for a period not to exceed 10 years, additional adjustments in the maximum monthly rents or additional project rental assistance, or additional Indian housing block grant funds under the Native American Housing Assistance and Self-Determination Act of 1996, as applicable, for dwelling units in multifamily housing projects that are provided project-based rental assistance under a covered multifamily assistance program, in such amounts as may be necessary to amortize a portion of the cost of energy efficiency and conservation measures for such projects;
- (4) develop a competitive process for the award of such additional assistance for multifamily housing projects seeking to implement energy efficiency, renewable energy sources, or conservation measures; and
- (5) waive or modify any existing statutory or regulatory provision that would otherwise impair the implementation or effectiveness of the demonstration program under this section, including provisions relating to methods for rent adjustments, comparability standards, maximum rent schedules, and utility allowances; notwithstanding the pre-

- ceding provisions of this paragraph, the Secretary may not waive any statutory requirement relating to fair housing, non-discrimination, labor standards, or the environment, except pursuant to existing authority to waive nonstatutory environmental and other applicable requirements.
- (d) REQUIREMENT.—During the 4-year period beginning 12 months after the date of the enactment of this Act, the Secretary shall carry out demonstration programs under this section with respect to not fewer than 50.000 dwelling units.
 - (e) SELECTION.-
- (1) Scope.—In order to provide a broad and representative profile for use in designing a program which can become operational and effective nationwide, the Secretary shall carry out the demonstration program under this section with respect to dwelling units located in a wide variety of geographic areas and project types assisted by the various covered multifamily assistance programs and using a variety of energy efficiency and conservation and funding techniques to reflect differences in climate, types of dwelling units and technical and scientific methodologies, and financing options. The Secretary shall ensure that the geographic areas included in the demonstration program include dwelling units on Indian lands (as such term is defined in section 2601 of the Energy Policy Act of 1992 (25 U.S.C. 3501), to the extent that dwelling units on Indian land have the type of residential structures that are the focus of the demonstration program.
- (2) PRIORITY.—The Secretary shall provide priority for selection for participation in the program under this section based on the extent to which, as a result of assistance provided, the project will comply with the energy efficiency standards under subsection (a), (b), or (c) of section 284 of this subtitle.
- (f) USE OF EXISTING PARTNERSHIPS.—To the extent feasible, the Secretary shall—
- (1) utilize the Partnership for Advancing Technology in Housing of the Department of Housing and Urban Development to assist in carrying out the requirements of this section and to provide education and outreach regarding the demonstration program authorized under this section; and
- (2) consult with the Secretary of Energy, the Administrator of the Environmental Protection Agency, and the Secretary of the Army regarding utilizing the Building America Program of the Department of Energy, the Energy Star Program, and the Army Corps of Engineers, respectively, to determine the manner in which they might assist in carrying out the goals of this section and providing education and outreach regarding the demonstration program authorized under this section.
- (g) LIMITATION.—No amounts made available under the American Recovery and Reinvestment Act of 2009 (Public Law 111–5) may be used to carry out the demonstration program under this section.
 - (h) Reports.—
- (1) ANNUAL.—Not later than the expiration of the 2-year beginning upon the date of the enactment of this Act, and for each year thereafter during the term of the demonstration program, the Secretary shall submit a report to the Congress annually that describes and assesses the demonstration program under this section.
- (2) FINAL.—Not later than 6 months after the expiration of the 4-year period described in subsection (d), the Secretary shall submit a final report to the Congress assessing the demonstration program, which—
- (A) shall assess the potential for expanding the demonstration program on a nationwide basis; and
- (B) shall include descriptions of—

- (i) the size of each multifamily housing project for which assistance was provided under the program;
- (ii) the geographic location of each project assisted, by State and region;
- (iii) the criteria used to select the projects for which assistance is provided under the program;
- (iv) the energy efficiency and conservation measures and financing sources used for each project that is assisted under the program;
- (v) the difference, before and during participation in the demonstration program, in the amount of the monthly assistance payments under the covered multifamily assistance program for each project assisted under the program:
- (vi) the average length of the term of the such assistance provided under the program for a project:
- (vii) the aggregate amount of savings generated by the demonstration program and the amount of savings expected to be generated by the program over time on a perunit and aggregate program basis;
- (viii) the functions performed in connection with the implementation of the demonstration program that were transferred or contracted out to any third parties;
- (ix) an evaluation of the overall successes and failures of the demonstration program;
- (x) recommendations for any actions to be taken as a result of the such successes and failures.
- (3) CONTENTS.—Each annual report pursuant to paragraph (1) and the final report pursuant to paragraph (2) shall include—
- (A) a description of the status of each multifamily housing project selected for participation in the demonstration program under this section; and
- (B) findings from the program and recommendations for any legislative actions.
- (i) COVERED MULTIFAMILY ASSISTANCE PROGRAM.—For purposes of this section, the term "covered multifamily assistance program" means—
- (1) the program under section 8 of the United States Housing Act of 1937 (42 U.S.C. 1437f) for project-based rental assistance;
- (2) the program under section 202 of the Housing Act of 1959 (12 U.S.C. 1701q) for assistance for supportive housing for the elderly;
- (3) the program under section 811 of the Cranston-Gonzalez National Affordable Housing Act (42 U.S.C. 8013) for supportive housing for persons with disabilities;
- (4) the program under section 236 of the National Housing Act (12 U.S.C. 1715z-1 for assistance for rental housing projects;
- (5) the program under section 515 of the Housing Act of 1949 (42 U.S.C. 1485) for rural rental housing; and
- (6) the program for assistance under the Native American Housing Assistance and Self-Determination Act of 1996 (25 U.S.C. 4111).
- (j) AUTHORIZATION OF APPROPRIATIONS.— There is authorized to be appropriated to carry out this section, including providing rent adjustments, additional project rental assistance, and incentives, \$50,000,000 for each fiscal year in which the demonstration program under this section is carried out.
- (k) REGULATIONS.—Not later than the expiration of the 180-day period beginning on the date of the enactment of this Act, the Secretary shall issue any regulations necessary to carry out this section.

SEC. 286. ADDITIONAL CREDIT FOR FANNIE MAE AND FREDDIE MAC HOUSING GOALS FOR ENERGY-EFFICIENT AND LOCA-TION-EFFICIENT MORTGAGES.

Section 1336(a) of the Housing and Community Development Act of 1992 (12 U.S.C. 4566(a)), as amended by the Federal Housing

Finance Regulatory Reform Act of 2008 (Public Law 110–289; 122 Stat. 2654), is amended—

- (1) in paragraph (2), by striking "paragraph (5)" and inserting "paragraphs (5) and (6)"; and
- (2) by adding at the end the following new paragraph:
- "(6) ADDITIONAL CREDIT.—
- "(A) IN GENERAL.—In assigning credit toward achievement under this section of the housing goals for mortgage purchase activities of the enterprises, the Director shall assign—
- "(i) more than 125 percent credit, for any such purchase that both—
- "(I) complies with the requirements of such goals: and
- "(II)(aa) supports housing that meets the energy efficiency standards under section 284(a) of the Green Resources for Energy Efficient Neighborhoods Act of 2009; or
- "(bb) is a location-efficient mortgage, as such term is defined in section 1335(e); and
- "(ii) credit in addition to credit under clause (i), for any such purchase that both—
- "(I) complies with the requirements of such goals, and
- "(II) supports housing that complies with the enhanced energy efficiency and conservation standards, or the green building standards, under section 284(b) of such Act, or both,

and such additional credit shall be given based on the extent to which the housing supported with such purchases complies with such standards.

"(B) TREATMENT OF ADDITIONAL CREDIT.— The availability of additional credit under this paragraph shall not be used to increase any housing goal, subgoal, or target established under this subpart."

SEC. 287. DUTY TO SERVE UNDERSERVED MARKETS FOR ENERGY-EFFICIENT AND LOCATION-EFFICIENT MORTGAGES.

Section 1335 of Federal Housing Enterprises Financial Safety and Soundness Act of 1992 (12 U.S.C. 4565), as amended by the Federal Housing Finance Regulatory Reform Act of 2008 (Public Law 110–289; 122 Stat. 2654), is amended—

- (1) in subsection (a)(1), by adding at the end the following new subparagraph:
- ``(D) Markets for energy-efficient and location-efficient mortgages.—
- "(i) DUTY.—Subject to clause (ii), the enterprise shall develop loan products and flexible underwriting guidelines to facilitate a secondary market for energy-efficient and location-efficient mortgages on housing for very low-, low-, and moderate-income families, and for second and junior mortgages made for purposes of energy efficiency or renewable energy improvements, or both.
- "(ii) AUTHORITY TO SUSPEND.—Notwithstanding any other provision of this section, the Director may suspend the applicability of the requirement under clause (i) with respect to an enterprise, for such period as is necessary, if the Director determines that exigent circumstances exist and such suspension is appropriate to ensure the safety and soundness of the portfolio holdings of the enterprise.";
- (2) by adding at the end the following new subsection:
- "(e) DEFINITIONS.—For purposes of this section, the following definitions shall apply:
- "(1) ENERGY-EFFICIENT MORTGAGE.—The term 'energy-efficient mortgage' means a mortgage loan under which the income of the borrower, for purposes of qualification for such loan, is considered to be increased by not less than \$1 for each \$1 of savings projected to be realized by the borrower as a result of cost-effective energy-saving design, construction or improvements (including use of renewable energy sources, such as solar,

geothermal, biomass, and wind, super-insulation, energy-saving windows, insulating glass and film, and radiant barrier) for the home for which the loan is made.

- "(2) LOCATION-EFFICIENT MORTGAGE.—The term 'location-efficient mortgage' means a mortgage loan under which—
- "(A) the income of the borrower, for purposes of qualification for such loan, is considered to be increased by not less than \$1 for each \$1 of savings projected to be realized by the borrower because the location of the home for which loan is made will result in decreased transportation costs for the household of the borrower; or
- "(B) the sum of the principal, interest, taxes, and insurance due under the mortgage loan is decreased by not less than \$1 for each \$1 of savings projected to be realized by the borrower because the location of the home for which loan is made will result in decreased transportation costs for the household of the borrower."

SEC. 288. CONSIDERATION OF ENERGY EFFI-CIENCY UNDER FHA MORTGAGE IN-SURANCE PROGRAMS AND NATIVE AMERICAN AND NATIVE HAWAIIAN LOAN GUARANTEE PROGRAMS.

(a) FHA MORTGAGE INSURANCE.—

(1) REQUIREMENT.—Title V of the National Housing Act is amended by adding after section 542 (12 U.S.C. 1735f-20) the following new section:

"SEC. 543. CONSIDERATION OF ENERGY EFFI-CIENCY.

- "(a) UNDERWRITING STANDARDS.—The Secretary shall establish a method to consider, in its underwriting standards for mortgages on single-family housing meeting the energy efficiency standards under section 284(a) of the Green Resources for Energy Efficient Neighborhoods Act of 2009 that are insured under this Act, the impact that savings on utility costs has on the income of the mortgagor.
- "(b) GoAL.—It is the sense of the Congress that, in carrying out this Act, the Secretary should endeavor to insure mortgages on single-family housing meeting the energy efficiency standards under section 284(a) of the Green Resources for Energy Efficient Neighborhoods Act of 2009 such that at least 50,000 such mortgages are insured during the period beginning upon the date of the enactment of such Act and ending on December 31, 2012."
- (2) REPORTING ON DEFAULTS.—Section 540(b) of the National Housing Act (12 U.S.C. 1735f-18(b)) is amended by adding at the end the following new paragraph:
- "(3) With respect to each collection period that commences after December 31, 2011, the total number of mortgages on single-family housing meeting the energy efficiency standards under section 284(a) of the Green Resources for Energy Efficient Neighborhoods Act of 2009 that are insured by the Secretary during the applicable collection period, the number of defaults and foreclosures occurring on such mortgages during such period, the percentage of the total of such mortgages insured during such period on which defaults and foreclosure occurred, and the rate for such period of defaults and foreclosures on such mortgages compared to the overall rate for such period of defaults and foreclosures on mortgages for single-family housing insured under this Act by the Secretary.
- (b) Indian Housing Loan Guarantees.—
- (1) REQUIREMENT.—Section 184 of the Housing and Community Development Act of 1992 (12 U.S.C. 1715z-13a) is amended—
- (A) by redesignating subsection (l) as subsection (m); and
- (B) by inserting after subsection (k) the following new subsection:
- "(1) CONSIDERATION OF ENERGY EFFI-CIENCY.—The Secretary shall establish a

method to consider, in its underwriting standards for loans for single-family housing meeting the energy efficiency standards under section 284(a) of the Green Resources for Energy Efficient Neighborhoods Act of 2009 that are guaranteed under this section, the impact that savings on utility costs has on the income of the borrower."

(2) REPORTING ON DEFAULTS.—Section 540(b) of the National Housing Act (12 U.S.C. 1735f-18(b)), as amended by subsection (a)(2) of this section, is further amended by adding at the end the following new paragraph:

- '(4) With respect to each collection period that commences after December 31, 2011, the total number of loans guaranteed under section 184 of the Housing and Community Development, Act, of 1992 (12 U.S.C. 1715z-13a) on single-family housing meeting the energy efficiency standards under section 284(a) of the Green Resources for Energy Efficient Neighborhoods Act of 2009 that are guaranteed by the Secretary during the applicable collection period, the number of defaults and foreclosures occurring on such loans during such period, the percentage of the total of such loans guaranteed during such period on which defaults and foreclosure occurred, and the rate for such period of defaults and foreclosures on such loans compared to the overall rate for such period of defaults and foreclosures on loans for single-family housing guaranteed under such section 184 by the Secretary.
- (c) NATIVE HAWAIIAN HOUSING LOAN GUARANTEES.—
- (1) REQUIREMENT.—Section 184A of the Housing and Community Development Act of 1992 (12 U.S.C. 1715z-13b) is amended by inserting after subsection (1) the following new subsection:

"(m) ENERGY-EFFICIENT HOUSING REQUIRE-MENT.—The Secretary shall establish a method to consider, in its underwriting standards for loans for single-family housing meeting the energy efficiency standards under section 284(a) of the Green Resources for Energy Efficient Neighborhoods Act of 2009 that are guaranteed under this section, the impact that savings on utility costs has on the income of the borrower."

(2) REPORTING ON DEFAULTS.—Section 540(b) of the National Housing Act (12 U.S.C. 1735f–18(b)), as amended by the preceding provisions of this section, is further amended by adding at the end the following new paragraph:

(5) With respect to each collection period that commences after December 31, 2011, the total number of loans guaranteed under section 184A of the Housing and Community Development Act of 1992 (12 U.S.C. 1715z-13b) on single-family housing meeting the energy efficiency standards under section 284(a) of the Green Resources for Energy Efficient Neighborhoods Act of 2009 that are guaranteed by the Secretary during the applicable collection period, the number of defaults and foreclosures occurring on such loans during such period, the percentage of the total of such loans guaranteed during such period on which defaults and foreclosure occurred, and the rate for such period of defaults and foreclosures on such loans compared to the overall rate for such period of defaults and foreclosures on loans for single-family housing guaranteed under such section 184A by the Secretary.

SEC. 289. ENERGY-EFFICIENT MORTGAGES AND LOCATION-EFFICIENT MORTGAGES EDUCATION AND OUTREACH CAM-PAIGN.

Section 106 of the Energy Policy Act of 1992 (12 U.S.C. 1701z-16) is amended by adding at the end the following new subsection:

- "(g) EDUCATION AND OUTREACH CAMPAIGN.-
- "(1) DEVELOPMENT OF ENERGY- AND LOCATION-EFFICIENT MORTGAGES OUTREACH PROGRAM.—

"(A) COMMISSION.—The Secretary, in consultation and coordination with the Secretary of Energy, the Secretary of Education, the Secretary of Agriculture, and the Administrator of the Environmental Protection Agency, shall establish a commission to develop and recommend model mortgage products and underwriting guidelines that provide market-based incentives to prospective home buyers, lenders, and sellers to incorporate energy efficiency upgrades and location efficiencies in new mortgage loan transactions.

"(B) REPORT.—Not later than 24 months after the date of the enactment of this Act, the Secretary shall provide a written report to the Congress on the results of work of the commission established pursuant to subparagraph (A) and that identifies model mortgage products and underwriting guidelines that may encourage energy and location efficiency.

"(2) IMPLEMENTATION.—After submission of the report under paragraph (1)(B), the Secin consultation and coordination retary, with the Secretary of Energy, the Secretary of Education, and the Administrator of the Environmental Protection Agency, shall carry out a public awareness, education, and outreach campaign based on the findings of the commission established pursuant to paragraph (1) to inform and educate residential lenders and prospective borrowers regarding the availability, benefits, advantages, and terms of energy-efficient mortgages and location-efficient mortgages made available pursuant to this section, energy-efficient and location-efficient mortgages that meet the requirements of section 1335 of the Housing and Community Development Act of 1992 (42 U.S.C. 4565), and other mortgages, including mortgages for multifamily housing, that have energy improvement features or location efficiency features and to publicize such availability, benefits, advantages, and terms. Such actions may include entering into a contract with an appropriate entity to publicize and market such mortgages through appropriate media.

- "(3) RENEWABLE ENERGY HOME PRODUCT EXPOS.—The Congress hereby encourages the Secretary of Housing and Urban Development to work with appropriate entities to organize and hold renewable energy expositions that provide an opportunity for the public to view and learn about renewable energy products for the home that are currently on the market.
- "(4) AUTHORIZATION OF APPROPRIATIONS.— There is authorized to be appropriated to the Secretary to carry out this subsection \$5,000,000 for each of fiscal years 2010 through 2014"

SEC. 290. COLLECTION OF INFORMATION ON EN-ERGY-EFFICIENT AND LOCATION-EF-FICIENT MORTGAGES THROUGH HOME MORTGAGE DISCLOSURE ACT.

- (a) IN GENERAL.—Section 304(b) of the Home Mortgage Disclosure Act of 1975 (12 U.S.C. 2803(b)) is amended—
- (1) in paragraph (3), by striking "and" at the end;
- (2) in paragraph (4), by striking the period at the end and inserting a semicolon; and
- (3) by adding at the end the following new paragraphs:
- "(5) the number and dollar amount of mortgage loans for single-family housing and for multifamily housing that are energyefficient mortgages (as such term is defined in section 1335 of Housing and Community Development Act of 1992); and
- "(6) the number and dollar amount of mortgage loans for single-family housing and for multifamily housing that are location-efficient mortgages (as such term is defined in section 1335 of Housing and Community Development Act of 1992)."

(b) APPLICABILITY.—The amendment made by subsection (a) shall apply with respect to the first calendar year that begins after the expiration of the 30-day period beginning on the date of the enactment of this Act.

SEC. 291. ENSURING AVAILABILITY OF HOME-OWNERS INSURANCE FOR HOMES NOT CONNECTED TO ELECTRICITY GRID

- (a) CONGRESSIONAL INTENT.—The Congress intends that—
- (1) consumers shall not be denied homeowners insurance for a dwelling (as such term is defined in subsection (c)) based solely on the fact that the dwelling is not connected to or able to receive electricity service from any wholesale or retail electric power provider:
- (2) States should ensure that consumers are able to obtain homeowners insurance for such dwellings;
- (3) States should support insurers that develop voluntary incentives to provide such insurance; and
- (4) States may not prohibit insurers from offering a homeowners insurance product specifically designed for such dwellings.
- (b) INSURING HOMES AND RELATED PROPERTY IN INDIAN AREAS.—Notwithstanding any other provision of law, dwellings located in Indian areas (as such term is defined in section 4 of the Native American Housing Assistance and Self-Determination Act of 1996 (25 U.S.C. 4103)) and constructed or maintained using assistance, loan guarantees, or other authority under the Native American Housing Assistance and Self-Determination Act of 1996 may be insured by any tribally owned self-insurance risk pool approved by the Secretary of Housing and Urban Development.
- (c) DWELLING.—For purposes of this section, the term "dwelling" means a residential structure that—
- (1) consists of one to four dwelling units;
- (2) is provided electricity from renewable energy sources; and
- (3) is not connected to any wholesale or retail electrical power grid.

SEC. 292. MORTGAGE INCENTIVES FOR ENERGY-EFFICIENT MULTIFAMILY HOUSING.

- (a) IN GENERAL.—The Secretary of Housing and Urban Development shall establish incentives for increasing the energy efficiency of multifamily housing that is subject to a mortgage to be insured under title II of the National Housing Act (12 U.S.C. 1707 et seq.) so that the housing meets the energy efficiency standards under section 284(a) of this subtitle and incentives to encourage compliance of such housing with the energy efficiency and conservation standards, and the green building standards, under section 284(b) of this subtitle, to the extent that such incentives are based on the impact that savings on utility costs has on the operating costs of the housing, as determined by the Secretary.
- (b) INCENTIVES.—Such incentives may include, for any such multifamily housing that complies with the energy efficiency standards under section 284(a)—
- (1) providing a discount on the chargeable premiums for the mortgage insurance for such housing from the amount otherwise chargeable for such mortgage insurance;
- (2) allowing mortgages to exceed the dollar amount limits otherwise applicable under law to the extent such additional amounts are used to finance improvements or measures designed to meet the standards referred to in subsection (a); and
- (3) reducing the amount that the owner of such multifamily housing meeting the standards referred to in subsection (a) is required to contribute.

SEC. 293. ENERGY-EFFICIENT CERTIFICATIONS FOR MANUFACTURED HOUSING WITH MORTGAGES.

Section 526 of the National Housing Act (12 U.S.C. 1735f-4(a)) is amended—

(1) in subsection (a)-

(A) by striking ", other than manufactured homes." each place such term appears;

(B) by inserting after the period at the end the following: "The energy performance requirements developed and established by the Secretary under this section for manufactured homes shall require energy star rating for wall fixtures, appliances, and equipment in such housing.";

(C) by inserting "(1)" after "(a)"; and

(D) by adding at the end the following new paragraphs:

"(2) The Secretary shall require, with respect to any single- or multi-family residential housing subject to a mortgage insured under this Act, that any approval or certification of the housing for meeting any energy efficiency or conservation criteria, standards, or requirements pursuant to this title and any approval or certification required pursuant to this title with respect to energyconserving improvements or any renewable energy sources, such as wind, solar energy geothermal, or biomass, shall be conducted only by an individual certified by a home energy rating system provider who has been accredited to conduct such ratings by the Home Energy Ratings System Council, the Residential Energy Services Network. or such other appropriate national organization, as the Secretary may provide, or by licensed professional architect or engineer. If any organization makes a request to the Secretary for approval to accredit individuals to conduct energy efficiency or conservation ratings, the Secretary shall review and approve or disapprove such request not later than the expiration of the 6-month period beginning upon receipt of such request.

"(3) The Secretary shall periodically examine the method used to conduct inspections for compliance with the requirements under this section, analyze various other approaches for conducting such inspections, and review the costs and benefits of the current method compared with other methods.";

and
(2) in subsection (b), by striking ", other than a manufactured home,".

SEC. 294. ASSISTED HOUSING ENERGY LOAN PILOT PROGRAM.

- (a) AUTHORITY.—Not later than the expiration of the 12-month period beginning on the date of the enactment of this Act, the Secretary shall develop and implement a pilot program under this section to facilitate the financing of cost-effective capital improvements for covered assisted housing projects to improve the energy efficiency and conservation of such projects.
- (b) LOANS.—The pilot program under this section shall involve not less than three and not more than five lenders, and shall provide for a privately financed loan to be made for a covered assisted housing project, which shall—
- (1) finance capital improvements for the project that meet such requirements as the Secretary shall establish, and may involve contracts with third parties to perform such capital improvements, including the design of such improvements by licensed professional architects or engineers;
- (2) have a term to maturity of not more than 20 years, which shall be based upon the duration necessary to realize cost savings sufficient to repay the loan;
- (3) be secured by a mortgage subordinate to the mortgage for the project that is insured under the National Housing Act; and
- (4) provide for a reduction in the remaining principal obligation under the loan based on

the actual resulting cost savings realized from the capital improvements financed with the loan.

- (c) UNDERWRITING STANDARDS.—The Secretary shall establish underwriting requirements for loans made under the pilot program under this section, which shall—
- (1) require the cost savings projected to be realized from the capital improvements financed with the loan, during the term of the loan, to exceed the costs of repaying the loan:
- (2) allow the designer or contractor involved in designing capital improvements to be financed with a loan under the program to carry out such capital improvements; and
- (3) include such energy, audit, property, financial, ownership, and approval requirements as the Secretary considers appro-
- (d) TREATMENT OF SAVINGS.—The pilot program under this section shall provide that the project owner shall receive the full financial benefit from any reduction in the cost of utilities resulting from capital improvements financed with a loan made under the program.
- (e) COVERED ASSISTED HOUSING PROJECTS.— For purposes of this section, the term "covered assisted housing project" means a housing project that—
- (1) is financed by a loan or mortgage that is—
- (A) insured by the Secretary under-
- (i) subsection (d)(3) of section 221 of the National Housing Act (12 U.S.C. 17151), and bears interest at a rate determined under the proviso of section 221(d)(5) of such Act; or
 - (ii) subsection (d)(4) of such section 221.
- (B) insured or assisted under section 236 of the National Housing Act (12 U.S.C. 1715z-1);
- (2) at the time a loan under this section is made, is provided project-based rental assistance under section 8 of the United States Housing Act of 1937 (42 U.S.C. 1437f) for 50 percent or more of the dwelling units in the project; and
- (3) is not a housing project owned or held by the Secretary, or subject to a mortgage held by the Secretary.

SEC. 295. MAKING IT GREEN.

- (a) PARTNERSHIPS WITH TREE-PLANTING OR-GANIZATIONS.—The Secretary shall establish and provide incentives for developers of housing for which any HUD financial assistance, as determined by the Secretary, is provided for development, maintenance, operation, or other costs, to enter into agreements and partnerships with tree-planting organizations, nurseries, and landscapers to certify that trees, shrubs, grasses, and other plants are planted in the proper manner, are provided adequate maintenance, and survive for at least 3 years after planting or are replaced. The financial assistance determined by the Secretary as eligible under this section shall take into consideration such factors as cost effectiveness and affordability.
- (b) MAKING IT GREEN PLAN.—In the case of any new or substantially rehabilitated housing for which HUD financial assistance, as determined in accordance with subsection (a), is provided by the Secretary for the development, construction, maintenance, rehabilitation, improvement, operation, or costs of the housing, including financial assistance provided through the Community Development Block Grant program under title I of the Housing and Community Development Act of 1974 (42 U.S.C. 5301 et seq.), the Secretary shall require the development of a plan that provides for—
- (1) in the case of new construction and improvements, siting of such housing and improvements in a manner that provides for energy efficiency and conservation to the extent feasible, taking into consideration location and project type;

- (2) minimization of the effects of construction, rehabilitation, or other development on the condition of existing trees;
- (3) selection and installation of indigenous trees, shrubs, grasses, and other plants based upon applicable design guidelines and standards of the International Society for Arboriculture:
- (4) post-planting care and maintenance of the landscaping relating to or affected by the housing in accordance with best management practices; and
- (5) establishment of a goal for minimum greenspace or tree canopy cover for the housing site for which such financial assistance is provided, including guidelines and timetables within which to achieve compliance with such minimum requirements.
- (c) Partnerships.—In carrying out this section, the Secretary is encouraged to consult, as appropriate, with national organizations dedicated to providing housing assistance and related services to low-income families, such as the Alliance for Community Trees and its affiliates, the American Nursery and Landscape Association, the American Society of Landscape Architects, and the National Arbor Day Foundation.

SEC. 296. RESIDENTIAL ENERGY EFFICIENCY BLOCK GRANT PROGRAM.

Title I of the Housing and Community Development Act of 1974 (42 U.S.C. 5301 et seq.) is amended by adding at the end the following new section:

"SEC. 123. RESIDENTIAL ENERGY EFFICIENCY BLOCK GRANT PROGRAM.

- "(a) IN GENERAL.—To the extent amounts are made available for grants under this section, the Secretary shall make grants under this section to States, metropolitan cities and urban counties, Indian tribes, and insular areas to carry out energy efficiency improvements in new and existing single-family and multifamily housing.
 - "(b) Allocations.—
- "(1) In general.—Of the total amount made available for each fiscal year for grants under this section that remains after reserving amounts pursuant to paragraph (2), the Secretary shall allocate for insular areas, for metropolitan cities and urban counties, and for States, an amount that bears the same ratio to such total amount as the amount allocated for such fiscal year under section 106 for Indian tribes, for insular areas, for metropolitan cities and urban counties, and for States, respectively, bears to the total amount made available for such fiscal year for grants under section 106.
- "(2) SET ASIDE FOR INDIAN TRIBES.—Of the total amount made available for each fiscal year for grants under this section, the Secretary shall allocate not less than 1 percent to Indian tribes.
 - "(c) Grant Amounts.—
- "(1) ENTITLEMENT COMMUNITIES.—From the amounts allocated pursuant to subsection (b) for metropolitan cities and urban counties for each fiscal year, the Secretary shall make a grant for such fiscal year to each metropolitan city and urban county that complies with the requirement under subsection (d), in the amount that bears the same ratio such total amount so allocated as the amount of the grant for such fiscal year under section 106 for such metropolitan city or urban county bears to the aggregate amount of all grants for such fiscal year under section 106 for all metropolitan cities and urban counties.
- "(2) STATES.—From the amounts allocated pursuant to subsection (b) for States for each fiscal year, the Secretary shall make a grant for such fiscal year to each State that complies with the requirement under subsection (d), in the amount that bears the same ratio such total amount so allocated as the

- amount of the grant for such fiscal year under section 106 for such State bears to the aggregate amount of all grants for such fiscal year under section 106 for all States. Grant amounts received by a State shall be used only for eligible activities under subsection (e) carried out in nonentitlement areas of the State.
- "(3) Indian tribes.—From the amounts allocated pursuant to subsection (b) for Indian tribes, the Secretary shall make grants to Indian tribes that comply with the requirement under subsection (d) on the basis of a competition conducted pursuant to specific criteria, as the Secretary shall establish by regulation, for the selection of Indian tribes to receive such amount.
- "(4) Insular areas.—From the amounts allocated pursuant to subsection (b) for insular areas, the Secretary shall make a grant to each insular area that complies with the requirement under subsection (d) on the basis of the ratio of the population of the insular area to the aggregate population of all insular areas. In determining the distribution of amounts to insular areas, the Secretary may also include other statistical criteria as data become available from the Bureau of Census of the Department of Labor, but only if such criteria are set forth by regulation issued after notice and an opportunity for comment.
 - "(d) STATEMENT OF ACTIVITIES.—
- "(1) REQUIREMENT.—Before receipt the receipt in any fiscal year of a grant under subsection (c) by any grantee, the grantee shall have prepared a final statement of housing energy efficiency objectives and projected use of funds as the Secretary shall require and shall have provided the Secretary with such certifications regarding such objectives and use as the Secretary may require. In the case of metropolitan cities, urban counties, units of general local government, and insular areas receiving grants, the statement of projected use of funds shall consist of proposed housing energy efficiency activities. In the case of States receiving grants, the statement of projected use of funds shall consist of the method by which the States will distribute funds to units of general local government.
- "(2) PUBLIC PARTICIPATION.—The Secretary may establish requirements to ensure the public availability of information regarding projected use of grant amounts and public participation in determining such projected use.
 - "(e) ELIGIBLE ACTIVITIES.—
- "(1) REQUIREMENT.—Amounts from a grant under this section may be used only to carry out activities for single-family or multifamily housing that are designed to improve the energy efficiency of the housing so that the housing complies with the energy efficiency standards under section 284(a) of the Green Resources for Energy Efficient Neighborhoods Act of 2009, including such activities to provide energy for such housing from renewable sources, such as wind, waves, solar, biomass, and geothermal sources.
- "(2) PREFERENCE FOR COMPLIANCE BEYOND BASIC REQUIREMENTS.—In selecting activities to be funded with amounts from a grant under this section, a grantee shall give more preference to activities based on the extent to which the activities will result in compliance by the housing with the enhanced energy efficiency and conservation standards, and the green building standards, under section 284(b) of such Act.
- "(f) REPORTS.—Each grantee of a grant under this section for a fiscal year shall submit to the Secretary, at a time determined by the Secretary, a performance and evaluation report concerning the use of grant amounts, which shall contain an assessment by the grantee of the relationship of such use

to the objectives identified in the grantees statement under subsection (d).

"(g) APPLICABILITY OF CDBG PROVISIONS.—Sections 109, 110, and 111 of the Housing and Community Development Act of 1974 (42 U.S.C. 5309, 5310, 5311) shall apply to assistance received under this section to the same extent and in the same manner that such sections apply to assistance received under title I of such Act.

"(h) AUTHORIZATION OF APPROPRIATIONS.— There is authorized to be appropriated for grants under this section \$2,500,000,000 for fiscal year 2010 and such sums as may be necessary for each fiscal year thereafter."

SEC. 297. INCLUDING SUSTAINABLE DEVELOP-MENT AND TRANSPORTATION STRATEGIES IN COMPREHENSIVE HOUSING AFFORDABILITY STRATE-GIES.

Section 105(b) of the Cranston-Gonzalez National Affordable Housing Act (42 U.S.C. 12705(b)) is amended—

- (1) by striking "and" at the end of paragraph (19);
- (2) by striking the period at the end of paragraph (20) and inserting "; and";
- (3) and by inserting after paragraph (20) the following new paragraphs:
- "(21) describe the jurisdiction's strategies to encourage sustainable development for affordable housing, including single-family and multifamily housing, as measured by—
- "(A) greater energy efficiency and use of renewable energy sources, including any strategies regarding compliance with the energy efficiency standards under section 284(a) of the Green Resources for Energy Efficient Neighborhoods Act of 2009 and with the enhanced energy efficiency and conservation standards, and the green building standards, under section 284(b) of such Act;
- "(B) increased conservation, recycling, and reuse of resources:
- "(C) more effective use of existing infrastructure:
- "(D) use of building materials and methods that are healthier for residents of the housing, including use of building materials that are free of added known carcinogens that are classified as Group 1 Known Carcinogens by the International Agency for Research on Cancer: and
- "(E) such other criteria as the Secretary determines, in consultation with the Secretary of Energy, the Secretary of Agriculture, and the Administrator of the Environmental Protection Agency, are in accordance with the purposes of this paragraph;
- "(22) describe the jurisdiction's efforts to coordinate its housing strategy with its transportation planning strategies to ensure to the extent practicable that residents of affordable housing have access to public transportation."

SEC. 298. GRANT PROGRAM TO INCREASE SUSTAINABLE LOW-INCOME COMMUNITY DEVELOPMENT CAPACITY.

- (a) IN GENERAL.—The Secretary may make grants to nonprofit organizations to use for any of the following purposes:
- (1) Training, educating, supporting, or advising an eligible community development organization or qualified youth service and conservation corps in improving energy efficiency, resource conservation and reuse, design strategies to maximize energy efficiency, installing or constructing renewable energy improvements (such as wind, wave, biomass, and geothermal sources), and effective use of existing infrastructure in affordable housing and economic development activities in low-income communities, taking into consideration energy efficiency standards under section 284(a) of this subtitle and with the enhanced energy efficiency and conservation standards,

and the green building standards, under section 284(b) of this subtitle.

- Providing loans, predevelopment assistance to eligible community development organizations or qualified youth service and conservation corps to carry out energy efficiency improvements that comply with the energy efficiency standards under section 284(a) of this subtitle, resource conservation and reuse, and effective use of existing infrastructure in affordable housing and economic development activities in low-income communities. In providing assistance under this paragraph, the Secretary shall give more preference to activities based on the extent to which the activities will result in compliance with the enhanced energy efficiency and conservation standards, and the green building standards, under section 284(b) of this subtitle.
- (3) Such other purposes as the Secretary determines are in accordance with the purposes of this subsection.
- (b) APPLICATION REQUIREMENT.—To be eligible for a grant under this section, a nonprofit organization shall prepare and submit to the Secretary an application at such time, in such manner, and containing such information as the Secretary may require.
- (c) AWARD OF CONTRACTS.—Contracts for architectural or engineering services funded with amounts from grants made under this section shall be awarded in accordance with chapter 11 of title 40, United States Code (relating to selection of architects and engineers)
- (d) MATCHING REQUIREMENT.—A grant made under this section may not exceed the amount that the nonprofit organization receiving the grant certifies, to the Secretary, will be provided (in cash or in-kind) from nongovernmental sources to carry out the purposes for which the grant is made.
- (e) DEFINITIONS.—For purposes of this section, the following definitions shall apply:
- (1) The term "nonprofit organization" has the meaning given such term in section 104 of the Cranston-Gonzalez National Affordable Housing Act (42 U.S.C. 12704).
- (2) The term "eligible community development organization" means—
- (A) a unit of general local government (as defined in section 104 of the Cranston-Gonzalez National Affordable Housing Act (42 U.S.C. 12704));
- (B) a community housing development organization (as defined in section 104 of the Cranston-Gonzalez National Affordable Housing Act (42 U.S.C. 12704));
- (C) an Indian tribe or tribally designated housing entity (as such terms are defined in section 4 of the Native American Housing Assistance and Self-Determination Act of 1996 (25 U.S.C. 4103)); or
- (D) a public housing agency, as such term is defined in section 3(b) of the United States Housing Act of 1937 (42 U.S.C. 1437(b)).
- (3) The term "low-income community" means a census tract in which 50 percent or more of the households have an income which is less than 80 percent of the greater of—
- (A) the median gross income for such year for the area in which such census tract is located; or
- (B) the median gross income for such year for the State in which such census tract is located.
- (f) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to the Secretary to carry out this section \$10,000,000 for each of fiscal years 2010 through 2014.

SEC. 299. HOPE VI GREEN DEVELOPMENTS RE-QUIREMENT.

(a) MANDATORY COMPONENT.—Section 24(e) of the United States Housing Act of 1937 (42 U.S.C. 1437v(e)) is amended by adding at the end the following new paragraph:

- "(4) GREEN DEVELOPMENTS REQUIREMENT.—
 "(A) REQUIREMENT.—The Secretary may
 not make a grant under this section to an
 applicant unless the proposed revitalization
- not make a grant under this section to an applicant unless the proposed revitalization plan of the applicant to be carried out with such grant amounts meets the following requirements:
- "(i) Green communities criteria check-List.—All residential construction under the proposed plan complies with the national Green Communities criteria checklist for residential construction that provides criteria for the design, development, and operation of affordable housing, as such checklist is in effect for purposes of this paragraph pursuant to subparagraph (D) at the date of the application for the grant, or any substantially equivalent standard or standards as determined by the Secretary, as follows:
- "(I) The proposed plan shall comply with all items of the national Green Communities criteria checklist for residential construction that are identified as mandatory.
- "(II) The proposed plan shall comply with such other nonmandatory items of such national Green Communities criteria checklist so as to result in a cumulative number of points attributable to such nonmandatory items under such checklist of not less than—
- "(aa) 25 points, in the case of any proposed plan (or portion thereof) consisting of new construction; and
- "(bb) 20 points, in the case of any proposed plan (or portion thereof) consisting of rehabilitation
- "(ii) GREEN BUILDINGS CERTIFICATION SYSTEM.—All nonresidential construction under the proposed plan complies with all minimum required levels of the green building rating systems and levels identified by the Secretary pursuant to subparagraph (C), as such systems and levels are in effect for purposes of this paragraph pursuant to subparagraph (D) at the time of the application for the grant.
 - "(B) VERIFICATION.—
- "(i) IN GENERAL.—The Secretary shall verify, or provide for verification, sufficient to ensure that each proposed revitalization plan carried out with amounts from a grant under this section complies with the requirements under subparagraph (A) and that the revitalization plan is carried out in accordance with such requirements and plan.
- "(ii) TIMING.—In providing for such verification, the Secretary shall establish procedures to ensure such compliance with respect to each grantee, and shall report to the Congress with respect to the compliance of each grantee, at each of the following times:
- "(I) Not later than 6 months after execution of the grant agreement under this section for the grantee.
- $``(\Pi)$ Upon completion of the revitalization plan of the grantee.
- "(C) IDENTIFICATION OF GREEN BUILDINGS RATING SYSTEMS AND LEVELS.—
- "(i) IN GENERAL.—For purposes of this paragraph, the Secretary shall identify rating systems and levels for green buildings that the Secretary determines to be the most likely to encourage a comprehensive and environmentally sound approach to ratings and standards for green buildings. The identification of the ratings systems and levels shall be based on the criteria specified in clause (ii), shall identify the highest levels the Secretary determines are appropriate above the minimum levels required under the systems selected. Within 90 days of the completion of each study required by clause (iii), the Secretary shall review and update the rating systems and levels, or identify alternative systems and levels for purposes of this paragraph, taking into account the conclusions of such study.

- "(ii) CRITERIA.—In identifying the green rating systems and levels, the Secretary shall take into consideration—
- "(I) the ability and availability of assessors and auditors to independently verify the criteria and measurement of metrics at the scale necessary to implement this paragraph;

"(II) the ability of the applicable ratings system organizations to collect and reflect public comment;

"(III) the ability of the standards to be developed and revised through a consensus-based process;

"(IV) An evaluation of the robustness of the criteria for a high-performance green building, which shall give credit for promoting—

"(aa) efficient and sustainable use of water, energy, and other natural resources;

"(bb) use of renewable energy sources;

- "(cc) improved indoor and outdoor environmental quality through enhanced indoor and outdoor air quality, thermal comfort, acoustics, outdoor noise pollution, day lighting, pollutant source control, sustainable land-scaping, and use of building system controls and low- or no-emission materials, including preference for materials with no added carcinogens that are classified as Group 1 Known Carcinogens by the International Agency for Research on Cancer; and
- "(dd) such other criteria as the Secretary determines to be appropriate; and
- "(V) national recognition within the building industry.
- "(iii) 5-YEAR EVALUATION.—At least once every 5 years, the Secretary shall conduct a study to evaluate and compare available third-party green building rating systems and levels, taking into account the criteria listed in clause (ii).
- "(D) APPLICABILITY AND UPDATING OF STANDARDS.—
- "(i) APPLICABILITY.—Except as provided in clause (ii) of this subparagraph, the national Green Communities criteria checklist and green building rating systems and levels referred to in clauses (i) and (ii) of subparagraph (A) that are in effect for purposes of this paragraph are such checklist systems, and levels as in existence upon the date of the enactment of the Green Resources for Energy Efficient Neighborhoods Act of 2009.
- "(ii) UPDATING.—The Secretary may, by regulation, adopt and apply, for purposes of this paragraph, future amendments and supplements to, and editions of, the national Green Communities criteria checklist, any standard or standards that the Secretary has determined to be substantially equivalent to such checklist, and the green building ratings systems and levels identified by the Secretary pursuant to subparagraph (C)."
- (b) SELECTION CRITERIA; GRADED COMPONENT.—Section 24(e)(2) of the United States Housing Act of 1937 (42 U.S.C. 1437v(e)(2)) is amended—
- (1) in subparagraph (K), by striking "and" at the end;
- (2) by redesignating subparagraph (L) as subparagraph (M); and
- (3) by inserting after subparagraph (K) the following new subparagraph:
- "(L) the extent to which the proposed revitalization plan—
- "(i) in the case of residential construction, complies with the nonmandatory items of the national Green Communities criteria checklist identified in paragraph (4)(A)(i), or any substantially equivalent standard or standards as determined by the Secretary, but only to the extent such compliance exceeds the compliance necessary to accumulate the number of points required under such paragraph; and
- "(ii) in the case of nonresidential construction, complies with the components of the green building rating systems and levels

identified by the Secretary pursuant to paragraph (4)(C), but only to the extent such compliance exceeds the minimum level required under such systems and levels; and". SEC. 299A. CONSIDERATION OF ENERGY EFFI-

CIENCY IMPROVEMENTS IN AP-PRAISALS.

- (a) Appraisals in Connection With Feder-ALLY Related Transactions.—
- (1) REQUIREMENT.—Section 1110 of the Financial Institutions Reform, Recovery, and Enforcement Act of 1989 (12 U.S.C. 3339) is amended—
- (A) in paragraph (1), by striking "and" at the end:
- (B) by redesignating paragraph (2) as paragraph (3); and
- (C) by inserting after paragraph (1) the following new paragraph:
- "(2) that such appraisals be performed in accordance with appraisal standards that require, in determining the value of a property, consideration of any renewable energy sources for, or energy efficiency or energy-conserving improvements or features of, the property; and".
- (2) REVISION OF APPRAISAL STANDARDS.—Each Federal financial institutions regulatory agency shall, not later than 6 months after the date of the enactment of this Act, revise its standards for the performance of real estate appraisals in connection with federally related transactions under the jurisdiction of the agency to comply with the requirement under the amendments made by paragraph (1) of this subsection.
- (b) APPRAISER CERTIFICATION AND LICENSING REQUIREMENTS.—Section 1116 of the Financial Institutions Reform, Recovery, and Enforcement Act of 1989 (12 U.S.C. 3345) is amended—
- (1) in subsection (a), by inserting before the period at the end the following: ", and meets the requirements established pursuant to subsection (f) for qualifications regarding consideration of any renewable energy sources for, or energy efficiency or energyconserving improvements or features of, the property":
- (2) in subsection (c), by inserting before the period at the end the following: ", which shall include compliance with the requirements established pursuant to subsection (f) regarding consideration of any renewable energy sources for, or energy efficiency or energy-conserving improvements or features of, the property";
- (3) in subsection (e), by striking "The" and inserting "Except as provided in subsection (f), the"; and
- (4) by adding at the end the following new subsection:
- "(f) REQUIREMENTS FOR APPRAISERS REGARDING ENERGY EFFICIENCY FEATURES.—The Appraisal Subcommittee shall establish requirements for State certification of State certified real estate appraisers and for State licensing of State licensed appraisers, to ensure that appraisers consider and are qualified to consider, in determining the value of a property, any renewable energy sources for, or energy efficiency or energy-conserving improvements or features of, the property."
- (c) GUIDELINES FOR APPRAISING PHOTO-VOLTAIC MEASURES AND TRAINING OF AP-PRAISERS.—Section 1122 of the Financial Institutions Reform, Recovery, and Enforcement Act of 1989 (12 U.S.C. 3351) is amended by adding at the end the following new subsection:
- "(g) GUIDELINES FOR APPRAISING PHOTO-VOLTAIC MEASURES AND TRAINING OF AP-PRAISERS.—The Appraisal Subcommittee shall, in consultation with the Secretary of Housing and Urban Development, the Federal National Mortgage Association, and the Federal Home Loan Mortgage Corporation, establish specific guidelines for—

- "(1) appraising off- and on-grid photovoltaic measures for compliance with the appraisal standards prescribed pursuant to section 1110(2);
- "(2) requirements under section 1116(f) for certification of State certified real estate appraisers and for State licensing of State licensed appraisers, to ensure that appraisers consider, and are qualified to consider, such photovoltaic measures in determining the value of a property; and
- "(3) training of appraisers to meet the requirements established pursuant to paragraph (2) of this subsection."

SEC. 299B. HOUSING ASSISTANCE COUNCIL.

The Secretary shall require the Housing Assistance Council—

- (1) to encourage each organization that receives assistance from the Council with any amounts made available from the Secretary to provide that any structures and buildings developed or assisted under projects, programs, and activities funded with such amounts complies with the energy efficiency standards under section 284(a) of this subtitle; and
- (2) to establish incentives to encourage each such organization to provide that any such structures and buildings comply with the energy efficiency and conservation standards, and the green building standards, under section 284(b) of such Act.

SEC. 299C. RURAL HOUSING AND ECONOMIC DE-VELOPMENT ASSISTANCE.

The Secretary shall—

- (1) require each tribe, agency, organization, corporation, and other entity that receives any assistance from the Office of Rural Housing and Economic Development of the Department of Housing and Urban Development to provide that any structures and buildings developed or assisted under activities funded with such amounts complies with the energy efficiency standards under section 284(a) of this subtitle; and
- (2) establish incentives to encourage each such tribe, agency, organization, corporation, and other entity to provide that any such structures and buildings comply with the enhanced energy efficiency and conservation standards, and the green building standards, under section 284(b) of such Act.

SEC. 299D. LOANS TO STATES AND INDIAN TRIBES TO CARRY OUT RENEWABLE ENERGY SOURCES ACTIVITIES.

- (a) ESTABLISHMENT OF FUND.—There is established in the Treasury of the United States a fund, to be known as the "Alternative Energy Sources State Loan Fund".
 - (b) Expenditures —
- (1) IN GENERAL.—Subject to paragraph (2), on request by the Secretary, the Secretary of the Treasury shall transfer from the Fund to the Secretary such amounts as the Secretary determines are necessary to provide loans under subsection (c)(1).
- (2) ADMINISTRATIVE EXPENSES.—Of the amounts in the Fund, not more than 5 percent shall be available for each fiscal year to pay the administrative expenses of the Department of Housing and Urban Development to carry out this section.
 - (c) LOANS TO STATES AND INDIAN TRIBES.—
- (1) IN GENERAL.—The Secretary shall use amounts in the Fund to provide loans to States and Indian tribes to provide incentives to owners of single-family and multifamily housing, commercial properties, and public buildings to provide—
- (A) renewable energy sources for such structures, such as wind, wave, solar, biomass, or geothermal energy sources, including incentives to companies and business to change their source of energy to such renewable energy sources and for changing the sources of energy for public buildings to such renewable energy sources;

- (B) energy efficiency and energy conserving improvements and features for such structures; or
- (C) infrastructure related to the delivery of electricity and hot water for structures lacking such amenities.
- (2) ELIGIBILITY.—To be eligible to receive a loan under this subsection, a State or Indian tribe, directly or through an appropriate State or tribal agency, shall submit to the Secretary an application at such time, in such manner, and containing such information as the Secretary may require.
- (3) CRITERIA FOR APPROVAL.—The Secretary may approve an application of a State or Indian tribe under paragraph (2) only if the Secretary determines that the State or tribe will use the funds from the loan under this subsection to carry out a program to provide incentives described in paragraph (1) that—
- (A) requires that any such renewable energy sources, and energy efficiency and energy conserving improvements and features, developed pursuant to assistance under the program result in compliance of the structure so improved with energy efficiency requirements determined by the Secretary; and
- (B) includes such compliance and audit requirements as the Secretary determines are necessary to ensure that the program is operated in a sound and effective manner.
- (4) PREFERENCE.—In making loans during each fiscal year, the Secretary shall give preference to States and Indian tribes that have not previously received a loan under this subsection.
- (5) MAXIMUM AMOUNT.—The aggregate outstanding principal amount from loans under this subsection to any single State or Indian tribe may not exceed \$500,000,000.
- (6) LOAN TERMS.—Each loan under this subsection shall have a term to maturity of not more than 10 years and shall bear interest at annual rate, determined by the Secretary, that shall not exceed interest rate charged by the Federal Reserve Bank of New York to commercial banks and other depository institutions for very short-term loans under the primary credit program, as most recently published in the Federal Reserve Statistical Release on selected interest rates (daily or weekly), and commonly referred to as the H.15 release, preceding the date of a determination for purposes of applying this paragraph.
- (7) LOAN REPAYMENT.—The Secretary shall require full repayment of each loan made under this section.
- (d) INVESTMENT OF AMOUNTS.—
- (1) IN GENERAL.—The Secretary of the Treasury shall invest such amounts in the Fund that are not, in the judgment of the Secretary of the Treasury, required to meet needs for current withdrawals.
- (2) OBLIGATIONS OF UNITED STATES.—Investments may be made only in interest-bearing obligations of the United States.
 - (e) Reports.—
- (1) REPORTS TO SECRETARY.—For each year during the term of a loan made under subsection (c), the State or Indian tribe that received the loan shall submit to the Secretary a report describing the State or tribal alternative energy sources program for which the loan was made and the activities conducted under the program using the loan funds during that year.
- (2) REPORT TO CONGRESS.—Not later than September 30 of each year that loans made under subsection (c) are outstanding, the Secretary shall submit a report to the Congress describing the total amount of such loans provided under subsection (c) to each eligible State and Indian tribe during the fiscal year ending on such date, and an evaluation on effectiveness of the Fund.

- (f) AUTHORIZATION OF APPROPRIATIONS.—There is authorized to be appropriated to the Fund \$5,000,000,000.
- (g) DEFINITIONS.—For purposes of this section, the following definitions shall apply:
- (1) INDIAN TRIBE.—The term "Indian tribe" has the meaning given such term in section 4 of the Native American Housing Assistance and Self-Determination Act of 1996 (25 U.S.C. 4103).
- (2) STATE.—The term "State" means each of the several States, the Commonwealth of Puerto Rico, the District of Columbia, the Commonwealth of the Northern Mariana Islands, Guam, the Virgin Islands, American Samoa, the Trust Territories of the Pacific, or any other possession of the United States. SEC. 299E. GREEN BANKING CENTERS.
- (a) INSURED DEPOSITORY INSTITUTIONS.— Section 8 of the Federal Deposit Insurance Act (12 U.S.C. 1818) is amended by adding at the end the following new subsection:
 - "(x) 'GREEN BANKING' CENTERS.—
- "(1) IN GENERAL.—The Federal banking agencies shall prescribe guidelines encouraging the establishment and maintenance of 'green banking' centers by insured depository institutions to provide any consumer who seeks information on obtaining a mortgage, home improvement loan, home equity loan, or renewable energy lease with additional information on—
- "(A) obtaining an home energy rating or audit for the residence for which such mortgage or loan is sought;
- "(B) obtaining financing for cost-effective energy-saving improvements to such property; and
- "(C) obtaining beneficial terms for any mortgage or loan, or qualifying for a larger mortgage or loan, secured by a residence which meets or will meet energy efficiency standards.
- "(2) INFORMATION AND REFERRALS.—The information made available to consumers under paragraph (1) may include—
- "(A) information on obtaining a home energy rating and contact information on qualified energy raters in the area of the residence:
- "(B) information on the secondary market guidelines that permit lenders to provide more favorable terms by allowing lenders to increase the ratio on debt-to-income requirements or to use the projected utility savings as a compensating factor;
- "(C) information including eligibility information about, and contact information for, any conservation or renewable energy programs, grants, or loans offered by the Secretary of Housing and Urban Development, including the Energy Efficient Mortgage Program:
- "(D) information including eligibility information about, and contact information for, any conservation or renewable energy programs, grants, or loans offered for qualified military personal, reservists, and veterans by the Secretary of Veterans Affairs;
- "(E) information about, and contact information for, the Office of Efficiency and Renewable Energy at the Department of Energy, including the weatherization assistance program;
- "(F) information about, and contact information for, the Energy Star Program of the Environmental Protection Agency;
- "(G) information from, and contact information for, the Federal Citizen Information Center of the General Services Administration on energy-efficient mortgages and loans, home energy rating systems, and the availability of energy-efficient mortgage information from a variety of Federal agencies: and
- "(H) such other information as the agencies or the insured depository institution may determine to be appropriate or useful.".

- (b) INSURED CREDIT UNIONS.—Section 206 of the Federal Credit Union Act (12 U.S.C. 1786) is amended by adding at the end the following new subsection:
- lowing new subsection:
 "(x) 'GREEN BANKING' CENTERS.—
- "(1) In general.—The Board shall prescribe guidelines encouraging the establishment and maintenance of 'green banking' centers by insured credit unions to provide any member who seeks information on obtaining a mortgage, home improvement loan, home equity loan, or renewable energy lease with additional information on—
- "(A) obtaining an home energy rating or audit for the residence for which such mortgage or loan is sought;
- "(B) obtaining financing for cost-effective energy-saving improvements to such property; and
- "(C) obtaining beneficial terms for any mortgage or loan, or qualifying for a larger mortgage or loan, secured by a residence which meets or will meet energy efficiency standards.
- "(2) INFORMATION AND REFERRALS.—The information made available to members under paragraph (1) may include—
- "(A) information on obtaining a home energy rating and contact information on qualified energy raters in the area of the residence;
- "(B) information on the secondary market guidelines that permit lenders to provide more favorable terms by allowing lenders to increase the ratio on debt-to-income requirements or to use the projected utility savings as a compensating factor:
- "(C) information including eligibility information about, and contact information for, any conservation or renewable energy programs, grants, or loans offered by the Secretary of Housing and Urban Development, including the Energy Efficient Mortgage Program;
- "(D) information including eligibility information about, and contact information for, any conservation or renewable energy programs, grants, or loans offered for qualified military personal, reservists, and veterans by the Secretary of Veterans Affairs:
- "(E) information about, and contact information for, the Office of Efficiency and Renewable Energy at the Department of Energy, including the weatherization assistance program:
- "(F) information from, and contact information for, the Federal Citizen Information Center of the General Services Administration on energy-efficient mortgages and loans, home energy rating systems, and the availability of energy-efficient mortgage information from a variety of Federal agencies; and
- "(G) such other information as the Board or the insured credit union may determine to be appropriate or useful.".

SEC. 299F. GAO REPORTS ON AVAILABILITY OF AFFORDABLE MORTGAGES.

- (a) STUDY.—The Comptroller General of the United States shall periodically, as necessary to comply with subsection (b), examine the impact of this subtitle and the amendments made by this subtitle on the availability of affordable mortgages in various areas throughout the United States, including cities having older infrastructure and limited space for the development of new housing.
- (b) TRIENNIAL REPORTS.—The Comptroller General shall submit a report once every 3 years to the Committee on Financial Services of the House of Representatives and the Committee on Banking, Housing, and Urban Affairs of the Senate that shall include—
- (1) a detailed statement of the most recent findings pursuant to subsection (a); and
- (2) if the Comptroller General finds that this subtitle or the amendments made by

this subtitle have directly or indirectly resulted in consequences that limit the availability or affordability of mortgages in any area or areas within the United States, including any city having older infrastructure and limited space for the development of new housing, any recommendations for any additional actions at the Federal, State, or local levels that the Comptroller General considers necessary or appropriate to mitigate such effects.

The first report under this subsection shall be submitted not later than the expiration of the 3-year period beginning on the date of the enactment of this Act.

SEC. 299G. PUBLIC HOUSING ENERGY COST RE-PORT.

- (a) COLLECTION OF INFORMATION BY HUD. The Secretary of Housing and Urban Development shall obtain from each public housing agency, by such time as may be necessary to comply with the reporting requirement under subsection (b), information regarding the energy costs for public housing administered or operated by the agency. For each public housing agency, such information shall include the monthly energy costs associated with each separate building and development of the agency, for the most recently completed 12-month period for which such information is available, and such other information as the Secretary determines is appropriate in determining which public housing buildings and developments are most in need of repairs and improvements to reduce energy needs and costs and become more energy efficient.
- (b) REPORT.—Not later than the expiration of the 12-month period beginning on the date of the enactment of this Act, the Secretary of Housing and Urban Development shall submit a report to the Congress setting forth the information collected pursuant to subsection (a).

SEC. 299H. SECONDARY MARKET FOR RESIDENTIAL RENEWABLE ENERGY LEASE INSTRUMENTS.

- (a) Purposes.—The purposes of this section are— $\,$
- (1) to encourage residential use of renewable energy systems by minimizing up-front costs and providing immediate utility cost savings to consumers through leasing of such systems to homeowners;
- (2) to reduce carbon emissions and the use of nonrenewable resources;
- (3) to encourage energy-efficient residential construction and rehabilitation;
- (4) to encourage the use of renewable resources by homeowners;
- (5) to minimize the impact of development on the environment;
 - (6) to reduce consumer utility costs; and
- (7) to encourage private investment in the green economy.
- (b) RESIDUAL VALUE OF RENEWABLE ENERGY ASSET.—The Secretary of Housing and Urban Development shall establish a means of determining the residual value of a renewable energy asset such that a secondary market for residential renewable energy lease instruments may be facilitated. Such means may include, without limitation, the calculation of residual value based on the net present value of projected future energy production of the renewable energy asset.

SEC. 299I. GREEN GUARANTEES.

- (a) AUTHORITY TO GUARANTEE "GREEN PORTION" OF ELIGIBLE MORTGAGES.—
- (1) IN GENERAL.—The Secretary of Housing and Urban Development may make commitments to guarantee under this section and may guarantee, the repayment of the portions of the principal obligations of eligible mortgages that are used to finance eligible sustainable building elements for the housing that is subject to the mortgage.

- (2) AMOUNT OF GUARANTEE.—A guarantee under this section by the Secretary in connection with an eligible mortgage shall not exceed a percentage of the green portion (as such term is defined in subsection (g)) of the mortgage, as shall be established by the Secretary and may be established on a regional basis as the Secretary determines appropriate.
- (b) ELIGIBLE MORTGAGES.—To be considered an eligible mortgage for purposes of this section, a mortgage shall comply with all of the following requirements:
- (1) Acquisition or construction of Hous-ING.—The mortgage shall be made for the acquisition or construction of single- or multifamily housing and repayment of the mortgage shall be secured by an interest in such housing.
- (2) FINANCING OF ELIGIBLE SUSTAINABLE BUILDING ELEMENTS THROUGH GREEN PORTION OF MORTGAGE.—A portion of the principal obligation of the mortgage, which meets the requirements under subsection (c), shall be used only for financing the provision of eligible sustainable building elements for the housing for which the mortgage was made.
- (3) MAXIMUM MORTGAGE AMOUNT.—The principal obligation of the mortgage (including the eligible portion of such mortgage, and such initial service charges, appraisal, inspection, and other fees as the Secretary shall approve) may not exceed the following amounts:
- (A) SINGLE-FAMILY HOUSING.—Such dollar amounts for single-family housing as the Secretary shall establish, which may be established on the basis of the number of dwelling units in the housing, as the Secretary considers appropriate.
- (B) MULTIFAMILY HOUSING.—Such dollar amounts for multifamily housing as the Secretary shall establish, which may be established on the basis of the number of dwelling units in the housing and the number of bedrooms in such dwelling units, as the Secretary considers appropriate.
- (4) REPAYMENT.—The mortgage meets such requirements as the Secretary shall establish to ensure that there is a reasonable prospect of repayment of the principal and interest on the obligation by the mortgagor.
- (5) MORTGAGE TERMS.—The mortgage shall meet such requirements with respect to loan-to-value ratio, mortgagor credit scores, debt-to-income ratio, and other underwriting standards, term to maturity, interest rates and amortization, including amortization of the green portion of the mortgage, and other mortgage terms as the Secretary shall establish.
- (c) LIMITATIONS ON GREEN PORTION OF MORTGAGE.—The requirements under this subsection with respect to the green portion of an eligible mortgage are as follows:
- (1) PERCENTAGE LIMITATION.—Such portion shall not exceed, in the case of single-family or multifamily housing, 10 percent of the total principal obligation of the mortgage.
- (2) DOLLAR AMOUNT LIMITATION.—Such portion shall not exceed—
- (A) in the case of single-family housing, such maximum dollar amount limitation as the Secretary shall establish, which may be established on the basis of the number of dwelling units in the housing, as the Secretary considers appropriate; and
- (B) in the case of multifamily housing, such maximum dollar amount limitation as the Secretary shall establish, which limitation may be established on the basis of the number of dwelling units in the housing and the number of bedrooms in such dwelling units, as the Secretary considers appropriate.
- (3) COST-EFFECTIVENESS LIMITATION.—Such portion shall not exceed the total present value of the savings (as determined in ac-

- cordance with subsection (d)) attributable to the incorporation of the eligible sustainable building elements to be financed with the green portion of the mortgage that are to be realized over the useful life of such elements.
- (d) ELIGIBLE SUSTAINABLE BUILDING ELE-MENTS.—The Secretary may not guarantee any eligible mortgage under this section unless the mortgagor has demonstrated, in accordance with such requirements as the Secretary shall establish, the amount of savings attributable to incorporation of the sustainable building elements to be financed with the green portion of the mortgage, as measured by the National Green Building Standard for all residential construction developed by the National Association of Home Builders and the U.S. Green Building Council, and approved by the American National Standards Institute, as updated and in effect at the time of such demonstration.
 - (e) GUARANTEE FEE.—
- (1) ASSESSMENT AND COLLECTION.—The Secretary shall assess and collect fees for guarantees under this section in amounts that the Secretary determines are sufficient to cover the costs (as such term is defined in section 502 of the Federal Credit Reform Act of 1990 (2 U.S.C. 661a)) of such guarantees.
- (2) AVAILABILITY.—Fees collected under this subsection shall be deposited by the Secretary in the Treasury of the United States and shall remain available until expended, subject to such other conditions as are contained in annual appropriations Acts.
 - (f) PAYMENT OF GUARANTEE.—
 - (1) Default.—
- (A) RIGHT TO PAYMENT.—If a mortgagor under a mortgage guaranteed under this section defaults (as defined in regulations issued by the Secretary and specified in the guarantee contract) on the obligation under the mortgage—
- (i) the holder of the guarantee shall have the right to demand payment of the unpaid amount of the guaranteed portion of the mortgage, to the extent provided under subsection (a)(2), from the Secretary; and
- (ii) within such period as may be specified in the guarantee or related agreements, the Secretary shall pay to the holder of the guarantee, to the extent provided under subsection (a)(2), the unpaid interest on, and unpaid principal of the portion of guaranteed portion of the mortgage with respect to which the borrower has defaulted, unless the Secretary finds that there was no default by the borrower in the payment of interest or principal or that the default has been remedied.
- (B) FORBEARANCE.—Nothing in this paragraph precludes any forbearance by the holder of an eligible mortgage for the benefit of the mortgagor which may be agreed upon by the parties to the mortgage and approved by the Secretary.
 - (2) Subrogation.—
- (A) In General.—If the Secretary makes a payment under paragraph (1), the Secretary shall be subrogated to the rights of the recipient of the payment as specified in the guarantee or related agreements including, if appropriate, the authority (notwithstanding any other provision of law)—
- (i) to complete, maintain, operate, lease, or otherwise dispose of any property acquired pursuant to such guarantee or related agreements; or
- (ii) to permit the mortgagor, pursuant to an agreement with the Secretary, to continue to occupy the property subject to the mortgage, if the Secretary determines such occupancy to be appropriate.
- (B) SUPERIORITY OF RIGHTS.—The rights of the Secretary, with respect to any property acquired pursuant to a guarantee or related agreements, shall be superior to the rights of

any other person with respect to the property.

- (C) TERMS AND CONDITIONS.—A guarantee agreement shall include such detailed terms and conditions as the Secretary determines appropriate to protect the interests of the United States in the case of default.
- (3) FULL FAITH AND CREDIT.—The full faith and credit of the United States is pledged to the payment of all guarantees issued under this section with respect to principal and interest.
- (g) DEFINITIONS.—For purposes of this section, the following definitions shall apply:
- (1) ELIGIBLE MORTGAGE.—The term "eligible mortgage" means a mortgage that meets the requirements under subsection (b).
- (2) GREEN PORTION.—The term "green portion" means, with respect to an eligible mortgage, the portion of the mortgage principal referred to in subsection (b)(2) that is attributable, as determined in accordance with regulations issued by the Secretary, to the increased costs incurred in financing provision of sustainable building elements for the housing for which the mortgage was made, as compared to the costs that would have been incurred in financing the provision of other building elements for the housing for the same purposes that are commonly or conventionally used but are not sustainable building elements.
- (3) GUARANTEED PORTION.—The term "guaranteed portion" means, with respect to an eligible mortgage guaranteed under this section, the green portion of the mortgage that is so guaranteed.
- (4) MORTGAGE.—The term "mortgage" has the meaning given such term in section 201 of the National Housing Act (12 U.S.C. 1707).
- (5) MULTIFAMILY HOUSING.—The term "multifamily housing" means a residential property consisting of five or more dwelling units.
- (6) SECRETARY.—The term "Secretary" means the Secretary of Housing and Urban Development.
- (7) SINGLE-FAMILY HOUSING.—The term "single-family housing" means a residential property consisting of one to four dwelling units.
- (8) SUSTAINABLE BUILDING ELEMENT.—The term "sustainable building element" means such building elements, as the Secretary shall define, that have energy efficiency or environmental sustainability qualities that are superior to such qualities for other building elements for the same purposes that are commonly or conventionally used.
- (h) AUTHORIZATION OF APPROPRIATIONS.— There is authorized to be appropriated for costs (as such term is defined in section 502 of the Federal Credit Reform Act of 1990 (2 U.S.C. 661a) of guarantees under this section \$500,000,000 for each of fiscal years 2010 through 2014.
- (i) REGULATIONS.—The Secretary shall issue any regulations necessary to carry out this section

TITLE III—REDUCING GLOBAL WARMING POLLUTION

SEC. 301. SHORT TITLE.

This title, and sections 112, 116, 221, 222, 223, and 401 of this Act, and the amendments made by this title and those sections, may be cited as the "Safe Climate Act".

Subtitle A—Reducing Global Warming Pollution

SEC. 311. REDUCING GLOBAL WARMING POLLUTION.

The Clean Air Act (42 U.S.C. and following) is amended by adding after title VI the following new title:

"TITLE VII—GLOBAL WARMING POLLUTION REDUCTION PROGRAM "PART A—GLOBAL WARMING POLLUTION REDUCTION GOALS AND TARGETS

"SEC. 701. FINDINGS AND PURPOSE.

- "(a) FINDINGS.—The Congress finds as follows:
- "(1) Global warming poses a significant threat to the national security, economy, public health and welfare, and environment of the United States, as well as of other nations.
- (2) Reviews of scientific studies, including by the Intergovernmental Panel on Climate Change and the National Academy of Sciences, demonstrate that global warming is the result of the combined anthropogenic greenhouse gas emissions from numerous sources of all types and sizes. Each increment of emission, when combined with other emissions, causes or contributes materially to the acceleration and extent of global warming and its adverse effects for the lifetime of such gas in the atmosphere. Accordingly, controlling emissions in small as well as large amounts is essential to prevent, slow the pace of, reduce the threats from, and mitigate global warming and its adverse effects.
- "(3) Because they induce global warming, greenhouse gas emissions cause or contribute to injuries to persons in the United States, including—
- "(A) adverse health effects such as disease and loss of life:
- "(B) displacement of human populations;
- "(C) damage to property and other interests related to ocean levels, acidification, and ice changes;
- "(D) severe weather and seasonal changes; "(E) disruption, costs, and losses to business, trade, employment, farms, subsistence, aesthetic enjoyment of the environment, recreation, culture, and tourism;
- "(F) damage to plants, forests, lands, and waters:
 - "(G) harm to wildlife and habitat;
- "(H) scarcity of water and the decreased abundance of other natural resources;
- "(I) worsening of tropospheric air pollution;
- $\mbox{``(J)}$ substantial threats of similar damage; and
- "(K) other harm.
- "(4) That many of these effects and risks of future effects of global warming are widely shared does not minimize the adverse effects individual persons have suffered, will suffer, and are at risk of suffering because of global warming.
- "(5) That some of the adverse and potentially catastrophic effects of global warming are at risk of occurring and not a certainty does not negate the harm persons suffer from actions that increase the likelihood, extent, and severity of such future impacts.
- "(6) Nations of the world look to the United States for leadership in addressing the threat of and harm from global warming. Full implementation of the Safe Climate Act is critical to engage other nations in an international effort to mitigate the threat of and harm from global warming.
- "(7) Global warming and its adverse effects are occurring and are likely to continue and increase in magnitude, and to do so at a greater and more harmful rate, unless the Safe Climate Act is fully implemented and enforced in an expeditious manner.
- "(b) PURPOSE.—It is the general purpose of the Safe Climate Act to help prevent, reduce the pace of, mitigate, and remedy global warming and its adverse effects. To fulfill such purpose, it is necessary to—
- "(1) require the timely fulfillment of all governmental acts and duties, both substantive and procedural, and the prompt

compliance of covered entities with the requirements of the Safe Climate Act;

"(2) establish and maintain an effective, transparent, and fair market for emission allowances and preserve the integrity of the cap on emissions and of offset credits;

"(3) advance the production and deployment of clean energy and energy efficiency technologies; and

"(4) ensure effective enforcement of the Safe Climate Act by citizens, States, Indian tribes, and all levels of government because each violation of the Safe Climate Act is likely to result in an additional increment of greenhouse gas emission and will slow the pace of implementation of the Safe Climate Act and delay the achievement of the goals set forth in section 702, and cause or con-

"SEC. 702. ECONOMY-WIDE REDUCTION GOALS.

fects.

"The goals of the Safe Climate Act are to reduce steadily the quantity of United States greenhouse gas emissions such that—

tribute to global warming and its adverse ef-

"(1) in 2012, the quantity of United States greenhouse gas emissions does not exceed 97 percent of the quantity of United States greenhouse gas emissions in 2005;

"(2) in 2020, the quantity of United States greenhouse gas emissions does not exceed 80 percent of the quantity of United States greenhouse gas emissions in 2005;

"(3) in 2030, the quantity of United States greenhouse gas emissions does not exceed 58 percent of the quantity of United States greenhouse gas emissions in 2005; and

"(4) in 2050, the quantity of United States greenhouse gas emissions does not exceed 17 percent of the quantity of United States greenhouse gas emissions in 2005.

"SEC. 703. REDUCTION TARGETS FOR SPECIFIED SOURCES.

- "(a) In General.—The regulations issued under section 721 shall cap and reduce annually the greenhouse gas emissions of capped sources each calendar year beginning in 2012 such that—
- "(1) in 2012, the quantity of greenhouse gas emissions from capped sources does not exceed 97 percent of the quantity of greenhouse gas emissions from such sources in 2005;
- "(2) in 2020, the quantity of greenhouse gas emissions from capped sources does not exceed 83 percent of the quantity of greenhouse gas emissions from such sources in 2005;
- "(3) in 2030, the quantity of greenhouse gas emissions from capped sources does not exceed 58 percent of the quantity of greenhouse gas emissions from such sources in 2005; and
- "(4) in 2050, the quantity of greenhouse gas emissions from capped sources does not exceed 17 percent of the quantity of greenhouse gas emissions from such sources in 2005.
- "(b) DEFINITION.—For purposes of this section, the term 'greenhouse gas emissions from such sources in 2005' means emissions to which section 722 would have applied if the requirements of this title for the specified year had been in effect for 2005

"SEC. 704. SUPPLEMENTAL POLLUTION REDUC-TIONS.

"For the purposes of decreasing the likelihood of catastrophic climate change, preserving tropical forests, building capacity to generate offset credits, and facilitating international action on global warming, the Administrator shall set aside the percentage specified in section 781 of the quantity of emission allowances established under section 721(a) for each year, to be used to achieve a reduction of greenhouse gas emissions from deforestation in developing countries in accordance with part E. In 2020, activities supported under part E shall provide greenhouse gas reductions in an amount equal to an additional 10 percentage points of reductions from United States greenhouse

gas emissions in 2005. The Administrator shall distribute these allowances with respect to activities in countries that enter into and implement agreements or arrangements relating to reduced deforestation as described in section 754(a)(2).

"SEC. 705. REVIEW AND PROGRAM REC-OMMENDATIONS.

- "(a) IN GENERAL.—The Administrator shall, in consultation with appropriate Federal agencies, submit to Congress a report not later than July 1, 2013, and every 4 years thereafter, that includes—
- "(1) an analysis of key findings based on the latest scientific information and data relevant to global climate change;
- "(2) an analysis of capabilities to monitor and verify greenhouse gas reductions on a worldwide basis, including for the United States, as required under the Safe Climate Act; and
- "(3) an analysis of the status of worldwide greenhouse gas reduction efforts, including implementation of the Safe Climate Act and other policies, both domestic and international, for reducing greenhouse gas emissions, preventing dangerous atmospheric concentrations of greenhouse gases, preventing significant irreversible consequences of climate change, and reducing vulnerability to the impacts of climate change.
- "(b) EXCEPTION.—Paragraph (3) of subsection (a) shall not apply to the first report submitted under such subsection.
- ''(e) Latest Scientific Information.—The analysis required under subsection (a)(1) shall—
- "(1) address existing scientific information and reports, considering, to the greatest extent possible, the most recent assessment report of the Intergovernmental Panel on Climate Change, reports by the United States Global Change Research Program, the Natural Resources Climate Change Adaptation Panel established under section 475 of the American Clean Energy and Security Act of 2009, and Federal agencies, and the European Union's global temperature data assessment;
 - "(2) review trends and projections for—
- "(A) global and country-specific annual emissions of greenhouse gases, and cumulative greenhouse gas emissions produced between 1850 and the present, including—
- "(i) global cumulative emissions of anthropogenic greenhouse gases;
- "(ii) global annual emissions of anthropogenic greenhouse gases; and
- "(iii) by country, annual total, annual per capita, and cumulative anthropogenic emissions of greenhouse gases for the top 50 emitting nations:
- "(B) significant changes, both globally and by region, in annual net non-anthropogenic greenhouse gas emissions from natural sources, including permafrost, forests, or oceans:
- "(C) global atmospheric concentrations of greenhouse gases, expressed in annual concentration units as well as carbon dioxide equivalents based on 100-year global warming potentials;
- "(D) major climate forcing factors, such as aerosols;
- "(E) global average temperature, expressed as seasonal and annual averages in land, ocean, and land-plus-ocean averages; and
 - "(F) sea level rise;
- "(3) assess the current and potential impacts of global climate change on—
- "(A) human populations, including impacts on public health, economic livelihoods, subsistence, human infrastructure, and displacement or permanent relocation due to flooding, severe weather, extended drought, erosion, or other ecosystem changes;
- "(B) freshwater systems, including water resources for human consumption and agri-

- culture and natural and managed ecosystems, flood and drought risks, and relative humidity:
- "(C) the carbon cycle, including impacts related to the thawing of permafrost, the frequency and intensity of wildfire, and terrestrial and ocean carbon sinks:
- "(D) ecosystems and animal and plant populations, including impacts on species abundance, phenology, and distribution;
- "(E) oceans and ocean ecosystems, including effects on sea level, ocean acidity, ocean temperatures, coral reefs, ocean circulation, fisheries, and other indicators of ocean ecosystem health:
- "(F) the cryosphere, including effects on ice sheet mass balance, mountain glacier mass balance, and sea-ice extent and volume:
- "(G) changes in the intensity, frequency, or distribution of severe weather events, including precipitation, tropical cyclones, tornadoes, and severe heat waves;
 - "(H) agriculture and forest systems; and
- "(I) any other indicators the Administrator deems appropriate;
- "(4) summarize any significant socio-economic impacts of climate change in the United States, including the territories of the United States, drawing on work by Federal agencies and the academic literature, including impacts on—
 - "(A) public health;
- "(B) economic livelihoods and subsistence; "(C) displacement or permanent relocation due to flooding, severe weather, extended drought, erosion, or other ecosystem changes:
- "(D) human infrastructure, including coastal infrastructure vulnerability to extreme events and sea level rise, river floodplain infrastructure, and sewer and water management systems;
- "(E) agriculture and forests, including effects on potential growing season, distribution, and yield:
- "(F) water resources for human consumption, agriculture and natural and managed ecosystems, flood and drought risks, and relative humidity:
 - "(G) energy supply and use; and
- "(H) transportation;
- "(5) in assessing risks and impacts, use a risk management framework, including both qualitative and quantitative measures, to assess the observed and projected impacts of current and future climate change, accounting for—
- "(A) both monetized and non-monetized losses:
- "(B) potential nonlinear, abrupt, or essentially irreversible changes in the climate system;
- $\mbox{``(C)}$ potential nonlinear increases in the cost of impacts;
- ``(D) potential low-probability, high impact events; and
- "(E) whether impacts are transitory or essentially permanent; and
- "(6) based on the findings of the Administrator under this section, as well as assessments produced by the Intergovernmental Panel on Climate Change, the United States Global Change Research program, and other relevant scientific entities—
- "(A) describe increased risks to natural systems and society that would result from an increase in global average temperature 3.6 degrees Fahrenheit (2 degrees Celsius) above the pre-industrial average or an increase in atmospheric greenhouse gas concentrations above 450 parts per million carbon dioxide equivalent; and
 - "(B) identify and assess—
- "(i) significant residual risks not avoided by the thresholds described in subparagraph

- "(ii) alternative thresholds or targets that may more effectively limit the risks identified pursuant to clause (i); and
- "(iii) thresholds above those described in subparagraph (A) which significantly increase the risk of certain impacts or render them essentially permanent.
- "(d) STATUS OF MONITORING AND VERIFICATION CAPABILITIES TO EVALUATE GREENHOUSE GAS REDUCTION EFFORTS.—The analysis required under subsection (a)(2) shall evaluate the capabilities of the monitoring, reporting, and verification systems used to quantify progress in achieving reductions in greenhouse gas emissions both globally and in the United States (as described in section 702), including—
- "(1) quantification of emissions and emission reductions by entities participating in the cap and trade program under this title;
- "(2) quantification of emissions and emission reductions by entities participating in the offset program under this title;
- "(3) quantification of emission and emissions reductions by entities regulated by performance standards;
- "(4) quantification of aggregate net emissions and emissions reductions by the United States; and
- "(5) quantification of global changes in net emissions and in sources and sinks of greenhouse gases.
- "(e) STATUS OF GREENHOUSE GAS REDUCTION EFFORTS.—The analysis required under subsection (a)(3) shall address—
- "(1) whether the programs under Safe Climate Act and other Federal statutes are resulting in sufficient United States greenhouse gas emissions reductions to meet the emissions reduction goals described in section 702, taking into account the use of offsets; and
- "(2) whether United States actions, taking into account international actions, commitments, and trends, and considering the range of plausible emissions scenarios, are sufficient to avoid—
- "(A) atmospheric greenhouse gas concentrations above 450 parts per million carbon dioxide equivalent;
- "(B) global average surface temperature 3.6 degrees Fahrenheit (2 degrees Celsius) above the pre-industrial average, or such other temperature thresholds as the Administrator deems appropriate; and
- "(C) other temperature or greenhouse gas thresholds identified pursuant to subsection (c)(6)(B).
 - "(f) RECOMMENDATIONS.—
- "(I) LATEST SCIENTIFIC INFORMATION.— Based on the analysis described in subsection (a)(1), each report under subsection (a) shall identify actions that could be taken to—
- "(A) improve the characterization of changes in the earth-climate system and impacts of global climate change;
- "(B) better inform decision making and actions related to global climate change;
- $\mbox{\ensuremath{^{\prime\prime}}}(C)$ mitigate risks to natural and social systems; and
- $\lq\lq(D)$ design policies to better account for climate risks.
- "(2) MONITORING, REPORTING AND VERIFICATION.—Based on the analysis described in subsection (a)(2), each report under subsection (a) shall identify key gaps in measurement, reporting, and verification capabilities and make recommendations to improve the accuracy and reliability of those capabilities.
- ¹(3) STATUS OF GREENHOUSE GAS REDUCTION EFFORTS.—Based on the analysis described in subsection (a)(3), taking into account international actions, commitments, and trends, and considering the range of plausible emissions scenarios, each report under subsection (a) shall identify—

- "(A) the quantity of additional reductions required to meet the emissions reduction goals in section 702;
- "(B) the quantity of additional reductions in global greenhouse gas emissions needed to avoid the concentration and temperature thresholds identified in subsection (e); and
- "(C) possible strategies and approaches for achieving additional reductions.
- "(g) AUTHORIZATION OF APPROPRIATIONS. There are authorized to be appropriated to carry out this section such sums as may be necessary.

"SEC. 706. NATIONAL ACADEMY REVIEW.

- "(a) IN GENERAL -Not later than 1 year after the date of enactment of this title, the Administrator shall offer to enter into a contract with the National Academy of Sciences (in this section referred to as the 'Academy') under which the Academy shall, not later than July 1, 2014, and every 4 years thereafter, submit to Congress and the Administrator a report that includes-
- "(1) a review of the most recent report and recommendations issued under section 705;
- "(2) an analysis of technologies to achieve reductions in greenhouse gas emissions.
- "(b) FAILURE TO ISSUE A REPORT -In the event that the Administrator has not issued all or part of the most recent report required under section 705, the Academy shall conduct its own review and analysis of the required information.
- "(c) TECHNOLOGICAL INFORMATION.—The analysis required under subsection (a)(2) shall-
- "(1) review existing technological information and reports, including the most recent reports by the Department of Energy, the United States Global Change Research Program, the Intergovernmental Panel on Climate Change, and the International Energy Agency and any other relevant information on technologies or practices that reduce or limit greenhouse gas emissions;
- "(2) include the participation of technical experts from relevant private industry sec-
- "(3) review the current and future projected deployment of technologies and practices in the United States that reduce or limit greenhouse gas emissions, including-
- "(A) technologies for capture and sequestration of greenhouse gases;
- "(B) technologies to improve energy efficiency;
- "(C) low- or zero-greenhouse gas emitting energy technologies;
- "(D) low- or zero-greenhouse gas emitting
- "(E) biological sequestration practices and technologies; and
- "(F) any other technologies the Academy deems relevant; and
- "(4) review and compare the emissions reduction potential, commercial viability, market penetration, investment trends, and deployment of the technologies described in paragraph (3), including-
- '(A) the need for additional research and development, including publicly funded research and development;
- '(B) the extent of commercial deployment. including, where appropriate, a comparison to the cost and level of deployment of conventional fossil fuel-fired energy technologies and devices; and
- "(C) an evaluation of any substantial technological, legal, or market-based barriers to commercial deployment.
 - "(d) Recommendations.
- "(1) LATEST SCIENTIFIC INFORMATION.-Based on the review described in subsection (a)(1), the Academy shall identify actions that could be taken to-

- "(A) improve the characterization of changes in the earth-climate system and impacts of global climate change;
- "(B) better inform decision making and actions related to global climate change;
- "(C) mitigate risks to natural and social
- "(D) design policies to better account for climate risks; and
- "(E) improve the accuracy and reliability of capabilities to monitor, report, and verify greenhouse gas emissions reduction efforts.
- "(2) TECHNOLOGICAL INFORMATION.—Based on the analysis described in subsection (a)(2), the Academy shall identify-
- "(A) additional emissions reductions that may be possible as a result of technologies described in the analysis:
- '(B) barriers to the deployment of such technologies: and
- '(C) actions that could be taken to speed deployment of such technologies.
- "(3) STATUS OF GREENHOUSE GAS REDUCTION EFFORTS.—Based on the review described in subsection (a)(1), the Academy shall identify-
- "(A) the quantity of additional reductions required to meet the emissions reduction goals described in section 702; and
- "(B) the quantity of additional reductions in global greenhouse gas emissions needed to avoid the concentration and temperature thresholds described in section 705(c)(6)(A) or identified pursuant to section 705(c)(6)(B).
- "(e) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to carry out this section such sums as may be necessary.

"SEC. 707. PRESIDENTIAL RESPONSE AND REC-OMMENDATIONS.

- "(a) AGENCY ACTIONS.—The President shall direct relevant Federal agencies to use existing statutory authority to take appropriate actions identified in the reports submitted under sections 705 and 706, and to address any shortfalls identified in such reports, not later than July 1, 2015, and every 4 years
- (b) PLAN —In the event that the Administrator or the National Academy of Sciences has concluded, in the most recent report submitted under section 705 or 706 respectively. that the United States will not achieve the necessary domestic greenhouse gas emissions reductions, or that global actions will not maintain safe global average surface temperature and atmospheric greenhouse gas concentration thresholds, the President shall, not later than July 1, 2015, and every President 4 years thereafter, submit to Congress a plan identifying domestic and international actions that will achieve necessary additional greenhouse gas reductions, including any recommendations for legislative action.

"PART B—DESIGNATION AND REGISTRATION OF GREENHOUSE GASES "SEC. 711. DESIGNATION OF GREENHOUSE GASES.

- "(a) GREENHOUSE GASES .- For purposes of this title, the following are greenhouse
- "(1) Carbon dioxide.
- "(2) Methane.
- "(3) Nitrous oxide.
- "(4) Sulfur hexafluoride.
- "(5) Hydrofluorocarbons emitted from a chemical manufacturing process at an industrial stationary source.
 - '(6) Any perfluorocarbon.
- "(7) Nitrogen trifluoride.
- "(8) Any other anthropogenic gas designated as a greenhouse gas by the Administrator under this section.
- (b) Determination on Administrator's INITIATIVE.—The Administrator shall, rule-
- "(1) determine whether 1 metric ton of another anthropogenic gas makes the same or

greater contribution to global warming over 100 years as 1 metric ton of carbon dioxide;

"(2) determine the carbon dioxide equivalent value for each gas with respect to which the Administrator makes an affirmative determination under paragraph (1);

"(3) for each gas with respect to which the Administrator makes an affirmative determination under paragraph (1) and that is used as a substitute for a class I or class II substance under title VI, determine the extent to which to regulate that gas under section 619 and specify appropriate compliance obligations under section 619;

"(4) designate as a greenhouse gas for purposes of this title each gas for which the Administrator makes an affirmative determination under paragraph (1), to the extent that it is not regulated under section 619;

"(5) specify the appropriate compliance obligations under this title for each gas designated as a greenhouse gas under paragraph

- $\overset{ ext{(4)}}{\text{.}}$ (c) Petitions to Designate a Green-HOUSE GAS .-
- "(1) IN GENERAL.—Any person may petition the Administrator to designate as a greenhouse gas any anthropogenic gas 1 metric ton of which makes the same or greater contribution to global warming over 100 years as 1 metric ton of carbon dioxide.
- (2) CONTENTS OF PETITION.—The petitioner shall provide sufficient data, as specified by rule by the Administrator, to demonstrate that the gas is likely to be designated as a greenhouse gas and is likely to be produced, imported, used, or emitted in the United States. To the extent practicable, the petitioner shall also identify producers, importers, distributors, users, and emitters of the gas in the United States.
- "(3) REVIEW AND ACTION BY THE ADMINIS-TRATOR.—Not later than 90 days after receipt of a petition under paragraph (2), the Administrator shall determine whether the petition is complete and notify the petitioner and the public of the decision.
- '(4) ADDITIONAL INFORMATION.—The Administrator may require producers, importers, distributors, users, or emitters of the gas to provide information on the contribution of the gas to global warming over 100 years compared to carbon dioxide.
- "(5) Treatment of petition.—For any substance used as a substitute for a class I or class II substance under title VI, the Administrator may elect to treat a petition under this subsection as a petition to list the substance as a class II, group II substance under section 619, and may require the petition to be amended to address listing criteria promulgated under that section.
- "(6) Determination.—Not later than 2 years after receipt of a complete petition, the Administrator shall, after notice and an opportunity for comment-
- "(A) issue and publish in the Federal Register-
- "(i) a determination that 1 metric ton of the gas does not make a contribution to global warming over 100 years that is equal to or greater than that made by 1 metric ton of carbon dioxide; and
 - (ii) an explanation of the decision; or
- "(B) determine that 1 metric ton of the gas makes a contribution to global warming over 100 years that is equal to or greater than that made by 1 metric ton of carbon dioxide, and take the actions described in subsection (b) with respect to such gas.
- -The Adminis-'(7) Grounds for denial. trator may not deny a petition under this subsection solely on the basis of inadequate Environmental Protection Agency resources or time for review.
- "(d) SCIENCE ADVISORY BOARD CONSULTA-TION.

- "(1) Consultation.—The Administrator shall—
- "(A) give notice to the Science Advisory Board prior to making a determination under subsection (b)(1), (c)(6), or (e)(2)(B);
- "(B) consider the written recommendations of the Science Advisory Board under paragraph (2) regarding the determination; and
- "(C) consult with the Science Advisory Board regarding such determination, including consultation subsequent to receipt of such written recommendations.
- "(2) FORMULATION OF RECOMMENDATIONS.— Upon receipt of notice under paragraph (1)(A) regarding a pending determination under subsection (b)(1), (c)(6), or (e)(2)(B), the Science Advisory Board shall—
- "(A) formulate recommendations regarding such determination, subject to a peer review process; and
- "(B) submit such recommendations in writing to the Administrator.
- "(e) Manufacturing and Emission No-
- "(1) NOTICE REQUIREMENT.—
- "(A) IN GENERAL.—Effective 24 months after the date of enactment of this title, no person may manufacture or introduce into interstate commerce a fluorinated gas, or emit a significant quantity, as determined by the Administrator, of any fluorinated gas that is generated as a byproduct during the production or use of another fluorinated gas, unless—
- "(i) the gas is designated as a greenhouse gas under this section or is an ozone-depleting substance listed as a class I or class II substance under title VI;
- "(ii) the Administrator has determined that 1 metric ton of such gas does not make a contribution to global warming over 100 years that is equal to or greater than that made by 1 metric ton of carbon dioxide; or
- "(iii) the person manufacturing or importing the gas for distribution into interstate commerce, or emitting the gas, has submitted to the Administrator, at least 90 days before the start of such manufacture, introduction into commerce, or emission, a notice of such person's manufacture, introduction into commerce, or emission of such gas, and the Administrator has not determined that that notice or a substantially similar notice submitted by that person is incomplete.
- "(B) ALTERNATIVE COMPLIANCE.—For a gas that is a substitute for a class I or class II substance under title VI and either has been listed as acceptable for use under section 612 or is currently subject to evaluation under section 612, the Administrator may accept the notice and information provided pursuant to that section as fulfilling the obligation under clause (iii) of subparagraph (A).
- "(2) REVIEW AND ACTION BY THE ADMINIS-
- "(A) COMPLETENESS.—Not later than 90 days after receipt of notice under paragraph (1)(A)(iii) or (B), the Administrator shall determine whether the notice is complete.
- "(B) DETERMINATION.—If the Administrator determines that the notice is complete, the Administrator shall, after notice and an opportunity for comment, not later than 12 months after receipt of the notice—
- "(i) issue and publish in the Federal Register—
- "(I) a determination that 1 metric ton of the gas does not make a contribution to global warming over 100 years that is equal to or greater than that made by 1 metric ton of carbon dioxide: and
 - "(II) an explanation of the decision; or
- "(ii) determine that 1 metric ton of the gas makes a contribution to global warming over 100 years that is equal to or greater than that made by 1 metric ton of carbon dioxide,

- and take the actions described in subsection (b) with respect to such gas.
- (b) with respect to such gas.

 "(f) REGULATIONS.—Not later than one year after the date of enactment of this title, the Administrator shall promulgate regulations to carry out this section. Such regulations shall include—
- "(1) requirements for the contents of a petition submitted under subsection (e);
- "(2) requirements for the contents of a notice required under subsection (e); and
- "(3) methods and standards for evaluating the carbon dioxide equivalent value of a gas.
- "(g) GASES REGULATED UNDER TITLE VI.— The Administrator shall not designate a gas as a greenhouse gas under this section to the extent that the gas is regulated under title
- VI.
 "(h) SAVINGS CLAUSE.—Nothing in this section shall be interpreted to relieve any person from complying with the requirements of section 612.

"SEC. 712. CARBON DIOXIDE EQUIVALENT VALUE OF GREENHOUSE GASES.

- "(a) MEASURE OF QUANTITY OF GREENHOUSE GASES.—Any provision of this title or title VIII that refers to a quantity or percentage of a quantity of greenhouse gases shall mean the quantity or percentage of the greenhouse gases expressed in carbon dioxide equivalents.
- "(b) INITIAL VALUE.—Except as provided by the Administrator under this section or section 711—
- "(1) the carbon dioxide equivalent value of greenhouse gases for purposes of this Act shall be as follows:

"CARBON DIOXIDE EQUIVALENT OF 1 TON OF LISTED GREENHOUSE GASES

Greenhouse gas (1 metric ton)	Carbon dioxide equivalent (metric tons)
Carbon diox- ide	1
Methane	25
Nitrous oxide	298
HFC-23	14,800
HFC-125	3,500
HFC-134a	1,430
HFC-143a	4,470
HFC-152a	124
HFC-227ea	3,220
HFC-236fa	9,810
HFC-4310mee	1,640
CF ₄	7,390
C ₂ F ₆	12,200
C ₄ F ₁₀	8,860
C ₆ F ₁₄	9,300
SF ₆	22,800
NF ₃	17,200

and

"(2) the carbon dioxide equivalent value for purposes of this Act for any greenhouse gas not listed in the table under paragraph (1) shall be the 100-year Global Warming Potentials provided in the Intergovernmental Panel on Climate Change Fourth Assessment Report.

'(c) Periodic Review.—

- "(1) Not later than February 1, 2017, and (except as provided in paragraph (3)) not less than every 5 years thereafter, the Administrator shall—
- "(A) review and, if appropriate, revise the carbon dioxide equivalent values established under this section or section 711(b)(2), based on a determination of the number of metric tons of carbon dioxide that makes the same contribution to global warming over 100 years as 1 metric ton of each greenhouse gas; and
- "(B) publish in the Federal Register the results of that review and any revisions.
- "(2) A revised determination published in the Federal Register under paragraph (1)(B) shall take effect for greenhouse gas emissions starting on January 1 of the first calendar year starting at least 9 months after the date on which the revised determination was published.
- "(3) The Administrator may decrease the frequency of review and revision under paragraph (1) if the Administrator determines that such decrease is appropriate in order to synchronize such review and revision with any similar review process carried out pursuant to the United Nations Framework Convention on Climate Change, done at New York on May 9, 1992, or to an agreement negotiated under that convention, except that in no event shall the Administrator carry out such review and revision any less frequently than every 10 years.
- "(d) METHODOLOGY.—In setting carbon dioxide equivalent values, for purposes of this section or section 711, the Administrator shall take into account publications by the Intergovernmental Panel on Climate Change or a successor organization under the auspices of the United Nations Environmental Programme and the World Meteorological Organization.

"SEC. 713. GREENHOUSE GAS REGISTRY.

- "(a) DEFINITIONS.—For purposes of this section:
- "(1) CLIMATE REGISTRY.—The term 'Climate Registry' means the greenhouse gas emissions registry jointly established and managed by more than 40 States and Indian tribes in 2007 to collect high-quality greenhouse gas emission data from facilities, corporations, and other organizations to support various greenhouse gas emission reporting and reduction policies for the member States and Indian tribes.
- "(2) REPORTING ENTITY.—The term 'reporting entity' means—
 - "(A) a covered entity;
 - "(B) an entity that—
- "(i) would be a covered entity if it had emitted, produced, imported, manufactured, or delivered in 2008 or any subsequent year more than the applicable threshold level in the definition of covered entity in paragraph (13) of section 700: and
- "(ii) has emitted, produced, imported, manufactured, or delivered in 2008 or any subsequent year more than the applicable threshold level in the definition of covered entity in paragraph (13) of section 700, provided that the figure of 25,000 tons of carbon dioxide equivalent is read instead as 10,000 tons of carbon dioxide equivalent and the figure of 460,000,000 cubic feet is read instead as 184,000,000 cubic feet;
- "(C) any other entity that emits a greenhouse gas, or produces, imports, manufactures, or delivers material whose use results or may result in greenhouse gas emissions if the Administrator determines that reporting under this section by such entity will help achieve the purposes of this title or title VIII:
- "(D) any vehicle fleet with emissions of more than 25,000 tons of carbon dioxide equivalent on an annual basis, if the Administrator determines that the inclusion of

such fleet will help achieve the purposes of this title or title VIII; or

"(E) any entity that delivers electricity to a facility in an energy-intensive industrial sector that meets the energy or greenhouse gas intensity criteria in section 764(b)(2)(A)(i).

"(b) REGULATIONS.—

"(1) IN GENERAL.—Not later than 6 months after the date of enactment of this title, the Administrator shall issue regulations establishing a Federal greenhouse gas registry. Such regulations shall—

"(A) require reporting entities to submit to the Administrator data on—

"(i) greenhouse gas emissions in the United States:

"(ii) the production and manufacture in the United States, importation into the United States, and, at the discretion of the Administrator, exportation from the United States, of fuels and industrial gases the uses of which result or may result in greenhouse gas emissions:

"(iii) deliveries in the United States of natural gas, and any other gas meeting the specifications for commingling with natural gas for purposes of delivery, the combustion of which result or may result in greenhouse gas emissions; and

"(iv) the capture and sequestration of greenhouse gases;

"(B) require covered entities and, where appropriate, other reporting entities to submit to the Administrator data sufficient to ensure compliance with or implementation of the requirements of this title;

"(C) require reporting of electricity delivered to facilities in an energy-intensive industrial sector that meets the energy or greenhouse gas intensity criteria in section 764(b)(2)(A)(i);

"(D) ensure the completeness, consistency, transparency, accuracy, precision, and reliability of such data;

"(E) take into account the best practices from the most recent Federal, State, tribal, and international protocols for the measurement, accounting, reporting, and verification of greenhouse gas emissions, including protocols from the Climate Registry and other mandatory State or multistate authorized programs;

"(F) take into account the latest scientific research;

"(G) require that, for covered entities with respect to greenhouse gases to which section 722 applies, and, to the extent determined to be appropriate by the Administrator, for covered entities with respect to other greenhouse gases and for other reporting entities, submitted data are based on—

"(i) continuous monitoring systems for fuel flow or emissions, such as continuous emission monitoring systems;

"(ii) alternative systems that are demonstrated as providing data with the same precision, reliability, accessibility, and timeliness, or, to the extent the Administrator determines is appropriate for reporting small amounts of emissions, the same precision, reliability, and accessibility and similar timeliness, as data provided by continuous monitoring systems for fuel flow or emissions; or

"(iii) alternative methodologies that are demonstrated to provide data with precision, reliability, accessibility, and timeliness, or, to the extent the Administrator determines is appropriate for reporting small amounts of emissions, precision, reliability, and accessibility, as similar as is technically feasible to that of data generally provided by continuous monitoring systems for fuel flow or emissions, if the Administrator determines that, with respect to a reporting entity, there is no continuous monitoring system or

alternative system described in clause (i) or (ii) that is technically feasible;

"(H) require that the Administrator, in determining the extent to which the requirement to use systems or methodologies in accordance with subparagraph (G) is appropriate for reporting entities other than covered entities or for greenhouse gases to which section 722 does not apply, consider the cost of using such systems and methodologies, and of using other systems and methodologies that are available and suitable, for quantifying the emissions involved in light of the purposes of this title, including the goal of collecting consistent entitywide data:

"(I) include methods for minimizing double reporting and avoiding irreconcilable double reporting of greenhouse gas emissions;

"(J) establish measurement protocols for carbon capture and sequestration systems, taking into consideration the regulations promulgated under section 813:

"(K) require that reporting entities provide the data required under this paragraph in reports submitted electronically to the Administrator, in such form and containing such information as may be required by the Administrator:

"(L) include requirements for keeping records supporting or related to, and protocols for auditing, submitted data;

"(M) establish consistent policies for calculating carbon content and greenhouse gas emissions for each type of fossil fuel with respect to which reporting is required;

"(N) subsequent to implementation of policies developed under subparagraph (M), provide for immediate dissemination, to States, Indian tribes, and on the Internet, of all data reported under this section as soon as practicable after electronic audit by the Administrator and any resulting correction of data, except that data shall not be disseminated under this subparagraph if—

"(i) its nondissemination is vital to the national security of the United States, as determined by the President; or

"(ii) it is confidential business information that cannot be derived from information that is otherwise publicly available and that would cause significant calculable competitive harm if published, except that—

"(I) data relating to greenhouse gas emissions, including any upstream or verification data from reporting entities, shall not be considered to be confidential business information; and

"(II) data that is confidential business information shall be provided to a State or Indian tribe within whose jurisdiction the reporting entity is located, if the Administrator determines that such State or Indian tribe has in effect protections for confidential business information that are at least as protective as protections applicable to the Federal Government:

"(O) prescribe methods by which the Administrator shall, in cases in which satisfactory data are not submitted to the Administrator for any period of time, estimate emission, production, importation, manufacture, or delivery levels—

"(i) for covered entities with respect to greenhouse gas emissions, production, importation, manufacture, or delivery regulated under this title to ensure that emissions, production, importation, manufacture, or deliveries are not underreported, and to create a strong incentive for meeting data monitoring and reporting requirements—

"(I) with a conservative estimate of the highest emission, production, importation, manufacture, or delivery levels that may have occurred during the period for which data are missing; or

"(II) to the extent the Administrator considers appropriate, with an estimate of such

levels assuming the unit is emitting, producing, importing, manufacturing, or delivering at a maximum potential level during the period, in order to ensure that such levels are not underreported and to create a strong incentive for meeting data monitoring and reporting requirements; and

"(ii) for covered entities with respect to greenhouse gas emissions to which section 722 does not apply and for other reporting entities, with a reasonable estimate of the emission, production, importation, manufacture, or delivery levels that may have occurred during the period for which data are missing;

"(P) require the designation of a designated representative for each reporting entity:

"(Q) require an appropriate certification, by the designated representative for the reporting entity, of accurate and complete accounting of greenhouse gas emissions, as determined by the Administrator; and

"(R) include requirements for other data necessary for accurate and complete accounting of greenhouse gas emissions, as determined by the Administrator, including data for quality assurance of monitoring systems, monitors and other measurement devices, and other data needed to verify reported emissions, production, importation, manufacture, or delivery.

"(2) TIMING.—

"(A) CALENDAR YEARS 2007 THROUGH 2010.—For a base period of calendar years 2007 through 2010, each reporting entity shall submit annual data required under this section to the Administrator not later than March 31, 2011. The Administrator may waive or modify reporting requirements for calendar years 2007 through 2010 for categories of reporting entities to the extent that the Administrator determines that the reporting entities did not keep data or records necessary to meet reporting requirements. The Administrator may, in addition to or in lieu of such requirements, collect information on energy consumption and production.

"(B) SUBSEQUENT CALENDAR YEARS.—For calendar year 2011 and each subsequent calendar year, each reporting entity shall submit quarterly data required under this section to the Administrator not later than 60 days after the end of the applicable quarter, except when the data is already being reported to the Administrator on an earlier timeframe for another program.

"(3) WAIVER OF REPORTING REQUIREMENTS.— The Administrator may waive reporting requirements under this section for specific entities to the extent that the Administrator determines that sufficient and equally or more reliable verified and timely data are available to the Administrator and the public on the Internet under other mandatory statutory requirements.

"(4) ALTERNATIVE THRESHOLD.—The Administrator may, by rule, establish applicability thresholds for reporting under this section using alternative metrics and levels, provided that such metrics and levels are easier to administer and cover the same size and type of sources as the threshold defined in this section.

"(c) Interrelationship With Other Systems.—In developing the regulations issued under subsection (b), the Administrator shall take into account the work done by the Climate Registry and other mandatory State or multistate programs. Such regulations shall include an explanation of any major differences in approach between the system established under the regulations and such registries and programs.

"PART C—PROGRAM RULES "SEC. 721. EMISSION ALLOWANCES.

"(a) IN GENERAL.—The Administrator shall establish a separate quantity of emission allowances for each calendar year starting in 2012, in the amounts prescribed under subsection (e).

"(b) IDENTIFICATION NUMBERS.—The Administrator shall assign to each emission allowance established under subsection (a) a unique identification number that includes the vintage year for that emission allowance.

"(c) Legal Status of Emission Allow-Ances.—

"(1) IN GENERAL.—An allowance established by the Administrator under this title does not constitute a property right, nor does any offset credit or other instrument established or issued under the American Clean Energy and Security Act of 2009, and the amendments made thereby, for the purpose of demonstrating compliance with this title.

"(2) TERMINATION OR LIMITATION.—Nothing in this Act or any other provision of law shall be construed to limit or alter the authority of the United States, including the Administrator acting pursuant to statutory authority, to terminate or limit allowances, offset credits, or term offset credits."

"(3) OTHER PROVISIONS UNAFFECTED.—Except as otherwise specified in this Act, nothing in this Act relating to allowances, offset credits, or term offset credits, established or issued under this title shall affect the application of any other provision of law to a covered entity, or the responsibility for a covered entity to comply with any such provision of law.

"(d) SAVINGS PROVISION.—Nothing in this part shall be construed as requiring a change of any kind in any State law regulating electric utility rates and charges, or as affecting any State law regarding such State regulation, or as limiting State regulation (including any prudency review) under such a State law. Nothing in this part shall be construed as modifying the Federal Power Act or as affecting the authority of the Federal Energy Regulatory Commission under that Act. Nothing in this part shall be construed to interfere with or impair any program for competitive bidding for power supply in a State in which such program is established. "(e) ALLOWANCES FOR EACH CALENDAR

"(e) ALLOWANCES FOR EACH CALENDAR YEAR.—

"(1) IN GENERAL.—Except as provided in paragraph (2), the number of emission allowances established by the Administrator under subsection (a) for each calendar year shall be as provided in the following table:

"Calendar year	Emission allowances (in millions)
2012	4,627
2013	4,544
2014	5,099
2015	5,003
2016	5,482
2017	5,375
2018	5,269
2019	5,162
2020	5,056
2021	4,903
2022	4,751
2023	4,599

"Calendar year	Emission allowances (in millions)
2024	4,446
2025	4,294
2026	4,142
2027	3,990
2028	3,837
2029	3,685
2030	3,533
2031	3,408
2032	3,283
2033	3,158
2034	3,033
2035	2,908
2036	2,784
2037	2,659
2038	2,534
2039	2,409
2040	2,284
2041	2,159
2042	2,034
2043	1,910
2044	1,785
2045	1,660
2046	1,535
2047	1,410
2048	1,285
2049	1,160
2050 and each year thereafter	1,035

"(2) REVISION.—

"(A) IN GENERAL.—The Administrator may adjust, in accordance with subparagraph (B), the number of emission allowances established pursuant to paragraph (1) if, after notice and an opportunity for public comment, the Administrator determines that—

"(i) United States greenhouse gas emissions in 2005 were other than 7,206 million metric tons carbon dioxide equivalent:

"(ii) if the requirements of this title for 2012 had been in effect in 2005, section 722 would have required emission allowances to be held for other than 66.2 percent of United States greenhouse gas emissions in 2005;

"(iii) if the requirements of this title for 2014 had been in effect in 2005, section 722 would have required emission allowances to be held for other than 75.7 percent of United States greenhouse gas emissions in 2005; or

"(iv) if the requirements of this title for 2016 had been in effect in 2005, section 722 would have required emission allowances to be held for other than 84.5 percent United States greenhouse gas emissions in 2005.

"(B) ADJUSTMENT FORMULA.—

"(i) IN GENERAL.—If the Administrator adjusts under this paragraph the number of emission allowances established pursuant to paragraph (1), the number of emission allowances the Administrator establishes for any

given calendar year shall equal the product of—

"(I) United States greenhouse gas emissions in 2005, expressed in tons of carbon dioxide equivalent;

"(II) the percent of United States greenhouse gas emissions in 2005, expressed in tons of carbon dioxide equivalent, that would have been subject to section 722 if the requirements of this title for the given calendar year had been in effect in 2005; and

"(III) the percentage set forth for that calendar year in section 703(a), or determined under clause (ii) of this subparagraph.

"(ii) Targets.—In applying the portion of the formula in clause (i)(III) of this subparagraph, for calendar years for which a percentage is not listed in section 703(a), the Administrator shall use a uniform annual decline in the amount of emissions between the years that are specified.

"(iii) CARBON DIOXIDE EQUIVALENT VALUE.—
If the Administrator adjusts under this paragraph the number of emission allowances established pursuant to paragraph (1), the Administrator shall use the carbon dioxide equivalent values established pursuant to section 712.

"(iv) LIMITATION ON ADJUSTMENT TIMING.— Once a calendar year has started, the Administrator may not adjust the number of emission allowances to be established for that calendar year.

"(C) LIMITATION ON ADJUSTMENT AUTHOR-ITY.—The Administrator may adjust under this paragraph the number of emission allowances to be established pursuant to paragraph (1) only once.

"(f) COMPENSATORY ALLOWANCE.-

"(1) IN GENERAL.—The regulations promulgated under subsection (h) shall provide for the establishment and distribution of compensatory allowances for—

"(A) the destruction, in 2012 or later, of fluorinated gases that are greenhouse gases if—

"(i) allowances or offset credits were retired for their production or importation;

"(ii) such gases are not required to be destroyed under any other provision of law;

"(B) the nonemissive use, in 2012 or later, of petroleum-based or coal-based liquid or gaseous fuel, petroleum coke, natural gas liquid, or natural gas as a feedstock, if allowances or offset credits were retired for the greenhouse gases that would have been emitted from their combustion; and

"(C) the conversionary use, in 2012 or later, of fluorinated gases in a manufacturing process, including semiconductor research or manufacturing, if allowances or offset credits were retired for the production or importation of such gas.

"(2) ESTABLISHMENT AND DISTRIBUTION.—

"(A) IN GENERAL.—Not later than 90 days after the end of each calendar year, the Administrator shall establish and distribute to the entity taking the actions described in subparagraph (A), (B), or (C) of paragraph (1) a quantity of compensatory allowances equivalent to the number of tons of carbon dioxide equivalent of avoided emissions achieved through such actions. In establishing the quantity of compensatory allowances, the Administrator shall take into account the carbon dioxide equivalent value of any greenhouse gas resulting from such action.

"(B) SOURCE OF ALLOWANCES.—Compensatory allowances established under this subsection shall not be emission allowances established under subsection (a).

"(C) IDENTIFICATION NUMBERS.—The Administrator shall assign to each compensatory allowance established under subparagraph (A) a unique identification number.

- "(3) DEFINITIONS.—For purposes of this subsection—
- "(A) the term 'destruction' means the conversion of a greenhouse gas by thermal, chemical, or other means to another gas or set of gases with little or no carbon dioxide equivalent value;
- "(B) the term 'nonemissive use' means the use of fossil fuel as a feedstock in an industrial or manufacturing process to the extent that greenhouse gases are not emitted from such process, and to the extent that the products of such process are not intended for use as, or to be contained in, a fuel; and
- "(C) the term 'conversionary use' means the conversion during research or manufacturing of a fluorinated gas into another greenhouse gas or set of gases with a lower carbon dioxide equivalent value.
 - "(4) FEEDSTOCK EMISSIONS STUDY.—
- "(A) The Administrator may conduct a study to determine the extent to which petroleum-based or coal-based liquid or gaseous fuel, petroleum coke, natural gas liquid, or natural gas are used as feedstocks in manufacturing processes to produce products and the greenhouse gas emissions resulting from such uses.
- "(B) If as a result of such a study, the Administrator determines that the use of such products by noncovered sources results in substantial emissions of greenhouse gases and that such emissions have not been adequately addressed under other requirements of this Act, the Administrator may, after notice and comment rulemaking, promulgate a regulation reducing compensatory allowances commensurately if doing so will not result in shifting such emissions to noncovered sources.
- "(g) FLUORINATED GASES ASSESSMENT.—No later than March 31, 2014, the Administrator shall complete an assessment of the regulation of non-HFC fluorinated gases under this title to determine whether the most appropriate point of regulation is at the gas manufacturer or importer level, or at the source of emissions downstream. If the Administrator determines, based on consideration of environmental effectiveness, cost effectiveness, administrative feasibility, extent of coverage of emissions, competitiveness and relevant considerations consistent other with the purposes of this title, that emissions of non-HFC fluorinated gases can best regulated by designating downstream emission sources as covered entities with compliance obligations under section 722, the Administrator shall, after notice and comment rulemaking, change the definition of covered entity and the compliance obligations under section 722 with respect to non-HFC fluorinated gases accordingly, consistent with the purposes of this title, and establish such other requirements as are necessary to ensure compliance for such entities with the requirements of this title.
- "(h) REGULATIONS.—Not later than 24 months after the date of enactment of this title, the Administrator shall promulgate regulations to carry out the provisions of this title.

"SEC. 722. PROHIBITION OF EXCESS EMISSIONS.

"(a) Prohibition.—Except as provided in subsection (c), effective January 1, 2012, each covered entity is prohibited from emitting greenhouse gases and having attributable greenhouse gas emissions, in combination, in excess of its allowable emissions level. A covered entity's allowable emissions level for each calendar year is the number of emission allowances (or offset credits or other allowances as provided in subsection (d)) it holds as of 12:01 a.m. on April 1 (or a later date established by the Administrator under subsection (j)) of the following calendar year.

- "(b) METHODS OF DEMONSTRATING COMPLIANCE.—Except as otherwise provided in this section, the owner or operator of a covered entity shall not be considered to be in compliance with the prohibition in subsection (a) unless, as of 12:01 a.m. on April 1 (or a later date established by the Administrator under subsection (j)) of each calendar year starting in 2013, the owner or operator holds a quantity of emission allowances (or offset credits or other allowances as provided in subsection (d)) at least as great as the quantity calculated as follows:
- "(1) ELECTRICITY SOURCES.—For a covered entity described in section 700(13)(A), 1 emission allowance for each ton of carbon dioxide equivalent of greenhouse gas that such covered entity emitted in the previous calendar year, excluding emissions resulting from the combustion of—
- "(A) petroleum-based or coal-based liquid fuel:
- "(B) natural gas liquid;
- "(C) renewable biomass or gas derived from renewable biomass; or
- "(D) petroleum coke or gas derived from petroleum coke.
- "(2) FUEL PRODUCERS AND IMPORTERS.—For a covered entity described in section 700(13)(B), 1 emission allowance for each ton of carbon dioxide equivalent of greenhouse gas that would be emitted from the combustion of any petroleum-based or coal-based liquid fuel, petroleum coke, or natural gas liquid, produced or imported by such covered entity during the previous calendar year for sale or distribution in interstate commerce, assuming no capture and sequestration of any greenhouse gas emissions.
- "(3) INDUSTRIAL GAS PRODUCERS AND IM-PORTERS.—For a covered entity described in section 700(13)(C), 1 emission allowance for each ton of carbon dioxide equivalent of fossil fuel-based carbon dioxide, nitrous oxide, or any other fluorinated gas that is a greenhouse gas (except for nitrogen trifluoride), or any combination thereof, produced or imported by such covered entity during the previous calendar year for sale or distribution in interstate commerce.
- "(4) NITROGEN TRIFLUORIDE SOURCES.—For a covered entity described in section 700(13)(D), 1 emission allowance for each ton of carbon dioxide equivalent of nitrogen trifluoride that such covered entity emitted in the previous calendar year.
- "(5) GEOLOGICAL SEQUESTRATION SITES.— For a covered entity described in section 700(13)(E), 1 emission allowance for each ton of carbon dioxide equivalent of greenhouse gas that such covered entity emitted in the previous calendar year.
- "(6) INDUSTRIAL STATIONARY SOURCES.—For a covered entity described in section 700(13)(F), (G), or (H), 1 emission allowance for each ton of carbon dioxide equivalent of greenhouse gas that such covered entity emitted in the previous calendar year, excluding emissions resulting from—
- "(A) the combustion of petroleum-based or coal-based liquid fuel;
- "(B) the combustion of natural gas liquid; "(C) the combustion of renewable biomass or gas derived from renewable biomass;
- "(D) the combustion of petroleum coke or gas derived from petroleum coke; or
- "(E) the use of any fluorinated gas that is a greenhouse gas purchased for use at that covered entity, except for nitrogen trifluoride.
- "(7) INDUSTRIAL FOSSIL FUEL-FIRED COMBUSTION DEVICES.—For a covered entity described in section 700(13)(I), 1 emission allowance for each ton of carbon dioxide equivalent of greenhouse gas that the devices emitted in the previous calendar year, excluding emissions resulting from the combustion of—

- "(A) petroleum-based or coal-based liquid fuel:
 - "(B) natural gas liquid:
- "(C) renewable biomass or gas derived from renewable biomass: or
- "(D) petroleum coke or gas derived from petroleum coke.
- "(8) NATURAL GAS LOCAL DISTRIBUTION COM-PANIES.—For a covered entity described in section 700(13)(J), 1 emission allowance for each ton of carbon dioxide equivalent of greenhouse gas that would be emitted from the combustion of the natural gas, and any other gas meeting the specifications for commingling with natural gas for purposes of delivery, that such entity delivered during the previous calendar year to customers that are not covered entities, assuming no capture and sequestration of that greenhouse gas.
- "(9) ALGAE-BASED FUELS.—Where carbon dioxide (or another greenhouse gas) generated by a covered entity is used as an input in the production of algae-based fuels, the Administrator shall ensure that emission allowances are required to be held either for the carbon dioxide generated by a covered entity that is used to grow the algae or for the portion of the carbon dioxide emitted from combustion of the fuel produced from such algae that is attributable to carbon dioxide generated by a covered entity, but not for both.
- "(10) FUGITIVE EMISSIONS.—The greenhouse gas emissions to which paragraphs (1), (4), (6), and (7) apply shall not include fugitive emissions of greenhouse gas, except to the extent the Administrator determines that data on the carbon dioxide equivalent value of greenhouse gas in the fugitive emissions can be provided with sufficient precision, reliability, accessibility, and timeliness to ensure the integrity of emission allowances, the allowance tracking system, and the cap on emissions.
- "(11) EXPORT EXEMPTION.—This section shall not apply to any petroleum-based or coal-based liquid fuel, petroleum coke, natural gas liquid, fossil fuel-based carbon dioxide, nitrous oxide, or fluorinated gas that is exported for sale or use.
- "(12) NATURAL GAS LIQUIDS.—For natural gas liquids, the covered entity subject to the requirement stated in paragraph (2) shall be the owner of the natural gas liquids at the point the natural gas liquids are separated into merchantable products.
- "(13) APPLICATION OF MULTIPLE PARAGRAPHS.—For a covered entity to which more than 1 of paragraphs (1) through (8) apply, all applicable paragraphs shall apply, except that not more than 1 emission allowance shall be required for the same emission.
- "(14) APPLICATION TO FRACTIONS OF TONS.— In applying paragraphs (1) through (8), any amount less than 1 ton of carbon dioxide equivalent of emissions or attributable greenhouse gas emissions shall be treated as 1 ton of such carbon dioxide equivalent.
 - "(c) Phase-in of Prohibition.—
- "(1) INDUSTRIAL STATIONARY SOURCES.—The prohibition under subsection (a) shall first apply to a covered entity described in section 700(13)(D), (F), (G), (H), or (I), with respect to emissions occurring during calendar year 2014.
- "(2) NATURAL GAS LOCAL DISTRIBUTION COM-PANIES.—The prohibition under subsection (a) shall first apply to a covered entity described in section 700(13)(J) with respect to deliveries occurring during calendar year 2016.
- "(d) ADDITIONAL METHODS.—In addition to using the method of compliance described in subsection (b), a covered entity may do the following:
 - "(1) Offset credits.—

"(A) IN GENERAL.—Covered entities collectively may, in accordance with this paragraph, use offset credits to demonstrate compliance for up to a maximum of 2 billion tons of greenhouse gas emissions annually. The ability to demonstrate compliance with offset credits shall be divided pro rata among covered entities by allowing each covered entity to satisfy a percentage of the number of allowances required to be held under subsection (b) to demonstrate compliance by holding 1 domestic offset credit or 1.25 international offset credits in lieu of an emission allowance, except as provided in subparagraph (D).

"(B) APPLICABLE PERCENTAGE.—The percentage referred to in subparagraph (A) for a given calendar year shall be determined by dividing 2 billion by the sum of 2 billion plus the number of emission allowances established under section 721(a) for the previous year, and multiplying that number by 100. Not more than one half of the applicable percentage under this paragraph may be used by holding domestic offset credits, and not more than one half of the applicable percentage under this paragraph may be used by holding international offset credits, except as provided in subparagraph (C).

"(C) Modified percentages.—If the Administrator determines that domestic offset credits available for use in demonstrating compliance in any calendar year at domestic offset prices generally equal to or less than emission allowance prices, are likely to offset less than 0.9 billion tons of greenhouse gas emissions (measured in tons of carbon dioxide equivalents), for purposes of compliance demonstration in that year the Administrator shall—

"(i) increase the percentage of emissions that can be offset through the use of international offset credits to reflect the amount that 1.0 billion exceeds the number of domestic offset credits the Administrator determines is available, at prices generally equal to or less than emission allowance prices, for that year, up to a maximum of 0.5 billion tons of greenhouse gas emissions; and

"(ii) decrease the percentage of emissions that can be offset through the use of domestic offset credits by the same amount.

"(D) INTERNATIONAL OFFSET CREDITS.—Notwithstanding subparagraph (A), to demonstrate compliance prior to calendar year 2018, a covered entity may use 1 international offset credit in lieu of an emission allowance up to the amount permitted under this paragraph.

"(E) PRESIDENT'S RECOMMENDATION.—The President may make a recommendation to Congress as to whether the number 2 billion specified in subparagraphs (A) and (B) should be increased or decreased.

"(2) TERM OFFSETT CREDITS.—

"(A) IN GENERAL.—Covered entities may, in accordance with this paragraph, use non-expired term offset credits instead of domestic offset credits for purposes of temporarily demonstrating compliance with this section.

"(B) AMOUNT.—The combined quantity of term offset credits and domestic offset credits used by a covered entity to demonstrate compliance for its emissions or attributable greenhouse gas emissions in any given year shall not exceed the quantity of domestic offset credits that a covered entity is entitled to use for that year to demonstrate compliance in accordance with paragraph (1).

"(Ĉ) EXPIRATION.—A term offset credit shall expire in the year after its term ends. The term of a term offset credit shall be calculated by adding to the year of issuance the number of years equal to the length of the crediting period for the practice or project for which the term offset credit was issued, but in no case shall be later than the date 5 years from the date of issuance.

"(D) DEMONSTRATING COMPLIANCE UPON EXPIRATION OF TERM OFFSET CREDIT.—With respect to the emissions for which a covered entity is using term offset credits to demonstrate compliance temporarily with this section, the owner or operator of a covered entity shall not be considered to be in compliance with the prohibition in subsection (a) unless, as of 12:01 a.m. on April 1 (or a later date established by the Administrator under subsection (j)) of the calendar year in which a term offset credit expires, the owner or operator holds—

"(i) for purposes of finally demonstrating compliance, an allowance or a domestic offset credit; or

"(ii) for purposes of temporarily demonstrating compliance, a non-expired term offset credit.

Domestic offset credits used for purposes of finally demonstrating compliance under this subparagraph shall not be subject to the percentage limitations in subparagraph (B).

'(E) FINANCIAL ASSURANCE.—A covered entity may not use a term offset credit to demonstrate compliance temporarily unless it simultaneously provides to the Administrator financial assurance that, at the end of the term offset credit's crediting term, the covered entity will have sufficient resources to obtain the quantity of allowances or credits necessary to demonstrate final compliance. The Administrator shall issue regulations establishing requirements for such financial assurance, which shall take into account the increased risk associated with longer crediting terms. These regulations shall take into account the total number of tons of carbon dioxide equivalent of greenhouse gas emissions for which a covered entity is demonstrating compliance temporarily, and may set a limit on this amount. In the event that a covered entity that used term offset credits to demonstrate compliance temporarily fails to meet the requirements of subparagraph (D) at the end of the term offset credits' crediting term, if the financial assurance mechanism fails to provide to the Administrator the number of allowances or offset credits for which the crediting term has expired, then the Administrator shall retire that number of allowances with the vintage year 2 years after the year in which the term offset credit expires in the same amount. Allowances so retired shall not be counted as emission allowances established for that calendar year under section 721(a).

"(3) INTERNATIONAL EMISSION ALLOW-ANCES.—To demonstrate compliance, a covered entity may hold an international emission allowance in lieu of an emission allowance, except as modified under section 728(d).

"(4) COMPENSATORY ALLOWANCES.—To demonstrate compliance, a covered entity may hold a compensatory allowance obtained under section 721(f) in lieu of an emission allowance.

"(e) RETIREMENT OF ALLOWANCES AND CREDITS.—As soon as practicable after a deadline established for covered entities to demonstrate compliance with this title, the Administrator shall retire the quantity of allowances or credits required to be held under this title.

"(f) ALTERNATIVE METRICS.—For categories of covered entities described in subparagraph (B), (C), (D), (G), (H), or (I) of section 700(13), the Administrator may, by rule, establish an applicability threshold for inclusion under those subparagraphs using an alternative metric and level, provided that such metric and level are easier to administer and cover the same size and type of sources as the threshold defined in such subparagraphs.

"(g) THRESHOLD REVIEW.—For each category of covered entities described in subparagraph (B), (C), (D), (G), (H), or (I) of sec-

tion 700(13), the Administrator shall, in 2020 and once every 8 years thereafter, review the carbon dioxide equivalent emission threshold that is used to define covered entities in such category. After consideration of—

"(1) emissions from covered entities in such category, and from other entities of the same type that emit less than the threshold amount for the category (including emission sources that commence operation after the date of enactment of this title that are not covered entities); and

"(2) whether greater greenhouse gas emission reductions can be cost-effectively achieved by lowering the applicable threshold.

the Administrator may by rule lower such threshold to not less than 10,000 tons of carbon dioxide equivalent emissions. In determining the cost effectiveness of potential reductions from lowering the threshold for covered entities, the Administrator shall consider alternative regulatory greenhouse gas programs, including setting standards under other titles of this Act.

"(h) DESIGNATED REPRESENTATIVES.—The regulations promulgated under section 721(h) shall require that each covered entity, and each entity holding allowances or offset credits or receiving allowances or offset credits from the Administrator under this title, submit to the Administrator a certificate of representation designating a designated representative.

"(i) EDUCATION AND OUTREACH.—

"(1) IN GENERAL.—The Administrator shall establish and carry out a program of education and outreach to assist covered entities, especially entities having little experience with environmental regulatory requirements similar or comparable to those under this title, in preparing to meet the compliance obligations of this title. Such program shall include education with respect to using markets to effectively achieve such compliance.

"(2) FAILURE TO RECEIVE INFORMATION.—A failure to receive information or assistance under this subsection may not be used as a defense against an allegation of any violation of this title.

"(j) ADJUSTMENT OF DEADLINE.—The Administrator may, by rule, establish a deadline for demonstrating compliance, for a calendar year, later than the date provided in subsection (a), as necessary to ensure the availability of emissions data, but in no event shall the deadline be later than June 1.

"(k) NOTICE REQUIREMENT FOR COVERED ENTITIES RECEIVING NATURAL GAS FROM NATURAL GAS LOCAL DISTRIBUTION COMPANIES.—
The owner or operator of a covered entity that takes delivery of natural gas from a natural gas local distribution company shall, not later than September 1 of each calendar year, notify such natural gas local distribution company in writing that such entity will qualify as a covered entity under this title for that calendar year.

"(1) COMPLIANCE OBLIGATION.—For purposes of this title, the year of a compliance obligation is the year in which compliance is determined, not the year in which the greenhouse gas emissions occur or the covered entity has attributable greenhouse gas emissions.

"SEC. 723. PENALTY FOR NONCOMPLIANCE.

"(a) ENFORCEMENT.—A violation of any prohibition of, requirement of, or regulation promulgated pursuant to this title shall be a violation of this Act. It shall be a violation of this Act for a covered entity to emit greenhouse gases and have attributable greenhouse gas emissions, in combination, in excess of its allowable emissions level as provided in section 722(a). Each ton of carbon dioxide equivalent for which a covered entity fails to demonstrate compliance under section 722 shall be a separate violation. In the

event that a covered entity fails to demonstrates compliance at the expiration of a term offset credit's crediting term as required by section 722(d)(2)(D), the year of the violation shall be the year in which the term offset credit expires.

"(b) Excess Emissions Penalty.—

"(1) IN GENERAL.—The owner or operator of any covered entity that fails for any year to comply, on the deadline described in section 722(a), (d)(2) or (j), shall be liable for payment to the Administrator of an excess emissions penalty in the amount described in paragraph (2).

"(2) AMOUNT.—The amount of an excess emissions penalty required to be paid under paragraph (1) shall be equal to the product obtained by multiplying—

"(A) the tons of carbon dioxide equivalent of greenhouse gas emissions or attributable greenhouse gas emissions for which the owner or operator of a covered entity failed to demonstrate compliance under section 722 on the deadline: by

"(B) twice the auction clearing price for the earliest vintage year emission allowances in the last auction carried out pursuant to section 791 before such deadline.

"(3) TIMING.—An excess emissions penalty required under this subsection shall be immediately due and payable to the Administrator, without demand, in accordance with regulations promulgated by the Administrator, which shall be issued not later than 2 years after the date of enactment of this title

"(4) No effect on liability.—An excess emissions penalty due and payable by the owners or operators of a covered entity under this subsection shall not diminish the liability of the owners or operators for any fine, penalty, or assessment against the owners or operators for the same violation under any other provision of this Act or any other

"(c) Excess Emissions Allowances.—The owner or operator of a covered entity that fails for any year to comply on the deadline described in section 722(a), (d)(2) or (j) shall be liable to offset the covered entity's excess combination of greenhouse gases emitted and attributable greenhouse gas emissions by an equal quantity of emission allowances during the following calendar year, or such longer period as the Administrator may prescribe. During the year in which the covered entity failed to comply, or any year thereafter, the Administrator may deduct the emission allowances required under this subsection to offset the covered entity's excess greenhouse gas emissions or attributable greenhouse gas emissions.

"SEC. 724. TRADING.

"(a) PERMITTED TRANSACTIONS.—Except as otherwise provided in this title, the lawful holder of an emission allowance, compensatory allowance, or offset credit may, without restriction, sell, exchange, transfer, hold for compliance in accordance with section 722, or request that the Administrator retire the emission allowance, compensatory allowance, or offset credit.

"(b) No RESTRICTION ON TRANSACTIONS.— The privilege of purchasing, holding, selling, exchanging, transferring, and requesting retirement of emission allowances, compensatory allowances, or offset credits shall not be restricted to the owners and operators of covered entities, except as otherwise provided in this title.

"(c) EFFECTIVENESS OF ALLOWANCE TRANS-FERS.—No transfer of an allowance, offset credit or term offset credit shall be effective for purposes of this title until a certification of the transfer, signed by the designated representative of the transferor, is received and recorded by the Administrator in accordance with regulations promulgated under section 721(h).

"(d) ALLOWANCE TRACKING SYSTEM.—The regulations promulgated under section 721(h) shall include a system for issuing, recording, holding, and tracking allowances, offset credits, and term offset credits that shall specify all necessary procedures and requirements for an orderly and competitive functioning of the allowance and offset credit markets. Such regulations shall provide for appropriate publication of the information in the system on the Internet.

"SEC. 725, BANKING AND BORROWING.

"(a) Banking.—An emission allowance may be used to comply with section 722 or section 723 for emissions in—

"(1) the vintage year for the allowance; or "(2) any calendar year subsequent to the vintage year for the allowance.

"(b) EXPIRATION.—

"(1) REGULATIONS.—The Administrator may establish by regulation criteria and procedures for determining whether, and for implementing a determination that, the expiration of an allowance offset credit, or term offset credit, established or issued under the American Clean Energy and Security Act of 2009 or the amendments made thereby or expiration of the ability to use an international emission allowance to comply with section 722, is necessary to ensure the authenticity and integrity of allowances, offset credits, or term offset credits or the allowance tracking system.

"(2) GENERAL RULE.—Allowance, offset credit, or term offset credit, established or issued under the American Clean Energy and Security Act of 2009 or the amendments made thereby, shall not expire unless—

"(A) it is retired by the Administrator pursuant to this title; or

"(B) it is determined to expire or to have expired by a specific date by the Administrator in accordance with regulations promulgated under paragraph (1).

''(3) INTERNATIONAL EMISSION ALLOW-ANCES.—The ability to use an international emission allowance to comply with section 722 shall not expire unless—

"(A) the allowance is retired by the Administrator pursuant to this title; or

"(B) the ability to use such allowance to meet such compliance obligation requirements is determined to expire or to have expired by a specific date by the Administrator in accordance with regulations promulgated under paragraph (1).

"(c) Borrowing Future Vintage Year Al-LOWANCES.—

"(1) Borrowing without interest.—In addition to the uses described in subsection (a), an emission allowance may be used to demonstrate compliance under section 722 or comply with section 723 for emissions, production, importation, manufacture, or deliveries in the calendar year immediately preceding the vintage year for the allowance.

"(2) Borrowing with interest.—

"(A) IN GENERAL.—A covered entity may demonstrate compliance under section 722 in a specific calendar year for up to 15 percent of its emissions by holding emission allowances with a vintage year 1 to 5 years later than that calendar year.

"(B) LIMITATIONS.—An emission allowance borrowed pursuant to this paragraph shall be an emission allowance that is established by the Administrator for a specific future calendar year under section 721(a) and that is held by the borrower.

"(C) PREPAYMENT OF INTEREST.—For each emission allowance that an owner or operator of a covered entity borrows pursuant to this paragraph, such owner or operator shall, at the time it borrows the allowance, hold for retirement by the Administrator, and the

Administrator shall retire, a quantity of emission allowances that is equal to the product obtained by multiplying—

"(i) 0.08; by

"(ii) the number of years between the calendar year in which the allowance is being used to satisfy a compliance obligation and the vintage year of the allowance.

"SEC. 726. STRATEGIC RESERVE.

"(a) STRATEGIC RESERVE AUCTIONS.-

"(1) IN GENERAL.—Once each quarter of each calendar year for which allowances are established under section 721(a), the Administrator shall auction strategic reserve allowances.

"(2) RESTRICTION TO COVERED ENTITIES.—In each auction conducted under paragraph (1), only covered entities that the Administrator expects will be required to comply with section 722 in the following calendar year shall be eligible to make purchases.

"(b) POOL OF EMISSION ALLOWANCES FOR STRATEGIC RESERVE AUCTIONS.—

"(1) FILLING THE STRATEGIC RESERVE INITIALLY —

"(A) IN GENERAL.—The Administrator shall, not later than 2 years after the date of enactment of this title, establish a strategic reserve account, and shall place in that account an amount of emission allowances established under section 721(a) for each calendar year from 2012 through 2050 in the amounts specified in subparagraph (B) of this paragraph.

"(B) AMOUNT.—The amount referred to in subparagraph (A) shall be—

"(i) for each of calendar years 2012 through 2019, 1 percent of the quantity of emission allowances established for that year pursuant to section 721(e)(1);

"(ii) for each of calendar years 2020 through 2029, 2 percent of the quantity of emission allowances established for that year pursuant to section 721(e)(1); and

"(iii) for each of calendar years 2030 through 2050, 3 percent of the quantity of emission allowances established for that year pursuant to section 721(e)(1).

"(C) EFFECT ON OTHER PROVISIONS.—Any provision in this title (except for subparagraph (B) of this paragraph) that refers to a quantity or percentage of the emission allowances established for a calendar year under section 721(a) shall be considered to refer to the amount of emission allowances as determined pursuant to section 721(e), less any emission allowances established for that year that are placed in the strategic reserve account under this paragraph.

"(2) SUPPLEMENTING THE STRATEGIC RE-SERVE.—The Administrator shall also—

"(A) at the end of each calendar year, transfer to the strategic reserve account each emission allowance that was offered for sale but not sold at any auction conducted under section 791; and

"(B) deposit emission allowances established under subsection (g) from auction proceeds into the strategic reserve, to the extent necessary to maintain the reserve at its original size.

 $\mbox{``(c)}$ Minimum Strategic Reserve Auction Price.—

"(1) IN GENERAL.—At each strategic reserve auction, the Administrator shall offer emission allowances for sale beginning at a minimum price per emission allowance, which shall be known as the 'minimum strategic reserve auction price'.

"(2) INITIAL MINIMUM STRATEGIC RESERVE AUCTION PRICES.—The minimum strategic reserve auction price shall be \$28 (in constant 2009 dollars) for the strategic reserve auctions held in 2012. For the strategic reserve auctions held in 2013 and 2014, the minimum strategic reserve auction price shall be the strategic reserve auction price for the previous year increased by 5 percent plus the

rate of inflation (as measured by the Consumer Price Index for All Urban Consumers).

"(3) MINIMUM STRATEGIC RESERVE AUCTION PRICE IN SUBSEQUENT YEARS.—For each strategic reserve auction held in 2015 and each year thereafter, the minimum strategic reserve auction price shall be 60 percent above a rolling 36-month average of the daily closing price for that year's emission allowance vintage as reported on registered carbon trading facilities, calculated using constant dollars.

"(d) QUANTITY OF EMISSION ALLOWANCES RELEASED FROM THE STRATEGIC RESERVE.—

"(1) INITIAL LIMITS.—For each of calendar years 2012 through 2016, the annual limit on the number of emission allowances from the strategic reserve account that may be auctioned is an amount equal to 5 percent of the emission allowances established for that calendar year under section 721(a). This limit does not apply to international offset credits sold on consignment pursuant to subsection

"(2) LIMITS IN SUBSEQUENT YEARS.—For calendar year 2017 and each year thereafter, the annual limit on the number of emission allowances from the strategic reserve account that may be auctioned is an amount equal to 10 percent of the emission allowances established for that calendar year under section 721(a). This limit does not apply to international offset credits sold on consignment pursuant to subsection (h).

"(3) ALLOCATION OF LIMITATION.—Onefourth of each year's annual strategic reserve auction limit under this subsection shall be made available for auction in each quarter. Any allowances from the strategic reserve account that are made available for sale in a quarterly auction and not sold shall be rolled over and added to the quantity available for sale in the following quarter, except that allowances not sold at auction in the fourth quarter of a year shall not be rolled over to the following calendar year's auctions, but shall be returned to the strategic reserve account.

"(e) PURCHASE LIMIT.—

"(1) IN GENERAL.—Except as provided in paragraph (2) or (3), the annual number of emission allowances that a covered entity may purchase at the strategic reserve auctions in each calendar year shall not exceed 20 percent of the covered entity's combined greenhouse gas emissions and attributable greenhouse gas emissions during the most recent year for which allowances or offset credits were retired under section 722.

"(2) 2012 LIMIT.—For calendar year 2012, the maximum aggregate number of emission allowances that a covered entity may purchase from that year's strategic reserve auctions shall be 20 percent of the covered entity's combined greenhouse gas emissions and attributable greenhouse gas emissions that the covered entity reported to the registry established under section 713 for 2011 and that would be subject to section 722(a) if occurring in later calendar years.

"(3) NEW ENTRANTS.—The Administrator shall, by regulation, establish a separate purchase limit applicable to entities that expect to become a covered entity in the year of the auction, permitting them to purchase emission allowances at the strategic reserve auctions in their first calendar year of operation in an amount of at least 20 percent of their expected combined greenhouse gas emissions and attributable greenhouse gas emissions for that year.

"(f) DELEGATION OR CONTRACT.—Pursuant to regulations under this section, the Administrator may, by delegation or contract, provide for the conduct of strategic reserve auctions under the Administrator's supervision by other departments or agencies of the Fed-

eral Government or by nongovernmental agencies, groups, or organizations.

"(g) USE OF AUCTION PROCEEDS.-

"(1) DEPOSIT IN STRATEGIC RESERVE FUND.— The proceeds from strategic reserve auctions shall be placed in the Strategic Reserve Fund established under section 793(1), and shall be available without further appropriation or fiscal year limitation for the purposes described in this subsection.

"(2) INTERNATIONAL OFFSET CREDITS FOR REDUCED DEFORESTATION.—The Administrator shall use the proceeds from each strategic reserve auction to purchase international offset credits issued for reduced deforestation activities pursuant to section 743(e). The Administrator shall retire those international offset credits and establish a number of emission allowances equal to 80 percent of the number of international offset credits so retired. Emission allowances established under this paragraph shall be in addition to those established under section 721(a).

"(3) EMISSION ALLOWANCES.—The Administrator shall deposit emission allowances established under paragraph (2) in the strategic reserve, except that, with respect to any such emission allowances in excess of the amount necessary to fill the strategic reserve to its original size, the Administrator shall—

"(A) except as provided in subparagraph (B), assign a vintage year to the emission allowance, which shall be no earlier than the year in which the allowance is established under paragraph (2), and shall treat such allowances as ones that are not designated for distribution or auction for purposes of section 782(q) and (r); and

"(B) to the extent any such allowances cannot be assigned a vintage year because of the limitation in paragraph (4), retire the allowances

"(4) LIMITATION.—In no case may the Administrator assign under paragraph (3)(A) more emission allowances to a vintage year than the number of emission allowances from that vintage year that were placed in the strategic reserve account under subsection (b)(1).

''(h) AVAILABILITY OF INTERNATIONAL OFFSET CREDITS FOR AUCTION.—

"(1) IN GENERAL.—The regulations promulgated under section 721(h) shall allow any entity holding international offset credits from reduced deforestation issued under section 743(e) to request that the Administrator include such offset credits in an upcoming strategic reserve auction. The regulations shall provide that—

"(A) such international offset credits will be used to fill bid orders only after the supply of strategic reserve allowances available for sale at that auction has been depleted;

"(B) international offset credits may be sold at a strategic reserve auction under this subsection only if the Administrator determines that it is highly likely that covered entities will, to cover emissions occurring in the year the auction is held, use offset credits to demonstrate compliance under section 722 for emissions equal to or greater than 80 percent of 2 billion tons of carbon dioxide equivalent;

"(C) upon sale of such international offset credits, the Administrator shall retire those international offset credits, and establish and provide to the purchasers a number of emission allowances equal to 80 percent of the number of international offset credits so retired, which allowances shall be in addition to those established under section 721(a); and

"(D) for international offset credits sold pursuant to this subsection, the proceeds for the entity that offered the international offset credits for sale shall be the lesser of"(i) the average daily closing price for international offset credits sold on registered exchanges (or if such price is unavailable, the average price as determined by the Administrator) during the six months prior to the strategic reserve auction at which they were auctioned, with the remaining funds collected upon the sale of the international offset credits deposited in the Treasury; and

"(ii) the amount received for the international offset credits at the auction.

"(2) Proceeds.—For international offset credits sold pursuant to this subsection, notwithstanding section 3302 of title 31, United States Code, or any other provision of law, within 90 days of receipt, the United States shall transfer the proceeds from the auction, as defined in paragraph (1)(D), to the entity that offered the international offset credits for sale. No funds transferred from a purchaser to a seller of international offset credits under this paragraph shall be held by any officer or employee of the United States or treated for any purpose as public monies.

"(3) Pricing.—When the Administrator acts under this subsection as the agent of an entity in possession of international offset credits, the Administrator is not obligated to obtain the highest price possible for the international offset credits, and instead shall auction such international offset credits in the same manner and pursuant to the same rules (except as modified in paragraph (1)) as set forth for auctioning strategic reserve allowances. Entities requesting that such international offset credits be offered for sale at a strategic reserve auction may not set a minimum reserve price for their international offset credits that is different than the minimum strategic reserve auction price set pursuant to subsection (c).

"(i) INITIAL REGULATIONS.—Not later than 24 months after the date of enactment of this title, the Administrator shall promulgate regulations, in consultation with other appropriate agencies, governing the auction of allowances under this section. Such regulations shall include the following requirements:

"(1) FREQUENCY; FIRST AUCTION.—Auctions shall be held four times per year at regular intervals, with the first auction to be held no later than March 31, 2012.

"(2) AUCTION FORMAT.—Auctions shall follow a single-round, sealed-bid, uniform price format.

"(3) Participation; financial assurance.—Auctions shall be open to any covered entity eligible to purchase emission allowances at the auction under subsection (a)(2), except that the Administrator may establish financial assurance requirements to ensure that auction participants can and will perform on their bids.

"(4) DISCLOSURE OF BENEFICIAL OWNER-SHIP.—Each bidder in an auction shall be required to disclose the person or entity sponsoring or benefitting from the bidder's participation in the auction if such person or entity is, in whole or in part, other than the bidder.

"(5) PURCHASE LIMITS.—No person may, directly or in concert with another participant, purchase more than 20 percent of the allowances offered for sale at any quarterly auction

"(6) PUBLICATION OF INFORMATION.—After the auction, the Administrator shall, in a timely fashion, publish the identities of winning bidders, the quantity of allowances obtained by each winning bidder, and the auction clearing price.

"(7) OTHER REQUIREMENTS.—The Administrator may include in the regulations such other requirements or provisions as the Administrator, in consultation with other

agencies as appropriate, considers appropriate to promote effective, efficient, transparent, and fair administration of auctions under this section.

"(j) REVISION OF REGULATIONS.—The Administrator may, at any time, in consultation with other agencies as appropriate, revise the initial regulations promulgated under subsection (i). Such revised regulations need not meet the requirements identified in subsection (i) by promulgating new regulations if the Administrator determines that an alternative auction design would be more effective, taking into account factors including costs of administration, transparency, fairness, and risks of collusion or manipulation. In determining whether and how to revise the initial regulations under this subsection, the Administrator shall not consider maximization of revenues to the Federal Government

"SEC. 727. PERMITS.

"(a) PERMIT PROGRAM.—For stationary sources subject to title V of this Act that are covered entities, the provisions of this title shall be implemented by permits issued to such covered entities (and enforced) in accordance with the provisions of title V, as modified by this title. Any such permit issued by the Administrator, or by a State or Indian tribe with an approved permit program, shall require the owner or operator of a covered entity to hold allowances or offset credits at least equal to the total annual amount of carbon dioxide equivalents for its combined emissions and attributable greenhouse gas emissions to which section 722 applies. No such permit shall be issued that is inconsistent with the requirements of this title, and title V as applicable. Nothing in this section regarding compliance plans or in title V shall be construed as affecting allowances or offset credits. Submission of a statement by the owner or operator, or the designated representative of the owners and operators, of a covered entity that the owners and operators will hold allowances or offset credits for the entity's combined emissions and attributable greenhouse gas emissions to which section 722 applies shall be deemed to meet the proposed and approved planning requirements of title V. Recordation by the Administrator of transfers of allowances and offset credits shall amend automatically all applicable proposed or approved permit applications, compliance plans, and permits.

'(b) MULTIPLE OWNERS.—No permit shall be issued under this section and no allowances or offset credits shall be disbursed under this title to a covered entity or any other person until the designated representative of the owners or operators has filed a certificate of representation with regard to matters under this title, including the holding and distribution of emission allowances and the proceeds of transactions involving emission allowances. Where there are multiple holders of a legal or equitable title to. or a leasehold interest in, such a covered entity or other entity or where a utility or industrial customer purchases power under a long-term power purchase contract from an independent power production facility that is a covered entity, the certificate shall

"(1) that emission allowances and the proceeds of transactions involving emission allowances will be deemed to be held or distributed in proportion to each holder's legal, equitable, leasehold, or contractual reservation or entitlement; or

"(2) if such multiple holders have expressly provided for a different distribution of emission allowances by contract, that emission allowances and the proceeds of transactions involving emission allowances will be deemed to be held or distributed in accordance with the contract.

A passive lessor, or a person who has an equitable interest through such lessor, whose rental payments are not based, either directly or indirectly, upon the revenues or income from the covered entity or other entity shall not be deemed to be a holder of a legal, equitable, leasehold, or contractual interest for the purpose of holding or distributing emission allowances as provided in this subsection, during either the term of such leasehold or thereafter, unless expressly provided for in the leasehold agreement. Except as otherwise provided in this subsection, where all legal or equitable title to or interest in a covered entity, or other entity, is held by a single person, the certificate shall state that all emission allowances received by the entity are deemed to be held for that person.

"(c) Prohibition.—It shall be unlawful for any person to operate any stationary source subject to the requirements of this section except in compliance with the terms and requirements of a permit issued by the Administrator or a State or Indian tribe with an approved permit program in accordance with this section. For purposes of this subsection, compliance, as provided in section 504(f), with a permit issued under title V which complies with this title for covered entities shall be deemed compliance with this subsection as well as section 502(a).

"(d) RELIABILITY.—Nothing in this section or title V shall be construed as requiring termination of operations of a stationary source that is a covered entity for failure to have an approved permit, or compliance plan, that is consistent with the requirements in the second and fifth sentences of subsection (a) concerning the holding of allowances or offset credits, except that any such covered entity may be subject to the applicable enforcement provision of section 113.

"(e) REGULATIONS.—Not later than 2 years after the date of enactment of this title, the Administrator shall promulgate regulations to implement this section. To provide for permits required under this section, each State in which one or more stationary sources that are covered entities are located shall submit, in accordance with this section and title V, revised permit programs for approval.

"SEC. 728. INTERNATIONAL EMISSION ALLOW-ANCES.

"(a) QUALIFYING PROGRAMS.—The Administrator, in consultation with the Secretary of State, may by rule designate an international climate change program as a qualifying international program if—

"(1) the program is run by a national or supranational foreign government, and imposes a mandatory absolute tonnage limit on greenhouse gas emissions from 1 or more foreign countries, or from 1 or more economic sectors in such a country or countries; and

"(2) the program is at least as stringent as the program established by this title, including provisions to ensure at least comparable monitoring, compliance, enforcement, quality of offsets, and restrictions on the use of offsets

"(b) DISQUALIFIED ALLOWANCES.—An international emission allowance may not be held under section 722(d)(2) if it is in the nature of an offset instrument or allowance awarded based on the achievement of greenhouse gas emission reductions or avoidance, or greenhouse gas sequestration, that are not subject to the mandatory absolute tonnage limits referred to in subsection (a)(1).

"(c) Retirement.

"(1) ENTITY CERTIFICATION.—The owner or operator of an entity that holds an international emission allowance under section

722(d)(2) shall certify to the Administrator that such international emission allowance has not previously been used to comply with any foreign, international, or domestic greenhouse gas regulatory program.

"(2) Retirement.

"(A) FOREIGN AND INTERNATIONAL REGU-LATORY ENTITIES.—The Administrator, in consultation with the Secretary of State, shall seek, by whatever means appropriate, including agreements and technical cooperation on allowance tracking, to ensure that any relevant foreign, international, and domestic regulatory entities—

"(i) are notified of the use, for purposes of compliance with this title, of any international emission allowance; and

"(ii) provide for the disqualification of such international emission allowance for any subsequent use under the relevant foreign, international, or domestic greenhouse gas regulatory program, regardless of whether such use is a sale, exchange, or submission to satisfy a compliance obligation.

"(B) DISQUALIFICATION FROM FURTHER USE.—The Administrator shall ensure that, once an international emission allowance has been disqualified or otherwise used for purposes of compliance with this title, such allowance shall be disqualified from any further use under this title.

"(d) USE LIMITATIONS.—The Administrator may, by rule, apply a limit to the percentage of the combined greenhouse gas emissions and attributable greenhouse gas emissions of a covered entity with respect to which compliance may be demonstrated by holding international emission allowances under section 722(d)(2), consistent with the purposes of the Safe Climate Act.

"PART D—OFFSETS

"SEC. 731. OFFSETS INTEGRITY ADVISORY BOARD.

"(a) ESTABLISHMENT.—Not later than 30 days after the date of enactment of this title, the Administrator shall establish an independent Offsets Integrity Advisory Board. The Advisory Board shall make recommendations to the Administrator for use in promulgating and revising regulations under this part and part E, and for ensuring the overall environmental integrity of the programs established pursuant to those regulations.

"(b) MEMBERSHIP.—The Advisory Board shall be comprised of at least nine members. Each member shall be qualified by education, training, and experience to evaluate scientific and technical information on matters referred to the Board under this section. The Administrator shall appoint Advisory Board members, including a chair and vice-chair of the Advisory Board. Terms shall be 3 years in length, except for initial terms, which may be up to 5 years in length to allow staggering. Members may be reappointed only once for an additional 3-year term, and such second term may follow directly after a first term.

"(c) ACTIVITIES.—The Advisory Board established pursuant to subsection (a) shall—

"(1) provide recommendations, not later than 90 days after the Advisory Board's establishment and periodically thereafter, to the Administrator regarding offset project types that should be considered for eligibility under section 733, taking into consideration relevant scientific and other issues, including—

"(A) the availability of a representative data set for use in developing the activity baseline:

"(B) the potential for accurate quantification of greenhouse gas reduction, avoidance, or sequestration for an offset project type;

"(C) the potential level of scientific and measurement uncertainty associated with an offset project type; and

- "(D) any beneficial or adverse environmental, public health, welfare, social, economic, or energy effects associated with an offset project type;
- "(2) make available to the Administrator its advice and comments on offset methodologies that should be considered under regulations promulgated with respect to section 734, including methodologies to address the issues of additionality, activity baselines, quantification methods, leakage, uncertainty, permanence, and environmental integrity;
- "(3) make available to the Administrator, and other relevant Federal agencies, its advice and comments regarding scientific, technical, and methodological issues specific to the issuance of international offset credits under section 743;
- "(4) make available to the Administrator, and other relevant Federal agencies, its advice and comments regarding scientific, technical, and methodological issues associated with the implementation of part E:
- "(5) make available to the Administrator its advice and comments on areas in which further knowledge is required to appraise the adequacy of existing, revised, or proposed methodologies for use under this part and part E, and describe the research efforts necessary to provide the required information; and
- "(6) make available to the Administrator its advice and comments on other ways to improve or safeguard the environmental integrity of programs established under this part and part E.
- '(d) SCIENTIFIC REVIEW OF OFFSET AND DE-FORESTATION REDUCTION PROGRAMS.—Not later than January 1, 2017, and at five-year intervals thereafter, the Advisory Board shall submit to the Administrator and make available to the public an analysis of relevant scientific and technical information related to this part and part E. The Advisory Board shall review approved and potential scientific studies, offset methodologies, project monitoring, offset project verification reports, and audits related to this part and part E, and evaluate the net emissions effects of implemented offset projects. The Advisory Board shall recommend changes to offset methodologies, protocols, or project types, or to the overall offset program under this part, to ensure that offset credits issued by the Administrator do not compromise the integrity of the annual emission reductions established under section 703, and to avoid or minimize adverse effects to human health or the environment.

"SEC. 732. ESTABLISHMENT OF OFFSETS PROGRAM.

- "(a) REGULATIONS.—Not later than 2 years after the date of enactment of this title, the Administrator, in consultation with appropriate Federal agencies and taking into consideration the recommendations of the Advisory Board, shall promulgate regulations establishing a program for the issuance of offset credits in accordance with the requirements of this part. The Administrator shall periodically revise these regulations as necessary to meet the requirements of this part.
- "(b) REQUIREMENTS.—The regulations described in subsection (a) shall—
- "(1) authorize the issuance of offset credits with respect to qualifying offset projects that result in reductions or avoidance of greenhouse gas emissions, or sequestration of greenhouse gases:
- "(2) ensure that such offset credits represent verifiable and additional greenhouse gas emission reductions or avoidance, or increases in sequestration:
- "(3) ensure that offset credits issued for sequestration offset projects are only issued for greenhouse gas reductions that are permanent;

- "(4) provide for the implementation of the requirements of this part; and
- "(5) include as reductions in greenhouse gases reductions achieved through the destruction of methane and its conversion to carbon dioxide, and reductions achieved through destruction of chlorofluorocarbons or other ozone depleting substances, if permitted by the Administrator under section 619(b)(9) and subject to the conditions specified in section 619(b)(9), based on the carbon dioxide equivalent value of the substance destroyed.
- "(c) COORDINATION TO MINIMIZE NEGATIVE EFFECTS.—In promulgating and implementing regulations under this part, the Administrator shall act (including by rejecting projects, if necessary) to avoid or minimize, to the maximum extent practicable, adverse effects on human health or the environment resulting from the implementation of offset projects under this part.
- "(d) OFFSET REGISTRY.—The Administrator shall establish within the allowance tracking system established under section 724(d) an Offset Registry for qualifying offset projects and offset credits issued with respect thereto under this part.
- "(e) LEGAL STATUS OF OFFSET CREDIT.—An offset credit does not constitute a property right.
- "(f) FEES.—The Administrator shall assess fees payable by offset project developers in an amount necessary to cover the administrative costs to the Environmental Protection Agency of carrying out the activities under this part. Amounts collected for such fees shall be available to the Administrator for carrying out the activities under this part to the extent provided in advance in appropriations Acts.

"SEC. 733. ELIGIBLE PROJECT TYPES.

- "(a) LIST OF ELIGIBLE PROJECT TYPES.—
- "(1) IN GENERAL.—As part of the regulations promulgated under section 732(a), the Administrator shall establish, and may periodically revise, a list of types of projects eligible to generate offset credits, including international offset credits, under this part.
- "(2) ADVISORY BOARD RECOMMENDATIONS.— In determining the eligibility of project types, the Administrator shall take into consideration the recommendations of the Advisory Board. If a list established under this section differs from the recommendations of the Advisory Board, the regulations promulgated under section 732(a) shall include a justification for the discrepancy.
- (3) INITIAL DETERMINATION.—The Administrator shall establish the initial eligibility list under paragraph (1) not later than one year after the date of enactment of this title. The Administrator shall add additional project types to the list not later than 2 years after the date of enactment of this title. In determining the initial list, the Administrator shall give priority to consideration of offset project types that are recommended by the Advisory Board and for which there are well developed methodologies that the Administrator determines would meet the criteria of section 734, with such modifications as the Administrator deems appropriate. In establishing methodologies pursuant to section 734, the Administrator shall give priority to methodologies for offset project types included on the initial eligibility list.
- "(b) MODIFICATION OF LIST.—The Adminis-
- "(1) may at any time, by rule, add a project type to the list established under subsection (a) if the Administrator, in consultation with appropriate Federal agencies and taking into consideration the recommendations of the Advisory Board, determines that the project type can generate ad-

- ditional reductions or avoidance of greenhouse gas emissions, or sequestration of greenhouse gases, subject to the requirements of this part;
- "(2) may at any time, by rule, determine that a project type on the list does not meet the requirements of this part, and remove the project type from the list established under subsection (a), in consultation with appropriate Federal agencies and taking into consideration any recommendations of the Advisory Board; and
- "(3) shall consider adding to or removing from the list established under subsection (a), at a minimum, project types proposed to the Administrator—
- ``(A) by petition pursuant to subsection (c); or
- "(B) by the Advisory Board.
- "(c) PETITION PROCESS.—Any person may petition the Administrator to modify the list established under subsection (a) by adding or removing a project type pursuant to subsection (b). Any such petition shall include a showing by the petitioner that there is adequate data to establish that the project type does or does not meet the requirements of this part. Not later than 12 months after receipt of such a petition, the Administrator shall either grant or deny the petition and publish a written explanation of the reasons for the Administrator's decision. The Administrator may not deny a petition under this subsection on the basis of inadequate Environmental Protection Agency resources or time for review.

"SEC. 734. REQUIREMENTS FOR OFFSET PROJECTS.

- "(a) METHODOLOGIES.—As part of the regulations promulgated under section 732(a), the Administrator shall establish, for each type of offset project listed as eligible under section 733, the following:
- "(1) ADDITIONALITY.—A standardized methodology for determining the additionality of greenhouse gas emission reductions or avoidance, or greenhouse gas sequestration, achieved by an offset project of that type. Such methodology shall ensure, at a minimum, that any greenhouse gas emission reduction or avoidance, or any greenhouse gas sequestration, is considered additional only to the extent that it results from activities that—
- "(A) are not required by or undertaken to comply with any law, including any regulation or consent order:
- "(B) were not commenced prior to January 1, 2009, except in the case of—
- "(i) offset project activities that commenced after January 1, 2001, and were registered as of the date of enactment of this title under an offset program with respect to which the Administrator has made an affirmative determination under section 740(a)(2); or
- "(ii) activities that are readily reversible, with respect to which the Administrator may set an alternative earlier date under this subparagraph that is not earlier than January 1, 2001, where the Administrator determines that setting such an alternative date may produce an environmental benefit by removing an incentive to cease and then reinitiate activities that began prior to January 1, 2009; and
- $\mbox{``(C)}$ exceed the activity baseline established under paragraph (2).
- "(2) ACTIVITY BASELINES.—A standardized methodology for establishing activity baselines for offset projects of that type. The Administrator shall set activity baselines to reflect a conservative estimate of business-asusual performance or practices for the relevant type of activity such that the baseline provides an adequate margin of safety to ensure the environmental integrity of offsets calculated in reference to such baseline.

- "(3) QUANTIFICATION METHODS.—A standardized methodology for determining the extent to which greenhouse gas emission reductions or avoidance, or greenhouse gas sequestration, achieved by an offset project of that type exceed a relevant activity baseline, including protocols for monitoring and accounting for uncertainty.
- "(4) LEAKAGE.—A standardized methodology for accounting for and mitigating potential leakage, if any, from an offset project of that type, taking uncertainty into account.
 - "(b) ACCOUNTING FOR REVERSALS.—
- "(1) IN GENERAL.—For each type of sequestration project listed under section 733, the Administrator shall establish requirements to account for and address reversals, including—
- "(A) a requirement to report any reversal with respect to an offset project for which offset credits have been issued under this part;
- "(B) provisions to require emission allowances to be held in amounts to fully compensate for greenhouse gas emissions attributable to reversals, and to assign responsibility for holding such emission allowances;
- "(C) any other provisions the Administrator determines necessary to account for and address reversals.
- "(2) MECHANISMS.—The Administrator shall prescribe mechanisms to ensure that any sequestration with respect to which an offset credit is issued under this part results in a permanent net increase in sequestration, and that full account is taken of any actual or potential reversal of such sequestration, with an adequate margin of safety. The Administrator shall prescribe at least one of the following mechanisms to meet the requirements of this paragraph:
- "(A) An offsets reserve, pursuant to paragraph (3).
- "(B) Insurance that provides for purchase and provision to the Administrator for retirement of an amount of offset credits or emission allowances equal in number to the tons of carbon dioxide equivalents of greenhouse gas emissions released due to reversal.
- "(C) Another mechanism that the Administrator determines satisfies the requirements of this part.
- "(3) Offsets reserve.—
- "(A) IN GENERAL.—An offsets reserve referred to in paragraph (2)(A) is a program under which, before issuance of offset credits under this part, the Administrator shall subtract and reserve from the quantity to be issued a quantity of offset credits based on the risk of reversal. The Administrator shall—
- "(i) hold these reserved offset credits in the offsets reserve; and
- "(ii) register the holding of the reserved offset credits in the Offset Registry established under section 732(d).
 - "(B) Project reversal.—
- "(i) IN GENERAL.—If a reversal has occurred with respect to an offset project for which offset credits are reserved under this paragraph, the Administrator shall retire offset credits or emission allowances from the offsets reserve to fully account for the tons of carbon dioxide equivalent that are no longer sequestered.
- 'i(ii) INTENTIONAL REVERSALS.—If the Administrator determines that a reversal was intentional, the offset project developer for the relevant offset project shall place into the offsets reserve a quantity of offset credits, or combination of offset credits and emission allowances, equal in number to the number of reserve offset credits that were canceled due to the reversal pursuant to clause (i).

- "(iii) UNINTENTIONAL REVERSALS.—If the Administrator determines that a reversal was unintentional, the offset project developer for the relevant offset project shall place into the offsets reserve a quantity of offset credits, or combination of offset credits and emission allowances, equal in number to half the number of offset credits that were reserved for that offset project, or half the number of reserve offset credits that were canceled due to the reversal pursuant to clause (i), whichever is less.
- "(C) USE OF RESERVED OFFSET CREDITS.— Offset credits placed into the offsets reserve under this paragraph may not be used to comply with section 722.
 - "(c) CREDITING PERIODS.—
- "(1) IN GENERAL.—For each offset project type, the Administrator shall specify a crediting period, and establish provisions for petitions for new crediting periods, in accordance with this subsection.
- "(2) DURATION.—The crediting period shall be no less than 5 and no greater than 10 years for any project type other than those involving sequestration.
- "(3) ELIGIBILITY.—An offset project shall be eligible to generate offset credits under this part only during the project's crediting period. During such crediting period, the project shall remain eligible to generate offset credits, subject to the methodologies and project type eligibility list that applied as of the date of project approval under section 735, except as provided in paragraph (4) of this subsection.
- "(4) PETITION FOR NEW CREDITING PERIOD.—An offset project developer may petition for a new crediting period to commence after termination of a crediting period, subject to the methodologies and project type eligibility list in effect at the time when such petition is submitted. A petition may not be submitted under this paragraph more than 18 months before the end of the pending crediting period. The Administrator may limit the number of new crediting periods available for projects of particular project types.
- "(d) ENVIRONMENTAL INTEGRITY.—In establishing the requirements under this section, the Administrator shall apply conservative assumptions or methods to maximize the certainty that the environmental integrity of the cap established under section 703 is not compromised.
- "(e) PRE-EXISTING METHODOLOGIES.—In promulgating requirements under this section, the Administrator shall give due consideration to methodologies for offset projects existing as of the date of enactment of this title.
- "(f) ADDED PROJECT TYPES.—The Administrator shall establish methodologies described in subsection (a), and, as applicable, requirements and mechanisms for reversals as described in subsection (b), for any project type that is added to the list pursuant to section 733.

"SEC. 735. APPROVAL OF OFFSET PROJECTS.

- "(a) APPROVAL PETITION.—An offset project developer shall submit an offset project approval petition providing such information as the Administrator requires to determine whether the offset project is eligible for issuance of offset credits under rules promulgated pursuant to this part.
- "(b) TIMING.—An approval petition shall be submitted to the Administrator under subsection (a) no later than the time at which an offset project's first verification report is submitted under section 736.
- "(c) APPROVAL PETITION REQUIREMENTS.— As part of the regulations promulgated under section 732, the Administrator shall include provisions for, and shall specify, the required components of an offset project approval petition required under subsection (a), which shall include—

- "(1) designation of an offset project developer; and
- "(2) any other information that the Administrator considers to be necessary to achieve the purposes of this part.
- "'(d) APPROVAL AND NOTIFICATION.—Not later than 90 days after receiving a complete approval petition under subsection (a), the Administrator shall make the approval petition publicly available, approve or deny the petition in writing and if the petition is denied, provide the reasons for denial, and make the Administrator's written decision publicly available. After an offset project is approved, the offset project developer shall not be required to resubmit an approval petition during the offset project's crediting period, except as provided in section 734(c)(4).
- "(e) APPEAL.—The Administrator shall establish procedures for appeal and review of determinations made under subsection (d).
- "(f) VOLUNTARY PREAPPROVAL REVIEW.— The Administrator may establish a voluntary preapproval review procedure, to allow an offset project developer to request the Administrator to conduct a preliminary eligibility review for an offset project. Findings of such reviews shall not be binding upon the Administrator. The voluntary preapproval review procedure—
- "(1) shall require the offset project developer to submit such basic project information as the Administrator requires to provide a meaningful review; and
- "(2) shall require a response from the Administrator not later than 6 weeks after receiving a request for review under this subsection.

"SEC. 736. VERIFICATION OF OFFSET PROJECTS.

- "(a) IN GENERAL.—As part of the regulations promulgated under section 732(a), the Administrator shall establish requirements, including protocols, for verification of the quantity of greenhouse gas emission reductions or avoidance, or sequestration of greenhouse gases, resulting from an offset project. The regulations shall require that an offset project developer shall submit a report, prepared by a third-party verifier accredited under subsection (d), providing such information as the Administrator requires to determine the quantity of greenhouse gas emission reductions or avoidance, or sequestration of greenhouse gases, resulting from the offset project.
- "(b) SCHEDULE.—The Administrator shall prescribe a schedule for the submission of verification reports under subsection (a).
- "(c) VERIFICATION REPORT REQUIRE-MENTS.—The Administrator shall specify the required components of a verification report required under subsection (a), which shall include—
- "(1) the name and contact information for a designated representative for the offset project developer;
- "(2) the quantity of greenhouse gases reduced, avoided, or sequestered;
- "(3) the methodologies applicable to the project pursuant to section 734:
- $\lq\lq(4)$ a certification that the project meets the applicable requirements;
- $\lq\lq(5)$ a certification establishing that the conflict of interest requirements in the regulations promulgated under subsection (d)(1) have been complied with; and
- "(6) any other information that the Administrator considers to be necessary to achieve the purposes of this part.
 - "(d) VERIFIER ACCREDITATION.—
- "(1) IN GENERAL.—As part of the regulations promulgated under section 732(a), the Administrator shall establish a process and requirements for periodic accreditation of third-party verifiers to ensure that such verifiers are professionally qualified and have no conflicts of interest.

"(2) STANDARDS.—

"(A) AMERICAN NATIONAL STANDARDS INSTI-ACCREDITATION.—The TUTE Administrator may accredit, or accept for purposes of accreditation under this subsection, verifiers accredited under the American National Standards Institute (ANSI) accreditation program in accordance with ISO 14065. The Administrator shall accredit, or accept for accreditation, verifiers under this subparagraph only if the Administrator finds that the American National Standards Institute accreditation program provides sufficient assurance that the requirements of this part will be met.

"(B) EPA ACCREDITATION.—As part of the regulations promulgated under section 732(a), the Administrator may establish accreditation standards for verifiers under this subsection, and may establish related training and testing programs and requirements.

"(3) PUBLIC ACCESSIBILITY.—Each verifier meeting the requirements for accreditation in accordance with this subsection shall be listed in a publicly accessible database, which shall be maintained and updated by the Administrator.

"SEC. 737. ISSUANCE OF OFFSET CREDITS.

- "(a) DETERMINATION AND NOTIFICATION.— Not later than 90 days after receiving a complete verification report under section 736, the Administrator shall—
- "(1) make the report publicly available;
- "(2) make a determination of the quantity of greenhouse gas emissions that have been reduced or avoided, or greenhouse gases that have been sequestered, by the offset project; and
- "(3) notify the offset project developer in writing of such determination and make such determination publicly available.
- "(b) ISSUANCE OF OFFSET CREDITS.—The Administrator shall issue one offset credit to an offset project developer for each ton of carbon dioxide equivalent that the Administrator has determined has been reduced, avoided, or sequestered during the period covered by a verification report submitted in accordance with section 736, only if—
- "(1) the Administrator has approved the offset project pursuant to section 735; and
- ``(2) the relevant emissions reduction, avoidance, or sequestration has—
- "(A) already occurred, during the offset project's crediting period; and
 - "(B) occurred after January 1, 2009.
- "(c) APPEAL.—The Administrator shall establish procedures for appeal and review of determinations made under subsection (a).
- "(d) TIMING.—Offset credits meeting the criteria established in subsection (b) shall be issued not later than 2 weeks following the verification determination made by the Administrator under subsection (a).
- "(e) REGISTRATION.—The Administrator shall assign a unique serial number to and register each offset credit to be issued in the Offset Registry established under section 732(d)

"SEC. 738. AUDITS.

"(a) IN GENERAL.—The Administrator shall, on an ongoing basis, conduct random audits of offset projects, offset credits, and practices of third-party verifiers. In each year, the Administrator shall conduct audits, at minimum, for a representative sample of project types and geographic areas.

"(b) DELEGATION.—The Administrator may delegate to a State or tribal government the responsibility for conducting audits under this section if the Administrator finds that the program proposed by the State or tribal government provides assurances equivalent to those provided by the auditing program of the Administrator, and that the integrity of the offset program under this part will be maintained. Nothing in this subsection shall

prevent the Administrator from conducting any audit the Administrator considers necessary and appropriate.

"SEC. 739. PROGRAM REVIEW AND REVISION.

"At least once every 5 years, the Administrator shall review and, based on new or updated information and taking into consideration the recommendations of the Advisory Board, update and revise—

- "(1) the list of eligible project types established under section 733:
- "(2) the methodologies established, including specific activity baselines, under section 734(a)."
- "(3) the reversal requirements and mechanisms established or prescribed under section 734(b):
- "(4) measures to improve the accountability of the offsets program; and
- "(5) any other requirements established under this part to ensure the environmental integrity and effective operation of this part. "SEC. 740. EARLY OFFSET SUPPLY.
- "(a) PROJECTS REGISTERED UNDER OTHER GOVERNMENT-RECOGNIZED PROGRAMS.—Except as provided in subsection (b) or (c), the Administrator shall issue one offset credit for each ton of carbon dioxide equivalent emissions reduced, avoided, or sequestered—
- "(1) under an offset project that was started after January 1, 2001;
- "(2) for which a credit was issued under any regulatory or voluntary greenhouse gas emission offset program that the Administrator determines—
- "(A) was established under State or tribal law or regulation prior to January 1, 2009, or has been approved by the Administrator pursuant to subsection (e):
- "(B) has developed offset project type standards, methodologies, and protocols through a public consultation process or a peer review process;
- "(C) has made available to the public standards, methodologies, and protocols that require that credited emission reductions, avoidance, or sequestration are permanent, additional, verifiable, and enforceable:
- "(D) requires that all emission reductions, avoidance, or sequestration be verified by a State or tribal regulatory agency or an accredited third-party independent verification body."
- "(E) requires that all credits issued are registered in a publicly accessible registry, with individual serial numbers assigned for each ton of carbon dioxide equivalent emission reductions, avoidance, or sequestration;
- "(F) ensures that no credits are issued for an activity if the entity administering the program, or a program administrator or representative, has funded, solicited, or served as a fund administrator for the development of the activity: and
- "(3) for which the credit described in paragraph (2) is transferred to the Administrator.
- "(b) INELIGIBLE CREDITS.—Subsection (a) shall not apply to offset credits that have expired or have been retired, canceled, or used for compliance under a program established under State or tribal law or regulation.
- "(c) LIMITATION.—Notwithstanding subsection (a)(1), offset credits shall be issued under this section—
- "(1) only for reductions or avoidance of greenhouse gas emissions, sequestration of greenhouse gases, or destruction of chlorofluorocarbons (subject to the conditions specified in section 619(b)(9) and based on the carbon dioxide equivalent value of the substance destroyed), that occur after January 1. 2009; and
- "(2) only until the date that is 3 years after the date of enactment of this title, or the date that regulations promulgated under section 732(a) take effect, whichever occurs sooner.

- "(d) RETIREMENT OF CREDITS.—The Administrator shall seek to ensure that offset credits described in subsection (a)(2) are retired for purposes of use under a program described in subsection (b).
- "(e) OTHER PROGRAMS.—(1) Offset programs that either—
- "(A) were not established under State or tribal law or regulation; or
- "(B) were not established prior to January 1, 2009.

but that otherwise meet all of the criteria of subsection (a)(2) may apply to the Administrator to be approved under this subsection as an eligible program for early offset credits under this section.

"(2) The Administrator shall approve any such program that the Administrator determines has criteria and methodologies of at least equal stringency to the criteria and methodologies of the programs established under State or tribal law or regulation that the Administrator determines meet the criteria of subsection (a)(2). The Administrator may approve types of offsets under any such program that are subject to criteria and methodologies of at least equal stringency to the criteria and methodologies for such types of offsets applied under the programs established under State or tribal law or regulation that the Administrator determines meet the criteria of subsection (a)(2). The Administrator shall make a determination on any application received under this section by no later than 180 days from the date of receipt of the application.

"SEC. 741. ENVIRONMENTAL CONSIDERATIONS.

- "If the Administrator lists forestry or other relevant land management-related offset projects as eligible offset project types under section 733, the Administrator, in consultation with appropriate Federal agencies, shall promulgate regulations for the selection and use of species in such offset projects—
- "(1) to ensure that native species are given primary consideration in such projects;
- "(2) to enhance biological diversity in such projects:
- "(3) to prohibit the use of federally designated or State-designated noxious weeds;
- "(4) to prohibit the use of a species listed by a regional or State invasive plant authority within the applicable region or State; and
- "(5) in the case of forestry offset projects, in accordance with widely accepted, environmentally sustainable forestry practices.

"SEC. 742. TRADING.

"Section 724 shall apply to the trading of offset credits.

"SEC. 743. INTERNATIONAL OFFSET CREDITS.

- "(a) IN GENERAL.—The Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development, may issue, in accordance with this section, international offset credits based on activities that reduce or avoid greenhouse gas emissions, or increase sequestration of greenhouse gases, in a developing country. Such credits may be issued for projects eligible under section 733 or as provided in subsection (c), (d), or (e) of this section.
 - "(b) ISSUANCE.—
- "(1) REGULATIONS.—Not later than 2 years after the date of enactment of this title, the Administrator, in consultation with the Secretary of State, the Administrator of the United States Agency for International Development, and any other appropriate Federal agency, and taking into consideration the recommendations of the Advisory Board, shall promulgate regulations for implementing this section. Except as otherwise provided in this section, the issuance of

international offset credits under this section shall be subject to the requirements of this part.

"(2) REQUIREMENTS FOR INTERNATIONAL OFF-SET CREDITS.—The Administrator may issue international offset credits only if—

"(A) the United States is a party to a bilateral or multilateral agreement or arrangement that includes the country in which the project or measure achieving the relevant greenhouse gas emission reduction or avoidance, or greenhouse gas sequestration, has occurred:

"(B) such country is a developing country; and

"(C) such agreement or arrangement-

"(i) ensures that the requirements of this part apply to the issuance of international offset credits under this section; and

"(ii) provides for the appropriate distribution of international offset credits issued.

"(c) SECTOR-BASED CREDITS.-

"(1) IN GENERAL.—In order to minimize the potential for leakage and to encourage countries to take nationally appropriate mitigation actions to reduce or avoid greenhouse gas emissions, or sequester greenhouse gases, the Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development. shall—

"(A) identify sectors of specific countries with respect to which the issuance of international offset credits on a sectoral basis is appropriate; and

"(B) issue international offset credits for such sectors only on a sectoral basis.

"(2) IDENTIFICATION OF SECTORS.—

"(A) GENERAL RULE.—For purposes of paragraph (1)(A), a sectoral basis shall be appropriate for activities—

"(i) in countries that have comparatively high greenhouse gas emissions, or comparatively greater levels of economic development; and

"(ii) that, if located in the United States, would be within a sector subject to the compliance obligation under section 722.

"(B) FACTORS.—In determining the sectors and countries for which international offset credits should be awarded only on a sectoral basis, the Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development, shall consider the following factors:

"(i) The country's gross domestic product.
"(ii) The country's total greenhouse gas emissions.

"(iii) Whether the comparable sector of the United States economy is covered by the compliance obligation under section 722.

"(iv) The heterogeneity or homogeneity of sources within the relevant sector.

"(v) Whether the relevant sector provides products or services that are sold in internationally competitive markets.

"(vi) The risk of leakage if international offset credits were issued on a project-level basis, instead of on a sectoral basis, for activities within the relevant sector.

"(vii) The capability of accurately measuring, monitoring, reporting, and verifying the performance of sources across the relevant sector.

"(viii) Such other factors as the Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development, determines are appropriate to—

"(I) ensure the integrity of the United States greenhouse gas emissions cap established under section 703; and

"(II) encourage countries to take nationally appropriate mitigation actions to reduce or avoid greenhouse gas emissions, or sequester greenhouse gases.

"(3) SECTORAL BASIS.—

"(A) DEFINITION.—In this subsection, the term 'sectoral basis' means the issuance of international offset credits only for the quantity of sector-wide reductions or avoidance of greenhouse gas emissions, or sector-wide increases in sequestration of greenhouse gases, achieved across the relevant sector of the economy relative to a domestically enforceable baseline level of absolute emissions established in an agreement or arrangement described in subsection (b)(2)(A) for the sector.

"(B) BASELINE.—The baseline for a sector shall be established on an absolute basis and at levels of greenhouse gas emissions consistent with the thresholds identified in section 705(e)(2) and lower than would occur under a business-as-usual scenario taking into account relevant domestic or international policies or incentives to reduce greenhouse gas emissions, among other factors, and additionality and performance shall be determined on the basis of such baseline.

"(d) Credits Issued by an International Body.—

"(1) IN GENERAL.—The Administrator, in consultation with the Secretary of State, may issue international offset credits in exchange for instruments in the nature of offset credits that are issued by an international body established pursuant to the United Nations Framework Convention on Climate Change, to a protocol to such Convention, or to a treaty that succeeds such Convention. The Administrator may issue international offset credits under this subsection only if, in addition to the requirements of subsection (b), the Administrator has determined that the international body that issued the instruments has implemented substantive and procedural requirements for the relevant project type that provide equal or greater assurance of the integrity of such instruments as is provided by the requirements of this part. Starting January 1, 2016, the Administrator shall issue no offset credit pursuant to this subsection if the activity generating the greenhouse gas emissions reductions or avoidance, or greenhouse gas sequestration, occurs in a country and sector identified by the Administrator under subsection (c).

"(2) RETIREMENT.—The Administrator, in consultation with the Secretary of State, shall seek, by whatever means appropriate, including agreements, arrangements, or technical cooperation with the international issuing body described in paragraph (1), to ensure that such body—

"(A) is notified of the Administrator's issuance, under this subsection, of an international offset credit in exchange for an instrument issued by such international body; and

"(B) provides, to the extent feasible, for the disqualification of the instrument issued by such international body for subsequent use under any relevant foreign or international greenhouse gas regulatory program, regardless of whether such use is a sale, exchange, or submission to satisfy a compliance obligation.

 $\lq\lq(\mathbf{e})$ Offsets From Reduced Deforest-Ation.—

"(1) REQUIREMENTS.—The Administrator, in accordance with the regulations promulgated under subsection (b)(1) and an agreement or arrangement described in subsection (b)(2)(A), shall issue international offset credits for greenhouse gas emission reductions achieved through activities to reduce deforestation only if, in addition to the requirements of subsection (b)—

"(A) the activity occurs in-

"(i) a country listed by the Administrator pursuant to paragraph (2);

"(ii) a state or province listed by the Administrator pursuant to paragraph (5); or

"(iii) a country listed by the Administrator pursuant to paragraph (6);

"(B) except as provided in paragraph (5) or (6), the quantity of the international offset credits is determined by comparing the national emissions from deforestation relative to a national deforestation baseline for that country established, in accordance with an agreement or arrangement described in subsection (b)(2)(A), pursuant to paragraph (4);

"(C) the reduction in emissions from deforestation has occurred before the issuance of the international offset credit and, taking into consideration relevant international standards, has been demonstrated using ground-based inventories, remote sensing technology, and other methodologies to ensure that all relevant carbon stocks are accounted;

"(D) the Administrator has made appropriate adjustments, such as discounting for any additional uncertainty, to account for circumstances specific to the country, including its technical capacity described in paragraph (2)(A):

"(E) the activity is designed, carried out, and managed—

"(i) in accordance with widely accepted, environmentally sustainable forest management practices:

"(ii) to promote or restore native forest species and ecosystems where practicable, and to avoid the introduction of invasive nonnative species:

"(iii) in a manner that gives due regard to the rights and interests of local communities, indigenous peoples, forest-dependent communities, and vulnerable social groups;

"(iv) with consultations with, and full participation of, local communities, indigenous peoples, and forest-dependent communities, in affected areas, as partners and primary stakeholders, prior to and during the design, planning, implementation, and monitoring and evaluation of activities; and

"(v) with equitable sharing of profits and benefits derived from offset credits with local communities, indigenous peoples, and forest-dependent communities; and

"(F) the reduction otherwise satisfies and is consistent with any relevant requirements established by an agreement reached under the auspices of the United Nations Framework Convention on Climate Change.

"(2) ELIGIBLE COUNTRIES.—The Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development, and in accordance with an agreement or arrangement described in subsection (b)(2)(A), shall establish, and periodically review and update, a list of the developing countries that have the capacity to participate in deforestation reduction activities at a national level, including—

"(A) the technical capacity to monitor, measure, report, and verify forest carbon fluxes for all significant sources of greenhouse gas emissions from deforestation with an acceptable level of uncertainty, as determined taking into account relevant internationally accepted methodologies, such as those established by the Intergovernmental Panel on Climate Change;

"(B) the institutional capacity to reduce emissions from deforestation, including strong forest governance and mechanisms to equitably distribute deforestation resources for local actions; and

 $\mbox{``(C)}$ a land use or forest sector strategic plan that—

"(i) assesses national and local drivers of deforestation and forest degradation and identifies reforms to national policies needed to address them;

- "(ii) estimates the country's emissions from deforestation and forest degradation;
- "(iii) identifies improvements in data collection, monitoring, and institutional capacity necessary to implement a national deforestation reduction program; and
- "(iv) establishes a timeline for implementing the program and transitioning to low-emissions development with respect to emissions from forest and land use activities.
- "(3) PROTECTION OF INTERESTS.—With respect to an agreement or arrangement described in subsection (b)(2)(A) that addresses international offset credits under this subsection, the Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development, shall seek to ensure the establishment and enforcement by such country of legal regimes, processes, standards, and safeguards that—
- "(A) give due regard to the rights and interests of local communities, indigenous peoples, forest-dependent communities, and vulnerable social groups;
- "(B) promote consultations with, and full participation of, forest-dependent communities and indigenous peoples in affected areas, as partners and primary stakeholders, prior to and during the design, planning, implementation, and monitoring and evaluation of activities; and
- "(C) encourage equitable sharing of profits and benefits derived from international offset credits with local communities, indigenous peoples, and forest-dependent communities
- "(4) NATIONAL DEFORESTATION BASELINE.—A national deforestation baseline established under this subsection shall—
 - "(A) be national in scope;
- "(B) be consistent with nationally appropriate mitigation commitments or actions with respect to deforestation, taking into consideration the average annual historical deforestation rates of the country during a period of at least 5 years, the applicable drivers of deforestation, and other factors to ensure additionality:
- "(C) establish a trajectory that would result in zero net deforestation by not later than 20 years after the national deforestation baseline has been established:
- "(D) be adjusted over time to take account of changing national circumstances;
- "(E) be designed to account for all significant sources of greenhouse gas emissions from deforestation in the country; and
- "(F) be consistent with the national deforestation baseline, if any, established for such country under section 754(d)(1) and (2).
- "(5) STATE-LEVEL OR PROVINCE-LEVEL ACTIVITIES.—
- "(A) ELIGIBLE STATES OR PROVINCES.—The Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development, shall establish within 2 years after the date of enactment of this title, and periodically review and update, a list of states or provinces in developing countries where—
- "(i) the developing country is not included on the list of countries established pursuant to paragraph (6)(A);
- "(ii) the state or province by itself is a major emitter of greenhouse gases from tropical deforestation on a scale commensurate to the emissions of other countries; and
- "(iii) the state or province meets the eligibility criteria in paragraphs (2) and (3) for the geographic area under its jurisdiction.
- "(B) ACTIVITIES.—The Administrator may issue international offset credits for greenhouse gas emission reductions achieved through activities to reduce deforestation at a state or provincial level that meet the requirements of this section. Such credits shall

- be determined by comparing the emissions from deforestation within that state or province relative to the state or province deforestation baseline for that state or province established, in accordance with an agreement or arrangement described in subsection (b)(2)(A), pursuant to subparagraph (C) of this paragraph.
- "(C) STATE OR PROVINCE DEFORESTATION BASELINE.—A state or province deforestation baseline shall—
- "(i) be consistent with any existing nationally appropriate mitigation commitments or actions for the country in which the activity is occurring, taking into consideration the average annual historical deforestation rates of the state or province during a period of at least 5 years, relevant drivers of deforestation, and other factors to ensure additionality:
- "(ii) establish a trajectory that would result in zero net deforestation by not later than 20 years after the state or province deforestation baseline has been established; and
- "(iii) be designed to account for all significant sources of greenhouse gas emissions from deforestation in the state or province and adjusted to fully account for emissions leakage outside the state or province.
- "(D) PHASE OUT.—Beginning 5 years after the first calendar year for which a covered entity must demonstrate compliance with section 722(a), the Administrator shall issue no further international offset credits for eligible state-level or province-level activities to reduce deforestation pursuant to this paragraph.
- "(6) PROJECTS AND PROGRAMS TO REDUCE DEFORESTATION.—
- "(A) ELIGIBLE COUNTRIES.—The Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development, shall establish within 2 years after the date of enactment of this title, and periodically review and update, a list of developing countries each of which—
- "(i) the Administrator determines, based on recent, credible, and reliable emissions data, accounts for less than 1 percent of global greenhouse gas emissions and less than 3 percent of global forest-sector and land use change greenhouse gas emissions; and
- "(ii) has, or in the determination of the Administrator is making a good faith effort to develop, a land use or forest sector strategic plan that meets the criteria described in paragraph (2)(C).
- "(B) ACTIVITIES.—The Administrator may issue international offset credits for green-house gas emission reductions achieved through project or program level activities to reduce deforestation in countries listed under subparagraph (A) that meet the requirements of this section. The quantity of international offset credits shall be determined by comparing the project-level or program-level emissions from deforestation to a deforestation baseline for such project or program established pursuant to subparagraph (C).
- "(C) PROJECT-LEVEL OR PROGRAM-LEVEL BASELINE.—A project-level or program-level deforestation baseline shall—
- "(i) be consistent with any existing nationally appropriate mitigation commitments or actions for the country in which the project or program is occurring, taking into consideration the average annual historical deforestation rates relevant to the specific project or program during a period of at least 5 years, applicable drivers of deforestation, and other factors to ensure additionality:
- "(ii) be designed to account for all significant sources of greenhouse gas emissions

- from deforestation in the project or program boundary; and
- "(iii) be adjusted to fully account for emissions leakage outside the project or program boundary.
- "(D) Phase out.—(i) Beginning 5 years after the first calendar year for which a covered entity must demonstrate compliance with section 722(a), the Administrator shall issue no further international offset credits for project-level or program-level activities pursuant to this paragraph, except as provided in clause (ii).
- "(ii) The Administrator may extend the phase out deadline for the issuance of international offset credits under this paragraph by up to 8 years with respect to eligible activities taking place in a least developed country, which for purposes of this paragraph is defined as a foreign country that the United Nations has identified as among the least developed of developing countries at the time that the Administrator determines to provide an extension, if the Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development, determines the country—
- "(I) lacks sufficient capacity to adopt and implement effective programs to achieve reductions in deforestation measured against national baselines;
- "(II) is receiving support under part E to develop such capacity; and
- "(III) has developed and is working to implement a credible national strategy or plan to reduce deforestation.
- "(7) DEFORESTATION.—In implementing this subsection, the Administrator, taking into consideration the recommendations of the Advisory Board, may include forest degradation, or soil carbon losses associated with forested wetlands or peatlands, within the meaning of deforestation.
- "(8) Consultation.—In implementing this subsection, the Administrator shall consult with the Secretary of Agriculture on relevant matters within such Secretary's area of expertise.
- "(f) Modification of Requirements.promulgating regulations under subsection (b)(1) with respect to the issuance of international offset credits under subsection (c), (d), or (e), the Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development, may modify or omit a requirement of this part (excluding the requirements of this section) if the Administrator determines that the application of that requirement to such subsection is not feasible. In modifying or omitting such a requirement on the basis of infeasibility, the Administrator, in consultation with the Secretary of State and the Administrator of the United States Agency for International Development, shall ensure, with an adequate margin of safety, the integrity of international offset credits issued under this section and of the greenhouse gas emissions cap established pursuant to section 703
- (g) AVOIDING DOUBLE COUNTING.--The Administrator, in consultation with the Secretary of State, shall seek, by whatever means appropriate, including agreements, arrangements, or technical cooperation, to ensure that activities on the basis of which international offset credits are issued under this section are not used for compliance with an obligation to reduce or avoid greenhouse gas emissions, or increase greenhouse gas sequestration, under a foreign or international regulatory system. In addition, no international offset credits shall be issued for emission reductions from activities with respect to which emission allowances were allocated under section 781 for distribution under part E.

"(h) LIMITATION.—The Administrator shall not issue international offset credits generated by projects based on the destruction of hydrofluorocarbons.

"PART E—SUPPLEMENTAL EMISSIONS REDUCTIONS FROM REDUCED DEFORESTATION

"SEC. 751. DEFINITIONS.

"In this part:

"(1) LEAKAGE PREVENTION ACTIVITIES.—The term 'leakage prevention activities' means activities in developing countries that are directed at preserving existing forest carbon stocks, including forested wetlands and peatlands, that might, absent such activities, be lost through leakage.

"(2) NATIONAL DEFORESTATION REDUCTION ACTIVITIES.—The term 'national deforestation reduction activities' means activities in developing countries that reduce a quantity of greenhouse gas emissions from deforestation that is calculated by measuring actual emissions against a national deforestation baseline established pursuant to section 754(d)(1) and (2).

"(3) SUBNATIONAL DEFORESTATION REDUC-TION ACTIVITIES.—The term 'subnational deforestation reduction activities' means activities in developing countries that reduce a quantity of greenhouse gas emissions from deforestation that are calculated by measuring actual emissions using an appropriate baseline established by the Administrator that is less than national in scope.

"(4) SUPPLEMENTAL EMISSIONS REDUC-TIONS.—The term 'supplemental emissions reductions' means greenhouse gas emissions reductions achieved from reduced or avoided deforestation under this part.

"(5) USAID.—The term 'USAID' means the United States Agency for International Development.

"SEC. 752. FINDINGS.

"Congress finds that-

"(1) as part of a global effort to mitigate climate change, it is in the national interest of the United States to assist developing countries to reduce and ultimately halt emissions from deforestation;

"(2) deforestation is one of the largest sources of greenhouse gas emissions in developing countries, amounting to roughly 20 percent of overall emissions globally;

"(3) recent scientific analysis shows that it will be substantially more difficult to limit the increase in global temperatures to less than 2 degrees centigrade above preindustrial levels without reducing and ultimately halting net emissions from deforestation;

"(4) reducing emissions from deforestation is highly cost-effective, compared to many other sources of emissions reductions:

"(5) in addition to contributing significantly to worldwide efforts to address global warming, assistance under this part will generate significant environmental and social cobenefits, including protection of biodiversity, ecosystem services, and forest-related livelihoods; and

"(6) under the Bali Action Plan, developed country parties to the United Nations Framework Convention on Climate Change, including the United States, committed to 'enhanced action on the provision of financial resources and investment to support action on mitigation and adaptation and technology cooperation,' including, inter alia, consideration of 'improved access to adequate, predictable, and sustainable financial resources and financial and technical support, and the provision of new and additional resources, including official and concessional funding for developing country parties'.

"SEC. 753. SUPPLEMENTAL EMISSIONS REDUC-TIONS THROUGH REDUCED DEFOR-ESTATION.

"(a) REGULATIONS.—Not later than 2 years after the date of enactment of this title, the Administrator, in consultation with the Administrator of USAID and any other appropriate agencies, shall promulgate regulations establishing a program to use emission allowances set aside for this purpose under section 781 to reduce greenhouse gas emissions from deforestation in developing countries in accordance with the requirements of this part.

"(b) OBJECTIVES.—The objectives of the program established under this section shall be to—

"(1) achieve supplemental emissions reductions of at least 720,000,000 tons of carbon dioxide equivalent in 2020, a cumulative amount of at least 6,000,000,000 tons of carbon dioxide equivalent by December 31, 2025, and additional supplemental emissions reductions in subsequent years;

"(2) build capacity to reduce deforestation in developing countries experiencing deforestation, including preparing developing countries to participate in international markets for international offset credits for reduced emissions from deforestation; and

"(3) preserve existing forest carbon stocks in countries where such forest carbon may be vulnerable to international leakage, particularly in developing countries with largely intact native forests.

"SEC. 754. REQUIREMENTS FOR INTERNATIONAL DEFORESTATION REDUCTION PROGRAM.

"(a) ELIGIBLE COUNTRIES.—The Administrator may support activities under this part only with respect to a developing country that—

"(1) the Administrator, in consultation with the Administrator of USAID, determines is experiencing deforestation or forest degradation or has standing forest carbon stocks that may be at risk of deforestation or degradation; and

"(2) has entered into a bilateral or multilateral agreement or arrangement with the United States establishing the conditions of its participation in the program established under this part, which shall include an agreement to meet the standards established under subsection (d) for the activities to which those standards apply.

"(b) ACTIVITIES.—

"(1) AUTHORIZED ACTIVITIES.—Subject to the requirements of this part, the Administrator, in consultation with the Administrator of USAID, may support activities to achieve the objectives identified in section 753(b), including—

"(A) national deforestation reduction activities:

"(B) subnational deforestation reduction activities, including pilot activities that reduce greenhouse gas emissions but are subject to significant uncertainty;

"(C) activities to measure, monitor, and verify deforestation, avoided deforestation, and deforestation rates:

"(D) leakage prevention activities;

"(E) development of measurement, monitoring, and verification capacities to enable a country to quantify supplemental emissions reductions and to generate for sale offset credits from reduced or avoided deforestation:

"(F) development of governance structures to reduce deforestation and illegal logging;

"(G) enforcement of requirements for reduced deforestation or forest conservation;

"(H) efforts to combat illegal logging and increase enforcement cooperation;

"(I) providing incentives for policy reforms to achieve the objectives identified in section 753(b); and

"(J) monitoring and evaluation of the results of the activities conducted under this section.

"(2) ACTIVITIES SELECTED BY USAID.-

"(A) The Administrator of USAID, in consultation with the Administrator, may select for support and implementation pursuant to subsection (c) any of the activities described in paragraph (1), consistent with this part and the regulations promulgated under subsection (d), and subject to the requirement to achieve the objectives listed in section 753(b)(1).

"(B) With respect to the activities listed in subparagraphs (D) through (J) of paragraph (1), the Administrator of USAID, in consultation with the Administrator, shall have primary but not exclusive responsibility for selecting the activities to be supported and implemented.

"(3) INTERAGENCY COORDINATION.—The Administrator and the Administrator of USAID shall jointly develop and biennially update a strategic plan for meeting the objectives listed in section 753(b) and shall execute a memorandum of understanding delineating the agencies' respective roles in implementing this part.

"(c) Mechanisms.—

"(1) IN GENERAL.—The Administrator may support activities to achieve the objectives identified in section 753(b) by—

"(A) developing and implementing programs and projects that achieve such objectives; and

"(B) distributing emission allowances to a country that is eligible under subsection (a), to a private or public group (including international organizations), or to an international fund established by an international agreement to which the United States is a party, to carry out activities to achieve such objectives.

"(2) USAID ACTIVITIES.—With respect to activities selected and implemented by the Administrator of USAID pursuant to subsection (b)(2), the Administrator shall distribute emission allowances as provided in paragraph (1) of this subsection based upon the direction of the Administrator of USAID, subject to the availability of allowances for such activities.

"(3) IMPLEMENTATION THROUGH INTERNATIONAL ORGANIZATIONS.—If support is distributed through an international organization, the agency responsible for selecting activities in accordance with subsection (b)(1) or (2), in consultation with the Secretary of State, shall ensure the establishment and implementation of adequate mechanisms to apply and enforce the eligibility requirements and other requirements of this section.

"(4) ROLE OF THE SECRETARY OF STATE.— The Administrator may not distribute emission allowances under this part to the government of another country or to an international organization or international fund unless the Secretary of State has concurred with such distribution.

"(d) STANDARDS.—The Administrator, in consultation with the Administrator of USAID, shall promulgate regulations establishing standards to ensure that supplemental emissions reductions achieved through supported activities are additional, measurable, verifiable, permanent, and monitored, and account for leakage and uncertainty. In addition, such standards shall—

"(1) require the establishment of a national deforestation baseline for each country with national deforestation reduction activities that is used to account for reductions achieved from such activities;

"(2) provide that a national deforestation baseline established under paragraph (1) shall—

"(A) be national in scope;

- "(B) be consistent with nationally appropriate mitigation commitments or actions with respect to deforestation, taking into consideration the average annual historical deforestation rates of the country during a period of at least 5 years, the applicable drivers of deforestation, and other factors to ensure additionality;
- "(C) establish a trajectory that would result in zero net deforestation by not later than 20 years from the date the baseline is established:
- "(D) be adjusted over time to take account of changing national circumstances;
- "(E) be designed to account for all significant sources of greenhouse gas emissions from deforestation in the country; and
- "(F) be consistent with the national deforestation baseline, if any, established for such country under section 743(e)(4);
- "(3) with respect to support provided pursuant to subsection (b)(1)(A) or (B), require supplemental emissions reductions to be achieved and verified prior to compensation through the distribution of emission allowances under this part:
- "(4) with respect to accounting for subnational deforestation reduction activities that lack the standardized or precise measurement and monitoring techniques needed for a full accounting of changes in emissions or baselines, or are subject to other sources of uncertainty, apply a conservative discount factor to reflect the uncertainty regarding the levels of reductions achieved;
- "(5) ensure that activities under this part shall be designed, carried out, and managed—
- "(A) in accordance with widely accepted, environmentally sustainable forest management practices;
- "(B) to promote or restore native forest species and ecosystems where practicable, and to avoid the introduction of invasive nonnative species;
- "(C) in a manner that gives due regard to the rights and interests of local communities, indigenous peoples, forest-dependent communities, and vulnerable social groups;
- "(D) with consultations with, and full participation of, local communities, indigenous peoples, and forest-dependent communities in affected areas, as partners and primary stakeholders, prior to and during the design, planning, implementation, and monitoring and evaluation of activities; and
- "(E) with equitable sharing of profits and benefits derived from the activities with local communities, indigenous peoples, and forest-dependent communities; and
- "(6) with respect to support for all activities under this part, seek to ensure the establishment and enforcement, by the country in which the activities occur, of legal regimes, standards, processes, and safeguards that—
- "(A) give due regard to the rights and interests of local communities, indigenous peoples, forest-dependent communities, and vulnerable social groups;
- "(B) promote consultations with local communities and indigenous peoples and forest-dependent communities in affected areas, as partners and primary stakeholders, prior to and during the design, planning, implementation, monitoring, and evaluation of activities under this part; and
- "(C) encourage equitable sharing of profits and benefits from incentives for emissions reductions or leakage prevention with local communities, indigenous peoples, and forestdependent communities.
- "(e) Scope.—(1) The Administrator shall include within the scope of activities under this part reduced emissions from forest degradation.
- "(2) The Administrator, in consultation with the Administrator of USAID, may de-

- cide, taking into account any advice from the Advisory Board, to expand, where appropriate, the scope of activities under this part to include reduced soil carbon-derived emissions associated with deforestation and degradation of forested wetlands and peatlands.
- "(f) ACCOUNTING.—The Administrator shall establish a publicly accessible registry of the supplemental emissions reductions achieved through support provided under this part each year, after appropriately discounting for uncertainty and other relevant factors as required by the standards established under subsection (d).
- "(g) Transition to National Reductions.—Beginning 5 years after the date that a country entered into the agreement or arrangement required under subsection (a)(2), the Administrator shall provide no further compensation through emission allowances to that country under this part for any subnational deforestation reduction activities, except that the Administrator may extend this period by an additional 5 years if the Administrator, in consultation with the Administrator of USAID, determines that—
- "(1) the country is making substantial progress towards adopting and implementing a program to achieve reductions in deforestation measured against a national baseline;
- "(2) the greenhouse gas emissions reductions achieved are not resulting in significant leakage; and
- "(3) the greenhouse gas emissions reductions achieved are being appropriately discounted to account for any leakage that is occurring.

The limitation under this subsection shall not apply to support for activities to further the objectives listed in section 753(b)(2) or (3)

- "(h) COORDINATION WITH U.S. FOREIGN AS-SISTANCE.—Subject to the direction of the President, the Administrator and the Administrator of USAID shall, to the extent practicable and consistent with the objectives of this program, seek to align activities under this section with broader development, poverty alleviation, or natural resource management objectives and initiatives in the recipient country.
- "(i) SUPPORT AS SUPPLEMENT.—The provision of support for activities under this part shall be used to supplement, and not to supplant, any other Federal, State, or local support available to carry out such qualifying activities under this part.
- "(j) NOT ELIGIBLE FOR OFFSET CREDIT.—Activities that receive support under this part shall not be issued offset credits for the greenhouse gas emissions reductions or avoidance, or greenhouse gas sequestration, produced by such activities.

"SEC. 755. REPORTS AND REVIEWS.

- "(a) REPORTS.—Not later than January 1, 2014, and annually thereafter, the Administrator and the Administrator of USAID shall submit to the Committee on Energy and Commerce and the Committee on Foreign Affairs of the House of Representatives, and the Committee on Environment and Public Works and the Committee on Foreign Relations of the Senate, and make available to the public, a report on the support provided under this part during the prior fiscal year. The report shall include—
- "(1) a statement of the quantity of supplemental emissions reductions for which compensation in the form of emission allowances was provided under this part during the prior fiscal year, as registered by the Administrator under section 754(f); and
- "(2) a description of the national and subnational deforestation reduction activities, capacity-building activities, and leakage prevention activities supported under this part, including a statement of the quantity

of emission allowances distributed to each recipient for each activity during the prior fiscal year, and a description of what was accomplished through each of the activities.

- "(b) REVIEWS.—Not later than 4 years after the date of enactment of this title and every 5 years thereafter, the Administrator and the Administrator of USAID, taking into consideration any evaluation by or recommendations from the Advisory Board established under section 731, shall conduct a review of the activities undertaken pursuant to this part and make any appropriate changes in the program established under this part, consistent with the requirements of this part, based on the findings of the review. The review shall include the effects of the activities on—
- "(1) total documented carbon stocks of each country that directly or indirectly received support under this part compared with such country's national deforestation baseline established under section 754(d)(1) and (2):
- "(2) the number of countries with the capacity to generate for sale instruments in the nature of offset credits from forest-related activities, and the amount of such activities;
- "(3) forest governance in each country that directly or indirectly received support under this part;
- "(4) indigenous peoples and forest-dependent communities residing in areas affected by such activities;
- "(5) biodiversity and ecosystem services within forested areas associated with the activities;
- $\lq\lq(6)$ subnational and international leakage; and
- "(7) any program or mechanism established under the United Nations Framework Convention on Climate Change related to greenhouse gas emissions from deforestation.

"SEC. 756. LEGAL EFFECT OF PART.

- "(1) IN GENERAL.—Nothing in this part supersedes, limits, or otherwise affects any restriction imposed by Federal law (including regulations) on any interaction between an entity located in the United States and an entity located in a foreign country.
- "(2) ROLE OF THE SECRETARY OF STATE.— Nothing in this part shall be construed as affecting the role of the Secretary of State or the responsibilities of the Secretary under section 622(c) of the Foreign Assistance Act of 1961."

SEC. 312. DEFINITIONS.

Title VII of the Clean Air Act, as added by section 311 of this Act, is amended by inserting before part A the following new section: "SEC. 700. DEFINITIONS.

- "In this title:
- "(1) ADDITIONAL.—The term 'additional', when used with respect to reductions or avoidance of greenhouse gas emissions, or to sequestration of greenhouse gases, means reductions, avoidance, or sequestration that result in a lower level of net greenhouse gas emissions or atmospheric concentrations than would occur in the absence of an offset project.
- "(2) ADDITIONALITY.—The term 'additionality' means the extent to which reductions or avoidance of greenhouse gas emissions, or sequestration of greenhouse gases, are additional.
- "(3) ADVISORY BOARD.—The term 'Advisory Board' means the Offsets Integrity Advisory Board established under section 731.
- "(4) Affiliated.—The term 'affiliated'—
- "(A) when used in relation to an entity means owned or controlled by, or under common ownership or control with, another entity, as determined by the Administrator; and
- "(B) when used in relation to a natural gas local distribution company, means owned or

controlled by, or under common ownership or control with, another natural gas local distribution company, as determined by the Administrator.

- "(5) ALLOWANCE.—The term 'allowance' means a limited authorization to emit, or have attributable greenhouse gas emissions in an amount of, 1 ton of carbon dioxide equivalent of a greenhouse gas in accordance with this title. Such term includes an emission allowance, a compensatory allowance, and an international emission allowance, but does not include an international reserve allowance established under section 766.
- "(6) ATTRIBUTABLE GREENHOUSE GAS EMISSIONS.—The term 'attributable greenhouse gas emissions', for a given calendar year, means—
- "(A) for a covered entity that is a fuel producer or importer described in paragraph (13)(B), greenhouse gases that would be emitted from the combustion of any petroleum-based or coal-based liquid fuel, petroleum coke, or natural gas liquid, produced or imported by that covered entity during that calendar year for sale or distribution in interstate commerce, assuming no capture and sequestration of any greenhouse gas emissions:
- "(B) for a covered entity that is an industrial gas producer or importer described in paragraph (13)(C), the tons of carbon dioxide equivalent of any gas described in clauses (i) through (vi) of paragraph (13)(C)—
- "(i) produced or imported by such covered entity during that calendar year for sale or distribution in interstate commerce; or
- "(ii) released as fugitive emissions in the production of fluorinated gas; and
- "(C) for a natural gas local distribution company described in paragraph (13)(J), greenhouse gases that would be emitted from the combustion of the natural gas, and any other gas meeting the specifications for commingling with natural gas for purposes of delivery, that such entity delivered during that calendar year to customers that are not covered entities, assuming no capture and sequestration of that greenhouse gas.
- "(7) BIOLOGICAL SEQUESTRATION; BIOLOGICALLY SEQUESTREED.—The terms 'biological sequestration' and 'biologically sequestered' mean the removal of greenhouse gases from the atmosphere by terrestrial biological means, such as by growing plants, and the storage of those greenhouse gases in plants or soils.
- "(8) CAPPED EMISSIONS.—The term 'capped emissions' means greenhouse gas emissions to which section 722 applies, including emissions from the combustion of natural gas, petroleum-based or coal-based liquid fuel, petroleum coke, or natural gas liquid to which section 722(b)(2) or (8) applies.
- "(9) CAPPED SOURCE.—The term 'capped source' means a source that directly emits capped emissions.
- "(10) CARBON DIOXIDE EQUIVALENT.—The term 'carbon dioxide equivalent' means the unit of measure, expressed in metric tons, of greenhouse gases as provided under section 711 or 712.
- "(11) CARBON STOCK.—The term 'carbon stock' means the quantity of carbon contained in a biological reservoir or system which has the capacity to accumulate or release carbon.
- "(12) COMPENSATORY ALLOWANCE.—The term 'compensatory allowance' means an allowance issued under section 721(f).
- "(13) COVERED ENTITY.—The term 'covered entity' means each of the following:
 - "(A) Any electricity source.
- "(B) Any stationary source that produces, and any entity that (or any group of two or more affiliated entities that, in the aggregate) imports, for sale or distribution in interstate commerce in 2008 or any subse-

- quent year, petroleum-based or coal-based liquid fuel, petroleum coke, or natural gas liquid, the combustion of which would emit 25,000 or more tons of carbon dioxide equivalent, as determined by the Administrator.
- "(C) Any stationary source that produces, and any entity that (or any group of two or more affiliated entities that, in the aggregate) imports, for sale or distribution in interstate commerce, in bulk, or in products designated by the Administrator, in 2008 or any subsequent year 25,000 or more tons of carbon dioxide equivalent of—
 - "(i) fossil fuel-based carbon dioxide;
 - "(ii) nitrous oxide;
 - "(iii) perfluorocarbons;
 - "(iv) sulfur hexafluoride;
- "(v) any other fluorinated gas, except for nitrogen trifluoride, that is a greenhouse gas, as designated by the Administrator under section 711: or
- "(vi) any combination of greenhouse gases described in clauses (i) through (v).
- "(D) Any stationary source that has emitted 25,000 or more tons of carbon dioxide equivalent of nitrogen trifluoride in 2008 or any subsequent year.
 - "(E) Any geologic sequestration site.
- "(F) Any stationary source in the following industrial sectors:
 - "(i) Adipic acid production.
 - "(ii) Primary aluminum production.
 - "(iii) Ammonia manufacturing.
- "(iv) Cement production, excluding grinding-only operations.
 - "(v) Hydrochlorofluorocarbon production.
- "(vi) Lime manufacturing.
- "(vii) Nitric acid production.
- "(viii) Petroleum refining.
- "(ix) Phosphoric acid production.
- "(x) Silicon carbide production.
- "(xi) Soda ash production.
- "(xii) Titanium dioxide production.
- "(xiii) Coal-based liquid or gaseous fuel production.
- "(G) Any stationary source in the chemical or petrochemical sector that, in 2008 or any subsequent year—
- "(i) produces acrylonitrile, carbon black, ethylene, ethylene dichloride, ethylene oxide, or methanol; or
- "(ii) produces a chemical or petrochemical product if producing that product results in annual combustion plus process emissions of 25,000 or more tons of carbon dioxide equivalent.
 - "(H) Any stationary source that—
- "(i) is in one of the following industrial sectors: ethanol production; ferroalloy production; fluorinated gas production; food processing; glass production; hydrogen production; iron and steel production; lead production; pulp and paper manufacturing; and zinc production; and
- "(ii) has emitted 25,000 or more tons of carbon dioxide equivalent in 2008 or any subsequent year.
- "(I) Any fossil fuel-fired combustion device (such as a boiler) or grouping of such devices that—
- "(i) is all or part of an industrial source not specified in subparagraph (D), (F), (G), or (H); and
- "(ii) has emitted 25,000 or more tons of carbon dioxide equivalent in 2008 or any subsequent year.
- "(J) Any natural gas local distribution company that (or any group of 2 or more affiliated natural gas local distribution companies that, in the aggregate), in 2008 or any subsequent year, delivers 460,000,000 cubic feet or more of natural gas, and any other gas meeting the specifications for commingling with natural gas for purposes of delivery, to customers that are not covered entities.
- "(14) CREDITING PERIOD.—The term 'crediting period' means the period with respect

- to which an offset project is eligible to earn offset credits under part D, as determined under section 734(c).
- "(15) DESIGNATED REPRESENTATIVE.—The term 'designated representative' means, with respect to a covered entity, a reporting entity (as defined in section 713), an offset project developer, or any other entity receiving or holding allowances, offset credits, or term offset credits under this title, an individual authorized, through a certificate of representation submitted to the Administrator by the owners and operators or similar entity official, to represent the owners and operators or similar entity official in all matters pertaining to this title (including the holding, transfer, or disposition of allowances or offset credits), and to make all submissions to the Administrator under this title.
- "(16) DEVELOPING COUNTRY.—The term 'developing country' means a country eligible to receive official development assistance according to the income guidelines of the Development Assistance Committee of the Organization for Economic Cooperation and Development.
- "(17) DOMESTIC OFFSET CREDIT.—For purposes of part D, the term 'domestic offset credit' means an offset credit issued under part D, other than an international offset credit. For purposes of part C, the term means any offset credit issued under the American Clean Energy and Security Act of 2009, or the amendments made thereby. The term does not include a term offset credit.
- "(18) ELECTRICITY SOURCE.—The term 'electricity source' means a stationary source that includes one or more utility units.
- "(19) EMISSION.—The term 'emission' means the release of a greenhouse gas into the ambient air. Such term does not include gases that are captured and geologically sequestered, except to the extent that they are later released into the atmosphere, in which case compliance must be demonstrated pursuant to section 722(b)(5)
- "(20) EMISSION ALLOWANCE.—The term 'emission allowance' means an allowance established under section 721(a) or section 726(g)(2) or (h)(1)(C).
- "(21) FAIR MARKET VALUE.—The term 'fair market value' means the average daily closing price on registered exchanges or, if such a price is unavailable, the average price as determined by the Administrator, during a specified time period, of an emission allowance.
- "(22) FEDERAL LAND.—The term 'Federal land' means land that is owned by the United States, other than land held in trust for an Indian or Indian tribe.
- "(23) FOSSIL FUEL.—The term 'fossil fuel' means natural gas, petroleum, or coal, or any form of solid, liquid, or gaseous fuel derived from such material, including consumer products that are derived from such materials and are combusted.
- "(24) FOSSIL FUEL-FIRED.—The term 'fossil fuel-fired' means powered by combustion of fossil fuel, alone or in combination with any other fuel, regardless of the percentage of fossil fuel consumed.
- "(25) FUGITIVE EMISSIONS.—The term 'fugitive emissions' means emissions from leaks, valves, joints, or other small openings in pipes, ducts, or other equipment, or from vents
- "(26) GEOLOGIC SEQUESTRATION; GEOLOGICALLY SEQUESTERED.—The terms 'geologic sequestration' and 'geologically sequestered' mean the sequestration of greenhouse gases in subsurface geologic formations for purposes of permanent storage.
- "(27) GEOLOGIC SEQUESTRATION SITE.—The term 'geologic sequestration site' means a site where carbon dioxide is geologically sequestered.

- "(28) GREENHOUSE GAS.—The term 'greenhouse gas' means any gas described in section 711(a) or designated under section 711, except to the extent that it is regulated under title VI.
- "(30) Hold.—The term 'hold' means, with respect to an allowance, offsets credit, or term offset credit, to have in the appropriate account in the allowance tracking system established under section 724(d), or submit to the Administrator for recording in such account.
- "(31) INDUSTRIAL SOURCE.—The term 'industrial source' means any stationary source that—
- "(A) is not an electricity source; and
- "(B) is in-
- "(i) the manufacturing sector (as defined in North American Industrial Classification System codes 31, 32, and 33); or
- "(ii) the natural gas processing or natural gas pipeline transportation sector (as defined in North American Industrial Classification System codes 211112 and 486210).
- "(32) INTERNATIONAL EMISSION ALLOW-ANCE.—The term 'international emission allowance' means a tradable authorization to emit 1 ton of carbon dioxide equivalent of greenhouse gas that is issued by a national or supranational foreign government pursuant to a qualifying international program designated by the Administrator pursuant to section 728(a).
- "(33) INTERNATIONAL OFFSET CREDIT.—The term 'international offset credit' means an offset credit issued by the Administrator under section 743.
- "(34) Leakage.—Except as provided in part F, the term 'leakage' means a significant increase in greenhouse gas emissions, or significant decrease in sequestration, which is caused by an offset project or activities under part E and occurs outside the boundaries of the offset project or the relevant program or project under part E.
- "(35) MINERAL SEQUESTRATION.—The term 'mineral sequestration' means sequestration of carbon dioxide from the atmosphere by capturing carbon dioxide into a permanent mineral, such as the aqueous precipitation of carbonate minerals that results in the storage of carbon dioxide in a mineral form.
- "(36) NATURAL GAS LIQUID.—The term 'natural gas liquid' means ethane, butane, isobutane, natural gasoline, and propane.
- "(37) NATURAL GAS LOCAL DISTRIBUTION COMPANY.—The term 'natural gas local distribution company' has the meaning given the term 'local distribution company' in section 2(17) of the Natural Gas Policy Act of 1978 (15 U.S.C. 3301(17)).
- "(38) OFFSET CREDIT.—For purposes of this section and part D, the term 'offset credit' means an offset credit issued under part D. For purposes of part C, the term means any offset credit issued under the American Clean Energy and Security Act of 2009, or the amendments made thereby. The term does not include a term offset credit.
- "(39) OFFSET PROJECT.—The term 'offset project' means a project or activity that reduces or avoids greenhouse gas emissions, or sequesters greenhouse gases, and for which offset credits are or may be issued under part D
- "(40) OFFSET PROJECT DEVELOPER.—The term 'offset project developer' means the individual or entity designated as the offset project developer in an offset project approval petition under section 735(c)(1).
- "(41) PETROLEUM.—The term 'petroleum' includes crude oil, tar sands, oil shale, and heavy oils.
- $``(\overset{\circ}{42})$ RENEWABLE BIOMASS.—The term 'renewable biomass' means any of the following:
- "(A) Materials, pre-commercial thinnings, or removed invasive species from National

- Forest System land and public lands (as defined in section 103 of the Federal Land Policy and Management Act of 1976 (43 U.S.C. 1702)), including those that are byproducts of preventive treatments (such as trees, wood, brush, thinnings, chips, and slash), that are removed as part of a federally recognized timber sale, or that are removed to reduce hazardous fuels, to reduce or contain disease or insect infestation, or to restore ecosystem health, and that are—
- "(i) not from components of the National Wilderness Preservation System, Wilderness Study Areas, Inventoried Roadless Areas, old growth stands, late-successional stands (except for dead, severely damaged, or badly infested trees), components of the National Landscape Conservation System, National Monuments, National Conservation Areas, Designated Primitive Areas, or Wild and Scenic Rivers corridors:
- "(ii) harvested in environmentally sustainable quantities, as determined by the appropriate Federal land manager; and
- "(iii) harvested in accordance with Federal and State law, and applicable land management plans.
- "(B) Any organic matter that is available on a renewable or recurring basis from non-Federal land or land belonging to an Indian or Indian tribe that is held in trust by the United States or subject to a restriction against alienation imposed by the United States, including—
 - "(i) renewable plant material, including—
 - "(I) feed grains;
 - "(II) other agricultural commodities;
 - "(III) other plants and trees; and
 - "(IV) algae; and
 - "(ii) waste material, including-
 - "(I) crop residue:
- "(II) other vegetative waste material (including wood waste and wood residues):
- "(III) animal waste and byproducts (including fats, oils, greases, and manure):
 - "(IV) construction waste; and
 - ``(V) food waste and yard waste.
- "(C) Residues and byproducts from wood, pulp, or paper products facilities.".
- "(43) RETIRE.—The term 'retire', with respect to an "allowance, offset credit, or term offset credit, established or issued under the American Clean Energy and Security Act of 2009 or the amendments made thereby, means to disqualify such allowance or offset credit for any subsequent use under this title, regardless of whether the use is a sale, exchange, or submission of the allowance, offset credit, or term offset credit to satisfy a compliance obligation.
- "(44) REVERSAL.—The term 'reversal' means an intentional or unintentional loss of sequestered greenhouse gases to the atmosphere.
- "(45) SEQUESTERED AND SEQUESTRATION.— The terms 'sequestered' and 'sequestration' mean the separation, isolation, or removal of greenhouse gases from the atmosphere, as determined by the Administrator. The terms include biological, geologic, and mineral sequestration, but do not include ocean fertilization techniques.
- "(46) STATIONARY SOURCE.—The term 'stationary source' means any integrated operation comprising any plant, building, structure, or stationary equipment, including support buildings and equipment, that is located within one or more contiguous or adjacent properties, is under common control of the same person or persons, and emits or may emit a greenhouse gas.
- "(47) STRATEGIC RESERVE ALLOWANCE.—The term 'strategic reserve allowance' means an emission allowance reserved for, transferred to, or deposited in the strategic reserve under section 726.
- (48) Ton.—The term 'ton' means metric ton.

- "(49) UNCAPPED EMISSIONS.—The term 'uncapped emissions' means emissions of greenhouse gases emitted after December 31, 2011, that are not capped emissions.
- "(50) UNITED STATES GREENHOUSE GAS EMISSIONS.—The term 'United States greenhouse gas emissions' means the total quantity of annual greenhouse gas emissions from the United States, as calculated by the Administrator and reported to the United Nations Framework Convention on Climate Change Secretariat.
- "(51) UTILITY UNIT.—The term 'utility unit' means a combustion device that, on January 1, 2009, or any date thereafter, is fossil fuel-fired and serves a generator that produces electricity for sale, unless such combustion device, during the 12-month period starting the later of January 1, 2009, or the commencement of commercial operation and each calendar year starting after such later date—
- "(A) is part of an integrated cycle system that cogenerates steam and electricity during normal operation and that supplies one-third or less of its potential electric output capacity and 25 MW or less of electrical output for sale: or
- "(B) combusts materials of which more than 95 percent is municipal solid waste on a heat input basis.
- "(52) VINTAGE YEAR.—The term 'vintage year' means the calendar year for which an emission allowance is established under section 721(a) or which is assigned to an emission allowance under section 726(g)(3)(A), except that the vintage year for a strategic reserve allowance shall be the year in which such allowance is purchased at auction."

Subtitle B-Disposition of Allowances

SEC. 321. DISPOSITION OF ALLOWANCES FOR GLOBAL WARMING POLLUTION REDUCTION PROGRAM.

Title VII of the Clean Air Act, as added by section 311 of this Act, is amended by adding at the end the following part:

"PART H—DISPOSITION OF ALLOWANCES "SEC. 781. ALLOCATION OF ALLOWANCES FOR SUPPLEMENTAL REDUCTIONS.

- "(a) IN GENERAL.—The Administrator shall allocate for each vintage year the following percentage of the emission allowances established under section 721(a), for distribution in accordance with part E:
- "(1) For vintage years 2012 through 2025, 5 percent.
- "(2) For vintage years 2026 through 2030, 3 percent.
- "(3) For vintage years 2031 through 2050, 2 percent.
- "(b) ADJUSTMENT.—The Administrator shall modify the percentages set forth in subsection (a) as necessary to ensure the achievement of the annual supplemental emission reduction objective for 2020, and the cumulative reduction objective through 2025, set forth in section 753(b)(1).
- "(c) CARRYOVER.—If the Administrator has not distributed all of the allowances allocated pursuant to this section for a given vintage year by the end of that year, all such undistributed emission allowances shall, in accordance with section 782(s), be exchanged for allowances from the following vintage year and treated as part of the allocation for supplemental reductions under this section for that later vintage year.

"SEC. 782. ALLOCATION OF EMISSION ALLOW-ANCES.

- "(a) ELECTRICITY CONSUMERS.—(1) The Administrator shall allocate emission allowances for the benefit of electricity consumers, to be distributed in accordance with section 783(b), (c), and (d) in the following amounts:
- "(A) For vintage years 2012 and 2013: 43.75 percent of the emission allowances established for each year under section 721(a).

- "(B) For vintage years 2014 and 2015: 38.89 percent of the emission allowances established for each year under section 721(a).
- "(C) For vintage years 2016 through 2025: 35.00 percent of the emission allowances established for each year under section 721(a).
- "(D) For vintage year 2026: 28 percent of the emission allowances established for that year under section 721(a).
- "(E) For vintage year 2027: 21 percent of the emission allowances established for that year under section 721(a).
- "(F) For vintage year 2028: 14 percent of the emission allowances established for that year under section 721(a).
- "(G) For vintage year 2029: 7 percent of the emission allowances established for that year under section 721(a).
- "(2) The Administrator shall allocate emission allowances for energy efficiency, renewable electricity, and low income ratepayer assistance programs administered by small electricity local distribution companies, to be distributed in accordance with section 783(e) in the following amounts:
- "(A) For vintage years 2012 through 2025: 0.5 percent of the emission allowances established each year under section 721(a).
- "(B) For vintage year 2026: 0.4 percent of the emission allowances established for that year under section 721(a).
- "(C) For vintage year 2027: 0.3 percent of the emission allowances established for that year under section 721(a).
- "(D) For vintage year 2028: 0.2 percent of the emission allowances established for that year under section 721(a).
- "(E) For vintage year 2029: 0.1 percent of the emission allowances established for that year under section 721(a).
- "(3) For vintage year 2012, the Administrator shall allocate 0.35 percent of emission allowances established for such year under section 721(a) to avoid disincentives to the continued use of existing energy-efficient cogeneration facilities at industrial parks, to be distributed in accordance with section 783(f).
- "(b) NATURAL GAS CONSUMERS.—The Administrator shall allocate emission allowances for the benefit of natural gas consumers to be distributed in accordance with section 784 in the following amounts:
- "(1) For vintage years 2016 through 2025, 9 percent of the emission allowances established for each year under section 721(a).
- "(2) For vintage year 2026, 7.2 percent of the emission allowances established for that year under section 721(a).
- "(3) For vintage year 2027, 5.4 percent of the emission allowances established for that year under section 721(a).
- "(4) For vintage year 2028, 3.6 percent of the emission allowances established for that year under section 721(a).
- "(5) For vintage year 2029, 1.8 percent of the emission allowances established for that year under section 721(a).
- "(c) Home Heating Oil and Propane Consumers.—The Administrator shall allocate emission allowances for the benefit of home heating oil and propane consumers to be distributed in accordance with section 785 in the following amounts:
- "(1) For vintage years 2012 and 2013, 1.875 percent of the emission allowances established for each year under section 721(a).
- ``(2) For vintage years 2014 and 2015, 1.67 percent of the emission allowances established for each year under section 721(a).
- "(3) For vintage years 2016 through 2025, 1.5 percent of the emission allowances established for each year under section 721(a).
- "(4) For vintage year 2026, 1.2 percent of the emission allowances established for that year under section 721(a).

- "(5) For vintage year 2027, 0.9 percent of the emission allowances established for that year under section 721(a).
- "(6) For vintage year 2028, 0.6 percent of the emission allowances established for that year under section 721(a).
- "(7) For vintage year 2029, 0.3 percent of the emission allowances established for that year under section 721(a).
- "(d) Low Income Consumers.—For each vintage year starting in 2012, the Administrator shall auction, pursuant to section 791, 15 percent of the emission allowances established for each year under section 721(a), with the proceeds used for the benefit of low income consumers to fund the program set forth in subtitle C of title IV of American Clean Energy and Security Act of 2009 and the amendments made thereby.
 - "(e) TRADE-VULNERABLE INDUSTRIES.-
- "(1) IN GENERAL.—The Administrator shall allocate emission allowances to energy-intensive, trade-exposed entities, to be distributed in accordance with section 765, in the following amounts:
- "(A) For vintage years 2012 and 2013, up to 2.0 percent of the emission allowances established for each year under section 721(a).
- "(B) For vintage year 2014, up to 15 percent of the emission allowances established for that year under section 721(a).
- "(C) For vintage year 2015, up to the product of— $\,$
- "(i) the amount specified in paragraph (2); multiplied by
- "(ii) the quantity of emission allowances established for 2015 under section 721(a) divided by the quantity of emission allowances established for 2014 under section 721(a).
- ''(D) For vintage year 2016, up to the product of—
- "(i) the amount specified in paragraph (3); multiplied by
- "(ii) the quantity of emission allowances established for 2015 under section 721(a) divided by the quantity of emission allowances established for 2014 under section 721(a).
- "(E) For vintage years 2017 through 2025, up to the product of—
- "(i) the amount specified in paragraph (4); multiplied by
- "(ii) the quantity of emission allowances established for that year under section 721(a) divided by the quantity of emission allowances established for 2016 under section 721(a).
- "(F) For vintage years 2026 through 2050, up to the product of the amount specified in paragraph (4)—
- "(i) multiplied by the quantity of emission allowances established for the applicable year during 2026 through 2050 under section 721(a) divided by the quantity of emission allowances established for 2016 under section 721(a); and
- "(ii) multiplied by a factor that shall equal 90 percent for 2026 and decline 10 percent for each year thereafter until reaching zero, except that, if the President modifies a percentage for a year under subparagraph (A) of section 767(c)(3), the highest percentage the President applies for any sector under that subparagraph for that year (not exceeding 100 percent) shall be used for that year instead of the factor otherwise specified in this clause.
- "(2) CARRYOVER.—After the Administrator distributes emission allowances pursuant to section 765 for any given vintage year, any emission allowances allocated to energy-intensive, trade-exposed entities pursuant to this subsection that have not been so distributed shall, in accordance with subsection (s), be exchanged for allowances from the following vintage year and treated as part of the allocation to such entities for that later vintage year.

- "(f) DEPLOYMENT OF CARBON CAPTURE AND SEQUESTRATION TECHNOLOGY.—
- "(1) ANNUAL ALLOCATION.—The Administrator shall allocate emission allowances for the deployment of carbon capture and sequestration technology to be distributed in accordance with section 786 in the following amounts:
- "(A) For vintage years 2014 through 2017, 1.75 percent of the emission allowances established for each year under section 721(a).
- "(B) For vintage years 2018 and 2019, 4.75 percent of the emission allowances established for each year under section 721(a).
- "(C) For vintage years 2020 through 2050, 5 percent of the emission allowances established for each year under section 721(a).
- "(2) CARRYOVER.—If the Administrator has not distributed all of the allowances allocated pursuant to this subsection for a given vintage year by the end of that year, all such undistributed emission allowances shall, in accordance with subsection (s), be exchanged for allowances from the following vintage year and treated as part of the allocation for the deployment of carbon capture and sequestration technology under this subsection for that later vintage year.
- "(g) INVESTMENT IN ENERGY EFFICIENCY AND RENEWABLE ENERGY.—The Administrator shall allocate emission allowances to invest in energy efficiency and renewable energy as follows:
- "(1) To be distributed in accordance with section 132 of the American Clean Energy and Security Act of 2009 in the following amounts:
- "(A) For vintage years 2012 through 2015, 9.5 percent of the emission allowances established for each year under section 721(a).
- "(B) For vintage years 2016 through 2017, 6.5 percent of the emission allowances established for each year under section 721(a).
- "(C) For vintage years 2018 through 2021, 5.5 percent of the emission allowances established for each year under section 721(a).
- "(D) For vintage years 2022 through 2025, 1.0 percent of the emission allowances established for each year under section 721(a).
- "(E) For vintage years 2026 through 2050, 4.5 percent of the emission allowances established for each year under section 721(a).
- "(F) At the same time allowances are distributed under subparagraph (D) for each of the vintage years 2022 through 2025, 3.55 percent of emission allowances established under section 721(a) for the vintage year four years after that vintage year shall also be distributed (which shall be in addition to the emission allowances distributed under subparagraph (E)).
- "(2) To be distributed in accordance with section 304 of the Energy Conservation and Production Act, as amended by section 201 of the American Clean Energy and Security Act of 2009, for each vintage year from 2012 through 2050, 0.5 percent of emission allowances established for that year under section 721(a).
- "(3) To be distributed among the States in accordance with the formula in section 132(b) of the American Clean Energy and Security Act of 2009 and to be used exclusively for the purposes of section 202 of the American Clean Energy and Security Act of 2009 in the following amounts:
- "(A) For vintage years 2012 through 2017, 0.05 percent of the emission allowances established for each year under section 721(a).
- "(B) For vintage years 2018 through 2050, 0.03 percent of the emission allowances established for each year under section 721(a).
- "(h) ENERGY RESEARCH AND DEVELOP-
- "(1) ENERGY INNOVATION HUBS.—For vintage years 2012 through 2050, the Administrator shall allocate 0.45 percent of the emission allowances established under section 721(a) to

be distributed to Energy Innovation Hubs in accordance with section 171 of the American Clean Energy and Security Act of 2009.

- "(2) ADVANCED ENERGY RESEARCH.—For vintage years 2012 through 2050, the Administrator shall allocate 1.05 percent of the emission allowances established under section 721(a) for the Advanced Research Project Agency-Energy to be distributed in accordance with section 172 of the American Clean Energy and Security Act of 2009.
- "(i) INVESTMENT IN CLEAN VEHICLE TECHNOLOGY.—The Administrator shall allocate emission allowances to invest in the development and deployment of clean vehicles, to be distributed in accordance with section 124 of the American Clean Energy and Security Act of 2009 in the following amounts:
- "(1) For vintage years 2012 through 2017, 3 percent of the emission allowances established for each year under section 721(a).
- "(2) For vintage years 2018 through 2025, 1 percent of the emission allowances established for each year under section 721(a).
- "(j) DOMESTIC FUEL PRODUCTION.—For vintage years 2014 through 2026, the Administrator shall allocate and distribute according to section 787—
- "(1) 2 percent of the emission allowances established for each year under section 721(a) to domestic petroleum refineries that are covered entities pursuant to section 700(13)(F)(viii), including small business refiners; and
- "(2) an additional 0.25 percent of the emissions allowances established for each year under section 721(a) to small business refiners that are covered entities pursuant to section 700(13)(F)(viii).
- "(k) INVESTMENT IN WORKERS.—The Administrator shall auction pursuant to section 791 emission allowances for the benefit of workers pursuant to part 2 of subtitle B of the American Clean Energy and Security Act of 2009 in the following amounts, and shall deposit into the Climate Change Worker Adjustment Assistance Fund established pursuant to section 793, and report to the Secretary of Labor on, the proceeds from the sale of these allowances:
- "(A) For vintage years 2012 through 2021, 0.5 percent of the emission allowances established for each year under section 721(a).
- "(B) For vintage years 2022 through 2050, 1.0 percent of the emission allowances established for each year under section 721(a).
- All amounts deposited into the fund shall be available to the Secretary of Labor until expended to carry out part 2 of subtitle B of title IV of the American Clean Energy and Security Act of 2009. Of the amounts deposited, not more than \$10,000,000 shall be available to the Secretary of Labor for Federal administration costs of such part 2 each fiscal year.
- "(2) The Administrator shall auction, pursuant to section 791, 0.75 percent of the emission allowances established for each of vintage years 2012 and 2013 under section 721(a), and shall deposit the proceeds in the Energy Efficiency and Renewable Energy Worker Training Fund established by section 422 of the American Clean Energy and Security Act of 2009.
- "(1) DOMESTIC ADAPTATION.—The Administrator shall allocate emission allowances for domestic adaptation as follows:
- "(1) To be distributed in accordance with section 453 of the American Clean Energy and Security Act of 2009 in the following amounts:
- "(A) For vintage years 2012 through 2021, 0.9 percent of the emission allowances established for each year under section 721(a).
- "(B) For vintage years 2022 through 2026, 1.9 percent of the emission allowances established for each year under section 721(a).

- "(C) For vintage years 2027 through 2050, 3.9 percent of the emission allowances established for each year under section 721(a).
- "(2) For vintage year 2012 and thereafter, the Administrator shall auction, pursuant to section 791, 0.1 percent of the emission allowances established for each year under section 721(a), and shall deposit the proceeds in the Climate Change Health Protection and Promotion Fund established by section 467 of the American Clean Energy and Security Act of 2009.
- "(m) WILDLIFE AND NATURAL RESOURCE AD-APTATION.—The Administrator shall allocate emission allowances for wildlife and natural resource adaptation as follows:
- "(1) To be distributed to State agencies in accordance with section 480(a) of the American Clean Energy and Security Act of 2009 in the following amounts:
- "(A) For vintage years 2012 through 2021, 0.385 percent of the emission allowances established for each year under section 721(a).
- "(B) For vintage years 2022 through 2026, 0.77 percent of the emission allowances established for each year under section 721(a).
- "(C) For vintage years 2027 through 2050, 1.54 percent of the emission allowances established for each year under section 721(a).
- "(2) To be auctioned pursuant to section 791, with the proceeds to be deposited in the Natural Resources Climate Change Adaptation Fund established pursuant to section 480(b), in the following amounts:
- "(A) For vintage years 2012 through 2021, 0.615 percent of the emission allowances established for each year under section 721(a).
- "(B) For vintage years 2022 through 2026, 1.23 percent of the emission allowances established for each year under section 721(a).
- "(C) For vintage years 2027 through 2050, 2.46 percent of the emission allowances established for each year under section 721(a).
- "(n) INTERNATIONAL ADAPTATION.—The Administrator shall allocate emission allowances for international adaptation to be distributed in accordance with part 2 of subtitle E of title IV of the American Clean Energy and Security Act of 2009 in the following
- "(1) For vintage years 2012 through 2021, 1.0 percent of the emission allowances established for each year under section 721(a).
- "(2) For vintage years 2022 through 2026, 2.0 percent of the emission allowances established for each year under section 721(a).
- "(3) For vintage years 2027 through 2050, 4.0 percent of the emission allowances established for each year under section 721(a).
- "(0) INTERNATIONAL CLEAN TECHNOLOGY DE-PLOYMENT.—The Administrator shall allocate emission allowances for international clean technology deployment for distribution in accordance with subtitle D of title IV of the American Clean Energy and Security Act of 2009 in the following amounts:
- "(1) For vintage years 2012 through 2021, 1.0 percent of the emission allowances established for each year under section 721(a).
- "(2) For vintage years 2022 through 2026, 2.0 percent of the emission allowances established for each year under section 721(a).
- "(3) For vintage years 2027 through 2050, 4.0 percent of the emission allowances established for each year under section 721(a).
- "(p) RELEASE OF FUTURE ALLOWANCES.— The Administrator shall make future year allowances available by auctioning allowances, pursuant to section 791, in the following amounts:
- "(1) In each of calendar years 2014 through 2019, a string of 0.70 billion allowances with vintage years 12 to 17 years after the year of the auction, with an equal number of allowances from each vintage year in the string.
- "(2) In each of calendar years 2020 through 2025, a string of 0.50 billion allowances with vintage years 12 to 17 years after the year of

- the auction, with an equal number of allowances from each vintage year in the string.
- "(3) In each of calendar years 2026 through 2030, a string of 0.3 billion allowances with vintage years 12 to 17 years after the year of the auction, with an equal number of allowances from each vintage year in the string.
 - "(q) DEFICIT REDUCTION.—
- "(1) For each of vintage years 2012 through 2025, any allowances not allocated for distribution or auction pursuant to section 781 or subsections (s) and (t) of this section, or disbursed pursuant to section 790, shall be auctioned by the Administrator pursuant to section 791 and the proceeds shall be deposited into the Treasury.
- "(2) Unless otherwise specified, any allowances allocated pursuant to subsections (s) and (t) and not distributed by March 31 of the calendar year following the allowance's vintage year, shall be auctioned by the Administrator and the proceeds shall be deposited into the Treasury.
- "(3) For auctions conducted through calendar year 2020 pursuant to subsection (p), the auction proceeds shall be deposited into the Treasury.
- "(r) CLIMATE CHANGE CONSUMER REFUND.—
 "(1) For each of vintage years 2026 through 2050, the Administrator shall auction the following allowances established under section 721(a) and deposit the proceeds into the Climate Change Consumer Refund Account:
- "(A) Any allowances not allocated for distribution or auction pursuant to section 781 or subsections (a) through (p) of this section, or disbursed pursuant to section 790.
- "(B) Unless otherwise specified, any allowances allocated pursuant to subsections (a) through (o) and not distributed by March 31 of the calendar year following the allowance's vintage year.
- "(2) For auctions conducted pursuant to subsection (p) in calendar years 2021 and thereafter, the Administrator shall place the proceeds from the sales of the these allowances into the Climate Change Consumer Refund Account.
- "(3) Funds deposited into the Climate Change Consumer Refund Account shall be used as specified in section 789 and shall be available for expenditure, without further appropriation or fiscal year limitation.
- ''(s) Treatment of Carryover Allow-Ances.—
- "(1) IN GENERAL.—If there are undistributed allowances from a vintage year for supplemental reductions pursuant to section 781(c), energy-intensive, trade-exposed industries pursuant to subsection (e)(2) of this section, deployment of carbon capture and sequestration technology pursuant to subsection (f)(2) of this section, or supplemental agriculture and renewable energy pursuant to subsection (u)(2) of this section, the Administrator shall—
- "(A) use the undistributed allowances to increase for the same vintage year—
- "(i) the allocation of allowances to be auctioned for deficit reduction pursuant to subsection (q) or for consumer refunds pursuant to subsection (r);
- "(ii) the allocation of allowances to be auctioned for low income consumers pursuant to subsection (d); or
 - "(iii) a combination of both; and
 - "(B) except as provided in paragraph (2)—
- "(i) decrease by the same amount for the following vintage year the allocation for the purpose for which the allocation was increased pursuant to subparagraph (A); and
- "(ii) increase by the same amount for the following vintage year the allocation for the purpose for which the undistributed allowances were originally allocated.

- "(2) EXCESS UNDISTRIBUTED ALLOWANCES.—
 (A) For each vintage year for which this subsection applies, the Administrator shall determine whether—
- "(i) the total quantity of undistributed allowances for that vintage year that were allocated pursuant to section 781(c), and subsections (e)(2), (f)(2), and (u)(2) of this section. exceeds
- "(ii) the total quantity of allowances allocated pursuant to subsection (d), (q) and (r) for the following vintage year, decreased by the quantity of allowances for that following vintage year set aside for the reserve established by section 791(f).
- "(B) If the Administrator determines under subparagraph (A) that the quantity described in subparagraph (A)(i) exceeds the quantity described in subparagraph (A)(ii), paragraph (1)(B)(ii) of this subsection shall not apply. Instead, for each purpose described in section 781(c), or subsections (e)(2), (f)(2), and (u)(2) of this section for which undistributed allowances for a given vintage year were allocated, the Administrator shall increase the allocation for the following vintage year by the amount that is the product of—
- "(i) the number of undistributed allowances for that purpose, times
- ''(ii) the quantity described in subparagraph (A)(ii) divided by the quantity described in subparagraph (A)(i).
- "(t) COMPENSATION FOR EARLY ACTORS.— For vintage year 2012, the Administrator shall allocate for compensation for early actors 1 percent of emission allowances established under section 721(a), to be distributed in accordance with section 795 of the American Clean Energy and Security Act of 2009.
- "(u) SUPPLEMENTAL AGRICULTURE AND RENEWARLE ENERGY —
- "(1) IN GENERAL.—For vintage years 2012 through 2016, the Administrator shall allocate 0.28 percent of emission allowances established under section 721(a), to be distributed in accordance with section 788 of the American Clean Energy and Security Act of 2009
- "(2) CARRYOVER.—After the Administrator distributes emission allowances pursuant to section 788 for any given vintage year, any emission allowances allocated to supplemental agriculture and renewable energy pursuant to this subsection that have not been so distributed shall, in accordance with subsection (s), be exchanged for allowances from the following vintage year and treated as part of the allocation to such entities for that later vintage year.

"SEC. 783. ELECTRICITY CONSUMERS.

- "(a) DEFINITIONS.—For purposes of this section:
- "(1) COAL-FUELED UNIT.—The term 'coalfueled unit' means a utility unit that derives at least 85 percent of its heat input from coal, petroleum coke, or any combination of these 2 fuels.
- "(2) ELECTRICITY LOCAL DISTRIBUTION COM-PANY.—The term 'electricity local distribution company' means an electric utility—
- "(A) that has a legal, regulatory, or contractual obligation to deliver electricity directly to retail consumers in the United States, regardless of whether that entity or another entity sells the electricity as a commodity to those retail consumers; and
- "(B) the retail rates of which, except in the case of an electric cooperative, are regulated or set by—
 - "(i) a State regulatory authority;
- "(ii) a State or political subdivision thereof (or an agency or instrumentality of, or corporation wholly owned by, either of the foregoing); or
- "(iii) an Indian tribe pursuant to tribal law.
- "(3) ELECTRICITY SAVINGS; RENEWABLE ENERGY RESOURCE.—The terms 'electricity sav-

- ings' and 'renewable energy resource' shall have the meaning given those terms in section 610 of the Public Utility Regulatory Policies Act of 1978 (as added by section 101 of the American Clean Energy and Security Act of 2009).
- "(4) INDEPENDENT POWER PRODUCTION FACILITY.—The term 'independent power production facility' means a facility—
- "(A) that is used for the generation of electric energy, at least 80 percent of which is sold at wholesale; and
- "(B) the sales of the output of which are not subject to retail rate regulation or setting of retail rates by—
 - "(i) a State regulatory authority;
- "(ii) a State or political subdivision thereof (or an agency or instrumentality of, or corporation wholly owned by, either of the foregoing):
 - "(iii) an electric cooperative; or
- "(iv) an Indian tribe pursuant to tribal
- "(5) LONG-TERM CONTRACT GENERATOR.—The term 'long-term contract generator' means a qualifying small power production facility, a qualifying cogeneration facility), an independent power production facility, or a facility for the production of electric energy for sale to others that is owned and operated by an electric cooperative that is—
 - "(A) a covered entity; and
- $\mbox{``(B)}$ as of the date of enactment of this title—
- "(i) a facility with 1 or more sales or tolling agreements executed before March 1, 2007, that govern the facility's electricity sales and provide for sales at a price (whether a fixed price or a price formula) for electricity that does not allow for recovery of the costs of compliance with the limitation on greenhouse gas emissions under this title, provided that such agreements are not between entities that are affiliates of one another; or
- "(ii) a facility consisting of 1 or more cogeneration units that makes useful thermal energy available to an industrial or commercial process with 1 or more sales agreements executed before March 1, 2007, that govern the facility's useful thermal energy sales and provide for sales at a price (whether a fixed price or price formula) for useful thermal energy that does not allow for recovery of the costs of compliance with the limitation on greenhouse gas emissions under this title, provided that such agreements are not between entities that are affiliates of one another.
- "(6) MERCHANT COAL UNIT.—The term 'merchant coal unit' means a coal-fueled unit that—
- "(A) is or is part of a covered entity:
- "(B) is not owned by a Federal, State, or regional agency or power authority; and
- "(C) generates electricity solely for sale to others, provided that all or a portion of such sales are made by a separate legal entity that—
- "(i) has a full or partial ownership or leasehold interest in the unit, as certified in accordance with such requirements as the Administrator shall prescribe; and
- "(ii) is not subject to retail rate regulation or setting of retail rates by—
- "(I) a State regulatory authority;
- "(II) a State or political subdivision thereof (or an agency or instrumentality of, or corporation wholly owned by, either of the foregoing);
 - "(III) an electric cooperative; or
- "(IV) an Indian tribe pursuant to tribal law.
- "(7) MERCHANT COAL UNIT SALES.—The term 'merchant coal unit sales' means sales to others of electricity generated by a merchant coal unit that are made by the owner or leaseholder described in paragraph (6)(C).

- "(8) NEW COAL-FUELED UNIT.—The term 'new coal-fueled unit' means a coal-fueled unit that commenced operation on or after January 1, 2009 and before January 1, 2013.
- "(9) NEW MERCHANT COAL UNIT.—The term 'new merchant coal unit' means a merchant coal unit—
- "(A) that commenced operation on or after January 1, 2009 and before January 1, 2013; and
- "(B) the actual, on-site construction of which commenced prior to January 1, 2009.
- "(10) QUALIFYING SMALL POWER PRODUCTION FACILITY; QUALIFYING COGENERATION FACILITY.—The terms 'qualifying small power production facility' and 'qualifying cogeneration facility' have the meanings given those terms in section 3(17)(C) and 3(18)(B) of the Federal Power Act (16 U.S.C. 796(17)(C) and 796(18)(B)).
- "(11) SMALL LDC.—The term 'small LDC' means, for any given year, an electricity local distribution company that delivered less than 4,000,000 megawatt hours of electric energy directly to retail consumers in the preceding year.
- "(12) STATE REGULATORY AUTHORITY.—The term 'State regulatory authority' has the meaning given that term in section 3(17) of the Public Utility Regulatory Policies Act of 1978 (16 U.S.C. 2602(17)).
- "(13) USEFUL THERMAL ENERGY.—The term 'useful thermal energy'has the meaning given that term in section 371(7) of the Energy Policy and Conservation Act (42 U.S.C. 6341(7)).
- ''(b) ELECTRICITY LOCAL DISTRIBUTION COMPANIES.—
- "(1) DISTRIBUTION OF ALLOWANCES.—Not later than September 30 of 2011 and each calendar year thereafter through 2028, the Administrator shall distribute to electricity local distribution companies for the benefit of retail ratepayers the quantity of emission allowances allocated for the following vintage year pursuant to section 782(a)(1). Notwithstanding the preceding sentence, the Administrator shall withhold from distribution under this subsection a quantity of emission allowances equal to the lesser of 14.3 percent of the quantity of emission allowances allocated under section 782(a)(1) for the relevant vintage year, or 105 percent of the emission allowances for the relevant vintage year that the Administrator anticipates will be distributed to merchant coal units and to longterm contract generators, respectively, under subsections (c) and (d). If not required by subsections (c) and (d) to distribute all of these reserved allowances, the Administrator shall distribute any remaining emission allowances to electricity local distribution companies in accordance with this subsection.
- "(2) DISTRIBUTION BASED ON EMISSIONS.—
- "(A) IN GENERAL.—For each vintage year, 50 percent of the emission allowances available for distribution under paragraph (1), after reserving allowances for distribution under subsections (c) and (d), shall be distributed by the Administrator among individual electricity local distribution companies ratably based on the annual average carbon dioxide emissions attributable to generation of electricity delivered at retail by each such company during the base period determined under subparagraph (B).
 - "(B) BASE PERIOD.—
- "(i) VINTAGE YEARS 2012 AND 2013.—For vintage years 2012 and 2013, an electricity local distribution company's base period shall be—
 - "(I) calendar years 2006 through 2008; or
- "(II) any 3 consecutive calendar years between 1999 and 2008, inclusive, that such company selects, provided that the company timely informs the Administrator of such selection.

- "(ii) VINTAGE YEARS 2014 AND THEREAFTER.— For vintage years 2014 and thereafter, the base period shall be—
- ``(I) the base period selected under clause (i); or
- "(II) calendar year 2012, in the case of an electricity local distribution company that owns, co-owns, or purchases through a power purchase agreement (whether directly or through a cooperative arrangement) a substantial portion of the electricity generated by a new coal-fueled unit, provided that such company timely informs the Administrator of its election to use 2012 as its base period.
- "(C) DETERMINATION OF EMISSIONS.—
- "(i) DETERMINATION FOR 1999-2008.—As part of the regulations promulgated pursuant to subsection, the Administrator, after consultation with the Energy Information Administration, shall determine the average amount of carbon dioxide emissions attributable to generation of electricity delivered at retail by each electricity local distribution company for each of the years 1999 through 2008, taking into account entities' electricity generation, electricity purchases, and electricity sales. In the case of any electricity local distribution company that owns, co-owns, or purchases through a power purchase agreement (whether directly or through a cooperative arrangement) a substantial portion of the electricity generated by, a coal-fueled unit that commenced operation after January 1, 2006 and before December 31, 2008, the Administrator shall adjust the emissions attributable to such company's retail deliveries in calendar years 2006 through 2008 to reflect the emissions that would have occurred if the relevant unit were in operation during the entirety of such 3-year period.
- "(ii) ADJUSTMENTS FOR NEW COAL-FUELED UNITS —
- "(I) VINTAGE YEARS 2012 AND 2013.—For purposes of emission allowance distributions for vintage years 2012 and 2013, in the case of any electricity local distribution company that owns, co-owns, or purchases through a power purchase agreement (whether directly or through a cooperative arrangement) a substantial portion of the electricity generated by, a new coal-fueled unit, the Administrator shall adjust the emissions attributable to such company's retail deliveries in the applicable base period to reflect the emissions that would have occurred if the new coalfueled unit were in operation during such period.
- "(II) VINTAGE YEAR 2014 AND THEREAFTER.— Not later than necessary for use in making emission allowance distributions under this subsection for vintage year 2014, the Administrator shall, for any electricity local distribution company that owns, co-owns, or purchases through a power purchase agreement (whether directly or through a cooperative arrangement) a substantial portion of the electricity generated by a new coalfueled unit and has selected calendar year 2012 as its base period pursuant to subparagraph (B)(ii)(II), determine the amount of carbon dioxide emissions attributable to generation of electricity delivered at retail by such company in calendar year 2012. If the relevant new coal-fueled unit was not yet operational by January 1, 2012, the Administrator shall adjust such determination to reflect the emissions that would have occurred if such unit were in operation for all of calendar year 2012.
- "(iii) REQUIREMENTS.—Determinations under this paragraph shall be as precise as practicable, taking into account the nature of data currently available and the nature of markets and regulation in effect in various regions of the country. The following requirements shall apply to such determinations:

- "(I) The Administrator shall determine the amount of fossil fuel-based electricity delivered at retail by each electricity local distribution company, and shall use appropriate emission factors to calculate carbon dioxide emissions associated with the generation of such electricity.
- "(II) Where it is not practical to determine the precise fuel mix for the electricity delivered at retail by an individual electricity local distribution company, the Administrator may use the best available data, including average data on a regional basis with reference to Regional Transmission Organizations or regional entities (as that term is defined in section 215(a)(7) of the Federal Power Act (16 U.S.C. 824o(a)(7)), to estimate fuel mix and emissions. Different methodologies may be applied in different regions if appropriate to obtain the most accurate estimate.
 - "(3) DISTRIBUTION BASED ON DELIVERIES -
- "(A) INITIAL FORMULA.—Except as provided in subparagraph (B), for each vintage year, the Administrator shall distribute 50 percent of the emission allowances available for distribution under paragraph (1), after reserving allowances for distribution under subsections (c) and (d), among individual electricity local distribution companies ratably based on each electricity local distribution company's annual average retail electricity deliveries for calendar years 2006 through 2008, unless the owner or operator of the company selects 3 other consecutive years between 1999 and 2008, inclusive, and timely notifies the Administrator of its selection.
- "(B) UPDATING.—Prior to distributing 2015 vintage year emission allowances under this paragraph and at 3-year intervals thereafter, the Administrator shall update the distribution formula under this paragraph to reflect changes in each electricity local distribution company's service territory since the most recent formula was established. For each successive 3-year period, the Administrator shall distribute allowances ratably among individual electricity local distribution companies based on the product of—
- "(i) each electricity local distribution company's average annual deliveries per customer during calendar years 2006 through 2008, or during the 3 alternative consecutive years selected by such company under subparagraph (A); and
- "(ii) the number of customers of such electricity local distribution company in the most recent year in which the formula is updated under this subparagraph.
- (4) Prohibition against excess distribu-TIONS.—The regulations promulgated under subsection shall ensure that, notwithstanding paragraphs (2) and (3), no electricity local distribution company shall receive a greater quantity of allowances under this subsection than is necessary to offset any increased electricity costs to such company's retail ratepayers, including increased costs attributable to purchased power costs, due to enactment of this title. Any emission allowances withheld from distribution to an electricity local distribution company pursuant to this paragraph shall be distributed among all remaining electricity local distribution companies ratably based on emissions pursuant to paragraph (2).
- "(5) USE OF ALLOWANCES.—
- "(A) RATEPAYER BENEFIT.—Emission allowances distributed to an electricity local distribution company under this subsection shall be used exclusively for the benefit of retail ratepayers of such electricity local distribution company and may not be used to support electricity sales or deliveries to entities or persons other than such ratepayers.
- "(B) RATEPAYER CLASSES.—In using emission allowances distributed under this sub-

- section for the benefit of ratepayers, an electricity local distribution company shall ensure that ratepayer benefits are distributed—
- "(i) among ratepayer classes ratably based on electricity deliveries to each class; and
- "(ii) equitably among individual ratepayers within each ratepayer class, including entities that receive emission allowances pursuant to part F.
- "(C) LIMITATION.—In general, an electricity local distribution company shall not use the value of emission allowances distributed under this subsection to provide to any rate-payer a rebate that is based solely on the quantity of electricity delivered to such ratepayer. To the extent an electricity local distribution company uses the value of emission allowances distributed under this subsection to provide rebates, it shall, to the maximum extent practicable, provide such rebates with regard to the fixed portion of ratepayers' bills or as a fixed credit or rebate on electricity bills.
- "(D) INDUSTRIAL RATEPAYERS.—Notwithstanding subparagraph (C), if compliance with the requirements of this title results (or would otherwise result) in an increase in electricity costs for industrial retail ratepayers of any given electricity local distribution company (including entities that receive emission allowances pursuant to part F), such electricity local distribution company—
- "(i) shall pass through to industrial retail ratepayers their ratable share (based on deliveries to each ratepayer class) of the value of the emission allowances distributed to such company under this subsection, to reduce electricity cost impacts on such ratepayers; and
- "(ii) may do so based on the quantity of electricity delivered to individual industrial retail ratepayers.
- "(E) GUIDELINES.—As part of the regulations promulgated under subsection, the Administrator shall, after consultation with State regulatory authorities, prescribe guidelines for the implementation of the requirements of this paragraph. Such guidelines shall include requirements to ensure that industrial retail ratepayers (including entities that receive emission allowances under part F) receive their ratable share of the value of the allowances distributed to each electricity local distribution company pursuant to this subsection.
 - "(6) REGULATORY PROCEEDINGS.-
- "(A) REQUIREMENT.—No electricity local distribution company shall be eligible to receive emission allowances under this subsection or subsection (e) unless the State regulatory authority with authority over such company's retail rates, or the entity with authority to regulate or set retail electricity rates of an electricity local distribution company not regulated by a State regulatory authority, has—
- "(i) after public notice and an opportunity for comment, promulgated a regulation or completed a rate proceeding (or the equivalent, in the case of a ratemaking entity other than a State regulatory authority) that provides for the full implementation of the requirements of paragraph (5) of this subsection and the requirements of subsection (e); and
- "(ii) made available to the Administrator and the public a report describing, in adequate detail, the manner in which the requirements of paragraph (5) and the requirements of subsection (e) will be implemented.
- "(B) UPDATING.—The Administrator shall require, as a condition of continued receipt of emission allowances under this subsection by an electricity local distribution company, that a new regulation be promulgated or rate proceeding be completed, after public notice

and an opportunity for comment, and a new report be made available to the Administrator and the public, pursuant to subparagraph (A), not less frequently than every 5 years.

"(7) PLANS AND REPORTING.—

"(A) REGULATIONS.—As part of the regulations promulgated under subsection, the Administrator shall prescribe requirements governing plans and reports to be submitted in accordance with this paragraph.

'(B) PLANS.—Not later than April 30 of 2011 and every 5 years thereafter through 2026, each electricity local distribution company shall submit to the Administrator a plan, approved by the State regulatory authority or other entity charged with regulating tor setting the retail rates of such company, describing such company's plans for the disposition of the value of emission allowances to be received pursuant to this subsection and subsection (e), in accordance with the requirements of this subsection and subsection (e). Such plan shall include a description of the manner in which the company will provide to industrial retail ratepayers (including entities that receive emission allowances under part F) their ratable share of the value of such allowances.

"(C) REPORTS.—Not later than June 30 of 2013 and each calendar year thereafter through 2031, each electricity local distribution company shall submit a report to the Administrator, and to the relevant State regulatory authority or other entity charged with regulating or setting the retail electricity rates of such company, describing the disposition of the value of any emission allowances received by such company in the prior calendar year pursuant to this subsection and subsection (e), including—

"(i) a description of sales, transfer, exchange, or use by the company for compliance with obligations under this title, of any such emission allowances;

"(ii) the monetary value received by the company, whether in money or in some other form, from the sale, transfer, or exchange of any such emission allowances;

"(iii) the manner in which the company's disposition of any such emission allowances complies with the requirements of this subsection and of subsection (e), including each of the requirements of paragraph (5) of this subsection, including the requirement that industrial retail ratepayers (including entities that receive emission allowances under part F) receive their ratable share of the value of such allowances; and

"(iv) such other information as the Administrator may require pursuant to subparagraph (A).

"(D) PUBLICATION.—The Administrator shall make available to the public all plans and reports submitted under this subsection, including by publishing such plans and reports on the Internet.

"(8) AUDITS.—Each year, the Administrator shall audit a representative sample of electricity local distribution companies to ensure that emission allowances distributed under this subsection have been used exclusively for the benefit of retail ratepayers and that such companies are complying with the requirements of this subsection and of subsection (e), including the requirement that industrial retail ratepayers (including entities that receive emission allowances under part F) receive their ratable share of the value of such allowances. In selecting companies for audit, the Administrator shall take into account any credible evidence of noncompliance with such requirements. The Administrator shall make available to the public a report describing the results of each such audit, including by publishing such report on the Internet.

"(9) ENFORCEMENT.—A violation of any requirement of this subsection or of subsection (e) shall be a violation of this Act. Each emission allowance the value of which is subsection or of subsection (e) shall be a separate violation.

"(c) MERCHANT COAL UNITS.—

"(1) QUALIFYING EMISSIONS.—The qualifying emissions for a merchant coal unit for a given calendar year shall be the product of the number of megawatt hours of merchant coal unit sales generated by such unit in such calendar year and the average carbon dioxide emissions per megawatt hour generated by such unit during the base period under paragraph (2), provided that the number of megawatt hours in a given calendar year for purposes of such calculation shall be reduced in proportion to the portion of such unit's carbon dioxide emissions that are either—

"(A) captured and sequestered in such calendar year; or

"(B) attributable to the combustion or gasification of biomass, to the extent that the owner or operator of the unit is not required to hold emission allowances for such emissions

"(2) Base Period.—For purposes of this subsection, the base period for a merchant coal unit shall be—

"(A) calendar years 2006 through 2008; or

"(B) in the case of a new merchant coal unit—

"(i) the first full calendar year of operation of such unit, if such unit commences operation before January 1, 2012;

"(ii) calendar year 2012, if such unit commences operation on or after January 1, 2012. "(iii) calendar year 2013, if such unit commences operation on or after October 1, 2012,

and before January 1, 2013.

"(3) PHASE-DOWN SCHEDULE.—The Administrator shall identify an annual phase-down factor, applicable to distributions to merchant coal units for each of vintage years 2012 through 2029, that corresponds to the overall decline in the amount of emission allowances allocated to the electricity sector in such years pursuant to section 782(a)(1). Such factor shall—

"(A) for vintage year 2012, be equal to 1.0; "(B) for each of vintage years 2013 through 2029, correspond to the quotient of—

"(i) the quantity of emission allowances allocated under section 782(a)(1) for such vintage year; divided by

"(ii) the quantity of emission allowances allocated under section 782(a)(1) for vintage year 2012.

"(4) DISTRIBUTION OF EMISSION ALLOW-ANCES.—Not later than March 1 of 2013 and each calendar year through 2030, the Administrator shall distribute emission allowances of the preceding vintage year to the owner or operator of each merchant coal unit described in subsection (a)(6)(C) in an amount equal to the product of—

"(A) 0.5;

"(B) the qualifying emissions for such merchant coal unit for the preceding year, as determined under paragraph (1); and

"(C) the phase-down factor for the preceding calendar year, as identified under paragraph (3).

"(5) ADJUSTMENT.—

"(A) STUDY.—Not later than July 1, 2014, the Administrator, in consultation with the Federal Energy Regulatory Commission, shall complete a study to determine whether the allocation formula under paragraph (3) is resulting in, or is likely to result in, windfall profits to merchant coal generators or substantially disparate treatment of merchant coal generators operating in different markets or regions.

"(B) REGULATION.—If the Administrator, in consultation with the Federal Energy Regulatory Commission, makes an affirmative finding of windfall profits or disparate treatment under subparagraph (A), the Administrator shall, not later than 18 months after the completion of the study described in subparagraph (A), promulgate regulations providing for the adjustment of the allocation formula under paragraph (3) to mitigate, to the extent practicable, such windfall profits, if any, and such disparate treatment, if any.

"(6) LIMITATION ON ALLOWANCES.—Notwithstanding paragraph (4) or (5), for each vintage year the Administrator shall distribute under this subsection no more than 10 percent of the total quantity of emission allowances available for such vintage year for distribution to the electricity sector under section 782(a)(1). If the quantity of emission allowances that would otherwise be distributed pursuant to paragraph (4) or (5) for any vintage year would exceed such limit, the Administrator shall distribute 10 percent of the total emission allowances available for distribution under section 782(a)(1) for such vintage year ratably among merchant coal generators based on the applicable formula under paragraph (4) or (5).

"(7) ELIGIBILITY.—The owner or operator of a merchant coal unit shall not be eligible to receive emission allowances under this subsection for any vintage year for which such owner or operator has elected to receive emission allowances for the same unit under subsection (d).

"(d) Long-term Contract Generators.—

"(1) DISTRIBUTION.—Not later than March 1 of 2013 and each calendar year through 2030, the Administrator shall distribute to the owner or operator of each long-term contract generator a quantity of emission allowances of the preceding vintage year that is equal to the sum of—

"(A) the number of tons of carbon dioxide emitted as a result of a qualifying electricity sales agreement referred to in subsection (a)(5)(B)(i); and

"(B) the incremental number of tons of carbon dioxide emitted solely as a result of a qualifying thermal sales agreement referred to in subsection (a)(5)(B)(ii), provided that in no event shall the Administrator distribute more than 1 emission allowance for the same ton of emissions.

"(2) LIMITATION ON ALLOWANCES.— Notwithstanding paragraph (1), for each vintage year the Administrator shall distribute under this subsection no more than 4.3 percent of the total quantity of emission allowances available for such vintage year for distribution to the electricity sector under section 782(a)(1). If the quantity of emission allowances that would otherwise be distributed pursuant to paragraph (1) for any vintage year would exceed such limit, the Administrator shall distribute 4.3 percent of the total emission allowances available for distribution under section 782(a)(1) for such vintage year ratably among long-term contract generators based on paragraph (1).

"(3) ELIGIBILITY.-

"(A) FACILITY ELIGIBILITY.—The owner or operator of a facility shall cease to be eligible to receive emission allowances under this subsection upon the earliest date on which the facility no longer meets each and every element of the definition of a long-term contract generator under subsection (a)(5).

"(B) CONTRACT ELIGIBILITY.—The owner or operator of a facility shall cease to be eligible to receive emission allowances under this subsection based on an electricity or thermal sales agreement referred to in subsection (a)(5)(B) upon the earliest date that such agreement—

"(i) expires;

"(ii) is terminated; or

- "(iii) is amended in any way that changes the location of the facility, the price (whether a fixed price or price formula) for electricity or thermal energy sold under such agreement, the quantity of electricity or thermal energy sold under the agreement, or the expiration or termination date of the agreement.
- "(4) DEMONSTRATION OF ELIGIBILITY.—To be eligible to receive allowance distributions under this subsection, the owner or operator of a long-term contract generator shall submit each of the following in writing to the Administrator within 180 days after the date of enactment of this title, and not later than September 30 of each vintage year for which such generator wishes to receive emission allowances:
- "(A) A certificate of representation described in section 700(15).
- "(B) An identification of each owner and each operator of the facility.
- "(C) An identification of the units at the facility and the location of the facility.
- "(D) A written certification by the designated representative that the facility meets all the requirements of the definition of a long-term contract generator.
- "(E) The expiration date of each qualifying electricity or thermal sales agreement referred to in subsection (a)(5)(B).
- "(F) A copy of each qualifying electricity or thermal sales agreement referred to in subsection (a)(5)(B).
- "(5) NOTIFICATION.—Not later than 30 days after, in accordance with paragraph (3), a facility or an agreement ceases to meet the eligibility requirements for distribution of emission allowances pursuant to this subsection, the designated representative of such facility shall notify the Administrator in writing when, and on what basis, such facility or agreement ceased to meet such requirements.
 - "(e) SMALL LDCs.-
- "(1) DISTRIBUTION.—Not later than September 30 of each calendar year from 2011 through 2028, the Administrator shall, in accordance with this subsection, distribute emission allowances allocated pursuant to section 782(a)(2) for the following vintage year. Such allowances shall be distributed ratably among small LDCs based on historic emissions in accordance with the same measure of such emissions applied to each such small LDC for the relevant vintage year under subsection (b)(2) of this section.
- "(2) USES.—A small LDC receiving allowances under this section shall use such allowances exclusively for the following purposes:
- "(A) Cost-effective programs to achieve electricity savings, provided that such savings shall not be transferred or used for compliance with section 610 of the Public Utility Regulatory Policies Act of 1978.
- "(B) Deployment of technologies to generate electricity from renewable energy resources, provided that any Federal renewable electricity credits issued based on generation supported under this section shall be submitted to the Federal Energy Regulatory Commission for voluntary retirement and shall not be used for compliance with section 610 of the Public Utility Regulatory Policies Act of 1978.
- "(C) Assistance programs to reduce electricity costs for low-income residential ratepayers of such small LDC, provided that such assistance is made available equitably to all residential ratepayers below a certain income level, which shall not be higher than 200 percent of the poverty line (as that term is defined in section 673(2) of the Community Services Block Grant Act (42 U.S.C. 9902(2)).
- "(3) REQUIREMENTS.—As part of the regulations promulgated under subsection, the Administrator shall prescribe—

- "(A) after consultation with the Federal Energy Regulatory Commission, requirements to ensure that programs and projects under paragraph (2)(A) and (B) are consistent with the standards established by, and effectively supplement electricity savings and generation of electricity from renewable energy resources achieved by, the Combined Efficiency and Renewable Electricity Standard established under section 610 of the Public Utility Regulatory Policies Act of 1978;
- "(B) eligibility criteria and guidelines for consumer assistance programs for low-income residential ratepayers under paragraph (2)(C); and
- "(C) such other requirements as the Administrator determines appropriate to ensure compliance with the requirements of this subsection.
- "(4) REPORTING.—Reports submitted under subsection (b)(7) shall include, in accordance with such requirements as the Administrator may prescribe—
- "(A) a description of any facilities deployed under paragraph (2)(A), the quantity of resulting electricity generation from renewable energy resources;
- "(B) an assessment demonstrating the cost-effectiveness of, and electricity savings achieved by, programs supported under paragraph (2)(B); and
- "(C) a description of assistance provided to low-income retail ratepayers under paragraph (2)(C).
- (f) CERTAIN COGENERATION FACILITIES.—
- (1) ELIGIBLE COGENERATION FACILITIES.—For purposes of this subsection, an "eligible cogeneration facility" is a facility that—
- (A) is a qualifying co-generation facility (as that term is defined in section 3(18)(B) of the Federal Power Act (16 U.S.C. 796(18)(B));
- (B) derives 80 percent or more of its heat input from coal, petroleum coke, or any combination of these 2 fuels;
- (C) has a nameplate capacity of 100 megawatts or greater;
- (D) was in operation as of January 1, 2009, and remains in operation as of the date of any distribution of emission allowances under this subsection;
- (E) in calendar years 2006 through 2008 sold, and as of the date of any distribution of emission allowances under this section sells, steam or electricity directly and solely to multiple, separately-owned industrial or commercial facilities co-located at the same site with the cogeneration facility; and
- (F) is not eligible to receive allowances under any other subsection of this section or under part F of this title.
- (2) DISTRIBUTION.—The Administrator shall distribute the emission allowances allocated pursuant to section 782(a)(3) to owners or operators of eligible cogeneration facilities ratably based on the carbon dioxide emissions of each such facility in calendar years 2006 through 2008. The Administrator—
- (A) shall not, in any year, distribute emission allowances under this subsection to the owner or operator of any eligible cogeneration facility in excess of the amount necessary to offset such facility's cost of compliance with the requirements of this title in that year; and
- (B) may distribute such allowances over a period of years if annual distributions under this subsection would otherwise exceed the limitation in subparagraph (A), provided that in no event shall distributions be made under this subsection after calendar year 2025.
- (3) REQUIREMENTS.—The Administrator shall, by regulation, establish requirements to ensure that the value of any emission allowances distributed pursuant to this subsection are passed through, on an equitable basis, to the facilities to which the relevant cogeneration facility provides electricity or

- steam deliveries, including any facility owned or operated by the owner or operator of the cogeneration facility.
- "(g) REGULATIONS.—Not later than 2 years after the date of enactment of this title, the Administrator, in consultation with the Federal Energy Regulatory Commission, shall promulgate regulations to implement the requirements of this section.

"SEC. 784. NATURAL GAS CONSUMERS.

- "(a) DEFINITIONS.—For purposes of this section:
- "(1) COST-EFFECTIVE.—The term 'cost-effective', with respect to an energy efficiency program, means that the program meets the Total Resource Cost Test, which requires that the net present value of economic benefits over the life of the program, including avoided supply and delivery costs and deferred or avoided investments, is greater than the net present value of the economic costs over the life of the program, including program costs and incremental costs borne by the energy consumer.
- "(2) NATURAL GAS LOCAL DISTRIBUTION COM-PANY.—The term 'natural gas local distribution company' means a natural gas local distribution company that is a covered entity.
- "(3) Non-covered entity.—The term 'non-covered entity' means, when used in reference to a date or period prior to the enactment of this title, an entity that would not have been a covered entity if this title had been in effect during such date or period.
- "(4) STATE REGULATORY AUTHORITY.—The term 'State regulatory authority' has the meaning given the term 'State commission' in section 2(8) of the Natural Gas Act (15 U.S.C. 717a(8)).
- "(b) DISTRIBUTION.—Not later than June 30 of 2015 and each calendar year thereafter through 2028, the Administrator shall distribute to natural gas local distribution companies for the benefit of retail rate-payers the quantity of emission allowances allocated for the following vintage year pursuant to section 782(b). Such allowances shall be distributed among local natural gas distribution companies based on the following formula:
- "(1) INITIAL FORMULA.—Except as provided in paragraph (2), for each vintage year, the Administrator shall distribute emission allowances among natural gas local distribution companies ratably based on each such company's annual average retail natural gas deliveries for 2006 through 2008 to customers that were non-covered entities, unless the owner or operator of the company selects 3 other consecutive years between 1999 and 2008, inclusive, and timely notifies the Administrator of its selection
- "(2) UPDATING.—Prior to distributing 2019 vintage year emission allowances and at 3-year intervals thereafter, the Administrator shall update the distribution formula under this subsection to reflect changes in each natural gas local distribution company's service territory since the most recent formula was established. For each successive 3-year period, the Administrator shall distribute allowances ratably among natural gas local distribution companies based on the product of—
- "(A) each natural gas local distribution company's average annual natural gas deliveries per customer to customers that were non-covered entities during calendar years 2006 through 2008, or during the 3 alternative consecutive years selected by such company under paragraph (1); and
- "(B) the number of customers of such natural gas local distribution company that are not covered entities in the most recent year in which the formula is updated under this paragraph.
 - "(c) USE OF ALLOWANCES.—

- "(1) RATEPAYER BENEFIT.—Emission allowances distributed to a natural gas local distribution company under this section shall be used exclusively for the benefit of retail ratepayers of such natural gas local distribution company other than covered entities and may not be used to support natural gas sales or deliveries to entities or persons other than such ratepayers.
- "(2) RATEPAYER CLASSES.—In using emission allowances distributed under this section for the benefit of ratepayers, a natural gas local distribution company shall ensure that ratepayer benefits are distributed—
- "(A) among ratepayer classes ratably based on natural gas deliveries to each class, excluding deliveries to covered entities; and
- "(B) equitably among individual ratepayers other than covered entities within each ratepayer class.
- "(3) LIMITATION.—In general, a natural gas local distribution company shall not use the value of emission allowances distributed under this section to provide to any rate-payer a rebate that is based solely on the quantity of natural gas delivered to such ratepayer. To the extent a natural gas local distribution company uses the value of emission allowances distributed under this section to provide rebates, it shall, to the maximum extent practicable, provide such rebates with regard to the fixed portion of ratepayers' bills or as a fixed creditor rebate on natural gas bills.
- "(4) INDUSTRIAL RATEPAYERS.—Notwithstanding paragraph (3), if compliance with the requirements of this title results (or would otherwise result) in an increase in natural gas costs for industrial retail ratepayers of any given natural gas local distribution company that are not covered entities (including entities that receive emission allowances pursuant to part F), such natural gas local distribution company—
- "(A) shall pass through to industrial retail ratepayers that are not covered entities their ratable share (based on deliveries to each ratepayer class) of the value of the emission allowances distributed to such company under this subsection, to reduce natural gas cost impacts on such ratepayers; and
- "(B) may do so based on the quantity of natural gas delivered to individual industrial retail ratepayers.
- "(5) ENERGY EFFICIENCY PROGRAMS.—The value of no less than one third of the emission allowances distributed to natural gas local distribution companies pursuant to this section in any calendar year shall be used for cost-effective energy efficiency programs for natural gas consumers. Such programs must be authorized and overseen by the State regulatory authority, or by the entity with authority to regulate or set retail natural gas rates in the case of a natural gas local distribution company that is not regulated by a State regulatory authority.
- "(6) CERTAIN INTRACOMPANY DELIVERIES.—If a natural gas local distribution company makes an intracompany delivery of natural gas to a customer that is not a covered entity, for which such company is required to hold emission allowances under section 722, such customer shall, for purposes of this section, be considered a retail ratepayer and a member of a ratepayer class to be determined by the relevant State regulatory authority, or other entity with authority to regulate or set natural gas rates in the case of a company not regulated by a State regulatory authority.
- "(7) GUIDELINES.—As part of the regulations promulgated under subsection (h), the Administrator shall, after consultation with State regulatory authorities, prescribe guidelines for the implementation of the requirements of this subsection. Such guide-

lines shall include requirements to ensure that industrial retail ratepayers that are not covered entities (including entities that receive emission allowances under part F) receive their ratable share of the value of the allowances distributed to each natural gas local distribution company pursuant to this section.

"(d) Regulatory Proceedings.—

- "(1) REQUIREMENT.—No natural gas local distribution company shall be eligible to receive emission allowances under this section unless the State regulatory authority with authority over the retail rates of such company, or the entity with authority to regulate or set retail rates of a natural gas local distribution company not regulated by a State regulatory authority, has—
- "(A) after public notice and an opportunity for comment, promulgated a regulation or completed a public rate proceeding (or the equivalent, in the case of a ratemaking entity other than a State regulatory authority) that provides for the full implementation of the requirements of subsection (c); and
- "(B) made available to the Administrator and the public a report describing, in adequate detail, the manner in which the requirements of subsection (c) will be implemented.
- "(2) UPDATING.—The Administrator shall require, as a condition of continued receipt of emission allowances under this section, that a new regulation be promulgated or rate proceeding be completed, after public notice and an opportunity for comment, and a new report be made available to the Administrator and the public, pursuant to paragraph (1), not less frequently than every 5 years.
 - "(e) PLANS AND REPORTING.-
- "(1) REGULATIONS.—As part of the regulations promulgated under subsection (h), the Administrator shall prescribe requirements governing plans and reports to be submitted in accordance with this subsection.
- "(2) PLANS.—Not later than April 30 of 2015 and every 5 years thereafter through 2025, each natural gas local distribution company shall submit to the Administrator a plan, approved by the State regulatory authority or other entity charged with regulating or setting the retail rates of such company, describing such company's plans for the disposition of the value of emission allowances to be received pursuant to this section, in accordance with the requirements of this section.
- "(3) REPORTS.—Not later than June 30 of 2017 and each calendar year thereafter through 2031, each natural gas local distribution company shall submit a report to the Administrator, approved by the relevant State regulatory authority or other entity charged with regulating or setting the retail natural gas rates of such company, describing the disposition of the value of any emission allowances received by such company in the prior calendar year pursuant to this section, including—
- "(A) a description of sales, transfer, exchange, or use by the company for compliance with obligations under this title, of any such emission allowances;
- "(B) the monetary value received by the company, whether in money or in some other form, from the sale, transfer, or exchange of emission allowances received by the company under this section;
- "(C) the manner in which the company's disposition of emission allowances received under this section complies with the requirements of this section, including each of the requirements of subsection (c):
- "(D) the cost-effectiveness of, and energy savings achieved by, energy efficiency programs supported through such emission allowances; and

- "(E) such other information as the Administrator may require pursuant to paragraph (1).
- "(4) PUBLICATION.—The Administrator shall make available to the public all plans and reports submitted by natural gas local distribution companies under this subsection, including by publishing such plans and reports on the Interport
- and reports on the Internet.

 "(f) AUDITS.—Each year, the Administrator shall audit a representative sample of natural gas local distribution companies to ensure that emission allowances distributed under this section have been used exclusively for the benefit of retail ratepayers and that such companies are complying with the requirements of this section. In selecting companies for audit, the Administrator shall take into account any credible evidence of noncompliance with such requirements. The Administrator shall make available to the public a report describing the results of each such audit, including by publishing such report on the Internet.
- "(g) ENFORCEMENT.—A violation of any requirement of this section shall be a violation of this Act. Each emission allowance the value of which is used in violation of the requirements of this section shall be a separate violation.
- "(h) REGULATIONS.—Not later than January 1, 2014, the Administrator, in consultation with the Federal Energy Regulatory Commission, shall promulgate regulations to implement the requirements of this section.
- "SEC. 785. HOME HEATING OIL, PROPANE, AND KEROSENE CONSUMERS.
- "(a) DEFINITIONS.—For purposes of this section:
- "(1) CARBON CONTENT.—The term 'carbon content' means the amount of carbon dioxide that would be emitted as a result of the combustion of a fuel.
- "(2) Cost-effective.—The term 'cost-effective' has the meaning given that term in section 784(a)(1).
- "(3) OILHEAT FUEL.—The term 'oilheat fuel' means fuel that—
 - "(A) is-
 - "(i) No. 1 distillate;
 - "(ii) No. 2 dyed distillate;
- "(iii) a liquid blended with No. 1 distillate or No. 2 dved distillate: or
- "(iv) a biobased liquid; and
- "(B) is used as a fuel for nonindustrial commercial or residential space or hot water heating.
- "(b) DISTRIBUTION AMONG STATES.—Not later than September 30 of each of calendar years 2011 through 2028, the Administrator shall distribute among the States, in accordance with this section, the quantity of emission allowances allocated for the following vintage year pursuant to section 782(c). The Administrator shall distribute emission allowances among the States under this section each year ratably based on the ratio
- "(1) the carbon content of oilheat fuel, propane, and kerosene sold to consumers within each State in the preceding year for residential or commercial uses; to
- "(2) the carbon content of oilheat fuel, propane, and kerosene sold to consumers within the United States in the preceding year for residential or commercial uses.
- "(c) USE OF ALLOWANCES.—
- "(1) In General.—States shall use emission allowances distributed under this section exclusively for the benefit of consumers of oilheat fuel, propane, or kerosene for residential or commercial purposes. Such proceeds shall be used exclusively for—
- "(A) cost-effective energy efficiency programs for consumers that use oilheat fuel, propane, or kerosene for residential or commercial purposes; or
- "(B) rebates or other direct financial assistance programs for consumers of oilheat

fuel, propane, or kerosene used for residential or commercial purposes.

"(2) ADMINISTRATION AND DELIVERY MECHANISMS.—In administering programs supported by this section, States shall

"(A) use no less than 50 percent of the value of emission allowances received under this section for cost-effective energy efficiency programs to reduce consumers' overall fuel costs:

"(B) to the extent practicable, deliver consumer support under this section through existing energy efficiency and consumer energy assistance programs or delivery mechanisms, including, where appropriate, programs or mechanisms administered by parties other than the State; and

"(C) seek to coordinate the administration and delivery of energy efficiency and consumer energy assistance programs supported under this section, with one another and with existing programs for various fuel types, so as to deliver comprehensive, fuel-blind, coordinated programs to consumers.

"(d) REPORTING.—Each State receiving emission allowances under this section shall submit to the Administrator, within 12 months of each receipt of such allowances, a report, in accordance with such requirements as the Administrator may prescribe, that.—

"(1) describes the State's use of emission allowances distributed under this section, including a description of the energy efficiency and consumer assistance programs supported with such allowances;

"(2) demonstrates the cost-effectiveness of, and the energy savings and greenhouse gas emissions reductions achieved by, energy efficiency programs supported under this section: and

"(3) includes a report prepared by an independent third party, in accordance with such regulations as the Administrator may promulgate, evaluating the performance of the energy efficiency and consumer assistance programs supported under this section.

"(e) ENFORCEMENT.—If the Administrator determines that a State is not in compliance with this section, the Administrator may withhold a portion of the emission allowances, the quantity of which is equal to up to twice the quantity of the allowances that the State failed to use in accordance with the requirements of this section, that such State would otherwise be eligible to receive under this section in later years. Allowances withheld pursuant to this subsection shall be distributed among the remaining States ratably in accordance with the formula in subsection (b).

"SEC. 787. ALLOCATIONS TO REFINERIES.

"(a) PURPOSE.—The purpose of this section is to provide emission allowance rebates to petroleum refineries in the United States in a manner that promotes energy efficiency and a reduction in greenhouse gas emissions at such facilities.

"(b) DEFINITIONS.—In this section:

"(1) EMISSIONS.—The term 'emissions' includes direct emissions from fuel combustion, process emissions, and indirect emissions from the generation of electricity, steam, and hydrogen used to produce the output of a petroleum refinery or the petroleum refinery sector.

"(2) PETROLEUM REFINERY.—The term 'petroleum refinery' means a facility classified under code 324110 of the North American Industrial Classification System of 2002.

"(3) SMALL BUSINESS REFINER.—The term 'small business refiner' means a refiner that meets the applicable Federal refinery capacity and employee limitations criteria described in section 45H(c)(1) of the Internal Revenue Code of 1986 (as in effect on the date of enactment of this section and without re-

gard to section 45H(d)). Eligibility of a small business refiner under this paragraph shall not be recalculated or disallowed on account of (i) its merger with another small business refiner or refiners after December 31, 2002 or (ii) its acquisition of another small business refiner (or refinery of such refiner) after December 31, 2002.

"(c) IN GENERAL.—For each vintage year between 2014 and 2026, the Administrator shall distribute allowances pursuant to this section to owners and operators of petroleum refineries, including small business refiners, in the United States.

"(d) DISTRIBUTION SCHEDULE.—The Administrator shall distribute emission allowances pursuant to the regulations issued under subsection (e) for each vintage year no later than October 31 of the preceding calendar year

"(e) REGULATIONS.—Not later than 3 years after the date of enactment of this title, the Administrator, in consultation with the Administrator of the Energy Information Administration, shall promulgate regulations that establish a formula for distributing emission allowances consistent with the purpose of this section. In establishing such formula, the Administrator shall consider the relative complexity of refinery processes and appropriate mechanisms to take energy efficiency and greenhouse gas reductions into account. If a petroleum refinery's electricity provider received a free allocation of emission allowances pursuant to section 782(a). the Administrator shall take this free allocation into account when establishing such formula to avoid rebates to a petroleum refinery for costs that the Administrator determines were not incurred by the petroleum refinery because the allowances were freely allocated to the petroleum refinery's electricity provider and used for the benefit of the petroleum refinery. This formula shall apply separately to the distribution of allowances allocated pursuant to section 782(j)(1) and to those allocated under section 782(i)(2).

"SEC. 788. SUPPLEMENTAL AGRICULTURE AND RENEWABLE ENERGY INCENTIVES PROGRAMS.

"(a) IN GENERAL.—Emission allowances allocated pursuant to section 782(u) shall be distributed by the Administrator at the direction of the Secretary of Energy and the Secretary of Agriculture in accordance with this section. Not less than 50 percent of the allowances shall be available for the program established pursuant to subsection (b). "(b) AGRICULTURE INCENTIVES PROGRAM.—

"(1) ESTABLISHMENT.—The Secretary of Agriculture shall establish by rule a program to provide incentives in the form of emission allowances for activities undertaken in the agriculture sector that reduce greenhouse gas emissions or sequester carbon. Under this program, the Secretary of Agriculture shall provide incentives for projects and activities that—

"(A) reduce or avoid greenhouse gas emissions, or sequester greenhouse gases, but do not meet the criteria for offset credits established under the American Clean Energy and Security Act of 2009;

"(B) support actions to adapt to climate change; or

"(C) prevent conversion of land that would increase greenhouse gas emissions (including projects and activities that complement or supplement conservation programs administered by the Secretary).

"(2) CONSIDERATIONS.—In designing this program, the Secretary shall ensure that it provides support for—

"(A) development and demonstration of practices to reduce greenhouse gas emissions or sequester carbon in agricultural operations where there are limited recognized opportunities to achieve such emissions reductions or sequestration; and

"(B) projects that reduce greenhouse gas emissions or increase sequestration of greenhouse gases and also achieve other significant environmental benefits, such as the improvement of water or air quality.

"(3) RESEARCH.—The Secretary shall establish by rule a program to conduct research to develop additional projects and activities for crops to find additional techniques and methods to reduce greenhouse gas emissions or sequester greenhouse gases that may or may not meet the criteria for offset credits established under the American Clean Energy and Security Act of 2009.

"(4) USE OF INFORMATION.—Information and data generated by this program should, where relevant, be used to inform the development of additional offset practices and methodologies.

"(c) RENEWABLE ENERGY INCENTIVES PROGRAM.—The Secretary of Energy and the Administrator shall establish by rule a program to provide allowances to State and local governments to support the deployment of renewable energy infrastructure."

"SEC. 789. CLIMATE CHANGE CONSUMER RE-FUNDS.

"(a) REFUND.—In each year after deposits are made to the Climate Change Consumer Refund Account, the Secretary of the Treasury shall provide tax refunds on a per capita basis to each household in the United States that shall collectively equal the amount deposited into the Climate Change Consumer Refund Account.

"(b) LIMITATIONS.—The Secretary of the Treasury shall establish procedures to ensure that individuals who are not—

"(1) citizens or nationals of the United States: or

"(2) immigrants lawfully residing in the United States.

United States, are excluded for the purpose of calculating and distributing refunds under this section.

"SEC. 790. EXCHANGE FOR STATE-ISSUED ALLOW-ANCES.

"(a) IN GENERAL.—Not later than one year after the date of enactment of this title, the Administrator shall issue regulations allowing any person in the United States to exchange greenhouse gas emission allowances issued before December 31, 2011, by the State of California or for the Regional Greenhouse Gas Initiative, or the Western Climate Initiative (in this section referred to as 'State allowances') for emission allowances established by the Administrator under section

"(b) REGULATIONS.—Regulations issued under subsection (a) shall—

"(1) provide that a person exchanging State allowances under this section receive emission allowances established under section 721(a) in the amount that is sufficient to compensate for the cost of obtaining and holding such State allowances;

"(2) establish a deadline by which persons must exchange the State allowances;

"(4) require that, once exchanged, the credit or other instrument be retired for purposes of use under the program by or for which it was originally issued.

"(5) provide that the Federal emission allowances disbursed pursuant to this section shall be deducted from the allowances to be auctioned pursuant to section 782(d); and

"(c) Cost of Obtaining State Allow-Ance.—For purposes of this section, the cost of obtaining a State allowance shall be the average auction price, for emission allowances issued in the year in which the State allowance was issued, under the program under which the State allowance was issued. "SEC. 791. AUCTION PROCEDURES.

"(a) IN GENERAL.—To the extent that auctions of emission allowances by the Administrator are authorized by this part, such auctions shall be carried out pursuant to this

section and the regulations established hereunder.

- "(b) INITIAL REGULATIONS.—Not later than 12 months after the date of enactment of this title, the Administrator, in consultation with other agencies, as appropriate, shall promulgate regulations governing the auction of allowances under this section. Such regulations shall include the following requirements:
- "(1) FREQUENCY; FIRST AUCTION.—Auctions shall be held four times per year at regular intervals, with the first auction to be held no later than March 31, 2011.
- "(2) AUCTION SCHEDULE: CURRENT AND FU-TURE VINTAGES.—The Administrator shall, at each quarterly auction under this section. offer for sale both a portion of the allowances with the same vintage year as the year in which the auction is being conducted and a portion of the allowances with vintage years from future years. The preceding sentence shall not apply to auctions held before 2012, during which period, by necessity, the Administrator shall auction only allowances with a vintage year that is later than the year in which the auction is held. Beginning with the first auction and at each quarterly auction held thereafter, the Administrator may offer for sale allowances with vintage years of up to four years after the year in which the auction is being conducted, except as provided in section 782(p).
- "(3) AUCTION FORMAT.—Auctions shall follow a single-round, sealed-bid, uniform price format.
- "(4) PARTICIPATION; FINANCIAL ASSUR-ANCE.—Auctions shall be open to any person, except that the Administrator may establish financial assurance requirements to ensure that auction participants can and will perform on their bids.
- "(5) DISCLOSURE OF BENEFICIAL OWNER-SHIP.—Each bidder in the auction shall be required to disclose the person or entity sponsoring or benefitting from the bidder's participation in the auction if such person or entity is, in whole or in part, other than the bidder.
- "(6) PURCHASE LIMITS.—No person may, directly or in concert with another participant, purchase more than 5 percent of the allowances offered for sale at any quarterly auction.
- "(7) PUBLICATION OF INFORMATION.—After the auction, the Administrator shall, in a timely fashion, publish the identities of winning bidders, the quantity of allowances obtained by each winning bidder, and the auction clearing price.
- "(8) OTHER REQUIREMENTS.—The Administrator may include in the regulations such other requirements or provisions as the Administrator, in consultation with other agencies, as appropriate, considers appropriate to promote effective, efficient, transparent, and fair administration of auctions under this section.
- (c) REVISION OF REGULATIONS.—The Administrator may, in consultation with other agencies, as appropriate, at any time, revise the initial regulations promulgated under subsection (b) by promulgating new regulations. Such revised regulations need not meet the requirements identified in subsection (b) if the Administrator determines that an alternative auction design would be more effective, taking into account factors including costs of administration, transparency, fairness, and risks of collusion or manipulation. In determining whether and how to revise the initial regulations under this subsection, the Administrator shall not consider maximization of revenues to the Federal Government
- "(d) RESERVE AUCTION PRICE.—The minimum reserve auction price shall be \$10 (in constant 2009 dollars) for auctions occurring

- in 2012. The minimum reserve price for auctions occurring in years after 2012 shall be the minimum reserve auction price for the previous year increased by 5 percent plus the rate of inflation (as measured by the Consumer Price Index for all urban consumers).
- "(e) DELEGATION OR CONTRACT.—Pursuant to regulations under this section, the Administrator may by delegation or contract provide for the conduct of auctions under the Administrator's supervision by other departments or agencies of the Federal Government or by nongovernmental agencies, groups, or organizations.
- "(f) SMALL BUSINESS REFINER RESERVE.— The Administrator shall, in accordance with this subsection, issue regulations setting aside a specified number of allowances that small business refiners may purchase at the average auction price and may use to demonstrate compliance pursuant to section 722. These regulations shall provide the following:
- "(1) AMOUNT.—The Administrator shall place in the small business refiner reserve account allowances that are to be sold at auction pursuant to the allocations in section 782 in an amount equal to—
- "(A) 6.2 percent of the emission allowances established under section 721(a) for each vintage year from 2012 through 2013:
- "(B) 5.4 percent of the emission allowances established under section 721(a) for each vintage year from 2014 through 2015; and
- "(C) 4.9 percent of the emission allowances established under section 721(a) for each vintage year from 2016 through 2024.
- "(2) ALLOWED PURCHASES.—From January 1 of the calendar year that matches the vintage year for which allowances have been placed in the reserve, through January 14 of the following year, small business refiners (as defined in section 787(b)) may purchase allowances from this reserve at the price determined pursuant to paragraph (3).
- "(3) PRICE.—The price for allowances purchased from this reserve shall be the average auction price for allowances of the same vintage year purchased at auctions conducted pursuant to this section during the 12 months preceding the purchase of the allowances.
- "(4) USE OF ALLOWANCES.—Allowances purchased from this reserve shall only be used by the purchaser to demonstrate compliance pursuant to section 722 for attributable greenhouse gas emissions in the calendar year that matches the vintage year of the purchased allowance. Allowances purchased from this reserve may not be banked, traded or borrowed.
- "(5) LIMITATIONS ON PURCHASE AMOUNT.— The Administrator, by regulation adopted after public notice and an opportunity for comment, shall establish procedures to distribute the ability to purchase allowances from the reserve fairly among all small business refiners interested in purchasing allowances from this reserve so as to address the potential that requests to purchase allowances exceed the number of allowances available in the reserve. This regulation may place limits on the number of allowances a small business refiner may purchase from the reserve.
- "(6) UNSOLD ALLOWANCES.—Vintage year allowances not sold from the reserve on or before January 15 of the calendar year following the vintage year shall be sold at an auction conducted pursuant to this section no later than March 31 of the calendar year following the vintage year. If significantly more allowances are being placed in the reserve than are being purchased from the reserve several years in a row, the Administrator may adjust either the percent of allowances placed in the reserve or the date by

which allowances may be purchased from the reserve.

"SEC. 792. AUCTIONING ALLOWANCES FOR OTHER ENTITIES.

- "(a) CONSIGNMENT.—Any entity holding emission allowances or compensatory allowances may request that the Administrator auction, pursuant to section 791, the allowances on consignment.
- "(b) PRICING.—When the Administrator acts under this section as the agent of an entity in possession of emission allowances or compensatory allowances, the Administrator is not obligated to obtain the highest price possible for the allowances, and instead shall auction consignment allowances in the same manner and pursuant to the same rules as auctions of other allowances under section 791. The Administrator may permit the entity offering the allowance for sale to condition the sale of its allowances pursuant to this section on a minimum reserve price that is different than the reserve auction price set pursuant to section 791(d).
- "(c) PROCEEDS.—For emission allowances and compensatory allowances auctioned pursuant to this section, notwithstanding section 3302 of title 31, United States Code, or any other provision of law, within 90 days of receipt, the United States shall transfer the proceeds from the auction to the entity which held the allowances auctioned. No funds transferred from a purchaser to a seller of emission allowances or compensatory allowances under this subsection shall be held by any officer or employee of the United States or treated for any purpose as public monies.
- "(d) UNSOLD ALLOWANCES.—Allowances offered for sale under this section that are not sold shall be returned to the entity in possession of the allowance, notwithstanding section 726(b)(2)(A).
- "(e) REGULATIONS.—The Administrator shall issue regulations within 24 months after the date of enactment of this title to implement this section.

"SEC. 793. ESTABLISHMENT OF FUNDS.

- "There is hereby established in the Treasury of the United States the following separate accounts:
 - "(1) The Strategic Reserve Fund.
- "(2) The Climate Change Consumer Refund Account.
- "(3) The Climate Change Worker Adjustment Assistance Fund.

"SEC. 794. OVERSIGHT OF ALLOCATIONS.

- "(a) IN GENERAL.—Not later than January 1, 2014, and every 2 years thereafter, the Comptroller General of the United States shall carry out and report to Congress on the results of a review of programs administered by the Federal Government that distribute emission allowances or funds from any Federal auction of allowances.
- "(b) CONTENTS.—Each such report shall include a comprehensive evaluation of the administration and effectiveness of each program, including—
- "(1) the efficiency, transparency, and soundness of the administration of each program;
- "(2) the performance of activities receiving assistance under each program;
- "(3) the cost-effectiveness of each program in achieving the stated purposes of the program; and
- "(4) recommendations, if any, for legislative, regulatory, or administrative changes to each program to improve its effectiveness.
- "(c) Focus.—In evaluating program performance, each review under this section review shall address the effectiveness of such programs in—
 - "(1) creating and preserving jobs;
- "(2) ensuring a manageable transition for working families and workers;

- "(3) reducing the emissions, or enhancing sequestration, of greenhouse gases;
- "(4) developing clean technologies; and
- "(5) building resilience to the impacts of climate change.

"SEC. 795. EXCHANGE FOR EARLY ACTION OFF-SET CREDITS.

"(a) IN GENERAL.—Emission allowances allocated pursuant to section 782(t) shall be distributed by the Administrator in accordance with this section. Not later than one year after the date of enactment of this title, the Administrator shall issue regulations allowing—

"(1) any person in the United States to exchange instruments in the nature of offset credits issued before January 1, 2009, by a State or voluntary offset program with respect to which the Administrator has made an affirmative determination under section 740(a)(2), for emissions allowances established by the Administrator under section 721(a); and

"(2) the Administrator to provide compensation in the form of emission allowances to entities that do not meet the criteria of paragraph (1) and meet the criteria of this paragraph for documented early reductions or avoidance of greenhouse gas emissions or greenhouse gases sequestered before January 1, 2009, from projects begun before January 1, 2009 where—

"(A) the entity publicly stated greenhouse gas reduction goals and publicly reported against those goals;

"(B) the entity demonstrated entity-wide net greenhouse gas reductions; and

"(C) the entity demonstrates the actual projects undertaken to make reductions and documents the reductions (e.g., through documentation of engineering projects).

"(b) REGULATIONS.—Regulations issued under subsection (a) shall—

"(1) provide that a person exchanging credits under subsection (a)(1) receive emission allowances established under section 721(a) in an amount for which the monetary value is equivalent to the average monetary value of the credits during the period from January 1, 2006, to January 1, 2009, as adjusted for inflation to reflect current dollar values at the time of the exchange;

"(2) provide that a person receiving compensation for documented early action under subsection (a)(2) shall receive emission allowances established under section 721(a) in an amount that is approximately equivalent in value to the carbon dioxide equivalent per ton value received by entities in exchange for credits under paragraph (1) (as adjusted for inflation to reflect current dollar values at the time of the exchange), as determined by the Administrator:

"(3) provide that only reductions or avoidance of greenhouse gas emissions, or sequestration of greenhouse gases, achieved by activities in the United States between January 1, 2001, and January 1, 2009, may be compensated under this section, and only credits issued for such activities may be exchanged under this section:

"(4) provide that only credits that have not been retired or otherwise used to meet a voluntary or mandatory commitment, and have not expired, may be exchanged under sub-

section (a)(1);

"(5) require that, once exchanged, the credit be retired for purposes of use under the program by or for which it was originally issued; and

"(6) establish a deadline by which persons must exchange the credits or request compensation for early action under this section.

"(c) Participation.—Participation in an exchange of credits for allowances or compensation for early action authorized by this section shall not preclude any person from participation in an offset credit program es-

tablished under the American Clean Energy and Security Act of 2009.

"(d) DISTRIBUTION.—Of the emission allowances distributed under this section, a quantity equal to 0.75 percent of vintage year 2012 emission allowances established under section 721(a) shall be distributed pursuant to subsection (a)(1), and a quantity equal to 0.25 percent of vintage year 2012 emission allowances established under section 721(a) shall be distributed pursuant to subsection (a)(2)."

Subtitle C—Additional Greenhouse Gas Standards

SEC. 331. GREENHOUSE GAS STANDARDS.

The Clean Air Act (42 U.S.C. 7401 and following), as amended by subtitles A and B of this title, is further amended by adding the following new title after title VII:

"TITLE VIII—ADDITIONAL GREENHOUSE GAS STANDARDS

"SEC. 801. DEFINITIONS.

"For purposes of this title, terms that are defined in title VII, except for the term 'stationary source', shall have the meaning given those terms in title VII.

"PART A—STATIONARY SOURCE STANDARDS

"SEC. 811. STANDARDS OF PERFORMANCE.

"(a) Uncapped Stationary Sources.—

"(1) INVENTORY OF SOURCE CATEGORIES.—(A) Within 12 months after the date of enactment of this title, the Administrator shall publish under section 111(b)(1)(A) an inventory of categories of stationary sources that consist of those categories that contain sources that individually had uncapped greenhouse gas emissions greater than 10,000 tons of carbon dioxide equivalent and that, in the aggregate, were responsible for emitting at least 20 percent annually of the uncapped greenhouse gas emissions.

"(B) The Administrator shall include in the inventory under this paragraph each source category that is responsible for at least 10 percent of the uncapped methane emissions in 2005. Notwithstanding any other provision, the inventory required by this section shall not include sources of enteric fermentation. The list under this paragraph shall include industrial sources, the emissions from which, when added to the capped emissions from industrial sources, constitute at least 95 percent of the greenhouse gas emissions of the industrial sector.

"(C) For purposes of this subsection, emissions shall be calculated using tons of carbon dioxide equivalents. In promulgating the inventory required by this paragraph and the schedule required under by paragraph (2)(C), the Administrator shall use the most current emissions data available at the time of promulgation, except as provided in subparagraph (B).

"(D) Notwithstanding any other provisions, the Administrator may list under 111(b) any source category identified in the inventory required by this subsection without making a finding that the source category causes or contributes significantly to, air pollution with may be reasonably anticipated to endanger public health or welfare.

"(2) STANDARDS AND SCHEDULE.—(A) For each category identified as provided in paragraph (1), the Administrator shall promulgate standards of performance under section 111 for the uncapped emissions of greenhouse gases from stationary sources in that category and shall promulgate corresponding regulations under section 111(d).

"(B) The Administrator shall promulgate standards as required by this subsection for stationary sources in categories identified as provided in paragraph (1) as expeditiously as practicable, assuring that—

"(i) standards for identified source categories that, combined, emitted 80 percent or

more of the greenhouse gas emissions of the identified source categories shall be promulgated not later than 3 years after the date of enactment of this title and shall include standards for natural gas extraction; and

"(ii) for all other identified source categories—

"(I) standards for not less than an additional 25 percent of the identified categories shall be promulgated not later than 5 years after the date of enactment of this title;

"(II) standards for not less than an additional 25 percent of the identified categories shall be promulgated not later than 7 years after the date of enactment of this title; and

"(III) standards for all the identified categories shall be promulgated not later than 10 years after the date of enactment of this title.

"(C) Not later than 24 months after the date of enactment of this title and after notice and opportunity for comment, the Administrator shall publish a schedule establishing a date for the promulgation of standards for each category of sources identified pursuant to paragraph (1). The date for each category shall be consistent with the requirements of subparagraph (B). The determination of priorities for the promulgation of standards pursuant to this paragraph is not a rulemaking and shall not be subject to judicial review, except that failure to promulgate any standard pursuant to the schedule established by this paragraph shall be subject to review under section 304(a)(2).

"(D) Notwithstanding section 307, no action of the Administrator listing a source category under paragraph (1) shall be a final agency action subject to judicial review, except that any such action may be reviewed under section 307 when the Administrator issues performance standards for such category.

"(b) CAPPED SOURCES.—No standard of performance shall be established under section 111 for capped greenhouse gas emissions from a capped source unless the Administrator determines that such standards are appropriate because of effects that do not include climate change effects. In promulgating a standard of performance under section 111 for the emission from capped sources of any air pollutant that is not a greenhouse gas, the Administrator shall treat the emission of any greenhouse gas by those entities as a nonair quality public health and environmental impact within the meaning of section 111(a)(1).

"(c) PERFORMANCE STANDARDS.—For purposes of setting a performance standard for source categories identified pursuant to subsection (a)—

"(1) The Administrator shall take into account the goal of reducing total United States greenhouse gas emissions as set forth in section 702.

"(2) The Administrator may promulgate a design, equipment, work practice, or operational standard, or any combination thereof, under section 111 in lieu of a standard of performance under that section without regard to any determination of feasibility that would otherwise be required under section 111(h).

"(3) Notwithstanding any other provision, in setting the level of each standard required by this section, the Administrator shall take into account projections of allowance prices, such that the marginal cost of compliance (expressed as dollars per ton of carbon dioxide equivalent reduced) imposed by the standard would not, in the judgement of the Administrator, be expected to exceed the Administrator's projected allowance prices over the time period spanning from the date of initial compliance to the date that the next

revisions of the standard would come into effect pursuant to the schedule under section

"(d) DEFINITIONS.—In this section, the terms 'uncapped greenhouse gas emissions' and 'uncapped methane emissions' mean those greenhouse gas or methane emissions, respectively, to which section 722 would not have applied if the requirements of this title had been in effect for the same year as the emissions data upon which the list is based.

"(e) Study of the Effects of Perform-ANCE STANDARDS.

"(1) STUDY.—The Administrator shall conduct a study of the impacts of performance standards required under this section, which shall evaluate the effect of such standards on

"(A) costs of achieving compliance with the economy-wide reduction goals specified in section 702 and the reduction targets specified in section 703;

(B) available supply of offset credits; and "(C) ability to achieve the economy-wide reduction goals specified in section 702 and any other benefits of such standards.

(2) REPORT.—The Administrator shall submit to the House Energy and Commerce Committee a report that describes the results of the study not later than 18 months after the publication of the standards required under subsection (a)(2)(B)(i).

"PART C-EXEMPTIONS FROM OTHER **PROGRAMS**

"SEC. 831. CRITERIA POLLUTANTS.

"As of the date of the enactment of the Safe Climate Act, no greenhouse gas may be added to the list under section 108(a) on the basis of its effect on global climate change.

"SEC. 832. INTERNATIONAL AIR POLLUTION.

'Section 115 shall not apply to an air pollutant with respect to that pollutant's contribution to global warming.

"SEC. 833. HAZARDOUS AIR POLLUTANTS.

"No greenhouse gas may be added to the list of hazardous air pollutants under section 112 unless such greenhouse gas meets the listing criteria of section 112(b) independent of its effects on global climate change.

"SEC. 834. NEW SOURCE REVIEW.

"The provisions of part C of title I shall not apply to a major emitting facility that is initially permitted or modified after January 1, 2009, on the basis of its emissions of any greenhouse gas.

"SEC. 835. TITLE V PERMITS.

'Notwithstanding any provision of title III or V. no stationary source shall be required to apply for, or operate pursuant to, a permit under title V. solely because the source emits any greenhouse gases that are regulated solely because of their effect on global climate change."

SEC. 332. HFC REGULATION.

(a) IN GENERAL.—Title VI of the Clean Air Act (42 U.S.C. 7671 et seq.) (relating to stratospheric ozone protection) is amended by adding at the end the following:

"SEC, 619, HYDROFLUOROCARBONS (HFCS),

"(a) Treatment as Class II. Group II Sub-STANCES.—Except as otherwise provided in this section, hydrofluorocarbons shall be treated as class II substances for purposes of applying the provisions of this title. The Administrator shall establish two groups of class II substances. Class II, group I subshall stances include hydrochlorofluorocarbons (HCFCs) pursuant to section 602(b). Class II, group II substances shall include each of the fol-

- "(1) Hydrofluorocarbon-23 (HFC-23). "(2) Hydrofluorocarbon-32 (HFC-32).
- "(3) Hydrofluorocarbon-41 (HFC-41).
- "(4) Hydrofluorocarbon-125 (HFC-125).
- "(5) Hydrofluorocarbon-134 (HFC-134).

- "(6) Hydrofluorocarbon-134a (HFC-134a).
- "(7) Hydrofluorocarbon-143 (HFC-143).
- "(8) Hydrofluorocarbon-143a (HFC-143a).
- "(9) Hydrofluorocarbon-152 (HFC-152).
- "(10) Hydrofluorocarbon-152a (HFC-152a). "(11) Hydrofluorocarbon-227ea (HFC-227ea).
- "(12) Hydrofluorocarbon-236cb (HFC-236cb).
- "(13) Hydrofluorocarbon-236ea (HFC-236ea).
- "(14) Hydrofluorocarbon-236fa (HFC-236fa). "(15) Hydrofluorocarbon-245ca (HFC-245ca).
- "(16) Hydrofluorocarbon-245fa (HFC-245fa). Hydrofluorocarbon-365mfc 365mfc).
- "(18) Hydrofluorocarbon-43-10mee (HFC-43-

"(19) Hydrofluoroolefin-1234yf (HFO-1234yf). "(20) Hydrofluoroolefin-1234ze (HFO-1234ze). Not later than 6 months after the date of enactment of this title, the Administrator shall publish an initial list of class II, group II substances, which shall include the substances listed in this subsection. The Administrator may add to the list of class II, group II substances any other substance used as a substitute for a class I or II substance if the Administrator determines that 1 metric ton of the substance makes the same or greater contribution to global warming over 100 years as 1 metric ton of carbon dioxide. Within 24 months after the date of enactment of this section, the Administrator shall amend the regulations under this title (including the regulations referred to in sections 603, 608, 609, 610, 611, 612, and 613) to apply to class II, group II substances.

(b) Consumption and Production of CLASS II, GROUP II SUBSTANCES.

"(1) IN GENERAL.

"(A) CONSUMPTION PHASE DOWN.—In the case of class II, group II substances, in lieu of applying section 605 and the regulations thereunder, the Administrator shall promulgate regulations phasing down the consumption of class II, group II substances in the United States, and the importation of products containing any class II, group II substance, in accordance with this subsection within 18 months after the date of enactment of this section. Effective January 1, 2012, it shall be unlawful for any person to produce any class II, group II substance, import any class II, group II substance, or import any product containing any class II, group II substance without holding one consumption allowance or one destruction offset credit for each carbon dioxide equivalent ton of the class II, group II substance. Any person who exports a class II, group II substance for which a consumption allowance was retired may receive a refund of that allowance from the Administrator following the export.

"(B) PRODUCTION.—If the United States becomes a party or otherwise adheres to a multilateral agreement, including any amendment to the Montreal Protocol on Substances That Deplete the Ozone Layer, that restricts the production of class II, group II substances, the Administrator shall promulgate regulations establishing a baseline for the production of class II, group II substances in the United States and phasing down the production of class II, group II substances in the United States, in accordance with such multilateral agreement and subject to the same exceptions and other provisions as are applicable to the phase down of consumption of class II, group II substances under this section (except that the Administrator shall not require a person who obtains production allowances from the Administrator to make payment for such allowances if the person is making payment for a corresponding quantity of consumption allowances of the same vintage year). Upon the effective date of such regulations, it shall be unlawful for any person to produce any class II, group II substance without holding one consumption allowance and one production

allowance, or one destruction offset credit, for each carbon dioxide equivalent ton of the class II, group II substance.

"(C) INTEGRITY OF CAP.—To maintain the integrity of the class II, group II cap, the Administrator may, through rulemaking, limit the percentage of each person's compliance obligation that may be met through the use of destruction offset credits or banked allowances.

"(D) COUNTING OF VIOLATIONS.—Each consumption allowance, production allowance, or destruction offset credit not held as required by this section shall be a separate violation of this section.

"(2) SCHEDULE.—Pursuant to the regulations promulgated pursuant to paragraph (1)(A), the number of class II, group II consumption allowances established by the Administrator for each calendar year beginning in 2012 shall be the following percentage of the baseline, as established by the Administrator pursuant to paragraph (3):

"Calendar Year	Percent of Baseline
2012	90
2013	87.5
2014	85
2015	82.5
2016	80
2017	77.5
2018	75
2019	71
2020	67
2021	63
2022	59
2023	54
2024	50
2025	46
2026	42
2027	38
2028	34
2029	30
2030	25
2031	21
2032	17
after 2032	15

"(3) BASELINE.—(A) Within 12 months after the date of enactment of this section, the Administrator shall promulgate regulations to establish the baseline for purposes of paragraph (2). The baseline shall be the sum, expressed in metric tons of carbon dioxide equivalents, of-

"(i) the annual average consumption of all class II substances in calendar years 2004, 2005, and 2006; plus

"(ii) the annual average quantity of all class II substances contained in imported products in calendar years 2004, 2005, and 2006.

"(B) Notwithstanding subparagraph (A), if the Administrator determines that the baseline is higher than 370 million metric tons of carbon dioxide equivalents, then the Administrator shall establish the baseline at 370 million metric tons of carbon dioxide equiva-

"(C) Notwithstanding subparagraph (A), if the Administrator determines that the baseline is lower than 280 million metric tons of carbon dioxide equivalents, then the Administrator shall establish the baseline at 280 million metric tons of carbon dioxide equiva-

"(4) DISTRIBUTION OF ALLOWANCES.-

"(A) IN GENERAL.—Pursuant to the regulations promulgated under paragraph (1)(A), for each calendar year beginning in 2012, the Administrator shall sell consumption allowances in accordance with this paragraph.

'(B) ESTABLISHMENT OF POOLS.—The Administrator shall establish two allowance pools. Eighty percent of the consumption allowances available for a calendar year shall be placed in the producer-importer pool, and 20 percent of the consumption allowances available for a calendar year shall be placed in the secondary pool.

(C) Producer-importer pool.

"(i) AUCTION.—(I) For each calendar year, the Administrator shall offer for sale at auction the following percentage of the consumption allowances in the producer-importer pool:

"Calendar Year	Percent Available for Auction
2012	10
2013	20
2014	30
2015	40
2016	50
2017	60
2018	70
2019	80
2020 and thereafter	90

"(II) Any person who produced or imported any class II substance during calendar year 2004, 2005, or 2006 may participate in the auction. No other persons may participate in the auction unless permitted to do so pursuant to subclause (III).

"(III) Not later than three years after the date of the initial auction and from time to time thereafter, the Administrator shall determine through rulemaking whether any persons who did not produce or import a class II substance during calendar year 2004. 2005, or 2006 will be permitted to participate in future auctions. The Administrator shall base this determination on the duration, consistency, and scale of such person's purchases of consumption allowances in the secondary pool under subparagraph (D)(ii)(III), as well as economic or technical hardship and other factors deemed relevant by the Administrator.

"(IV) The Administrator shall set a minimum bid per consumption allowance of the following:

"(aa) For vintage year 2012, \$1.00.

"(bb) For vintage year 2013, \$1.20.

"(cc) For vintage year 2014, \$1.40.

"(dd) For vintage year 2015, \$1.60.

"(ee) For vintage year 2016, \$1.80.

"(ff) For vintage year 2017, \$2.00.

"(gg) For vintage year 2018 and thereafter, \$2.00 adjusted for inflation after vintage year 2017 based upon the producer price index as published by the Department of Commerce.

"(ii) NON-AUCTION SALE .- (I) For each calendar year, as soon as practicable after auction, the Administrator shall offer for sale the remaining consumption allowances in the producer-importer pool at the following prices:

'(aa) A fee of \$1.00 per vintage year 2012 allowance.

'(bb) A fee of \$1.20 per vintage year 2013 allowance.

"(cc) A fee of \$1.40 per vintage year 2014 allowance.

"(dd) For each vintage year 2015 allowance, a fee equal to the average of \$1.10 and the auction clearing price for vintage year 2014 allowances.

"(ee) For each vintage year 2016 allowance, a fee equal to the average of \$1.30 and the auction clearing price for vintage year 2015 allowances.

"(ff) For each vintage year 2017 allowance, a fee equal to the average of \$1.40 and the auction clearing price for vintage year 2016 allowances.

'(gg) For each allowance of vintage year 2018 and subsequent vintage years, a fee equal to the auction clearing price for that vintage vear.

'(II) The Administrator shall offer to sell the remaining consumption allowances in the producer-importer pool to producers of class II. group II substances and importers of class II, group II substances in proportion to their relative allocation share.

'(III) Such allocation share for such sale shall be determined by the Administrator using such producer's or importer's annual average data on class II substances from calendar years 2004, 2005, and 2006, on a carbon dioxide equivalent basis, and-

'(aa) shall be based on a producer's production, plus importation, plus acquisitions and purchases from persons who produced class II substances in the United States during calendar years 2004, 2005, or 2006, less exportation, less transfers and sales to persons who produced class II substances in the United States during calendar years 2004, 2005, or 2006; and

"(bb) for an importer of class II substances that did not produce in the United States any class II substance during calendar years 2004, 2005, and 2006, shall be based on the importer's importation less exportation.

For purposes of item (aa), the Administrator shall account for 100 percent of class II, group II substances and 60 percent of class II, group I substances. For purposes of item (bb), the Administrator shall account for 100 percent of class II, group II substances and 100 percent of class II, group I substances.

(IV) Any consumption allowances made available for nonauction sale to a specific producer or importer of class II, group II substances but not purchased by the specific producer or importer shall be made available for sale to any producer or importer of class II substances during calendar years 2004, 2005, or 2006. If demand for such consumption allowances exceeds supply of such consumption allowances, the Administrator shall develop and utilize criteria for the sale of such consumption allowances that may include pro rata shares, historic production and importation, economic or technical hardship, or other factors deemed relevant by the Administrator. If the supply of such consumption allowances exceeds demand, the Administrator may offer such consumption allowances for sale in the secondary pool as set forth in subparagraph (D).

"(D) SECONDARY POOL .- (i) For each calendar year, as soon as practicable after the auction required in subparagraph (C), the Administrator shall offer for sale the consumption allowances in the secondary pool at the prices listed in subparagraph (C)(ii).

"(ii) The Administrator shall accept applications for purchase of secondary pool consumption allowances from-

"(I) importers of products containing class II, group II substances;

"(II) persons who purchased any class II, group II substance directly from a producer or importer of class II, group II substances for use in a product containing a class II, group II substance, a manufacturing process, or a reclamation process;

"(III) persons who did not produce or import a class II substance during calendar year 2004, 2005, or 2006, but who the Administrator determines have subsequently taken significant steps to produce or import a substantial quantity of any class II, group II substance; and

"(IV) persons who produced or imported any class II substance during calendar year 2004, 2005, or 2006.

"(iii) If the supply of consumption allowances in the secondary pool equals or exceeds the demand for consumption allowances in the secondary pool as presented in the applications for purchase, the Administrator shall sell the consumption allowances in the secondary pool to the applicants in the amounts requested in the applications for purchase. Any consumption allowances in the secondary pool not purchased in a calendar year may be rolled over and added to the quantity available in the secondary pool in the following year.

"(iv) If the demand for consumption allowances in the secondary pool as presented in the applications for purchase exceeds the supply of consumption allowances in the secondary pool, the Administrator shall sell the consumption allowances as follows:

"(I) The Administrator shall first sell the consumption allowances in the secondary pool to any importers of products containing class II, group II substances in the amounts requested in their applications for purchase. If the demand for such consumption allowances exceeds supply of such consumption allowances, the Administrator shall develop and utilize criteria for the sale of such consumption allowances among importers of products containing class II, group II substances that may include pro rata shares. historic importation, economic or technical hardship, or other factors deemed relevant by the Administrator.

'(II) The Administrator shall next sell any remaining consumption allowances to persons identified in subclauses (II) and (III) of clause (ii) in the amounts requested in their applications for purchase. If the demand for such consumption allowances exceeds remaining supply of such consumption allowances, the Administrator shall develop and utilize criteria for the sale of such consumption allowances among subclauses (II) and (III) applicants that may include pro rata shares, historic use, economic or technical hardship, or other factors deemed relevant by the Administrator.

"(III) The Administrator shall then sell any remaining consumption allowances to persons who produced or imported any class II substance during calendar year 2004, 2005, or 2006 in the amounts requested in their applications for purchase. If demand for such consumption allowances exceeds remaining supply of such consumption allowances, the Administrator shall develop and utilize criteria for the sale of such consumption allowances that may include pro rata shares, historic production and importation, economic or technical hardship, or other factors deemed relevant by the Administrator.

"(IV) Each person who purchases consumption allowances in a non-auction sale under this subparagraph shall be required to disclose the person or entity sponsoring or benefitting from the purchases if such person or

entity is, in whole or in part, other than the purchaser or the purchaser's employer.

- "(E) DISCRETION TO WITHHOLD ALLOW-ANCES.—Nothing in this paragraph prevents the Administrator from exercising discretion to withhold and retire consumption allow-ances that would otherwise be available for auction or nonauction sale. Not later than 18 months after the date of enactment of this section, the Administrator shall promulgate regulations establishing criteria for withholding and retiring consumption allow-ances
- "(5) Banking.—A consumption allowance or destruction offset credit may be used to meet the compliance obligation requirements of paragraph (1) in—
- "(A) the vintage year for the allowance or destruction offset credit; or
- "(B) any calendar year subsequent to the vintage year for the allowance or destruction offset credit.
 - "(6) AUCTIONS.-
- "(A) INITIAL REGULATIONS.—Not later than 18 months after the date of enactment of this section, the Administrator shall promulgate regulations governing the auction of allowances under this section. Such regulations shall include the following requirements:
- "(i) FREQUENCY; FIRST AUCTION.—Auctions shall be held one time per year at regular intervals, with the first auction to be held no later than October 31. 2011.
- "(ii) AUCTION FORMAT.—Auctions shall follow a single-round, sealed-bid, uniform price format.
- "(iii) FINANCIAL ASSURANCE.—The Administrator may establish financial assurance requirements to ensure that auction participants can and will perform on their bids.
- "(iv) DISCLOSURE OF BENEFICIAL OWNER-SHIP.—Each bidder in the auction shall be required to disclose the person or entity sponsoring or benefitting from the bidder's participation in the auction if such person or entity is, in whole or in part, other than the bidder
- "(v) Publication of Information.—After the auction, the Administrator shall, in a timely fashion, publish the number of bidders, number of winning bidders, the quantity of allowances sold, and the auction clearing price.
- "(vi) BIDDING LIMITS IN 2012.—In the vintage year 2012 auction, no auction participant may, directly or in concert with another participant, bid for or purchase more allowances offered for sale at the auction than the greater of—
- "(I) the number of allowances which, when added to the number of allowances available for purchase by the participant in the producer-importer pool non-auction sale, would equal the participant's annual average consumption of class II, group II substances in calendar years 2004, 2005, and 2006; or
- "(II) the number of allowances equal to the product of—
- "(aa) 1.20 multiplied by the participant's allocation share of the producer-importer pool non-auction sale as determined under paragraph (4)(C)(ii); and
- "(bb) the number of vintage year 2012 allowances offered at auction.
- "(vii) BIDDING LIMITS IN 2013.—In the vintage year 2013 auction, no auction participant may, directly or in concert with another participant, bid for or purchase more allowances offered for sale at the auction than the product of—
- "(I) 1.15 multiplied by the ratio of the total number of vintage year 2012 allowances purchased by the participant from the auction and from the producer-importer pool non-auction sale to the total number of vintage year 2012 allowances in the producer-importer pool; and

- "(II) the number of vintage year 2013 allowances offered at auction.
- "(viii) BIDDING LIMITS IN SUBSEQUENT YEARS.—In the auctions for vintage year 2014 and subsequent vintage years, no auction participant may, directly or in concert with another participant, bid for or purchase more allowances offered for sale at the auction than the product of—
- "(I) 1.15 multiplied by the ratio of the highest number of allowances required to be held by the participant in any of the three prior vintage years to meet its compliance obligation under paragraph (1) to the total number of allowances in the producer-importer pool for such vintage year; and
- "(II) the number of allowances offered at auction for that vintage year.
- "(ix) OTHER REQUIREMENTS.—The Administrator may include in the regulations such other requirements or provisions as the Administrator considers necessary to promote effective, efficient, transparent, and fair administration of auctions under this section.
- "(B) REVISION OF REGULATIONS.—The Administrator may, at any time, revise the initial regulations promulgated under subparagraph (A) based on the Administrator's experience in administering allowance auctions by promulgating new regulations. Such revised regulations need not meet the requirements identified in subparagraph (A) if the Administrator determines that an alternative auction design would be more effective, taking into account factors including costs of administration, transparency, fairness, and risks of collusion or manipulation. In determining whether and how to revise the initial regulations under this paragraph. the Administrator shall not consider maximization of revenues to the Federal Government
- "(C) DELEGATION OR CONTRACT.—Pursuant to regulations under this section, the Administrator may, by delegation or contract, provide for the conduct of auctions under the Administrator's supervision by other departments or agencies of the Federal Government or by nongovernmental agencies, groups, or organizations.
- "(7) PAYMENTS FOR ALLOWANCES.—
- "(A) INITIAL REGULATIONS.—Not later than 18 months after the date of enactment of this section, the Administrator shall promulgate regulations governing the payment for allowances purchased in auction and non-auction sales under this section. Such regulations shall include the requirement that, in the event that full payment for purchased allowances is not made on the date of purchase, equal payments shall be made one time per calendar quarter with all payments for allowances of a vintage year made by the end of that vintage year.
- "(B) REVISION OF REGULATIONS.— The Administrator may, at any time, revise the initial regulations promulgated under subparagraph (A) based on the Administrator's experience in administering collection of payments by promulgating new regulations. Such revised regulations need not meet the requirements identified in subparagraph (A) if the Administrator determines that an alternative payment structure or frequency would be more effective, taking into account factors including cost of administration, transparency, and fairness. In determining whether and how to revise the initial regulations under this paragraph, the Administrator shall not consider maximization of revenues to the Federal Government.
- "(C) PENALTIES FOR NON-PAYMENT.—Failure to pay for purchased allowances in accordance with the regulations promulgated pursuant to this paragraph shall be a violation of the requirements of subsection (b). Section 113(c)(3) shall apply in the case of any person who knowingly fails to pay for pur-

- chased allowances in accordance with the regulations promulgated pursuant to this paragraph.
- "(8) IMPORTED PRODUCTS.—If the United States becomes a party or otherwise adheres to a multilateral agreement, including any amendment to the Montreal Protocol on Substances That Deplete the Ozone Layer, which restricts the production or consumption of class II, group II substances—
- "(A) as of the date on which such agreement or amendment enters into force, it shall no longer be unlawful for any person to import from a party to such agreement or amendment any product containing any class II, group II substance whose production or consumption is regulated by such agreement or amendment without holding one consumption allowance or one destruction offset credit for each carbon dioxide equivalent ton of the class II, group II substance;
- "(B) the Administrator shall promulgate regulations within 12 months of the date the United States becomes a party or otherwise adheres to such agreement or amendment, or the date on which such agreement or amendment enters into force, whichever is later, to establish a new baseline for purposes of paragraph (2), which new baseline shall be the original baseline less the carbon dioxide equivalent of the annual average quantity of any class II substances regulated by such agreement or amendment contained in products imported from parties to such agreement or amendment in calendar years 2004, 2005, and 2006;
- "(C) as of the date on which such agreement or amendment enters into force, no person importing any product containing any class II, group II substance may, directly or in concert with another person, purchase any consumption allowances for sale by the Administrator for the importation of products from a party to such agreement or amendment that contain any class II, group II substance restricted by such agreement or amendment; and
- "(D) the Administrator may adjust the two allowance pools established in paragraph (4) such that up to 90 percent of the consumption allowances available for a calendar year are placed in the producer-importer pool with the remaining consumption allowances placed in the secondary pool.
 - "(9) Offsets.-
- "(A) CHLOROFLUOROCARBON DESTRUCTION.—Within 18 months after the date of enactment of this section, the Administrator shall promulgate regulations to provide for the issuance of offset credits for the destruction, in the calendar year 2012 or later, of chlorofluorocarbons in the United States. The Administrator shall establish and distribute to the destroying entity a quantity of destruction offset credits equal to 0.8 times the number of metric tons of carbon dioxide equivalents of reduction achieved through the destruction. No destruction offset credits shall be established for the destruction of a class II, group II substance.
- "(B) DEFINITION.—For purposes of this paragraph, the term 'destruction' means the conversion of a substance by thermal, chemical, or other means to another substance with little or no carbon dioxide equivalent value and no ozone depletion potential.
- "(C) REGULATIONS.—The regulations promulgated under this paragraph shall include standards and protocols for project eligibility, certification of destroyers, monitoring, tracking, destruction efficiency, quantification of project and baseline emissions and carbon dioxide equivalent value, and verification. The Administrator shall ensure that destruction offset credits represent real and verifiable destruction of chlorofluorocarbons or other class I or class

II, group I, substances authorized under subparagraph (D).

"(D) OTHER SUBSTANCES.—The Administrator may promulgate regulations to add to the list of class I and class II, group I, substances that may be destroyed for destruction offset credits, taking into account a candidate substance's carbon dioxide equivalent value, ozone depletion potential, prevalence in banks in the United States, and emission rates, as well as the need for additional cost containment under the class II, group II cap and the integrity of the class II, group II cap. The Administrator shall not add a class I or class II, group I substance to the list if the consumption of the substance has not been completely phased-out internationally (except for essential use exemptions or other similar exemptions) pursuant to the Montreal Protocol.

"(E) EXTENSION OF OFFSETS.—(i) At any time after the Administrator promulgates regulations pursuant to subparagraph (A), the Administrator may, pursuant to the requirements of part D of title VII and based on the carbon dioxide equivalent value of the substance destroyed, add the types of destruction projects authorized to receive destruction offset credits under this paragraph to the list of types of projects eligible for offset credits under section 733. If such projects are added to the list under section 733, the issuance of offset credits for such projects under part D of title VII shall be governed by the requirements of such part D, while the issuance of offset credits for such projects under this paragraph shall be governed by the requirements of this paragraph. Nothing in this paragraph shall affect the issuance of offset credits under section 740.

"(ii) The Administrator shall not make the addition under clause (i) unless the Administrator finds that insufficient destruction is occurring or is projected to occur under this paragraph and that the addition would increase destruction.

"(iii) In no event shall more than one destruction offset credit be issued under title VII and this section for the destruction of the same quantity of a substance.

"(10) LEGAL STATUS OF ALLOWANCES AND CREDITS.—None of the following constitutes a property right:

"(A) A production or consumption allowance.

"(B) A destruction offset credit.

"(c) DEADLINES FOR COMPLIANCE.—Notwithstanding the deadlines specified for class II substances in sections 608, 609, 610, 612, and 613 that occur prior to January 1, 2009, the deadline for promulgating regulations under those sections for class II, group II substances shall be January 1, 2012.

"(d) EXCEPTIONS FOR ESSENTIAL USES.— Notwithstanding any phase down of production and consumption required by this section, to the extent consistent with any applicable multilateral agreement to which the United States is a party or otherwise adheres, the Administrator may provide the following exceptions for essential uses:

"(1) MEDICAL DEVICES.—The Administrator, after notice and opportunity for public comment, and in consultation with the Commissioner of the Food and Drug Administration, may provide an exception for the production and consumption of class II, group II substances solely for use in medical devices.

"(2) AVIATION AND SPACE VEHICLE SAFETY.— The Administrator, after notice and opportunity for public comment, may authorize the production and consumption of limited quantities of class II, group II substances solely for the purposes of aviation or space vehicle safety if either the Administrator of the Federal Aviation Administration or the Administrator of the National Aeronautics and Space Administration, in consultation with the Administrator, determines that no safe and effective substitute has been developed and that such authorization is necessary for aviation or space flight safety purposes.

"(e) DEVELOPING COUNTRIES.—Notwithstanding any phase down of production required by this section, the Administrator, after notice and opportunity for public comment, may authorize the production of limited quantities of class II, group II substances in excess of the amounts otherwise allowable under this section solely for export to, and use in, developing countries. Any production authorized under this subsection shall be solely for purposes of satisfying the basic domestic needs of such countries as provided in applicable international agreements, if any, to which the United States is a party or otherwise adheres.

"(f) NATIONAL SECURITY; FIRE SUPPRESSION, ETC.—The provisions of subsection (f) and paragraphs (1) and (2) of subsection (g) of section 604 shall apply to any consumption and production phase down of class II, group II substances in the same manner and to the same extent, consistent with any applicable international agreement to which the United States is a party or otherwise adheres, as such provisions apply to the substances specified in such subsection.

"(g) ACCELERATED SCHEDULE.—In lieu of section 606, the provisions of paragraphs (1), (2), and (3) of this subsection shall apply in the case of class II, group II substances.

"(1) IN GENERAL.—The Administrator shall promulgate initial regulations not later than 18 months after the date of enactment of this section, and revised regulations any time thereafter, which establish a schedule for phasing down the consumption (and, if the condition in subsection (b)(1)(B) is met, the production) of class II. group II substances that is more stringent than the schedule set forth in this section if based on the availability of substitutes, the Administrator determines that such more stringent schedule is practicable, taking into account technological achievability, safety, and other factors the Administrator deems relevant, or if the Montreal Protocol, or any applicable international agreement to which the United States is a party or otherwise adheres, is modified or established to include a schedule or other requirements to control or reduce production, consumption, or use of any class II, group II substance more rapidly than the applicable schedule under this section.

"(2) PETITION.—Any person may submit a petition to promulgate regulations under this subsection in the same manner and subject to the same procedures as are provided in section 606(b).

"(3) INCONSISTENCY.—If the Administrator determines that the provisions of this section regarding banking, allowance rollover, or destruction offset credits create a significant potential for inconsistency with the requirements of any applicable international agreement to which the United States is a party or otherwise adheres, the Administrator may promulgate regulations restricting the availability of banking, allowance rollover, or destruction offset credits to the extent necessary to avoid such inconsistence.

"(h) EXCHANGE.—Section 607 shall not apply in the case of class II, group II substances. Production and consumption allowances for class II, group II substances may be freely exchanged or sold but may not be converted into allowances for class II, group I substances.

"(i) LABELING.—(1) In applying section 611 to products containing or manufactured with class II, group II substances, in lieu of the words 'destroying ozone in the upper atmosphere' on labels required under section 611

there shall be substituted the words 'contributing to global warming'.

"(2) The Administrator may, through rulemaking, exempt from the requirements of section 611 products containing or manufactured with class II, group II substances determined to have little or no carbon dioxide equivalent value compared to other substances used in similar products.

"(j) Nonessential Products.—For the purposes of section 610, class II, group II substances shall be regulated under section 610(b), except that in applying section 610(b) the word 'hydrofluorocarbon' shall be substituted for the word 'chlorofluorocarbon' and the term 'class II, group II' shall be substituted for the term 'class I'. Class II, group II substances shall not be subject to the provisions of section 610(d).

"(k) INTERNATIONAL TRANSFERS.—In the

"(k) INTERNATIONAL TRANSFERS.—In the case of class II, group II substances, in lieu of section 616, this subsection shall apply. To the extent consistent with any applicable international agreement to which the United States is a party or otherwise adheres, including any amendment to the Montreal Protocol, the United States may engage in transfers with other parties to such agreement or amendment under the following conditions:

"(1) The United States may transfer production allowances to another party to such agreement or amendment if, at the time of the transfer, the Administrator establishes revised production limits for the United States accounting for the transfer in accordance with regulations promulgated pursuant to this subsection.

"(2) The United States may acquire production allowances from another party to such agreement or amendment if, at the time of the transfer, the Administrator finds that the other party has revised its domestic production limits in the same manner as provided with respect to transfers by the United States in the regulations promulgated pursuant to this subsection.

"(1) RELATIONSHIP TO OTHER LAWS.—

"(1) STATE LAWS.—For purposes of section 116, the requirements of this section for class II, group II substances shall be treated as requirements for the control and abatement of air pollution.

"(2) MULTILATERAL AGREEMENTS.—Section 614 shall apply to the provisions of this section concerning class II, group II substances, except that for the words 'Montreal Protocol' there shall be substituted the words 'Montreal Protocol, or any applicable multilateral agreement to which the United States is a party or otherwise adheres that restricts the production or consumption of class II, group II substances,' and for the words 'Article 4 of the Montreal Protocol' there shall be substituted 'any provision of such multilateral agreement regarding trade with non-parties'.

"(3) FEDERAL FACILITIES.—For purposes of section 118, the requirements of this section for class II, group II substances and corresponding State, interstate, and local requirements, administrative authority, and process and sanctions shall be treated as requirements for the control and abatement of air pollution within the meaning of section 118.

"(m) Carbon Dioxide Equivalent Value.—
(1) In lieu of section 602(e), the provisions of this subsection shall apply in the case of class II, group II substances. Simultaneously with establishing the list of class II, group II substances, and simultaneously with any addition to that list, the Administrator shall publish the carbon dioxide equivalent value of each listed class II, group II substance, based on a determination of the number of metric tons of carbon dioxide that makes the same contribution to global warming over

100 years as 1 metric ton of each class II, group II substance.

"(2) Not later than February 1, 2017, and not less than every 5 years thereafter, the Administrator shall—

"(A) review, and if appropriate, revise the carbon dioxide equivalent values established for class II, group II substances based on a determination of the number of metric tons of carbon dioxide that makes the same contributions to global warming over 100 years as 1 metric ton of each class II, group II substance; and

"(B) publish in the Federal Register the results of that review and any revisions.

"(3) A revised determination published in the Federal Register under paragraph (2)(B) shall take effect for production of class II, group II substances, consumption of class II, group II substances, and importation of products containing class II, group II substances starting on January 1 of the first calendar year starting at least 9 months after the date on which the revised determination was published

"(4) The Administrator may decrease the frequency of review and revision under paragraph (2) if the Administrator determines that such decrease is appropriate in order to synchronize such review and revisions with any similar review process carried out pursuant to the United Nations Framework Convention on Climate Change, an agreement negotiated under that convention, The Vienna Convention for the Protection of the Ozone Layer, or an agreement negotiated under that convention, except that in no event shall the Administrator carry out such review and revision any less frequently than every 10 years.

"(n) REPORTING REQUIREMENTS.—In lieu of subsections (b) and (c) of section 603, paragraphs (1) and (2) of this subsection shall apply in the case of class II, group II substances."

"(1) IN GENERAL.—On a quarterly basis, or such other basis (not less than annually) as determined by the Administrator, each person who produced, imported, or exported a class II, group II substance, or who imported a product containing a class II, group II substance, shall file a report with the Administrator setting forth the carbon dioxide equivalent amount of the substance that such person produced, imported, or exported, as well as the amount that was contained in products imported by that person, during the preceding reporting period. Each such report shall be signed and attested by a responsible officer. If all other reporting is complete, no such report shall be required from a person after April 1 of the calendar year after such person permanently ceases production importation, and exportation of the substance. as well as importation of products containing the substance, and so notifies the Administrator in writing. If the United States becomes a party or otherwise adheres to a multilateral agreement, including any amendment to the Montreal Protocol on Substances That Deplete the Ozone Layer, that restricts the production or consumption of class II, group II substances, then, if all other reporting is complete, no such report shall be required from a person with respect to importation from parties to such agreement or amendment of products containing any class II, group II substance restricted by such agreement or amendment, after April 1 of the calendar year following the year during which such agreement or amendment enters into force.

"(2) Baseline reports for class II, group II substances.—

"(A) IN GENERAL.—Unless such information has been previously reported to the Administrator, on the date on which the first report under paragraph (1) of this subsection is required to be filed, each person who produced, imported, or exported a class II, group II substance, or who imported a product containing a class II substance, (other than a substance added to the list of class II, group II substances after the publication of the initial list of such substances under this section), shall file a report with the Administrator setting forth the amount of such substance that such person produced, imported, exported, or that was contained in products imported by that person, during each of calendar years 2004, 2005, and 2006.

"(B) PRODUCERS.—In reporting under subparagraph (A), each person who produced in the United States a class II substance during calendar years 2004, 2005, or 2006 shall—

"(i) report all acquisitions or purchases of class II substances during each of calendar years 2004, 2005, and 2006 from all other persons who produced in the United States a class II substance during calendar years 2004, 2005, or 2006, and supply evidence of such acquisitions and purchases as deemed necessary by the Administrator; and

"(ii) report all transfers or sales of class II substances during each of calendar years 2004, 2005, and 2006 to all other persons who produced in the United States a class II substance during calendar years 2004, 2005, or 2006, and supply evidence of such transfers and sales as deemed necessary by the Administrator.

"(C) ADDED SUBSTANCES.—In the case of a substance added to the list of class II, group II substances after publication of the initial list of such substances under this section, each person who produced, imported, exported, or imported products containing such substance in calendar year 2004, 2005, or 2006 shall file a report with the Administrator within 180 days after the date on which such substance is added to the list, setting forth the amount of the substance that such person produced, imported, and exported, as well as the amount that was contained in products imported by that person, in calendar years 2004, 2005, and 2006.

''(0) STRATOSPHERIC OZONE AND CLIMATE PROTECTION FUND.—

"(1) IN GENERAL.—There is established in the Treasury of the United States a Stratospheric Ozone and Climate Protection Fund.

"(2) DEPOSITS.—The Administrator shall deposit all proceeds from the auction and non-auction sale of allowances under this section into the Stratospheric Ozone and Climate Protection Fund.

"(3) USE.—Amounts deposited into the Stratospheric Ozone and Climate Protection Fund shall be available, subject to appropriations, exclusively for the following purposes:

"(A) RECOVERY, RECYCLING, AND RECLAMA-TION.—The Administrator may utilize funds to establish a program to incentivize the recovery, recycling, and reclamation of any Class II substances in order to reduce emissions of such substances.

"(B) MULTILATERAL FUND.—If the United States becomes a party or otherwise adheres to a multilateral agreement, including any amendment to the Montreal Protocol on Substances That Deplete the Ozone Layer, which restricts the production or consumption of class II, group II substances, the Administrator may utilize funds to meet any related contribution obligation of the United States to the Multilateral Fund for the Implementation of the Montreal Protocol or similar multilateral fund established under such multilateral agreement.

"(C) BEST-IN-CLASS APPLIANCES DEPLOY-MENT PROGRAM.—The Secretary of Energy is authorized to utilize funds to carry out the purposes of section 214 of the American Clean Energy and Security Act of 2009. "(D) LOW GLOBAL WARMING PRODUCT TRANSITION ASSISTANCE PROGRAM.—

"(i) IN GENERAL.—The Administrator, in consultation with the Secretary of Energy, may utilize funds in fiscal years 2012 through 2022 to establish a program to provide financial assistance to manufacturers of products containing class II, group II substances to facilitate the transition to products that contain or utilize alternative substances with no or low carbon dioxide equivalent value and no ozone depletion potential.

"(ii) DEFINITION.—In this subparagraph, the term 'products' means refrigerators, freezers, dehumidifiers, air conditioners, foam insulation, technical aerosols, fire protection systems, and semiconductors.

"(iii) FINANCIAL ASSISTANCE.—The Administrator may provide financial assistance to manufacturers pursuant to clause (i) for—

"(I) the design and configuration of new products that use alternative substances with no or low carbon dioxide equivalent value and no ozone depletion potential; and

"(II) the redesign and retooling of facilities for the manufacture of products in the United States that use alternative substances with no or low carbon dioxide equivalent value and no ozone depletion potential.

"(iv) REPORTS.—For any fiscal year during which the Administrator provides financial assistance pursuant to this subparagraph, the Administrator shall submit a report to the Congress within 3 months of the end of such fiscal year detailing the amounts, recipients, specific purposes, and results of the financial assistance provided.".

(b) TABLE OF CONTENTS.—The table of contents of title VI of the Clean Air Act (42 U.S.C. 7671 et seq.) is amended by adding the following new item at the end thereof:

"Sec. 619. Hydrofluorocarbons (HFCs)."

(c) FIRE SUPPRESSION AGENTS.—Section 605(a) of the Clean Air Act (42 U.S.C. 7671(a)) is amended—

(1) by striking "or" at the end of paragraph (2):

(2) by striking the period at the end of paragraph (3) and inserting "; or"; and

(3) by adding the following new paragraph after paragraph (3):

"(4) is listed as acceptable for use as a fire suppression agent for nonresidential applications in accordance with section 612(c).".

(d) MOTOR VEHICLE AIR CONDITIONERS.—

(1) Section 609(e) of the Clean Air Act (42 U.S.C. 7671h(e)) is amended by inserting ", group I" after each reference to "class II" in the text and heading.

(2) Section 609 of the Clean Air Act (42 U.S.C. 7671h) is amended by adding the following new subsection after subsection (e):

"(f) CLASS II, GROUP II SUBSTANCES.—

"(1) REPAIR.—The Administrator may promulgate regulations establishing requirements for repair of motor vehicle air conditioners prior to adding a class II, group II substance.

"(2) SMALL CONTAINERS.—(A) The Administrator may promulgate regulations establishing servicing practices and procedures for recovery of class II, group II substances from containers which contain less than 20 pounds of such class II, group II substances.

"(B) Not later than 18 months after enactment of this subsection, the Administrator shall either promulgate regulations requiring that containers which contain less than 20 pounds of a class II, group II substance be equipped with a device or technology that limits refrigerant emissions and leaks from the container and limits refrigerant emissions and leaks during the transfer of refrigerant from the container to the motor vehicle air conditioner or issue a determination that such requirements are not necessary or appropriate.

- "(C) Not later than 18 months after enactment of this subsection, the Administrator shall promulgate regulations establishing requirements for consumer education materials on best practices associated with the use of containers which contain less than 20 pounds of a class II, group II substance and prohibiting the sale or distribution, or offer for sale or distribution, of any class II, group II substance in any container which contains less than 20 pounds of such class II, group II substance, unless consumer education materials consistent with such requirements are displayed and available at point-of-sale locations, provided to the consumer, or included in or on the packaging of the container which contain less than 20 pounds of a class II. group II substance.
- "(D) The Administrator may, through rulemaking, extend the requirements established under this paragraph to containers which contain 30 pounds or less of a class II, group II substance if the Administrator determines that such action would produce significant environmental benefits.
- "(3) RESTRICTION OF SALES.—Effective January 1, 2014, no person may sell or distribute or offer to sell or distribute or otherwise introduce into interstate commerce any motor vehicle air conditioner refrigerant in any size container unless the substance has been found acceptable for use in a motor vehicle air conditioner under section 612.".
- (e) SAFE ALTERNATIVES POLICY.—Section 612(e) of the Clean Air Act (42 U.S.C. 7671k(e)) is amended by inserting "or class II" after each reference to "class I".

SEC. 333. BLACK CARBON.

- (a) DEFINITION.—As used in this section, the term "black carbon" means primary light absorbing aerosols, as defined by the Administrator, based on the best available regionee.
- (b) BLACK CARBON ABATEMENT REPORT.— Not later than one year after the date of enactment of this section, the Administrator shall, in consultation with other appropriate Federal agencies, submit to Congress a report regarding black carbon emissions. The report shall include the following:
- (1) A summary of the current information and research that identifies—
- (A) an inventory of the major sources of black carbon emissions in the United States and throughout the world, including—
- (i) an estimate of the quantity of current and projected future emissions; and
- (ii) the net climate forcing of the emissions from such sources, including consideration of co-emissions of other pollutants:
- (B) effective and cost-effective control technologies, operations, and strategies for additional domestic and international black carbon emissions reductions, such as diesel retrofit technologies on existing on-road, non-road, and stationary engines and programs to address residential cookstoves, and forest and agriculture-based burning;
- (C) potential metrics and approaches for quantifying the climatic effects of black carbon emissions, including its radiative forcing and warming effects, that may be used to compare the climate benefits of different mitigation strategies, including an assessment of the uncertainty in such metrics and approaches; and
- (D) the public health and environmental benefits associated with additional controls for black carbon emissions.
 - (2) Recommendations regarding-
- (A) development of additional emissions monitoring techniques and capabilities, modeling, and other black carbon-related areas of study;
- (B) areas of focus for additional study of technologies, operations, and strategies with the greatest potential to reduce emissions of

- black carbon and associated public health, economic, and environmental impacts associated with these emissions; and
- (C) actions, in addition to those identified by the Administrator under section 851 of the Clean Air Act (as added by subsection (c)), the Federal Government may take to encourage or require reductions in black carbon emissions.
- (c) BLACK CARBON MITIGATION.—Title VIII of the Clean Air Act, as added by section 331 of this Act, and amended by section 222 of this Act, is further amended by adding after part D the following new part:

"PART E-BLACK CARBON

"SEC. 851. BLACK CARBON.

- "(a) Domestic Black Carbon Mitiga-TION.—Not later than 18 months after the date of enactment of this section, the Administrator, taking into consideration the public health and environmental impacts of black carbon emissions, including the effects on global and regional warming, the Arctic. and other snow and ice-covered surfaces, shall propose regulations under the existing authorities of this Act to reduce emissions of black carbon or propose a finding that existing regulations promulgated pursuant to this Act adequately regulate black carbon emissions. Not later than two years after the date of enactment of this section, the Administrator shall promulgate final regulations under the existing authorities of this Act or finalize the proposed finding. Such regulations shall not apply to specific types, classes, categories, or other suitable groupings of emissions sources that the Administrator finds are subject to adequate regulation.
- "(b) International Black Carbon Mitigation —
- "(1) REPORT.—Not later than one year after the date of enactment of this section, the Administrator, in coordination with the Secretary of State and other appropriate Federal agencies, shall transmit a report to Congress on the amount, type, and direction of all present United States financial, technical, and related assistance to foreign countries to reduce, mitigate, and otherwise abate black carbon emissions.
- "(2) OTHER OPPORTUNITIES.—The report required under paragraph (1) shall also identify opportunities and recommendations, including action under existing authorities, to achieve significant black carbon emission reductions in foreign countries through technical assistance or other approaches to—
- "(A) promote sustainable solutions to bring clean, efficient, safe, and affordable stoves, fuels, or both stoves and fuels to residents of developing countries that are reliant on solid fuels such as wood, dung, charcoal, coal, or crop residues for home cooking and heating, so as to help reduce the public health, environmental, and economic impacts of black carbon emissions from these sources by—
- "(i) identifying key regions for large-scale demonstration efforts, and key partners in each such region; and
- "(ii) developing for each such region a large-scale implementation strategy with a goal of collectively reaching 20,000,000 homes over 5 years with interventions that will—
- "(I) increase stove efficiency by over 50 percent (or such other goal as determined by the Administrator):
- "(II) reduce emissions of black carbon by over 60 percent (or such other goal as determined by the Administrator); and
- "(III) reduce the incidence of severe pneumonia in children under 5 years old by over 30 percent (or such other goal as determined by the Administrator);
- "(B) make technological improvements to diesel engines and provide greater access to fuels that emit less or no black carbon;

- "(C) reduce unnecessary agricultural or other biomass burning where feasible alternatives exist:
- "(D) reduce unnecessary fossil fuel burning that produces black carbon where feasible alternatives exist:
- "(E) reduce other sources of black carbon emissions; and
- "(F) improve capacity to achieve greater compliance with existing laws to address black carbon emissions.".
- (d) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated such sums as are necessary to carry out this section.

SEC. 334. STATES.

Section 116 of the Clean Air Act (42 U.S.C. 7416) is amended by adding the following at the end thereof: "For the purposes of this section, the phrases 'standard or limitation respecting emissions of air pollutants' and 'requirements respecting control or abatement of air pollution' shall include any provision to: cap greenhouse gas emissions, require surrender to the State or a political subdivision thereof of emission allowances or offset credits established or issued under this Act, and require the use of such allowances or credits as a means of demonstrating compliance with requirements established by a State or political subdivision thereof."

SEC. 335, STATE PROGRAMS.

Title VIII of the Clean Air Act, as added by section 331 of this Act and amended by several sections of this Act, is further amended by adding after part E (as added by section 333(c) of this Act) the following new part:

"PART F-MISCELLANEOUS

"SEC. 861. STATE PROGRAMS.

"Notwithstanding section 116, no State or political subdivision thereof shall implement or enforce a cap and trade program that covers any capped emissions emitted during the years 2012 through 2017. For purposes of this section, the term 'cap and trade program' means a system of greenhouse gas regulation under which a State or political subdivision issues a limited number of tradable instruments in the nature of emission allowances and requires that sources within its jurisdiction surrender such tradeable instruments for each unit of greenhouse gases emitted during a compliance period. For purposes of this section, a 'cap-and-trade program' does not include a target or limit on greenhouse gas emissions adopted by a State or political subdivision that is implemented other than through the issuance and surrender of a limited number of tradable instruments in the nature of emission allowances, nor does it include any other standard, limit, regulation, or program to reduce greenhouse gas emissions that is not implemented through the issuance and surrender of a limited number of tradeable instruments in the nature of emission allowances. For purposes of this section, the term 'cap and trade program' does not include, among other things, fleetwide motor vehicle emission requirements that allow greater emissions with increased vehicle production, or requirements that fuels, or other products, meet an average pollution emission rate or lifecycle greenhouse gas standard.

"SEC. 862. GRANTS FOR SUPPORT OF AIR POLLU-TION CONTROL PROGRAMS.

"The Administrator is authorized to make grants to air pollution control agencies pursuant to section 105 for purposes of assisting in the implementation of programs to address global warming established under the Safe Climate Act.".

SEC. 336. ENFORCEMENT.

(a) REMAND.—Section 307(b) of the Clean Air Act (42 U.S.C. 7607(b)) is amended by adding the following new paragraphs at the end thereof:

- "(3) If the court determines that any action of the Administrator is arbitrary, capricious, or otherwise unlawful, the court may remand such action, without vacatur, if vacatur would impair or delay protection of the environment or public health or otherwise undermine the timely achievement of the purposes of this Act.
- "(4) If the court determines that any action of the Administrator is arbitrary, capricious, or otherwise unlawful, and remands the matter to the Administrator, the Administrator shall complete final action on remand within an expeditious time period no longer than the time originally allowed for the action or one year, whichever is less, unless the court on motion determines that a shorter or longer period is necessary, appropriate, and consistent with the purposes of this Act. The court of appeals shall have jurisdiction to enforce a deadline for action on remand under this subparagraph."
- (b) PETITION FOR RECONSIDERATION.—Section 307(d)(7)(B) of the Clean Air Act (42 U.S.C. 7607(d)(7)(B)) is amended as follows:
- (1) By inserting after the second sentence "If a petition for reconsideration is filed, the Administrator shall take final action on such petition, including promulgation of final action either revising or determining not to revise the action for which reconsideration is sought, within 150 days after the petition is received by the Administrator or the petition shall be deemed denied for the purpose of judicial review."
- (2) By amending the third sentence to read as follows: "Such person may seek judicial review of such denial, or of any other final action, by the Administrator, in response to a petition for reconsideration, in the United States court of appeals for the appropriate circuit (as provided in subsection (b))."

SEC. 337. CONFORMING AMENDMENTS.

- (a) FEDERAL ENFORCEMENT.—Section 113 of the Clean Air Act (42 U.S.C. 7413) is amended as follows:
- (1) In subsection (a)(3), by striking "or title VI," and inserting "title VI, title VII, or title VIII".
- (2) In subsection (b), by striking "or a major stationary source" and inserting "a major stationary source, or a covered EGU under title VIII" in the material preceding paragraph (1).
- (3) In paragraph (2) of subsection (b), by striking "or title VI" and inserting "title VI, title VII, or title VIII".
 - (4) In subsection (c)—
- (A) in the first sentence of paragraph (1), by striking "or title VI (relating to stratospheric ozone control)," and inserting "title VI, title VII, or title VIII."; and
- (B) in the first sentence of paragraph (3), by striking "or VI" and inserting "VI, VII, or VIII".
- (5) In subsection (d)(1)(B), by striking "or VI" and inserting "VI, VII, or VIII".
- (6) In subsection (f), in the first sentence, by striking "or VI" and inserting "VI, VII, or VIII".
- (b) RETENTION OF STATE AUTHORITY.—Section 116 of the Clean Air Act (42 U.S.C. 7416) is amended as follows:
- (1) By striking "and 233" and inserting "233".
- (2) By striking "of moving sources)" and inserting "of moving sources), and 861 (preempting certain State greenhouse gas programs for a limited time)".
- (c) Inspections, Monitoring, and Entry.—Section 114(a) of the Clean Air Act (42 U.S.C. 7414(a)) is amended by striking "section 112," and all that follows through "(ii)" and inserting the following: "section 112, or any regulation of greenhouse gas emissions under title VII or VIII, (ii)".

- (d) ENFORCEMENT.—Subsection (f) of section 304 of the Clean Air Act (42 U.S.C. 7604(f)) is amended as follows:
- (1) By striking "; or" at the end of paragraph (3) thereof and inserting a comma.
- (2) By striking the period at the end of paragraph (4) thereof and inserting ", or".
- (3) By adding the following after paragraph (4) thereof:
- "(5) any requirement of title VII or VIII.".

 (e) ADMINISTRATIVE PROCEEDINGS AND JUDICIAL REVIEW.—Section 307 of the Clean Air Act (42 U.S.C. 7607) is amended as follows:
- (1) In subsection (a), by striking ", or section 306" and inserting "section 306, or title VII or VIII".
 - (2) In subsection (b)(1)—
- (A) by striking ",," and inserting "," in each place such punctuation appears; and
- (B) by striking "section 120," in the first sentence and inserting "section 120, any final action under title VII or VIII,".
- (3) In subsection (d)(1) by amending subparagraph (S) to read as follows:
- "(S) the promulgation or revision of any regulation under title VII or VIII,".

SEC. 338. DAVIS-BACON COMPLIANCE.

- (a) IN GENERAL.—Notwithstanding any other provision of law and in a manner consistent with other provisions in this Act. to receive emission allowances or funding under this Act, or the amendments made by this Act, the recipient shall provide reasonable assurances that all laborers and mechanics employed by contractors and subcontractors on projects funded directly by or assisted in whole or in part by and through the Federal Government pursuant to this Act, or the amendments made by this Act, or by any entity established in accordance with this Act, or the amendments made by this Act, including the Carbon Storage Research Corporation, will be paid wages at rates not less than those prevailing on projects of a character similar in the locality as determined by the Secretary of Labor in accordance with subchapter IV of chapter 31 of title 40, United States Code (commonly known as the "Davis-Bacon Act"). With respect to the labor standards specified in this section, the Secretary of Labor shall have the authority and functions set forth in Reorganization Plan Numbered 14 of 1950 (64 Stat. 1267; 5 U.S.C. App.) and section 3145 of title 40, United States Code.
- (b) EXEMPTION.—Neither subsection (a) nor the requirements of subchapter IV of chapter 31 of title 40, United States Code, shall apply to retrofitting of the following:
- (1) Single family homes (both attached and detached) under section 202.
- (2) Owner-occupied residential units in larger buildings that have their own dedicated space-conditioning systems under section 202.
- (3) Residential buildings (as defined in section 202(a)(5)) if designed for residential use by less than 4 families.
- (4) Nonresidential buildings (as defined in section 202(a)(1)) if the net interior space of such nonresidential building is less than 6,500 square feet.

SEC. 339. NATIONAL STRATEGY FOR DOMESTIC BIOLOGICAL CARBON SEQUESTRA-TION.

Not later than 1 year after the date of enactment of this Act, the Administrator of the Environmental Protection Agency, in consultation with the Secretary of Energy, the Secretary of Agriculture, the Secretary of the Interior, and the heads of such other relevant Federal agencies as the President may designate, shall submit to Congress a report setting forth a unified and comprehensive strategy to address the key legal, regulatory, technological, and other barriers to maximizing the potential for sustainable

biological sequestration of carbon within the United States.

SEC. 340. REDUCING ACID RAIN AND MERCURY POLLUTION.

Not later than 18 months after the date of enactment of this Act, the Administrator shall submit to Congress a report that analyzes the effects of different carbon dioxide reduction strategies and technologies on the emissions of mercury, sulfur dioxide, and nitrogen oxide, which cause acid rain, particulate matter, ground level ozone, mercury contamination, and other environmental problems. The report shall assess a variety of carbon reduction technologies, including the application of various carbon capture and sequestration technologies for both new and existing power plants. The report shall assess the current scientific and technical understanding of the interplay between the various technologies and emissions of air pollutants, identify hurdles to strategies that could cost-effectively reduce emissions of multiple pollutants, and make appropriate recommendations.

Subtitle D—Carbon Market Assurance SEC. 341. CARBON MARKET ASSURANCE.

(a) AMENDMENT.—The Federal Power Act (16 U.S.C. 791a and following) is amended by adding at the end the following:

"PART IV—CARBON MARKET ASSURANCE "SEC. 401. OVERSIGHT AND ASSURANCE OF CARBON MARKETS.

- "(a) DEFINITIONS.—In this section:
- "(1) CONTRACT OF SALE.—The term 'contract of sale' includes sales, agreements of sale, and agreements to sell.
- "(1) COVERED ENTITY.—The term 'covered entity' shall have the meaning given in section 700 of the Clean Air Act.
- "(2) REGULATED ALLOWANCE.—The term 'regulated allowance' means any emission allowance, compensatory allowance, offset credit, or Federal renewable electricity credit established or issued under the American Clean Energy and Security Act of 2009.
- "(3) REGULATED INSTRUMENT.—The term regulated instrument' means a regulated allowance or a regulated allowance derivative.
- "(b) REGULATED ALLOWANCE MARKET.—
- "(1) AUTHORITY.—The Commission shall promulgate regulations for the establishment, operation, and oversight of markets for regulated allowances not later than 18 months after the date of the enactment of this section, and from time to time thereafter as may be appropriate.
- "(2) REGULATIONS.—The regulations promulgated pursuant to paragraph (1) shall—
- "(A) provide for effective and comprehensive market oversight:
- "(B) prohibit fraud, market manipulation, and excess speculation, and provide measures to limit unreasonable fluctuation in the prices of regulated allowances;
- "(C) facilitate compliance with title VII of the Clean Air Act by covered entities;
- "(D) ensure market transparency and recordkeeping deemed necessary and appropriate by the Commission to provide for efficient price discovery; prevention of fraud, market manipulation, and excess speculation; and compliance with title VII of the Clean Air Act and section 610 of the Public Utility Regulatory Policies Act of 1978;
- "(E) as necessary, ensure that position limitations for individual market participants are established with respect to each class of regulated allowances;
- "(F) as necessary, ensure that margin requirements are established for each class of regulated allowances;
- "(G) provide for the formation and operation of a fair, orderly and liquid national market system that allows for the best execution in the trading of regulated allowances:

- "(H) limit or eliminate counterparty risks, market power concentration risks, and other risks associated with trading regulated allowances outside of trading facilities
- "(I) establish standards for qualification as, and operation of, trading facilities for regulated allowances;
- "(J) establish standards for qualification as, and operation of, clearing organizations for trading facilities for regulated allowances; and
- "(K) include such other requirements as necessary to preserve market integrity and facilitate compliance with title VII of the Clean Air Act and section 610 of the Public Utility Regulatory Policies Act of 1978 and the regulations promulgated under such title and such section.
 - "(3) Enforcement.—
- "(A) IN GENERAL.—If the Commission determines, after notice and an opportunity for a hearing on the record, that any entity has violated any rule or order issued by the Commission under this subsection, the Commission may issue an order—
- "(i) prohibiting the entity from trading on a trading facility for regulated allowances registered with the Commission, and requiring all such facilities to refuse the entity all privileges for such period as may be specified in the order:
- "(ii) if the entity is registered with the Commission in any capacity, suspending for a period of not more than 6 months, or revoking, the registration of the entity;
- "(iii) assessing the entity a civil penalty of not more than \$1,000,000 per day per violation for as long as the violation continues (and in determining the amount of a civil penalty, the Commission shall take into account the nature and seriousness of the violation and the efforts to remedy the violation); and
- "(iv) requiring disgorgement of unjust profits, restitution to entities harmed by the violation as determined by the Commission, or both.
- "(B) AUTHORITY TO SUSPEND OR REVOKE REGISTRATION.—The Commission may suspend for a period of not more than 6 months, or revoke, the registration of a trading facility for regulated allowances or of a clearing organization registered by the Commission if, after notice and opportunity for a hearing on the record, the Commission finds that—
- "(i) the entity violated any rule or order issued by the Commission under this subsection; or
- "(ii) a director, officer, employee, or agent of the entity has violated any rule or order issued by the Commission under this subsection.
- "(C) CEASE AND DESIST PROCEEDINGS.—
- "(i) IN GENERAL.—If the Commission determines that any entity may be violating, may have violated, or may be about to violate any provision of this part, or any regulation promulgated by, or any restriction, condition, or order made or imposed by, the Commission under this Act, and if the Commission finds that the alleged violation or threatened violation, or the continuation of the violation, is likely to result in significant harm to covered entities or market participants, or significant harm to the public interest, the Commission may issue a temporary order requiring the entity—
- "(I) to cease and desist from the violation or threatened violation;
- "(II) to take such action as is necessary to prevent the violation or threatened violation; and
- ''(III) to prevent, as the Commission determines to be appropriate— $\,$
- "(aa) significant harm to covered entities or market participants;
- "(bb) significant harm to the public interest; and

- "(cc) frustration of the ability of the Commission to conduct the proceedings or to redress the violation at the conclusion of the proceedings.
- "(ii) TIMING OF ENTRY.—An order issued under clause (i) shall be entered only after notice and opportunity for a hearing, unless the Commission determines that notice and hearing before entry would be impracticable or contrary to the public interest.
- "(iii) Effective DATE.—A temporary order issued under clause (i) shall—
- ``(I) become effective upon service upon the entity: and
- "(II) unless set aside, limited, or suspended by the Commission or a court of competent jurisdiction, remain effective and enforceable pending the completion of the proceedings.
- $\lq\lq(D)$ Proceedings regarding dissipation or conversion of assets.—
- "(i) IN GENERAL.—In a proceeding involving an alleged violation of a regulation or order promulgated or issued by the Commission, if the Commission determines that the alleged violation or related circumstances are likely to result in significant dissipation or conversion of assets, the Commission may issue a temporary order requiring the respondent to take such action as is necessary to prevent the dissipation or conversion of assets.
- "(ii) TIMING OF ENTRY.—An order issued under clause (i) shall be entered only after notice and opportunity for a hearing, unless the Commission determines that notice and hearing before entry would be impracticable or contrary to the public interest.
- "(iii) EFFECTIVE DATE.—A temporary order issued under clause (i) shall—
- ``(I) become effective upon service upon the respondent; and
- "(II) unless set aside, limited, or suspended by the Commission or a court of competent jurisdiction, remain effective and enforceable pending the completion of the proceedings.
 - "(E) REVIEW OF TEMPORARY ORDERS.—
- "(i) APPLICATION FOR REVIEW.—At any time after a respondent has been served with a temporary cease-and-desist order pursuant to subparagraph (C) or order regarding the dissipation or conversion of assets pursuant to subparagraph (D), the respondent may apply to the Commission to have the order set aside, limited, or suspended.
- "(ii) NO PRIOR HEARING.—If a respondent has been served with a temporary order entered without a prior hearing of the Commission—
- "(I) the respondent may, not later than 10 days after the date on which the order was served, request a hearing on the application; and
- "(II) the Commission shall hold a hearing and render a decision on the application at the earliest practicable time.
- "(iii) Judicial review.
- "(I) IN GENERAL.—An entity shall not be required to submit a request for rehearing of a temporary order before seeking judicial review in accordance with this subparagraph.
- "(II) TIMING OF REVIEW.—Not later than 10 days after the date on which a respondent is served with a temporary cease-and-desist order entered with a prior hearing of the Commission, or 10 days after the date on which the Commission renders a decision on an application and hearing under clause (i) with respect to any temporary order entered without such a prior hearing—
- "(aa) the respondent may obtain a review of the order in a United States circuit court having jurisdiction over the circuit in which the respondent resides or has a principal place of business, or in the United States Court of Appeals for the District of Columbia Circuit, for an order setting aside, limiting,

- or suspending the effectiveness or enforcement of the order; and
- "(bb) the court shall have jurisdiction to enter such an order.
- "(III) No PRIOR HEARING.—A respondent served with a temporary order entered without a prior hearing of the Commission may not apply to the applicable court described in subclause (II) except after a hearing and decision by the Commission on the application of the respondent under clauses (i) and (ii).
- "(iv) PROCEDURES.—Section 222 and Part III shall apply to—
- "(I) an application for review of an order under clause (i); and
- "(II) an order subject to review under clause (iii).
- "(v) No AUTOMATIC STAY OF TEMPORARY ORDER.—The commencement of proceedings under clause (iii) shall not, unless specifically ordered by the court, operate as a stay of the order of the Commission.
- "(F) ACTIONS TO COLLECT CIVIL PENALTIES.—If any person fails to pay a civil penalty assessed under this subsection after an order assessing the penalty has become final and unappealable, the Commission shall bring an action to recover the amount of the penalty in any appropriate United States district court.
- "(4) Transaction fees.-
- "(A) In general.—The Commission shall, in accordance with this paragraph, establish and collect transaction fees designed to recover the costs to the Federal Government of the supervision and regulation of regulated allowance markets and market participants, including related costs for enforcement activities, policy and rulemaking activities, administration, legal services, and international regulatory activities.
- "(B) INITIAL FEE RATE.—Each trading facility on or through which regulated allowances are transacted shall pay to the Commission a fee at a rate of not more than \$15 per \$1,000,000 of the aggregate dollar amount of sales of regulated allowances transacted through the facility.
- "(C) ANNUAL ADJUSTMENT OF FEE RATE.—The Commission shall, on an annual basis—
- "(i) assess the rate at which fees are to be collected as necessary to meet the cost recovery requirement in subparagraph (A); and
- "(ii) consistent with subparagraph (B), adjust the rate as necessary in order to meet the requirement.
- "(D) REPORT ON ADEQUACY OF FEES IN RE-COVERING COSTS.—The Commission, shall, on an annual basis, report to the Committee on Energy and Commerce of the House of Representatives and the Committee on Energy and Natural Resources of the Senate on the adequacy of the transaction fees in providing funding for the Commission to regulate the regulated allowance markets.
- "(5) JUDICIAL REVIEW.—Judicial review of actions taken by the Commission under this subsection shall be pursuant to part III.
- "(6) ADDITIONAL EMPLOYEES REPORT APPOINTMENT.—Within 18 months after the date of the enactment of this section, the Commission shall submit to the President, the Committee on Energy and Commerce of the House of Representatives, and the Committee on Energy and Natural Resources of the Senate, a report that contains recommendations as to how many additional employees would be necessary to provide robust oversight and enforcement of the regulations promulgated under this subsection. As soon as practicable after the completion of the report, subject to appropriations, the Commission shall appoint the recommended number of additional employees for such purposes.
- "(e) WORKING GROUP.—

"(1) ESTABLISHMENT.—Not later than 30 days after the date of the enactment of this section, the President shall establish an interagency working group on carbon market oversight, which shall include the Administrator of the Environmental Protection Agency and representatives of other relevant agencies, to make recommendations to the Commodity Futures Trading Commission regarding proposed regulations for the establishment, operation, and oversight of markets for regulated allowance derivatives.

"(2) REPORT.—Not later than 180 days after the date of the enactment of this section, and biennially thereafter, the interagency working group shall submit a written report to the President and Congress that includes its recommendations to the Commodity Futures Trading Commission regarding proposed regulations for the establishment, operation, and oversight of markets for regulated allowance derivatives and any recommendations to Congress for statutory changes needed to ensure the establishment, operation, and oversight of transparent, fair, stable, and efficient markets for regulated allowance derivatives.

"(d) PENALTY FOR FRAUD AND FALSE OR MISLEADING STATEMENTS.—A person convicted under section 1041 of title 18, United States Code, may be prohibited from holding or trading regulated allowances for a period of not more than 5 years pursuant to the regulations promulgated under this section, except that, if the person is a covered entity, the person shall be allowed to hold sufficient regulated allowances to meet its compliance obligations

"(e) Relation to State Law.—Nothing in this section shall preclude, diminish or qualify any authority of a State or political subdivision thereof to adopt or enforce any unfair competition, antitrust, consumer protection, securities, commodities or any other law or regulation, except that no such State law or regulation may relieve any person of any requirement otherwise applicable under this section.

"(f) Market Reports.—

"(1) COLLECTION AND ANALYSIS OF INFORMA-TION.—The Commission, in conjunction with the Commodity Futures Trading Commission shall, on a continuous basis, analyze the following information on the functioning of the markets for regulated instruments established under this part:

"(A) The status of, and trends in, the markets, including prices, trading volumes, transaction types, and trading channels and mechanisms.

"(B) Spikes, collapses, and volatility in prices of regulated instruments, and the causes therefor.

"(C) The relationship between the market for regulated allowances and allowance derivatives, and the spot and futures markets for energy commodities, including electricity.

"(D) The economic effects of the markets, including to macro- and micro-economic effects of unexpected significant increases and decreases in the price of regulated instruments.

"(E) Any changes in the roles, activities, or strategies of various market participants.

"(F) Regional, industrial, and consumer responses to the markets, and energy investment responses to the markets.

"(G) Any other issue related to the markets that the Commission, Commodity Futures Trading Commission, deems appropriate.

"(2) ANNUAL REPORTS TO THE CONGRESS.— Not later than 1 month after the end of each calendar year, the Commission, in conjunction with the Federal agency, shall submit to the President, the Committee on Agriculture and Committee on Energy and Commerce of the House of Representatives, and the Committee on Agriculture, Nutrition, and Forestry and Committee on Energy and Natural Resources of the Senate, and make available to the public, a report on the matters described in paragraph (1) with respect to the year, including recommendations for any administrative or statutory measures the Commission, and the Commodity Futures Trading Commission consider necessary to address any threats to the transparency, fairness, or integrity of the markets in regulated instruments.

"SEC. 402. APPLICABILITY OF PART III PROVISIONS.

"(a) SECTIONS 301, 304, AND 306.—Sections 301, 304, and 306 shall not apply to this part. "(b) SECTION 315.—In applying section 315(a) to this part, the words "person or entity" shall be substituted for the words "licensee or public utility". In applying section 315(b) to this part, the words "an entity" shall be substituted for the words "a licensee or public utility" and the words "such entity" shall be substituted for the words "such entity" shall be substituted for the words "such licensee or public utility."

"(c) SECTION 316.—Section 316(a) shall not apply to section 401(d).".

(b) CRIMINAL PROHIBITION AGAINST FRAUD AND FALSE OR MISLEADING STATEMENTS.—

(1) Chapter 47 of title 18, United States Code, is amended by adding at the end the following:

"\$ 1041. Fraud and false statements in connection with regulated allowances

"Whoever in connection with a transaction involving a regulated allowance (as defined in section 401(a) of the Federal Power Act, as added by section 341 of the American Clean Energy and Security Act of 2009), knowingly—

"(1) makes or uses a materially false or misleading statement, writing, representation, scheme, or device; or

"(2) falsifies, conceals, or covers up by any trick, scheme, or device any material fact, shall be fined not more than \$5,000,000 (or \$25,000,000 in the case of an organization) or imprisoned not more than 20 years, or both."

(2) The table of sections at the beginning of chapter 47 of title 18, United States Code, is amended by adding at the end the following new item:

"1041. Fraud and false statements in connection with regulated allowances."

SEC. 342. CARBON DERIVATIVE MARKETS.

(a) Section 1a(14) of the Commodity Exchange Act (7 U.S.C. 1a(14)) is amended by striking "or an agricultural commodity" and inserting ", an agricultural commodity, or any emission allowance, compensatory allowance, offset credit, or Federal renewable electricity credit established or issued under the American Clean Energy and Security Act of 2009".

(b) Section 4(c) of such Act (7 U.S.C. 6(c)) is amended by adding at the end the following:

"(6) This subsection does not apply to any agreement, contract, or transaction for any emission allowance, compensatory allowance, offset credit, or Federal renewable electricity credit established or issued under the American Clean Energy and Security Act of 2009."

Subtitle E—Additional Market Assurance

SEC. 351. REGULATION OF CERTAIN TRANS-ACTIONS IN DERIVATIVES INVOLV-ING ENERGY COMMODITIES.

(a) ENERGY COMMODITY DEFINED.—Section 1a of the Commodity Exchange Act (7 U.S.C. 1a) is amended—

(1) in paragraph (14), by inserting ", an energy commodity," after "excluded commodity";

(2) by redesignating paragraphs (13) through (21) and paragraphs (22) through (34) as paragraphs (14) through (22) and paragraphs (24) through (36), respectively;

(3) by inserting after paragraph (12) the following:

"(13) ENERGY COMMODITY.—The term 'energy commodity' means—

"(A) coal;

"(B) crude oil, gasoline, diesel fuel, jet fuel, heating oil, and propane;

"(C) electricity (excluding financial transmission rights which are subject to regulation and oversight by the Federal Energy Regulatory Commission);

"(D) natural gas; and

"(E) any other substance (other than an excluded commodity, a metal, or an agricultural commodity) that is used as a source of energy, as the Commission, in its discretion, deems appropriate.": and

(4) by inserting after paragraph (22) (as so redesignated by paragraph (2) of this subsection) the following:

"(23) INCLUDED ENERGY TRANSACTION.—The term 'included energy transaction' means a contract, agreement, or transaction in an energy commodity for future delivery that provides for a delivery point of the energy commodity in the United States or a territory or possession of the United States, or that is offered or transacted on or through a computer terminal located in the United States.".

(b) EXTENSION OF REGULATORY AUTHORITY TO SWAPS INVOLVING ENERGY TRANSACTIONS.—Section 2(g) of such Act (7 U.S.C. 2(g)) is amended by inserting "or an energy commodity" after "agricultural commodity"

modity'

(c) ELIMINATION OF EXEMPTION FOR OVER-THE-COUNTER SWAPS INVOLVING ENERGY COM-MODITIES.—Section 2(h)(1) of such Act (7 U.S.C. 2(h)(1)) is amended by inserting "(other than an energy commodity)" after "exempt commodity".

(d) EXTENSION OF REGULATORY AUTHORITY TO INCLUDED ENERGY TRANSACTIONS ON FOREIGN BOARDS OF TRADE.—Section 4 of such

Act (7 U.S.C. 6) is amended—

(1) in subsection (a), by inserting ", and which is not an included energy transaction" after "territories or possessions" the 2nd place it appears; and

(2) in subsection (b), by adding at the end the following: "The preceding sentence shall not apply with respect to included energy transactions."

(e) LIMITATION OF GENERAL EXEMPTIVE AUTHORITY OF THE CFTC WITH RESPECT TO INCLUDED ENERGY TRANSACTIONS.—

(1) IN GENERAL.—Section 4(c) of such Act (7 U.S.C. 6(c)) is amended by adding at the end the following:

"(6) The Commission may not exempt any included energy transaction from the requirements of subsection (a), unless the Commission provides 60 days advance notice to the Congress and the Position Limit Energy Advisory Group and solicits public comment about the exemption request and any proposed Commission action."

(2) NULLIFICATION OF NO-ACTION LETTER EXEMPTIONS TO CERTAIN REQUIREMENTS APPLICABLE TO INCLUDED ENERGY TRANSACTIONS.—Beginning 180 days after the date of the enactment of this Act, any exemption provided by the Commodity Futures Trading Commission that has allowed included energy transactions (as defined in section 1a(13) of the Commodity Exchange Act) to be conducted without regard to the requirements of section 4(a) of such Act shall be null and void.

(f) REQUIREMENT TO ESTABLISH UNIFORM SPECULATIVE POSITION LIMITS FOR ENERGY TRANSACTIONS.—

(1) IN GENERAL.—Section 4a(a) of such Act (7 U.S.C. 6a(a)) is amended—

(A) by inserting "(1)" after "(a)";

- (B) by inserting after the 2nd sentence the following: "With respect to energy transactions, the Commission shall fix limits on the aggregate number of positions which may be held by any person for each month across all markets subject to the jurisdiction of the Commission.":
- (C) in the 4th sentence by inserting ", consistent with the 3rd sentence," after "Commission"; and
- (D) by adding after and below the end the following:
- "(2)(A) Not later than 60 days after the date of the enactment of this paragraph, the Commission shall convene a Position Limit Energy Advisory Group consisting of representatives from—
- "(i) 7 predominantly commercial short hedgers of the actual energy commodity for future delivery:
- "(ii) 7 predominantly commercial long hedgers of the actual energy commodity for future delivery:
- "(iii) 4 non-commercial participants in markets for energy commodities for future delivery; and
- "(iv) each designated contract market or derivatives transaction execution facility upon which a contract in the energy commodity for future delivery is traded, and each electronic trading facility that has a significant price discovery contract in the energy commodity.
- "(B) Not later than 60 days after the date on which the advisory group is convened under subparagraph (A), and annually thereafter, the advisory group shall submit to the Commission advisory recommendations regarding the position limits to be established in paragraph (1).
- "(C) The Commission shall have exclusive authority to grant exemptions for bona fide hedging transactions and positions from position limits imposed under this Act on energy transactions."
 - (2) CONFORMING AMENDMENTS.—
- (A) SIGNIFICANT PRICE DISCOVERY CONTRACTS.—Section 2(h)(7) of such Act (7 U.S.C. 2(h)(7)) is amended—
- $(i) \ in \ subparagraph \ (A) \!\!-\!\!\!-\!\!\!\!-$
- (I) by inserting "of this paragraph and section 4a(a)" after "(B) through (D)"; and
- (II) by inserting ''of this paragraph'' before the period; and
- (ii) in subparagraph (C)(ii)(IV)—
- (I) in the heading, by striking "LIMITATIONS OR"; and
- (II) by striking "position limitations or".(B) CONTRACTS TRADED ON OR THROUGH DES-
- (B) CONTRACTS TRADED ON OR THROUGH DES-IGNATED CONTRACT MARKETS.—Section 5(d)(5) of such Act (7 U.S.C. 7(d)(5)) is amended—
- (i) in the heading by striking "LIMITATIONS OR"; and
- (ii) by striking "position limitations or".
- (C) CONTRACTS TRADED ON OR THROUGH DE-RIVATIVES TRANSACTION EXECUTION FACILI-TIES.—Section 5a(d)(4) of such Act (7 U.S.C. 7a(d)(4)) is amended—
- (i) in the heading by striking "LIMITATIONS OR"; and
- (ii) by striking "position limits or".
- (g) ELIMINATION OF THE SWAPS LOOPHOLE.— Section 4a(c) of such Act (7 U.S.C. 6a(c)) is amended—
 - (1) by inserting "(1)" after "(c)"; and
- (2) by adding after and below the end the following:
- "(2) For the purposes of contracts of sale for future delivery and options on such contracts or commodities, the Commission shall define what constitutes a bona fide hedging transaction or position as a transaction or position that—
- "(A)(i) represents a substitute for transactions made or to be made or positions taken or to be taken at a later time in a physical marketing channel;

- "(ii) is economically appropriate to the reduction of risks in the conduct and management of a commercial enterprise; and
- "(iii) arises from the potential change in the value of— $\,$
- "(I) assets that a person owns, produces, manufactures, processes, or merchandises or anticipates owning, producing, manufacturing, processing, or merchandising;
- "(II) liabilities that a person owns or anticipates incurring; or
- "(III) services that a person provides, purchases, or anticipates providing or purchasing; or
- "(B) reduces risks attendant to a position resulting from a transaction that—
- "(i) was executed pursuant to subsection (d), (g), (h)(1), or (h)(2) of section 2, or an exemption issued by the Commission by rule, regulation or order; and
- "(ii) was executed opposite a counterparty for which the transaction would qualify as a bona fide hedging transaction pursuant to paragraph (2)(A) of this subsection.".
- (h) DETAILED REPORTING AND DISAGGREGATION OF MARKET DATA.—Section 4 of such Act (7 U.S.C. 6) is amended by adding at the end the following:
- "(e) DETAILED REPORTING AND DISAGGREGATION OF MARKET DATA.—
- "(1) INDEX TRADERS AND SWAP DEALERS RE-PORTING.—The Commission shall issue a proposed rule defining and classifying index traders and swap dealers (as those terms are defined by the Commission) for purposes of data reporting requirements and setting routine detailed reporting requirements for any positions of such entities in contracts traded on designated contract markets, over-thecounter markets, derivatives transaction execution facilities, foreign boards of trade subject to section 4(f), and electronic trading facilities with respect to significant price discovery contracts not later than 120 days after the date of the enactment of this subsection, and issue a final rule within 180 days after such date of enactment.
- "(2) DISAGGREGATION OF INDEX FUNDS AND OTHER DATA IN MARKETS.—Subject to section 8 and beginning within 60 days of the issuance of the final rule required by paragraph (1), the Commission shall disaggregate and make public weekly—
- "(A) the number of positions and total notional value of index funds and other passive, long-only and short-only positions (as defined by the Commission) in all markets to the extent such information is available; and
- "(B) data on speculative positions relative to bona fide physical hedgers in those markets to the extent such information is available.
- "(3) DISCLOSURE OF IDENTITY OF HOLDERS OF POSITIONS IN INDEXES IN EXCESS OF POSITION LIMITS.—The Commission shall include in its weekly Commitment of Trader reports the identity of each person who holds a position in an index in excess of a limit imposed under section 4i.".
- (i) AUTHORITY TO SET LIMITS TO PREVENT EXCESSIVE SPECULATION IN INDEXES.—
- (1) IN GENERAL.—Section 4a of such Act (7 U.S.C. 6a) is amended by adding at the end the following:
- "(f) The provisions of this section shall apply to the amounts of trading which may be done or positions which may be held by any person under contracts of sale of an index for future delivery on or subject to the rules of any contract market, derivatives transaction execution facility, or over-the-counter market, or on an electronic trading facility with respect to a significant price discovery contract, in the same manner in which this section applies to contracts of sale of a commodity for future delivery.".
- (2) REGULATIONS.—The Commodity Futures Trading Commission shall issue regulations

under section 4a(f) of the Commodity Exchange Act within 180 days after the date of the enactment of this Act.

SEC. 352. NO EFFECT ON AUTHORITY OF THE FEDERAL ENERGY REGULATORY COMMISSION.

Section 2 of the Commodity Exchange Act (7 U.S.C. 2) is amended by adding at the end the following:.

"(j) This Act shall not be interpreted to affect the jurisdiction of the Federal Energy Regulatory Commission with respect to the authority of the Federal Energy Regulatory Commission under the Federal Power Act (16 U.S.C. 791a et seq.), the Natural Gas Act (15 U.S.C. 717 et seq.), or other law to obtain information, carry out enforcement actions, or otherwise carry out the responsibilities of the Federal Energy Regulatory Commission."

SEC. 353. INSPECTOR GENERAL OF THE COM-MODITY FUTURES TRADING COM-MISSION.

- (a) ELEVATION OF OFFICE.—
- (1) Inclusion of cftc in definition of establishment.—
- (A) Section 12(1) of the Inspector General Act of 1978 (5 U.S.C. App.) is amended by striking "or the Federal Cochairpersons of the Commissions established under section 15301 of title 40, United States Code;" and inserting "the Federal Cochairpersons of the Commissions established under section 15301 of title 40, United States Code; or the Chairman of the Commodity Futures Trading Commission;".
- (B) Section 12(2) of the Inspector General Act of 1978 (5 U.S.C. App.) is amended by striking "or the Commissions established under section 15301 of title 40, United States Code," and inserting "the Commissions established under section 15301 of title 40, United States Code, or the Commodity Futures Trading Commission."
- (2) EXCLUSION OF CFTC FROM DEFINITION OF DESIGNATED FEDERAL ENTITY.—Section 8G(a)(2) of the Inspector General Act of 1978 (5 U.S.C. App.) is amended by striking "the Commodity Futures Trading Commission,".
- (b) Provisions Relating to Pay and Personnel Authority.—
- (1) PROVISION RELATING TO THE POSITION OF INSPECTOR GENERAL OF THE CFTC.—In the case of the Inspector General of the Commodities Futures Trading Commission, subsections (b) and (c) of section 4 of the Inspector General Reform Act of 2008 (Public Law 110-409) shall apply in the same manner as if the Commission was a designated Federal entity under section 8G. The Inspector General of the Commodities Futures Trading Commission shall not be subject to section 3(e) of such Act.
- PROVISION RELATING TO OTHER PER-SONNEL.—Notwithstanding paragraphs (7) and (8) of section 6(a) of the Inspector General Act of 1978 (5 U.S.C. App.), the Inspector General of the Commodities Futures Trading Commission may select, appoint, and employ such officers and employees as may be necessary for carrying out the functions, powers, and duties of the Office of Inspector General and to obtain the temporary or intermittent services of experts or consultants or an organization of experts or consultants. subject to the applicable laws and regulations that govern such selections, appointments, and employment, and the obtaining of such services, within the Commodities Futures Trading Commission.
 - (c) EFFECTIVE DATE; TRANSITION RULE.—
- (1) EFFECTIVE DATE.—The amendments made by this section shall take effect 30 days after the date of the enactment of this Act.
- (2) Transition Rule.—An individual serving as Inspector General of the Commodity

Futures Trading Commission on the effective date of this section pursuant to an appointment made under section 8G of the Inspector General Act of 1978 (5 U.S.C. App.)—

- (A) may continue so serving until the President makes an appointment under section 3(a) of such Act consistent with the amendments made by this section; and
- (B) shall, while serving under subparagraph (A), remain subject to the provisions of section 8G of such Act which apply with respect to the Commodity Futures Trading Commission.

SEC. 354. SETTLEMENT AND CLEARING THROUGH REGISTERED DERIVATIVES CLEAR-ING ORGANIZATIONS.

- (a) IN GENERAL.—
- (1) APPLICATION TO EXCLUDED DERIVATIVE TRANSACTIONS.—
- (A) Section 2(d)(1) of the Commodity Exchange Act (7 U.S.C. 2(d)(1)) is amended—
- (i) by striking "and" at the end of subparagraph (A):
- (ii) by striking the period at the end of subparagraph (B) and inserting "; and"; and (iii) by adding at the end the following:
- "(C) except as provided in section 4(f), the agreement, contract, or transaction is settled and cleared through a derivatives clearing organization registered with the Commission."
- (B) Section 2(d)(2) of such Act (7 U.S.C. 2(d)(2)) is amended—
- (i) by striking "and" at the end of subparagraph (B);
- (ii) by striking the period at the end of subparagraph (C) and inserting "; and"; and
- (iii) by adding at the end the following: "(D) except as provided in section 4(f), the agreement, contract, or transaction is settled and cleared through a derivatives clear-
- agreement, contract, or transaction is settled and cleared through a derivatives clearing organization registered with the Commission.".
- (2) APPLICATION TO CERTAIN SWAP TRANS-ACTIONS.—Section 2(g) of such Act (7 U.S.C. 2(g)) is amended—
- (A) by striking "and" at the end of paragraph (2);
- (B) by striking the period at the end of paragraph (3) and inserting "; and"; and
- (C) by adding at the end the following:
- "(4) except as provided in section 4(f), settled and cleared through a derivatives clearing organization registered with the Commission.".
- (3) Application to certain transactions in exempt commodities.—
- (A) Section 2(h)(1) of such Act (7 U.S.C. 2(h)(1)) is amended—
- (i) by striking "and" at the end of subparagraph (A):
- (ii) by striking the period at the end of subparagraph (B) and inserting "; and"; and (iii) by adding at the end the following:
- "(C) except as provided in section A(f), is settled and cleared through a derivatives clearing organization registered with the Commission."
- (B) Section 2(h)(3) of such Act (7 U.S.C. 2(h)(3)) is amended—
- (i) by striking "and" at the end of subparagraph (A);
- (ii) by striking the period at the end of subparagraph (B) and inserting "; and"; and (iii) by adding at the end the following:
- "(C) except as provided in section 4(f), settled and cleared through a derivatives clearing organization registered with the Commission.".
- (4) GENERAL EXEMPTIVE AUTHORITY.—Section 4(c)(1) of such Act (7 U.S.C. 6(c)(1)) is amended by inserting "the agreement, contract, or transaction, except as provided in section 4(h), will be settled and cleared through a derivatives clearing organization registered with the Commission and" before "the Commission determines".

- (5) CONFORMING AMENDMENT RELATING TO SIGNIFICANT PRICE DISCOVERY CONTRACTS.—Section 2(h)(7)(D) of such Act (7 U.S.C. 2(h)(7)(D)) is amended by striking the designation and heading for the subparagraph and all that follows through "As part of" and inserting the following:
- "(D) REVIEW OF IMPLEMENTATION.—As part of"
- (b) ALTERNATIVES TO CLEARING THROUGH DESIGNATED CLEARING ORGANIZATIONS.—Section 4 of such Act (7 U.S.C. 6), as amended by section 351(h) of this Act, is amended by adding at the end the following:
- (f) ALTERNATIVES TO CLEARING THROUGH DESIGNATED CLEARING ORGANIZATIONS.—
- "(1) SETTLEMENT AND CLEARING THROUGH CERTAIN OTHER REGULATED ENTITIES.—An agreement, contract, or transaction, or class thereof, relating to an excluded commodity, that would otherwise be required to be settled and cleared by section 2(d)(1)(C), 2(g)(4), 2(h)(1)(C), or 2(h)(3)(C) of this Act, or subsection (c)(1) of this section may be settled and cleared through an entity listed in subsections (a) or (b) of section 409 of the Federal Deposit Insurance Corporation Improvement Act of 1991.
- "(2) WAIVER OF CLEARING REQUIREMENT.—
- "(A) The Commission, in its discretion, may exempt an agreement, contract, or transaction, or class thereof, that would otherwise be required by section 2(d)(1)(C), 2(d)(2)(D), 2(g)(4), 2(h)(1)(C), or 2(h)(3)(C) of this Act, or subsection (c)(1) of this section to be settled and cleared through a derivatives clearing organization registered with the Commission from such requirement.
- "(B) In granting exemptions pursuant to subparagraph (A), the Commission shall consult with the Securities and Exchange Commission and the Board of Governors of the Federal Reserve System regarding exemptions that relate to excluded commodities or entities for which the Securities Exchange Commission or the Board of Governors of the Federal Reserve System serve as the primary regulator.
- "(C) Before granting an exemption pursuant to subparagraph (A), the Commission shall find that the agreement, contract, or transaction, or class thereof—
- "(i) is highly customized as to its material terms and conditions;
- "(ii) is transacted infrequently;
- "(iii) does not serve a significant price-discovery function in the marketplace; and
- "(iv) is being entered into by parties who can demonstrate the financial integrity of the agreement, contract, or transaction and their own financial integrity, as such terms and standards are determined by the Commission. The standards may include, with respect to any federally regulated financial entity for which net capital requirements are imposed, a net capital requirement associated with any agreement, contract, or transaction subject to an exemption from the clearing requirement that is higher than the net capital requirement that would be associated with such a transaction were it cleared
- "(D) Any agreement, contract, or transaction, or class thereof, which is exempted pursuant to subparagraph (A) shall be reported to the Commission in a manner designated by the Commission, or to such other entity the Commission deems appropriate.
- "(E) The Commission, the Securities and Exchange Commission and the Board of Governors of the Federal Reserve System shall enter into a memorandum of understanding by which the information reported to the Commission pursuant to subparagraph (D) with regard to excluded commodities or entities for which the Securities Exchange Commission or the Board of Governors of the Federal Reserve System serve as the primary

- regulator may be provided to the other agencies.
- "(g) SPOT AND FORWARD EXCLUSION.—The settlement and clearing requirements of section 2(d)(1)(C), 2(d)(2)(D), 2(g)(4), 2(h)(1)(C), 2(h)(3)(C), or 4(c)(1) shall not apply to an agreement, contract, or transaction of any cash commodity for immediate or deferred shipment or delivery, as defined by the Commission."
- (c) ADDITIONAL REQUIREMENTS APPLICABLE TO APPLICANTS FOR REGISTRATION AS A DERIVATIVE CLEARING ORGANIZATION.—Section 5b(c)(2) of such Act (7 U.S.C. 7a-1(c)(2)) is amended by adding at the end the following:
- "(O) DISCLOSURE OF GENERAL INFORMATION.—The applicant shall disclose publicly and to the Commission information concerning—
- "(i) the terms and conditions of contracts, agreements, and transactions cleared and settled by the applicant;
- "(ii) the conventions, mechanisms, and practices applicable to the contracts, agreements, and transactions;
- "(iii) the margin-setting methodology and the size and composition of the financial resource package of the applicant; and
- "(iv) other information relevant to participation in the settlement and clearing activities of the applicant.
- "(P) DAILY PUBLICATION OF TRADING INFORMATION.—The applicant shall make public daily information on settlement prices, volume, and open interest for contracts settled or cleared pursuant to the requirements of section 2(d)(1)(C), 2(d)(2)(D), 2(g)(4), 2(h)(1)(C), 2(h)(3)(C) or 4(c)(1) of this Act by the applicant if the Commission determines that the contracts perform a significant price discovery function for transactions in the cash market for the commodity underlying the contracts.
- "(Q) FITNESS STANDARDS.—The applicant shall establish and enforce appropriate fitness standards for directors, members of any disciplinary committee, and members of the applicant, and any other persons with direct access to the settlement or clearing activities of the applicant, including any parties affiliated with any of the persons described in this subparagraph."
 - (d) AMENDMENTS.—
- (1) Section 409 of the Federal Deposit Insurance Corporation Improvement Act of 1991 (12 U.S.C. 4422) is amended by adding at the end the following:
- "(c) CLEARING REQUIREMENT.—A multilateral clearing organization described in subsections (a) or (b) of this section shall comply with requirements similar to the requirements of sections 5b and 5c of the Commodity Exchange Act.".
- (2) Section 407 of the Legal Certainty for Bank Products Act of 2000 (7 U.S.C. 27e) is amended by inserting "and the settlement and clearing requirements of sections 2(d)(1)(C), 2(d)(2)(D), 2(g)(4), 2(h)(1)(C), 2(h)(3)(C), and 4(c)(1) of such Act" after "the clearing of covered swap agreements".
- (e) EFFECTIVE DATE.—The amendments made by this section shall take effect 150 days after the date of the enactment of this Act.
- (f) Transaction Rule.—Any agreement, contract, or transaction entered into before the date of the enactment of this Act or within 150 days after such date of enactment, in reliance on subsection (d), (g), (h)(1), or (h)(3) of section 2 of the Commodity Exchange Act or any other exemption issued by the Commission Futures Trading Commission by rule, regulation, or order shall, within 90 days after such date of enactment, unless settled and cleared through an entity registered with the Commission as a derivatives clearing organization or another clearing entity pursuant to section 4(f) of such Act, be

reported to the Commission in a manner designated by the Commission, or to such other entity as the Commission deems appropriate. SEC. 355. LIMITATION ON ELIGIBILITY TO PUR-

CHASE A CREDIT DEFAULT SWAP.

(a) IN GENERAL.—Section 4c of the Commodity Exchange Act (7 U.S.C. 6c) is amended by adding at the end the following:

"(h) LIMITATION ON ELIGIBILITY TO PURCHASE A CREDIT DEFAULT SWAP.—It shall be unlawful for any person to enter into a credit default swap unless the person—

"(1) owns a credit instrument which is insured by the credit default swap:

"(2) would experience financial loss if an event that is the subject of the credit default swap occurs with respect to the credit instrument: and

"(3) meets such minimum capital adequacy standards as may be established by the Commission, in consultation with the Board of Governors of the Federal Reserve System, or such more stringent minimum capital adequacy standards as may be established by or under the law of any State in which the swap is originated or entered into, or in which possession of the contract involved takes

(b) ELIMINATION OF PREEMPTION OF STATE BUCKETING LAWS REGARDING NAKED CREDIT DEFAULT SWAPS.—Section 12(e)(2)(B) of such Act (7 U.S.C. 16(e)(2)(B)) is amended by inserting "(other than a credit default swap in which the purchaser of the swap would not experience financial loss if an event that is the subject of the swap occurred)" before "that is excluded".

(c) DEFINITION OF CREDIT DEFAULT SWAP.— Section 1a of such Act (7 U.S.C. 1a), as amended by section 351(a) of this Act, is amended by adding at the end the following:

- '(37) CREDIT DEFAULT SWAP.—The term 'credit default swap' means a contract which insures a party to the contract against the risk that an entity may experience a loss of value as a result of an event specified in the contract, such as a default or credit downgrade. A credit default swap that is traded on or cleared by a registered entity shall be excluded from the definition of a security as defined in this Act and in section 2(a)(1) of the Securities Act of 1933 or section 3(a)(10) of the Securities Exchange Act of 1934, except it shall be deemed a security solely for purpose of enforcing prohibitions against insider trading in sections 10 and 16 of the Securities Exchange Act of 1934.".
 (d) EFFECTIVE DATE.—The amendments
- (d) EFFECTIVE DATE.—The amendments made by this section shall be effective for credit default swaps (as defined in section 1a(37) of the Commodity Exchange Act) entered into after 60 days after the date of the enactment of this section.

SEC. 356. TRANSACTION FEES.

(a) IN GENERAL.—Section 12 of the Commodity Exchange Act (7 U.S.C. 16) is amended by redesignating subsections (e), (f), and (g) as subsections (f), (g), and (h), respectively, and inserting after subsection (d) the following:

"(e) CLEARING FEES.—

- "(1) IN GENERAL.—The Commission shall, in accordance with this subsection, charge and collect from each registered clearing organization, and each such organization shall pay to the Commission, transaction fees at a rate calculated to recover the costs to the Federal Government of the supervision and regulation of futures markets, except those directly related to enforcement.
- $\lq\lq(2)$ FEES ASSESSED PER SIDE OF CLEARED CONTRACTS.—
- "(A) IN GENERAL.—The Commission shall determine the fee rate referred to in paragraph (1), and shall apply the fee rate per side of any transaction cleared.

"(B) AUTHORITY TO DELEGATE.— The Commission may determine the procedures by

which the fee rate is to be applied on the transactions subject to the fee, or delegate the authority to make the determination to any appropriate derivatives clearing organization.

"(3) EXEMPTIONS.—The Commission may not impose a fee under paragraph (1) on—

"(A) a class of contracts or transactions if the Commission finds that it is in the public interest to exempt the class from the fee; or

 $\lq\lq(B)$ a contract or transaction cleared by a registered derivatives clearing organization that is—

"(i) subject to fees under section 31 of the Securities Exchange Act of 1934; or

"(ii) a security as defined in the Securities Act of 1933 or the Securities Exchange Act of 1934.

"(4) DATES FOR PAYMENT OF FEES.—The fees imposed under paragraph (1) shall be paid on or before—

"(A) March 15 of each year, with respect to transactions occurring on or after the preceding September 1 and on or before the preceding December 31; and

"(B) September 15 of each year, with respect to transactions occurring on or after the preceding January 1 and on or before the preceding August 31.

"(5) ANNUAL ADJUSTMENT OF FEE RATES.—

"(A) In general.—Not later than April 30 of each fiscal year, the Commission shall, by order, adjust each fee rate determined under paragraph (2) for the fiscal year to a uniform adjusted rate that, when applied to the estimated aggregate number of cleared sides of transactions for the fiscal year, is reasonably likely to produce aggregate fee receipts under this subsection for the fiscal year equal to the target offsetting receipt amount for the fiscal year.

"(B) DEFINITIONS.—In subparagraph (A):

- "(i) ESTIMATED AGGREGATE NUMBER OF CLEARED SIDES OF TRANSACTIONS.—The term restimated aggregate number of cleared sides of transactions' means, with respect to a fiscal year, the aggregate number of cleared sides of transactions to be cleared by registered derivatives clearing organizations during the fiscal year, as estimated by the Commission, after consultation with the Office of Management and Budget, using the methodology required for making projections pursuant to section 257 of the Balanced Budget and Emergency Deficit Control Act of 1985.
- "(ii) Target offsetting receipt amount' means, with respect to a fiscal year, the total level of Commission budget authority for all non-enforcement activities of the Commission, as contained in the regular appropriations Acts for the fiscal year.

"(C) NO JUDICIAL REVIEW.—An adjusted fee rate prescribed under subparagraph (A) shall not be subject to judicial review.

"(6) PUBLICATION.—Not later than April 30 of each fiscal year, the Commission shall cause to be published in the Federal Register notices of the fee rates applicable under this subsection for the succeeding fiscal year, and any estimate or projection on which the fee rates are based.

"(7) ESTABLISHMENT OF FUTURES AND OPTIONS TRANSACTION FEE ACCOUNT; DEPOSIT OF FEES.—There is established in the Treasury of the United States an account which shall be known as the 'Futures and Options Transaction Fee Account'. All fees collected under this subsection for a fiscal year shall be deposited in the account. Amounts in the account are authorized to be appropriated to fund the expenditures of the Commission."

(b) EFFECTIVE DATE.—The amendments made by subsection (a) shall apply to fiscal years beginning 30 or more days after the date of the enactment of this Act.

(c) Transition Rule.—If this section becomes law after March 31 and before September 1 of a fiscal year, then paragraphs (5)(A) and (6) of section 12(e) of the Commodity Exchange Act shall be applied, in the case of the 1st fiscal year beginning after the date of the enactment of this Act, by substituting "August 31" for "April 30".

SEC. 357. NO EFFECT ON ANTITRUST LAW OR AUTHORITY OF THE FEDERAL TRADE COMMISSION.

(a) Nothing in this subtitle shall be construed to modify, impair, or supersede the operation of any of the antitrust laws. For purposes of this subsection, the term "antitrust laws" has the meaning given it in subsection (a) of the 1st section of the Clayton Act (15 U.S.C. 12(a)), except that such term includes section 5 of the Federal Trade Commission Act (15 U.S.C. 45) to the extent that such term applies to unfair methods of competition.

(b) Nothing in this subtitle shall be construed to affect or diminish the jurisdiction or authority of the Federal Trade Commission with respect to its authorities under the Federal Trade Commission Act (15 U.S.C. 41 et seq.) or the Energy Independence and Security Act of 2007 (Public Law 110–140) to obtain information, to carry out enforcement activities, or otherwise to carry out the responsibilities of the Federal Trade Commission.

SEC. 358. EFFECT OF DERIVATIVES REGULATORY REFORM LEGISLATION.

(a) STATUTES.—Upon the passage of legislation that includes derivatives regulatory reform, sections 351, 352, 354, 355, 356, and 357 shall be repealed.

(b) REGULATIONS.—Upon the passage of legislation that includes derivatives regulatory reform, any regulations promulgated under section 351, 352, 354, 355, 356, or 357 shall be considered null and void.

SEC. 359. CEASE-AND-DESIST AUTHORITY.

(a) NATURAL GAS ACT.—Section 20 of the Natural Gas Act (15 U.S.C. 717s) is amended by adding the following at the end:

"(e) CEASE-AND-DESIST PROCEEDINGS; TEM-PORARY ORDERS; AUTHORITY OF THE COMMIS-SION.—

"(1) IN GENERAL.—If the Commission finds. after notice and opportunity for hearing, that any entity may be violating, may have violated, or may be about to violate any provision of this Act, or any rule, regulation, restriction, condition, or order made or imposed by the Commission under the authority of this Act, the Commission may publish its findings and issue an order requiring such entity, and any other entity that is, was, or would be a cause of the violation, due to an act or omission the entity knew or should have known would contribute to such violation, to cease and desist from committing or causing such violation and any future violation of the same provision, rule, or regulation. Such order may, in addition to requiring an entity to cease and desist from committing or causing a violation, require such entity to comply, to provide an accounting and disgorgement, or to take steps to effect compliance, with such provision, rule, or regulation, upon such terms and conditions and within such time as the Commission may specify in such order. Any such order may, as the Commission deems appropriate, require future compliance or steps to effect future compliance, either permanently or for such period of time as the Commission may speci-

fy.

"(2) TIMING OF ENTRY.—An order issued under this subsection shall be entered only after notice and opportunity for a hearing, unless the Commission determines that notice and hearing prior to entry would be impracticable or contrary to the public interest.

- "(f) HEARING.—The notice instituting proceedings pursuant to subsection (e) shall fix a hearing date not earlier than 30 days nor later than 60 days after service of the notice unless an earlier or a later date is set by the Commission with the consent of any respondent so served.
- "(g) TEMPORARY ORDER.—Whenever the Commission determines that—
- "(1) a respondent may take actions to dissipate or convert assets prior to the completion of the proceedings referred to in subsection (e), and such assets would be necessary to comply with or otherwise satisfy a final enforcement order of the Commission pursuant to alleged violations or threatened violations specified in the notice instituting proceedings; or
- "(2) a respondent is engaged in actual or threatened violations of this Act or a Commission rule, regulation, restriction or order referred to in subsection (e).
- the Commission may issue a temporary order requiring the respondent to take such action to prevent dissipation or conversion of assets, significant harm to energy consumers, or substantial harm to the public interest, frustration of the Commission's ability to conduct the proceedings, or frustration of the Commission's ability to redress said violation at the conclusion of the proceedings, as the Commission deems appropriate pending completion of such proceedings
 - "(h) REVIEW OF TEMPORARY ORDERS.—
- "(1) COMMISSION REVIEW.—At any time after the respondent has been served with a temporary cease-and-desist order pursuant to subsection (g), the respondent may apply to the Commission to have the order set aside, limited, or suspended. If the respondent has been served with a temporary cease-and-desist order entered without a prior Commission hearing, the respondent may, within 10 days after the date on which the order was served, request a hearing on such application and the Commission shall hold a hearing and render a decision on such application at the earliest possible time.
- "(2) JUDICIAL REVIEW.—Within—
- "(A) 10 days after the date the respondent was served with a temporary cease-and-desist order entered with a prior Commission hearing; or
- "(B) 10 days after the Commission renders a decision on an application and hearing under paragraph (1),
- with respect to any temporary cease-and-desist order entered without a prior Commission hearing, the respondent may apply to the United States circuit court having jurisdiction over the circuit in which the respondent resides or has its principal place of business, or to the United States Court of Appeals for the District of Columbia Circuit, for an order setting aside, limiting, or suspending the effectiveness or enforcement of the order, and the court shall have jurisdiction to enter such an order. A respondent served with a temporary cease-and-desist order entered without a prior Commission hearing may not apply to the court except after hearing and decision by the Commission on the respondent's application under paragraph (1) of this subsection.
- "(3) NO AUTOMATIC STAY OF TEMPORARY ORDER.—The commencement of proceedings under paragraph (2) of this subsection shall not, unless specifically ordered by the court, operate as a stay of the Commission's order.
- "(4) EXCLUSIVE REVIEW.—Sections 19(d) and 24 shall not apply to a temporary order entered pursuant to this section.
- "(i) IMPLEMENTATION.—The Commission is authorized to adopt rules, regulations, and orders as it deems appropriate to implement this section.".

- (c) NATURAL GAS POLICY ACT OF 1978.—Section 504 of the Natural Gas Policy Act of 1978 (15 U.S.C. 3414) is amended by adding the following at the end:
- "(d) Cease-and-desist Proceedings; Temporary Orders; Authority of the Commission —
- "(1) IN GENERAL.—If the Commission finds, after notice and opportunity for hearing, that any entity may be violating, may have violated, or may be about to violate any provision of this Act, or any rule, regulation, restriction, condition, or order made or imposed by the Commission under the authority of this Act, the Commission may publish its findings and issue an order requiring such entity, and any other entity that is, was, or would be a cause of the violation, due to an act or omission the entity knew or should have known would contribute to such violation, to cease and desist from committing or causing such violation and any future violation of the same provision, rule, or regulation. Such order may, in addition to requiring an entity to cease and desist from committing or causing a violation, require such entity to comply, to provide an accounting and disgorgement, or to take steps to effect compliance, with such provision, rule, or regulation, upon such terms and conditions and within such time as the Commission may specify in such order. Any such order may, as the Commission deems appropriate, require future compliance or steps to effect future compliance, either permanently or for such period of time as the Commission may speci-
- "(2) TIMING OF ENTRY.—An order issued under this subsection shall be entered only after notice and opportunity for a hearing, unless the Commission determines that notice and hearing prior to entry would be impracticable or contrary to the public interest.
- "(3) Hearing.—The notice instituting proceedings pursuant to paragraph (1) shall fix a hearing date not earlier than 30 days nor later than 60 days after service of the notice unless an earlier or a later date is set by the Commission with the consent of any respondent so served.
- "(4) TEMPORARY ORDER.—Whenever the Commission determines that—
- "(A) a respondent may take actions to dissipate or convert assets prior to the completion of the proceedings referred to in paragraph (1) and such assets would be necessary to comply with or otherwise satisfy a final enforcement order of the Commission pursuant to alleged violations or threatened violations specified in the notice instituting proceedings; or
- "(B) a respondent is engaged in actual or threatened violations of this Act or a Commission rule, regulation, restriction or order referred to in paragraph (1),
- the Commission may issue a temporary order requiring the respondent to take such action to prevent dissipation or conversion of assets, significant harm to energy consumers, or substantial harm to the public interest, frustration of the Commission's ability to conduct the proceedings, or frustration of the Commission's ability to redress said violation at the conclusion of the proceedings, as the Commission deems appropriate pending completion of such proceedings.
 - "(5) REVIEW OF TEMPORARY ORDERS.—
- "(A) COMMISSION REVIEW.—At any time after the respondent has been served with a temporary cease-and-desist order pursuant to paragraph (4), the respondent may apply to the Commission to have the order set aside, limited, or suspended. If the respondent has been served with a temporary cease-and-desist order entered without a prior

- Commission hearing, the respondent may, within 10 days after the date on which the order was served, request a hearing on such application and the Commission shall hold a hearing and render a decision on such application at the earliest possible time.
 - "(B) JUDICIAL REVIEW.—Within—
- "(i) 10 days after the date the respondent was served with a temporary cease-and-desist order entered with a prior Commission hearing; or
- "(ii) 10 days after the Commission renders a decision on an application and hearing under subparagraph (A), with respect to any temporary cease-and-desist order entered without a prior Commission hearing, the respondent may apply to the United States circuit court having jurisdiction over the circuit in which the respondent resides or has its principal place of business, or to the United States Court of Appeals for the District of Columbia Circuit, for an order setting aside, limiting, or suspending the effectiveness or enforcement of the order, and the court shall have jurisdiction to enter such an order. A respondent served with a temporary cease-and-desist order entered without a prior Commission hearing may not apply to the court except after hearing and decision by the Commission on the respondent's application under paragraph (1) of this subsection.
- "(C) NO AUTOMATIC STAY OF TEMPORARY ORDER.—The commencement of proceedings under subparagraph (B) of this paragraph shall not, unless specifically ordered by the court, operate as a stay of the Commission's order.
- "(6) IMPLEMENTATION.—The Commission is authorized to adopt rules, regulations, and orders as it deems appropriate to implement this subsection.".

SEC. 360. PRESIDENTIAL REVIEW OF REGULATIONS.

Not later than 24 months after the date of enactment of this Act, the President shall review the offset regulations and derivatives regulations promulgated pursuant to the American Clean Energy and Security Act of 2009. The President shall determine whether such regulations adequately protect the United States financial system from systemic risk.

TITLE IV—TRANSITIONING TO A CLEAN ENERGY ECONOMY

Subtitle A—Ensuring Real Reductions in Industrial Emissions

SEC. 401. ENSURING REAL REDUCTIONS IN INDUSTRIAL EMISSIONS.

Title VII of the Clean Air Act is amended by inserting after part E the following new part:

"PART F—ENSURING REAL REDUCTIONS IN INDUSTRIAL EMISSIONS

"SEC. 761. PURPOSES.

- ''(a) PURPOSES OF PART.—The purposes of this part are—
- "(1) to promote a strong global effort to significantly reduce greenhouse gas emissions, and, through this global effort, stabilize greenhouse gas concentrations in the atmosphere at a level that will prevent dangerous anthropogenic interference with the climate system; and
- "(2) to prevent an increase in greenhouse gas emissions in countries other than the United States as a result of direct and indirect compliance costs incurred under this title.
- "(b) PURPOSES OF SUBPART 1.—The purposes of subpart 1 are additionally—
- "(1) to provide a rebate to the owners and operators of entities in domestic eligible industrial sectors for their greenhouse gas emission costs incurred under this title, but not for costs associated with other related or unrelated market dynamics;

- "(2) to design such rebates in a way that will prevent carbon leakage while also rewarding innovation and facility-level investments in energy efficiency performance improvements; and
- "(3) to eliminate or reduce distribution of emission allowances under subpart 1 when such distribution is no longer necessary to prevent carbon leakage from eligible industrial sectors.
- "(c) PURPOSES OF SUBPART 2.—The purposes of subpart 2 are additionally—
- "(1) to induce foreign countries, and, in particular, fast-growing developing countries, to take substantial action with respect to their greenhouse gas emissions consistent with the Bali Action Plan developed under the United Nations Framework Convention on Climate Change: and
- "(2) to ensure that the measures described in subpart 2 are designed and implemented in a manner consistent with applicable international agreements to which the United States is a party.

"SEC. 762. DEFINITIONS.

"In this part:

- "(1) CARBON LEAKAGE.—The term 'carbon leakage' means any substantial increase (as determined by the Administrator) in greenhouse gas emissions by industrial entities located in other countries if such increase is caused by an incremental cost of production increase in the United States resulting from the implementation of this title.
- "(2) COVERED GOOD.—The term 'covered good' means a good that, as identified by the Administrator by regulation, is either—
- "(A) entered under a heading or subheading of the Harmonized Tariff Schedule of the United States that corresponds to the NAICS code for an eligible industrial sector, as established in the concordance between NAICS codes and the Harmonized Tariff Schedule of the United States prepared by the United States Census Bureau; or
- "(B) a manufactured item for consumption.
 "(3) ELIGIBLE INDUSTRIAL SECTOR.—The term 'eligible industrial sector' means an industrial sector determined by the Administrator under section 763(b) to be eligible to receive emission allowance rebates under subpart 1.
- "(4) INDUSTRIAL SECTOR.—The term 'industrial sector' means any sector that is in the manufacturing sector (as defined in NAICS codes 31, 32, and 33) or that beneficiates or otherwise processes (including agglomeration) metal ores, including iron and copper ores, soda ash, or phosphate. The extraction of metal ores, soda ash, or phosphate shall not be considered to be an industrial sector.
- ``(5) Manufactured item for consumption.—
- "(A) IN GENERAL.—The term 'manufactured item for consumption' means any good—
- "(i) that includes in substantial amounts one or more goods like the goods produced by an eligible industrial sector;
- "(ii) with respect to which an international reserve allowance program pursuant to subpart 2 is in effect with regard to the eligible industrial sector and the quantity of international reserve allowances is not zero pursuant to section 768(b);
- "(iii) with respect to which the trade intensity of the industrial sector that produces the good, as measured consistent with section 763(b)(2)(A)(iii), is at least 15 percent; and
- "(iv) for which the domestic producers of the good have demonstrated, and the Administrator has determined, that the application of the international reserve allowance program pursuant to subpart 2 is technically and administratively feasible and appropriate to achieve the purposes of this part, taking into account the energy and green-

house gas intensity of the industrial sector that produces the good, as measured consistent with section 763(b)(2)(A)(ii), and the ability of such producers to pass on cost increases and other appropriate factors.

- "(B) RULE OF CONSTRUCTION.—A determination of the Administrator under subparagraph (A)(iv) shall not be considered to be a determination of the President under section 767(b).
- $\lq\lq(6)$ NAICS.—The term 'NAICS' means the North American Industrial Classification System of 2002.
- "(7) OUTPUT.—The term 'output' means the total tonnage or other standard unit of production (as determined by the Administrator) produced by an entity in an industrial sector. The output of the cement sector is hydraulic cement, and not clinker.

"Subpart 1—Emission Allowance Rebate Program

"SEC. 763. ELIGIBLE INDUSTRIAL SECTORS.

"(a) LIST.-

- "(1) INITIAL LIST.—Not later than June 30, 2011, the Administrator shall publish in the Federal Register a list of eligible industrial sectors pursuant to subsection (b). Such list shall include the amount of the emission allowance rebate per unit of production that shall be provided to entities in each eligible industrial sector in the following two calendar years pursuant to section 764.
- "(2) SUBSEQUENT LISTS.—Not later than February 1, 2013, and every four years thereafter, the Administrator shall publish in the Federal Register an updated version of the list published under paragraph (1).
 - "(b) Eligible Industrial Sectors.—
- "(1) IN GENERAL.—Not later than June 30, 2011, the Administrator shall promulgate a rule designating, based on the criteria under paragraph (2), the industrial sectors eligible for emission allowance rebates under this subpart
- ``(2) Presumptively eligible industrial sectors.—
- "(A) ELIGIBILITY CRITERIA.—
- "(i) IN GENERAL.—An owner or operator of an entity shall be eligible to receive emission allowance rebates under this subpart if such entity is in an industrial sector that is included in a six-digit classification of the NAICS that meets the criteria in both clauses (ii) and (iii), or the criteria in clause (iv).
- '(ii) ENERGY OR GREENHOUSE GAS INTENSITY.—As determined by the Administrator, the industrial sector had—
- "(I) an energy intensity of at least 5 percent, calculated by dividing the cost of purchased electricity and fuel costs of the sector by the value of the shipments of the sector, based on data described in subparagraph (D);
- "(II) a greenhouse gas intensity of at least 5 percent, calculated by dividing—
- "(aa) the number 20 multiplied by the number of tons of carbon dioxide equivalent greenhouse gas emissions (including direct emissions from fuel combustion, process emissions, and indirect emissions from the generation of electricity used to produce the output of the sector) of the sector based on data described in subparagraph (D); by
- "(bb) the value of the shipments of the sector, based on data described in subparagraph (D).
- "(iii) TRADE INTENSITY.—As determined by the Administrator, the industrial sector had a trade intensity of at least 15 percent, calculated by dividing the value of the total imports and exports of such sector by the value of the shipments plus the value of imports of such sector, based on data described in subparagraph (D).
- "(iv) Very high energy or greenhouse gas intensity.—As determined by the Ad-

- ministrator, the industrial sector had an energy or greenhouse gas intensity, as calculated under clause (ii)(I) or (II), of at least 20 percent.
- "(B) METAL AND PHOSPHATE PRODUCTION CLASSIFIED UNDER MORE THAN ONE NAICS CODE.—For purposes of this section, the Administrator shall—
- "(i) aggregate data for the beneficiation or other processing (including agglomeration) of metal ores, including iron and copper ores, soda ash, or phosphate with subsequent steps in the process of metal and phosphate manufacturing, regardless of the NAICS code under which such activity is classified; and
- "(ii) aggregate data for the manufacturing of steel with the manufacturing of steel pipe and tube made from purchased steel in a nonintegrated process.
- "(C) EXCLUSION.—The petroleum refining sector shall not be an eligible industrial sector.
 - "(D) DATA SOURCES.—
- "(i) ELECTRICITY AND FUEL COSTS, VALUE OF SHIPMENTS.—The Administrator shall determine electricity and fuel costs and the value of shipments under this subsection from data from the United States Census Annual Survey of Manufacturers. The Administrator shall take the average of data from as many of the years of 2004, 2005, and 2006 for which such data are available. If such data are unavailable, the Administrator shall make a determination based upon 2002 or 2006 data from the most detailed industrial classification level of Energy Information Agency's Manufacturing Energy Consumption Survey (using 2006 data if it is available) and the 2002 or 2007 Economic Census of the United States (using 2007 data if it is available). If data from the Manufacturing Energy Consumption Survey or Economic Census are unavailable for any sector at the six-digit classification level in the NAICS, then the Administrator may extrapolate the information necessary to determine the eligibility of a sector under this paragraph from available Manufacturing Energy Consumption Survey or Economic Census data pertaining to a broader industrial category classified in the NAICS. If data relating to the beneficiation or other processing (including agglomeration) of metal ores, including iron and copper ores, soda ash, or phosphate are not available from the specified data sources, the Administrator shall use the best available Federal or State government data and may use, to the extent necessary, representative data submitted by entities that perform such beneficiation or other processing (including agglomeration), in making a determination. Fuel cost data shall not include the cost of fuel used as feedstock by an industrial sec-
- "(ii) IMPORTS AND EXPORTS.—The Administrator shall base the value of imports and exports under this subsection on United States International Trade Commission data. The Administrator shall take the average of data from as many of the years of 2004, 2005, and 2006 for which such data are available. If data from the United States International Trade Commission are unavailable for any sector at the six-digit classification level in the NAICS, then the Administrator may extrapolate the information necessary to determine the eligibility of a sector under this paragraph from available United States International Trade Commission data pertaining to a broader industrial category classified in the NAICS.
- "(iii) PERCENTAGES.—The Administrator shall round the energy intensity, greenhouse gas intensity, and trade intensity percentages under subparagraph (A) to the nearest whole number.
- "(iv) Greenhouse gas emission calculations.—When calculating the tons of carbon

dioxide equivalent greenhouse gas emissions for each sector under subparagraph (A)(ii)(II)(aa), the Administrator—

"(I) shall use the best available data from as many of the years 2004, 2005, and 2006 for which such data is available; and

"(II) may, to the extent necessary with respect to a sector, use economic and engineering models and the best available information on technology performance levels for such sector.

"(3) ADMINISTRATIVE DETERMINATION OF ADDITIONAL ELIGIBLE INDUSTRIAL SECTORS.—

"(A) UPDATED TRADE INTENSITY DATA.—The Administrator shall designate as eligible to receive emission allowance rebates under this subpart an industrial sector that.—

"(i) met the energy or greenhouse gas intensity criteria in paragraph (2)(A)(ii) as of the date of promulgation of the rule under paragraph (1); and

"(ii) meets the trade intensity criteria in paragraph (2)(A)(iii), using data from any year after 2006.

"(B) INDIVIDUAL SHOWING PETITION.—

"(i) PETITION.—In addition to designation under paragraph (2) or subparagraph (A) of this paragraph, the owner or operator of an entity in an industrial sector may petition the Administrator to designate as eligible industrial sectors under this subpart an entity or a group of entities that—

"(I) represent a subsector of a six-digit section of the NAICS code; and

"(II) meet the eligibility criteria in both clauses (ii) and (iii) of paragraph (2)(A), or the eligibility criteria in clause (iv) of paragraph (2)(A).

"(ii) DATA.—In making a determination under this subparagraph, the Administrator shall consider data submitted by the petitioner that is specific to the entity, data solicited by the Administrator from other entities in the subsector, if such other entities exist, and data specified in paragraph (2)(D).

"(iii) Basis of subsector determination.—The Administrator shall determine an entity or group of entities to be a subsector of a six-digit section of the NAICS code based only upon the products manufactured and not the industrial process by which the products are manufactured, except that the Administrator may determine an entity or group of entities that manufacture a product from primarily virgin material to be a separate subsector from another entity or group of entities that manufacture the same product primarily from recycled material.

"(iv) USE OF MOST RECENT DATA.—In determining whether to designate a sector or subsector as an eligible industrial sector under this subparagraph, the Administrator shall use the most recent data available from the sources described in paragraph (2)(D), rather than the data from the years specified in paragraph (2)(D), to determine the trade intensity of such sector or subsector, but only for determining such trade intensity.

"(v) FINAL ACTION.—The Administrator shall take final action on such petition no later than 6 months after the petition is received by the Administrator.

"SEC. 764. DISTRIBUTION OF EMISSION ALLOW-ANCE REBATES.

"(a) DISTRIBUTION SCHEDULE.—

"(1) IN GENERAL.—For each vintage year, the Administrator shall distribute pursuant to this section emission allowances made available under section 782(e), no later than October 31 of the preceding calendar year. The Administrator shall make such annual distributions to the owners and operators of each entity in an eligible industrial sector in the amount of emission allowances calculated under subsection (b), except that—

"(A) for vintage years 2012 and 2013, the distribution for a covered entity shall be

pursuant to the entity's indirect carbon factor as calculated under subsection (b)(3);

"(B) for vintage year 2026 and thereafter, the distribution shall be pursuant to the amount calculated under subsection (b) multiplied by, except as modified by the President pursuant to section 767(d)(1)(C) for a sector—

"(i) 90 percent for vintage year 2026;

"(ii) 80 percent for vintage year 2027; "(iii) 70 percent for vintage year 2028;

"(iv) 60 percent for vintage year 2029;

"(v) 50 percent for vintage year 2030;

"(vi) 40 percent for vintage year 2031;

"(vii) 30 percent for vintage year 2032;

"(viii) 20 percent for vintage year 2033; "(ix) 10 percent for vintage year 2034; and

"(x) 0 percent for vintage year 2035 and thereafter.

"(2) RESUMPTION OF REDUCTION.—If the President has modified the percentage stated in paragraph (1)(B) under section 767(d)(1)(C), and the President subsequently makes a determination under section 767(c) for an eligible industrial sector that more than 85 percent of United States imports for that sector are produced or manufactured in countries that have met at least one of the criteria in that section, then the 10-year reduction schedule set forth in paragraph (1)(B) of this subsection shall begin in the next vintage year, with the percentage reduction based on

the amount of the distribution of emission

allowances under this section in the previous

"(3) Newly Eligible Sectors.—In addition to receiving a distribution of emission allowances under this section in the first distribution occurring after an industrial sector is designated as eligible under section 763(b)(3), the owner or operator of an entity in that eligible industrial sector may receive a prorated share of any emission allowances made available for distribution under this section that were not distributed for the year in which the petition for eligibility was granted under section 763(b)(3)(A).

"(4) CESSATION OF QUALIFYING ACTIVITIES.—
If, as determined by the Administrator, a facility is no longer in an eligible industrial sector designated under section 763—

"(A) the Administrator shall not distribute emission allowances to the owner or operator of such facility under this section; and

"(B) the owner or operator of such facility shall return to the Administrator all allowances that have been distributed to it for future vintage years and a pro-rated amount of allowances distributed to the facility under this section for the vintage year in which the facility ceases to be in an eligible industrial sector designated under section 763.

"(b) CALCULATION OF DIRECT AND INDIRECT CARBON FACTORS.—

"(1) IN GENERAL.—

"(A) COVERED ENTITIES.—Except as provided in subsection (a), for covered entities that are in eligible industrial sectors, the amount of emission allowance rebates shall be based on the sum of the covered entity's direct and indirect carbon factors.

"(B) OTHER ELIGIBLE ENTITIES.—For entities that are in eligible industrial sectors but are not covered entities, the amount of emission allowance rebates shall be based on the entity's indirect carbon factor.

"(C) NEW ENTITIES.—Not later than 2 years after the date of enactment of this title, the Administrator shall issue regulations governing the distribution of emission allowance rebates for the first and second years of operation of a new entity in an eligible industrial sector. These regulations shall provide for—

"(i) the distribution of emission allowance rebates to such entities based on comparable entities in the same sector; and "(ii) an adjustment in the third and fourth years of operation to reconcile the total amount of emission allowance rebates received during the first and second years of operation to the amount the entity would have received during the first and second years of operation had the appropriate data been available.

''(2) DIRECT CARBON FACTOR.—The direct carbon factor for a covered entity for a vintage year is the product of—

"(A) the average annual output of the covered entity for the two years preceding the year of the distribution; and

"(B) the most recent calculation of the average direct greenhouse gas emissions (expressed in tons of carbon dioxide equivalent) per unit of output for all covered entities in the sector, as determined by the Administrator under paragraph (4).

"(3) Indirect carbon factor.—

"(A) IN GENERAL.—The indirect carbon factor for an entity for a vintage year is the product obtained by multiplying the average annual output of the entity for the two years preceding the year of the distribution by both the electricity emissions intensity factor determined pursuant to subparagraph (B) and the electricity efficiency factor determined pursuant to subparagraph (C) for the year concerned.

"(B) ELECTRICITY EMISSIONS INTENSITY FACTOR.—

"(i) IN GENERAL.—Each person selling electricity to the owner or operator of an entity in any sector designated as an eligible industrial sector under section 763(b) shall provide the owner or operator of the entity and the Administrator, on an annual basis, the electricity emissions intensity factor for the entity. The electricity emissions intensity factor for the entity, expressed in tons of carbon dioxide equivalents per kilowatt hour, is determined by dividing—

"(I) the annual sum of the hourly product of—

"(aa) the electricity purchased by the entity from that person in each hour (expressed in kilowatt hours); multiplied by

"(bb) the marginal or weighted average tons of carbon dioxide equivalent per kilowatt hour that are reflected in the electricity charges to the entity, as determined by the entity's retail rate arrangements: by

"(II) the total kilowatt hours of electricity purchased by the entity from that person during that year.

"(ii) USE OF OTHER DATA TO DETERMINE FACTOR.—Where it is not possible to determine the precise electricity emissions intensity factor for an entity using the methodology in clause (i), the person selling electricity shall use the monthly average data reported by the Energy Information Administration or collected and reported by the Administrator for the utility serving the entity to determine the electricity emissions intensity factor.

"(C) ELECTRICITY EFFICIENCY FACTOR.—The electricity efficiency factor is the average amount of electricity (in kilowatt hours) used per unit of output for all entities in the relevant sector, as determined by the Administrator based on the best available data, including data provided under paragraph (6).

"(D) INDIRECT CARBON FACTOR REDUCTION.—
If an electricity provider received a free allocation of emission allowances pursuant to section 782(a), the Administrator shall adjust the indirect carbon factor to avoid rebates to the eligible entity for costs that the Administrator determines were not incurred by the eligible entity because the allowances were freely allocated to the eligible entity's electricity provider and used for the benefit of industrial consumers.

"(4) GREENHOUSE GAS INTENSITY CALCULA-TIONS.—The Administrator shall calculate the average direct greenhouse gas emissions (expressed in tons of carbon dioxide equivalent) per unit of output and the electricity efficiency factor for all covered entities in each eligible industrial sector every four years, using an average of the four most recent years of the best available data. For purposes of the lists required to be published no later than February 1, 2013, the Administrator shall use the best available data for the maximum number of years, up to 4 years, for which data are available.

"(5) Ensuring efficiency improvements.— When making greenhouse gas calculations, the Administrator shall—

"(A) limit the average direct greenhouse gas emissions per unit of output, calculated under paragraph (4), for any eligible industrial sector to an amount that is not greater than it was in any previous calculation under this subsection;

"(B) limit the electricity emissions intensity factor, calculated under paragraph (3)(B) and resulting from a change in electricity supply, for any entity to an amount that is not greater than it was during any previous year; and

"(C) limit the electricity efficiency factor, calculated under paragraph (3)(C), for any eligible industrial sector to an amount that is not greater than it was in any previous calculation under this subsection.

"(6) DATA SOURCES.—For the purposes of this subsection—

"(A) the Administrator shall use data from the greenhouse gas registry established under section 713, where it is available; and

"(B) each owner or operator of an entity in an eligible industrial sector and each department, agency, and instrumentality of the United States shall provide the Administrator with such information as the Administrator finds necessary to determine the direct carbon factor and the indirect carbon factor for each entity subject to this section

"(c) Total Maximum Distribution.—Notwithstanding subsections (a) and (b), the Administrator shall not distribute more allowances for any vintage year pursuant to this section than are allocated for use under this subpart pursuant to section 782(e) for that vintage year. For any vintage year for which the total emission allowance rebates calculated pursuant to this section exceed the number of allowances allocated pursuant to section 782(e), the Administrator shall reduce each entity's distribution on a pro rata basis so that the total distribution under this section equals the number of allowances allocated under section 782(e).

"(d) Iron and Steel Sector.—For purposes of this section, the Administrator shall consider as in different industrial sectors—

"(1) entities using integrated iron and steelmaking technologies (including coke ovens, blast furnaces, and other iron-making technologies); and

"(2) entities using electric arc furnace technologies.

(e) Metal, Soda Ash, or Phosphate Pro-DUCTION CLASSIFIED UNDER MORE THAN ONE NAICS CODE.—For purposes of this section, the Administrator shall not aggregate data for the beneficiation or other processing (including agglomeration) of metal ores, soda ash, or phosphate with subsequent steps in the process of metal, soda ash, or phosphate manufacturing. The Administrator shall consider the beneficiation or other processing (including agglomeration) of metal ores. soda ash, or phosphate to be in separate industrial sectors from the metal, soda ash, or phosphate manufacturing sectors. Industrial sectors that beneficiate or otherwise process (including agglomeration) metal ores, soda ash, or phosphate shall not receive emission allowance rebates under this section related to the activity of extracting metal ores, soda ash, or phosphate.

"(f) COMBINED HEAT AND POWER.—For purposes of this section, and to achieve the purpose set forth in section 761(b)(2), the Administrator may consider entities to be in different industrial sectors or otherwise take into account the differences among entities in the same industrial sector, based upon the extent to which such entities use combined heat and power technologies.

"Subpart 2—Promoting International Reductions in Industrial Emissions "SEC. 765. INTERNATIONAL NEGOTIATIONS.

"(a) FINDING.—Congress finds that the purposes of this subpart, as set forth in section 761(c), can be most effectively addressed and achieved through agreements negotiated between the United States and foreign countries."

"(b) STATEMENT OF POLICY.—It is the policy of the United States to work proactively under the United Nations Framework Convention on Climate Change, and in other appropriate fora, to establish binding agreements, including sectoral agreements, committing all major greenhouse gas-emitting nations to contribute equitably to the reduction of global greenhouse gas emissions.

"(c) NOTIFICATION OF FOREIGN COUNTRIES.—

"(1) IN GENERAL.—As soon as practicable after the date of the enactment of this title, the President shall provide a notification on climate change described in paragraph (2) to each foreign country the products of which are not exempted under section 768(a)(1)(E).

"(2) NOTIFICATION DESCRIBED.—A notification described in this paragraph is a notification that consists of—

``(A) a statement of the policy of the United States described in subsection (b); and

"(B) a declaration—

"(i) requesting the foreign country to take appropriate measures to limit the greenhouse gas emissions of the foreign country; and

"(ii) indicating that, beginning on January 1, 2020, the international reserve requirements of this subpart may apply to a covered good.

"SEC. 766. UNITED STATES NEGOTIATING OBJECTIVES WITH RESPECT TO MULTILATERAL ENVIRONMENTAL NEGOTIATIONS

"(a) IN GENERAL.—The negotiating objectives of the United States with respect to multilateral environmental negotiations described in this subpart are—

"(1) to reach an internationally binding agreement in which all major greenhouse gas-emitting countries contribute equitably to the reduction of global greenhouse gas emissions:

"(2)(A) to include in such international agreement provisions that recognize and address the competitive imbalances that lead to carbon leakage and may be created between parties and non-parties to the agreement in domestic and export markets; and

"(B) not to prevent parties to such agreement from addressing the competitive imbalances that lead to carbon leakage and may be created by the agreement among parties to the agreement in domestic and export markets: and

"(3) to include in such international agreement agreed remedies for any party to the agreement that fails to meet its greenhouse gas reduction obligations in the agreement.

"(b) RULE OF CONSTRUCTION.—Nothing in subsection (a)(2) shall be construed to require the United States to alter the provisions of section 764.

"SEC. 767. PRESIDENTIAL REPORTS AND DETERMINATIONS.

"(a) REPORT.—Not later than January 1, 2017, and every 2 years thereafter, the President shall submit a report to Congress on the

effectiveness of the distribution of emission allowance rebates under subpart 1 in mitigating carbon leakage in eligible industrial sectors. Such report shall also include—

"(1) an assessment, for each eligible industrial sector receiving emission allowance rebates, as to whether, and by how much, the per unit cost of production has increased for that sector as a result of compliance with section 722 (as determined in a manner consistent with section 764(b)), taking into account the provision of the emission allowance rebates to that industrial sector and the benefit received by that industrial sector from the provision of free allowances to electricity providers pursuant to section 782(a);

"(2) recommendations on how to better achieve the purposes of this subpart, including an assessment of the feasibility and usefulness of an international reserve allowance program for the eligible industrial sector under section 768:

"(3) to the extent the President determines that an international reserve allowance program would not be useful for the eligible industrial sector because its exposure to carbon leakage is the result of competition in export markets with goods produced in countries not implementing similar greenhouse gas emission reduction policies, an identification of, and to the extent appropriate a description of how the President will implement, alternative actions or programs consistent with the purposes of this subpart (and, in such case, the President may determine not to apply an international reserve allowance program to the eligible industrial sector under subsection (b)); and

"(4) an assessment of the amount and duration of assistance, including distribution of free allowances, being provided to industrial sectors in other developed countries to mitigate costs of compliance with domestic greenhouse gas reduction programs in such countries.

"(b) Presidential Determination.—

"(1) IN GENERAL.—If, by January 1, 2018, a multilateral agreement consistent with the negotiating objectives set forth in section 766 has not entered into force with respect to the United States, the President shall establish an international reserve allowance program for each eligible industrial sector to the extent provided under section 768 unless—

"(A) the President determines and certifies to the Congress with respect to such eligible industrial sector that such program would not be in the national economic interest or environmental interest of the United States; and

"(B) not later than 90 days after the President transmits the certification described in subparagraph (A), a joint resolution is enacted into law that approves the determination of the President described in subparagraph (A).

"(2) CONTENTS OF JOINT RESOLUTION.—For purposes of this subsection, the term 'joint resolution' means only a joint resolution of the two Houses of Congress, the matter after the resolving clause of which is as follows: 'That the Congress approves the determination of the President under section 768(b)(1)(A) of the Clean Air Act transmitted to the Congress on ____.', the blank space being filled with the appropriate date.

"(3) CONGRESSIONAL PROCEDURES.—Subsections (c), (d), (e), and (f) of section 152 of the Trade Act of 1974 (19 U.S.C. 2192 (c), (d), (e), and (f)) shall apply to a joint resolution under this subsection to the same extent as such subsections apply to a joint resolution under section 152 of such Act.

"(4) RULE OF CONSTRUCTION.—For purposes of this section and section 768, if the President transmits a multilateral agreement to Congress (regardless of whether it is transmitted as a treaty for ratification by the Senate or another international agreement for implementation by law enacted by the Congress) indicating that the agreement is consistent with the negotiating objectives set forth in section 766, such agreement will be considered to be consistent with such negotiating objectives as of the date on which the Senate ratifies the treaty, or legislation is enacted implementing such other agreement, unless the Senate (in the case of ratification) or the implementing legislation expressly provides that the multilateral agreement shall not be treated as consistent with such negotiating objectives for purposes of this section and section 768.

"(c) DETERMINATIONS WITH RESPECT TO ELIGIBLE INDUSTRIAL SECTORS.—If the President establishes an international reserve allowance program pursuant to subsection (b), then not later than June 30, 2018, and every four years thereafter, the President, in consultation with the Administrator and other appropriate agencies, shall determine, for each eligible industrial sector, whether or not more than 85 percent of United States imports of covered goods with respect to that sector are produced or manufactured in countries that have met at least one of the following criteria:

"(1) The country is a party to an international agreement to which the United States is a party that includes a nationally enforceable and economy-wide greenhouse gas emissions reduction commitment for that country that is at least as stringent as that of the United States.

"(2) The country is a party to a multilateral or bilateral emission reduction agreement for that sector to the which the United States is a party.

"(3) The country has an annual energy or greenhouse gas intensity, as described in section 763(b)(2)(A)(ii), for the sector that is equal to or less than the energy or greenhouse gas intensity for such industrial sector in the United States in the most recent calendar year for which data are available.

"(d) Effect of Presidential Determina-

"(1) REQUIRED ACTIONS.—If the President makes a determination under subsection (c) with respect to an eligible industrial sector that 85 percent or less of United States imports of covered goods with respect to the sector are produced or manufactured in countries that have met one or more of the criteria in subsection (c), then the President shall, not later than June 30, 2018, and every four years thereafter—

"(A) assess the extent to which the emission allowance rebates provided pursuant to subpart 1 and the benefit received by that industrial sector from the provision of free allowances to electricity providers pursuant to section 782(a) have mitigated or addressed, or could mitigate or address, carbon leakage in that sector:

"(B) assess the extent to which an international reserve allowance program has mitigated or addressed, or could mitigate or address, carbon leakage in that sector; and

"(C) with respect to that sector—

"(i) modify the percentage by which direct and indirect carbon factors will be multiplied under section 764(a)(1)(B); and

"(ii) apply or continue to apply an international reserve allowance program under section 768 with respect to imports of covered goods with respect to that sector.

"(2) Prohibited actions.—If the President makes a determination under subsection (c) with respect to an eligible industrial sector that more than 85 percent of United States imports of covered goods with respect to the sector are produced or manufactured in countries that have met one or more of the

criteria in subsection (c), then the President may not apply or continue to apply an international reserve allowance program under section 768 with respect to imports of covered goods with respect to that sector.

"(e) REPORT TO CONGRESS.—Not later than June 30, 2018, and every four years thereafter, the President shall transmit to the Congress a report providing notice of any determination made under subsection (c), explaining the reasons for such determination, and identifying the actions taken by the President under subsection (d).

"SEC. 768. INTERNATIONAL RESERVE ALLOW-ANCE PROGRAM.

"(a) ESTABLISHMENT.—

"(1) IN GENERAL.—The Administrator, with the concurrence of Commissioner responsible for U.S. Customs and Border Protection, shall issue regulations—

"(A) establishing an international reserve allowance program for the sale, exchange, purchase, transfer, and banking of international reserve allowances for covered goods with respect to the eligible industrial sector;

"(B) ensuring that the price for purchasing the international reserve allowances from the United States on a particular day is equivalent to the auction clearing price for emission allowances under section 722 for the most recent emission allowance auction;

"(C) establishing a general methodology for calculating the quantity of international reserve allowances that a United States importer of any covered good must submit:

"(D) requiring the submission of appropriate amounts of such allowances for covered goods with respect to the eligible industrial sector that enter the customs territory of the United States:

``(E) exempting from the requirements of subparagraph (D) such products that are the origin of—

"(i) any country determined to meet any of the standards provided in section 767(c);

"(ii) any foreign country that the United Nations has identified as among the least developed of developing countries; or

"(iii) any foreign country that the President has determined to be responsible for less than 0.5 percent of total global greenhouse gas emissions and less than 5 percent of United States imports of covered goods with respect to the eligible industrial sector;

"(F) specifying the procedures that U.S. Customs and Border Protection will apply for the declaration and entry of covered goods with respect to the eligible industrial sector into the customs territory of the United States; and

"(G) establishing procedures that prevent circumvention of the international reserve allowance requirement for covered goods with respect to the eligible industrial sector that are manufactured or processed in more than one foreign country.

"(2) PURPOSE OF PROGRAM.—The Administrator shall establish the program under paragraph (1) consistent with international agreements to which the United States is a party, in a manner that minimizes the likelihood of carbon leakage as a result of differences between—

"(A) the direct and indirect costs of complying with section 722; and

"(B) the direct and indirect costs, if any, of complying in other countries with green-house gas regulatory programs, requirements, export tariffs, or other measures adopted or imposed to reduce greenhouse gas emissions.

"(b) EMISSION ALLOWANCE REBATES.—In establishing a general methodology for purposes of subsection (a)(1)(C), the Administrator shall include an adjustment to the quantity of international reserve allowances based on the value of emission allowance re-

bates distributed under subpart 1 and the benefit received by the eligible industrial sector concerned from the provision of free allowances to electricity providers pursuant to section 782(a) and may, if appropriate, determine that the quantity of international reserve allowances should be reduced as low as to zero.

"(c) EFFECTIVE DATE.—The international reserve allowance program may not apply to imports of covered goods entering the customs territory of the United States before January 1, 2020.

"(d) COVERED ENTITIES.—International reserve allowances may not be used by covered entities to comply with section 722.

"SEC. 769. IRON AND STEEL SECTOR.

"For purposes of this subpart, the Administrator shall consider to be in the same eligible industrial sector—

"(1) entities using integrated iron and steelmaking technologies (including coke ovens, blast furnaces, and other iron-making technologies); and

"(2) entities using electric arc furnace technologies.".

Subtitle B—Green Jobs and Worker Transition

PART 1—GREEN JOBS

SEC. 421. CLEAN ENERGY CURRICULUM DEVELOPMENT GRANTS.

(a) AUTHORIZATION.—The Secretary of Education is authorized to award grants, on a competitive basis, to eligible partnerships to develop programs of study (containing the information described in section 122(c)(1)(A) of the Carl D. Perkins Career and Technical Education Act of 2006 (20 U.S.C. 2342)), that are focused on emerging careers and jobs in the fields of clean energy, renewable energy, energy efficiency, climate change mitigation, and climate change adaptation. The Secretary of Education shall consult with the Secretary of Labor and the Secretary of Energy prior to the issuance of a solicitation for grant applications.

(b) ELIGIBLE PARTNERSHIPS.—For purposes of this section, an eligible partnership shall include—

(1) at least 1 local educational agency eligible for funding under section 131 of the Carl D. Perkins Career and Technical Education Act of 2006 (20 U.S.C. 2351) or an area career and technical education school or education service agency described in such section:

(2) at least 1 postsecondary institution eligible for funding under section 132 of such Act (20 U.S.C. 2352); and

(3) representatives of the community including business, labor organizations, and industry that have experience in fields as described in subsection (a).

(c) APPLICATION.—An eligible partnership seeking a grant under this section shall submit an application to the Secretary at such time and in such manner as the Secretary may require. Applications shall include—

(1) a description of the eligible partners and partnership, the roles and responsibilities of each partner, and a demonstration of each partner's capacity to support the program:

(2) a description of the career area or areas within the fields as described in subsection (a) to be developed, the reason for the choice, and evidence of the labor market need to prepare students in that area;

(3) a description of the new or existing program of study and both secondary and post-secondary components;

(4) a description of the students to be served by the new program of study;

(5) a description of how the program of study funded by the grant will be replicable and disseminated to schools outside of the partnership, including urban and rural areas;

- (6) a description of applied learning that will be incorporated into the program of study and how it will incorporate or reinforce academic learning;
- (7) a description of how the program of study will be delivered;
- (8) a description of how the program will provide accessibility to students, especially economically disadvantaged, low performing, and urban and rural students;
- (9) a description of how the program will address placement of students in nontraditional fields as described in section 3(20) of the Carl D. Perkins Career and Technical Education Act of 2006 (20 U.S.C. 2302(20)); and
- (10) a description of how the applicant proposes to consult or has consulted with a labor organization, labor management partnership, apprenticeship program, or joint apprenticeship and training program that provides education and training in the field of study for which the applicant proposes to develop a curriculum.
- (d) PRIORITY.—The Secretary shall give priority to applications that—
- (1) use online learning or other innovative means to deliver the program of study to students, educators, and instructors outside of the partnership; and
- (2) focus on low performing students and special populations as defined in section 3(29) of the Carl D. Perkins Career and Technical Education Act of 2006 (20 U.S.C. 2302(29)).
- (e) PEER REVIEW.—The Secretary shall convene a peer review process to review applications for grants under this section and to make recommendations regarding the selection of grantees. Members of the peer review committee shall include—
- (1) educators who have experience implementing curricula with comparable purposes; and
- (2) business and industry experts in fields as described in subsection (a).
- (f) USES OF FUNDS.—Grants awarded under this section shall be used for the development, implementation, and dissemination of programs of study (as described in section 122(c)(1)(A) of the Carl D. Perkins Career and Technical Education Act (20 U.S.C. 2342(c)(1)(A))) in career areas related to clean energy, renewable energy, energy efficiency, climate change mitigation, and climate change adaptation

SEC. 422. INCREASED FUNDING FOR ENERGY WORKER TRAINING PROGRAM.

- (a) Authorization.—Section 171(e)(8) of the Workforce Investment Act of 1998 (29 U.S.C. 2916(e)(8)) is amended by striking "\$125,000,000" and inserting "\$150,000,000".
- (b) ESTABLISHMENT OF FUND.—There is hereby established in the Treasury a separate account that shall be known as the Energy Efficiency and Renewable Energy Worker Training Fund.
- (c) AVAILABILITY OF AMOUNTS.—Subject to subtitle F of title IV, all amounts deposited into the Energy Efficiency and Renewable Energy Worker Training Fund shall be available to the Secretary to carry out section 171(e)(8) of the Workforce Investment Act of 1998 (29 U.S.C. 2916(e)(8)) subject to further appropriation.

SEC. 423. DEVELOPMENT OF INFORMATION AND RESOURCES CLEARINGHOUSE FOR VOCATIONAL EDUCATION AND JOB TRAINING IN RENEWABLE ENERGY SECTORS.

(a) DEVELOPMENT OF CLEARINGHOUSE.—Not later than 18 months after the date of enactment of this Act, the Secretary of Labor, in collaboration with the Secretary of Energy and the Secretary of Education, shall develop an internet based information and resources clearinghouse to aid career and technical education and job training programs for the renewable energy sectors. In establishing the clearinghouse, the Secretary shall—

- (1) collect and provide information that addresses the consequences of rapid changes in technology and regional disparities for renewable energy training programs and provides best practices for training and education in light of such changes and disparities:
- (2) place an emphasis on facilitating collaboration between the renewable energy industry and job training programs and on identifying industry and technological trends and best practices, to better help job training programs maintain quality and relevance; and
- (3) place an emphasis on assisting programs that cater to high-demand middle-skill, trades, manufacturing, contracting, and consulting careers.
- (b) Solicitation and Consultation.—In developing the clearinghouse pursuant to subsection (a), the Secretary shall solicit information and expertise from businesses and organizations in the renewable energy sector and from institutions of higher education, career and technical schools, and community colleges that provide training in the renewable energy sectors. The Secretary shall solicit a comprehensive peer review of the clearinghouse by such entities not less than once every 2 years. Nothing in this subsection should be interpreted to require the divulgence of proprietary or competitive information.
 - (c) CONTENTS OF CLEARINGHOUSE.—
- (1) SEPARATE SECTION FOR EACH RENEWABLE ENERGY SECTOR.—The clearinghouse shall contain separate sections developed for each of the following renewable energy sectors:
 - (A) Solar energy systems.
 - (B) Wind energy systems.
- (C) Energy transmission systems.
- (D) Geothermal systems of energy and heating.
- (E) Energy efficiency technical training. (2) Additional requirements.—In addition to the information required in subsection (a), each section of the clearinghouse shall include information on basic environmental science and processes needed to understand renewable energy systems. Federal government and industry resources, and points of contact to aid institutions in the development of placement programs for apprenticeships and post graduation opportunities, and information and tips about a green workplace, energy efficiency, and relevant environmental topics and information on available industry recognized certifications in each area.
- (d) DISSEMINATION.—The clearinghouse shall be made available via the Internet to the general public. Notice of the completed clearinghouse and any major revisions thereto shall also be provided—
- (1) to each Member of Congress; and
- (2) on the websites of the Departments of Education, Energy, and Labor.
- (e) REVISION.—The Secretary of Labor shall revise and update the clearinghouse on a regular basis to ensure its relevance.

SEC. 424. MONITORING PROGRAM EFFECTIVENESS.

The Secretary of Labor shall monitor the potential growth of affected and displaced workers to ensure that the necessary funding continues to support the number of workers affected.

SEC. 424A. GREEN CONSTRUCTION CAREERS DEMONSTRATION PROJECT.

(a) ESTABLISHMENT AND AUTHORITY.—The Secretary of Labor, in consultation with the Secretary of Energy, shall, not later than 180 days after the enactment of this Act, establish a Green Construction Careers demonstration project by rules, regulations, and guidance in accordance with the provisions of this section. The purpose of the dem-

onstration project shall be to promote middle class careers and quality employment practices in the green construction sector among targeted workers and to advance efficiency and performance on construction projects related to this Act. In order to advance these purposes, the Secretary shall identify projects, including residential retrofitting projects, funded directly by or assisted in whole or in part by or through the Federal Government pursuant to this Act or by any other entity established in accordance with this Act, to which all of the following shall apply.

(b) REQUIREMENTS.—The Secretaries may establish such terms and conditions for the demonstration projects as the Secretaries determine are necessary to meet the purposes of subsection (a), including establishing minimum proportions of hours to be worked by targeted workers on such projects. The Secretaries may require the contractors and subcontractors performing construction services on the project to comply with the terms and conditions as a condition of receiving funding or assistance from the Federal Government under this Act.

(c) EVALUATION.—The Secretaries shall evaluate the demonstration projects against the purposes of this section at the end of 3 years from initiation of the demonstration project. If the Secretaries determine that the demonstration projects have been successful, the Secretaries may identify further projects to which of the provisions of this section shall apply

(d) GAO REPORT.—The Comptroller General shall prepare and submit a report to the Committee on Health, Education, Labor and Pensions and the Committee on Energy and Natural Resources of the Senate and the Committee on Education and Labor and the Committee on Energy and Commerce of the House of Representatives not later than 5 years after the date of enactment of this Act, which shall advise the committees of the results of the demonstration projects and make appropriate recommendations.

(e) DEFINITION AND DESIGNATION OF TARGETED WORKERS.—As used in this section, the term "targeted worker" means an individual who resides in the same labor market area (as defined in section 101(18) of the Workforce Investment Act of 1998 (29 U.S.C. 2801(18))) as the project and who—

(1) is a member of a targeted group, within the meaning of section 51 of the Internal Revenue Code of 1986, other than an individual described in subsection (d)(1)(C) of such section:

(2)(A) resides in a census tract in which not less than 20 percent of the households have incomes below the Federal poverty guidelines; or

- (B) is a member of a family that received a total family income that, during the 2-year period prior to employment on the project or admission to the pre-apprenticeship program, did not exceed 200 percent of the Federal poverty guidelines (exclusive of unemployment compensation, child support payments, payments described in section 101(25)(A) of the Workforce Investment Act (29 U.S.C. 2801(25)(A)), and old-age and survivors insurance benefits received under section 202 of the Social Security Act (42 U.S.C. 402); or
- (3) is a displaced homemaker, as such term is defined in section 3(10) of the Carl D. Perkins Career and Technical Education Act of 2006 (20 U.S.C. 2302(10)).
- (f) QUALIFIED PRE-APPRENTICESHIP PROGRAM.—A qualified pre-apprenticeship program is a pre-apprenticeship program that has demonstrated an ability to recruit, train, and prepare for admission to apprenticeship programs individuals who are targeted workers.

- (g) QUALIFIED APPRENTICESHIP AND OTHER TRAINING PROGRAMS.—
- (1) Participation by each contractor required.—Each contractor and subcontractor that seeks to provide construction services on projects identified by the Secretaries pursuant to subsection (a) shall submit adequate assurances with its bid or proposal that it participates in a qualified apprenticeship or other training program, with a written arrangement with a qualified pre-apprenticeship program, for each craft or trade classification of worker that it intends to employ to perform work on the project.
- (2) DEFINITION OF QUALIFIED APPRENTICE-SHIP OR OTHER TRAINING PROGRAM.—
- (A) IN GENERAL.—For purposes of this section, the term "qualified apprenticeship or other training program" means an apprenticeship or other training program that qualifies as an employee welfare benefit plan, as defined in section 3(1) of the Employee Retirement Income Security Act of 1974 (29 U.S.C. 1002(1)).
- (B) CERTIFICATION OF OTHER PROGRAMS IN CERTAIN LOCALITIES.—In the event that the Secretary of Labor certifies that a qualified apprenticeship or other training program (as defined in subparagraph (A)) for a craft or trade classification of workers that a prospective contractor or subcontractor intends to employ, is not operated in the locality where the project will be performed, an apprenticeship or other training program that is not an employee welfare benefit plan (as defined in such section) may be certified by the Secretary as a qualified apprenticeship or other training program provided it is registered with the Office of Apprenticeship of the Department of Labor, or a State apprenticeship agency recognized by the Office of Apprenticeship for Federal purposes.
- (h) FACILITATING COMPLIANCE.—The Secretary may require Federal contracting agencies, recipients of Federal assistance, and any other entity established in accordance with this Act to require contractors to enter into an agreement in a manner comparable with the standards set forth in sections 3 and 4 of Executive Order 13502 in order to achieve the purposes of this section, including any requirements established by subsection (b).
- (i) LIMITATION.—The requirements of this section shall not apply to any project funded under this Act in American Samoa, Guam, the Commonwealth of the Northern Mariana Islands, the Commonwealth of Puerto Rico, or the United States Virgin Islands, unless participation is requested by the governor of such territories within 1 year of the promulgation of rules under this Act.

PART 2—CLIMATE CHANGE WORKER ADJUSTMENT ASSISTANCE

SEC. 425. PETITIONS, ELIGIBILITY REQUIRE-MENTS, AND DETERMINATIONS.

- (a) Petitions.—
- (1) FILING.—A petition for certification of eligibility to apply for adjustment assistance for a group of workers under this part may be filed by any of the following:
 - (A) The group of workers.
- (B) The certified or recognized union or other duly authorized representative of such workers.
- (C) Employers of such workers, one-stop operators or one-stop partners (as defined in section 101 of the Workforce Investment Act of 1998 (29 U.S.C. 2801)), including State employment security agencies, or the State dislocated worker unit established under title I of such Act, on behalf of such workers.
- The petition shall be filed simultaneously with the Secretary of Labor and with the Governor of the State in which such workers' employment site is located.

- (2) ACTION BY GOVERNORS.—Upon receipt of a petition filed under paragraph (1), the Governor shall—
- (A) ensure that rapid response activities and appropriate core and intensive services (as described in section 134 of the Workforce Investment Act of 1998 (29 U.S.C. 2864)) authorized under other Federal laws are made available to the workers covered by the petition to the extent authorized under such laws; and
- (B) assist the Secretary in the review of the petition by verifying such information and providing such other assistance as the Secretary may request.
- (3) ACTION BY THE SECRETARY.—Upon receipt of the petition, the Secretary shall promptly publish notice in the Federal Register and on the website of the Department of Labor that the Secretary has received the petition and initiated an investigation.
- (4) HEARINGS.—If the petitioner, or any other person found by the Secretary to have a substantial interest in the proceedings, submits not later than 10 days after the date of the Secretary's publication under paragraph (3) a request for a hearing, the Secretary shall provide for a public hearing and afford such interested persons an opportunity to be present, to produce evidence, and to be heard.
 - (b) ELIGIBILITY.—
- (1) IN GENERAL.—A group of workers shall be certified by the Secretary as eligible to apply for adjustment assistance under this part pursuant to a petition filed under subsection (a) if—
- (A) the group of workers is employed in—(i) energy producing and transforming industries:
- (ii) industries dependent upon energy industries:
- (iii) energy-intensive manufacturing industries:
- (iv) consumer goods manufacturing; or
- (v) other industries whose employment the Secretary determines has been adversely affected by any requirement of title VII of the Clean Air Act:
- (B) the Secretary determines that a significant number or proportion of the workers in such workers' employment site have become totally or partially separated, or are threatened to become totally or partially separated from employment; and
- (C) the sales, production, or delivery of goods or services have decreased as a result of any requirement of title VII of the Clean Air Act, including—
- (i) the shift from reliance upon fossil fuels to other sources of energy, including renewable energy, that results in the closing of a facility or layoff of employees at a facility that mines, produces, processes, or utilizes fossil fuels to generate electricity:
- (ii) a substantial increase in the cost of energy required for a manufacturing facility to produce items whose prices are competitive in the marketplace, to the extent the cost is not offset by allowance allocation to the facility pursuant to title VII of the Clean Air Act; or
- (iii) other documented occurrences that the Secretary determines are indicators of an adverse impact on an industry described in subparagraph (A) as a result of any requirement of title VII of the Clean Air Act.
- (2) WORKERS IN PUBLIC AGENCIES.—A group of workers in a public agency shall be certified by the Secretary as eligible to apply for climate change adjustment assistance pursuant to a petition filed if the Secretary determines that a significant number or proportion of the workers in the public agency have become totally or partially separated from employment, or are threatened to become totally or partially separated as a re-

- sult of any requirement of title VII of the Clean Air Act.
- (3) ADVERSELY AFFECTED SERVICE WORKERS.—A group of workers shall be certified as eligible to apply for climate change adjustment assistance pursuant to a petition filed if the Secretary determines that—
- (A) a significant number or proportion of the service workers at an employment site where a group of workers has been certified by the Secretary as eligible to apply for adjustment assistance under this part pursuant to paragraph (1) have become totally or partially separated from employment, or are threatened to become totally or partially separated; and
- (B) a loss of business in the firm providing service workers to an employment site is directly attributable to one or more of the documented occurrences listed in paragraph (1)(C).
- (c) Authority to Investigate and Collect Information.—
- (1) IN GENERAL.—The Secretary shall, in determining whether to certify a group of workers under subsection (d), obtain information the Secretary determines to be necessary to make the certification, through questionnaires and in such other manner as the Secretary determines appropriate from—
 - (A) the workers' employer;
- (B) officials of certified or recognized unions or other duly authorized representatives of the group of workers; or
- (C) one-stop operators or one-stop partners (as defined in section 101 of the Workforce Investment Act of 1998 (29 U.S.C. 2801)); or
- (2) VERIFICATION OF INFORMATION.—The Secretary shall require an employer, union, or one-stop operator or partner to certify all information obtained under paragraph (1) from the employer, union, or one-stop operator or partner (as the case may be) on which the Secretary relies in making a determination under subsection (d), unless the Secretary has a reasonable basis for determining that such information is accurate and complete without being certified.
- (3) PROTECTION OF CONFIDENTIAL INFORMATION.—The Secretary may not release information obtained under paragraph (1) that the Secretary considers to be confidential business information unless the employer submitting the confidential business information had notice, at the time of submission, that the information would be released by the Secretary, or the employer subsequently consents to the release of the information. Nothing in this paragraph shall be construed to prohibit the Secretary from providing such confidential business information to a court in camera or to another party under a protective order issued by a court.
- (d) DETERMINATION BY THE SECRETARY OF LABOR.—
- (1) IN GENERAL.—As soon as possible after the date on which a petition is filed under subsection (a), but in any event not later than 40 days after that date, the Secretary, in consultation with the Secretary of Energy and the Administrator, as necessary, shall determine whether the petitioning group meets the requirements of subsection (b) and shall issue a certification of eligibility to apply for assistance under this part covering workers in any group which meets such requirements. Each certification shall specify the date on which the total or partial separation began or threatened to begin. Upon reaching a determination on a petition, the Secretary shall promptly publish a summary of the determination in the Federal Register and on the website of the Department of Labor, together with the Secretary's reasons for making such determination.
- (2) ONE YEAR LIMITATION.—A certification under this section shall not apply to any

worker whose last total or partial separation from the employment site before the worker's application under section 426(a) occurred more than 1 year before the date of the petition on which such certification was granted.

- (3) REVOCATION OF CERTIFICATION.—Whenever the Secretary determines, with respect to any certification of eligibility of the workers of an employment site, that total or partial separations from such site are no longer a result of the factors specified in subsection (b)(1), the Secretary shall terminate such certification and promptly have notice of such termination published in the Federal Register and on the website of the Department of Labor, together with the Secretary's reasons for making such determination. Such termination shall apply only with respect to total or partial separations occurring after the termination date specified by the Secretary.
- (e) INDUSTRY NOTIFICATION OF ASSISTANCE.—Upon receiving a notification of a determination under subsection (d) with respect to a domestic industry the Secretary of Labor shall notify the representatives of the domestic industry affected by the determination, employers publicly identified by name during the course of the proceeding relating to the determination, and any certified or recognized union or, to the extent practicable, other duly authorized representative of workers employed by such representatives of the domestic industry, of—
- (1) the adjustment allowances, training, and other benefits available under this part;
- (2) the manner in which to file a petition and apply for such benefits; and
- (3) the availability of assistance in filing such petitions:
- (4) notify the Governor of each State in which one or more employers in such industry are located of the Secretary's determination and the identity of the employers; and
- (5) upon request, provide any assistance that is necessary to file a petition under subsection (a).
- (f) BENEFIT INFORMATION TO WORKERS, PROVIDERS OF TRAINING.—
- (1) IN GENERAL.—The Secretary shall provide full information to workers about the adjustment allowances, training, and other benefits available under this part and about the petition and application procedures, and the appropriate filing dates, for such allowances, training and services. The Secretary shall provide whatever assistance is necessary to enable groups of workers to prepare petitions or applications for program benefits. The Secretary shall make every effort to insure that cooperating State agencies fully comply with the agreements entered into under section 426(a) and shall periodically review such compliance. The Secretary shall inform the State Board for Vocational Education or equivalent agency, the one-stop operators or one-stop partners (as defined in section 101 of the Workforce Investment Act of 1998 (29 U.S.C. 2801), and other public or private agencies, institutions, and employers, as appropriate, of each certification issued under subsection (d) and of projections, if available, of the needs for training under as a result of such certification.
- (2) Notice by Mail.—The Secretary shall provide written notice through the mail of the benefits available under this part to each worker whom the Secretary has reason to believe is covered by a certification made under subsection (d)—
- (A) at the time such certification is made, if the worker was partially or totally separated from the adversely affected employment before such certification, or—
- (B) at the time of the total or partial separation of the worker from the adversely af-

fected employment, if subparagraph (A) does not apply.

(3) NEWSPAPERS; WEBSITE.—The Secretary shall publish notice of the benefits available under this part to workers covered by each certification made under subsection (d) in newspapers of general circulation in the areas in which such workers reside and shall make such information available on the website of the Department of Labor.

SEC. 426. PROGRAM BENEFITS.

- (a) CLIMATE CHANGE ADJUSTMENT ALLOWANCE.—
- (1) ELIGIBILITY.—Payment of a climate change adjustment allowance shall be made to an adversely affected worker covered by a certification under section 425(b) who files an application for such allowance for any week of unemployment which begins on or after the date of such certification, if the following conditions are met:
- (A) Such worker's total or partial separation before the worker's application under this part occurred—
- (i) on or after the date, as specified in the certification under which the worker is covered, on which total or partial separation began or threatened to begin in the adversely affected employment;
- (ii) before the expiration of the 2-year period beginning on the date on which the determination under section 425(d) was made; and
- (iii) before the termination date, if any, determined pursuant to section 425(d)(3).
- (B) Such worker had, in the 52-week period ending with the week in which such total or partial separation occurred, at least 26 weeks of full-time employment or 1,040 hours of part time employment in adversely affected employment, or, if data with respect to weeks of employment are not available, equivalent amounts of employment computed under regulations prescribed by the Secretary. For the purposes of this paragraph, any week in which such worker—
- (i) is on employer-authorized leave for purposes of vacation, sickness, injury, maternity, or inactive duty or active duty military service for training:
- (ii) does not work because of a disability that is compensable under a workmen's compensation law or plan of a State or the United States;
- (iii) had his employment interrupted in order to serve as a full-time representative of a labor organization in such firm; or
- (iv) is on call-up for purposes of active duty in a reserve status in the Armed Forces of the United States, provided such active duty is "Federal service" as defined in section 8521(a)(1) of title 5, United States Code, shall be treated as a week of employment.
- (C) Such worker is enrolled in a training program approved by the Secretary under subsection (b)(2).
- (2) INELIGIBILITY FOR CERTAIN OTHER BENE-FITS.—An adversely affected worker receiving a payment under this section shall be ineligible to receive any other form of unemployment insurance for the period in which such worker is receiving a climate change adjustment allowance under this section.
 - (3) REVOCATION.—If—
 - (A) the Secretary determines that-
 - (i) the adversely affected worker-
- (I) has failed to begin participation in the training program the enrollment in which meets the requirement of paragraph (1)(C); or
- (II) has ceased to participate in such training program before completing such training program; and
- (ii) there is no justifiable cause for such failure or cessation; or
- (B) the certification made with respect to such worker under section 425(d) is revoked under paragraph (3) of such section,

- no adjustment allowance may be paid to the adversely affected worker under this part for the week in which such failure, cessation, or revocation occurred, or any succeeding week, until the adversely affected worker begins or resumes participation in a training program approved by the Secretary under section (b)(2).
- (4) WAIVERS OF TRAINING REQUIREMENTS.— The Secretary may issue a written statement to an adversely affected worker waiving the requirement to be enrolled in training described in subsection (b)(2) if the Secretary determines that it is not feasible or appropriate for the worker, because of 1 or more of the following reasons:
- (A) RECALL.—The worker has been notified that the worker will be recalled by the employer from which the separation occurred.
 - (B) MARKETABLE SKILLS.—
- (i) IN GENERAL.—The worker possesses marketable skills for suitable employment (as determined pursuant to an assessment of the worker, which may include the profiling system under section 303(j) of the Social Security Act (42 U.S.C. 503(j)), carried out in accordance with guidelines issued by the Secretary) and there is a reasonable expectation of employment at equivalent wages in the foreseeable future
- (ii) MARKETABLE SKILLS DEFINED.—For purposes of clause (i), the term "marketable skills" may include the possession of a post-graduate degree from an institution of higher education (as defined in section 102 of the Higher Education Act of 1965 (20 U.S.C. 1002)) or an equivalent institution, or the possession of an equivalent postgraduate certification in a specialized field.
- (C) RETIREMENT.—The worker is within 2 years of meeting all requirements for entitlement to either—
- (i) old-age insurance benefits under title II of the Social Security Act (42 U.S.C. 401 et seg.) (except for application therefor); or
- (ii) a private pension sponsored by an employer or labor organization.
- (D) HEALTH.—The worker is unable to participate in training due to the health of the worker, except that a waiver under this subparagraph shall not be construed to exempt a worker from requirements relating to the availability for work, active search for work, or refusal to accept work under Federal or State unemployment compensation laws.
- (E) ENROLLMENT UNAVAILABLE.—The first available enrollment date for the training of the worker is within 60 days after the date of the determination made under this paragraph, or, if later, there are extenuating circumstances for the delay in enrollment, as determined pursuant to guidelines issued by the Secretary.
- (F) TRAINING NOT AVAILABLE.—Training described in subsection (b)(2) is not reasonably available to the worker from either governmental agencies or private sources (which may include area career and technical education schools, as defined in section 3 of the Carl D. Perkins Career and Technical Education Act of 2006 (20 U.S.C. 2302), and employers), no training that is suitable for the worker is available at a reasonable cost, or no training funds are available.
- (5) WEEKLY AMOUNTS.—The climate change adjustment allowance payable to an adversely affected worker for a week of unemployment shall be an amount equal to 70 percent of the average weekly wage of such worker, but in no case shall such amount exceed the average weekly wage for all workers in the State where the adversely affected worker resides.
- (6) MAXIMUM DURATION OF BENEFITS.—An eligible worker may receive a climate change adjustment allowance under this subsection for a period of not longer than 156 weeks.

- (b) EMPLOYMENT SERVICES AND TRAINING.—
 (1) INFORMATION AND EMPLOYMENT SERV-
- (1) INFORMATION AND EMPLOYMENT SERV-ICES.—The Secretary shall make available, directly or through agreements with the States under section 427(a) to adversely affected workers covered by a certification under section 425(a) the following information and employment services:
- (A) Comprehensive and specialized assessment of skill levels and service needs, including through—
- (i) diagnostic testing and use of other assessment tools; and
- (ii) in-depth interviewing and evaluation to identify employment barriers and appropriate employment goals.
- (B) Development of an individual employment plan to identify employment goals and objectives, and appropriate training to achieve those goals and objectives.
- (C) Information on training available in local and regional areas, information on individual counseling to determine which training is suitable training, and information on how to apply for such training.
- (D) Information on training programs and other services provided by a State pursuant to title I of the Workforce Investment Act of 1998 and available in local and regional areas, information on individual counseling to determine which training is suitable training, and information on how to apply for such training.
- (E) Information on how to apply for financial aid, including referring workers to educational opportunity centers described in section 402F of the Higher Education Act of 1965 (20 U.S.C. 1070a-16), where applicable, and notifying workers that the workers may request financial aid administrators at institutions of higher education (as defined in section 102 of such Act (20 U.S.C. 1002)) to use the administrators' discretion under section 479A of such Act (20 U.S.C. 1087tt) to use current year income data, rather than preceding year income data, for determining the amount of need of the workers for Federal financial assistance under title IV of such Act (20 U.S.C. 1070 et seq.).
- (F) Short-term prevocational services, including development of learning skills, communications skills, interviewing skills, punctuality, personal maintenance skills, and professional conduct to prepare individuals for employment or training.
- (G) Individual career counseling, including job search and placement counseling, during the period in which the individual is receiving a climate change adjustment allowance or training under this part, and after receiving such training for purposes of job placement.
- (H) Provision of employment statistics information, including the provision of accurate information relating to local, regional, and national labor market areas including—
- (i) job vacancy listings in such labor market areas:
- (ii) information on jobs skills necessary to obtain jobs identified in job vacancy listings described in subparagraph (A);
- (iii) information relating to local occupations that are in demand and earnings potential of such occupations; and
- (iv) skills requirements for local occupations described in subparagraph (C).
- (I) Information relating to the availability of supportive services, including services relating to child care, transportation, dependent care, housing assistance, and need-related payments that are necessary to enable an individual to participate in training.
 - (2) Training.—
- (A) APPROVAL OF AND PAYMENT FOR TRAINING.—If the Secretary determines, with respect to an adversely affected worker that—
- (i) there is no suitable employment (which may include technical and professional em-

- ployment) available for an adversely affected worker:
- (ii) the worker would benefit from appropriate training;
- (iii) there is a reasonable expectation of employment following completion of such training;
- (iv) training approved by the Secretary is reasonably available to the worker from either governmental agencies or private sources (including area career and technical education schools, as defined in section 3 of the Carl D. Perkins Career and Technical Education Act of 2006, and employers);
- (v) the worker is qualified to undertake and complete such training; and
- (vi) such training is suitable for the worker and available at a reasonable cost,
- the Secretary shall approve such training for the worker. Upon such approval, the worker shall be entitled to have payment of the costs of such training (subject to the limitations imposed by this section) paid on the worker's behalf by the Secretary directly or through a voucher system.
- (B) DISTRIBUTION.—The Secretary shall establish procedures for the distribution of the funds to States to carry out the training programs approved under this paragraph, and shall make an initial distribution of the funds made available as soon as practicable after the beginning of each fiscal year.
- (C) ADDITIONAL RULES REGARDING APPROVAL OF AND PAYMENT FOR TRAINING.—
- (i) For purposes of applying subparagraph (A)(iii), a reasonable expectation of employment does not require that employment opportunities for a worker be available, or offered, immediately upon the completion of training approved under such subparagraph.
- (ii) If the costs of training an adversely affected worker are paid by the Secretary under subparagraph (A), no other payment for such costs may be made under any other provision of Federal law. No payment may be made under subparagraph (A) of the costs of training an adversely affected worker or an adversely affected incumbent worker if such costs—
- (I) have already been paid under any other provision of Federal law: or
- (II) are reimbursable under any other provision of Federal law and a portion of such costs have already been paid under such other provision of Federal law.
- The provisions of this clause shall not apply to, or take into account, any funds provided under any other provision of Federal law which are used for any purpose other than the direct payment of the costs incurred in training a particular adversely affected worker, even if such use has the effect of indirectly paying or reducing any portion of the costs involved in training the adversely affected worker
- (D) TRAINING PROGRAMS.—The training programs that may be approved under subparagraph (A) include—
- (i) employer-based training, including—
- (I) on-the-job training if approved by the Secretary under subsection (c); and
- (II) joint labor-management apprenticeship programs;
- (ii) any training program provided by a State pursuant to title I of the Workforce Investment Act of 1998;
- (iii) any training program approved by a private industry council established under section 102 of such Act;
- (iv) any programs in career and technical education described in section 3(5) of the Carl D. Perkins Career and Technical Education Act of 2006:
- (v) any program of remedial education;
- (vi) any program of prerequisite education or coursework required to enroll in training that may be approved under this paragraph;

- (vii) any training program for which all, or any portion, of the costs of training the worker are paid—
- (I) under any Federal or State program other than this part; or
 - (II) from any source other than this part;
- (viii) any training program or coursework at an accredited institution of higher education (described in section 102 of the Higher Education Act of 1965 (20 U.S.C. 1002)), including a training program or coursework for the purpose of—
 - (I) obtaining a degree or certification; or
- (II) completing a degree or certification that the worker had previously begun at an accredited institution of higher education; and
- (ix) any other training program approved by the Secretary.
- (3) SUPPLEMENTAL ASSISTANCE.—The Secretary may, as appropriate, authorize supplemental assistance that is necessary to defray reasonable transportation and subsistence expenses for separate maintenance in a case in which training for a worker is provided in a facility that is not within commuting distance of the regular place of residence of the worker.
 - (c) On-the-Job Training Requirements.-
- (1) IN GENERAL.—The Secretary may approve on-the-job training for any adversely affected worker if—
- (A) the Secretary determines that on-the-
- (i) can reasonably be expected to lead to suitable employment with the employer offering the on-the-job training:
- (ii) is compatible with the skills of the worker:
- (iii) includes a curriculum through which the worker will gain the knowledge or skills to become proficient in the job for which the worker is being trained; and
- (iv) can be measured by benchmarks that indicate that the worker is gaining such knowledge or skills; and
- (B) the State determines that the on-thejob training program meets the requirements of clauses (iii) and (iv) of subparagraph (A).
- (2) MONTHLY PAYMENTS.—The Secretary shall pay the costs of on-the-job training approved under paragraph (1) in monthly installments.
- (3) CONTRACTS FOR ON-THE-JOB TRAINING.—
- (A) IN GENERAL.—The Secretary shall ensure, in entering into a contract with an employer to provide on-the-job training to a worker under this subsection, that the skill requirements of the job for which the worker is being trained, the academic and occupational skill level of the worker, and the work experience of the worker are taken into consideration.
- (B) TERM OF CONTRACT.—Training under any such contract shall be limited to the period of time required for the worker receiving on-the-job training to become proficient in the job for which the worker is being trained, but may not exceed 156 weeks in any case.
- (4) EXCLUSION OF CERTAIN EMPLOYERS.—The Secretary shall not enter into a contract for on-the-job training with an employer that exhibits a pattern of failing to provide workers receiving on-the-job training from the employer with—
- (A) continued, long-term employment as regular employees; and
- (B) wages, benefits, and working conditions that are equivalent to the wages, benefits, and working conditions provided to regular employees who have worked a similar period of time and are doing the same type of work as workers receiving on-the-job training from the employer.
- (d) ADMINISTRATIVE AND EMPLOYMENT SERVICES FUNDING.—

- (1) ADMINISTRATIVE FUNDING.—In addition to any funds made available to a State to carry out this section for a fiscal year, the State shall receive for the fiscal year a payment in an amount that is equal to 15 percent of the amount of such funds and shall—
- (A) use not more than ¾ of such payment for the administration of the climate change adjustment assistance for workers program under this part, including for—
- (i) processing waivers of training requirements under subsection (a)(4);
- (ii) collecting, validating, and reporting data required under this part; and
- (iii) administering the Climate Change Adjustment Assistance Allowance payments; and
- (B) use not less than \(^{1}\)3 of such payment for information and employment services under subsection (b)(1).
 - (2) EMPLOYMENT SERVICES FUNDING.—
- (A) IN GENERAL.—In addition to any funds made available to a State to carry out subsection (b)(2) and the payment under paragraph (1) for a fiscal year, the Secretary shall provide to the State for the fiscal year a reasonable payment for the purpose of providing employment and services under subsection (b)(1).
- (B) VOLUNTARY RETURN OF FUNDS.—A State that receives a payment under subparagraph (A) may decline or otherwise return such payment to the Secretary.
- (e) JOB SEARCH ALLOWANCES.—The Secretary of Labor may provide adversely affected workers a one-time job search allowance in accordance with regulations prescribed by the Secretary. Any job search allowance provided shall be available only under the following circumstances and conditions:
- (1) The worker is no longer eligible for the climate change adjustment allowance under subsection (a) and has completed the training program required by subsection (a)(1)(E).
- (2) The Secretary determines that the worker cannot reasonably be expected to secure suitable employment in the commuting area in which the worker resides.
- (3) An allowance granted shall provide reimbursement to the worker of all necessary job search expenses as prescribed by the Secretary in regulations. Such reimbursement under this subsection may not exceed \$1,500 for any worker.
 - (f) RELOCATION ALLOWANCE AUTHORIZED.—
- (1) IN GENERAL.—Any adversely affected worker covered by a certification issued under section 425 may file an application for a relocation allowance with the Secretary and the Secretary may grant the relocation allowance, subject to the terms and conditions of this subsection.
- (2) CONDITIONS FOR GRANTING ALLOWANCE.— A relocation allowance may be granted if all of the following terms and conditions are met:
- (A) ASSIST AN ADVERSELY AFFECTED WORK-ER.—The relocation allowance will assist an adversely affected worker in relocating within the United States.
- (B) LOCAL EMPLOYMENT NOT AVAILABLE.— The Secretary determines that the worker cannot reasonably be expected to secure suitable employment in the commuting area in which the worker resides.
- (C) TOTAL SEPARATION.—The worker is totally separated from employment at the time relocation commences.
- (D) SUITABLE EMPLOYMENT OBTAINED.—The worker— $\,$
- (i) has obtained suitable employment affording a reasonable expectation of longterm duration in the area in which the worker wishes to relocate; or
- (ii) has obtained a bona fide offer of such employment.

- (E) APPLICATION.—The worker filed an application with the Secretary at such time and in such manner as the Secretary shall specify by regulation.
- (3) AMOUNT OF ALLOWANCE.—The relocation allowance granted to a worker under paragraph (1) includes—
- (A) all reasonable and necessary expenses (including, subsistence and transportation expenses at levels not exceeding amounts prescribed by the Secretary in regulations) incurred in transporting the worker, the worker's family, and household effects; and
- (B) a lump sum equivalent to 3 times the worker's average weekly wage, up to a maximum payment of \$1,500.
- (4) LIMITATIONS.—A relocation allowance may not be granted to a worker unless—
- (A) the relocation occurs within 182 days after the filing of the application for relocation assistance; or
- (B) the relocation occurs within 182 days after the conclusion of training, if the worker entered a training program approved by the Secretary under subsection (b)(2).
- (g) Health Insurance Continuation.—Not later than 1 year after the date of enactment of this part, the Secretary of Labor shall prescribe regulations to provide, for the period in which an adversely affected worker is participating in a training program described in subsection (b)(2), 80 percent of the monthly premium of any health insurance coverage that an adversely affected worker was receiving from such worker's employer prior to the separation from employment described in section 425(b), to be paid to any health care insurance plan designated by the adversely affected worker receiving an allowance under this section.

SEC. 427. GENERAL PROVISIONS.

- (a) AGREEMENTS WITH STATES.—
- (1) IN GENERAL.—The Secretary is authorized on behalf of the United States to enter into an agreement with any State, or with any State agency (referred to in this section as "cooperating States" and "cooperating States agencies" respectively). Under such an agreement, the cooperating State agency—
- (A) as agent of the United States, shall receive applications for, and shall provide, payments on the basis provided in this part:
- (B) in accordance with paragraph (6), shall make available to adversely affected workers covered by a certification under section 425(d) the employment services described in section 426(b)(1):
- (C) shall make any certifications required under section 425(d);
- (D) shall otherwise cooperate with the Secretary and with other State and Federal agencies in providing payments and services under this part.

Each agreement under this section shall provide the terms and conditions upon which the agreement may be amended, suspended, or terminated.

- (2) FORM AND MANNER OF DATA.—Each agreement under this section shall—
- (A) provide the Secretary with the authority to collect any data the Secretary determines necessary to meet the requirements of this part; and
- (B) specify the form and manner in which any such data requested by the Secretary shall be reported.
- (3) RELATIONSHIP TO UNEMPLOYMENT INSURANCE.—Each agreement under this section shall provide that an adversely affected worker receiving a climate change adjustment allowance under this part shall not be eligible for unemployment insurance otherwise payable to such worker under the laws of the State.
- (4) REVIEW.—A determination by a cooperating State agency with respect to entitle-

ment to program benefits under an agreement is subject to review in the same manner and to the same extent as determinations under the applicable State law and only in that manner and to that extent.

- (5) COORDINATION.—Any agreement entered into under this section shall provide for the coordination of the administration of the provisions for employment services, training, and supplemental assistance under section 426 and under title I of the Workforce Investment Act of 1998 upon such terms and conditions as are established by the Secretary in consultation with the States and set forth in such agreement. Any agency of the State jointly administering such provisions under such agreement shall be considered to be a cooperating State agency for purposes of this part.
- (6) RESPONSIBILITIES OF COOPERATING AGENCIES.—Each cooperating State agency shall, in carrying out paragraph (1)(B)—
- (A) advise each worker who applies for unemployment insurance of the benefits under this part and the procedures and deadlines for applying for such benefits:
- (B) facilitate the early filing of petitions under section 425(a) for any workers that the agency considers are likely to be eligible for benefits under this part:
- (C) advise each adversely affected worker to apply for training under section 426(b) before, or at the same time, the worker applies for climate change adjustment allowances under section 426(a):
- (D) perform outreach to, intake of, and orientation for adversely affected workers and adversely affected incumbent workers covered by a certification under section 426(a) with respect to assistance and benefits available under this part;
- (E) make employment services described in section 426(b)(1) available to adversely affected workers and adversely affected incumbent workers covered by a certification under section 425(d) and, if funds provided to carry out this part are insufficient to make such services available, make arrangements to make such services available through other Federal programs; and
- (F) provide the benefits and reemployment services under this part in a manner that is necessary for the proper and efficient administration of this part, including the use of state agency personnel employed in accordance with a merit system of personnel administration standards, including—
- (i) making determinations of eligibility for, and payment of, climate change readjustment allowances and health care benefit replacement amounts:
- (ii) developing recommendations regarding payments as a bridge to retirement and lump sum payments to pension plans in accordance with this subsection; and
- (iii) the provision of reemployment services to eligible workers, including referral to training services.
- (7) In order to promote the coordination of workforce investment activities in each State with activities carried out under this part, any agreement entered into under this section shall provide that the State shall submit to the Secretary, in such form as the Secretary may require, the description and information described in paragraphs (8) and (14) of section 112(b) of the Workforce Investment Act of 1998 (29 U.S.C. 2822(b)) and a description of the State's rapid response activities under section 221(a)(2)(A).
 - (8) CONTROL MEASURES.—
- (A) IN GENERAL.—The Secretary shall require each cooperating State and cooperating State agency to implement effective control measures and to effectively overset the operation and administration of the climate change adjustment assistance program

- under this part, including by means of monitoring the operation of control measures to improve the accuracy and timeliness of the data being collected and reported.
- (B) DEFINITION.—For purposes of subparagraph (A), the term "control measures" means measures that—
- (i) are internal to a system used by a State to collect data; and
- (ii) are designed to ensure the accuracy and verifiability of such data.
 - (9) Data reporting.—
- (A) IN GENERAL.—Any agreement entered into under this section shall require the cooperating State or cooperating State agency to report to the Secretary on a quarterly basis comprehensive performance accountability data, to consist of—
- (i) the core indicators of performance described in subparagraph (B)(i);
- (ii) the additional indicators of performance described in subparagraph (B)(ii), if any; and
- (iii) a description of efforts made to improve outcomes for workers under the climate change adjustment assistance program.
- (B) Core indicators described.—
- (i) IN GENERAL.—The core indicators of performance described in this subparagraph are—
- (I) the percentage of workers receiving benefits under this part who are employed during the second calendar quarter following the calendar quarter in which the workers cease receiving such benefits;
- (II) the percentage of such workers who are employed in each of the third and fourth calendar quarters following the calendar quarter in which the workers cease receiving such benefits; and
- (III) the earnings of such workers in each of the third and fourth calendar quarters following the calendar quarter in which the workers cease receiving such benefits.
- (ii) ADDITIONAL INDICATORS.—The Secretary and a cooperating State or cooperating State agency may agree upon additional indicators of performance for the climate change adjustment assistance program under this part, as appropriate.
- (C) STANDARDS WITH RESPECT TO RELI-ABILITY OF DATA.—In preparing the quarterly report required by subparagraph (A), each cooperating State or cooperating State agency shall establish procedures that are consistent with guidelines to be issued by the Secretary to ensure that the data reported are valid and reliable.
- (10) Verification of eligibility for program benefits.—
- (A) IN GENERAL.—An agreement under this section shall provide that the State shall periodically redetermine that a worker receiving benefits under this part who is not a citizen or national of the United States remains in a satisfactory immigration status. Once satisfactory immigration status has been initially verified through the immigration status verification system described in section 1137(d) of the Social Security Act (42 U.S.C. 1320b-7(d)) for purposes of establishing worker's eligibility for unemployment compensation, the State shall reverify the worker's immigration status if the docuinitial mentation provided during verification will expire during the period in which that worker is potentially eligible to receive benefits under this part. The State shall conduct such redetermination in a timely manner, utilizing the immigration status verification system described in section 1137(d) of the Social Security Act (42 U.S.C. 1320b-7(d)).
- (B) PROCEDURES.—The Secretary shall establish procedures to ensure the uniform application by the States of the requirements of this paragraph.

- (b) Administration Absent State Agreement.—
- (1) In any State where there is no agreement in force between a State or its agency under subsection (a), the Secretary shall promulgate regulations for the performance of all necessary functions under section 426, including provision for a fair hearing for any worker whose application for payments is denied
- (2) A final determination under paragraph (1) with respect to entitlement to program benefits under section 426 is subject to review by the courts in the same manner and to the same extent as is provided by section 205(g) of the Social Security Act (42 U.S.C. 405(g)).
- (c) Prohibition on Contracting With Private Entities.—Neither the Secretary nor a State may contract with any private forprofit or nonprofit entity for the administration of the climate change adjustment assistance program under this part.
 - (d) PAYMENT TO THE STATES .-
- (1) IN GENERAL.—The Secretary shall from time to time certify to the Secretary of the Treasury for payment to each cooperating State the sums necessary to enable such State as agent of the United States to make payments provided for by this part.
- (2) RESTRICTION.—All money paid a State under this subsection shall be used solely for the purposes for which it is paid; and money so paid which is not used for such purposes shall be returned, at the time specified in the agreement under this section, to the Secretary of the Treasury.
- (3) BONDS.—Any agreement under this section may require any officer or employee of the State certifying payments or disbursing funds under the agreement or otherwise participating in the performance of the agreement, to give a surety bond to the United States in such amount as the Secretary may deem necessary, and may provide for the payment of the cost of such bond from funds for carrying out the purposes of this part.
- (e) LABOR STANDARDS.—
- (1) PROHIBITION ON DISPLACEMENT.—An individual in an apprenticeship program or onthe-job training program under this part shall not displace (including a partial displacement, such as a reduction in the hours of non-overtime work, wages, or employment benefits) any employed employee.
- (2) PROHIBITION ON IMPAIRMENT OF CONTRACTS.—An apprenticeship program or onthe-job raining program under this Act shall not impair an existing contract for services or collective bargaining agreement, and no such activity that would be inconsistent with the terms of a collective bargaining agreement shall be undertaken without the written concurrence of the labor organization and employer concerned.
- (3) ADDITIONAL STANDARDS.—The Secretary, or a State acting under an agreement described in subsection (a) may pay the costs of on-the-job training, notwithstanding any other provision of this section, only if—
- (A) in the case of training which would be inconsistent with the terms of a collective bargaining agreement, the written concurrence of the labor organization concerned has been obtained;
- (B) the job for which such adversely affected worker is being trained is not being created in a promotional line that will infringe in any way upon the promotional opportunities of currently employed individuals:
- (C) such training is not for the same occupation from which the worker was separated and with respect to which such worker's group was certified pursuant to section 425(d):
- (D) the employer is provided reimbursement of not more than 50 percent of the wage

- rate of the participant, for the cost of providing the training and additional supervision related to the training; and
- (E) the employer has not received payment under with respect to any other on-the-job training provided by such employer which failed to meet the requirements of subparagraphs (A) through (D).
- (f) DEFINITIONS.—As used in this part the following definitions apply:
 (1) The term "adversely affected employ-
- (1) The term "adversely affected employment" means employment at an employment site, if workers at such site are eligible to apply for adjustment assistance under this part.
- (2) The term "adversely affected worker" means an individual who has been totally or partially separated from employment and is eligible to apply for adjustment assistance under this part.
- (3) The term "average weekly wage" means ½3 of the total wages paid to an individual in the quarter in which the individual's total wages were highest among the first 4 of the last 5 completed calendar quarters immediately before the quarter in which occurs the week with respect to which the computation is made. Such week shall be the week in which total separation occurred, or, in cases where partial separation is claimed, an appropriate week, as defined in regulations prescribed by the Secretary.
- (4) The term "average weekly hours" means the average hours worked by the individual (excluding overtime) in the employment from which he has been or claims to have been separated in the 52 weeks (excluding weeks during which the individual was sick or on vacation) preceding the week specified in the last sentence of paragraph (4).
- (5) The term "benefit period" means, with respect to an individual—
- (Å) the benefit year and any ensuing period, as determined under applicable State law, during which the individual is eligible for regular compensation, additional compensation, or extended compensation; or
- (B) the equivalent to such a benefit year or ensuing period provided for under the applicable Federal unemployment insurance law.
- (6) The term "consumer goods manufacturing" means the electrical equipment, appliance, and component manufacturing industry and transportation equipment manufacturing.
- (7) The term "employment site" means a single facility or site of employment.
- (8) The term "energy-intensive manufacturing industries" means all industrial sectors, entities, or groups of entities that meet the energy or greenhouse gas intensity criteria in section 765(b)(2)(A)(i) of the Clean Air Act based on the most recent data available.
- (9) The term "energy producing and transforming industries" means the coal mining industry, oil and gas extraction, electricity power generation, transmission and distribution, and natural gas distribution.
- (10) The term "industries dependent on energy industries" means rail transportation and pipeline transportation.
- (11) The term "on-the-job training" means training provided by an employer to an individual who is employed by the employer.
- (12) The terms "partial separation" and "partially separated" refer, with respect to an individual who has not been totally separated, that such individual has had—
- (A) his or her hours of work reduced to 80 percent or less of his average weekly hours in adversely affected employment; and
- (B) his or her wages reduced to 80 percent or less of his average weekly wage in such adversely affected employment.
- (13) The term "public agency" means a department or agency of a State or political

subdivision of a State or of the Federal government.

- (14) The term "Secretary" means the Secretary of Labor.
- (15) The term "service workers" means workers supplying support or auxiliary services to an employment site.
- (16) The term "State agency" means the agency of the State which administers the State law.
- (17) The term "State law" means the unemployment insurance law of the State approved by the Secretary of Labor under section 3304 of the Internal Revenue Code of 1954.
- (18) The terms "total separation" and "totally separated" refer to the layoff or severance of an individual from employment with an employer in which adversely affected employment exists.
- (19) The term "unemployment insurance" means the unemployment compensation payable to an individual under any State law or Federal unemployment compensation law, including chapter 85 of title 5, United States Code, and the Railroad Unemployment Insurance Act. The terms "regular compensation", "additional compensation", and "extended compensation" have the same respective meanings that are given them in section 205(2), (3), and (4) of the Federal-State Extended Unemployment Compensation Act of 1970 (26 U.S.C. 3304 note.)
- (20) The term "week" means a week as defined in the applicable State law.
- (21) The term "week of unemployment" means a week of total, part-total, or partial unemployment as determined under the applicable State law or Federal unemployment insurance law.
- (g) SPECIAL RULE WITH RESPECT TO MILITARY SERVICE.—
- (1) IN GENERAL.—Notwithstanding any other provision of this part, the Secretary may waive any requirement of this part that the Secretary determines is necessary to ensure that an adversely affected worker who is a member of a reserve component of the Armed Forces and serves a period of duty described in paragraph (2) is eligible to receive a climate change adjustment allowance, training, and other benefits under this part in the same manner and to the same extent as if the worker had not served the period of duty.
- (2) PERIOD OF DUTY DESCRIBED.—An adversely affected worker serves a period of duty described in this paragraph if, before completing training under this part, the worker—
- (A) serves on active duty for a period of more than 30 days under a call or order to active duty of more than 30 days; or
- (B) in the case of a member of the Army National Guard of the United States or Air National Guard of the United States, performs full-time National Guard duty under section 502(f) of title 32, United States Code, for 30 consecutive days or more when authorized by the President or the Secretary of Defense for the purpose of responding to a national emergency declared by the President and supported by Federal funds.
- (h) FRAUD AND RECOVERY OF OVERPAY-MENTS.—
- (1) RECOVERY OF PAYMENTS TO WHICH AN INDIVIDUAL WAS NOT ENTITLED.—If the Secretary or a court of competent jurisdiction determines that any person has received any payment under this part to which the individual was not entitled, such individual shall be liable to repay such amount to the Secretary, as the case may be, except that the Secretary shall waive such repayment if such agency or the Secretary determines that—
- (A) the payment was made without fault on the part of such individual; and

- (B) requiring such repayment would cause a financial hardship for the individual (or the individual's household, if applicable) when taking into consideration the income and resources reasonably available to the individual (or household) and other ordinary living expenses of the individual (or household).
- (2) MEANS OF RECOVERY.—Unless an overpayment is otherwise recovered, or waived under paragraph (1), the Secretary shall recover the overpayment by deductions from any sums payable to such person under this part, under any Federal unemployment compensation law or other Federal law administered by the Secretary which provides for the payment of assistance or an allowance with respect to unemployment. Any amount recovered under this section shall be returned to the Treasury of the United States.
- (i) REGULATIONS.—The Secretary shall prescribe such regulations as may be necessary to carry out the provisions of this part.
- (j) STUDY ON OLDER WORKERS.—The Secretary shall conduct a study examine the circumstances of older adversely affected workers and the ability of such workers to access their retirement benefits. The Secretary shall transmit a report to Congress not later than 2 years after the date of enactment of this part on the findings of the study and the Secretary's recommendations on how to ensure that adversely affected workers within 2 years of retirement are able to access their retirement benefits.
- [(k) SPENDING LIMIT.—For each fiscal year, the total amount of funds disbursed for the purposes described in section 426 shall not exceed the amount deposited in that fiscal year into the Climate Change Worker Assistance Fund established under section [782(j)] of the Clean Air Act. The annual spending limit for any succeeding year shall be increased by the difference, if any, between the amount of the prior year's disbursements and the spending limitation for that year. The Secretary shall promulgate rules to ensure that this spending limit is not exceeded. Such rules shall provide that workers who receive any of the benefits described in section 426 receive full benefits, and shall include the establishment of a waiting list for workers in the event that the requests for assistance exceed the spending limit.]

Subtitle C—Consumer Assistance SEC. 431. ENERGY REFUND PROGRAM.

The Social Security Act (42 U.S.C. 201 et seq.) is amended by adding at the end the following:

"TITLE XXII—ENERGY REFUND PROGRAM "SEC. 2201. ENERGY REFUND PROGRAM.

- "(a) In General.—The Secretary shall formulate and administer the program provided for in this section, which shall be known as the 'Energy Refund Program', and under which eligible low-income households are provided cash payments to reimburse the households for the estimated loss in their purchasing power resulting from the American Clean Energy and Security Act of 2009.
- "(b) ENTITLEMENT OF ELIGIBLE HOUSEHOLDS TO CASH PAYMENTS.—At the request of the State agency of a State, each eligible low-income household in the State shall be entitled to receive monthly cash payments under this section in an amount equal to the monthly energy refund amount determined under subsection (d).
- "(c) ELIGIBILITY.-
- "(1) ELIGIBLE HOUSEHOLDS.—A household shall be considered to be an eligible low-income household for purposes of this section if
- "(A) the gross income of the household does not exceed the greater of—
 - "(i) 150 percent of the poverty line; or

- "(ii) the greatest amount of household gross income in respect of which a benefit could be payable under subsection (d)(2)(B);
- "(B) the State agency of the State in which the household is located determines that the household is participating in—
- "(i) the Supplemental Nutrition Assistance Program authorized by the Food and Nutrition Act of 2008 (7 U.S.C. 2011 et seq.);
- "(ii) the Food Distribution Program on Indian Reservations authorized by section 4(b) of such Act (7 U.S.C. 2013(b)); or
- "(iii) the program for nutrition assistance in Puerto Rico or American Samoa under section 19 of such Act (7 U.S.C. 2028);
- "(C) the household consists of a single individual or a married couple, and—
- "(i) receives the subsidy described in section 1860D-14 of this Act (42 U.S.C. 1395w-114); or
- ''(ii)(I) participates in the program under title XVIII of this Act; and
- "(II) meets the income requirements described in section 1860D-14(a)(1) or (a)(2) of this Act (42 U.S.C. 1395w-114(a)(1) or (a)(2)); or
- "(D) the household consists of a single individual or a married couple, and receives benefits under the supplemental security income program under title XVI of this Act (42 U.S.C. 1381–1383f).
- "(2) STREAMLINED PARTICIPATION FOR CERTAIN BENEFICIARIES.—The Secretary shall—
- "(A) periodically estimate the number of eligible beneficiaries and households, and the number of participating beneficiaries and households, for the Energy Refund Program; and
- "(B) develop procedures, in consultation with the Commissioner of Social Security, the Railroad Retirement Board, the Secretary of Veterans Affairs, and the State agencies, to ensure that low-income beneficiaries of the benefit programs administered by such entities receive the energy refund for which the beneficiaries are eligible under the Energy Refund Program.
- "(3) LIMITATION.—Notwithstanding any other provision of law, the Secretary shall provide refunds to United States citizens, United States nationals, and individuals lawfully residing in the United States who qualify for a refund under paragraph (1)(A), and shall establish procedures to ensure that other individuals do not receive refunds.
- "(4) National Standards.—The Secretary shall consult with the Secretary of Agriculture and establish uniform national standards of eligibility ensuring that States may seamlessly co-administer the energy refund program with the Supplemental Nutrition Assistance Program in accordance with the provisions of this section. No State agency shall impose any other standard or requirement as a condition of eligibility or refund receipt under the program. Assistance in the Energy Refund Program shall be furnished promptly to all eligible households who make application for such participation or are already enrolled in any program referred to in paragraph (1).
 - "(d) Monthly Energy Refund Amount.-
- "(1) ESTIMATED ANNUAL TOTAL LOSS IN PURCHASING POWER.—Not later than August 31 of each fiscal year, the Energy Information Administration shall estimate the annual total loss in purchasing power that will result from American Clean Energy and Security Act of 2009 in the next fiscal year for households of each size with gross income equal to 150 percent of the poverty line, based on the projected total market value of all compliance costs (including, but not limited to, the emissions allowances used to demonstrate compliance with title VII of the Clean Air Act in the next fiscal year, and excluding costs that are not projected to be incurred

by households as a result of allowances freely allocated and intended for residential consumer assistance pursuant to sections 785 through 785 of the Clean Air Act), in a way generally recognized as suitable by experts.

"(2) MONTHLY ENERGY REFUND.—The monthly energy refund amount for an eligible household under this section shall be—

"(A) if the gross income of the household does not exceed 150 percent of the poverty line applicable to the household—

"(i) if the household has 1, 2, 3, or 4 members, $\frac{1}{12}$ of the amount estimated under paragraph (1) for a household of the same size, rounded to the nearest whole dollar amount; or

"(ii) if the household has 5 or more members, ½2 of the arithmetic mean value of the amounts estimated under paragraph (1) for households with 5 or more members, rounded to the nearest whole dollar amount: or

"(B) if the gross income of the household exceeds 150 percent of the poverty line applicable to the household, ½2 of the amount (if any) by which—

"(i) the amount estimated under paragraph (1) for a household of the same size: exceeds

"(ii) 20 percent of the amount by which the gross income of the household exceeds 150 percent of the poverty line.

"(e) DELIVERY MECHANISM.-

"(1) Subject to standards and an implementation schedule set by the Secretary, the energy refund shall be provided in monthly installments via—

"(A) direct deposit into the eligible household's designated bank account:

"(B) the State's electronic benefit transfer system; or

"(C) another Federal or State mechanism, if such a mechanism is approved by the Secretary.

"(2) Such standards shall include—

"(A)(i) defining the required level of recipient protection regarding privacy;

"(ii) guidance on how recipients are offered choices, when relevant, about the delivery mechanism;

"(iii) guidance on ease of use and access to the refund, including the prohibition of fees charged to recipients for withdrawals or other services; and

"(iv) cost-effective protections against improper accessing of the energy refund;

"(B) operating standards that provide for interoperability between States and law enforcement monitoring; and

"(C) other standards, as determined by the Secretary or the Secretary's designee.

"(f) ADMINISTRATION.—

"(1) IN GENERAL.—The State agency of each participating State shall assume responsibility for the certification of applicant households and for the issuance of refunds and the control and accountability thereof.

"(2) PROCEDURES.—Under standards established by the Secretary, the State agency shall establish procedures governing the administration of the Energy Refund Program that the State agency determines best serve households in the State, including households with special needs, such as households with special needs, such as households in rural areas, homeless individuals, and households residing on reservations as defined in the Indian Child Welfare Act of 1978 and the Indian Financing Act of 1974. In carrying out this paragraph, a State agency—

"(A) shall provide timely, accurate, and fair service to applicants for, and participants in, the Energy Refund Program;

"(B) shall permit an applicant household to apply to participate in the program at the time that the household first contacts the State agency, and shall consider an application that contains the name, address, and signature of the applicant to be sufficient to constitute an application for participation;

"(C) shall screen any applicant household for the Supplemental Nutrition Assistance Program, the State's medical assistance program under section XIX of this Act, State Childrens Health Insurance Program under section XXI of this Act, and a State program that provides basic assistance under a State program funded under title IV of this Act or with qualified State expenditures as defined in section 409(a)(7) of this Act for eligibility for the Energy Refund Program and, if eligible, shall enroll such applicant household in the Energy Refund Program;

"(D) shall complete certification of and provide a refund to any eligible household not later than 30 days following its filing of an application:

"(E) shall use appropriate bilingual personnel and materials in the administration of the program in those portions of the State in which a substantial number of members of low-income households speak a language other than English; and

"(F) shall utilize State agency personnel who are employed in accordance with the current standards for a Merit System of Personnel Administration or any standards later prescribed by the Office of Personnel Management pursuant to section 208 of the Intergovernmental Personnel Act of 1970 (42 U.S.C. 4728) modifying or superseding such standards relating to the establishment and maintenance of personnel standards on a merit basis to make all tentative and final determinations of eligibility and ineligibility.

"(3) Regulations —

"(A) Except as provided in subparagraph (B), the Secretary shall issue such regulations consistent with this section as the Secretary deems necessary or appropriate for the effective and efficient administration of the Energy Refund Program, and shall promulgate all such regulations in accordance with the procedures set forth in section 553 of title 5, United States Code.

"(B) Without regard to section 553 of title 5 of such Code, the Administrator may by rule promulgate as final, to be effective until no later than two years after the date of the enactment of the American Clean Energy and Security Act of 2009, any procedures that are substantially the same as the procedures governing the Supplemental Nutrition Assistance Program in section 273.2, 273.12, or 273.15 of title 7, Code of Federal Regulations.

"(C) Notwithstanding subsection (i)(4), the Secretary may promulgate regulations allowing for streamlined eligibility determinations for some or all households which include individuals receiving assistance under a State plan approved under title XIX or XXI of this Act. The regulations may institute procedures whereby the income and family size information used for determining eligibility under such title XIX or XXI may be the basis for determining eligibility for the Energy Refund Program.

"(D) Notwithstanding any other provision of this section, the Secretary may authorize States to provide benefits under this section on a quarterly basis if the Secretary determines that the amount of the benefits that would be provided on a monthly basis to households is insufficient to be efficiently paid on a monthly basis in light of the administrative expenses of the Energy Refund Program.

"(g) TREATMENT.—The value of the refund provided under this section shall not be considered income or resources for any purpose under any Federal, State, or local laws, including, but not limited to, laws relating to an income tax, or public assistance programs (including, but not limited to, health care, cash aid, child care, nutrition programs, and

housing assistance) and no participating State or political subdivision thereof shall decrease any assistance otherwise provided an individual or individuals because of the receipt of a refund under this section.

"(h) PROGRAM INTEGRITY.—For purposes of ensuring program integrity and complying with the requirements of the Improper Payment Information Act of 2002, the Secretary shall, to the maximum extent possible, rely on and coordinate with the quality control sample and review procedures of paragraphs (2), (3), (4), and (5) of section 16(c) of the Food and Nutrition Act of 2008 (7 U.S.C. 2025(c)).

"(i) Definitions.—

"(1) SECRETARY.—The term 'Secretary' means the Secretary of Health and Human Services or the head of another agency designated by the Secretary of Health and Human Services.

"(2) ELECTRONIC BENEFIT TRANSFER SYSTEM.—The term 'electronic benefit transfer system' means a system by which household benefits or refunds defined under subsection (e) are issued from and stored in a central databank via electronic benefit transfer cards.

"(3) GROSS INCOME.—The term 'gross income' means the gross income of a household that is determined in accordance with standards and procedures established under section 5 of the Food and Nutrition Act of 2008 (7 U.S.C. 2014) and its implementing regulations.

"(4) HOUSEHOLD.—

"(A) The term 'household' means-

"(i) in subparagraphs (A) and (B) of subsection (c)(1) of this section, except as provided in subparagraph (C) of this paragraph, an individual or a group of individuals who are a household under section 3(n) of the Food and Nutrition Act of 2008 (7 U.S.C. 2012(n));

"(ii) in subsection (c)(1)(C) of this section, a single individual or married couple that receives benefits under section 1860D-14 of this Act (42 U.S.C. 1395w-114); and

"(iii) in subsection (c)(1)(D) of this section, a single individual or married couple that receives benefits under the supplemental security income program under title XVI of this Act (42 U.S.C. 1381–1383f).

"(B) The Secretary shall establish rules for providing the energy refund in an equitable and administratively simple manner to households where the group of individuals who live together includes members not all of whom are described in a single clause of subparagraph (A), or includes additional members not described in any such clause.

"(C) The Secretary shall establish rules regarding the eligibility and delivery of the energy refund to groups of individuals described in section 3(n)(4) or (5) of the Food and Nutrition Act of 2008 (7 U.S.C. 2012(n)).

"(5) POVERTY LINE.—The term 'poverty line' has the meaning given the term in section 673(2) of the Community Services Block Grant Act (42 U.S.C. 9902(2)), including any revision required by that section.

"(6) STATE.—The term 'State' means the 50 States, the District of Columbia, the Commonwealth of Puerto Rico, American Samoa, the United States Virgin Islands, Guam, and the Commonwealth of the Northern Mariana Islands.

"(7) STATE AGENCY.—The term 'State agency' means an agency of State government, including the local offices thereof, that has responsibility for administration of the 1 or more federally aided public assistance programs within the State, and in those States where such assistance programs are operated on a decentralized basis, the term shall include the counterpart local agencies administering such programs.

"(8) OTHER TERMS.—Other terms not defined in this title shall have the same meaning applied in the Supplemental Nutrition Assistance Program authorized by the Food and Nutrition Act of 2008 (7 U.S.C. 2011 et seq.) unless the Secretary finds for good cause that application of a particular definition would be detrimental to the purposes of the Energy Refund Program."

SEC. 432. MODIFICATION OF EARNED INCOME CREDIT AMOUNT FOR INDIVIDUALS WITH NO QUALIFYING CHILDREN.

- (a) IN GENERAL.—Subsection (b) of section 32 of the Internal Revenue Code of 1986 is amended by adding at the end the following new paragraph:
- "(4) SPECIAL RULE FOR INDIVIDUALS WITH NO QUALIFYING CHILDREN WHO ARE AFFECTED BY THE AMERICAN CLEAN ENERGY AND SECURITY ACT OF 2009.—
- "(A) IN GENERAL.—In the case of any household which the Secretary determines experienced a reduction in purchasing power as a result of the provisions of, or amendments made by, the American Clean Energy and Security Act of 2009 (determined without regard to this paragraph and section 2201 of the Social Security Act)—
- "(i) INCREASE IN CREDIT PERCENTAGE AND PHASEOUT PERCENTAGE.—The table contained in paragraph (1)(A) shall be applied by substituting '15.3' for '7.65'.
- "(ii) INCREASE IN BEGINNING PHASEOUT AMOUNT.—The table contained in paragraph (2)(A) shall be applied by substituting \$11,640' for \$5,280'.
 - "(B) INFLATION ADJUSTMENT.—
- "(i) IN GENERAL.—In the case of any taxable year beginning after 2012, the \$11,640 amount in subparagraph (A)(ii) shall be increased by an amount equal to—
 - "(I) such dollar amount, multiplied by
- "(II) the cost of living adjustment determined under section 1(f)(3) for the calendar year in which the taxable year begins determined by substituting 'calendar year 2011' for 'calendar year 1992' in subparagraph (B) thereof.
- "(ii) ROUNDING.—Subparagraph (A) of subsection (j)(2) shall apply after taking into account any increase under clause (i) in the same manner as if such increase were under paragraph (1) of subsection (j).
- "(iii) COORDINATION WITH OTHER INFLATION ADJUSTMENTS.—Paragraph (1) of subsection (j) shall not apply to the dollar amount substituted under subparagraph (A)(ii)." (b) EFFECTIVE DATE.—The amendment
- (b) EFFECTIVE DATE.—The amendment made by this section shall apply to taxable years beginning after December 31, 2011.

SEC. 433. PROTECTION OF SOCIAL SECURITY AND MEDICARE TRUST FUNDS.

- (a) OASDI TRUST FUNDS.—Section 201 of the Social Security Act (42 U.S.C. 401) is amended by adding at the end the following new subsection:
- (o) The Secretary of the Treasury shall transfer from time to time to the Federal Old-Age and Survivors Insurance Trust Fund and the Federal Disability Insurance Trust Fund, from amounts in the general fund of the Treasury that are not otherwise appropriated, such sums as the Chief Actuary of the Social Security Administration calculates as necessary (and so certifies to such Secretary) for any fiscal year, on account of changes in benefit costs and changes in tax revenue attributable to the provisions of the American Clean Energy and Security Act of 2009 and the amendments made thereby, in order to place each of such Trust Funds in the same position at the end of such fiscal year as the position in which such Trust Fund would have been if such changes had not occurred.".
- (b) HI TRUST FUND.—Section 1817 of such Act (42 U.S.C. 1395i) is amended by adding at the end the following new subsection:

"(1) Transfers to Account for Changes IN BENEFIT COSTS AND CHANGES IN TAX REV-ENUE ATTRIBUTABLE TO THE AMERICAN CLEAN ENERGY AND SECURITY ACT OF 2009.—The Secretary of the Treasury shall transfer from time to time to the Trust Fund, from amounts in the general fund of the Treasury that are not otherwise appropriated, such sums as the Chief Actuary of the Centers for Medicare & Medicaid Services calculates as necessary (and so certifies to such Secretary) for any fiscal year, on account of changes in benefit costs and changes in tax revenue attributable to the provisions of the American Clean Energy and Security Act of 2009 and the amendments made thereby, in order to place the Trust Fund in the same position at the end of such fiscal year as the position in which it would have been if such changes had not occurred."

Subtitle D—Exporting Clean Technology SEC. 441. FINDINGS AND PURPOSES.

- (a) FINDINGS.—Congress finds the following:
- (1) Protecting Americans from the impacts of climate change requires global reductions in greenhouse gas emissions.
- (2) Although developing countries are historically least responsible for the cumulative greenhouse gas emissions that are causing climate change and continue to have very low per capita greenhouse gas emissions, their overall greenhouse gas emissions are increasing as they seek to grow their economies and reduce energy poverty for their populations.
- (3) Many developing countries lack the financial and technical resources to adopt clean energy technologies and absent assistance their greenhouse gas emissions will continue to increase.
- (4) Investments in clean energy technology cooperation can substantially reduce global greenhouse gas emissions while providing developing countries with incentives to adopt policies that will address competitiveness concerns related to regulation of United States greenhouse gas emissions.
- (5) Investments in clean technology in developing countries will increase demand for clean energy products, open up new markets for United States companies, spur innovation, and lower costs.
- (6) Under Article 4 of the United Nations Framework Convention on Climate Change, developed country parties, including the United States, committed to "take all practicable steps to promote, facilitate, and finance, as appropriate, the transfer of, or access to, environmentally sound technologies and know-how to other parties, particularly developing country parties, to enable them to implement the provisions of the Convention".
- (7) Under the Bali Action Plan, developed country parties to the United Nations Framework Convention on Climate Change, including the United States, committed to "enhanced action on the provision of financial resources and investment to support action on mitigation and adaptation and technology cooperation," including, inter alia, consideration of "improved access to adequate, predictable, and sustainable financial resources and financial and technical support, and the provision of new and additional fresources, including official and concessional funding for developing country parties".
- (8) Intellectual property rights are a key driver of investment and research and development in, and the global deployment of, clean technologies.
- (9) Innovative clean technologies, including U.S. and multilateral financing mechanisms for their deployment, are critical to mitigating global warming pollution, preventing catastrophic changes to the climate,

- and developing robust economies around the world.
- (10) Any weakening of intellectual property rights protection poses a substantial competitive risk to U.S. companies and the creation of high-quality U.S. jobs, inhibiting the creation of new "green" employment and the transformational shift to the "Green Economy" of the 21st Century.
- (11) Any U.S. funding directed toward assisting developing countries with regard to exporting clean technology should promote the robust compliance with and enforcement of existing international legal requirements for the protection of intellectual property rights as formulated in the Agreement on Trade-Related Aspects of Intellectual Property Rights, referred to in section 101(d)(15) of the Uruguay Round Agreements Act (19 U.S.C.3511(d)(15) and in applicable intellectual property provisions of bilateral trade agreements.
- (b) PURPOSES.—The purposes of this subtitle are—
- (1) to provide United States assistance and leverage private resources to encourage widespread implementation, in developing countries, of activities that reduce, sequester, or avoid greenhouse gas emissions; and
- (2) to provide such assistance in a manner that—
- (A) encourages such countries to adopt policies and measures, including sector-based and cross-sector policies and measures, that substantially reduce, sequester, or avoid greenhouse gas emissions;
- (B) promotes the successful negotiation of a global agreement to reduce greenhouse gas emissions under the United Nations Framework Convention on Climate Change; and
- (C) promotes robust compliance with and enforcement of existing international legal requirements for the protection of intellectual property rights, as formulated in the Agreement on Trade-Related Aspects of Intellectual Property Rights referred to in section 101(d)(15) of the Uruguay Round Agreements Act (19 U.S.C. 3511(d)(15)) and in applicable intellectual property provisions of bilateral trade agreements.

SEC. 442. DEFINITIONS.

In this subtitle:

- (1) ALLOWANCE.—The term "allowance" means an emission allowance established under section 721 of the Clean Air Act.
- (2) APPROPRIATE CONGRESSIONAL COMMITTEES.—The term "appropriate congressional committees" means—
- (A) the Committees on Energy and Commerce, Foreign Affairs, and Financial Services of the House of Representatives; and
- (B) the Committees on Environment and Public Works, Energy and Natural Resources, and Foreign Relations of the Senate.
- (3) CONVENTION.—The term "Convention" means the United Nations Framework Convention on Climate Change, done at New York on May 9, 1992, and entered into force on March 21, 1994.
- (4) DEVELOPING COUNTRY.—The term "developing country" means a country eligible to receive official development assistance according to the income guidelines of the Development Assistance Committee of the Organization for Economic Cooperation and Development.
- (5) ELIGIBLE COUNTRY.—The term "eligible country" means a developing country that is determined by the interagency group under section 444 to be eligible to receive assistance under this subtitle.
- (6) INTERAGENCY GROUP.—The term "interagency group" means the group established by the President under section 443 to administer the program established under this subtitle.

- (7) LEAST DEVELOPED COUNTRY.—The term "least developed country" means a foreign country the United Nations has identified as among the least developed of developing countries.
- (8) QUALIFYING ACTIVITY.—The term "qualifying activity" means an activity that meets the criteria in section 445.
- (9) QUALIFYING ENTITY.—The term "qualifying entity" means a national, regional, or local government in, or a nongovernmental organization or private entity located or operating in, an eligible country.

SEC. 443. GOVERNANCE.

- (a) OVERSIGHT.—The Secretary of State, or such other Federal agency head as the President may designate, in consultation with the interagency group established under subsection (b), shall oversee distributions of allowances allocated under section 782(o) of the Clean Air Act (as added by section 321 of this Act) for distribution pursuant to this subtifile.
- (b) INTERAGENCY GROUP.—The President shall establish an interagency group to administer the program established under this subtitle. The Members of the interagency group shall include—
 - (1) the Secretary of State;
- (2) the Administrator of the Environmental Protection Agency;
 - (3) the Secretary of Energy:
 - (4) the Secretary of the Treasury;
 - (5) the Secretary of Commerce;
- (6) the Administrator of the United States Agency for International Development; and
- (7) any other head of a Federal agency or executive branch appointee that the President may designate.
- (c) CHAIRPERSON.—The Secretary of State shall serve as the chairperson of the interagency group.
- (d) SUPPLEMENT NOT SUPPLANT.—Allowances distributed pursuant to this subtitle shall be used to supplement, and not to supplant, any other Federal, State, or local resources available to carry out activities that are qualifying activities under this subtitle.

SEC. 444. DETERMINATION OF ELIGIBLE COUNTRIES

TRIES.

- (a) IN GENERAL.—The interagency group shall determine a country to be an eligible country for the purposes of this subtitle if a country meets the following criteria:
- (1) The country is a developing country that—
- (A) has entered into an international agreement to which the United States is a party, under which such country agrees to take actions to produce measurable, reportable, and verifiable greenhouse gas emissions mitigation; or
- (B) is determined by the interagency group to have in force national policies and measures that are capable of producing measurable, reportable, and verifiable greenhouse gas emissions mitigation.
- (2) The country has developed a nationally appropriate mitigation strategy that seeks to achieve substantial reductions, sequestration, or avoidance of greenhouse gas emissions, relative to business-as-usual levels.
- (3) Subject to subsection (b)(1), such other criteria as the President determines will serve the purposes of this subtitle or other United States national security, foreign policy, environmental, or economic objectives including robust compliance with and enforcement of existing international legal requirements for the protection of intellectual property rights for clean technology, as formulated in the Agreement on Trade-Related Aspects of Intellectual Property Rights, referred to in section 101(d)(15) of the Uruguay Round Agreements Act (19 U.S.C. 3511(d)(15)) and in applicable intellectual property provisions of bilateral trade agreements.

- (b) Exceptions.—
- (1) Subsection (a)(3) applies only to bilateral assistance under section 446(c)(4).
- (2) The eligibility criteria in this section do not apply in the case of least developed countries receiving assistance under section 445(7) for the purpose of building capacity to meet such eligibility criteria.

SEC. 445. QUALIFYING ACTIVITIES.

Assistance under this subtitle may be provided only to qualifying entities for clean technology activities (including building relevant technical and institutional capacity) that contribute to substantial, measurable, reportable, and verifiable reductions, sequestration, or avoidance of greenhouse gas emissions including—

- (1) deployment of technologies to capture and sequester carbon dioxide emissions from electric generating units or large industrial sources (except that assistance under this subtitle for such deployment shall be limited to the cost of retrofitting existing facilities with such technologies or the incremental cost of purchasing and installing such technologies at new facilities);
- (2) deployment of renewable electricity generation from wind, solar, sustainably produced biomass, geothermal, marine, or hydrokinetic sources;
- (3) substantial increases in the efficiency of electricity transmission, distribution, and consumption;
- (4) deployment of low- or zero emissions technologies that are facing financial or other barriers to their widespread deployment which could be addressed through support under this subtitle in order to reduce, sequester, or avoid emission:
- (5) reduction in transportation sector emissions through increased transportation system and vehicle efficiency or use of transportation fuels that have lifecycle greenhouse gas emissions that are substantially lower than those attributable to fossil fuel-based alternatives:
- (6) reduction in black carbon emissions; or
- (7) capacity building activities, including—
 (A) developing and implementing methodologies and programs for measuring and quantifying greenhouse gas emissions and verifying emissions mitigation;
- (B) assessing, developing, and implementing technology and policy options for greenhouse gas emissions mitigation and avoidance of future emissions, including sector and cross-sector mitigation strategies;
- (C) providing other forms of technical assistance to facilitate the qualification for, and receipt of, assistance under this Act.

 SEC. 446. ASSISTANCE.
- (a) IN GENERAL.—The Secretary of State, or such other Federal agency head as the President may designate, is authorized to provide assistance, through the distribution of allowances, allocated for such purpose under section 782(o) of the Clean Air Act (as added by section 321 of this Act) for qualifying activities that take place in eligible countries, in accordance with the requirements of this subtitle.
- (b) DEFINITION.—For the purposes of this section the term "clean technology" means any technology or service related to the qualifying activities identified in section 445.
- (c) DISTRIBUTION OF ALLOWANCES.—
- (1) IN GENERAL.—The Secretary of State, or such other Federal agency head as the President may designate, after consultation with the interagency group, shall distribute allowances under this subtitle—
- (A) in the form of bilateral assistance in accordance with paragraph (4);
- (B) to multilateral funds or institutions pursuant to the Convention or an agreement negotiated under the Convention; or

- (C) through some combination of the mechanisms identified in subparagraphs (A) and (B)
- (2) GLOBAL ENVIRONMENT FACILITY.—For any allowances provided to the Global Environment Facility pursuant to paragraph (1)(B), the President shall designate the Secretary of the Treasury to distribute those allowances to the Global Environment Facility.
- (3) DISTRIBUTION THROUGH INTERNATIONAL FUND OR INSTITUTION.—If allowances are distributed to a multilateral fund or institution, as authorized in paragraph (1), the Secretary of State, or such other Federal agency head as the President may designate, shall seek to ensure the establishment and implementation of adequate mechanisms to—
- (A) apply and enforce the criteria for determination of eligible countries and qualifying activities under sections 444 and 445, respectively;
- (B) require public reporting describing the process and methodology for selecting the ultimate recipients of assistance and a description of each activity that received assistance, including the amount of obligations and expenditures for assistance; and
- (C) require that no funds be expended for the benefit of any qualifying activity where that activity or any activity relating to a qualifying activity under section 445 undermines the robust compliance with and enforcement of existing legal requirements for the protection of intellectual property rights for clean technology, as formulated in the Agreement on Trade-Related Aspects of Intellectual Property Rights, referred to in section 101(d)(15) of the Uruguay Round Agreements Act (19 U.S.C. 3511(d)(15)).
 - (4) BILATERAL ASSISTANCE.-
- (A) IN GENERAL.—Bilateral assistance under paragraph (1) shall be carried out by the Administrator of the United States Agency for International Development, in consultation with the interagency group.
- (B) LIMITATIONS.—Not more than 15 percent of allowances made available to carry out bilateral assistance under this subtitle in any year shall be distributed to support activities in any single country.
- (C) SELECTION CRITERIA.—Not later than 2 years after the date of enactment of this subtitle, the Administrator of the United States Agency for International Development, after consultation with the interagency group, shall develop and publish a set of criteria to be used in evaluating activities within eligible countries for bilateral assistance under this subtitle.
- (D) CRITERIA REQUIREMENTS.—The criteria under subparagraph (C) shall require that—
- (i) the activity is a qualifying activity;
- (ii) the activity will be conducted as part of an eligible country's nationally appropriate mitigation strategy or as part of an eligible country's actions towards providing a nationally appropriate mitigation strategy to reduce, sequester, or avoid emissions being implemented by the eligible country;
- (iii) the activity will not have adverse effects on human health, safety, or welfare, the environment, or natural resources;
- (iv) any technologies deployed through bilateral assistance under this subtitle will be properly implemented and maintained;
- (v) the activity will not cause any net loss of United States jobs or displacement of United States production;
- (vi) costs of the activity will be shared by the host country government, private sector parties, or a multinational development bank, except that this clause does not apply to least developed countries;
- (vii) the activity would not undermine the protection of intellectual property rights for clean technology, as formulated in the

Agreement on Trade-Related Aspects of Intellectual Property Rights, referred to in section 101(d)(15) of the Uruguay Round Agreements Act (19 U.S.C. 3511(d)(15)) and applicable intellectual property provisions of bilateral trade agreements; and

(viii) the activity meets such other requirements as the interagency group determines appropriate to further the purposes of this subtitle.

- (E) CRITERIA PREFERENCES.—The criteria under subparagraph (C) shall give preference to activities that—
- (i) promise to achieve large-scale greenhouse gas reductions, sequestration, or avoidance at a national, sectoral or crosssectoral level:
- (ii) have the potential to catalyze a shift within the host country towards widespread deployment of low- or zero-carbon energy technologies;
- (iii) build technical and institutional capacity and other activities that are unlikely to be attractive to private sector funding; or
- (iv) maximize opportunities to leverage other sources of assistance and catalyze private-sector investment.
- (d) Monttoring, Evaluation, and Enforcement.—The Secretary of State, or such other Federal agency head as the President may designate, in consultation with the interagency group, shall establish and implement a system to monitor and evaluate the performance of activities receiving assistance under this subtitle. The Secretary of State, or such other Federal agency head as the President may designate, shall have the authority to suspend or terminate assistance in whole or in part for an activity if it is determined that the activity is not operating in compliance with the approved proposal.

(e) COORDINATION WITH U.S. FOREIGN AS-SISTANCE.—Subject to the direction of the President, the Secretary of State shall, to the extent practicable, seek to align activities under this section with broader development, poverty alleviation, or natural resource management objectives and initiatives in the recipient country.

(f) ANNUAL REPORTS.—Not later than March 1, 2012, and annually thereafter, the President shall submit to the appropriate congressional committees a report on the assistance provided under this subtitle during the prior fiscal year. Such report shall include—

- (1) a description of the amount and value of allowances distributed during the prior fiscal year;
- (2) a description of each activity that received assistance during the prior fiscal year, and a description of the anticipated and actual outcomes;
- (3) an assessment of any adverse effects to human health, safety, or welfare, the environment, or natural resources as a result of activities supported under this subtitle:
- (4) an assessment of the success of the assistance provided under this subtitle to improving the technical and institutional capacity to implement substantial emissions reductions:
- (5) an estimate of the greenhouse gas emissions reductions, sequestration, or avoidance achieved by assistance provided under this subtitle during the prior fiscal year; and
- (6) an assessment whether any funds expended for the benefit of any qualifying activity undermined the protection of intellectual property rights for clean technology, as formulated in the Agreement on Trade-Related Aspects of Intellectual Property Rights, referred to in section 101(d)(15) of the Uruguay Round Agreements Act (19 U.S.C. 3511(d)(15)) and applicable intellectual property provisions of bilateral trade agreements.
- (g) NOT ELIGIBLE FOR OFFSET CREDIT.—Activities that receive support under this sub-

title shall not be issued offset credits for the greenhouse gas emissions reductions or avoidance, or greenhouse gas sequestration, produced by such activities.

Subtitle E—Adapting to Climate Change PART 1—DOMESTIC ADAPTATION Subpart A—National Climate Change Adaptation Program

SEC. 451. GLOBAL CHANGE RESEARCH AND DATA MANAGEMENT.

- (a) SHORT TITLE.—This section may be cited as the "Global Change Research and Data Management Act of 2009".
 - (b) GLOBAL CHANGE RESEARCH.-
- (1) PURPOSE.—The purpose of this subsection is to provide for the continuation and coordination of a comprehensive and integrated United States observation, research, and outreach program which will assist the Nation and the world to understand, assess, predict, and respond to the effects of human-induced and natural processes of global change.
- (2) Definitions.—For purposes of this subsection—
- (A) the term "global change" means human-induced or natural changes in the global environment (including alterations in climate, land productivity, oceans or other water resources, atmospheric chemistry, biodiversity, and ecological systems) that may alter the capacity of the Earth to sustain life:
- (B) the term "global change research" means study, monitoring, assessment, prediction, and information management activities to describe and understand—
- (i) the interactive physical, chemical, and biological processes that regulate the total Earth system;
- (ii) the unique environment that the Earth provides for life;
- (iii) changes that are occurring in the Earth system; and
- (iv) the manner in which such system, environment, and changes are influenced by human actions:
- (C) the term "interagency committee" means the interagency committee established under paragraph (3);
- (D) the term "Plan" means the National Global Change Research and Assessment Plan developed under paragraph (5);
- (E) the term "Program" means the United States Global Change Research Program established under paragraph (4); and
- (F) the term "regional climate change" means the natural or human-induced changes manifested in the local or regional environment (including alterations in weather patterns, land productivity, water resources, sea level rise, atmospheric chemistry, biodiversity, and ecological systems) that may alter the capacity of a specific region to support current or future social and economic activity or natural ecosystems.
- (3) Interagency cooperation and coordination.—
- (A) ESTABLISHMENT.—The President shall establish or designate an interagency committee to ensure cooperation and coordination of all Federal research activities pertaining to processes of global change for the purpose of increasing the overall effectiveness and productivity of Federal global change research efforts. The interagency committee shall include research and program representatives of agencies conducting global change research, agencies with authority over resources likely to be affected by global change, and agencies with authorto mitigate human-induced global itv change.
- (B) FUNCTIONS OF THE INTERAGENCY COM-MITTEE.—The interagency committee shall—
- (i) serve as the forum for developing the Plan and for overseeing its implementation;

- (ii) serve as the forum for developing the vulnerability assessment under paragraph (7).
- (iii) ensure cooperation among Federal agencies with respect to global change research activities;
- (iv) work with academic, State, industry, and other groups conducting global change research, to provide for periodic public and peer review of the Program;
- (v) cooperate with the Secretary of State in—
- (I) providing representation at international meetings and conferences on global change research in which the United States participates; and
- (II) coordinating the Federal activities of the United States with programs of other nations and with international global change research activities;
- (vi) work with appropriate Federal, State, regional, and local authorities to ensure that the Program is designed to produce information needed to develop policies to mitigate human-induced global change and to reduce the vulnerability of the United States and other regions to global change:
- (vii) facilitate ongoing dialog and information exchange with regional, State, and local governments and other user communities; and
- (viii) identify additional decisionmaking groups that may use information generated through the Program.
- (4) UNITED STATES GLOBAL CHANGE RE-SEARCH PROGRAM.—
- (A) ESTABLISHMENT.—The President shall establish an interagency United States Global Change Research Program to improve understanding of global change, to respond to the information needs of communities and decisionmakers, and to provide periodic assessments of the vulnerability of the United States and other regions to global and regional climate change. The Program shall be implemented in accordance with the Plan.
- (B) LEAD AGENCY.—The lead agency for the United States Global Change Research Program shall be the Office of Science and Technology Policy.
- (C) Interagency program activities.—The Director of the Office of Science and Technology Policy, in consultation with the interagency committee, shall identify activities included in the Plan that involve participation by 2 or more agencies in the Program, and that do not fall within the current fiscal year budget allocations of those participating agencies, to fulfill the requirements of this section. The Director of the Office of Science and Technology Policy shall allocate funds to the agencies to conduct the identified interagency activities. Such activities may include—
- (i) development of scenarios for climate, land-cover change, population growth, and socioeconomic development:
- (ii) calibration and testing of alternative regional and global climate models;
- (iii) identification of economic sectors and regional climatic zones; and
- (iv) convening regional workshops to facilitate information exchange and involvement of regional, State, and local decisionmakers, non-Federal experts, and other stakeholder groups in the activities of the Program.
- (D) Workshops.—The Director shall ensure that at least one workshop is held per year in each region identified by the Plan under paragraph (5)(B)(xi) to facilitate information exchange and outreach to regional, State, and local stakeholders as required by this section.
- (E) AUTHORIZATION OF APPROPRIATIONS.— There are authorized to be appropriated to the Office of Science and Technology Policy

for carrying out this paragraph \$10,000,000 for each of the fiscal years 2009 through 2014.

- (5) NATIONAL GLOBAL CHANGE RESEARCH AND ASSESSMENT PLAN.—
- (A) IN GENERAL.—The President shall develop a National Global Change Research and Assessment Plan for implementation of the Program. The Plan shall contain recommendations for global change research and assessment. The President shall submit an outline for the development of the Plan to the Congress within 1 year after the date of enactment of this Act, and shall submit a completed Plan to the Congress within 3 vears after the date of enactment of this Act. Revised Plans shall be submitted to the Congress at least once every 5 years thereafter. In the development of each Plan, the President shall conduct a formal assessment process under this paragraph to determine the needs of appropriate Federal, State, regional, and local authorities and other interested parties regarding the types of information needed by them in developing policies to mitigate human-induced global change and to reduce society's vulnerability to global change and shall utilize these assessments, including the reviews by the National Academy of Sciences and the National Governors Association under subparagraphs (E) and (F), in developing the Plan.
- (B) CONTENTS OF THE PLAN.—The Plan shall—
- (i) establish, for the 10-year period beginning in the year the Plan is submitted, the goals and priorities for Federal global change research which most effectively advance scientific understanding of global change and provide information of use to Federal, State, regional, and local authorities in the development of policies relating to global change:
- (ii) describe specific activities, including efforts to determine user information needs, research activities, data collection, database development, and data analysis requirements, development of regional scenarios, assessment of model predictability, assessment of climate change impacts, participation in international research efforts, and information management, required to achieve such goals and priorities;
- (iii) identify relevant programs and activities of the Federal agencies that contribute to the Program directly and indirectly;
- (iv) set forth the role of each Federal agency in implementing the Plan;
- (v) consider and utilize, as appropriate, reports and studies conducted by Federal agencies, the National Research Council, or other entities;
- (vi) make recommendations for the coordination of the global change research and assessment activities of the United States with such activities of other nations and international organizations, including—
- (I) a description of the extent and nature of international cooperative activities;
- (II) bilateral and multilateral efforts to provide worldwide access to scientific data and information; and
- (III) improving participation by developing nations in international global change research and environmental data collection;
- (vii) detail budget requirements for Federal global change research and assessment activities to be conducted under the Plan;
- (viii) catalog the type of information identified by appropriate Federal, State, regional, and local decisionmakers needed to develop policies to reduce society's vulnerability to global change and indicate how the planned research will meet these decisionmakers' information needs;
- (ix) identify the observing systems currently employed in collecting data relevant to global and regional climate change research and prioritize additional observation

- systems that may be needed to ensure adequate data collection and monitoring of global change:
- (x) describe specific activities designed to facilitate outreach and data and information exchange with regional, State, and local governments and other user communities; and
- (xi) identify and describe regions of the United States that are likely to experience similar impacts of global change or are likely to share similar vulnerabilities to global change.
- (C) RESEARCH ELEMENTS.—The Plan shall include at a minimum the following research elements:
- (i) Global measurements, establishing worldwide to regional scale observations prioritized to understand global change and to meet the information needs of decision-makers on all relevant spatial and time scales.
- (ii) Information on economic, demographic, and technological trends that contribute to changes in the Earth system and that influence society's vulnerability to global and regional climate change.
- (iii) Development of indicators and baseline databases to document global change, including changes in species distribution and behavior, extent of glaciations, and changes in sea level.
- (iv) Studies of historical changes in the Earth system, using evidence from the geological and fossil record.
- (v) Assessments of predictability using quantitative models of the Earth system to simulate global and regional environmental processes and trends.
- (vi) Focused research initiatives to understand the nature of and interaction among physical, chemical, biological, land use, and social processes related to global and regional climate change.
- (vii) Focused research initiatives to determine and then meet the information needs of appropriate Federal, State, and regional decisionmakers
- (D) INFORMATION MANAGEMENT.—The Plan shall incorporate, to the extent practicable, the recommendations relating to data acquisition, management, integration, and archiving made by the interagency climate and other global change data management working group established under subsection (c)(3).
- (E) NATIONAL ACADEMY OF SCIENCES EVAL-UATION.—The President shall enter into an agreement with the National Academy of Sciences under which the Academy shall—
- (i) evaluate the scientific content of the Plan: and
- (ii) recommend priorities for future global and regional climate change research and assessment.
- (F) NATIONAL GOVERNORS ASSOCIATION EVALUATION.—The President shall enter into an agreement with the National Governors Association Center for Best Practices under which that Center shall—
- (i) evaluate the utility to State, local, and regional decisionmakers of each Plan and of the anticipated and actual information outputs of the Program for development of State, local, and regional policies to reduce vulnerability to global change; and
- (ii) recommend priorities for future global and regional climate change research and as-
- (G) Public participation.—In developing the Plan, the President shall consult with representatives of academic, State, industry, and environmental groups. Not later than 90 days before the President submits the Plan, or any revision thereof, to the Congress, a summary of the proposed Plan shall be published in the Federal Register for a public comment period of not less than 60 days.
 - (6) BUDGET COORDINATION.—

- (A) IN GENERAL.—The President shall provide general guidance to each Federal agency participating in the Program with respect to the preparation of requests for appropriations for activities related to the Program.
- (B) CONSIDERATION IN PRESIDENT'S BUDGET.—The President shall submit, at the time of his annual budget request to Congress, a description of those items in each agency's annual budget which are elements of the Program.
 - (7) VULNERABILITY ASSESSMENT.—
- (A) REQUIREMENT.—Within 1 year after the date of enactment of this Act, and at least once every 5 years thereafter, the President shall submit to the Congress an assessment which—
- (i) integrates, evaluates, and interprets the findings of the Program and discusses the scientific uncertainties associated with such findings:
- (ii) analyzes current trends in global change, both human-induced and natural, and projects major trends for the subsequent 25 to 100 years:
- (iii) based on indicators and baselines developed under paragraph (5)(C)(iii), as well as other measurements, analyzes changes to the natural environment, land and water resources, and biological diversity in—
- (I) major geographic regions of the United States; and
 - (II) other continents;
- (iv) analyzes the effects of global change, including the changes described in clause (iii), on food and fiber production, energy production and use, transportation, human health and welfare, water availability and coastal infrastructure, and human social and economic systems, including providing information about the differential impacts on specific geographic regions within the United States, on people of different income levels within those regions, and for rural and urban areas within those regions; and
- (v) summarizes the vulnerability of different geographic regions of the world to global change and analyzes the implications of global change for the United States, including international assistance, population displacement, food and resource availability, and national security.
- (B) USE OF RELATED REPORTS.—To the extent appropriate, the assessment produced pursuant to this paragraph may coordinate with, consider, incorporate, or otherwise make use of related reports, assessments, or information produced by the United States Global Change Research Program, regional, State, and local entities, and international organizations, including the World Meteorological Organization and the Intergovernmental Panel on Climate Change.
- (8) POLICY ASSESSMENT.—Not later than 1 year after the date of enactment of this Act, and at least once every 4 years thereafter, the President shall enter into a joint agreement with the National Academy of Public Administration and the National Academy of Sciences under which the Academies shall—
- (A) document current policy options being implemented by Federal, State, and local governments to mitigate or adapt to the effects of global and regional climate change;
- (B) evaluate the realized and anticipated effectiveness of those current policy options in meeting mitigation and adaptation goals;
- (C) identify and evaluate a range of additional policy options and infrastructure for mitigating or adapting to the effects of global and regional climate change:
- (D) analyze the adoption rates of policies and technologies available to reduce the vulnerability of society to global change with an evaluation of the market and policy obstacles to their adoption in the United States; and

- (E) evaluate the distribution of economic costs and benefits of these policy options across different United States economic sectors
- (9) ANNUAL REPORT.—Each year at the time of submission to the Congress of the President's budget request, the President shall submit to the Congress a report on the activities conducted pursuant to this subsection, including—
- (A) a description of the activities of the Program during the past fiscal year;
- (B) a description of the activities planned in the next fiscal year toward achieving the goals of the Plan; and
- (C) a description of the groups or categories of State, local, and regional decision-makers identified as potential users of the information generated through the Program and a description of the activities used to facilitate consultations with and outreach to these groups, coordinated through the work of the interagency committee.
- (10) Relation to other authorities.—The President shall— $\,$
- (A) ensure that relevant research, assessment, and outreach activities of the National Climate Program, established by the National Climate Program Act (15 U.S.C. 2901 et seq.), are considered in developing national global and regional climate change research and assessment efforts; and
- (B) facilitate ongoing dialog and information exchange with regional, State, and local governments and other user communities through programs authorized in the National Climate Program Act (15 U.S.C. 2901 et seq.).
- (11) REPEAL.—The Global Change Research Act of 1990 (15 U.S.C. 2921 et seq.) is amended by striking titles I and III thereof.
- (12) GLOBAL CHANGE RESEARCH INFORMATION.—The President shall establish or designate a Global Change Research Information Exchange to make scientific research and other information produced through or utilized by the Program which would be useful in preventing, mitigating, or adapting to the effects of global change accessible through electronic means.
 - (13) ICE SHEET STUDY AND REPORT.—
 - (A) STUDY.—
- (i) REQUIREMENT.—The Director of the National Science Foundation and the Administrator of National Oceanic and Atmospheric Administration shall enter into an arrangement with the National Academy of Sciences to complete a study of the current status of ice sheet melt, as caused by climate change, with implications for global sea level rise.
- (ii) CONTENTS.—The study shall take into consideration—
- (I) the past research completed related to ice sheet melt as reviewed by Working Group I of the Intergovernmental Panel on Climate Change:
- (II) additional research completed since the fall of 2005 that was not included in the Working Group I report due to time constraints; and
- (III) the need for an accurate assessment of changes in ice sheet spreading, changes in ice sheet flow, self-lubrication, the corresponding effect on ice sheets, and current modeling capabilities.
- (B) REPORT.—Not later than 18 months after the date of enactment of this Act, the National Academy of Sciences shall transmit to the Committee on Science and Technology of the House of Representatives and the Committee on Commerce, Science, and Transportation of the Senate a report on the key findings of the study conducted under subparagraph (A), along with recommendations for additional research related to ice sheet melt and corresponding sea level rise.
- (14) HURRICANE FREQUENCY AND INTENSITY STUDY AND REPORT.—
- (A) STUDY.—

- (i) REQUIREMENT.—The Administrator of the National Oceanic and Atmospheric Administration and the Director of the National Science Foundation shall enter into an arrangement with the National Academy of Sciences to complete a study of the current state of the science on the potential impacts of climate change on patterns of hurricane and typhoon development, including storm intensity, track, and frequency, and the implications for hurricane-prone and typhoon-prone coastal regions.
- (ii) CONTENTS.—The study shall take into consideration—
- (I) the past research completed related to hurricane and typhoon development, track, and intensity as reviewed by Working Groups I and II of the Intergovernmental Panel on Climate Change;
- (II) additional research completed since the fall of 2005 that was not included in the Working Group I and II reports due to time constraints:
- (III) the need for accurate assessment of potential changes in hurricane and typhoon intensity, track, and frequency and of the current modeling and forecasting capabilities and the need for improvements in forecasting of these parameters; and
- (IV) the need for additional research and monitoring to improve forecasting of hurricanes and typhoons and to understand the relationship between climate change and hurricane and typhoon development.
- (B) REPORT.—Not later than 18 months after the date of enactment of this Act, the National Academy of Sciences shall transmit to the Committee on Science and Technology of the House of Representatives and the Committee on Commerce, Science, and Transportation of the Senate a report on the key findings of the study conducted under subparagraph (A).
- (c) CLIMATE AND OTHER GLOBAL CHANGE DATA MANAGEMENT.—
- (1) PURPOSES.—The purposes of this subsection are to establish climate and other global change data management and archiving as Federal agency missions, and to establish Federal policies for managing and archiving climate and other global change data.
- (2) Definitions.—For purposes of this subsection— $\,$
- (A) the term "metadata" means information describing the content, quality, condition, and other characteristics of climate and other global change data, compiled, to the maximum extent possible, consistent with the requirements of the "Content Standard for Digital Geospatial Metadata" (FGDC-STD-001-1998) issued by the Federal Geographic Data Committee, or any successor standard approved by the working group; and
- (B) the term "working group" means the interagency climate and other global change data management working group established under paragraph (3).
- (3) Interagency climate and other global change data management working group.—
- (A) ESTABLISHMENT.—The President shall establish or designate an interagency climate and other global change data management working group to make recommendations for coordinating Federal climate and other global change data management and archiving activities.
- (B) MEMBERSHIP.—The working group shall include the Administrator of the National Aeronautics and Space Administration, the Administrator of the National Oceanic and Atmospheric Administration, the Secretary of Energy, the Secretary of Defense, the Director of the National Science Foundation, the Director of the United States Geological Survey, the Archivist of the United States,

- the Administrator of the Environmental Protection Agency, the Secretary of the Smithsonian Institution, or their designees, and representatives of any other Federal agencies the President considers appropriate.
- (C) REPORTS.—Not later than 1 year after the date of enactment of this Act, the working group shall transmit a report to the Congress containing the elements described in subparagraph (D). Not later than 4 years after the initial report under this subparagraph, and at least once every 4 years thereafter, the working group shall transmit reports updating the previous report. In preparing reports under this subparagraph, the working group shall consult with expected users of the data collected and archived by the Program.
- (D) CONTENTS.—The reports and updates required under subparagraph (C) shall—
- (i) include recommendations for the establishment, maintenance, and accessibility of a catalog identifying all available climate and other global change data sets:
- (ii) identify climate and other global change data collections in danger of being lost and recommend actions to prevent such loss;
- (iii) identify gaps in climate and other global change data and recommend actions to fill those gaps;
- (iv) identify effective and compatible procedures for climate and other global change data collection, management, and retention and make recommendations for ensuring their use by Federal agencies and other appropriate entities:
- (v) develop and propose a coordinated strategy for funding and allocating responsibilities among Federal agencies for climate and other global change data collection, management, and retention;
- (vi) make recommendations for ensuring that particular attention is paid to the collection, management, and archiving of metadata:
- (vii) make recommendations for ensuring a unified and coordinated Federal capital investment strategy with respect to climate and other global change data collection, management, and archiving:
- (viii) evaluate the data record from each observing system and make recommendations to ensure that delivered data are free from time-dependent biases and random errors before they are transferred to long-term archives; and
- (ix) evaluate optimal design of observation system components to ensure a cost-effective, adequate set of observations detecting and tracking global change.

SEC. 452. NATIONAL CLIMATE SERVICE.

- (a) SHORT TITLE.—This section may be cited as the "National Climate Service Act of 2009".
- (b) PURPOSE.—The purpose of this section is to establish a National Climate Service and to define the activities to be undertaken within the National Oceanic and Atmospheric Administration to—
- (1) advance understanding of climate variability and change at the global, national, regional, and local levels;
- (2) provide forecasts, warnings, and other information to the public on variability and change in weather and climate that affect geographic areas, natural resources, infrastructure, economic sectors, and communities; and
- (3) support development of adaptation and response plans by Federal agencies, State, local, and tribal governments, the private sector, and the public.
 - (c) DEFINITIONS.—In this section:
- (1) ADVISORY COMMITTEE.—The term "Advisory Committee" means the Climate Service

- Advisory Committee established under subsection (f).
- (2) DIRECTOR.—The term "Director" means the Director of the Climate Service Office.
- (3) REPRESENTATIVE.—The term "representative" means an individual who is not a full-time or part-time employee of the Federal Government and who is appointed to an advisory committee to represent the views of an entity or entities outside the Federal Government.
- (4) SPECIAL GOVERNMENT EMPLOYEE.—The term "Special Government Employee" has the same meaning as in section 202(a) of title 18, United States Code.
- (5) UNDER SECRETARY.—The term "Under Secretary" means the Under Secretary of Commerce for Oceans and Atmosphere.
- (d) Interagency Development of a National Climate Service.—
- (1) IN GENERAL.—The President shall—
- (A) initiate a process within 30 days after the date of enactment of this Act through the Committee on Environment and Natural Resources of the National Science and Technology Council and led by the Director of the Office of Science and Technology Policy, to evaluate alternative structures to support a collaborative, interagency research and operational program that will achieve the goal of meeting the needs of decisionmakers in—
- (i) Federal agencies;
- (ii) State, local, and tribal governments;
- (iii) regional entities and other stakeholders and users.
- for reliable, timely, and relevant information related to climate variability and change:
- (B) within 1 year after the date of enactment of this Act complete pursuant to paragraph (2) a survey of the needs of current and future users of information related to climate variability and change;
- (C) within 2 years after the date of enactment of this Act report to Congress under paragraph (3) the results of the evaluation described in subparagraph (A) and provide a plan to establish a collaborative, interagency research and operational program to deliver information related to climate variability and change to all users; and
- (D) within 3 years after the date of enactment of this Act, and after delivery of the report to Congress required under subparagraph (C), establish a National Climate Service, based upon the information obtained through the process described in subparagraph (A), that meets the goal described in subparagraph (A).
- (2) SURVEY OF NEED FOR CLIMATE SERV-ICES.—
- (A) IN GENERAL.—The Director of the Office of Science and Technology Policy, through the Committee on Environment and Natural Resources, shall provide a report to Congress within 1 year after the date of enactment of this Act that compiles information on the current climate products being delivered by each Federal agency and its partner organizations to users and stakeholders, and on the needs of users and stakeholders for new climate products and services.
- (B) CONTENTS OF THE REPORT.—The report shall identify—
- (i) specific user groups and stakeholders that currently are served by each Federal agency and its partner organizations;
- (ii) the type of climate products and services currently delivered to specific users groups and stakeholders, and the specific Federal agency office, program, or partner organization that delivers these products and services:
- (iii) potential user groups and stakeholders that may be served by expanding climate products and services;

- (iv) specific needs for new climate products and services to be delivered by each Federal agency and its partner organizations identified by user groups and stakeholders;
- (v) a characterization of the different user and stakeholder groups that were surveyed by each Federal agency; and
- (vi) a list of non-Federal entities that deliver climate products and services.
- (3) Report to congress.-
- (A) IN GENERAL.—Within 2 years after the date of enactment of this Act, the Director of the Office of Science and Technology Policy shall report to the President and the Congress on a proposal, prepared through the Committee on Environment and Natural Resources, to establish and operate a National Climate Service. The report shall include—
- (i) a description of the alternative structures considered;
- (ii) a description of the structure proposed for a National Climate Service, including a discussion of the benefits of this structure as compared to the alternatives considered:
- (iii) designation of a specific office or agency that will lead the National Climate Service and that shall be accountable for the daily operation of the National Climate Service;
- (iv) a description of the role and capability of each Federal agency, including a list of all entities within each agency or supported with agency funds that currently provide or may provide climate products or services;
- (v) a description of the mechanisms that will be used to ensure ongoing communication and information exchange among the Federal agencies and between Federal agencies and their respective user and stakeholder communities including—
- (I) mechanisms to facilitate ongoing dialogue with non-Federal organizations providing climate services;
- (II) mechanisms to facilitate ongoing dialogue with regional, State, local, and tribal governments, the private sector, and other users and stakeholders on the development and delivery of climate services;
- (III) mechanisms to collect information, observations, and other data relevant for improving climate products and services; and
- (IV) designation of points of contact for each Federal agency with responsibilities to deliver climate services;
- (vi) a detailed description of the processes and procedures that will be necessary to coordinate observations and information collection by different Federal agencies to ensure the compatibility of information and to facilitate data and information exchange among Federal agencies and with non-Federal entities, and a designation of the agency or agencies that would be responsible for ongoing oversight of these functions:
- (vii) a detailed description of how research findings and climate impact assessments produced through the United States Global Change Research Program and the other activities undertaken within the United States Global Change Research Program would be integrated with the activities undertaken by a National Climate Service;
- (viii) a list of the existing observation and monitoring systems or programs operated by each Federal agency that provide data, observations, and other information that may be used to develop or improve climate products and services;
- (ix) a description of new infrastructure, equipment, personnel or other resources, by agency, that may be needed to achieve the goals of a National Climate Service, and the time period over which these new resources will be allocated:
- (x) an identification of the activities that may be undertaken in cooperation with international partners;

- (xi) the mechanisms established to provide quality assurance and quality control of climate service products and services, and the agency or agencies designated to conduct and oversee these mechanisms:
- (xii) an identification of non-Federal entities that provide climate products and services, and a description of the relationship envisioned between a National Climate Service and the non-Federal entities providing climate services; and
- (xiii) responses to the comments received during the public comment period.
- (B) DRAFT REPORT.—Prior to the submission of the final report, the Director of the Office of Science and Technology Policy shall publish a draft report in the Federal Register with a comment period of at least 30 days.
- (C) CONSULTATION.—In developing the report, the Director of the Office of Science and Technology Policy shall consult with State, local, and tribal governments, regional entities, the private sector, and other users and stakeholder groups, and Congress.
- (4) ANNUAL REPORT.—The Director of the Office of Science and Technology Policy shall transmit to the Congress at the time of the President's fiscal year 2013 budget request, and annually thereafter, a report on the annual anticipated cost of carrying out the research and operational activities of the National Climate Service, with a description of the budget for each Federal agency's activities.
 - (e) CLIMATE SERVICE PROGRAM.—
- (1) IN GENERAL.—The Under Secretary, building upon the resources of the National Weather Service and other weather and climate programs in the National Oceanic and Atmospheric Administration, shall establish a Climate Service Program.
- (2) CLIMATE SERVICE OFFICE.—The Under Secretary shall establish a Climate Service Office and shall appoint a Director of the Office to collaborate with the leadership of the National Oceanic and Atmospheric Administration line offices to perform the duties assigned to the Office. The Climate Service Office shall—
- (A) coordinate programs at the National Oceanic and Atmospheric Administration to ensure the timely production and distribution of data and information on global, national, regional, and local climate variability and change over all time scales relevant for planning and response, including intraseasonal, interannual, decadal, and multidecadal time periods;
- (B) ensure exchange of information between the research and operational offices at the National Oceanic and Atmospheric Administration to identify research needs for improving climate products and services and ensure the timely and orderly transition of research findings, improved technologies, models, and other tools to the National Oceanic and Atmospheric Administration's operations;
- (C) ensure operational quality control of all Climate Service Program products including a transparent and open accounting of all the assumptions built into the global, national, regional, and local weather and climate computer models upon which such products are based;
- (D) ensure a continuous level of high-quality data collected through a national observation and monitoring infrastructure, including at a minimum performing regular maintenance and verification, and periodic upgrades;
- (E) serve as liaison to and exchange information with other Federal agencies that provide climate services in order to—

- (i) ensure the timely dissemination of data and information on weather and climate produced by the National Oceanic and Atmospheric Administration to other Federal agencies.
- (ii) ensure that data and information collected by other Federal agencies relevant to improving climate services are made available to the National Oceanic and Atmospheric Administration;
- (iii) facilitate the development and delivery of climate products and services to relevant stakeholders; and
- (iv) obtain information from other Federal agencies to improve the development and dissemination by the National Oceanic and Atmospheric Administration of information on weather and climate to other Federal agencies for the development of climate service products by those agencies;
- (F) ensure cooperation and collaboration, as appropriate, of the Climate Service Program with State, local, and tribal governments, regional entities, academic and nonprofit research organizations, and private sector entities, including weather information providers and other stakeholders; and
- (G) ensure exchange of data, information, and research with the United States Global Change Research Program to support the development of assessments required under the Global Change Research Act of 1990 (15 U.S.C. 2921 et seq.).
 - (3) CLIMATE SERVICE PROGRAM.—
- (A) IN GENERAL.—The Under Secretary shall operate the Climate Service Program through a national center, the Climate Service Office, and a network of regional and local facilities, including the established regional and local offices of the National Weather Service, 6 Regional Climate Centers, the offices of the Regional Integrated Sciences and Assessments program, the National Integrated Drought Information System, and any other National Oceanic and Atmospheric Administration or National Oceanic and Atmospheric Administration-supported regional and local entities, as appropriate.
- (B) REGIONAL CLIMATE CENTERS PROGRAM.— The Under Secretary shall maintain a network of 6 Regional Climate Centers to work cooperatively with the State Climate Offices to—
- (i) collect and exchange data and information needed to characterize, understand, and forecast regional and local weather and climate:
- (ii) facilitate collection and exchange of data and information between the States and Federal Government on weather and climate in conjunction with the National Climatic Data Center;
- (iii) support research and observations;
- (iv) obtain input on stakeholder needs for weather and climate information and products; and
- (v) support State and local adaptation and response planning.
- (C) REGIONAL INTEGRATED SCIENCES AND AS-SESSMENTS PROGRAM.—The Under Secretary shall maintain a network of offices as part of the Regional Integrated Sciences and Assessments Program. Such offices shall engage in cooperative research, development, and demonstration projects with the academic community, State Climate Offices, Regional Climate Offices, and other users and stakeholders on climate products, technologies, models, and other tools to improve understanding and forecasting of regional and local climate variability and change and the effects on economic activities, natural resources, and water availability, and other effects on communities, to facilitate development of regional and local adaptation plans to respond to climate variability and change, and any other needed research identified by

- the Under Secretary or the Advisory Committee.
- (D) OTHER OFFICES.—In carrying out the functions of the Climate Service Program, the Under Secretary shall utilize the assets and expertise of—
- (i) the National Weather Service to-
- (I) deliver operational weather and climate forecasts, warnings, products, and information through the Climate Service Programs Division, Local Weather Forecast Offices, Weather Service Offices, and River Forecast Centers; and
- (II) develop climate forecast models and tools through the National Centers for Environmental Prediction;
- (ii) the National Environmental Satellite, Data, and Information Service to provide data services and support for product development and operations through the National Climatic Data Center and the Regional Climate Centers:
- (iii) the Office of Oceanic and Atmospheric Research to— $\,$
- (I) provide research on product development;
- (II) improve weather and climate forecast models;
- (III) provide new technologies and methods of observation; and
- (IV) oversee the National Oceanic and Atmospheric Administration supported research performed by the Joint Cooperative Institutes, universities, and other non-Federal entities:
- (iv) the National Integrated Drought Information System to—
- (I) provide an effective drought warning system:
- (II) coordinate and integrate Federal research on droughts:
- (III) collect and integrate information on key indicators of drought:
- (IV) make usable, reliable, and timely forecasts and assessments of drought, including assessments of the severity of drought conditions and effects:
- (V) communicate drought forecasts, conditions, and effects to Federal, State, tribal, and local governments, regional entities, the private sector, and the public; and
- (VI) coordinate with State Climate Offices and RISA teams to assess management practices and technologies, and the effects of both, used for drought mitigation at the local, State, and regional levels; and
- (v) any other National Oceanic and Atmospheric Administration offices or programs, as appropriate.
- (E) Mission.—The Under Secretary shall ensure that the core functions and missions of the National Weather Service, the National Integrated Drought Information System, and any other programs within the National Oceanic and Atmospheric Administration are not diminished or neglected by the establishment of the Climate Service Program or the duties imposed on such offices or programs under this paragraph.
- (F) PROGRAM ELEMENTS.—The Climate Service Program shall—
- (i) conduct analyses of and studies relating to the effects of weather and climate on communities, including effects on agricultural production, natural resources, energy supply and demand, recreation, and other sectors of the economy;
- (ii) carry out observations, data collection, and monitoring of atmospheric and oceanic conditions on a statewide, regional, national, and global basis:
- (iii) provide information and technical support for Federal, regional, State, tribal, and local government efforts to assess and respond to climate variability and change;
- (iv) develop systems for the management and dissemination of data, information, and assessments, including mechanisms for con-

- sultation with current and potential users and other stakeholders;
- (v) conduct research to improve forecasting, characterization, and understanding of weather and climate variability and change and its effects on communities, including its effects on agricultural production, natural resources, energy supply and demand, recreation, and other sectors of the economy; and
- (vi) develop tools to facilitate the use of climate information by local and regional stakeholders.
- (f) CLIMATE SERVICE ADVISORY COM
- (1) IN GENERAL.—The Under Secretary shall establish a Climate Service Advisory Committee to provide advice on—
 - (A) climate service product development;
- (B) delivery of services to decisionmakers and other stakeholders;
- (C) infrastructure to support observations and monitoring;
- (D) computation and modeling needs, research needs, and other resources needed to develop, distribute, and ensure the utility of climate data, products, and services; and
- (E) any other topics as may be requested by the Under Secretary or Congress. (2) MEMBERS.—
- (A) IN GENERAL.—The Advisory Committee shall be composed of at least 25 members appointed by the Under Secretary. Each member of the Advisory Committee shall be qualified either—
- (i) by education, training, and experience to evaluate scientific and technical information on matters referred to the Advisory Committee under this subsection; or
- (ii) to evaluate the utility and need for climate products by planners, decisionmakers, the private sector, and the public.
- (B) TERMS OF SERVICE.—Members shall be appointed for 3-year terms, renewable once, and shall serve at the discretion of the Under Secretary. Vacancy appointments shall be for the remainder of the unexpired term of the vacancy, and an individual so appointed may subsequently be appointed for 2 full 3-year terms if the remainder of the unexpired term is less than one year.
- (C) CHAIRPERSON.—The Under Secretary shall designate a chairperson from among the members of the Advisory Committee. The designated Chairperson shall alternate between a member who is appointed as a representative and a member who is appointed as a Special Government Employee.
 - (D) Subcommittees.
- (i) ESTABLISHMENT.—The Advisory Committee shall establish—
- (I) a Subcommittee on Science and Technology to advise the Climate Service Program on needed research, technology development, and additional observations, and on any other scientific or technical issues as appropriate; and
- (II) a Subcommittee on Product Development and Delivery composed primarily of representatives of the community of potential users of the products developed and delivered by the Climate Service Program.
- The Advisory Committee may establish such additional subcommittees of its members as may be necessary.
 - (ii) Appointment.—
- (I) FULL ADVISORY COMMITTEE.—At least 50 percent of the members of the Advisory Committee shall be appointed as Special Government Employees.
- (II) Subcommittees.—At least 75 percent of the members of the Subcommittee on Science and Technology shall be appointed as Special Government Employees. Not more than 25 percent of the members of the Subcommittee on Product Development and Delivery shall be appointed as Special Government Employees.

- (3) Administrative provisions.—
- (A) REPORTING.—The Advisory Committee shall report to the Under Secretary and the appropriate requesting party.
- (B) ADMINISTRATIVE SUPPORT.—The Under Secretary shall provide administrative support to the Advisory Committee.
- (C) MEETINGS.—The Advisory Committee shall meet at least twice each year and at other times at the call of the Under Secretary or the Chairperson.
- (D) COMPENSATION AND EXPENSES.—A member of the Advisory Committee shall not be compensated for service on the Advisory Committee, but may be allowed travel expenses, including per diem in lieu of subsistence, in accordance with subchapter I of chapter 57 of title 5, United States Code.
- (4) EXPIRATION.—Section 14 of the Federal Advisory Committee Act (5 U.S.C. App.) shall not apply to the Climate Service Advisory Committee.
- (g) REPEAL.—The National Climate Program Act (15 U.S.C. 2901 et seq.) is repealed.
- (h) ESTABLISHMENT OF REGIONAL INTEGRATED SCIENCES AND ASSESSMENTS TEAMS.—
- (1) IN GENERAL.—In maintaining the network of Regional Integrated Sciences and Assessments (RISA) Teams under subsection (e)(3)(C), the Under Secretary shall utilize a competitive, peer-reviewed selection process. Teams shall conduct applied regional climate research and projects to address the needs of local and regional decisionmakers for information and tools to develop adaptation and response plans to climate variability and change. The awards shall be administered through a cooperative agreement between the National Oceanic and Atmospheric Administration and the RISA Team. Each award shall be for a period of five years.
- (2) RISA TEAMS.—Teams shall be composed of multi-institutional partnerships whose individual members may include—
- (A) institutions of higher education, as defined in section 101(a) of the Higher Education Act of 1965 (20 U.S.C. 1001(a));
- (B) minority serving institutions, as defined in section 371(a) of the Higher Education Act of 1965; and
- (C) nongovernmental research organizations, Federal agencies, State and local agencies, tribal organizations, and for-profit
- (3) CONSIDERATIONS.—In making awards under this subsection, the Under Secretary shall consider—
- (A) the overall geographic distribution of RISA Teams and existing gaps in applied research to support local and regional decisionmakers;
- (B) the team's ability to contribute to the National Oceanic and Atmospheric Administration's efforts to deliver climate services in the region; and
- (C) the team's proposal to integrate social and physical sciences research to address the effects of climate variability and change on the ecology, economy, infrastructure, and communities in the region
- (i) Survey of Need for Climate Services.—
- (1) IN GENERAL.—The Under Secretary shall provide a report to Congress within 9 months after the date of enactment of this Act that compiles information on the current climate products being delivered by the National Oceanic and Atmospheric Administration and its partner organizations to users and stakeholders and on the needs of users and stakeholders for new climate products and services.
- (2) CONTENTS OF REPORT.—The report shall identify— $\,$
- (A) specific user groups and stakeholders that currently are served by the National

- Oceanic and Atmospheric Administration and its partner organizations;
- (B) the type of climate products and services currently delivered to specific user groups and stakeholders and the specific National Oceanic and Atmospheric Administration office or partner organization that delivers these products and services;
- (C) potential user groups and stakeholders that may be served by expanding climate products and services; and
- (D) specific needs for new climate products and services identified by user groups and stakeholders.
- (3) CONSULTATION.—The Under Secretary shall consult with the Climate Service Advisory Committee in the preparation of this report.
 - (j) IMPLEMENTATION PLAN.—
- (1) In General.—The Under Secretary shall prepare a plan for creating a Climate Service Program in the National Oceanic and Atmospheric Administration and delivering climate products and services to the National Oceanic and Atmospheric Administration users and stakeholders. The plan shall be submitted to the President and the Congress within 1 year after the date of enactment of this Act.
- (2) DRAFT PLAN.—Prior to the submission of the final plan, the Under Secretary shall publish a draft plan in the Federal Register with a public comment period of at least 30 days.
 - (3) CONTENTS.—The plan shall—
- (A) identify the current gaps in climate services and outline the process and resources the National Oceanic and Atmospheric Administration will use to fill these gaps:
- (B) describe the roles of the National Oceanic and Atmospheric Administration line offices and the National Oceanic and Atmospheric Administration partner organizations in the development and delivery of climate products and services;
- (C) describe the development and implementation of quality assurance and control mechanisms for climate products and services delivered by the National Oceanic and Atmospheric Administration and its partner organizations;
- (D) identify the mechanisms and opportunities for determining user needs and engaging in a two-way dialogue with users that will inform climate product and service development and delivery of authoritative, timely, and useful information on climate variability and change and the effects on local, State, regional, national, and global scales:
- (E) identify new responsibilities or tasks to be undertaken by existing National Oceanic and Atmospheric Administration line offices and partner organizations:
- (F) identify new infrastructure, equipment, personnel, or other resources needed to implement the proposed plan; and
- (G) include responses to the comments received during the public comment period.
- (4) CONTINUITY OF SERVICE.—During the development of the implementation plan, the public comment period, and final plan, the National Oceanic and Atmospheric Administration shall continue to provide climate services to the user community.
- (5) CONSULTATION.—In developing the plan, the Under Secretary shall consult with user groups and stakeholders, State Climate Offices, Regional Climate Centers, other Federal agencies, the Climate Service Advisory Committee, and Congress.
- (6) COORDINATION WITH INTERAGENCY DEVELOPMENT OF A NATIONAL CLIMATE SERVICE.—In preparing the plan required under this subsection, the Under Secretary shall consult with the Director of the Office of Science and Technology Policy to ensure that the pro-

- gram developed by the Agency will serve the needs of a National Climate Service.
- (k) SUMMER INSTITUTES PROGRAM AT THE REGIONAL CLIMATE CENTERS.—
 - (1) Definitions.—In this subsection:
- (A) SUMMER INSTITUTE.—The term "summer institute" means an institute, operated during the summer, that—
- (i) is hosted by a Regional Climate Center or an eligible partner;
- (ii) is operated for a period of not less than 2 weeks; and
- (iii) provides direct interaction of middle school and high school teacher and undergraduate student participants with personnel of the Regional Climate Centers or eligible partners who have scientific expertise in weather and climate.
- (B) ELIGIBLE PARTNER.—The term "eligible partner" means— $\,$
- (i) the science, engineering, or mathematics department at an institution of higher education; or
- (ii) a nonprofit entity with expertise in providing educational enrichment experiences for students.
- (2) Summer institutes program authorized —
- (A) IN GENERAL.—The Under Secretary shall establish a summer institutes program, to be conducted in cooperation with the Regional Climate Centers, which may include an eligible partner. The purpose of the program is to provide training and professional enrichment by providing opportunities for interaction between participants and climate scientists in a research and operational setting to—
- (i) enable middle school and high school teachers to integrate weather and climate sciences into their curricula; and
- (ii) encourage undergraduate students to pursue further study and careers in weather and climate sciences.
- (B) REQUIRED ACTIVITIES.—Funds authorized under this subsection shall be used for—
- (i) providing educational opportunities for middle school and high school teachers and undergraduate students not achievable inside the classroom;
- (ii) exposing such teachers and students to researchers, scientists, or engineers who can demonstrate their daily activities to the teachers and students;
- (iii) exposing teachers and students to scientific methods in a research discovery setting; and
- (iv) assisting teachers with curriculum development in the areas of weather and climate science.
- (3) PRIORITY.—The Under Secretary shall ensure that each summer institute program authorized under paragraph (2) includes students from groups underrepresented in the fields of science, technology, engineering, and mathematics teaching, including women and members of minority groups.
- (4) REPORT TO CONGRESS.—The Under Secretary shall submit to Congress a biennial report on the activities conducted under this subsection, including the number of participants and the new curricula developed in atmospheric and climate sciences.
- (1) CLEARINGHOUSE OF FEDERAL CLIMATE SERVICE PRODUCTS AND LINKS TO FEDERAL AGENCIES PROVIDING CLIMATE SERVICES.—
- (1) IN GENERAL.—The Under Secretary shall establish and maintain a clearinghouse to inform State, local, and tribal governments and the public about the information and services available to—
- (A) assess the impacts of climate variability and change at different geographic scales:
- (B) characterize and forecast climate variability and change for specific regions, resources, and economic sectors; and

- (C) develop and implement adaptation strategies to reduce vulnerabilities to climate variability and change.
- (2) OTHER RESOURCES.—The clearinghouse shall include hyperlinks to Internet sites that describe the activities, information, and resources of—
 - (A) the Federal Government;
 - (B) State and local governments;
 - (C) the private sector;
- (D) nongovernmental and nonprofit entities and organizations; and
 - (E) international organizations.
- (m) Financial Burden.—Nothing in this section shall be construed as authorizing the National Climate Service or the Climate Service Program at the National Oceanic and Atmospheric Administration to require State, tribal, or local governments to develop adaptation or response plans or to take any other action in response to variations in climate that may result in an increased financial burden to such governments.

SEC. 453. STATE PROGRAMS TO BUILD RESIL-IENCE TO CLIMATE CHANGE IM-PACTS.

- (a) DEFINITIONS.—For purposes of this section:
- (1) ALLOWANCE.—The term "allowance" means an emission allowance established under section 721 of the Clean Air Act (as added by section 311 of this Act).
- (2) INDIAN TRIBE.—The term "Indian tribe" has the meaning given the term in section 4 of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450b).
- (3) VINTAGE YEAR.—The term "vintage year" has the meaning given that term under section 700 of the Clean Air Act (as added by section 312 of this Act).
- (b) REGULATIONS; COORDINATION.—Not later than 2 years after the date of enactment of this Act, the Administrator, or such Federal agency head or heads as the President may designate, shall promulgate regulations to implement the requirements of this section. If the President designates more than 1 Federal agency to implement this section, the President shall require such agencies to establish a memorandum of understanding providing for coordination of rulemaking and other implementing activities, in accordance with the requirements of this section.
 - (c) DISTRIBUTION OF ALLOWANCES.—
- (1) In GENERAL.—Not later than September 30 of each of calendar years 2011 through 2049, the Administrator shall distribute, in accordance with this section, allowances allocated for the following vintage year pursuant to section 782(1) of the Clean Air Act (as added by section 321 of this Act). The Administrator shall reserve 1 percent of such allowances for distribution to Indian tribes in accordance with subsection (d). The remainder of such allowances shall be distributed ratably among the States based on the product of—
- (A) each State's population; and
- (B) each State's allocation factor as determined under paragraph (2).
- (2) STATE ALLOCATION FACTORS.—
- (A) IN GENERAL.—Except as provided in subparagraph (B), the allocation factor for a State shall be the quotient of—
- (i) the per capita income of all individuals in the United States, divided by
- (ii) the per capita income of all individuals in such State.
- (B) LIMITATION.—If the allocation factor for a State as calculated under subparagraph (A) would exceed 1.2, then the allocation factor for such State shall be 1.2. If the allocation factor for a State as calculated under subparagraph (A) would be less than 0.8, then the allocation factor for such State shall be 0.8.
- (C) PER CAPITA INCOME.—For purposes of this paragraph, per capita income shall be—

- (i) determined at 2-year intervals; and (ii) subject to subparagraph (D), equal to the average of the annual per capita incomes
- the average of the annual per capita incomes for the most recent period of 3 consecutive years for which satisfactory data are available from the Department of Commerce at the time such determination is made.
- (D) REVENUE DIRECTLY RESULTING FROM A PRESIDENTIALLY DECLARED MAJOR DISASTER. For purposes of this paragraph, per capita income from one or more of the following sources shall be reduced or excluded if the Secretary of Commerce (in consultation with the Administrator and the secretaries or administrators of the departments or agencies involved) determines that the income accrues to persons as the result of a Major Disaster (as declared by the President of the United States) and if the Secretary finds that the inclusion of one or more of these income sources, in whole or in part, results in a transitory, rather than a sustainable, increase in a State's per capita income level relative to the national average:
- (i) Property and casualty insurance (including homeowners and renters insurance).
- (ii) The National Flood Insurance Program of the Federal Emergency Management Agency.
- (iii) The Individual and Family Grants Program of the Federal Emergency Management Agency.
- (iv) The Disaster Housing Program of the Federal Emergency Management Agency.
- (v) The Community Development Block Grant Program of the Department of Housing and Urban Development.
- (vi) The Disaster Unemployment Assistance Program of the Department of Labor
- (vii) Any other source determined appropriate by the Administrator.
- (d) DISTRIBUTION TO INDIAN TRIBES.—The Administrator, or such Federal agency head or heads as the President may designate, shall promulgate regulations establishing a program to distribute allowances on a competitive basis to Indian tribes, in accordance with the requirements of this section. Such allowances shall be used exclusively in accordance with the requirements of subsection (e). Beginning with vintage year 2015, Indian tribes with a tribal adaptation plan approved pursuant to subsection (f) shall be given priority in selection of programs or projects for receipt of emission allowances under this subsection.
 - (e) USE OF ALLOWANCES.—
- (1) IN GENERAL.—States and Indian tribes shall use allowances distributed under this section exclusively for the implementation of projects, programs, or measures to build resilience to the impacts of climate change, including—
- (A) extreme weather events such as flooding and tropical evelones:
- (B) more frequent heavy precipitation events:
- (C) water scarcity and adverse impacts on water quality;
- (D) stronger and longer heat waves;
- (E) more frequent and severe droughts;
- (F) rises in sea level;
- (G) ecosystem disruption;
- (H) increased air pollution; and
- (I) effects on public health.
- (2) PRIORITY IN PROJECTS TO REDUCE FLOOD EVENTS.—When implementing any project, program, or measure supported under this section and designed to reduce flood events, a State or Indian tribe should consider prioritizing projects that seek to—
- (A) mitigate the destructive impacts of climate-related increases in the duration, frequency, or magnitude of rainfall or runoff, including snowmelt runoff, as well as hurricanes;
- (B) improve flood protection for densely populated urban areas; and

- (C) mitigate the destructive impact of ocean-related climate change effects, including effects on bays, estuaries, populated barrier islands and other ocean-related features, through a variety of means and measures, including the construction of jetties, levies, and other coastal structures in densely populated coastal areas impacted by climate change.
- (3) STATE AND TRIBAL ADAPTATION PLANS.— Upon approval of a State or tribal climate adaptation plan under subsection (f), allowances received by a State under this section shall be used in accordance with such plan.
- (4) SUPPLEMENT, NOT SUPPLANT.—It is the intent of the Congress that allowances distributed to carry out this section should be used to supplement, and not replace, existing sources of funding used to build resilience to the impacts of climate change identified in paragraph (1).
- (5) RESEARCH ON HURRICANES.—The authorized uses of allowances under this section shall include establishment of projects or programs to conduct research and monitoring on the effect of ongoing climate change on the frequency and intensity of hurricanes.
- (f) STATE AND TRIBAL CLIMATE ADAPTATION PLANS.—
- (1) In general.—The regulations promulgated pursuant to subsection (b) shall include requirements for submission and approval of State or tribal climate adaptation plans under this section. Beginning with vintage year 2015, distribution of allowances to a State pursuant to this section shall be contingent on approval of a State climate adaptation plan for such State that meets the requirements of such regulations. Requirements for tribal climate adaptation plans may vary from those of State adaptation plans to the extent necessary to account for the special circumstances of Indian tribes.
- (2) REQUIREMENTS.—Regulations promulgated under this section shall require, at minimum, that State and tribal climate adaptation plans—
- (A) assess and prioritize the State's or Indian tribe's vulnerability to a broad range of impacts of climate change, based on the best available science:
- (B) include an assessment of potential for carbon reduction through changes to land management policies (including enhancement or protection of forest carbon sinks);
- (C) identify and prioritize specific cost-effective projects, programs, and measures to build resilience to current and predicted impacts of climate change;
- (D) ensure that the State or Indian tribe fully considers and undertakes, to the maximum extent practicable, initiatives that—
- (i) protect or enhance natural ecosystem functions, including protection, maintenance, or restoration of natural infrastructure such as wetlands, reefs, and barrier islands to buffer communities from floodwaters or storms, watershed protection to maintain water quality and groundwater recharge, or floodplain restoration to improve natural flood control capacity; or
- (ii) use non-structural approaches including practices that utilize, enhance, or mimic the natural hydrologic cycle processes of infiltration, evapotranspiration, and reuse;
- (E) be revised and resubmitted for approval not less frequently than every 5 years; and
- (F) be consistent with Federal conservation and environmental laws and, to the maximum extent practicable, avoid environmental degradation.
- (3) COORDINATION WITH PRIOR PLANNING EFFORTS.—In implementing this subsection, the Administrator, or such Federal agency head or heads as the President may designate, shall—

- (A) draw upon lessons learned and best practices from preexisting State and tribal climate adaptation planning efforts;
- (B) seek to avoid duplication of such efforts; and
- (C) ensure that the plans developed under this section reflect and are fully consistent with State natural resources adaptation plans developed under section 479 of this Act.
- (g) REPORTING.—Each State or Indian tribe receiving allowances under this section shall submit to the Administrator, or such Federal agency head or heads as the President may designate, within 12 months after each receipt of such allowances and once every 2 years thereafter until the value of any allowances received under this section has been fully expended, a report that—
- (1) provides a full accounting for the State's or Indian tribe's use of allowances distributed under this section, including a description of the projects, programs, or measures supported using such allowances:
- (2) includes a report prepared by an independent third party, in accordance with such regulations as are promulgated by the Administrator or such other Federal agency head or heads as the President may designate, evaluating the performance of the projects, programs, or measures supported under this section: and
- (3) identifies any use by the State or Indian tribe of allowances distributed under this section for the reduction of flood and storm damage and the effects of climate change on water and flood protection infrastructure.
- (h) Enforcement.—If the Administrator, or such Federal agency head or heads as the President may designate, determines that a State or Indian tribe is not in compliance with this section, the Administrator or such other agency head may withhold a quantity of the allowances equal to up to twice the quantity of allowances that the State or Indian tribe failed to use in accordance with the requirements of this section, that such State or Indian tribe would otherwise be eligible to receive under this section in 1 or more later years. Allowances withheld pursuant to this subsection shall be distributed among the remaining States or Indian tribes ratably in accordance with the formula in subsection (c) in the case of allowances withheld from a State, or in accordance with subsection (d) in the case of allowances withheld from an Indian tribe.

Subpart B—Public Health and Climate Change

SEC. 461. SENSE OF CONGRESS ON PUBLIC HEALTH AND CLIMATE CHANGE.

- It is the sense of the Congress that the Federal Government, in cooperation with international, State, tribal, and local governments, concerned public and private organizations, and citizens, should use all practicable means and measures—
- (1) to assist the efforts of public health and health care professionals, first responders, States, tribes, municipalities, and local communities to incorporate measures to prepare health systems to respond to the impacts of climate change;
 - (2) to ensure—
- (A) that the Nation's health professionals have sufficient information to prepare for and respond to the adverse health impacts of climate change:
- (B) the utility and value of scientific research in advancing understanding of—
- (i) the health impacts of climate change; and
- (ii) strategies to prepare for and respond to the health impacts of climate change;
- (C) the identification of communities vulnerable to the health effects of climate change and the development of strategic re-

- sponse plans to be carried out by health professionals for those communities;
- (D) the improvement of health status and health equity through efforts to prepare for and respond to climate change; and
- (E) the inclusion of health policy in the development of climate change responses;
- (3) to encourage further research, interdisciplinary partnership, and collaboration among stakeholders in order to—
- (A) understand and monitor the health impacts of climate change; and
- (B) improve public health knowledge and response strategies to climate change;
- (4) to enhance preparedness activities, and public health infrastructure, relating to climate change and health:
- (5) to encourage each and every American to learn about the impacts of climate change on health; and
- (6) to assist the efforts of developing nations to incorporate measures to prepare health systems to respond to the impacts of climate change.

SEC. 462. RELATIONSHIP TO OTHER LAWS

Nothing in this subpart in any manner limits the authority provided to or responsibility conferred on any Federal department or agency by any provision of any law (including regulations) or authorizes any violation of any provision of any law (including regulations), including any health, energy, environmental, transportation, or any other law or regulation.

SEC. 463. NATIONAL STRATEGIC ACTION PLAN.

- (a) REQUIREMENT.—
- (1) IN GENERAL.—The Secretary of Health and Human Services, within 2 years after the date of the enactment of this Act, on the basis of the best available science, and in consultation pursuant to paragraph (2), shall publish a strategic action plan to assist health professionals in preparing for and responding to the impacts of climate change on public health in the United States and other nations, particularly developing nations.
- (2) CONSULTATION.—In developing or making any revision to the national strategic action plan, the Secretary shall—
- (A) consult with the Director of the Centers for Disease Control and Prevention, the Administrator of the Environmental Protection Agency, the Director of the National Institutes of Health, the Secretary of Energy, other appropriate Federal agencies, Indian tribes, State and local governments, public health organizations, scientists, and other interested stakeholders; and
- (B) provide opportunity for public input.
- (b) Contents.—
- (1) IN GENERAL.—The Secretary, acting through the Director of the Centers for Disease Control and Prevention and other appropriate Federal agencies, shall assist health professionals in preparing for and responding effectively and efficiently to the health effects of climate change through measures including—
- (A) developing, improving, integrating, and maintaining domestic and international disease surveillance systems and monitoring capacity to respond to health-related effects of climate change, including on topics addressing—
- (i) water, food, and vector borne infectious diseases and climate change;
- (ii) pulmonary effects, including responses to aeroallergens;
- (iii) cardiovascular effects, including impacts of temperature extremes;
- (iv) air pollution health effects, including heightened sensitivity to air pollution;
 - (v) hazardous algal blooms;
- (vi) mental and behavioral health impacts of climate change;
- (vii) the health of refugees, displaced persons, and vulnerable communities;

- (viii) the implications for communities vulnerable to health effects of climate change, as well as strategies for responding to climate change within these communities; and
- (ix) local and community-based health interventions for climate-related health impacts;
- (B) creating tools for predicting and monitoring the public health effects of climate change on the international, national, regional, State, and local levels, and providing technical support to assist in their implementation;
- (C) developing public health communications strategies and interventions for extreme weather events and disaster response situations;
- (D) identifying and prioritizing communities and populations vulnerable to the health effects of climate change, and determining actions and communication strategies that should be taken to inform and protect these communities and populations from the health effects of climate change;
- (E) developing health communication, public education, and outreach programs aimed at public health and health care professionals, as well as the general public, to promote preparedness and response strategies relating to climate change and public health, including the identification of greenhouse gas reduction behaviors that are health-promoting; and
- (F) developing academic and regional centers of excellence devoted to—
- (i) researching relationships between climate change and health;
- (ii) expanding and training the public health workforce to strengthen the capacity of such workforce to respond to and prepare for the health effects of climate change:
- (iii) creating and supporting academic fellowships focusing on the health effects of climate change; and
- (iv) training senior health ministry officials from developing nations to strengthen the capacity of such nations to—
- (I) prepare for and respond to the health effects of climate change; and
- (II) build an international network of public health professionals with the necessary climate change knowledge base;
- (G) using techniques, including health impact assessments, to assess various climate change public health preparedness and response strategies on international, national, State, regional, tribal, and local levels, and make recommendations as to those strategies that best protect the public health;
- (H)(i) assisting in the development, implementation, and support of State, regional, tribal, and local preparedness, communication, and response plans (including with respect to the health departments of such entities) to anticipate and reduce the health threats of climate change; and
- (ii) pursuing collaborative efforts to develop, integrate, and implement such plans;
- (I) creating a program to advance research as it relates to the effects of climate change on public health across Federal agencies, including research to—
- (i) identify and assess climate change health effects preparedness and response strategies;
- (ii) prioritize critical public health infrastructure projects related to potential climate change impacts that affect public health; and
- (iii) coordinate preparedness for climate change health impacts, including the development of modeling and forecasting tools;
- (J) providing technical assistance for the development, implementation, and support of preparedness and response plans to anticipate and reduce the health threats of climate change in developing nations; and

- (K) carrying out other activities determined appropriate by the Secretary to plan for and respond to the impacts of climate change on public health.
- (c) REVISION.—The Secretary shall revise the national strategic action plan not later than July 1, 2014, and every 4 years thereafter, to reflect new information collected pursuant to implementation of the national strategic action plan and otherwise, including information on—
- (1) the status of critical environmental health parameters and related human health impacts;
- (2) the impacts of climate change on public health; and
- (3) advances in the development of strategies for preparing for and responding to the impacts of climate change on public health.
 - (d) Implementation.—
- (1) IMPLEMENTATION THROUGH HHS.—The Secretary shall exercise the Secretary's authority under this subpart and other provisions of Federal law to achieve the goals and measures of the national strategic action plan.
- (2) OTHER PUBLIC HEALTH PROGRAMS AND INITIATIVES.—The Secretary and Federal officials of other relevant Federal agencies shall administer public health programs and initiatives authorized by provisions of law other than this subpart, subject to the requirements of such statutes, in a manner designed to achieve the goals of the national strategic action plan.
- (3) CDC.—In furtherance of the national strategic action plan, the Secretary, acting through the Director of the Centers for Disease Control and Prevention and the head of any other appropriate Federal agency, shall—
- (A) conduct scientific research to assist health professionals in preparing for and responding to the impacts of climate change on public health; and
 - (B) provide funding for-
- (i) research on the health effects of climate change; and
- (ii) preparedness planning on the international, national, State, tribal, regional, and local levels to respond to or reduce the burden of health effects of climate change; and
- (C) carry out other activities determined appropriate by the Director or the head of such agency to prepare for and respond to the impacts of climate change on public health.

SEC. 464. ADVISORY BOARD.

- (a) ESTABLISHMENT.—The Secretary shall establish a permanent science advisory board comprised of not less than 10 and not more than 20 members.
- (b) APPOINTMENT OF MEMBERS.—The Secretary shall appoint the members of the science advisory board from among individuals—
- (1) who have expertise in public health and human services, climate change, and other relevant disciplines; and
- (2) at least $\frac{1}{2}$ of whom are recommended by the President of the National Academy of Sciences.
- (c) Functions.—The science advisory board shall—
- (1) provide scientific and technical advice and recommendations to the Secretary on the domestic and international impacts of climate change on public health, populations and regions particularly vulnerable to the effects of climate change, and strategies and mechanisms to prepare for and respond to the impacts of climate change on public health; and
- (2) advise the Secretary regarding the best science available for purposes of issuing the national strategic action plan.

SEC. 465, REPORTS.

- (a) NEEDS ASSESSMENT.—
- (1) IN GENERAL.—The Secretary shall seek to enter into, by not later than 6 months after the date of the enactment of this Act, an agreement with the National Research Council and the Institute of Medicine to complete a report that—
- (A) assesses the needs for health professionals to prepare for and respond to climate change impacts on public health; and
- (B) recommends programs to meet those needs.
- (2) SUBMISSION.—The agreement under paragraph (1) shall require the completed report to be submitted to the Congress and the Secretary and made publicly available not later than 1 year after the date of the agreement.
- (b) CLIMATE CHANGE HEALTH PROTECTION AND PROMOTION REPORTS.—
- (1) IN GENERAL.—The Secretary, in consultation with the advisory board established under section 464, shall ensure the issuance of reports to aid health professionals in preparing for and responding to the adverse health effects of climate change that—
- (A) review scientific developments on health impacts of climate change; and
- (B) recommend changes to the national strategic action plan.
- (2) SUBMISSION.—The Secretary shall submit the reports required by paragraph (1) to the Congress and make such reports publicly available not later than July 1, 2013, and every 4 years thereafter.

SEC. 466. DEFINITIONS.

- In this subpart:
- (1) HEALTH IMPACT ASSESSMENT.—The term "health impact assessment" means a combination of procedures, methods, and tools by which a policy, program, or project may be judged as to its potential effects on the health of a population, and the distribution of those effects within the population.
- (2) NATIONAL STRATEGIC ACTION PLAN.—The term "national strategic action plan" means the plan issued and revised under section 463.
- (3) SECRETARY.—Unless otherwise specified, the term "Secretary" means the Secretary of Health and Human Services.

SEC. 467. CLIMATE CHANGE HEALTH PROTECTION AND PROMOTION FUND.

- (a) ESTABLISHMENT OF FUND.—Subject to subtitle F of title IV, there is hereby established in the Treasury a separate account that shall be known as the Climate Change Health Protection and Promotion Fund.
- (b) AVAILABILITY OF AMOUNTS.—Subject to Subtitle F of title IV, all amounts deposited into the Climate Change Health Protection and Promotion Fund shall be available to the Secretary to carry out this subpart subject to further appropriation.
- (c) DISTRIBUTION OF FUNDS BY HHS.—In carrying out this subpart, the Secretary may make funds deposited in the Climate Change Health Protection and Promotion Fund available to—
- (1) other departments, agencies, and offices of the Federal Government:
- (2) foreign, State, tribal, and local governments; and
- (3) such other entities as the Secretary determines appropriate.
- (d) SUPPLEMENT, NOT REPLACE.—It is the intent of Congress that funds made available to carry out this subpart should be used to supplement, and not replace, existing sources of funding for public health.

Subpart C—Natural Resource Adaptation SEC. 471. PURPOSES.

The purposes of this subpart are to—

(1) establish an integrated Federal program to protect, restore, and conserve the Nation's natural resources in response to the

- threats of climate change and ocean acidification; and
- (2) provide financial support and incentives for programs, strategies, and activities that protect, restore, and conserve the Nation's natural resources in response to the threats of climate change and ocean acidification.

SEC. 472. NATURAL RESOURCES CLIMATE CHANGE ADAPTATION POLICY.

It is the policy of the Federal Government, in cooperation with State and local governments, Indian tribes, and other interested stakeholders to use all practicable means and measures to protect, restore, and conserve natural resources to enable them to become more resilient, adapt to, and withstand the impacts of climate change and ocean acidification.

SEC. 473. DEFINITIONS.

In this subpart:

- (1) COASTAL STATE.—The term "coastal State" has the meaning given the term in section 304 of the Coastal Zone Management Act of 1972 (16 U.S.C. 1453).
- (2) CORRIDORS.—The term "corridors" means areas that provide connectivity, over different time scales (including seasonal or longer), of habitat or potential habitat and that facilitate the ability of terrestrial, marine, estuarine, and freshwater fish, wildlife, or plants to move within a landscape as needed for migration, gene flow, or dispersal, or in response to the impacts of climate change and ocean acidification or other impacts.
- (3) ECOLOGICAL PROCESSES.—The term "ecological processes" means biological, chemical, or physical interaction between the biotic and abiotic components of an ecosystem and includes—
 - (A) nutrient cycling;
 - (B) pollination;
 - (C) predator-prey relationships;
 - (D) soil formation;
 - (E) gene flow;
 - (F) disease epizootiology;
 - (G) larval dispersal and settlement;
- (H) hydrological cycling;
- (I) decomposition; and
- (J) disturbance regimes such as fire and flooding.
- (4) HABITAT.—The term "habitat" means the physical, chemical, and biological properties that are used by fish, wildlife, or plants for growth, reproduction, survival, food, water, and cover, on a tract of land, in a body of water, or in an area or region.
- (5) INDIAN TRIBE.—The term "Indian tribe" has the meaning given the term in section 4 of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450b).
- (6) NATURAL RESOURCES.—The term "natural resources" means the terrestrial, freshwater, estuarine, and marine fish, wildlife, plants, land, water, habitats, and ecosystems of the United States.
- (7) NATURAL RESOURCES ADAPTATION.—The term "natural resources adaptation" means the protection, restoration, and conservation of natural resources to enable them to become more resilient, adapt to, and withstand the impacts of climate change and ocean acidification.
- (8) RESILIENCE.—Each of the terms "resilience" and "resilient" means the ability to resist or recover from disturbance and preserve diversity, productivity, and sustainability.
 - (9) STATE.—The term "State" means-
 - $(A) \ a \ State \ of \ the \ United \ States;$
 - (B) the District of Columbia; and
- (C) the Commonwealth of Puerto Rico, Guam, the United States Virgin Islands, the Northern Mariana Islands, and American Samoa.

SEC. 474. COUNCIL ON ENVIRONMENTAL QUAL-ITY.

The Chair of the Council on Environmental Quality shall—

- (1) advise the President on implementation and development of—
- (A) a Natural Resources Climate Change Adaptation Strategy required under section 476; and
- (B) Federal natural resource agency adaptation plans required under section 478;
- (2) serve as the Chair of the Natural Resources Climate Change Adaptation Panel established under section 475; and
- (3) coordinate Federal agency strategies, plans, programs, and activities related to protecting, restoring, and maintaining natural resources to become more resilient, adapt to, and withstand the impacts of climate change and ocean acidification.

SEC. 475. NATURAL RESOURCES CLIMATE CHANGE ADAPTATION PANEL.

- (a) ESTABLISHMENT.—Not later than 90 days after the date of the enactment of this subpart, the President shall establish a Natural Resources Climate Change Adaptation Panel, consisting of—
- (1) the head, or their designee, of each of—
 (A) the National Oceanic and Atmospheric Administration:
- (B) the Forest Service:
- (C) the National Park Service;
- (D) the United States Fish and Wildlife Service:
- (E) the Bureau of Land Management;
- (F) the United States Geological Survey;
- (G) the Bureau of Reclamation;
- (H) the Bureau of Indian Affairs;
- (I) the Environmental Protection Agency; and
 - (J) the Army Corps of Engineers;
- (2) the Chair of the Council on Environmental Quality; and
- (3) the heads of such other Federal agencies or departments with jurisdiction over natural resources of the United States, as determined by the President.
- (b) FUNCTIONS.—The Panel shall serve as a forum for interagency consultation on and the coordination of the development and implementation of a national Natural Resources Climate Change Adaptation Strategy required under section 476.
- (c) CHAIR.—The Chair of the Council on Environmental Quality shall serve as the Chair of the Panel.

SEC. 476. NATURAL RESOURCES CLIMATE CHANGE ADAPTATION STRATEGY.

- (a) IN GENERAL.—Not later than one year after the date of the enactment of this subpart, the President, through the Natural Resources Climate Change Adaptation Panel established under section 475, shall develop a Natural Resources Climate Change Adaptation Strategy to protect, restore, and conserve natural resources to enable them to become more resilient, adapt to, and withstand the impacts of climate change and ocean acidification and to identify opportunities to mitigate those impacts.
- (b) DEVELOPMENT AND REVISION.—In developing and revising the Strategy, the Panel shall—
- (1) base the strategy on the best available science;
- (2) develop the strategy in close cooperation with States and Indian tribes;
- (3) coordinate with other Federal agencies as appropriate;
- (4) consult with local governments, conservation organizations, scientists, and other interested stakeholders:
- (5) provide public notice and opportunity for comment; and
- (6) review and revise the Strategy every 5 years to incorporate new information regarding the impacts of climate change and ocean acidification on natural resources and ad-

- vances in the development of strategies for becoming more resilient and adapting to those impacts.
- (c) CONTENTS.—The National Resources Adaptation Strategy shall include—
- (1) an assessment of the vulnerability of natural resources to climate change and ocean acidification, including the shortterm, medium-term, long-term, cumulative, and synergistic impacts:
- (2) a description of current research, observation, and monitoring activities at the Federal, State, tribal, and local level related to the impacts of climate change and ocean acidification on natural resources, as well as identification of research and data needs and priorities;
- (3) identification of natural resources that are likely to have the greatest need for protection, restoration, and conservation because of the adverse effects of climate change and ocean acidification;
- (4) specific protocols for integrating climate change and ocean acidification adaptation strategies and activities into the conservation and management of natural resources by Federal departments and agencies to ensure consistency across agency jurisdictions and resources;
- (5) specific actions that Federal departments and agencies shall take to protect, conserve, and restore natural resources to become more resilient, adapt to, and withstand the impacts of climate change and ocean acidification, including a timeline to implement those actions;
- (6) specific mechanisms for ensuring communication and coordination among Federal departments and agencies, and between Federal departments and agencies and State natural resource agencies, United States territories, Indian tribes, private landowners, conservation organizations, and other nations that share jurisdiction over natural resources with the United States;
- (7) specific actions to develop and implement consistent natural resources inventory and monitoring protocols through interagency coordination and collaboration; and
- (8) a process for guiding the development of detailed agency- and department-specific adaptation plans required under section 478 to address the impacts of climate change and ocean acidification on the natural resources in the jurisdiction of each agency.
- (d) IMPLEMENTATION.—Consistent with its authorities under other laws and with Federal trust responsibilities with respect to Indian lands, each Federal department or agency with representation on the National Resources Climate Change Adaptation Panel shall consider the impacts of climate change and ocean acidification and integrate the elements of the strategy into agency plans, environmental reviews, programs, and activities related to the conservation, restoration, and management of natural resources.

SEC. 477. NATURAL RESOURCES ADAPTATION SCIENCE AND INFORMATION.

- (a) COORDINATION.—Not later than 90 days after the date of the enactment of this subpart, the Secretary of Commerce, acting through the Administrator of the National Oceanic and Atmospheric Administration, and the Secretary of the Interior, acting through the Director of the United States Geological Survey, shall establish a coordinated process for developing and providing science and information needed to assess and address the impacts of climate change and ocean acidification on natural resources. The process shall be led by the National Climate Change and Wildlife Science Center established within the United States Geological Survey under subsection (d) and the National Climate Service of the National Oceanic and Atmospheric Administration.
- (b) FUNCTIONS.—The Secretaries shall ensure that such process avoids duplication

- and that the National Oceanic and Atmospheric Administration and the United States Geological Survey shall—
- (1) provide technical assistance to Federal departments and agencies, State and local governments, Indian tribes, and interested private landowners in their efforts to assess and address the impacts of climate change and ocean acidification on natural resources;
- (2) conduct and sponsor research and provide Federal departments and agencies, State and local governments, Indian tribes, and interested private landowners with research products, decision and monitoring tools and information, to develop strategies for assisting natural resources to become more resilient, adapt to, and withstand the impacts of climate change and ocean acidification; and
- (3) assist Federal departments and agencies in the development of the adaptation plans required under section 478.
- (c) SURVEY.—Not later than one year after the date of enactment of this subpart and every 5 years thereafter, the Secretary of Commerce and the Secretary of the Interior shall undertake a climate change and ocean acidification impact survey that—
- (1) identifies natural resources considered likely to be adversely affected by climate change and ocean acidification;
- (2) includes baseline monitoring and ongoing trend analysis:
- (3) uses a stakeholder process to identify and prioritize needed monitoring and research that is of greatest relevance to the ongoing needs of natural resource managers to address the impacts of climate change and ocean acidification; and
- (4) identifies decision tools necessary to develop strategies for assisting natural resources to become more resilient and adapt to and withstand the impacts of climate change and ocean acidification.
- (d) NATIONAL CLIMATE CHANGE AND WILD-LIFE SCIENCE CENTER.— (1) ESTABLISHMENT.—The Secretary of the
- (1) ESTABLISHMENT.—The Secretary of the Interior shall establish the National Climate Change and Wildlife Science Center within the United States Geological Survey.
- (2) FUNCTIONS.—The Center shall, in collaboration with Federal and State natural resources agencies and departments, Indian tribes, universities, and other partner organizations—
- (A) assess and synthesize current physical and biological knowledge and prioritize scientific gaps in such knowledge in order to forecast the ecological impacts of climate change on fish and wildlife at the ecosystem, habitat, community, population, and species levels:
- (B) develop and improve tools to identify, evaluate, and, where appropriate, link scientific approaches and models for forecasting the impacts of climate change and adaptation on fish, wildlife, plants, and their habitats, including monitoring, predictive models, vulnerability analyses, risk assessments, and decision support systems to help managers make informed decisions;
- (C) develop and evaluate tools to adaptively manage and monitor the effects of climate change on fish and wildlife at national, regional, and local scales; and
- (D) develop capacities for sharing standardized data and the synthesis of such data.
 - (e) SCIENCE ADVISORY BOARD.—
- (1) ESTABLISHMENT.—Not later than 180 days after the date of enactment of this subpart, the Secretary of Commerce and the Secretary of the Interior shall establish and appoint the members of a Science Advisory Board, to be comprised of not fewer than 10 and not more than 20 members—

- (A) who have expertise in fish, wildlife, plant, aquatic, and coastal and marine biology, ecology, climate change, ocean acidification, and other relevant scientific disciplines;
- (B) who represent a balanced membership among Federal, State, Indian tribes, and local representatives, universities, and conservation organizations; and
- (C) at least $\frac{1}{2}$ of whom are recommended by the President of the National Academy of Sciences.
- (2) DUTIES.—The Science Advisory Board shall—
- (A) advise the Secretaries on the state-ofthe-science regarding the impacts of climate change and ocean acidification on natural resources and scientific strategies and mechanisms for protecting, restoring, and conserving natural resources to enable them to become more resilient, adapt to, and withstand the impacts of climate change and ocean acidification; and
- (B) identify and recommend priorities for ongoing research needs on such issues.
- (3) COLLABORATION.—The Science Advisory Board shall collaborate with other climate change and ecosystem research entities in other Federal agencies and departments.
- (4) AVAILABILITY TO THE PUBLIC.—The advice and recommendations of the Science Advisory Board shall be made available to the public.

SEC. 478. FEDERAL NATURAL RESOURCE AGENCY ADAPTATION PLANS.

- (a) DEVELOPMENT.—Not later than 1 year after the date of the development of a Natural Resources Climate Change Adaptation Strategy under section 476, each department or agency that has a representative on the Natural Resources Climate Change Adaptation Panel established under section 475 shall—
- (1) complete an adaptation plan for that department or agency, respectively, implementing the Natural Resources Climate Change Adaptation Strategy under section 476 and consistent with the Natural Resources Climate Change Adaptation Policy under section 472, detailing the department's or agency's current and projected efforts to address the potential impacts of climate change and ocean acidification on natural resources within the department's or agency's jurisdiction and necessary additional actions, including a timeline for implementation of those actions;
- (2) provide opportunities for review and comment on that adaptation plan by the public, including in the case of a plan by the Bureau of Indian Affairs, review by Indian tribes; and
- (3) submit such plan to the President for approval.
- (b) REVIEW BY PRESIDENT AND SUBMISSION TO CONGRESS.—
- (1) REVIEW BY PRESIDENT.—The President shall—
- (A) approve an adaptation plan submitted under subsection (a)(3) if the plan meets the requirements of subsection (c) and is consistent with the strategy developed under section 476:
- $\left(B\right)$ decide whether to approve the plan within 60 days after submission; and
- (C) if the President disapproves a plan, direct the department or agency to submit a revised plan to the President under subsection (a)(3) within 60 days after such disapproval.
- (2) SUBMISSION TO CONGRESS.—Not later than 30 days after the date of approval of such adaptation plan by the President, the department or agency shall submit the approved plan to the Committee on Natural Resources of the House of Representatives, the Committee on Energy and Natural Resources of the Senate, and the committees of

- the House of Representatives and the Senate with principal jurisdiction over the department or agency.
- (c) REQUIREMENTS.—Each adaptation plan shall—
- (1) establish programs for assessing the current and future impacts of climate change and ocean acidification on natural resources within the department's or agency's, respectively, jurisdiction, including cumulative and synergistic effects, and for identifying and monitoring those natural resources that are likely to be adversely affected and that have need for conservation:
- (2) identify and prioritize the department's or agency's strategies and specific conservation actions to address the current and future impacts of climate change and ocean acidification on natural resources within the scope of the department's or agency's jurisdiction and to develop and implement strategies to protect, restore, and conserve such resources to become more resilient, adapt to, and better withstand those impacts, including—
- (A) the protection, restoration, and conservation of terrestrial, marine, estuarine, and freshwater habitats and ecosystems:
- (B) the establishment of terrestrial, marine, estuarine, and freshwater habitat linkages and corridors;
- (C) the restoration and conservation of ecological processes;
- (D) the protection of a broad diversity of native species of fish, wildlife, and plant populations across their range; and
- (E) the protection of fish, wildlife, and plant health, recognizing that climate can alter the distribution and ecology of parasites, pathogens, and vectors;
- (3) describe how the department or agency will integrate such strategies and conservation activities into plans, programs, activities, and actions of the department or agency, related to the conservation and management of natural resources and establish new plans, programs, activities, and actions as necessary:
- (4) establish methods for assessing the effectiveness of strategies and conservation actions taken to protect, restore, and conserve natural resources to enable them to become more resilient, adapt to, and withstand the impacts of climate change and ocean acidification, and for updating those strategies and actions to respond to new information and changing conditions;
- (5) include a description of current and proposed mechanisms to enhance cooperation and coordination of natural resources adaptation efforts with other Federal agencies, State and local governments, Indian tribes, and nongovernmental stakeholders:
- (6) include specific written guidance to resource managers to—
- (A) explain how managers are expected to address the effects of climate change and ocean acidification;
- (B) identify how managers are to obtain any site-specific information that may be necessary; and
- (C) reflect best practices shared among relevant agencies, while also recognizing the unique missions, objectives, and responsibilities of each agency; and
- (7) identify and assess data and information gaps necessary to develop natural resources adaptation plans and strategies.
 - (d) IMPLEMENTATION.-
- (1) IN GENERAL.—Upon approval by the President, each department or agency that serves on the Natural Resources Climate Change Adaptation Panel shall implement its adaptation plan through existing and new plans, policies, programs, activities, and actions to the extent not inconsistent with existing authority.
 - (2) CONSIDERATION OF IMPACTS.—

- (A) IN GENERAL.—To the maximum extent practicable and consistent with applicable law, every natural resource management decision made by the department or agency shall consider the impacts of climate change and ocean acidification on those natural resources
- (B) GUIDANCE.—The Council on Environmental Quality shall issue guidance for Federal departments and agencies for considering those impacts.
- (e) REVISION AND REVIEW.—Not less than every 5 years, each adaptation plan under this section shall be reviewed and revised to incorporate the best available science and other information regarding the impacts of climate change and ocean acidification on natural resources.

SEC. 479. STATE NATURAL RESOURCES ADAPTATION PLANS.

- (a) REQUIREMENT.—In order to be eligible for funds under section 480, not later than 1 year after the development of a Natural Resources Climate Change Adaptation Strategy required under section 476 each State shall prepare a State natural resources adaptation plan detailing the State's current and projected efforts to address the potential impacts of climate change and ocean acidification on natural resources and coastal areas within the State's jurisdiction.
 - (b) REVIEW OR APPROVAL.—
- (1) IN GENERAL.—Each State adaptation plan shall be reviewed and approved or disapproved by the Secretary of the Interior and, as applicable, the Secretary of Commerce. Such approval shall be granted if the plan meets the requirements of subsection (c) and is consistent with the Natural Resources Climate Change Adaptation Strategy required under section 476.
- (2) APPROVAL OR DISAPPROVAL.—Within 180 days after transmittal of such a plan, or a revision to such a plan, the Secretary of the Interior and, as applicable, the Secretary of Commerce shall approve or disapprove the plan by written notice.
- (3) RESUBMITTAL.—Within 90 days after transmittal of a resubmitted adaptation plan as a result of disapproval under paragraph (3), the Secretary of the Interior and, as applicable, the Secretary of Commerce, shall approve or disapprove the plan by written notice.
- (c) CONTENTS.—A State natural resources adaptation plan shall—
- (1) include a strategy for addressing the impacts of climate change and ocean acidification on terrestrial, marine, estuarine, and freshwater fish, wildlife, plants, habitats, ecosystems, wildlife health, and ecological processes, that—
- (A) describes the impacts of climate change and ocean acidification on the diversity and health of the fish, wildlife and plant populations, habitats, ecosystems, and associated ecological processes:
- (B) establishes programs for monitoring the impacts of climate change and ocean acidification on fish, wildlife, and plant populations, habitats, ecosystems, and associated ecological processes;
- (C) describes and prioritizes proposed conservation actions to assist fish, wildlife, plant populations, habitats, ecosystems, and associated ecological processes in becoming more resilient, adapting to, and better withstanding those impacts;
- (D) includes strategies, specific conservation actions, and a time frame for implementing conservation actions for fish, wildlife, and plant populations, habitats, ecosystems, and associated ecological processes;
- (E) establishes methods for assessing the effectiveness of strategies and conservation actions taken to assist fish, wildlife, and plant populations, habitats, ecosystems, and associated ecological processes in becoming

more resilient, adapt to, and better withstand the impacts of climate changes and ocean acidification and for updating those strategies and actions to respond appropriately to new information or changing conditions;

- (F) is incorporated into a revision of the State wildlife action plan (also known as the State comprehensive wildlife strategy)—
- (i) that has been submitted to the United States Fish and Wildlife Service; and
- (ii) that has been approved by the Service or on which a decision on approval is pending; and
 - (G) is developed—
- (i) with the participation of the State fish and wildlife agency, the State coastal agency, the State agency responsible for administration of Land and Water Conservation Fund grants, the State Forest Legacy program coordinator, and other State agencies considered appropriate by the Governor of such State; and
- (ii) in coordination with the Secretary of the Interior, and where applicable, the Secretary of Commerce and other States that share jurisdiction over natural resources with the State; and
- (2) include, in the case of a coastal State, a strategy for addressing the impacts of climate change and ocean acidification on the coastal zone that—
- (A) identifies natural resources that are likely to be impacted by climate change and ocean acidification and describes those impacts;
- (B) identifies and prioritizes continuing research and data collection needed to address those impacts including—
- (i) acquisition of high resolution coastal elevation and nearshore bathymetry data:
- (ii) historic shoreline position maps, erosion rates, and inventories of shoreline features and structures:
- (iii) measures and models of relative rates of sea level rise or lake level changes, including effects on flooding, storm surge, inundation, and coastal geological processes:
- (iv) habitat loss, including projected losses of coastal wetlands and potentials for inland migration of natural shoreline habitats:
- (v) ocean and coastal species and ecosystem migrations, and changes in species population dynamics;
- (vi) changes in storm frequency, intensity, or rainfall patterns:
- (vii) saltwater intrusion into coastal rivers and aquifers:
- (viii) changes in chemical or physical characteristics of marine and estuarine systems;
 (ix) increased harmful algal blooms; and
 - (x) spread of invasive species;
- (C) identifies and prioritizes adaptation strategies to protect, restore, and conserve natural resources to enable them to become more resilient, adapt to, and withstand the impacts of climate change and ocean acidification, including—
- (i) protection, maintenance, and restoration of ecologically important coastal lands, coastal and ocean ecosystems, and species biodiversity and the establishment of habitat buffer zones, migration corridors, and climate refugia; and
- (ii) improved planning, siting policies, and hazard mitigation strategies;
- (D) establishes programs for the long-term monitoring of the impacts of climate change and ocean acidification on the ocean and coastal zone and to assess and adjust, when necessary, such adaptive management strategies:
- (E) establishes performance measures for assessing the effectiveness of adaptation strategies intended to improve resilience and the ability of natural resources in the coastal zone to adapt to and withstand the impacts of climate change and ocean acidifica-

- tion and of adaptation strategies intended to minimize those impacts on the coastal zone and to update those strategies to respond to new information or changing conditions; and
- (F) is developed with the participation of the State coastal agency and other appropriate State agencies and in coordination with the Secretary of Commerce and other appropriate Federal agencies.
- (d) PUBLIC INPUT.—States shall provide for solicitation and consideration of public and independent scientific input in the development of their plans.
- (e) COORDINATION WITH OTHER PLANS.—The State plan shall take into consideration research and information contained in, and coordinate with and integrate the goals and measures identified in, as appropriate, other natural resources conservation strategies, including—
 - (1) the national fish habitat action plan;
- (2) plans under the North American Wetlands Conservation Act (16 U.S.C. 4401 et seg.):
- (3) the Federal, State, and local partnership known as "Partners in Flight";
- (4) federally approved coastal zone management plans under the Coastal Zone Management Act of 1972 (16 U.S.C. 1451 et seq.);
- (5) federally approved regional fishery management plants and habitat conservation activities under the Magnuson-Stevens Fishery Conservation and Management Act (16 U.S.C. 1801 et seq.);
 - (6) the national coral reef action plan;
- (7) recovery plans for threatened species and endangered species under section 4(f) of the Endangered Species Act of 1973 (16 U.S.C. 1533(f));
- (8) habitat conservation plans under section 10 of that Act (16 U.S.C. 1539);
- (9) other Federal, State, and tribal plans for imperiled species;
- (10) State or tribal hazard mitigation plans;
- (11) State or tribal water management plans; and
- (12) other State-based strategies that comprehensively implement adaptation activities to remediate the effects of climate change and ocean acidification on terrestrial, marine, and freshwater fish, wildlife, plants, and other natural resources.
- (f) UPDATING.—Each State plan shall be updated not less than every 5 years.
- (g) FUNDING.—
- (1) In GENERAL.—Funds allocated to States under section 480 shall be used only for activities that are consistent with a State natural resources adaptation plan that has been approved by the Secretaries of Interior and Commerce
- (2) FUNDING PRIOR TO THE APPROVAL OF A STATE PLAN.—Until the earlier of the date that is 3 years after the date of the enactment of this subpart or the date on which a State receives approval for the State strategy, a State shall be eligible to receive funding under section 480 for adaptation activities that are—
- (A) consistent with the comprehensive wildlife strategy of the State and, where appropriate, other natural resources conservation strategies; and
- (B) in accordance with a workplan developed in coordination with—
- (i) the Secretary of the Interior; and
- (ii) the Secretary of Commerce, for any coastal State subject to the condition that coordination with the Secretary of Commerce shall be required only for those portions of the strategy relating to activities affecting the coastal zone.
- (3) PENDING APPROVAL.—During the period for which approval by the applicable Secretary of a State plan is pending, the State may continue receiving funds under section

480 pursuant to the workplan described in paragraph (2)(B).

SEC. 480. NATURAL RESOURCES CLIMATE CHANGE ADAPTATION FUND.

- (a) ALLOCATIONS TO STATES.—100 percent of the emission allowances made available for each year to carry out this subpart shall be provided to States to carry out natural resources adaptation activities in accordance with State natural resources adaptation plans approved under section 479. Specifically—
- (1) 84.4 percent shall be available to State wildlife agencies in accordance with the apportionment formula established under the second subsection (c) of section 4 of the Pittman-Robertson Wildlife Restoration Act (16 U.S.C. 669c), as added by section 902(e) of H.R. 5548 as introduced in the 106th Congress and enacted into law by section 1(a)(2) of Public Law 106-553 (114 Stat. 2762A-119); and
- (2) 15.6 percent shall be available to State coastal agencies pursuant to the formula established by the Secretary of Commerce under section 306(c) of the Coastal Management Act of 1972 (16 U.S.C. 1455(c)).
 - (b) ESTABLISHMENT OF FUND.—
- (1) ESTABLISHMENT.—Subject to Subtitle F of title IV, there is hereby established in the Treasury a separate account that shall be known as the Natural Resources Climate Change Adaptation Fund.
- (2) AUTHORIZATION OF APPROPRIATIONS.—Subject to Subtitle F of this title IV, there are authorized to be appropriated for subsection (c) such sums as are deposited in the Natural Resources Climate Change Fund, and the amounts appropriated for subsection (c) shall be no less than the total estimated annual deposits in the Natural Resources Climate Change Adaptation Fund.
 - (c) ALLOCATIONS TO FEDERAL AGENCIES.—
- (1) DEPARTMENT OF THE INTERIOR.—Of the amounts made available for each fiscal year to carry out this subpart—
- (A) 27.6 percent shall be allocated to the Secretary of the Interior for use in funding—
- (i) natural resources adaptation activities
- (I) under endangered species, migratory species, and other fish and wildlife programs administered by the National Park Service, the United States Fish and Wildlife Service, the Bureau of Indian Affairs, and the Bureau of Land Management;
- (II) on wildlife refuges, National Park Service land, and other public land under the jurisdiction of the United States Fish and Wildlife Service, the Bureau of Land Management, the Bureau of Indian Affairs, or the National Park Service; or
- (III) within Federal water managed by the Bureau of Reclamation and the National Park Service; and
- (ii) for the implementation of the National Fish and Wildlife Habitat and Corridors Identification Program pursuant to section 481;
- (B) 8.1 percent shall be allocated to the Secretary of the Interior for natural resources adaptation activities carried out under cooperative grant programs, including—
- (i) the cooperative endangered species conservation fund authorized under section 6 of the Endangered Species Act of 1973 (16 U.S.C. 1535);
- (ii) programs under the North American Wetlands Conservation Act (16 U.S.C. 4401 et seq.);
- (iii) the Neotropical Migratory Bird Conservation Fund established by section 478(a) of the Neotropical Migratory Bird Conservation Act (16 U.S.C. 6108(a));
- (iv) the Coastal Program of the United States Fish and Wildlife Service;
- (v) the National Fish Habitat Action Plan; (vi) the Partners for Fish and Wildlife Program;

- (vii) the Landowner Incentive Program;
- (viii) the Wildlife Without Borders Program of the United States Fish and Wildlife Service; and
- (ix) the Migratory Species Program and Park Flight Migratory Bird Program of the National Park Service; and
- (C) 4.9 percent shall be allocated to the Secretary of the Interior to provide financial assistance to Indian tribes to carry out natural resources adaptation activities through the Tribal Wildlife Grants Program of the United States Fish and Wildlife Service and in accordance with the Indian Self-Determination and Educational Assistance Act (25 U.S.C. 450(f).
 - (2) LAND AND WATER CONSERVATION FUND.—
- (A) Deposits.-
- (i) IN GENERAL.—Of the amounts made available for each fiscal year to carry out this subpart, 19.5 percent shall be deposited into the Land and Water Conservation Fund established under section 2 of the Land and Water Conservation Fund Act of 1965 (16 U.S.C. 4601-5).
- (ii) USE OF DEPOSITS.— (I) Deposits into the Land and Water Conservation Fund under this paragraph shall be supplemental to authorizations provided under section 3 of the Land and Water Conservation Fund Act of 1965 (16 U.S.C. 4601-6), which shall remain available for nonadaptation needs.
- (II) There are authorized to be appropriated for activities in this subpart such sums as are deposited in the Land and Water Conservation Fund pursuant to section 480(c)(3)(A)(ii), and the amounts appropriated for this paragraph shall be no less than the total estimated annual deposits in the Land and Water Conservation Fund.
- (B) ALLOCATIONS.—Of the amounts deposited under this paragraph into the Land and Water Conservation Fund—
- (i) % shall be allocated to the Secretary of the Interior and made available on a competitive basis to carry out natural resources adaptation activities through the acquisition of land and interests in land under section 6 of the Land and Water Conservation Fund Act of 1965 (16 U.S.C. 4601-8)—
- (I) to States in accordance with their natural resources adaptation plans, and to Indian tribes;
- (II) notwithstanding section 5 of that Act (16 U.S.C. 4601-7); and
- (III) in addition to any funds provided pursuant to annual appropriations Acts, the Energy Policy Act of 2005 (42 U.S.C. 15801 et seq.), or any other authorization for non-adaptation needs:
- (ii) ¼ shall be allocated to the Secretary of the Interior to carry out natural resources adaptation activities through the acquisition of lands and interests in land under section 7 of the Land and Water Conservation Fund Act of 1965 (16 U.S.C. 4601–9);
- (iii) % shall be allocated to the Secretary of Agriculture and made available to the States and Indian tribes to carry out natural resources adaptation activities through the acquisition of land and interests in land under section 7 of the Forest Legacy Program under the Cooperative Forestry Assistance Act of 1978 (16 U.S.C. 2103c); and
- (iv) ½ shall be allocated to the Secretary of Agriculture to carry out natural resources adaptation activities through the acquisition of land and interests in land under section 7 of the Land and Water Conservation Fund Act of 1965 (16 U.S.C. 4601–9).
- (C) EXPENDITURE OF FUNDS.—In allocating funds under subparagraph (B), the Secretary of the Interior and the Secretary of Agriculture shall take into consideration factors including—
- (i) the availability of non-Federal contributions from State, local, or private sources;

- (ii) opportunities to protect fish and wildlife corridors or otherwise to link or consolidate fragmented habitats:
- (iii) opportunities to reduce the risk of catastrophic wildfires, drought, extreme flooding, or other climate-related events that are harmful to fish and wildlife and people; and
- (iv) the potential for conservation of species or habitat types at serious risk due to climate change, ocean acidification, and other stressors.
- (3) FOREST SERVICE.—Of the amounts made available for each fiscal year to carry out this subpart, 8.1 percent shall be allocated to the Secretary of Agriculture for use in funding natural resources adaptation activities carried out on national forests and national grasslands under the jurisdiction of the Forest Service and for natural resource adaptation activities on state and private lands carried out under the Cooperative Forestry Assistance Act of 1978.
- (4) DEPARTMENT OF COMMERCE.—Of the amounts made available for each fiscal year to carry out this subpart, 11.5 percent shall be allocated to the Secretary of Commerce for use in funding natural resources adaptation activities to protect, maintain, and restore coastal, estuarine, and marine resources, habitats, and ecosystems, including such activities carried out under—
- (A) the coastal and estuarine land conservation program;
- (B) the community-based restoration program;
- (C) the Coastal Zone Management Act of 1972 (16 U.S.C. 1451 et seq.), that are specifically designed to strengthen the ability of coastal, estuarine, and marine resources, habitats, and ecosystems to adapt to and withstand the impacts of climate change and ocean acidification:
 - (D) the Open Rivers Initiative;
- (E) the Magnuson-Stevens Fishery Conservation and Management Act (16 U.S.C. 1801 et seq.);
- (F) the Marine Mammal Protection Act of 1972 (16 U.S.C. 1361 et seq.);
- (G) the Endangered Species Act of 1973 (16 U.S.C. 1531 et seq.);
- (H) the Marine Protection, Research, and Sanctuaries Act of 1972 (33 U.S.C. 1401 et seq.);
- (1) the Coral Reef Conservation Act of 2000 (16 U.S.C. 6401 et seq.); and
- (J) the Estuary Restoration Act of 2000 (33 U.S.C. 2901 et seq.).
- (5) ENVIRONMENTAL PROTECTION AGENCY.—
 Of the amounts made available each fiscal year to carry out this section, 12.2 percent shall be allocated to the Administrator for use in natural resources adaptation activities restoring and protecting—
- (A) large-scale freshwater aquatic ecosystems, such as the Everglades, the Great Lakes, Flathead Lake, the Missouri River, the Mississippi River, the Colorado River, the Sacramento-San Joaquin Rivers, the Ohio River, the Columbia-Snake River System, the Apalachicola, Chattahoochee, and Flint River System, the Connecticut River, and the Yellowstone River;
- (B) large-scale estuarine ecosystems, such as Chesapeake Bay, Long Island Sound, Puget Sound, the Mississippi River Delta, the San Francisco Bay Delta, Narragansett Bay, and Albemarle-Pamlico Sound; and
- (C) freshwater and estuarine ecosystems, watersheds, and basins identified as priorities by the Administrator, working in cooperation with other Federal agencies, States, Indian tribes, local governments, scientists, and other conservation partners.
- (6) CORPS OF ENGINEERS.—Of the amounts made available each fiscal year to carry out this section, 8.1 percent shall be available to the Secretary of the Army for use by the

- Corps of Engineers to carry out natural resources adaptation activities restoring—
- (A) large-scale freshwater aquatic ecosystems, such as the ecosystems described in paragraph (5)(A);
- (B) large-scale estuarine ecosystems, such as the ecosystems described in paragraph (5)(B):
- (C) freshwater and estuarine ecosystems, watersheds, and basins identified as priorities by the Corps of Engineers, working in cooperation with other Federal agencies, States, Indian tribes, local governments, scientists, and other conservation partners; and
- (D) habitats and ecosystems through the implementation of estuary habitat restoration projects authorized by the Estuary Restoration Act of 2000 (33 U.S.C. 2901 et seq.), project modifications for improvement of the environment, aquatic restoration and protection projects authorized by section 206 of the Water Resources Development Act of 1996 (33 U.S.C. 2330), and other appropriate programs and activities.
- (d) USE OF FUNDS BY FEDERAL DEPARTMENTS AND AGENCIES.—Funds allocated to Federal departments and agencies under this section shall only be used for natural resources adaptation activities that are consistent with an adaptation plan developed and approved by the President under section 478
- (e) STATE COST SHARING.—Notwithstanding any other provision of law, a State that receives a grant with amounts allocated under this section shall use funds from non-Federal sources to pay at least 10 percent of the costs of each activity carried out using amounts provided under the grant.

SEC. 481. NATIONAL WILDLIFE HABITAT AND CORRIDORS INFORMATION PROGRAM.

- (a) ESTABLISHMENT.—Within 6 months of the date of enactment of this subpart, the Secretary of the Interior, in cooperation with the States and Indian tribes, shall establish a National Fish and Wildlife Habitat and Corridors Information Program in accordance with the requirements of this section.
- (b) PURPOSE.—The purpose of this program is to—
- (1) support States and Indian tribes in the development of a geographic information system database of fish and wildlife habitat and corridors that would inform planning and development decisions within each State and Indian tribe, enable each State and Indian tribe to model climate impacts and adaptation, and provide geographically specific enhancements of State and tribal wildlife action plans:
- (2) ensure the collaborative development, with the States and Indian tribes, of a comprehensive, national geographic information system database of maps, models, data, surveys, informational products, and other geospatial information regarding fish and wildlife habitat and corridors, that—
- (A) is based on consistent protocols for sampling and mapping across landscapes that take into account regional differences; and
 - (B) that utilizes—
- (i) existing and planned State- and tribalbased geographic information system databases; and
- (ii) existing databases, analytical tools, metadata activities, and other information products available through the National Biological Information Infrastructure maintained by the Secretary and nongovernmental organizations; and
- (3) facilitate the use of such databases by Federal, State, local, and tribal decision-makers to incorporate qualitative information on fish and wildlife habitat and corridors at the earliest possible stage to—

- (A) prioritize and target natural resources adaptation strategies and activities;
- (B) avoid, minimize, and mitigate the impacts on fish and wildlife habitat and corridors in siting energy development, water, transmission, transportation, and other land use projects;
- (C) assess the impacts of existing development on habitats and corridors; and
- (D) develop management strategies to enhance the ability of fish, wildlife, and plant species to migrate or respond to shifting habitats within existing habitats and corridors.
- (c) Habitat and Corridors Information System.—
- (1) IN GENERAL.—The Secretary, in cooperation with the States and Indian tribes, shall develop a Habitat and Corridors Information System.
 - (2) CONTENTS.—The System shall-
- (A) include maps, data, and descriptions of fish and wildlife habitat and corridors, that—
- (i) have been developed by Federal agencies, State wildlife agencies and natural heritage programs, Indian tribes, local governments, nongovernmental organizations, and industry:
- (ii) meet accepted Geospatial Interoperability Framework data and metadata protocols and standards;
- (B) include maps and descriptions of projected shifts in habitats and corridors of fish and wildlife species in response to climate change:
- (C) assure data quality and make the data, models, and analyses included in the System available at scales useful to decision-makers—
- (i) to prioritize and target natural resources adaptation strategies and activities;
- (ii) to assess the impacts of proposed energy development, water, transmission, transportation, and other land use projects and avoid, minimize, and mitigate those impacts on habitats and corridors;
- (iii) to assess the impacts of existing development on habitats and corridors; and
- (iv) to develop management strategies to enhance the ability of fish, wildlife, and plant species to migrate or respond to shifting habitats within existing habitats and corridors:
- (D) establish a process for updating maps and other information as landscapes, habitats, corridors, and wildlife populations change or as other information becomes available:
- (E) encourage the development of collaborative plans by Federal and State agencies and Indian tribes to monitor and evaluate the efficacy of the System to meet the needs of decisionmakers:
- (F) identify gaps in habitat and corridor information, mapping, and research that should be addressed to fully understand and assess current data and metadata, and to prioritize research and future data collection activities for use in updating the System and provide support for those activities;
- (G) include mechanisms to support collaborative research, mapping, and planning of habitats and corridors by Federal and State agencies, Indian tribes, and other interested stakeholders:
- (H) incorporate biological and geospatial data on species and corridors found in energy development and transmission plans, including renewable energy initiatives, transportation, and other land use plans;
- (I) be based on the best scientific information available; and
- (J) identify, prioritize, and describe key parcels of non-Federal land located within the boundaries of units of the National Park System, National Wildlife Refuge System, National Forest System, or National Grass-

- land System that are critical to maintenance of wildlife habitat and migration corridors
- (d) FINANCIAL AND OTHER SUPPORT.—The Secretary may provide support to the States and Indian tribes, including financial and technical assistance, for activities that support the development and implementation of the System.
- (e) COORDINATION.—The Secretary, in cooperation with the States and Indian tribes, shall make recommendations on how the information developed in the System may be incorporated into existing relevant State and Federal plans affecting fish and wildlife, including land management plans, the State Comprehensive Wildlife Conservation Strategies, and appropriate tribal conservation plans, to ensure that they—
- (1) prevent unnecessary habitat fragmentation and disruption of corridors;
- (2) promote the landscape connectivity necessary to allow wildlife to move as necessary to meet biological needs, adjust to shifts in habitat, and adapt to climate change; and
- (3) minimize the impacts of energy, development, water, transportation, and transmission projects and other activities expected to impact habitat and corridors.
 - (f) DEFINITIONS.—In this section:
- (1) GEOSPATIAL INTEROPERABILITY FRAME-WORK.—The term "Geospatial Interoperability Framework" means the strategy utilized by the National Biological Information Infrastructure that is based upon accepted standards, specifications, and protocols adopted through the International Standards Organization, the Open Geospatial Consortium, and the Federal Geographic Data Committee, to manage, archive, integrate, analyze, and make accessible geospatial and biological data and metadata.
- (2) SECRETARY.—The term "Secretary" means the Secretary of the Interior.

SEC. 482. ADDITIONAL PROVISIONS REGARDING INDIAN TRIBES.

- (a) FEDERAL TRUST RESPONSIBILITY.—Nothing in this subpart is intended to amend, alter, or give priority over the Federal trust responsibility to Indian tribes.
- (b) EXEMPTION FROM FOIA.—Information received by a Federal agency pursuant to this Act relating to the location, character, or ownership of human remains of a person of Indian ancestry; or resources, cultural items, uses, or activities identified by an Indian tribe as traditional or cultural because of the long-established significance or ceremonial nature to the Indian tribe; shall not be subject to disclosure under section 552 of title 5, United States Code, if the head of the agency, in consultation with the Secretary of the Interior and an affected Indian tribe, determines that disclosure may—
- (1) cause a significant invasion of privacy; (2) risk harm to the human remains or resources, cultural items, uses, or activities; or
- (3) impede the use of a traditional religious site by practitioners
- (c) APPLICATION OF OTHER LAW.—The Secretary of the Interior may apply the provisions of Public Law 93–638 where appropriate in the implementation of this subpart.

PART 2—INTERNATIONAL CLIMATE CHANGE ADAPTATION PROGRAM

SEC. 491. FINDINGS AND PURPOSES.

- (a) FINDINGS.—Congress finds the following:
- (1) Global climate change is a potentially significant national and global security threat multiplier and is likely to exacerbate competition and conflict over agricultural, vegetative, marine, and water resources and to result in increased displacement of people, poverty, and hunger within developing countries

- (2) The strategic, social, political, economic, cultural, and environmental consequences of global climate change are likely to have disproportionate adverse impacts on developing countries, which have less economic capacity to respond to such impacts.
- (3) The countries most vulnerable to climate change, due both to greater exposure to harmful impacts and to lower capacity to adapt, are developing countries with very low industrial greenhouse gas emissions that have contributed less to climate change than more affluent countries.
- (4) To a much greater degree than developed countries, developing countries rely on the natural and environmental systems likely to be affected by climate change for sustenance, livelihoods, and economic growth and stability.
- (5) Within developing countries there may be varying climate change adaptation and resilience needs among different communities and populations, including impoverished communities, children, women, and indigenous peoples.
- (6) The consequences of global climate change, including increases in poverty and destabilization of economies and societies, are likely to pose long-term challenges to the national security, foreign policy, and economic interests of the United States.
- (7) It is in the national security, foreign policy, and economic interests of the United States to recognize, plan for, and mitigate the international strategic, social, political, cultural, environmental, health, and economic effects of climate change and to assist developing countries to increase their resilience to those effects.
- (8) Under Article 4 of the United Nations Framework Convention on Climate Change, developed country parties, including the United States, committed to "assist the developing country parties that are particularly vulnerable to the adverse effects of climate change in meeting costs of adaptation to those adverse effects".
- (9) Under the Bali Action Plan, developed country parties to the United Nations Framework Convention on Climate Change, including the United States, committed to "enhanced action on the provision of financial resources and investment to support action on mitigation and adaptation and technology cooperation," including, inter alia, consideration of "improved access to adequate, predictable, and sustainable financial resources and financial and technical support, and the provision of new and additional resources, including official and concessional funding for developing country parties".
- (b) Purposes.—The purposes of this part are— $\,$
- (1) to provide new and additional assistance from the United States to the most vulnerable developing countries, including the most vulnerable communities and populations therein, in order to support the development and implementation of climate change adaptation programs and activities that reduce the vulnerability and increase the resilience of communities to climate change impacts, including impacts on water availability, agricultural productivity, flood risk, coastal resources, timing of seasons, biodiversity, economic livelihoods, health and diseases, and human migration; and
- (2) to provide such assistance in a manner that protects and promotes the national security, foreign policy, environmental, and economic interests of the United States to the extent such interests may be advanced by minimizing, averting, or increasing resilience to climate change impacts.

${\bf SEC.~492.~DEFINITIONS.}$

In this part:

- (1) ALLOWANCE.—The term "allowance" means an emission allowance established under section 721 of the Clean Air Act.
- (2) APPROPRIATE CONGRESSIONAL COMMITTEES.—The term "appropriate congressional committees" means—
- (A) the Committees on Energy and Commerce, Financial Services, and Foreign Affairs of the House of Representatives; and
- (B) the Committees on Environment and Public Works and Foreign Relations of the Senate.
- (3) DEVELOPING COUNTRY.—The term "developing country" means a country eligible to receive official development assistance according to the income guidelines of the Development Assistance Committee of the Organization for Economic Cooperation and Development.
- (4) MOST VULNERABLE DEVELOPING COUNTRIES.—The term "most vulnerable developing countries" means, as determined by the Administrator of USAID, developing countries that are at risk of substantial adverse impacts of climate change and have limited capacity to respond to such impacts, considering the approaches included in any international treaties and agreements.
- (5) MOST VULNERABLE COMMUNITIES AND POPULATIONS.—The term "most vulnerable communities and populations" means communities and populations that are at risk of substantial adverse impacts of climate change and have limited capacity to respond to such impacts, including impoverished communities, children, women, and indigenous peoples.
- (6) PROGRAM.—The term "Program" means the International Climate Change Adaptation Program established under section 493.
- (7) USAID.—The term "USAID" means the United States Agency for International Development.
- (8) UNITED NATIONS FRAMEWORK CONVENTION ON CLIMATE CHANGE.—The term "United Nations Framework Convention on Climate Change" or "Convention" means the United Nations Framework Convention on Climate Change done at New York on May 9, 1992, and entered into force on March 21, 1994.

SEC. 493. INTERNATIONAL CLIMATE CHANGE ADAPTATION PROGRAM.

- (a) ESTABLISHMENT.—The Secretary of State, in consultation with the Administrator of USAID, the Secretary of the Treasury, and the Administrator of the Environmental Protection Agency, shall establish an International Climate Change Adaptation Program in accordance with the requirements of this part.
- (b) ALLOWANCE ACCOUNT.—Allowances allocated pursuant to section 782(n) of the Clean Air Act shall be available for distribution to carry out the Program established under subsection (a).
- (c) SUPPLEMENT NOT SUPPLANT.—Assistance provided under this part shall be used to supplement, and not to supplant, any other Federal, State, or local resources available to carry out activities of the type carried out under the Program.

SEC. 494. DISTRIBUTION OF ALLOWANCES.

- (a) IN GENERAL.—The Secretary of State, or such other Federal agency head as the President may designate, after consultation with the Secretary of the Treasury, the Administrator of USAID, and the Administrator of the Environmental Protection Agency, shall direct the distribution of allowances to carry out the Program—
- (1) in the form of bilateral assistance pursuant to the requirements under section 495;
- (2) to multilateral funds or international institutions pursuant to the Convention or an agreement negotiated under the Convention; or
- (3) through a combination of the mechanisms identified under paragraphs (1) and (2).

- (b) LIMITATION.-
- (1) CONDITIONAL DISTRIBUTION TO MULTILAT-ERAL FUNDS OR INTERNATIONAL INSTITU-TIONS.—In any fiscal year, the Secretary of State, or such other Federal agency head as the President may designate, in consultation with the Administrator of USAID, the Secretary of the Treasury, and the Administrator of the Environmental Protection Agency, shall distribute at least 40 percent and up to 60 percent of the allowances available to carry out the Program to one or more multilateral funds or international institutions that meet the requirements of paragraph (2), if any such fund or institution exists, and shall annually certify in a report to the appropriate congressional committees that any multilateral fund or international institution receiving allowances under this section meets the requirements of paragraph (2) or that no multilateral fund or international institution that meets the requirements of paragraph (2) exists, as the case may be. The Secretary of State shall notify the appropriate congressional committees not less than 15 days prior to any transfer of allowances to a multilateral fund or international institution pursuant to this section.
- (2) MULTILATERAL FUND OR INTERNATIONAL INSTITUTION ELIGIBILITY.—A multilateral fund or international institution is eligible to receive allowances available to carry out the Program—
- (A) if-
- (i) such fund or institution is established pursuant to— $\,$
- (I) the Convention: or
- (II) an agreement negotiated under the Convention: or
- (ii) the allowances are directed to one or more multilateral development banks or international development institutions, pursuant to an agreement negotiated under such Convention: and
 - (B) if such fund or institution—
- (i) specifies the terms and conditions under which the United States is to provide allowances to the fund or institution, and under which the fund or institution is to provide assistance to recipient countries:
- (ii) ensures that assistance from the United States to the fund or institution and the principal and income of the fund or institution are disbursed only for purposes that are consistent with those described in section 491(b)(1):
- (iii) requires a regular meeting of a governing body of the fund or institution that includes representation from countries among the most vulnerable developing countries and provides public access:
- (iv) requires that local communities and indigenous peoples in areas where any activities or programs are planned are engaged through adequate disclosure of information, public participation, and consultation; and
- (v) prepares and makes public an annual report that—
- (I) describes the process and methodology for selecting the recipients of assistance from the fund or institution, including assessments of vulnerability;
- (II) describes specific programs and activities supported by the fund or institution and the extent to which the assistance is addressing the adaptation needs of the most vulnerable developing countries, and the most vulnerable communities and populations therein:
- (III) describes the performance goals for assistance authorized under the fund or institution and expresses such goals in an objective and quantifiable form, to the extent practicable:
- (IV) describes the performance indicators to be used in measuring or assessing the achievement of the performance goals described in subclause (III);

- (V) provides a basis for recommendations for adjustments to assistance authorized under this part to enhance the impact of such assistance; and
- (VI) describes the participation of other nations and international organizations in supporting and governing the fund or institution.
 - (c) Oversight .-
- (1) DISTRIBUTION TO MULTILATERAL FUNDS OR INTERNATIONAL INSTITUTIONS.—The Secretary of State, or such other Federal agency head as the President may designate, in consultation with the Administrator of USAID, shall oversee the distribution of allowances available to carry out the Program to a multilateral fund or international institution under subsection (b).
- (2) BILATERAL ASSISTANCE.—The Administrator of USAID, in consultation with the Secretary of State, shall oversee the distribution of allowances available to carry out the Program for bilateral assistance under section 495.

SEC. 495, BILATERAL ASSISTANCE.

- (a) ACTIVITIES AND FOREIGN AID.—
- (1) IN GENERAL.—In order to achieve the purposes of this part, the Administrator of USAID may carry out programs and activities and distribute allowances to any private or public group (including international organizations and faith-based organizations), association, or other entity engaged in peaceful activities to—
- (A) provide assistance to the most vulnerable developing countries for—
- (i) the development of national or regional climate change adaptation plans, including a systematic assessment of socioeconomic vulnerabilities in order to identify the most vulnerable communities and populations:
 - (ii) associated national policies; and
- (iii) planning, financing, and execution of adaptation programs and activities;
- (B) support investments, capacity-building activities, and other assistance, to reduce vulnerability and promote community-level resilience related to climate change and its impacts in the most vulnerable developing countries, including impacts on water availability, agricultural productivity, flood risk, coastal resources, timing of seasons, biodiversity, economic livelihoods, health, human migration, or other social, economic, political, cultural, or environmental matters;
- (C) support climate change adaptation research in or for the most vulnerable developing countries;
- (D) reduce vulnerability and provide increased resilience to climate change for local communities and livelihoods in the most vulnerable developing countries by encouraging—
- (i) the protection and rehabilitation of natural systems;
- (ii) the enhancement and diversification of agricultural, fishery, and other livelihoods; and
 - (iii) the reduction of disaster risks;
- (E) support the deployment of technologies to help the most vulnerable developing countries respond to the destabilizing impacts of climate change and encourage the identification and adoption of appropriate renewable and efficient energy technologies that are beneficial in increasing community-level resilience to the impacts of global climate change in those countries; and
- (F) encourage the engagement of local communities through disclosure of information, consultation, and the communities' informed participation relating to the development of plans, programs, and activities to increase community-level resilience to climate change impacts.
- (2) LIMITATIONS.—Not more than 10 percent of the allowances made available to carry

- out bilateral assistance under this part in any year shall be distributed to support activities in any single country.
- (3) Prioritizing assistance. assistance under this section, the Administrator of USAID shall give priority to countries, including the most vulnerable communities and populations therein, that are most vulnerable to the adverse impacts of climate change, determined by the likelihood and severity of such impacts and the country's capacity to adapt to such impacts.
 - (b) Community Engagement.-
- (1) IN GENERAL.—The Administrator of USAID shall ensure that local communities. including the most vulnerable communities and populations therein, in areas where any programs or activities are carried out pursuant to this section are engaged in, through disclosure of information, public participation, and consultation, the design, implementation, monitoring, and evaluation of such programs and activities.
- (2) Consultation and disclosure.—For each country receiving assistance under this section, the Administrator of USAID shall establish a process for consultation with, and disclosure of information to, local, national, and international stakeholders regarding any programs and activities carried out pursuant to this section.
 - (c) COORDINATION.-
- (1) ALIGNMENT OF ACTIVITIES.—Subject to the direction of the President and the Secretary of State, the Administrator of USAID shall, to the extent practicable, seek to align activities under this section with broader development, poverty alleviation, or natural resource management objectives and initiatives in the recipient country.
- (2) COORDINATION OF ACTIVITIES —The Administrator of USAID shall ensure that there is coordination among the activities under this section, subtitle D of this title, and part E of title VII of the Clean Air Act, in order to maximize the effectiveness of United States assistance to developing countries.
 - (d) Reporting.-
- (1) INITIAL REPORT.—Not later than 180 days after the date of enactment of this part, the Administrator of USAID, in consultation with the Secretary of State, shall submit to the President and the appropriate congressional committees an initial report that-
- (A) based on the most recent information available from reliable public sources or knowledge obtained by USAID on a reliable basis, as determined by the Administrator of USAID, identifies the developing countries. including the most vulnerable communities and populations therein, that are most vulnerable to climate change impacts and in which assistance may have the greatest and most sustainable benefit in reducing vulnerability to climate change; and
- (B) describes the process and methodology for selecting the recipients of assistance under subsection (a)(1).
- (2) ANNUAL REPORTS.—Not later than 18 months after the date on which the initial report is submitted pursuant to paragraph (1), and annually thereafter, the Administrator of USAID, in consultation with the Secretary of State, shall submit to the President and the appropriate congressional committees a report that-
- (A) describes the extent to which global climate change, through its potential negative impacts on sensitive populations and natural resources in the most vulnerable developing countries, may threaten, cause, or exacerbate political, economic, environmental, cultural, or social instability or international conflict in those regions;
- (B) describes the ramifications of any potentially destabilizing impacts climate change may have on the national security,

- foreign policy, and economic interests of the United States, including-
- (i) the creation of environmental migrants and internally displaced peoples;
- (ii) international or internal armed conflicts over water, food, land, or other resources:
- (iii) loss of agricultural and other livelihoods, cultural stability, and other causes of increased poverty and economic destabiliza-
- (iv) decline in availability of resources needed for survival, including water;
- (v) increased impact of natural disasters (including droughts, flooding, and other severe weather events);
- (vi) increased prevalence or virulence of climate-related diseases; and
 - (vii) intensified urban migration;
- (C) describes how allowances available under this section were distributed during the previous fiscal year to enhance the national security, foreign policy, and economic interests of the United States and assist in avoiding the economically, politically, environmentally, culturally, and socially destabilizing impacts of climate change in most vulnerable developing countries;
- (D) identifies and recommends the developing countries, including the most vulnerable communities and populations therein. that are most vulnerable to climate change impacts and in which assistance may have the greatest and most sustainable benefit in reducing vulnerability to climate change, including in the form of deploying technologies, investments, capacity-building activities, and other types of assistance for adaptation to climate change impacts and approaches to reduce greenhouse gases in ways that may also provide community-level resilience to climate change impacts; and
- (E) describes cooperation undertaken with other nations and international organizations to carry out this part.
- (e) MONITORING AND EVALUATION.-
- (1) IN GENERAL.—The Administrator of USAID shall establish and implement a system to monitor and evaluate the effectiveness and efficiency of assistance provided under this section in order to maximize the long-term sustainable development impact of such assistance, including the extent to which such assistance is meeting the purposes of this part and addressing the adaptation needs of developing countries.
- (2) REQUIREMENTS.—In carrying out paragraph (1), the Administrator of USAID shall-
- (A) in consultation with national governments in recipient countries, establish performance goals for assistance authorized under this section and express such goals in an objective and quantifiable form, to the extent practicable:
- (B) establish performance indicators to be used in measuring or assessing the achievement of the performance goals described in subparagraph (A), including an evaluation
- (i) the extent to which assistance under this section provided for disclosure of information to, consultation with, and informed participation by local communities;
- (ii) the extent to which local communities participated in the design, implementation, and evaluation of programs and activities implemented pursuant to this section; and
- (iii) the impacts of such participation on the goals and objectives of the programs and activities implemented under this section;
- (C) provide a basis for recommendations for adjustments to assistance authorized under this section to enhance the impact of such assistance; and
- (D) include, in the annual report to the appropriate congressional committees and other relevant agencies required under sub-

section (d)(2), findings resulting from the monitoring and evaluation of programs and activities under this section.

Subtitle F-Deficit Neutral Budgetary Treatment

SEC. 496. DEFICIT NEUTRALITY.

- (a) FUNDS ESTABLISHED.—Funds established under sections 422, 467, and 480 of this Act are to be treated as separate accounts in the Treasury and shall be known as "the Funds'
- (b) AVAILABILITY.—Funds appropriated or made available pursuant to sections 422(b). 467(b). and 480(b)(2) are only available for the purposes set forth under this Act. Receipts in the Funds and appropriations therefrom shall not be available and are precluded from obligation for any other purpose.
- (c) ESTIMATION OF BUDGETARY IMPACT.— For the purposes of estimating the revenue and spending effects of this Act:
- (1) the revenue assumed to be deposited into the Funds established under sections 422, 467, and 480, shall be attributed to this Act: and
- (2) the authorization or availability of appropriations from the Funds shall be treated as new direct spending and attributed to this
- (d) BUDGETARY TREATMENT.—For the purposes of section 257 of the Balanced Budget and Emergency Deficit Control Act of 1985, the Funds, and amounts subsequently appropriated or made available for the purposes for which such Funds were established, shall be deemed to be included on the list of appropriations referenced under section 250(c)(17) of that Act. Such appropriations from each Fund shall not be in excess of the amounts deposited into the respective Fund in the previous year.

TITLE V-AGRICULTURAL AND FORESTRY RELATED OFFSETS

Subtitle A—Offset Credit Program From **Domestic Agricultural and Forestry Sources** SEC. 501. DEFINITIONS.

- (a) IN GENERAL.—In this title:
- (1) ADDITIONAL.—The term "additional" when used with respect to reductions or avoidance of greenhouse gas emissions, or to sequestration of greenhouse gases, means reductions, avoidance, or sequestration that result in a lower level of net greenhouse gas emissions or atmospheric concentrations than would occur in the absence of an offset project.
- ADDITIONALITY.—The (2)"additionality" means the extent to which reductions or avoidance of greenhouse gas emissions, or sequestration of greenhouse gases, are additional.
- (3) ADMINISTRATOR.—The term "Administrator" means the Administrator of the Environmental Protection Agency.
- (4) ADVISORY COMMITTEE.—The term "Advisory Committee" means the USDA Greenhouse Gas Emission Reduction and Sequestration Advisory Committee established under section 1245(f) of the Food Security Act of 1985 (16 U.S.C. 3845).
- (5) GREENHOUSE GAS.—The term "greenhouse gas" means any of the following:
 - (A) Carbon dioxide.
 - (B) Methane.
 - (C) Nitrous oxide.
 - (D) Sulfur hexafluoride.
- (E) Hydrofluorocarbons from a chemical manufacturing process at an industrial stationary source.
 - (F) Any perfluorocarbon.
 - (G) Nitrogen trifluoride.
- (H) Any other anthropogenic gas designated as a greenhouse gas by the Administrator.
- (6) LEAKAGE.—The term "leakage" means a significant and quantifiable increase in

- greenhouse gas emissions, or a significant and quantifiable decrease in sequestration, which is caused by an offset practice and occurs outside the boundaries of the offset practice.
- (7) Offset credit.—The term "offset credit" means a tradeable compliance instrument that—
- (A) represents the reduction, avoidance, or sequestration of 1 ton of carbon dioxide equivalent; and
 - (B) is issued pursuant to this title.
- (8) OFFSET PRACTICE.—The term "offset practice" means an activity that reduces, avoids, or sequesters greenhouse gas emissions, and for which offset credits may be issued pursuant to this title.
- (9) OFFSET PRODUCER.—The term "offset producer" means an owner, operator, landlord, tenant, or sharecropper who has or shares responsibility for ensuring that an offset practice is established and maintained during the crediting period for purposes of an offset credit.
- (10) OFFSET PROJECT.—The term "offset project" means a practice or set of practices that reduce or avoid greenhouse gas emissions, or sequester greenhouse gases as implemented by an offset producer.
- (11) OFFSET PROJECT DEVELOPER.—The term "offset project developer" means the offset producer or designee of the offset producer.
- (12) PRACTICE TYPE.—The term "practice type" means a discrete category of offset practices for which the Secretary develops a standardized methodology to accurately estimate the amount of greenhouse gas emissions reduced or avoided or greenhouse gases sequestered.
- (13) REVERSAL.—The term "reversal" means an intentional or unintentional loss of sequestered greenhouse gases to the atmosphere.
- (14) SECRETARY.—The term "Secretary" means the Secretary of Agriculture.
- (15) SEQUESTRATION AND SEQUESTERED.— The terms "sequestered" and "sequestration" mean the separation, isolation, or removal of greenhouse gases from the atmosphere, as determined by the Secretary. The terms include biological sequestration, but do not include ocean fertilization techniques.
- (16) TERM OFFSET CREDIT.—The term "term offset credit" means a compliance instrument authorized under section 504(d).
- (b) AGRICULTURAL AND FORESTRY EXCEPTION TO DEFINITION OF CAPPED SECTOR.—For purposes of this title and title III of this Act, and amendments made by such titles, the term "capped sector" means a sector of economic activity that directly emits capped emissions, including the industrial sector, the electricity generation sector, the transportation sector, and the residential and commercial sectors (to the extent they burn oil or natural gas), but not including the agricultural or forestry sectors.

SEC. 502. ESTABLISHMENT OF OFFSET CREDIT PROGRAM FROM DOMESTIC AGRICULTURAL AND FORESTRY SOURCES.

- (a) ESTABLISHMENT.—Not later than 1 year after the date of enactment of this title, the Secretary shall establish a program governing the generation of offset credits from domestic agricultural and forestry sources.
- (b) REQUIREMENTS.—The program described in subsection (a) shall—
- (1) ensure that offset credits represent verifiable and additional greenhouse gas emission reductions or avoidance, or increases in sequestration; and
- (2) ensure that offset credits issued for sequestration offset projects are only issued for greenhouse gas reductions that result in a permanent net reduction in atmospheric greenhouse gases.

- (c) DUTIES OF SECRETARY.—In addition to the duties described in subsection (a) and section 1245 of the Food Security Act of 1985 (16 U.S.C. 3845), the Secretary shall, with respect to practices relating to offset credits from agricultural and forestry sources—
- (1) establish by rule methodologies by practice types for quantifying greenhouse gas benefits;
- (2) establish by rule methodologies for each practice type for establishing activity baselines and determining additionality;
- (3) establish by rule methodologies by practice types for accounting for and mitigating potential leakage:
- (4) establish rules to account for and address reversals;
- (5) establish rules to require third-party verification;
- (6) provide technical assistance to offset project developers using funds appropriated to the Conservation Operations account:
- (7) establish rules for approval of offset project plans;
- (8) establish rules for certification of implementation of offset project plans;
- (9) establish by rule requirements for reporting and record keeping; and
- (10) conduct audits.

SEC. 503. LIST OF ELIGIBLE DOMESTIC AGRICUL-TURAL AND FORESTRY OFFSET PRACTICE TYPES.

- (a) LIST REQUIRED.—
- (1) PREPARATION AND PUBLICATION.—Not later than 1 year after the date of enactment of this title, the Secretary shall prepare and publish in the Federal Register a list of domestic agricultural and forestry practice types that are eligible to generate offset credits under this title because the practices avoid or reduce greenhouse gas emissions or sequester greenhouse gases.
- (2) RECOMMENDATIONS.—In preparing the list under paragraph (1), the Secretary shall take into consideration the recommendations of the Advisory Committee.
- (b) INITIAL LIST.—At a minimum, the list prepared under this section shall include those practices that avoid or reduce greenhouse gas emissions or sequester greenhouse gases, such as—
- (1) agricultural, grassland, and rangeland sequestration and management practices, including—
- (A) altered tillage practices;
- (B) winter cover cropping, continuous cropping, and other means to increase biomass returned to soil in lieu of planting followed by fallowing:
- (C) reduction of nitrogen fertilizer use or increase in nitrogen use efficiency:
- (D) reduction in the frequency and duration of flooding of rice paddies:
- (E) reduction in carbon emissions from organic soils:
- ganic soils;

 (F) reduction in greenhouse gas emissions from manure and effluent; and
- (G) reduction in greenhouse gas emissions due to changes in animal management practices, including dietary modifications;
- (2) changes in carbon stocks attributed to land use change and forestry activities, including—
- (A) afforestation or reforestation of acreage that is not forested;
- (B) forest management resulting in an increase in forest carbon stores including but not limited to harvested wood products;
- (C) management of peatland or wetland;
- (D) conservation of grassland and forested land;
- (E) improved forest management, including accounting for earbon stored in wood products;
- (F) reduced deforestation or avoided forest conversion;
- (G) urban tree-planting and maintenance;
- (H) agroforestry; and

- (I) adaptation of plant traits or new technologies that increase sequestration by forests; and
- (3) manure management and disposal, including—
 - (A) waste aeration;
 - (B) biogas capture and combustion; and
- (C) application to fields as a substitute for commercial fertilizer.
- (c) Additions and Revisions to List.-
- (1) PERIODIC REVISION.—Not later than 2 years after the date of enactment of this title, and every 2 years thereafter, the Secretary, after public notice and opportunity for comment, shall add to and revise the types of offset practices to the list established under subsection (a) if those types of practices meet the standards for environmental integrity that are consistent with the purposes of this title.
- (2) CONSIDERATION OF PETITIONS.—The Secretary shall—
- (A) consider petitions to add types of offset practices to the list established under subsection (a); and
- (B) add those types of offset practices to the list if the types of offset practices meet standards for environmental integrity consistent with the purposes of this title.
- (3) TIME FOR CONSIDERATION OF PETITIONS.—Not later than 1 year after the receipt of a petition under paragraph (2), the Secretary shall make a decision to either grant or deny the petition and publish a written explanation of the reasons for the Secretary's decision. The Secretary may not deny a petition under this subsection on the basis of inadequate Department of Agriculture resources at the time of the review.

SEC. 504. REQUIREMENTS FOR DOMESTIC AGRI-CULTURAL AND FORESTRY PRAC-TICES.

- (a) METHODOLOGIES.—
- (1) IN GENERAL; CONDITION.—In promulgating regulations under section 502, the Secretary shall establish methodologies for domestic agricultural and forestry practices listed under section 503, if the Secretary determines that methodologies can be established for such practices that meet each of the requirements of this section. The Secretary shall only issue offset credits under this title pursuant to promulgated methodologies applicable to the offset practice that avoided or reduced greenhouse gas emissions or sequestered greenhouse gases.
- (2) SPECIFIED METHODOLOGIES.—The Secretary shall establish the following methodologies under this section:
- (A) ACTIVITY BASELINES.—A standardized methodology for establishing activity baselines for an offset practice of that type. The Secretary shall set activity baselines to reflect a conservative estimate of performance or activities for the relevant type of practice (excluding changes in performance or activities due to the availability of offset credits) such that the baseline provides an adequate margin of safety to ensure the environmental integrity of offset credits calculated in reference to such baseline.
- (B) ADDITIONALITY.—A standardized methodology for determining the additionality of greenhouse gas emissions reduction or avoidance, or greenhouse gas sequestration, achieved by an offset practice of that type. Such methodology shall ensure, at a minimum, that any greenhouse gas emission reduction or avoidance, or any greenhouse gas sequestration, is considered additional only to the extent that it results from activities that—
- (i) are not required by existing government regulations, as determined by the Secretary;
- (ii) were not commenced prior to January 1, 2009, except in the case of—

- (I) offset project activities that commenced after January 1, 2001, and were registered as of the date of enactment of this title under an offset program with respect to which an affirmative determination has been made under section 740 of the Clean Air Act; or
- (II) activities that are readily reversible, with respect to which the Secretary may set an alternative earlier date under this subparagraph that is not earlier than January 1, 2001, where the Secretary determines that setting such an alternative date may produce an environmental benefit by removing an incentive to cease and then reinitiate activities that began prior to January 1, 2009; and
- (iii) exceed the applicable activity baseline established under paragraph (2).
- (C) QUANTIFICATION METHODS.—A standardized methodology for determining the extent to which greenhouse gas emission reductions or avoidance, or greenhouse gas sequestration, achieved by an offset practice of that type exceeded a relevant activity baseline, including methods for monitoring and accounting for uncertainty.
- (D) LEAKAGE.—A standardized methodology for accounting for and mitigating potential leakage, if any, from an offset practice of that type, taking uncertainty into account, excluding international indirect land use changes unless a positive determination is made under section 211(o)(13)(C)(iii) of the Clean Air Act.
 - (b) Special Considerations.—
- (1) EXISTING OFFSET PRACTICES.—In establishing the methodologies under subsection (a), the Secretary shall give due consideration to methodologies for offset practices existing as of the date of the enactment of this title.
- (2) CERTAIN FACTORS.—As part of the methodologies established under subsection (a), the Secretary shall establish a formula that takes into account the components of the practice, the characteristics of the land on which the practice is applied, the crop produced, and such other factors as determined appropriate by the Secretary.
 - (c) Accounting for Reversals.—
- (1) IN GENERAL.—Except as provided in subsection (d) with respect to issuance of a term offset credit, for each type of practice listed under section 503, the Secretary shall establish requirements to account for and address reversals, including—
- (A) a requirement to report any reversal with respect to an offset practice for which offset credits have been issued under this title:
- (B) provisions to require emission allowances or offset credits to be held in amounts to fully compensate for greenhouse gas emissions attributable to reversals, and to assign responsibility for holding such emission allowances; and
- (C) any other provisions that the Secretary determines to be necessary to account for and address reversals.
 - (2) MECHANISMS.—
- (A) IN GENERAL.—The Secretary shall prescribe mechanisms to ensure that any sequestration of greenhouse gases, with respect to which an offset credit is issued under this title, results in a permanent net increase in sequestration of greenhouse gases, and that full account is taken of any actual or potential reversal of such sequestration, with an adequate margin of safety.
- (B) SPECIFIC MECHANISMS.—The Secretary shall make available one or more of the following mechanisms to meet the requirements of this paragraph:
- (i) An offsets reserve, pursuant to paragraph (3).
- (ii) Insurance that provides for purchase and provision to the Secretary for retire-

- ment of a quantity of offset credits or emission allowances equal in number to the tons of carbon dioxide equivalents of greenhouse gas emissions released due to reversal.
- (iii) Another mechanism if the Secretary determines it is necessary to satisfy the requirements of this title, taking into account whether the reversal was intentional or unintentional.
 - (3) Offsets reserve.—
- (A) IN GENERAL.—An offsets reserve referred to in paragraph (2)(B)(i) is a program under which, before issuance of offset credits under this title, the Secretary shall—
- (i) subtract and reserve from the quantity to be issued a quantity of offset credits based on the risk of reversal:
- (ii) hold those reserved offset credits in the offsets reserve; and
- (iii) register the holding of the reserved offset credits in an offset registry.
 - (B) PRACTICE REVERSAL.—
- (i) In GENERAL.—If a reversal has occurred with respect to an offset practice within an offset project, for which offset credits are reserved under this paragraph, the Secretary shall retire offset credits from the offsets reserve to fully account for the tons of carbon dioxide equivalent that are no longer sequestered.
- (ii) INTENTIONAL REVERSALS.—If the Secretary determines that a reversal was intentional, the offset practice developer for the relevant offset practice shall place into the offsets reserve a quantity of offset credits, or combination of offset credits and emission allowances, equal in number to the number of reserve offset credits that were retired pursuant to clause (i).
- (iii) Unintentional REVERSALS.—If the Secretary determines that a reversal was unintentional, the offset project developer for the relevant offset project shall place into the offsets reserve a quantity of offset credits, or combination of offset credits and emission allowances, equal in number to half the number of offset credits that were reserved for that offset project, or half the number of reserve offset credits that were canceled due to the reversal pursuant to clause (i), whichever is less, except that the Secretary may lower this amount based on undue hardship in the event of a catastrophic occurrence.
- (C) USE OF RESERVED OFFSET CREDITS.—Offset credits placed into the offsets reserve under this paragraph may not be used to comply with section 722 of the Clean Air Act.
 - (d) TERM OFFSET CREDITS.—
- (1) APPLICABILITY.—With respect to a practice listed under section 503 that sequesters greenhouse gases and has a crediting period of no more than five years, the Secretary may address reversals pursuant to this subsection in lieu of permanently accounting for reversals pursuant to subsection (c).
- (2) ACCOUNTING FOR REVERSALS.—For such practices or projects implementing such practices, the Secretary shall require only reversals that occur during the crediting period to be accounted for and addressed pursuant to subsection (c).
- (3) CREDITS ISSUED.—For practices or projects regulated pursuant to paragraph (2), the Secretary shall issue under section 507 a term offset credit, in lieu of an offset credit, for each ton of carbon dioxide equivalent that has been sequestered.
 - (e) CREDITING PERIODS.-
- (1) IN GENERAL.—For each offset practice type within an offset project, the Secretary shall specify a crediting period, and establish provisions for reenrollment for a subsequent crediting period, in accordance with this subsection.
- (2) DURATION.—The crediting period shall have a term of up to—

- (A) 5 years for agricultural sequestration practices;
- (B) 20 years for forestry sequestration practices; and
- (C) 10 years for other practice types that reduce or avoid greenhouse gas emissions or sequester greenhouse gases.
- (3) ELIGIBILITY.—An offset practice, within an offset project, shall— $\,$
- (A) be eligible to generate offset credits under this title only during the crediting period of the offset practice; and
- (B) remain eligible to generate offset credits, only during the crediting period, subject to the methodologies and practice type eligibility list that applied as of the date of the project approval.
- (4) REENROLLMENT FOR SUBSEQUENT CREDITING PERIOD.—
- (A) REENROLLMENT AUTHORIZED; TIME FOR REENROLLMENT.—An offset project developer may reenroll for a subsequent crediting period, to commence after termination of the current crediting period, subject to the methodologies and practice type eligibility list in effect at the time of reenrollment. Reenrollment may not occur more than 18 months before the end of the crediting period then in effect.
- (B) LIMITATION.—The Secretary may limit the number of subsequent crediting periods available for a particular practice type.
- (f) ENVIRONMENTAL INTEGRITY.—In establishing the requirements under this section, the Secretary shall apply conservative assumptions or methods to ensure the environmental integrity of the cap established under section 703 of the Clean Air Act is not compromised.

SEC. 505. PROJECT PLAN SUBMISSION AND APPROVAL.

- (a) PROJECT PLAN REQUIRED.—An offset project developer shall submit to the Secretary an offset project plan for approval.
- (b) REQUIREMENTS.—As part of the regulations promulgated under this title, the Secretary shall include provisions for, and shall specify, the required components of an offset project plan, including—
- (1) designation of an offset project developer;
- (2) a list and schedule of the practices to be implemented;
- (3) any other information that the Secretary considers to be necessary—
- (A) to determine whether the offset practice, within the offset project, is eligible for issuance of offset credits under regulations promulgated under this title; and
 - (B) to achieve the purposes of this title.
- (c) TIME FOR CONSIDERATION; NOTIFICATION.—Not later than 90 days after receiving a complete offset project plan under subsection (a), the Secretary shall—
- (1) approve the plan in writing and include an estimate of the offset project credits that will be earned if the plan is implemented, subject to verification of all project-specific variables; or
- (2) if the plan is denied, provide the reasons for denial in writing.
- (d) APPEAL.—The Secretary shall establish procedures for appeal and review of determinations made under this section.
- (e) RESUBMISSION.—After an offset project plan is approved, the offset project developer shall not be required to resubmit a project plan during the crediting period.

SEC. 506. VERIFICATION OF OFFSET PRACTICES.

- (a) IN GENERAL.—As part of the regulations promulgated under this title, the Secretary shall establish requirements to verify—
- (1) that offset practices in an approved offset project plan have been implemented; and
- (2) the quantity of greenhouse gas emission reductions or avoidance, or sequestration of greenhouse gases, resulting from an offset practice and project.

- (b) Verification Reports.—
- (1) IN GENERAL.—The regulations described in subsection (a) shall require an offset project developer to submit a report, prepared by a third-party verifier accredited under subsection (c).
- (2) REQUIREMENTS.—The Secretary shall specify the components of a verification report required under paragraph (1), including—
- (A) the name and contact information for the offset project developer;
- (B) a certification that the project plan has been implemented;
- (C) the quantity of greenhouse gases reduced, avoided, or sequestered;
- (D) a certification establishing that the conflict of interest requirements in the regulations promulgated under this title have been complied with:
- (E) any other information that the Secretary requires to determine the quantity of greenhouse gas emission reduction or avoidance, or sequestration of greenhouse gases, resulting from the offset practice and project; and
- (F) any other information that the Secretary considers to be necessary to achieve the purposes of this title.
 - (c) Verifier Accreditation.—
- (1) In GENERAL.—As part of the regulations promulgated under this title, the Secretary shall establish a process and requirements for periodic accreditation of third-party verifiers for offset credits under this program to ensure that those verifiers are professionally qualified and have no conflicts of interest.
- (2) PUBLIC ACCESSIBILITY.—Each verifier meeting the requirements for accreditation in accordance with this subsection shall be listed in a publicly accessible database, which shall be maintained and updated by the Secretary.

SEC. 507. CERTIFICATION OF OFFSET CREDITS.

- (a) DETERMINATION AND NOTIFICATION.—Not later than 90 days after receiving a complete verification report, the Secretary shall—
- (1) make a determination of the quantity of greenhouse gas emissions that have been reduced or avoided, or greenhouse gases that have been sequestered, by the offset practice in an approved and verified offset project plan; and
- (2) notify the offset project developer in writing of the determination.
- (b) ISSUANCE OF OFFSET CREDITS.—The Secretary shall issue 1 offset credit to an offset project developer for each ton of carbon dioxide equivalent that the Secretary determines has been reduced, avoided, or sequestered during the crediting period. Offset credits may be issued only for greenhouse gas emissions reduced, avoided, or sequestered after January 1, 2009.
- (c) APPEAL.—The Secretary shall establish procedures for appeal and review of determinations made under subsection (a).
- (d) TIMING.—Offset credits meeting the criteria described in subsection (b) shall be issued by the Secretary not later than 14 days after the date on which the Secretary makes a determination under subsection (a).
- (e) REGISTRATION.—The Secretary shall obtain from the Administrator a unique serial number to allow for the registration of each offset credit to be issued under this title.

SEC. 508. OWNERSHIP AND TRANSFER OF OFFSET CREDITS.

- (a) OWNERSHIP.—Initial ownership of an offset credit shall lie with the offset project developer, unless otherwise specified in a legally binding contract or agreement.
- (b) Transferability.—An offset credit issued under this title may be sold, traded, or transferred, unless the offset credit has expired or been retired.

SEC. 509. PROGRAM REVIEW AND REVISION.

- At least once every 5 years, the Secretary shall review and, based on new or updated information and taking into consideration the recommendations of the Advisory Board, update and revise—
- (1) the list of eligible practice types established under section 503;
- (2) the methodologies established, including specific activity baselines, under section 504(a):
- (3) the reversal requirements and mechanisms established or prescribed under subsections (c) and (d) of section 504;
- (4) measures to improve the accountability of the offsets program; and
- (5) any other requirements established under this title to ensure the environmental integrity and effective operation of this title.

SEC. 510. ENVIRONMENTAL CONSIDERATIONS.

- If the Secretary lists forestry practices as eligible offset practice types under section 503, the Secretary, in consultation with appropriate Federal agencies, shall promulgate regulations for the selection and use of species in forestry and other relevant land management-related offset practices—
- (1) to ensure that native species are given primary consideration in such practices;
- (2) to encourage the conservation of biological diversity in such practices;
- (3) to prohibit the use of federally designated or State-designated noxious weeds;
- (4) to prohibit the use of a species listed by a regional or State invasive plant authority within the applicable region or State; and
- (5) in accordance with widely accepted, environmentally sustainable forestry practices.

SEC, 511, AUDITS.

- (a) AUDITS REQUIRED.—The Secretary shall conduct, on an annual basis, random audits of offset projects, offset credits, and the practices of third-party verifiers. At a minimum, the Secretary shall conduct audits each year for a representative sample of practice types and geographical areas.
- (b) ADDITIONAL AUTHORITY.—Nothing in this section prevents the Secretary from conducting any audit the Secretary considers to be necessary.

Subtitle B—USDA Greenhouse Gas Emission Reduction and Sequestration Advisory Committee

SEC. 531. ESTABLISHMENT OF USDA GREEN-HOUSE GAS EMISSION REDUCTION AND SEQUESTRATION ADVISORY COMMITTEE.

Section 1245 of the Food Security Act of 1985 (16 U.S.C. 3854), as added by section 2709 of the Food, Conservation, and Energy Act of 2008 (Public Law 110–246; 122 Stat. 1809), is amended by adding at the end the following new subsection:

- $\lq\lq(f)$ USDA GREENHOUSE GAS EMISSION REDUCTION AND SEQUESTRATION ADVISORY COMMITTEE.—
- "(1) ESTABLISHMENT.—Not later than 30 days after the date of the enactment of the American Clean Energy and Security Act of 2009, the Secretary shall establish an independent advisory committee, to be known as the 'USDA Greenhouse Gas Emission Reduction and Sequestration Advisory Committee', to provide scientific and technical advice on establishing, implementing, and ensuring the overall environmental integrity of an offset program for domestic agricultural and forestry practices that reduce or avoid greenhouse gas emissions, or sequester greenhouse gases.
- "(2) MEMBERSHIP.—The Advisory Committee shall be comprised of nine members, including a chairperson and vice-chairperson, appointed by the Secretary. Each member shall be qualified by education,

training, and experience to evaluate scientific and technical information for domestic agricultural and forestry offset practices that reduce or avoid greenhouse gas emissions or sequester greenhouse gases.

"(3) TERMS.—Terms shall be 3 years in length, except for the initial terms, which may be up to 5 years in length to allow staggered terms. Members may be reappointed only once for an additional 3-year term, and such term may follow directly after a first term.

 $\begin{tabular}{ll} ``(4) & DUTIES.—The & Advisory & Committee \\ shall— & \\ \end{tabular}$

- "(A) provide options and recommendations, not later than 180 days after the date of the enactment of the American Clean Energy and Security Act of 2009, to the Secretary regarding the establishment of methodologies as described in section 504 of such Act, taking into account relevant scientific information, including—
- "(i) the availability of representative data for use in developing an activity baseline for a land area, forest, soil, industry sector, and facility type;
- "(ii) the potential for accurate quanitification of greenhouse gas reduction, or sequestration for an offset practice type;
- "(iii) the potential level of scientific and measurement uncertainty associated with an offset practice type; and
- "(iv) the use of practice methodologies that account for common practice or other direct comparisons within a relevant land area, industry sector, forest, soil, or facility type:
- "(B) make available to the Secretary options and recommendations for the program as a whole and on offset methodologies for each practice type that should be considered under regulations promulgated pursuant to section 504 of the American Clean Energy and Security Act of 2009, including methodologies to address the issues of additionality, activity baselines, measurement, leakage, including the application of sector specific leakage factors, uncertainty, permanence, and environmental integrity:
- "(C) make available to the Secretary advice and comment on areas where further knowledge is required to appraise the adequacy of existing, revised, or proposed methodologies and describe the research efforts necessary to provide the required information:
- "(D) make available to the Secretary advice and comments on other ways to improve or safeguard the environmental integrity of the offset practice types listed under section 503 of the American Clean Energy and Security Act of 2009; and
- $\lq\lq(E)$ provide options and recommendations regarding new practice types.
- "(5) SCIENTIFIC REVIEW OF OFFSET PROGRAM.—Not later than January 1, 2017, and at 5-year intervals thereafter, the Advisory Committee shall—
- "(A) submit to the Secretary and make available to the public an analysis of relevant scientific and technical information regarding agricultural and forestry offset practices that reduce or avoid greenhouse gas emissions or sequester greenhouse gases;
- "(B) review approved and potential practice types, methodologies, scientific studies, offset project monitoring, offset project verification reports, reporting of reversals, audits related to the offset program, and other relevant information needed to evaluate the offset program;
- "(C) evaluate the net emission effects of implemented offset projects; and
- "(D) recommend changes to offset methodologies, procedures, practice types, or the overall program to ensure that—

- "(i) the offset practices result in reduced or avoided greenhouse gas emissions or sequestration of greenhouse gases;
- "(ii) the offset credits issued by the Secretary do not compromise the integrity of the annual emissions reductions established under section 703 of the Clean Air Act; and
- "(iii) the offset program avoids or minimizes adverse affects to human health and the environment.
- "(6) COORDINATION.—To avoid duplication, the Advisory Committee shall coordinate its activities with those of any other Federal advisory committees working in related areas, and shall to the maximum extent possible use research data and services of the research, education, extension agencies of the Department of Agriculture.
- (7) CONSULTATION.—On a periodic basis, the Advisory Committee shall consult with, and be informed by the views of, the Offsets Integrity Advisory Board established under section 731 of the Clean Air Act.
- "(8) MEETING.—The Advisory Committee shall meet on at least a quarterly basis each year.
- "(9) ADMINISTRATIVE SUPPORT AND FUND-ING.—The Secretary may provide such administrative and funding support as necessary to enable the Advisory Committee to carry out its duties under this section.
- "(10) REPORT.—For each fiscal year, the Secretary shall submit to Congress a report on—
- "(A) the status and progress on the offset practices:
- practices;
 "(B) the general status of cooperation and research and development; and
- "(C) the plans for addressing future issues and concerns.".

Subtitle C-Miscellaneous

SEC. 551. INTERNATIONAL INDIRECT LAND USE CHANGES.

Section 211(o) of the Clean Air Act (42 U.S.C. 7545(o)) is amended by adding at the end the following

- ``(13) International indirect land use changes.—
- "(A) EXCLUSION FROM REGULATORY REQUIRE-MENTS REGARDING LIFECYCLE GREENHOUSE GAS EMISSIONS.—Notwithstanding the definition of 'lifecycle greenhouse gas emissions' in paragraph (1)(H), for purposes of determining whether the fuel meets a definition in paragraph (1) or complies with paragraph (2)(A)(i), the Administrator shall exclude emissions from indirect land use changes outside the renewable fuel's feedstock's country of origin.
- "(B) NATIONAL ACADEMIES OF SCIENCE RE-PORT.—(i) Not later than 6 months after the date of enactment of this paragraph, the Administrator and the Secretary of Agriculture shall jointly arrange for the National Academies of Science to review and report on specified issues related to indirect greenhouse gas emissions related to transportation fuels.
- "(ii) The report shall evaluate and report on whether there are economic and environmental models and methodologies that individually, or as a system, can project with reliability, predictability, and confidence—
- "(I) for purposes of determining whether the fuel meets a definition in paragraph (1) or complies with paragraph (2)(A)(1), indirect land use changes that are related to the production of renewable fuels and that may occur outside the country in which the feedstocks are grown, and the impacts of these changes on greenhouse gas emissions; and
- "(II) indirect effects, both domestic and international, related to the production and importation of non-renewable transportation fuels that have significant greenhouse gas emissions, and the impact of these effects on greenhouse gas emissions.

- "(iii) The report shall include a review and assessment of all pertinent scientific studies, methodologies and data, shall evaluate potential methodologies for calculating such emissions (including an evaluation of methods for annualizing emissions associated with forest degradation or land conversion), and shall make appropriate recommendations. The recommendations shall address indirect effects, both domestic and international, related to the production and importation of non-renewable transportation fuels that have significant greenhouse gas emissions. The report shall use appropriate validation procedures, including sensitivity analyses, of how results change as assumptions change. The evaluation shall include for a model, a methodology, or a system of models-
- "(I) an assessment of how reliably the models, methodologies, or systems track actual outcomes over historical periods using available historical data; and
- "(II) an assessment of how reliably the models, methodologies or systems will project future outcomes.
- "(iv) The report shall be publicly available and shall include sufficient information and data such that economists and other scientists with relevant expertise that are not on the National Academies of Science panel can fully evaluate the conclusions of the report.
- "(v) The report shall be completed within three years of the date of enactment of this paragraph.
- "(C) DETERMINATION.—(i) The Administrator and the Secretary of Agriculture shall, after notice and an opportunity for public comment, determine whether, for purposes of determining compliance with the percent reductions in lifecycle greenhouse gas emissions specified in paragraph (1) for various renewable fuels, scientifically valid models and methodologies exist to project indirect land use changes that are related to the production of renewable fuels and that occur outside the country in which the feedstocks are grown, and the impact of these changes on greenhouse gas emissions.
- "(ii) The determination shall take into account the findings and recommendations of the report required under subparagraph (B), as well as other available scientific, economic, and other relevant information. The Administrator and the Secretary may also consider methods used by the Environmental Protection Agency, the Department of Agriculture, and other Federal agencies to assess or guide their related policies.
- (iii) The Administrator and the Secretary of Agriculture shall publish a proposed determination not later than 4 years after date of enactment of this paragraph, and shall publish a final determination not later than 5 years after date of enactment of this paragraph. An explanation and justification of the determination shall be included in the proposed and final actions, together with a response to comments received.
- "(D) RESPONSE TO DETERMINATION.—(i) In the event of a positive determination under subparagraph (C), the Administrator and the Secretary of Agriculture shall, after notice and an opportunity for public comment, by the same date jointly establish a methodology (or methodologies) to calculate greenhouse gas emissions from indirect land use changes that are attributable to the production of renewable fuels and that occur outside the country in which feedstocks are grown for purposes of calculating a renewable fuel's lifecycle greenhouse gas emissions to determine whether the fuel meets a definition in paragraph (1) or complies with paragraph (2)(A)(i). The exclusion in subparagraph (A) shall end, and the Administrator shall issue a regulation by the same

- date that shall include emissions from indirect land use changes outside the renewable fuel's feedstock's country of origin for purposes of calculating a renewable fuel's lifecycle greenhouse gas emissions to determine whether the fuel meets a definition in paragraph (1) or complies with paragraph (2)(A)(i) for renewable fuels sold in the calendar year following the year of the positive determination. The effective date of the regulation shall be six years after the date of enactment of this paragraph.
- "(ii) A negative determination under subparagraph (C) shall include a statement of the basis for the determination.
- "(E) ACCOUNTABILITY.—The joint duties and actions of the Administrator and the Secretary of Agriculture shall be subject to sections 304 and 307 of this Act as if they were the duties and actions of the Administrator alone"

SEC. 552. BIOMASS-BASED DIESEL.

Section 211(o)(2)(A) of the Clean Air Act (42 U.S.C. 7545(o)(2)(A)) is amended by adding at the end the following new clause:

"(v) Grandfathering biomass-based diesel...—The Administrator shall promulgate regulations exempting from the lifecycle greenhouse gas requirements in subparagraphs (B) and (D) of paragraph (1) up to the greater of 1 billion gallons or the volume mandate adopted pursuant to subparagraph (B)(ii) of biomass-based diesel annually from facilities that commenced construction before the date of enactment of the Energy Independence and Security Act of 2007.".

SEC. 553. MODIFICATION OF DEFINITION OF RE-NEWARLE BIOMASS.

- (a) NATIONAL ACADEMY OF SCIENCES REPORT.—Not later than 1 year after the date of enactment of this Act, the Administrator of the Environmental Protection Agency, the Secretary of Agriculture, and the Federal Energy Regulatory Commission shall jointly arrange for the National Academy of Sciences to evaluate how sources of renewable biomass contribute to the goals of increasing America's energy independence, protecting the environment, and reducing global warming pollution.
 - (b) Modification.—
- (1) EPA MODIFICATION AUTHORITY.—After reviewing the report required by subsection (a), the Administrator of the Environmental Protection Agency, in concurrence with the Secretary of Agriculture, may, by regulation and after public notice and comment, modify the non-Federal lands portion of the definition of "renewable biomass" in sections 211(o)(1)(I) and 700 of the Clean Air Act in order to advance the goals of increasing America's energy independence, protecting the environment, and reducing global warming pollution.
- (2) FERC MODIFICATION AUTHORITY.—After reviewing the report required by subsection (a), the Federal Energy Regulatory Commission, in concurrence with the Secretary of Agriculture, may, by regulation and after public notice and comment, modify the non-Federal lands portion of the definition of "renewable biomass" in section 610 of the Public Utility Regulatory Policies Act of 1978 in order to advance the goals of increasing America's energy independence, protecting the environment, and reducing global warming pollution.
 - (c) Federal Lands.—
- (1) SCIENTIFIC REVIEW.—The Secretary of the Interior, the Secretary of Agriculture, and the Administrator of the Environmental Protection Agency shall conduct a joint scientific review, within one year after the date of enactment of this Act, to evaluate how sources of biomass from Federal lands could

contribute to the goals of increasing America's energy independence, protecting the environment, and reducing global warming pollution

(2) Modification authority.—Based on the scientific review, the agencies may, by rule, modify the definition of "renewable biomass" from Federal lands in sections 211(o)(1)(1) and 700 of the Clean Air Act and section 610 of the Public Utility Regulatory Policies Act of 1978 as appropriate to advance the goals of increasing America's energy independence, protecting the environment, and reducing global warming pollution.

The SPEAKER pro tempore. After 3 hours of debate on the bill, as amended. with 21/2 hours equally divided and controlled by the Chair and ranking minority member of the Committee on Energy and Commerce and 30 minutes equally divided and controlled by the Chair and ranking minority member of the Committee on Ways and Means, it shall be in order to consider a further amendment in the nature of a substitute printed in part B of the report, if offered, by the gentleman from Virginia (Mr. FORBES) or his designee, which shall be considered read, and shall be debatable for 30 minutes, equally divided and controlled by the proponent and an opponent.

The gentleman from California (Mr. WAXMAN) and the gentleman from Texas (Mr. BARTON) each will control 1 hour and 15 minutes. The gentleman from New York (Mr. RANGEL) and the gentleman from Michigan (Mr. CAMP) each will control 15 minutes of debate on the bill.

The Chair recognizes the gentleman from California.

GENERAL LEAVE

Mr. WAXMAN. Madam Speaker, I ask unanimous consent that all Members may have 5 legislative days in which to revise and extend their remarks on the legislation under consideration.

The SPEAKER pro tempore. Is there objection to the request of the gentleman from California?

There was no objection.

Mr. WAXMAN. Madam Speaker, I yield myself such time as I may consume.

Today we are taking a decisive and historic action to promote America's energy security and to create millions of clean-energy jobs that will drive our economic recovery and long-term growth.

This bill, when enacted into law, will break our dependence on foreign oil, make our Nation the world leader in clean-energy jobs and technology, and cut global warming pollution. As a result of these new policy settings, we will create millions of clean-energy jobs for America and restore our technological leadership in clean energy. We are also protecting consumers.

The bill tackles big problems that have been ignored for far too long. It proposes solutions that will transform our economic and clean-air environment.

There is a remarkable coalition behind this bill. Electric utilities support

the bill. Manufacturers support the bill. Farmers support the bill, and so do the Nation's leading environmental organizations, labor unions, and faithbased groups.

There are many Members responsible for this remarkable coalition. On the Energy and Commerce Committee. JOHN DINGELL helped forge compromises with the auto industry. RICK BOUCHER developed ideas that will provide a future for coal. MIKE DOYLE addressed the concerns of the steel industry and other trade-vulnerable industries. The chairman of the Ways and Means Committee worked with us to make sure that the interest of low-income families are fully protected. And the chairman of the Agriculture Committee made sure the legislation addresses the concerns of farmers and makes them part of our energy future.

The need to act is clear and urgent. There is a national security imperative to act. This legislation at long last begins to break our addiction to imported foreign oil and put us on a path to true energy security.

There is a scientific imperative to act. The evidence on global warming, on the consequences of carbon emission is overwhelming, and we have based our bill on the science. And there is a moral imperative to act. We have obligations to protect and preserve the environment for our children and the generations that follow.

And there is an economic imperative to act. This legislation is an enormous jobs bill for America. It will promote investment and growth for decades ahead, creating jobs for the new-energy economy of the 21st century.

People in industry have told us that as soon as this legislation becomes law, we will find billions of dollars invested in infrastructure over the next 5 years. We can see an incredible lost opportunity if we don't act now. There are amazing developing new technological centers around the U.S., and we can see those jobs going overseas and that technological superiority going overseas as well.

And this bill is affordable. Contrary to what we will hear from our friends on the other side of the aisle, the Congressional Budget Office found that this legislation will cost households an average of only \$175 in 2020, less than 50 cents a day. EPA's analysis put the cost at 22 to 30 cents a day, less than the cost of a single postage stamp, while lowering utility bills by 7 percent.

This bill is a tremendous opportunity to prevent a dangerous threat while creating millions of new jobs and driving economic growth. It will end our dependence on foreign oil and keep us more secure. This bill will drive a new era of sustainable growth and innovation, and I urge all Members to support it.

House of Representatives, Committee on the Judiciary, Washington, DC, June 24, 2009.

Hon. HENRY A. WAXMAN,

Chairman, Committee on Energy and Commerce, House of Representatives, Washington, DC. DEAR CHAIRMAN WAXMAN: This is to advise

DEAR CHAIRMAN WAXMAN: This is to advise you that, as a result of your having consulted with us on provisions in H.R. 2454, the American Clean Energy and Security Act of 2009, that fall within the rule X jurisdiction of the Committee on the Judiciary, we are able to agree to waive seeking any formal referral of the bill, in order that it may proceed without delay to the House floor for consideration.

The Judiciary Committee takes this action with the understanding that by forgoing further consideration of H.R. 2454 at this time, we do not waive any jurisdiction over subject matter contained in this or similar legislation. We reserve the right to seek appointment of an appropriate number of conferees to any House-Senate conference involving this important legislation, and request your support if such a request is made.

I would appreciate your including this letter in the Congressional Record during consideration of the bill on the House floor. Thank you for your attention to our requests, and for the cooperative relationship between our two committees.

Sincerely.

JOHN CONYERS, JR.

Chairman.

HOUSE OF REPRESENTATIVES, COM-MITTEE ON SCIENCE AND TECH-NOLOGY.

Washington, DC, June 19, 2009.

Hon. Henry A. Waxman,

Chairman, Committee on Energy and Commerce, House of Representatives, Rayburn House Office Building, Washington, DC.

DEAR CHAIRMAN WAXMAN: I write to you regarding H.R. 2454, the American Clean Energy and Security Act of 2009. This legislation was initially referred to the Committee on Energy and Commerce and in addition to the Committees on Foreign Affairs, Financial Services, Education and Labor, Science and Technology, Transportation. and-Infrastructure, Natural Resources, Agriculture, and Ways and Means.

H.R. 2454 was reported to the House by the Committee on Energy and Commerce on June 5, 2009. I recognize and appreciate your desire to bring this legislation before the House in an expeditious manner, and, accordingly, I will waive further consideration of this bill in Committee. However, agreeing to waive consideration of this bill should not be construed as the Committee on Science and Technology waiving its jurisdiction over H.R. 2454.

Further, I request your support for the appointment of Science and Technology Committee conferees during any House-Senate conference convened on this, or any similar legislation. I also ask that a copy of this letter and your response be placed in the Congressional Record during consideration of this bill on the House floor.

I look forward to working with you as we prepare to pass this important legislation.

Sincerely,

BART GORDON,
Chairman.

HOUSE OF REPRESENTATIVES,
COMMITTEE ON ENERGY AND COMMERCE,
Washington, DC, June 24, 2009.
Hon. BART GORDON,

Chairman, House Committee on Science and Technology, Washington, DC.

DEAR CHAIRMAN GORDON: Thank you for your letter regarding H.R. 2454, the "American Clean Energy and Security Act of 2009."

The letter noted that certain provisions of the bill are within the jurisdiction of the Committee on Science and Technology under rule X of the Rules of the House.

The Committee on Energy and Commerce recognizes the jurisdictional interest of the Committee on Science and Technology in these provisions. We appreciate your agreement to forgo action on the bill, and I concur that this agreement does not in any way prejudice the Committee on Science and Technology with respect to the appointment of conferees or its jurisdictional prerogatives on this bill or similar legislation in the future

I will include our letters in the Congressional Record during consideration of the bill on the House floor. Again I appreciate your cooperation regarding this important legislation.

Sincerely,

HENRY A. WAXMAN.

HOUSE OF REPRESENTATIVES, COMMITTEE ON ENERGY AND COMMERCE, Washington, DC, June 25, 2009.

Hon. EDOLPHUS TOWNS,

Chairman, House Committee on Oversight and Government Reform, Washington DC.

DEAR CHAIRMAN TOWNS: Thank you for your letter regarding H.R. 2454, the "American Clean Energy and Security Act of 2009." The letter noted that provisions of the bill are within the jurisdiction of the Committee on Oversight and Government Reform under rule X of the Rules of the House.

The Committee on Energy and Commerce recognizes the jurisdictional interest of the Committee on Oversight and Government Reform in these provisions. We appreciate your agreement to work with us without sequential referral, and I concur that this agreement does not in any way prejudice the Committee on Oversight with respect to its jurisdictional prerogatives on this bill or similar legislation in the future. I also agree to support a request by the Committee with respect to serving as conferees on the bill, consistent with the Speaker's practice in this regard.

I will include our letters in the Congressional Record during consideration of the bill on the House floor. Again I appreciate your cooperation regarding this important legislation.

Sincerely,

HENRY A. WAXMAN, Chairman.

HOUSE OF REPRESENTATIVES, COM-MITTEE ON OVERSIGHT AND GOV-ERNMENT REFORM,

Washington, DC, June 25, 2009.

Hon. HENRY A. WAXMAN,

Chairman, House Committee on Energy and Commerce, Rayburn House Office Building, Washington, DC.

DEAR CHAIRMAN WAXMAN: I am writing regarding H.R. 2454, the "American Clean Energy and Security Act of 2009". I appreciate your commitment and willingness to work with the Committee on Oversight and Government Reform on the provisions of H.R. 2454 that fall within the Oversight Committee's jurisdiction. These provisions include matters such as, but not limited to, federal procurement requirements and the elevation of the Inspector General of the Commodity Futures Trading Commission.

In the interest of expediting consideration of H.R. 2454, the Oversight Committee agreed to work with you on these provisions without a sequential referral of the bill. This should not be construed as a waiver of the Oversight Committee's legislative jurisdiction over subjects addressed in H.R. 2454 that fall within the jurisdiction of the Committee.

The Committee maintains its interest in any provisions of the bill that are within the Committee's jurisdiction. I therefore request your support for the appointment of conferees from the Oversight Committee should H.R. 2454 or a similar bill be considered in conference with the Senate.

I also respectfully request that you include our exchange of letters on this matter in the Congressional Record during consideration of this legislation on the House floor.

Thank you for your attention to these matters.

Sincerely,

EDOLPHUS TOWNS, Chairman.

HOUSE OF REPRESENTATIVES, COMMITTEE ON ENERGY AND COMMERCE, Washington, DC, June 26, 2009.

Hon. HOWARD L. BERMAN,

Chairman, House Committee on Foreign Affairs, Washington DC.

DEAR CHAIRMAN BERMAN: Thank you for your letter regarding H.R. 2454, the "American Clean Energy and Security Act of 2009." The letter noted that certain provisions of the bill are within the jurisdiction of the Committee on Foreign Affairs under rule X of the Rules of the House.

The Committee on Energy and Commerce recognizes the jurisdictional interest of the Committee on Foreign Affairs in these provisions. We appreciate your agreement to forgo action on the bill, and I concur that this agreement does not in any way prejudice the Committee on Foreign Affairs with respect to its jurisdictional prerogatives on this bill or similar legislation in the future. I also agree to support a request by the Committee with respect to serving as conferees on the bill, consistent with the Speaker's practice in this regard.

I will include our letters in the Congressional Record during consideration of the bill on the House floor. Again I appreciate your cooperation regarding this important legislation.

Sincerely,

HENRY A. WAXMAN, Chairman.

HOUSE OF REPRESENTATIVES, COMMITTEE ON FOREIGN AFFAIRS, Washington, DC, June 26, 2009.

Hon. HENRY A. WAXMAN,

Chairman, Committee on Energy and Commerce, Washington, DC.

DEAR MR. CHAIRMAN: I am writing to you concerning H.R. 2454, the American Clean Energy and Security Act of 2009.

This bill contains provisions within the Rule X jurisdiction of the Committee on Foreign Affairs. In the interest of permitting your Committee to proceed expeditiously to floor consideration of this important bill, I am willing to waive this Committee's right to mark up this bill. I do so with the understanding that by waiving consideration of the bill, the Committee on Foreign Affairs does not waive any future jurisdictional claim over the subject matters contained in the bill which fall within its Rule X jurisdiction.

Further, I request your support for the appointment of Foreign Affairs Committee conferees during any House-Senate conference convened on this legislation. I would ask that you place this letter into the Congressional Record during floor consideration of H.R. 2454.

I look forward to working with you as we move this important measure through the legislative process.

Sincerely,

 $\begin{array}{c} \text{Howard L. Berman,} \\ \textbf{\textit{Chairman.}} \end{array}$

House of Representatives, Committee on Energy and Commerce, Washington, DC, June 26, 2009.

Hon. HOWARD L. BERMAN,

Chairman, House Committee on Foreign Affairs, Washington DC.

DEAR CHAIRMAN BERMAN: Thank you for your letter regarding H.R. 2454, the "American Clean Energy and Security Act of 2009." The letter noted that certain provisions of the bill are within the jurisdiction of the Committee on Foreign Affairs under rule X of the Rules of the House.

The Committee on Energy and Commerce recognizes the jurisdictional interest of the Committee on Foreign Affairs in these provisions. We appreciate your agreement to forgo action on the bill, and I concur that this agreement does not in any way prejudice the Committee on Foreign Affairs with respect to its jurisdictional prerogatives on this bill or similar legislation in the future. I also agree to support a request by the Committee with respect to serving as conferees on the bill, consistent with the Speaker's practice in this regard.

I will include our letters in the Congressional Record during consideration of the bill on the House floor. Again I appreciate your cooperation regarding this important legislation.

Sincerely,

HENRY A. WAXMAN, Chairman.

HOUSE OF REPRESENTATIVES, COM-MITTEE ON SCIENCE AND TECH-NOLOGY,

Washington, DC, June 25, 2009.

Hon. Henry A. Waxman,

 ${\it Chairman, Committee \ on \ Energy \ and \ Commerce,} \\ {\it Washington, DC.}$

DEAR CHAIRMAN WAXMAN: I write to you regarding Congressman Boccieri's amendment to the amendment in the nature of a substitute to H.R. 2454, the American Clean Energy and Security Act of 2009.

It is my understanding that you are seeking my support to have this amendment made in order for floor consideration. I will support this amendment being made in order, but only with the understanding that the programs contained in this amendment are within the sole jurisdiction of the Committee on Science and Technology based on our Rule X jurisdiction over the National Institutes of Standards and Technology. In addition, I ask for your commitment that the Science and Technology Committee will be given deference in any House-Senate conference on any matters relating to this provision or any similar provision.

I look forward to working with you as we prepare to pass this important legislation.

 ${\bf Sincerely,}$

 $\begin{array}{c} \text{Bart Gordon,} \\ \textit{Chairman.} \end{array}$

House of Representatives, Committee on Energy and Commerce, Washington, DC, June 25, 2009.

Hon. BART GORDON,

Chairman, Committee on Science and Technology, Washington, DC.

DEAR CHAIRMAN GORDON: Thank you for your letter regarding Congressman Boccieri's amendment to the amendment in the nature of a substitute to H.R. 2454, the American Clean Energy and Security Act of 2009

I agree that the programs contained within this amendment would receive an exclusive referral to the Committee on Science and Technology. I also agree that the inclusion of this provision in H.R. 2454 should not be construed to give the Committee on Energy and Commerce a jurisdictional claim to the provision. In addition, I agree to defer to the

Science and Technology Committee in any House-Senate conference on any matters relating to this provision or any similar provision

I appreciate your support of this amendment, and I appreciate your cooperation regarding this important legislation.

Sincerely.

HENRY A. WAXMAN,

Chairman. I reserve the balance of my time.

Mr. BARTON of Texas. Madam Speaker, I ask unanimous consent that the ranking member of the Agriculture Committee, the gentleman from Oklahoma (Mr. Lucas), control the first 15 minutes of debate on the minority side.

The SPEAKER pro tempore. Is there objection to the request of the gentleman from Texas?

There was no objection.

Mr. LUCAS. Madam Speaker, I thank the gentleman from Texas, and I yield myself such time as I may consume.

The Waxman-Markey bill promises to destroy our standard of living and the quality of life with higher energy costs, higher food prices, and lost jobs. The bill is the single largest economic threat to our farmers and ranchers in decades. We have more than 115 agricultural and food groups who publicly oppose this bill as of today, and I ask that the list be entered in the RECORD.

Do you know why? The greatest threat to our agricultural producers is ignored. Under H.R. 2454, input costs will escalate as a direct result of the energy tax. Meanwhile, the markets for their crops will shrink because of fortheir crops whose governments will not place burdens on their farmers. They will be able to undersell us.

And what about the billions of dollars annually that farmers are supposed to garner selling offset credits? Many farmers will not be able to participate. Soil sequestration of carbon was going to be the way for farmers to generate credits, but if the producer started soil tillage practices before 2001, they will be ineligible to participate.

The amendment does not exempt agriculture from performance standards in the bill, which means the EPA could tell our producers how to manage their farms.

This bill will tax you. This bill will destroy the livelihoods of those who live and work in rural America, those who work every day to consistently provide our Nation and the world with a safe, affordable, abundant food and fiber supply. Agriculture sits squarely in the crosshairs of this bill because it is energy intensive. Whether it is the fuel for the tractor, the fertilizer for the crops, or the delivery of food to the grocery store, agriculture uses a great deal of energy throughout production and processing.

Although USDA hasn't devoted any time or resources to complete an economic analysis of how this bill will impact farmers, the Heritage Foundation has. A recent study from the Heritage Foundation revealed that by the year 2035, the average net income for farms

will be decreased by 57 percent. And also by 2035, gasoline and diesel costs are expected to be 58 percent higher and electric rates 90 percent higher. For example, residents in Oklahoma can expect their electric rates to increase by \$300 million.

So why are we doing this bill? So the U.S. can lead on climate change in the world? We can lead when China and India have refused to participate? We can lead when Europe is willing to do half of what this bill calls for? We can lead when the rest of the developing world is unable to do anything at all about climate change?

Some of my idealistic colleagues will say we have to set a standard for the rest of the world. But I say I will not make any constituents poor—poorer—so that others can get richer at our expense. My friends, this is the wrong bill at the wrong time for the wrong reason.

Madam Speaker, I reserve the balance of my time.

Mr. WAXMAN. Madam Speaker, at this time I am delighted to yield to the gentleman from Massachusetts (Mr. MARKEY), the chairman of the Subcommittee on Energy and the Environment as well as the Select Committee on Global Warming. He has played the fundamental role of shepherding this bill through our committee and working to get it to the floor today. I yield to Mr. MARKEY 3 minutes.

Mr. MARKEY of Massachusetts. I thank the gentleman from California, and I thank him and his staff for the outstanding leadership and vision which he has provided on this legislation. This is the culmination of a career of work for the gentleman from California, and it is my honor to have been allowed to partner with him in order to construct this legislation that we bring to the floor here today.

I want to thank, as the gentleman from California has noted, the other Members who have worked on this legislation: Mr. DINGELL, Mr. BOUCHER, Mr. DOYLE, Mr. INSLEE, Mr. GREEN, Mr. BUTTERFIELD, Mr. STUPAK, Mr. RUSH. So many Members, including Members off the committee like HENRY CUELLAR from the State of Texas who worked with us on natural gas-related issues. We would not be here unless we had the cooperation of so many Members across the full spectrum of the House.

During this process, we have received valuable input and expertise from other leaders in the House, like Chairman RANGEL on trade issues, Chairman PETERSON on agriculture issues, amongst, again, many others.

The legislation we have before us today is the most important energy and environment legislation to ever have been considered in the history of the United States. The consequences for our country are great unless we act to deal with these issues.

This legislation sets a new course for our country, creating millions of new, clean-energy jobs while reducing our dependence upon imported oil. And when it becomes law, and it will, for the first time in the history of the United States Congress, for the first time in the history of our country, we will put enforceable limits on global warming pollution.

At its core, however, this is a jobs bill. It will create millions of new, clean-energy jobs in whole new industries with incentives to drive competition in the energy marketplace. It sets ambitious and achievable standards for energy efficiency and renewable energy from solar, wind, geothermal, biomass so that by 2020, 20 percent of America's energy will be clean.

It saves consumers money by updating efficiency standards for new buildings, appliances, and lighting systems. It invests \$10 billion a year in energy efficiency programs in States across this country.

The SPEAKER pro tempore. The gentleman's time has expired.

Mr. WAXMAN. Madam Speaker, I yield the gentleman an additional minute.

Mr. MARKEY of Massachusetts. And it starts the much-needed process of making our electric grid a smart grid so we can plug in the hybrid and electric cars of the future into an advanced, efficient energy network that by the year 2030 we will be raising a generation of children who know not how to receive gasoline at a gasoline station but, rather, by plugging their cars into a plug so that the electricity that we are generating ensures that those vehicles are being run for the benefit of our people.

This is a revolution. This is a moment in history. This is what the American people were calling for in the election of 2008, a fundamental change that breaks our dependence upon imported oil, creates millions of new jobs, reduces the amount of pollution that we send up into the atmosphere, and points us in a new direction in our country that breaks with the pattern of cyclical dependence on imported oil coming from OPEC that holds our Nation hostage.

I urge an "aye" vote on this bill.

Madam Speaker, I rise in strong support of H.R. 2454, the Waxman-Markey American Clean Energy and Security Act.

I want to start by thanking the Chairman of the Energy and Commerce Committee and my partner in this legislation, HENRY WAXMAN. He and I and our staffs have worked tirelessly on this bill, and his leadership, patience and fortitude have been remarkable.

And I want to thank all of my Energy and Commerce colleagues, especially RICK BOUCHER, JOHN DINGELL, MIKE DOYLE, JAY INSLEE, GENE GREEN, GK BUTTERFIELD, BART STUPAK and so many others. And special thanks to Speaker NANCY PELOSI on her outstanding leadership on these issues since she became Speaker.

And during this process we have received valuable input and expertise from other leaders in the House like Chairman RANGEL on trade issues and Mr. PETERSON on agriculture issues

The legislation we have before us today is the most important energy and environmental legislation in the history of our country. It sets a new course for our country, one that steers us away from foreign oil and towards a path of clean American energy.

It will create millions of new clean energy jobs while reducing our dependence on foreign oil.

And when it becomes law, it will, for the first time in the history of the United States Congress, put enforceable limits on global warming pollution.

I also want to take time to commend my colleague JOHN MCHUGH for his outstanding leadership on acid rain and air pollution control.

His state and my state both share a common problem of transported air pollution which falls in New York and New England as acid rain.

JOHN MCHUGH has worked tirelessly to protect public health and the environment from the deleterious effects of air pollution, especially the problems of acid rain and toxic mercury pollution.

Reducing emissions of greenhouse gases must be done immediately to stop global warming, but we must also continue to reduce emissions of NO_x SO_x and mercury.

The technologies that we will use to reduce global warming pollution will also reduce other pollutants that kill our citizens and damage our environment.

We need to get the programs, including the Clean Air Interstate Rule and facility-specific mercury regulations, back on track.

Representative MCHUGH has introduced H.R. 1841, legislation that would help protect public health and fight acid rain.

That legislation describes well the problems we face today in fighting acid rain, soot and smog and sets forth thoughtful solutions to those problems. I agree with the gentleman

(1) reductions of atmospheric sulfur dioxide and nitrogen oxide from utility plants, in addition to the reductions required under the Clean Air Act (42 U.S.C. 7401 et seq.), are needed to reduce acid deposition and its serious adverse effects on public health, natural resources, building structures, sensitive ecosystems, and visibility; (2) sulfur dioxide and nitrogen oxide contribute to the development of fine particulates, suspected of causing human mortality and morbidity to a significant extent; (3) regional nitrogen oxide reductions of 75 percent in the Eastern United States, in addition to the reductions required under the Clean Air Act, may be necessary to protect sensitive watersheds from the effects of nitrogen deposition; (4) since the Clean Air Act Amendments of 1990 were enacted, some acidic lakes in the Adirondacks in the State of New York have started to slowly show chemical recovery from acid rain, demonstrating that sulfur dioxide and nitrogen oxide regulations can be implemented in a cost-effective manner, but the recovery is progressing at a slower rate than originally intended; (5) nitrogen oxide is highly mobile and can lead to ozone formation hundreds of miles from the emitting source; (6) on March 10, 2005, the Environmental Protection Agency (EPA) issued the Clean Air Interstate Rule (CAIR) to require additional reductions in sulfur dioxide and nitrogen oxide in 28 Eastern States and the District of Columbia; (7) these reductions represent approximately a 70 percent reduction in sulfur dioxide and a 60 percent reduc-

tion in nitrogen oxide in the affected States; (8) on July 11, 2008, the United States Court of Appeals for the District of Columbia Circuit vacated CAIR and on December 23, 2008, the same court remanded the rule back to the EPA without vacature; (9) fossil fuel-fired electric generating units emit approximately 1/3 of the total mercury emissions in the United States; (10) mercury is considered a neurotoxin which can bioaccumulate as it moves its way up the food chain and is especially harmful to young children and developing fetuses; (11) according to the EPA, there were 3.080 fish advisories for mercury in 2006; there are over 90 fish advisories for mercury in New York alone, with blanket warning for the Adirondack and Catskill Mountains: (12) on March 15, 2005, EPA issued the Clean Air Mercury Rule (CAMR), which for the first time sought to regulate mercury emissions from power plants, but used a less restrictive cap-and-trade approach for this very harmful substance and would take a full decade to implement; (13) on February 8, 2008, the United States Court of Appeals for the District of Columbia Circuit vacated CAMR: and (14) on February 23, 2009, the Supreme Court denied a request to reconsider the decision.

This bill includes a study on the effects of different carbon reduction strategies on reducing emissions of NO_X , SO_X and mercury. Such a study will ensure that as we move to control greenhouse gas emissions, particularly from coal fired power plants that emit mercury, NO_X and SO_X , we do not lose the opportunity to implement the most cost effective ways of controlling soot, smog and mercury.

This is exactly the type of very thoughtful work that JOHN MCHUGH has done during his many years in Congress to protect public health and fight acid rain and I am proud to stand beside this champion of environmental protection as we move to pass this legislation.

At its core, this is a jobs bill. It will create millions of new, clean energy jobs in whole new industries with incentives to drive competition in the energy marketplace.

It sets ambitious and achievable standards for energy efficiency and renewable energy from solar, wind, geothermal and biomass, so that by 2020, 20 percent of America's energy will be clean.

It saves consumers money by updating efficiency standards for our new buildings and the appliances and lighting systems we use. It invests \$10 billion a year in energy efficiency programs in states across the country.

And it starts the much-needed process of making our electric grid a Smart Grid, so we can plug in the hybrid and electric cars of the future into an advanced, efficient, domestically-powered energy network that will give consumers more control of their power bill.

It makes nearly \$200 billion in investments in clean energy technologies, including \$20 billion in vital clean energy research and development.

And it does all this while nearly doubling the size of the economy by 2030, remaining budget neutral, and costing the average American family less than a postage stamp a day—a small price to pay as we transition off foreign oil once and for all.

By bringing competition and efficiency back to the energy marketplace, Waxman-Markey will deliver consumer savings. America's low-income families will actually benefit by \$40 a year in 2020, and the energy efficiency poli-

cies alone will save American families more than \$200 every year by 2030.

This bill address a technological imperative to lead on clean energy, the economic imperative to compete in a global clean energy race, and the moral imperative to protect our planet and the rights of all to live and prosper for generations to come.

This bill has the goals of the moon landing, the moral imperative of the Civil Rights Act, and the scope of the Clean Air Act, wrapped up in one.

I believe this is the most important vote we will take in our lives. The entire world is watching us. Our children and grandchildren are watching us. We have a choice to make and the fate of the planet hangs in the balance.

We cannot afford to be governed by fear and cling to the failed policies that have brought us to this crisis. As the President said yesterday: "We cannot be afraid of the future, and we can't be prisoners of the past."

Scientists say that global warming is a dangerous man-made problem.

Today we are saying clean energy will be the American-made solution.

This is an historic bill. This is a historic vote. This is a historic choice.

I urge my colleagues to support the Waxman-Markey American Clean Energy and Security Act. Vote "aye."

□ 1300

Mr. LUCAS. Madam Speaker, I recognize the gentleman from Virginia (Mr. GOODLATTE) for 2 minutes.

(Mr. GOODLATTE asked and was given permission to revise and extend his remarks.)

Mr. GOODLATTE. Madam Speaker, I rise in strong opposition to this bill.

I agree with one thing the gentleman from Massachusetts had to say and, that is, this bill has very important consequences, but those consequences are devastating for the future of the economy of this country, and it's in pursuit of the fantasy of thinking that this legislation will cause us to be able to turn down the thermostat of the world by reducing ${\rm CO}_2$ gas emissions when China and India and other nations are pumping more and more ${\rm CO}_2$ gas into the atmosphere all the time.

We would be far better served with legislation that devotes itself to developing new technologies before we slam the door on our traditional sources of energy like coal and oil and natural gas and nuclear power, the most CO₂-free emission that we have; and this bill does nothing to promote it.

It stifles the ability of the people of this country to have the kind of competitiveness they need in the world to be able to get inexpensive sources of energy. So I strongly oppose this legislation.

You know, we, Republicans and Democrats, offered over 200 amendments to try to improve this bill. They made in order one. In shutting down this democratic process, the Speaker of the House has taken away the voice of the American people. The simple truth behind this legislation is it raises taxes, kills jobs, and will lead to more government intrusion.

It is estimated this bill will raise electricity rates 90 percent, gasoline prices 74 percent, natural gas prices 55 percent—and that's in addition to the expected rise in all of those sources of energy because this Congress, for the last 2½ years, has refused to take up a real American energy plan to devote more to producing domestic sources of all of our traditional sources of energy and developing new sources.

We support the effort for energy efficiency. We support the effort to promote new and alternative forms of energy. We do not support this kind of suicide for the American economy.

I urge my colleagues to oppose this legislation.

It would be true democracy to allow the people's representatives to have a say about what is in this legislation. However, committees with jurisdiction, including the Agriculture Committee, were not allowed to mark-up the bill and make changes.

The simple truth behind this legislation—it raises taxes, kills jobs and will lead to more government intrusion. Many have said the "Peterson compromise" is a win for farmers. Let me be clear, this legislation is not a win for American famers. Agriculture is an energy intensive industry, and this legislation will make the cost of energy even higher for everyone.

In effect this legislation turns off the ability to produce energy from reliable sources in favor of energy technologies that have not proven that they can meet the energy demands of our nation. We cannot ignore that America's economy is intrinsically linked to the availability and affordability of energy. During this economic slow-down we should adopt policies that seek to rebuild our economy and create more jobs. We need reliable and affordable energy supplies. Unfortunately, cap and trade legislation would only further cripple our economy.

Mr. WAXMAN. Madam Speaker, I want to yield now to the gentleman who had been the chairman of the Energy Subcommittee on our full committee last Congress and who was instrumental in getting the first draft of the legislation that we worked off, but more importantly, as a knowledgeable individual of this area and from a constituency that has a special concern about the problems, he was able to negotiate with us so that we could reach some of the accommodations in this legislation that has made it a much better bill.

I yield, with great admiration, 5 minutes to the gentleman from Virginia (Mr. BOUCHER).

(Mr. BOUCHER asked and was given permission to revise and extend his remarks.)

Mr. BOUCHER. I thank the gentleman from California for yielding and congratulate him on the tremendous leadership that he has shown in bringing this measure to the House floor this afternoon.

Madam Speaker, I rise in strong support of the bill, and I urge its approval

by the House. It achieves broad reductions in greenhouse gases, enhances America's energy security, and by placing a price on carbon dioxide emissions, will unleash investments in clean-energy technologies that will create millions of new American jobs.

These energy technologies will evolve from America's laboratories; they will be deployed at home; they will be exported around the world; they will be the foundation for our next technology revolution. And it all starts here with passage today of the Clean Energy Security Act.

Approximately 80 percent of the electricity in the district that I represent is coal-generated. Coal production is one of our region's major industries, and it is a major employer of our constituents. Not surprisingly, my focus in the shaping of the bill in the Energy and Commerce Committee was to keep electricity rates affordable and to enable utilities to continue using coal, which accounts for fully 51 percent of America's electricity generation. Both of these goals have been achieved in the bill that is before us today.

Electricity rates will be only modestly affected. The nonpartisan Congressional Budget Office says that by 2020, the cost of the entire program for the typical American family will be \$175 per year. The Environmental Protection Agency projects that the nearer-term cost for the typical family from all elements of this legislation will be between \$80 and \$110 per year; that's about 20 cents a day for the typical American family. And so the claims by the opponents that this legislation will impose enormous electricity price increases are simply wrong.

The Environmental Protection Agency projects that by 2020, the usage of coal in our economy will grow as compared to today's usage. Now, that may seem somewhat counterintuitive in a bill that regulates greenhouse gas emissions, so let me repeat that: the EPA projects that by 2020, coal usage in America, under the terms of this bill, will actually grow.

As transportation electrifies and the demand for electricity increases, coal, our most abundant fuel, will still be the fuel of choice to meet that rising demand. The claims of opponents that the $\rm CO_2$ controls under the bill will force utilities to surrender coal use, causing an overreliance on natural gas with attendant broad economic harm to the Nation, are also simply wrong.

This is a responsible measure. It is carefully balanced; it reduces greenhouse gases by 83 percent by the year 2050 as compared to 2005 levels; it keeps electricity rates affordable; it enables coal usage to grow as the demand for electricity increases nationwide; and it opens the door to a more secure energy future and the creation of millions of new jobs, innovating, deploying and exporting to the world the new, low-carbon-dioxide-emitting technologies that will power our energy future.

Now, these are sound reasons to approve the bill; but for those who still harbor doubts, let me make a more practical argument to vote for passage.

In March of 2007, the Supreme Court held that carbon dioxide is a pollutant. Under that ruling, and the terms of the existing Clean Air Act, the Environmental Protection Agency is now effectively required to regulate CO2 emissions, and so Federal regulation for greenhouse gases is now inevitable. It is not a question of whether we are going to have regulation. The only question is whether the regulation will be our carefully balanced, congressionally adopted, economically sustainable regulation, as contained within the bill before us today, or whether we will have EPA's regulation under the blunt instrument of the Clean Air Act where economic considerations cannot be fully waived.

Given that choice, and the path this bill charts for affordable electricity, for increased coal use, and for new job creation, I would urge the Members to make the reasonable decision to approve today the Clean Energy Security Act.

Mr. LUCAS. Madam Speaker, I yield 2 minutes to the gentleman from Kansas (Mr. MORAN).

Mr. MORAN of Kansas. I thank the gentleman for yielding.

Madam Speaker, there is an assertion, a story around Congress today that with the adoption of the Peterson amendment, the negotiations between the chairman of the Agriculture Committee and the chairman of the Commerce Committee, that this bill somehow now becomes acceptable, something advantageous for those of us who represent rural America. I can assure my colleagues, Republican or Democrat, who come from rural America and who represent agricultural interests that nothing could be further from the truth. While the Peterson amendment substantially improves the bill, at least modestly improves the bill, the end result is nothing but something that is disadvantageous and negative for rural economies

Agriculture had thought at one point in time there would be something they could gain from sequestering carbon in the soil, and yet this bill still provides no assurance that the EPA—not the Department of Agriculture, but that the EPA will allow that to occur. If they would, then the Department of Agriculture is involved; but once again, agriculture is not even mentioned in this bill in regard to offsets.

In addition to that, the electric cooperatives are still disadvantaged. If you come from rural America, the allowances that this bill allows are advantages to those who live on the west and east coasts, and yet those of us who represent some of the poor areas of the country, we will be transferring our income and wealth to those coasts.

This bill, in my opinion, is a jobs bill, as indicated by the gentleman from

Massachusetts, but it is a jobs elimination bill. This bill creates a significant competitive disadvantage for American small business and agriculture as we try to compete in the global economy in which other countries do not abide by these caps, rules, or regulations.

I would assert that during my time in Congress there is no piece of legislation that will be more damaging to the future of rural America, to the future of small farms and businesses than the bill that is before us today. This bill—a jobs bill, as described by the gentleman from Massachusetts—is a job elimination bill, not a job creation bill. I urge my colleagues, both Republicans and Democrats, who come from the Midwest, who come from rural America to vote "no."

Mr. WAXMAN. Madam Speaker, it is my privilege now to yield 1 minute to a very important member of the committee, Mr. ENGEL.

Mr. ENGEL. I thank the chairman for yielding to me, and I rise in support of this bill as I supported it in committee.

I think this bill goes a great step in the right direction. It will revitalize our economy by creating millions of clean-energy jobs, increase our national security by reducing our dependence on foreign oil, and help preserve our planet by reducing greenhouse gas emissions.

But I want to mention, as I did in committee, my disappointment that the bill does not contain strong enough language in terms of flex-fuel cars in this country. I believe very strongly that the United States needs to move towards cars manufactured in America that can run on methanol, ethanol, and gasoline. If you give gasoline competition with ethanol and methanol, I believe that it will reduce the price of gasoline. So I am disappointed that while the bill goes a step in that direction, it doesn't go totally in the direction that I would like to see.

Yesterday, Energy Secretary Chu said all new cars should have flex-fuel capacity in this country. And I would like to enter this into the RECORD from The Des Moines Register.

Madam Speaker, flex-fuel vehicles would only cost \$90 or \$100 per car, and it would be very important to moving us in that direction.

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. WAXMAN. I yield the gentleman

Mr. ENGEL. I thank the chairman.

Just 6 months ago, the CEOs of GM, Chrysler and Ford appeared before the House Financial Services Committee, and each committed to making 50 percent of their cars flex-fuel vehicles by 2012. They are reneging now, and I believe that we should have strong language to move them back to their original position. I really believe that flex-fuel cars are the way to go.

But we have a bill before us, and the bill is much, much more positive than anything else. It is a big step in the right direction. And I think that our colleagues who are on the fence—as I pointed out, the bill doesn't give everything to everybody and it doesn't do nearly what I would like it to do, but I think it does enough so that we ought to move this country in the right direction to make ourselves energy independent, to reduce the warming of our planet, and to reduce the greenhouse gases.

So I would urge my colleagues for a "yes" vote. We can work afterwards to make the bill better, we can work afterwards to have the policies that we want to see, but rejection of this bill would be a terrible step in the wrong direction.

I urge my colleagues to vote "yes."

[From the Des Moines Register, June 22, 2009]

Chu: All New Cars Should Have Flex-Fuel Capacity

(By Thomas Beaumont)

U.S. Energy Secretary Steven Chu said in Des Moines today the nation's car manufacturers ought to make all new automobiles able to run on E85 ethanol-blended fuel.

But Chu said the government could face resistance should it insist on the new standard, despite two of the nation's three main automakers' having recently filed for bankruptcy protection.

Chu, in Iowa awarding the state a share of its federal stimulus money, later said all pumps ought to offer at least a blend of 15 percent ethanol.

"We should think about doing the following. I've been told it costs about \$100 in gaskets and fuel lines to turn a car so that it can go all the way to E85," Chu said, addressing public officials and news media at the Des Moines Botanical Center.

E85 is a blend of 85 percent ethanol and 15 percent gasoline. Iowa is the nation's leading producer of ethanol.

"But a new car, it would only cost \$100 out of \$15,000. Wouldn't it be nice to put in those fuel lines and gaskets so that we can use any ratio we wanted," Chu added. "It's just a thought, I don't think you're going to get any objections in this audience."

Chu stopped short of saying the Obama administration would require the companies to build all vehicles as flex-fuel-ready. "It's beginning to be discussed." Chu said.

"It's beginning to be discussed," Chu said. "But, again, it's one of those things where I think with virtually anything, once the government steps in the natural tendency is to resist government intervention."

General Motors and Chrysler have recently sought bankruptcy. The federal government would become a majority shareholder in GM.

There is legislation pending in Congress that would require all domestic automobiles to eventually make all vehicles capable of running on E85.

Monte Shaw, executive director of the Iowa Renewable Fuel Association said the government's new financial stake in the auto industry means it can require the higher renewable fuel standard.

"Clearly, if the White House decided they wanted GM and Chrysler to do this, they would do it," Shaw said. "I think it would be good. Once one company goes that way, I think it puts pressure on the other automakers not to be left out."

Mr. LUCAS. Madam Speaker, I recognize the gentleman from Ohio (Mr. Latta) for 1 minute.

Mr. LATTA. I thank the gentleman for yielding.

Madam Speaker, I rise today in opposition to this massive national energy

You know, we are all for clean energy. And Republicans have put forth an all-of-the-above strategy, and that's the strategy we need to do in this country. We can't pick winners and losers.

I represent a very interesting district in Ohio. Not only do I represent the largest manufacturing district in the State of Ohio, I represent the largest agricultural district. Ohio uses 87 percent of its coal for our generation. What this bill is going to do is kill jobs in Ohio, and we are struggling right now. It's tough.

One of the things that a lot of people don't realize out there because we have so few farmers out there that are left, less than 1 percent in Ohio, is that we have so many of our farmers, my relatives included, that not only work a full day on the farm, but they go out we've got to have jobs going both ways parallel with each other.

This bill is not going to help these people out there. This bill is going to kill jobs across this country. And when the Secretary of Agriculture was before us not too long ago, I posed this question: Is China going to comply with what we're going to do? And the answer was, Well, maybe not this month, or maybe not next month, but it's going to happen.

The SPEAKER pro tempore. The gentleman's time has expired.

Mr. LUCAS. I yield the gentleman an additional 15 seconds.

Mr. LATTA. We can't put the American farmer behind the proverbial eight ball. We've got to be able to compete against the world, and this bill is going to kill that ability to do that.

I thank the gentleman for yielding.

□ 1315

Mr. WAXMAN. Madam Speaker, it's my distinct honor to yield 2 minutes to the chairman emeritus of our committee who has been the leader in fashioning so many important legislative proposals that are now law and are serving our country so well, the gentleman from Michigan (Mr. DINGELL).

(Mr. DINGELL asked and was given permission to revise and extend his remarks.)

Mr. DINGELL. I thank my good friend from California for his kind remarks, and I express my appreciation to him.

Madam Speaker, I rise in support of the Clean Energy Security Act. But before I address my remarks, I want to congratulate you on your distinguished service here and wish you well in the future and express my personal distress that you are leaving us.

Now, my colleagues on the Republican side, they are very anxious to criticize the bill. And there are criticisms that can be had. There is not one of the 435 of us that could not come forward with statements in saying that

the bill could be improved and that there are faults in the bill. Both of those statements are true.

But the harsh fact of the matter is it is urgent that we commence acting upon this legislation. It is based largely on the recommendations of USCAP, which is a diverse group of environmental groups and industry with a shared desire for a commonsense bill to address climate change. That process began last year with the drafting of the initial versions of this legislation, which were taken and which were then handled by my friend from California. I would note that those proposals have undergone significant improvement by reason of the work of Members of this Congress and this committee.

Now, there are some hard facts to be addressed. There's a scientific consensus that we need to address climate change quickly and effectively. We need and industry needs certainty. This bill gives certainty to American industry. Without this certainty new expansion and new investment in this difficult time is not going to occur. There will be jobs which will flow from this legislation.

Actions by the Supreme Court, and I urge my colleagues to be scared to death of this—

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. WAXMAN. I yield the gentleman an additional minute.

Mr. DINGELL. Actions by the Supreme Court in a recent endangerment finding by EPA makes it critically important that we act. Otherwise, greenhouse gases will be regulated by EPA. And if you want something to shudder about, I beg you to take a look at that because we will see better than 300 different kinds of regulations coming from Federal and State bodies if we're charged with this.

Now, the bill does protect the consumers. It's going to cost consumers about \$175 a year. It will also protect American manufacturing, and there are provisions in the legislation for that. And it has, in addition to that, additional programs which will meet the concerns of all of our branches of industry—coal, electric utility, manufacturing, chemicals—and also the securities market, which will be controlled under an amendment offered by our good friend and colleague Mr. STUPAK.

I am happy that this bill does have a dedicated allowance for natural resource adaptation and significant protection in acquisition of lands.

This is a good bill. I urge my colleagues to support it.

Madam Speaker, I rise in support of the American Clean Energy and Security Act.

Is the bill before us perfect? No. But I have long told my friends on both the right and the left, we must not let the perfect be the enemy of the good.

The legislation before us is largely based on the recommendations of USCAP, a diverse group of environmental groups and industry with a shared desire for a commonsense bill to address climate change.

One might ask why such a diverse group would agree on a matter like this. Well, the answer is three-fold:

- 1. There is scientific consensus that we need to address climate change quickly and effectively.
- 2. We need, and industry needs, certainty. Without this certainty, expansion and new investment is not going to happen.
- 3. Actions by the Supreme Court which led to the recent endangerment finding by EPA makes it critically important we act. If we do not, we will face regulation under the Clean Air Act—and I assure you, the Clean Air Act was not designed to regulate greenhouse gases.

I am pleased with the provisions of the bill to protect consumers—the legislation will cost consumers on average only \$175 per yearand protect American manufacturing and pave the way for the green jobs of the future. In fact, my home state of Michigan just had some wonderful news today: General Electric has decided to locate a new research & development facility, working on renewable energy technologies and other green jobs in the 15th District, which I have the honor of representing. We have the best workers in the world in Michigan and I look forward to many more green job announcements just like this thanks to provisions in this bill. However, job protection and creation warrants a very watchful eve to ensure the United States does not face job leakage and these matters will need to be readdressed if we do see such consequences.

We have seen remarkable innovations from our automakers and this bill builds on those successes by providing allowance values for retooling existing plants to make the cars of the future and new, green job creation here at home.

I am very pleased the bill includes an amendment I offered to establish a Clean Energy Bank. As we transition to clean energy, we must fund the R&D as well as deployment of these energy sources to meet the mounting demand for zero-carbon technology to dramatically reduce our greenhouse gas emissions.

Finally, I am very pleased that this bill includes a dedicated allowance for natural resource adaptation. The great conservationist and the 26th President of these United States, Theodore Roosevelt, taught us that conservation is a great moral issue—that it is our duty, as it insures the safety and continuance of the nation.

This is a good bill and I urge my colleagues to support it.

Mr. LUCAS. Madam Speaker, I wish to recognize the gentleman from Texas (Mr. CONAWAY) for I minute.

Mr. CONAWAY. Madam Speaker, I too congratulate you on your long distinguished service.

There's an old Western movie entitled "Bad Day at Black Rock." Madam Speaker, if this bill passes today, this will be a bad day at Black Rock for America.

This bill will raise energy costs. Our President has said they will skyrocket. Claims of higher coal usage at lower costs are nonsensical on their face. The sense of urgency is muted by the fact that we delay implementation of many of these provisions for years and years

in order to convince people to vote for this nonsense. It has no meaningful effect.

We all want to breathe clean air. We all want to drink clean water. God has put us on this Earth as responsible stewards of these resources, and we ought to use them responsibly. This bill does not do it. In fact, it does nothing good. The only meaningful thing that it might do is provide a relatively meaningless photo op for our President in December in Copenhagen as he stands to brag about what America has done while the leaders of India and China laugh at us behind his back.

A vote for this bill is a vote to lower living standards for all Americans for the foreseeable future. I urge my colleagues to vote against this bill. It does nothing good.

Mr. WAXMAN. Madam Speaker, I yield 1 minute to my colleague from California (Ms. Eshoo), who is a very important member for our committee.

Ms. ESHOO. I thank our very distinguished chairman for yielding.

First, Madam Speaker, congratulations to you and God speed.

There may be no more critical issue facing our Nation today than that of our energy future and the desperate need for new policies that will dramatically and forever change how we live and work in our country. Our national security is irrevocably linked to it. Our economic stability depends on it. The future of our planet, the legacy of health and prosperity we all want to leave for our children cannot be assured without it. So it's time to take up this energy bill.

In this season of days we are granted in this honorable institution, this is truly a historic moment. By passing this act, we are guaranteeing an investment of \$190 billion in new, cleanenergy technologies and energy efficiency, creating jobs, spurring on new industries, and fulfilling the desire of all Americans that each of us in our own way can make this a better world.

In my home district of Silicon Valley, dozens of burgeoning companies at the cutting edge of green and clean-energy technology are poised for an explosion in innovation and healthy, sustainable economic growth.

The SPEAKER pro tempore. The time of the gentlewoman has expired.

Mr. WAXMAN. I yield another 30 seconds to the gentlewoman.

Ms. ESHOO. I thank the gentleman.

It's a particular pride for me to have had the opportunity to work on this act and to influence some of its outcome. I'm proud that my own bill, H.R. 1742, the Electric Vehicle Infrastructure Act, which will allow State and local governments to apply for financial assistance for the deployment of regional infrastructure to support the widespread use of electric vehicles, is included.

We are a hardworking people, Madam Speaker, who face the future with optimism and hope. This act embodies these qualities, a vehicle for our willingness to work hard, to innovate, to imagine a better future, and then to reach out and grasp it.

Mr. LUCAS. Madam Speaker, I yield 1 minute to the gentleman from Iowa (Mr. KING).

Mr. KING of Iowa. I thank the gentleman from Oklahoma for yielding.

Madam Speaker, first I would say that the canard of this court case that says the EPA will regulate CO₂ regardless, it takes a little change in Interior approps to fix that. We're the United States Congress. We don't capitulate to cap-and-tax because a court made a ruling; we tell them what the American people think.

Second, this bill freezes or rolls back oil, natural gas, coal, nuclear, and biofuels. We'll have less. We are not going to break dependency on foreign oil with less energy. Iowa no-till corn farmers, 6.2 million acres; 5 million of them went in before 2001, and only 25 percent of those that went in afterwards will be able to qualify because they rotate. So we're down to 4.8 percent of the guys doing it right. One out of 20 are going to get any benefit out of the Peterson amendment that's been incorporated into this bill.

And, furthermore, when Speaker Pelosi set up the cap-and-trade and bought the carbon credits, I can't verify that any of that changed any behavior for the positive. The ones I could verify had already been in place.

We've seen the example in Spain. It's a colossal mistake there, a political and an economic error. This could be the most colossal mistake ever made in the history of the United States Congress.

Mr. WAXMAN. Madam Speaker, I am pleased at this point to yield 1 minute to my good friend and colleague from southern California (Mrs. CAPPS).

Mrs. CAPPS. Madam Speaker, I rise with great pride today to express my support for the American Clean Energy and Security Act.

Over the last two Congresses, thanks to tremendous leadership, we have built a record on energy and climate policy that indicates that the time for action is now. America is ready. The world is watching. We must transition to a clean-energy economy so that we can create jobs, achieve energy independence, and protect our planet.

We have before us a powerful, thorough, and effective bill. It includes a nationwide renewable electricity standard. It contains critical investments in energy efficiency. It requires immediate significant reductions in greenhouse gas emissions that are harming the health of our people and our planet.

The bill also makes substantial investments in domestic, international, natural resource, and public health adaptations that are crucial to the continuing prosperity of our Nation and our world.

Madam Speaker, to protect our health, to protect our economy, our national security, and our planet, we must enact comprehensive climate legislation and we must enact it now. We cannot sit idly by. I hope others will join me in seizing this opportunity to transition our economy to a new, clean-energy economy.

I urge a "yes" vote on this bill.

Mr. LUCAS. Madam Speaker, once again I would like to yield 1 minute to the gentleman from Pennsylvania (Mr. Thompson).

Mr. THOMPSON of Pennsylvania. I thank my friend from Oklahoma for vielding.

I have more concerns with this legislation than I even have time to discuss. But since agriculture is Pennsylvania's number one industry and because I'm a member of the House Agriculture Committee, I would like to focus on the alarming effects cap-and-trade will have on the farmers in my home State.

This legislation, through mandates, attempts to decrease our use of fossil fuels. The whole point of cap-and-trade is to make fossil fuels, or 85 percent of the energy we consume, more expensive. Fossil fuels are essential for energy and electrical generation and also are equally important to use as a feed-stock in many goods that we utilize.

Agriculture is an energy-intensive industry, and natural gas will be capped under this legislation. Natural gas is a basic ingredient in fertilizer, which is a building block for all of the food the U.S. supplies. We can't make our food without fertilizer, and we can't make fertilizer without natural gas.

The dairy industry in my State is having a difficult time making profits because of falling milk prices. And while there are many reasons for low milk prices, energy costs are certainly part of that equation.

This legislation will do nothing to reduce our carbon emissions or help Pennsylvania agriculture and will only cause more economic hardship for many small farmers and businesses.

I urge my colleagues to reject this misguided measure.

Mr. WAXMAN. Madam Speaker, I am pleased to yield 2 minutes to the gentleman from Texas (Mr. Gene Green), who played a very significant role in developing this legislation.

Mr. GENE GREEN of Texas. Madam Speaker, like my colleagues, we will miss you and good luck in your new endeavor in the administration.

Today the House is set to consider the first comprehensive climate program in the history of the House of Representatives, and I support H.R. 2454.

This bill represents efforts to reach a consensus across our diverse membership and produce legislation that seeks to reduce greenhouse gas emissions both at home but also abroad. If Congress does nothing, greenhouse gas emissions could be regulated administratively through the EPA without input from Members that represent diverse constituencies nationwide.

I represent the Port of Houston, a petrochemical complex that stretches along the Texas gulf coast and is home

to thousands of chemical industry and petroleum refining jobs. We cannot allow the petrochemical and refining industries to migrate out of America. They are vital to our economy and to our national security, and we cannot outsource that capability.

These energy-intensive industries could be left vulnerable to foreign competitors not facing carbon regulations if we do not carefully craft transitional policies to prevent job loss and strengthen U.S. industries at home.

I want to thank Congressman INSLEE and Congressman Doyle for putting forth a proposal to provide 15 percent of the free allowances to emission-intensive industries to address competitive concerns, especially in the chemical industry. If a manufacturing facility is energy intensive and trade exposed, allowances will be provided to that facility on a production output basis, providing rebates for both the direct and indirect costs of complying with the climate program. These rebates will level the playing field relative to imports while encouraging emission reductions.

The bill also helps protects the U.S. domestic refining industry while creating a climate-change program. Our domestic refiners will face a competitive disadvantage with foreign competitors that are not subject to carbon regulations. U.S. refiners in this bill will receive 2 percent of the allowances starting in 2014 and ending in 2026, plus an additional .25 percent for small business refiners.

□ 1330

That's over one-half of the projected 4 percent of refined emissions. This funding will help defray expenses associated with direct and indirect costs and their stationary source of emissions under the cap as well as help improve the efficiency of refineries through technical and feedstock changes.

To level the playing field, foreign importers of refined oil must pay for carbon content of imported fuel, just as our domestic producers have to do, Madam Speaker.

And that's why I think this bill is a good first step. If I were writing it, it would be different.

Madam Speaker, today the House is set to consider the first comprehensive climate program in the history of the U.S. House of Representatives and I support H.R. 2454.

This bill represents efforts to reach consensus across our diverse membership and produce legislation that seeks to reduce greenhouse gas emissions both at home and abroad

If Congress does nothing, greenhouse gas emissions could be regulated administratively through the EPA without input from Members that represent diverse constituencies nationwide.

I represent the port of Houston, a petrochemical complex that stretches along the Texas Gulf Coast and is home to thousands of chemical industry and petroleum refining jobs.

We cannot allow the petrochemical and refining industries to migrate out of America. They are vital to our economy, to our national security, and we cannot outsource this capa-

These energy-intensive industries could be left vulnerable to foreign competitors not facing carbon regulations if we do not carefully craft transitional policies to prevent job loss and strengthen U.S. industries at home.

I want to thank Congressman INSLEE and Congressman DOYLE for putting forward a proposal to provide 15 percent of free allowances to emissions-intensive industries to address competitiveness concerns, especially in the chemical industry.

If a manufacturing facility is energy-intensive and trade-exposed, allowances will be provided to that facility on a production output basis, providing rebates for both the direct and indirect costs of complying with the climate program.

These rebates will level the playing field relative to imports while encouraging emission reductions.

The bill also helps protect the U.S. domestic refining industry while creating a climate change program.

Our domestic refiners will face a competitive disadvantage with foreign competitors that are not subject to carbon regulations.

U.S. refiners will receive 2 percent of allowances starting in 2014 and ending in 2026. plus an additional .25 percent for small business refiners. That's over one-half of the projected 4 percent of refinery emissions.

This funding will help defray expenses associated with the direct and indirect costs of their stationary source emissions under the cap, as well as help improve the energy efficiency of refineries through technological and feedstock changes.

To level the playing field, foreign importers of refined oil must pay for the carbon content of imported fuel, as do domestic refiners.

While I believe the refining industry could use additional assistance, and I hope any final agreement does so, this is a reasonable first step to protecting our energy infrastructure and keeping good-paying jobs here at home.

These proposals, however, cannot substitute for the need for a strong international agreement with binding carbon reductions amongst the world's largest emitters, including developing countries.

Mr. LUCAS. Madam Speaker, I yield myself the remainder of my time.

The SPEAKER pro tempore. The gentleman has 3\% minutes remaining.

Mr. LUCAS. Madam Speaker, my fellow Members, let me rise to conclude the House Agriculture Republican portion of this discussion this evening and remind my colleagues one more time that this bill has a tremendous effect on rural America and production agriculture. When 115 farm groups send in letters, and food groups, expressing their opposition to the bill, that says something, 115 groups.

Madam Speaker, I submit a list of these groups for the RECORD.

Agriculture Groups Oppose to Waxman-Markey—as of June 26, 2009

- 1. Agribusiness Association of Iowa
- 2. Agricultural Retailers Association
- 3. Agrium Inc.
- 4. Alabama Farmers Federation
- 5. American Agri-Women
- 6. American Farm Bureau Association
- 7. American Farmers & Ranchers

- 8. American Feed Industry Association 9. American Frozen Food Institute
- 10. American Meat Institute
- 11. American Plant Food Corporation
- 12. AmeriFlax
- 13. Associated Industries of Florida
- 14. Beck' Superior Hybrids
- 15. Brandt Consolidated
- 16. CF Industries
- 17. Chemical Industry Council of Illinois
- 18. CHS Inc.
- 19. Corn Producers Association of Texas
- 20. D.B. Western, Inc.
- 21. Far West Agribusiness Association
- 22. Florida Chamber of Commerce
- 23. Florida Farm Bureau Federation
- 24. Florida Fertilizer & Agrichemical Association
- 25. Florida Strawberry Growers Association
- 26. Food Industry Environmental Council 27. GROWMARK
- 28. Hardee County Farm Bureau (FL)
- 29. Hillsborough County Farm Bureau (FL) 30. Illinois Farm Bureau
- 31. Illinois Fertilizer & Chemical Associa-
- 32. Indiana Beef Cattle Association
- 33. Indiana Farm Bureau
- 34. Indiana Grain & Feed Association
- 35. Indiana Office of Energy Development
- 36. Indiana Plant Food & Ag Chemicals Association
- 37. Indiana Pork Producers Association
- 38. Indiana Professional Dairy Producers
- 39. Indiana State Department of Agriculture
- 40. Indiana State Poultry Association
- 41. Institute for Shortening and Edible Oils
- 42. International Raw Materials, Ltd.
- 43. J.R. Simplot Company
- 44. Kansas Agribusiness Retailers Associa-
- 45. Kansas Grain and Feed Association
- 46. Minnesota Agri-Growth Council
- 47. Minnesota Corn Growers Association
- 48. Minnesota Crop Production Retailers
- 49. Missouri Agribusiness Association
- 50. Missouri Farm Bureau
- 51. Montana Agricultural Business Associa-
- 52. National Cattlemen's Beef Association
- 53. National Chicken Council
- 54. National Grain and Feed Association
- 55. National Grange
- 56. National Meat Association
- 57. National Oilseed Processors Association
- 58. National Pork Producers Council
- 59. National Turkey Federation 60. Nebraska Farm Bureau
- 61. NCRA
- 62. Nebraska Agri-Business Association
- 63. New Mexico Peanut Growers Associa-
- 64. North American Millers Association
- 65. North Carolina Peanut Growers Association
- 66. North Dakota Agricultural Association
- 67. North Dakota Barley Council
- 68. North Dakota Farm Bureau
- 69. North Dakota Grain Dealers Association
- 70. North Dakota Grain Growers Associa-
- 71. North Dakota Soybean Growers Association
- 72. North Dakota Stockmen's Association 73. North Dakota Wheat Commission
- 74. Northern Canola Growers Association
- 75. Northern Pulse Growers Association 76. Ohio Corn Growers Association
- 77. Ohio Farm Bureau
- 78. Ohio Poultry Association
- 79. Ohio Rural Electric Cooperatives, Inc.
- 80. Ohio Wheat Growers Association
- 81. Oklahoma Ag Retailers Association
- 82. Oklahoma Grain & Feed Association 83. Oklahoma Peanut Commission

- 84. Oklahoma Seed Trade Association
- 85. Oklahoma Wheat Growers Association
- 86. Panhandle Peanut Growers Association
- 87. Peace River Valley Citrus Growers Association
- 88. Peanut Growers Cooperative Marketing Association
- 89. Polk County Farm Bureau (FL)
- 90. PotashCorp
- 91. Rocky Mountain Agribusiness Association
 - 92. Sarasota County Farm Bureau (FL)
 - 93. Society of American Florists
- Fertilizer 94. South Carolina Agrichemicals Association
- 95. South Carolina Peanut Growers Association 96. South Dakota Agri-Business Associa-
- tion 97. South Dakota Farm Bureau
 - 98. South Dakota Grain & Feed Association
 - 99. Southern Crop Production Association
- 100. Southwest Council of Agribusiness
- 101. Terra Industries Inc.
- 102. Texas Agricultural Cooperative Council
 - 103. Texas Cattle Feeders Association
 - 104. Texas Farm Bureau
- 105 Texas Grain & Feed Association
- 106. Texas Peanut Producers Board
- 107. Texas Sheep & Goat Raisers Association
 - 108. Texas Wheat Producers Association

 - 109. The Andersons, Inc. 110. The Fertilizer Institute
 - 111. The McGregor Company
- 112. Todd Staples, Commissioner, Texas Department of Agriculture
 - 113. Tom Farms (Kip Tom, CEO)
- 114. United Egg Producers
- 115 USA Rice Federation
- 116. Virginia Peanut Growers Association
- 117 W.B. Johnston Grain Co.
- 118. Western Peanut Growers Association
- 119 Western Plant Health Association 120. Wyoming Stock Growers Association

Madam Speaker, I would also be remiss if I didn't express my appreciation and the appreciation of my colleagues on the Republican side of the Agriculture Committee to Chairman PE-TERSON. He made, we believe, goodfaith efforts with Chairman WAXMAN to try to correct the worst features of this

bill. Unfortunately, good faith in the

legislative process doesn't always cure

every problem. The fundamental underlying issue still is this bill will raise the cost of energy for production agriculture, an energy-intensive business. It will reduce our competitiveness with our competitors around the world, South America, Asia, Europe. But look at the way the so-called grand compromise on agriculture was put together. "Compromise" is a phrase used in one of the

electronic publications this morning.

Indirect land use, where an agency of the Federal Government can determine how your corn farm or your wheat farm affects farms on other continents and tell you to change the way you do your business? Now, I know the bill says that can't happen for 5 years, and we will have a study and a moratorium for another year. But 6 years from now, 6 years from now, it comes at us like a brick bat.

The section of the bill talking about farms being able to be rewarded for good stewardship, carbon sequestration and those kinds of matters, the bill

says the amendment adopted, the practices can only be rewarded if they began after 2001. You heard my friend from Iowa talk about the percentage of corn farmers who adopted those good practices before 2001.

How do you explain to the folks back home that the good farmers, the good stewards, don't get anything, but the bad farmers who waited until they were shamed or embarrassed into adopting the best practices get rewarded?

Renewable fuel. Yes, we protect facilities that were under construction or have been completed or in production in 2007 and before, but that doesn't apply to everything since then. If you have got a mature ethanol plant, you are in good shape. But does that mean no one else can build an ethanol plant?

We, on the minority side of the Ag Committee, view ourselves as the conscience of the body. We have a responsibility to defend rural America and production agriculture. We thank Chairman Peterson for what he tried to accomplish, but we believe it is not enough to protect the future of farming and ranching and the folks out in rural America. That's why we have to be united in our opposition against this bill

I am a farmer by trade. I may not always be a Member of this body, but I am going home to Oklahoma. I can't vote for this and go home to Oklahoma.

Mr. WAXMAN. Madam Speaker, I am pleased to yield to the vice chairman of the Commerce Committee, the gentlewoman from Colorado (Ms. DEGETTE) for 90 seconds

(Ms. DEGETTE asked and was given permission to revise and extend her remarks.)

Ms. DEGETTE. Madam Speaker, I rise today in support of this important energy and environmental legislation, probably the most important this body has ever considered.

And I will say to my friends who say it's not enough, that we need to remember how important it is for us to put together a framework in place so that we can assure energy independence and create jobs.

In Colorado, Madam Speaker, in 2004, our voters passed a renewable energy standard, the first time that it was done in any State by ballot initiative. Industry opposed it universally, but yet it passed 53-47 percent. That standard was 10 percent by 2015, and we exceeded that standard within 2 years. Two years later, we came back to the Colorado Legislature. We doubled that standard. It was bipartisan and industry supported it.

When people see the wonderful framework we are putting in place today for energy independence, which will create jobs, they will embrace this concept. They will embrace the concept of becoming independent from foreign oil and making sure that we develop clean alternative sources of energy, which are going to benefit our children and our children's children.

One last thing. According to the Congressional Budget Office, this bill will cost the typical family less than that of a postage stamp per day.

And I will say, once we develop these clean alternative energy sources, we will benefit, because we will regain our place in the world as a leader in technology and as a leader in clean alternative sources of energy.

I want to urge my colleagues to support this legislation, which relies on scientific evidence to set our Nation's policy.

Mr. BARTON of Texas. Madam Speaker, I want to yield 3 minutes to the deputy ranking member of the Energy and Commerce Committee, Mr. BLUNT of Missouri.

Mr. BLUNT. I thank the gentleman for yielding.

Madam Speaker, you and I came to the House of Representatives at the same time. We have often voted differently, but I have always appreciated your public service and will continue to and wish you well in the new responsibility that you are taking and well in the other announcement that you made today.

I think this bill, Madam Speaker, heads the country very much in the wrong direction. It's the wrong direction for America. It's the wrong direction for our economy. It puts us at a competitive disadvantage. The Republican alternative that many Democrats could easily support would look for more American energy, would look for more ways to conserve the energy we use, and would invest in the future in a way that makes our energy future make sense.

We have 28 percent to 30 percent of all the coal in the world. If this was something that the majority wanted to do, the majority would be saying, if this country could put a man on the Moon in a decade, we could find a way to use coal in a way that doesn't create an immediate penalty on every coalproducing utility in America. In Mr. WAXMAN's State, I have great respect for him, the primary sponsor of the bill, less than 4 percent of California's electricity comes from coal.

In Mr. MARKEY's State, less than 24 percent of the electricity comes from coal. In Missouri, more than 85 percent of the electricity comes from coal, and we are not the top State. We are in the top 10. We will be affected by this dramatically, but so will everybody from, say. Pittsburgh to Wyoming.

This is going to impact utility bills unfairly. It will impact job opportunity unfairly. And, frankly, the jobs we lose in our part of the country, and in the country generally, are not likely to relocate somewhere else in America. They are more likely—these manufacturing jobs use lots of energy—to locate in a country that has less environmental standards than we do, the ultimate lose-lose. We lose the jobs. You actually put more of these things in the air than you would otherwise, and Americans suffer because of that.

In our State, the estimate is that utility bills would go up 40 percent in the first 5 years, 80 percent in the first 10 years, and even more after the various allowances are gone. This is unfair to American families, and, frankly, the less you can afford to put in new windows, new insulation, new everything else, the harder a burden this is going to be.

I urge my colleagues to vote this bill down and work together to have a better bill for America.

Mr. WAXMAN. Madam Speaker, I want to yield to the gentleman from Pennsylvania (Mr. DOYLE) a minute, with an option for another one, if he needs it. And I want to point out the essential role that he played in making sure this legislation protected those industries that are vulnerable to trade that might be at their disadvantage. I thank him for the work he has done.

Mr. DOYLE. Madam Speaker, today we have a historic opportunity to create thousands of clean-energy jobs, to secure this country's energy future, and to give our kids and grandkids a brighter, cleaner planet. Madam Speaker, we do that while protecting our basic industries like steel, aluminum, cement, and our ratepayers, both residential, commercial and industrial

I was proud to work on this committee with my friend and colleague JAY INSLEE to develop a formula that looks at our carbon intensive industries like steel, that have trade pressures, and level the playing field for them so that we don't lose jobs. This bill wasn't going to cause any jobs to be lost. This is a job-creating bill, and you don't need to take my word for it.

I have a letter from the international president of the steelworkers union—people whose very jobs would be on the line if we didn't get this right—who endorses this bill, who says this bill will create more jobs for steelworkers in Pittsburgh.

And we do that by rewarding efficiencies. We say to our carbon-intensive industries, Be average in your sector. We will make you whole for the cost of this program.

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. WAXMAN. I yield the gentleman an additional 30 seconds.

Mr. DOYLE. For those industries that invest and become more efficient, we give them more rewards. We encourage efficiency in our markets at the same time, giving them a level playing field with their competitors. We do the same thing in the electricity markets.

Every one of my constituents get their electricity from coal. We protect those ratepayers. Thirty-five percent of the allocations in this bill go towards protecting residential, commercial and industrial ratepayers. This is not a job loser. This is not a rate hike for consumers; \$173 a year for the average family in America as a result of this bill. That's a small price to pay for a cleaner planet and more jobs for America

Mr. BARTON of Texas. Madam Speaker, I yield 1 minute to the distinguished Representative from Washington State, Mr. HASTINGS.

Mr. HASTINGS of Washington. I thank the gentleman for yielding.

Madam Speaker, this bill was written in a fantasy land where unemployment isn't reaching 10 percent, thousands haven't lost homes to foreclosure, and millions haven't witnessed half their retirement savings disappear. By imposing this national energy tax and creating a massive new bureaucracy to regulate the entire economy, this bill will drive up the cost of doing business in America, sending jobs overseas to China and India, nations that flat out refuse to reduce their own carbon emissions.

We are told America must lead by example. Are we to believe that after the government drives America's economy further into the gutter, the rest of the world will do the same?

Madam Speaker, America should not be the first lemming to jump off the cliff just because NANCY PELOSI and Al Gore are convinced that China, India and Russia and others will follow us over the ledge. Republicans have an all-of-the-above energy plan to build more nuclear power and invest in cleaner alternative energies funded by drilling oil here in America. Yet, Madam Speaker, Democrats refuse to even allow a vote on this plan.

So I urge my colleagues to vote "no" on this bill.

Madam Speaker, this bill has been written in a fantasyland where unemployment isn't reaching 10 percent, thousands haven't lost their homes to foreclosure, and millions haven't witnessed half of their 401k's and retirement savings disappear.

By imposing a national energy tax, our economy will shrink in size, millions of jobs will be lost, energy costs will, to use the President's own word, "skyrocket", and gas prices will again reach record highs.

By creating a massive new government bureaucracy to regulate the entire economy, this bill will drive up the cost of doing business in America, sending jobs overseas to countries like China and India, nations that flat-out reject reducing their carbon emissions, and that are building coal-fired energy plants at a breakneck pace.

Democrats are trying to impose a highpriced, gourmet energy plan that restricts and dictates what specific sources of energy America should use. What our country actually needs is Republicans' all-of-the-above approach that says yes to nuclear power, yes to alternative energy, yes to wind and solar power, yes to energy from wood-waste and biomass, yes to hydro power, and, yes to opening more areas to drilling for oil and natural gas in America to reduce our vulnerability to spikes in prices at the pump because of turmoil in overseas oil nations.

America's economy can't afford this Democrat plan to cherry-pick a few high-priced energy sources. Creating green jobs makes good sense, but creating nuclear jobs, drilling jobs, green jobs and all new energy jobs is far. far better for America's economy.

America's economy is ailing, and enacting a new national energy tax is like a doctor ordering his sick patient to go stand outside in the cold rain. Our economy needs to recover, not be made sicker.

We're told America must lead by example, and then the rest of the world will follow. Are we to believe that after the federal government drives America's economy further into the gutter, the rest of world will do the same?

Yet, Democrats have refused to condition putting this national energy tax into force upon reciprocal action by China and the world's other nations.

Madam Speaker, America should not be the first lemming to jump off the cliff just because NANCY PELOSI and Al Gore are convinced that China, India, Russia and others will follow us over the ledge.

And what would this Democrat scheme do with the hundreds of billions of dollars taxed away from families and businesses? Shockingly, this bill would give away billions in foreign aid. In fact, this bill pays four times as much in foreign aid than it provides to the over two and half million Americans who will lose their jobs because of this bill. And on top of that foreign aid, it pays five times as much to countries to protect tropical trees than it does to helo jobless Americans.

We don't need the biggest job-killing tax in history to reduce carbon emissions and put in place cleaner energy sources.

We can promote nuclear power that emits no carbon and we can invest in new alternative energies funded by revenues from simply getting our oil here in America rather than from volatile foreign nations.

This is the Republicans' all-of-the-above energy plan—called the American Energy Act. Yet the Democrats refuse to even allow a vote on it

Democrats are forcing Congress to either accept or reject their national energy tax and high-priced, gourmet energy mandates. The only right choice to protect our economy and American jobs is to vote no.

Mr. WAXMAN. Madam Speaker, I am pleased at this time to yield 1½ minutes to the gentleman from Illinois, who made sure in this legislation, among other important contributions, that we looked out for the interests of low-income people.

Mr. RUSH. Madam Speaker, today marks a historic chance to move our great country forward and transform our economy for the demands of the 21st century.

I fully support this bill. It will not only make our country more substantive and energy efficient, but it would also provide jobs and economic opportunities for all of our citizens while opening an entirely new sector of our economy. I really must begin by thanking Chairman WAXMAN and Chairman MARKEY for their hardworking staffs and for all the work that they have done to improve this bill as it made its way through the legislative process and onto the floor today.

With the chairman's help, we were able to strengthen this legislation by not only protecting low-, moderate-, and middle-income families from rising energy costs, but also providing real assistance for communities like the one I represent for new career path-

ways to move out of poverty and to move into quality, career-oriented jobs in construction and energy-related fields.

\sqcap 1345

Some of these provisions that we were able to get in the bill are the low-income allowances, 60 percent of all the total allowances go to low-income people; local targeted hiring for middle class careers in construction; Low-Income Community Energy-Efficiency programs. The LICEEP program, the Low Income Community Energy-Efficiency Program, will provide loans, technical assistance, and grants to community development organizations to provide financing to minority entrepreneurs.

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. WAXMAN. I yield the gentleman an additional 30 seconds.

Mr. RUSH. The Public Housing Retrofit program, which I worked with the gentlelady from California, Ms. WATERS, as well as my colleague from Vermont, Mr. WELCH. It's a new program that provides grants to public housing agencies for energy retrofits and green investments in property.

Madam Speaker, this is a great bill. This is a good bill. This bill should pass. I urge all of my colleagues to vote in support of this bill.

Mr. BARTON of Texas. Madam Speaker, I'd like to yield 2 minutes to a member of the committee, the gentleman from Michigan (Mr. ROGERS).

Mr. ROGERS of Michigan. Madam Speaker, my appreciation for your years in the House and your great service here. Congratulations and great success in your new endeavor.

I agree, Madam Speaker, with President Obama and Warren Buffett: under this bill, "Electricity rates will necessarily skyrocket." Under this bill, we create the single largest energy tax in United States history. Warren Buffett called it "a huge tax, and there's no sense calling it anything else. Very poor people are going to pay a lot more for electricity."

Last night, in my district, a utility company calculated its estimate of what this bill will cost the families in my district. It will increase their electric rates \$500 a year—not your statistics from those who don't live in a place like Michigan; \$500 a year. And that doesn't incorporate the fact that their clothes will now be more expensive, their groceries will now be more expensive, their school supplies will now be more expensive.

If you haven't noticed, people are hurting around the United States. Adding costs today is absolutely the wrong direction. It will destroy \$1,400 in wages for the average family in my district. \$1,400. That's a \$2,000 swing. People in Michigan, who are already under assault, want to know what they're getting for that \$2,000 swing.

Well, they won't get a new nuclear plant. Not one. They will not get the modern electric grid that they need to carry clean electricity. Not going to get that. And they will not get a level playing field with China and India. And—make no mistake—they want to steal the jobs that make up our middle class. They're active and aggressive in doing it. You pass this bill, you won't be able to build anything in the United States of America. Their jobs are going overseas.

They will also see their gas prices rise, on average, 70 cents—70 cents a gallon to families who are already under financial crisis. And who gets their money? Wall Street will.

This bill takes millions, billions out of families' budgets and launders it through Wall Street. The same people who brought you the credit default swap in the housing market are now going to sell you carbon offset swaps. Billions of dollars from average Americans sent to Wall Street. That's no solution.

If you want an economy built on foreign manufacturing and financial engineering, vote "yes." But if you still want to live in a country that makes things, in a country that grows its own food and actually produces its own energy, vote "no."

Mr. WAXMAN. Madam Speaker, at this time I yield 2 minutes to the very distinguished chairman of the House Armed Services Committee, the gentleman from Missouri (Mr. SKELTON).

Mr. SKELTON. I certainly thank the gentleman for yielding. Madam Speaker, as a farm State Representative, I have said for quite some time that any climate change legislation approved by the House must take into consideration the unique needs of rural America, including those of farmers and rural electric cooperatives.

Since first being introduced, the climate change measure has improved a great deal, thanks in large part to the work of House Agriculture Committee Chairman COLLIN PETERSON and his negotiations with House Energy and Commerce Committee Chairman HENRY WAXMAN.

I first approached this legislation with a great deal of skepticism. I have since been pleased that some, though not all, concerns of utilities, electric cooperatives, and farmers have been addressed in the version of the bill that is being considered today.

As this bill was being drafted, I have heard the views of Fourth District residents and have raised them with the House leaders. To be sure, the measure before us is not perfect, but it's a step in the right direction.

I think it's important that we move this bill forward. After we pass it in the House, the measure will receive additional refinement in the other body. I think that the congressional leadership and the administration understand the concerns of rural America, and I will keep working to ensure our point of view is more completely addressed in the final bill.

Truth be told, Congress has an obligation to enact energy reform this

year, especially given that the U.S. Environmental Protection Agency, that is the EPA, is working right now to create tough, costly regulations on greenhouse gases emitted by livestock, farms, factories, and utilities. Without congressional action, the EPA will have free rein. That is unacceptable to me, and ought to be unacceptable to every farmer and business owner in Missouri.

Unlike the EPA proposal, the House bill would exempt livestock and farms from greenhouse gas regulation, and it would provide farmers an opportunity to potentially profit from their carbon-friendly farm practices by participating in the carbon market.

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. WAXMAN. I yield the gentleman an additional 30 seconds.

Mr. SKELTON. Also, for farmers, the legislation would correct a problem that has been lingering since enactment of the 2007 energy bill. For the next 5 years, it would prevent EPA from calculating indirect land use when determining how to implement our Nation's renewable fuel standard.

This is good news for ethanol and biodiesel production facilities and for the farmers who sell the goods to these facilities.

Energy reform is not just a matter of wanting to keep our air and planet clean, as worthy and important as those goals are. It's also a matter of national security.

In recent years, the Pentagon has taken a hard look at how climate change could have an impact on global security and stability.

Mr. BARTON of Texas. Madam Speaker, I yield 1 minute to a member of the committee, the gentleman from Georgia (Mr. GINGREY).

Mr. GINGREY of Georgia. Madam Speaker, we are at a crossroads. Our Nation faces significant challenges, with unemployment nearing 10 percent and trillion-dollar deficits piling up decades of debt for our children and our grandchildren.

However, congressional Democrats should not be so shortsighted to think that we cannot make a bad situation significantly worse by enacting legislation like this bill that will only knock more Americans off the assembly line and into the unemployment line.

This bill will impose the Pelosi Global Warming Tax on every single American household and business, raising home electricity costs and annual energy costs by almost \$3,000 for every family, and the only reduction will be in our Nation's gross domestic product by almost \$10 trillion and in the number of Americans employed by the millions

Madam Speaker, Washington cannot save this country. Only the American people and American ingenuity can. Unfortunately, congressional Democrats have already allowed the Federal Government to take over our banking industry, the automobile industry, and

now this House may very well vote to take over America's energy, with control over health care not far behind.

Let's stop the insanity and wake up to the reality imposed in the Global Pelosi Warming Tax and, in the words of another Californian, our distinguished former first lady, Nancy Reagan: Just say no.

Mr. WAXMAN. Madam Speaker, may I inquire about the time each side has remaining.

The SPEAKER pro tempore. The gentleman from California has $44\frac{1}{2}$ minutes remaining; the gentleman from Texas has $53\frac{1}{2}$ minutes remaining.

Mr. WAXMAN. Thank you. At this time I'd like to yield 1 minute to a distinguished member of our committee, the gentlewoman from Illinois (Ms. Schakowsky).

Ms. SCHAKOWSKY. Madam Speaker, I rise today in strong support of H.R. 2454 and congratulate Mr. WAXMAN for his leadership.

For over a century, the United States has embraced an energy policy based almost entirely on fossil fuels that have several dangerous consequences for today. This outdated policy has compromised our national security by making us reliant on foreign oil, has led the United States to lag behind other countries in the research and development of new energy technologies that would have created jobs, and has poison our planet. Now, today, we have the opportunity to change directions.

When I was back in my district last recess, I could feel the crackling of new innovation. S&C Electric is making our electric grid much smarter and more reliable. Northwestern University is enabling entrepreneurs who are utilizing nanotechnology and applying it to the energy field. Republic Doors and Windows, a Chicago business that made Energy Star windows, shut down. But those 260 skilled workers were rehired with help from the recovery bill that we passed.

These are just a few of the thousands of success stories around the country, and the 1.7 million good jobs that will be created with the passage of H.R. 2454.

Mr. BARTON of Texas. I'd like to yield 1 minute to a member of the committee, the gentleman from Nebraska, (Mr. TERRY).

Mr. TERRY. There's a vigorous debate about the anthropologic impact on our climate. I believe that we do have an obligation to reduce CO_2 , if we can. But this must be balanced with an equal obligation to treat our constituents in a manner that preserves our Nation's economic competitiveness.

Advocates for the cap-and-trade bill state that it will not significantly increase economic burdens on our constituents. This is just not true. The cap-and-tax bill also contains a renewable electric standard and other elements which will significantly increase costs to utilities and consumers. The Omaha Public Power District in my district conducted an independent

analysis of the cost to my constituents, free of political interference like the one put out by the EPA.

Even with the free allowances allocated under the Waxman-Markey capand-tax bill, Nebraskans will have to suffer a \$74 million bill in 2012, and increased to \$410 million a year by 2030 in the most optimistic case.

Vote against this bill.

Mr. WAXMAN. Madam Speaker, it's my privilege at this time to yield 1½ minutes to a gentleman who has worked successfully with Members representing disparate interests in different parts of the country to find workable solutions that helped lead to the consensus product we have today, the gentleman from Washington (Mr. INSLEE).

(Mr. INSLEE asked and was given permission to revise and extend his remarks.)

Mr. INSLEE. Madam Speaker, this bill renews some basic American values of confidence in ourselves, optimism about our future, and a "can-do" spirit. We support this bill because we believe Americans still have the right stuff that we had in the 1960s when we went to the Moon.

This bill calls forward Americans' future to get off of foreign oil, to put millions of people to work in clean technology, and to give our grandkids a chance at a future with a decent atmosphere like we grew up with.

The people who are against this bill, I urge them to avoid the pessimism and the lack of imagination that I have heard on the floor of this House.

Now, will this have some investment cost? Yes. And what is the best assessment of that cost? It is the Congressional Budget Office, a nonpartisan group that Republicans typically rely upon, and what have they said? They said this will cost a typical family of four 47 cents, a little more than the cost of a stamp.

Will we pay the cost of a stamp to get rid of five million barrels of oil a day from the Mid East? You bet we will. And this bill will do that. Will we pay a stamp to give our grandkids a future of an environment that's not going to destroy their health? You bet we will. Will we pay a stamp to give people at the Bright Source Company a chance? You bet we will.

We're going to put a stamp on America's future for the price of a stamp. It's a good deal for our future.

Mr. BARTON of Texas. Madam Speaker, I yield 1 minute to the distinguished chairman of the Republic Policy Committee, the gentleman from Michigan (Mr. McCotter).

□ 1400

Mr. McCOTTER. Today we consider a bill that claims the government can control the weather by raising your taxes, taking your job and dictating your life. In my State of Michigan, with a 15 percent unemployment rate, we know we cannot afford this cap-and-tax bill. Others, however, disagree.

"Make no mistake," President Obama pronounced, "this is a jobs bill." He is correct. This bill will destroy jobs. But then again, this comes from an administration that claimed its trillion-dollar stimulus bill would stop unemployment from going over 8 percent.

The argument for this bill is nuts on its face. Government cannot design our economy and prosperity. It can only engineer our decline in poverty. But such feelings explain why this job-killing cap-and-tax bill is a fundamental shift from a manufacturing economy to an old green economy called hunting and gathering.

Passing this abominable energy tax on working families in a recession shows this job-killing, budget-busting government doesn't understand how much real Americans are hurting for work. This is the hubris of Big Government, the delusion that our families' economic futures rest in the manicured hands of Congress rather than the hardworking hands of the American people.

I disagree, and I urge the rejection of this bill

Mr. WAXMAN. Madam Speaker, I am pleased at this time to yield $1\frac{1}{2}$ minutes to the gentlelady from Wisconsin (Ms. Baldwin) who is an important member of our committee in both the energy and the health areas.

Ms. BALDWIN. Thank you, Mr. Chairman

Madam Speaker, the Waxman-Markey American Clean Energy and Security Act represents our Nation's response to a challenge that has consequences of epic proportions. Global climate change must be addressed in a real and meaningful manner. Our greenhouse gas emissions have put our global environment, our security and our very social structure at risk; and if we fail to act, the impact will reverberate throughout this century with the loss of human lives, species destruction, destruction of ecosystems, declines in health and increased social conflict.

Climate change is a unique challenge in that our greatest obligation in tackling this threat is to the generations of Americans and people throughout the world who haven't even been born yet, the ones who will inhabit this planet long after we're all gone. The legislation we have before us addresses global climate change while spurring innovation, creating clean energy jobs and containing costs. It brings what we need in terms of leadership and commitment as we look toward Copenhagen and beyond. It recognizes that our Nation's security, our planet's sustainability and our children's future hang in the balance.

I urge my colleagues to support this bill and commit to a clean energy economy that creates jobs and protects our health, national security and planet for generations to come.

Mr. BARTON of Texas. Madam Speaker, I yield 2 minutes to a distin-

guished gentleman on the committee, a member of the Energy Solutions Group and a tireless worker on behalf of energy solutions for America, the gentleman from Illinois (Mr. Shimkus).

(Mr. SHIMKUS asked and was given permission to revise and extend his remarks.)

Mr. SHIMKUS. Madam Speaker, this bill is a disaster, and let me just explain who is opposed. Rural America is opposed to this bill. The manufacturing sector is opposed to this bill. Utilities are opposed to this bill. The transportation sector is opposed to this bill. Why? Because they believe Democrats. They believe John Dingell when he says, Nobody in this country realizes that a cap-and-trade is a tax, and it is a very big one. They believe Barack Obama when he said, Under my plan of a cap-and-trade system, electricity costs would necessarily skyrocket. What's the result? They believe the Pennsylvania Public Utility Commission that says, 66,000 Pennsylvanians will lose their jobs. Why am I so impassioned? These are miners who lost their jobs the last time we came to the well on climate legislation, when 1.200 miners lost their jobs, 35,000 miners lost their jobs in the State of Ohio.

What will this do to the average American? Here's one example. When the Democrats came into power, a gallon of gas was \$2.33. Today it's \$2.66. Add the cap-and-trade tax, 77 cents per gallon, and you're going to be paying \$3.43. Now that's okay in the big city; but in rural America where you've got to drive long distances to get to school, to get to the grocery store, to get to health care, rural America is poor. Why do we have the rich areas of this country attack the rural poor of America? This is a shame. How dare you do that to my constituents.

Mr. WAXMAN. Madam Speaker, I yield 1½ minutes to the gentleman from New York (Mr. Weiner) who has been a very constructive and important member of our committee and has played a very essential role in having us recognize the essential part that transportation efforts can play in reducing carbon emissions.

Mr. WEINER. The chairman will be recognized for generations to come for confronting the challenges that we face. You know, the fact of the matter is that the EPA, under a court's decision, is going to have the ability to write these regulations. We're taking the responsibility to do it here in this Congress. The fact of the matter is, despite some of the contrarian views on this floor, there is a real global crisis that we face. Despite the objections of my colleagues on the other side, there is a need to create new jobs, and this bill would create 1.7 million of them. But I want to give you one other reason that we should support this change in our policy. Ahmadinejad, the Saudi kingdom, they want exactly what my Republican friends are advocating-Don't do anything. Keep pumping the same amount of petroleum. Keep using

the same amount of oil. Every time we put the pump to our gas tanks, we are helping the tyrants in Iran and the tyrants in Saudi Arabia export their terrorism. Why do we keep doing it? We need to change our behavior, and this bill recognizes it. It reduces carbon emissions and makes our Earth safer, of course; but it also creates new jobs and takes away the lifeblood to these terrorist regimes. We can't come to the floor and say I'm outraged at what's going on in Iran, I'm outraged at what's going on around the world with the exporting of terrorism and then continue the same policies where we pay for them. That's what our present policy does. Our policies are paying for the terrorists around the world, whether we like it or not. The American people understand that. We need energy independence. We need a thriving economy that creates 1.7 million new jobs. We need to reduce the carbon emissions, despite the fact that still some people in this House deny it's a necessity. We need to act, and that's what the Democrats are doing.

GLOBAL WARMING WOW FACTS

The number of Category 4 and 5 hurricanes has almost doubled in the last 30 years. Source: Inconvenient Truth

Average global temperatures could increase 11 degrees Fahrenheit by the end of the century, with greater overall increases in the United States exceeding global averages, Source: US Global Change Research Program

By 2030, local temperatures in NYC could rise by two degrees. This compounds an existing problem, known as the "urban heat island effect." This is due to the fact the NYC's urban infrastructure absorbing and retaining heat. As a result, NYC is often four to seven degrees warmer than the surrounding suburbs, Source: PlaNYC 2030

KEY PROVISIONS IN THE BILL

Keep costs low for American families: the bill directs 15% of the allowances be auctioned with the proceeds going to consumers through a combination of refundable tax credits and electronic benefit payments. EPA and C130 estimate that the bill will cost American families less than 50 cents per day.

Bill will cut foreign dependence on oil: Would require electric utilities to meet 20% of their electricity demand through renewable energy sources and energy efficiency by 2020.

Cut Greenhouse gases: Bill reduces carbon emissions from major U.S. sources by 17% by 2020 and over 80% by 2050 compared to 2005 levels.

ECONOMIC BENEFITS

The stimulus bill and the energy bill will create 1.7 million new clean energy jobs nationwide, Source: Center for American Progress

The energy efficiency provisions alone in the Waxman-Markey bill will generate 770,000 jobs nationwide by 2030. Source: American Council for an Energy-Efficient Economy

Clean-energy investments create over 16 jobs for every \$1 million in spending. Spending on fossil fuels, by contrast, generates 5 jobs per \$1 million in spending. Source: Center for American Progress

NYS will see 109,000 new jobs and a net increase of about \$10 billion in clean-energy investments. Source: Center for American Progress

Mr. BARTON of Texas. Madam Speaker, I yield 1 minute to the gen-

tleman from California, Mr. "Surf's Up" ROHRABACHER.

Mr. ROHRABACHER. Thank you very much.

Wake up, America. What's happening on the floor today is a power grab that will leave you with empty pockets and no jobs. The jobs will go to China, and the economy will go to hell. Worse than that, the scientific basis for the claims being made to frighten us into accepting this economy-destroying legislation are wrong.

Wake up, America. There hasn't been any global warming, which is what we heard over and over and over again—there hasn't been any global warming for 10 years. In fact, the ice caps are melting, which we see over and over again. Yeah, they're melting on Mars too, which in any honest discussion would lead to the conclusion that the ice caps are melting and these things are happening because of solar activity, not because of the activity of human beings.

The science is wrong. The economics is wrong. You're going to cause great damage to the people of this country, to their well-being, in the name of phony science. There are hundreds and hundreds of scientific leaders, like Dr. Lindzen of the Massachusetts Institute of Technology, that have refuted the arguments. They are pleading with us. Pay attention to the good science. Don't hurt our people based on the false claim of global warming, which they don't even use that language anymore.

Mr. WAXMAN. Madam Speaker, I am pleased now to yield 1½ minutes to an important and distinguished member of the Energy and Commerce Committee, the gentleman from North Carolina (Mr. BUTTERFIELD).

Mr. BUTTERFIELD. I want to thank the chairman of the committee for giving me this very precious time this afternoon.

Madam Speaker, the House of Representatives is ready today to pass this historic legislation that will literally save the planet. You can call it a capand-tax all you want. You can say that the science does not support this legislation. You can say that the scientists are wrong. But I say, Republicans are wrong on this issue. We cannot afford to wait any longer to enact this legislation that will reduce greenhouse gas emissions. Chairman WAXMAN and Chairman Markey should each be commended for their extraordinary work in reaching a good compromise that will now allow this legislation to advance to the other body.

It saddens me that our Republican friends were not partners with us as we crafted this legislation, but Democrats understand the mandate of the American people, and we are moving forward. One of my roles as the vice chairman of the Energy subcommittee was to ensure that any increase in costs to consumers would be painless. So 15 percent of the allowances will be dedicated to providing a safety net for the

lowest-income Americans. My district is one of the poorest districts in America. My constituents are low-income families, and they need the assurance that their goods and services will not dramatically increase. I am pleased with the report from the Congressional Budget Office that estimates that lowincome households will actually see a net gain, not a loss, of \$40 per year as a result of the legislation in 2020. The CBO also says that it is estimated that as a result of this legislation, the average cost per household will be, as the gentleman from the State of Washington said, 48 cents a day.

I ask my colleagues to join with me in voting "yes" on this important legislation.

Mr. BARTON of Texas. Madam Speaker, I yield 1 minute to the gentle-lady on the committee from Nashville, Tennessee, Congresswoman BLACKBURN.

Mrs. BLACKBURN. Madam Speaker, this is not an energy bill. This is a tax bill. They're going to tax the air you breathe. It is a transfer-of-wealth bill. The American people are figuring this out. Our friends across the aisle have, indeed, become the party of punishment, and my constituents in Tennessee are being punished.

Listen to this: By 2012 we will lose 33,000 jobs. For the next 23 years, every year it is estimated this bill will cause us to lose 25,600 jobs. The American people are figuring this out. We want them to know it. When my colleagues come down here and talk about it being important and talk about it being historic, it's all from the negative. The impacts of this bill will shut small businesses. It will close family farms. It will shutter manufacturing plants, and those jobs will end up in China, in India. It will increase our taxes. The President told us so. Every household is going to pay between \$1,300 and \$3,100in new taxes every year. The cost of products will increase. The American people know that the bill chooses winners and losers, and the taxpayer is the big loser.

Mr. WAXMAN. Madam Speaker, I wish to yield 1 minute to the gentleman from Maryland (Mr. SARBANES).

Mr. SARBANES. I want to salute Chairman WAXMAN and Chairman MARKEY for their tremendous work on this bill.

When it comes to energy policy, the United States has been a sleeping giant; but the giant is beginning to stir. And with the passage of this legislation today, we'll awaken to a new era of possibility. That's what makes this so exciting.

This bill, the American Clean Energy and Security Act, is going to create a new framework and new space so that ordinary citizens and entrepreneurs can jump into that space and take us to the next level. And what most excites me is that this is about the future. The next generation is going to take these clean technologies, they're going to take this knowledge, and they're going to lead us to a new place.

I urge passage of this bill, and I congratulate its architects.

Mr. BARTON of Texas. I yield 1 minute to the distinguished gentleman from Oklahoma (Mr. COLE).

□ 1415

Mr. COLE. Madam Speaker, I rise today to speak against this flawed capand-trade, or rather, cap-and-tax legislation. There is no good time for a bad idea, Madam Speaker. This bad bill is nothing more or less than a national energy tax. The legislation will force American families to pay on average more than \$3,000 a year in additional energy costs.

The majority would like us to believe that passing this legislation will benefit all Americans. Nothing could be further from the truth. Under this bill, energy-producing States like Oklahoma will be economically punished and devastated. Residents in rural areas who must commute long distances to work will be disproportionately affected. Rising fuel prices, coupled with rising home energy costs, will force people to make ever tougher choices. Many will face reduced living standards; spending less, saving less, and going without many of the items they need for a decent life.

Madam Speaker, for over 100 years, the people in my State and my district have worked hard to produce the energy that this country needs. Now that energy is going to be taxed. Taking away their choices, their jobs and their future just isn't bad policy. It is punitive, and it is shameful.

Mr. WAXMAN. May I inquire how much time we have for the Energy and Commerce Committee?

The SPEAKER pro tempore. The gentleman from California has $36\frac{1}{2}$ minutes remaining.

The gentleman from Texas has 46¾ minutes remaining.

Mr. WAXMAN. At this time, I would like to yield to my colleague from California (Mr. McNerney) 1 minute.

Mr. McNERNEY. Thank you, Mr. Chairman.

Madam Speaker, I rise in strong support of the American Clean Energy and Security Act. I would also like to thank Chairman WAXMAN and Chairman MARKEY for their leadership on this issue.

Before I came to Congress, I developed new energy technologies. I have seen firsthand these industries develop by leaps and bounds. The economic benefits of the American Clean Energy and Security Act will be profound. This bill will create jobs across the country in fields as diverse as construction, engineering, education and others. These jobs will lay the foundation for long-term prosperity.

The American Clean Energy and Security Act is also a serious commitment to combating climate change. It is long past time for our country to lead in addressing this threat. Fewer emissions will mean cleaner, healthier air for our children and grandchildren.

I am also proud that the legislation includes key provisions that I wrote, including language that will spur the development of a more efficient electrical grid and provide funding for clean-energy job training. I also encourage that during the conference committee process, the opportunity is seized to strengthen the renewable energy standard. This will help ensure that the new energy projects created by this bill will utilize American-made components manufactured by American workers.

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. BARTON of Texas. I want to yield 1 minute to the distinguished ranking member of the Financial Services Committee, our expert on derivatives, Mr. SPENCER BACHUS.

Mr. BACHUS. Madam Speaker, as Under Secretary Robert Shapiro, under the Clinton administration, said, we are going to create a multitrillion dollar derivative market overnight. These will be based on carbon offsets.

These projects, most of them, we anticipate, will be in underdeveloped countries or foreign countries, almost all of them. And when you start a project, a clean-coal project in China or India, or you plant trees in Borneo and Brazil, who pays for it? The American taxpayers. Does it reduce discharges and pollution here? No. It absolutely allows you to discharge carbon dioxide into the environment here in the United States.

Before you vote for this bill, ask yourself, if the subprime lending market was hard to police, how do you police the derivatives market based on projects in China and Borneo? Ask yourself, am I going to stick my constituents with the cost of clean-coal projects in China? Go home and explain that to your constituents. Go home and explain how you're going to plant trees in Brazil. They are going to pay for it. It is going to allow more pollution here.

The SPEAKER pro tempore. The time of the gentleman has expired.

ANNOUNCEMENT BY THE SPEAKER PRO TEMPORE

Members are reminded to address their comments to the Chair.

Mr. WAXMAN. I wish to yield 1 minute to the gentlelady from Ohio (Ms. Sutton).

Ms. SUTTON. Madam Speaker, I rise in support of this legislation, and I want to thank the chairman for his leadership and for working with me and other Members of this House to address our concerns about manufacturing and jobs in this bill.

This bill isn't perfect. I have yet to see a bill that is. But the status quo is not the right choice. We must unleash the entrepreneurial spirit of this country and provide the economic opportunities that our constituents need. This bill is part of that mission. It is not the entire answer to all that ails us. But let there be no mistake. This is a jobs bill. This bill has support from groups that represent workers; the United

Steel Workers, the UAW, the SEIU, CWA, Building and Construction Trades and the AFL-CIO are all urging a "ves" vote on this legislation.

Madam Speaker, the people I represent are facing difficult times. They are looking for jobs, and sometimes they can't find them the way they used to. The inaction of the past has cost them dearly.

There are those who complain that this bill is not perfect. They say it won't do this or it won't do that. But we have got to get started and keep acting until we get it right and provide them with the chance that they need for a change in direction.

Mr. BARTON of Texas. I want to yield 1 minute to "Mr. Iowa Agriculture," Mr. LATHAM of Iowa.

Mr. LATHAM. I thank the gentleman.

Everyone understands that we are in the middle of a very difficult downturn in the economy, a recession. It is difficult enough today to create jobs. We have the second-highest tax rate in the world. We have the most onerous regulatory burden in the world. We have the most litigation in the world. So how do we create new jobs? Well, it is not with this tax-and-cap bill.

I will tell you, in China today they must think that Christmas is coming in June. If you look at this box here, it says "To China from the U.S. Congress." Well, let's see what is inside of it, okay?

What is inside of it is U.S. jobs. This is going to cost 17,000 jobs in Iowa in 2012 and each year after that. Nationwide, 2½ to 3 million jobs will be lost because of this bill.

If we are going to do anything to help the economy, let's not put another burden, let's not make us less competitive in the world, and let's not destroy hope for the next generation, which this bill does.

Please vote "no" and save our country.

Mr. WAXMAN. Madam Speaker, I'm pleased at this time to yield to a real leader from the State of Iowa who has taken an active role in this and so many other policy areas, Mr. BRALEY, for 1 minute.

Mr. BRALEY of Iowa. Madam Speaker, this is a defining moment in our country's history. And last night out at the White House, I saw the chairman holding his grandchild in his hands. The question every Member of this body is going to have to face when they look into the eyes of their children and grandchildren is, Where were you on this pivotal vote in our country's history? Where were you when we tried to free ourselves from our dependency on foreign oil? Where were you when we tried to create a new energy policy based on clean energy like the cleanenergy revolution taking place in my State of Iowa?

This bill won't cost jobs in Iowa. It will create thousands of jobs in clean energy. That is what the message is I'm sending to my children. That is the

message I'm sending to my grandchildren. This is the time to break away from Middle East oil oligarchs, set a new policy for our energy future. and send a message to the world that we will be leaders, not followers, when it comes to climate change.

Mr. BARTON of Texas. Madam Speaker, I want to yield myself 30 seconds just briefly.

According to David Sokol, the CEO of MidAmerican Energy, which serves most of the utility customers in the State of Iowa, the bill before us will raise utility prices, for every residential customer in Iowa, \$110 a month, or \$1.320 a year. That is not a job creator in Iowa; that is a job killer in Iowa.

I now want to yield 1 minute to a distinguished member of the committee from the great Keystone State, Mr. TIM MURPHY of Pennsylvania, 1 minute.

Mr. TIM MURPHY of Pennsylvania. A headline in yesterday's Pittsburgh paper said "More Pa. Residents Suffering in Recession, Poll Shows." And this is the time to give people in Pennsylvania, and throughout the Nation,

Pennsylvania and the Pittsburgh area is the area that was built upon energy. We had abundant supplies of coal, natural gas and water. That is why steel was there. We invested in the National Energy Technology labs, and we still have hundreds of years of coal.

Folks, this is a time when we need to improve the efficiency of wind and solar so we can have them as energy resources. But let's not abandon steel because you can't make it without coal. Let's not abandon coal. And let's make sure we invest in clean coal. This is a time when we say to kids that right now we get about 35 percent of our energy out of a lump of coal. And it does pollute. What we have to do is clean it up, invest in that and build clean-coal plants. Whoever figures out how to do that, that is Nobel Prize material. It is the scientific, technological, and educational challenge of our generation.

And what's more, you can't have lights on without doing that. Let's do all of the things we need to do. But this bill is not the way to do it. We can solve these problems. But we can't rush into it the way we are doing it now.

Mr. WAXMAN. Madam Speaker, at this time, I want to yield to the distinguished sole representative from the State of Vermont, a man we are very pleased to have on our committee and who has been a leader in some of the areas on this bill. He reminds us that efficiency is the way to go to use less fuel. I yield 1 minute to Mr. WELCH.

Mr. WELCH. Thank you, Mr. WAX-

Madam Speaker, although some dispute it, there is little doubt that oil is a finite resource and we are at or near peak oil, that global warming is real, that the threat to our economy is immediate and that the need to act is urgent.

And while our friends on the other side raise questions about how our ac-

tions will affect jobs and utility bills, those very legitimate concerns have been exhaustively addressed in this legislation.

But what they fail to acknowledge is that the cost of inaction is great in lost opportunity for jobs, a cleaner environment and a stronger economy. Many of the new jobs in Vermont and around the country are related to the new clean-energy economy.

Madam Speaker, today Congress will make a very fundamental decision. Will America confidently and directly declare a policy of American energy independence? Will it unleash the talents of our scientists and engineers. empower our entrepreneurs and manufacturers? Will it put to work our farmers, carpenters, masons, electricians plumbers through efficiency, and through renewable energy and through the new technology for coal?

The great decisions a nation makes, Madam Speaker, are always about facing our problems, not retreating from them, and about the conquest of hope over fear.

I first wanted to thank Chairman WAXMAN, Chairman MARKEY, and the Energy and Commerce Committee staff for their tremendous work and leadership on this legislation. To bring to the floor the first ever bill to address our global warming crisis was no small feat, and while we would all like to see changes in this bill, it represents the best step forward toward charting a new energy future for our country.

If civil rights was the issue of my generation, addressing climate change is the issue of today's. The young people and students across this country deserve great credit for providing the energy-renewable, of course-behind this historic legislation. They have the most at stake; they will inherit this planet and the economy we leave them. Their future must be addressed now.

Earlier this year when we first began taking testimony on this legislation, I had the opportunity to ask executives of some of the world's largest companies whether Congressional inaction for addressing climate change threatened their bottom line, their viability, and our economy. One by one, they each responded: "yes . . . yes . . . yes." These were our nation's economic leaders unanimously recognizing the urgent need for a new, post-carbon economy.

The scientific facts are clear: global warming is real, it is urgent and it threatens our economy, our national security, and our way of life if unaddressed. We must tackle this challenge squarely, like the confident nation that we are.

Addressing this challenge presents us with opportunity—an opportunity to create new, green jobs and build a stronger economy; an opportunity to make our country more secure and energy independent; and an opportunity to save on electric bills at home and turn better profits at the workplace.

This legislation sets us toward the bright future of a post-carbon economy. If we don't make this commitment now, nations like Japan, Germany, Brazil—countries around the world will outpace us and leave us far behind.

In this legislation, we take the bold steps necessary-with a firm cap on carbon pollution, new renewable energy and energy effi-

ciency standards, and investments in renewable energy development. But we also make policy changes throughout our energy economy that will help hard working Americans get and stay ahead.

We create a national Certified Clean Stove Program, building on Vermont's success to encourage those who heat their homes with wood stoves to install cleaner-burning stoves.

We establish the nation's first energy efficiency improvement target.

Among many consumer protection previsions, but critical for states like Vermont, we establish consumer rebates and weatherization efficiency investments to residents in states that rely upon home heating oil.

And we establish The Retrofit for Energy and Environmental Performance (REEP) Program to provide billions of dollars in financial incentives to homeowners and business owners to encourage them to retrofit the nation's existing buildings, which account for 10 percent of global carbon emissions. This program, supported by the Home Builders, Realtors, NRDC and others, will create thousands of iobs and help homeowners and business owners save on energy bills.

At less than the cost of a postage stamp a day, through this bold legislation we will make our nation more secure, create a new, more efficiency, more productive, more prosperous

energy future.

When President Kennedy said we would put a man on the moon, many thought it wasn't possible. We did it. Today, we take the bold and necessary step to address one of the most pressing and urgent challenges in generations.

As the author of the provisions of this bill that creates the Retrofit for Energy and Environmental Performance (REEP) Program Act. it is my goal to ensure the greatest possible participation in efforts to reduce energy consumption in residential and commercial build-

It has come to my attention that real estate investment trusts (REITs) may be reluctant to participate in this program as it is currently crafted. They are concerned that they may lose their REIT status unless the REEP grants are considered qualifying assets that generate qualifying income for the purposes of the REIT income and asset tests.

Listed REITs own and manage over 6 billion square feet of commercial real estate. This is a significant amount of property that, if retrofitted, could yield significant energy savings.

Therefore it is my hope that as this bill moves through the legislative process we will include the necessary clarifications to ensure that REITs will be able to fully participate in the REEP program.

Mr. BARTON of Texas. Madam Speaker, could I inquire as to when the majority is prepared to go to the Ways and Means Committee's time?

 $\operatorname{Mr.}$ WAXMAN. If the gentleman would yield to me, when our time expires for both committees. Perhaps we ought to let you take additional time at this point, because we have used far more than you have.

Mr. BARTON of Texas. I have agreed to do that. But my question is, when is it the intention to allow the Ways and Means Committee to use their time? Is that in the next 15 minutes or is it around 3 o'clock? When is your inclinaMr. WAXMAN. If the gentleman would yield, perhaps we can inquire of the Chair how much time is still available to the Energy and Commerce Committee.

The SPEAKER pro tempore. The gentleman from California has $32\frac{1}{2}$ minutes remaining.

The gentleman from Texas has 431/4 minutes remaining.

Mr. BARTON of Texas. I just need a planning estimate to tell the Members on my side when we are going to go to the Ways and Means. I'm not being argumentative.

Mr. WAXMAN. Why don't we discuss that informally?

Mr. BARTON of Texas. At this time, I want to yield to another distinguished member of the Energy and Commerce Committee from the Pelican State, Mr. SCALISE, 1 minute.

Mr. SCALISE. Madam Speaker, I want to thank the gentleman from Texas for yielding.

I stand here to strongly oppose this cap-and-trade national energy tax that is being proposed to be created here today.

One of the things we have heard is about jobs. Let's talk about jobs. The National Association of Manufacturers estimates the United States will lose 3 to 4 million jobs if this bill becomes law. The President's own budget director has said American families will see a \$1,200 increase per year on their electricity bill if this bill becomes law. That is the policy that they are trying to pass. That is the policy we are standing up and opposing today.

Let's talk about job loss. If you look at the bill, they have 55 pages in this bill dedicated to job losses. Now why would they put 55 pages in the bill dedicated to job losses if they didn't think this was going to lose jobs and run those jobs over to China and India?

And the real irony is for those who think that we need to reduce carbon emissions, this bill will actually increase carbon emissions because when that steel mill moves from the United States to Brazil, four times more carbon is emitted to produce steel in Brazil than in the United States. And not only do we lose jobs, they emit more carbon. This is a horrible way to wreck the American economy. We need to defeat it.

□ 1430

Mr. WAXMAN. Madam Speaker, I wish to yield to the gentleman from Michigan and chairman emeritus of our committee (Mr. DINGELL) so he and I could engage in a colloquy.

(Mr. DINGELL asked and was given permission to revise and extend his remarks.)

Mr. DINGELL. Madam Speaker, I ask my good friend to join in a colloquy about the electric transmission provisions. I support renewable power, as does he. However, there is a delicate State-Federal balance of authority in this area.

I yield to my good friend.

Mr. WAXMAN. I agree we must be sensitive to the State and Federal roles, but we must also move forward on transmission policy. My goal here is to take the first step.

Mr. DINGELL. I have concerns about the wisdom of splitting the country in two parts, into eastern and western interconnections, for the purpose of regulating transmissions. Does my colleague agree we should have a unified national transmission policy?

Mr. WAXMAN. Yes, that is my preference. However, there is more consensus about how to move forward in the western interconnect than there is in the eastern interconnect, and we should make the progress we can in the west. I will continue to work towards a policy that is comprehensive and effective.

Mr. DINGELL. I thank my good friend. I have a further question. I am also concerned that wilderness areas and conservation easements be fully protected, particularly in the eastern interconnection.

Mr. WAXMAN. This proposal leaves in place the current environmental protection in the eastern interconnection. The changes in the west account for the very sensitive nature of the lands there, including Federal lands.

Mr. DINGELL. Reclaiming my time, finally, the effect of this language on existing law is unclear, which might only lead to more litigation and delay.

Mr. WAXMAN. Well, we need a policy that is clear and can be implemented. This is only a partial step forward, as I have said, and I look forward to having your help in adopting a workable policy.

Mr. BARTON of Texas. I yield 1 minute to a distinguished senior member of the committee from the great State of Georgia, Mr. DEAL.

Mr. DEAL of Georgia. I thank the gentleman for yielding. There are many issues that need to be discussed. I rise in opposition to this legislation. One of the topics is that of jobs. We are told we are going to gain jobs. By most reasonable estimates, we are going to lose jobs. The best example of that is to look at what happened in Spain. Spain has traveled this path of renewables and green energy. Their estimate is that for every job they gained, they lost over two. I don't consider that to be a direction that our country needs to go, especially in these difficult economic times.

The second thing that needs to be said is that there is a disparity that is being created in the renewable portfolio requirements. For portions of the country such as Georgia and the Southeast, in general, we don't have the volume of alternatives that are allowed under this legislation, especially if we are not going to get credit for the nuclear plants that we are trying to bring on board in our State. Therefore, we will have to purchase those credits from some other part of the country, something that I think will have an undoubtable, definite negative effect

on the power bills of the citizens of my State.

I rise in opposition to the legislation and urge my colleagues to vote against it.

Mr. WAXMAN. Madam Speaker, I yield 1 minute to the gentleman from Georgia (Mr. Scott) for the purpose of a colloquy.

Mr. SCOTT of Georgia. Madam Speaker, let me thank Chairman WAX-MAN for the excellent job he has done in providing leadership and for expanding the renewable energy standard to reflect the interests of my constituents in Georgia, and certainly the Energy Star home labeling program.

As you know, Mr. Chairman, there is one issue that I have discussed with you that I am very concerned about that we are working our way through, and I would like to enter into a colloquy with you. I am concerned about the jurisdiction of derivatives.

I serve on the Agriculture Committee and the Financial Services Committee. We feel very strongly that any language in this dealing with the regulation of derivatives certainly should be handled by the Financial Services and Agriculture Committees, and you and I have discussed that, and I would like to know how that is done, particularly in view of the fact that 95 percent of the 500 largest global corporations use derivatives for risk management.

I yield to the gentleman.

Mr. WAXMAN. You and others have expressed concern about this issue. This matter will be determined by the work of the Financial Services Committee and the Agriculture Committee. We have a placeholder in the bill. Once they agree on the issue that is within their jurisdiction, it will be placed in the bill.

I want to point out that you have a unique role in that because you are on both committees and have a special interest on this question. So I look forward to seeing your work on that matter.

Mr. SCOTT of Georgia. I thank you, and with that I will certainly support the bill and urge my colleagues to support the bill.

Mr. BARTON of Texas. I yield myself 15 seconds.

We have just experienced something somewhat revolutionary. We have a bill before us that has a placeholder in the bill. We are passing a bill with a placeholder to be determined later. I have never seen a final passage on a bill that had a placeholder in the bill.

With that, I yield to Mr. PITTS, a member of the committee from the State of Pennsylvania, for 1 minute.

Mr. PITTS. Madam Speaker, like all of us, I believe we should work to decrease the amount of greenhouse gas emissions in our atmosphere, and we should be good stewards of this Earth and its resources. However, I don't believe this bill will accomplish a dramatic decrease in greenhouse gas emissions; yet I do believe it will have a crippling effect on our economy for years.

No matter how you doctor or tailor it, it is a tax, a national energy tax that will hurt each and every household. It will destroy sectors of our economy and cause job losses at an unprecedented rate.

Here is a chart that shows the jobs losses in thousands of jobs here, nearly 2 million jobs, 2012; 2035, over 2 million jobs a year. We should be protecting our environment through innovation, through entrepreneurship and cooperation, but this bill tries to cut carbon emissions through punishment taxation, heavy hand of government, and litigation.

The bill as originally introduced, analyzed by the PUC, a bipartisan group in Pennsylvania, said it would cost Pennsylvanians 66,000 jobs by the year 2020.

I urge my colleagues to consider just how irresponsible it is to move legislation that is going to cost so many jobs, so much damage to our economy, and yet it is anticipated to slow temperature increases by only two-tenths of 1 degree Fahrenheit by the end of the century. There is a better way.

Mr. WAXMAN. Madam Speaker, I yield 1 minute to the gentleman from Maine (Mr. MICHAUD) for the purposes of a colloquy.

Mr. MICHAUD. I rise for a colloquy with the chairman of the Agriculture Committee, Chairman PETERSON. I want to thank Chairman PETERSON for his hard work on that legislation, and I seek clarification of two provisions in section 788 of the bill relative to the forest land and forestry sector.

Specifically, on page 198, line 14 of the bill, I would like to know if the agricultural sector language includes forest lands and forestry sector. Also, on page 199, line 22 of the bill, I would like to know, does the term "projects" include sustainable forest practices, such as avoided deforestation agreement?

Mr. PETERSON. I want to thank the gentleman for his work on improving the definition in this bill and assure him that, just as with many USDA conservation programs, forest land fully qualifies for this energy incentive program and it is our intent that it be included in this section. Both the terms "agriculture sector" and "projects" in 788 are inclusive of forest land and could be used to provide incentives for private forest land owners who may not otherwise qualify to participate in the ag offset program.

I will continue to work with the gentleman. He can be assured this will be included.

Mr. MICHAUD. I thank the gentleman for that.

Mr. BARTON of Texas. I yield myself another 15 seconds.

I want to tell all of the Members, if you haven't made your deal yet, come on down to the floor. What we are seeing is unprecedented. We're making deals on the floor. I want to commend Mr. WAXMAN; at least he is now doing it in public. I mean, that is unprecedented, but at least it is transparent.

With that, I yield 2 minutes to the gentleman from Florida (Mr. STEARNS). ANNOUNCEMENT BY THE SPEAKER PRO TEMPORE

The SPEAKER pro tempore. The gentleman will suspend.

Members are reminded to address their remarks to the Chair.

Mr. STEARNS. Madam Speaker, you know, this is a defining moment. And "where were you when this legislation came on the floor" is going to be something that you're going to remember.

As the ranking member has indicated, the lobbying on this by Vice President Gore and the President and all of the people has been tremendous, and there is a possibility that they still don't have the votes. One of the reasons is there is not a fairness factor here.

China adds more CO_2 to the atmosphere each year than any other nation in the world. However, they have consistently said they reject any binding international cap on such emissions and claim the right to continue to increase its release of greenhouse gases while at the same time we are going to pass—attempt to pass this legislation.

My colleagues, without equivalent efforts by China and India to limit greenhouse gas emissions, the United States stands to lose many hundreds of thousands of jobs to these countries that will profit from this bill today.

The proponents of this legislation say we should make unilateral reductions, unilateral disarmament, which will in turn impose moral pressure on other countries. I find it hard to believe that China and India will reduce their economic growth and idle their people because they are willing to adopt a cap-and-trade. The cap-andtrade is flawed. China and India are not going to go forward. Any meaningful effort to achieve long-term, sustainable reductions in global greenhouse gas emissions depend on the development and deployment of new energy technologies, we all agree, we must include clean coal technologies, carbon capture and sequestration, and advanced nuclear power generations. I had an amendment that was designed to do this. It was not allowed.

The rapid development demonstration of widespread deployment of such technologies are of paramount importance in any reasonable and any effective effort to address CO_2 reductions. The massive new regulatory burdens imposed by this cap-and-trade scheme will invariably cut the growth and innovation in this country and we will lose jobs. Let's foster new technology. Let's not pass this bill.

Last night, I offered two substantive amendments to improve this flawed legislation. One of my amendments would have allowed states that have existing nuclear power plants to more easily meet the Renewable Electricity Standard by excluding all electricity generated by nuclear power from a retail electric suppliers bases amount. My other amendment would have eliminated the home Energy Star labeling program that will further reduce property values at a time when many homeowners

have seen their equity and retirement savings vanish. Unfortunately, both of these amendments were struck down by the Rules Committee along with 221 other amendments.

Quoting from yesterday's Wall Street Journal editorial, Americans should know that those Members who vote for this climate bill are voting for what is likely to be the biggest tax in American history."

In fact this cap and tax scheme could cost families up to \$3,100 more per year and result in real GDP losses of \$9.6 trillion over the life of the bill, especially if we do it alone.

China adds more CO₂ to the atmosphere each year than any other nation in the world, however they have consistently rejected any binding international cap on such emissions and claims the right to continue to increase its release of greenhouse gases. Without equivalent efforts by China and India to limit greenhouse gas emissions, the U.S. stands to lose many hundreds of thousands of jobs to these countries that will profit from this bill.

The proponents of this legislation say we should make unilateral reductions, which will in turn impose moral pressure on other countries to reduce their emissions. I find it hard to believe that other nations would follow the United States in reducing economic growth and idling millions of workers. Although cap and trade is flawed, there is much that we can do to reduce carbon emissions and our dependence on imported energy sources.

Any meaningful effort to achieve long-term, sustainable reductions in global greenhouse gas emissions will depend on the development and deployment of new energy technologies, including advanced clean coal technologies, carbon capture and sequestration and advanced nuclear power generators. The rapid development, demonstration and widespread deployment of such technologies are of paramount importance in any reasoned and effective effort to address carbon dioxide reductions.

The massive new regulatory burdens imposed by this cap and trade tax scheme will inevitably undercut the growth and innovation we desperately need to build lasting and effective solutions. Fostering new technology and scientific research across all sectors of the economy, not capping our economy and trading U.S. jobs, will guard our nations security and increase our energy independence.

I encourage all my colleagues to join me in strong opposition to this legislation.

Mr. WAXMAN. Madam Speaker, I reserve the balance of my time.

Mr. BARTON of Texas. Madam Speaker, I yield 3 minutes to the gentleman from Virginia (Mr. CANTOR), the distinguished minority whip.

Mr. CANTOR. Madam Speaker, if there is one thing everyone in this Chamber should be able to agree on, it is that we need to focus on job creation and relieve the burden on middle-class families, not increase it. Yet the evidence suggests that by taking up this cap-and-trade bill, we are abandoning this fundamental mission.

According to an MIT study, the legislation before us will force America's middle-class families to pay as much as \$3,100 in higher prices every year. The EPA, meanwhile, estimates that a family of four will eventually pay an additional average of \$1,100 each year.

The impact on jobs is equally dismal. A CRA International study finds the legislation, when fully implemented, will cost America 2.3 to 2.7 million jobs. This, at a time when hundreds of thousands of workers are losing their jobs every month.

In the midst of a severe recession, why would we even contemplate a plan that amounts to a growth-killing mill-stone around the neck of small businesses and all American consumers.

Madam Speaker, it is not the utilities, the oil companies, and the other producers who will bear the cost of this new regime. We already know that the companies will pass their higher costs along to the consumers and small businesses that rely on their services. This means more expensive bills for all Americans on everything from electricity to heating to gasoline to groceries.

We also can't forget that this national energy tax comes down hardest on the poor. The highest income quintile spends less than 5 percent of its income on energy-intensive products, but our families in the lowest income quintile spend over 20 percent on those items—this, according to CBO.

□ 1445

Madam Speaker, with a watchful eye toward the consequences for jobs and economic growth, let us give thoughtful consideration to the limited benefits this unilateral action will bring about. Even if the bill cuts U.S. carbon emissions to 83 percent of current levels by 2050, we still are only anticipated to slow global temperature increases by a mere two-tenths of a degree.

And then there's the real elephant in the room, India and China. Both of these freewheeling nations are growing rapidly and not prepared to slow down. Do we really want to hamstring U.S. industry and put it at a competitive disadvantage to Asia? Can we be so naive to assume our businesses, jobs—and emissions—won't emigrate to China and India?

Moving to eliminate CO_2 from the atmosphere is a noble endeavor, but taking this kind of action without enforceable carbon commitments from our competitors is only an exercise in futility.

Madam Speaker, Republicans remain committed to bringing a swift end to the recession and paving the path to prosperity. We intend to focus on policies that will put people back to work and grow the economy. That does not include this cap-and-trade proposal. With stakes so high, gambling the house away on such a high-cost, low-reward program is a grave mistake that Republicans will not support.

Mr. BARTON of Texas. I yield 1 minute to the distinguished gentlelady from West Virginia, Congresswoman CAPITO.

Mrs. CAPITO. Madam Speaker, at a time when families are already struggling to meet their basic needs, the last thing we need is a new energy tax on all consumers, and that's exactly what this cap-and-trade bill is. It is a national energy tax that will burden consumers, burden businesses, and particularly burden the lower-income families in this country. It picks regional winners and losers, with coal-dependent States like mine, West Virginia, bearing the brunt of this bill.

Under this bill, we will actually be penalized for our lower-cost power and will have to pay more to continue using our greatest resource, coal. We should be innovating towards clean coal and carbon sequestration where we can continue to use our most abundant resource.

We all want cleaner sources of fuel and more efficient energy, but this capand-trade bill is not the way forward. This bill is a jobs killer. This bill has real costs for real people. Vote "no" on this bill.

The SPEAKER pro tempore. The gentleman from New York is recognized for 15 minutes.

Mr. RANGEL. Mr. Speaker, I rise today in support of the American Clean Energy and Security Act of 2009 and urge my colleagues to support it.

Listening to the beginning of this debate. I'm convinced that—one of the people on the other side said that our voting today will be well remembered, not by Democrats and Republicans, but by the entire world. We know that we have a crisis. It is a universal crisis: it's a crisis that affects our country and our communities. But the ironic thing about it with the other side, all of their comments have been in criticism of the great work that has been done by Congressmen WAXMAN and MARKEY and their committee, the Ways and Means Committee, and those that were concerned about perfecting something to protect the people of this Earth. And just as they will remember the courageous and political forces that were put together to make this great contribution to humankind, they also will remember the negative political shots that have been taken and the absence of any positive program that the minorities have brought forward.

I congratulate our great Speaker for coordinating this effort. People call it, on the other side, "deals," when they don't have any ideas to put forward. But "deals," if it means bringing people together and getting a better bill and moving forward in order to provide a majority, then I'm proud to be on this side of the aisle.

Mr. Speaker, I reserve the balance of my time.

Mr. BARTON of Texas. I yield 1 minute to the member of the committee from the Golden State of California (Mr. RADANOVICH).

Mr. RADANOVICH. Mr. Speaker, I rise in strong opposition to the global cap-and-tax bill that is on the floor today. You don't have to look any further than my own beloved State of California to see environmental alarmism at its worst. California has

adopted its own renewable energy standard and carbon cap-and-trade scheme. It's killing business in California and driving people out of the State in record numbers.

Rural and agricultural communities will be most affected by this bill, forcing local agriculture producers to pay more for seed, equipment, machinery, steel, and other supplies. If you like getting your oil from Hugo Chavez, with cap-and-tax you're going to love getting breakfast, lunch and dinner from him too.

If we were truly interested in achieving dramatic reductions in CO_2 emissions without destroying our economy, we should preserve our robust economy and allow the free market to continue to produce commercially viable energy efficiencies and clean-energy technologies

I urge my colleagues to do something good for the economy and the environment and put this bill where it belongs, in the recycle bin.

Mr. BARTON of Texas. Will the gentleman from New York yield for a procedural inquiry?

Mr. RANGEL. I would be glad to.

Mr. BARTON of Texas. I've got two nonmembers of the Ways and Means Committee that I would like to go out of order to get us in balance so Mr. CAMP and you can balance each other.

Mr. RANGEL. I yield to the gentleman.

Mr. BARTON of Texas. I yield 1 minute to the gentleman from New York (Mr. Lee), and I want to thank Mr. RANGEL for his courtesy.

Mr. LEE of New York. I thank my friend for yielding.

The people in my district know only too well that when Washington applies itself to a problem, it overregulates and always hides the true cost to the taxpayer. This bill is truly no different with it being over 1,100 pages in length and 50 pages dedicated to regulating light bulbs.

In order to garner enough votes, the majority has tried to shift the most punitive cost of this bill to later years so they can get it passed. Early on, it will be the government footing this enormous bill with your tax dollars, and then down the road this subsidy will shift to consumers who will pay directly to sustain this program through higher, job-killing energy prices. Either way, it's the taxpayer who bears the burden.

This bill is truly a pipe dream. We need to focus on an energy solution that rewards innovation using American-made energy, not trying to find a way to tax our way to prosperity and continue this horrific job loss. That is why I urge my colleagues to oppose this bill.

Mr. BARTON of Texas. Mr. Speaker, I yield 1 minute to the distinguished Congresswoman from Illinois, a member of the Science Committee, Congresswoman BIGGERT.

Mrs. BIGGERT. I thank the gentleman for yielding.

Mr. Speaker, I rise in opposition to the American Clean Energy and Security Act.

In my home State of Illinois, we depend on nuclear, coal, and natural gas for our electricity. Because this bill discriminates against these energy sources, Illinois will be hit especially hard. Gas prices could rise by 77 cents a gallon and diesel by 88 cents a gallon. This is part of an entirely arbitrary penalty on oil and gas that is passed straight on to the consumer.

H.R. 2454 does little to incentivize new nuclear production, despite the fact that nuclear power is safe and emissions free, and what little it does is grossly inadequate concerning the overall goal of this bill.

I am deeply concerned also that there is no framework for an international agreement on climate change in this bill. In the absence of such framework, and in agreement from developing nations, my district can count on losing thousands of jobs to countries like India and China if this legislation is enacted.

Mr. Speaker, I oppose this bill and urge my colleagues to do the same.

Mr. RANGEL. Mr. Speaker, I yield 2 minutes to the gentleman from Michigan, Chairman Levin.

(Mr. LEVIN asked and was given permission to revise and extend his remarks.)

Mr. LEVIN. Action on climate change is a policy, indeed, a moral imperative. Prompt action is a vital part of our legacy to the Nation, and to our children and grandchildren.

As we act, we can and must ensure that the U.S. energy-intensive industries are not placed at a competitive disadvantage by nations that have not made a similar commitment to reduce greenhouse gases.

After discussions between the Energy and Commerce and the Ways and Means Committees and the administration, we have developed reasonable and effective provisions which involve the President and the Congress in taking action—no more than necessary—to ensure that this important legislation is trade-neutral for our energy-intensive industries.

We want to see a meaningful international agreement. If we are unable to do so through an international agreement, this legislation ensures that the U.S. will avoid carbon leakage in its energy-intensive and trade-sensitive industries.

There are some critics—and we may hear from them today—who claim that these changes make the bill subject to trade challenges. They are wrong. Just today, the World Trade Organization and the U.N. Environment Program issued a report which confirms that "WTO rules do not trump environmental requirements."

Mr. CAMP. Mr. Speaker, I yield myself 3 minutes.

As a candidate, the President stated that under his energy plan "electricity rates would necessarily skyrocket." I give him credit, he was being honest with the American people.

Today, the Nation's unemployment level is fast approaching 10 percent. That means one out of every 10 Americans will soon be without a job and without a paycheck to provide for themselves and their families. Yet, this national energy tax will drive up prices while making jobs scarcer. In fact, one utility which is even supporting this legislation has already applied to State regulators to raise their electricity rates in anticipation of the cost of complying with this national energy tax.

While the Speaker wants us to pay more in energy taxes, China and India have repeatedly said they will not follow suit. They will not impose those hardships on their people. This shouldn't surprise us. As our mothers used to ask, if everyone else jumped off a cliff, would you? Of course not. Neither will China and India. They recognize enacting these caps is like jumping off an economic cliff.

So what does a "yes" vote mean? It means more American manufacturing jobs move to China and India, fewer Americans have jobs, and there is no reduction in global greenhouse gases. And because this bill was rushed to the floor, because the American people were not given a chance to review it because their Representatives were not given a chance to improve it through the committee process, this bill contains numerous flaws.

The border measures, which the Committee on Ways and Means has not reviewed, are an area open for our trading partners to retaliate against our goods and against our workers. How does this help our economy? How does this help families? How does this help our environment? It doesn't.

Now, I know promises have been made that your constituents won't be harmed by this bill, that it contains plenty of consumer protections. What are those protections? Who's going to get them? Not the middle class. Not the people the President promised to protect, families making less than \$250,000 a year. Somewhere in this House late at night someone made the decision to eliminate the tax credits designed to help middle class families pay for these high energy prices.

Here are the plain and simple facts: under the Speaker's national energy tax, a family of four with income over \$33,000 per year will lose under this bill. They, and 235 million other Americans, will pay higher costs and receive no help in offsetting those costs. Let's be clear what this means: three out of every four Americans will pay more under this bill.

The Speaker's national energy tax is bad for our economy, bad for families who are already struggling to make ends meet, and it will do nothing to reduce global greenhouse gas emissions. It's all pain and no gain. I urge my colleagues to vote "no" on this bill.

Mr. Speaker, I reserve the balance of my time.

Mr. RANGEL. When the Republican Party becomes the protector of the poor, it's a day that I've been waiting for.

I would like to yield 2 minutes to Mr. LARSON, an outstanding leader of the Democratic Party.

Mr. LARSON of Connecticut. I thank the distinguished chairman.

Mr. Speaker, it has been an interesting day in listening to the claims that have emanated from the other side of the aisle, claims about honesty, claims about being forthright. The President of the previous administration, President Bush, stood on the floor and claimed our addiction to oil, and everybody put their head in the sand and did nothing as we continued to send and export American dollars overseas.

We send American taxpayer dollars overseas to Russia, to Saudi Arabia, to Libya, to Venezuela, all the people that you have chimed in about today. That's the real tax that we are paying because of our increasing addiction and our need to stand up and rid ourselves of dependency on foreign soil.

So the challenge faces us once again—it was here 30 years ago, and we didn't have the courage to make the stand, nor the patriotic fervor or fiber to stand up and do the right thing.

□ 1500

Stop this addiction. If T. Boone Pickens can get out front across this country and talk about this awful addiction, and, as Thomas Friedman said very eloquently, if the American policy of the previous administration is to "leave no mullah behind" and find our funds that we pay with American taxpayers going to fund our enemies' efforts against our own troops in our efforts against terrorism, that is what this is about in the final analysis. It's about this great country of ours and making a stand for what we believe in, standing up for American dominance and superiority.

Yes, the Chinese and Indian nations are out there competing. We want to compete against them because we have better technology. We just have to make the investment here and not in Saudi Arabia and Libya and Venezuela and Russia. That's what the policy of previous administrations have led us to. And that's where it must end today, on this floor.

Mr. CAMP. Mr. Speaker, I wish the gentleman's passion was directed at bringing the bill before the Ways and Means Committee.

With that, Mr. Speaker, I yield 1 minute to the distinguished gentleman from California (Mr. HERGER).

Mr. HERGER. Mr. Speaker, not only is this legislation not the right thing; this legislation is one of the most overreaching, damaging pieces of legislation that has ever come before this House of Representatives.

This national energy tax is a job killer and will cost American families over \$3,000 per year while doing very little

to affect global temperatures. Rural America, low- and middle-income families, and our farmers will suffer the most under this new tax.

Mr. Speaker, we all want to protect our environment. But we should accomplish that through innovation and investment, not by government micromanagement that undercuts Americans' ability to compete globally.

I urge all Members to protect the American economy and livelihoods of millions of American families and say "no" to this gigantic national energy tax

Mr. RANGEL. Mr. Speaker, I would like to yield 2 minutes to the gentleman from Massachusetts, Chairman NEAL.

Mr. NEAL of Massachusetts. I want to commend Mr. RANGEL and Mr. WAXMAN and Mr. MARKEY, who have attempted against long odds to forge a consensus on this legislation.

Mr. Speaker, the bottom line to this legislation as proposed today is it will make America less dependent on foreign oil. And, remember, despite protestations to the contrary from our friends on the other side, there is an element on the other side who rejects to this day the concept of climate change and global warming. It is very difficult to find middle ground if there's a side that simply rejects the science of our times. Part of our job in leadership in governing is to make some difficult decisions and, indeed, some very tough choices. This climatechange bill we have before us today makes those tough choices for our future and our children's future. It's in the interest of America, but just as importantly, it's in the interest of the world. America leads the way, and this is an opportunity for us to reclaim that leadership.

This legislation will lead our consumers, our businesses, and our communities towards smarter, cleaner, and more efficient energy use. And it will not be alone. Strong trade enforcement mechanisms will mean that the American business community will not be disadvantaged by importers who skirt the rules. This long legislation is a vote for innovation and environmental stewardship.

I almost would be remiss if I didn't mention this as well. For the previous 8 years, the administration rejected the idea of global warming. The other side was given fancy talking points to grudgingly acknowledge that perhaps it might be happening but to spin the argument that it presented a peril to our times. You would be hard pressed to find scientists anywhere across this globe who have not at least forged a consensus on identifying and defining the problem. As is always the case in public life, it is difficult once definition has settled in to offer a solution. This legislation today offers a solution.

Mr. CAMP. Mr. Speaker, I yield 1 minute to a true American hero, a distinguished member of the Ways and Means Committee, the gentleman from Texas (Mr. SAM JOHNSON).

Mr. SAM JOHNSON of Texas. Mr. Speaker, as a clean-energy advocate, I believe we should be good stewards of the Earth and its resources.

We're in the midst of a long recession. Yet the Democrats want to impose a massive new energy tax on American families and businesses, costing every American family heavily. Americans are sick and tired of Democrats spending too much, taxing too much, and borrowing too much.

With the price at the pump rising 65 percent this year, the Democrats would create a 70-cent-per-gallon tax hike. With unemployment close to 10 percent, the Democrats would kill 2½ million jobs per year. My district alone would lose 3,000 jobs per year.

Democrat Congressman John DINGELL said it best, Nobody in this country realizes that cap-and-trade is a tax, and it's a great big one.

This is America. Let's don't sell it down the river.

Mr. RANGEL. Mr. Speaker, it's my honor to yield 1 minute to Mr. BLUMENAUER, an outstanding advocate of prevention of global warming.

Mr. BLUMENAUER. I appreciate the gentleman's courtesy.

For the last $2\frac{1}{2}$ years, I have had the privilege of working with the Speaker's Select Committee on Global Warming, driving home the reality of climate change. Today we have a major opportunity to rebuild and renew America while protecting the planet.

I want to thank the Ways and Means Committee and the Commerce Committee for working with me to harness billions of dollars over the life of this bill to develop transportation that reduces carbon footprint for transit, bike, and pedestrian, development patterns, things that will make a difference for a country that emits more carbon with its transportation than China, India, and Europe combined. We have an opportunity to protect the planet, but unless you're prepared to lead, China and India will continue to pollute more and more.

This is the first step in this leadership, and I urge the courage to vote "yes" on this legislation today.

Mr. CAMP. Mr. Speaker, I yield 2 minutes to a distinguished member of the Ways and Means Committee, the gentleman from Georgia (Mr. LINDER).

Mr. LINDER. I thank the chairman for yielding.

Mr. Speaker, I will submit a statement for the Record, but I'm not going to read that statement. I want to respond to the gentleman from Connecticut, who said we need some honesty in this discussion, and the gentleman from Illinois this morning on the rule. The gentleman from Illinois said on the rule that there are zero peer-reviewed articles by scientists who disagree with the notion that humans are causing global warming.

That will come as a surprise to Professor Morner from the University of Stockholm, who has written 520 himself on sea levels. He's the world's fore-

most expert on sea levels. Or Richard Lindzen from MIT, the Alfred P. Sloan professor of meteorology at MIT, who has written many peer-reviewed articles. He is a denier. Professor Willie Soon from MIT, one of the world's foremost scientists on precipitation. John Christy and Roy Spencer from Huntsville, Alabama. Fred Singer, who was responsible for leading the charge to get all of our weather satellites in the air from Northern Virginia.

And the five authors of the first IPCC report who wrote in their scientific reports that there is no evidence that humans are causing any of this. And those five sentences were removed by a bureaucrat who replaced them with one sentence that said, It's clear that humans are the cause. In a court action under oath, that bureaucrat was asked why he removed those sentences and replaced them, and he said because of intense pressure from the top of the United States Government.

There are 32,000 scientists, 9,000 Ph.D.s and 23,000 masters in science who signed a petition against this silliness that we're discussing, and they want to join the deniers Galileo and Einstein. Einstein questioned Newton's 200 years of settled science, and he was sent a letter by 100 of the most important scientists in the world who challenged him on his questioning of that settled science, and he said, You would think one of them might have produced a fact.

That's all we ask from you is a fact. Not a computer model but a fact.

"Energy Stamps" in Democrat Bill Is the Biggest Welfare Program Ever—16 Times Bigger than the Current Welfare Program

Mr. Chairman, some Members deny this bill is a massive tax hike. To them, I can only say you're not paying attention. Everything takes energy. If you raise the price of energy, as this bill does, you raise the price of everything. CBO admits it, again and again.

The authors know very well their bill is a massive tax hike. That's why, as this chart shows, they create the largest welfare program in U.S. history, to relieve some. This legislation would pay checks—call them energy stamps—to 16 times as many people as are on welfare now.

Here's what it says on page 1010:

"The Secretary shall . . . administer . . . the 'Energy Refund Program' . . under which eligible low-income households are provided cash payments to reimburse the households for the estimated loss in their purchasing power resulting from (this bill) . . . each eligible low-income household . . shall be entitled to receive monthly cash payments . . if . . . the gross income of the household does not exceed . . . 150 percent of the poverty line . . ."

65 million Americans fall below 150 percent of poverty. Every one would receive a monthly energy stamp check, on top of any welfare or other benefits they collect now.

Amazingly, this number is down from prior versions because Democrats, predictably, removed any vestige of middle class tax relief.

So the other 235 million Americans would get nothing but a new National Energy Tax.

Every family of four earning over \$33,000 "loses"—getting no energy stamps but all the energy tax hikes.

So much for the President's pledge to cut taxes for 95 percent of Americans. And so much for the Speaker's pledge this won't raise costs for American families.

In his 1935 State of the Union Address, Franklin Roosevelt said "continued dependence upon relief induces a spiritual and moral disintegration fundamentally destructive to the national fiber. To dole out relief in this way is to administer a narcotic, a subtle destroyer of the human spirit."

On that President Roosevelt was right, as surely as this legislation is wrong.

Vote "no."

Mr. RANGEL. Mr. Speaker, I yield for the purpose of making a unanimous consent request to the gentleman from Virginia (Mr. CONNOLLY).

(Mr. CONNOLLY of Virginia asked and was given permission to revise and extend his remarks.)

Mr. CONNOLLY of Virginia. Mr. Speaker, it is an honor to speak in support of this historic legislation. Congress has never faced a challenge of such magnitude, complexity, or urgency. Global climate change is an existential threat that undermines our national security and imperils our coastal cities, agricultural heartland, and economic vitality.

After enduring eight years of intransigence, denial, and fealty to special interests, we are poised to transform the marketplace and spur a new generation of technological and industrial innovation.

By creating incentives for clean energy we will jump-start job creation and investment in production of advanced batteries, wind turbines, solar panels, geothermal systems, carbon capture and storage, and cellulosic biofuels. The dozens of companies that support this legislation have told us that they are poised to make these investments.

Although we have seen an alarming rise in greenhouse gas pollution, we also know that it is not too late to act. From New Orleans to Glacier National Park to the Everglades, by acting now we will protect America's iconic places and our national identity.

I thank Chairman WAXMAN, Chairman MARKEY, and their committee for leading the effort to write this legislation. Like many of my colleagues, I ran for Congress in order to restore economic growth, reform health care, and address global warming. We have made progress on the first pledge and are embarking on the second. With my vote for this bill I redeem my pledge to begin to address global warming and ask my colleagues to join me.

I also wish to thank Chairman WAXMAN. Chairman MARKEY, and the staff of the Energy and Commerce Committee for their collaboration in drafting this bill. When this discussion draft was released in March, the American Clean Energy and Security Act did not provide dedicated funding for local governments through the State Energy and Environmental Development (SEED) or Retrofit for Energy and Environmental Performance (REEP) programs. I wrote to Chairman Waxman and requested that a portion of funding through these programs be dedicated to local governments, to support local efforts to improve buildings' efficiency and reduce greenhouse gas pollution. The Committee responded to my request by dedicating SEED funding to local governments and by ensuring that REEP funding would support local weatherization programs. These important changes ensure that Northern Virginia localities can continue to lead efforts to reduce residents' electric bills and greenhouse gas pollution. These changes are very significant for Virginia. According to the Congressional Research Service, Virginia will receive between \$108 and \$216 million in SEED funding in 2012. As a result of the changes I requested, between \$13.5 and \$27 million should flow directly to local government programs to reduce pollution.

In my letter to Chairman WAXMAN, I also requested reforms to the transmission line siting process in order to protect environmental and cultural resources. Northern Virginians know that we must act to correct deficiencies to the 2005 Energy Policy Act, which created a National Interest Electric Transmission Corridor process that granted unprecedented authority for federal agencies to site transmission lines without regard for the impact on environmental and cultural resources or property values. Fortunately, the manager's amendment that is incorporated in the American Clean Energy and Security Act takes the important first step of ensuring that state and federal environmental agencies and land managers have a seat at the table in the planning process. Although additional reform of the transmission siting process is still needed, this change will better enable us to protect important Northern Virginia resources such as Manassas National Battlefield Park. Prince William Forest Park. and Shenandoah National Park.

I also applaud Chairman WAXMAN for incorporating an amendment proposed by the Sustainable Energy and Environment Caucus, of which I am a member. This amendment ensures that the Federal government will derive 20% of its energy from renewable sources by 2020. This proposal, which Chairman WAXMAN incorporated into the manager's amendment, is particularly important for Northern Virginia because it will result in renewable energy deployment to power Federal facilities in the National Capital Region. This is important because we must move to clean energy generation if our region is to achieve ground level ozone reductions, which are essential for public health, as recommended by the Environ-

mental Protection Agency.
Finally, I thank Mr. WAXMAN for incorporating language that expresses the sense of Congress that the International Civil Aviation Association limit aviation-related emissions worldwide. Following Committee passage of H.R. 2454, the Washington Airports Task Force asked members of the Northern Virginia delegation to identify a role for the International Civil Aviation Association in limiting emissions, and I asked the Committee to see if they could address the Washington Airports Task Force's request. I believe that the language incorporated in Mr. Waxman's manager's amendment is a step in the right direction, and appreciate his willingness to address this issue at such a late point in the legislative process.

In summary, Chairman WAXMAN, Chairman MARKEY, and the staff on the Energy and Commerce Committee have been very responsive to my requests for changes to this bill that benefit Northern Virginia. I greatly appreciate their willingness to work with members like me to ensure that this legislation will benefit residents of Northern Virginia and

across the country. As important as it is to have sound overarching legislation, I believe it also is essential that the legislative process allow individuals and businesses from across the country to have a role in crafting any bill. Because of the outstanding work by Chairman WAXMAN, Chairman MARKEY, and their committee, this bill has evolved to reflect the needs of Northern Virginians and others from across the country.

Finally, I would like to offer special praise to my colleague from Virginia, Mr. BOUCHER, As a senior member of the Energy and Commerce Committee, Mr. BOUCHER played a central role in writing the American Clean Energy and Security Act. He is the only Virginia Congressman on that Committee, and I believe he did an outstanding job representing the interests of the Commonwealth. Specifically, he ensured that coal-reliant states like ours can transition to cleaner energy sources without creating price spikes and without negatively impacting regions where coal extraction is important economically. This was a difficult balance to strike, and required the skill and experience of a legislator of Mr. BOUCHER's caliber. Years from now, when coal extraction and electricity generation is substantially cleaner than today, and when Virginia finally has significant renewable electricity generation, we may look back and thank Mr. BOUCHER for his role in crafting this legislation that made such a transition possible.

Congress has never dealt with such a complex bill of such fundamental importance to our economy, environment, and quality of life. Led by Mr. WAXMAN and Mr. MARKEY, the American Clean Energy and Security Act reflects a carefully crafted consensus that has the support of large utilities like Dominion and environmental organizations alike. While forging this consensus the Committee found time to address requests from members representing diverse regions of the nation with competing needs. I thank Chairman WAXMAN, Chairman MARKEY, and I am proud to cast my vote for the American Clean Energy and Security Act.

Mr. RANGEL. Mr. Speaker, at this time it's my pleasure to yield 1 minute to the gentlewoman from Nevada (Ms. Berkley), an outstanding member of the Committee on Ways and Means.

Ms. BERKLEY. I thank the chairman for yielding.

Mr. Speaker, I rise today in support of this bill. It addresses climate change, promotes the development of clean-energy sources, and brings us closer to our goal of securing America's energy independence. This bill also takes extra steps to protect consumers while creating new green jobs.

Nevada is in the forefront of renewable energy use. In 1997 Nevada enacted a renewable portfolio standard requiring that 20 percent of our electricity comes from renewable sources by 2015. Nevada's solar potential, coupled with our State's geothermal and wind resources, will bring jobs to Nevada and make us a leader in the use of production of clean energy.

In contrast, the alternative proposed by the House Republicans continues the same old failed policies, including the Yucca Mountain project. It doubles the amount of nuclear waste that can be shipped to Nevada and jams twice as much of this radioactive garbage down our throats. The Republican plan to more than double the size of the Yucca Mountain dump would only double the danger to families in Nevada and across our Nation at a cost of hundreds of billions of dollars.

I urge all of my colleagues to support this bill.

Mr. CAMP. Mr. Speaker, I yield 1 minute to a distinguished member of the Ways and Means Committee and the ranking member on the House Budget Committee, the gentleman from Wisconsin (Mr. RYAN).

Mr. RYAN of Wisconsin. I thank the

gentleman for yielding.

Mr. Speaker, this bill is not about science, it's not about costs and benefits; it's about ideology. Because if you look at the costs and benefits, the goal of this bill is to reduce global warming by 2/10 of a degree over a hundred years, hit our economy with this massive tax increase on homeowners, on people buying gasoline, heating their homes, hit manufacturing at a time when our competitors will not do this. This bill will result in jobs leaving the Midwest and jobs leaving America and going to other countries. And for every 1 ton of greenhouse gases we reduce, what will China do? Thev'll increase greenhouse gases by 3 tons. And that means more dirty air. That means more greenhouse gases. What will the U.S. have achieved? They will have pushed production off our shores. Jobs will be lost. Prices will go up. And other countries will take those jobs and put more greenhouse gases in the atmosphere.

This unilateral big government, Big Brother bill is not good for the planet. It's not good for our economy. And it sure as heck is not good for the Midwest. And I encourage my colleagues not to vote ideology, vote your districts and your constituents.

Mr. RANGEL. Mr. Speaker, I yield 1 minute to an outstanding Democratic leader, the gentleman from Maryland

(Mr. Van Hollen).

Mr. VAN HOLLEN. Mr. Speaker, this is an historic day for this House of Representatives. After years of delay and inaction, we're finally poised to embrace America's clean-energy future and adopt an energy strategy for the 21st century.

This act delivers on the change that President Obama has called for in our energy policy. It will strengthen our national security by slashing our dependence on foreign oil by as much as 2 million barrels a day by 2030, which is as much as we export from the Persian Gulf today. We will use those hundreds of billions of dollars instead right here at home on homegrown, clean energy. And by doing so, we're going to create millions of jobs, high-skilled, well-paying jobs that will focus on renewable energy and energy efficiency. And we will do all that without adding a single penny to our national debt.

Mr. Speaker, I especially want to thank Mr. RANGEL, Mr. WAXMAN, Mr.

MARKEY, Mr. DINGELL, Mr. INSLEE, Mr. GORDON, and their staff for the collaborative effort that went into the final provisions establishing a Clean Energy Deployment Administration. As a result of this effort, America is going to have an independent—

The SPEAKER pro tempore (Mr. PASTOR of Arizona). The time of the gentleman has avaised

tleman has expired.

Mr. VAN HOLLEN. Well capitalized bank charged with the exclusive mission of accelerating the deployment of clean energy.

The SPEAKER pro tempore. The time of the gentleman has expired.

□ 1515

Mr. CAMP. Mr. Speaker, at this time, I yield 1 minute to a distinguished member of the Ways and Means Committee, the gentlewoman from Florida (Ms. GINNY BROWN-WAITE).

Ms. GINNY BROWN-WAITE of Florida. You know, this bill started out as the cap-and-tax bill, then it became the clean energy bill because my colleagues on the other side of the aisle realized it wasn't selling anymore at home. It should really be called the Let's Send More Jobs to China Act.

This bill is going to cost people in the State of Florida an additional \$500 on their utility bills, but let's look at the jobs that are going to be lost. In my district alone, we will lose 2,100 manufacturing jobs, 3,200 construction jobs, and 1,900 retail and wholesale jobs.

Personal income loss for Florida's Fifth District in 2012 will be over \$508 million. America cannot afford this at a time when our economy is so fragile. Gasoline prices under this will rise substantially. Electricity prices will rise up to 90 percent.

This is a bad bill. This is a bill that is going to cost Americans not only more in their wallets but certainly jobs going elsewhere.

Mr. RANGEL. Mr. Speaker, I would like to recognize the gentleman from Chicago, Illinois (Mr. DAVIS) for 1 minute.

Mr. DAVIS of Illinois. Mr. Speaker, I rise in strong support of H.R. 2454.

I want to commend Chairman WAX-MAN, Chairman RANGEL, Mr. BARTON, Chairman Peterson, Chairman Mar-KEY, Mr. DINGELL, and all of those who have worked so hard to reach compromises which help to make this legislation possible. Especially do I want to commend Representative BOBBY RUSH for his hard work to protect low-inconsumers, Representative BUTTERFIELD for making sure that Historically Black Colleges and Universities and predominantly black institutions had an opportunity to be involved in the research and job creation.

And I also want to thank Representatives JAN SCHAKOWSKY and DONNA CHRISTENSEN for their hard work on environmental issues to help reduce health disparities. It's a good bill, Mr. Speaker, and I urge all of my colleagues to vote in favor of it.

Mr. CAMP. At this time, I yield 1 minute, Mr. Speaker, to a distinguished gentleman from the Ways and Means Committee, Mr. DAVIS.

Mr. DAVIS of Kentucky. Mr. Speaker, this legislation will increase utility bills, raise the price of a gallon of gas, push fuel prices and food prices to new heights, and increase the cost of nearly every consumer product. It is a national energy tax. Let's make that clear. This will punish middle class families, farmers, the elderly, and small businesses both in Kentucky and especially across the Nation.

America needs a comprehensive energy plan, not a national energy tax. Local, State and Federal officials have stressed the need for policy to create jobs. This cap-and-trade proposal will fail to do that when America needs them most. We will lose jobs. Manufacturers will simply move their plants to other countries with cheaper energy and lower taxes, hurting American workers and the environment globally.

In the past 4½ years, I have watched House Democrats defeat every meaningful proposal for energy independence and job creation that has been proposed in this Chamber, and we have got to bring an end to that.

This bill is nothing more than the economic colonization of the heartland by the coastal States like New York and California.

The one thing that I will tell you is it is not about energy. It is about confiscation of wealth. Vote "no" to protect our children's future.

Mr. RANGEL. At this time, I would like to inquire—I only have one speaker, that would be me, to conclude, so I would like to see whether the other side has more than one speaker.

Mr. CAMP. We have five speakers remaining.

Mr. \Breve{RANGEL} . I reserve the balance of my time.

Mr. CAMP. At this time, Mr. Speaker, I yield 1 minute to the distinguished member of the Ways and Means Committee, the gentleman from Texas (Mr. BRADY).

Mr. BRADY of Texas. Mr. Speaker, I have two young children, so the environment is very important to me, but I question the benefits of this bill and strongly oppose its devastating cost.

This bill won't impact the natural cycle of the Earth's temperature. It will cost Texas families dearly in bigger utility bills, higher energy costs, and losing nearly 200,000 jobs, many of them in southeast Texas in our energy refining, paper, steel, and ag industries. And with China and India not likely to go along, this will have no environmental benefits at all.

The protectionist trade measures added in secret at the 11th hour are so rigid, they undermine our ability to reach an international agreement on carbon emissions, which is the best way to protect American jobs here. And they are written so poorly, it will be difficult to defend the measure against trade challenges by our competitors. And I should point out, that

WTO report referenced earlier today doesn't even deal with the border measures that are under consideration in this bill.

Instead of rushing this 1,200-page bill through Congress with no time to read it, a better solution is for both parties to get serious about increasing cleaner-burning fuel, like nuclear and natural gas, accelerating research.

That makes more sense, creates jobs and produces real environmental results without the devastating cost to families and businesses from cap and trade.

Mr. RANGEL. The gentleman from Ohio (Mr. RYAN), not a member of the committee but an outstanding Member of this body, I would like to yield 1 minute to him.

Mr. RYAN of Ohio. I would like to thank the gentleman and thank the chairman for this bill. You know, we hear a lot from the other side about, if we pass this bill, all these jobs are going to go to China; if we pass this bill, gas is going to go up higher.

The jobs already went to China. That's what this bill is all about. Come to Youngstown, Ohio. See how many jobs have already gone to China.

This bill is about revitalizing manufacturing. And your energy policy has already been implemented, and it gave us \$4 a gallon gas here. And we have a \$700 billion transfer in wealth from this country to states that want to fly planes into our building.

And this bill is about creating programs like the green bank that will loan \$750 billion to companies that want to create alternative energy resources. This bill has in it \$30 billion for auto suppliers, medium and small auto suppliers, to refurbish and retool so that they can sell their products into these windmill companies.

Everyone is talking about losing jobs. Come to my district. Parker-Hannifin Corporation in Cleveland, they make the hydraulics that go into windmills. Thomas Steel, they make the specialty steel that goes into solar panels. When these businesses explode—Roth Brothers makes an electrical system that goes into a wind cube that will sit on top of the buildings. In Youngstown, Ohio, in Akron, Ohio, there will be jobs because this bill passes. We need to nudge this industry and unleash the creative power.

Mr. CAMP. Madam Speaker, I yield 1 minute to a distinguished member of the Ways and Means Committee, the gentleman from Louisiana.

Mr. BOUSTANY. I thank our ranking member.

This bill is a unilateral blueprint for economic disarmament of the United States, let's be clear. Responsible energy production in the Gulf of Mexico is the backbone of American energy security and it creates good, high-paying jobs. This bill, their bill, dramatically increases taxes and will kill American jobs.

Now, I have repeatedly questioned Secretary Geithner about the job loss that's going to be caused by new taxes on American energy producers. I have asked the administration to prove its claim of saving jobs, and they can't do it

And no one can define what a green job is and how these displaced workers will transition to one. Secretary Geithner says, "The administration believes that oil and gas preferences distort markets by encouraging more investment in the oil and gas industry that would occur under a neutral system."

Again, he goes on to say, "To the extent the credit encourages overproduction of oil, it is detrimental to long-term energy security." Who in this country believes we have enough American-made energy?

If we want to move towards cleaner energy and renewable energy, as this bill purports to do, it's clear we need a transition strategy that involves natural gas. It must be part of that. This administration must stop its attack on American business and American independent oil and gas producers if we are going to make this a reality.

The American public deserves a comprehensive energy plan that creates jobs, spurs innovation, and unleashes American genius. That's how we will solve this problem.

Mr. CAMP. I yield 1 minute to a distinguished member of the Ways and Means Committee, the gentleman from Nevada (Mr. HELLER).

Mr. HELLER. Thank you. I appreciate the Member for yielding.

Here is the bill again. I think we have seen this a couple of times. Here is the bill. It is 1,201 pages. What does this cost the American taxpayer? It is \$700 million a page for this bill. What does this bill do? Every time you flip on your light switch, you are taxed. Every time you drive your kids to school, you are taxed. Every time you cook your family dinner, you are taxed. Air travel, food prices, electricity costs, gas prices, transportation cost, all will skyrocket under this bill.

This bill will cost my district a half billion dollars in economic activity. It will cost my district 5,500 jobs. It will cost my district nearly 650 million in personal income loss in just the first year.

Nevada, as a whole, will lose 14,000 jobs. Mining, housing, farming, ranching, tourism industries will be devastated at a time when Nevadans are hurting. The majority can't afford the time for hearings or debate, but Americans can't afford this bill.

Mr. CAMP. Madam Speaker, at this time, I yield 1 minute to a distinguished member of the Ways and Means Committee, the gentleman from Illinois (Mr. ROSKAM).

Ms. ROSKAM. I thank the gentleman for yielding.

You know what's happening in suburban Chicago is there are businesses who are really in a touch-and-go position right now. They are treading water. They are barely keeping their heads above the surface of the water.

And what they expect from this Congress is for us to come along and literally throw them a lifeline. But you know what this bill is? This bill is a bowling ball. It comes along, it says, Hey, there you go. Hit that with a thud right on your chest. Deal with it, because we are debating ideology today.

My district says let's do the right thing, let's do the transformational thing, but let's not give our markets over to the Chinese, where they have clearly said they are not in this game. Let's not give our markets over to the Indians where they say they are not in this game. Let's not put an additional \$3,100 tax on a family of four. Let's offer a lifeline to the American public. Let's pull the plug on this bill.

Mr. CAMP. At this time, Madam Speaker, I have one speaker remaining. The SPEAKER pro tempore (Mrs.

TAUSCHER). The gentleman has 1 minute remaining.

Mr. CAMP. At this time, I yield 1 minute to the distinguished gentleman from the Ways and Means Committee, the gentleman from California (Mr. NUNES).

Mr. NUNES. Madam Speaker, don't be deceived by the comments of the Democratic Party. This bill is a tax increase. This bill is the largest tax increase in American history.

I ask my Democratic friends, Is this really what you have come to? Do you want to throw away the economic prosperity for nothing, because that's what this bill does. And for what, to satisfy the twisted desires of radical environmentalists.

I would ask my colleagues one more question. How will you force China, India, and anyone else to accept this economic suicide pact? The dirty little secret is that you can't.

While you congratulate each other today, I remind my colleagues the State of California is out of water. We have communities with 40 percent unemployment. And in the meantime, Democrats bring up fairy-tale legislation to the floor, phantom green job legislation.

However, we agree on one thing. We should try to reduce our carbon emissions. Republicans have a plan, an allthe-above plan where we drill for American resources, we drill for oil in America. We take the revenue and we put it into solar, wind, nuclear technologies. That's a real plan, Madam Speaker. This bill is a scam.

Mr. RANGEL. I would like to yield to Mr. FATTAH of Pennsylvania for the purpose of a unanimous consent request.

(Mr. FATTAH asked and was given permission to revise and extend his remarks.)

Mr. FATTAH. I thank the gentleman for yielding.

Madam Speaker, I rise for a unanimous consent in support of this very important bill on behalf of my four children and for millions of young Americans who we hope never to see another die on a foreign battlefield trying to get oil from some other place in

the world. We need independence in our energy.

Mr. RANGEL. Madam Speaker, I would just like to conclude, this is a very historic moment in our Nation's life where we have an opportunity to provide leadership to the whole world to prevent the continuation of the global warming. I wish it had been more positive from the other side that they would have had some contribution to make in order to make certain that our Nation maintains the leadership that it has.

I would like to yield the balance of my time to Chairman WAXMAN of the Energy and Commerce Committee, with your kind permission.

The SPEAKER pro tempore. The gentleman from California is recognized for $2\frac{1}{2}$ minutes.

□ 1530

Mr. WAXMAN. At this point I'd like to yield 1 minute for the purpose of a colloquy to the gentleman from Florida (Mr. Grayson).

Mr. GRAYSON. I rise to enter into a colloquy with the chairman of the Energy and Commerce Committee, Mr. WAXMAN.

My attention today is to draw attention to the need for further research and work concerning the effect of ongoing changes in climate and on the frequency and intensity and effects of hurricanes.

As you know, damages from hurricanes—in terms of human lives, infrastructure, and property—have grown in scope and cost; and it is critical that we continue to make progress in furthering our understanding of the science behind hurricanes. Doing so will ultimately help vulnerable communities in my district, in Florida, and elsewhere in the United States prepare for and reduce the impacts from hurricanes.

I ask that a portion of the allowance value in H.R. 2454 be directed towards research on hurricanes at a new \$50 million National Hurricane Research Center in my district in Orlando. The National Hurricane Research Center in Orlando will be a worldwide center of expertise in the 21st-century science of meteorology.

In a world already affected by global warming, it will help to develop both short-range and long-range hurricane forecasting, conduct practical research on mitigation of hurricane damage, disseminate to the public realtime information on hurricanes—

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. WAXMAN. I yield the gentleman

Mr. GRAYSON. Advise policymakers and the public, and expand knowledge on what can and should be done to impact the frequency, course, and human and property consequences of hurricanes.

Mr. WAXMAN. I share the gentleman's concern about the need for research on hurricane intensity and frequency and effects. The harm from hurricanes is only going to increase with global warming, and we need to better understand the connections and impacts.

H.R. 2454 includes domestic adaptation provisions giving States substantial resources to study and adapt to climate change. Based on our estimates, the bill will provide up to \$1 billion per year from 2012, when the program starts, through 2021. From 2022 through 2026, the amount will be over \$2 billion annually.

Research on hurricanes is explicitly listed as an authorized use of these revenues. The project the gentleman mentions is among the type of activity that would be eligible to received funding under these provisions.

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. WAXMAN. I yield the gentleman an additional 30 seconds.

Mr. GRAYSON. Mr. Chairman, I understand that H.R. 2454 includes provisions directing allowance value towards State adaptation. I hope that we will be able to work together as this bill moves forward to make certain that hurricane research receives full funding and that we are able to ensure that the work of the National Hurricane Research Center will be supported.

Mr. WAXMAN. The gentleman has

Mr. WAXMAN. The gentleman has discussed this project with me, and I think it's a very worthwhile project. I look forward to working on it and making it a priority as the legislative process moves on.

Mr. GRAYSON. I thank the chairman for his support of our efforts to ensure that our hurricane research efforts are adequately supported.

Mr. BARTON of Texas. Can I inquire how much time we have on the last part of the debate?

The SPEAKER pro tempore. The gentleman from Texas has 30¾ minutes remaining. The gentleman from California has 28½ minutes remaining.

Mr. BARTON of Texas. Well, I want to compliment Chairman WAXMAN on apparently getting another vote—of Congressman GRAYSON—at the cost of 4,100 jobs in Congressman GRAYSON's district in the year 2012.

With that, I want to yield 1 minute to a distinguished member of the committee, the gentleman from Kentucky (Mr. WHITFIELD.)

Mr. WHITFIELD. Mr. Speaker, I rise to speak in opposition to the bill. This legislation is not so much about stopping the import of foreign oil as it is designed to change the way we produce electricity in America.

Today, 52 percent of all electricity produced is produced with coal, and this bill will require the use of permits to burn coal. In my State of Kentucky, the utilities believe—and they have looked at this closely—that in order to comply with this legislation, they will have to spend an additional \$500 million.

As we look around the country, we see that only about eight States will

really benefit in the sense that their electricity rates will not go up. The problem with this is that as you increase the cost to produce electricity, that makes the United States less competitive in the global marketplace, because when companies decide where they're going to locate and build new plants, they look at cost of production, and one big cost is electricity.

And so those of us who oppose it do so genuinely because we believe that at a time when we are in an economic recession, we should not be jeopardizing more jobs.

Mr. WAXMAN. I'm pleased at this time to yield 1 minute to the gentlewoman from Illinois (Mrs. HALVORSON).

Mrs. HALVORSON. Mr. Speaker, I thank the gentleman for yielding. Chairman Waxman, I'm pleased, as I know you are, with the work of the Energy and Commerce and Agriculture Committee and what we have done to address the concerns of agriculture producers and forest landowners in this historic bill.

I would like to clarify provisions in this bill regarding section 795, Exchange for Early Action Offset Credits, and section 740, Requirement of Early Offset Supply. These provisions attempt to fairly compensate farmers and others who have been enrolled in voluntary offset programs since 2001.

I have noted the legislative goal of providing equity and fairness to those early actors and believe that further clarity would improve the understanding of those who are eligible under the requirements in section 740. Therefore, to remove the possibility of uncertainty of economic harm to the holders of potential credits under section 740 and those that would be compensated under section 795, it is my understanding that registries like the Chicago Climate Exchange and their partners should qualify in all respects to the provisions—

The SPEAKER pro tempore. The time of the gentlewoman has expired.

Mr. WAXMAN. I yield the gentlewoman an additional 30 seconds.

Mrs. HALVORSON. Provisions in section 740(a)(2). I believe this is in the spirit and intention of the legislation. Is that the chairman's understanding?

Mr. WAXMAN. The gentlewoman is correct that the provisions of section 795 and 740 are intended to fairly compensate farmers and their partners who have enrolled in voluntary programs and have taken early action to reduce carbon pollution.

All existing voluntary offset programs with strong standards for environmental integrity would meet the requirements of section 740. We expect that offset credits registered with the Chicago Climate Exchange, along with the credits from other recognized voluntary programs, will provide an important source of offset credits in the early years of the program.

Mr. BARTON of Texas. I planted some trees on my grandfather's farm 30 years ago. I hope that that qualifies under that section of the bill.

I want to yield 2 minutes to the distinguished member of the committee, the gentleman from Arizona (Mr. Shadegg).

Mr. SHADEGG. I thank the gentleman for yielding. Passing this bill at this time will be a tragic error. It simply cannot be justified on a cost-benefit analysis. Every day we make decisions in our lives by balancing the costs of our decisions with the benefits of those decisions; and on that basis, this bill can't be justified.

As a Republican who crossed my leadership on many major-profile bills, I urge my colleagues on the other side who are being pressured and all my colleagues who have doubts to carefully think through this vote. Crossing your leadership is not fun or easy, but sometimes its the right thing to do. I know. I've done it.

First, while we have been told that the science on this issue is settled, it clearly is not and is becoming less and less settled every day. Carbon dioxide emissions in the United States have gone up every year since 2001, but global temperatures have remained flat.

Carbon dioxide emissions are going up; global temperatures have been flat since 2001. They have stopped going up almost a decade ago.

More and more scientists are coming forward every day casting doubt on the alleged consensus that greenhouse gases are causing global warming.

Joanne Simpson, the first woman in America to receive a meteorological Ph.D., expressed relief upon her retirement last year, saying she could now speak freely about her nonbelief. Dr. Kiminori Itoh, a Japanese environmental physical chemist, recently said—and he contributed to the U.N. climate report—he called man-made warming the worst scientific scandal in history.

Second, even if you assume that man-made greenhouse gases and carbon dioxide are causing global warming, this bill can't be justified because it doubles the cost of reducing carbon dioxide emissions.

Witnesses testified before our committee that they can control CO_2 , but that the cost of doing so under this bill would be twice as much. And why is that? It's because they have to pay first to buy carbon credits and then they have to spend the capital to improve their plants.

Mr. BARTON of Texas. I yield the gentleman 15 seconds.

MR. SHADEGG. Those costs get passed on to American consumers. Why should we double those costs? My colleagues on the other side want the revenue of the carbon credits that have to be purchased. That money ought to go into the capital cost of reducing carbon emissions, but that money won't do one bit for that cause.

I urge my colleagues to vote against this dangerous bill.

Mr. WAXMAN. Mr. Speaker, I'm pleased at this time to yield 1 minute for the purpose of a colloquy to the dis-

tinguished chairman of the Agriculture Committee, the gentleman from Minnesota (Mr. Peterson).

Mr. PETERSON. I want to thank Chairman Waxman for his leadership and cooperation on this bill and would ask him to engage in a colloquy regarding subtitle E of title III, which contains a host of provisions amending the Commodity Exchange Act.

Mr. WAXMAN. I'd be pleased to do

Mr. PETERSON. These provisions are among those that triggered the referral of H.R. 2454 to the Agriculture Committee, which has jurisdiction over the CEA. Some of these provisions would deal with over-the-counter energy derivatives and credit default swaps, mirror provisions in legislation, H.R. 977, passed by our committee in February. Other provisions are similar, and still others are wholly different. H.R. 977 is awaiting action in the Financial Services Committee.

As the gentleman knows the Financial Services and Agriculture Committees will be working on financial regulation reform, part of which will include derivatives regulation reform. As such, Chairman Frank and I initially resisted the inclusion of these CEA amendments in H.R. 2454. However, we understand that some Members feel strongly about sending a signal to address potential excessive speculation in derivative markets and rein in some of the current trading practices on Wall Street.

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. WAXMAN. I yield the gentleman an additional 30 seconds.

Mr. PETERSON. To that end, we agreed not to object to the inclusion of the CEA amendment subject to the understanding that the ultimate resolution of these provisions would take place in the context of financial regulation reform legislation. I want to confirm this understanding we have among the chairmen.

Mr. WAXMAN. The gentleman has correctly described our understanding.

Mr. PETERSON. I want to thank the distinguished chairman for his confirmation, and I look forward to working with him on this bill as it moves through the legislative process.

Mr. BARTON of Texas. I yield myself 15 seconds to explain what they just said. What they just said was, Mr. Speaker, is that you have got something in the bill that we don't agree with, but we're going to let you put it in the bill with the understanding we will take it out later on in Agriculture and Financial Services. I commend the Agriculture chairman for his strong resistance to that part of the bill.

I want to yield 2 minutes to a distinguished member of the committee, the ranking member of the Oversight and Investigation Subcommittee, the gentleman from Oregon (Mr. WALDEN).

Mr. WALDEN. I want to talk about a couple of things here involving this bill: process, cost, and language.

This is the 309 pages that were printed at 1:34 in the morning and submitted to the Rules Committee sometime around 2:49 this morning. Nobody—it's impossible—I can't imagine anybody's read this.

I've just discovered they change the hydro language so that—it used to say before 1992 it counted, now they have gone back 4 years. Somewhere in the middle of the night we have added 4 years of hydro as renewable. It's page after page after page of technical changes that have major, major impact.

There were nine committees this bill was referred to, and yet only one of them was allowed to have a markup on the bill, the Energy and Commerce Committee. The other eight waived. So a lot of this got put together in the dark of night, backroom deals, whatever you want to say, private conversations; but no committees held a hearing on this new bill, 309 pages, amending the 1,201 that are sitting there on the desk.

Costs. Look at fuel costs: \$811 more for Oregonians in 2012. If you're a PacifiCorp customer in Oregon, you can expect in 2012 to pay 17.7 percent higher electricity costs. They have run the numbers according to the bill.

You want to talk about a massive new welfare program for energy? It's in here too. In fact, this energy tax refund, in effect, this proposed energy stamp bill, 16 times the current U.S. welfare program, the TANF program. Sixteen times. It's a whole new welfare program for energy.

□ 1545

If energy costs aren't going up on the rest of us, why do they have to have this? Because it does drive up energy costs. That's going to hurt small businesspeople. It's going to hurt families. It's going to cost jobs. And we don't know for sure what else it does because I can't imagine anybody on this floor has read every word of this bill that was filed at 2:49 a.m. in the Rules Committee and been able to juxtapose what's here against the 1,201 pages.

Turge a "no" vote on this bill.

Mr. WAXMAN. Madam Speaker, I am pleased at this time to yield 1 minute to the very distinguished Representative from the State of Iowa (Mr. Bos-WELL).

(Mr. BOSWELL asked and was given permission to revise and extend his remarks.)

Mr. BOSWELL. I will say, with some reservation, that I support H.R. 2454, the American Clean Energy and Security Act. I am pleased with the deal between Chairman Peterson and Chairman Waxman to protect America's farmers and ensure many of agriculture's concerns were resolved. They both should be commended for their hard work. This bill makes tremendous progress on jobs, energy, national security and the environment. However, one troubling issue remains. A formula

partially based on retail sales means consumers in coal-reliant States, like Iowa and the Midwest, who need the most help will see greater rate increases than consumers in other parts of the country.

When Iowa's unemployment rate is at its highest in over 20 years, Iowans are struggling to repay student loans, pay rent, and put food on the table, why are we asking those of us in the heartland to shoulder more of the burden than others? This is neither fair nor equitable because it creates winners and losers.

I am not giving up. This bill is worth supporting; but it is my hope that when the House addresses this legislation again, the allocation formula will be more equitable for Iowans and Midwesterners alike.

I rise today with some reservation to support for H.R. 2454, the American Clean Energy and Security Act. I am proud that this legislation preempts potentially devastating regulation by the EPA, and responds to our constituents' demands to prevent that from happening. I am also proud that it would harness the most innovative workforce in the world to create a clean energy future, creating millions of jobs in the process. Energy independence is vital to our national security and economic future, and this legislation advances this goal while confronting the serious challenge of climate change.

However, when we started this process I had a list of many things which concerned me and needed to be addressed, such as fixing the indirect land use issues under the Renewable Fuel Standard-2, a robust agricultural offset provision which recognized early adaptors and was exclusively operated by USDA to implement and oversee the agriculture and forestry offset program, and the 50–50 allocation formula. I was pleased with the deal that was struck between Chairman PETERSON and Chairman WAXMAN to ensure many of those issues were resolved. They both should be commended for their hard work.

However, one key concern has yet to be addressed. As currently written, this legislation provides local distribution companies with allowances through a formula equally weighted between historic emissions and retail sales. Since the intent of the legislation is to reduce emissions, and the intent of providing allowances is to protect consumers from price increases, basing allowances on retail sales reduces the legislation's effectiveness. While certain providers will receive enough allowances to offset 100 percent of the cost of compliance, many companies throughout the Midwest will be forced to purchase numerous allowances, passing those prices on to their consumers. Consumers in coal-reliant states such as lowa-who need the most help-will see far greater rate increases than consumers in other parts of the country.

This doesn't have to happen. Congressman LOEBSACK and I offered an amendment to change the formula so that allowances will be distributed based solely on historic emissions. I am gravely disappointed that the Rules Committee did not make this amendment in order.

Under the amendment I had hoped to offer on the floor today, a utility would receive emission allowances based only on its emitting assets, like coal and natural gas-fired plants. It would not receive emission allowances for non-emitting nuclear and hydro assets, because they don't need them.

As such, there will not be enough allowances for higher-emitting electric utilities in the Midwest that need them to comply with H.R. 2454. This makes the bill very different from the Clean Air Act, which distributed sulfur dioxide emission allowances only to utilities that actually had sulfur dioxide emissions to reduce.

Under the current formula, utilities in my area will only receive 65 percent of compliance costs at most, and less than 50 percent in some areas—the shortfall will cost hundreds of millions of dollars. When you compare this to other regions of the country they will receive 100 percent of the needed allocations. Because of this inequity consumers in the Midwest will have to make up the difference; their rates will go up far more than consumers in other areas. This is neither fair nor equitable, because it creates winners and losers.

The retail sales component of the formula benefits companies like FPL and Exelon with heavy nuclear or hydro assets, because they will receive emission allowances for assets that don't emit.

They don't need these windfall allowances to comply with the bill's cap, so they can sell them in a carbon trading market for a profit.

If you don't believe that, just read a June 10th Bernstein Research analysis, in which Exelon's CEO, John Rowe, predicted that H.R. 2454 "will add \$700 to \$750 million to Exelon's annual revenues."

In these tough economic times when lowa's unemployment rate is at its highest in over 20 years, when lowan's are struggling to repay student loans, pay rent, and put food on the table, why are we asking those of us in the heartland to shoulder more of the burden than others?

I would also like to take a moment to talk about another amendment I tried to offer. My amendment would have provided a government backed loan guarantee for the construction of a renewable fuel pipeline.

Transporting fuels by rail and truck has higher energy input requirements and much higher greenhouse gas emissions. CO₂ emissions are reduced by 30 percent when comparing liquid fuel transported by pipelines vs. railcars and 87 percent when comparing pipelines to trucks.

Even though my amendment to bring equity to the formula was not ruled in order I am not giving up. I plan to work with my colleagues in the other body to bring this serious issue to light and to work towards a solution that works for lowa families. It is my hope that when the House addresses this legislation again the allocation formula will be more equitable for lowan's and Midwesterners alike.

Mr. BARTON of Texas. Madam Speaker, I yield 3 minutes to the ranking member of the Energy and Air Quality Subcommittee, Mr. UPTON of Michigan.

Mr. UPTON. Madam Speaker, there's an old saying, "Will the last one out please turn out the lights." Well, this bill turns out the lights for many Americans. And no matter what you say, this bill does not have the job protections that will prevent jobs from leaving our country and going to India or China. What do you tell that small

refinery that came to our committee a couple of weeks ago, a small refinery that's got 1,200 jobs—that it's going to cost \$150 million to ramp up the changes that they're going to have to do, and they're going to end up going out of business? That asphalt and that petroleum is going to be made someplace else—India.

What do you tell that small company that I visited last month in Niles, Michigan, a company that figures out that their energy costs are going to increase by perhaps as much as \$20,000 dollars a month? Well, they're thinking about it. They want to stay in business. They're thinking about telling the folks not to come to work anymore during the day so they can do the night shift, and they can maybe pay lower utility rates. There are more coal-fired plants in China than there are in the United States, India and Britain combined; and it's going to double by the year 2030. Emissions in China are going to grow by 86 percent.

What does this bill do about emissions in China or India? It does nothing. Environmental restrictions in this country, protections, are the reason why steel, per ton, has one-third the emissions in this country than in China. We want those jobs to stay in this country and not go to China. Michigan, my State, we're already at 15 percent unemployment and headed maybe towards 20. We were told earlier this week that we're going to have as many as 100,000 people, unemployed folks, lose their benefits that they're receiving today because those benefits are going to be exhausted. I didn't come up with the figure that gasoline costs were going to increase by 77 cents a gallon because of this legislation or that diesel prices were going up 88 cents a gallon. It wasn't me. It was the CBO who said that. I hope and pray that they're wrong because I want to protect our workers here to make sure that we can grow jobs, not lose them.

Consumers Energy came up with a study, a major utility in my part of the State, that shows that the estimate of the impact, including certain requirements in this bill, are going to grow as much as 38 percent by the year 2024. Some folks say that it's only going to cost a postage stamp. Well, I'm glad I bought a lot of promise stamps because these stamps are good for life. If they're not worth 44 cents, these may be worth thousands of dollars apiece based on what these costs are going to do to the average consumer.

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. UPTON. Let me just close. We as Members of Congress may have to declare these in our financial disclosure reports if we bought more than 10 of them.

Mr. WAXMAN. Madam Speaker, I yield 1 minute to the gentlelady from Texas (Ms. Jackson-Lee).

Ms. JACKSON-LEE of Texas. I thank the gentleman very much. As he

knows, we've been working on this because I come from an area that certainly has vested in the energy industry with a number of jobs that are tied, huge numbers of jobs.

To my constituents, we are working on your behalf today. This bill does not discount your jobs or your commitment to this Nation because 1.7 million jobs will be created, \$750 per household will occur in savings and \$29 billion in consumer savings will occur.

Also, I appreciate the chairman for working with me to ensure that we are investing in small business, guaranteeing that minority- and womenowned businesses will be involved in energy-innovative competition, language and amendments that I got into this legislation.

In addition, we are still working on the question of whether or not our older homes will be impacted negatively. The language in the bill says new construction only. I want to continue to work with the chairman to ensure that we will also have additional protection for older homes. Jobs—we are going to protect jobs.

The SPEAKER pro tempore. The time of the gentlewoman has expired.

Mr. WAXMAN. I yield the gentlelady 30 additional seconds.

Ms. JACKSON-LEE of Texas. There is language in the bill that I wish my friends would read because we insist that the Secretary of Labor shall monitor the potential growth of affected and displaced workers, if any, and continue to have the funding that I got in the bill to ensure that they're not left out in the cold. Mr. Chairman, in spite of the good work, there are those who are saying that our breakthroughs in alternative low-carbon technologies will not be fast enough, that we're going to lose petroleum jobs, we're going to lose jobs. I believe we can work through this and we will not lose jobs but gain jobs because of the new technology. However there is still time to work on this issue of the large and small refineries so that can be efficient and operational. Also manufacturing under this bill will only be efficient not extinguished.

I would like to yield to the chairman. Mr. WAXMAN. I say to you that they are wrong. This bill is going to produce breakthroughs. It pushes the development of new technology, and it's going to lead to more jobs.

Ms. JACKSON-LEE of Texas. Will you continue to work with me?

Mr. WAXMAN. I look forward to working with you. You have played an important role and made enormous contributions to this legislation. I thank the gentlelady.

Mr. BARTON of Texas. Could I inquire as to the time remaining on both sides, Madam Speaker?

The SPEAKER pro tempore. The gentleman from Texas has 22¼ minutes remaining. The gentleman from California has 23 minutes remaining.

Mr. BARTON of Texas. I yield 1 minute to a member of the committee

from Denton, Texas, or actually Flower Mound, Texas, Dr. BURGESS.

Mr. BURGESS. I thank the chairman for yielding.

Madam Speaker, last night I offered an amendment that would prohibit the transfer of or receipt of carbon and credit derivatives. And why is that important? Well, this bill will ensure a price for carbon, and it's going to ensure a market for trading carbon credits. This is a breeding ground for financial malfeasance. We are aware that if something has a price. Wall Street will find a way to create a financial instrument to option, swap or hedge and create fees for trading those instruments and drive value from the price of the underlying asset. The current financial crisis has heightened our awareness of the use of derivatives. Here is the problem: None of us can visualize a ton of carbon dioxide, yet that's what we're going to be buying and selling in these credits. Where would you put a ton of carbon dioxide? What kind of container would it come in? In fact, we've had multiple hearings in our committee about problems with the futures market in trading oil. But at least someone eventually has to take possession of that oil. No one has to take possession of that chunk of blue sky that we are going to call a ton of carbon dioxide. My amendment would have stopped the invention of carbon credit derivatives before it starts. It would have stopped the next Enron before it starts. Unfortunately my attempt to prohibit this activity was denied. I can only ask

Mr. WAXMAN. Madam Speaker, I yield 1 minute to the gentleman from New Jersey (Mr. HOLT) for the purpose of a colloquy.

Mr. HOLT. Madam Speaker, I thank the Chair.

Energy, climate and environment are principal subjects that I have spoken about and worked on for decades, before and since I first came to Congress and to work on these issues. I believe. is a principal reason my constituents sent me to Congress. I admire the chairman's skill in assembling a bill, and I fully support the chairman's efforts to reduce the release of greenhouse gases. However, I'm deeply concerned that the bill does not include the research funding necessary to reach the target of 80 percent emission reduction set in the bill. We must transform the way we produce and use energy. We cannot meet this goal with today's technologies; and this bill, as written, will not provide the billions of dollars needed to fund and develop the future technologies.

So I'm here to ask the chairman of the committee if I may have his assurance that he will work with me to increase the amount of research and development funding in this bill and other legislation that we need in order to reduce our reliance on foreign fuels and to slow the rate of growth of climate change.

Mr. WAXMAN. I thank the gentleman for his comments. There is

much in this bill to promote research and to bring about the necessary innovation.

The SPEAKER pro tempore. The time of the gentleman has expired.

Mr. WAXMAN. I yield myself another 10 seconds.

However, I agree that we will need billions more in research and development funding into new innovative ways to produce and use energy. I pledge to work with you to provide additional funding for energy research and development in this bill as this bill moves forward.

Mr. BARTON of Texas. I yield for a unanimous consent request to a member of the committee, Mr. BUYER of Indiana.

(Mr. BUYER asked and was given permission to revise and extend his remarks.)

Mr. BUYER. Madam Speaker, I rise in opposition to this legislation.

I rise in defense of the Midwest and the State of Indiana to oppose this carbon cap and tax bill. This is the most economically disastrous energy policy our nation has ever considered. It's over 1200 pages and full of last minute changes! This is not the way, or the time, to consider a rushed policy that will devastate our economy. The American people deserve more from their Representatives than a bill of empty promises that will send their jobs overseas, raise the cost of living, and increase our dependence on energy from foreign countries.

Over the past few years, I have participated in multiple hearings concerning carbon dioxide emission control. During the mark-up of H.R. 2454 by the Energy and Commerce Committee. I. along with my colleagues, continued to raise concerns about this policy's negative effects on American ratepayers, businesses and industry. Importantly, we offered many amendments in the mark-up we would like to consider on the Floor today, but we have been denied the opportunity. We would have added nuclear energy—the cleanest and most efficient energy generation—but were denied. Other amendments would have offered offramps should this legislation prove too costly to the American people. Unfortunately, no significant changes providing off-ramps or safetyvalves have been offered to the American people, and our concerns have not been addressed.

H.R. 2454 would hand down the single biggest energy tax in the history of our country. Now is not the time! The unemployment rate is at the highest we have seen in over 25 years. Our automotive industry is just beginning new business plans. This week we are selling off more of our national debt to foreign countries, and next month we are considering a national healthcare plan projected to cost \$3.4 trillion! It is not the time to pass a policy that will result in an annual additional cost of \$1,241 more in energy costs for a family of four. It is not the time to pass a policy that will drive up the price of goods and services, or export our hard-earned jobs to countries like China. This legislation will kill jobs. Let's talk numbers. An estimated 1,145,000 will be lost under cap and trade. There is a whole section dedicated to unemployment with a price tag to the taxpayer of over a billion dollars! Farmers

will also suffer. This act would lower farm profits by 28: percent in 2012 alone, and 57 percent from 2012–2035. Projections show this would result in total gross domestic product losses averaging \$383 billion annually from 2012–2035 and cost our country a total of \$9.4 trillion dollars. Where will that money come from?

Well, under this proposal, the Midwest, for one. This cap and tax bill unfairly targets the heartland of our nation. Indiana is the sixth highest carbon dioxide emitting state in the nation. As a state reliant on coal for 96 percent of its electricity, Indiana would be unfairly burdened by the current legislative proposal for producing American-made goods with American-made energy. What kind of energy policy is that? Under the current language, permits are allocated to utilities using a basis of 50 percent of their emissions and 50 percent of their retail sales-providing utilities without emissions access to allowances. Sending allowances to those that do not require them does not benefit the people or states that need them most. I offered an amendment in Rules to correct this bad policy. My amendment would have modified the utility allocation formula to being strictly based on 100% of a utility's emissions. It is common sense: the utilities reliant on the costlier fuel should be the ones receiving the help. We shouldn't be handing out allowances to those who do not need them! Under the current formula, utilities of similar size in California would get 2.43 times the allowances of an Indiana utility—and a Washington utility would receive 8.84 times the allowances of a utility in Indiana! That is not acceptable! Under the current bill, our rates will rise by a projected 90 percent by 2035, driving our manufacturing jobs elsewhere and the costs of goods sky high. The State of Indiana has worked hard over the past several years to bring new jobs and industries to Hoosiers. This bill could undo all the progress we have made. Unfortunately, my amendment was denied by the Rules Committee

I call upon my colleagues to see this is not the time for this bill. An energy tax anticipated to slow temperature increases by merely hundredths of a single degree Fahrenheit by 2050 is not good policy. I strongly urge Members to protect the economic well-being of the American people and vote no on this bill.

Mr. BARTON of Texas. Madam Speaker, I yield 2 minutes to the distinguished ranking member of the climate change committee and the former chairman of both the Judiciary and the Science Committees, Mr. SENSENBRENNER of Wisconsin.

(Mr. SENSENBRENNER asked and was given permission to revise and extend his remarks.)

SENSENBRENNER. Madam Mr. Speaker, this bill is not only everything that the opponents have said it is, but it is also a massive transfer of wealth from the United States to foreign countries. And the reason it is that is because this bill legalizes offsets. Over 40 percent of the offsets that have been created under the Kyoto Protocol have come from China. The \$2.2 trillion that will be transferred through purchase of offsets in foreign countries will be the largest nonmilitary foreign aid bill that this House of Representatives has ever passed.

The chart that is beside me here shows that the \$2.2 trillion in foreign giveaways is equal to 210 times the amount of money we give to help people with domestic heating oil and propane; 119 times the amount of money we give for making buildings more efficient; 111 times the money we give for clean vehicle technology; 33 times the money that we give for domestic natural gas consumers; 11 times the amount that we give for the domestic industrial sector; and five times the amount that we give to help out our domestic electric consumers.

Madam Speaker, this money should be spent at home. We have enough problems at home that we have to deal with, and I think the Congress has recognized this today. But let's not send more money overseas, money that will come through higher prices at the pump, higher bills from our utilities, higher food prices when we buy them in the supermarket.

Vote this bill down, and keep the money at home.

Mr. WAXMAN. Madam Speaker, at this time I yield 2 minutes to the gentleman from Massachusetts, Chairman Frank, for purposes of a colloquy.

□ 1600

The SPEAKER pro tempore. The gentleman from Massachusetts (Mr. FRANK) is recognized for 2 minutes.

Mr. FRANK of Massachusetts. Madam Speaker, I yield to the gentleman from New York (Mr. McMahon).

 $\operatorname{Mr.}$ McMAHON. Thank you, Chairman Frank.

Madam Speaker, I rise today to thank Chairman Frank, Chairman Waxman, Chairman Markey and Chairman Peterson for agreeing to include in this good piece of legislation the manager's amendment language that makes clear that the sections of this bill that relate to the regulation of energy commodity derivatives shall be superseded by future Congressional financial regulatory reform if it comes forward.

Specifically, the manager's amendment would add section 358 that renders "null and void" the sections of the American Clean Energy and Security Act dealing with energy commodity derivatives, as well as all related agency regulations, after Congress adopts future derivative reform legislation.

I and many of my colleagues in the New Democratic Coalition have expressed concerns about many of the provisions included in subtitles D and E of this bill. The energy bill is not the place to set regulatory policy over our financial services industry.

In coordination with the New Dems Financial Services Task Force, I'm in the process of crafting a bill that will take some of the best ideas of the President and the Congress to forge a consensus that protects American jobs and financial innovation. And while I

and many of my colleagues would have liked to strike altogether much of the derivatives language from this bill, we understand the need to move this process forward and section 358 will allow us to provide a clean slate when we take up comprehensive reform this year.

Despite the mess at AIG, the overthe-counter derivative market helps companies manage risks and create jobs. We also live in an age of a truly global economy. And if we don't get this right, many of our financial sector jobs, particularly in New York, will just disappear or be shipped offshore.

Again, Madam Speaker, I thank our chairmen for the inclusion of section 358 in the manager's amendment. I and the New Dems look forward to working with you and having future discussions with the Senate and the White House.

Mr. FRANK of Massachusetts. Madam Speaker, I will take back my time. You now have the answer, listening to the gentleman address myself, Mr. WAXMAN, Mr. MARKEY and Mr. PETERSON, to that age-old question of how many chairmen does it take to answer a colloquy?

I ask the gentleman from Massachusetts for 1 additional minute to finish the response to the colloquy.

Mr. MARKEY. I yield further.

Mr. FRANK of Massachusetts. And I want to say that the gentleman from New York has been a very articulate advocate for the very important functions of the financial community in New York in which many of the people in his district live, and he is very well informed about it. We agree with him, myself and members of the Financial Services Committee and the Agriculture Committee. Chairman PETER-SON, the gentleman from Minnesota, and I have worked with the gentleman from Massachusetts (Mr. MARKEY) and the gentleman from California (Mr. WAXMAN). And we have the agreement he alluded to.

We are hard at work on a comprehensive, and I believe responsible, proposal for regulation of financial derivatives in their entirety. And it will, under the terms of this bill, become the operative word. So what we have here is a placeholder to tell Members we are aware of it.

Earlier today, Chairman Gensler of the CFTC and Chairwoman Shapiro, in case we didn't have enough chair people in this, met with Mr. PETERSON and myself. I am optimistic that we will have a proposal that responsibly, appropriately and toughly regulates derivatives without doing them harm. The gentleman is to be congratulated for making sure that that will be what will be in the bill.

Mr. McMAHON. Thank you, Chairman Frank, and to all the chairmen for your strong leadership in crafting this important piece of legislation and reaching out to form this consensus.

With that, I urge my colleagues to support H.R. 2454.

PARLIAMENTARY INQUIRY

Mr. GOHMERT. I have a parliamentary inquiry.

The SPEAKER pro tempore. The gentleman will state his parliamentary inquiry.

Mr. GOHMERT. Madam Speaker, in order to find out what we are doing, how much damage we are doing to the country, I tried to get a copy of the bill. We have out here on the table H.R. 2454 that has 1,090 pages in it. But I understood since debate in here that there are another 300 pages that were added in the middle of the night.

My inquiry is how do I get a copy of the other 300 pages that people here on the floor haven't had a chance to read or see? Where do we get that before we slam this and cram this down on the American people?

The SPEAKER pro tempore. The amendment is printed in the Rules

Committee report.

Mr. GOHMÊRT. In the Rules Committee report. And Madam Speaker, where would I get that report?

The SPEAKER pro tempore. The rule was passed earlier today.

Mr. GOHMERT. Rules passed it earlier today?

The SPEAKER pro tempore. The rule

was passed earlier today.

Mr. GOHMERT. That says basically we are going to the floor without everybody being able to get a copy in the Speaker's Lobby as is normally required?

The SPEAKER pro tempore. The gentleman is not asking a parliamentary inquiry.

Mr. GOHMERT. Well, I'm asking an inquiry because I really want to know. Normally, the rules require we have access to a copy of the bill so we can look at it.

The SPEAKER pro tempore. The amendment was included in the Rules Committee report.

Mr. GOHMERT. My inquiry is, where is it? There is one copy in the Rules Committee? Is that the answer?

The SPEAKER pro tempore. It was part of the Rules Committee report that was part of the rule that was passed earlier today.

Mr. GOHMERT. It was part of the rule passed earlier today. But where is a physical copy I can get, read and look at?

The SPEAKER pro tempore. The Chair is not responsible for dissemination of documents.

Mr. GOHMERT. The Chair is not responsible for disseminating copies. I appreciate that. I was just asking for where I can get a copy. I know that your hands are full. And congratulations on the position. I think the President did a great thing. But I'm still needing a copy of the other 300 mysterious pages that we don't get to see here.

PARLIAMENTARY INQUIRY

Mr. BARTON of Texas. Madam Speaker, I'm going to ask a parliamentary inquiry.

The SPEAKER pro tempore. The gentleman will state his parliamentary inquiry.

Mr. BARTON of Texas. Is there somewhere physically in the House of Representatives a copy of what we are voting on?

The SPEAKER pro tempore. The engrossing paper is at the desk. As to copies, the gentleman has not stated a parliamentary inquiry that the Chair can answer.

Mr. BARTON of Texas. All right. Let me digest that, Madam Speaker.

In the meantime, I want to yield 1 minute to the distinguished Congressman from California (Mr. McCLINTOCK) 1 minute.

Mr. McCLINTOCK. I thank the gentleman for yielding.

Madam Speaker, when we talk about Herbert Hoover's mishandling of the recession of 1929, the very first thing that economists point to is the Smoot-Hawley Tariff Act that imposed new taxes on over 20,000 imported products.

I believe the Waxman-Markey bill is going to be looked back upon as our generation's Smoot-Hawley Act. In fact, it is worse. It imposes new taxes on an infinitely larger number of domestic products on a scale that utterly dwarfs Smoot-Hawley. At least Hoover could argue that Smoot-Hawley made domestic products more competitive with imports. Waxman-Markey disadvantages American products.

When California adopted similar carbon restrictions 3 years ago, we too were promised an explosion of green jobs. Instead, California's unemployment rate has skyrocketed to one of the highest in the country.

I believe that if this bill becomes law, history guarantees us two things. Number one, the planet will continue to warm and to cool as it has been doing for billions of years; and two, Congress will have just delivered a staggering blow to our Nation's economy just at the time when it is most vulnerable.

Mr. MARKEY. We would like to reserve at this time.

PARLIAMENTARY INQUIRY

Mr. BARTON of Texas. I have another parliamentary inquiry.

The SPEAKER pro tempore. The gentleman will state his parliamentary inquiry.

Mr. BARTON of Texas. Is there a rule of the House that requires a copy of the pending legislation to be present in or near the body?

The SPEAKER pro tempore. The official papers are at the desk. The Chair is not aware of a rule concerning additional copies.

Mr. BARTON of Texas. So there is no such rule?

The SPEAKER pro tempore. The Chair is not aware of one.

Mr. BARTON of Texas. I appreciate that honest answer

I want to yield 1 minute to the gentleman from Pennsylvania (Mr. DENT).

Mr. DENT. Madam Speaker, I rise in strong opposition to this national energy tax. This bill is all cost and no benefit. And I want to read some excerpts from a letter that was sent to

me from the Pennsylvania Public Utility Commission:

"This policy will have a profound adverse impact on the Commonwealth of Pennsylvania. If the Waxman-Markey bill were to pass, Pennsylvania is looking at a bleak scenario, a net loss of as many as 66,000 jobs, a sizeable hike in the electric bills of residential customers, an increase in natural gas prices, and significant downward pressure on our gross State product."

"The cost estimates are staggering."
"Congress has a responsibility to en-

congress has a responsibility to ensure that legislation enacted on this important topic is in the best interests of every State and region in the United States."

"Residents of Pennsylvania will be severely and disproportionately harmed. It will be impossible to rapidly or immediately stop using power generated at existing coal-fired or natural gas-fired power plants without causing severe and protracted reliability problems."

"Is Pennsylvania ready to acquiesce behind Federal legislation that will choke off our economy by displacing thousands of jobs and increasing utility bills for residential taxpayers? We hope not."

That is the Pennsylvania PUC. I say, save jobs. Save money. Vote "no."

Mr. MARKEY. The Chair recognizes the gentleman from Rhode Island (Mr. LANGEVIN) for 1 minute.

(Mr. LANGEVIN asked and was given permission to revise and extend his remarks.)

Mr. LANGEVIN. I thank the gentleman for yielding.

Madam Speaker, I rise today in strong support of the American Clean Energy and Security Act. I thank our leaders who made this bill a priority, especially Chairman WAXMAN and the gentleman from Massachusetts (Mr. MARKEY) who worked tirelessly to bring this bill to the floor today.

I have long been an advocate for reducing harmful carbon emissions and investing in a clean-energy economy. The effects of climate change are already beginning, and we must act now not only for this generation but for generations yet to come. By increasing the renewable energy standard, capping carbon emissions and investing in the creation of domestic clean-energy jobs, this bill is directing our Nation towards a sustainable and economically viable energy future.

This bill also establishes five programs to protect consumers from energy price increases. I want to say that again. It establishes programs to protect consumers from energy price increases.

I urge my colleagues to vote "yes" on the American Clean Energy and Security Act. It is time for America once again to lead on sustainable energy.

PARLIAMENTARY INQUIRY

Mr. BARTON of Texas. I have one more parliamentary inquiry.

The SPEAKER pro tempore. The gentleman will state his parliamentary inquiry.

Mr. BARTON of Texas. If a bill for which there is no copy were to actually pass this body, could the bill without a copy be sent to the Senate for its consideration, having no copy?

The SPEAKER pro tempore. The official copy will be at the desk. The Chair cannot comment about extra copies.

Mr. BARTON of Texas. The official copy will be at the desk. Could I inquire as to when that copy will be at the desk? Is it necessary that the official copy be at the desk in order for final passage to occur?

The SPEAKER pro tempore. The official copy is always at the desk during consideration of the bill.

Mr. BARTON of Texas. Then where is it, Madam Speaker?

The SPEAKER pro tempore. At the desk.

Mr. BARTON of Texas. Is it now at the desk? Is it now—I appreciate the Congressman who brought it in. Oh, that is not it. That is not at the desk.

Well, while we research whether the official copy is at the desk, I'm going to yield 1 minute to the gentlelady from Oklahoma, Congresswoman FALLIN, for 1 minute.

Ms. FALLIN. Madam Speaker, I have to say that I am outraged. Here we are getting ready to vote on a piece of legislation, and we haven't even seen 300 pieces of this legislation. No one can even find the bill or even knows where it is at. And here we are talking about major policy that could change the face of America, that will certainly be a large tax increase to our taxpayers. And here we don't even know where the bill is. I'm just shocked at the way we are running this House today before we leave to go on our Independence Day holiday.

And I will say that the government's first priority right now should be addressing our economy and jobs. And economists can tell you that one of the surest ways to prolong a recession and to damage an economy is to raise taxes. My friends on the other side of the aisle apparently didn't get that memo.

This plan for carbon emissions taxes amounts to a \$646 billion tax increase on the American public. It will have a negative effect upon every American family, upon business and upon family farms. Family energy costs will increase. In fact, it is said that utility costs can go up anywhere from 30 to 50 percent, not to even mention what cost increases will be upon manufacturing.

So Madam Speaker, I will just tell you that I hope we get a copy of the bill so we can at least look at it before we enact this policy.

Mr. MARKEY. I continue to reserve. Mr. BARTON of Texas. Madam Speaker, I'm going to ask unanimous consent for a brief recess to find the official copy that includes everything passed at the Rules Committee last night, because I am told that what is at the desk is missing 300 pages. That cannot be the official copy.

The SPEAKER pro tempore. Is there objection to the request of the gentleman from Texas?

Mr. MARKEY. I would object, but ask the gentleman to yield to me if he would.

Mr. BARTON of Texas. Why don't you reserve the right to object?

Mr. MARKEY. I reserve the right to object.

Mr. BARTON of Texas. I will be happy to yield to my friend from Massachusetts on his reservation.

Mr. MARKEY. The manager's amendment, which I think is what is of concern to him, is on the Rules Committee Web site that can be accessed right now, and has been there and available for any Member or any citizen of the United States to be able to read. It is on the Web site.

Mr. BARTON of Texas. Do Members have access to the Web site on the floor of the House?

Mr. MARKEY. In the Cloakroom there is access to it. We have these similar technological capacities in our cloak room, yes.

Mr. BARTON of Texas. In the Cloak-room, but not on the floor.

Mr. MARKEY. It is also available at the desk.

□ 1615

Mr. BARTON of Texas. Reclaiming my time on the gentleman's reservation on my unanimous consent request, what is at the desk for any Member of this body who is engaged in the debate is not apparently the official copy. It is missing 300 pages. Now what is on the Web site is almost immaterial because it is unprecedented in this gentleman's history in the Congress to not have some, usually at least two copies that both sides can access during the debate on the floor.

I am just asking for a 15-minute recess to get an actual copy that we can access.

I yield to the gentleman on his reservation.

Mr. MARKEY of Massachusetts. I continue to reserve my right to objection, there is a copy up there on the Speaker's podium at the desk.

Mr. BARTON of Texas. It is missing 300 pages.

Mr. MARKEY of Massachusetts. It is not missing the 300 pages. They are all up there. Everything you are looking for is up there next to the Speaker, and it is available on the Rules Committee Web site for anyone and everyone to have access to. But it is sitting right up there. The 300 pages are right up there.

Mr. BARTON of Texas. I am going to ask a unanimous consent request to give me a minute to go down and look at that and see if it is actually 1,300 pages.

Mr. MARKEY of Massachusetts. I would have to object at this time because the actual document is sitting there right now, and has been sitting there, as it has been on the Web site for the entirety of this debate.

Mr. BARTON of Texas. So the gentleman does object?

Mr. MARKEY of Massachusetts. I do object, yes.

PARLIAMENTARY INQUIRY

Mr. GOHMERT. Parliamentary inquiry.

The SPEAKER pro tempore. The gentleman from Texas will state his parliamentary inquiry.

Mr. GOHMERT. My parliamentary inquiry, I was just at the dais and the clerks, as always, were immensely helpful. But apparently the official copy of the 1,090 pages are there, and then the additional 300 pages are sitting beside it, and the Clerk is having to go through and is in the process as we speak of going through and figuring out where the extra 300 pages that has been added goes in the official copy. So even as I speak, Madam Speaker, the official copy is not truly an official copy because it doesn't have all of the amendments in it.

And since the rule says there is an official copy at the desk, my inquiry is whether it is truly an official copy if it, as yet, does not have all of the pages in the official copy.

The SPEAKER pro tempore. The Clerk is currently executing the order of the House in House Resolution 587.

Mr. GOHMERT. Right, to put the extra pages into the official copy. But is it required that it actually be a full official copy put together before you satisfy the requirement of having an official copy at the desk?

The SPĒĂKER pro tempore. The two components of the official copy are there together, so it is, in effect, the official copy.

Mr. GOHMERT. So the two together in two different piles that are being worked out together is the official copy. I appreciate the explanation.

Mr. BARTON of Texas. I am parliamentary inquiried out, Madam Speaker, so I am going to yield 1 minute to the chairman of the Republican Study Committee, Mr. PRICE from Georgia.

Mr. PRICE of Georgia. Madam Speaker, this would be humorous if it weren't so doggone sad.

This national energy tax bill will impose a massive tax that even the President's own aides have admitted would cost \$2 trillion to taxpayers.

The President himself boasted about the enormous cost saying, "under my plan of cap-and-trade system, electricity rates would necessarily skyrocket."

Indeed, this plan would increase taxes on American families by \$3,100 and raise their energy bill by \$1,500 a year. This national energy tax will force many businesses to outsource jobs overseas or close their doors altogether, which will cost over a million jobs annually.

Amazingly, it will have little or no impact on the environment. Many experts believe the environment will be adversely affected since many companies will be forced overseas where emission and environmental standards are minimal or nonexistent.

Hundreds of groups such as the NFIB, the U.S. Chamber, and the National Association of Manufacturers oppose this legislation. Tax and government watchdog groups, including the National Taxpayer Union, Americans for Tax Reform, and Citizens Against Government Waste, oppose this legislation.

This bill is bad for the environment and bad for the American people. Just vote "no."

Mr. MARKEY of Massachusetts. I continue to reserve.

Mr. BARTON of Texas. Madam Speaker, I yield 1 minute to the gentleman from California (Mr. BILBRAY).

Mr. BILBRAY. Madam Speaker, as someone who has spent a decade regulating air pollution, I look at this bill, of what I can read of it that is presented, and come to the conclusion that the greatest threat to the environment seems to be all of the smoke coming out of the backroom deals that appear to have been made to put this package together.

People may talk about the aspects of clean coal. Clean coal is as logical as safe cigarettes, and that is trying to be

sold in this document.

I have to say, in all fairness, what I see here is a huge tax scheme that doesn't fulfill the mandates that the U.N. Convention on Climate Change set as a minimum. In fact, it not only does not fulfill the need of the environment; it does it 5 years late and short. So it is late and short on this task.

Madam Speaker, we have seen legislation come over this floor before. Twenty years ago this body approved a snake oil called ethanol and methanol and MTBE, and today, we still don't have the bravery to admit the mistake and correct it with this bill. We continue the past mistakes. The difference between the mistake we did with methanol and ethanol is the fact that it will take 150 years to correct the mistake that Congress is about ready to do if we pass this piece of legislation.

I look forward to having to spend the next 100 years having to try to correct this mistake.

Mr. MARKEY of Massachusetts. I continue to reserve.

PARLIAMENTARY INQUIRY

Mr. SHADEGG. Madam Speaker, parliamentary inquiry.

The SPEAKER pro tempore. The gentleman from Arizona will state his parliamentary inquiry.

liamentary inquiry.
Mr. SHADEGG. I simply want to clarify the points that the gentleman from Texas (Mr. GOHMERT) was making before and make sure I understand this.

This is the printed version of the bill which apparently went to Rules last night. As I understand it, these are the 304 pages that make up the manager's amendment. And together, as I understand the Chair's ruling, this constitutes the official copy; is that correct?

The SPEAKER pro tempore. The Clerk is currently integrating the pages of the amendments with the original copy of the bill. It is available for Members to see. It is right where it is meant to be, and yes, it is the official version.

Mr. SHADEGG. Further parliamentary inquiry.

The SPEAKER pro tempore. The gentleman may state his parliamentary inquiry.

Mr. SHADEGG. Each of these pages, as I understand it, could change a page in this matter, and so the Clerk is presently trying to meld these together. So you can't read this without also reading this, and this modifies any given page in this: is that correct?

The SPEAKER pro tempore. The Clerk is executing the order of the House according to its terms.

Mr. SHADEGG. I thank the Speaker. Mr. BARTON of Texas. Madam Speaker, I want to yield 1 minute to the gentleman from Missouri (Mr. AKIN).

Mr. AKIN. Madam Speaker, I am the ranking member of the Armed Services Subcommittee on Seapower. We have talked a lot about climate change and global things and taxes, but my concern is very specific with this bill.

I have had a chance to tour the huge shipyards where the steel frames go up and the nuclear reactors go into the ships of our mighty Navy, and every single step of the way, there is energy involved in making the steel, in making the aluminum for the aircraft, heavy, heavy uses of energy in welding the steel together.

If this bill passes, it is a major threat to heavy industry because it increases the cost of energy. When we increase the cost of ships and planes, we are going to be able to buy less because we are not going to have enough money in the defense budget to be able to buy as many, and in that regard we become more vulnerable as a Nation.

This bill, while it has not been talked about in this regard, is a serious threat to our industrial base and, therefore, a threat to the security of our Nation.

Mr. MARKEY of Massachusetts. I continue to reserve.

Mr. BARTON of Texas. Madam Speaker, I have been so confused by all of the parliamentary inquiries, I have lost track of time. How much time remains?

The SPEAKER pro tempore. The gentleman from Texas has 13½ minutes remaining. The gentleman from California has 17¾ remaining.

Mr. BARTON of Texas. I yield 1 minute to the gentleman from Lubbock, Texas (Mr. Neugebauer).

Mr. NEUGEBAUER. Madam Speaker, one of the sayings we have in Texas is, when someone is pretending to be a cowboy, we say that fella is all hat and no cattle.

A lot of people have come down here today to try to represent that this is an energy bill. Well, let me tell you, it is not an energy bill; it is all tax and no energy.

Some of the people were talking about the fact that we are going to make America more energy independent. We are not. This bill does not make America more energy independent.

Every day we get up and write other countries a check for nearly a billion dollars, \$900 million. Now, what we get to do with this new bill is we get to send \$15 billion in 2012 to countries so they can plant trees and give us credits. Now doesn't that make a lot of sense?

What this bill is, and I think the title is appropriate, cap-and-trade. It is going to cap energy production in America and trade away American jobs. I think the American people are kind of concerned about jobs right now. We have families that are losing their jobs and we have families that are trying to pay their utility costs and trying to afford their gasoline, and yet we have got a bill down here that evidently is all talk and no bill. Don't vote for this bill.

Mr. WAXMAN. Madam Speaker, I continue to reserve my time.

Mr. BARTON of Texas. Madam Speaker, I'm going to reserve my time because they have got more time than we've got.

Mr. WAXMAN. Madam Speaker, I'm pleased at this time to yield 1 minute to the gentlelady from Maryland (Ms. EDWARDS).

Ms. EDWARDS of Maryland. Madam Speaker, I rise today in strong favor and support of the American Clean Energy and Security Act of 2009. I am going to tell you, I was a reluctant comer, but I really commend Chairman MARKEY and Chairman WAXMAN on their leadership and dedication to this bill. This is a big step toward ensuring that our children live in a cleaner and better environment and that we preserve and protect our planet for future generations.

The Earth is warming and glaciers are melting, and some may question the science, but I am not one of them. By the time a child born today, in 2009, reaches first grade, we will reach peak carbon. And without a doubt, we must use every tool attainable to respond to this crisis. This bill is one of those tools, and perhaps our strongest yet. It is my hope as we continue forward we will increase our investment in renewables, that we will ensure that we preserve and protect our planet and reverse the warming of our Earth.

I want to again thank the chairman. And despite my concerns, I support this bill strongly. I urge my colleagues to join me. And the statements made earlier today questioning global warming underscores the importance of this legislation today.

Mr. TAYLOR. Madam Speaker, I ask unanimous consent to express my opposition to this bill and for permission to insert a statement in the RECORD.

Mr. TAYLOR. Madam Speaker, I rise in opposition to this bill.

One of the provisions of this bill would create a cap and trade system throughout the United States in an effort to reduce the production of global warming gases. This system would limit the amount global warming gases emitted through regulation of "allowances" to each company. If a company released more

gases than their "allowances" permitted the company would be taxed by the federal gov-

The system also would establish an "allowance" market that would permit companies to buy and sell "allowances." The same speculators who manipulated oil futures last year, pushing gasoline prices over \$4 per gallon will be trading in the cap and trade market, trying to figure out how to game the system at the expense of consumers and taxpavers.

I do not believe a cap and trade system is the approach that is best to reduce global warming gases. As a matter of fact I think it is a simple "Ponzi Scheme" that will increase energy prices. According to the Congressional Budget Office it will create a complex financial system that allows risky investment in the energy market increasing the cost of living per household by \$1600 per year. Additionally, I don't like the idea that a factory in one state is cleaner than it has to be so that another factory is dirtier than it should be. This could potentially leave Mississippi with the cancer causing agents and other states with the cred-

Madam Speaker, I'll be brief.

This is a bad deal for South Mississippi and my nation. I hope that we will defeat this bill.

□ 1630

Mr. BARTON of Texas. Madam Speaker, I vield 1 minute to another great Californian, Mr. ROYCE.

Mr. ROYCE. Madam Speaker, I don't know where this ends. This cap-and-trade bill would give Washington 17 percent control of the economy. Nationalizing health care, which is next on the majority agenda here, would give it another 16 percent. The Federal Government right now runs General Motors. The government has a huge equity stake in many of our financial institutions. This Congress is relentlessly politicizing our economy. It has got to stop.

And this bill is an expensive job killer that won't achieve its objectives. and I will just give an example—and that's what's left out of the bill. The bill does nothing to encourage nuclear power plant construction, a sure job creator, a source of clean energy. The Department of Energy reports that the best way for utilities to reduce carbon emissions is nuclear energy, yet nothing here in this bill.

This bill is a bureaucrat's dream, the scheme that we see before us. It gives the EPA, the DOE, the IRS, and many other bureaucracies levers over our energy markets. Some in Congress will have these bureaucrats in their crosshairs aiming to game the system as this massively complex plan is implemented.

I oppose this bill. Mr. WAXMAN. Madam Speaker, I yield 1 minute to the gentleman from Kansas (Mr. Moore).

Mr. MOORE of Kansas. Madam Speaker, I commend Chairmen WAX-MAN and MARKEY for crafting this historic energy legislation that will help our country make the transition to a new clean-energy economy.

I urge Members to vote in support of the underlying bill. Americans are demanding bold policies that will push our country in a new direction on energy and ensure a clean, secure energy future for America.

This legislation is a positive step forward, but I urge Chairman Waxman's leadership to go even further to strengthen the renewable electricity standard during the conference com-

A strong standard would mean more jobs in the United States and a larger share of domestic and clean energy. Our children and grandchildren are watching. If we don't take this step for them today to leave them with a world that is healthy and more secure, when will we? As a proud grandfather of nine, I urge my colleagues to vote in favor of this legislation.

Mr. BARTON of Texas. Madam Speaker, I reserve at this point.

Mr. WAXMAN. Madam Speaker, I yield 1 minute to the gentleman from the State of Oregon (Mr. BLUMENAUER).

Mr. BLUMENAUER. Madam Speaker, Chairman WAXMAN, I appreciate your courtesy as I appreciate your leader-

It's strange that the debate boils down to our friends from the minority party being unable to access the Web site of the Rules Committee to print out the rule that has been available to any Member of the House. And Lunderstand some of them were waving it earlier in the day talking about provisions that they didn't like. But I guess we shouldn't be surprised because this is the same leadership that continually misrepresents the MIT study, citing \$3.000 of costs that has been refuted by the author of that report and asks the Republican leadership to stop misrepresenting his handiwork.

The CBO and the EPA have given estimates that are pennies a day, not thousands of dollars a year. And we're not talking about the long-term benefits of transitioning to an economy of the future.

I appreciate the leadership. On a recent trip to China with the Speaker, we saw the Chinese moving ahead. This legislation is an opportunity for us to keep pace and assume our rightful leadership within an economy for the future.

Mr. WAXMAN. Madam Speaker, I reserve the balance of my time.

The SPEAKER pro tempore. The gentleman from Texas has 101/4 minutes remaining. The gentleman from California has 16 minutes remaining.

Mr. BARTON of Texas. I yield 1 minute to Mr. Poe of Texas.

Mr. POE of Texas. Madam Speaker, I appreciate the gentleman for yielding.

I represent southeast Texas, the energy capital of the United States. Twenty percent of the refineries in this country that help all these folks all over the fruited plain with energy, I represent them.

This week alone, we've had 86 people call and say, Vote for this bill. We've had 1,578 people in my district call and say vote "no" on this bill, almost 20 times the number of yes votes.

I'm an advocate for those people in southeast Texas. They believe, as I believe, we're going to close up America's energy with this bill. The CBO and the EPA says there's not going to be much difference in the climate if we pass this deal. Bummer. It's not even going to work.

And it's more important to realize this bill is about control, government control of our lives, our businesses, and everything we do. Washington, D.C. is going to dictate how we live and how we shall live and how our businesses will live. And it's all bad because D.C. is in control and not the people. This is a bad bill. Vote "no."

And that's just the way it is.

Mr. WAXMAN. Madam Speaker, I am pleased to yield at this time 1 minute to the gentleman from Colorado (Mr. PERLMUTTER), who has made many important contributions to this effort.

Mr. PERLMUTTER. Thank you, Chairman WAXMAN.

I rise in support of the Clean Energy Act here. And I want to read the first sentence of a letter we received today from the National Association of Realtors. The National Association of Realtors supports H.R. 2998 (2454) the American Clean Energy and Security Act, which addresses a broad and global array of issues.

In closing, the National Association of Realtors ask for the favorable passage of this, as do Duke Energy, American Electric Power, BP Amoco, GE, and the American Institute of Architects.

This bill is designed to help us with national security, the climate, and jobs. My friend, Mr. Poe, from Texas says, Just vote no. Well, that's the party of the status quo. Just vote no, we like the status quo.

It is time for a change, ladies and gentlemen. We can't afford the status quo, and this bill brings us in that change and a new direction.

Mr. BARTON of Texas. Madam Speaker, I yield 1 minute to Mr. GOHMERT of Texas.

Mr. GOHMERT. Madam Speaker, you know, I've been trying to get through what I could of this bill and then finding out, well, actually, it's another bill. And then you have to incorporate all these other pages into it because I'd like to know what we're doing to the American people.

We've had people say we're playing politics on this side. If we wanted to play politics, because we know in our hearts this is bad for America, we would let you pass it and let you lose your jobs. But I've grown kind of fond of some of my friends on the other side; I'd like to keep you around.

But let me tell you, those who say there won't be any job loss, we're going to create jobs, let me just read you some of the things that are in your bill. The climate change adjustment allowance: when you lose your job, for any week of unemployment you are going to get some unemployment assistance after that. That's in there.

You've got some relocation allowance. But the coup de grace is that if you're an older American and you lose your job because of this, we fund a study in here

So I would encourage my colleagues, if you lose your job because of this bill, you probably are going to be able to get assistance because you lost your job because of this bill. Don't vote for it.

Mr. WAXMAN. Madam Speaker, at this time, I want to yield to my good friend, a leader in environmental areas and many others as well, the gentleman from Texas, Mr. Doggett.

Mr. DOGGETT. I thank the gentleman.

Earlier today, I voiced my strong objections to this bill. I voted against the rule to permit this bill because of its rejection of some amendments that I thought were important to improve the legislation.

For three reasons, I'm voting for final passage. First, I've been listening to the debate, not so much those who support the bill that I'm not all that enthusiastic about, but listening to the "flat earth society," the climate denials, some of the most inane arguments that I have heard against refusing to act on this vital national security challenge.

Second, I believe there is still some hope to make improvements to this bill once it gets out of the House. Better to have a seat at the table to try to influence the change that is needed in this legislation.

And, third, I'm convinced that unless we act today, the Senate will not act. And unless we act in this Congress, we will not get the international agreements we need to address this serious challenge.

I am voting "yes" in the hopes that we will have a better bill and we will have the international accord that we so desperately need to deal with this critical matter.

Mr. WAXMAN. Madam Speaker, at this time, I have an additional colleague who wants to address this issue before we close. I am very pleased to recognize her for 1 minute because she is a good friend and a very important Member of the House of Representatives, a colleague from California, BARBARA LEE.

Ms. LEE of California. I want to thank the Chair for yielding and also for your leadership. You and Mr. MARKEY, everyone has done a phenomenal job on this bill.

I rise today in support of H.R. 2454, which really does send a clear and unequivocal message that polluting our planet, our communities, and our livelihood no longer comes without a cost. This bill will create millions of highpaying, career-term green jobs that represent a much-needed pathway out of poverty for millions of individuals across this country, and I am pleased to see the inclusion of much-needed funding for the Green Jobs Act.

I must also be clear in saying that in America we should do more to address the climate crisis than provided for in this bill, but this is an unbelievable first start.

I believe we can produce more renewable electricity and achieve more aggressive emission reductions over time. I also recognize that passing the American Clean Energy and Security Act is a major, major bold critical first step toward achieving our goal of realizing a greener future.

As a person of faith, and as a long-time advocate for safeguarding our environment for future generations, Mr. Chairman, Madam Speaker, I think it's our moral and our ethical imperative and our responsibility to support this bill.

Mr. WAXMAN. Madam Speaker, we reserve the right to close on the debate, so I will now look to the other side to complete their statements.

Mr. PRICE of Georgia. Madam Speaker, unanimous consent request.

The SPEAKER pro tempore. The gentleman will state his request.

Mr. PRICE of Georgia. Madam Speaker, it's been estimated, with great accuracy, that between 2.3 million and 2.7 million jobs will be lost each year with this bill. I would ask unanimous consent that the House rise for a moment of silence to recognize those who will lose their jobs because of this bill.

Mr. WAXMAN. I reserve the right to object.

The SPEAKER pro tempore. The gentleman from California reserves the right to object.

Mr. WAXMAN. I object.

The SPEAKER pro tempore. The gentleman has objected.

Mr. PRICE of Georgia. I thank the Speaker.

Mr. BARTON of Texas. I yield 3 minutes to the distinguished Republican Conference chairman, Mr. PENCE of Indiana

(Mr. PENCE asked and was given permission to revise and extend his remarks.)

Mr. PENCE. I thank the gentleman for yielding.

It's hard to know where to start. I've got to think, Madam Speaker, a lot of people who are looking in on this debate and hearing about copies filed, esoteric process really don't care very much about all that because this economy is hurting. American families are struggling under the weight of the worst recession in a generation. Families in my district are losing their jobs. small businesses and family farms are struggling, and all they've seen out of Washington, D.C. so far is a gusher of runaway Federal spending, deficits, debt and bailouts. They didn't think it could get worse, but here we go.

In the midst of the worst recession in a generation, this administration and this majority in Congress are prepared to pass a national energy tax that will raise the cost of energy on every American family. Now, my colleague sporting the green lapel button, who I greatly respect, said that there is a lot of

dispute about how much the average American household will pay if this national energy tax becomes law, and that's true. There are estimates ranging from a few hundred dollars a year, to the Heritage Foundation's over \$4,000 a year. The estimate I prefer was from candidate Barack Obama, who said in January 2008 to the San Francisco Chronicle, and I shall quote with the deepest respect: "Under my plan of cap-and-trade system, electricity rates would necessarily skyrocket. That will cost money. They"-referring to the utility companies—"They will pass that money on to consumers." Now-President Barack Obama.

Now, I know earlier this week the President of the United States said that polluters are going to pay the cost of this national energy tax. That's not what he said last year. Now, I don't know how you all define "skyrocket" when the President said electricity rates would necessarily "skyrocket under my cap-and-trade plan," but I would be prepared to defer to you.

□ 1645

I define "skyrocket" as a prescription for economic decline. There may be a dispute in the numbers about how much I'll be paying in my electrical bill or how much the costs of goods and services are going to go up. But there is no dispute that this cap-and-trade legislation will cost millions of American jobs. Raising the cost of energy is a bad idea in prosperous times. Raising a national energy tax in the worst recession in a generation is a profoundly bad idea.

But for anyone looking in, Madam Speaker, let me say, we are in the minority, as we have been reminded with some firmness on this debate on occasion today. We don't have the votes to stop this bill. But you do.

If you oppose the national energy tax, call your Congressman right now. If you think we can do better to serve the interests of the American people and achieve energy independence with an all-of-the-above strategy, call your congressman right now.

Alexander Hamilton said it best: "Here, sir, the people govern."

We can stop this bill. We can do better. And so we must.

PARLIAMENTARY INQUIRY

Mr. BARTON of Texas. Madam Speaker, I have one more parliamentary inquiry.

The SPEAKER pro tempore. The gentleman will state his parliamentary inquiry.

Mr. BARTON of Texas. Under the rules that we operate on, the leader-ship on both sides, each is allowed 1 minute to speak at any time. Will that time come out of this debate, or does that time come out of the debate on the Forbes amendment?

The SPEAKER pro tempore. It depends on what part of the debate they are yielded to.

Mr. BARTON of Texas. I'm sorry?

The SPEAKER pro tempore. It depends on what part of the debate they are yielded to.

Mr. BARTON of Texas. Would Mr. WAXMAN yield for a question, then?

I'm trying to figure out if I need to reserve 1 minute for Mr. BOEHNER to speak now or if the Speaker and the majority leader are going to speak later and not in this part of the debate.

Mr. WAXMAN. Will the gentleman yield?

Mr. BARTON of Texas. I would be happy to yield.

Mr. WAXMAN. We're ready to conclude the general debate. We will then move on to the amendment, and in the course of the discussion of the amendment in the nature of a substitute, our leadership plans to speak, and they will close the debate for our side as we move to vote on that amendment and then passage on the bill.

Mr. BARTON of Texas. Then I will yield myself the balance of my time, Madam Speaker.

The SPEAKER pro tempore. The gentleman from Texas has 51/4 minutes remaining.

(Mr. BARTON of Texas asked and was given permission to revise and extend his remarks.)

Mr. BARTON of Texas. Madam Speaker, before I begin I want to compliment you on your speakership of this debate. As always, you've been gracious and temperate and fair, and we wish you the very best in your new position at the Department of State.

As the country western song goes, Madam Speaker, I've got a long way to go and a short time to get there. So I'm trying to get through in the next 5 minutes the major issues on the debate before us.

I want to first start with the socalled compromise the chairman of the Agriculture Committee and the chairman of the Energy and Commerce Committee have worked out. As we have seen during the debate by the number of colloquies, the compromise is a work in process. I've seen it amended and referred and rebutted several times on the majority side.

But if you will look to my far left on this chart, in the base text of the bill, there is a provision that gives the Administrator of the EPA the right at any time, at any time, to designate any man-made gas as a greenhouse gas subject to the regulations of this bill. As far as I can tell, that paragraph trumps everything that Chairman PETERSON has attempted to negotiate with Chairman WAXMAN.

The second thing that I want to point out is the basic math of their allowance system simply doesn't work. The transportation sector today is responsible for 35 percent of the greenhouse gas emissions in the United States, 35 percent. If you count the good work that Mr. DINGELL did and the good work that Mr. Green did on the majority side in getting allowances for the transportation sector, they get a grand total of 4 percent, 4 percent. Well 4 from 35 is 31 percent. When you get down to 2050, you have to reduce CO₂ emissions by 83 percent, which only

leaves 17 percent of total emissions from the baseline year. You've got to cut the transportation sector in half. And if you assume that we're not going to develop some sort of a giant rubberband for general aviation, you can't put an electric battery or a nuclear reactor in an airplane. General aviation is going to have to use fossil fuel. You simply can't get to that 83 percent reduction from the 2005 baseline with the math in their bill. It is a physical impossibility.

The third point: The science is not there to back it up. There is an EPA report that has been suppressed, that was never made a part of the record, that we are trying to get as we speak that raises grave doubts about the endangerment finding. Now, if you don't have an endangerment finding, you don't need this bill. We don't need this bill. And for some reason, the EPA saw fit not to include that in making the decision. We have e-mails that show that the director of the subcabinet agency within the EPA said the decision has been made the report is not helpful. It's not only not helpful; it's harmful. So the science isn't there.

The next point: No matter how you cut it, costs are going up. Just basic math. Just basic math. In Iowa the CEO of the utility that provides most of the electricity for Iowa says in Iowa alone, costs are going to go up \$110 a month per residential customer. That's \$1,200 a year. Gasoline prices are going to go up somewhere between 40 to 70 cents a gallon. If you take a midpoint of, say, 50 cents a gallon and assume that the husband and wife work outside the home and they each drive a thousand miles a month, you're going to have a gasoline price increase per family in America of about \$800. That is \$2,000 a year per family in 2012. It's not a postage stamp.

Now, there are estimates as high as \$6,000 a year, but as a baseline let's start with \$2,000. That's in the first year and every year thereafter. If you look at this chart here on unemployment, if it goes below the bar, that's negative: 2015, 2.3 million jobs; 2025, 2.7 million. Go on down the road. It averages over 2 million jobs every year.

Now, you talk about a green job revolution. In Spain they have been trying to do that, Madam Speaker. And in Spain for every green job they've created, they have lost two conventional jobs. And the green jobs they have created in Spain have cost about \$1.2 million per job created in terms of government subsidies. That's not a revolution that I want to be part of, Madam Speaker.

I simply cannot express enough to get to 83 percent baseline reduction in CO_2 by the year 2050, which doesn't change in this bill, you have to reduce the emissions in the United States to the level that we had in 1910. And if you want to look at it on a per capita basis, assuming the population is going to average about 1 percent growth a year, it takes us back to 1875.

This is a bad bill. It deserves to be defeated. Please vote "no."

This legislation threatens to lock the United States into an era of economic stagnation and global decline, thanks to a massive national energy tax that will kill American industry and send jobs overseas.

We are here today voting on one of the most significant pieces of energy legislation ever, and we have only had the final text for a matter of hours. Surely, a majority of the Members have not read any of the bill, and I doubt that one in a hundred have read the 400 new pages that were turned in to the Rules Committee in the dark hours of this morning. This is not the way this Congress should do business. It is not the way the American people expect us to do business. What happened to the promises of the President and the Speaker of transparency?

This bill will cause the average American's electricity bill to increase by 77 percent to 129 percent. Filling up the gas tank will cost anywhere from 60 percent to 144 percent more. That means, at today's prices, gasoline would be well over \$4 per gallon. As we all vividly remember from last summer, \$4 gas is painful and unsustainable.

The negative economic effects of this bill will hit some parts of the country worse than others. The Democrats cite a recent CBO study, which is now based on outdated text, which says that the negative economic impact will only be \$175 per household. I dispute this analysis because it ignores the full negative consequences of this legislation, in that the study completely ignored the economic damage from restricting energy use. Well, gross costs will be closer to \$900 per household. And if average gross costs will be \$900, then I can only imagine how bad it will be in the Midwest and Southeast who are going to be much harder hit.

The cost of home heating oil and natural gas will nearly double. An independent analysis of the latest Waxman-Markey text explains that when all of the tax impacts have been added up, the lost GDP in 2035 works out to \$6,790 per family-of-four and that is before they pay their \$4,600 share of the carbon taxes. That puts the costs per family for the whole energy tax aggregated from 2012 to 2035 to \$114,915. Do you think the above estimate will help the American economy? Of course not.

If Democrats manage to pass this fiasco, millions of lost American jobs will likely be sent overseas. Already the recession seems to deepen by the day. The national unemployment rate is 9.4 percent and President Obama has already declared that we are going to see it topping 10 percent. All this even though this House passed the President's Stimulus bill in January without even taking the time to read that bill either. Michigan has an unemployment rate of over 14 percent. South Carolina has an unemployment rate of over 12 percent. North Carolina and California have over 11 percent unemployment. Ohio and Indiana have over 10 percent unemployment. Using the latest numbers, in May of 2009, 14 states have double-digit unemployment, with another 5 states between 9 and 10 percent. We should pass legislation that seeks to decrease unemployment—let's not add fuel to the fire.

This bill would create a trillion dollar carbon derivatives market. We introduced an amendment to ban speculators from participating in the market during mark-up because we don't think that our economy can withstand another AIG Credit Default Swap Crisis. And we certainly cannot afford another multi-billion dollar bail-out

Because there is so little protection for industry jobs that rely heavily on affordable and dependable baseload power, I think we can expect to start buying more Mexican cement, Chinese fertilizer and Indian steel.

How can we cap global greenhouse emissions without the participation of China and India? Not only does China reject any mandatory caps on its emissions, but they demanded that we subsidize them in their quest for better technology. Well, I have good news for China—this bill has plenty of handouts for foreign polluters at the expense of American industry. So, congratulations.

This bill is reckless and does not have a safety valve or exit ramp, even though my colleagues and I introduced several safety valves during the mark-up. It seems to me that it would be a good idea to kill this bill if gas goes up to \$5 or electricity bills double because of this legislation. But, obviously my colleagues on the other side of the aisle are willing to roll the dice with the American economy. We filed these amendments with the Rules Committee and were shut out completely. The Democrats are so unconfident in the costs and repercussions of their own bill that they cannot even risk an amendment that would sunset the policies when costs and unemployment resulting from this Act cripple the American economy.

This bill grants near-dictatorial powers to the head of the Environmental Protection Agency to sacrifice the American economy in the cause of suppressing greenhouse gases. If you think suppression is the wrong word, I want you to know that it was just yesterday we learned that the EPA administrator and the Obama Administration suppressed an inconvenient dissent offered by a career EPA official.

It seems clear that officials who already engage in political suppression of opposition opinion are hardly the people in whom we want to invest the future of the U.S. economy.

Let's investigate that scandal, but in the meantime, let's turn back this power grab today and go to work on an all-of-the-above energy solution that includes nuclear and offshore drilling.

The SPEAKER pro tempore. The time of the gentleman has expired.

The gentleman from California has 13 minutes remaining.

Mr. WAXMAN. Madam Speaker, I yield myself the balance of my time. I won't take 13 minutes.

My colleagues, we have a unique historical opportunity today to pass a bill that will lead us to greater independence as a Nation, controlling our own national security. We have an opportunity to transform our economy with new jobs. And we must do something about the carbon emissions that are causing such an enormous problem to our planet. We have this opportunity because President Obama has set this high on his agenda. We have it because of the commitment of Speaker Pelosi. We have it because the scientists are telling us there's an overwhelming consensus that, despite the comments that we have heard from the other side of the aisle, global warming is real, and it's moving very rapidly, and we may get to a point that will be a tipping point. Our actions will make no difference after that.

Let us not lose this historical opportunity for our national security, for jobs in this country, to protect our environment, to make us the leader once again in the international community, and to get them to join with us in doing what we must to avoid the disasters that many scientists have predicted. Vote for this legislation.

Mr. POLIS. Madam Speaker I rise today in support of this legislation, and urge its passage.

I also would like to thank Chairman WAXMAN for his hard work on this bill, it is of incredible importance and he has taken that responsibility to heart.

I also thank the chairman for including two of my amendments within the manager's amendment, provisions that are important to ensure quality clean energy jobs training programs are accessible to all communities and that state SEED funds can go directly to renewable energy producers ensuring we get the most for our clean energy investment.

Mr. Speaker, today we will be casting an historic vote, a vote of moral responsibility, a vote of economic prosperity, and a vote FOR our nation's future and our nation's leadership on the international stage.

We've heard the arguments against acting, we've heard the nay sayers and those who would rather fear something they don't understand then roll up our sleeves and work to solve a monumental challenge.

To my younger colleagues and the millions of young men and women in this country who are embarking on their adult lives, who are starting young families and are looking to a brighter future I say . . . This is our generation's space race, this is our generations cold war, this is our generation's greatest challenge and it is past time that we accept that challenge to do better rather than shy away in the face of the unknown.

I'd just like to reiterate the scale of this issue, and say that I find it truly troubling that when we are faced with overwhelming credible and independent scientific evidence, and we can see the effects of a changing climate in our daily lives, the delusion it takes to drum up facts and figures paid for by oil companies and promote those as if they were science is truly reaching a new low.

This bill is not a tax. This bill isn't even a preverbal tax, and to paint something as a tax simply because you don't understand it is irresponsible.

We simply can't afford to do nothing.

Opponents of action would continue the status quo of doing nothing, which has cost the average family a \$1,000 increase in energy bills over the past eight years.

America's energy costs will increase by \$420 billion annually within the next 5 years if we do nothing to reduce our dependence on oil and fossil fuels. That amounts to \$3,500 annually for every family in the nation.

This bill has oversight after oversight, and ensures that consumers aren't hurt at all.

This bill is good for our economy. Low income consumers are protected first, the CBO estimates that this bill will save low income

consumers \$40 by 2020. The energy efficiency provisions in this bill could save \$750 per household by 2020 and \$3,900 per household by 2030.

My colleague on the other side of the aisle seems to be giving data compiled by the partisan Heritage foundation, espousing to know something about my district.

But Coloradans already know that in our state we already have many of the provisions that this bill makes federal, like a Renewable Energy Portfolio Standard. These policies have made Colorado a clean energy leader and have brought our state high tech and high quality jobs.

T encourage my colleagues and the American people to learn about this critical issue, learn about the science, learn about the market mechanisms that this bill creates . . . and DON'T BUY the falsities that big oil and big energy companies are spending millions to promote.

We've had enough. We've had enough of old ideas, of fear, of just saying no to a better tomorrow and we've had enough of old technology running our country and economy into the ground.

It's time we take a significant step forward, shaking the special interests and act boldly for the good of our country. You might be scared, but don't hurt our country because of that fear.

This bill is our Apollo project, our Manhattan project but now we act for a nobler cause and we must act in bold and decisive terms.

I urge passage of this legislation.

Mr. HÖLT. Madam Speaker, I rise today in support of H.R. 2454, the American Clean Energy and Security Act of 2009.

For years, the consensus in the scientific community has been that the release of greenhouse gasses into the atmosphere is altering the Earth's climate in ways that are expensive and deadly. This is one of the principle subjects I have spoken about and worked on for decades—before and since I first ran for office—and it is one of the reasons, I believe that my constituents sent me to Congress.

Today the House of Representatives at last is taking sweeping action to cap greenhouse gas emissions, promote the production of renewable energy, and make our homes, cars, and businesses more energy efficient. This legislation would require that we reduce our carbon emissions by 17 percent from 2005 levels by 2020 and 80 percent by 2050. It would implement a Renewable Electricity Standard that would require electric utilities to provide 20 percent of their electricity from renewable sources by 2020. It would make historic investments new clean energy technologies and energy efficiency, including energy efficiency and renewable energy, carbon capture and sequestration, electric and other advanced technology vehicles, and research and development. These provisions would help to slow the rate of global warming and preserve our environment for future generations. Further, a recent report from the Center for American Progress estimates that these provisions would help to create 1.7 million new, high skilled clean energy jobs over the next decade.

Opponents of this bill have argued that it would cost American families over \$500 a year in additional energy costs. While it is true that there would be increases in the cost of energy, this bill would return almost 50 percent of the proceeds from the cap-and-trade

auction to consumers. In my home state of New Jersey, families who currently pay \$100 on their monthly energy bill would see their bill increase by less than \$3 a month. If you include the savings that would come through the energy efficiency provisions in this legislation American families could save \$4,000 by 2030 on their energy bills.

According to the Environmental Protection Agency, in New Jersey climate change has caused temperatures to be 4 degrees warmer than they were in 1970. Over the past century precipitation has increased by 5 percent and severe weather incidents have increased by 12–20 percent, and sea level along our coast is increasing .14 inches a year. It is worth devoting some money and effort to slow the devastating climate change is having on our state.

I am pleased that several provisions that I wrote were included in this bill. I worked with Rep. GEORGE MILLER and Rep. JERRY MCNERNEY authorize the WaterSense program that would help consumers identify water efficient products. Water efficiency saves energy by reducing the amount of energy used to heat, transport, and clean water. The savings are substantial and real. According to the Environmental Protection Agency, if only one out of every 100 American homes retrofitted their homes with water-efficient fixtures, we would save 100 GWh of electricity, enough energy to power more than 9,000 homes for an entire year, while reducing greenhouse gas emissions by 80,000 tons.

Rep. JARED POLIS and I wrote a provision that would require the Departments of Energy, Labor and Education to compile an online database for a renewable energy curriculum that would be easily accessible to community colleges, vocational schools and universities looking to create training programs but lacking local or technical expertise. The transformation to a clean energy future will require a trained workforce and our amendment would ensure that these communities, whether in rural Wyoming or urban Pittsburg, have easy access to green jobs training in new energy and new manufacturing sectors so they can prosper in a new energy economy.

I worked with Rep. Rosa DELAURO, Rep. TAMMY BALDWIN, and Rep. BRIAN BAIRD to include a provision that would allow the Secretary of Energy to create a research program to study the role that human behavior will play in energy consumption and climate change. Changing consumer behavior offers a promising opportunity to promote energy independence and reduce greenhouse gas emissions, however there is still much to be learned about the forces that drive consumer actions.

As a member of the Committee on Natural Resources, I worked to make sure that sufficient funding from the cap and trade auction would be used for domestic and international adaptation. Funding allocated under this provision would help to ensure the protection, restoration, and conservation of natural resources and enable them to become more resilient, adapt to and withstand the impacts of climate change and ocean acidification. It will require the study of how wildlife corridors will change as climate change affects migration patterns and identify the steps to minimize the effects of climate change on migratory species. It would be used to protect the public health from the effects of climate change. Internationally, it would be used to prevent the tropical deforestation that is adding billions of tons of carbon to our atmosphere.

I remain deeply concerned that this bill does not include the necessary research and development funding that is needed to reach the 80 percent reduction target set in H.R. 2425. We will not be able to meet this goal with today's technologies, and as written, the bill does not provide the billions of dollars a year that will be needed to develop them. This is not a small or parochial concern. If Americans and others around the world are to embrace a transformation in the way we use and produce energy, they must know that our effort includes the engine to drive the innovation for that transformation. Without a very robust research effort-many billions of dollars-the vision of transformation will be a mirage and the public will know it. I have been assured by MARKEY. Chairman WAXMAN, Chairman Speaker PELOSI, members of the Administration and members of the Senate that they understand this shortcoming and that they will work with me to increase the research funding to drive the innovation we need to transform the way we produce and use energy.

Ultimately, I support this bill because doing nothing is not an option. If we continue on the same path the U.S. Global Change Research Program estimates that average global temperatures will increase 11 degrees Fahrenheit by the end of the century, causing among other effects a rise in sea level of 3 to 4 feet, completely flooding low lying areas like the Everglades and Cape Canaveral or Cape May. By passing this legislation we can slow the rate of climate change, we can create millions of new jobs, save consumers money through energy efficiency, and end our reliance on foreign fossil fuels. I urge my colleagues to support it.

Mr. HIMES. Madam Speaker, I rise in support of the Manager's Amendment to H.R. 2454, the American Clean Energy and Security Act.

According to the Department of Energy the building sector is responsible for 39 percent of total U.S. CO₂ emissions. At long last, and due in part to the improvements contained in this amendment, Congress is acting to decrease the negative effect buildings have on our environment. Over the past year, members of the Financial Services Committee have met with a wide array of housing advocates, nonprofits and agency leaders to craft legislation that improves the energy efficiency of housing while creating sustainable and affordable communities for our citizens.

The result of this painstaking work is a bill known as the Green Resources for Energy Efficient Neighborhoods, or GREEN, Act, led by my esteemed colleague from Colorado Mr. PERLMUTTER and currently contained within the Manager's Amendment to H.R. 2454. Through a broad array of public and private incentives, it seeks to encourage energy efficiency and develop renewable energy sources for housing and commercial buildings in order to achieve the changes in the housing sector that will help build America's clean energy economy for the next century.

A provision I contributed to the GREEN Act provides incentives to lenders and financial institutions to help consumers who build, buy or remodel their homes and businesses to improve their energy efficiency—lowering their energy bills, curbing waste and reducing carbon emissions all at once. I strongly encourage my colleagues to support these priorities by passage of the amendment and of the underlying legislation.

While I support many of the changes in the Manager's Amendment, I do have concerns about provisions in the Amendment which address over-the-counter derivatives, a matter which falls properly within the jurisdiction of the Financial Services Committee, and which I believe would best be addressed in that setting.

These reservations notwithstanding, I strongly encourage the passage of the Manager's Amendment and of the American Clean Energy and Security Act, which marks a historic step toward innovation and energy independence for our Nation.

Mr. MATHESON. Madam Speaker, the two great energy issues our generation faces right now are domestic energy security and climate change. These issues deserve our active attention, and they deserve action. Unfortunately, the bill we are considering today does not appropriately address these issues.

Some continue to argue that climate change is not happening. In fact, scientific consensus has clearly been established that climate change is a very real, significant problem and we need to determine an effective way to reduce global greenhouse gas emissions. However, this legislation has problems.

The early-year carbon reduction targets assume an aggressive pace of new technological development that may be unachievable. These targets received little attention in the debates that have taken place on this bill.

I remain concerned that this energy bill will result in unfair regional wealth transfers. The one-size-fits all renewable electricity standard is not the right approach to address climate change. It is an add-on without a purpose. Data shows that the renewable targets in this bill are only slightly better than business-asusual. So why are we bothering to dictate these standards when we should encourage the 15 States that currently do not have renewable energy targets to find something workable for their communities?

The bill's distribution of emission allowances also creates regional inequities. The "50–50" formula in the bill gives extra, unneeded allowances to utilities with lower fossil fuels resources, and less to utilities with greater reliance on fossil fuel resources. Those regions that receive excessive allowances would sell those allowances to other regions of the country that received less.

With respect to carbon markets, this bill overreaches and will effectively destroy the derivatives market. Many people seem to confuse the different types of markets that exist. The futures market contains listed derivatives-these are standardized exchange-traded agreements. There is also a market for cleared derivatives, which are standard contracts that are privately negotiated but booked with a clearinghouse as a counterparty. And finally, you have the over-the-counter derivatives market where people negotiate deals to fit the needs of everyone ranging from utilities, to airlines, to banks, and finally, regular investors. This is a very complicated financial system and while it is clear that we are not appropriately regulating this market today, we should also avoid gutting the market altogether. I think there is a reasonable way to structure the new carbon market and to address deficiencies in the commodity markets. The provisions in the bill are not the right approach, and these provisions of the bill were

never really debated in a House committee hearing.

There are also some changes made to the offsets section which are troubling to me. I have been supportive of the effort to build a strong, accountable offsets program and I am sorry to see that this bill allows USDA to try to establish a much looser, less effective program. This is short-sighted because unless offsets signify real, verifiable carbon reductions, they will be worthless. This is problematic because buying and using offsets is much cheaper for businesses than it is to buy allowances.

I have been advocating for the inclusion of transmission language in order to build much-needed infrastructure. However, this bill only addresses the Western Interconnection, not the whole country. That doesn't get at the underlying problem which is the lack of electricity transmission capacity across the Nation. I wish this bill had taken an approach similar to the one the Senate is considering.

Finally, the issue of energy independence calls for additional items that are not included in today's bill. In the long run, technological advances will provide new options to help this country gain a more secure, stable energy profile. In the interim, we need policies that keep all options on the table for the development and use of conventional energy sources.

As a result of all of these concerns, I will vote against this legislation. However, I will continue to work on the important issues of climate change and energy independence.

Mr. KUČINICH. Madam Speaker, I rise in opposition to H.R. 2454, the American Clean Energy and Security Act of 2009. The reason is simple. It won't address the problem. In fact, it might make the problem worse.

It sets targets that are too weak, especially in the short term, and sets about meeting those targets through Enron-style accounting methods. It gives new life to one of the primary sources of the problem that should be on its way out—coal—by giving it record subsidies. And it is rounded out with massive corporate giveaways at taxpayer expense. There is \$60 billion for a single technology which may or may not work, but which enables coal power plants to keep warming the planet at least another 20 years.

Worse, the bill locks us into a framework that will fail. Science tells us that immediately is not soon enough to begin repairing the planet. Waiting another decade or more will virtually guarantee catastrophic levels of warming. But the bill does not require any greenhouse gas reductions beyond current levels until 2030.

Today's bill is a fragile compromise, which leads some to claim that we cannot do better. I respectfully submit that not only can we do better; we have no choice but to do better. Indeed, if we pass a bill that only creates the illusion of addressing the problem, we walk away with only an illusion. The price for that illusion is the opportunity to take substantive action.

There are several aspects of the bill that are problematic:

1. Overall targets are too weak. The bill is predicated on a target atmospheric concentration of 450 parts per million, a target that is arguably justified in the latest report from the Intergovernmental Panel on Climate Change, but which is already out of date. Recent science suggests 350 parts per million is nec-

essary to help us avoid the worst effects of global warming.

- 2. The offsets undercut the emission reductions. Offsets allow polluters to keep polluting; they are rife with fraudulent claims of emissions reduction; they create environmental, social, and economic unintended adverse consequences; and they codify and endorse the idea that polluters do not have to make sacrifices to solve the problem.
- 3. It kicks the can down the road. By requiring the bulk of the emissions to be carried out in the long term and requiring few reductions in the short term, we are not only failing to take the action when it is needed to address rapid global warming, but we are assuming the long term targets will remain intact.
- 4. EPA's authority to help reduce greenhouse gas emissions in the short- to mediumterm is rescinded. It is our best defense against a new generation of coal power plants. There is no room for coal as a major energy source in a future with a stable climate.
- 5. Nuclear power is given a lifeline instead of phasing it out. Nuclear power is far more expensive, has major safety issues including a near release in my own home state in 2002, and there is still no resolution to the waste problem. A recent study by Dr. Mark Cooper showed that it would cost \$1.9 trillion to \$4.1 trillion more over the life of 100 new nuclear reactors than to generate the same amount of electricity from energy efficiency and renewables.
- 6. Dirty Coal is given a lifeline instead of phasing it out. Coal-based energy destroys entire mountains, kills and injures workers at higher rates than most other occupations, decimates ecologically sensitive wetlands and streams, creates ponds of ash that are so toxic the Department of Homeland Security will not disclose their locations for fear of their potential to become a terrorist weapon, and fouls the air and water with sulfur oxides, nitrogen oxides, particulates, mercury, polycyclic aromatic hydrocarbons, and thousands of other toxic compounds that cause asthma, birth defects, learning disabilities, and pulmonary and cardiac problems for starters. In contrast, several times more jobs are yielded by renewable energy investments than comparable coal investments.
- 7. The \$60 billion allocated for Carbon Capture and Sequestration (CCS) is triple the amount of money for basic research and development in the bill. We should be pressuring China, India, and Russia, to slow and stop their power plants now instead of enabling their perpetuation. We cannot create that pressure while spending unprecedented amounts on a single technology that may or may not work. If it does not work on the necessary scale, we have then spent 10-20 years emitting more CO₂, which we cannot afford to do. In addition, those who will profit from the technology will not be viable or able to stem any leaks from CCS facilities that may occur 50, 100. or 1000 years from now.
- 8. Carbon markets can and will be manipulated using the same Wall Street sleights of hand that brought us the financial crisis.
- 9. It is regressive. Free allocations doled out with the intent of blunting the effects on those of modest means will pale in comparison to the allocations that go to polluters and special interests. The financial benefits of offsets and unlimited banking also tend to accrue to large corporations. And of course, the trillion dollar

- carbon derivatives market will help Wall Street investors. Much of the benefits designed to assist consumers are passed through coal companies and other large corporations, on whom we will rely to pass on the savings.
- 10. The Renewable Electricity Standard, RES, is not an improvement. The 15 percent RES standard would be achieved even if we failed to act.
- 11 Dirty energy options qualify as "renewable": The bill allows polluting industries to qualify as "renewable energy." Trash incinerators not only emit greenhouse gases, but also emit highly toxic substances. These plants disproportionately expose communities of color and low-income to the toxics. Biomass burners that allow the use of trees as a fuel source are also defined as "renewable." Under the bill, neither source of greenhouse gas emissions is counted as contributing to global warming.
- 12. It undermines our bargaining position in international negotiations in Copenhagen and beyond. As the biggest per capita polluter, we have a responsibility to take action that is disproportionately stronger than the actions of other countries. It is, in fact, the best way to preserve credibility in the international context.
- 13. International assistance is much less than demanded by developing countries. Given the level of climate change that is already in the pipeline, we are going to need to devote major resources toward adaptation. Developing countries will need it the most, which is why they are calling for much more resources for adaptation and technology transfer than is allocated in this bill. This will also undercut our position in Copenhagen.
- I offered eight amendments and cosponsored two more that collectively would have turned the bill into an acceptable starting point. All amendments were not allowed to be offered to the full House. Three amendments endeavored to minimize the damage that will be done by offsets, a method of achieving greenhouse gas reductions that has already racked up a history of failure to reduce emissions—increasing emissions in some cases—while displacing people in developing countries who rely on the land for their well being.

Three other amendments would have made the Federal Government a force for change by requiring all Federal energy to eventually come from renewable resources, by requiring the Federal Government to transition to electric and plug-in hybrid cars, and by requiring the installation of solar panels on government rooftops and parking lots. These provisions would accelerate the transition to a green economy.

Another amendment would have moved up the year by which reductions of greenhouse gas emissions were required from 2030 to 2025. It would have encouraged the efficient use of allowances and would have reduced opportunities for speculation by reducing the emission value of an allowance by a third each year.

The last amendment would have removed trash incineration from the definition of renewable energy. Trash incineration is one of the primary sources of environmental injustice in the country. It is a primary source of compounds in the air known to cause cancer, asthma, and other chronic diseases. These facilities are disproportionately sited in communities of color and communities of low income.

Furthermore, incinerators emit more carbon dioxide per unit of electricity produced than coal-fired power plants.

Passing a weak bill today gives us a weak bill tomorrow. Rejecting a weak bill today gives us another chance to pass something more in line with the science tomorrow.

Mr. DICKS. Madam Speaker, as the chairman of the Interior Appropriations Subcommittee and someone who is very concerned about the need to safeguard wildlife and ecosystems from global warming, I wish to express my strong support for the "American Clean Energy and Security Act of 2009." I believe that the policy provisions in this legislation, coupled with a new core funding stream for wildlife and natural resources derived from a portion of the Federal revenues from expected cap-and-trade legislation will provide the policy response necessary to tackle this significant challenge.

I am very much aware of the need to take action to address global warming, and I have held hearings to examine the impact of climate change on many of the agencies and resources under my subcommittee's jurisdiction. I have consistently stated my belief that climate change may be the emerging issue of our time. Climate change will alter the face of our planet in ways we cannot yet fully comprehend, and I believe it is our responsibility not only to do as much as possible to halt or slow it, but also to do everything in our power to protect the earth's resources from its impacts so that future generations will be able to benefit from them as we and past generations have done.

Our Nation's wildlife is one critically important resource that is particularly vulnerable to climate change and is also a resource that is a fundamental part of America's history and character. Conservation of wildlife and wildlife habitat is a core value shared by all Americans.

America's wildlife is vital to our Nation for many reasons. Wildlife conservation provides economic, social, educational, recreational, emotional, and spiritual benefits. The economic value of the outdoor recreation industry—hunting, fishing, and wildlife viewing, hiking, paddling—alone is estimated to contribute \$730 billion annually to the U.S. economy. Wildlife habitat, including forests, grasslands, riparian lands, wetlands, rivers and other water bodies, is an essential component of the American landscape, and is protected and valued by Federal, State, and local governments, Tribes, private landowners, and conservation organizations.

Unfortunately, it is becoming increasingly apparent that the effect of climate change on wildlife will be profound. The Intergovernmental Panel on Climate Change reports have made clear that global warming is occurring, that it is exacerbated by human activity, and that it will have devastating impacts on wildlife and wildlife habitat. In addition, a recent report, Global Climate Change in the United States, was released by the Administration and reflects the most current information from our Nation's leading scientists who agree that the impacts from climate change are already being felt and will continue to increase.

Global warming is already impacting all of us: threatening the water we drink, the air we breathe, the medicines we use, the food we eat, the forests and fisheries we depend on, the special places we take our children. Wildlife is suffering from massive changes in habitat, particularly in the arctic, and shifts in ranges and timing of migration and breeding cycles. Continued global warming could lead to large-scale species extinctions. These impacts add to and compound the adverse effects wildlife and its habitat already suffer from land development, energy development, road construction, and other human activities, and from other threats such as invasive species and disease.

According to the IPCC, global warming and associated sea level rise will continue for centuries due to the timescales associated with climate processes and feedbacks, even if greenhouse gas concentrations are stabilized now or in the very near future. I believe that, as a nation, we must craft responses and mechanisms now to help navigate the threats global warming poses to the natural resources that we all depend upon for survival.

To conserve natural resources and wildlife in the face of the far-reaching effects of global warming, there is a need for a coordinated, national strategy based on sound scientific information to ensure that impacts on wildlife that span government jurisdictions are effectively addressed and to ensure that Federal funds are prudently committed. Ensuring strategic and efficient allocation of funding is something of particular interest to me as an appropriator.

To that end, I have acted within my capacity as a lead appropriator on this issue to advance steps necessary to combat the climate change impacts we have already set underway. I have worked to establish the Global Warming and Wildlife Science center at the U.S. Geological Survey, now receiving its second year of funding. Also in the recent FY09 omnibus appropriations bill and the FY2010 Interior Appropriations bill. I have provided direction to the Department of the Interior to develop a national strategy to address global warming's impacts on fish, wildlife, and natural resources.

The American Clean Energy and Security Act will help ensure that the pressing needs that are faced by the agencies and programs under the Interior and Environment appropriations subcommittee to help wildlife and wildlife habitat are addressed strategically, based on a foundation of sound scientific information, and that funding is driven through proven programs at the Federal, State and tribal levels in the most efficient way possible. I have also included significant funding increases. But I can only do so much in the Interior Appropriations bill.

I also have one additional but very significant point to make about funding to address impacts to natural resources and wildlife from global warming. It is essential that actions to safeguard wildlife and the natural resources will all depend upon receiving adequate funding. Addressing the greatest conservation challenge of our time will require long-term investments of the magnitude that only the revenue stream created by comprehensive climate and energy legislation can provide. While I support dedicating more of the allowances under this bill to natural resources adaptation, the 1 percent currently contained in the bill represents an important start of the problem. As I have indicated, the impacts are occurring today and the need is urgent. Paying for these investments through climate revenues takes the burden of protecting these resources off taxpaying citizens and onto the polluting entities responsible for causing global warming pollution.

The Interior and Environment appropriations subcommittee allocation is woefully stressed just dealing with the current needs of the agencies and programs under its jurisdiction. Our Federal land management agencies have tremendous backlogs for operations and maintenance of our national wildlife refuges, parks, forests, and other public lands. This situation was greatly exacerbated under the Bush administration budgets and prior Congresses. Hundreds of important biologist positions have been cut, and the agencies' budgets are far below what they have needed just to keep up with inflation. These programs have been starved to the point where they are on life support. It became apparent in hearings the subcommittee has held on global warming that the land management agencies are already seeing the results of climate change on the ground, but that they have few, if any, resources to deal with these changes. With the effects of global warming only expected to increase in severity in the coming years, I believe it is crucial to infuse a new core funding stream into our efforts to address this crisis, and I am pleased that the American Clean Energy and Security Act provides an important new funding stream.

This is a great Nation with a unique and irreplaceable natural heritage. We must take steps now to protect our wonderful wildlife from the ravages of climate change. With this in mind, I plan to vote for the American Clean Energy and Security Act of 2009.

Mr. CONYERS. Madam Speaker, I rise in support of H.R. 2454, "The American Clean Energy and Security Act of 2009," because, as a nation, we simply cannot afford to delay addressing the cataclysmic economic, national security, and environmental threats posed by global climate change any longer. Although imperfect, this piece of legislation is a necessary precondition for crafting a global solution to climate change. With this vote today, the United States reclaims the mantle of world leadership in addressing the single most important issue facing the planet.

The opponents of this legislation will argue that we are taxing away our economic prosperity and our jobs. This could not be further from the truth. For 22- to 30-cents a day, less than the cost of a stamp, this bill will transform our economy by investing in new energy technologies that will create whole new industries and millions of jobs. All together, this legislation will create 1.7 million new jobs, 53,816 of which will be located in my home State of Michigan. This bill isn't a job killer. In fact, it will unleash a flood of jobs created by a mean, lean, and innovative energy sector.

This bill also furthers other important national priorities. If enacted, this bill would finally break the chokehold the OPEC cartel has over our energy security, provide a lifetime of clean air for our children and their children, and prevent the threats of environmental catastrophes like hurricanes, draughts, and famines.

We must consider the costs of inaction. During the Bush-Cheney years, our dependence on foreign oil increased, average household energy costs went up \$1,100, and job growth slowed to a crawl. Throughout this time, the threat of climate change multiplied as the administration ignored reality and the scientific

community and turned a blind eye to the plight of future generations.

Although this is not the bill I would have written, the costs of inaction are simply too great to ignore. A vote for this bill is a vote for jobs at home, energy independence, and a livable world for all.

Mr. STUPAK. Madam Speaker, I rise to support and discuss regulations I included in the American Clean Energy and Security Act to prevent excessive energy speculation, which has played a role in the run away energy prices we saw last year, and are seeing in the first half of 2009.

In January, oil was trading at \$35 per barrel. Today, it is trading near \$70 per barrel. The price for oil has doubled in the midst of a global recession. Oil supplies are at a 20-year high, and demand is at a 10-year low, yet oil prices have skyrocketed since the beginning of the year. If this is based on supply and demand, what is happening to explain rising oil prices? If supply is up and demand is down during this global recession, why would oil continue to climb?

The Federal Energy Regulatory Commission, the Senate, as well as a number of respected oil market traders and analysts, have pointed to excessive speculation in the energy markets as the primary reason we see price spikes and volatility in the marketplace. In May, I introduced the Prevent Unfair Manipulation of Prices Act, or the PUMP Act of 2009. I worked with Energy and Commerce Chairman WAXMAN and Subcommittee Chairman MARKEY to include the bulk of my bill into the American Clean Energy and Security Act, which is on the floor today.

This legislation is not new; I have been introducing this bill in one form or another since April 2006. But new weaknesses in our regulatory structure, brought to light by the financial crisis and spikes in the price of oil last year, are addressed in the 2009 PUMP Act.

The need for this legislation is two fold: 1. the dramatic rise in prices of oil and natural gas, and 2. the new carbon derivatives trading market created by the ACES bill. Some object to the inclusion of regulations on derivatives in this energy bill. I believe ACES proposed capand-trade program is fatally flawed without strong regulations to police this market from run-away price swings on carbon.

Addressing excessive energy speculation should be a key part of any new energy policy pursued, because a dramatic spike in oil prices or carbon prices, would further devastate our already weakened economy. According to NYMEX officials, less than 1/10 of one percent of futures trades in crude oil ever result in physical delivery. Most futures traders are not interested in delivery of a product, they are interested in profit. When speculators increase their investments, physical hedgersbusinesses like airlines, trucking companies, and other industries that actually use the energy being traded-represent a smaller and smaller portion of the market. They are being squeezed out!

As a growing majority of the market is controlled by speculators, crude oil is morphed from a commodity into a financial asset, traded for its financial value instead of its energy value! As a result, this excessive speculation by index speculators is a significant factor in the price Americans are paying for gasoline, diesel and home heating oil, and has similar affects on agricultural prices. For too long,

through loopholes, exemptions, and poor enforcement by the Commodity Futures Trading Commission, energy speculators have been able to avoid position limits. As a result, excessive speculation has exploded.

My legislation in the 2009 PUMP Act and in ACES is comprehensive, and changes the regulations for the energy markets in fundamental ways. It makes the Commodity Futures Trading Commission regulate all over-the-counter trades that are currently not regulated; it regulates foreign boards of trades' energy transactions that trade for delivery in the United States or on a computer located in the United States. These boards are subject to the same regulations as current markets, including large trader reporting, recordkeeping, and prohibitions against fraud and market manipulation.

Mv bill closes the swaps loophole; no longer allowing energy transactions to be excluded from the requirements of the Commodity Exchange Act. This would require the CFTC to provide greater oversight over these swap transactions. It bans naked credit default swaps. Naked credit default swaps, or one where the holder has no risk obligation on the swap, which creates a moral hazard by incentivizing economic loss. It sets aggregate position limits for energy speculators across all markets; it includes a CFTC Inspector General provision that makes that office independent and accountable. It also requires all trades be cleared through a designated clearing organization, eliminating the unregulated "dark mar-

My bill allows the CFTC to collect fees and create an independent funding stream for oversight and enforcement of commodity markets. Finally, it includes carbon derivatives as a regulated energy commodities under the authority of the CFTC. This incorporates all greenhouse gas emissions, offsets, and financial products derived from carbon credits.

As the House works on the ACES bill, it is important that carbon trading not lead to a speculative bubble like we saw in the 2008 oil markets. Congress needs to pass legislation to set strong position limits, and ensure that excessive speculation does not allow speculators to detach carbon or energy prices from supply and demand fundamentals.

I am committed to continuing to work with my colleagues in passing legislation for the President to sign that sets strong position limits and improves CFTC enforcement to end this excessive speculation and provide relief to American consumers.

Ms. WOOLSEY. Madam Speaker, as a mother and grandmother, the health of our earth is at the top of my list of concerns so that my kids and grandkids aren't left with the messes we've created. For too long, we have ignored the warning signs that human activities having a negative impact on our environment. It's up to us to change our ways, use our brains, and stop our bad behavior.

The facts are clear. The time for debate on whether or not global climate change exists is over. What we need to do now, is address the problem before it's too late. We need to listen to the world scientific community, and act immediately to curb our carbon emissions. That's why I support H.R. 2454, the American Clean Energy and Security Act.

The single most important part of this bill is that it puts in place the federal structure to, for the first time, seriously regulate carbon emis-

sions that are adversely affecting our climate. And with proper oversight and science—with the right people in charge—this bill will do what we need to do.

Now, it's never easy to change the status quo. There's a lot of money out there for people who would continue the practices that we know are harmful to all of us. And we all know how that money can be used to muddy the issues and derail the will of the people.

The plain fact of the matter is this: Without this bill, without a strict regime for controlling carbon emissions, Big Oil and Big Coal Win. And the environment, endangered species, our kids, our grandkids, you, and I will be the losers.

Now, people point to China and India, and all the carbon they emit as a big problem too, and they're right. But the United States leads the world in carbon emissions and, as the world leader, it's our responsibility to lead the world in a new direction. The burden falls on America to set the tone. By instituting a cap and trade system, we are showing the rest of the world that we're serious about addressing the issue, and proving to them that it can be done.

Madam Speaker, I'm not willing to risk our future by doing nothing. I urge my colleagues to support this bill, take a stand, and lead the world in addressing the issue of global climate change.

Mr. KIND. Madam Speaker, I rise today to express my qualified support for the landmark bill before us, H.R. 2454, the American Clean Energy Security Act.

Global climate change poses grave risks to our planet, our economy, and our way of life; it, therefore, cries out for bold action to reverse mankind's contribution to the problem. At the same time, taking such action offers us the tremendous opportunity to remake our energy infrastructure to become less dependent on foreign sources of energy, improve the health of our population and environment, and create high-paying jobs here in America.

The sponsors of H.R. 2454 and its many champions here in the House claim that it will do all of these things-that it will ignite America's leadership in reducing global greenhouse gas emissions to sustainable levels, shift our nation's energy paradigm away from polluting sources and into clean, renewable ones, and create millions of jobs for domestic workers. I also believe this is the case. However, I fear that under this bill, progress toward these goals will come at great cost to American families, particularly in the area of western Wisconsin I represent and others like it. I am disappointed we did not have more time to debate the cost of the legislation and address our concerns through additional consideration of the bill in the Ways and Means Committee.

H.R. 2454 will require utilities and other greenhouse gas emitters to hold an allowance for each ton of these gases they emit. In the beginning of the program, the government will give a large number of these away to regulated utilities with the requirement that the value of these free allowances be used to mitigate the cost to consumers. While some people are very comfortable with this arrangement, I am not so confident that utilities will pass on the full value of these allowances to ratepayers. The initial years of the European Emissions Trading System demonstrated that giving valuable allowances to utilities for free encourages them to pocket the value rather

than reducing electricity rates. Whether the bill's additional layers of administration, oversight, and bureaucracy will be effective at preventing this from happening here is an experiment I would rather not impose on my constituents in western Wisconsin.

I am also concerned that the ACES bill is skewed against regions like mine that are rural and heavily dependent on coal for energy. The formula it establishes for doling out the free allowances to utilities provides more to those areas that need them the least—those that have a lot of zero-emission hydro or nuclear power—rather than those areas like Wisconsin that need the allowances because of their higher emissions. The federal government helped subsidize the hydro and nuclear plants in other parts of the country; ratepayers in my district should not have to send more money their way while we seek to realize the same low-carbon generation.

Finally, the bill allocates funds derived from consumers and spends it on such things as international deforestation, investments in technology, and wildlife adaptation. While these are worthwhile goals that will need to be addressed in the context of combating climate change, I do not think we should do so by putting an additional financial burden on those who can least afford it.

That is why I introduced H.R. 2757, the Consumer Assistance Rebate for Energy, or CARE, Act. This bill would have ensured that any money raised by the government as a result of climate change legislation would be given back to consumers directly to help them cope with any price increases for energy and consumer goods. The EPA stated in its analysis of the ACES bill that this type of approach is the least burdensome on low-income consumers, and that it achieves greenhouse gas reductions at a lower overall cost than the ACES system of free allowances to businesses and utilities.

While I wish my concerns about consumer protection had been addressed more fully in the bill before us, the legislation has changed for the better since being reported out of the Energy and Commerce Committee, and there is enough in the bill to recommend it that I am willing to support its passage today so that it will move to the Senate where it can be improved further.

The American Clean Energy Security Act will live up to its name in many ways. It will transition our energy systems away from unsustainable, polluting fossil fuels and toward clean, renewable resources such as wind, solar, biomass, and hydrogen. It will provide an unprecedented investment in the technologies and industries of tomorrow, creating more than 4,000 jobs in my Congressional District alone, and millions nationwide.

America is the nation that invented solar cell technology decades ago, and the investments we make in the coming years will allow us to regain our leadership in the world and be the center of innovation and industry that will drive the clean energy revolution.

The bill also includes funding to help our natural resources, and fish and wildlife in particular, adapt to the changes in their habitat that have already begun.

Finally, the bill includes opportunities for farmers, ranchers, and foresters to be a part of the climate solution, which is critical for my district, where agriculture remains the largest industry. The USDA, in consultation with EPA,

will establish a program where businesses and utilities can meet their greenhouse gas obligations by paying farmers who help sequester carbon. This new revenue stream will be very important in helping the agriculture sector cope with higher costs for energy, fuel, and fertilizer.

Again, I wish we had had more time to deliberate on this extremely large and complex piece of legislation. I wish the bill contained more direct, more transparent ways of compensating consumers. I wish the bill treated regions equitably. But I support strong action on climate change and the creation of millions of new jobs, and I will vote to move this bill forward in the hope that the Senate will pass a bill that works better for more Americans.

Mr. COSTELLO. Madam Speaker, I rise today in opposition to H.R. 2454, the American Clean Energy and Security Act of 2009.

I believe that climate change is occurring, and that increased greenhouse gas emissions have profoundly impacted our climate and our resources. To combat these changes, we need to develop a sustainable energy policy that will meet our energy needs today without compromising the ability of our children and grandchildren to meet their energy needs tomorrow.

For these reasons, I support a balanced energy plan that will increase our energy independence by promoting the development and deployment of 1) renewable domestic sources of energy, such as ethanol and biodiesel, and 2) technology that will use traditional fuels in a cleaner way, such as clean coal carbon capture and storage. These energy sources eventually may satisfy the needs of the entire country, but they are still being developed and expanded. We must ensure that Americans maintain access to affordable and reliable energy until these sources are broadly available.

I oppose H.R. 2454 because it does not provide a bridge for coal and other fossil fuels to develop and demonstrate new technologies to provide reliable energy and meet the necessary reductions in greenhouse gas emissions. The timelines contained in this legislation do not provide sufficient time to put these technologies in place. Manufacturers and utility companies will be forced to stop using the affordable, abundant fuels they use today and transition to far more expensive energy sources. As a result, this bill will force our most affordable domestic energy source, coal, into extinction. Energy costs will skyrocket and workers will face layoffs and plant closures. American families cannot face these additional burdens during these difficult economic times.

In addition, we cannot ignore the fact that climate change is a global problem and requires a global solution. We must consider the consequences of enacting this legislation when other countries, like China and India, have not taken steps to reduce their own carbon emissions. Without some measure of equity on this issue, our emissions may appear to decrease, but they will simply shift overseas, taking jobs and industries with them.

Madam Speaker, I oppose H.R. 2454 because it does not do enough to bridge the transition to clean energy sources, to prevent spikes in electricity costs, to protect workers from new layoffs, or to provide a global solution to climate change. Quite simply, it is the wrong bill at the wrong time. I ask my colleagues to join me in opposing this measure.

Mr. YOUNG of Florida. Madam Speaker, I rise in opposition to H.R. 2454, the so-called

American Clean Energy and Security Act. Throughout my time in Congress I have supported protecting America's environment and climate as well as incentives for clean alternative energy, including solar, wind, and biofuels. It is in our county's best interest environmentally, economically, and for our national security to transition away from imported oil to domestically available, renewable, and clean sources of alternative energy.

For instance, I have supported efforts by the

For instance, I have supported efforts by the City of St. Petersburg to power 40 of the city's parks entirely using a sustainable solar energy network which will allow these parks to be removed from the city's power grid.

In the 110th Congress I was a cosponsor of the Clean Energy Tax Stimulus Act of 2008. This measure would have provided for the continuation of eight clean energy production and efficiency tax benefits in order to incentivize important alternative energy investment and production.

I am also supportive of initiatives to require auto manufacturers to increase the fuel efficiency of the cars sold in America. In fact, in March I signed a letter to President Obama to urge him to take the strongest stand possible to increase the Corporate Average Fuel Economy (CAFE) standards. Last Congress I was a cosponsor of the Fuel Economy Reform Act which would have raised CAFE standards to 35 miles per gallon over the next decade.

And I have long been supportive of protecting Florida's environment and our military's training needs by opposing offshore drilling in the Eastern Gulf of Mexico.

I also believe in creating and supporting new green jobs. At the same time that we encourage conservation and the production of renewable resources, we must also help prepare Americans to work in these new green jobs. That is why I voted in favor of the Green Energy Education Act. This legislation would authorize funds to be made available to support advanced energy and green building training and graduate programs throughout the country.

Despite my support for clean energy and a clean environment, I must oppose this cap and trade legislation which will impose increased costs on American citizens who have done nothing wrong. At a time when the people of Pinellas County and our nation are hurting, it is incomprehensible that the House will knowingly approve legislation that will impose a new energy tax on American citizens, will put American companies at a competitive disadvantage, and will endanger the jobs of American workers.

Supporters of this legislation have tried to claim that the cap and trade scheme will only cost some negligible amount, a postage stamp per day or \$15 per month. They claim that a report by the Congressional Budget Office backs up this statement. However, if you actually take the time to read the CBO's report, you will understand that this is simply not true. The analysis only includes one limited portion of the 1,201 page bill. The analysis does not include the effects from the lower incomes and lost jobs that the CBO predicts will occur. The analysis does not include the effects from the decreased retirement accounts that will be realized as the value of stocks decline, as the CBO predicts. The analysis does not include the increased costs of producing goods in the United States, as the CBO predicts. In short, to say that this legislation will not hurt American families is simply misleading.

If this legislation is signed into law, energy costs are going to rise. Even the President acknowledges that electricity rates are going to "necessarily skyrocket." Britain's Taxpaver Alliance estimates that families there are paying \$1,300 more in taxes after the implementation of a similar program only a few short years ago. In drafting this legislation, proposals were offered to suspend the cap and trade program if gas prices rose above \$5 per gallon, if electricity prices rose by 10 percent, or if the unemployment rate hits an unthinkable 15 percent. All three of these sensible ideas were voted down by supporters of this bill. All Americans will be impacted by these higher energy prices, but the hardest hit will be the low income and the many of my constituents are seniors who live on fixed incomes.

I do not think that I need to remind any of my colleagues of the energy crisis of last summer. I remember all to well the stories from my constituents of the difficulty they had in dealing with \$4 per gallon gasoline. However, a study conducted by the American Petroleum Institute has found that the impact from this legislation will add an additional 77 cents to the price of a gallon of gasoline, and even higher costs for critical diesel fuel. In the last two years alone more than 5,000 trucking companies with at least five trucks went out of business, costing a countless number of jobs. Is this really the type of result we want?

Inexplicably, this legislation would spend seven percent of the cap and trade allowances—paid for by American consumers—in foreign countries. Let me repeat that: this bill will send \$302 billion U.S. tax dollars under cap and trade to foreign countries. Most of this money is set aside to plant trees. The Congressional Budget Office has said that "the allowances spent overseas would impose a net cost on U.S. households: They would bear the cost of the allowances but would not receive the value."

The cap and trade scheme also creates a new tradable commodity that Wall Street investors will be able to buy and manipulate. The pollution allowances will be traded and sold on the open market to the highest bidder. Companies who will be forced to buy these to provide necessary energy and products will pass on these costs to consumers. Even worse, this bill sets a minimum price for which the allowances can be sold for, not a maximum price to prevent the fleecing of American consumers. After the financial collapse of last year, we should not allow Wall Street speculators and commodity traders to hold the American people hostage in this way. I thought the purpose of this legislation was to protect the environment, not to help Wall Street get richer.

Also included in this bill is a one-size-fits-all nationwide renewable energy standard that favors certain regions of the country at the expense of others. It is estimated that residents in Florida will be forced to pay an additional \$339 million in their energy bills within only a few years, while the residents of some states in the northeast and the west coast will be heavily subsidized. Fundamentally, I believe that the federal government must get out of the business of picking winners and losers.

These are just some of the things that we actually know are in the bill. But there is no way for Members to understand everything that is included. The bill itself is 1,201 pages that few, if any of us have read. Then only this

morning, the Democrat leadership unveiled and added on a 309 page manager's amendment. The Washington Post says that this is a "1,201 page measure filled with political compromises, directives, subsidies and selections of winners and losers that members won't be able to analyze before the vote and that leaves us wondering how effective it will be." The St. Petersburg Times, which supports the legislation, admits that the bill is "imperfect". "not ideal," and that it includes "weasel language." Even the Chairman of the Agriculture Committee COLIN PETERSON, who was one of the principal negotiators of the final bill that we are discussing today, said, "The truth is, nobody knows for sure how this is going to work." Despite the importance of this issue, only one amendment has been allowed to even be considered by the House. The fact of the matter is, this legislation sets emission standards from now until 2050, and will affect our American way of life even further out from there. The initial reaction from my constituents in Pinellas County is that there is no need to rush through this process without understanding the effect on our nation the over the next 40 years. About 80 percent of the calls and e-mails that I have received have opposed this cap and trade bill.

We all agree that the United States must begin the transition to domestically available, renewable, and clean sources of energy. We should work to make it easier for this change to happen, and it is appropriate for the government to provide incentives, not penalties, on those who do the right thing by investing in new sources of energy. We can do this by following in the tradition of the Manhattan Project, where the United States government brought our best and brightest minds together to create the atomic bomb to win World War II. The New Manhattan Project for Energy Independence, which my colleagues and I will have an opportunity to support, will provide funding for American universities, scientists, and inventors to come together and create more energy efficient and affordable cars, buildings, advanced power plants, advanced biofuels, and carbon capturing technology to help clean our air. This can be accomplished without imposing new tax increases on the American people while taking the steps necessary to secure a clean and secure future. We can take this important step by including Democrats and Republicans working together. rather than refusing to even consider suggestions from Republican members or even letting us know of details of this cap and trade bill as it was being written.

This is the right way to approach our future energy and environmental needs. The wrong way is to punish average American citizens simply for going about their everyday lives—picking their children up from school, starting a small business, keeping their family cool in the summer and warm in the winter, or trying to make ends meet. And that's who this bill taxes and punishes.

Madam Speaker, if this was truly an energy bill, there is little doubt in my mind that both sides could come together, as we have done so many times in the past, to find a bipartisan solution that will help this country move in the right direction and reduce our dependence on imported oil, lower our energy costs, and reduce carbon emissions without punishing American families. Unfortunately, this legislation only amounts to imposing a new burden

on the American people at a time when they are already overburdened and I cannot support what the Wall Street Journal has called "the biggest tax in American history." Let's vote this down so we can go back and work together and do what's right for America.

Mr. MEEK of Florida. Madam Speaker, I stand for the creation of new American jobs, for less dependence on foreign energy, and for a reduction in the carbon pollution that causes global warming.

This bill is about national security, creating jobs in a new energy economy, and defending consumers through a fiscally responsible bill with consumer protections.

These investments will also spur new jobs. The Political Economy Research Institute estimates that 3.5 jobs will be created in the new green job sector for every 1 job that is fossil fuel source based in Florida. This could mean over 94,000 jobs in Florida alone.

Too often our foreign policy decisions are affected by the regional stability of oil producing countries. In Iraq we are paying for our oil-centric obsession and Floridians have paid over \$37 billion for the war there. This legislation offers incentives that promote energy efficiency and that will break our addiction to foreign oil. We must be focused on research and development for green technologies and end the obsession with crude oil that is fueling too much of our economy.

The bill is not perfect—few landmark bills are. Once the Senate takes up the bill later this year, this bill will be further improved and will address the shortcomings that exist in this version. My mission will be to ensure that the final legislation that is passed will include the necessary consumer protections to minimize price increases.

We cannot wait to act on climate change legislation. Florida is already experiencing eroding shorelines, flooding and dying coral reefs. In particular, the Everglades face severely altered water flows and harmful invasive species. This will also have a devastating impact on Florida's economy. In 2007, tourists flocking to Florida's beaches and other priceless environmental areas spent over \$65 billion in Florida.

Without aggressively capping carbon emissions, the earth's temperature will continue to rise, causing more extreme storms and altered ocean conditions which will have a devastating effect on Florida's ecosystem.

The American Clean Energy and Security Act (ACES) works to minimize price increases for consumers. On average the EPA estimates that this bill will cost an average household \$98 to \$140 per year in price increases, while holding those in the lowest income quintile harmless.

Without carbon emissions caps, we have seen energy prices fluctuate drastically. By regulating carbon intensive goods and creating a transparent market this bill will help to stabilize those prices and help protect consumers.

By investing in conservation, efficiency and renewables, Florida residents will see lower costs in energy though building weatherization improvement benefits, and energy efficiency savings.

Mr. TEAGUE. Madam Speaker, as most of my colleague know by this point, I'm an oil man.

Always have been. Always will be. When I was 17 years old, my father became sick, so I went to work in the oil fields, making \$1.50 an hour on a pulling unit, to help support the family.

I kept at it until I had my own company, employing and providing quality health care for 250 people.

Over the years, I've done just about everything there is to do in oil and gas around New Mexico. People know that HARRY TEAGUE is an oil man, and I am proud of that.

In 2007, when I announced that I would be running for Congress, people were surprised to find an oil man like myself campaigning on a platform that emphasized energy independence through a focus on the development of full and diverse slate of energy sources. Not only was I advocating increased production of our valuable petroleum resources. I told people in Hobbs, Roswell, Carlsbad and across Southern New Mexico that technologies like wind, solar, and biofuels were not only good for the environment, but would also create jobs in our communities and bolster our national security.

I did not wait long after being sworn in as a Member of the 111th Congress to turn my campaign platform into a legislative record. The very first bill I introduced, H.R. 451, provides a multiyear extension of the Renewable Energy Tax Credit. I worked hard to have that legislation included in the House version stimulus package, and when you signed the American Recovery and Reinvestment Act into law on February 17, 2009, the production credit was included.

I am proud to say that H.R. 451 not only gave one of the largest boosts we have ever given to renewable energy production in this country, but it also saved the oil and gas industry \$13.1 billion dollars in prospective tax increases.

As the 111th Congress continued, I likewise continued my work promoting energy production in America. I passed several amendments to various legislation promoting renewable energy, and I worked tirelessly to ensure the Budget Resolution passed by Congress did not include tax hikes on oil and natural gas.

Then came the American Clean Energy and Security Act, which is the bill we're here debating today.

When the legislation was introduced and then reported out of committee, I must say, I was deeply skeptical. I had one central concern:

I worried that this bill would hurt the rural communities and small towns and cities that I represent in Congress.

So, I had a choice. I could stand by and issue my reservations and my opposition from the sidelines. Or I could get involved, and stand up for the good people in New Mexico I represent, and advocate for changes that would help people and businesses in my district.

Madam Speaker, anyone who knows me from the oil fields of Hobbs, New Mexico knows one thing: If there's one thing I know, it's hard work. And if there's a job to be done, I'm going to get it done.

The very first thing I saw to in the bill is that there would be no taxes, no additional costs, and no added red tape at the wellhead. I knew we needed to keep this bill away from production because we need more energy in this country, and putting taxes on the folks who produce it makes then produce less energy, not more.

Once I saw that oil and gas producers would not be covered by the legislation, I noted other improvements that had to be made.

The first thing was that portions of the bill threaten to put small refiners out of business. Smaller refiners process below about 200,000 barrels a day, while larger refiners typically process closer to 1.5 million barrels. The difference is drastic. Despite their small size, small refiners still supply about 11 percent of the United States market, serving mainly rural areas and military installations.

The legislation as reported from committee contained only two percent of available allocations for the entire refining sectors stationary emissions, even though refiners emit 3.8 percent of carbon across our economy. Small refiners operate at extraordinarily thin margins and would be fighting for that limited allocation with super-majors like ExxonPhillips, Chevron, and ConocoPhillips. Smaller companies would likely not survive.

If refiners close in rural areas, gas prices there would have to skyrocket in order to attract supplies from the coasts and other refining centers. Thousands of job losses from refinery closings would also result.

To prevent this terrible situation from coming to pass in rural America, I proposed that small refiners receive an allocation for all of their stationary source emissions and further mechanisms that would limit their exposure to the volatility that may exist in the market for allowances for fuels.

I am very pleased that this provision has been included in the bill.

Additionally, I was deeply concerned with the economic livelihood of 180,000 Southern New Mexicans in my Congressional district who get their power from rural electric coops. While the bill's sponsors claim that electric utilities were "held whole" with allowance allocations when the bill was reported out of committee, in reality there were regional disparities that unfairly punished rural electric coops. For example, in regions that possess abundant sources of carbon-neutral electricity like hydro and nuclear, consumers would receive far above their needed allocations. But in New Mexico and other states that rely in large part on coal and other carbon sources for electricity, consumers would only receive a portion of the allowances they need to cover their carbon emissions.

To remedy this problem, I proposed that emission allocations be distributed on the basis of carbon intensity rather than the number of people who receive the electricity and that no utilities should receive more than 100 percent of allocations. Allocations over 100 percent would then be redistributed to consumers in places like New Mexico.

I also proposed the same carbon molecule shouldn't be given allowances twice in its life cycle in one part of the country, while a carbon molecule being used in New Mexico receives zero allocations.

Now, we didn't get everything we asked for. But working with Chairman COLLIN PETERSON of the Agriculture Committee and the National Rural Electric Cooperatives Association, we were able to get language in the bill that will protect rural electric coops from costly rate hikes.

Madam Speaker, this bill is not perfect. In fact, it is far from perfect.

We need to do more for rural coops. We need to improve this bill so that it promotes the use of clean burning natural gas.

I do thank my friends on the Energy and Commerce Committee for working with me to address my concerns regarding small business refiners and rural electric coops.

Mr. JORDAN of Ohio. Madam Speaker, I rise today in opposition to this bill. Simply put, this is bad policy for America, particularly the Midwest. In an independent study, my district is the fourth-most impacted district in the nation by this disastrous legislation. The parts of our nation that are powered by coal-burning plants and are heavy in manufacturing and agriculture—like the part of Ohio I get to represent—will be devastated.

Make no mistake, we are about to vote on the largest tax increase and transfer of wealth in American history. In a misguided attempt by the federal government to put a command and control bureaucracy in charge of our national energy economy, this Congress will raise the energy costs of every American who drives a car or turns on a light switch. And for what? Even supporters of this legislation admit that this bill will have a negligible impact on global temperatures.

By unilaterally disarming ourselves, we become less economically competitive for the 21st century. We are preparing, Madam Speaker, to cede our global leadership role to foreign competitors by capping our growth and innovation, and trading even more manufacturing jobs overseas.

Republicans have a better way forward. We have an all-of-the-above energy solution that increases domestic production and use of our own resources and creates incentives to move us toward clean, renewable, and reliable sources of energy like nuclear, wind, solar, and bio-fuels. And we do it the way America has always done it—through the ingenuity and innovation of the American entrepreneur and worker, not top down federal government mandates. I encourage my colleagues to vote down this National Energy Tax and to support real American energy solutions.

Ms. KILPATRICK of Michigan. Madam

Speaker, I rise in strong support of H.R 2454, the American Clean Energy and Security Act (ACES) of 2009. This long overdue, necessary, and needed step will make the earth a better place, reduce our dependence on foreign oil, by cutting our use of foreign oil by more than five million barrels per day. The cost of this legislation is just 22 to 30 cents per day—less than the price of a postage stamp-or \$80 to \$111 per year, according to the EPA. This bill means more than 1.7 million jobs for our nation, 54,000 for the State of Michigan and 23,000 jobs for the City of Detroit. In order to ensure that we no longer import hundreds of barrels of oil per day, to have cleaner air, cleaner land, cleaner water and a better future for my grandchildren and all children, most, if not all, Americans are willing to make that investment.

This bill represents the largest investment in jobs by our government since the Great Depression. Michigan, and America, must become part of the new technology which is renewable technology. The factories and industries that once built cars and trucks can now build wind turbines, solar panels, and help get our electrical grid more efficient and effective. Replacing our nation's old-fashioned, outdated, outmoded and obsolete fossil fuel based energy production equipment will result in new research, new manufacturing, new energy sources and new jobs. Michigan desperately needs this legislation.

I am blessed to represent the people of the 13th Congressional District of Michigan. The 13th Congressional District of Michigan has the highest percent and number of low income families in the State of Michigan. Contrary to what opponents of this bill say, this bill will not add to the already burdensome pain our citizens have already endured and continue to endure. Among other things, the bill provides \$40 per month to low income families to help offset potential increases in energy. In fact, the Congressional Budget Office (CBO) has estimated that the bill would actually save low income consumers money on their utility bills. The wealthiest twenty percent of American households would only experience modest, affordable rate increases.

This bill will create the largest growth in jobs in the private sector since the Great Depression. According to the Environmental Protection Agency and the Congressional Budget Office, 1.7 million jobs will be created that cannot be resourced to other countries. These are good paying and secure jobs that will restore businesses and bring economic stability to our cities, counties and states. According to the Political Economy Research Institute, Michigan stands to gain 54,000 jobs or 5.4% jobs for every resident in the state. That means 23,000 new jobs in Detroit alone.

This legislation is the work of many Committees and has been carefully crafted to avoid any undue burdens on agriculture and rural families. Farmers spend more money than any other industry on energy, which only underscores the fact that we need new energy policies that will lower their costs and lower their dependence on fuel. This legislation provides farmers and the agricultural industry with unique opportunities to make money in energy, through siting windmills or solar panels on their lands, or growing crops suitable for the production of biofuels. The bill provides assistance to farmers and agricultural businesses as we transition to renewable energy by providing them with free emissions allowances.

This legislation does not force other countries to reduce their emissions. This legislation cannot do that, anyway. It does show the world that the United States is ready to take the lead in the fight against climate change. China and other European countries that have relied on fossil fuels have shown a willingness to start the fight against global warming. This is our opportunity, once again, to be the world leader that we have always been.

The reduction of the greenhouse gases is not only good for our health and our children's health—it sets the nation on a new pathway using Free-Enterprise principles. Polluted air affects our elderly and young people the most. That's why the American Lung Association supports this bill.

This bill is 30 years overdue, if we had started back then, we would not only be much less dependent on foreign oil, but our water, air and earth would be cleaner. For the government to involve itself in the public health, the economy and national security is the oldest role of the government in the United States. This partnership of the government in these goals has added to the quality of the life we enjoy.

We have the opportunity, and I will say the responsibility to grow jobs in Detroit, Michigan and America. We have a duty to promote renewable energy, clean the air, clean the

water, clean the earth and deal with climate change. The nation that leads the effort toward clean and renewable energy will not only make our world a better place for our children, our grandchildren, and our families, but it will lead the world economy for the next hundred for H.R. 2454, the American Clean Energy and Security Act of 2009.

Ms. HERSETH SANDLIN. Madam Speaker, today the House is voting on a bill that is designed to shape the course of our nation's economy and way of life for decades to come. Unfortunately, I believe the process has been too rushed, and I cannot support the bill in its current form.

I believe it's imperative for Congress to address climate change. I agree with the scientific consensus that human activity has substantially increased the accumulation of greenhouse gases and is contributing to a rise in average global temperature. This rise threatens to create a number of dramatic and negative impacts. With much of South Dakota's economy dependent on agriculture, which in turn depends on our climate, global warming could have a profound effect on South Dakota's economy and our way of life.

Moreover, the alternative to no action by Congress is action by the U.S. Environmental Protection Agency (EPA) under the Clean Air Act to step in and in a more punitive fashion dictate rules and impose costs on industry. Given the complexity both of the climate change problem and the steps needed to address it, we need to take time to get it right. The stakes are simply too high for a rushed solution that can potentially create more problems than it solves.

While I can't support the bill before the House today, it has already come a long way from where it started both in its discussion draft form and in the form the Energy and Commerce Committee approved. Both of those versions were imperfect and incomplete and would have imposed regional inequities on a greater scale than the legislation before the House today. Since the committee approved its version of the bill, there have been some positive changes made, most notably in the agricultural sector.

Important and common sense improvements have been made that go a long way towards recognizing the value that agricultural producers in South Dakota can bring to the climate change issue. I commend Agriculture Committee Chairman PETERSON'S efforts as he worked together with many members of the Agriculture Committee to ensure that agriculture's concerns are addressed in this legislation. This has been a priority for me over a long period of time, and I am pleased with the progress made.

The inclusion of an agricultural and forestry offsets program will enable farmers, ranchers and forest owners to fully participate in a market-based carbon offset program, earning income for activities they undertake to address global climate change while also ensuring environmental integrity and protecting early actors. Importantly, these provisions put the U.S. Department of Agriculture (USDA), not the EPA, in charge of regulating the use of farm and forestry projects intended to offset carbon dioxide emissions from industrial sources. The EPA itself has estimated that agricultural and forest lands currently sequester approximately 12 percent of our nation's carbon emissions

and that the agriculture and forest sectors can sequester up to 25 percent of emissions. As such, the agriculture and forestry industries must play an essential role in efforts to mitigate climate change.

I am pleased that the manager's amendment also corrects the controversial and unproven methods for calculating indirect emissions through the lifecycle greenhouse gas analysis for biofuels. EPA's current indirect land use proposal would be put on hold for five years pending a needed scientific study and consultation with federal agencies and Congress. Importantly, USDA, the Energy Department or EPA could veto the results of the study if it is not based on sound, peer-reviewed science. The bill also makes it very clear that agriculture and forestry sectors will be exempt from the greenhouse gas emission reduction requirements.

Lastly, this bill ensures that Wall Street speculators will not be able to further drive up energy costs through dark market and secretive trading of derivatives of carbon allowances, offset credits, or renewable electricity credits by requiring that all carbon derivatives trading is conducted only on Commodity Futures Trading Commission-regulated markets.

However, while I am supportive of many of the changes made to the bill that stand to benefit agriculture, serious substantive and process concerns remain when it comes to doing right by rural America. The following represent some of my concerns.

I have heard from several utilities serving South Dakota, such as Black Hills Corporation, which serves tens of thousands of South Dakotans, that the allowances for emissions in the bill still aren't fairly distributed and this disparity could mean dramatic rate hikes for its customers in South Dakota.

Additionally, the bill does not adequately fix the flawed definition of renewable biomass in the Renewable Fuels Standard (RFS) or in the proposed Renewable Electricity Standard (RES). Again, the definition of biomass has improved greatly from the highly restrictive definition included in the discussion draft. However, the flawed definition used in the final bill before the House today unnecessarily and unwisely excludes much federally-sourced biomass from counting toward the RFS and a new RES. It also overlooks the essential role forests can and should play in sustainably generating renewable energy, ensuring our nation meets the cellulosic biofuels mandate in the RFS, moving our nation toward energy independence, and creating jobs in rural communities across the nation. I continue to believe strongly that we can take advantage of this amazing potential within the existing protections provided under current environmental laws and responsible forest management pol-

I have worked for nearly two years to broaden the biomass definition to allow for federally-sourced biomass to count toward the RFS and have urged its inclusion in this legislation, as well as the application of this definition to the RES. Overall, a federal RES presents tremendous economic opportunities for South Dakota in large part because of our state's tremendous wind potential. That is why I was a strong supporter of including an RES in the 2007 Energy Bill, and helped generate support for the RES Amendment when it passed the House. An RES has the potential to create

thousands of jobs and generate economic development all across South Dakota, for farmers, ranchers, and rural communities, as well as our sovereign Native American tribes. And much of what is in the RES in this bill presents great opportunity for South Dakota.

However, the definition of biomass added in the manager's amendment is still flawed. I am concerned with the "harvested in environmentally sustainable quantities" requirement, which I think invites new analysis, appeals and/or litigation about biomass in general, but more specifically, about trees that have been killed by fires or insect epidemics. Likewise, I'm concerned with the "old growth" and "latesuccessional" forest stands restriction because there is no generally accepted definition of either term, and the bill doesn't define either term. So, that would leave an avenue open for challenges, and would leave uncertainty about supply for potential investors. These are some but not all of my concerns regarding the biomass provisions included in the manager's amendment. I hope they will be addressed during the remainder of the legislative proc-

Underlying these specific policy concerns are serious concerns about the rushed process for such an important and consequential bill. This bill is intended to help guide the economic future of our nation for decades and I think the process of fixing the bill since it's been approved by the committee has been too rushed, and has raised too many questions about whether the concerns of rural America are adequately addressed. Therefore, I will vote against this bill, but I hope that the legislative process will address these concerns, and ultimately, a bill can be presented to the House that treats South Dakota and rural America fairly as it moves the nation toward the new energy economy and addresses the real threat of climate change for our nation's future

Mr. ETHERIDGE. Madam Speaker, I rise reluctantly to speak on H.R. 2456, the American Clean Energy and Security Act of 2009.

This is not a perfect bill, and I will work for its improvement before it comes back here for another vote.

However, one thing is clear to most Americans: the time for action is now. Last summer we had gas prices that hit more than \$4 per gallon. Last winter some folks could not afford to heat their homes. We need to start a clean energy economy that will reduce our dependence on foreign oil and position America as a leader in a new technological industry.

America has traditionally been a global leader in innovation and economic growth, and this legislation takes a first step to get America running on new energy technologies. We have the technology and the research infrastructure to create new ideas. We have talented people ready to go to work. And we certainly need the jobs, especially in North Carolina. This bill will put people to work creating the industries of the 21st Century.

We have seen that our current energy policy is not working. By doing nothing, or delaying action, we risk further crippling our economy. That is not a risk we can afford. We will continue to use oil, coal and natural gas, solar, wind, hydroelectric, and nuclear, but should also create new sources of energy and develop efficient technologies. We need to start an energy economy today, with a policy of "all

of the above."

This is an economic imperative, to create jobs and to prevent spikes in energy costs. This is a national security priority, to reduce our dependence on foreign oil and to keep the hundreds of billions of dollars we send overseas here at home. This is a competitiveness issue, to make America a leader in an emerging industry and promote research and development here in the U.S.A.

North Carolina has always been a leader in technology, and has the potential to meet America's energy needs through our agricultural strength. Moving forward towards a clean energy economy will be a boon for North Carolinians and the whole country.

This is not a perfect bill. It contains some protections for low and moderate income families, but does not do enough for the middle class. It makes some efforts to prevent regional price differences, but does not do enough to recognize the investments North Carolina's rate payers have already made. It takes some steps to establish goals for international climate negotiations and to ensure that the United States is not placed at a competitive disadvantage, but it should do more to protect American companies if we take responsible action and other nations do not.

I will reserve the right to work to improve this bill to improve its consumer relief provisions, promote regional fairness, and ensure that our businesses have a level playing field with their international competitors. But I will vote for this bill today to move us forward into the future that America needs and deserves.

Mr. MOORE of Kansas. Madam Speaker, I commend Chairman WAXMAN and Chairman MARKEY for crafting this truly historic energy legislation that will help our country make the transition to a new, clean energy economy.

I want to also thank Chairman Waxman for including a bill I drafted, H.R. 2246, in the manager's amendment. This bipartisan legislation, which I introduced with my friend from Illinois, Congresswoman JUDY BIGGERT, will establish the Community Building Code Administration Grant, or CBCAG, Program.

This competitive grant program will help with local building code enforcement by authorizing \$100 million over 5 years, capping awards at \$1 million per recipient, and requiring recipients to match a portion of funds received.

Much attention has been focused on the huge energy savings that can be achieved by increased energy efficiency in buildings, which consume nearly 40 percent of all energy and 70 percent of the electricity produced in the U.S.

But building codes don't make a difference unless they are enforced by local code officials who are properly trained and have sufficient resources to inspect buildings for compliance. It will save taxpayer dollars as well—according to a study conducted by the National Institute of Building Sciences, for every \$1 spent on mitigation saves \$4 in future disaster assistance.

H.R. 2246 is supported by the International Code Council, the Alliance to Save Energy and many other organizations. Again, I'm pleased my legislation has been incorporated into the manager's amendment to the American Clean Energy and Security Act.

I support the underlying bill and urge members to vote in favor of passage. But, I also strongly urge Chairman WAXMAN and Leadership to strengthen the Renewable Electricity Standard (R.E.S.) during the Conference Committee.

I commend Chairman WAXMAN and Chairman MARKEY for crafting this truly historic energy legislation that will help our country make the transition to a new clean energy economy.

The strong R.E.S. that we started with has unfortunately been watered down so significantly that it will not even provide an incentive to maintain current levels of renewable deployment.

Kansas utilities, like those of so many other states, are on track to cost-effectively meet a state R.E.S. of 10 percent by 2011. A federal goal of 6 percent by 2012 would provide no incentive for new investments in wind development or manufacturing.

That means that more jobs will be left on the table and that the U.S. will continue to lag behind the 37 countries around the world that have a binding, long-term commitment to renewable energy development.

The global marketplace is watching us. Companies both here and abroad are waiting to see if we enact an R.E.S. that will provide a true commitment to transitioning our economy to cleaner forms of energy.

They are making critical decisions on whether and where to build new manufacturing facilities or retool their companies to create new, high-quality jobs.

We can decide right now if we are going to build more of the new energy components right here in the United States or continue to import them from overseas.

Kansas is thrilled that Siemens chose to build nacelles for wind turbines in Hutchinson, creating 400 jobs in one small town and supply chain opportunities for hundreds of companies in the region. Several recent reports project job growth in the tens of thousands in our industrial heartland if we make a real commitment to renewable energy.

A stronger national R.E.S. is the most important policy tool we have to make sure new energy projects utilize American-made components manufactured by American workers.

Harnessing renewable energy also builds our rural communities—this "new crop" sustains farmers and ranchers and keeps the schools, clinics, roads and services strong in America's small towns.

A stronger national R.E.S. would also benefit consumers by holding down energy prices and protecting them against the price spikes of fossil fuels by promoting fuel diversity.

In fact, numerous independent studies have shown that the R.E.S. saves consumers money on their energy bills in all regions of the country.

In addition, a strong national R.E.S. will ensure that currently available clean technology is deployed quickly to help achieve greater emission reductions in the future at a lower cost.

And perhaps most importantly, Americans are demanding bold policies that will push our country in a new direction on energy and ensure a clean, secure energy future for America

In April a national poll found that 75 percent of Third District residents support a R.E.S. of 25 percent by 2025. This support is strong across all counties of my state and throughout all regions of the country.

That is why I urge Chairman WAXMAN and House Leadership to strengthen the R.E.S. as this legislation moves forward.

Ms. MARKEY of Colorado. Madam Speaker, I rise today in support of the transmission

siting section of the manager's amendment to the American Clean Energy and Security Act of 2009. Yesterday, Congressman INSLEE and I offered this amendment to strengthen siting authority within the Western Interconnection, which extends from Colorado to the west coast.

My home state of Colorado has enormous renewable energy potential, but our outdated transmission infrastructure is inadequate to bring these resources to where they are needed. According to the Renewable Resource Generation Development Areas Task Force, Colorado has eight potential high concentration wind development areas and two potential high concentration solar development areas capable of generating more than 96 GW and 26 GW of energy, respectively. These estimates show that Colorado is more than able to generate excess renewable electricity for export to other states, and does not take into account smaller scale projects or distributed generation.

For western states like Colorado, the renewable energy potential is there, but the areas with the best wind and solar resources are often in remote areas that lack adequate transmission lines to transport the energy to where it is needed. As I travel to the Eastern Plains of Colorado, the landowners often tell me they are more than willing for wind and solar developers to install wind turbines and solar panels on their property, because for them it is an economic development tool. Ranchers can receive compensation by putting wind turbines on their land and their cattle can still graze under the towers.

Our current transmission system has evolved from local demands without an integrated national plan. Implementation of interstate transmission lines requires coordinating the regulatory permitting processes in each of the individual states and localities that the line will traverse. Our amendment builds upon the existing regional planning section of the American Clean Energy and Security Act and adds a siting plan for the Western Interconnection. This siting plan gives the Federal Energy Regulatory Commission backstop siting authority to ensure the construction of high-priority interstate transmission lines. Self identified regional planning entities will build a national transmission plan from the bottom up and with higher priority given to meet the demand of deploying renewable electricity generation projects. Our amendment will give ample deference to states and will encourage state and local participation throughout the planning and siting process.

In addition to the Inslee/Markey transmission siting amendment, I would like to express my strong support of Chairman PETERSON's agriculture amendment. My district in eastern Colorado contains some of the best agricultural land in Colorado. Weld County, in the 4th CD, is the number one ranking county in the state for agricultural products sold and eighth in the nation. I worked hard with my colleagues on the Agriculture committee to ensure that Colorado's farmers and ranchers will be able to benefit from the programs in this legislation.

I support authorizing the Secretary of Agriculture to carry out the agriculture and forestry related offsets programs in Title V of the American Clean Energy and Security Act. The United States Department of Agriculture conservation programs and the Department's ex-

tensive knowledge of optimizing agricultural practices leave them well poised to establish measurable and reliable offsets. Furthermore, the multitude of USDA offices near likely offset projects leave the Department in a better position to provide regulatory and technical assistance to farmers and ranchers.

Finally, I would like to express my support of amending the definition of renewable biomass in the renewable electricity standard and the renewable fuels standard of the Energy Independence and Security Act of 2007 to include infested trees removed from public lands. The Forest Service expects this bark beetle outbreak will kill most of the mature lodgepole pines covering 2.2 million acres in Colorado and southern Wyoming within the next 5 years. Some estimates indicate almost 2 million acres the have already been decimated. While it is not our intention to incentivize unnecessary cutting in our public lands, work is already being done in our public lands to remove trees killed by bark beetles to reduce the threat of wildfires and preserve forest health. We should utilize this available

We have an opportunity to be smarter about the way we create and use energy. By utilizing the great renewable electricity potential in the west, we can invest in our future and put Americans back to work.

Mr. FATTAH. Madam Speaker, I thank you for allowing me the time to speak on this topic of paramount importance. Climate change and the problem of rising carbon emissions is one of the most important public policy quandaries that the nation currently faces. Congress needs to take the lead in helping to solve this issue. Therefore, I implore my fellow members of Congress to vote yes and help pass the American Clean Energy and Security Act, H.R. 2454.

As you well know, H.R. 2454 is a broad-based bill that includes a number of initiatives on clean energy, economic development, and climate change. Taken together, these initiatives will create the national policy framework and all important funding streams that are needed to adequately tackle the threat posed by rising carbon emissions.

Moreover, the incentives contained within H.R. 2454 will help strengthen and support those emerging renewable energy industries to help create jobs that will enable millions of Americans to get back to work. I know that these jobs will be created because I have already seen it happening in my home state of Pennsylvania. I have seen the jobs created by the wind and solar manufactures, and I have spoken to the leaders of local Philadelphia business who have told me how important the clean energy industry is to the Philadelphia region.

Moreover, I have read the studies that show how many jobs will be created if Congress passes H.R. 2454. For example, in a 2008 report published by the Clean Air Council entitled "Job Opportunities for the Green Economy," it was estimated that over 533,000 jobs in Pennsylvania alone will see growth or wage increases by putting global energy solutions to work. As the world moves into a less carbon intensive future, these new industries will allow the country to thrive as they become the new economic engines that power future growth.

I believe that our nation needs a comprehensive energy strategy that makes our nation more energy efficient, decreases our reliance on foreign oil, creates jobs, and helps prevent increases in carbon emissions. I am not alone in my beliefs. People throughout the nation want Congress to get moving on reducing carbon emissions. These Americans understand that climate change is one of the most important issues that face the nation today. They understand that the rapidly changing climate that is due to rising carbon emissions is having a profound impact on the nation's forests, coastal areas, drinking water, and other important ecosystems that human beings rely on.

Therefore, I implore my fellow members of Congress to pass the American Clean Energy and Security Act. Help put our nation on track to a cleaner energy future.

Mr. OLSON. Madam Speaker, this Democratic cap-and-tax plan is simply a shell game designed to funnel billions of taxpayer and industry dollars through government to fund their restrictive energy plan. Faced with an outcry over the impact their plan will have on family budgets, Democrats have tried to buy off opposition by offering "rebates" to help offset increased costs.

Let's be clear, this rebate is nothing more than the government giving you your own money back. It is typical Washington: steal your wallet, and pat themself on the back for giving you back the spare change. And let's not forget the fundamental failure of this job-killing plan—it doesn't even reduce carbon emissions.

According to analysis from the Heritage Foundation, hard working folks in my congressional district alone will lose nearly 5,000 jobs in 2012 alone. That is just one year of job losses in one district and the numbers only go up from there. And the average household in Texas could pay an additional \$1,136 for household goods and services over a given year.

My office has received 680 calls this week on cap-and-tax and 671 of them strongly urged me to oppose this bill. In these times of economic hardship, Congress must be focused on creating and maintaining jobs. My Democratic colleagues who are advocating for this legislation tout the fact that more "green" jobs will be created by this job.

What they fail to mention is that good paying jobs that already exist in this country will be shipped overseas and our national unemployment rate will increase. We have already seen this happen in Spain, where a study found that for every one green job created two other jobs were lost. I do not want this for my constituents, I do not want this for the businesses in the 22nd District of Texas, and I do not want this for the American people.

Madam Speaker, this is simply a scheme to restrict needed energy and decide who is worthy of working in which government approved energy job. That is not the role of government and Americans should be outraged. The stimulus plan was designed to create jobs through billions and billions of tax dollars. It has not created the jobs it promised and this energy shell game will not work either.

Mr. TIAHRT. Madam Speaker, I heard of a climatologist who went to apply for a job recently. During his interview, he was asked, "What do you predict will happen with the earth's climate next year'?" He immediately replied, "Whatever you want me to predict."

Unfortunately, this joke seems to hit a little too close to home, when we are considering

global warming legislation. Rather than responding to serious questions with serious answers, Congress is replying with what we think people want to hear. Rather than considering all angles before offering a solution, Congress is rushing through legislation in hopes to score points with voters back home. And instead of basing a bill on sound scientific data, we will be considering legislation that is devoid of input from this side of the aisle.

I rise today to express my strong opposition to Waxman-Markey "cap and tax" bill. I believe there are three interrelated problems with this misguided legislation. I am concerned with the process by which we have arrived at the point we are today. I am concerned with the political showmanship that has gone on as the bill was written. And I am concerned with the policy itself, which bears the tragic scars of both the process and the politics.

Madam Speaker, from the beginning of the 111th Congress to the present, the cap-andtax bill has been subjected to unfortunate abuses of the legislative process. In April, the Energy and Commerce Committee held four days of hearings, with the intention of, according to the Committee's website, "examine the views of the Administration and a broad range of stakeholders." on a discussion draft of Chairman WAXMAN's bill. However, these hearings reflected only the Chairman's perspective. Only four of the twenty-one witnesses called before the Committee expressed any opposition to cap-and-tax, despite a petition signed by more than thirty thousand meteorologists, climatologists, and other scientists stating their skepticism about the evidence of man-made greenhouse gases being responsible for increases in the earth's temperature. Contrary to claims made by the Committee, and witnesses at the hearing, there is no "overwhelming consensus" in favor of the hypothesis of humancaused global warming. There was also a report issued by Republicans on the Senate Environment and Public Works Committee outlining the dissent views of more than 700 scientists opposing the idea of manmade global warming. Clearly, no consensus has been reached.

Madam Speaker, This bill was drafted without input from our side of the aisle. At no point was any Republican consulted regarding the contents of the bill. In the rush to get the legislation passed through Committee, it seems no one had time to read the entire bill, or figure out what it means. Committee members repeatedly asked questions regarding the potential cost of particular provisions or amendments, but received no answers.

All of this raises the question, "why"? Why was the bill rushed through the Committee, With hardly enough time to read it, let alone determine the impact that it would have on American taxpayers, farms, and businesses? The only answer I can come up with is the desire on the part of some in this body to score points with their voters back home.

Which brings me to the third problem with Chairman WAXMAN's cap and tax bill—its just bad policy. Earlier this week, Investor's Business Daily had a front page article about the failures of Europe's program, called the Emissions Trading Scheme, or ETS. The article cites numerous studies finding that the ETS has significantly increased energy prices, "with funcertain' effects on greenhouse gas emissions." That hardly sounds like a model of success that we should be emulating here in the United States.

Proponents of the cap and tax bill claim that they have learned from Europe's mistakes, but I disagree, Madam Speaker. The article identifies the giving away of the program's carbon allowances as the largest reason for the program's failure. This bill follows that same model, giving away roughly 85 percent of the emissions allowances.

The entire idea of a cap and trade program fails in practice. We are told, "The cost of polluting will be paid by the polluters." And believe me, the authors of this bill expect them to pay a hefty price. In fact, President Obama's budget assumes that even with the sale of only 15 percent of the total emissions permits, the federal government will still take in more than \$650 billion. As the cap gets lower, and there are fewer permits available, the cost for "polluters" is going to grow ever higher. But that is exactly what the authors want. President Obama recently stated that the only way for a cap-and-trade system to work is for energy prices to "skyrocket."

There is nothing in the bill to keep the "polluters" from passing those skyrocketing costs on to the consumers. In fact, they will be forced to so. Any business that cannot pass the costs on to consumers runs the risk of being driven out of business. In the end, it will be the American taxpayer that foots the bill for this program, in the form of higher prices at the pump, higher home energy bills, and lost economic growth. But don't just take my word for it. Even the director of the Congressional Budget Office has said that, "under a cap-and-trade program, consumers would ultimately bear most of the costs of emission reductions."

One analysis of this bill found that if the standards within the bill are met, by 2035 Americans will see gas prices rise 74 percent, electricity prices increase by 90 percent, and a loss of at least 850,000 jobs every year. The average American household will see its annual energy bill go up by nearly \$1,500. For my home state of Kansas in particular, we are going to have to purchase an estimated \$206.8 million worth of carbon credits. That is \$206 million more that Kansans are going to have to pay in energy costs every year. My district will be particularly hard-hit, as estimates show my district standing to lose nearly half a billion dollars of production in 2012, and more than 5,000 non-agriculture jobs. It's this kind of economic pain that advocates are counting on to force a reduction in carbon emissions

The European system proves this idea doesnt work. With no signs of a reduction in carbon emissions, Europeans have seen their household energy costs rise by 16%, and the industrial energy costs increase by 32%.

Spain is an especially poignant example of the failure of the European system. They committed to reaching the benchmarks set out by the Kyoto Protocol, with renewable energy standards, so-called green-collar jobs, and a commitment to reduce their carbon emission levels. But the high cost of energy in Spain has destroyed their economy, which is currently facing a 17.5% unemployment rate. Proponents of this bill say that we will be creating new, green jobs. But most of these jobs are temporary construction jobs that go away once facilities, like wind farms for example, are built. In Spain, for every 4 jobs that were created, 9 were lost due to the higher cost of doing business under the Emissions Scheme. We should avoid going down this same path.

There is huge potential for exploitation of the system, on multiple levels. Especially with permits being given out, rather than auctioned, government officials are in a prime position to divert additional credits towards industries or companies of their choice. There is also the possibility that utilities here in the United States could follow the lead of one European company that immediately raised their rate by 70%, explaining to customers that the rate hike was necessary to cover the costs of capand-trade. But this utility company was given more credits than it needed, and sold them on the open market.

Tack on a renewables standard to this bill, and we have the perfect recipe for failure. No place that has implemented a renewable standard has ever been able to meet the required levels. And there is little to indicate that a federal standard would be any different. As a 2008 article in the Energy Law Journal stated, "The DOE has little, if any, experience in administering a program on the scale of a national RPS, and has shown no indication that enforcement of a major program is within the agency's capabilities...[this is] an area in which the DOE has already failed to show effective leadership."

So what we have here is a bill that has been rammed through with no minority input, to create a system that is ripe for abuse, costs the American taxpayer thousands of dollars, cripples our businesses, and in the end, has no measureable result. This is a bill I cannot support, and urge my colleagues to reject as well. Instead, I would encourage my colleagues to join me in supporting the American Energy Act, a comprehensive energy bill that increases access to domestic energy sources, encourages conservation, and promotes the increased use of renewable sources of energy.

Across this country, we are, once again, seeing gas prices rise. Since the beginning of the year, gas prices are up 60 cents, and crude oil has raised more than \$20 a barrel, with no end in sight. Just last week, Russian oil executives predicted that crude prices could reach \$250 per barrel.

It is possible for us to relieve some of this pressure by tapping into our own vast resources. The Department of Energy estimates that nearly 20 billion barrels of recoverable oil lie offshore beneath restricted waters, the equivalent to nearly 30 years worth of current imports from Saudi Arabia. Substantial offshore natural gas reserves are also restricted. Even though longstanding restrictions on offshore energy production were lifted last year, the process of leasing these areas falls under the jurisdiction of the Department of the Interior.

Unfortunately, new Secretary of the Interior Ken Salazar refuses to allow additional drilling permits, dredging up every excuse not to produce energy in these areas. The Alaskan National Wildlife Refuge, reported to hold more than 10 billion barrels of oil continues to remain off-limits. He has also sought to block progress on oil shale, a promising source of oil trapped in rock under parts of Colorado, Utah, and Wyoming. The Department of the Interior has even cancelled some existing oil and gas leases.

Often, environmental concerns are cited as the reason for opposing additional drilling. However, technological advances have greatly increased the safety of drilling. During hurricanes Rita and Katrina, less than one cup of oil was spilled in the Gulf of Mexico, despite damage to more than 120 drilling platforms. There is absolutely no reason why permits for additional drilling should be denied. Furthermore, revenue generated by these oil leases will be invested in the development of cleaner, alternative sources of energy. The end result is a reduced dependency on foreign oil, lower levels of pollution, and new jobs for Americans, all without crippling our economy.

Lastly, Madam Speaker, the American Energy Act includes one key source that could provide clean energy without emissions nuclear power. The Department of Energy has stated that the best way for energy companies to reduce their carbon emissions is to increase their use of nuclear energy. Despite encouragement from DoE, and the fact that that it has been proven safe by countries like France, where more than 80% of their electricity is generated by nuclear power, the Waxman-Markey bill does nothing to encourage nuclear power.

Instead, this administration has begun to walk away from the hundreds of millions of dollars spent on the nuclear storage facility at Yucca Mountain, Nevada. The American Energy Act would provide the Nuclear Regulatory Commission authority to complete its review of the Yucca Mountain facility, repeal the limitations on Yucca's Mountain's storage capacity, and establishes a method for recycling spent nuclear fuel in the U.S. Furthermore, it would reduce the bureaucratic hoops and length of time required to receive a permit for the construction of new nuclear plants.

In conclusion, let me again encourage my colleagues to join me in rejecting the Waxman-Markey cap-and-tax bill that would cripple our economy, without addressing their environmental concerns. Instead, lets support the American Energy Act, which provides real solutions for our energy problems in an economically, and environmentally sound manner.

Mr. BURTON of Indiana. Madam Speaker, if this energy tax passes, the estimated job loss or my district is an average of 3,702 jobs per year from 2012 through 2035. If this bill passes it will mean financial ruin for thousands of my constituents.

5th CD Gross State Product Loss for 2012: \$361.7 million

5th CD Gross State Product Loss on average from 2012–2035: \$720.1 million

5th CD Personal Income Loss in 2012: \$458.7 million

\$458.7 million 5th CD Personal Income Loss on average

from 2012–2035: \$265.7 million 5th CD Non-farm Job Loss in 2012: 4,552

5th CD Non-farm Job Loss in 2012: 4,552 5th CD Non-farm Job Loss on average from 2012–2035: 3.702

THE CONSEQUENCES OF CAP AND TAX

Over 1,200 pages long, H.R. 2454 contains four sections outlining mandates for renewable energy, mandates for energy efficiency, a capand-tax proposal, and a "transitioning" section focused on forestalling expected job loss.

HIGHER ENERGY PRICES

Every consumer will pay for this both directly and indirectly.

Independent researchers, CBO, and the President all agree that this cost will be passed to consumers.

every provision in the bill either increases the cost of energy directly or tried to keep it from increasing too much.

Example: new federal renewable electricity standard that would likely cause electricity prices to spike.

This is the ultimate regressive consumption tax to the tune of nearly \$3,000 per year according to the Heritage Foundation.

The costs per family for the whole energy tax aggregated from 2012 to 2035 are estimated to be \$71,493.

FEWER JOBS

Yesterday in the Rose Garden, President Obama said that Cap-and-Trade was a "jobs bill." Yet many studies reports rampant job loss through the year 2035.

A national energy tax would undoubtedly outsource millions of manufacturing jobs to countries such as China and India.

According to the independent Charles River Associates International, H.R. 2454 would result in a "net reduction in U.S. employment of 2.3 million to 2.7 million jobs each year of the policy through 2030," even after the "creation" of new green jobs.

Green Jobs Are a Proven Failure: According to a recent study that reviewed the impact of "green jobs" in Spain, the U.S. can expect 2.2 jobs to be destroyed for every 1 renewable job financed by the government. Only 1 in 10 of the jobs actually created through green investment is permanent, and since 2000, Spain has spent 753,778 U.S. dollars to create each "green job," including subsidies of more than \$1,319,783 per wind industry job.

GOVERNMENT MANDATES AND INTERVENTION

This includes new federal mandates on everything from outdoor light bulbs and table lamps to water dispensers, commercial hot food cabinets, and Jacuzzis.

Establishes a myriad of new federal agencies intertwined between at least 21 established agencies with the mission of reallocating trillions of taxpayer dollars. According the U.S. Chamber of Commerce, the bill will impose 397 new federal regulations that require traditional agency rulemakings.

The bill transfers wealth from rural areas to cities. States like California, Washington, and New Jersey would receive more emission credits than they need, enabling them to sell surplus credits to smaller facilities in states like Ohio that receive maybe half of the credits they need—making the rich, richer, and the poor, poorer.

The bill would also increase the demand for electricity (to fuel plug-in vehicles via new hybrid incentives) at the same time as the other portions of the bill cause consumer electricity costs to spike.

Although the bill includes "free" allowances for some sectors, economists agree that even if 100 percent of the industry's emissions were initially covered by free allocations, the bill's declining carbon cap will force higher and higher costs onto the American public.

According to the Heritage Foundation, by 2035 this legislation would:

Reduce aggregate gross GDP by \$9.4 tril-

Raise electricity rates 90 percent;

Raise gasoline prices by 58 percent:

Raise residential natural gas prices by 55 percent; and

Increase inflation-adjusted federal debt by 26 percent, or \$28,728 additional federal debt per person, again after adjusting for inflation.

Furthermore, a recent poll shows that 78 percent of individuals questioned said that a \$50 increase in monthly utility bills would be a hardship.

58 percent of respondents say that they are unwilling to pay any more than they currently pay for electricity to combat climate change.

To that end, one-half of those polled oppose enacting a carbon tax to fund energy research (up from 31 percent in 2007).

In addition, the bill:

Creates a Derivatives Market for Companies like AIG: Companies like AIG and ENRON will be participating in a new derivatives market that is much more volatile than housing or natural gas. This new unregulated derivatives market will be more perilous for companies like these than the traditional ones that got them into trouble in the first place. In addition, since the created artificial market contains no transparency, it is more likely to attract traders intent on imposing Ponzi schemes in the same spirit of Bernie Madoff and swindle thousands of Americans.

Devastates Rural America: Rural households spend 58% more on fuel than urban residents as a percentage of their income. The Heritage Foundation estimates farm income will drop by \$50 billion by 2035.

Concedes to the Competition: Currently, China accounts for 85% of global growth in coal each year and is the world's largest annual emitter of greenhouse gases. China's energy usage rose by 7.2% last year and they are building approximately two coal fired power plants per week to keep up with demand. Recently, at a U.N. conference, the Chinese government's advisory panel on climate change asserted that the cap and tax targets were too low by stating Given that, it is natural for China to have some increase in its emissions, so it is not possible for China in that context to accept a binding or compulsory target. In addition, India will not agree to any cap on their total energy production, and many believe India will double their coal-fired-capacity by 2030.

Discriminates Against Developing Nations: The bill creates a new program under USAID to provide U.S. foreign aid to developing countries for their efforts to adapt to climate change. Essentially, the bill is sending tax-payer funds to encourage third world nations to not develop carbon emitting energy sources keeping them at a competitive disadvantage from developed nations for even more decades to come.

Establishes an Unrealistic Renewable Energy Standard (RES): "Cap and tax" does not take into account the fact that additional hydropower, nuclear and advanced fossil coal power plants cannot be deployed quickly enough to meet expected growth in electricity demand while also dramatically reducing greenhouse gas (GHG) emissions. Since renewable technology accounts for a small percentage of energy demand, consumers can expect not only higher rates, but more transmission problems during peak hours of demand. Additionally, the bill preempts at least 23 state renewable electricity standards.

Includes Davis-Bacon: "Cap and tax" expands Davis-Bacon prevailing wage requirements to many provisions of the bill. This policy has been shown to increase public construction costs by anywhere from 5 to 38 percent above projected costs for the same project in the private sector.

Groups Scoring as a Key Vote: 60 Plus Association, Americans for Prosperity, Americans for Tax Reform (double-rating), Citizens Against Government Waste, Club for Growth, FreedomWorks, Independent Petroleum Association of America, National Association of

Manufacturers, National Association of Wholesaler-Distributors, National Cattleman Beef Association, National Federation of Independent Businesses, National Taxpayers Union, Small Business & Entrepreneurship Council (SBE Council).

Mr. PAULSEN. Madam Speaker, it must be a priority to work aggressively and prudently as a nation to cut greenhouse gas emissions. However, I believe we can do this without the current "cap and trade" plan we are voting on today.

Reducing emissions and strengthening our environment are important priorities—priorities I support. However, the "cap and trade" bill before us today is just a fancy way of masking "tax and spend"—and it is the wrong approach to addressing this issue.

America needs a comprehensive energy solution to reduce our dependence on foreign oil and jump-start our economy, but it should not be at the expense of every American taxpayer.

Analysis shows cap and trade will raise gas prices, raise electricity prices and eliminate American jobs. Studies have shown up to 2.5 million jobs will be lost, making America less globally competitive.

In the worst recession in over 70 years, this legislation would exacerbate our situation by increasing energy costs for every sector of our economy. If the priority is jobs, it is stunning to me that we're bringing this bill to the floor that will create a national energy tax on every working family and every small business in America.

There are several common sense, bipartisan solutions that invest in new, clean and reliable sources of energy. I'm supporting a plan that aggressively reduces emissions, promotes conservation, creates jobs and strengthens our environment by promoting nuclear energy—a zero emissions, renewable source. It also boosts domestic supplies of both natural gas and oil.

I hope today that we do what is right for America, by voting down this cap and trade proposal and moving forward with a plan that will work for—not against—all Americans.

Mr. OBERSTAR. Madam Speaker, I rise today in support of H.R. 2454, the "American Clean Energy and Security Act of 2009".

This bill seeks to promote clean energy use and reduce carbon emissions in the United States. The legislation will create millions of new clean energy jobs, enhance America's energy independence, and protect the environment. Additionally, this bill recognizes the important role that transportation plays in addressing global climate change, and I am pleased that the Committee on Energy and Commerce has worked in concert with the Committee on Transportation and Infrastructure in crafting key provisions of this bill.

According to the U.S. Environmental Protection Agency (EPA), nearly 30 percent of the total greenhouse gas emissions produced by the United States comes from the transportation sector, second only to electricity generation. The U.S. Department of Energy (DOE) reports that the carbon dioxide emissions from the transportation sector grew 25.4 percent between 1990 and 2006, an average of 1.4 percent each year. The most recent DOE data show that transportation produces more metric tons of energy-related carbon dioxide than the residential and commercial sectors, and almost as much as the industrial sector.

Nearly all of these transportation-related emissions come from the use of petroleum products. The transportation sector accounts for 68 percent of the total U.S. petroleum consumption; Americans used almost 14 million barrels of oil each day for transportation purposes in 2006. According to the Federal Highway Administration (FHWA), the amount of miles Americans drive each year has grown three times faster than the U.S. population, and almost twice as fast as vehicle registrations. Private vehicles are now the largest contributor to household "carbon footprints"accounting for 55 percent of carbon emissions from U.S. households. Federal policies over the last 50 years, however, have done little to address the growing problem of greenhouse gas emissions.

A February 2008 report by ICF International released by the American Public Transportation Association found that a person who switches a 20-mile round trip commute alone from car to existing public transportation, can reduce his or her annual carbon dioxide emissions by 4,800 pounds per year. This dramatic energy savings is equal to a 10 percent reduction in all greenhouse gas emissions produced by a typical two-adult, two-car household. Furthermore, if Americans used public transit at the same rate as Europeans-for roughly 10 percent of their daily travel needs-the United States could reduce its dependence on imported oil by more than 40 percent, nearly equal to the 550 million barrels of crude oil that we import from Saudi Arabia each year.

To reduce America's carbon footprint and to encourage the development and expansion of sustainable transportation options, the American Clean Energy and Security Act will implement a number of initiatives to significantly reduce transportation-related greenhouse gas emissions. These provisions represent the next steps to mitigate the negative impact the transportation sector has on climate protection, while increasing the livability of our communities nationwide.

Under the American Clean Energy and Security Act, States will receive allowances for clean energy and energy efficiency investments, and are authorized to use up to 10 percent of these allowances for certain transportation projects. States may use allowances to fulfill the local matching requirement to receive Federal funds for projects like public transportation system improvements, clean fuel buses, or construction of bicycle facilities. While this provision offers only a small portion of the funds needed to address surface transportation-related greenhouse gas emissions, it is a very good first step.

Additional provisions of the legislation expand the scope of current surface transportation planning to include emissions reduction requirements administered by the Department of Transportation (DOT). The Act requires EPA, in consultation with DOT, to set national emission reduction goals, but requires DOT to set transportation-related emissions reduction performance measures for each State and large metropolitan areas. States and metropolitan planning organizations (MPOs) must individualized transportation-related emissions reductions targets, and the Act reguires public notice of those targets, including an assessment of how well States and MPOs are meeting emission reduction goals.

These important transportation planning provisions are also included in the Surface Trans-

portation Authorization Act of 2009, legislation that the Subcommittee on Highways and Transit passed unanimously this week by voice vote, and which I plan to bring before the full Committee on Transportation and Infrastructure and the House soon after the fourth of July recess.

These transformational changes to our surface transportation planning requirements, especially when coupled with dedicated funding for clean energy transportation projects, will save fuel, reduce emissions, and advance America's long-sought goal of energy independence.

In addition to these important transportation provisions, I am very pleased that agreement has been reached to clarify the definition of renewable biomass. I want to commend the leadership of my Minnesota colleague, COLLIN PETERSON, Chairman of the Committee on Agriculture, for his superb advocacy for rural America and the wood product industry. The new biomass definition and provisions that provide credit for forestry and wood products for carbon sequestration are essential to ensure that our vital wood product sector is not disadvantaged in the climate change legislation.

I am also very pleased that additional language has been added to ensure that the iron ore sector will receive emission allowances, and I greatly appreciate Chairman WAXMAN's willingness to work with my colleague BART STUPAK and me on this important iron ore mining clarification.

While I am prepared to support this legislation today, I continue to have concerns with the climate change bill regarding the border adjustment mechanism. It is imperative that the final climate change legislation contain strong safeguards to ensure that our manufacturing sector is not disadvantaged by imports from nations that have not implemented carbon reduction technologies.

Without further improvements, it is likely that the steel, wood product, and other energy-intensive sectors of our economy would face unfair competition from nations with insufficient environmental safeguards. I am encouraged by the important contributions that my colleagues MIKE DOYLE, JAY INSLEE, CHARLIE RANGEL, and SANDY LEVIN have made in this area, and I will continue to work with my colleagues to make additional improvements.

We must also ensure that the final climate change bill addresses regional concerns regarding the allocation of emissions allowances to utilities in the Midwest. While I am pleased that improvements were made to assist rural electrical cooperatives, I remain concerned that the current formula, which would allocate emissions allowances to utilities based on a combination of sales and emissions, would unfairly impact Midwestern power producers, and I am hopeful that further refinements can be made to ensure regional equity.

For these reasons and more, I support H.R. 2454, the "American Clean Energy and Security Act of 2009", and urge my colleagues to do the same.

Mr. RAHALL. Madam Speaker, the Congress would be unwise to sit by and simply allow the Environmental Protection Agency to regulate a reduction in greenhouse gas emissions, as the agency has been mandated to do by the Supreme Court. Similarly, it would be a mistake to sit back and allow other countries to devise international rules that will affect America's economic and energy interests.

I do not agree with those who advocate for sitting on our hands and just saying no to everything, sight unseen. The international community has no interest in protecting American businesses, and the Environmental Protection Agency is not required by the Supreme Court to consider the views of our constituents or the economic consequences to our communities.

I believe America is the one nation best equipped to lead such a multinational effort and, in doing so, to strike a balance between environmental preservation and the preservation of jobs. The hands-off approach of recent years did nothing to help promote new energy technologies, or to advance carbon capture and sequestration, or to protect American jobs.

It is evident that wishing that this complex issue would simply go away will not lead to better results for our Nation or the people we represent. And "just saying no" to any and all proposals, sight unseen, is unrealistic and irresponsible.

For those reasons, I chose to work with my colleagues and with numerous stakeholders—including the coal industry, manufacturers, and labor—to positively influence this bill and America's climate change strategies. And for those reasons our coal miners and responsible industry members have been at the table, too, rather than on the sidelines.

I thank Chairman WAXMAN, who has made many concessions in this bill, and I thank leadership for listening to my concerns about this legislation and moving to help address them.

As well, I commend my colleague RICK BOUCHER, from southwestern Virginia, who serves on the Energy and Commerce Committee and worked in determined fashion to make improvements to the bill that we both sought. I am grateful that he has been so welcoming of my views and supportive of our interests—such as ensuring the availability of \$10 billion to advance carbon capture and sequestration technologies and other changes that are beneficial to the people of our neighboring districts.

While this bill is greatly improved from the discussion draft that was first circulated in March of this year—and opponents were saying no even before that draft was written—more improvements are needed to gain my support.

Coal does much more than keep the lights on in big cities across America. In southern West Virginia, it covers the mortgage, puts food on the family dinner table, and keeps open the doors of small businesses. While the emissions target in the early years of this program has been lowered from the 20% cap initially contained in this bill, there remains widespread concern that even the reduced cap—17% in 2020—is still too high and too soon to incentivize rapid development and deployment of carbon capture and sequestration technologies, so as to ensure coal mining jobs for the future. We must allow time for expensive clean coal technologies to come on line.

These technologies are critical to lowering emissions across multiple sectors of our economy. And they are necessary for keeping hardworking coal miners in the jobs they want, providing power for the country they love.

For these reasons, I cannot cast my vote for

Mr. CALVERT. Madam Speaker, Families in communities across our nation continue to

struggle through the most difficult economy most of them have ever experienced. Nationally, our unemployment rate is nearing 10 percent. In California, the unemployment rate has soared to 11 percent and in some of the hardest hit portions of my congressional district it has reached almost 18 percent.

Like many Americans, I am dismayed by the decision of the Democratic leadership to bring such an economically damaging bill to the House floor in the midst of these historically difficult times.

Economic organizations and think tanks from around the country have studied the economic impacts of the bill before us . . . and the results are not good. A study conducted by the National Black Chamber of Commerce determined that by 2030 the Waxman-Markey bill will cut net employment by 2.5 million jobs—even after accounting for new "green" jobs. Similar studies by the Brookings Institution and the Heritage Foundation also project huge job losses.

Ironically the Democratic leadership in Congress and the Democratic Administration have made job creation one of their biggest priorities this year. During the consideration of the stimulus bill we repeatedly heard claims that the bill would "save or create more than 3.5 million jobs." As most Americans know, the bill has yet to deliver as promised. I think it is no table that as we consider another major piece of legislation both the Administration and Democratic leadership are eerily silent on their job creation predictions.

The reality is the bill before us will kill jobs, weaken our economic security, and enacts punitive measures that will only make matters worse for families struggling to get by. I urge all of my colleagues to vote against this poorty conceived bill that is being pushed through with little to no time for debate or discussion.

Mr. GARRETT of New Jersey. Madam Speaker, I rise in opposition to the so-called cap & trade legislation before us. While there are countless reasons to oppose it, including the millions of jobs that are expected to be lost, I wanted to take a moment to speak on the amendment that I offered to this legislation. More than 200 amendments were offered to this legislation in addition to my amendment, and all of them, with the exception of one, was rejected by the Democrat majority.

My amendment would have stricken all sections of H.R. 2454 that deal with the regulation of derivatives. This bipartisan effort was supported by six cosponsors, including Democratic Reps. MIKE MCMAHON and DAVID SCOTT as well as FSC Ranking Member BACHUS and several others.

Despite lacking any jurisdiction and expertise, the Energy & Commerce Committee added sections to this bill imposing costly new regulations on this portion of our financial services sector. I think we can all agree that a broader discussion within Congress need to take place on these issues, including at the committees of jurisdiction where there is experience and expertise in dealing with them.

Just one week ago, Congress received an outline of President Obama's financial regulatory reform plan, which includes suggestions for the regulation of derivatives. The Financial Services Committee has not yet had a chance to digest the President's proposal, nor has it fully debated this issue within the context of broader financial regulatory reform, which will continue to be the focus of our committee's work over the next several months.

It is not appropriate to enact language that regulates a portion of the derivatives market, potentially in a manner that conflicts with later consensus on how to regulate the industry at large. Ninety-four percent of the 500 largest global companies use derivatives to manage risk and maintain stable consumer prices. Given the importance of these financial products, Congress needs to tread carefully as it looks at regulatory options for these markets. Over-regulation or improper regulation that might sound good politically could have major unintended negative consequences, not just for our financial markets, but for our broader economy.

The sections that remain in this bill that deal with the regulation of our derivatives markets are but one of many reasons to oppose this massive and massively-flawed piece of legislation.

Ms. SCHWARTZ. Madam Speaker, I rise today in support of the American Clean Energy and Security Act (ACES). This historic initiative will create jobs in new renewable energy industries and energy efficiency, reduce American dependence on imported oil, and decrease the greenhouse gas emissions that are causing global climate change.

The growth of these new industries will enhance the ability of the United States to produce its own energy and reduce the need for oil imports from foreign countries. We currently import nearly 60 percent of our energy needs from abroad. This imbalance makes our country dependent upon foreign countries for the fuel that keeps our economy running. It is estimated that ACES will reduce U.S. oil consumption by 2 million barrels per day by 2030.

Growing our domestic clean energy industry and reducing our use of foreign oil will have an important tangible benefit—reducing the greenhouse gas emissions that are causing global climate change. The Nobel-Prize winning Intergovernmental Panel on Climate Change has determined that significant reductions in greenhouse gas emissions, like carbon dioxide, are necessary to mitigate significant environmental consequences. ACES meets this challenge by creating a framework to reduce U.S. emissions 83 percent below 2005 levels by 2050.

ACES accomplishes these goals while limiting costs to businesses and the consumer. The nonpartisan Congressional Budget Office has determined that implementing this bill would cost the average household about 48-cents per day. ACES also includes assistance for energy-intensive manufacturing industries like steel, cement, and glass to ensure that these industries remain economically competitive in the global marketplace as we strengthen our environmental laws and transitioned to clean energy and greater energy efficiency.

I am proud that this bill includes a provision I spearheaded that will require the Environmental Protection Agency Administrator to create a national strategy to reduce carbon emissions through biologic sequestration. Carbon dioxide can be absorbed from the atmosphere into plants, trees, and other vegetation through the natural process of photosynthesis. My provision would ensure that we utilize natural landscape and green infrastructure to maximize our ability to remove carbon from the atmosphere through a determined strategy for reforestation, improved agricultural practices, and urban greening.

This important legislation defines new energy goals for our nation and enables us to

lead the world towards a clean energy future. For businesses and families back home it identifies a way forward to not only reduce harmful carbon emissions but to create new economic opportunities, new "green" jobs, conservation and energy efficiency, and alternative, cleaner sources of energy. Together these actions will better ensure our nation's security, economy, and health. I urge my colleagues to vote "yes" on this important bill.

Mr. GRIJALVA. Madam Speaker, I rise in support of the legislation before us today.

As the Chair of the Subcommittee on National Parks, Forests and Public Lands of the House Natural Resources Committee, I have held a series of hearings on the impacts that climate change is having, and will have, on our lands, waters, and wildlife. In response, my congressional colleagues and I developed a bill to give state and federal natural resource managers the tools to respond and adapt to these impacts. That bill is included within the American Clean Energy and Security Act which I strongly urge my colleagues to support today.

Any serious attempt to address climate change must include a focus on the management of our nation's natural resources. Our land, water, fish and wildlife resources are critical to public health and the American economy.

These natural resources are also vulnerable to a wide range of physical, biological, economic, and social effects as a result of climate change. At the same time, public lands and resources represent some of the best opportunities we have for implementing natural resource adaptation strategies to help mitigate some of those effects.

Unfortunately, the previous Administration pursued a "Head in the Sand" policy regarding climate change and, as a result, the gap between what we know about climate change, and what federal and state resource management agencies are doing about it, has never been wider.

After the Natural Resources Committee held a series of hearings on the impacts that climate change is having, and will have, on our lands, our oceans, and our wildlife, several of my colleagues and I introduced H.R. 2192 to promote a proactive federal-state partnership to address the impacts of climate change on our nation's natural resources and provide the direction and the tools that resource managers will need to develop mitigation and adaptation strategies for our land, water, and wildlife.

We are gratified that the Energy and Commerce Committee shares the belief that this is an important piece of the puzzle and has elected to include our legislation as part of the bill before us today.

The bill establishes a Natural Resources Climate Change Adaptation Panel made up of Federal agencies responsible for managing our Nation's natural resources. The Panel's mission will be to foster the kind of interagency and federal-state cooperation and planning that is both critical in responding to climate change and, so far, sorely lacking.

The Panel will be tasked with developing a comprehensive, national strategy for combating climate change. Once the national strategy is in place, each Federal agency with jurisdiction over natural resources will be required to translate that broader plan into a climate change response tailored specifically to their programs and activities. Furthermore,

funding will be authorized to assist states in developing similar state-wide adaptation plans that lead to concrete, on the ground actions to address the impacts of climate change on the natural resources they manage.

In addition, the bill will streamline, centralize and improve the collection and dissemination of climate-related scientific information. This provision will ensure that Federal climate research will be better funded, more aggressive and more easily available to land managers, policy-makers and the public.

Finally, the bill will create a centralized database of geographic mapping information designed to identify significant wildlife habitat and migration corridors. Such areas must be included in any ecosystem-level adaptation planning efforts.

These efforts are belated—we cannot hope to reverse a decade of inaction immediately—but they are important tools and these provisions are an important step forward in developing a response to climate change that will protect the lands and waters owned, and deeply valued, by the American people.

We have wasted valuable time when we should have been working to stop harmful global warming, but with this vote to rein in carbon emissions, we will take a big step toward joining the rest of the world in addressing mankind's impact on our environment. Our existence on this planet depends on our taking action now rather than later, and therefore, I urge passage of the legislation today.

Mr. BACHUS. Madam Speaker, I rise in opposition to the Waxman-Markey bill.

This legislation creates a new multi-trillion dollar market for Carbon Allowance Derivatives overnight, all without one hearing before the Financial Services Committee. This continues a disturbing pattern of conduct of passing sweeping legislative proposals without consideration of the consequences and ramifications.

While Congress and financial regulators continue to work to determine how best to oversee existing derivatives markets, it is illadvised to rubber stamp the creation of a brand new, hard to price, and convoluted Carbon Allowance Derivative Market. The new market would be open to potential abuse because it will be difficult for regulators to understand and monitor.

Under the Waxman-Markey bill the government would issue allowances (carbon allowance permits) that allow companies to emit a certain amount of greenhouse gases. Companies that emit too much can buy allowances from companies that produce less than their limit. In addition to carbon allowances, there are carbon offsets which allow companies to emit greenhouse gases in excess of the federal cap or limit. They do this by investing in projects that cut emissions and it is anticipated that many of these projects will be in developing countries C.F.T.C. Commissioner Bart Chilton anticipates that overnight the bill will create a \$2 trillion dollar market, which he describes as "the biggest of any commodities derivative product in the next five years." Robert Shapiro, a former undersecretary of Commerce in the Clinton administration and a cofounder of the US climate Task Force warns that "we are on the verge of creating a new trillion dollar market in financial assets that will be securitized, derivatized, and speculated by Wall Street, like the mortgage-backed securities market." Mother Jones' Rachel Morris warns that without strong financial regulation of the market you could have abuses, over leveraging and ultimately collapse of the market. Democratic Senator JEFF BINGAMAN has described these offset projects as "fraught with opportunity for game playing, which will be fully exploited, I'm sure."

Many of these projects will be created in developing countries. A clean coal project in China or India could be used for carbon offsets, as could a tree planting project in Brazil or Borneo. As much as China needs to clean up their environment, should Americans pay for it? Should a tree planting project in Borneo allow the discharge of more pollution in America? Many of these remote projects will be notoriously difficult to confirm and monitor. Even in America with a well-established regulatory system we witnessed abuses in the subprime mortgage market. The derivatives market has the potential for even greater game playing in remote countries with questionable rule of law and little regulation.

Michele Čhan of Friends of the Earth says if not properly regulated the offset derivatives could become what she calls "subprime carbon"—futures contracts that promise emissions reductions but fail to deliver and then become toxic or worthless. Already the financial markets and speculators are planning how to slice and dice them and sell them to investors. It sounds altogether too familiar—a brand new, hard to price, vast convoluted market of carbon derivatives. And if these warnings are correct, one that certainly could pose a systemic risk in the financial markets.

If you liked what Wall Street did with the securitization of subprime mortgages, you'll love what they are going to do with carbon derivatives.

Finally, "cap and tax" will have a devastating impact on my home state of Alabama. The bias against coal and the renewable energy mandates will force consumers in Alabama to buy expensive "green power" from other states, which will raise energy costs across the board. One study has projected that the typical family in Alabama could eventually see electricity bills rise by more than \$1500 a year. Higher energy costs will make our manufacturers less competitive, and Alabama and the rest of our country will lose jobs to nations like China, Korea, and Mexico which have lower energy costs.

This bill is bad for Alabama, bad for the U.S. economy, and doesn't even begin to solve the serious energy challenges facing our nation.

I urge my colleagues to join me in opposing this legislation.

Mr. STARK. Madam Speaker, I rise today in opposition to the American Clean Energy and Security Act (H.R. 2454). Global warming is real. Man causes it and it threatens nearly every aspect of life. We are right to act with urgency to end our nation's addiction to fossil fuels and combat global warming. But we cannot waste this opportunity by moving a deeply flawed bill that provides too much to special interests and too little to the environment and consumers. I cannot support the American Clean Energy and Security Act in its current form.

This legislation continues the "clean coal" myth by providing at least \$60 billion for pie in the sky projects that will only continue the destruction of mountains and waterways at the hands of coal mining operations. More importantly, the bill takes away a vital weapon in the

fight to defeat new coal burning plants by repealing the EPA's current authority to regulate greenhouse gas emissions, including the emissions of individual power plants. The result will be a rush to build new coal powered plants over the next decade and then an intense lobbying effort to ensure that these plants are grandfathered in by the time the rules are supposedly set to tighten in 2020.

The creation of a massive, trillion-dollar new carbon market should scare all of us. The new, highly complex carbon market will be ripe with opportunities for Wall Street speculation and manipulation. The Commissioner of the Commodity Futures Trading Commission estimates that the carbon market will consist of 180 million contracts within 5 years, making it the world's largest commodity and derivatives market. The subsequent market volatility will hurt consumers by ensuring that energy prices continue to fluctuate. Market volatility will also dissuade long-term investments in clean energy and efficiency. This is the scenario that has played out in the European Union, where prices have swung wildly and some power plants have actually switched back to coal due to the low cost of emissions permits.

Many of these problems could have been dealt with through amendments that were brought before the Committee on Rules yesterday. One amendment that I cosponsored would have reigned in the carbon market by only allowing entities covered under the Cap and Trade program to trade allowances. This amendment would have greatly curtailed the ability of Wall Street to influence the carbon market and would have protected our economy from another financial meltdown. Unfortunately, this amendment was not allowed to come to the floor for a vote. I also cosponsored an amendment that would have continued EPA's current authority to regulate greenhouse gas emissions under the Clean Air Act. This authority would provide a backstop should the new cap and trade regime prove ineffective. Sadly, this amendment was also not allowed to come to the floor.

I commend the emission reduction targets laid out in the legislation. I am not convinced, however, that these targets will be met in the near future due to the many loopholes and dubious offset provisions contained in the bill. This bill unfortunately continues the Congressional tradition of subsidizing the fossil fuel industry. Only this time it is cloaked in the disguise of environmentalism and the subsidies come in the form of free allowances, institutionalization of the "clean coal" fiction, and the gutting of EPA authority.

We have the opportunity and the responsibility to confront catastrophic global warming with bold action. Congress should seize that opportunity by passing legislation that would end our addiction to fossil fuels, prove our leadership to the world, and build a foundation for long-term prosperity. This legislation falls short of these goals. Many have said that this vote is a historic one that we will be judged by. In my view, history will judge this legislation as a missed opportunity. I urge my colleagues to oppose the bill in its current form and work to bring a truly progressive bill to the floor.

Mr. LANGEVIN. Madam Speaker, I rise today in strong support of H.R. 2454, the American Clean Energy and Security Act. I thank our leaders who made this bill a priority,

especially Speaker PELOSI, Leader HOYER, Chairman WAXMAN, Chairman RANGEL, Chairman PETERSON, and Chairman MARKEY, who worked tirelessly to bring this bill to the floor today.

I have long been an advocate for reducing harmful carbon emissions and investing in a clean energy economy. The path that we are on is unsustainable. Last year's spike in gasoline prices and home heating oil was only a small example of the challenges our nation faces due to our reliance on foreign oil. The effects of climate change are already beginning, and I believe that we must act now if we are to stop—and ultimately reverse—the damage done to our planet and our economy.

I support this legislation because it will set our nation on a path toward an energy independent future. The bill increases the renewable energy standard to 20 percent by 2020, which means that more of the energy we all use at home will come from clean, renewable resources. It caps harmful carbon emissions that are damaging our environment and ecosystem through a responsible and transparent approach, reaching an overall reduction of 83 percent by 2050. With this reduction, it is my hope that we will be the first generation to pass on a healthier planet to our children and our grandchildren.

The \$90 billion investment included in this bill will help create 1.7 million clean energy jobs throughout the nation, particularly in manufacturing industries as demand for construction of renewable energy components will dramatically increase. Increased funding for research and development of renewable technologies, including wind, solar, and wave energy, will drive American entrepreneurship and competitiveness to make the U.S. a global leader in clean energy development.

This bill was also carefully written to ensure that consumers are not overburdened by any increase in cost. Allowances are provided to electricity, natural gas, and heating oil companies that must be redirected to their customers. Low-income families are given even further protections in the bill and will receive specific allowances in the form of monthly energy refunds. The Congressional Budget Office (CBO) estimates that protecting our nation through a cap on emissions would cost an average family \$175 per year, or less than 50 cents a day, by 2020. Alternatively, if we fail to act and continue to rely on oil, energy prices per household are estimated to reach \$3,500 annually. Further, CBO has determined that the bill meets PAYGO requirements and will not increase the deficit.

Lastly, it must be noted that our nation spends over \$400 billion for foreign oil each year. The time has come to stop investing our taxpayers dollars overseas, and to bring them home to invest in clean energy jobs and a healthier planet for our citizens. By increasing the renewable energy standard, capping carbon emissions, and investing in the creation of domestic jobs, this bill is directing our nation towards a sustainable and economically viable energy future. I urge my colleagues to invest in the future of this great nation, and vote yes on the American Energy and Security Act.

Mr. BERMAN. Madam Speaker, I rise in strong support of H.R. 2454, the American Clean Energy and Security Act of 2009.

This groundbreaking legislation will help protect our environment and create an estimated 37 million jobs in the United States over the

next 20 years by significantly reducing greenhouse gas emissions, implementing a renewable electricity standard, providing incentives for the adoption of energy efficiency measures, and promoting renewable energy technology research and development.

H.R. 2454 also provides assistance to developing countries to help them adapt to the effects of climate change, deploy clean energy technologies, and reduce emissions from deforestation.

Some of the world's poorest countries—including those that have contributed the least to the problem of climate change—will suffer the most immediate and severe consequences of global warming if we don't take action to reverse it.

Many developing countries face the threat of flooding, the loss of arable lands, and the spread of climate-related diseases, such as malaria and cholera.

A recent World Bank study estimated that storm surges resulting from rising sea levels could threaten 52 million people and 29,000 square kilometers of agricultural land in developing coastal countries around the world.

H.Ř. 2454 will help people in low-income countries prepare for and adapt to climate change by strengthening local planning capacity and promoting the development and implementation of national adaptation programs.

This legislation also provides financial and technical assistance and leverages private sector involvement to mitigate the emissions of greenhouse gases in developing countries.

This will help reduce the impact of climate change here in the United States and benefit the American economy by encouraging innovation in green technologies and the creation of high quality jobs.

Finally, the bill will help reduce greenhouse gas emissions by helping low-income countries reduce emissions associated with deforestation

Madam Speaker, the programs on international adaptation, clean technology, forestation as well as provisions for international offsets will all require close collaboration between the Environmental Protection Agency, the United States Agency for International Development, and the Department of State.

In international negotiations on framework agreements to carry out these programs, I expect the Department to continue to have responsibility to approve the initiation of such negotiations, consistent with current law and regulations.

I also expect that USAID, which has significant expertise in dealing with a range of environmental activities overseas, will play a central role in planning and helping administer these critical programs.

Madam Speaker, the international provisions in this legislation are crucial for the successful completion of climate change negotiations in Copenhagen later this year.

They will demonstrate to the rest of the world that the United States is truly committed to working cooperatively with other nations to tackle the global challenges of climate change.

I thank my good friends Chairman WAXMAN and Chairman MARKEY for working closely with me to develop and refine the international provisions in this important legislation, and urge all of my colleagues to vote yes.

Mr. McCAUL. Madam Speaker, "Electricity rates would necessarily skyrocket." That is a direct quote from President Obama describing

his "Cap and Trade" plan. I agree with the President. That is why we call it Cap and Tax. This is a failed European model that should not be imported into the United States. We've already seen the effects in Europe where household energy prices went up 25% and emissions were not reduced. This is the wrong bill at the wrong time. Imposing a national energy tax on the working families in my district who are already struggling to make ends meet is wrong. And who benefits from this? You guessed it, Wall Street, not Main Street.

While I strongly support investing in alternative energy and green technology, I cannot support this bill.

Overall, in my home state of Texas, energy costs will increase by \$1.15 billion imposing an enormous tax each year on every Texas family. All of this for something that simply won't work.

Companies that are not able to meet the cap will simply move their manufacturing facilities overseas to countries with fewer regulations. Nationwide, our country will lose around 2.5 million jobs and Texas alone could lose 277,000 jobs in the first year alone. Perhaps that is why the U.S. Chamber, the National Association of Manufacturers, the Farm Bureau, and dozens of other organizations oppose this plan.

I continue to support the American Energy Act which increases our domestic energy supply by developing more of our resources here in the United States, investing in alternative fuels and offering incentives for better efficiency and conservation—without placing a greater burden on our families, our businesses and our economy.

Mr. POSEY. Madam Speaker, I rise to express my strong concerns about the bill before us—a bill which no one has read. This morning members of Congress were told about the addition of 309 pages that were added to this bill early this morning. No one has read it.

Why the rush? Why does Congress have to pass this bill today, before everyone can read it and understand what this new language is doing? When Congress did this with the stimulus bill earlier this year it was discovered after passage of that bill that it contained bonus payments for AIG employees. But this bill, affecting every segment of our economy, has much broader applications. We and the American people have a right to know what is in this bill, how it will affect the American people, and what impact it will have on our economy. Nobody knows that this morning. We do not even have a cost estimate on this latest version of the bill from the Congressional Budget Office (CBO). No one knows what it will cost. My rule is that if you are not going to give Members of Congress the time to read the bill, a cost estimate of the bill, and an ability to understand its impact on the taxpayers and American businesses. I'm going to vote

Supporters of the bill claim that it will only cost the average American \$175 per year. This is a fatally flawed estimate for three reasons: (1) this figure is derived from a selective reading of the CBO cost estimate, (2) 3 days after the CBO issued their cost estimate 300 additional pages were added to the bill, and (3) at 3 a.m. last night another 309 pages were added to the bill. This bill has grown by nearly 70% since CBO's cost estimate was prepared.

The CBO estimate has serious deficiencies. In fact if you read the entire CBO estimate you

would find that they highlight the deficiencies, deficiencies that are being conveniently ignored. The most critical flaw is that CBO picked a year as the basis for their estimate that is before the most costly parts of the bill take effect. This excludes hundreds of billions of dollars from the cost estimate. The footnote on page 4 of the estimate says that they exclude from the costs estimate the "decrease in gross domestic product (GDP)" resulting from the bill. Most estimates conclude that it will result in \$1-\$2 trillion in lost economic activity in the U.S. translating into a loss of over 2.5 million jobs. The CBO fails to incorporate tens of billions of increased costs to the states which will be passed on through higher state taxes. CBO lists a number of other cost estimate omissions.

When you factor in the deficiencies of the CBO estimate most analyses put the cost estimate at between \$750 and \$3100 per year. Washington has a habit of underestimating the cost of legislation. They are doing so again today. That's why this bill was significantly changed last night and rushed to the floor before Members of Congress have had a chance to read the bill and understand what the changes do.

This 1200-plus page bill started out as legislation aimed at improving the environment but it has become a means of raising money to pay for larger, more intrusive government while having little impact on the global environment.

The idea behind "Cap and Trade" is to purposely increase the cost of energy that is produced using fossil fuels like natural gas, coal or petroleum. Nearly 85% of electricity across the U.S. is generated using these sources of tuel. The price of everything you buy will go up, from gas to food, because there will be a hidden national energy tax built into the price of everything.

Senator CARDIN (D-MD) told the Washington Post that, "This is the greatest revenue generating [read tax] proposal of our time." This bill moves money from the family budget to Washington.

Estimates are that this bill will have a negligible effect on the global environment. It is estimated that if enacted, this bill will lower the global temperature two-tenths of one percent. This is equivalent to the annual fluctuation in global temperatures. Also, this fails to acknowledge the fact that China, India and the rest of the developing world are exempt from such regulations and their emissions will far exceed any reductions that result from this bill.

This costly national energy tax will put American products at a competitive disadvantage and further erode the ability of the American worker to compete with China, India and the rest the developing world. The result will be the loss of millions of jobs as more businesses move to countries that will not impose these caps on their citizens. Businesses that otherwise might have built facilities in the U.S. will instead open up factories in countries that are exempt from these regulations. It's no wonder China has called for the U.S. to pass this energy tax bill. With a national unemplovment rate nearing 10%, it's estimated that this tax will cost Americans another 2.5 million iobs.

I oppose this plan and will vote against it because it is not good for the American worker, small businesses, seniors on fixed incomes, or families struggling to pay their bills and mortgages. Washington doesn't need more of your money, it needs to control spending. Europe adopted a similar plan several years ago and it forced jobs to leave Europe, caused electricity prices to skyrocket, and they have little to show for the costs. It's all pain and no gain. Check out the non-partisan Tax Foundation's online energy tax calculator (www.taxfoundation.org/capandtrade) to figure out how much it may cost you.

Finally, it is a sad day for the Congress and the American people that the Speaker chose to rush this bill through the Congress without an open debate and amendment process. Members of Congress asked that 224 amendments be allowed to be considered to this bill. Unfortunately, the Speaker allowed only one amendment to be offered. Among the amendments denied were one to: (1) suspend the bill if gas exceeds \$5 per gallon; (2) suspend the bill if electricity prices increase more than 10%: and (3) suspend the bill if unemployment exceeds 15%. These and many more amendments were reasonable and worthy of consideration. They should have been allowed, as they are in the best interest of the American people

Again, I rise in strong opposition to this bill and urge my colleagues to vote down this bill. It will further harm our economy and slow our economic recovery.

Mr. PAYNE. Madam Speaker, today I rise on behalf of the 1 billion people who live on less than \$1.25 a day and who will most acutely feel the impacts of climate change.

At first glance, climate change is a lot about numbers—temperature rise of 2 degrees, 450 parts per million, a 25–40 percent reduction in greenhouse gas emissions, one percent of allowances. The list goes on.

However, climate change is more than science and numbers. At the end of the day, climate change is about people. Climate change is happening far more rapidly than first thought. For the world's poor the climate crisis not looming on the horizon. It is happening today. The impacts are hitting the world's poorest first and worst—those least responsible for climate change.

Poor communities—individuals eking out an existence on less than \$1.25 a day-are the hardest hit and have the fewest resources to adapt. Harsher climate conditions mean these vulnerable communities are facing more severe, more frequent, and more intense floods, droughts, and cyclones-leading to natural disasters and major disruptions in agricultural growing seasons. Climate change is increasing malnutrition as agricultural productivity declines. In Africa, agricultural productivity is predicted to decrease by as much as 50 percent over the next decade. A quarter billion people will be facing water scarcity. The United States will not be isolated from these events. If left unabated, the spillover caused by climate change will be visited upon U.S. shores.

As resources like water and arable land become scarcer, outbreaks of conflict, mass migration, and refugee crises will rise. A recent report released by CARE, UN University, and Columbia University's Center for International Earth Science Information Network reveals that climate change is expected to spur human migration and displacement on a scale never before seen. According to the International Organization for Migration, as many as 200 million climate migrants may be forced to cross borders by 2050.

One man from Niger interviewed for the study said: "I have been suffering from the rain water shortage, which made the river very shallow and decreased my fish production, which had negative implications on my income. If the situation does not improve, I might leave for another country like some of my friends and relatives did; they left for Nigeria and Burkina Faso and settled there." Left unchecked, climate change will force him, and hundreds of thousands like him, to migrate from home.

These negative impacts will be even greater on women and girls. As primary family caretakers, food providers, and health care providers, women will be forced to walk further to fetch ever scarcer water. They will have to work harder to squeeze a harvest out of the earth to feed their families. As the burden increases, children will be pulled out of school—the girl child will undoubtedly be first.

Passing this bill is imperative. It begins our iourney of tackling climate change. It begins to assist poor communities in their efforts to adapt to climate impacts. The challenge of climate change is not insurmountable. We know adaptation works-and it can be fairly simple-though it can also require substantial resources. Development assistance organizations like Oxfam and CARE are allies in this struggle. For example, Oxfam is working with communities in El Salvador to plant mangroves as a natural coastal buffer to protect against severe storms. CARE is partnering with women in Bangladesh who identified duck rearing as a viable adaptive alternative to rearing chickens, since chickens were getting wiped out in increasing flood disasters.

The reality for poor vulnerable communities on the receiving end of the effects of climate change is that the situation is dire. The least developed countries face the brunt of the impacts but contribute less than half a percent of global greenhouse gas emissions. Climate change is not something of the future, the impacts are already happening. For over 100 of the countries most vulnerable to the impacts of climate change, international adaptation will be the key that unlocks their commitment to a global agreement on climate change.

Climate change is a study of injustice—those hardest hit by climate change are the least responsible for it. As a global leader, the U.S. has a critical role to play: our leadership can help bring other countries along—we simply cannot tackle climate change alone. As a global problem, climate change requires a global solution based on a shared sense of community. That solution starts here with this

My esteemed colleagues, I call upon you to pass this bill that will begin to provide President Obama with some of the tools he needs to conclude a global climate agreement. While we might focus on the numbers in this bill, let us remember that this issue is really about people everywhere. People matter. The poor matter. Their livelihoods matter. Their survival matters. This bill marks a historic beginning of putting the U.S. back in the fore of global leadership on climate change. Thank you.

Mrs. CHRISTENSEN. Madam Speaker, the American Clean Energy and Security Act of 2009 is about the future. All the decisions that we know must be made, that we have put off for far too long on energy independence, climate change and retooling our economy for the industries of the future must be made now.

As this bill was crafted, I know that we were careful in making sure that all the regions of our country, from the coal producers, to the oil producers, to the environmentalists, to the farmers, to the climate change experts to those concerned about costs and the transition to green jobs were heard from and our committees and membership worked hard on a bill that will be the first foot forward to the goals that we want to achieve for the 21st century.

While this bill is in no way a panacea to the myriad of issues before us, it certainly is a progressive step towards creating clean energy jobs, achieving energy independence, reducing global warming and slowing climate change.

As a representative of one of the offshore territories of the United States, I would reiterate that the U.S. territories, like other distressed economies around the Nation, stand to be disproportionately affected by the impact of climate change. We are also disproportionately dependent on diesel for power generation and vulnerable to its shifting costs.

On the other hand our geography and natural resources have the potential to promote and utilize a diverse portfolio of renewable energy options. I am proud that my colleagues have recognized this and that this legislation contains language that will help us prepare for the coming challenges and the shift to a greener economy.

Madam Speaker, The American Clean Energy and Security Act undoubtedly responds to the call of countless citizens who have clearly articulated this generation and this Congress must invest in renewable energy, green jobs, clean technology, and adaptation strategies—domestically and internationally—to buffer the ramifications of climate change while at the same time ensuring that the cost will not be prohibitive to poor and middle income Americans.

I am proud that we are responding to the President's vision and mandate to meet our country's climate and energy security needs, in the near future and beyond.

We have accomplished an amazing feat by arriving to where we are today. I implore my colleagues here today to put politics aside and keep the interest of the American people at heart throughout this process.

Let us make this a truly historic day as we hold true to the commitment of leading the world into an economy of 21st century clean technology and industry.

Mr. GRAVES. Madam Speaker, I rise today

Mr. GRAVES. Madam Speaker, I rise today in strong opposition to the energy tax reck-lessly being forced through the legislative process only to harm small business owners, farmers, and families in Missouri.

As a 6th generation farmer I can tell you that it is an extremely energy intensive practice. Sixty-five percent of a farmer's costs are dedicated to electricity, fuel, fertilizer, and chemicals; even a slight increase in costs would have a damaging effect on farmers.

When it comes to rising fuel prices, we farmers drive trucks because we have to haul stuff. I would challenge any of my colleagues to come to Missouri and try doing farm chores in a Prius.

Those claiming this bill benefits agriculture don't know a thing about the business. Agriculture producers are price takers on both ends of the equation. It is one of the few industries in the world that purchases its inputs at retail to sell its end product at wholesale.

Farmers have very little ability to pass their own costs onto their customers and even those costs that agriculture producers can pass on will mean only one thing: higher food prices for American families.

Rising food prices will be an indirect tax imposed on American families by this Cap and Tax bill and its effects won't just be confined to agriculture. Business everywhere will be confronted by a new dueling reality of seeing their own energy costs rise and the disposable income of their customers fall. All this can accomplish is to restrain future economic growth and lead to long-term joblessness.

That is if there are any jobs left. None of the regulations or increased costs in this bill will be shouldered by our trading partners and competitors. How can we expect our businesses to remain competitive and create jobs when we are imposing new taxes not only on those same businesses, but their customers as well?

Let's be honest with ourselves. This legislation is nothing more than a thinly veiled attempt to address climate change, while its actual goal is to direct more taxpayer dollars to the government coffers to fund a big government agenda, including the federal takeover of health care.

Today I strongly urge my colleagues to stand with me. It is irresponsible of Congress to use taxation as an answer to our nation's challenges. Voting against this bill will demonstrate your willingness to work together towards real energy solutions for our future and our children's future.

Mr. WAXMAN. Madam Speaker, I yield back the balance of my time.

AMENDMENT IN THE NATURE OF A SUBSTITUTE

AMENDMENT IN THE NATURE OF A SUBSTITUTION OFFERED BY MR. FORBES

Mr. FORBES. Madam Speaker, I have an amendment in the nature of a substitute at the desk.

The SPEAKER pro tempore. The Clerk will designate the amendment.

The text of the amendment in the nature of a substitute is as follows:

Amendment in the nature of a substitute offered by Mr. FORBES:

Strike all after the enacting clause and insert the following:

SECTION 1. SHORT TITLE.

This Act may be cited as the "New Manhattan Project for Energy Independence".

SEC. 2. DEFINITIONS.

In this Act—

- (1) COMMISSION.—The term "Commission" means the Commission established under section 7.
- (2) RESEARCH.—The term "research" includes research on the technologies, materials, and manufacturing processes required to achieve the goals described in section 3.

SEC. 3. GOALS.

- (a) IN GENERAL.—The purpose of this Act is to enable the achievement of each of the following goals:
- (1) VEHICLE FUEL EFFICIENCIES AND ALTERNATIVE FUEL SOURCES.—Development and manufacturing of a plug-in hybrid vehicle, alternative fuel vehicle, electric vehicle, hydrogen fuel cell vehicle, or other alternative technology vehicle—
- (A) that is not more than 10 percent more expensive than a comparable model vehicle of the same model year;
 - (B) with-
- (i) equal acceleration, horsepower, and top speed performance; and
- (ii) not more than 20 percent reduction in cargo space.

as compared to a comparable model vehicle of the same model year;

- (C) that meets or exceeds Federal safety standards;
- (D) that can travel at least 750 miles between refueling; and
- (E) in the case of a gasoline powered vehicle, that can travel at least 70 miles per gallon of gasoline.
- (2) GREEN BUILDINGS.—Develop and build an energy efficient residential or commercial building that—
- (A) uses no more than 50 percent of the energy of the average new building of similar size and type;
- (B) costs no more than 15 percent more to construct than the cost of a building of similar size and type; and
- (C) can be effectively reproduced in a variety of climate environments found in the United States
- (3) SOLAR POWER.—Construction of a large scale solar thermal power plant or solar photovoltaic power plant capable of generating 300 megawatts or more at a cost of 10 cents or less per kilowatt-hour when all capital and operating expenses are calculated into the cost.
- (4) BIOFUELS.—Development and production of a biofuel that, when mass produced, does not exceed 105 percent of the cost for the energy equivalent of unleaded gasoline when all capital and operating expenses are calculated into the cost of the biofuel.
- (5) CARBON SEQUESTRATION.—Development and implementation of a carbon capture and storage system for a large scale coal-burning power plant that does not increase operating costs more than 15 percent compared to a baseline design without carbon capture and storage while providing an estimated chance of carbon dioxide escape no greater than 1 percent over 5,000 years.
- $\begin{array}{lll} \textbf{(6)} & \textbf{NUCLEAR} & \textbf{WASTE.--} \textbf{Development} & \textbf{o} \\ \textbf{both---} & \end{array}$
- (A) a validated process for remediation of the radioactive waste form so it is no longer harmful to the health or welfare of the environment or individuals for a period to be determined by the Commission, which shall be not less than 5.000 years; and
- (B) a model that accounts for all the effects of nuclear waste in that process.
- (7) NUCLEAR FUSION.—Development of a sustainable nuclear fusion reaction capable of providing a large-scale (greater than 300 megawatts), sustainable source of electricity for residential, commercial, or government entities.
- (b) AMENDMENT OF GOALS.—The Secretary of Energy may amend a goal described in subsection (a) pursuant to a recommendation from the Commission under section 7(b)(5), or on his own initiative, if such amendment serves the purpose of achieving the goal of United States energy independence through the development of technologies that lead to the widespread adoption of improvements that increase energy supply or energy efficiency.

SEC. 4. SUMMIT.

- (a) IN GENERAL.—Not later than 60 days after the date of enactment of this Act, the President shall convene a summit that includes—
- (1) the principal advisors and directors of all programs in the Federal Government related to the achievement of the goals described in section 3:
 - (2) the members of the Commission; and
- (3) leading researchers at the Federal laboratories and representatives of private sector partners engaged in the production and manufacturing of technologies necessary to achieve the goals described in section 3.
- (b) PURPOSE.—The summit shall be for the purpose of reviewing the progress and prom-

ise for each of these technologies, the interrelationship of these technologies to each other, and additional funding resources needed to accelerate the progress of these programs toward achieving the goals described in section 3.

SEC. 5. GRANT PROGRAM.

- (a) IN GENERAL.—The Secretary of Energy, in consultation with the Secretary of Defense, the Secretary of Transportation, the Administrator of the Environmental Protection Agency, and other Federal agencies as appropriate, shall carry out a program consisting of a collaborative effort with industry, government, and academia to support research, development, demonstration, and commercial application activities related to achieving the goals described in section 3.
- (b) GRANTS.—Such program shall consist of grants to researchers, large and small businesses, National Laboratories, institutions of higher education, or any other qualified applicant, including veterans.
- (c) LIMITATION ON AMOUNT.—No grant shall be made under this section in an amount that exceeds 5 percent of the amount authorized under section 8(1) for prizes for the achievement of the same goal.
- (d) COST SHARING.—The Federal share of the costs of a project for which a grant is made under this section shall not exceed 15 percent.

SEC. 6. PRIZE PROGRAM.

- (a) PRIZE AUTHORITY.—
- (1) IN GENERAL.—The Secretary of Energy shall carry out a program to competitively award cash prizes in conformity with this section to advance the research, development, demonstration, and commercial application necessary to achieve the goals described in section 3.
- (2) ADVERTISING AND SOLICITATION OF COMPETITORS.—
- (A) ADVERTISING.—The Secretary shall widely advertise prize competitions under this section to encourage broad participation by researchers, large and small businesses, institutions of higher education, and any other qualified applicants, including veterans.
- (B) ANNOUNCEMENT THROUGH FEDERAL REGISTER NOTICE.—The Secretary shall announce each prize competition under this section by publishing a notice in the Federal Register. This notice shall include essential elements of the competition such as the subject of the competition, the duration of the competition, the eligibility requirements for participation in the competition, the process for participants to register for the competition, the amount of the prize, and the criteria for awarding the prize, which shall include, at a minimum, the achievement of one of the goals described in section 3.
- (3) ANNOUNCEMENT OF PRIZES.—The Secretary may not issue a notice required by paragraph (2)(B) until all the funds needed to pay out the announced amount of the prize have been appropriated.
 - (b) PRIZE CATEGORIES.—
- (1) CATEGORIES.—The Secretary of Energy shall establish a single prize under this section for each of the goals described in paragraphs (1) through (7) of section 3.
- (2) CRITERIA.—In establishing the criteria required by this section, the Secretary—
- (A) shall consult with other Federal agencies, including the National Science Foundation; and
- (B) may consult with other experts such as private organizations, including professional societies, industry associations, and the National Academy of Sciences and the National Academy of Engineering.
- (c) ELIGIBILITY.—To be eligible to win a prize under this section, an individual or entity—

- (1) shall have complied with all the requirements in accordance with the Federal Register notice required under subsection (a)(2)(B):
- (2) in the case of a private entity, shall be incorporated in and maintain a primary place of business in the United States, and in the case of an individual, whether participating singly or in a group, shall be a citizen of, or an alien lawfully admitted for permanent residence in, the United States; and
- (3) shall not be a Federal entity, a Federal employee acting within the scope of his employment, or an employee of a national laboratory acting within the scope of his employment.
 - (d) AWARD SELECTION.—
- (1) IN GENERAL.—The Secretary of Energy shall award prizes under this section on the basis of the criteria published in the notice required under subsection (a)(2)(B), after receiving the recommendations of the Commission under section 7(b)(3).
- (2) CONGRESSIONAL NOTIFICATION.—If the Secretary awards a prize under paragraph (1) in a manner that does not conform to the recommendations of the Commission, the Secretary shall transmit a report to the Congress explaining the reasons for such action.
- (e) INTELLECTUAL PROPERTY.—The Federal Government shall not, by virtue of offering or awarding a prize under this section, be entitled to any intellectual property rights derived as a consequence of, or direct relation to, the participation by a registered participant in a competition authorized by this section. This subsection shall not be construed to prevent the Federal Government from negotiating a license for the use of intellectual property developed for a prize competition under this section.
 - (f) LIABILITY.—
- (1) WAIVER OF LIABILITY.—The Secretary of Energy may require registered participants to waive claims against the Federal Government (except claims for willful misconduct) for any injury, death, damage, or loss of property, revenue, or profits arising from the registered participants' participation in a competition under this section. The Secretary shall give notice of any waiver required under this paragraph in the notice required by subsection (a)(2)(B).
 - (2) LIABILITY INSURANCE.—
- (A) REQUIREMENTS.—Registered participants in a prize competition under this section shall be required to obtain liability insurance or demonstrate financial responsibility, in amounts determined by the Secretary, for claims by—
- (i) a third party for death, bodily injury, or property damage or loss resulting from an activity carried out in connection with participation in a competition under this section; and
- (ii) the Federal Government for damage or loss to Government property resulting from such an activity.
- (B) FEDERAL GOVERNMENT INSURED.—The Federal Government shall be named as an additional insured under a registered participant's insurance policy required under subparagraph (A) with respect to claims described in clause (i) of that subparagraph, and registered participants shall be required to agree to indemnify the Federal Government against third party claims for damages arising from or related to competition activities under this section.
- (g) NONSUBSTITUTION.—The programs created under this section shall not be considered a substitute for Federal research and development programs.

SEC. 7. COMMISSION.

(a) ESTABLISHMENT.—There shall be established the New Manhattan Project Commission on Energy Independence.

- (b) FUNCTIONS.—The Commission shall—(1) not later than 1 year after the date
- (1) not later than 1 year after the date of enactment of this Act, submit to Congress and the President a report containing—
- (A) recommendations on steps that must be taken in order for the United States to achieve 50 percent energy independence within 10 years and 100 percent energy independence within 20 years; and
- (B) an assessment of the impact of foreign energy dependence on United States national security:
- (2) advise the Secretary of Energy on the design and operation of the grant program established under section 5;
- (3) make recommendations to the Secretary of Energy on the design and operation, including selection criteria, of the prize program carried out under section 6:
- (4) make recommendations to the Secretary of Energy selecting participants who have achieved a goal for which a prize will be awarded under section 6; and
- (5) submit recommendations to Congress for any amendments to make the goals described in section 3 more stringent, as appropriate because of changing circumstances, if such amendments serve the purpose of achieving the goal of United States energy independence through the development of technologies that lead to the widespread adoption of improvements that increase energy supply or energy efficiency.
- (c) Membership.—The Commission shall be composed of 13 members as follows:
- (1) The Under Secretary for Science of the Department of Energy.
- (2) The Administrator of the Research and Innovative Technology Administration.
- (3) The Director of the National Science Foundation.
- (4) The Chairman of the Federal Laboratory Consortium for Technology Transfer.
- (5) The President of the National Academy of Sciences.
- (6) 2 members appointed by the Speaker of the House of Representatives.
- (7) 2 members appointed by the minority leader of the House of Representatives.
- (8) 2 members appointed by the majority leader of the Senate.
- (9) 2 members appointed by the minority leader of the Senate.
- (d) TERMS OF MEMBERSHIP.—Each member of the Commission appointed under subsection (c)(6) through (9) shall be appointed for a term of two years, except that of the members first appointed, one under each of those paragraphs shall be appointed for a term of one year. A member of the Commission may serve after the expiration of the member's term until a successor has taken office.
- (e) VACANCIES.—A vacancy in the Commission shall not affect its powers but, in the case of a member appointed under subsection (c)(6) through (9), shall be filled in the same manner as the original appointment was made. Any member appointed to fill a vacancy for an unexpired term shall be appointed for the remainder of such term.
- (f) QUORUM.—Seven members of the Commission shall constitute a quorum.
- (g) MEETINGS.—The Commission shall meet at the call of the Chairman or a majority of its members.
- (h) COMPENSATION.—(1) Each member of the Commission shall serve without compensation.
- (2) While away from their homes or regular places of business in the performance of duties for the Commission, members of the Commission shall be allowed travel expenses, including per diem in lieu of subsistence, at rates authorized for employees of agencies under sections 5702 and 5703 of title 5, United States Code.

- (i) STAFF.—Subject to rules prescribed by the Commission, the Commission may appoint personnel as it considers appropriate.
- (j) APPLICABILITY OF CERTAIN CIVIL SERVICE LAWS.—The staff of the Commission shall be appointed subject to the provisions of title 5 United States Code, governing appointments in the competitive service, and shall be paid in accordance with the provisions of chapter 51 and subchapter III of chapter 53 of that title relating to classification and General Schedule pay rates.
- (k) EXPERTS AND CONSULTANTS.—The Commission may procure temporary and intermittent services under section 3109(b) of title 5. United States Code.
- (1) HEARINGS AND SESSIONS.—The Commission may, for the purpose of carrying out this Act, hold hearings, sit and act at times and places, take testimony, and receive evidence as the Commission considers appropriate.
- (m) POWERS OF MEMBERS AND AGENTS.—Any member or agent of the Commission may, if authorized by the Commission, take any action which the Commission is authorized to take by this section.

 (n) OBTAINING OFFICIAL DATA.—The Com-
- (n) OBTAINING OFFICIAL DATA.—The Commission may secure directly from any department or agency of the United States information necessary to enable it to carry out this Act. Upon request of the Commission, the head of that department or agency shall furnish that information to the Commission. (O) SUBPOENA POWER.—
- (1) IN GENERAL.—The Commission may issue subpoenas requiring the attendance and testimony of witnesses and the production of any evidence relating to any matter under investigation by the Commission. The attendance of witnesses and the production of evidence may be required from any place within the United States at any designated place of hearing within the United States.
- (2) FAILURE TO OBEY A SUBPOENA.—If a person refuses to obey a subpoena issued under paragraph (1), the Commission may apply to a United States district court for an order requiring that person to appear before the Commission to give testimony, produce evidence, or both, relating to the matter under investigation. The application may be made within the judicial district where the hearing is conducted or where that person is found, resides, or transacts business. Any failure to obey the order of the court may be punished by the court as civil contempt.
- (3) SERVICE OF SUBPOENAS.—The subpoenas of the Commission shall be served in the manner provided for subpoenas issued by a United States district court under the Federal Rules of Civil Procedure for the United States district courts.
- (4) SERVICE OF PROCESS.—All process of any court to which application is made under paragraph (2) may be served in the judicial district in which the person required to be served resides or may be found.
- (p) FEDERAL ADVISORY COMMITTEE ACT.— Section 14 of the Federal Advisory Committee Act (5 U.S.C. App.) shall not apply to the Commission

SEC. 8. AUTHORIZATION OF APPROPRIATIONS.

- There are authorized to be appropriated to the Secretary of Energy—
- (1) for the period encompassing fiscal years 2010 through 2019— $\,$
- (A) \$500,000,000 for awarding the prize under section 6 for meeting the goal described in section 3(1);
- (B) \$250,000,000 for awarding the prize under section 6 for meeting the goal described in section 3(2);
- (C) \$250,000,000 for awarding the prize under section 6 for meeting the goal described in section 3(3);
- (D) \$1,000,000,000 for awarding the prize under section 6 for meeting the goal described in section 3(4);

- (E) \$1,000,000,000 for awarding the prize under section 6 for meeting the goal described in section 3(5);
- (F) \$1,000,000,000 for awarding the prize under section 6 for meeting the goal described in section 3(6);
- (G) \$10,000,000,000 for awarding the prize under section 6 for meeting the goal described in section 3(7); and
- (H) \$10,000,000,000 for carrying out the grant program under section 5; and
- (2) such sums as may be necessary for carrying out this Act for subsequent fiscal years.

The SPEAKER pro tempore. Pursuant to House Resolution 587, the gentleman from Virginia (Mr. FORBES) and a Member opposed each will control 15 minutes.

The Chair recognizes the gentleman from Virginia.

Mr. FORBES. Madam Speaker, I yield myself such time as I may consume.

Madam Speaker, first of all, I would like to thank the Rules Committee for allowing me to bring this amendment by making it in order. No matter what the motivation or the intentions, I appreciate that opportunity. And I want to make it clear this amendment is not an addition. It is an amendment in the nature of a substitute that would replace the current bill on the floor.

Madam Speaker, I would also like to make clear that this is not a Democratic amendment, obviously, and I think we will hear from the Democratic leadership in a few minutes to make that clear. It's not a Republican amendment, and we will probably hear from the Republican leadership to that extent in just a few moments. But it is an amendment that's overwhelmingly supported by the American people.

I never cease to be amazed at how day after day we come in this body, and as we enter this great Chamber, we somehow put on our adversarial robes and we pick up our adversarial clubs and then we go about our business. But, unfortunately, the adversarial process often leads us to be more concerned with scoring points than we are with winning solutions. In this debate I have listened to today there are good men and women on both sides, and there are smart men and women on both sides, and they all believe they are right. But there are limits to the good ideas that we can bring into this one Chamber about energy.

The reality is if you're from a coal area, the people back at home know you're going to be fighting for coal. If you're from a gas area, you're going to be fighting for gas. And if you're from an area with a lot of wind or solar technology, that's what you're going to be certain it's going to solve our energy problem. But even the majority can't always be right, and that's why only 33 percent of the people in America approve of what Congress is doing currently today.

This amendment, Madam Speaker, is the new Manhattan Project for energy independence. A lot of people have talked about doing something like this. Today we have an opportunity to do it. And it has a novel approach. It says that instead of the 435 of us on this floor bringing our ideas and imposing them on the American people, what we do is bring together a commission of the brightest men and women in America, from government, from the private sector, from academics, and we have them create in the next year a plan of energy for this country that would get us 50 percent independent from foreign oil in 10 years and 100 percent in 20 years or tell us why we can't get there.

□ 1700

And this amendment also realizes that in this bill on the floor today, we are essentially redistributing another \$800 billion of taxpayer money because we think we know what's best for Americans. The new Manhattan Project amendment would set seven goals for energy independence. They are goals that almost everybody agrees we need to reach energy independence: doubling vehicle fuel efficiency, cutting home and business energy usage in half, having solar power work as cheaply as coal, making biofuels work as cheaply as gasoline, safely and cheaply storing carbon emissions from our coal-fired plants, safely storing nuclear waste and producing electricity from nuclear fusion reactions. Then through grants and prizes it energizes an entire Nation to reach those goals through their innovation and their ideas and their imagination. But, Madam Speaker, perhaps the most important thing this amendment does is it restores American competitiveness by sending out two signals.

First of all, it sends a signal out across this country to the American people that we trust them and America is coming back on its competitive edge. And, secondly, it sends a shot across the bow of every country in the world, telling them we are not going to surrender, that we are going to come back, and we are going to compete, and we are going to win on a fair playing field, and we are going to restore a competitive advantage that is going to lead us for the next 50 years.

And then finally, Madam Speaker, it invigorates a whole generation of Americans to go into math and science and be a part of our energy solution for years to come.

And so with that, Madam Speaker, I hope that we will pass this amendment, and I reserve the balance of my time.

Mr. WAXMAN. Madam Speaker, I rise in opposition to this proposal.

The SPEAKER pro tempore. The gentleman from California is recognized for 15 minutes.

Mr. WAXMAN. I yield myself such time as I might consume.

This amendment is more of the same from the Republicans. After 8 years of failed energy policies, the Republican answer to our energy problems is to do more research and to provide people with prizes for good ideas.

Well, during the last 8 years, the average American family has seen its en-

ergy cost increase by nearly \$2,800 a year. Those are increases in gasoline prices, home heating, electricity bills. American families cannot afford the same failed policies.

Now, I like the idea of having good, innovative approaches to our challenges. I don't mind giving people awards if they come up with good ideas, but I think good ideas come up with market incentives and competition and rewarding people for good ideas with something more than a good ribbon to pin on their chest.

This amendment strikes the whole bill and substitutes this idea of giving prizes. Could you imagine, giving prizes. Why didn't you give out prizes in the last 8 years, and maybe our energy problems would have been solved if we had given out more prizes for good ideas.

But the bill before us, the American Clean Energy and Security Act, is a comprehensive energy policy. It will create new clean-energy jobs, increase our energy independence and dramatically cut pollution. We are talking about 1.7 million new jobs.

This bill will save 240 million barrels of oil each year. That's oil we don't have to import from the Middle East. And this bill is going to help consumers, because the energy efficiency provisions alone will save consumers \$750 per year by 2020.

This bill before us makes a landmark investment in the future of the country by providing \$190 billion through 2025 to increase our efficiency and deploy cutting edge energy technologies. We provide for renewable energy, coal with carbon capture and storage, nuclear power and advance technologies, electric vehicles, smart grid transmission, energy efficiency. I could go on.

This substitute amounts to a grant program and a competition with prizes for good ideas. There is no comparison between the two.

The bill before us is a real solution to our very real energy challenges. The Republican amendment simply fails to rise to the challenge.

I urge its defeat and reserve the balance of my time.

Mr. FORBES. Madam Speaker, the gentleman mentions those 8 years of bad ideas. That's why these similar concepts were endorsed in the campaign by President Obama, Senator McCAIN, Senator Clinton and also individuals like Newt Gingrich.

I would like to yield 1 minute to the distinguished gentleman from Illinois (Mr. Schock).

Mr. SCHOCK. Madam Speaker, I woke up this morning to the front page of my hometown paper, which read, Peoria's unemployment rate crosses double digits for first time in two decades.

At a time when our communities across this country are losing work and out of jobs, we in this body are passing a piece of legislation that will only do more, only put more people out on the street and in the unemployment lines.

This bill, on the average, will add to Illinois residents the cost equal to 1 month of their electricity bill. In essence, we are adding a 13th month to their utility bill. It doesn't matter whether my constituents are senior citizens living on a fixed income, families, businesses, we are asking them to pay more at a time when they have less.

Now, there is not a person in this room that doesn't want more of the same, more green energy, more wind, more nuclear, more solar power. But I, for one, believe we can get there without putting the conventional methods of energy out of business.

The Forbes amendment will do just that. It is creative ideas, incentivizing the behaviors that we want as opposed to what we don't that we need.

I urge a "yes" vote on this amendment and a "no" on the cap-and-tax bill.

Mr. WAXMAN. Madam Speaker, I would yield 1 minute to my cosponsor of the legislation that's before us. My name came first, his second, because I am older and I am chairman of the full committee. He is chairman of the subcommittee. But the real author of the legislation, he has worked on this problem for many, many years, is ED MARKEY.

Mr. MARKEY of Massachusetts. Thank you, Mr. Chairman.

With our bill, we will take back America's position as the technological leader, give back money to consumers by lowering energy bills, send back the millions of barrels of oil we import from foreign dictators every day, and we will export wind turbines and solar panels that say "Made in America" instead of continuing to import millions of barrels of oil a day that say "Made by OPEC."

This bill has the ambition of the Moon landing, the moral imperative of the Civil Rights Act, and the scope of the Clean Air Act all wrapped up in one. All we are hearing here this evening are the same discredited policies from the past that have gotten us into this economic national security and environmental situation that we live with today.

Vote "no" on this substitute and vote "aye" for the bill that we are considering. The gentleman from California has done an excellent job in bringing us to this point.

Vote "no" on this substitute.

Mr. FORBES. Madam Speaker, I would like to yield 1 minute to the distinguished gentleman from South Carolina (Mr. INGLIS).

Mr. INGLIS. I thank the gentleman for yielding.

This is not the time for a tax increase. It's not the time for another Wall Street trading scheme, and it's not the time to burden American manufacturing. It is the time to inspire innovation through amendments like Mr. FORBES' and to come together to find a solution that breaks our addiction to oil, that creates new energy jobs, and that cleans up the air.

We can get there if we stop this capand-trade, do some fresh thinking, and then come together for America's sake around a revenue-neutral tax swap. It would start with a tax cut on FICA taxes, then in equal amount, we would shift the tax onto carbon. We could then apply that tax to imported as well as domestically produced goods. Just like the fair tax, we would just be changing what we tax.

We would be swapping a FICA tax cut for a similar tax on carbon. The accountability of a revenue-neutral tax swap would cause old fuels to lose out to new fuels. We would be building nuclear power plants, and free enterprise would deliver the triple play of this American century.

Ladies and gentleman, let's support the Forbes amendment for innovation, stop the cap-and-trade, and solve the problem.

Mr. WAXMAN. Madam Speaker, I would like to inquire of the gentleman from Virginia (Mr. FORBES) who is controlling the time, how many speakers do you have? We have two on our side.

Mr. FORBES. I would say to the gentleman, we have three, maybe four more speakers.

Mr. WAXMAN. We will reserve the balance of our time.

Mr. FORBES. Madam Speaker, can you tell us how much time we have remaining.

The SPEAKER pro tempore. The gentleman from Virginia has 9 minutes remaining. The gentleman from California has 11 minutes remaining.

Mr. FORBES. Madam Speaker, I would like to yield 1 minute to the gentleman from Virginia (Mr. GOODLATTE).

Mr. GOODLATTE. I thank the gentleman for yielding and commend him for offering this amendment, which is a great opportunity for our colleagues on the other side of the aisle to stop putting the cart before the horse and suppressing our traditional sources of energy, oil, natural gas, coal. Doesn't even do anything for nuclear power, and yet you want to push us into a direction where the technology doesn't yet exist.

This legislation, this amendment, this substitute is exactly what you can need. You can vote for this, put us on a Manhattan Project to develop the new green technology that we need in this country, to do it in a way that is commercially feasible, to do it in a way that can rise up to replacing the 95 percent of our sources of energy that we have in our country this day, that you can push down in this legislation.

And if you were to vote for that and against the underlying bill, we would be putting this country on a course in a bipartisan fashion that would lead our country to exactly what we need. Unlike the Markey-Waxman approach, this amendment does not pick winners or losers in technology. It allows the ingenuity of American citizens to create the technology that will make our country energy independent.

I urge my colleagues to support the gentleman's substitute.

This amendment focuses on making our country energy independent through the innovation of American individuals and businesses, not through government mandates and intrusion. Unlike the Waxman-Markey approach, this amendment does not pick winners and losers in technology but allows the ingenuity of American citizens to create the technology that will make our country energy independent while at the same time reducing carbon emissions.

Most importantly, the Forbes Amendment won't raise the cost of living to American consumers or hinder the ability for American businesses to compete. The technology that a new Manhattan Project could spur has the ability to rebuild our economy and make it stronger than ever before.

The Forbes Amendment is the right approach to make our country energy independent while reducing carbon emissions. I encourage all my colleagues to vote for this amendment.

Mr. FORBES. Madam Speaker, I would like to yield 1 minute to the distinguished gentlelady from Minnesota (Mrs. BACHMANN).

Mrs. BACHMANN. I thank the gentleman from Virginia. I support the gentleman's amendment.

We know, Madam Speaker, that this national energy tax will cost the American people \$2 trillion. We know that. We know this will result in a loss of 2.5 million jobs every year for the American people. We know that. We know this will result in a reduced standard of living for Americans. We know that. What is the point and what's the benefit?

But what is worse than this is the fact that now, because of this underlying bill, the Federal Government will virtually have control over every aspect of lives for the American people. It is time to stand up and say, We get to choose. We choose liberty or we choose tyranny. It's one of the two.

The underlying bill represents the tyranny and the intervention of the Federal Government. Mr. FORBES' amendment represents liberty for the American people.

It's our choice. What will we choose today? Will we choose liberty or will we choose tyranny?

I choose Mr. FORBES' amendment.

Mr. FORBES. Madam Speaker, I yield 1 minute to the distinguished gentleman from Texas, the ranking member of the Energy and Commerce Committee, Mr. BARTON.

Mr. BARTON of Texas. Madam Speaker, I rise in strong support of the Forbes amendment. This is not a comprehensive substitute, because the majority party, which controls the Rules Committee, ruled out of order and didn't make it in order on the floor either the Republican leadership comprehensive substitute or the Energy and Commerce Committee comprehensive substitute.

So they did rule in order Mr. Forbes' substitute. And I will guarantee you, this is better than the base bill.

It doesn't wreck the economy. It does include, and you can count on the inge-

nuity of the American people, through an incentives package, to unleash the productivity and innovativeness of our folks in the United States to find new solutions to our energy and environmental problems.

But it doesn't have this boondoggle cap-and-trade program that will wreck the economy, deindustrialize America, and make us a second-rate economic power. It is not a comprehensive substitute, but it is darn better than the base bill.

Vote for it.

Mr. FORBES. Madam Speaker, can you tell me how much additional time we have?

The SPEAKER pro tempore. The gentleman from Virginia has 6 minutes remaining. The gentleman from California has 11 minutes remaining.

Mr. FORBES. Madam Speaker, I yield myself 5 minutes.

□ 1715

Mr. FORBES. Madam Speaker, I yield myself 5 minutes.

Madam Speaker, we have heard a lot today about how these ideas of a new Manhattan Project were stale ideas of this party. I stated at the beginning that, unfortunately, we get so tied up in this Chamber in our adversarial process that all we're concerned about is how many points we take from each other.

The reality is that a project like this, the new Manhattan Project, or you can call it a "poppy project," were concepts that were talked about by President Obama during the campaign, by Senator Clinton during the campaign, by Senator McCain during the campaign and, as I mentioned earlier, by former Speaker Newt Gingrich, and many other people.

They're concepts that have been approved by 77 percent of the American people. And what they do is substitute for taxation of the American people the concept of innovation and trusting the ideas of the ingenuity and imagination of people across America.

We talked about what this bill can do if we reach just one of these goals. Just one of these goals, it could change and save us as much as \$100 billion. But, most of all, Madam Speaker, this trusts the American people to do what they always do, and that is find a way to win, if we don't quit before they have a chance to win. And it sends a message to them at a time when they're back on their heels and they need some wins, that we trust that they, with their imagination and innovation, can do things that this body can't do and can't dictate to them.

Perhaps it was best said by Mr. Friedman in a New York Times article that he wrote—and I don't agree with everything he says, but I agree with this. He said, I want an energy bubble. I want so many people throwing crazy dollars at every idea and every garage that we have a hundred thousand people trying a hundred thousand things, five of which might work and two

might be the next green Google. But I don't want a Manhattan Project of 12 people in Los Alamos. I want it to be like the IT revolution: everyone becoming a programmer. Only, in this case, it's everyone becoming a green innovator. What IT was to the eighties and nineties, ET, energy technology, will be to the early 21st century.

Madam Speaker, this amendment gives us that opportunity. This amendment will birth that ability for Americans to create the energy solutions that we need as we go forward into the next several decades and to give our children and our grandchildren the competitive edge to compete in a world economy.

With that, Madam Speaker, I reserve the balance of my time.

Mr. WAXMAN. Madam Speaker, I'm pleased at this time to yield 1 minute to the majority leader so that he may speak on this amendment and the legislation that's before us, the gentleman from Maryland (Mr. HOYER.)

Mr. HOYER. I thank the gentleman for yielding. Mark this day, June 26, 2009. My colleagues, we have an opportunity to serve in a historic session of the Congress of the United States. We have an opportunity to take action that will make a major difference in the security and independence and environment of our globe as well as our country.

We have been given the privilege by our fellow citizens to serve at a time of historic change and meeting challenges that were the subject of this past Presidential campaign. And in this past Presidential campaign there were three major candidates. You could perhaps name more, but there were two, certainly, at the end.

And the campaign of Senator McCain and Senator Obama had something in common. They were both for comprehensive cap-and-trade legislation, the candidate you supported and the candidate I supported. They put an agenda of action before the American people that they would pursue if they were elected President of the United States. Only one could be elected, but presumably both would have followed through on their commitment, as this President has, and we are today.

This is a transformative moment. This is a moment to build a clean-energy future for our country. This is a moment to create jobs in America. This is a moment to take on, at long last, a defining challenge of our time—global warming. I know my colleagues can seize this moment, if they only will

The substitute talks about a Manhattan Project. I think the sentiments expressed in the substitute are good ones. The objectives are good ones. But Americans voted for action, not additional studies. America voted to make a difference, not to make a point. America voted for the change we could believe in. That's what this bill represents

I know they can look back from a future in which America is independent of foreign oil. There has been much talk about taxes. Tragically, almost every debate we have on this floor devolves into: We're going to raise your taxes

My fellow Americans know about having their expenses raised and because the foreign potentates who hold us hostage because they provide so much of our energy gave us a new tax at the gas pump—and every American remembers it. Why? Because we have not taken the action necessary to become energy independent.

And so our gasoline prices at the pump for my commuters who drive sometimes an hour or an hour and a half to get to work to support their families paid an additional \$2.50 per gallon tax imposed by those from abroad who provide us energy.

This bill is about making sure that foreign interests cannot raise the expenses of our families. This bill is about making sure that we in America provide our energy, efficient energy, clean energy, energy that will not bring our globe to a heating process that will drown out what the Navy calls the littorals, the seashores, where most of our people live.

My colleagues, this bill, the American Clean Energy and Security Act, is a true turning point. This is one of the historic actions we will take not just in this Congress, but as Members of Congress, for however long a tenure we may have.

It's a complex bill because we face a complex problem. But we can sum up its outcome simply: new American jobs, less dependence on foreign energy, a reduction in the carbon pollution that causes global warming.

How does this bill accomplish those goals? Among its most important provisions are a requirement that utilities meet 20 percent of electric demand through renewable sources and energy efficiency by 2020.

I'm old enough to remember the lines of the seventies when you waited in line an hour or two or three to put gasoline in your car so you could get your child to school, get to work, pick up your child from child care. America should have acted, but we did not. Today, we're going to act.

Significant new investments in renewables, carbon capture and sequestration, electric vehicles, and cuttingedge energy research, all of that is in this bill to take action, change that America can believe in. And energy savings standards for buildings, appliances, and industries.

This bill also creates a clean-energy bank to fund promising energy projects across America. Investment in America's ingenuity and innovative entrepreneurial spirit, that's what this bill is about. That is why it's so important to America.

It invests in high-tech transmission lines to build the essential foundation for a more efficient grid. That is essential if the energy we produced can be delivered to those who need it in businesses and in homes.

New transmission lines comprised of superconducting cable and other efficient wires will carry more power within existing rights-of-way with less land use is included. The result will be a more secure, environmentally friendly grid. That's what this bill does.

I worked with the chairman and Representative INSLEE to ensure that those transmission provisions were included because they are such an important part of a more cost-effective, energy efficient future that our country needs.

Of course, the bill also includes the reduction of our carbon emissions by 17 percent by 2020. Some would like to do more. Some would like to do less. But we have reached a compromise. That is the legislative process. And it is compromise that can pass this House and pass that Senate and be signed by the President and become law. And make progress. That's what our responsibility is. And then, more than an 80 per reduction by 2050.

We can fight global warming with the same kind of market-based cap-and-trade solution that was so effective in combating acid rain at minimal cost in the 1990s. Global warming threatens every one of us. There was disagreement on that for a long period of time—some 7 years in the Bush administration, until the last year, President Bush, our President, decided that, yes, global warming was in fact a challenge that must be met.

This is not a partisan issue. This is an issue on which we have reached consensus. Global warming threatens every one of us. It will affect the kind of lives our children will lead and the kind of prosperity our country and our world will enjoy.

To those who complain about the cost of the bill, I answer that we are all paying the cost of carbon emissions already, and certainly, as I pointed out earlier, paying the cost of being hostage to those abroad who provide our energy.

The longer we wait to act, the more we will pay year after year after year. But if we take action now, we can get jobs, growth, clean energy, and energy independence for less than the price of a postage stamp a day for each of us, according to the EPA and CBO.

And with this bill passed and signed, the United States will finally be able to argue persuasively and credibly for global action on a challenge that knows no borders. We understand that if the Chinese do not act, or the Indians don't act, the air that they belch will soon come to this continent and our children and families will be at risk.

This is a global problem. But America is the leader. America must lead. America must set the example. This bill does exactly that.

At the same time, action on global warming will send a powerful job-creating price signal to the private sector, spurring innovation in every part of the renewable energy economy. Jobs, jobs, jobs. That is one of the reasons

why the U.S. Climate Action Partnership, a business coalition dedicated to fighting climate change has argued that "the way we produce and use energy must fundamentally change both nationally and globally"—and that this coming change represents an excellent opportunity for economic growth.

And that is why another coalition of 19 businesses, including the Pacific Gas and Electric Company, Duke Energy, National Grid, H.P., Starbucks, and Nike wrote to President Obama that this bill "will drive investment into cost-saving, energy saving technologies and job-creating innovation, create the next wave of jobs in the new energy economy and will provide the predictability we need to plan for future business success."

Those aren't my words. Those are the words of leaders in the corporate community in America who know something about innovation, enterprise, and free markets.

It has long been understood that acting on global warming is a moral necessity as well as an intellectual necessity. But now, more and more of us are realizing that it makes powerful economic sense as well.

Madam Speaker, let me as an aside thank you for your presiding at this time on this historic bill and for presiding over so much legislation in such a fair and effective fashion.

□ 1730

This House will miss your service, but the country will enjoy your continuing service. I thank you, Madam Speaker.

Madam Speaker, a future of clean energy is well worth the price. A Republican governor, inaugurated in the State of Maryland, in his inaugural address said that the cost of failure far exceeds the price of progress.

The cost of failure for the last three to four decades has cost this country. Progress will be far less expensive than failure. My children, my grandchildren and the generations to come will be either the beneficiaries of our stewardship or the victims of our neglect.

I urge my colleagues this day to reject this substitute, not because it is bad for the words that it incorporates, but because its effect would be to stop action so desperately needed by this country and this globe.

I urge my colleagues, defeat this substitute, pass this bill, and take this historic opportunity for our children, our grandchildren and generations yet unborn.

Mr. FORBES. Madam Speaker, may I request how much time is remaining?

The SPEAKER pro tempore. The gentleman from Virginia has $3\frac{1}{2}$ minutes remaining. The gentleman from California has 10 minutes remaining.

Mr. FORBES. Madam Speaker, I vield myself 1½ minutes.

Madam Speaker, the distinguished minority leader just said that Americans must lead; and lead, they must. He also indicated that the cost of their failure would be passed on to our children and grandchildren.

As one of only 17 Members in this body that has voted against every bailout bill and stimulus bill we have passed, I ask the American people who watch here, what has been the enormous cost of our failure in spending all of those dollars, and what have you got from it? Also, Madam Speaker, I would say this—that the American people can lead. They're not stupid. Only 33 percent of them approve of what we're doing.

We have a choice. Only in this body could they believe that we could say words like. We're going to create jobs by destroying jobs. We're going to reduce your taxes by increasing your taxes. We're going to come in here with all your parochialism, and we can create a plan for you that is far better than the brightest experts on energy could do by having this amendment. We prefer taxation over innovation of the American people. Or we'll have a bill like this that only sets a 20 percent goal in 11 years for renewable energy, where in this bill we set a 50 percent goal of dependence from foreign oil in 10 years and 100 percent in 20 years. And, finally, that in this bill we know we're going to spend \$800 billion that probably won't work.

In our bill and this amendment, Madam Speaker, we know that we only pay \$24 billion, and we only have to pay it when we get the results.

With that, I reserve the balance of my time.

Mr. WAXMAN. Madam Speaker, I understand that our side has the right to

The SPEAKER pro tempore. The gentleman is correct.

Mr. WAXMAN. I reserve the balance of my time.

Mr. FORBES. Madam Speaker, I yield the balance of my time to the distinguished minority leader, the gentleman from Ohio (Mr. BOEHNER).

The SPEAKER pro tempore. The gentleman from Ohio is recognized for 2 minutes.

Mr. BOEHNER. Let me thank my colleague for yielding.

Madam Speaker, I congratulate you on your upcoming marriage and your new job. All of us on the Republican side of the aisle thank you for your service to this institution and your service in the Chair. Good luck to you.

My colleagues, we've been through a very difficult time in our economy. We've had the great economic shocks of last fall, and we've seen unemployment climbing month after month after month. It is now at some 9.4 percent.

Earlier this year we passed a 1,100-page bill that no one read. It was supposed to be about putting the American people back to work again. It was supposed to be about stimulating our economy. And all we heard during that debate was about jobs, jobs and jobs. It's pretty clear that what the bill really ended up being was nothing more

than spending, spending and more spending, because since that bill passed, some 1.7 million Americans have lost their jobs. So when we look at the legislation that continues to go through here, the American people are seeing an awful lot of spending, an awful lot of money going to government, but they're not seeing new jobs.

Now we come to what I believe is the most profound piece of legislation that has come to the floor of this House in the last 100 years. It's hard to say in the first 6 months of the new Congress that this could be the defining vote and the defining bill for this Congress, but I really, truly believe that this is the defining bill.

The problems that this bill attempts to go after are the issues of climate change and cleaning up our air, and, secondly, to build a new alternative energy industry in the United States. Those are really the two issues. Well, I guess a third issue would be jobs. Those are the goals that this bill attempts to go after. But when you look at the structure that's being built, it defies anyone's imagination to believe that the Federal Government could create such an elaborate process to deliver on those three goals.

I've got a chart here that goes through all of the agencies involved, all of the structures that are created under this bill. It's all being done, of course, by the Environmental Protection Agency. They are at the center of this.

But if you look at all of the different agencies involved, you will see that we've got the Federal Energy Regulatory Commission involved. We've got the United States Department of Agriculture that's going to be involved. The Internal Revenue Service will be engaged in this bill as well. The Department of the Treasury. I wish I could tell you what FWS was, but somebody could probably tell me. We have the Commodity Futures Trading Commission that's going to be involved in helping to regulate this. The National Oceanic and Atmospheric Administration, the Weather Service, basically. The Department of Health and Human Services is going to be involved in putting this together. The Department of State will play a big role in making sure that we get cleaner air and green energy. We've got the Department of Energy, of course, the Department of Labor, the U.S. Army Corps of Engineers, the Bureau of Indian Affairs, and the Bureau of Land Management. All these Federal agencies are going to take part in trying to put this bill into action.

But that's not all. Not even close. We've got the Offsets Integrity Advisory Board. We also have a Carbon Markets Oversight Interagency Working Group that is going to try to help control who gets these carbon credits and who doesn't, how they can be traded and how they can't, and where in the world these offsets are going to be.

They don't have to be in the United States. We're going to see billions of

American tax dollars being shipped around the world. Whether it's replanting forests in other parts of the world, they're going to help clean up our air. I'm sure our constituents want our money being shipped overseas to plant trees.

But that's not all. That's not all. It's not even close. We've got the Consumer Refunds Fund that is going to be outlined here. We've got the International Reserve Allowance Program here. How about the domestic offset providers? We've got the offset traders and the national offset providers. We've got the Clean Vehicle Technical Advisory Board. We have a Carbon Capture Board. And it goes on and on and on.

This elaborate government structure that will cost the American people several trillion dollars over the next 10 years, all in an effort to clean up our air, will help build a new alternative energy industry in the United States and help create jobs in our country. I don't believe there are hardly any people in America who believe that this giant government bureaucracy is going to be able to deliver on the three goals that you outline.

And it's not just the cost, and it's not just the bureaucracy. Listen, there's not a Member in this body that doesn't want to improve the air quality in our country and around the world. There isn't a Member in this body who doesn't believe that speeding up the development of alternative sources of energy isn't good for America. No one. There's complete agreement on that.

But do we need to go through all of this? Do we need to have a national energy tax on every person in America who would drive a car, who would flip on a light switch or who would buy an American-made product, because virtually every American-made product has an awful lot of energy in it.

That's not enough. If you look at this bill and you look at the analysis of this bill, you'll see that two-and-a-half million jobs on average will be lost each and every year over the next 10 years as a result of this bill. Some of those people happen to reside in my district, in Middletown, Ohio, where AK Steel is headquartered. They make steel the old-fashioned way. They bring in iron ore, coal and limestone. You get it hot enough, you've got steel. The cost of their steel will increase 30 to 40 percent if this bill were to pass. And at a time when we're trying to help the American automobile industry get back on its feet, the last thing they're going to do is pay 30 or 40 percent more for their

So what are they going to do? They're going to bring it in from China, they'll bring it in from India, who are not burdened under this regulatory scheme, nor are they burdened under our current environmental regulations. So what happens is, high-energy jobs in America are going to get shipped overseas at exactly the wrong time.

The American people sent us here to help this economy, to get them back to work. This is the biggest job-killing bill that has ever been on the floor of the House of Representatives, right here, this bill, and I don't think that's what the American people want.

But if our goals are to clean up the air, to build a alternative energy business in the United States, a thriving one, and to create jobs, there's a better way to do this, and it's the all-of-the-above strategy that we've been talking about in this Chamber for nearly a year. That is to say, we need to have more alternative sources, whether they be solar, wind, geothermal.

We can produce those additional types of energy and help renew them. But, in the meantime, America needs energy to grow our economy, so we need to have more drilling for oil and gas in the United States. There's no question about it. We need to increase the supply of American-made energy so that we bring down the price.

What we do in our bill is, we take all the royalties from the development of additional oil and gas reserves in the United States and we plow it back into renewable sources of energy. As a result, our bill puts more money into renewables and speeding up the development of renewables at a faster pace than the bill on the floor of the House today.

That's not enough. We need to do all of the above. We need to develop clean coal technology. We need to be serious about nuclear energy. There's nothing in this bill before us that's going to allow us to produce nuclear energy in any kind of a quick way, or, frankly, any at all. But we all know it's the cleanest source of energy that we can have in the United States. So why shouldn't we do all of the above?

Because here's what all-of-the-above does for us: It gives us cleaner air. It gives us lower energy prices. It really does move us quickly away from our dependence on all the foreign sources of oil that we have to rely on today. And it will do more in a very simple way than this big complex bureaucracy that is being outlined in this bill.

Why can't we do all of the above? Why do we have to try to establish this giant structure that attempts to put some cap in, but really doesn't, when we can do something simple that will help lower prices for Americans while cleaning up the air and moving us to alternative sources of energy. No, that's not what we're dealing with here today.

And if all of this wasn't enough, I woke up this morning and realized that last night at 3:09 a.m., a 300-page manager's amendment was dropped into the hopper, at 3:09 a.m.

□ 1745

I have spent most of the day trying to look at this 309-page bill and trying to come up with and understand what this 309-page amendment to the 1,200-page bill really does? As I started to go through this, I didn't get past the first page, where on page 16, line 5 strike

1992 and insert 1988, and on line 13 strike 1992 and insert 1988. This appears to deal with the hydropower, and I'm trying to figure out what is the impact of this date change? Nowhere in this manager's amendment can I find out what the impact of that is.

Then we get to page 2, not from components of the National Wilderness Preservation System, Wilderness Study Areas, Inventoried Roadless Areas or old growth stands and late-successional stands. So does this mean that renewable biomass is not defined by what it is but rather where it comes from? And why was this change made at 3:09 a.m. this morning?

We get to page 9, the President shall ensure that, of the total amount of electricity Federal agencies consume in the United States during each calendar year, the following percentage shall be renewable electricity.

We are going to mandate to every Federal agency how much electricity they buy that comes from renewable sources. And in here we have this year, 2012, 6 percent, 2013, 6 percent, 2014 we go to 9½ percent, 2016 we go to 13 percent. 2018 we go to 16½ percent. And 2020 through 2039, 20 percent of the electricity that goes into every Federal agency has to come from renewable sources. Do we have any idea whether this is possible? I can't find the answer here.

On Page 10 it says, contracts for renewable energy, a contract for the acquisition of electricity generated from a renewable energy resource for the Federal Government may be made for a period of not more than 20 years. Twenty-year contracts. What if the price of renewable energy goes down? Are taxpayers going to be stuck with a contract that is written today as opposed to what that contract could be negotiated for 10 years from now? I can't tell, because there is no answer here.

Or we get on page 12, renewable biomass. The term "renewable" means any of the following. And it goes through of this language. Of course, there is nothing renewable in a National Wilderness Preservation System or a Wilderness Study Area or Inventoried Roadless Areas or old growth stands or late-successional stands except for dead, severely damaged or badly infested trees. Wasn't this the same language that we had on page 2? And why is it being repeated again? I can't tell as I read through this.

So we get to page 16, so that the vehicle or engine is capable of alternative fuel. First we are going to require now every car sold in America, it has to have an engine that is capable of operating on an alternative fuel. So what if you have a car that doesn't operate on a renewable fuel? Are we going to buy the car back from the American people? Are we going to reimburse them for their cost? I can't tell, because, again, this was dropped at 3:09 a.m., and no one probably has had a chance to read it.

How about on page 24, there are authorized to be appropriated such sums

as may be necessary to carry out this paragraph. It sounds like a blank check to me.

Or on page 26, this section applies only to States located in the Western Interconnection and does not apply to States located in the Eastern Interconnection, to the States of Alaska or Hawaii or ERCOT. So are we going to have different rates for different parts of the country under this amendment that was filed at 3:09 a.m. this morning?

Then we get to Page 30. The Federal Energy Regulatory Commission shall act as the lead agency for purposes of coordinating all applicable Federal authorizations and related environmental reviews. So now we have FERC is in charge of coordinating environmental reviews, as I read this. Is that what Greenpeace demanded be part of this bill? Then we get to page 34. Page 34, it says not later than 1 year after August 8. 2005—

PARLIAMENTARY INQUIRIES

Mr. WAXMAN. Madam Speaker, I have a parliamentary inquiry.

The SPEAKER pro tempore. The gentleman will suspend.

Does the gentleman yield for a parliamentary inquiry?

Mr. BOEHNER. I would be happy to yield to the gentleman.

Mr. WAXMAN. The Republican leader was yielded the balance of the time, which I think amounted to around 4 or 5 minutes. He has talked for around 20. I know we have this "magic" minute that gives leaders a lot of extra time to speak, but I'm just wondering if there is some limit under the rules on the time that a leader may take, even though the time yielded was not 20 or 30 minutes.

The SPEAKER pro tempore. It is the custom of the House to hear the leaders' remarks.

Mr. WAXMAN. Further parliamentary inquiry.

The SPEAKER pro tempore. Does the gentleman yield for a parliamentary inquiry?

Mr. BOEHNER. I will be happy to yield to the gentleman.

Mr. WAXMAN. I know it is the custom of the House to give a little extra latitude. Is there any outside limit to the amount of time a leader might take? And do we have historical records that might be broken tonight? Or is this an attempt to try to get some people to leave on a close vote?

The SPEAKER pro tempore. It is the custom of the House to hear to the leaders' remarks.

Mr. BOEHNER. Reclaiming my time, the gentleman has had his 30 years to put this bill together, and the House is going to spend a whopping 5 hours debating the most profound piece of legislation to come to this floor in 100 years. And the chairman has the audacity to drop a 300-plus-page amendment in the hopper at 3:09 a.m. this morning. And so I would ask my colleagues, don't you think the American people expect us to understand what is in this bill before we vote on it?

So we get to page 34. Not 1 year after August 8, 2005. Now, wait a minute. One year later? One year after August of 2005? Wasn't that 3 years ago? I'm just trying to understand what the gentleman has in his amendment.

Then we get to page 36, high efficiency gas turbine research, development and demonstration. Now, I'm trying to figure out who inserted this broad new section of the bill that is covered nowhere in the underlying bill.

Then we get to page 39, \$65 million for each of the fiscal years 2011 through 2014, \$65 million for 3 years. And who is going to get this money? I can't tell in this amendment.

And as we go through this, page 41, determine any geographic area within the contiguous United States that lacks a Federal power marketing agency. Because, you know, we can't move power around the country without a Federal power marketing agency. We do it today, but now we have to have a new government agency to do this. We are doing it already.

Or same page, 41, the establishment of any new Federal lending authority, including authorization of additional lending authority for existing Federal agencies, not to exceed \$3.5 billion per geographic area identified in subsection (a)(1). This is \$3.5 billion in loans for each geographic area, but we don't know how many geographic areas are included or how many billions in total we are really talking about.

How about on page 42, any source of funds, including Federal funds provided through the Robert T. Stafford Disaster Relief and Emergency Assistance Act, shall qualify as the building owner's 50 percent contribution. Now, let me make sure I get this straight. So now you can use federal money for non-Federal matching requirements. How much is all of this going to cost?

Or on page 45—remember now, this is the amendment. This is not the bill. This is the amendment filed at 3:09 a.m. On Page 45, this section shall apply only to construction beginning after the date of enactment of this Act. For those of you who don't know it, all of California housing standards are now going to be imposed on every American community. You don't have the right to have your own building standards in your community or in your State. Hell, no, the Federal Government is going to tell you what they are. And guess what? We all get to have California standards. Who is going to pay the price for those new homes? How are we going to do affordable housing when we are pushing up the cost of houses? And while I'm at it, we have to have an energy rating for every home in America. In this bill, we require every home to have an energy rating. And if you are going to sell your house, guess what? You have to have a review, bring people in, have them check out your windows, your appliances, your hot water heater, your door, make sure that your house is energy efficient. And guess what if it

isn't? You have got to bring it up to standards before you can sell it. Now what kind of bizarre notion is that?

Well, we get to page 46 at the bottom, a plan for local governmental actions to be taken to establish and sustain local building code enforcement administration functions, without continuing Federal support, at a level at least equivalent to that proposed in the grant application. Do you all get that? It doesn't explain it. But here is what it is. The Federal Government is going to mandate all of these new standards on every house built in America. It is going to cost your local building department all kinds of money to enforce this and to revise their code. And when the money runs out, we are going to allow them to apply for a grant to the United States Government. I'm sure my constituents will love that.

Page 48, each building code enforcement department receiving a grant under subsection (a) shall empanel a code administration and enforcement team consisting of at least one full-time building code enforcement officer, a city planner, and a health planner or similar officer.

Now I have some big towns in my district. Hamilton, Middletown and Westchester can probably afford this new enforcement. But I can take you to Chickasaw, Mercer County, in my district. They don't have one full-time person that works for the village. Not one. Look at the mandate on every city and village in America right here in this bill.

So that we are not only going to tell you what the codes are going to be. But we are going to tell you how many people you need to hire to enforce this in this section of this code. See, we actually did take time, most of today, trying to understand what was in here.

How about on page 53, solar energy systems building permit requirements for receipt of community development block grants. So what are we doing here to amend the community development block grant program? Are we going to impose global warming requirements on all the cities who get CDBG monies from us? That is what it appears to say to me.

□ 1800

Or on page 54, any metropolitan city or urban county, during such fiscal year the cost of any permit or license, for construction or installation of any solar energy system for any structure, that is required by the metropolitan city or urban county, or by any other political subdivision of such city or county complies with paragraph (2).

So now we are going to tell them what to charge for their building permits as well in every city in America.

Then we get to page 56. The Secretary of Energy shall issue regulations to prohibit any private covenant, contract provision, lease provision, homeowners' association rule or bylaw.

Let me read this again: The Secretary of Energy here in Washington,

DC, shall issue regulations to prohibit any private covenant, contract provision, lease provision, homeowners' association rule or bylaw. Just for those of you who didn't think there might not be a lot of government bureaucracy in this bill.

We get to page 63. The amount necessary to change consumer behavior to purchase water efficient products and services. So now—let me read this again and make sure that I am right. The amount necessary to change consumer behavior to purchase water efficient products and services. So we are going to provide the American people with money in order to change their behavior so they will buy goods and services that they don't want to buy.

I wonder how much that will cost.

Page 64, subsection 2, to create jobs through the retooling and expansion of manufacturing facilities to produce clean energy technologies to create jobs. So how many jobs is this going to create? Will it replace the 2.5 million jobs that will be lost each year as a result of this bill? I can't tell.

Now going to page 68, the Secretary shall award grants to States to establish revolving loan funds to provide loans to small and medium-sized manufacturers. So who is going to compensate manufacturers for putting them out of business with more loans?

Let me get to page 70. In particular, where mass layoffs have resulted in a precipitous increase in unemployment. So we have a provision in here that recognizes that millions of American jobs are going to be lost; but don't worry, don't worry, we are going to extend your unemployment. Most of my constituents who are unemployed don't want more unemployment. They want a job, and this is going to kill them.

I hate to do this to all of you, I do. I hate to do this, but when you file a 300-page amendment at 3:09 in the morning, somebody needs to work on it, and I worked on it today and I want to make sure that everybody understands what is in this 300-page amendment.

Page 76. Certification by Hollings Manufacturing Extension Center. A Hollings Manufacturing Extension Center or other entity designated by the Secretary for purposes of providing certification under clause so and so and so and so.

So now, why are we singling out one company, one company, and where did this company come from?

Further down the page on page 76, Repayment upon relocation outside the United States. In general. If a person receives a loan under paragraph (1) to finance the cost of reequipping, expanding, or establishing a manufacturing facility as described in subsection (c)(1)(A) or to reduce the energy intensity of a manufacturing facility and such person relocates the production activities of such manufacturing facility outside the United States.

So we recognize here that we are going to force companies to take their jobs and ship them overseas. It is right here. It is right here in the bill, and I am glad it is recognized by my colleagues.

Then we go to page 80, to support manufacturers in their identification of and diversification to new markets. Another admission that the bill before us is going to kill millions of small businesses and even tens of millions of jobs, so we have to have an effort in here to support manufacturers in their identification and diversification into new markets.

Then we get to page 83. Consumer Behavior Research. The Secretary of Energy is authorized to establish a research program to identify the factors affecting consumer actions to conserve energy and make improvements in energy efficiency. Through the program the Secretary will make grants to public and private institutions of higher education to study the effects of consumer behavior on total energy use.

Do we really need to spend government money to do a study on why people don't want to pay twice the cost and get half the quality?

Page 87, the development of a global framework for the regulation of greenhouse gas emissions from civil aircraft that recognizes the uniquely international nature of the industry and treats commercial aviation industries in all countries fairly.

Will this include China and India? I can't tell from the amendment that we have in front of us.

On page 92, we want to make sure that the structure have appropriate electrical outlets with the facility and capacity to recharge a standard electric passenger vehicle, including an electric hybrid vehicle, where such vehicle would normally be parked.

Oh, no, we are not just going to take the California standard and impose it on every community in America, oh, no. Now we are going to tell you where the electric outlets are going to be and how big they have to be to charge a hybrid vehicle.

I just don't understand whether this would apply to nursing homes where there are no cars.

Oh, here we are, page 96. Existing structures. For existing structures, a reduction in energy consumption from the previous level of consumption for the structure, as determined in accordance with energy audits performed both before and after any rehabilitation or improvements undertaken to reduce such consumption, that exceeds the reduction necessary for compliance with the energy efficiency standards under subsection (a) then in effect and applicable to existing structures.

So not only are we going to tell every community in America what the building codes are going to be, what the efficiency standards are going to be, but if you make changes to your house, you have to have another study done to show how much increase in energy efficiency was gained. That will help sell a lot of new houses and a lot of old ones.

Page 97, for manufactured housing, energy star rating with respect to fixtures, appliances, and equipment in such housing, as such standard or successor standard is in effect for purposes of this section.

Please, is there anything that we are not regulating in this bill?

How about page 105. Waive or modify any existing statutory or regulatory provision that would otherwise impair the implementation or effectiveness of the demonstration program under this section, including provisions relating to methods for rent adjustments, comparability standards, maximum rent schedules, and utility allowances; notwithstanding the preceding provisions of this paragraph, the Secretary may not waive any statutory requirement relating to fair housing, non-discrimination, labor standards, or the environment.

Now in implementing this demo program, rising rent can be dismissed out of hand, but labor standards or the environment cannot, as I read it.

Let me go to page 107. No amounts made available under the American Recovery and Reinvestment Act of 2009 can be used to carry out the demonstration program under this section.

So if no stimulus funds can be used, and the majority claims stimulus funds are for job creation, is this demo going to create one new job? I don't think so.

Page 112, additional credit for Fannie Mae and Freddie Mac housing goals for energy-efficient and location-efficient mortgages. Oh, yeah. Oh yeah, everybody listen up here. It is not enough that we have huge problems with Fannie Mae and Freddie Mac, they are at the core of the credit meltdown we have had in our country, but we are going to give them a little more money so they can have goals for energy-efficient and location-efficient mortgages. Now we are going to tell Fannie Mae and Freddie Mac what kind of mortgages we are going to have in the marketplace.

How about page 113. Supports housing that complies with enhanced energy efficiency and conservation standards, or the green building standards, under section 284 of such Act.

This is the Federal Government using Fannie Mae and Freddie Mac to impose new Federal building codes and standards across the country.

Let me go to page 114. The Federal Housing Enterprises Financial Safety and Soundness Act of 1992, as amended, by the Federal Housing Finance Regulatory Reform Act of 2008.

If this is supposed to be about energy, why are we further bogging it down with trying to solve problems for Fannie Mae and Freddie Mac?

Page 115, the term "energy-efficient mortgage" means a mortgage loan under which the income of the borrower, for purposes of qualification for such loan, is considered to be increased by not less than \$1 for each \$1 of savings projected to be realized by the borrower as a result of cost-effective energy-saving designs.

I'm sure that will create a lot of jobs. And then we get to page 141, the Cranston-Gonzalez National Affordable Housing Act is amended. Why are we amending the Cranston-Gonzalez National Affordable Housing Act? thought we were doing an energy bill here.

Page 142, use of building materials and methods that are healthier for residents of the housing, including the use of building materials that are free of added known carcinogens that are classified as Group 1 Known Carcinogens by the International Agency for Research on Cancer.

We are going to outline building materials as well, it appears.

Then we have a grant program to increase the sustainability of low-income community development capacity. We are going to provide loans, grants, or predevelopment assistance to eligible community development organizations or qualified youth service and conservation corps to carry out energy efficiency improvements.

I just want to know if ACORN would

qualify for these grants.

And on page 146, we have another authorization here. There are authorized to be appropriated to the Secretary to carry out this section \$10 million for each of the fiscal years 2010 through 2014.

So all the Members know, we have spent all of the year's income by April 16th. Everything we spend here, we have to borrow from our kids and grandchildren and the Chinese and everybody else who wants to loan us money.

Page 148, 25 points, in the case of any proposed plan, or portion thereof, consisting of new construction. So now we have a new government formula to determine winners and losers when it comes to the building of new houses.

Page 149, at the bottom, for purposes of this paragraph, the Secretary shall identify rating systems and levels for green buildings that the Secretary determines to be the most likely to encourage a comprehensive and environmentally sound approach to ratings and standards for green buildings.

So the government is going to decide what is green, not the American people.

In identifying these green rating systems, the Secretary has to take into consideration the ability and availability of assessors and auditors to independently verify the criteria and measurement of metrics at the scale necessary to implement this paragraph.

She also has to improve indoor and outdoor environmental quality through enhanced indoor and outdoor air quality, thermal comfort, acoustics, outdoor noise pollution, day lighting, pollutant source control, sustainable landscaping, and use of building system controls and low- or no-emission materials, and such other criteria as determined by the Secretary.

So why are we giving the Secretary all of this authority under this Act to determine virtually everything?

□ 1815

The Secretary may, by regulation, adopt and apply, for purposes of this paragraph, future amendments and supplements to, and editions of, the national Green Communities criteria checklist, any standard or standards that the Secretary has determined to be substantially equivalent to such checklist, and the green building ratings systems.

So a lot of power for the new Secretary without any congressional oversight.

Now I really hate to do this, but when you file a 300-page amendment at 3:09 a.m., the American people have a right to know what's in this bill and they have a right to know what we're voting on.

Let me get to the bottom of page 155: Revision of Appraisal Standards. Each Federal financial institutions regulatory agency shall, not later than 6 months after the date of the enactment of this Act. revise its standards for the performance of real estate appraisers in connection with federally related transactions under the jurisdiction of the agency to comply with the requirement under the amendments made by paragraph (1) of this sub-

So now we have to retrain every anpraiser in America so that they understand this law, so that they know how to properly appraise the value of someone's property. And they need to meet the requirements established pursuant to subsection (f) for qualifications regarding consideration of any renewable energy sources, or energy efficiency.

So every appraiser is not only going to be retrained but now we're going to have to send them all to school.

Let me get to page 157: The Appraisal Subcommittee—another new part of the bureaucracy-shall establish requirements for State certification of State certified real estate appraisers and for State licensing of State licensed appraisers, to ensure that appraisers are qualified to consider, in determining the value of a property, any renewable energy sources for, or energy efficiency or energy-conserving improvements or features of, the propertv.

Interesting.

And the Secretary—on page 158 shall require the Housing Assistance Council to encourage each organization that receives assistance from the Council with any amounts made available from the Secretary to provide that any structures and buildings developed or assisted under projects, programs, and activities funded with such amounts complies with the energy efficiency standards under section 284(a) of this subtitle.

More power for a lot of unelected bureaucrats.

Then on page 160, the middle of the page, it says:

In General. The Secretary shall use amounts in the Fund to provide loans to States and Indian tribes to provide

incentives to owners of single-family and multifamily housing, commercial properties, and public buildings to provide renewable energy sources, and it goes on and gives a whole long list. But there is no appropriation in here for it.

And then on page 164 we authorize another \$5 billion and there is no idea where this money comes from.

Page 165. Green Banking Centers. It's not going to do houses and commercial properties and multifamily housing. Now we're going to have Green Banking Centers.

The Federal banking agencies shall prescribe guidelines encouraging the establishment and maintenance of "green banking" centers by insured depository institutions to provide any consumer who seeks information on obtaining a mortgage, home improvement loan, home equity loan, or renewable energy lease with additional information

Are you kidding me? I've heard of blackmail, but now I know what greenmail really is.

On page 170 at the top of the page, section 299F.

Government Accountability Office Reports on Availability of Affordable Mortgages.

Really. After we drive the price of every mortgage up in America, we're going to have them do a report on affordable mortgages. Guess whatthey're going to be a hell of a lot more expensive.

Ŷou get to page 173.

The Secretary of Housing and Urban Development may make commitments to a guarantee under this section and may guarantee the repayment of the portions of the principal obligations of eligible mortgages that are used to finance eligible sustainable building elements for the housing that is subject to the mortgage.

So now we're not only going to guarantee the mortgage but we're going to guarantee the improvements to the property as well.

Page 180. And I would direct all of your attention if you have a copy of this to section 3 of that page:

The full faith and credit of the United States is pledged to the payment of all guarantees issued under this section with respect to principal and interest.

The term "green portion" means, with respect to an eligible mortgage, the portion of the mortgage principal referred to in subsection (b)(2) that is attributable, as determined in accordance with regulations issued by the

So we've got a new government program and we're going to guarantee this with the full faith and credit of the United States.

Then on page 184:

On April 1 (or a later date established by the administrator under subsection (j)) of the calendar year in which a term offset credit expires, the owner or operator holds for purposes of finally demonstrating compliance, an allowance or a domestic offset credit.

I read it because I cannot tell you what that means.

On page 190 at the bottom of the page it talks about algae.

And on page 189 we've got Renewable Biomass. This is the third definition of Renewable Biomass that we have just in the manager's amendment, much less in the bill.

This caught my attention, at the bottom of page 191, section 3, for vintage year 2012.

Are we talking about wine?

Then we get to page 208. Carbon Derivative Markets. Now we've already heard enough about credit default swaps, but I think most of you know that under this section, the Commodity Exchange Act is amended by striking "or an agricultural commodity" and inserting "an agricultural commodity, or any emission allowance, compensatory allowance, offset credit, or Federal renewable electricity credit established or issued under this Act."

So now we're going to let those governed under the CFTC trade these credits with others around the world.

And on page 209 it talks about the effect of derivatives regulatory reform legislation. Upon passage of this legislation that includes derivatives, regulatory reform, sections 351, 352, 354, 355, 356 or 357 shall be repealed.

Any idea of the derivatives regulations that we're repealing in this bill? You probably didn't know we were doing that.

Then on page 210:

To prevent an increase in greenhouse gas emissions in countries other than the United States—I presume that means countries like India and China—to induce foreign countries, and, in particular, fast-growing developing countries, to take substantial action with respect to their greenhouse gas emissions.

India and China have made it perfectly clear to every one of us that they have no interest and will not go down this path.

It further goes on to ensure that the measures described in subpart 2 are designed and implemented in a manner consistent with applicable international agreements to which the United States is a party.

The very structure of the border provisions, however, makes this impossible to achieve. The Wall Street Journal said the other day and suggested that this bill really could start a trade war and that if we begin to try to impose our bureaucracy on other countries, we could just have that.

Let me get to page 225. Distribution of Emission Allowance Rebates. Further down the page, it says, Shall be pursuant to the entity's indirect carbon factor as calculated under subsection (b)(3).

Can anybody tell me how to calculate an indirect carbon factor or what an indirect carbon factor is?

Then we get to page 226. That more than 85 percent of United States imports for that sector are produced or manufactured in countries that have met one of the criteria in that section, then the 10-year reduction schedule set forth in this subsection shall begin in the next vintage year.

So now we're going to try to control imports from countries based on what they're doing with regard to their energy policy.

Use of Other Data to Determine Factor, page 231. Where it is not possible to determine the precise electricity emissions intensity factor for an entity using the methodology in clause (i). In what instances would it not be possible to determine what that is?

Then we get to page 233:

In each eligible industrial sector every 4 years, using an average of the four most recent years of the best available data. For purposes of the lists required to be published no later than February 1, 2013, the Administrator shall use the best available data for the maximum number of years, up to 4 years, for which data are available.

Why every 4 years? What's this data used for? Then it goes on: The Administrator shall limit the average direct greenhouse gas emissions per unit output, calculated under paragraph (4), for any eligible industrial sector to an amount that is not greater than it was in any previous calculation under this subsection.

So what is the cost of this provision? Or on page 234: The Administrator shall use data from the greenhouse gas registry established under section 713. How much is this going to cost?

Promoting International Reductions in Industrial Emissions, page 236. Congress finds that for the purposes of this subpart, as set forth in section 761(c), can be most effectively addressed and achieved through agreements negotiated between the United States and foreign countries.

It is the policy of the United States to work proactively under the United Nations Framework Convention on Climate Change, and in other appropriate fora, to establish binding agreements, including sectoral agreements, committing all major greenhouse gas-emitting nations to contribute equitably to the reduction of global greenhouse emissions.

The bottom line of all of this is all pain for United States citizens and no gain.

Then we get to page 237: The President shall provide a notification on climate change described in paragraph (2) to each foreign country the products of which are not exempted under section 768

This is less than a fig leaf here. They're trying to pretend that this notification will satisfy the consultation required by the WTO rules. It won't end there and it's going to result in retaliation against United States exports.

Then we get further down on that page: Requesting the foreign country to take appropriate measures to limit the greenhouse gas emissions in those countries

So if they're really nice they won't have to but if we can, we can force them to adopt our bizarre regulatory scheme.

Then we get to page 238. United States Negotiating Objectives with Respect to Multilateral Environmental Negotiations.

□ 1830

So here we are telling the administration what their objectives are going to be as they negotiate environmental issues with other countries around the world.

Presidential Reports, page 239: Not later than January 1, 2017, and every 2 years thereafter, the President shall submit a report to Congress on the effectiveness of the distribution of emission allowance rebates under subpart 1 in mitigating carbon leakage in eligible industrial sectors.

Let me go to page 260: Modification of Earned Income Credit Amount For Individuals With No Qualifying Children.

Why does this bill neglect middle class families in America? Why is it that we're only going to help some people who will qualify for the earned income credit for individuals with no qualifying children?

Further down here it says: the Secretary determines experienced a reduction in purchasing power as a result of the provisions of this act.

That's a flat-out admission that every American is going to pay more for all of their energy. And it goes on and on and on.

Ladies and gentlemen, does this give you some idea of why the American people think their Congress is out of touch? The idea that the Federal Government can create this giant bureaucracy to try to control how much CO_2 gets into atmosphere.

We know that if we were to do our all-of-the-above energy strategy, we'd see renewable sources of energy on the scene, available, producing jobs more quickly than under the underlying bill. We know that under our bill, you could actually have nuclear energy plants being built, cleaning up the air at a much faster rate than the underlying bill

But there's really a big underlying difference between our approach and the approach of my colleagues on the other side of the aisle, and that is trusting the American people. If we give the American people the right incentives, they'll make the right decisions. But that's not what we have on the floor today. What we have on the floor today is typical big government. And the fight that we have between the two sides of the aisle really boils down to one word: It boils down to freedom. The freedom to allow the American people to live their lives without all of these extra taxes and all of this bureaucracy.

And I would just say to my colleagues, I did my best to try to get through the 300-page amendment that

was filed at 3:09 in the morning. Obviously somebody knew this was coming, but it wasn't filed until 3:09 this morning.

This is not the way we should be doing legislation. The American people expect more of us. And you know what? They deserve a lot more from us.

So I would say to my colleagues let's not go down this path of increasing taxes on every single American. Let's not go down the path of moving millions of jobs to China, India, and other countries around the world. Let's trust the American people. Let's give them our all-of-the-above energy act and allow America to flourish, to allow jobs to flourish, and, most importantly, to allow freedom to flourish.

Mr. WAXMAN. Madam Speaker, the minority leader was yielded 2½ minutes. Could you tell us how much time he consumed?

The SPEAKER pro tempore. The gentleman used a customary amount of time.

Mr. WAXMAN. Well, Madam Speaker, the 2½ minutes was extended to over an hour, and this is from the same party that had a 15-minute roll call extended into 3 hours while they tried to twist the arms of their own people.

Madam Speaker, to close the debate, I wish to yield the balance of my time, and I presume it will not be an hour or two, to our distinguished Speaker because of whose leadership we have the attempt to do something that the Republicans neglected, and that's to help our country deal with our energy problems, Speaker NANCY PELOSI.

Ms. PELOSI. I thank the gentleman for yielding.

Madam Speaker, I want to join those who have sung your praises as a distinguished presider over hundreds of hours of debate in the House of Representatives. Your service here, your leadership here will long be remembered and be an inspiration to us. Katherine will be very missed, but now she's off to college. Thank you, ELLEN TAUSCHER, for being such a great chairwoman and presider over the House of Representatives.

Madam Speaker, I also wish to acknowledge the leadership of our chairmen, who so ably brought this important legislation, this historic and transformational legislation, to the floor: Chairman Waxman of the Energy and Commerce Committee, Chairman Markey of the Energy Security and Climate Change Committee, Chairman Rangel of the Ways and Means Committee, and Chairman Peterson of the Agriculture Committee. We thank them for their leadership and for giving us this opportunity today.

Madam Speaker, no matter how long this Congress wants to talk about it, we cannot hold back the future. And so in order to move on with the future, I want to yield back my time, submit my statement for the RECORD, and urge my colleagues to vote for this important legislation.

And when you do, just remember these four words for what this legislation means: jobs, jobs, jobs, and jobs.

Let's vote for jobs.

Madam Speaker, today the House has an opportunity to pass historic and transformative legislation: the American Clean Energy and Security Act.

I would like to acknowledge the authors of the legislation: Chairman WAXMAN of the Committee on Energy and Commerce and Chairman MARKEY of the Select Committee on Energy Security and Climate Change.

I would also like to acknowledge: Chairman COLLIN PETERSON of the Agriculture Committee for bringing the priorities of America's farmers to this bill and Chairman RANGEL who helped ensure that this bill is fiscally responsible and fully paid for.

And I would like to acknowledge the many staff who worked so hard on this legislation.

In his inaugural speech, President Obama called upon us to, "harness the sun and the winds and the soil to fuel our cars and run our factories."

One week and one day later, we did just that. We passed the American Recovery and Reinvestment Act—the single largest investment in history in clean energy—with over \$69 billion for new investments in clean energy.

Shortly thereafter, we passed the Omnibus spending bill, with significant investments in advanced energy research and the labs and equipment necessary to perform the next generation of advanced energy research.

We passed the Budget, which included a 10% increase in investment in clean energy and energy efficiency.

This was building upon the work of the last Congress: The Farm Bill was the first in history to include a real investment in energy independence, with over \$1 billion to leverage renewable energy industry investments in new technologies and new feedstocks.

And the historic and bipartisan energy bill signed by President Bush increased fuel efficiency standards for vehicles for the first time in 30 years and redirected this country's energy policy toward clean, renewable energy.

Creating a new energy policy and addressing the global climate crisis is: Energy independence is: a national security issue by reducing our dependence on foreign oil; an environmental and health issue; it is a moral issue; and it is an economic issue for America's families.

There are four words that can describe this bill: jobs, jobs, jobs, and jobs.

Madam Speaker, we debate this legislation as millions of Americans are struggling in this economy. This is our moment to transform our economy and create jobs.

This is the moment when we can unleash private sector investment in clean energy to create millions of new jobs and make America the global innovation leader. It will promote clean energy technology—made in America. It will put America in the lead in the global competition.

As we rebuild America in a green way, we will create jobs that cannot be shipped overseas. We are creating a framework in which innovation can occur and that gives business certainty that we are moving to a clean energy economy. That will unleash innovation, investment, and venture capital to drive new technologies into the market.

America's farmers will fuel America's energy independence. They will do so with carbon-off-setting crops and forests, and biofuel and wind farms to repower America.

This historic legislation is the product of months of consensus building to achieve an effective and affordable transition to a clean energy future.

I am so pleased that the diverse coalition supporting this bill includes everyone from: The Union of Concerned Scientists to the Evangelical Climate Initiative and the U.S. Conference of Catholic Bishops; from the business community to labor organizations, from the U.S. Steelworkers of America; from the U.S. Conference of Mayors to members of the U.S. Climate Action Partnership, a coalition of business and nonprofit groups.

Today, we have an opportunity to lead America toward an effective and affordable transition to a clean energy future. It is a moment we cannot afford to miss. We have a responsibility to create jobs and make America more secure, protect the health of our citizens, and honor our moral responsibility to our children and our future generations.

Vote to create jobs. Let's put this Congress on the right side of the future. Vote yes on the American Clean Energy and Security Act.

I urge my colleagues on both sides of the aisle to protect God's beautiful creation by supporting this legislation.

ORGANIZATIONS EXPRESSING SUPPORT FOR HOUSE PASSAGE OF THE AMERICAN CLEAN ENERGY AND SECURITY ACT

ELECTRIC UTILITIES AND ENERGY COMPANIES

Duke Energy
Exelon
PG&E Corporation
FPL Group
Austin Energy
National Grid
PNM Resources
Avista
NRG Energy Inc.
PSE+G
Edison Electric Institute

Edison Electric Institute ConEdison Constellation Energy Entergy Austin Energy Renewable Fuels Assn.

MANUFACTURING, INDUSTRY AND CORPORATE

GE
Dow Chemical
Dow Corning
National Semiconductor
HP
Business Council on Sustainable Energy
Solar Power Industries

Alcoa John Deere Alstom Power

Johnson & Johnson Siemens

Rio Tinto BP Solar Symantec

Applied Materials

eBay Levi Strauss Nike

Starbucks Aspen/Snowmass

Seventh Generation Clif Bar

Kleiner Perkins Caufield & Buyers Calpine Corp. Genpower BluewaterWind

LABOR

Steelworkers Boilermakers Communications Workers Laborers International Services Employees

Utilities Workers Union **Building and Construction Trades**

FARM AND AGRICULTURE

National Farmers Union American Farmland Trust Growth Energy

COMMUNITY, FAITH AND ENVIRONMENT

U.S. Conference of Mayors Environmental Defense Fund League of Women Voters National Parks Conservation Assn. National Wildlife Federation National Resource Defense Council The Wilderness Society American Institute of Architects World Resources Institute

Pew Center on Global Climate Change

The Nature Conservancy Sierra Club

HipHop Caucus

Center for American Progress

Latino Coalition

Union of Concerned Scientists

National Congress of American Indians World Wildlife Fund

American Public Health Association Defenders of Wildlife

League of Conservation Voters

Pew Environment Group National Audubon Society Renewable Fuels Assn.

American Chemical Society

American Rivers Clean Water Action

Earthjustice

Environment America

International Forum on Globalization Oxfam Oceana

Physicians for Social Responsibility Jewish Council for Public Affairs Izaak Walton League of America Baptist Pastors and Theologians

Woods Hole Research Center/20 eminent

scientists and leaders

United Nations Foundation

The Episcopal Church

United States Conf. of Catholic Bishops

Catholic Relief Services

Evangelical Climate Initiative

National Council of Churches

National Assn. of Clean Air Agencies

Trout Unlimited

United Methodist Church-General Board of Church & Society

Evangelical Lutheran Church in America Climate Communities/ICLEI-Local Governments for Sustainability USA

Mr. WOLF. Madam Speaker, our country has always been the world's innovation leader, and I believe innovation and not taxation must be the answer to the energy challenges we face.

That's why I support the Forbes amendment which would substitute this bill with a new Manhattan project for energy independence, bringing together the best and brightest minds of a new generation of scientists, engineers and researchers in a unified national challenge just as we did with the original Manhattan project in World War II.

Like the first project, which was launched to ensure the security of our country, today our national security depends on our ability to produce reliable, cost-effective and environmentally friendly sources of energy to fuel our economy.

This project would award significant cash prizes to the first person or entity to achieve set energy goals, such as doubling car fuel efficiency to 70 mpg while keeping vehicles affordable, cutting home and business energy usage in half, making solar power work at the

same cost as coal, making the production of biofuels cost-competitive with gasoline, safely and cheaply storing carbon emissions from coal-powered plants, safely storing or neutralizing nuclear waste, and producing usable electricity from a nuclear fusion reaction.

Just like the challenge of the space program to put a man on the moon in a decade, I believe by working together, a new Manhattan project could transform our nation's energy security. But the "cap-and-trade" plan the House considered is the wrong solution at the wrong time. We can do better and I think this alternative is a better solution.

The SPEAKER pro tempore. The question is on the amendment in the nature of a substitute offered by the gentleman from Virginia (Mr. FORBES).

The question was taken; and the Speaker pro tempore announced that the noes appeared to have it.

RECORDED VOTE

Mr. FORBES. Madam Speaker, I demand a recorded vote.

A recorded vote was ordered.

Forbes

Aderholt

Fleming

The vote was taken by electronic device, and there were—ayes 172, noes 256, not voting 5, as follows:

[Roll No. 476]

AYES-172

Miller (MI)

Young (FL)

Akin Fortenberry Miller, Gary Alexander Franks (AZ) Moran (KS) Altmire Frelinghuysen Myrick Gallegly Austria Neugebauer Bachmann Gerlach Nunes Gingrey (GA) Bachus Olson Barrett (SC) Gohmert Paul Barrow Goodlatte Paulsen Bartlett Granger Pence Barton (TX) Graves Petri Biggert Guthrie Pitts Bilbray Hall (TX) Platts Bilirakis Harper Poe (TX) Bishop (UT) Hastings (WA) Posey Blackburn Hensarling Putnam Blunt Herger Radanovich Hoekstra. Boehner Rehberg Holden Bonner Reichert Bono Mack Hunter Roe (TN) Boozman Inglis Rogers (AL) Boren Issa Boustany Jenkins Rogers (KY) Brady (TX) Johnson (IL) Rogers (MI) Rohrabacher Brown (SC) Johnson, Sam Brown-Waite Jones King (IA) Rooney Ros-Lehtinen Ginny Buchanan King (NY) Roskam Burgess Burton (IN) Kingston Royce Kirk Scalise Kline (MN) Buyer Schmidt Calvert Lamborn Schock Camp Lance Sensenbrenner Campbell Latham Sessions Cantor LaTourette Shadegg Cao Latta Shimkus Lee (NY) Capito Carney Lewis (CA) Simpson Carter Linder Smith (NE) Cassidy Lucas Smith (TX) Luetkemeyer Castle Souder Chaffetz Lummis Stearns Lungren, Daniel Coble Terry Coffman (CO) Thompson (PA) Mack Cole Thornberry Conaway Manzullo Tia.hrt. Crenshaw Marchant Tiberi Culberson Marshall Turner McCarthy (CA) Davis (KY) Upton McCaul Deal (GA) McClintock Walden Dent Wamp Diaz-Balart, L. Diaz-Balart, M. McCotter McHenry Waters Dreier McHugh Whitfield Wilson (SC) Duncan McKeon Wittman McMorris Ehlers Rodgers Wolf Emerson Young (AK) Mica Miller (FL) Fallin

Ackerman Adler (NJ) Andrews Arcuri Baird Baldwin Bean Becerra Berkley Berman Berry Bishop (GA) Bishop (NY) Blumenauer Boccieri Boswell Boucher Boyd Brady (PA) Braley (IA) Bright Broun (GA) Butterfield Capps Capuano Cardoza Carnahan Carson (IN) Castor (FL) Chandler Childers Clarke Clav Cleaver Clyburn Cohen Conyers Cooper Costa Costello Courtney Crowley Cuellar Cummings Dahlkemper Davis (AL) Davis (CA) Davis (IL) Davis (TN) DeFazio DeGette Delahunt DeLauro Dicks Dingell Doggett Donnelly (IN) Dovle Driehaus Edwards (MD) Edwards (TX) Ellison Ellsworth Engel Eshoo Etheridge Farr Fattah Filner Foster Foxx Frank (MA) Fudge Garrett (NJ) Giffords Gonzalez Gordon (TN) Gravson Green, Al Green, Gene

Brown, Corrine Connolly (VA) Griffith Grijalva Gutierrez

Honda Hoyer Inslee Israel Jackson (IL) Jackson-Lee (TX) Johnson (GA) Johnson, E. B. Jordan (OH) Kagen Kaniorski Kaptur Kennedy Kildee Kilpatrick (MI) Kilroy Kind Kirkpatrick (AZ) Kissell Klein (FL) Kosmas Kratovil Kucinich Langevin Larsen (WA) Larson (CT) Lee (CA) Levin Lewis (GA) Lipinski LoBiondo Loebsack Lofgren, Zoe Lowey Luján Lynch Maffei Maloney Markey (CO) Markey (MA) Massa Matheson Matsui McCarthy (NY) McCollum McDermott McGovern McIntvre McMahon McNerney Meek (FL) Meeks (NY) Melancon Michaud Miller (NC) Miller, George Minnick Mitchell Mollohan Moore (KS) Moore (WI) Murphy (CT) Murphy (NY) Murphy, Patrick Murphy, Tim Murtha Nadler (NY) Napolitano Neal (MA) Nye Oberstar

Hall (NY)

Halvorson

Harman

Heinrich

Heller

Higgins

Himes

Hinchey

Hinojosa

Hirono

Hodes

Holt

Abercrombie

NOES-256 Obey Olver Ortiz Pallone Pascrell Pastor (AZ) Herseth Sandlin Payne Perlmutter Perriello Peters Peterson Pingree (ME) Polis (CO) Pomeroy Price (GA) Price (NC) Quigley Rahall Rangel Reves Richardson Rodriguez Ross Rothman (NJ) Roybal-Allard Ruppersberger Rush Ryan (OH) Ryan (WI) Salazar Sánchez Linda Т. Sanchez, Loretta Sarbanes Schakowsky Schauer Schiff Schrader Schwartz Scott (GA) Scott (VA) Serrano Sestak Shea-Porter Sherman Shuler Sires Skelton Slaughter Smith (NJ) Smith (WA) Snyder Space Speier Spratt Stark Stupak Sutton Tanner Tauscher Taylor Teague Thompson (CA) Thompson (MS) Tierney Titus Tonko Towns Tsongas Van Hollen Velázquez Visclosky Walz Wasserman Schultz Watson Watt Waxman Weiner Welch Westmoreland

NOT VOTING-5

Wexler

Woolsey

Yarmuth

Wilson (OH)

Moran (VA) Flake Hastings (FL) Sullivan

□ 1859

Messrs. ADLER of New Jersey, PAT-RICK J. MURPHY of Pennsylvania, BERMAN, McMAHON, and

Shuler

Skelton

Snyder

Space

Speier

Spratt

Stupak

Sutton

Tauscher

Teague

Tierney

Titus

Slaughter

Smith (NJ)

Smith (WA)

Sires

MALONEY changed their vote from "aye" to "no."

McHENRY and Messrs. changed their vote from "no" to "aye. So the amendment was rejected.

The result of the vote was announced as above recorded.

The SPEAKER pro tempore (Mr. PAS-TOR of Arizona). The question is on the engrossment and third reading of the bill.

The bill was ordered to be engrossed and read a third time, and was read the third time.

The SPEAKER pro tempore. The question is on the passage of the bill.

The question was taken; and the Speaker pro tempore announced that the noes appeared to have it.

RECORDED VOTE

Mr. WAXMAN. Madam Speaker, I demand a recorded vote.

A recorded vote was ordered.

The SPEAKER pro tempore. Pursuant to clause 8 of rule XX. this 15minute vote on passage will be followed by a 5-minute vote on approval of the Journal, if ordered.

The vote was taken by electronic device, and there were—ayes 219, noes 212, not voting 3, as follows:

[Roll No. 477]

AYES-219

Abercrombie Eshoo Lipinski Ackerman Etheridge LoBiondo Adler (NJ) Farr Loebsack Fattah Andrews Lofgren, Zoe Baca Filner Lowey Frank (MA) Baird Luján Baldwin Fudge Lynch Giffords Bean Maffei Becerra. Gonzalez Malonev Markey (CO) Gordon (TN) Berkley Markey (MA) Berman Grayson Bishop (GA) Green, Al Matsui McCarthy (NY) Green, Gene Bishop (NY) Blumenauer Grijalva McCollum Boccieri Gutierrez McDermott Bono Mack Hall (NY) McGovern McHugh Halvorson Boswell Boucher Hare McMahon McNerney Harman Boyd Brady (PA) Heinrich Meek (FL) Bralev (IA) Higgins Meeks (NY) Brown, Corrine Hill Michaud Butterfield Himes Miller (NC) Capps Hinchev Miller, George Capuano Moore (KS) Hinojosa Cardoza Hirono Moore (WI) Moran (VA) Carnahan Hodes Carson (IN) Holt Murphy (CT) Castle Honda. Murphy (NY) Castor (FL) Murphy, Patrick Hover Chandler Inslee Murtha Nadler (NY) Clarke Israel Jackson (IL) Clav Napolitano Cleaver Jackson-Lee Neal (MA) Clyburn (TX) Oberstar Johnson (GA) Obev Cohen Connolly (VA) Johnson, E. B. Olver Convers Kagen Kanjorski Pascrell Cooper Pastor (AZ) Courtney Kaptur Crowley Kennedy Pavne Cuellar Kildee Pelosi Cummings Kilpatrick (MI) Perlmutter Davis (CA) Kilrov Perriello Davis (IL) Kind Peters Kirk DeGette Peterson Klein (FL) Pingree (ME) Delahunt Polis (CO) DeLauro Kosmas Dicks Kratovil Price (NC) Dingell Lance Quigley Doggett Langevin Rangel Doyle Larsen (WA) Larson (CT) Reichert Driehaus Reyes Edwards (MD) Richardson Lee (CA) Ellison Rothman (NJ) Roybal-Allard Levin Lewis (GA) Engel

Ruppersberger Rush Ryan (OH) Sánchez, Linda

Sanchez, Loretta Sarbanes Schakowsky Schauer Schiff Schrader Schwartz Scott (GA) Scott (VA) Serrano Sestak Shea-Porter Sherman

Aderholt

Alexander

Altmire

Arcuri

Austria

Bachus

Barrow

Bartlett

Berry

Biggert

Bilbray

Blunt

Boehner

Bonner

Boren

Bright

Boozman

Boustany

Brady (TX)

Broun (GA)

Brown (SC)

Ginny

Buchanan

Burton (IN)

Burgess

Buyer

Camp

Cantor

Capito

Carney

Carter

Cassidy

Chaffetz

Childers

Conaway

Costello

Crenshaw

Culberson

Dahlkemper

Davis (AL)

Davis (KY)

Davis (TN)

Deal (GA)

Diaz-Balart, L.

Diaz-Balart, M.

Donnelly (IN)

Edwards (TX)

DeFazio

Dent

Dreier

Duncan

Ehlers Ellsworth

Fallin

Forbes

Flake

Fleming

Coffman (CO)

Coble

Cole

Costa

Cao

Calvert

Campbell

Brown-Waite,

Bilirakis

Bishop (UT)

Blackburn

Bachmann

Barrett (SC)

Barton (TX)

Akin

Tonko Towns Tsongas Van Hollen Velázquez Walz Wasserman Schultz Waters Watson Watt Waxman Weiner Thompson (CA) Wexler Thompson (MS) Woolsey Varmuth

NOES-212

Fortenberry Mitchell Foster Mollohan Moran (KS) Foxx Franks (AZ) Frelinghuysen Murphy, Tim Myrick Neugebauer Gallegly Garrett (NJ) Nunes Gerlach Nve Gingrey (GA) Olson Gohmert Ortiz Goodlatte Pan1 Granger Paulsen Graves Pence Griffith Petri Guthrie Pitts Hall (TX) Platts Harper Poe (TX) Hastings (WA) Pomeroy Heller Posey Hensarling Price (GA) Herger Putnam Herseth Sandlin Radanovich Hoekstra Rahall Holden Rehberg Hunter Rodriguez Inglis Roe (TN) Tssa. Rogers (AL) Jenkins Rogers (KY) Johnson (IL) Rogers (MI) Johnson, Sam Rohrabacher Jones Rooney Jordan (OH) Ros-Lehtinen King (IA) Roskam King (NY) Ross Kingston Royce Kirkpatrick (AZ) Ryan (WI) Kissell Kline (MN) Salazar Scalise Kucinich Schmidt Lamborn Schock Latham Sensenbrenner LaTourette Sessions Latta Shadegg Lee (NY) Shimkus Lewis (CA) Shuster Linder Simpson Lucas Smith (NE) Luetkemever Smith (TX) Lummis Souder Lungren, Daniel Stark E. Stearns Mack Tanner Manzullo Taylor Marchant Terry Marshall Thompson (PA) Massa. Thornberry Matheson Tiahrt McCarthy (CA) Tiberi McCaul McClintock Turner Upton McCotter Visclosky McHenry Walden McIntvre Wamp McKeon Westmoreland McMorris Rodgers Whitfield Wilson (OH) Melancon Wilson (SC) Mica Miller (FL) Wittman Miller (MI) Wolf Young (AK) Miller, Gary Minnick Young (FL)

Mr. GOHMERT changed his vote from "aye" to "no."

Sullivan

NOT VOTING-

Hastings (FL)

 \Box 1917

So the bill was passed.

The result of the vote was announced as above recorded.

A motion to reconsider was laid on the table.

THE JOURNAL

The SPEAKER pro tempore (Mr. WEINER). Pursuant to clause 8 of rule XX, the unfinished business is the question on agreeing to the Speaker's approval of the Journal, which the Chair will put de novo.

The question is on the Speaker's approval of the Journal.

Pursuant to clause 1, rule I, the Journal stands approved.

THANKING STAFF INVOLVED IN PASSAGE OF ENERGY BILL

(Mr. WAXMAN asked and was given permission to address the House for 1 minute.)

Mr. WAXMAN. I would like to take a moment to thank the staff of the Office of Legislative Counsel and the Congressional Budget Office for their hard work on this bill. The efforts and dedication of Tim Brown, Warren Burke, Alison Bell, Pope Barrow and their colleagues in the Office of Legislative Counsel were indispensable in writing this wide-ranging and historic legisla-Similarly, Suzanne Mehlman, Dan Hoople and their colleagues at the Congressional Budget Office were essential in analyzing the complex financial and scoring issues associated with this bill. Both the staff of the Legislative Counsel and the CBO deserve to be thanked and congratulated for their outstanding work over the many late nights and weekends. We are very grateful for their service to the Nation.

I would like to add my appreciation to the fantastic job that our committee, subcommittee and select committee staffs have done in getting this legislation before the Congress of the

United States.

Mr. Speaker, I would like to yield to my colleague on this legislation, Congressman ED MARKEY.

Mr. MARKEY of Massachusetts. I thank you, Mr. Chairman. And I thank everyone who worked on this legislation, all of the Members on both sides of the aisle. But as Chairman WAXMAN just said, this took an enormous amount of work by a lot of staffers over a sustained, intense period of time. And I want to thank all of you for everything that you have done to make today possible.

I think you really do deserve a round of applause for the tremendous work that you have done. It is your victory as much as any Member, and we thank you for it.

Mr. WAXMAN. Reclaiming my time, I would like to read from page 333 of the manager's amendment and to indicate my gratitude to our staff director Phil Barnett; to the environmental staff on the committee, Greg Dotson, Lorie Schmidt, Alexandra Teitz, John

Jimison, Jeff Baran, Alex Barron, Ben Hengst, Melissa Bez, and Rob Cobbs.

Mr. MARKEY of Massachusetts. I would like to thank Joel Beauvais, Michael Goo, Danielle Baussan, Ana Unruh-Cohen. I would also like to thank Michal Freedhoff, Morgan Gray, Jonathan Phillips, Eban Burnham-Snyder, Jackie Chenault, Jeff Sharp, Ali Brodsky, Camilla Bausch, and especially Gerry Waldron and Jeff Duncan, along with Shannon Kenny, who is still sitting over there as well.

All of you were fantastic, and it's just a historic achievement. We thank you all so much for everything that you do.

Mr. WAXMAN. Mr. Speaker, I also wanted to add our appreciation to Matt Wiener, our staff assistant on this legislation.

I feel empowered because I only asked for 1 minute, and I have talked far more than 1 minute. I guess that's become a new tradition in the House, but I don't want to abuse it, and I yield back the balance of my time.

REPORT ON H.R. 3081, THE DE-PARTMENT OF STATE, FOREIGN OPERATIONS AND RELATED PRO-GRAMS APPROPRIATIONS ACT, 2010

Mrs. LOWEY, from the Committee on Appropriations, submitted a privileged report (Rept. No. 111–187) on the bill (H.R. 3081) making appropriations for the Department of State, foreign operations, and related programs for the fiscal year ending September 30, 2010, and for other purposes, which was referred to the Union Calendar and ordered to be printed.

The SPEAKER pro tempore (Mr. Luján). Pursuant to clause 1, rule XXI, all points of order are reserved on the bill.

REPORT ON H.R. 3082, MILITARY CONSTRUCTION AND VETERANS AFFAIRS APPROPRIATIONS ACT, 2010

Mr. EDWARDS of Texas, from the Committee on Appropriations, submitted a privileged report (Rept. No. 111-188) on the bill (H.R. 3082) making appropriations for military construction, the Department of Veterans Affairs, and related agencies for the fiscal year ending September 30, 2010, and for other purposes, which was referred to the Union Calendar and ordered to be printed.

The SPEAKER pro tempore. Pursuant to clause 1, rule XXI, all points of order are reserved on the bill.

PRIVILEGED REPORT ON RESOLUTION OF INQUIRY TO THE PRESIDENT

Mr. CONYERS, from the Committee on Judiciary, submitted an adverse privileged report (Rept. No. 111–189) on the resolution (H. Res. 537) requesting that the President and directing that the Attorney General transmit to the House of Representatives all information in their possession relating to specific communications regarding detainees and foreign persons suspected of terrorism, which was referred to the House Calendar and ordered to be printed.

□ 1930

SUPPORTING PRAGUE CON-FERENCE ON HOLOCAUST ERA ASSETS

Mr. WEXLER. Mr. Speaker, I ask unanimous consent that the Committee on Foreign Affairs be discharged from further consideration of the concurrent resolution (H. Con. Res. 89) supporting the goals and objectives of the Prague Conference on Holocaust Era Assets, and ask for its immediate consideration in the House.

The Clerk read the title of the concurrent resolution.

The SPEAKER pro tempore. Is there objection to the request of the gentleman from Florida?

There was no objection.

The text of the concurrent resolution is as follows:

H. CON. RES. 89

Whereas the Government of the Czech Republic will host a Conference on Holocaust Era Assets in Prague from June 26, 2009, through June 30, 2009;

Whereas the Prague Conference will facilitate a review of the 1998 Washington Conference on Holocaust Era Assets, which had participation of 44 nations, 13 nongovernmental organizations, scholars, and Holocaust survivors:

Whereas a high level United States delegation participated in the Washington Conference on Holocaust Era Assets led by Undersecretary of State Stuart Eizenstat, Nobel Peace Laureate Elie Wiesel, Federal Judge Abner Mikva, senior diplomats, and a bipartisan group of Members of Congress;

Whereas then-Secretary of State Madeleine Albright delivered the key note address at the Washington Conference on Holocaust Era Assets, articulating the United States commitment to Holocaust survivors and urging conference participants to "chart a course for finishing the job of returning or providing compensation for stolen Holocaust assets to survivors and the families of Holocaust victims.":

Whereas the Prague Conference is expected to take stock of issues agreed on at the Washington Conference, including financial assets, bank accounts, insurance issues, and other financial property;

Whereas the Prague Conference is expected to include a special session on social programs for Holocaust survivors and other victims of Nazi atrocities;

Whereas the Prague Conference is expected to include working groups on Holocaust education, remembrance and research, looted art, Judaica, Jewish cultural property, and immovable property, including both private, religious, and communal property;

Whereas United States participation and leadership at the highest level is critically important to ensure a successful outcome of the Prague Conference:

Whereas Congress supports further inclusion of Holocaust survivors and their advocates in the Prague Conference planning and proceedings:

Whereas the United States strongly supports an immediate and just restitution or compensation of property illegally confiscated during the last century by Nazi and Communist regimes:

Whereas many Holocaust survivors lack the means for even the most basic necessities, including proper housing and health care:

Whereas the United States and the international community has a moral obligation to uphold and defend the plight and dignity of Holocaust survivors and to ensure their well-being;

Whereas for the Prague Conference is a critical forum to effectively address the increasing economic, social, housing, and health care needs of Holocaust survivors in their waning years:

Whereas President Barack Obama, during his visit to the Yad Vashem Holocaust Memorial in Israel in July 2008, stated "Let our children come here and know this history so they can add their voices to proclaim 'never again.' And may we remember those who perished, not only as victims but also as individuals who hoped and loved and dreamed like us and who have become symbols of the human spirit."; and

Whereas the Prague Conference may represent the last opportunity for the international community to address outstanding Holocaust-era issues: Now, therefore, be it

Resolved by the House of Representatives (the Senate concurring), That Congress—

(1) supports the goals and objectives of the 2009 Prague Conference on Holocaust Era Assets;

(2) applauds the Government of the Czech Republic for its decision to host the Prague Conference and its unwavering commitment to address out standing Holocaust-era issues;

(3) expresses strong support for the decision to make the economic, social, housing, and health care needs of Holocaust survivors a major focus of the Prague Conference;

(4) urges the countries in Central and Eastern Europe, which have not already done so, to return looted and confiscated properties to their rightful owners or, where restitution is not possible, pay equitable compensation to the rightful owners in accordance with principles of justice and in an expeditious manner that is just, transparent, and fair.

(5) calls on the President to send a highlevel official, such as the Secretary of State, to represent the United States at the Prague Conference; and

(6) urges other invited nations to participate at a similarly high level.

Ms. JACKSON-LEE of Texas. Mr. Speaker, I rise today in support of H. Con. Res. 89, which supports the goals and objectives of the Prague Conference on Holocaust Era Assets. From June 26, 2009, through June 30, 2009, the Government of the Czech Republic will host a Conference in Prague of utmost importance, which will focus exclusively on the reparation of Holocaust Era Assets. The Prague Conference will facilitate a review of the 1998 Washington Conference on Holocaust Era Assets, which had participation of 44 nations, 13 nongovernmental organizations, scholars, and Holocaust survivors.

In his internationally recognized and critically acclaimed novel, "Night," Nobel Peace Prize winner Elie Weisel so chillingly depicted the Holocaust in the following vivid description:

"Never shall I forget that night, the first night in camp, which has turned my life into one long night, seven times cursed and seven times sealed. Never shall I forget that smoke. Never shall I forget the little faces of the children, whose bodies I saw turned into wreaths

of smoke beneath a silent blue sky. Never shall I forget those flames which consumed my faith forever. Never shall I forget that nocturnal silence which deprived me, for all eternity, of the desire to live. Never shall I forget those moments which murdered my God and my soul and turned my dreams to dust. Never shall I forget these things, even if I am condemned to live as long as God Himself. Never."

And never again shall we forget the atrocities that transpired during the Holocaust. As we go forward into the 21st Century, it is our job to make sure that the history of the Holocaust is re-told, so that such crimes against humanity never again recur. It is our job as humanitarians of the world to restore to victims of the Holocaust the private property and real property, chattels and assets which were so wrongfully taken by the nefarious acquisition of the Nazi regime during World War II, and restore to Holocaust Survivors and to their heirs that property which is rightfully theirs.

I sit on the Advisory Board of the Houston Holocaust Museum, and I understand the urgency and necessity expressed by former Secretary of State Madeleine Albright, when she delivered the keynote address at the Washington Conference on Holocaust Era Assets. Former Secretary Albright articulated the U.S. commitment to Holocaust survivors and urged conference participants to "chart a course for finishing the job of returning or providing compensation for stolen Holocaust assets to survivors and the families of Holocaust victims." The Prague Conference is expected to do just that. The Conference will take stock of issues agreed on at the Washington Conference, including financial assets, bank accounts, insurance issues, and other financial property. United States participation and leadership at the highest level is critically important to ensure a successful outcome of the Prague Conference. The Prague Congress supports further inclusion of Holocaust survivors and their advocates in the Prague Conference planning and proceedings, to provide direct testimony as to the ongoing repercussions of the Holocaust on survivors and the families of survivors.

While it is largely unspoken, many Holocaust survivors lack the means for even the most basic necessities, including proper housing and health care. We have a moral obligation to uphold and defend the plight and dignity of Holocaust survivors and to ensure their well-being. The Prague Conference is a critical forum to effectively address the increasing economic, social, housing, and health care needs of Holocaust survivors in their waning years.

On his visit to the Yad Vashem Holocaust Memorial in Israel in July 2008, President Barack Obama stated "Let our children come here and know this history so they can add their voices to proclaim 'never again.' And may we remember those who perished, not only as victims but also as individuals who hoped and loved and dreamed like us and who have become symbols of the human spirit."

I urge my colleagues to support this important Resolution today, which advocates for an immediate and just restitution or compensation of property illegally confiscated during the last century by Nazi and Communist regimes. I applaud the Government of the Czech Republic for its decision to host the Prague Conference

and its unwavering commitment to address outstanding Holocaust-era issues. Furthermore I express strong support for the decision to make the economic, social, housing, and health care needs of Holocaust survivors a major focus of the Prague Conference. Finally, this Resolution urges the countries in Central and Eastern Europe, which have not already done so, to return looted and confiscated properties to their rightful owners or, where restitution is not possible, pay equitable compensation to the rightful owners in accordance with principles of justice and in an expeditious manner that is just, transparent, and fair. I urge passage of H. Con. Res. 89.

The concurrent resolution was agreed to.

A motion to reconsider was laid on the table.

THE FOURTH OF JULY

(Mr. POE of Texas asked and was given permission to address the House for 1 minute.)

Mr. POE of Texas. Mr. Speaker, the most patriotic time of the year is at hand. I love the Fourth of July. It is picnics, hot dogs, potato salad and barbecue. It is kids decorating wagons with red, white and blue for neighborhood parades and little kids sitting on their dad's shoulders watching the parade. It is horses and cowboys. It is John Phillips Sousa and "The Stars and Stripes Forever." It is waving flags and thanking our troops for their service. It is yellow ribbons tied to trees.

The Fourth of July is a packed freeway and a long weekend. It is going to the beach and getting sand in everything. It is coolers, beach towels, blankets, sunscreen and the salty air.

It is the big fireworks display in the big cities and the small ones in the neighborhood. It is making circles in the air with sparklers. It is bottle rocket wars. It is Black Cat firecrackers and Roman candles. It is buy one, get four free.

It is stump speeches by politicians. It is people dressing up as Tom Jefferson and George Washington. It is snow cones and caramel apples. It is kids, grandkids and pets all packed in the Jeep and going for cotton candy.

Everybody is happy about the Fourth of July. There is nothing sad about freedom. After all, it is happy birthday to our country.

And that's just the way it is.

DEATH OF MICHAEL JACKSON, JUNE 25, 2009

(Ms. JACKSON-LEE of Texas asked and was given permission to address the House for 1 minute and to revise and extend her remarks.)

Ms. JACKSON-LEE of Texas. Mr. Speaker, I too wish our Nation a very happy birthday. But I rise in sadness to celebrate, but yet mourn, the passing of Michael Jackson, to celebrate a life that was full of artistry. It was, in essence, a joy to many who listened and those who danced.

Michael Jackson loved America. He was truly a story that came from the

very dreams that Americans have. Starting in the very bowels of a city called Gary, Indiana, living in a two bedroom bungalow, he rose to the highest pedestals of entertainment and, of course, iconic state.

He was the King of Pop. But he was also a quiet man, a man who, in fact, loved to give back and a humanitarian. For those of us who remember the words of "We Are the World," one of the first conglomerations of bringing people together, to be able to emphasize that we do have a responsibility to others. And then the song, "The Man in the Mirror," we can make a difference.

Born on August 29, 1958, in Gary, Indiana, he was one of the Jackson Five. But more importantly, he was a father. He was someone who would bring a face to America. I intend to introduce a resolution in honor of Michael Jackson because we believe in the good. And he was good. He saw our soldiers. He fought against HIV/AIDS. He wanted to show that he cared. And he did.

It is my pleasure to have hosted Michael Jackson on Capitol Hill in 2004 when he came to stand against AIDS and to fight that devastating disease.

Today I stand and recognize that he truly was a man who loved America.

Mr. Speaker, I stand before you today to remember and honor the memory of the King of Pop, Michael Jackson. Michael Jackson who was a charismatic musician and beloved American musician from a tender age, suffered from cardiac arrest today and died at the age of 50.

Michael Jackson truly was the King of Pop and a true icon that was world renowned. We watched a boy grow into a superstar before our eyes and enjoyed the music he brought to the world. The Jackson 5 were the first act in recorded history to have their first four major label singles ("I Want You Back", "ABC", "The Love You Save", and "I'll Be There") reach the top of the American charts.

Jackson was born on Aug. 29, 1958, in Gary, Indiana, the seventh of nine children. Five Jackson boys—Jackie, Tito, Jermaine, Marlon and Michael—first performed together at a talent show when Michael was 6. They walked off with first prize and went on to become a best-selling band, The Jackson Five.

Once Michael Jackson went solo we enjoyed such hits as Thriller, Beat It and Billie Jean and of course the legendary moonwalk. "Thriller" released in 1982, which became a smash hit yielded seven top-10 singles. The album sold 21 million copies in the United States and at least 27 million worldwide. It was a monumental moment in music history.

Not only an iconic singer and performer, Michael Jackson was a philanthropist and advocate for AIDS awareness and Child Hunger. Jackson co-wrote the charity single "We Are the World" with Lionel Richie, which was released worldwide to aid the poor in Africa and the US. He was one of 39 music celebrities who performed on the record. The single became one of the best-selling singles of all time, with nearly 20 million copies sold and millions of dollars donated to famine relief.

I was honored to personally meet with Michael Jackson on Capitol Hill in 2004 and am deeply saddened by his passing. He is survived by his three children, his brothers and

sisters, family, friends and a world full of fans. I will leave you all with a quote from Michael, "If you enter this world knowing you are loved and you leave this world knowing the same, then everything that happens in between can be dealt with."

HEARTBREAK ON CAPITOL HILL

(Mr. GOHMERT asked and was given permission to address the House for 1 minute.)

Mr. GOHMERT. Mr. Speaker, just moments ago on this floor there was cheering and there was clapping over the passing of the crap-and-trade bill. And it is a little tough to get excited. From a political standpoint, I should be overjoyed because I really believe in my heart that when the American people find out, and this is just a part of it, when they find out what has been done to them, they are going to be livid. And they are going to throw some people out of this body. I just know that will happen. But I care more about America than I do politics.

I know that we will be facing the single moms that we heard from last summer that can't afford the gasoline bill. They can't afford the propane.

You didn't do a great thing. You hurt some really decent families struggling and trying to make it. And this is going to be their death knell. It breaks my heart.

CELEBRATING BLACK MUSIC MONTH

(Mr. COHEN asked and was given permission to address the House for 1 minute.) $\,$

Mr. COHEN. This is Black Music Month. And we had a resolution to introduce and pass celebrating the 30th anniversary of Black Music Month. Because of the scheduling, it didn't come up. That is why I wanted to address that fact today.

Black Music Month is important because it reminds people of the history of music in this country and the contributions of black Americans. Much of that happened in my city in Memphis, at Stax Soulsville, home of Isaac Hayes, Sam and Dave, Stax Soulsville Records, Al Green, Willy Mitchell and others, also Detroit and Motown and New Orleans and Fats Domino, Professor Long Hair, and many great musicians.

But back to Kansas City, and Charlie Parker, and Miles Davis and Max Roach and Dizzy Gillespie, not all from Kansas City, but that from that jazz era, and others. Michael Jackson, of course, passed. Many great musicians whose music needs to be remembered and young people need to learn that music is a great way to pass on our culture and preserve it and a great way to enjoy their own life and experience a better way. I'm pleased this is the 30th anniversary of Black Music Month. And we need to enjoy music and soothe the soul.

SPECIAL ORDERS

The SPEAKER pro tempore. Under the Speaker's announced policy of January 6, 2009, and under a previous order of the House, the following Members will be recognized for 5 minutes each.

The SPEAKER pro tempore. Under a previous order of the House, the gentle-woman from California (Ms. WOOLSEY) is recognized for 5 minutes.

(Ms. WOOLSEY addressed the House. Her remarks will appear hereafter in the Extensions of Remarks.)

CELEBRATING THE ALBANIAN DIASPORA OF SOUTHEAST MICHIGAN

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from Michigan (Mr. Peters) is recognized for 5 minutes.

Mr. PETERS. Mr. Speaker, I rise today to celebrate the Albanian diaspora of southeast Michigan and to raise the concern they have expressed to me.

Respect for people of diverse cultures is an American value and has made our Nation great. Our national heritage reflects the cultural contributions of a wide range of ethnic groups.

I am fortunate to represent the Ninth District of Michigan, a district rich in ethnic and religious diversity and one that includes many families from the Balkan region. In my time as a Congressman and resident of the Ninth District, I have developed a strong bond with the Albanian American community. This is a people that strongly value community service, family, and education. These are the values we can all admire and strive to instill in our children.

The Albanian American community of southeast Michigan is relatively new to our country. Most are first- or second-generation Americans. However, this community has established strong roots in southeast Michigan, establishing churches, community centers and small businesses. These places preserve and celebrate Albanian culture. They help enrich the lives of fellow Albanian Americans and the broader community alike.

Saint Paul's Albanian Church in Rochester Hills, Michigan, a city in my district, boasts nearly 5,000 members and is a shining example of how the Albanian diaspora has taken root in southeast Michigan. These roots are nourished by the community's focus on family, a value deeply embedded in Albanian culture, and one that I greatly respect.

As with many new immigrant communities, the entrepreneurial spirit runs deep among our Albanian Americans. Our Nation has provided many Albanian Americans with their first opportunity for business success. Members of the community have embraced these opportunities and worked tirelessly for the success of their endeavors, helping to grow our economy and create jobs in our region.

The community's affinity for entrepreneurship is coupled with a deep appreciation for education. Albanian Americans recognize the invaluable return on investment that educational achievement brings to the next generation

I am particularly proud of the Albanian American community's patriotism, love for America and participation in the American democratic process.

Albanian Americans truly are full participants in the American democratic system. They understand that the essential element of a thriving democracy is active engagement.

Albanian Americans' unwavering dedication to democracy does not stop at our borders. The Albanian community is working tirelessly to bring attention to the needs of the emerging democracies in the Balkan region and to strengthen U.S.-Balkan relations.

I am proud of the relationship the city of Rochester Hills has formed with Tuz, Montenegro. For example, the Albanian American diaspora in Michigan and the city of Rochester Hills recently worked together to provide school supplies to the cities of Tuz, and I commend them for these efforts.

While many are aware of the efforts made by the Albanian American community to assist refugees during the Kosovo conflict, it is important to highlight important work still being performed by the Albanian American community.

The Albanian diaspora continues to seek further recognition for the Republic of Kosova and has been vital in helping former refugees rebuild their lives. The recent independence of the Republic of Kosova and the induction of Albania into NATO are a testament to the Albanian American community's progress.

The Albanian community in Michigan remains concerned with events and issues currently affecting their brethren and families overseas. Some particular concerns of my constituents I want to raise today relate to recent reports of inequities in the Montenegrin justice system. In particular, reputable human rights organizations like Amnesty International have reported that several Albanian American citizens convicted in connection with the Eagle's Flight case have been subject to torture and physical abuse. These incidents and reports have caused tremendous anxiety and uncertainty in the Albanian American community. It is my hope that the Montenegrin Government will work diligently to protect human rights and the rule of law in the exercise of justice in the future.

Whether fighting for justice, advancing democracy, supporting our schools, or working hard to strengthen our economy, Albanian Americans in my district and across America are helping to make our Nation even greater. It is an honor to represent a prominent Albanian American community here in the United States Congress.

WE ARE FREE

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from Michigan (Mr. McCotter) is recognized for 5 minutes.

Mr. McCOTTER. Mr. Speaker, from the hellish streets where Iranians demand freedom, voices arise to pray for deliverance and liberty; but, elsewhere, safely ensconced in freedom, others argue for appeasement and "neutrality." We must choose wisely between these competing voices and visions, lest we betray our allegiance to liberty.

Some voices allege America's support of Iranian democracy demonstrators harms their cause, strengthens the regime, increases the repression, and, once the freedom seekers are slaughtered, precludes "good" relations with the murderous mullahs.

Their siren song is wrong. Despite pronouncements, America has not intervened, the mullahs publicly accuse us of it, their illegitimate puppet Ahmadinejad demands our prostration at the regime's feet, and all the while, the regime butchers innocents.

□ 1945

On June 24, CNN recorded a call from a terrified Iranian girl, who told of democracy demonstrators being hacked with axes, shot or thrown from bridges. She pleaded: "You should stop this. You should help the people of Iran who demand freedom. You should help us. It's time to act." She was pleading to America. She was pleading to us.

Once, another generational chance for freedom was seized, as Soviet dissident and gulag prisoner Natan Sharansky attests, "We developed our own tapping language to communicate with each other between the crawls of our cells. We had to develop new communication methods to pass on this great, impossible news.

"Reagan dared to call of the great Soviet Union an evil empire. That moment made it impossible for anyone in the West to continue closing their eyes to the real nature of the Soviet Union.

"It was one of the most important, freedom-affirming declarations, and we all instantly knew it. For us, that was the moment that really marked the end for them, and the beginning for us. The beginning of a new revolution, a freedom revolution. Reagan's revolution."

As for voices clamoring for a "grand bargain" with Iran's inhumane regime if it clings to power, Sharansky warns: "How a government treats its own people cannot be separated from how that other countries." How did the regime treat the family of Neda Agha-Soltan, the student it shot in the streets? Her state executioners refused to tender Neda's body to her family; buried her without a funeral; banned all signs of mourning; and forced her family to flee from their Tehran home.

To defeat such a regime, Sharansky offers Reagan's example: "Ronald

Reagan had the moral clarity to understand the truth, and the courage both to speak the truth and to do what needed to be done to support it."

What concrete actions can we take today to aid the Iranian people's march to freedom?

We must increase funding for Radio Farda and other democracy building programs to provide the Iranian people with the free flow of information and communications in their struggle to be free

The President must use his full authority under the Iranian Sanctions Act to deter companies from investing in Iran's energy sector.

We must place column 2 tariff rates on Iran's remaining exports to the United States. We must pass the Global Online Freedom Act to prevent American companies from assisting foreign governments, including Iran, from censoring and monitoring their people on the Internet. We must pass the Iran Refined Petroleum Sanctions Act and the Iran Threat Reduction Act to embargo the flow of refined fuel to and increase the pressure upon the regime.

The President must prohibit regime members from entering the United States of America.

We must seek a United Nations Security Council resolution denouncing the regime; demanding a new, internationally monitored election; and tightening the current U.N. sanctions against the regime until this election occurs and its outcome's integrity verified.

We must work with American labor organizations to establish a support fund for Iranian workers striking in protest of the regime.

Finally, we must link all of our relations with Iran, and with those nations abetting the regime's perpetuation in defiance of its people's freedom to human rights.

If we pale and fail to take these measures, we will be haunted by the cries of the oppressed Iranians abandoned to preserve our neutrality in this time of moral crisis.

But, when we act, we will expand freedom to the oppressed and enslaved; and ensure it for our children and ourselves. Only then will we have honorably performed our duty to liberty by guaranteeing generations of Americans and Iranians may proclaim, "We are free."

RESIGNATION FROM THE HOUSE OF REPRESENTATIVES

The SPEAKER pro tempore laid before the House the following resignation from the House of Representatives:

 ${\tt JUNE~26,~2009.}$

House of Representatives, Washington, DC, Office of the Speaker, $U.S.\ Capitol$,

Washington, DC.

DEAR MADAM SPEAKER: This letter is to alert you that I have sent a letter to Governor Arnold Schwarzenegger of California

informing him that I will be resigning as the United States Representative for the 10th Congressional District of California effective immediately.

immediately.

In May, I had the distinguished honor of being nominated by President Obama to serve as Undersecretary of State for Arms Control and International Security. Keeping nuclear weapons out of the hands of terrorists, making sure other countries do not obtain them and, one day, I hope, ridding the world of these terrible weapons, has become my passion and, I hope, my life's work.

It has been an immense pleasure working with you Madam Speaker. I owe you, and my colleagues on both sides of the isle, a debt of gratitude for your leadership, guidance and dedication. I eagerly await the opportunity to work with you in my new role with the Obama Administration.

Sincerely,

ELLEN O. TAUSCHER.

JUNE 26, 2009

Congress of the United States, $House\ of\ Representatives,$

 $Washington,\,DC,$

Governor ARNOLD SCHWARZENEGGER,

California State Capitol Building, Sacramento,

DEAR GOVERNOR SCHWARZENEGGER: On May 5th, I was nominated by President Obama to serve as Undersecretary of State for Arms Control and International Security. Therefore I am resigning my position as the United States Representative for the 10th Congressional District of California effective immediately.

Thirteen years ago, the people of California's 10th Congressional district bestowed upon me the privilege of serving as their representative in Congress. It has been a remarkable period marked by tremendous challenges and remarkable achievements. I take great pride, along with my distinguished colleagues in the California delegation, in working to make our communities safer, California more prosperous and our nation more secure. No matter where I am serving in government, I always will remember those who sent me to Washington and I always will be grateful for their support and the trust they placed in me.

I also wanted to thank you for your leadership. It has been a pleasure to work with you and your staff and I look forward to continuing our productive relationship.

Sincerely.

ELLEN O. TAUSCHER.

ANNOUNCEMENT BY THE SPEAKER PRO TEMPORE

The SPEAKER pro tempore. Under clause 5(d) of rule XX, the Chair announces to the House that, in light of the resignation of the gentlewoman from California (Mrs. TAUSCHER), the whole number of the House is 433.

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from California (Mr. George Miller) is recognized for 5 minutes.

(Mr. GEORGE MILLER of California addressed the House. His remarks will appear hereafter in the Extensions of Remarks.)

HONORING FIRE CAPTAIN JAMES HALL

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from Ohio (Mr. BOCCIERI) is recognized for 5 minutes.

Mr. BOCCIERI. Mr. Speaker, there are difference makers among us. I rise today to honor a man who committed his life to public service and put his life on the line working to save people in our community.

Just a few short weeks ago, James Martin "Marty" Hall, City of Canton, Ohio Fire Captain of 15 years, made the ultimate sacrifice and died in the line of duty after suffering a fatal heart attack just hours after serving a volunteer fire shift at the Greentown Fire Department.

Captain Hall was a member of the City of Canton's fire force for more than 20 years.

Captain Hall clearly moved our community. Joining the thousands of friends and neighbors and loved ones who lined the streets of Canton for his funeral procession deeply moved me. This man was a respected member of our city who touched and saved many lives, including a child he performed CPR on after rescuing him from a burning home in Canton.

Captain Hall's peers called and said to him as they bid him farewell, "If you needed to be rescued, Captain Hall and his crew would be the crew you wanted coming for you."

Captain Hall was a hero in our community and in his home. Being a father of four small children, it was exceptionally emotional to witness his three daughters stand up at his funeral and say, "We're going to miss you, Daddy."

Their words should remind each of us that our time on Earth is limited and we must live fully each day. Captain Hall's passing shocked our community, and he will forever remain one of our community heroes.

My prayers and deepest condolences go out to his family as they grieve this tragic loss. Captain Hall's family and our community reflect on his service both in the military and as a firefighter.

Today, I take this moment to honor his life and his service to our country. We thank you, Marty, for your service.

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from North Carolina (Mr. JONES) is recognized for 5 minutes.

(Mr. JONES addressed the House. His remarks will appear hereafter in the Extensions of Remarks.)

SAD DAY FOR AMERICA

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from Indiana (Mr. SOUDER) is recognized for 5 minutes.

Mr. SOUDER. Mr. Speaker, this is a sad day for America, and I don't mean because of the death of Michael Jackson; I mean because if this legislation we just passed were to become law, tens and hundreds of thousands of people would lose their jobs.

In my district, we are already getting green jobs. We will have thousands of

green jobs, but we are going to lose tens of thousands of other jobs. My congressional district in northeast Indiana is the number one manufacturing district in the United States. One county has 57 percent of the people working in manufacturing. I heard on this floor that we don't have any manufacturing jobs left in America anymore. Oh, yes, we do.

In my district, we have 30,000 jobs related to the recreational vehicle area. We have 40,000 jobs related to auto and truck. We make boats. We have tire factories. We have axle factories and windshield factories. We are the manufacturing center, along with JOE DONNELLY'S district in the South Bend area and PETE VISCLOSKY'S in northwest Indiana.

We still have an industrial base, an industrial base that has tried to adjust and accommodate and make the changes they need to make. We have the most efficient steel factories in America. We have two steel factories that were roughly a billion dollars each to build, five new core facilities; the only two steel companies in America that haven't lost money because they have cut their costs 75 percent. They have their labor cost down at 4 to 5 percent, yet we are looking at energy costs that could go up 80 to 100 percent because, you know what, you can't power a steel plant in Indiana with solar panels. You cannot do this with windmills. Manufacturing takes an incredible amount of energy.

Now let me be honest. I admire the Amish. My great, great grandpa was one of the first Amish settlers in the State of Indiana. My great grandpa left about 1880. It is fine if you want to be Amish with no electricity and windmills and ride around in a horse and buggy, but that should be a choice, not pronounced on you by the Federal Government.

For people who want to come to the Notre Dame games in South Bend, I worry that in a couple years you can go over to Elkhart County, one of the largest Amish settlements, and go, Oh, look at that Amish farm. There's no electricity there. They're riding around in a buggy; but it won't be Amish. it will be everybody in the area because that is county that has 57 percent manufacturing, a county that the President went in with the stimulus package and said. This is the highest unemployment area in the United States, and we are going to bring you jobs. And instead, we are bringing death to manufacturing.

I just don't understand it. Maybe my district should introduce legislation to make it a national historical industrial park area where people could go and see what steel mills used to look like. They could go and see what axle companies used to look like. What it looked like to make the Silverado and the Sierra pickup before we drove them to China, before we moved the last companies out.

And in between, you could see soybean and corn farms, and apparently

we made some change here, but it is amazing we even had to make this change, that ethanol soy-diesel, we have the biggest integrated sov-diesel plant in the world. Dreyfus was worried down to the original draft of this bill they were going to be put out because they were cutting down trees to plant sovbeans and corn for ethanol, except our trees are already cut down. Oh, you mean they were going to cut down trees in Brazil? Well, not our companies. But because we are internationalists now and we're trying to be one world, if we grow soybeans in Indiana, then we have to offset it with trees in other places, and now maybe we won't have to offset it and maybe we won't wipe out soy-diesel and ethanol. What kind of joke is this?

I honestly did not think that this House could pass this bill.

These are hardworking, blue collar workers. Many in my area, if not most, union members. Look, they are not necessarily big fans of MARK SOUDER or Republicans. It is their constituency who they are putting out of work, people who didn't necessarily have a college degree, who worked in steel mills, who worked in auto places, who got up early in the morning and worked a hard day and thought they could make it in America.

But no, we are shipping their jobs away from America because now they are dirty, even though now they will go to other countries where it will be dirtier air?

What about farmers who get up and they work hard all day, six, seven days a week in the peak season, and now they are going to be told that their energy costs are going to go up. The REMCs in my area, which are huge, when I have gone to their meetings, 1,400 and 1,500, they say it is going to be \$60 to \$80 minimum a month on each of their people who are working hard ever day and are trying to figure out now, with a 15 percent average unemployment in my district, that they are supposed to take this kind of a heating bill.

I do not understand this. If you don't have steel, how do you have a military? Are we going to build our big aircraft carriers out of bamboo? What are we going to do here? Maybe we can have China build the steel for our military. That will work real well. They are our good buddies.

Before, when we heard the day of infamy from Franklin Delano Roosevelt, we at least had a manufacturing base to respond. This day of infamy, if this bill becomes law, we won't have a manufacturing base to respond.

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from Kansas (Mr. MORAN) is recognized for 5 minutes.

(Mr. MORAN of Kansas addressed the House. His remarks will appear hereafter in the Extensions of Remarks.) CAP-AND-TRADE NOT THE ANSWER

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from California (Mr. McClintock) is recognized for 5 minutes.

Mr. McCLINTOCK. Mr. Speaker, I had a strange sense of deja vu as I stood here on the floor of the House and watched all of the self-congratulatory rhetoric a few moments ago on the passage of the cap-and-trade bill, and I feel the need to rise to issue an urgent warning from the west coast.

I stood on the floor of the Senate of California 3 years ago and watched a very similar bill adopted and watched the same sort of self-congratulatory celebrations as we just saw here, and I have watched over those years as that measure has dramatically deepened California's recession. It uses a slightly different mechanism than cap-and-trade, but the objective is exactly the same, to force a dramatic reduction in carbon dioxide emissions.

\square 2000

Now, up until that bill took effect, California's unemployment numbers tracked very closely with the national unemployment rate. But then, in January of 2007, California's unemployment rate began a steady upward divergence from the national jobless figures. Today, California's unemployment rate is more than two points above the national rate and is at its highest point since 1941.

What happened in January of 2007? AB 32 took effect and it began shutting down entire sectors of California's economy.

Let me give you just one example from my own district. The city of Truckee, California, was about to sign a long-term power contract to get its electricity from a new EPA-approved coal-fired plant way off in Utah. But AB 32 and companion legislation caused them to abandon that contract. The replacement power that they acquired literally doubled their electricity costs.

So when economists warn that we can expect electricity prices to double under the cap-and-trade bill, I can tell you from the bitter experience of my district that that is not some future prediction. That is a historical fact.

Governor Schwarzenegger assured us at the time that AB 32 would mean an explosion of new, green jobs—exactly the same promises that we heard on this floor today.

Well, in California exactly the opposite has happened. We have lost so many jobs that the UCSB economic forecast is now using the D word—depression—to describe California's job market.

Mr. Speaker, the cap-and-trade bill proposes what amounts to endlessly increasing taxes on any enterprises that produce carbon dioxide or other so-called greenhouse gases. We need to understand exactly what that means. It has profound implications for agriculture, construction, cargo and pas-

senger transportation, energy production, baking and brewing—all of which produce enormous quantities of this innocuous, ubiquitous compound. In fact, every human being produces 2.2 pounds of carbon dioxide every day—just by breathing.

So applying a tax to the economy designed to radically constrict carbon dioxide emissions means radically constricting the economy. And this brings us to the fine point of the matter.

When we look back on the folly of the Hoover administration and how it turned the recession of 1929 into the Depression of the 1930s, the first thing that economists point to is the Smoot-Hawley Tariff Act that imposed new taxes on 20,000 imported products.

The Waxman-Markey bill, I'm afraid, is our generation's Smoot-Hawley that imposes new taxes on an infinitely larger list of domestic products on a scale that utterly dwarfs Smoot-Hawley.

Let's ignore for the moment the fact that the planet's climate is constantly changing and that long-term global warming has been going on since the last ice age. Let's ignore the fact within recorded history we know of periods when the Earth's climate has been much warmer than it is today, and others when it's been much cooler. Let's ignore the thousands of climate scientists and meteorologists who've concluded that human-produced greenhouse gases are, at most, a negligible factor in global warming or climate change.

Ignore all of that and we're still left with one lousy sense of timing. In the most serious recession since the Great Depression, why is it that Members of this House want to repeat the same mistakes that produced the Great Depression?

Watching how California has just wrecked its own economy and destroyed its own finances, why would Members of this House want to do the same thing to our Nation?

Mr. Speaker, this is deadly serious stuff. It transcends ideology and politics. This House has just made the biggest economic mistake since the days of Herbert Hoover.

Two things are certain if this measure becomes law. First, our planet is going to continue to warm and cool, as it's been doing for billions of years. And, secondly, this House will have just delivered a staggering blow to our Nation's economy at precisely that moment when the economy has been the most vulnerable.

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from California (Mr. Schiff) is recognized for 5 minutes.

(Mr. SCHIFF addressed the House. His remarks will appear hereafter in the Extensions of Remarks.)

BAD DAY FOR AMERICA

The SPEAKER pro tempore. Under a previous order of the House, the gen-

tleman from Texas (Mr. CONAWAY) is recognized for 5 minutes.

Mr. CONAWAY. Today is a bad day for America. We just passed and witnessed the passing of a bill that will have dramatic impact on our lives and our way of life for years to come if it should ever see the President's signature.

One matter of process. At 3:08, 3:09 this morning the Democrat majority landed on the Internet a 300-plus page amendment to the already bloated bill that was passed. Apparently, the bragging on the thousands and thousands of hours of work and hearings and process that had gone into the development of the bill that was filed on Monday left it a little short of the mark. In spite of all those thousands of hours, they were unable to get it right. So they had to use a little fine-tuning with a 300-pager that was dropped this morning. So, that issue aside, Mr. Speaker, it is a had bill

Science, Mr. Speaker, is never settled. Take the example of Galileo as an example. The consensus science of his time was that the Earth was the center of the universe. The Roman Catholic Church believed it and all the scientists who you and I have no clue who their names are believed it as well.

Galileo, on the other hand, bucked the system. He said, No, in fact the Sun was the center of the universe. He spent the last years of his life under house arrest because he bucked the consensus science.

You and I both know that both the consensus side of that day and Galileo were wrong. Most on the other side believe that Washington, D.C., is the center of the universe. But that's a different conversation.

Science is never settled. We should continue to ask the question; we should continue to ask whatever it is that's out there.

The sense of urgency that the other side used to try to pass this bill the way they have done it evaporates and is quite muted when you look at the details: 25-year exemptions for certain energy companies to allow them to get their power plants in under the wire to get support for this bill. Even the Ag amendment delays for 6 years the implementation of some of the provisions that will devastate Ag. And so this sense of urgency seems to evaporate as well.

The cost of this bill will be thousands of jobs, as has already been said over and over. The empirical data is the Spanish experiment of the last 12 years. A report there on their greening of their economy shows that for every single green job created, that two private sector jobs were destroyed. Of the green jobs created, only one in 10 were permanent jobs.

Our own President has said that his cap-and-trade bill, which is the one that just passed, will cause electricity rates to skyrocket. Skyrocket, Mr. Speaker. That does not sound good when you're talking about the cost of a

product that goes into every manufactured product in this country, that every one of us who likes air conditioning use. That's not a good idea.

This bill also, Mr. Speaker, nationalizes the building codes. No longer will you be able to look to your local planning and zoning commission, your local city council as to how the building code should be. You can't go to your State government. You're going to have to look to the Federal Government. Some bureaucrat in the bowels of the institution in Washington, D.C., is going to decide whether or not you can build a house and what those standards should be.

Congratulations. Thank you so very much, Mr. Tenth Amendment.

Mr. Speaker, MIT has a study that shows this will cost every family in America \$3,100 for implementation of this bill. All of the pain that's associated with this bill and, quite frankly, there is a lot of pain. And we will just begin to see it as the details unfold. So what do we get for that pain?

I've recently asked a climate scientist who feeds his family, basically, looking at this issue. I said, If we were able to pass the Waxman-Markey bill, can you in fact measure after 40 or 50 years the positive impact on our atmosphere? If we're going to spend \$3,100 per family to get this done, if we're going to lose all of these thousands of jobs and decrease the standard of living in America as a result of this deal, what do we get for our money?

He looked me right in the eye, Mr. Speaker, and said, Maybe. Maybe you can measure the impact? He said, Yeah, maybe.

The Congress of Racial Equality, not someone you would normally think would be doing things that Republicans would agree with, their spokesman, Niger Innis, talks about the study they performed that shows that should this happen or, actually, should America go to a zero carbon footprint over the next 100 years, that the impacts on the temperature will be like .07 degrees Celsius over that entire timeframe. Again, not measurable. So a lot of pain for no gain.

Mr. Speaker, I guess the call to action for all of this is for our fellow American citizens to get mad. I'm hoping that, Mr. Speaker, this next week before they go to their 4th of July parades in their cars, which is a limited opportunity because there will soon become a day they won't be able to drive those kinds of cars that they want. We will tell them the kind of cars they want to drive, not themselves.

But I hope they get mad, Mr. Speaker. I hope they use this climate change bill—global warming bill, because we changed the phraseology because the climate is not warming—I hope they use this to incent their TEA parties on the 4th of July to go after us on this deal. I hope they begin to call their Senators and tell them "no" on this deal.

Call your Congressman who voted for this nonsense. There are 219 of them. You can go to the Web and find out who they are. Start calling them now and tell them they made a mistake, Mr. Speaker.

This bill is bad for America, it's bad for our economy, and it will lower our standard of living. It was done simply to allow our President to have a photo op in Copenhagen in December while the Chinese and Indian leaders laughed behind his back.

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from Indiana (Mr. BURTON) is recognized for 5 minutes.

(Mr. BURTON of Indiana addressed the House. His remarks will appear hereafter in the Extensions of Remarks.)

THEIR LIVES, THEIR FORTUNES, AND THEIR SACRED HONOR

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from Texas (Mr. Poe) is recognized for 5 minutes.

Mr. POE of Texas. We all know that liberty is not free, and our history shows that it is cause to stand on principle. But freedom has always been worth the price.

Even before that magic list was published in 1776—on July 4—of the signers of the Declaration of Independence, those 56 men, the British knew who they were, and they had already marked down every Member of Congress suspected of putting their name to that treasonous document. All of them became the objects of individual manhunts by the British. Of course, the punishment for treason was death by hanging.

Of the 56 who signed the Declaration of Independence, nine of them died of wounds or hardships during the American War of Independence. Five were captured and imprisoned. In each case, they were treated brutally. Several lost their wives, their sons, or their entire families. One Member lost all 13 of his children.

Two wives were brutally treated. And all at one time or another were victims of manhunts or driven from their homes. Twelve signers of the Declaration had their homes completely burned. Seventeen lost everything that they owned. Yet not one defected or went back on their pledged word. Their honor and the Nation they sacrificed so much to create is, yes, still intact.

You see, they pledged to themselves their lives, their fortunes, and their sacred honor. And they did not go back on their word.

New Jersey signer, Abraham Clark, gave two sons to the officer corps in the Revolutionary Army. But they were captured and sent to the infamous British prison ship in New York harbor known as hell ship "Jersey," where thousands of Americans who had been captured were going to die.

They were treated with a special brutality because of their father, Abraham

Clark. But when the war was almost over, the British told Clark to come out in favor of the King and his sons' lives would be spared. Abraham Clark, in his anguished answer, replied, No.

Francis Lewis was a New York delegate. He saw his home plundered and his estates in what is now Harlem completely destroyed by the British. Mrs. Lewis, his wife, was captured and treated with great brutality because of her husband.

John Hart of Trenton, New Jersey, risked his life to return home to see his dying wife. But German Hessian soldiers rode after him and he escaped into the woods. While his wife lay on her deathbed, the soldiers ruined his farm and wrecked his homestead.

Hart, 65, hid in the woods as he was hunted throughout the countryside. When he finally made it home, he found that his wife had already been buried and his 13 children had disappeared. He never saw any of them again.

Judge Richard Stockton, another New Jersey signer, had rushed back to his estate in an effort to evacuate his wife and his children. The family found refuge with friends, but a sympathizer betrayed them. Judge Stockton was pulled from bed and brutally beaten and put in jail.

Congress finally arranged for Stockton's parole, but his health was ruined. He returned home to find his estate looted and did not live to see the triumph of the Revolution. His family was forced to live off charity after he died.

John Morton was a British sympathizer, but once he came to sign the Declaration of Independence, he changed his mind and came out strongly for independence. Most of his neighbors, however, in Pennsylvania, and his relatives, were British sympathizers and ostracized him.

When he died, just 1 year later after signing the Declaration of Independence, his last words to his tormenters were, "Tell them that they will live to see the hour when they shall acknowledge the signing of the declaration to have been the most glorious service that I have rendered to my country."

There were similar stories with the other 51 signers of the Declaration of Independence.

A person who did not sign the Declaration, but one of my favorite persons in history, and a son of liberty, was a schoolteacher by the name of Nathan Hale. He was from Connecticut. He was a 21-year-old teacher by trade, but joined the Colonial Army under George Washington.

At the Battle of Harlem Heights, George Washington was facing General Howe in battle and asked for a volunteer to go behind enemy lines and spy on behalf of the Colonial Army. Hale volunteered and went forward.

He disguised himself as a Dutch schoolmaster, set out on his mission for a week and he gathered information on the position of the British. But he was finally captured when returning to the American lines. Because of incriminating papers that he had in his position, the British knew that he was a spy.

\square 2015

It is said that his cousin, a British sympathizer under Howe's command, betrayed him. So Howe ordered Hale to be hanged the following day without trial.

On September 22, 1776, American patriot Nathan Hale was hanged for spying on British troops. His famous last words, I regret that I have but one life to give to my country.

Mr. Speaker, an amazing breed these early Americans. So this July 4th we should pledge to ourselves and our Nation that no matter the cost, we who live here now will not ever allow the flame of liberty or the flag of freedom to quietly disappear from our land, a land that God has shed His grace upon. And that's just the way it is.

The SPEAKER pro tempore. Under a previous order of the House, the gentle-woman from Ohio (Ms. KAPTUR) is recognized for 5 minutes.

(Ms. KAPTUR addressed the House. Her remarks will appear hereafter in the Extensions of Remarks.)

AMERICAN CLEAN ENERGY AND SECURITY ACT WILL CREATE GREEN JOBS

The SPEAKER pro tempore. Under a previous order of the House, the gentle-woman from Texas (Ms. Jackson-Lee) is recognized for 5 minutes.

Ms. JACKSON-LEE of Texas. I want to take this time to say to the distinguished Speaker that I have enjoyed working with him and I thank him for his leadership.

Mr. Speaker, I love America. There is no better country. And I think it is well to express it at the same time of acknowledging the importance of the world family and the respect and dignity that all people around the world deserve.

So as I stand before my colleagues today recognizing that in a few days we will celebrate America's birthday, it reminds me of the uniqueness of this country, that we have the opportunity to agree and disagree but that democracy stands. We have an opportunity to show people what they disbelieve. We have an opportunity to correct what others may have had a chance to misrepresent.

So it is important that we had a vigorous debate today on the American Clean Energy and Security Act of 2009. It is important that we respect the differences of our regions, my good friends on the other side of the aisle, Midwesterners, Southwesterners, people from the west coast. the east coast.

the southeastern part of the United States, our friends as far away as Hawaii and Alaska.

But it is important to note that there was a value that we were discussing. It was not a value to eliminate jobs, to punish certain regions or certain industries. For having been an oil and gas lawyer for a number of years, having worked in natural gas pipeline companies, I know the value of all of the hard work of those who are in that industry. In fact, it has been my argument that we should have a seamless energy policy that continues to enhance and to work with those who are existing in our energy industry today, but let's make it better.

Mr. Speaker, when the Wright Brothers created that small plane, almost a glider, in the Carolinas, it probably was flown by one person. But as we improved, we began to do jetliners and planes that could fly across the ocean, and we created jobs: pilots, flight attendants, airlines, and all the employees that come with it. So, in essence, even as our technology changes, jobs may change but jobs are created.

The American Clean Energy and Security Act will create some 1.7 million jobs and will unlock billions in industry investment and be a major job creator. And \$750 per household will, in fact, be part of the savings that many Americans will see. This doesn't include the new benefits that will come from new technology, reduced pollution, economic growth, or job creation.

I live in Houston. I live in the refinery corridor. So we know what pollution is all about, but we know what jobs are all about. So I believe we can have both.

This is the first step for this bill, Mr. Speaker. It moves to the Senate. And I have told my constituents that you have a guardian against the loss of jobs and that you will see savings, \$29 billion in consumer savings. The American Council for an Energy Efficient Economy found that energy-efficiency provisions in this bill will save \$29 billion. It is important to note as well that we have the opportunity to listen and change.

Let me just share with you some of the work after reading the bill until 5:30 a.m. in the morning on Thursday morning, reading the manager's amendment, which could actually be done, and knowing what is in front of us.

First of all, I discussed and got taken out the impact of building labeling on old buildings, old homes. So the bill was limited to new construction. And we are going to work to ensure that if they do a building-labeling program, as was brought to my attention by the National Realtors, that old buildings, old homes will not be labeled. Your value will not be devalued because of a lack of energy-efficiency efforts in

your home. We worked on that because we believe a home is to be cherished.

Then we opened up the opportunities to minority-owned and women-owned businesses, along with small businesses, to ensure that they would be guaranteed the right to be involved in energy-innovative companies. We did that because we were concerned about creating jobs and we know that small businesses do create jobs.

In addition, I was concerned about displacement, temporary displacement, even though some of these jobs, 1.7 million, will come to my community. So we have language that says the Secretary of Labor will monitor the potential growth of impacted and displaced workers to ensure that necessary funding, funding for training, funding for giving people a bridge to go into a new job, will be, in fact, included. We know that there are issues between big refineries and small refineries. Mr. Speaker, it is crucial that those issues be addressed as we make our way through the Senate.

We also know that the energy industry was divided. Some were supporting this legislation. Others were taking a backseat. Now they've come full circle and they believe that this is a time that they should rally to provide information.

Mr. Speaker, as I close, let me just say we are going to work this bill. We're not going to lose jobs. We are going to have an investment of green jobs and we're going to have an investment in our energy industry. And Houston will be fine. Texas will be fine. We will be working together.

REVISION TO ALLOCATIONS FOR CERTAIN HOUSE COMMITTEES FOR FISCAL YEAR 2010 AND THE PERIOD OF FISCAL YEARS 2010 THROUGH 2014

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from South Carolina (Mr. SPRATT) is recognized for 5 minutes.

Mr. SPRATT. Madam Speaker, under section 323 of S. Con. Res. 13, the concurrent resolution on the budget for fiscal year 2010, I hereby submit a revision to the budget allocations and aggregates for certain House committees for fiscal year 2010 and the period of fiscal years 2010 through 2014. This adjustment responds to House consideration of the bill H.R. 2454, the American Clean Energy and Security Act of 2009. A corresponding table is attached.

This revision represents an adjustment for the purposes of sections 302 and 311 of the Congressional Budget Act of 1974, as amended. For the purposes of the Congressional Budget Act of 1974, as amended, this revised allocation is to be considered as an allocation included in the budget resolution, pursuant to section 427(b) of S. Con. Res. 13.

DIRECT SPENDING LEGISLATION—AUTHORIZING COMMITTEE 302(a) ALLOCATIONS FOR RESOLUTION CHANGES

[Fiscal years, in millions of dollars]

House Assessibles	2009		2010		2010-2014 total	
House Committee -		Outlays	BA	Outlays	BA	Outlays
Current allocation:						
Energy and Commerce	11	2	10	13	-10	-2
Ways and Means	0	0	6.840	6.840	37.000	37.000
Change in the American Clean Energy and Security Act (H.R. 2454):			.,.	.,	. ,	, , , , , , , , , , , , , , , , , , , ,
Energy and Commerce	0	0	9.260	370	266.324	252,354
Ways and Means	0	0	0	0	4,416	4,416
Total	0	0	9,260	370	270,740	256,770
Revised allocation:			,			,
Energy and Commerce	11	2	9,270	383	266,314	252,352
Ways and Means	0	0	6,840	6,840	41,416	41,416

BUDGET AGGREGATES

[On-budget amounts, in millions of dollars]

	Fiscal year	Fiscal year	Fiscal years
	2009	2010	2010-2014
Current Aggregates: ¹ Budget Authority Outlays	3,668,788	2,882,117	n.a.
	3,357,366	2,999,049	n.a.
	1,532,579	1,653,728	10,500,149
(H.R. 2454): Budget Authority Outlays Revenues	0	9,260	n.a.
	0	370	n.a.
	0	948	260,543
Revised Aggregates: Budget Authority Outlays Revenues	3,668,788	2,891,377	n.a.
	3,357,366	2,999,419	n.a.
	1,532,579	1,654,676	10,760,692

 $^{^{\}rm 1}$ Current aggregates do not include the disaster allowance assumed in the budget resolution, which if needed will be excluded from current level with an emergency designation (section 423(b)).

The SPEAKER pro tempore. Under a previous order of the House, the gentleman from Texas (Mr. DOGGETT) is recognized for 5 minutes.

(Mr. DOGGETT addressed the House. His remarks will appear hereafter in the Extensions of Remarks.)

ENERGY AND JOBS

The SPEAKER pro tempore. Under the Speaker's announced policy of January 6, 2009, the gentleman from Texas (Mr. GOHMERT) is recognized for 60 minutes as the designee of the minority leader.

Mr. GOHMERT. Mr. Speaker, I appreciate the time.

This is a trying time. And I appreciate my friend from Texas' belief and hope in the future. I just have read enough of this bill and know enough to understand the consequences. And this isn't the whole bill. This is two-thirds of it. The other 300 pages, they allowed me to borrow a copy briefly earlier today during debate right before the debate closed. But this is about two-thirds of it.

We're having a job fair in Longview, Texas, Monday. That arose when I met with a bunch of my constituents, most of whom were African Americans, in a North Lufkin church a month or so ago who had lost jobs because jobs were being moved overseas. Energy was too costly here. The corporate tax is over twice as much here as what it is in China. And I have been hearing from other manufacturers that we have in our district that if this cap-and-trade bill goes through and becomes law, there will be many more lost jobs.

And it breaks my heart. It broke my heart to meet with those people there

in North Lufkin and others around my district who have lost jobs. So that's why I got to thinking what can I maybe do to help. I know the Texas Workforce Commission does a good job of having job fairs and trying to match up job openings with people's job skill sets and try to get people a job.

As someone said on the floor earlier on our side of the aisle, Our people are not interested in unemployment benefits; they're interested in a job. That's what they want. That's what they had.

We have continued to take actions for the last 2½ years since our friends across the aisle have been in the majority to place more and more of our energy off-limits, to make it more expensive.

I also have plants in my district that use natural gas as feedstock, feedstock meaning that natural gas is absolutely the most essential element to producing the things that they do like plastics and other materials. And natural gas under this cap-and-trade bill will naturally skyrocket. Our Democrat majority leadership is pushing to regulate and tax hydraulic fracking. which will make much of the gas that we're currently getting unavailable and will shove those prices even higher. I lost around 900 jobs in my district when the Abitibi paper mill closed because natural gas was more expensive here in the United States than it was virtually anywhere else. It was a Canadian company. They held on to the property hoping that one day they could reopen it and get back those 900 good jobs, but eventually they have announced they will not be reopening the plant. That was the price of natural gas that did that.

So I know with the job fair I've got coming up in Longview, we have over 60 employers there that will be offering jobs. We had over 600 people show up looking for jobs at the job fair in Lufkin, and I'm hoping it will go well.

But I have read enough of this bill and I know enough about the energy industry because we produce a lot of it in East Texas. We've got coal, we've got oil, we've got gas, solar, wind. But this bill is going to put a lot of people out of work. It's going to put people out of work all over the country. So the job fairs are not going to be adequate for the damage that this bill is going to do.

I have been joined by colleagues here on the floor who I think are as heartbroken as I am. And you would think we'd be giddy, you know, that our friends across the aisle have passed a bill that's going to come back to haunt them. It's going to cost jobs. It's going to make Americans mad. But I'm nothing but brokenhearted because I know what this will do to individuals.

And I know that my friend Mr. SOUDER is likewise affected, and I would like to yield to him.

Mr. SOUDER. I appreciate the honor of being an honorary Texan here tonight because in Indiana we're still unusual. I mean we still make things. We don't have the mountains like they have out West or beaches. What we have are hardworking Americans who are still competing worldwide in manufacturing.

And if you go into any of the types of plants—earlier I was talking about our steel mills in addition to the two SDI mini-mills with recycled steel. Everything they use, they recycle and use recycled materials, as does NuCor. I have a Valbruna steel mill. One of the interesting things that Valbruna has done is they built an additional facility because they're the number one provider of steel to the refinery industry in Texas and Louisiana. So in my district we're making the things still in America. Your options are basically Korea, Brazil, China, or Indiana steel in many of these cases.

But these factories take an incredible amount of energy. Some of our factories, we have 85 percent coal, 15 percent nuclear in our basic provision of things. And basically this bill doesn't like things that we can use in Indiana. It doesn't like coal. They really aren't too fond of nuclear. I think that a lot of the question of what to do with waste, I used to think it was driven by Jane Fonda in "The China Syndrome" movie, but that's us old people. I think the younger people are thinking of Homer Simpson coming in and kind of blowing up the city of Springfield all the time, and they think of that as nuclear energy. There are 13 or 15 or more plants on the drawing board right now,

but it may take 20 years to get there.
What do I do if I don't have coal?
Well, I could use gas and oil, but, boy,
those are kind of bad. We tried to get
the BP Refinery done in Indiana to
handle Canadian tar sands. There's another one over by Detroit. But they're
going to be tied up for 10, 15 years.
They were half of EPA discharge. But
Rahm Emanuel and others are saying,
Oh, no, we can't build that refinery. We
don't want any refineries in America.
Well, we make 58 percent of the RVs.

 $n.a. = \text{Not applicable because annual appropriations Acts for fiscal years} \\ 2011 \ through \ 2014 \ will \ not \ be \ considered \ until future \ sessions \ of \ Congress.$

 \square 2030

What are you going to do, put a little fan up on the roof to try to make these RVs go? International designs—800 people to design the big trucks in my district. How are we going to deliver goods to market? The rail is already jammed, the canals are jammed, the rivers are jammed. If we can't use trucks, which take up about 40 percent of the energy on our roads, how are we going to move around?

The foundries take this—it was the biggest ice cream plant in the world, an Edy's ice cream plant until they built one additional. But when you go in an ice cream plant, how do you think ice cream is made? You have got to deliver it there, the milk in, then you have got to process it and you have all these electrical machines powering this. You know, they can't do that with a couple of solar panels.

I have Kraft Caramels in my district, all sorts of things, not just kind of windshields and axles and stuff. How do you power these kinds of things? I am not against alternative energy at all. I worked hard.

In my district, in fact, Guardian windshields has learned that their process of windshields, if you think about it, took solar heat for a long time. And these solar panels in Nevada and other places are cracking. By going with Guardian, they are learning that they can make these panels more efficient, get 20 percent or more energy, and they don't crack. Spain is using them. The new model projects in the U.S. are using them, and they are going to have possibly hundreds of jobs making the windshields for the solar panel industry.

Of course, they had near a thousand jobs making windshields for SUVs, pickups and things that are now kind of on the bad list, so we will get green jobs, maybe half as many as we had before in that category.

I have Parker-Hannifin in New Haven. We have had an earmark to help them, to try to get the heat down inside of everything from your handheld, your BlackBerry, to wind turbines, and could possibly make the wind turbines 20 percent more efficient. We may have, at some point here, 200 people doing windmill turbines and other things, but that plant had 1,200 supplying traditional energy industries.

I have worked with people who are coming, trying to come up with alternative car engines.

One of my friends and supporters is putting in a huge wind farm. In Indiana, we have two basic areas that we can put wind farms. We might get to 4 percent, but we can't reach the targets in these bills. It's not that we are not committed to alternative energy, but we don't have as much wind and solar. We have to have traditional forms of energy: oil, gas, nuclear, coal, not just the alternative form, especially if they are going to put limitations on ethanol and biodiesel. So this is a critical time,

really, where we are trying to decide in America, are we going to have manufacturing or aren't we going to have manufacturing?

Are we basically going to basically have service jobs and then high-tech jobs? Yes, at a coffee house at different universities they sit around and go, Oh, this stuff sounds really great. And the others in their beach houses on the coast go, Oh, this stuff really sounds great. But what's missing in America is we are getting increasingly two classes of people, and the blue collar class of people who made things and had a decent living where they could get a house, maybe a boat where they could go on vacation, they are disappearing.

And the knowledge class, often in the liberal upper groups of the Democratic Party, are basically saying goodbye to their working class. And they are saying, You can either basically maybe bring us a drink, grill us a hamburger, or go get a doctorate and teach at a university.

What we are losing is the middle group of blue collar Americans who worked with their hands and worked in their fields, and they are basically knocking them out, and those jobs are going to other countries.

Mr. GOHMERT. And perhaps, Mr. SOUDER, that's why, on this map we have here, the dark red is high vulnerability under cap-and-tax to losses of jobs. That's why Indiana is in this area up here where apparently it's in the high vulnerability for high losses of jobs.

Texas, where I am from, it's in the medium vulnerability, but I already know. I have seen the loss of jobs we have

And actually, we have some of the same industries. We have a Nucor, but we have Tyler Pipe, Lufkin Industries involved in steel, but there is going to be a lot of loss of jobs.

Mr. SOUDER. The Heritage study showed that my congressional district is number one is loss. Next to the me is JOE DONNELLY in the South Bend district, who was number two. Congressman LATTA, who asked for the split out, just to my east in Ohio, is number three. MIKE PENCE, who is just to my south in that part of Indiana is number four. Congressman JORDAN is number five and Congressman BOEHNER is number six. Because not only do we have manufacturing, we tend to use coal and nuclear because alternative energy is less of an option in these heavy industrials. Then it kind of jumps up to Michigan.

The other thing that's noticeable in that map where the dark red is and the other is that's really where most of the water is in the United States, coming out of the Mississippi, and to manufacture, you need to have water and access to water. You are not going to move—you will see some in the orange States. You can move some steel and manufacturing into those areas, but basically you can't really transfer to

those light yellow because that's mostly desert area. And you can't power these big plants with just solar or wind, and they don't have enough water to supplement the traditional that you need in refineries and in steel mills and that type of thing, and they don't really have a plan.

That's why we Republicans, when you look at the actual details—if you could even stomach, by the way, the government making all these decisions rather than market, that's bad enough. I mean, that document basically is page after page of the government telling us how we should live, the government telling us how we should make things.

But the bottom line, when you look at that map, if it goes out of the red zone, it's basically going to Mexico, to China, to Korea, to South America. Because the areas that are lighter, where you conceivably could shift it, it's just not possible to build these plants there.

Mr. GOHMERT. I appreciate that, that's an excellent point.

For this heavy manufacturing, you do have to have water. Regardless of any other energy source you may have, it takes water. That's a great point, which is why the traditional iron belt was up here in the Midwest. In those areas, you had water. You had all the things you needed. You had good workers. You had everything you needed to produce those things.

And just as an aside, as a history major and history buff, it needs to be noted. When a Nation can no longer make the things from scratch that are required to defend itself at a time of war, then the country will be lost in the next big war. We are losing the steel industry weekly, and it won't be long before we cannot produce tanks, airplanes, things.

Right now, we are barely able to produce tires because so many of the tire plants have moved overseas. You have got to have tires. You have got to have rubber. You have got to have wood. You know, we cut out so much of the wood industry, and that continues to happen, and people would be surprised how much that's used for.

Natural gas helps—is part of the process of making so many of the parts for weaponry, and that will become more and more difficult to obtain.

Mr. SOUDER. Yes, I don't mean to monopolize the time, but when you say these things, to illustrate the manufacturing in my district. Michelin bought a U.S.—bought a BFGoodrich tire plant in my district with 1,600 people in it. They have invested \$15 million a year if they can become 5 percent more efficient, so they put \$120 million into this huge plant, and people don't even realize what they are putting in. And I was just part of a suit to say stop the dumping, because we can compete with China without the dumping, but not if you add 7 percent health care and then add a cap-and-trade and then add the other OSHA and all the types of regulations that are coming back that we had restricted, we can't compete in tires.

I have a lot of the defense industry. I have a BAE plant with 2,500 people working in it. They do a lot for Boeing. One Member just a moment ago referred to Wilbur and Orville Wright and the amazing thing, but, you know, we are going to go back to these kinds of paper airplanes if we are not careful here. Boeing, that's metal. It takes energy to build every part in that plane, and it takes energy to launch the plane. And it's not—let's just say, they don't have windmills on this thing. They don't have solar panels to get a jet up in the air.

I have NASA satellites. The ones that feed into The Weather Channel are made by ITT in Fort Wayne, and they actually are looking at being able to track, as my friend from Texas earlier said about, we don't really have the science on that. Well, that's what one of the companies in my district is looking at; can we get satellites up in the air to track the climate change? Because the truth is, we are doing this bill with no data.

But put a satellite up. You know what, it has aluminum on it. You know what takes an incredible amount of energy to make, aluminum. The electrical systems in a plane and a satellite are copper. You can't get copper if you can't mine for copper. You can't make—the smelting of copper takes an incredible amount of energy. Aluminum and copper take as much or more energy than steel. How do they think we are going to get airplanes? How do they think we are even going to track the climate change?

It is baffling that this bill could have gone through a Congress. I am going to make a flat-out statement. If most of the Members of Congress were businessmen, this would have never passed.

Mr. GOHMERT. I appreciate my friend's point, and that is a good point.

I think if most of the people in this House had read this bill and been given a chance to read the additional third that was added at 3 a.m. or so this morning, then I don't think this would have passed either.

But we have been joined by another friend, a former fellow judge, a district judge also. I would like to yield to my friend, Mr. Poe.

Mr. POE of Texas. Thank you for yielding, Judge GOHMERT. You know, we approach what we consider the most important of all days for our Republic, and that's Independence Day.

And this legislation that unfortunately passed tonight has not made us more independent, but it has made us more dependent. As a Nation, we are more dependent upon, now, government control of every aspect of our lives, our personal lives, our business lives.

When the government starts telling you what type of electricity you can have in your home, when the government starts telling you that you have to pass an energy efficiency before you can sell your home, maybe we have gone too far in the government con-

trolling our lives. But that's just a smidge of what has occurred in the passing of this legislation.

I am not sure what the goal of the legislation was. We heard different things. One was that it's going to create more jobs for Americans. Well, that's just not going to happen. All the sane studies show that that's not going to occur in the United States.

There will be government programs, which means subsidies paid by tax-payers to go to, quote, green jobs. Those are programs, and they will be created, subsidized by the taxpayers, to move us in a direction of the green environment, which I will say just a little bit more about in a minute.

But one group that has not been mentioned today in the House debate that talked about jobs, the National Black Chamber of Commerce said this legislation will cost 2.5 million jobs almost immediately. Well, that's a lot of Americans being put out of work when we are already having Americans losing their jobs.

We do have an example of a country that has tried this legislation. Although they didn't sign this one, it's one very similar. Spain has had this so-called idea of trying to control carbon emissions in their country for several years, and they have created jobs, but they have lost jobs. For every green job that they have created, by their own statistics, two other jobs have been lost.

Now, I am not a CPA like Mr. CONAWAY is, but it would seem to me the more green jobs you create, the more jobs you are going to lose.

And that's what Spain has done, and now they are trying to get out from under their own legislation that has cramped their economy because they are losing jobs by moving to this so-called green job economy. So we are losing American jobs overseas for a lot of reasons already, and a lot of it is because of the high cost of energy. Now we are going to have energy cost increase. So first idea, a goal to create American jobs, that's just fiction.

The second thing is that this is supposed to be a bill to save the planet. You know, humans are bad and that we are creating all this gas that we need to control, and it's all because of energy. And so if we have this legislation that passed, we are going to save the planet.

Up until a few months ago, we heard from those people. That was called global warming. But since global warming is not occurring, it is now changed to climate change. We changed the title, because global warming does not appear to be what those who claim it to be is occurring here.

Now we hear from the Congressional Budget Office, when they testified before the Senate several weeks ago, that the effect of this legislation will have little or no effect on climate change.

□ 2045

Now, the first goal, create jobs, is a fiction. The second goal, to control the

climate from bad humans, is not going to have any effect because of this legislation. And the third thing about this legislation is it costs too much; we can't afford it. We can't afford it even if it did create jobs or save the planet. But the billions of dollars in that 1,200 pages you have in front of you there, Judge Gohmert, that's going to cost Americans. It's not going to result in what we were all promised. So those are two items that I see as a major problem.

And another problem that I think is very paramount is the fact that we're going to turn our lives, our businesses over to government control. The government is going to control all energy in this country and it's going to tax it all. You turn on these lights here in the Capitol—of course this is the government, they don't have to pay their bills—but if you turn them on at home. the cost of electricity is going to go up. If you use natural gas, a hot water heater, that's going to go up. You drive down the street using gasoline, that's made from crude oil, that's going to go up. Because everything that uses energy—which is everything—will cost Americans more. The energy companies, the ones that stay in America, they will pass that tax on to consumers, and the consumers pay because the consumers always pay.

But the hardest hit group is going to be, as Mr. SOUDER from Indiana said, the small manufacturing plants in the United States. They have to use energy to produce their products. Whether it's a paper mill in east Texas or whether it's a van up in Indiana or whether it's a small steel mill in my district, they have to use some form of energy to produce the product.

Now, the cost of that energy is going to go up so high they cannot produce the product and sell it. Because, you see, over in China, they're producing the same product and can ship it to the United States cheaper because they're not bound by all of these energy regulations and are not taxed for use of energy as American manufacturing companies will be. And that's a sad thing because it has always been the small business—and really the small manufacturing companies—that's been the heart and soul of the American economy.

You know, there was a time when you could go into a Wal-Mart—vou've got them in your district, I don't know if Mr. CONAWAY has them in his, but we have a lot of Wal-Marts—but you could go into a Wal-Mart and they had a big sign that said "Made in America." They claimed that everything they sold in that Wal-Mart was made in America. Well, that sign isn't up anymore; it hasn't been up in years because I don't think they make anything in America that they sell at Wal-Mart. It irks me to no end. This time of year, you go into a Wal-Mart and you want to buy a flag, just like that one behind the Speaker, and it's made in China. We can't even make our own

flags because manufacturing in this country is being killed by the cost of doing business. And that bill in front of you, Judge GOHMERT, is not going to help that at all. It's going to just make the situation worse.

The last thing that bill does not do is create more energy. It taxes energy. It does not provide for more energy for Americans. Nuclear energy, I mean, even France, 80 percent of its energy comes from nuclear energy. And it can be done and created in a clean and safe way. We don't have any more nuclear plants in this country because of the fear tactics that have been placed upon the thoughts, so we don't use nuclear energy.

So we're not doing anything. We're not drilling offshore even for natural gas. Natural gas is supposed to be the product that we go from this one environment to this beautiful environment. Of course, we can't get there from here. And now the other side that voted for this bill says, well, we need natural gas to bridge that gap because it's clean. Well, they don't allow drilling. You can't drill anymore. You can't drill offshore. You can't drill anywhere that there is natural gas. So how are we supposed to have energy to get to the clean energy if we cannot, as a Nation, even drill for natural gas?

So there's no nuclear, no natural gas, and of course we can't use clean coal. We don't want to use any more of that nasty old crude oil, even though crude oil and its byproducts is in everything Americans use, from plastics to our radios to our cell phones. It's in everything. And it's a derivative of some product of crude oil. We are always going to need crude oil to build the products that we have in this country. You can't build them all from biodiesels.

And so the bill does not do what it's supposed to do. It doesn't create jobs, it doesn't help the climate, it doesn't give us a new alternative for energy until we get to this supposed clean energy. And of course I think the worst thing is it takes control of Americans and their independence and makes us slaves to the Federal Government and the Federal bureaucrats to run our lives every day.

I will yield back, Judge GOHMERT.

Mr. GOHMERT. I appreciate so much those sterling observations about what this bill does and the effect it's going to have.

I know last summer I was approached by so many different people about the high price of gasoline. And I know those same people are going to get hammered again as time marches on—the summer into the fall into winter—if this becomes law. And the only thing standing between it now and becoming law is the Senate, because the President is sure going to sign it if it gets there. But a single mom saying I don't make enough money to live in town, so I'm out in the rural area, which means I have to pay for more gasoline to get into town, I'm maxing out my credit

card every month just on gasoline. And it's getting close on whether I have enough leeway each month on my credit card to get enough gas to keep going back and forth to my job, because if I lose my job, I can't pay anything, including my credit card bill. And just the desperation in their eyes.

The things that are in this "crap and trade" bill, they're an inconvenience to the wealthy. They will be an inconvenience; but to people like that single mom and to so many others that are just struggling to get by—one 80-plusyear-old lady told me last summer, she said, you know, I started out in a house that had no running water and no power, we cooked with wood. And she said, Because of the price of fuel now, it looks like I'm going to finish my life in a house the way I started. This bill is going to do that.

And I know that privately there are people who are so pleased about this bill because they really believe if gasoline goes to \$10, \$20 a gallon, people won't use it and they will save the planet. And what they don't seem to understand is the only way you ever get a grip on pollution is to have an economy that is just thriving, that's doing so well in an advanced society, like ours has been, and then they're able to do something about pollution. But with this bill being passed, it is going to so cripple our economy. And when people lose their jobs and they're struggling and they can't make ends meet and they're using wood to cook food, they could care less about the environment. It's unfortunate, but it's true. They care more about living and sustainability.

And so what happens is these jobs will go to places like China, India, Brazil, where the pollution standards are not what they are here. And so they will put out, as we've already heard today, three, four, five, six times more pollution than we would if we kept the jobs here. And guess what? That pollution goes into the same atmosphere that these people over here are complaining about.

So by passing a bill that drives jobs, which this will, to other countries who don't have our pollution control and don't have our sensitivities to pollution, then we are doing such a disservice to the environment.

Mr. POE of Texas. Will the gentleman yield?

Mr. GOHMERT. I certainly will.

Mr. POE of Texas. Let me just speak to that issue of jobs. As you know, in my southeast Texas district I have 20 percent of the Nation's refineries; and those are blue collar jobs, union jobs. And it's a tremendous concern for not just management, but for those people who work in those refineries when they're told that the cost of producing energy—because they have to use, as you mentioned, fuel to produce energy—that they will be driven out of business and somewhere else where they didn't sign this 1,200-page bill. You know, China didn't sign that, Cuba

didn't sign it, India didn't sign it. They laugh at us for signing it. And they're really doing a better job of making sure that they produce energy cleanly.

Perfect example: as you know, and have also advocated, we should drill in the Gulf of Mexico for more crude oil and natural gas. We can do that safely and cleanly. But we're not doing it. So who's going to do that? The Cubans and the Chinese are going to be drilling in waters that are near the United States where we ought to be drilling. And I can assure you that those platforms that the Cubans are building and the Chinese are helping them build are not going to be near as safe, pollution safe, as what we can currently do. And so it makes no sense that we hurt ourselves in producing energy and automatically say we're going to punish energy consumption by taxing energy and its consumers, the American people, out of business in hopes that we can get a cleaner environment. We'll all be riding bicycles and living in towns where we used to have to use candles because we're not going to have the energy to take care of ourselves as we are doing now.

I would yield back. Thank you.

Mr. GOHMERT. Well, I appreciate those observations.

And we've gotten testimony and evidence in other hearings that indicate if we were to open up the Outer Continental Shelf of this country where drilling is not allowed, it would, within a couple of years, have added 1.2 million jobs—not just on the platform, we're talking about most of those jobs would be added throughout the country

We also understood from evidence presented that if you allowed drilling in ANWR, 1.1 million jobs added, there would be a handful, there would be some up in ANWR, but around the country to deal with all of that oil that would be produced. There are slopes in Alaska where drilling is not permitted that have incredible amounts of natural gas, that if allowed to drill, there is another 1.1 to 1.2 million jobs that would be added. If we just used the energy with which God has blessed our country, we would have 3.5 million more jobs. And then the President-it would suit me fine if President Obama took credit for it. If we start producing that, then he could live up to his pledge and say, see, I told you I would produce 3 million more jobs. Then he changed that to "save or produce" million jobs because he knew nobody could prove if he saved a job or not. But this would nearly produce 4 million jobs. And I would be happy with him taking credit just to have people employed and producing energy, making us less reliant on countries overseas.

And I appreciated the point our friend, MARK SOUDER, made earlier about you do have to use energy to produce these products. And it's the same with agriculture. You know, we have a good bit of agriculture in east

Texas where I'm from. And as one farmer pointed out, they don't make a Prius tractor. There is no hybrid tractor. And when you get away from the barn and you've got to have power, to my knowledge nobody makes a hybrid generator—which is a joke because a hybrid means you plug it in, and if you plug it in, you wouldn't-anyway, I won't explain it. But you have to use diesel, you have to use gasoline, kerosene, something to produce the energy that agriculture needs to produce.

And then the fertilizer, goodness sakes, it takes massive amounts of natural gas to produce the fertilizer that the farmers use to produce all the food we get. And so it is heartbreaking to know how agriculture, you know, it's just going to devastate the middle class, the lower middle class, particularly. And what we are going to see in the next days ahead is heartbreaking.

We are joined also by a friend who Mr. PoE indicated is a CPA. And I always appreciate the way he looks at things because it's such a straightforward approach. So I would like to yield to my friend, Mr. CONAWAY.

\square 2100

Mr. CONAWAY. I thank the gentleman. I appreciate that.

These are troubling times, and this bill is awfully troubling. The science that surrounds this climate change issue, everybody gets an opinion about it; but there's only a certain set of facts that we ought to deal with.

One of those facts is, if you would equate the Earth's atmosphere to a football stadium with 10,000 people in the stadium—to you guys from Texas, in Indiana we play a lot of football there. So there are 10,000 people in the stands. About 7,600 of those people are wearing jerseys that say "nitrogen" on the front; and about 2,100 or so have iersevs that say "oxygen" on them: and about 100 of them, or so, would say "argon." The remaining 100 or so jersevs in that stadium are referred to as trace elements. Among those trace elements are four jerseys—up from three 150 years ago—four jerseys that say "CO2." So the catastrophic disaster of biblical proportions that is being predicted by the zealots and the religious folks on this climate change thing argue that the addition of one more jersey that says CO2 on it to that stadium of 10,000 drives the change that they're talking about.

Now I'm skeptical. I get to be that way because everybody gets their own opinion. That's a fact. You get to interpret that fact however you want to. But the truth of the matter is, that's what they're asking us to believe. If you look at the 21 models that the Intergovernmental Panel on Climate Change used to predict this disaster, and they start in the year 2000, and you plot them on a graph over time, and they start out with a bracket, you've got the worst-case scenario on the top, the best-case scenario on the bottom, and then all those in the middle. They

start at a relatively narrow band, and they go out over time. They begin to spread a little bit. Then they get out a certain number of years, and they go straight up, big slash. It kind of looks like a hockey stick at that point. Right there is where Earth ends as we know it, life ends as we know it, under their scenario.

So you've got that graph plotted over time, starting in 2000. If you had plotted Earth's actual temperature for the last 9 years on that exact same graph. it's below the best-case scenario, and it's falling away from the path that their predictions are on.

Now, I've got a lot more experience in financial projections than I do climate change projections, but the concepts are the same. Whatever your time frame on your projection, the most accurate period is the near term. In other words, you should be able to get the close-in years right, so to speak. So what these climate signs are saying is, their 21 models couldn't get it right in the first 9 years.

Now what they've not been able to explain is there's some sort of a selfcorrecting mechanism in their scheme that somewhere out here, it brings them back in line with what's going on, and it marries it back up. So if your predictions don't get it right in the first 9 years, should we trust those predictions? The other question you have to ask yourself is, Did you come up with the model before you came up with the answer? Or did you come up with the answer, and then you derive a model to get there? I can't answer that

Now these models look incredibly accurate because they are fraught with algebraic equations and all kinds of high math and calculus and trigonometry and all this kind of stuff that I'm sure you have built into these things. They look very great, and they look very intellectual. But they are predictions. They are guesses. They start with a series of assumptions. And if you take them back in time-I don't know that if you put it back in time and put the really out numbers in there and ran them forward that they'd get it even better. So the models themselves are not working, and that's what's driving the change in terminology from global warming to climate change, man-made, by the way.

If you look at the quotes from our President, who is one of these aficionados, one of these people who has drunk the Kool-Aid, so to speakthis is a quote from Senator Obama who was then trying to convince us that he should be President of the United States. Apparently he convinced about 53 percent of us that that was a good idea.

I guess he must have been really tired that day, talking to the editorial board because he got very straightforward and didn't mince his words too well. He probably wishes he had these ones back. But he said, "Under my plan of a cap-and-trade system, electricity

rates would necessarily skyrocket." Well, to those of us from west Texas, that would mean that if I am paying \$2 for something today, then to skyrocket means that I am going to be paying \$7. \$8, \$9 for it at some point in the future. So it increased costs on the skyrocket thing.

And there's a ellipse here of where he goes on to talk about coal-fired powered plants and the coal industry having to be retrofitted and fixed and brought into the 21st century, so to speak, and the costs associated with those, that will cost money. And they, the energy producers, will pass that money on to consumers.

Now you and I are the consumers. Anybody who pays for the turning on of a lightbulb is a consumer in this regard.

Mr. SOUDER. Would the gentleman yield for a question?

Mr. CONAWAY. Sure.

Mr. SOUDER. If you could put your quote back up, I just want to say that you are just so incredibly not politically correct for this day and age.

Because American electricity rates would go up, but we're world citizens now. Surely you are not claiming that rates would go up in Pakistan, China and other places. We use a disproportionate amount of the energy of the world. So we should be willing to sacrifice so that all the world's citizens can benefit more by taking our jobs and having a better standard of living. Then we can be all more equal. You are just not being politically correct tonight.

Mr. CONAWAY. Well, I struggle with that, obviously.
Mr. SOUDER. You are acting like an

American, Congressman.

Mr. CONAWAY. These are American consumers, American jobs and American families that our good colleague from east Texas has been talking about. If you look at what other nations have done—and I am never one to say, Well, if so-and-so is doing it, we ought to do it too. But if you can learn from their example and apply it to your own circumstance, then there may be some value there. Australia. there's an editorial in today's Wall Street Journal that recounts Australia's struggle with this issue. Their Prime Minister, much like our President, ran last year on a platform that he and Obama would, together, cure this issue. To get it through their House of Representatives, he had to delay the implementation of it under their legislation until 2011.

So this urgency thing that you've been hearing about—that if we don't do something soon that life will end as we know it-apparently has softened a little bit under the new terms since the world's getting cooler instead of warmer. But the story went on to say that they would not get it through the senate in Australia.

New Zealand right after last year. right after the new government took over, suspended their cap-and-tax program within weeks of its initial implementation because they didn't believe

it was correct. Poland's leadership is now saying that we are skeptical on the science. The Czech Republic has folks saying, We are skeptical. There are scientists in this country that are beginning to say—politically correct now—to challenge this science associated with this because prior to this if you did it, you were called a Neanderthal, a knuckle dragger. One of our colleagues today called us "Flat Earth People." You know, those kinds of things. But now it's beginning to be a little more politically correct to be able to say, hey, the scientists never settle on any issue, certainly not something as unknown as this is going on. So the science is beginning to push back on them.

And one final thing for my colleague who mentioned the 20 percent refinery. There was an article in Bloomberg today, talking about how major oil companies intend to cope with this bill, and they intend to cope by reducing their emphasis on refining. No more investment. They will shut them in. They would rather buy the oil, produce the oil overseas, refine it overseas and import refined products to this country to sell as opposed to buying it. What we would prefer to do is produce the crude oil from the U.S., and refine it in U.S. refineries. Those are all U.S. jobs. But companies will adapt to this. They will figure out how to make this deal work, and it will be at the expense of the American economy and American jobs and American families who will be punished with this legislation.

So I appreciate my colleague leading the fight tonight, giving us this opportunity to talk to each other and the Speaker about what's going on because this is—as I mentioned earlier this afternoon, there is an old movie that was entitled, "Bad Day at Black Rock." Folks, this was a bad day at Black Rock for this country.

With that, I yield back.

Mr. GOHMERT. Thank you, Mr.

Mr. SOUDER. Will the judge yield for a minute?

Mr. GOHMERT. I will yield to my friend Mr. SOUDER.

Mr. SOUDER. You have been making a number of parliamentary points today during the debate and on the floor. You are an experienced judge as well as a Congressman. Is he allowed to use factual science on the floor? I don't know if we're allowed to really debate this stuff. This is mostly an ideological bill, not a factual bill. As Mr. Conaway correctly said, did they come to a conclusion and then make the facts fit the conclusion? It is really disturbing. Much of what's behind us is, in fact, that there's a group of people who feel guilty about us being such a successful Nation and about Western nations being so successful and that we use a disproportionate amount of the energy of the world and that somehow we should not do that. Some of the other western countries, like Australia and New Zealand, as you pointed out, are

like, Hey, what's going on here? Do we have to buy into this? What does it exactly mean that we need to sacrifice and go down in our lifestyle? What will we gain? Is the science really there?

Then the developing countries that want to be like the United States, they look at us like a model, and they are going, like Poland, Hey, what is this stuff here? Is this something that you guys came up with at some university or a couple guys smoking some marijuana cigarettes? Or is this real fundamental stuff? And maybe we ought to prove this before we give up our cars, before we give up our SUVs and our station wagons.

I mean, we've had this debate about the Volt and whether GM should go to an electric car that costs \$40,000. We talk about gas and oil and how you power these big trucks that I make in my district and how you power the RVs. How exactly are you going to tow a towable with a Smart Car? That the challenge is, how are you going to move around? And one of the questions is, I think they think that electric cars, when you plug them in, that the electricity is in the wall. What is going to make the power to power electric cars? And how many, kind of, regular people are going to be able to afford a \$40,000 electric car?

Which gets to the core of this bill. We've had Members on the floor today say, Oh, well, we're going to fix this because low-income people are going to get exemptions, and there's going to be this class that gets an exemption. About 80 to 90 percent of that bill are government preferences to try to fix the problem they are creating.

In fact, one of our colleagues, the Democrat from Oregon, Mr. DEFAZIO, in his 1-minute this morning made two terrific points. One was, the alternative jobs and alternative energy are being created faster now than they will be under this bill because we're moving in that direction already with the incentives in the market. And with some supplemental funding out of Congress, some tax incentives out of Congress, we're going to get major breakthroughs.

I have a car company in my district that may be able to get 60 miles a gallon out of E85. The test case shows they got 100 in the first test, and it's a new motor. But if we mandate electric cars, it will never come to market. Government doesn't make efficient decisions, that if they protect this class, protect this company, protect the TVA power system but not this power system, you get all these special categories.

But what we know is, as all of you have pointed out, the upper classes will figure that out. They're not going to get damaged much by this; and to some degree, they're going to try to cover and patch up in a mishmash of expensive government regulatory programs. And who gets lost in this? The very people that the other party promised to protect when they ran, the middle

class, the forgotten man and woman and young person who is somewhere in the middle, working hard and not, as Mr. DEFAZIO pointed out in his other point, making money on credit swaps.

We're going through one of the greatest financial messes in the world, and we have just set up a cap-and-trade. What does trade mean? We call it capand-tax. Cap and send the jobs to China. A number of different things. Mr. GOHMERT a while ago just coined another version of the bill. But the bottom line is, the trade is trading credits and swapping and then securitizing those in markets and encouraging other countries around the world to do this. This will be a boondoggle. How many trees did you plant in Brazil to offset your ethanol plant? How many whatever did you do in damming up a river, which historically the environmentalists were opposed to damming. Now they talk about hydropower. Which is it? You did a hydroplant in Thailand. Therefore, you get to have a credit swap worth \$50,000. You put that \$50,000 out. A number of people bid on it. That gets leveraged 30 times. We're creating a bigger mess than we have now, based on trying to do all sorts of equalization. This is a disaster, and it cannot happen without basically destroying our country.

We pointed out tonight different angles of this, and this is not—as Mr. Poe goes through his list on July 4 and our Founding Fathers and what they sacrificed for. They sacrificed for freedom, not for government setting up credit swaps, protecting one group of people against another group of people, one region against another group of people. Then when you complain, they make deals on the floor during the debate today. Oh, I didn't realize that. There's such a lack of understanding that it takes that many pages. By the time we get done with the regulations, there will be that stack across that whole top of the table, and they'll still be inventing it as people sue and go to court to judges, like my friend Mr. GOHMERT said.

Mr. GOHMERT. I appreciate so much, Mr. SOUDER, your great observations.

Thomas Jefferson said: "The natural progress of things is for liberty to yield and government to gain ground." And that's what we're seeing in this bill, the dramatic gains of the government's right to control your life in this bill are just extraordinary.

□ 2115

I do want to make a couple of quick points. Apparently we have about 7 or 8 minutes left.

For one thing, Mr. Conaway had mentioned earlier that it will likely cost the average family across America an extra \$3,031. And I know there will be some people out there who have seen some in the mainstream media say, oh, well, we saw where that guy from MIT said it won't cost that much. It may be \$300 or \$500 or \$600, but it won't be \$3100.

Those people just bought the Democratic talking points and didn't bother to check to see why it was that they are saving that it won't cost over \$3,000. From what I have read, apparently they are saying it won't cost over \$3.000 because even though the average family will pay more than \$3,000 additionally because of this bill, they are saying what you will get back from the government in the way of services and benefits will be a wash because of all that you will get out of the government as a result of that extra \$3,000 you pay for energy in the first year. It won't be that much, because you will be grateful for all you get. Baloney.

And another thing we heard in debate on the floor today about was, gee, the AFL-CIO leaders and other union leaders, we heard these union leaders were in support of this bill. Well, how about that? They were in favor of the government taking over GM and Chrysler. Why? Because they got a deal. They get to own the companies. Who knows what they have promised the union leaders to support this "crap-and-trade" bill.

It is a sad, sad day for America because the rank-and-file people in America are going to pay a severe price. This intrudes into their lives so much. And for my unfortunate Democratic friends who have not read this, they said, no, no, no. This will provide jobs, not take jobs. They just need to go to section 426 where it talks about the climate change adjustment allowance because there are provisions in it. They know that people are going to lose their jobs as a result of this bill. So it is built in here.

Now, you have to understand, though, it says here, you won't get such allowance for the first week you are unemployed. But then it will kick in after that. There is good stuff here. Over here it does mention that you're not going to get an adjustment allowance for that first week either that you're unemployed. They know this is going to cost so many jobs.

There is climate change adjustment assistance and relocation assistance. Unfortunately, it is not going to pay you to go get your job back from China, India, Brazil and Latin America. So that part of the relocation is not going to help. But I'll tell you the one that just galled me to no end. It says here, absolutely part of the law, the Secretary shall conduct a study to examine the circumstances of older adversely affected workers.

In other words, if you're over 50 or so and you lose your job—because you're going to, you're going to lose a lot of jobs here—and you lose your job, when you do as a result of this bill, don't worry. We are going to do a study about you and your lost job. That will warm your heart, won't it? It won't keep you warm on a cold night next winter when you lost your job as a result of this bill.

But the good news is, the Senate has still not acted. Mr. Speaker, it is not too late for people to let their Senator know, look, I know you're a Democrat. I know the pressure is enormous. I know they are promising you all kinds of things to get you to vote for this bill. But don't get sucked in, because we will be the ones, the constituents will say, for paying the price for your sin and error.

I would like to yield to my friend, Judge Poe, in our last few minutes.

Mr. POE of Texas. Thank you for vielding.

The concern that I have about this bill is that, as I mentioned at the outset, we love the fact that we are a free people and that we are an independent Nation. This bill makes us dependent on government. It will control our lives. We have to get permission from the government for every action we will take as individuals and as businesses. We do not have free will to make decisions, because the government won't let us have that free will to make decisions. Decisions will be made by the government. The government picks winners and losers in that bill because it creates great subsidies to some people to make them more dependent on government and government con-

That is not what America is about. America is about freedom. It is not about dependence.

So the sad part about the bill is the aspect that it creates right here in Washington, D.C., as Mr. CONAWAY said, the center of the universe to some, control over everybody from Indiana to Texas to California to Hawaii to Florida. And that ought not to be.

Mr. GOHMERT. Thank you, and I appreciate your observations. I would like to also observe, though, we heard during the debate today that the National Association of Realtors was supporting this. Obviously they didn't know about the 300 pages added at 3:08 a.m. this morning, because whoever that Realtor was that pushed that should lose their job because it is going to cost them commissions. It is going to cost them royally.

With that, Mr. Speaker, I would yield back time.

OMISSION FROM THE CONGRES-SIONAL RECORD OF THURSDAY, JUNE 25, 2009, AT PAGE H7437

RELATING TO IMPEACHMENT PROCEEDINGS OF JUDGE SAMUEL B. KENT—MESSAGE FROM THE SENATE (H. DOC. NO. 111–53)

The SPEAKER pro tempore laid before the House the following message from the Senate; which was read and referred to the managers on the part of the House appointed by House Resolution 565 and ordered to be printed:

I, Nancy Erickson, having custody of the seal of the United States Senate, hereby certify that the attached record is a true and correct copy of a record of the United States Senate, received by the United States Senate Sergeant at Arms from Samuel B. Kent on June 24, 2009, and presented to the Senate in open session on June 25, 2009.

In Witness Whereof, I have set my hand and caused to be affixed the Seal of the United States Senate at Washington, D.C., this 25th day of June, 2009.

I, Samuel B. Kent, Judge of the United States District Court for the Southern District of Texas, hereby tender my resignation as a Federal District Judge effective 30th June 2009.

SAMUEL B. KENT,

Dated 24 June 2009.

Witnessed: Terrance W. Gainer; 4:44 p.m., Andrew B. Willison.

SPECIAL ORDERS GRANTED

By unanimous consent, permission to address the House, following the legislative program and any special orders heretofore entered, was granted to:

(The following Members (at the request of Mr. Peters) to revise and extend their remarks and include extraneous material:)

Ms. Woolsey, for 5 minutes, today.

Mr. George Miller of California, for 5 minutes, today.

Mr. Peters, for 5 minutes, today.

Mr. Schiff, for 5 minutes, today.

Ms. KAPTUR, for 5 minutes, today.

Mr. SPRATT, for 5 minutes, today. Mr. DOGGETT, for 5 minutes, today.

Ms. Jackson-Lee of Texas, for 5 minutes, today.

(The following Members (at the request of Mr. CONAWAY) to revise and extend their remarks and include extraneous material:)

Mr. McCLINTOCK, for 5 minutes, today.

Mr. Conaway, for 5 minutes, today.

(The following Member (at his request) to revise and extend his remarks and include extraneous material:)

Mr. Boccieri, for 5 minutes, today.

BILL PRESENTED TO THE PRESIDENT

Lorraine C. Miller, Clerk of the House reports that on June 26, 2009 she presented to the President of the United States, for his approval, the following bills.

H.R. 1777. To make technical corrections to the Higher Education Act of 1965, and for other purposes.

ADJOURNMENT

Mr. GOHMERT. Mr. Speaker, pursuant to Senate Concurrent Resolution 31, 111th Congress, I move that the House do now adjourn.

The motion was agreed to; accordingly (at 9 o'clock and 21 minutes p.m.), the House adjourned until Tuesday, July 7, 2009, at 2 p.m.

$\begin{array}{c} {\tt EXECUTIVE~COMMUNICATIONS},\\ {\tt ETC}. \end{array}$

Under clause 2 of Rule XXIV, executive communications were taken from the Speaker's table and referred as follows:

2459. A letter from the U.S. Senate, transmitting a message from the Senate pertaining to the certification of the resignation of Samuel B. Kent, Judge of the United States District Court for the Southern District of Texas. Referred to the Managers on the part of the House appointed by House Resolution 565; (H. Doc. No. 111—53).

2460. A letter from the Fiscal Assistant Secretary, Department of the Treasury, transmitting the Department's report that no exceptions to the prohibition against favored treatment of a government securities broker or government securities dealer were granted by the Secretary during the period January 1, 2008, through December 31, 2008; to the Committee on Financial Services.

2461. A letter from the Fiscal Assistant Secretary, Department of the Treasury, transmitting the Department's report on two modifications to the auction process in 2008 that are deemed significant, pursuant to Public Law 103-202, section 203; to the Committee on Financial Services.

2462. A letter from the Chairman, Council of the District of Columbia, transmitting a copy of D.C. ACT 18-116, "City Market At O Street Project Financing Clarification Temporary Act of 2009", pursuant to D.C. Code section 1-233(c)(1); to the Committee on Oversight and Government Reform.

2463. A letter from the Chairman, Council of the District of Columbia, transmitting a copy of D.C. ACT 18-117, "DCPL Procurement Temporary Amendment Act of 2009", pursuant to D.C. Code section 1-233(c)(1); to the Committee on Oversight and Government Parform

2464. A letter from the Chairman, Council of the District of Columbia, transmitting a copy of D.C. ACT 18-118, "Day Care Facility Temporary Act of 2009", pursuant to D.C. Code section 1-233(c)(1); to the Committee on Oversight and Government Reform.

2465. A letter from the Chairman, Council of the District of Columbia, transmitting a copy of D.C. ACT 18-122, "Adoption and Safe Families Amendment Act of 2002", pursuant to D.C. Code section 1-233(c)(1); to the Committee on Oversight and Government Reform.

2466. A letter from the Chairman, Council of the District of Columbia, transmitting a copy of D.C. ACT 18-115, "Withholding of Tax on Lottery Winnings Temporary Act of 2009", pursuant to D.C. Code section 1-233(c)(1); to the Committee on Oversight and Government Reform.

2467. A letter from the Deputy Assistant Administrator for Regulatory Programs, NMFS, National Oceanic and Atmospheric Administration, transmitting the Administration's final rule — Taking and Importing Marine Mammals; Taking Marine Mammals Incidental to Missile Launch Activities at San Nicolas Island, CA [Docket No.: 090218189-9910-02] (RIN: 0648-AX29) received June 22, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Natural Resources.

2468. A letter from the Deputy Assistant Administrator for Operations, NMFS, National Oceanic and Atmospheric Administration, transmitting the Administration's final rule — Atlantic Highly Migratory Species; 2009 Atlantic Bluefin Tuna Quota Specifications and Effort Controls [Docket No.: 080728943-9716-02] (RIN: 0648-AX12) received June 22, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Natural Resources.

2469. A letter from the Deputy Assistant Administrator for Operations, NMFS, National Oceanic and Atmospheric Administration, transmitting the Administration's final rule — Taking of Marine Mammals Incidental to Commercial Fishing Operations; Atlantic Pelagic Longline Take Reduction

Plan [Docket No.: 070717352-8886-02] (RIN: 0648-AV65) received June 22, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Natural Resources.

2470. A letter from the Deputy Assistant Administrator for Operations, NMFS, National Oceanic and Atmospheric Administration, transmitting the Administration's final rule — Fisheries of the Exclusive Economic Zone Off Alaska; Bering Sea and Aleutian Islands Crab Rationalization Program; Amendment 27 [Docket No.: 080416577-9898-03] (RIN: 0648-AW73) received June 22, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Natural Resources.

2471. A letter from the Acting Director, Office of Sustainable Fisheries, NMFS, National Oceanic and Atmospheric Administration, transmitting the Administration's final rule — Fisheries of the Exclusive Economic Zone Off Alaska; Deep-Water Species Fishery by Catcher Vessels in the Gulf of Alaska [Docket No.: 0910091344-9056-02] (RIN: 0648-XP21) received June 22, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Natural Resources.

2472. A letter from the Acting Director, Office of Sustainable Fisheries, NMFS, National Oceanic and Atmospheric Administration, transmitting the Administration's final rule — Fisheries of the Exclusive Economic Zone Off Alaska; Pacific Cod by American Fisheries Act Catcher Processors Using Trawl Gear in the Bering Sea and Aleutian Islands Management Area [Docket No.: 0810141351-9087-02] (RIN: 0648-XP29) received June 22, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Natural Resources.

2473. A letter from the Acting Director, Office of Sustainable Fisheries, NMFS, National Oceanic and Atmospheric Administration, transmitting the Administration's final rule — Fisheries of the Exclusive Economic Zone Off Alaska; Northern Rockfish, Pacific Ocean Perch, and Pelagic Shelf Rockfish for Catcher Vessels Participating in the Limited Access Rockfish Fishery in the Central Regulatory Area of the Gulf of Alaska [Docket No.: 0910091344-9056-02] (RIN: 0648-XP22) received June 22, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Natural Resources.

2474. A letter from the Acting Director, Office of Sustainable Fisheries, NMFS, National Oceanic and Atmospheric Administration, transmitting the Administration's final rule — Fisheries of the Exclusive Economic Zone Off Alaska; Shallow-Water Species Fishery by Catcher Processors in the Gulf of Alaska [Docket No.: 0910091344-9056-02] (RIN: 0648-XP23) received June 22, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Natural Resources.

2475. A letter from the Deputy Assistant Administrator for Operations, NMFS, National Oceanic and Atmospheric Administration, transmitting the Administration's final rule — Fisheries in the Western Pacific Crustacean Fisheries; Deepwater Shrimp [Docket No.: 070719388-9911-04] (RIN: 0648-AV29) received June 22, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Natural Resources.

2476. A letter from the Program Analyst, Department of Transportation, transmitting the Department's final rule — Standard Insturment Approach Procedures, and Takeoff Minimums and Obstacle Departure Procedures; Miscellaneous Amendments [Docket No.: 30672 Amdt. No 3326] received June 24, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Transportation and Infrastructure.

2477. A letter from the Program Analyst, Department of Transportation, transmitting the Department's final rule — Standard Instrument Approach Procedures, and Takeoff Minimums and Obstacle Departure Procedures; Miscellaneous Amendments [Docket No.: 30673; Amdt. No. 3327] received June 24, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Transportation and Infrastructure.

2478. A letter from the Program Analyst, Department of Transportation, transmitting the Department's final rule — Airworthiness Directives; DORNIER LUFTFAHRT GmbH Models Dornier 228-100, Dornier 228-101, Dornier 228-200, Dornier 228-201, Dornier 228-202, and Dornier 228-212 Airplanes [Docket No.: FAA-2009-0284; Directorate Identifier 2009-CE-016-AD; Amendment 39-15939; AD 2009-12-16] (RIN: 2120-AA64) received June 24, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Transportation and Infrastructure.

2479. A letter from the Program Analyst, Department of Transportation, transmitting the Department's final rule — Airworthiness Directives; ATR Model ATR42-500 and ATR72-212A Airplanes [Docket No.: FAA-2009-0524; Directorate Identifier 2009-NM-030-AD; Amendment 39-15935; AD 2009-12-12] (RIN: 2120-AA64) received June 24, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Transportation and Infrastructure.

2480. A letter from the Program Analyst, Department of Transportation, transmitting the Department's final rule — Airworthiness Directives; Airbus Model A340-541 and -642 Airplanes [Docket No.: FAA-2009-0523; Directorate Identifier 2009-NM-018-AD; Amendment 39-15934; AD 2009-12-11] (RIN: 2120-AA64) received June 25, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Transportation and Infrastructure.

2481. A letter from the Program Analyst, Department of Transportation, transmitting the Department's final rule — Airworthiness Directives; ATR Model ATR42-200, ATR42-300, ATR42-300, ATR42-300, ATR42-300, ATR72-101, ATR72-201, ATR72-102, ATR72-202, ATR72-211, ATR72-212, and ATR72-212A Airplanes [Docket No.: FAA-2008-1237; Directorate Identifier 2008-NM-125-AD; Amendment 39-15932; AD 2009-12-09] (RIN: 2120-AA64) received June 24, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Transportation and Infrastructure.

2482. A letter from the Program Analyst, Department of Transportation, transmitting the Department's final rule — Airworthiness Directives; Aeromot-Industria Mecanico Metalurgica Itda. Model AMT-200 and AMT-300 Series Gliders [Docket No.: FAA-2009-0323 Directorate Identifier 2009-CE-012-AD; Amendment 39-15937; AD 2009-12-14] (RIN: 2120-AA64) received June 24, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Transportation and Infrastructure.

2483. A letter from the Regulations Officer, Federal Highway Administration, transmitting the Department's final rule — Worker Visibility [FHWA Docket No.: FHWA-2008-0157] (RIN: 2125-AF28) received June 24, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Transportation and Infrastructure.

2484. A letter from the Clerk of the House of Representatives, transmitting the annual compilation of personal financial disclosure statements and amendments thereto required to be filed by Members of the House with the Clerk of the House of Representatives, pursuant to Rule XXVI, clause 1, of the House Rules; (H. Doc. No. 111—54); to the Committee on Standards of Official Conduct and ordered to be printed.

2485. A letter from the Chief Counsel, Department of the Treasury, transmitting the Department's final rule — Offering of United States Savings Bonds, Series I — received June 22, 2009, pursuant to 5 U.S.C. 801(a)(1)(A); to the Committee on Ways and Means.

REPORTS OF COMMITTEES ON PUBLIC BILLS AND RESOLUTIONS

Under clause 2 of rule XIII, reports of committees were delivered to the Clerk for printing and reference to the proper calendar, as follows:

Mr. REYES: Permanent Select Committee on Intelligence. H.R. 2701. A bill to authorize appropriations for fiscal year 2010 for intelligence and intelligence-related activities of the United States Government, the Community Management Account, and the Central Intelligence Agency Retirement and Disability System, and for other purposes; with an amendment (Rept. 111–186). Referred to the Committee of the Whole House on the State of the Union.

Mrs. LOWEY: Committee on Appropriations. H.R. 3081. A bill making appropriations for the Department of State, foreign operations, and related programs for the fiscal year ending September 30, 2010, and for other purposes (Rept. 111–187). Referred to the Committee of the Whole House on the State of the Union.

Mr. EDWARDS of Texas: Committee on Appropriations. H.R. 3082. A bill making appropriations for military construction, the Department of Veterans Affairs, and related agencies for the fiscal year ending September 30, 2010, and for other purposes (Rept. 111–188). Referred to the Committee of the Whole House on the State of the Union.

Mr. CONYERS: Committee on the Judiciary. House Resolution 537. Resolution requesting that the President and directing that the Attorney General transmit to the House of Representatives all information in their possession relating to specific communications regarding detainees and foreign persons suspected of terrorism; adversely (Rept. 111–189). Referred to the House Calendar.

Ms. VELÁZQUEZ: Committee on Small Business. H.R. 2965. A bill to amend the Small Business Act with respect to the Small Business Innovation Research Program and the Small Business Technology Transfer Program, and for other purposes; with an amendment (Ret. 111–190 Pt. 1). Ordered to be printed.

TIME LIMITATION OF REFERRED BILL

Pursuant to clause 2 of rule XII the following action was taken by the Speaker:

H.R. 2965. Referral to the Committee on Science and Technology extended for a period ending not later than July 7, 2009.

PUBLIC BILLS AND RESOLUTIONS

Under clause 2 of rule XII, public bills and resolutions of the following titles were introduced and severally referred, as follows:

By Ms. SCHAKOWSKY (for herself, Ms. KILPATRICK of Michigan, Mrs. MILLER of Michigan, and Ms. Granger):

H.R. 3065. A bill to establish a chronic care improvement demonstration program for Medicaid beneficiaries with severe mental illnesses; to the Committee on Energy and Commerce.

By Mr. CUMMINGS:

H.R. 3066. A bill to authorize the Secretary of Housing and Urban Development to make temporary mortgage assistance loans to save the homes of unemployed homeowners who are delinquent on their mortgage payments; to the Committee on Financial Services.

Bv Mr. LATHAM:

H.R. 3067. A bill to amend title XVIII of the Social Security Act to reform Medicare pay-

ments to physicians and certain other providers and improve Medicare benefits, to encourage the offering of health coverage by small businesses, to provide tax incentives for the purchase of health insurance by individuals, to increase access to health care for veterans, to address the nursing shortage, and for other purposes; to the Committee on Energy and Commerce, and in addition to the Committees on Education and Labor, Ways and Means, Veterans' Affairs, and Armed Services, for a period to be subsequently determined by the Speaker, in each case for consideration of such provisions as fall within the jurisdiction of the committee concerned.

By Mr. FRANK of Massachusetts (for himself, Ms. WATERS, Mr. CARDOZA, and Ms. VELÁZQUEZ):

H.R. 3068. A bill to use amounts made available under the Troubled Assets Relief Program of the Secretary of the Treasury for relief for homeowners and neighborhoods; to the Committee on Financial Services.

By Mrs. MALONEY (for herself, Mr. SMITH of New Jersey, Mr. GORDON of Tennessee, Mr. BURTON of Indiana, Mr. LANGEVIN, Ms. GINNY BROWNWAITE of Florida, Mrs. NAPOLITANO, and Mr. KENNEDY):

H.R. 3069. A bill to direct the Secretary of Health and Human Services to conduct or support a comprehensive study comparing total health outcomes, including risk of autism, in vaccinated populations in the United States with such outcomes in unvaccinated populations in the United States, and for other purposes; to the Committee on Energy and Commerce.

By Ms. WATSON (for herself and Mr. BOOZMAN):

H.R. 3070. A bill to encourage the development and implementation of a comprehensive, global strategy for the preservation and reunification of families and the provision of permanent parental care for orphans, and for other purposes; to the Committee on Foreign Affairs

By Mr. CLAY:

H.R. 3071. A bill to amend the Public Health Service Act to establish a National Organ and Tissue Donor Registry Resource Center, to authorize grants for State organ and tissue donor registries, and for other purposes; to the Committee on Energy and Commerce

By Mr. CLAY (for himself, Mr. Blunt, Mr. Akin, Mr. Cleaver, Mrs. Emerson, Mr. Graves, Mr. Luetkemeyer, Mr. Skelton, and Mr. Carnahan):

H.R. 3072. A bill to designate the facility of the United States Postal Service located at 9810 Halls Ferry Road in St. Louis, Missouri, as the "Coach Jodie Bailey Post Office Building"; to the Committee on Oversight and Government Reform.

By Mr. NYE (for himself and Mr. HUNTER):

H.R. 3073. A bill to amend title 38, United States Code, to direct the Secretary of Veterans Affairs establish a grant program to provide assistance to veterans who are at risk of becoming homeless; to the Committee on Veterans' Affairs.

By Mr. ELLISON:

H.R. 3074. A bill to amend title XVIII of the Social Security Act to create a value indexing mechanism for the physician work component of the Medicare physician hospital service and for inpatient hospital services; to the Committee on Energy and Commerce, and in addition to the Committee on Ways and Means, for a period to be subsequently determined by the Speaker, in each case for consideration of such provisions as fall within the jurisdiction of the committee concerned.

By Mr. LEWIS of Georgia:

H.R. 3075. A bill to establish a National Parents Corps Program, and for other purposes; to the Committee on Education and Labor.

By Mr. LEWIS of Georgia:

H.R. 3076. A bill to establish a comprehensive process to inform American consumers about food and product recalls, and for other purposes; to the Committee on Energy and Commerce.

By Ms. McCOLLUM (for herself, Mr. PAYNE, Mrs. EMERSON, Mr. JACKSON of Illinois, Mr. GRIJALVA, Ms. LEE of California, Mr. McGovern, Mr. Honda, and Ms. Schakowsky):

H.R. 3077. A bill to authorize appropriations for fiscal years 2010 through 2014 to provide assistance to foreign countries to promote food security and agricultural development, to develop rural infrastructure and stimulate rural economies, and to improve emergency response to food crises, to amend the Foreign Assistance Act of 1961, and for other purposes; to the Committee on Foreign Affairs.

By Mr. HARE (for himself and Mr. LUETKEMEYER):

H.R. 3078. A bill to support after-school programs in rural areas of the United States by establishing a pilot program to assist communities establish, enhance, or expand rural after-school programs; to the Committee on Education and Labor.

By Ms. SPEIER (for herself, Mr. Lee of New York, Mr. Davis of Alabama, and Mr. Thompson of California):

H.R. 3079. A bill to amend the Internal Revenue Code of 1986 to allow loans from simplified employee pension accounts of small business owners for use in the small business; to the Committee on Ways and Means.

By Ms. SPEIER (for herself and Ms. SCHAKOWSKY):

H.R. 3080. A bill to prohibit the manufacture, sale, or distribution in commerce of any consumer product containing dimethylfumarate; to the Committee on Energy and Commerce.

By Mr. BOCCIERI (for himself, Mr. SPACE, Mr. DRIEHAUS, Mr. RYAN of Ohio, Ms. FUDGE, Ms. KAPTUR, Ms. KILROY, Ms. SUTTON, and Mr. PERRIELLO):

H.R. 3083. A bill to require the Secretary of Commerce to establish a program for the award of grants to States to establish revolving loan funds for small and medium-sized manufacturers to improve energy efficiency and produce clean energy technology, and for other purposes; to the Committee on Science and Technology.

By Mr. BAIRD:

H.R. 3084. A bill to restore Federal recognition to the Chinook Nation, and for other purposes; to the Committee on Natural Resources.

By Mr. BECERRA (for himself, Mr. NUNES, Mr. BLUMENAUER, Mr. HONDA, Mr. KILDEE, Mr. LUJÁN, Ms. McCollum, and Mr. Olver):

H.R. 3085. A bill to amend the Internal Revenue Code of 1986 to provide for the treatment of Indian tribal governments as State governments for purposes of determining the sources of support of charitable organizations; to the Committee on Ways and Means.

By Ms. BORDALLO:

H.R. 3086. A bill to coordinate authorities within the Department of the Interior and within the Federal Government to enhance the United States' ability to conserve global wildlife and biological diversity and for other purposes; to the Committee on Natural Resources, and in addition to the Committee on Foreign Affairs, for a period to be subsequently determined by the Speaker, in each case for consideration of such provisions as

fall within the jurisdiction of the committee concerned.

By Mr. BUTTERFIELD:

H.R. 3087. A bill to amend title 38, United States Code, to establish a deadline for decisions with respect to claims for benefits under laws administered by the Secretary of Veterans Affairs, and for other purposes; to the Committee on Veterans' Affairs.

By Mr. CARSON of Indiana (for himself and Mr. Braley of Iowa):

H.R. 3088. A bill to require an automobile manufacturer that the Federal Government has an ownership interest in or that has an outstanding loan from the Federal Government to purchase liability insurance from an insurance company; to the Committee on Financial Services.

By Ms. CASTOR of Florida (for herself and Ms. SCHAKOWSKY):

H.R. 3089. A bill to amend title XVIII of the Social Security Act to provide for standardized marketing requirements under the Medicare Advantage program and the Medicare Prescription Drug program and to provide for State certification prior to waiver of licensure requirements under the Medicare Prescription Drug program, and for other purposes; to the Committee on Ways and Means, and in addition to the Committee on Energy and Commerce, for a period to be subsequently determined by the Speaker, in each case for consideration of such provisions as fall within the jurisdiction of the committee concerned.

By Mrs. CHRISTENSEN (for herself, Mr. DAVIS of Illinois, Ms. BORDALLO, Ms. Roybal-Allard, Mr. Clyburn, Mr. Rangel, Ms. Lee of California, Mr. Honda, Mr. Cummings, Ms. Jack-SON-LEE of Texas, Ms. CLARKE, Mr. WATT, Mr. CLAY, Mr. THOMPSON of Mississippi Mr Meek of Florida Ms EDDIE BERNICE JOHNSON of Texas, Mr. AL GREEN of Texas, Mr. JOHNSON of Georgia, Mr. CLEAVER, Mr. ELLISON. Ms. Watson, Mr. Jackson of Illinois. Mr. Carson of Indiana, Mr. Towns, Ms. FUDGE. Ms. KILPATRICK of Michigan, Ms. RICHARDSON, Ms. BALDWIN, Mr. Fattah. Mr. Bishop of Georgia. Mr. Scott of Georgia, Mr. Payne, Mr. MEEKS of New York, Mr. GRIJALVA, Mr. Scott of Virginia, Mr. Davis of Alabama, Mr. Grayson, Ms. Edwards of Maryland, Ms. MOORE of Wisconsin, Ms. Corrine Brown of Florida, Ms. Waters, Ms. Hirono, Ms. DEGETTE, Mr. FALEOMAVAEGA, Ms. MATSUI, Mr. LEWIS of Georgia, Mr. GONZALEZ, Mr.Sablan. PIERLUISI, Mr. REYES, Mr. ORTIZ, Ms. VELÁZQUEZ, Mr. LUJÁN, Mr. HASTINGS of Florida, and Mr. CUELLAR):

H.R. 3090. A bill to improve the health of minority individuals, and for other purposes; to the Committee on Energy and Commerce, and in addition to the Committees on Ways and Means, Education and Labor, the Judiciary, Natural Resources, Armed Services, Veterans' Affairs, and Agriculture, for a period to be subsequently determined by the Speaker, in each case for consideration of such provisions as fall within the jurisdiction of the committee concerned.

By Mr. CROWLEY (for himself, Mr. HASTINGS of Florida, Ms. WATERS, and Mr. HINCHEY):

H.R. 3091. A bill to amend title XIX of the Social Security Act to provide incentives for increased use of HIV screening tests under the Medicaid Program; to the Committee on Energy and Commerce.

By Mrs. DAHLKEMPER (for herself, Mr. TIM MURPHY of Pennsylvania, Ms. SCHWARTZ, Mrs. HALVORSON, Mr. KENNEDY, Mr. PLATTS, Mrs. CAPPS, and Mr. KIND): H.R. 3092. A bill to amend title XIX of the Social Security Act to require States to cover medical nutritional therapy as part of Medicaid; to the Committee on Energy and Commerce.

By Mr. DENT (for himself, Mr. OLSON, Mr. EHLERS, Mr. MOORE of Kansas, Mr. PERLMUTTER, Mrs. MILLER of Michigan, Mr. PETRI, Mr. MICA, and Mr. CAMPBELL):

H.R. 3093. A bill to require the Transportation Security Administration to engage in a negotiated rulemaking process for the purposes of creating a security regiment for general aviation aircraft; to the Committee on Homeland Security.

By Ms. EDWARDS of Maryland:

H.R. 3094. A bill to strengthen the Occupational Safety and Health Act of 1970 by revising regulations to increase worker safety on construction sites and, consequently, to protect child trespassers from unforeseen dangers; to the Committee on Education and Labor.

By Mr. GRIFFITH:

H.R. 3095. A bill to improve the information in databases for individuals with cancer in the United States and to amend the Social Security Act to provide increased coverage for uninsured individuals upon first diagnosis of cancer; to the Committee on Energy and Commerce, and in addition to the Committee on Ways and Means, for a period to be subsequently determined by the Speaker, in each case for consideration of such provisions as fall within the jurisdiction of the committee concerned.

By Mr. HINCHEY:

H.R. 3096. A bill to provide additional housing assistance for certain individuals and households adversely affected by a major disaster; to the Committee on Transportation and Infrastructure.

By Mr. INSLEE (for himself and Mr. DICKS):

H.R. 3097. A bill to provide for equitable compensation to the Spokane Tribe of Indians of the Spokane Reservation for the use of tribal land for the production of hydropower by the Grand Coulee Dam, and for other purposes; to the Committee on Natural Resources.

By Ms. KILPATRICK of Michigan:

H.R. 3098. A bill to amend the Public Health Service Act to attract and retain trained health care professionals and direct care workers dedicated to providing quality care to the growing population of older Americans; to the Committee on Energy and Commerce.

By Mr. MARKEY of Massachusetts:

H.R. 3099. A bill to require a site operator of an international travel Web site to provide information on its Web site to consumers regarding the potential health and safety risks associated with overseas vacation destinations marketed on its Web site; to the Committee on Energy and Commerce.

By Mr. RUSH (for himself, Mr. Davis of Illinois, Mr. Johnson of Georgia, Ms. KILPATRICK of Michigan, Mr. CLAY, Mr. COHEN, Ms. FUDGE, Ms. NORTON, Mr. SCOTT of Virginia, Mr. Lewis of Georgia, Mr. Jackson of Illinois, Ms. Jackson-Lee of Texas, Mr. CLEAVER, and Mr. CARSON of Indiana):

H.R. 3100. A bill to establish the Food Desert Oasis Pilot Program, and for other purposes; to the Committee on Ways and Means, and in addition to the Committee on Agriculture, for a period to be subsequently determined by the Speaker, in each case for consideration of such provisions as fall within the jurisdiction of the committee concerned.

By Mr. MARKEY of Massachusetts: H.R. 3101. A bill to ensure that individuals with disabilities have access to emerging Internet Protocol-based communication and video programming technologies in the 21st Century; to the Committee on Energy and Commerce.

By Mrs. MILLER of Michigan (for herself, Mr. ROGERS of Michigan, Mr. HOEKSTRA, Mr. CAMP, Mr. McCOTTER, and Mr. UPTON):
H.R. 3102. A bill to increase the Federal

H.R. 3102. A bill to increase the Federal share for transportation projects for the State of Michigan; to the Committee on Transportation and Infrastructure.

By Mr. MORAN of Kansas:

H.R. 3103. A bill to revise certain requirements relating to the Department of Veterans Affairs pilot program of enhanced contract care authority for health care needs of veterans in highly rural areas; to the Committee on Veterans' Affairs.

By Mr. TIM MURPHY of Pennsylvania: H.R. 3104. A bill to require public reporting of health care-associated infections data by hospitals and ambulatory surgical centers, and for other purposes; to the Committee on Energy and Commerce.

By Mr. NUNES:

H.R. 3105. A bill to provide that operations of the Central Valley Project shall not be restricted pursuant to any biological opinion issued under the Endangered Species Act of 1973, if such restrictions would result in levels of export less than the historical maximum level of export; to the Committee on Natural Resources.

By Mr. PRICE of North Carolina:

H.R. 3106. A bill to amend the Solid Waste Disposal Act to direct the Administrator of the Environmental Protection Agency to establish a hazardous waste electronic manifest system; to the Committee on Energy and Commerce.

By Ms. ROS-LEHTINEN (for herself, Mr. Burton of Indiana, Mr. McCaul, and Mr. Poe of Texas):

H.R. 3107. A bill to prohibit the expenditure of United States taxpayer dollars on nuclear assistance to state sponsors of terrorism, and for other purposes; to the Committee on Foreign Affairs.

By Mr. ROSS:

H.R. 3108. A bill to amend part D of title XVIII of the Social Security Act to promote medication therapy management under the Medicare part D prescription drug program; to the Committee on Energy and Commerce, and in addition to the Committee on Ways and Means, for a period to be subsequently determined by the Speaker, in each case for consideration of such provisions as fall within the jurisdiction of the committee concerned.

By Mr. TEAGUE (for himself, Mr. GENE GREEN of Texas, Mr. SPACE, and Mr. GONZALEZ):

H.R. 3109. A bill to improve access to health care services in rural, frontier, and urban underserved areas in the United States by addressing the supply of health professionals and the distribution of health professionals to areas of need; to the Committee on Energy and Commerce, and in addition to the Committees on Ways and Means, Veterans' Affairs, Education and Labor, Armed Services, and Natural Resources, for a period to be subsequently determined by the Speaker, in each case for consideration of such provisions as fall within the jurisdiction of the committee concerned.

By Ms. WATSON (for herself and Mr. BOOZMAN):

H.R. 3110. A bill to provide United States citizenship for children adopted from outside the United States, and for other purposes; to the Committee on the Judiciary, and in addition to the Committee on Foreign Affairs, for a period to be subsequently determined by the Speaker, in each case for consideration of such provisions as fall within the jurisdiction of the committee concerned.

By Mr. PRICE of North Carolina (for himself, Mr. Jones, Mr. Coble, Ms. ROYBAL-ALLARD, Mr. DOYLE, Mr. BILBRAY, Mr. BUTTERFIELD, and Ms. LINDA T. SÁNCHEZ of California):

H. Con. Res. 160. Concurrent resolution honoring the American Kennel Club on its 125th anniversary; to the Committee on Oversight and Government Reform.

By Mr. McGOVERN (for himself, Mr. Wolf, and Mr. Wexler):

H. Res. 588. A resolution expressing the sense of the United States House of Representatives that the trial by the Government of the Russian Federation of Mikhail Khodorkovsky and Platon Lebedev constitutes a politically-motivated case of selective arrest and prosecution that serves as a test of the rule of law and independence of Russia's judicial system; to the Committee on Foreign Affairs.

By Mr. CLAY:

H. Res. 589. A resolution supporting the goals and ideals of National Minority Donor Awareness Day; to the Committee on Energy and Commerce.

By Mr. WU (for himself and Mr. WOLF): H. Res. 590. A resolution expressing grave concerns about the sweeping censorship, privacy, and cybersecurity implications of China's Green Dam filtering software, and urging U.S. high-tech companies to promote the Internet as a tool for transparency, freedom of expression, and citizen empowerment around the world; to the Committee on Foreign Affairs.

By Mr. BOEHNER (for himself, Mr. LaTourette, Mrs. Schmidt, Mr. Turner, Mr. Latta, Mr. Austria, Mr. Jordan of Ohio, and Mr. Tiberi):

- H. Res. 591. A resolution requesting that the President transmit to the House of Representatives all information in his possession relating to certain specific communications with and financial assistance provided to General Motors Corporation and Chrysler LLC; to the Committee on Financial Services
 - By Ms. WATERS (for herself, Mrs. Christensen, Ms. Lee of California, Mr. Hastings of Florida, Ms. Bordallo, Mr. Grijalva, Ms. Roy-Bal-Allard, Mr. McGovern, Mr. Lewis of Georgia, Mr. Massa, Ms. Kilroy, Mr. Towns, and Mr. Davis of Illinois):
- H. Res. 592. A resolution supporting the goals and ideals of National Clinicians HIV/AIDS Testing and Awareness Day, and for other purposes; to the Committee on Energy and Commerce.

By Mr. ABERCROMBIE (for himself and Ms. HIRONO):

H. Res. 593. A resolution recognizing and celebrating the 50th Anniversary of the entry of Hawaii into the Union as the 50th State; to the Committee on Oversight and Government Reform.

By Mr. DOYLE (for himself, Mr. TIM MURPHY of Pennsylvania, Mr. BRALEY of Iowa, Mr. WILSON of Ohio, Mr. THOMPSON of Pennsylvania, Mr. MURTHA, Mr. KANJORSKI, Mr. CARNEY, Mr. HOLDEN, Mr. SHUSTER, Mr. BRADY of Pennsylvania, Mr. ROONEY, Mr. ALTMIRE, Mr. DENT, Mr. BOCCIERI, Mr. DONNELLY of Indiana, Mr. PASCRELL, Mr. KRATOVIL, Mr. STUPAK, and Mr. DINGELL):

H. Res. 594. A resolution congratulating the Pittsburgh Penguins for winning the 2009 Stanley Cup Hockey Championship; to the Committee on Oversight and Government Reform.

By Mr. HASTINGS of Florida (for himself, Mr. BUTTERFIELD, Mr. RANGEL, Mr. PAYNE, Mr. LEWIS of Georgia, Mr. MEEKS of New York, Ms. CORRINE Brown of Florida, Mr. Rush, Ms. CLARKE, and Mr. Johnson of Georgia):

H. Res. 595. A resolution recognizing persons of African descent in Europe; to the Committee on Foreign Affairs.

By Mr. HASTINGS of Florida (for himself, Mr. Butterfield, Mr. Rangel, Mr. Payne, Mr. Lewis of Georgia, Mr. Meeks of New York, Ms. Corrine Brown of Florida, Ms. Moore of Wisconsin, Mr. Rush, Ms. Clarke, and Mr. Johnson of Georgia):

H. Res. 596. A resolution expressing support for the Black European Summit; to the Committee on Foreign Affairs.

By Mr. KING of Iowa:

H. Res. 597. A resolution amending the Rules of the House of Representatives to require the Committee on Rules to conduct its meetings and hearings in the Hall of the House, and for other purposes; to the Committee on Rules.

By Mr. LANGEVIN:

H. Res. 598. A resolution expressing the sense of the House of Representatives regarding the fire at the ABC Daycare Center in Hermosillo, Sonora, Mexico; to the Committee on Foreign Affairs.

By Mr. MARKEY of Massachusetts (for himself and Ms. Tsongas):

H. Res. 599. A resolution honoring the Minute Man National Historical Park on the occasion of its 50th Anniversary; to the Committee on Natural Resources.

By Ms. JACKSON-LEE of Texas (for herself and Ms. WATSON):

H. Res. 600. A resolution a Tribute to an American Legend and Musical Icon; to the Committee on Foreign Affairs.

By Mrs. McCARTHY of New York (for herself, Mrs. Lowey, and Mr. COURTNEY):

H. Res. 601. A resolution recognizing and honoring the Firefighter Cancer Support Network; to the Committee on Energy and Commerce.

By Mr. ROGERS of Michigan:

H. Res. 602. A resolution requesting that the President and directing that the Secretary of Defense transmit to the House of Representatives all information in their possession relating to specific communications regarding detainees and foreign persons suspected of terrorism; to the Committee on Armed Services.

By Ms. ROS-LEHTINEN (for herself, Mr. ROYCE, Mr. McDermott, Mr. Wilson of South Carolina, Mr. Bilirakis, and Mr. Manzullo):

H. Res. 603. A resolution recognizing the 140th anniversary of the birth of Mahatma Gandhi; to the Committee on Foreign Affairs.

By Ms. ROS-LEHTINEN (for herself, Mr. Rohrabacher, Mr. Burton of Indiana, Mr. Royce, and Mr. McCaul):

H. Res. 604. A resolution recognizing the vital role of the Proliferation Security Initiative in preventing the spread of weapons of mass destruction; to the Committee on Foreign Affairs.

By Ms. ROS-LEHTINEN (for herself, Mr. Poe of Texas, Mr. Bilirakis, Mr. BURTON of Indiana, Mr. ROHR-ABACHER, Mr. MARIO DIAZ-BALART of Florida, Mr. MINNICK, and Ms. WA-TERS):

H. Res. 605. A resolution recognizing the continued persecution of Falun Gong practitioners in China on the 10th anniversary of the Chinese Communist Party campaign to suppress the Falun Gong spiritual movement and calling for an immediate end to the campaign to persecute, intimidate, imprison, and torture Falun Gong practitioners; to the Committee on Foreign Affairs.

By Mr. ROTHMAN of New Jersey (for himself, Mr. ENGEL, Mr.

FALEOMAVAEGA, Mr. SIRES, Mr. LIPINSKI, Mrs. MALONEY, Mrs. TAUSCHER, Mr. SESTAK, Mr. PIERLUISI, Mr. JOHNSON of Georgia, Mr. HOLT, Mr. GOHMERT, Mr. MITCHELL, Mr. DOYLE, Ms. KILROY, Mr. SMITH of Washington, Mr. REICHERT, and Mr. VAN HOLLEN):

H. Res. 606. A resolution congratulating the United States Men's National Soccer Team for its epic victory over Spain, for achieving one of the biggest upsets in the history of International Soccer, and for earning the first advancement to a FIFA tournament final in the history of United States Soccer; to the Committee on Oversight and Government Reform.

PRIVATE BILLS AND RESOLUTIONS

Under clause 3 of rule XII, private bills and resolutions of the following titles were introduced and severally referred, as follows:

By Ms. CORRINE BROWN of Florida: H.R. 3111. A bill for the relief of Walter Enrique Lara; to the Committee on the Judiciary.

By Mr. DELAHUNT:

H.R. 3112. A bill to authorize the Secretary of the department in which the Coast Guard is operating to issue a certificate of documentation for operation in the coastwise trade for the vessel EQUULEUS; to the Committee on Transportation and Infrastructure.

ADDITIONAL SPONSORS

Under clause 7 of rule XII, sponsors were added to public bills and resolutions as follows:

H.R. 24: Mrs. Halvorson and Mr. Rahall. H.R. 118: Mr. Adler of New Jersey, Mr. Sires, Mr. Rothman of New Jersey, Mr. Andrews, and Mr. Pallone.

H.R. 197: Mr. SMITH of Nebraska.

H.R. 211: Mr. McIntyre.

H.R. 235: Mr. TONKO.

 $\rm H.R.~275;~Mr.~Jones,~Mr.~Barrow,~Mr.~Austria,~and~Mr.~Culberson.$

 $H.R.\ 391;\ Mr.\ Pence.$

H.R. 413: Mr. BOREN, Mr. KRATOVIL, Mr. BACA, Mr. GRAVES, Mr. POE of Texas, Ms. SCHWARTZ, Mr. WU, Mr. FARR, and Mr. CAMP. H.R. 422: Mr. CUMMINGS and Mr. BLUMENAUER.

H.R. 476: Mr. FILNER and Mr. SABLAN.

H.R. 503: Mr. TIERNEY and Mrs. NAPOLITANO.

H.R. 510: Mr. HILL.

H.R. 525: Mr. PLATTS.

H.R. 571: Mr. GORDON of Tennessee and Mr. CONAWAY.

H.R. 574: Mr. MEEKS of New York.

H.R. 600: Mrs. MALONEY.

H.R. 690: Mr. WAMP and Mrs. LUMMIS.

H.R. 697: Mr. MASSA.

H.R. 731: Ms. Schakowsky.

H.R. 747: Mr. MASSA.

H.R. 775: Mr. SHIMKUS, Mr. POE of Texas, Mrs. MILLER of Michigan, and Mr. SCHOCK.

H.R. 795: Mr. NEAL of Massachusetts, Mr. ELLISON, and Mr. FILNER.

H.R. 836: Mr. Hunter and Mr. Camp.

H.R. 983: Mr. Stearns.

H.R. 1020: Ms. Sutton, Mr. Grijalva, Mr. Murtha, Mr. Jackson of Illinois, Mr. Hall of New York, Ms. Clarke, and Mr. Al Green of Texas.

H.R. 1028: Mr. Patrick J. Murphy of Pennsylvania, Mr. Connolly of Virginia, Mr. Filner, and Mr. Snyder.

H.R. 1033: Mr. STARK.

- H.R. 1064: Mr. Visclosky, Mr. Neal of Massachusetts, and Ms. TSONGAS.
- H.R. 1077: Mr. LUETKEMEYER and Mrs. CAPPS.
- H.R. 1132: Mr. PETERSON and Mr. MoL-LOHAN.
- H.R. 1147: Mr. HARE, Mr. KILDEE, Mrs NAPOLITANO, and Mr. TIERNEY.
- H.R. 1179: Mr. LARSON of Connecticut, and Mr. Thompson of Pennsylvania.
- H.R. 1182: Mr. PAULSEN, Mr. MITCHELL, Mr. LEWIS of Georgia, and Mr. CONNOLLY of Vir-
- H.R. 1205: Mr. TIM MURPHY of Pennsylvania, Mr. HERGER, Mr. SCHAUER, and Mr.
 - H.R. 1207: Mr. DAVIS of Illinois.
- H.R. 1236: Mr. MEEK of Florida, Ms. LINDA T. SÁNCHEZ OF California, Mr. MILLER OF North Carolina, and Mr. DEFAZIO.
- H.R. 1242: Mrs. McMorris Rodgers.
- H.R. 1245: Mr. DEAL of Georgia, Mr. BAR-ROW, and Mr. FOSTER.
 - H.R. 1250: Mr. EHLERS.
- H.R. 1283: Mr. Heinrich.
- H.R. 1327: Mr. MASSA and Mr. NADLER of New York.
- H.R. 1339: Mr. LARSEN of Washington and Ms. Baldwin.
- H.R. 1346: Mr. HALL of New York.
- H.R. 1361: Ms. Schakowsky.
- H.R. 1402: Mr. BISHOP of Georgia, Ms. MAT-SUI, and Mr. LOEBSACK.
- H.R. 1410: Ms. HERSETH SANDLIN.
- H.R. 1412: Mr. Jackson of Illinois, Mr. MCDERMOTT, Mr. PASTOR of Arizona, Mr. HONDA, and Mr. GRAYSON.
 - H.R. 1441: Mr. BROUN of Georgia.
- H.R. 1454: Mr. Hastings of Florida.
- H.R. 1458: Mrs. MILLER of Michigan and Ms. Baldwin.
- H.R. 1479: Mr. Braley of Iowa.
- H.R. 1490: Ms. Schakowsky, Ms. Berkley, Ms. Bordallo, Mr. Rodriguez, Mr. Aber-CROMBIE, Mr. MILLER of North Carolina, Mr. BACA, and Mr. SNYDER.
 - H.R. 1503: Mrs. Blackburn.
- H.R. 1505: Mr. HOEKSTRA.
- H.R. 1509: Mr. BRIGHT.
- H.R. 1546: Mr. NYE and Ms. BORDALLO.
- H.R. 1547: Mr. McCotter. H.R. 1548: Mr. BUYER.
- H.R. 1551: Mr. HEINRICH.
- H.R. 1557: Mr. CAMP.
- H.R. 1558: Mr. Sestak and Ms. Kosmas.
- H.R. 1570: Mr. Loebsack and Mr. Terry.
- H.R. 1612: Mr. Gonzalez.
- H.R. 1616: Mr. BISHOP of New York.
- H.R. 1618: Mr. SERRANO.
- H.R. 1622: Mr. MARIO DIAZ-BALART of Flor-
- H.R. 1625: Mr. CARNEY and Mr. BISHOP of New York.
- H.R. 1633: Mr. GORDON of Tennessee and Ms. KOSMAS.
- H.R. 1670: Mr. Kanjorski and Mr. Pastor of Arizona.
- H.R. 1692: Mr. BRADY of Texas.
- H.R. 1705: Mr. COHEN.
- H.R. 1763: Mr. Hastings of Washington.
- H.R. 1799: Mr. Ross and Mr. Jones.
- H.R. 1816: Ms. CLARKE.
- H.R. 1880: Mr. MORAN of Virginia and Mr. MINNICK.
- H.R. 1881: Mr. ELLISON and Mr. HIMES.
- H.R. 1894: Mrs. MILLER of Michigan and Ms. JENKINS.
- H.R. 1933: Mr. CARSON of Indiana.
- H.R. 1970: Ms. Markey of Colorado and Mr. CARNAHAN.
- H.R. 2000: Mr. Pomeroy, Mr. Rohrabacher, and Mr. Royce.
 - H.R. 2006: Ms. Zoe Lofgren of California.
- H.R. 2017: Mr. PRICE of North Carolina and Mr. WITTMAN.
- H.R. 2026: Mr. PAUL, Mr. STEARNS, and Mr. ROONEY.
- H.R. 2034: Mrs. CAPITO.

- H.R. 2054: Mr. CLEAVER and Mr. WITTMAN. H.R. 2057: Ms. Lee of California, Mr. PAYNE, and Mr. PRICE of North Carolina.
- H.R. 2058: Ms. Bordallo and Mr. Meeks of New York.
- H.R. 2064: Mrs. MILLER of Michigan.
- $H.R.\ 2070:\ Mr.\ GRIJALVA.$
- H.R. 2089: Mr. PATRICK J. MURPHY of Pennsylvania, Mr. HILL, and Mr. WAXMAN.
- H.R. 2110: Ms. TITUS and Mr. CONAWAY.
- H.R. 2119: Mr. PAUL.
- H.R. 2137: Ms. Schakowsky.
- H.R. 2139: Mrs. Maloney, Ms. Corrine BROWN of Florida, Ms. BERKLEY, Mr. GER-LACH, Mrs. MILLER of Michigan, and Mr. SCHIFF.
 - H.R. 2159: Mr. LANCE.
- H.R. 2194: Mr. McCaul, Mr. Campbell, Mr. DONNELLY of Indiana, Mr. FATTAH, Ms. FUDGE, and Mr. HOYER.
- H.R. 2220: Mr. KILDEE and Mr. McCotter.
- H.R. 2227: Mr. McIntyre.
- H.R. 2233: Ms. RICHARDSON.
- H.R. 2245: Mr. LATOURETTE, Mrs. MILLER of Michigan, Mr. HINOJOSA, Mr. MICHAUD, Ms. ESHOO, Mr. WELCH, Mr. ROTHMAN of New Jersey, Mr. DAVIS of Alabama, Mr. McCaul, Mr. BRIGHT, and Ms. ROYBAL-ALLARD.
- H.R. 2251: Mr. KILDEE and Mr. PAUL.
- H.R. 2254: Mr. RANGEL and Mr. WITTMAN.
- H.R. 2266: Mr. Blumenauer, Mr. Aber-CROMBIE, and Mr. RYAN of Ohio.
- H.R. 2267: Mr. Foster, Mr. Blumenauer, Mr. Abercrombie, Mr. Ryan of Ohio, and Mr. Nadler of New York.
 - H.R. 2272: Mr. McGovern.
 - $H.R.\ 2287;\ Mr.\ Conaway$ and $Ms.\ Foxx.$
- H.R. 2296: Mr. ROONEY.
- H.R. 2303: Mr. MURPHY of New York, Mr. ACKERMAN, Mr. MEEKS of New York, Mr. TONKO and Mrs. McCarthy of New York.
- H.R. 2308: Mr. FARR.
- H.R. 2310: Mr. PERLMUTTER and Mr. FORTENBERRY.
- H.R. 2314: Mr. Moran of Virginia and Mr. Young of Alaska.
- H.R. 2329: Mr. GORDON of Tennessee.
- H.R. 2350: Mr. LATOURETTE and Mr. PASTOR of Arizona.
- H.R. 2363: Mr. CAO.
- H.R. 2365: Mr. MURTHA.
- H.R.2378: Mr. SPACE.
- H.R. 2404: Ms. Fudge.
- H.R. 2409: Mrs. McMorris Rodgers.
- H.R. 2413: Mr. HOLDEN, Mr. BRALEY of Iowa, Mr. Wolf, Mr. Moore of Kansas, and Mr.
- H.R. 2425: Mr. BOUCHER and Mr. DEFAZIO.
- H.R. 2452: Mr. JORDAN of Ohio, Mr. RUPPERSBERGER, and Mr. BARTON of Texas.
- H.R. 2456: Mr. HONDA.
- H.R. 2460: Mr. CARNAHAN and Mr. SCHIFF.
- H.R. 2478: Ms. Schakowsky, Mr. Patrick J. MURPHY of Pennsylvania, Mr. Peters, Mr. SIRES, and Mr. CALVERT.
- H.R. 2483: Mr. ISRAEL.
- H.R. 2497: Mr. SERRANO.
- H.R. 2499: Mr. Cassidy.
- H.R. 2502: Mr. INSLEE.
- H.R. 2517: Mr. SIRES, Ms. LEE of California, Mr. McMahon, Mr. Murphy of Connecticut. Mr. Scott of Virginia, and Mr. Maffei.
- H.R. 2537: Mr. McCaul and Mr. Gary G. MILLER of California
- H.R. 2567: Mr. ALTMIRE.
- H.R. 2578: Mr. EHLERS.
- H.R. 2590: Mr. BOUCHER.
- H.R. 2607: Ms. FOXX and Mr. GARRETT of New Jersey
- H.R. 2608: Ms. FOXX.
- H.R. 2662: Mr. Kratovil.
- H.R. 2676: Mr. PERRIELLO and Mr. WALZ.
- H.R. 2692: Mr. WILSON of Ohio.
- H.R. 2696: Mrs. Lowey.
- H.R. 2697: Ms. Speier.
- H.R. 2698: Mrs. McMorris Rodgers and Mr. GORDON of Tennessee.
- H.R. 2699: Mrs. McMorris Rodgers, Mr. SCHIFF, and Mr. GORDON of Tennessee.

- H.R. 2715: Mr. Alexander, Mr. Stearns, and Mr. SHIMKUS.
 - H.R. 2730: Mr. RYAN of Ohio.

JONES.

- H.R. 2743: Mr. MELANCON, Mr. CONAWAY, Mr. Peterson, Mr. Holt, Mr. Spratt, Mr. CALVERT, Mr. GARY G. MILLER of California, Mr. HILL, Mr. AKIN, Mr. PIERLUISI, Mr. ADERHOLT, Mr. CRENSHAW, and Mrs. LUMMIS. H.R. 2745: Mr. HALL of Texas and Mr.
- H.R. 2746: Ms. SUTTON and Mr. McNerney. H.R. 2778: Mr. HONDA, Mr. ABERCROMBIE, Ms. Bordallo, Mr. Baca, Mr. Gonzalez, Mr. HINOJOSA, Mr. CARDOZA, Mr. SALAZAR, Mr. CUELLAR, Mrs. NAPOLITANO, Mr. GRIJALVA, Mr. Ortiz, Mr. Pastor of Arizona, Mr. Lujan, Mr. Pierluisi, Mr. Rodriguez, SERRANO, Ms. ROYBAL-ALLARD, Mr. SIRES, and Mr. Sablan.
 - H.R. 2785: Mr. Young of Alaska.
- H.R. 2796: Mr. GARY G. MILLER of Cali-
- H.R. 2799: Mr. Moore of Kansas, Mr. Wolf, Mr. PRICE of Georgia, Ms. CORRINE BROWN of Florida, and Mr. McHugh.
 - H.R. 2808: Mr. Stearns and Mrs. Lummis.
 - H.R. 2817: Mr. SIRES.
- H.R. 2844: Mr. Boswell.
- H.R. 2846: Mr. BOOZMAN and Mr. DAVIS of Kentucky.
 - H.R. 2866: Mr. GRIFFITH and Mr. McIntyre.
 - H.R. 2882: Ms. Castor of Florida.
 - H.R. 2891: Ms. BORDALLO.
- H.R. 2894: Mr. GRIJALVA, Mr. TIM MURPHY of Pennsylvania, and Mr. MURTHA.
 - H.R. 2900: Mr. STEARNS.
- H.R. 2909: Ms. Delauro.
- H.R. 2923: Mr. BOOZMAN.
- H.R. 2926: Ms. Bordallo.
- H.R. 2939: Mr. Sessions. H.R. 2956: Mr. Wamp.
- H.R. 2963: Mr. WILSON of Ohio.
- H.R. 2965: Mr. Luján, and Mrs. Biggert.
- H.R. 3003: Mr. BOUCHER.
- H.R. 3017: Mr. McMahon, Ms. Giffords, and Mr. MILLER of North Carolina.
- H.R. 3025: Ms. Herseth Sandlin, Mr. Bar-ROW, Mr. SHULER, Mr. DAVIS of Tennessee, Mr. MATHESON, Mr. MOORE of Kansas, Mr. MELANCON, and Mr. CHILDERS.
 - H.R. 3039: Mrs. Maloney.
 - H.R. 3040: Mr. McGovern.
 - H.R. 3042: Mr. HARE.
- H.J. Res. 42: Mr. WALDEN, Mr. BACHUS, Mr. BOUSTANY, and Mr. OLSON.
- H.J. Res. 47: Mr. CARNEY and Mrs. McCar-
- THY of New York. H.J. Res. 54: Mr. BARRETT of South Carolina, Mr. Franks of Arizona, Mr. LUETKEMEYER, and Mr. BOOZMAN.
 - H.J. Res. 56: Mr. CAO.
- H.J. Res. 57: Mr. CAMP.
- H. Con. Res. 92: Mr. KUCINICH. H. Con. Res. 121: Mr. MANZULLO and Mr.
- RADANOVICH.
- H. Con. Res. 137: Ms. ROYBAL-ALLARD. H. Con. Res. 144: Mr. Braley of Iowa, Mr. MEEK of Florida, and Ms. LEE of California. H. Con. Res. 157: Mr. FLEMING and Mr. GOR-
- DON of Tennessee. H. Res. 11: Mr. FILNER, Mr. McNerney, Mr.
- KAGEN, and Ms. GRANGER. H. Res. 57: Mr. DOYLE, Mr. STUPAK, and Mr. MCNERNEY.
- H. Res. 69: Mr. BARROW, Mr. BARTON of Texas, Mr. Blunt, Mrs. Bono Mack, Mr. Braley of Iowa, Mr. Butterfield, BUYER, Mrs. CAPPS, Mr. MELANCON, Mr. MUR-PHY of Connecticut, Mr. TIM MURPHY of Pennsylvania, Mr. RADANOVICH, Mr. Ross, Mr. Rush, Ms. Castor of Florida, Mr. Doyle, Mr. ENGEL, Ms. Eshoo, Mr. GINGREY of Georgia, Mr. Hall of Texas, Mr. Sarbanes, Mr. SCALISE, Mr. SHADEGG, Mr. SHIMKUS, Mr. SPACE, Mr. STUPAK, Ms. SUTTON. Mr. MCNERNEY, Mr. MARKEY of Massachusetts, Mr. MATHESON, Ms. MATSUI, Mr. WAXMAN, Mr. Weiner, Mr. Welch, Mr. Roskam, Mr.

LOEBSACK, Mr. WAMP, Mr. GRAYSON, Mr. KRATOVIL, Ms. WATSON, Mr. RAHALL, Mr. HIGGINS, Mrs. DAVIS of California, Mr. NUNES, Mr. JACKSON of Illinois, Mr. BOSWELL, Mr. Moore of Kansas, Mr. Schiff, Mr. Crow-LEY, Mr. KISSELL, Mr. HONDA, Mr. CUELLAR, Mr. Johnson of Georgia, Ms. Markey of Colorado, Ms. Zoe Lofgren of California, Mr. GEORGE MILLER of California, Mr. MEEKS of New York, Mr. PASTOR of Arizona, Mr. PERLMUTTER, Mr. SALAZAR, Mr. RANGEL, Mr. SCOTT of Georgia, and Mr. WATT.

H. Res. 111: Mr. FILNER, Mr. McNerney, Mr. KAGEN, and Ms. GRANGER.

H. Res. 156: Mr. MINNICK.

H. Res. 285: Mr. Manzullo. H. Res. 409: Mr. Bonner, Mr. Barrett of South Carolina, Mr. SMITH of Nebraska, Mr. GERLACH, Mr. PUTNAM, and Mrs. BLACKBURN.

H. Res. 416: Mr. RUSH, Mr. FILNER, and Mr.

HINCHEY.

H. Res. 433: Mr. KUCINICH.

H. Res. 441: Mr. KANJORSKI, Mr. GONZALEZ, Mr. Neal of Massachusetts, Mr. Braley of Iowa, Mr. Lipinski, Mr. Doyle, Ms. Shea-PORTER, Mr. BISHOP of New York, Mr. CONNOLLY of Virginia, and Mr. HOLDEN.

H. Res. 458: Mr. GORDON of Tennessee and Mr. Blumenauer.

H. Res. 476: Mr. WAMP.

H. Res. 507: Mr. Brown of South Carolina and Mr. McNerney.

H. Res. 512: Mr. BONNER.

H. Res. 531: Mr. QUIGLEY and Mr. COSTELLO.

H. Res. 534: Mr. DRIEHAUS, Mr. TEAGUE, Mrs. Capps, Ms. Clarke, Ms. Pingree of Maine, Ms. BALDWIN, Ms. KILPATRICK of Michigan, Mr. WAXMAN, Mr. PASTOR of Arizona, Mr. Becerra, Mrs. Emerson, Mr. Brown of South Carolina, Ms. Fudge, Mr. HALL of Texas, Mr. HINCHEY, Ms. WATERS, Ms. Moore of Wisconsin, Ms. Hirono, Mr. ELLISON, Mr. WELCH, Ms. WASSERMAN SCHULTZ, Ms. VELÁZQUEZ, Ms. CASTOR OF Florida, Mr. Kratovil, Ms. Roybal-Allard, Mrs. Napolitano, Mr. Cardoza, Ms. Tson-GAS, Ms. MARKEY of Colorado, Mr. SIRES, Ms. ROS-LEHTINEN, Mr. STEARNS, Mr. EHLERS, Mr. Manzullo, Ms. Ginny Brown-Waite of Florida, Mrs. BIGGERT, Mr. UPTON, Mr. MCHENRY, Mr. GERLACH, Mrs. BLACKBURN, Mrs. Lummis, Mr. Fleming, Mr. King of New York, Ms. Foxx, Mr. Carson of Indiana, and Ms. Corrine Brown of Florida.

H. Res. 550: Mr. HONDA and Mr. CONYERS.

H. Res. 557: Mr. THORNBERRY and Mr. BOEHNER.

CONGRESSIONAL EARMARKS, LIM-ITED TAX BENEFITS. OR LIM-ITED TARIFF BENEFITS

Under clause 9 of rule XXI, lists or statements on congressional earmarks, limited tax benefits, or limited tariff benefits were submitted as follows:

The amendment to be offered by Representative FORBES, or a designee, to H.R. 2454, the American Clean Energy and Security Act of 2009, does not contain any congressional earmarks, limited tax benefits, or limited tariff benefits as defined in clause 9(d), 9(e), or 9(f) of Rule XXI.

DISCHARGE PETITIONS-ADDITIONS OR DELETIONS

The following Member added his name to the following discharge peti-

Petition 3 by Mr. LATOURETTE on House Resolution 359: Daniel E. Lungren.

EXTENSIONS OF REMARKS

COUNTY SUPERVISOR JOHN D. **JENKINS**

HON. GERALD E. CONNOLLY

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CONNOLLY of Virginia. Madam Speaker, I rise today in honor of Prince William County Supervisor John D. Jenkins and the years of service that he has selflessly devoted to his neighbors, constituents and friends. Supervisor Jenkins was recently awarded the Occoquan District Good Scout Award by the National Capital Area Council of the Boy Scouts of America. I cannot think of a more appropriate recognition of John's accomplishments in public service than an award based on the credo, "You are put here to do something for your fellow man and to take an active part in your community and its issues."

Supervisor Jenkins and his wife Ernestine moved to Prince William County in 1973 and immediately took a role in their neighborhood as the Forestdale representatives to the Dale City Civic Association. Their three sons were educated in the Prince William County Public School system and were Eagle Scouts in local Troop 1378. They have 14 grandchildren and two great grandchildren.

Supervisor Jenkins began his life in public office in October of 1982 when he was appointed to fill the vacant Neabsco District Supervisor's seat. He has since been reelected to that position 6 times. He has served two terms as Vice Chairman of the Board of County Supervisors, two terms as Chairman of the Northern Virginia Regional Commission, two terms as the State President of the Virginia Association of Planning District Commissions, two terms as the State President of the Virginia Association of Counties and two terms as the Chairman of the Virginia Railway Express Operations Board. John has served on boards and steering committees of the Virginia Municipal League, the Virginia Association of Counties, the National Association of Counties and represents the Board of County Supervisors on the Quantico Marine Corps and Fort Belvoir Base Realignment and Closing advisory committees.

Supervisor Jenkins has been a tireless advocate for many organizations throughout his 27-year tenure on the Board of County Supervisors. However, his involvement in the Scouts predates even his time in office, spanning 6 decades and involving countless Scouting Camp William B. Snyder causes. Haymarket, VA opened its doors in 2006 due in part to the Supervisor's efforts to end its stalled development. He is a fixture at local Scouting promotion ceremonies and often uses his considerable fundraising abilities on behalf of the Boy Scouts of America. His dedication to the Scouts is unquestioned and with his receipt of the Good Scout Award, the Boy Scouts of America recognize his devotion to the people of Prince William County. As a two-

A TRIBUTE TO PRINCE WILLIAM tour Vietnam Veteran and the longest serving county supervisor in Prince William County history, his career is one of service to country and community.

Madam Speaker, I ask that my colleagues join me in applauding Supervisor John D. Jenkins' dedication to his community. As a public servant he embodies the values the Bov Scouts hope to instill in their youth. He has taught generations of Scouts the nobility of public service and the great potential that it holds to help one's fellow man.

DEPARTMENT OF HOMELAND SE-CURITY APPROPRIATIONS ACT, 2010

SPEECH OF

HON. JERRY MORAN

OF KANSAS

IN THE HOUSE OF REPRESENTATIVES Wednesday, June 24, 2009

The House in Committee of the Whole House on the State of the Union had under consideration the bill (H.R. 2892) making appropriations for the Department of Homeland Security for the fiscal year ending September 30, 2010, and for other purposes:

Mr. MORAN of Kansas. Madam Chair, I come to the House of Representatives to encourage my colleagues to support and fund an urgent national security priority—the creation of the National Bio and Agro-Defense Facility, also known as NBAF.

From a rancher feeding his cattle this morning in Washington, Kansas, to a family sitting down for supper tonight here in Washington, D.C., Americans need to know that the United States is prepared to handle an outbreak of dangerous animal disease that could harm our country's economy and our food supply.

Our nation's current animal disease research center, located at Plum Island, New York, is well over 50 years old and can no longer meet our needs. With today's threat of bioterror attack, as well as the threat of natural and accidental outbreaks of foreign animal diseases, it is clear that more research capacity is needed. NBAF is needed to concentrate our efforts to assess disease threats to livestock, wildlife and humans, and to develop the vaccines and countermeasures against these threats. A modern, safe animal disease research laboratory is critical for protecting our

After years of study and a rigorous selection process, in January, the Department of Homeland Security unanimously chose to build NBAF at Kansas State University in Manhattan, Kansas. DHS found Kansas State University to be the best fit for this critical mission. Kansas was chosen because of the State's existing biosecurity research infrastructure, skilled animal science workforce, strong citizen support, and large cost-share contribution. At the time, NBAF was expected to be completed by 2015.

Despite the fact that there has never been stronger need for accelerated animal disease research, I am incredibly disappointed that NBAF may now be delayed. The President requested \$36 million in 2010 for NBAF design and construction. I have concerns that this investment is inadequate for moving forward with this security priority. But as the House today considers H.R. 2892, the FY 2010 Department of Homeland Security Appropriations Act, it appears that even the President's requested funding amount may not be provided. Citing safety concerns with researching foot and mouth disease, FMD, on the mainland, the spending bill provides no funding for NBAF. In addition, the bill requires yet another FMD risk analysis.

As a Member of Congress who represents a large agricultural district, I understand the importance of determining the risks associated with conducting FMD research, whether on an island or in the middle of the country. What we know is that studies by experts at DHS and elsewhere say that FMD can be safely studied on the mainland, as it is done in other countries like Canada, just across our northern border. Modern biocontainment technology has eliminated the need for locating this work on an island, like we did decades ago. The same state-of-the-art research methods and facilities allow the Centers for Disease Control and Prevention to research dangerous human diseases in the city of Atlanta. While I understand the risk associated with the research of any dangerous disease, it should not blind us to the risk of inaction. The bottom line is that if we do not build NBAF and increase our capacity to combat diseases, our country will be less safe.

The research that will be performed at NBAF is critical to secure America's food supply and protect our agricultural industries from animal disease outbreaks. A modern facility that can respond to outbreaks is urgently needed and must remain a top priority for the U.S. As the appropriations process moves forward, I strongly encourage my colleagues in Congress to fund and support NBAF.

VETERANS HEALTH CARE BUDGET AND TRANSPARENCY REFORM ACT OF 2009

SPEECH OF

HON. AL GREEN

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES Tuesday, June 23, 2009

Mr. AL GREEN of Texas. Mr. Speaker, I rise in strong support of H.R. 1016, the Veterans Health Care Budget Reform and Transparency Act.

The men and women who have served our nation in combat deserve to be provided with the very best that we have to offer. One part of achieving that is getting these men and women the best health care that they can possibly have. In turn, it is critically important that the Veterans' Administration (VA) have assurances regarding their funding in a timely manner so that the VA can deliver health care in an efficient and timely manner.

• This "bullet" symbol identifies statements or insertions which are not spoken by a Member of the Senate on the floor. Matter set in this typeface indicates words inserted or appended, rather than spoken, by a Member of the House on the floor.

This important legislation authorizes Congress to approve VA medical care appropriations one year in advance of the start of each fiscal year. While we still have much further to go in terms of making sure that every hero returning home has all the care that they need, this bill will at least ensure that the VA will be able to plan ahead of time and get the most out of each health care dollar that they are allocated. Furthermore, because many VA budget cycles have, in recent years, started on continuing resolutions, some decisions may have been made on the basis rather than on the basis of the most effective treatment. We cannot jeopardize the health of our nation's finest because of what amounts to nothing more than a bureaucratic difficulty.

I was proud to work with a number of colleagues to include a similar VA advanced appropriations provision in this year's congressional budget resolution, S. Con. Res. 13. Nevertheless, there is no reason why our veterans should need to count on Congress taking action every single year to keep this sensible policy in place. For this reason, it is imperative that we pass the Veterans Health Care Budget Reform and Transparency Act.

I am proud to be a co-sponsor of this important bill. I thank my good friend, the Chairman of the Veterans' Affairs Committee, Congressman FILNER for introducing it and I encourage all of my colleagues to vote in support.

PERSONAL EXPLANATION

HON. ALLYSON Y. SCHWARTZ

OF PENNSYLVANIA
IN THE HOUSE OF REPRESENTATIVES
Thursday, June 25, 2009

Ms. SCHWARTZ. Madam Speaker, during an absence yesterday, I regrettably missed rollcall vote No. 426. Had I been present, I would have voted in the following manner: rollcall No. 426: "no"

IN RECOGNITION OF THE STROKE COMEBACK CENTER

HON. GERALD E. CONNOLLY

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CONNOLLY of Virginia. Madam Speaker, I rise today to recognize the Stroke Comeback Center and the critical health care services that it provides to stroke survivors and their families.

The Stroke Comeback Center (SCC) is a non-profit organization that provides ongoing rehabilitation and therapy to help combat the devastating damage that strokes can cause. The mission of the SCC has been to pick up where traditional health care coverage leaves off by providing affordable speech and language therapy programs to stroke victims in a caring and supportive environment.

The SCC was founded in 2004 by Darlene Williamson and John Phillips based on the premise that stroke victims who suffer with communications problems can continue to improve with treatment and therapy. This theory went against the conventionally held belief that stroke survivors reached their maximum potential within the first few months of recovery.

In addition, most insurance companies cover only short term treatment, which can limit access to therapy and thereby inhibit recovery.

The SCC addresses these issues in a proactive and effective manner. Fees charged for services are on a sliding scale and are up to 75% less than at other facilities. No individual is ever turned away due to inability to pay. The programs offered by the SCC include group programs to assist with improvement of communication skills, computer assisted training, individual sessions and caregiver support meetings.

The growth of the SCC is a tribute to the success of its programs. In 2005, the SCC had five groups meeting two days per week. There are now 21 groups meeting four days per week. Since opening, the SCC has provided more than 7,000 hours of therapy to stroke survivors.

The SCC works closely with the American Heart Association, the Inova Mount Vernon Hospital, the National Rehabilitation Hospital and the George Washington University Department of Speech and Hearing Science.

Madam Speaker, I ask my colleagues to join me in recognizing the Stroke Comeback Center and its dedicated staff and volunteers. The services and programs offered by the SCC fill a void in the rehabilitation process and significantly improve the quality of lives of stroke survivors and their families.

CAP-AND-TAX DOES NOT WORK

HON. JOE WILSON

OF SOUTH CAROLINA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. WILSON of South Carolina. Madam Speaker, a national energy tax will do harm to American families by raising electric bills, gas prices, and food prices by thousands of dollars. Moreover, it will not achieve the goals of a cleaner environment.

As our European neighbors have learned from their own cap and trade scheme, costs go up but so do carbon emissions. Indeed, in the so-called market place of carbon trade, the American people will lose just as our European friends have. America will lose jobs and American families will lose money, and there is no excuse for the Democrat leadership in this House to place such a burden upon the American people.

I hope my colleagues will abandon this plan to raise taxes and realize that an all-of-the-above approach to our energy needs—one that has bipartisan support—is a far better course for this country to pursue.

In conclusion, God bless our troops, and we will never forget September 11th in the Global War on Terrorism.

HONORING THE HEROISM AND BRAVERY OF THE WOMAN AIRFORCE SERVICE PILOTS OF WORLD WAR II

HON. STEVE COHEN

OF TENNESSEE

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. COHEN. Madam Speaker, I rise today in support of H.R. 2014, which awarded the

Woman Airforce Service Pilots of World War II with a Congressional Gold Medal. Known as WASP, these courageous women faced incredible bias and hardship while serving our country. Out of the 300 recipients, three WASP are from the 9th district in Memphis, TN

Women were essential to our effort in World War II. In factories and shipyards throughout this nation, they provided the fundamental infrastructure and labor which allowed our military to prevail. We can't forget that just 23 years before the war, Rosie the Riveter didn't have the right to vote. Suddenly, she was the muscle behind the plane, the tank, the ship—in short the entire arsenal of democracy. The women of these times toiled selflessly. They were passionately patriotic.

The WASP were no exception. They were the backbone of the Army Air Corps and performed vital jobs such as delivering newly assembled planes to key military bases and test piloting new planes. They even flew the first jets. The WASP flew over 60 million miles in every type of aircraft. Without their work, the Army Air Corps would not have been able to function properly and domestic efforts would have been severely crippled, making it more difficult to receive crucial supplies, troops and planes.

I am very proud to have three WASP veterans living in my home district in Memphis, TN. Martha M. Carpenter, Frankie Yearwood and Lillian E. Goodman all graduated from the WASP program with extensive flight experience and training. Their jobs required incredible skill and were highly dangerous. Recently, Ms. Goodman recalled. "in my own class there were two girls and an instructor that went up in a twin engine plane . . . they crashed and were all killed." The women that Ms. Goodman remembers were sent home in unmarked pine boxes. Their service was not acknowledged. They were denied military funerals and their families were not permitted to put up a Gold Star in their memory. It wasn't until 1977 that Congress finally gave the WASP veteran status and benefits.

For all their patriotism and service, the WASP—all of whom were pilots before the war—faced harassment and shocking levels of discrimination during and after their service. Sadly, they were made to pay for their own flight training and for their own trip home after being discharged. When the war ended, some male combat veterans fought vigilantly to deny them equal veteran status.

For thirty years, the federal government classified WASP records. For too long, their heroism was kept out of the history books. Grandmothers could only tell incredible stories of serving as pilots in World War II to disbelieving grandchildren. President Carter helped to change all that by finally opening up the records and allowing Ms. Goodman, Ms. Carpenter, and Ms. Yearwood's service to be public.

The WASP's exemplary record and contributions towards the war effort were referenced in the 1993 congressional hearings which led to legislation allowing women to fly aircraft in combat roles. Currently, women make up more than 14% of the military on active duty and more than 17% of the reserve and National Guard. The Air Force has the highest percentage of women enlisted, as nearly 20% of its members on active duty and 25% of the National Air Force Reserve are

women. Ms. Carpenter, Mrs. Goodman, Ms. Yearwood and the other brave women of the WASP were pioneers for the dedicated women who serve in our military today and for all who face prejudice in pursuit of equality.

REPEAL TONNAGE TAX'S 30-DAY LIMIT ON DOMESTIC OPERATIONS

HON. EARL BLUMENAUER

OF OREGON

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. BLUMENAUER. Madam Speaker, U.S.-flag ships that compete in international trade face many disadvantages. The U.S. tax code should not be one of them. Today I am introducing legislation that will help smooth the seas for U.S.-flag shippers and increase their international competitiveness.

The version of the American Jobs Creation Act of 2004 that passed both the House and Senate provided for the application of a "tonnage tax" based on the tonnage of a vessel, rather than taxing the U.S. vessel's international income at corporate tax rates. In the conference process on that legislation, however, new language was inserted which states that a U.S. vessel cannot use the tonnage tax on its income from international operations if that vessel also operates in U.S. domestic commerce for more than 30 days per year.

This 30-day limitation dramatically limits the availability of the tonnage tax for those U.S. ships that operate in both domestic and international trade and hinders their competitiveness in foreign commerce. It is important to recognize that ships operating in U.S. domestic trade already have significant cost disadvantages. The inability of domestic operators to use the tonnage tax for their international service is a further burden on their competitive position in foreign commerce. Foreign registered ships now carry 97 percent of the imports and exports moving in United States international trade. These foreign vessels are not held to the higher Coast Guard operating standards that apply to Americanregistered ships and foreign vessels are virtually untaxed.

Adding to the perversity of the provision, in December 2006, Congress repealed the 30-day limit on domestic trading for approximately 50 ships operating in the Great Lakes. There are 13 U.S.-flag vessels outside of these Great Lakes ships that remain caught in these tax provisions. In the interest of providing equity to these 13 vessels, this legislation would repeal the 30-day limit on domestic operations, enabling these vessels to also utilize the tonnage tax on their international income. Under this legislation, these ships will continue to pay the normal 35 percent U.S. corporate tax rate on their income for operations in domestic commerce.

Repeal of the tonnage tax's 30-day limit on domestic operations is a necessary step toward providing tax equity between U.S.-flag and foreign flag vessels. I look forward to working with my colleagues to pass this important legislation.

IN RECOGNITION OF THE 2009 VIRGINIA HUMAN RIGHTS AWARDS

HON. GERALD E. CONNOLLY

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES Thursday, June~25,~2009

Mr. CONNOLLY of Virginia. Madam Speaker, I rise today to recognize the recipients of the 2009 Virginia Human Rights Awards. These awards were presented during a recent ceremony hosted jointly with the Prince William County Human Rights Commission.

Prince William County has long been an area of growth in our Northern Virginia region. As the county population grew in the early 1990s and the demographics shifted, the Board of County Supervisors recognized the need for a study to examine the county's ability to respond to increasing population diversity. The result of the study was the creation of a Human Rights Ordinance prohibiting discriminatory practices based on race, color, sex, national origin, religion, marital status or disability in employment, housing, public accommodations, education and credit in Prince William County. When the Board of County Supervisors established the Human Rights Ordinance in September of 1992, it created the Human Rights Commission to ensure that "each citizen is treated fairly, provided equal protection of the law and equal opportunity to participate in the benefits, rights, and privileges of community life."

The recipients of this year's awards have exhibited a devotion to "[eliminating] discrimination through civil and human rights law enforcement and [establishing] equal opportunity for all persons within the county through advocacy and education."

The recipients of the Prince William Human Rights Awards are Betty Covington from Prince William Public Schools and Dexter Fox with Unity in the Community.

The Virginia Human Rights Commissioner of the Year is Victor Dunbar, Chairman of the Fairfax County Human Rights Commission.

The Staff Member of the Year is Annie Carroll, Deputy Director of the Fairfax County Human Rights Commission.

The Virginia Human Rights Commemorative Award for contributions to human rights through the signing of the Civil Rights and Voting Rights Acts will be made posthumously to President Lyndon B. Johnson.

Madam Speaker, I ask that my colleagues join me in applauding the efforts of these individuals on behalf of harmony and equality in our communities. We are a happier, safer society when we promote fairness and justice. I would like to extend my unconditional support for the Human Rights Commission's mission and my deepest appreciation to those who take up the cause of human and civil rights.

EARMARK DECLARATION

HON. RANDY NEUGEBAUER

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. NEUGEBAUER. Madam Speaker, pursuant to the Republican standards on member requests, I am submitting the following information regarding congressionally directed ap-

propriation projects I sponsored as part of H.R. 2847, FY 2010 Department of the Interior, Environment and Related Agencies Appropriations Bill.

Agency/Account: U.S. EPA—State and Tribal Assistance Grant

Amount: \$439,065

Requesting Entity: City of Petersburg, P.O. Box 326 Petersburg, Texas 79250

Funding will enable the city of Petersburg to continue supplying quality drinking water to its residents. The Texas Commission on Environmental Quality has ordered the city to replace one of its elevated water tanks or place it offline or the city will be forced to pay penalties and fines. Loss of a water tank will reduce the water supply, as well as drop the water pressure which is important for fire fighting. Without a stable water supply, the city of Petersburg will not be able to maintain economic growth. The total cost of this project is \$798,300.

EARMARK DECLARATION

HON. TIM MURPHY

OF PENNSYLVANIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. TIM MURPHY of Pennsylvania. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010:

Requesting Member: Congressman TIM MURPHY

Bill Number: H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010

Account: State and Tribal Assistance Grant Program

Legal Name of Requesting Entity: Findlay Township Municipal Authority

Address of Requesting Entity: 1271 Route 30, Clinton, PA 15026–1537

Amount: \$500,000

Description of Request: to replace old and undersized water transmission lines, and to expand and upgrade the water and sewer infrastructure, to benefit the entire Township of Findlay in economic development and job creation, fire safety and environmental protection.

The water and sewer upgrades and expansion will serve businesses-and the 21,310 iobs being created—at three business parks in the Pittsburgh International Airport Corridor: the Chapman Commerce Center; the Clinton Commerce Park and the Route 30 Industrial Site. Furthermore, annual tax revenue generated at the three business parks is projected to be \$48.7 million. In terms of fire safety, the project will replace old and undersized water transmission lines to provide adequate fire flow for the entire township, including residents and businesses. In terms of environmental protection, the project will rectify a concern of the Pennsylvania Department of Environmental Protection that the sanitary sewer system capacity from Enlow Road to the Moon Township Interceptor must be expanded to adequately convey additional flow.

I certify that this project does not have a direct and foreseeable effect on the pecuniary interests of me or my spouse. I took extreme care to ensure that these projects are well vetted and strongly supported within the community. The Findlay Township Municipal Authority appropriation is of particular interest to my district and importance to my constituents.

EARMARK DECLARATION

HON. TOM COLE

OF OKLAHOMA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. COLE. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010:

Requesting Member: Congressman Tom COLE

Bill Number: H.R. 2996

Provision: Title I

Account: National Park Service—Construc-

Legal Name of Requesting Entity: "National Park Service—Chickasaw National Recreation Area"

Address of Requesting Entity: 1008 West Second Street, Sulphur, OK

Description of Request: Provide an earmark of \$500,000 for a design plan to construct a Visitor's Center at the Chickasaw National Recreation Area. The need for a Visitor's Center was identified in the recreation area's 1980 General Management Plan and 1994 Addendum to the 1980 General Management Plan. The Visitor's Center was previously budgeted for, but funds were reprogrammed for wildfire suppression. The Visitor's Center will provide those visiting the Chickasaw National Recreation Area a much needed centralized location where the Park Service may educate individuals on the ecosystems and history of the area. This will increase tourism to the recreation area, and thereby grow the local economy substantially.

Requesting Member: Congressman Tom Cole

Bill Number: H.R. 2996

Provision: Title II

Account: STAG Water and Wastewater Infrastructure

Legal Name of Requesting Entity: Lawton Ft. Sill Chamber of Commerce

Address of Requesting Entity: 9 SW "C" Avenue, Lawton, OK 73501

Description of Request: Provide an earmark of \$500,000 for water and sewer line expansions at the Lawton Industrial Park, in Lawton, OK. The Comanche County Industrial Development Authority recently purchased an additional 480 acres immediately southwest of the present industrial park for purposes of expansion. Before this development can begin, water and sewer lines must be expanded to the property. The industrial park expansion will allow for more commercial expansion, thus creating jobs and aiding Lawton's economy. For this project, 80 percent of funds will be used for construction costs, 12 percent will be used for contingency, 6 percent will be for engineering costs and 2 percent will be used for inspections.

EARMARK DECLARATION

HON. JOHN J. DUNCAN, JR.

OF TENNESSEE

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. DUNCAN. Madam Speaker, consistent with House Republican Earmark Standards, I am submitting the following earmark disclosure information for project requests that I made and which were included within H.R. 2996, "Making appropriations for the Department of Interior, environment, and related agencies for the fiscal year ending September 30, 2010."

Requesting Member: Congressman JOHN DUNCAN

Account: National Park Service, Save America's Treasures

Project Amount: \$200,000

Legal Name of Requesting Entity: Blount Mansion Association, 200 W. Hill Avenue, Knoxville, TN 37902

Description of Request: This funding will be used to upgrade and improve the National Historic Landmark.

IN RECOGNITION OF THE 25TH ANNIVERSARY OF THE ROTARY CLUB OF BURKE, VIRGINIA

HON. GERALD E. CONNOLLY

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. CONNOLLY of Virginia. Madam Speaker, I rise today to congratulate the Rotary Club of Burke, Virginia, on the occasion of its 25th Anniversary and to pay tribute to its significant contributions to the community.

The world's first service club, the Rotary Club of Chicago, Illinois, was formed on February 23, 1905, by Paul P. Harris. The name "Rotary" is derived from the early practice of The Rotary Club concept thrived in its early years, and, by 1921, there were chapters on six continents. In 1922, the name "Rotary International" was adopted. The objective of Rotary International is to encourage and foster the ideal of community service as a basis of worthy enterprise. International understanding, goodwill and peace are fostered through the shared commitment to service of Rotarians from 166 countries.

The Rotary Club of Burke was organized by Brian Tilbury and was chartered by Rotary International on June 30, 1984. Since that time, the Burke Rotary has grown in not only the number of active members, but also in the areas of community service.

The Burke Rotary participates in Polio Plus, which is dedicated to the eradication of polio in countries such as Afghanistan, India, Pakistan and Nigeria. Closer to home, The Rotary Club of Burke is a dependable ally in the Toys 4 Tots Program and the Northern Virginia Literacy Council. It also encourages involvement in the Medical Reserve Corps, a Fairfax County, Va., program that trains volunteers to provide vital services in the event of a public health emergency.

The Rotary Club of Burke has partnered with the Rotary Club of Annandale to provide scholarships to deserving students who wish

to pursue vocational training at Northern Virginia Community College. This partnership now provides six scholarships each year and has allowed approximately 40 individuals to continue their education and learn a marketable skill. The quality of life for each of these students and their families will be forever improved because of this opportunity.

Madam Speaker, I ask my colleagues to join me in congratulating The Rotary Club of Burke on the occasion of its 25th Anniversary and to express our gratitude for their contributions here at home and abroad.

EARMARK DECLARATION

HON. PHIL GINGREY

OF GEORGIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. GINGREY of Georgia. Madam Speaker, pursuant to the Republican Leadership standards on earmarks as well as in accordance with Clause 9 of Rule XXI, I am submitting the following information regarding the earmark I received as part of H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act for Fiscal Year 2010.

Requesting Member: Congressman Phil GINGREY

Bill Number: H.R. 2996

Account: Environmental Protection Agency; STAG Water and Wastewater Infrastructure Projects

Legal Name of Requesting Entity: Metropolitan North Georgia Water Planning District

Address of Requesting Entity: 40 Courtland Street, NE Atlanta, GA 30303

Description of Request:

The \$500,000 in STAG funding secured will be applied to this list of the Water District projects:

COBB COUNTY

Sweetwater Creek Sanitary Sewer Extension—This proposed extension of the Sweetwater Creek interceptor will provide gravity sewer service to much of the unsewered portion of southwestern Cobb County, including several dry sewer subdivisions. It will also extend service into the Sweetwater basin in Paulding County, eliminating the need for an additional treatment facility and comporting with our regional plan. The project includes about 20,000 linear feet of large diameter sewer. Estimated cost of this project is \$7,700,000.

Mack Dobbs Road Water Main Replacement—Replacement of 11,200 linear feet of existing 6-inch asbestos cement water main with 12-inch ductile iron between Cobb Parkway and Stilesboro Road. Estimated cost of this project is \$1,200,000.

Low Flow Toilet and Urinal Retrofit for 127 Cobb County Public Schools—A water conservation project which consists of replacing approximately 5,782 older, inefficient toilets and urinals and 2,478 miscellaneous faucets and pre-rinse spray valves in Cobb County Schools. The estimated cost of this project is \$875.000.

COBB COUNTY-MARIETTA WATER AUTHORITY

The Cobb County-Marietta Water Authority (CCMWA), a political subdivision of the State of Georgia, is a regional water wholesaler with 13 customers that serve over 790,000 people.

The customers include Cobb County, all of the municipalities within Cobb County, all of Paulding County, portions of Douglas County, Cherokee County, the City of Woodstock, and a small community in Fulton County.

Austell West Side Connector 24"-This pipeline project installs 8,000 feet of 24" ductile iron pipe to connect existing transmission lines. The pipeline will improve system flow capacity and provide redundancy to Cobb Hospital and high growth area along East-West Connector. The estimated cost of this project is \$2,549,800.

Five Million Gallon Steel Tank at Lost Mountain-This tank will provide enhanced fire protection. It will also increase system reliability by improving storage-to-production ratio and source water reliability for existing pump station. It will provide additional water storage for west Cobb County and Paulding County. The estimated cost of this project is \$3,500,000.

Five Million Gallon Steel Tank at Pete Shaw—This tank will provide enhanced fire protection. It will also increase system reliability by improving storage-to-production ratio. This tank will provide additional water storage capacity to east Cobb County. The estimated cost of this project is \$3,500,000.

Columns Drive Pipe Replacement-Replacement of approximately 600 linear feet of 36" ductile iron pipe with 54" restrained joint ductile iron pipe. This installation will eliminate a restriction in the main line from the Quarles Water Treatment Plant. The estimated cost of this project is \$780,600.

HALL COUNTY

Low Flow Toilet and Urinal Retrofit for Hall County Government Facilities-A water conservation project which consists of replacing all older, inefficient toilets and urinals in County facilities not already fitted with low flow systems including; Parks, Fire Stations, Senior Centers, Prisons, etc. The estimated cost of this project is \$190,000.

THE CITY OF GAINESVILLE

Flat Creek Watershed Improvement Plan and Ecosystem Restoration-The City of Gainesville and Hall County have developed a watershed improvement and ecosystem restoration plan for the Flat Creek watershed which includes several projects involving stream restoration and construction of storm water best management practices. The City is currently designing the Upper Flat Creek Stream Restoration and Regional Stormwater Detention Pond project. The estimated cost of this project is \$700,000. Other projects we are moving forward with would cost approximately

Gainesville/Hall County Water Main Extensions and Improvements projects-These projects include approximately 25 miles of 8"-20" water line extensions/improvements throughout Gainesville/Hall County. Projects will extend water service to new customers and improve fire and water service by installing fire hydrants in new locations and improving flow capacity and quality in the water distribution system. The cost of these projects is estimated to be \$13,200,000.

ROCKDALE COUNTY WATER RESOURCES

Distribution Waterline Replacements—A water conservation project to significantly reduce or eliminate unaccounted for water (i.e. reducing water leaks in public water supply distribution system). Estimated cost of this project is \$15,000,000.

sewer overflows and upgrade pumping station to meet current demands in a concentrated area. Estimated cost of this project is \$300.000.

THE CITY OF LOCUST GROVE

Water Supply Wells-The City of Locust Grove has drilled two additional wells for drinking water supply. These wells have already been drilled and permitted by GA EPD. The wells are needed to help supply enough water for current demand. The design has already been drawn. Estimated cost of this project is \$250,000.

THE CITY OF ROSWELL

Municipal Buildings Water Conservation Project—The condition of Roswell's municipal building restroom facilities vary widely in age, use, quality and repair. An initial assessment of the restrooms found 106 urinals, 295 toilets and 265 faucets to replace. The proposed water conservation project will purchase and install high-efficiency urinals, and toilets for the City's administrative, public safety, publicworks, recycling center and park buildings. Additionally the project could include low-flow faucets, eco-friendly sanitizer systems and to minimize restroom vandalism and maintenance the installation of stainless steel panels. new and replacement tile. The estimated cost for this project is \$500,000.

THE CITY OF ALPHARETTA

North Park Improvements: Construct off-line sediment forebay-A sediment forebay will allow silt to fall out in a confined area just prior to the lake. During non-storm flows, the creek will flow naturally into the lake. When it rains and the creek rises, water will be diverted to the forebay. The forebay will slow down the water, allowing time for much of the silt to fall out before discharging back into the lake. The forebay will be much easier to clean out than the lake itself.

North Park Improvements: Construct three enhanced swales to treat water coming from the softball fields and two parking lots-Enhanced swales are state recognized water quality Best Management Practices (BMPs) that allow for more water to infiltrate and be treated prior to entering the creek. As part of the installation of the enhanced swales, the water from these areas will be diverted to directly enter the lake instead of entering upstream through very eroded gullies. The gullies are so large that it is actually more cost effective to install the BMPs and divert the flow than it would be to repair the gullies, which are over 20 feet deep in some areas.

North Park Improvements: Modify the outlet control structure of the lake-The current outlet structure of the lake clogs in nearly every storm event, requiring parks maintenance personnel to have to remove debris to restore drainage. The outlet control structure can be modified to reduce clogging and provide improved water quality benefits for the lake. This will reduce necessary maintenance and give the lake an overall better aesthetic appearance.

Total cost for these improvements is: \$517,818.75. This price includes the cost to prepare conceptual and final design; construction of three improvements/BMPS; and model pollutant removal.

Wastewater Pump Station—To prevent RECOGNIZING CHILDREN'S MED-ICAL CENTER OF DALLAS FOR ITS RANKING AMONG THE TOP TEN CHILDREN'S HOSPITALS IN THE NATION

HON. EDDIE BERNICE JOHNSON

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Ms. EDDIE BERNICE JOHNSON of Texas. Madam Speaker, in 1913, a group of nurses established Children's Medical Center of Dallas as an open air clinic. Today, Children's Medical Center has been chosen among the top 10 children's hospitals in the nation, according to U.S. News & World Report. Children's provides exemplary care and resources to its thousands of patients, as well as a wide range of teaching opportunities to the future physicians and nurses of our country. As a former nurse, I am proud to have such an accomplished medical institution in my district and would like to extend warm congratulations to them for receiving such recognition.

Children's Medical Center of Dallas is a private, non-profit pediatric health care center. As one of the largest pediatric hospitals in the country, Children's treats approximately 360,000 patients a year, with treatments ranging from simple physical exams to specialized care in heart disease, oncology, orthopedics, kidney disorders, neurology, respiratory disorders, neonatal care, urology, diabetes, and digestive disorders. Furthermore, Children's is a major pediatric transplant center, and also is the only academic health care facility and only designated Level 1 trauma center in Texas. Children's Medical Center of Dallas is continuously conducting research and developing new and improved treatments and therapies regarding pediatric diseases.

It is my hope that Children's Medical Center of Dallas will continue its strong record of success and provide patients with excellent care. It shines as an example of excellence, and I truly appreciate the dedication put forth by the administrators, doctors, nurses, and everyone else there. Again, I offer my congratulations to Children's Medical Center of Dallas on its achievement of being named one of America's top 10 children's hospitals.

EARMARK DECLARATION

HON. DUNCAN HUNTER

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. HUNTER. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding an earmark I received as part of H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act. 2010:

I originally requested \$1 million in this legislation for the El Monte Valley Groundwater Recharge Project through the Environmental Protection Agency's State and Tribal Assistance Grant Water and Wastewater Infrastructure Project account. It is my understanding that \$500,000 was ultimately appropriated for this project by the Subcommittee and the entity to receive funding for this project is the

Helix Water District located at 7811 University Avenue, La Mesa, California 91941.

This is a groundwater recharge and habitat restoration effort led by the Helix Water District where it will secure highly treated wastewater from the Padre Dam Municipal Water District's Santee Water Recycling Facility, provide additional treatment to purify the wastewater, pump and pipe this water to surrounding basins and then release it into the San Diego Riverbed where it will be allowed to seep down to existing groundwater levels. As the purified water is maintained in this location, it will receive additional natural treatment as it percolates through native materials. Extraction wells will be installed at strategic locations for conveyance to a water treatment plant as a new source of water for all District

This action will assist in the continued goals of the San Diego County region to reduce its dependence on imported water from the Colorado River and Northern California by annually producing 5,000 acre-feet of locally available drinking water and meeting 10-15% of the Helix Water District's raw water needs. By raising the groundwater levels in El Monte Valley, revegetation of the riverbed is supported and a more natural habitat is created for recreation and wildlife. This project is the beginning of an 8-year program and has been endorsed by other elected officials, including California Assemblyman Joel Anderson and California State Senator Christine Kehoe, as well as the Association of California Water Agencies, Endangered Habitats League, San Diego County Water Authority, Padre Dam Municipal Water District, Otay Water District, and the Lakeside Water District.

IN RECOGNITION OF WOODBRIDGE MIDDLE SCHOOL

HON. GERALD E. CONNOLLY

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CONNOLLY of Virginia. Madam Speaker, I rise today to recognize Woodbridge Middle School as a leader in education reform. Woodbridge was recently designated as a 2009 School to Watch by the National Forum to Accelerate Middle-Grades Reform.

The Schools to Watch program was establish in 1999 with the purpose of identifying schools on a path to meeting the National Forum's criteria for high performing schools. There are four categories in which qualifying schools must excel to be selected as a School to Watch. First, students must be challenged academically with clear and well-communicated education goals. Second, a school must work to develop a well-rounded student. This is accomplished through programs that foster healthy physical, social, emotional and intellectual development. Third, a School to Watch must present students with a socially equitable learning environment where diversitv. civility. service. and democratic citizenship are valued. Finally, a qualifying school must have organizational structures in place that work to institutionalize the first three cri-

Consistent with the cooperative spirit of the Schools to Watch program, the motto that drives Woodbridge Middle School is, "We get

better together." Students, faculty and administration are held accountable for school performance and are encouraged to make the education experience a team effort. The staff is required to follow a set meeting schedule for the purpose of monitoring instructional and support programs. Students who are in danger of failing a course must work with parents and teachers to map out a plan to achieve a passing grade. No one is an island at Woodbridge Middle School where education is a community effort.

Madam Speaker, I ask that my colleagues join me in applauding Woodbridge Middle School on this prestigious designation and in encouraging it to continue these proven successful approaches to education. Woodbridge Middle School is a model that provides guidance in how to effectively improve our education system. The students, faculty and entire community benefit when we invest in our nation's future by providing our children with a productive and positive learning experience.

EARMARK DECLARATION

HON. MARY BONO MACK

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mrs. BONO MACK. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2892, Department of Homeland Security Act of 2010:

Requesting Member: MARY BONO MACK Bill Number: H.R. 2892

Account: Department of Homeland Security—State and Local Programs

Entity Requesting: City of Moreno Valley, 14177 Frederick Street, Moreno Valley, CA 88005

Description of Earmark: The City of Moreno Valley currently has plans to construct a new 8,000 square foot Emergency Operations Center (EOC). The City's current EOC consists of one room inside the existing Public Safety Building. With the new facility, the City will be fully prepared to respond to all emergency situations, restore services to our residents as quickly as possible, and provide effective communication among other agencies as well as with our residents. This request is to fund the purchase of new equipment such as telecommunications and video display, resource tracking software, and computers. The federal nexus is to assist federal, state and local authorities and help coordinate responses to emergencies such as earthquakes and wildfires.

Spending Plan: The total project construction costs for the Emergency Operations Center are \$4.5 million. The \$400,000 appropriation will be used to fund the purchase of equipment for the EOC. This project is currently out to bid for construction. This request is to fund the purchase of new equipment such as telecommunications and video display, resource tracking software, and computers.

THANKING ROBERT WARNICK FOR HIS SERVICE TO THE HOUSE

HON. ROBERT A. BRADY

OF PENNSYLVANIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. BRADY of Pennsylvania. Madam Speaker, on the occasion of his retirement on May 1, 2009, we rise to thank Mr. Robert "Bob" Warnick for thirty-one years of distinguished service to the United States House of Representatives. Bob has served this great institution as a valuable employee of House Information Resources, HIR, in the Office of the Chief Administrative Officer.

Bob began his tenure with the United States House of Representatives in May of 1978 in House Information Resources, HIR, as a Senior Systems Analyst, SSA. As an SSA, he successfully implemented a system to generate the Committee Calendar for the Committee on Public Works and Transportation using HIR's Legislative Information Management System, LIMS, developed a case history and mailing list system for the Helsinki Commission, and successfully implemented the first Correspondence Management System, CMS, on the Hill.

In 1987, he transferred to the Administrative Systems Division as the Senior Project Leader for LIMS. In 1995, he was promoted to Senior Systems Specialist and transferred to the Integration Group. As a senior member of this group, he was tasked with the design and implementation of several applications using Standard Generalized Mark-Up Language, SGML. As a proof of concept project, his group successfully converted and produced three House documents using SGML.

In 1996, he was transferred to the Cyber Congress task force within the Integration Group. He was appointed to the position of Senior Internet Systems Specialist when the Cyber Congress task force was renamed the Web System Branch, WSB. His important contributions as a team member in the CAO Advanced Business Solutions Web Solutions Branch have resulted in continued success of the Web Solutions Design team where he designed and implemented Member and Committee Web sites and provided a wealth of knowledge of the Web Indexed Document Automation, WIDA, service application to staff and Member offices.

On behalf of the entire House community, we extend congratulations to Robert "Bob" Warnick for many years of dedication and outstanding contributions to the United States House of Representatives. We wish Bob many wonderful years in fulfilling his retirement dreams.

COMMENDING ARTHUR LEE HENRY FOR BEING NAMED A STATE OF LOUISIANA "CITIZEN HERO"

HON. CHARLES W. BOUSTANY, JR.

OF LOUISIANA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. BOUSTANY. Madam Speaker, I rise today to honor Arthur Lee Henry, a true "Citizen Hero", as honored by the president of Victims and Citizens Against Crime.

Law enforcement officers in St. Landry Parish nominated Arthur for an incident that occurred in August of 2008, when he successfully disarmed a gunman on the campus of T.H. Harris Technical College in Opelousas, Louisiana. Upon seeing a man produce a gun and fire shots, Arthur quickly reacted and saved the lives of several innocent bystanders

Arthur, a happily-married man with two children, proudly serves as a custodian at the technical college, where he has worked for twelve years. Coworkers describe him as "a very professional individual", "a wonderful employee", and "an integral part of campus." Today, he will be attending a banquet to receive the award with the dean of the college, Allen Espree.

Again, congratulations to Arthur Lee Henry, one of Louisiana's "Citizen Heroes" for taking pride in the campus he proudly serves.

2009 CONGRESSIONAL AWARD RECIPIENTS

HON. THOMAS J. ROONEY

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. ROONEY. Madam Speaker, I rise today to honor the efforts and achievements of the 2009 Congressional Award recipients. Striving to better themselves and inspire others, these individuals have invested countless hours into public service, built their strength and endurance through academic and athletic pursuits, and explored their own abilities in new and challenging arenas. Volunteerism, self-discipline, and determination are hallmarks of this class of award recipients, and their passion rightfully deserves the admiration of this House.

The Congressional Awards recognize four avenues of individual growth—community service, physical fitness, exploration, and personal development—while acknowledging their interconnectivity in forming balanced and promising young citizens.

In their pursuit of these goals, recipients have encouraged the growth of new skills and greater confidence. For many, these projects will be the cornerstone for future endeavors, further enriching their lives and encouraging others to follow their lead.

The 2009 Congressional Award winners demonstrate dedication to improving their communities and making the world a better place.

The following are honored recipients of the 2009 Congressional Award:

Alec Kohli, Lukas Bergqvist, Ashley Macres, Kristen Glass, Stephanie Glass, Sarah Williams, Kelly Chen, Renee Jorgensen, Spencer Chase, Mark Felicio, Todd Lundrigan, George Major, Sarah Schwab, Charles Su. Christopher Barnum, Sacha Finn, Cameron Chalfant, John Hunsaker, Malinda Seu, Lynn Tse, Natalie Millman, Kathryn Gasparro, Heather Mauldin, Jena Mauldin, Andy Powers Davis, David Steinmetz, Christina DiMarzio, Courtney Cox, Hayley Gibson, Drake Gordon, Alexandra Abadia, Brian Asker, Christian Estevez, Jessica Fillhaber, Jordan Gallas, Stefan Hogle, Shannon Johnson, Kiera Kadri, Jesse Lively, Nicholas Lively, Adam Pere, Aleksi Poirier, Maxwell Poirier, Mitchell Poirier,

Faren Silverman, Philip Stumpf, Neil Zimmerman, Erin Brannen, Katherine Brattebo, Taylor Celedinas, Lyndsay Daubert, Elizabeth Doane, Michelle Hardin, Adam Hollander, Summer Lubart, Connor Melnyk, Amanda Pekar, Jessica Olsen, Joshua Howard, Michael Moroz, Jenna Harris, Ashley Newman, Weston Newman, Rebecca Brazeale, Jeralyn Westercamp, Katelyn Benton, Jonathan Bertsch, Kyle Felzien, Heather Layher, Josh Layher, Jacob Levi, Daniel Revard, Shelby Roth, Kathryn Vincent, Lyndsey Vincent, Megan Breeding, Shawn Bybee, lda Fischer, Hosanna Kabakoro, Mary Jordan Langfield, Elizabeth Middleton, Justin Novacek, Anna Sandven, Rvan Seastrom, Rebecka Seward, Candace Trautwein, Alexander Hawkins, Erica Newell, Melanie Spung, David Cieply, Emily Carlile, Alex Cain, Joshua Chudy, Lisa Huber, Jadhken Kerr, Jadhon Kerr, Rachel Battershaw, Annie Burke, Dakota Hauserman, Rachel Matthew, Denver Shipman, Scott Shipman, Emilee Whitesell, Mari Reeves, Tyler Wilcox. Brandi Thomas, Christopher Camillucci, Niels Steadman, Todd Sharpe, Kristen Barnett, Cassandra Dalrymple, Joanna Guy, Henry Zheng, Joseph Jendrusina, Veronica Kirin, Jenna Bjorke, Alexander Mace, Ashley Mace, Ami Mehta, Emma Frey, Kelsey Abele, Elizabeth Lewis, Tyler Camp, Daniel Clark, Cory Gargus, Chelsi Smith, Justin Armstrong, Mattie Carter, Ashley Cooper, Derek Lair, Steven Elliott, Alston Harris, Eleanor Hoppe, Sarah Smith, Colin Sorensen, Katherine Aronoff, Summer Brecht, Elizabeth Cubbage, Jordan Phifer, Eric Stump, Katie Stump, Rebecca Wentzel, Steven Zipparo, Giaquinto, Madeline Giaquinto, Gabrielle Sonam Shah, Nicholas Stango, John Voorhees, Samantha Albala, Patrick Chevalier, Robert Dorfman, Adam Gross, Megan Arguell, Alexandra Garney, Megan Partridge, Nevin Raj, Neal Bakshi, Elizabeth Bogdon, Sean Lu, Shiang, Rebecca Wu, Christina Borovilas, Mary-Katherine Rose, Sujay Tyle, Nandini Srinivasan, Michael Cox, Mike Eklund, Teor Khuon, Du Luong, Phong Ma, Quyen Ma, Nhan Nguyen, Tevorith Srong, Srun Chhang, Le Long, Phanit Nhem, Mi Ta, Camlung Ung, Kyle Zhu, Jazmin Richardson, Vinay Trivedi, Cuiping Chen, Cuiyu Chen, Jillian Comer, Elizabeth Donahoe, Jacob Feldman, Julie Ann Haldeman, Brittany Love, James McDonald, Julia Melin, Victoria Patchell, Marta Piotrowicz, Julia Powers, Jocelyn Simons, Michelle Wojciechowicz, Tyler Zimmerman, Stephanie Bernasconi, Luis Gutierrez, Joaquin Mondragon, Amin Ruiz, Brian Elgort, Ryan Kane, Kent Willis, Michele Felberg, Christina Noblett, Amanda Vining, John Bradshaw, Collin Evans, Christine Folger, Britt Brandon, Sarah Gresser, Alicia Hanson, Jonathan Hanson, McKenna Rankin, Marshall Christopher, Karen Pickens, Cassandra Tuten, Mark Van Wagenen, Jenessa Barch, Faith Jones, Amanda O'Malley, Katherine Shannon, George Smith III, Dana Mathews, Blythe Hall, Devin Hall, Kaitlin Smith, Jacqueline Bedsaul, Taryn Bierhuizen, Courtney Owens, Patrick Crow, Matthew Cutler, Sam Pauken, Stephanie Redfern, Jennifer Baltas, Alexander Grigg, Emily Green, David Ramish, Nicolo Mendolia, Alexander Chin, Chelsea Green, Ryan Pyke, Leanne Paulsen, Lauren Below, James Hilgendorf, Paul Isaac Picklesimer, John Tate Bauman, Nicole Clikeman, Beth Cochran, Alex Coolidge, Kali Gentleman, Jessica Griffith, Keegan Hall,

Tylor Hanzlik, Ian Kline, Edward, Lynch, Michael Aaron Meier, Stephanie Meisner, Christina Nielsen, Betsy Plemons, Christopher Plemons, Kurt B. Rangitsch, Sara Rangitsch, Katrina Sauter, Katherine Stewart, Lara Wilson

HONORING RECIPIENTS OF THE 2009 FAIRFAX COUNTY HUMAN RIGHTS AWARDS

HON. GERALD E. CONNOLLY

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CONNOLLY of Virginia. Madam Speaker, I rise to recognize the recipients of this year's Fairfax County Human Rights Awards. Jeannie Cummins Eisenhour, Philip N. Reeves, Robert B. Worley, and the Communities of Faith United for Housing will be honored on July 2nd 2009 for their dedication and commitment to the community.

Each year, the Fairfax County Human

Each year, the Fairfax County Human Rights Commission presents the Human Rights Awards to individuals, nonprofits, and business who "demonstrate accomplishments in eliminating discrimination on the basis of race, color, sex, religion, national origin, marital status, age or disability in the areas of employment, housing, public accommodations, private education and credit."

Ms. Eisenhour is recognized for her commitment to working with members of the community with disabilities, opening opportunities to them and educating the public on their specific needs. Her distinguished work has aided persons with disabilities throughout Fairfax County and the D.C. area. Her accomplishments include working with the Fairfax County Redevelopment and Housing Authority to ensure that it amend its universal design policy to accommodate those with special needs. Ms. Eisenhour is not only president of the board for the Coalition for Housing Opportunities in the Community for Everyone, but she also is director of development for RPJ Housing. She uses her positions to work tirelessly on behalf of disability groups to ensure accessible and affordable housing.

Philip N. Reeves is recognized for his work as a health services advocate, educator and author. After serving in the Air Force, he worked to develop the Leaders of Tomorrow program which works to eliminate discrimination in nursing and long term care methods. Robert B. Worley is a deserving recipient for

Robert B. Worley is a deserving recipient for his dedicated work on behalf of people in need in Fairfax County and the D.C. area. A leader of the United Way's Fairfax County/Falls Church campaign, he has been an indispensible asset to and dedicated fundraiser for local and regional charities. Mr. Worley has also dedicated his time working with organizations like the YMCA and the American Heart Association, raising funds to help those in need.

This year, The Virginia Peters Fair Housing Award and the Human Rights Award are being given to the Communities of Faith United for Housing (CFUH). The CFUH is an advocacy network of faith communities and nonprofit organizations that are committed to increasing the amount of affordable housing in Fairfax County for low-income families and individuals. The CFUH is especially dedicated to providing long term housing to the homeless or

those who are dangerously close to becoming homeless. They have dedicated time to educating the public and elected officials on how to do more to provide low-income housing and have worked with the community and the county to create the Plan to Prevent and End Homelessness. Their work has provided an invaluable service to the community.

Madam Speaker, I ask that my colleagues join me in honoring these individuals and their dedicated service to the community. Their commitment is deserving of not only the prestigious Human Rights Award, but of our respect and deep appreciation.

EARMARK DECLARATION

HON. JOHN R. CARTER

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CARTER. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act. 2010.

Requesting Member: JOHN R. CARTER Bill Number: H.R. 2996

Account: STAG

Requesting entity: City of Temple, TX Address of Requesting Entity: 2 North Main Street, Suite 306, Temple, TX 76501

Description: \$500,000 was secured for a wastewater Interceptor that will enable the construction of approximately 9,000 feet of wastewater main line and 11,500 feet of wastewater interceptor. \$50,000 will be spent on a Preliminary Design, \$155,000 on the Final Design, \$10,000 to Bid & Award construction, \$1.7 million for construction, and \$85,000 for construction administration. The total price for this project is \$2 million. The requesting entity will provide the required funding match. Construction of this piece of utility infrastructure will benefit taxpayers by providing wastewater service to Industrial Park tenants. Wastewater services are critical to the services required for a growing economy.

DEPARTMENT OF HOMELAND SE-CURITY APPROPRIATIONS ACT, 2010

SPEECH OF

HON. JERROLD NADLER

OF NEW YORK

IN THE HOUSE OF REPRESENTATIVES

Wednesday, June 24, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2892) making appropriations for the Department of Homeland Security for the fiscal year ending September 30, 2010, and for other purposes:

Mr. NADLER of New York. Madam Chair, I rise in support of H.R. 2892, the Homeland Security Appropriations Act for fiscal year 2010.

While the bill provides vitally necessary funds to secure our nation's safety, it also contains a troubling provision regarding people who are currently detained at the Guantanamo

Bay facility. This provision would prohibit the use of any funds in the bill to provide any immigration benefits to any Guantanamo detainee. Examples provided by the bill of such benefits include "a visa, admission into the United States, parole into the United States, or classification as a refugee or applicant for asylum." The language does include the proviso that nothing in this provision prohibits detainees from being brought into the United States for prosecution.

Now, I want to prosecute and punish anyone who has sought to harm the United States or is responsible for attacks on the United States and its people. But, we do not know that everyone in Guantanamo fits into this category. There are likely people still imprisoned at Guantanamo today who are there, not because they are a threat, but because our government can not figure out what to do with them. As you know, the Bush Administration already released many people from Guantanamo who were wrongly detained there and our courts have ordered the release of others who apparently were not linked to any terrorist organization and pose no threat to the United States. There were, and possibly still are, innocent people being detained by our government at Guantanamo Bay.

It is shameful for our country to deny a visa to an innocent person who we have determined is no threat to the United States, who the United States wrongly imprisoned for years, who may be prosecuted if returned to his own country, and who the United States may not be able to send to any other country. Frankly, if they are innocent of any crime and pose no threat to the United States, they should be allowed to come to the United States. In addition, I do not see how we can deny them asylum if we determine they have a legitimate fear of persecution if sent anywhere else.

Because the Homeland Security bill provides such critical funding to first responders all over the country, and especially to my city of New York, I can not justify voting against it. Funding for these services is desperately needed.

However, I want to warn my colleagues about the dangers of reflexively adding provisions to every appropriations bill that may end up further harming innocent people who were mistakenly imprisoned by our government. If you want to make a political point that you oppose terrorists, fine. But, you have to allow for the fact that until we know for sure that all of the people remaining at Guantanamo are terrorists, it is not right to punish everyone who is there just to make a political point. We have a moral obligation to do better.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. JAMES R. LANGEVIN

OF RHODE ISLAND

IN THE HOUSE OF REPRESENTATIVES $Wednesday, June\ 24,\ 2009$

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2647) to authorize appropriations for fiscal year 2010 for military activities of the Department of Defense; to prescribe military personnel

strengths for fiscal year 2010, and for other purposes:

Mr. LANGEVIN. Mr. Chair, I rise in support of the fiscal year 2010 National Defense Authorization Act, and I want to thank my good friend Chairman Skelton for his leadership in crafting an excellent bill.

This bill gives not only gives our service men and women the tools they need to keep our nation safe, but it also makes valuable investments in programs and projects that support our military families, increase oversight of our war efforts and further critical non-proliferation efforts. It recognizes the sacrifices made not only by our troops, but by their families as well, providing a 3.4 percent pay raise, expanded TRICARE coverage, and \$1.95 billion for military family housing. This measure will increase oversight and accountability by requiring the President to report on U.S. goals in Afghanistan and Pakistan and our redeployment from Iraq. It also adds \$2.5 billion to programs designed to stop the proliferation of nuclear weapons, one of the most urgent threats the world faces today. Finally, the bill strengthens our nation's missile defense capabilities, by increasing funding for systems vital to protect against real threats while balancing technology development to face the needs of tomorrow.

I am particularly pleased with the steps taken in this bill to ensure that contractor waste, fraud and abuse is brought to an end and that we have an efficient and fair system for meeting critical defense needs. During the Armed Services Committee's mark-up, I offered an amendment, which was adopted by voice vote, to alter the OMB Circular A-76 process for determining which activities are inherently governmental functions and vital to our national defense. My amendment will ensure the A-76 process is fair for our government workforce and provide the Obama Administration a chance to address past failures of the A-76 process.

This legislation also addresses the need to enhance our military's cybersecurity capabilities. Cyberspace is a growing component of the modern battlefield, and we must ensure our forces are prepared for the wars of tomorrow. I applaud the efforts of the Secretary of Defense and the services to meet the growing threat of cyberattacks. I am concerned, however, that individuals with critical cyber skills are not making a career in the uniformed services. We need to do everything in our power to recruit and retain talented and experienced individuals, and that is why I offered an amendment during committee consideration that requires the Secretary of Defense to submit to Congress a report assessing the challenges to retention and professional development of uniformed and civilian cyber operators. I am pleased that this requirement is now included in the bill before us today. This report will help define numbers of personnel, recruitment and retention incentives, policy impediments, and methods to improve interagency and academic outreach to individuals with critical cyber skills.

Finally, I also want to give praise to Secretary Gates, Chairman SKELTON and Chairwoman TAUSCHER for working with our military commanders to shape a budget that protects the U.S. and our allies from real ballistic missile threats. The bill provides \$9.3 billion for missile defense, supporting critical programs that are tested and operational and eliminating

unnecessary and unproven programs that waste taxpayer dollars.

The U.S. Intelligence Community estimates that the most significant ballistic missile threat to U.S. interests, deployed forces, and our allies comes from short- and medium-range ballistic missiles that represent 99% of the total number of ballistic missiles other than those held by the United States, NATO nations, Russia, and China. H.R. 2647 supports the President's request to increase funding by \$900 million for systems that counter this threat, such as the Aegis BMD system and the Terminal High Altitude Area Defense (THAAD) system.

Looking forward, this bill also provides \$1 billion to support the requests of President Obama, Secretary Gates, and the Chairman of the Joint Chiefs of Staff to support the development and operation of 30 Ground-based Midcourse Defense interceptors, designed to guard against future emerging threats. According to senior defense officials, these 30 interceptors are more than what is necessary to deal with any long-range threat from a rogue state in the near and mid-term. This will ensure our nation is able to face the threats of today and tomorrow.

Mr. Chair, this bill admirably balances critical national security needs with realistic budget considerations, and I am proud to support it. Again, I thank Chairman SKELTON for his leadership and urge my colleagues to vote for this important legislation.

A TRIBUTE IN RECOGNITION OF THE 25TH ANNIVERSARY OF SRO HOUSING CORPORATION AND THE GRAND OPENING OF ITS NEW JAMES M. WOOD APART-MENTS

HON. LUCILLE ROYBAL-ALLARD

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Ms. ROYBAL-ALLARD. Madam Speaker, I rise today to recognize SRO Housing Corporation, a nonprofit, community-based organization dedicated to building a vibrant community for homeless and very low-income individuals in the Central City East community of Downtown Los Angeles in the 34th District, an area more commonly known as "Skid Row."

Skid Row is home to one of the largest populations of homeless persons in the nation. To address the needs of this vulnerable population, the late James M. Wood, who served as the Chairman of the Community Redevelopment Agency of the City of Los Angeles, pursued a vision in the late 1970s to include in the revitalization of Downtown Los Angeles a plan to redevelop the Skid Row area and address its rampant homelessness.

In 1977 that plan began to take form as the City of Los Angeles adopted a redevelopment plan for the Downtown Los Angeles Central City East area to preserve and expand the single room occupancy hotels in the area. To acquire and rehabilitate the hotels, the Single Room Occupancy (SRO) Housing Corporation was founded in February 1984 by the Community Redevelopment Agency under the leadership of James Wood.

Through the development of thousands of affordable housing units, the SRO Housing

Corporation provides a full continuum of emergency, transitional, and permanent housing for Skid Row residents. This month's grand opening of the James Woods Apartments, at 408 E. 5th Street and 506 S. San Julian Street, is the most recent shining example of its successful efforts to develop clean, safe and affordable housing units. The project involved converting two decaying parking lots into a 5-story building containing 53 studio apartments with private bathrooms and kitchenettes.

The corporation also offers a wide array of supportive services for its clients, including food services, case management, transportation, support groups and referrals. Every week, SRO Housing serves nearly 4,000 meals in its emergency shelter and senior meal program as well as delivering over 8,000 pounds of food and fresh produce to all permanent-housing sites. This critical service ensures that very low-income individuals, who are attempting to sustain themselves on a fixed income, receive nutritious foods that would otherwise be absent from their diets. In addition, SRO Housing provides its residents with a way to regain basic living skills through classes in cooking, laundry, and money management.

The SRO Housing Corporation also works to build a sense of community belonging for its residents. It manages two public parks—the San Julian Park and Gladys Park—and operates the James Wood Community Center where area residents can socialize and have fun in safe, clean and public areas located in their own neighborhood.

With 25 years of experience, SRO Housing Corporation has a unique insight into the needs of the Skid Row community. More than 40 percent of its diverse and multi-cultural staff is made up of formerly homeless individuals, residents and community members whose history and life experiences are a source of inspiration to others.

Madam Speaker, on the occasion of SRO Housing Corporation's 25th Anniversary and the Grand Opening of its new James M. Wood Apartments, I join today with my congressional colleagues in recognizing all of the many dedicated people who make this fine organization the beacon of hope that it is today. I especially commend Anita Nelson who works day in and day out to keep James Wood's memory and mission alive as the corporation's Chief Executive Officer. I also pay tribute to the SRO Housing Corporation's community partners, supporters, invaluable volunteers, its entire staff and, most of all, the residents of the Skid Row community. Thousands of lives have been transformed and positively impacted through the wonderful work of SRO Housing Corporation and I wish everyone involved with this fine organization many more years of continued success.

EARMARK DECLARATION

HON. PETER J. ROSKAM

OF ILLINOIS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. ROSKAM. Madam Speaker, pursuant to Republican standards on disclosure for Member project requests, I am submitting the following information regarding a project I support for inclusion in H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act.

Congressman PETER J. ROSKAM: H.R. 2996. Environmental Protection Agency, STAG Water and Wastewater Infrastructure Project account for the Tubeway Drive Storm Water Lift Station Rehabilitation Project in Carol Stream, Illinois. The entity to receive funding for this project is the Village of Carol Stream, 500 North Gary Avenue, Carol Stream, IL 60188. It is my understanding that the funding would be used to rehabilitate and replace a 35-year-old storm water lift station at the end of its useful life. The Tubeway Drive Storm Water Lift Station is showing signs of corrosion, and is in need of desperate repair to alleviate flooding in the village. Under this rehabilitation project, the lift station will be totally replaced with new more efficient pumps, valving, backup systems and structures. Replacing the station in a timely manner will ensure storm water flows are effectively managed, preventing flood damage losses. Carol Stream has demonstrated a good-faith cost share in the project, providing a 45% commitment of matching funds. Severe flooding has plagued the village in the last year. Rains in September 2008 submerged 50 homes and damaged 400. This was followed in December by more rain, melting snow, and another round of flooding. Even last week the Daily Herald reported on how Carol Stream has had to deal with "severe flooding in several areas." This timely funding will bring much-needed relief to my constituents.

EARMARK DECLARATION

HON. JEFF MILLER

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. MILLER of Florida. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of the Fiscal Year 2010 National Defense Authorization bill.

Requesting Member: Congressman JEFF

Project Name: AFSOC Injury Prevention and Human Performance Initiative

Account: RDAF

Legal Name of Requesting Entity: University of Pittsburgh School of Health and Rehabilitative Services/Andrews Institute

Address of Requesting Entity: 1040 Gulf Breeze Parkway Gulf Breeze, FL 32561

Description of Request: \$1,000,000—AFSOC Injury Prevention and Human Performance Initiative, University of Pittsburgh School of Health and Rehabilitative Services/Andrews Institute. I requested these funds for an injury prevention and performance enhancement initiative that will achieve a critical doctrinal shift in human performance strategies in Air Force Special Operations. Phase 1 will include task and demand analyses to identify Air Force Special Operator-specific tasks during which injuries occur, mechanisms of injury, and the physiological requirements of training.

The entity to receive funding for this project is the University of Pittsburgh School of Health and the Andrews Institute located at 1040 Gulf Breeze Parkway Gulf Breeze, FL 32561. I certify that neither I nor my spouse has any financial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

Requesting Member: Congressman JEFF MILLER

Project Name: Anti-Materiel Explosive Round for Javelin Block II

Account: RDA

Legal Name of Requesting Entity: General Dynamics Ordinance and Tactical Systems, Niceville Operations

Address of Requesting Entity: 115 Hart Street Niceville, FL 32578

Description of Request: \$3,000,000—Anti-Materiel Explosive Round for Javelin Block II, General Dynamics. I requested these funds to provide the warfighter with a significant improvement in lethality against Military Operations in Urban Terrain (MOUT) structures. The funding will allow for a qualification program in FY 2010 and early fielding in FY 2012.

The entity to receive funding for this project is General Dynamics located at 115 Hart Street Niceville, FL 32578. I certify that neither I nor my spouse has any financial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

Requesting Member: Congressman JEFF

Project Name: Coordinated Operation of Unmanned Vehicles for Littoral Defense

Account: RDN

Legal Name of Requesting Entity: Florida Institute for Human and Machine Cognition

Address of Requesting Entity: 40 South Alcaniz Street, Pensacola, FL 32502

Description of Request: \$2,000,000—Co-ordinated Operation of Unmanned Vehicles for Littoral Defense, General Dynamics. I requested these funds to perform research to: develop a fully-functioning prototype of biologically inspired robotic concepts uniquely suited to the littoral environment; to develop and evaluate policies and metrics for optimal resource utilization and for effective configuration and control of hybrid teams of people and heterogeneous unmanned systems and to assure effective tasking of physically distributed humans and heterogeneous configurations of unmanned platforms to best support littoral operations.

The entity to receive funding for this project is the Florida Institute for Human and Machine Cognition located at 40 South Alcaniz Street, Pensacola, FL 32502. I certify that neither I nor my spouse has any financial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

Requesting Member: Congressman JEFF MILLER

Project Name: Eglin Air Force Base Range Operations Control Center (ROCC)

Account: RDAF

Legal Name of Requesting Entity: Cubic Corporation

Address of Requesting Entity: 1225 South Clark Street, Suite 702 Arlington, VA 22202

Description of Request: \$3,000,000—Eglin Air Force Base Range Operations Control Center (ROCC), Cubic Corporation. I requested these funds to address the increased testing and evaluation at Eglin AFB, the 46th Test Wing Super ROCC initiative is a phased effort involving development, procurement and military construction (MILCON) funding to meet the future need in the 2015-2020 timeframe. This project provides more effective control to better optimize range scheduling and increases flexibility in meeting the Eglin AFB test and training missions. By knowing the locations of all entities on the range, the Super ROCC will have great flexibility in reassigning missions to ground and air space previously not being used.

The entity to receive funding for this project is Cubic Corporation located at 1225 South Clark Street, Suite 702 Arlington, VA 22202. I certify that neither I nor my spouse has any fi-

nancial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

Requesting Member: Congressman JEFF

Project Name: Flight Test Operations Facility (413 FLTS)

Account: MCAF

Legal Name of Requesting Entity: Hurlburt Air Force Base

Address of Requesting Entity: Hurlburt Air Force Base

Description of Request: \$9,400,000—Flight Test Operations Facility (413 FLTS), Hurlburt Air Force Base. I requested these funds to a construct a facility to conduct developmental and qualification testing of aircraft. A modern facility is necessary to ensure mission success, minimize acquisition costs and fielding delays. Functional areas include administration, operations and special purpose areas including open storage area with SIPRNET, workshop/maintenance area with compressed air, a hoist system and an electrical system capable of providing multi-phase power and covered outside storage.

The entity to receive funding for this project is Hurlburt Air Force Base located at Hurlburt AFB, Florida. I certify that neither I nor my spouse has any financial interest in this project

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

Requesting Member: Congressman JEFF

Project Name: Gulf Range Mobile Instrumentation Capability

Account: RDDW

Legal Name of Requesting Entity: Prologic Address of Requesting Entity: 9400 Innovation Drive Manassas, VA 20110

Description of Request: \$3,000,000—Gulf Range Mobile Instrumentation Capability, Prologic. I requested these funds for Gulf Range Mobile Instrumentation Capability for the 46th Range Group (46 RANG. The 46th Range Group (46 RANG) has a need for a capability for remote test, collection, storage and relay of various data types. This capability can be accomplished with a Gulf Range Mobile Instrumentation Capability (GR—MIC). The GR—MIC is needed to support test events on the Eglin AFB range which occur over large geographic areas (land and sea based).

The entity to receive funding for this project is Prologic located at 9400 Innovation Drive Manassas, VA 20110. I certify that neither I nor my spouse has any financial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

Requesting Member: Congressman JEFF

Project Name: Intelligence Broadcast Receiver (IBR) for AFSOC MC 130 Aircraft

Account: PDW

Legal Name of Requesting Entity: DRS Technologies

Address of Requesting Entity: 651 Anchors St., Fort Walton Beach, FL 32548

Description of Request: \$2,500,000-Intelligence Broadcast Receiver (IBR) for AFSOC MC-130 Aircraft, DRS Technologies. I requested these funds to procure equipment that provides Air Force Special Operations Command (AFSOC) MC-130 Combat Shadow aircraft with vastly improved situational awareness in high threat arenas. These aircraft provide clandestine or low visibility, low level missions into denied areas to provide support to small SOF ground teams as well as to provide air refueling for specialized infiltration aircraft. This equipment provides real time information to include; immediate intelligence, Blue Force tracking (friendly units), and survivor information, greatly improving mission success and survivability.

The entity to receive funding for this project is DRS Technologies located at 651 Anchors St., Fort Walton Beach, FL 32548. I certify that neither I nor my spouse has any financial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

Requesting Member: Congressman JEFF MILLER

Project Name: Joint Gulf Complex Test and Training

Account: RDDW

Legal Name of Requesting Entity: Boeing Address of Requesting Entity: 634 Anchors St NW Fort Walton Beach, FL 32548

Description of Request: \$3,000,000—Joint Gulf Complex Test and Training, Boeing. I requested these funds to provide critical training

and mission rehearsal for Iraq and Afghanistan deployments. The range must accommodate requirements for joint testing of weapons systems that are revolutionary in nature and being developed for the War on Terrorism. The Joint Gulf Range must accommodate critical joint training requirements specifically in support of U.S. Air Force Special Operations Command and U.S. Special Operations Command.

The entity to receive funding for this project is Boeing located at 634 Anchors St NW Fort Walton Beach, FL 32548. I certify that neither I nor my spouse has any financial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable

Requesting Member: Congressman JEFF

Project Name: LAIRCM for AFSOC MC-130 Account: PDW

Legal Name of Requesting Entity: L-3 Crestview

Address of Requesting Entity: 5486 Fairchild Road Crestview, FL 32539

Description of Request: \$4,000,000—LAIRCM for AFSOC MC-130, L-3. I requested these funds for enhanced protection of AFSOC's C-130 aircraft operating in combat conditions where man-portable infrared missiles are present. Current countermeasures, during critical phases of their mission, have marginal effectiveness. This is needed to protect lives and assets in current and future missions in the Global War on Terror.

The entity to receive funding for this project is L-3 located at 5486 Fairchild Road Crestview, FL 32539. I certify that neither I nor my spouse has any financial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

Requesting Member: Congressman JEFF MILLER

Project Name: Mobile Learning Cultural Training for Military Personnel

Account: OMN

Legal Name of Requesting Entity: University of West Florida

Address of Requesting Entity: 11000 University Parkway Pensacola, FL 32514

Description of Request: \$1,500,000—Mobile Learning Cultural Training for Military Personnel, University of West Florida. I requested these funds to provide regional cultural awareness training through multiple mobile devices and through the Navy Knowledge Online (NKO) portal. Cultural awareness and language skills are critical for operations in Iraq and Afghanistan. This project builds on previous projects by the University of West Florida on mobile learning instructional delivery and on an Arabic Language and Cultural Awareness for-credit certificate program.

The entity to receive funding for this project is the University of West Florida located at

11000 University Parkway Pensacola, FL 32514. I certify that neither I nor my spouse has any financial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

Requesting Member: Congressman JEFF MILLER

Project Name: Moving Target Strike Account: RDAF

Legal Name of Requesting Entity: General Atomics/Alpha Data Corporation

Address of Requesting Entity: 1326 Lewis Turner Blvd Fort Walton Beach, FL 32547

Description of Request: \$3,000,000—Moving Target Strike, General Atomics/Alpha Data Corporation. I requested these funds for GPS-guided weapons systems. The project will demonstrate the ability to strike a time-critical moving target with a low cost GPS guided weapon using coordinates derived and communicated from a single platform. GPS guided weapons are replacing higher cost laser guided and seeker weapons throughout DoD. The ability to use the GPS guided weapons against moving targets furthers this trend and reduces overall costs of weapon systems.

The entity to receive funding for this project is General Atomics/Alpha Data Corporation located at 1326 Lewis Turner Blvd Fort Walton Beach, FL 32547. I certify that neither I nor my spouse has any financial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

Requesting Member: Congressman JEFF MILLER

Project Name: Virtual Perimeter Monitoring System (VPMS)

Account: RDDW

Legal Name of Requesting Entity: DRS Technologies

Address of Requesting Entity: 651 Anchors St., Fort Walton Beach, FL 32548

Description of Request: \$2,000,000—Virtual Perimeter Monitoring System (VPMS), DRS Technologies. I requested these funds to provide a perimeter monitoring system of remote sensors for detecting and alerting security personnel of intrusions in defined areas of interest at critical facilities. Virtual Perimeter Monitoring System (VPMS) provides continuous and persistent surveillance of areas of interest to include near real time monitoring of air fields, ports, depots and other critical infrastructures.

The entity to receive funding for this project is DRS Technologies located at 651 Anchors St., Fort Walton Beach, FL 32548. I certify that neither I nor my spouse has any financial interest in this project.

Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all

statutory requirements for matching funds where applicable.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. PHIL GINGREY

OF GEORGIA

IN THE HOUSE OF REPRESENTATIVES
Wednesday, June 24, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2647) to authorize appropriations for fiscal year 2010 for military activities of the Department of Defense, to prescribe military personnel strengths for fiscal year 2010, and for other purposes:

Mr. GINGREY of Georgia. Mr. Chair, as we consider H.R. 2647, the National Defense Authorization Act for Fiscal Year 2010, I would like to say a special thanks to Chairman SKELTON and Ranking Member MCKEON—as well as to subcommittee Chairman ABERCROMBIE and Ranking Member BARTLETT—for their tireless efforts in support of our soldiers, sailors, airmen, and marines who are bravely defending us at home and abroad.

While not a perfect bill, this legislation covers a wide scope of issues that are vitally important to our Armed Services, both active and reserve component, and it clearly addresses the most pressing needs of our troops in a very trying time for America. A 3.4% pay raise for all members of the Armed Forces will further reduce the military-civilian pay disparity. I am very pleased with the work the Committee has done this year to authorize \$368 million for the advance procurement of long-lead supplies needed to build 12 additional F-22's in 2011. The F-22 is the world's most capable fighter, and these funds will go a long way towards providing stability for our forces and ensuring that America maintains air dominance for the foreseeable future.

While I applaud the work of the Committee in addressing pressing readiness issues, I am however concerned about the deep cuts to missile defense. A viable missile defense system is critical to deterring and countering emerging threats to our national security—especially as Iran and North Korea develop their nuclear capabilities. I look forward to working with Chairman SKELTON, Ranking Member MCKEON, and the rest of the Committee as this bill moves forward to address these program needs.

While there is much to be proud of in this bill, I am disappointed that the Rules Committee failed to make any of my four amendments in order. These were commonsense amendments, Mr. Chair, that would make the Department of Defense (DoD) more effective in carrying out its mission.

The first amendment I offered to this bill would have ensured that no detainees at the Guantanamo Bay detention facility are transported to the United States. The American people have spoken on this issue with 55% of them opposed to allowing terrorists to be transported to American soil. Further, a June 12, 2009 letter from the Director of the Federal Bureau of Prisons to my colleague, Trent Franks, stated that "there is insufficient bed space in any high-security Federal prison to

confine these individuals. In addition, there are currently no beds available in our Administrative Maximum United States Penitentiary in Florence, Colorado, to confine any more Federal inmates, let alone any of the Guantanamo Bay detainees. If called upon to confine any of these detainees, we would most likely confine them in ADX Florence and in one or more high-security penitentiaries. Depending on the numbers, this might require us to transfer a sufficient number of inmates to other penitentiaries in order to create the necessary bed space. Such transfers would impose significant additional challenges on our agency." Clearly the transfer of these detainees to anywhere in America is dangerous and must be prohibited.

My second amendment would express the sense of Congress that active military personnel who live in or are stationed in Washington, DC, would be exempt from the District's firearms restrictions. On June 26, 2008, the Supreme Court of the United States in the case. District of Columbia v. Heller, held that the Second Amendment protects an individual's right to possess a firearm for traditionally lawful purposes, and thus, ruled that the District of Columbia's handgun ban and requirements that rifles and shotguns in the home be kept unloaded and disassembled or outfitted with a trigger lock to be unconstitutional. However, the D.C. City Council has circumvented the Supreme Court ruling by enacting the Firearms Control Emergency Amendment Act of 2008, making a waiver necessary to ensure that our military men and women-of which there are 40,000 in Washington and who have been trained in firearm use-are permitted to safely carry a firearm in the District.

A further amendment would prohibit DoD civilian employees from using official paid work time for union activities, ensuring that American taxpayers are not subsidizing labor organizations. DoD was one of the largest abusers of using "official time" for union activity. Its total number of official time hours in FY 2008 was 331,099 (a 5.1% increase from FY 2007). OPM estimated the official time wage cost for the DoD was \$12,141,699 for FY 2008, which is an \$855,694 increase from FY 2007. This is just one example of union activity being subsidized by taxpayer dollars on official time.

My final amendment would have provided the Secretary of Defense with a waiver from section 526 of the Energy Independence and Security Act of 2007 regarding the procurement of alternative fuels if the Secretary feels that a waiver is appropriate to enhance the readiness of the Armed Forces. Section 526 prohibits all federal agencies from contracting for alternative fuels that emit higher levels of greenhouse gas emissions than "conventional petroleum sources." DoD accounts for over 80% of all federal government fuel usage, and its annual fuel expense more than doubled between 2003 and 2007-from \$5.2 billion to \$12.6 billion. The Secretary of Defense needs a waiver from section 526 so that DoD's fuel costs can be kept low.

Mr. Chair, there is much to be proud of in this bill. I again commend Chairman SKELTON and Ranking Member McKEON for their efforts to keep this bill focused on the needs of the war-fighter, a fact that I hope is not lost as we progress through the amendment process.

CELEBRATING FISH AND LOAVES
COMMUNITY PANTRY'S MILLIONTH POUND SERVED

HON. JOHN D. DINGELL

OF MICHIGAN

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. DINGELL. Madam Speaker, I rise today to acknowledge, honor, and celebrate the Fish and Loaves Community Pantry for serving its one millionth pound of food to people in need from across the Downriver area. Since its opening in 2007, Fish and Loaves continues to collaborate with churches, food banks, and hundreds of volunteers to provide cost-free, quality groceries to thousands of families and individuals.

Tough economic times have made acquiring even basic necessities difficult for many residents of Southeastern Michigan. Many of the people that Fish and Loaves serve are below the poverty line, lack medical coverage, and struggle to pay for essential services.

The organizers of the Fish and Loaves Community Pantry recognized this and, in response, churches and volunteers joined together in remarkable collaboration to construct a special kind of food pantry. The facility, located in Taylor, is arranged as a small grocery store in which individuals may select the items they need most, which include quality products like fresh produce, dairy products, frozen meat, and perishable items. Of course, everything is still provided at no cost to the client. The pantry serves the residents of Taylor, Romulus, Allen Park, Southgate, Dearborn Heights, and Brownstown.

Fish and Loaves provides assistance to those in need with both efficiency and dignity by providing a wide variety of foods and household products from which to choose. The hard work and dedication of the Board and volunteers is the source of its great success and support it gives to the thousands of individuals and families it helps to feed.

Madam Speaker, I ask that all of my colleagues join me in honoring the Fish and Loaves Community Food Pantry on its millionth pound of food served. It is an exemplary organization that continues to be an invaluable member of the Southeastern Michigan community and for which I, and thousands others, are truly grateful.

EARMARK DECLARATION

HON. BRIAN P. BILBRAY

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. BILBRAY. Madam Speaker, I submit the following:

Requesting Member: Congressman BRIAN BII BRAY

Bill Number: H.R. 2996—Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010

Account: Environmental Protection Agency, State Tribal Assistance Grants

Legal Name of Requesting Entity: City of Carlsbad, CA

Address: 1200 Carlsbad Village Drive, Carlsbad, CA 92008

Description of Request: I received an earmark of \$500,000 for the Vista-Carlsbad Inter-

ceptor project (VC4), consisting of wastewater pipeline improvements project, including the construction of a new 24-inch HDPE forcemain, the trenchless rehabilitation (lining) of the existing 24-inch forcemain and refurbishment of pipeline appurtenances. VC4 is one of a number of joint wastewater projects between the cities of Vista and Carlsbad. VC4 is one of two pipelines that convey all of the wastewater from the City of Vista to the Encina regional wastewater treatment facility. In April 2007, the 24-inch ductile iron pipeline ruptured creating a significant sewage spill into the Buena Vista Lagoon. The 2,400 foot long 24-inch diameter pipeline receives flow from the cities of Carlsbad, Oceanside and Vista. This is the only year of funding needed to complete this aspect of the project. The cities of Carlsbad and Vista will provide the remaining funds required for the project directly.

EARMARK DECLARATION

HON. W. TODD AKIN

OF MISSOURI

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. AKIN. Madam Speaker, in accordance with House Republican Conference standards, and Clause 9 of rule XXI, I submit the following member requests regarding H.R. 2647, the National Defense Authorization Act of 2010.

Project: Air Filtrations Systems for Helicopters

Account: Department of Defense, Army, Aircraft Modifications

Legal Name of Requesting Entity: Aerospace Filtration Systems, Inc.

Address of Requesting Entity: 4 Research Park Dr, Suite 200, St Charles, MO, USA

Description of Request: To provide \$2,000,000 to install barrier filtration systems on National Guard aircraft. This request would allow the National Guard to obtain dramatic savings by reducing engine replacements and thus maintenance, keeping overall engine performance from being reduced due to erosion and Foreign Object damage (FOD), and increasing readiness rates of the ARNG fleet. The earmark will address a portion of the ARNG fleet to include: AH-64A APU Barrier Filter-32 Aircraft; AH-64D APU Barrier Filter-48 Aircraft; CH-47 APU Barrier Filter-80 Aircraft: OH-58A/C Engine Barrier Filter-50 Aircraft. AFS Barrier Filtration Systems capture 99% of the dirt and debris that would otherwise enter the engine or APU and cause a significant loss of performance. This prevents engines/APU's from being removed from the aircraft for costly maintenance or overhaul. Engine overhaul costs could cost as much as \$300,000 on one engine. By extending the life of the engine/APU up to 11 times, the savings from one installation kit could be as high as \$6.6M on one AH-64 helicopter alone. AFS barrier filters in use by the U.S. Army in the deserts of Iraq and Afghanistan have been proven extremely effective. These kits have allowed engines to reach TBO and have been a major part of unprecedented readiness rates for the aircraft fleets.

Project: Hyperspectral Imaging for Improved Force Protection (HYPER–IFP)

Account: Department of Defense, Army, RDT&E (CERDEC, NVESD, Special Projects)

Legal Name of Requesting Entity: Clean Earth Technologies, LLC.

Address of Requesting Entity: 13378 Lakefront Drive, Earth City, MO, USA

Description of Request: To provide \$5,400,000 for the Hyper-IFP (Hyper spectral Sensor for Improved Force Protection) Program. The introduction of a Hyper-IFP in FY08 is allowing the detection and recognition of humans (with a near zero false alarm rate) and providing indication of other certain physiological triggers that can indicate that a person is under extreme stress such as contemplating "bad" behavior. To date successful development, test and evaluation has been done in the lab, though these systems have not been fully optimized for theatre operation or for costs. The continued funding of Hyper-IFP will operationalize and integrate the knowledge gain in the lab and apply it in a true-fielded application at an affordable cost. The Hyper-IFP system will also be environmentally hardened to allow field deployment and allow integration w/other FP sensors in the last quarter of 2009. Hyper-IFP is focused on the missions of Perimeter Security, Suicide Bomb Detection and Urban Route Recon. Utility will be demonstrated through an evaluation in both the Southwest border and contingency mission in Southwest Asia. This effort will require leveraging the current Force Protection sensor suite designs for the missions cites to maintain interoperability. In the end, this request focuses on both achieving data verification, and the delivery of sufficient hardware to validate the Technical Data package for re-procurement as well as demonstrate the system's ability to deploy to DoD/DHS users for the missions described. The Night Vision Electronic Sensors Directorate, Ft. Belvoir, Virginia, is very supportive of this project.

Project: Backpack Medical Oxygen System (BMOS)

Account: Department of Defense, Air Force, RDT&E

Legal Name of Requesting Entity: Essex Cryogenics of Missouri Inc.

Address of Requesting Entity: 8007 Chivvis Drive, St. Louis, MO 63123–2395

Description of Request: To provide \$2,900,000 for improving Air Force oxygen generation technology for emergency field medical rescues. With modification, the Backpack Medical Oxygen System (BMOS) is the system that satisfies the USAF Requirement for a small deployable oxygen generator system. This spiral development program for the BMOS system will significantly decrease the time and funds required to field critical capabilities needed today by our warfighters. The U.S. Air Force requirement for oxygen is a minimum of 93% pure oxygen at 6 liters per minute for critically injured personnel and the BMOS satisfies that requirement.

Project: High Power Electrolytic Super-Capacitors Based on Conducting Polymers

Account: Department of Defense, Army, RDT&E, Weapons and Munitions Technology Legal Name of Requesting Entity: Crosslink,

Address of Requesting Entity: 950 Bolger Court, St. Louis, MO 63026

Description of Request: To provide \$9,000,000 for the development of State of the art electrolytic supercapacitors for the purpose of supplying Non-Line-of-Sight (NLOS) weapons, which are dubbed the "Objective Force Weapons," with quick discharging/recharging

energy storage systems that are capable of high power pulses, on the order of megawatts, to be delivered in the hundreds of microseconds to one millisecond time range to make these weapons successful. Approximately 21% of the funds will be used for salaries for four (4) employees, 43% for equipment and materials, and 36% for indirect costs associated with completing the project. This project has received past funding of \$2.6 million in FY'07, \$2.4 million in FY'08, and \$800,000 in FY'09. Crosslink, University of Missouri-St. Louis, University of Missouri-Rolla and University of Florida have collaborated to develop new polyaniline and PXDOT (poly(3,4-Alkylenedioxythiophene—Conjugated electroactive polymers). The results of this collaboration will be the development of devices capable of power delivery rates significantly faster than standard supercapacitors.

Project: Aircrew Body Armor and Load Carriage Vest System

Äccount: Other Procurement—U.S. Air Force

Legal Name of Requesting Entity: Eagle Industries

Address of Requesting Entity: 1000 Biltmore Drive, Fenton, MO 63026

Description of Request: To \$9,000,000 to issue the Aircrew Body Armor Load Carriage Vest System, an integrated body armor vest system, to aircrew personnel. The system provides fire retardancy and ballistics protection from a wide array of threats including small arms fire, fragmenting shrapnel and spall, while decreasing the heat stress and weight burdens faced by airmen. Currently issued aircrew flight equipment survival vests are not body armor-compatible due to weight, heat, and survivability concerns. Current issue is not fire retardant and fails to meet the present needs of the U.S. Air Force. Of the \$9 million, approximately 25% is for materials; 25% is for labor; and 50% is for armor and armor integration.

This request is consistent with the intended and authorized purpose of the U.S. Air Force—Other Procurement account. If funded in full, this is a one-time funding request with the goal of the Air Force using internally budgeted funding to continue fielding the system to aircrew personnel.

Project: Mission Equipment Technology Implementation (METI)

Account: Department of Defense, Army, RDT&F

Legal Name of Requesting Entity: QinetiQ North America (Formerly Westar Aerospace and Defense Group)

Address of Requesting Entity: 36 Research Park Ct., St. Charles, MO 63304, USA

Description of Request: To provide \$5,300,000 for funding to complete the METI plan initiated by the Aeromechanics division 3 years ago. This funding will complete the development of a robust enterprise level data repository that supports the Aviation Engineering Directorate's (AED) airworthiness release mission to rapidly develop and deploy mission equipment tools. The AED will have the capability to data mine and analyze complex data to determine trend information to reduce high cycle times between flight tests and airworthiness releases.

Project: Bonded Cellular Aluminum Tail Rotor Blades

Account: Department of Defense, Army, RDT&E

Legal Name of Requesting Entity: Kemco Aerospace Manufacturing

Address of Requesting Entity: 3616 Scarlet Oak Blvd., St. Louis, MO 63122

Description of Request: To \$3,600,000 for bonded cellular aluminum helicopter tail rotor blades that are well suited for military helicopter structures which operate in demanding environmental conditions and must be battle damage tolerant. Unlike traditional aluminum honevcomb, the vented/drained cellular bonded structure redistributes load paths around damaged areas and has eliminated corrosion problems associated with traditional aluminum honeycomb structures; dramatically improving life cycle costs. This technology offers significant advantages compared with current structural technologies that were designed over 30 years ago, including 82% reduced parts count, elimination of skin delamination, significantly enhanced battle damage tolerance and field reparability benefits. The tongue and groove joint structures reduce the amount of touch labor required as well as tooling costs. This has the potential to reduce procurement costs by 20-30%.

Project: Adaptive-Defense HIPPIE (Highspeed Internet Protocol Packet Inspection Engine) on a Chip.

Account: Department of Defense, Army, RDT&E

Legal Name of Requesting Entity TechGuard Security, LLC

Address of Requesting Entity: 743 Spirit 40 Park Drive, Chesterfield, MO 63005

Description of Request: Provide \$6.000.000 to enhance the Army's Cyber Security. This project puts the rapid and power-conserving High-speed Internet Protocol Packet Inspection Engine's (HIPPIE) security capability on a silicon chip. This funding will allow for development of a Nano-power supply and a nanomemory capability. It will enhance the coalition warrior and the US Warfighter's communication security and access control through discreet deployment with secure remote-controlled chip-level destruction in the event a device is compromised. This enhanced capability at the chip-level allows for deployment directly into the hands of the warfighter engaged in traditional and irregular warfare.

Project: JSOW-ER

Account: Department of Defense, Navy, RDT&E

Legal Name of Requesting Entity: LaBarge

Address of Requesting Entity: 9900 Clayton Road, St. Louis, MO 63124

Description of Request: Provide \$6,500,000 for Joint Stand Off Weapon (JSOW) a GPSguided air-to-ground weapon designed to attack a variety of targets in day, night and adverse weather conditions. The 70+ mile range of JSOW allows launch aircraft to stand off beyond the range of most Surface-to-Air missiles. There is a need for a small number of weapons with greater stand off. Currently the Navy fills this requirement with SLAM-ER, Harpoon and Tomahawk. The Navy completed its relatively small buy of fewer than 500 SLAM-ERs in 2004. A new variant of JSOW (JSOW-ER Block IV) would have a range and lethal capability equal to or greater than SLAM-ER and would satisfy the warfighter's need at less than half the cost of SLAM-ER. An existing engine from the Miniature Air-Launched Decoy program will be used to extend the range of JSOW-ER to more than four times of the current glide version.

RECOGNIZING GABRIEL PEREZ

HON. DALE E. KILDEE

OF MICHIGAN

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. KILDEE. Madam Speaker, Gabriel Perez, the Director of the Saginaw Michigan Aleda E. Lutz Veterans Affairs Medical Center, has been appointed as the new Health System Administrator/Medical Center Director of the Veterans Affairs HealthCare System in Phoenix, Arizona. He will start his new position on July 19, 2009.

Mr. Perez graduated from Loyola University in 1968, attended the University of California at Los Angeles Law School and obtained his Master's Degree in Public and Health Care Administration from the University of Southern California. Prior to his work with the Department of Veterans Affairs, Mr. Perez spent several years working for the Los Angeles County Department of Health Services and teaching courses at the university level in medical legal law and personnel.

Prior to becoming the Director of the Lutz Veterans Affairs Medical Center in 2000, Mr. Perez was the Chief Operating Officer and Acting Director of the Honolulu VA Medical and Regional Office Center. Since assuming his duties in Saginaw, he led the facility to improve its overall performance and move to a top ten spot among Department of Veterans Affairs facilities nationwide, ranking 3rd in the nation for its hospital grouping. From October 2005 to August 2006 he also served as Acting Director of the Veterans Affairs Ann Arbor Healthcare System.

Patient care and safety has been his primary concern and his practices have earned him the respect of his peers. The delivery efficiencies he developed have been adopted nationwide and have won awards for improving VeteranCare delivery. He is a member of several professional organizations and community groups. His work with veterans, Hispanics, workers and children has been recognized numerous times and he is a regular participant in efforts to promote veterans and Hispanics at the local and national levels.

Madam Speaker, Gabriel Perez has brought insight and innovation to the day-to-day operations of the Lutz Veterans Affairs Medical Center over the past 9 years. He has worked to enhance the health and well-being of veterans, improve service to veterans, and expand accessibility for all veterans. I congratulate him on his new position and wish him the best as he enters this new phase of his life.

EARMARK DECLARATION

HON. DONALD A. MANZULLO

OF ILLINOIS

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. MANZULLO. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding the earmark I secured as part of H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010.

My request, totaling \$280,000, will come from the Surveys, Investigations & Research

account at the U.S. Geological Survey (USGS) for the Groundwater and Stormwater Protection program in McHenry County, Illinois. The funding would be used to accelerate work on studies associated with the implementation of McHenry County's Groundwater Protection Program. McHenry County is continuing to experience rapid population growth and there is a critical need to plan for the future. The county's program is working to address the protection of groundwater resources, stormwater drainage and detention, stream and wetland protection, and sustainable growth all into a single program. Ongoing and future development poses serious challenges because of the reduction of the land's ability to absorb precipitation and the continuing pressure to develop flood prone areas. The McHenry County government has already invested over \$615,000 of local resources in studying local groundwater resources and stormwater investigations. The local USGS entity to receive funding for this request is the Illinois Water Science Center at 1201 West University Avenue, Suite 100, in Urbana, Illinois 61801, who will work in partnership with McHenry County to implement this initiative.

Madam Speaker, I want to take this opportunity to thank the Chairman of the House Appropriations Committee, Representative DAVID OBEY, and the Ranking Minority Member, Representative JERRY LEWIS, and the Chairman of the Interior and Environment Appropriations Subcommittee, Representative NORM DICKS, and the Ranking Minority Member, Representative MIKE SIMPSON, for working with me in a bipartisan manner to include this critical request in this spending bill.

EARMARK DECLARATION

HON. CHARLES W. DENT

OF PENNSYLVANIA

IN THE HOUSE OF REPRESENTATIVES Thursday, June~25,~2009

Mr. DENT. Madam Speaker, pursuant to the House Republican Leadership standards on earmarks, I am submitting the following information regarding projects that are listed in H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010:

Bill Number: H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010, Account: National Park Service, Save America's Treasures, Title: Saylor Cement Kilns Historic Preservation, Legal Name of Requesting Entity: County of Lehigh, Address of Requesting Entity: 17 South 7th Street, Allentown, PA 18101, Description of Request: This funding will be used to stabilize and restore the historic Coplay Company Cement Kilns, known locally as the Saylor Cement Kilns, a unique industrial feature built between 1892 and 1893 that is key to the Delaware & Lehigh National Heritage Corridor's industrial story. The Saylor Cement Kilns are in a state of serious decay, prompting concerns about public safety and liability, as well as the potential loss of a significant historical landmark in the Lehigh Valley region. Rehabilitating the kilns will have a positive impact on local economic development through increased heritage tourism. Once restored, the site will encourage use for historical education and community events.

Bill Number: H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010, Account: EPA, STAG Water and Wastewater Infrastructure Project, Title: Vera Cruz Wastewater Collection System, Legal Name of Requesting Entity: Lehigh County Authority, Address of Requesting Entity: 1053 Spruce Street, P.O. Box 3348, Allentown, PA 18106, Description of Request: This funding will be used to build a wastewater collection system for the Vera Cruz area of Upper Milford Township. On-lot sewer disposal systems in the area are failing, causing environmental damage and public health concerns. The project will provide central sewer service to approximately 284 properties in the village of Vera Cruz and the surrounding area. Funds will be used for construction, engineering services and purchase of capacity in downstream transportation and treatment fa-

EARMARK DECLARATION

HON. RODNEY P. FRELINGHUYSEN

OF NEW JERSEY

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. FRELINGHUYSEN. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of the Fiscal Year 2010 Interior, Environment and Related Agencies Appropriations Act.

Bill: H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010

Account: STAG Water and Wastewater Infrastructure

Legal Name and Address of Requesting Entity: Borough of Hopatcong located at 111 River Styx Road, Hopatcong, New Jersey 07843.

Description of Request: H.R. 2996 includes \$500,000 for the Borough of Hopatcong's Drinking Water Disinfection Improvement project to provide safe drinking water to the residents of the Borough. The funds will be used to install large diameter pipes at public community supply wells to improve the disinfection of the raw water before being distributed.

Bill: H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010

Account: Land Acquisition (Fish and Wildlife Service)

Legal Name and Address of Requesting Entity: The entity to receive funding for this project is the Great Swamp National Wildlife Refuge located at 241 Pleasant Plains Road, Basking Ridge, New Jersey 07920.

Description of Request: H.R. 2996 includes \$750,000 for the Great Swamp National Wild-life Refuge, a component of the Fish and Wild-life Service. The Great Swamp Refuge is located in Morris County, New Jersey, about 26 miles west of Manhattan's Times Square. The refuge was established by an act of Congress on November 3, 1960. The protection of this gem of wilderness in the heart of dense suburban development is one of the success stories of our National Wilderness Preservation System. The funding would be used to acquire an 18.31 acre parcel of land, known as the Great

Brook Property, adjacent to the Great Swamp National Wildlife Refuge, which provides critical habitat for numerous rare species.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. LYNN C. WOOLSEY

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Wednesday, June 24, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2647) to authorize appropriations for fiscal year 2010 for military activities of the Department of Defense, to prescribe military personnel strengths for fiscal year 2010, and for other purposes:

Ms. WOOLSEY. Mr. Chair, while I cannot support H.R. 2647, this legislation does contain important provisions regarding family and medical leave for military families.

Last session, Congress passed—also in a Defense Authorization bill—legislation to provide military families with up to 26 weeks of leave under the Family and Medical Leave Act (FMLA) to care for injured servicemembers. I had introduced this bill in the House, and its provisions implement one of the recommendations of the President's Commission on Care for America's Returning Wounded Warriors, chaired by Secretary Donna Shalala and Senator Bob Dole.

Also included in the final legislation was an amendment introduced by Representative ALTMIRE (with then Representative UDALL) to provide up to 12 weeks of leave for military families who need this leave to deal with qualifying exigencies arising out of the deployment of a servicemember to Iraq or Afghanistan.

Once this legislation became law, and the Bush Department of Labor issued regulations, we realized that corrections needed to be made to these FMLA provisions to truly effectuate their purpose to assist military families when these families need time off from work. Section 585 of H.R. 2647 does just that; and clarifies:

That family members of certain seriously ill and injured veterans are entitled to the 26 weeks of leave; and

That the family members of regular active servicemembers (and not just reservists and members of the national guard) are entitled to 12 weeks of leave for "exigencies" when they are deployed away from home.

Finally, Section 585 provides that exigency leave will be available when a servicemember is to be deployed anywhere overseas and not just overseas in support of a contingency operation (e.g. Iraq or Afghanistan).

The FMLA is intended to help individuals balance their family and work obligations. Millions of working people are now eligible for unpaid job protected leave. When the Act was passed in 1993, it was a giant step and is of great importance to working families.

Since a majority of military spouses work, they too must balance work and family. They work to put food on the table and support their families. But they face additional challenges because their lives are disrupted by multiple deployments, involving not only reservists and members in the National Guard, but those servicemembers in regular active duty as well.

The conflicts in Iraq and Afghanistan have resulted in over 34,000 casualties with many servicemembers being seriously wounded. These injured warriors need substantial support and care from their families, often for long periods of time, and some permanently. In addition, a recent Pentagon study found that 11 percent of Iraq veterans and 20 percent of Afghanistan veterans suffer from post-traumatic stress syndrome, an often disabling condition.

The expansion of the FMLA to include leave for military families was much needed. The provisions of Section 585 in H.R. 2647 help clarify the original intent of the law.

SUPPORTING HEALTH REFORM

HON. FORTNEY PETE STARK

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. STARK. Madam Speaker, this past Sunday my colleague from Pennsylvania, ALLYSON SCHWARTZ, addressed the issue of health reform in a guest editorial for the Philadelphia Inquirer. In her piece she laid out an indisputable case for why the current healthcare system has become unacceptable for Americans and what we must do to fix it. I encourage all of my colleagues to read the article and to work in the coming months to ensure that we enact affordable, quality health care for all.

 $\begin{array}{c} \hbox{[From the Philadelphia Inquirer June 21,} \\ 2009] \end{array}$

OP-ED HEADLINE: FIXING HEALTH CARE

Health-care reform is the number-one issue my constituents raise with me, and a leading concern of business owners. For Democrats in Congress, health-care reform is a moral and an economic imperative.

American families are facing inadequate health coverage, mounting bills, and lack of access to care. They like their doctors and appreciate the quality of care provided by their hospitals. But, they have deep worries that their current coverage may change suddenly and limit access to their doctor or to needed benefits

Business owners are struggling to pay for health benefits for their workers, forcing them to pass greater costs to employees or drop coverage.

Increasing costs for the federal government are neither sustainable, nor producing the health outcomes they should. Taxpayers pay 46 percent of our nation's \$2.5 trillion health-care costs. And, just as in the private market, costs are skyrocketing. The share of our GDP devoted to health-care spending has doubled in the last 20 years, threatening our budget stability.

The status quo is unacceptable and unsustainable. We must do a better job to contain costs for families, businesses, and the government, and to ensure meaningful, affordable coverage for all Americans.

Can we? I believe we can by keeping what works, fixing what doesn't, and demanding quality care and greater value for our dollar.

In the first three months of this new administration, we did more to strengthen health care than in the prior decade. We expanded affordable health coverage to 11 million American children, took major steps to modernize medicine through health-information technology, invested significantly in lifesaving medical research, and ensured that U.S. workers and their families hurt hardest by this recession continue to have access to health coverage when they lose a job

Building on these achievements, we can find a uniquely American solution to cost, coverage, and quality. This is essential if our businesses are to be economically competitive, our people healthier, and our federal budget balanced.

Here's what we should do:

First and foremost, we start with the acknowledgment that health care is a shared responsibility. Every American will be expected to get health coverage and employers will have to provide coverage or help pay to cover the cost of the uninsured.

As President Obama has said, if you have coverage, and you like it, you can keep it. This means work-based coverage for most Americans, Medicare for seniors, Medicaid for our poorest and sickest, and continued benefits for veterans.

For the nearly 50 million uninsured Americans, many of whom are working families, we will help you buy either private or public coverage. While everyone will have to pay part of their premiums, partial subsidies on a sliding scale will be established and can be used to buy either private or public insurance

To ensure affordable, meaningful coverage, we will change the ground rules in the insurance market. Denying coverage or charging more for preexisting conditions, health status, or sex is going to stop. Insurers will have to simplify terms and procedures. And, we expect insurers to pass those savings along to their consumers.

Next, we know that in order to control costs and improve health-care outcomes, delivery of health services must be more efficient, more accountable, and better coordinated. Changes in Medicare and the new public-insurance option will create choices for patients to find primary-care providers and will mean better continuity of care for those with chronic diseases. We will gather, analyze, and disseminate information on best practices to doctors, nurses, and health providers, and then expect them to use it. And, we must have a renewed focus on primary care, encouraging future health-care providers to enter the field and working to ensure their excellence.

Third, we have to strengthen our commitment to innovation and technology. Americans have always been scientists and innovators, and we must keep investing in the next generation of medicines, technologies, devices, and cures.

Finally, without increased personal responsibility, Americans will not be healthier. We must take greater responsibility in the way we get health care and the way we take care of ourselves. If we don't, we all pay the consequences—from lost productivity, to the cost of expensive care, to personal pain and suffering.

Setting our nation toward a healthier, more economically competitive future will take fair and responsible financial investment. We are committed to covering the cost of health reform. To do so, we will consider means that are appropriate, fair, shared, and the least disruptive to economic growth and financial security for our families. The president has asked that those making under \$250,000 not be burdened by higher taxes. These are the parameters; the decisions will be difficult, but ones that you have entrusted to us.

Much of the cost of health-care reform will come from savings within the system. Reducing hospitalizations, duplicative testing, and medical errors, ending the current overpayments to private insurance companies that contract with Medicare, and insisting on better prices for prescription drugs for seniors will result in hundreds of billions of dollars of savings.

Besides the significant dollars that will come from savings and new premiums paid by those currently uninsured, stakeholders in health care, including insurance companies, hospitals, doctors, pharmaceutical companies, medical-device manufacturers, have committed to reducing costs by \$2 trillion over 10 years. These savings should be passed along to consumers.

There will always be naysayers who say these decisions are too hard, that health-care reform cannot be done, but I believe that today even "Harry and Louise," who helped stop reform before, would tell us reform is a necessity. If our businesses are to be economically competitive, our families healthier, and our government fiscally sound, we must find a uniquely American solution to our health-care challenges.

The time to act is now.

PERSONAL EXPLANATION

HON. TIMOTHY V. JOHNSON

OF ILLINOIS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. JOHNSON of Illinois. Madam Speaker, on rollcall No. 425, I was present on the floor, but due to a malfunction, my vote was not recorded.

Due to insufficient time to consider the subject before us, adjournment was the most responsible alternative. Thus my vote below would be in the affirmative.

Had I been present, I would have voted "yes."

EARMARK DECLARATION

HON. DAVID DREIER

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. DREIER. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Fiscal Year 2010 Interior, Environment and Related Agencies Appropriations Act:

Requesting Member: Congressman DAVID DREIER

Bill Number: H.R. 2996, the Fiscal Year 2010 Interior, Environment and Related Agencies Appropriations Act

Account: EPA STAG Water and Wastewater Infrastructure Project

Legal Name of Requesting Entity: City of Arcadia. California

Address of Requesting Entity: 240 West Huntington Drive, Arcadia, CA 91066

Description of Request: Provide an earmark of \$500,000 for the cities of Arcadia and Sierra Madre for their Joint Water Infrastructure Projects. Arcadia's project will provide for the portion of the construction cost for the Baldwin Reservoir Rehabilitation Project (\$250,000). This project will provide for structural reinforcement of the existing reinforced concrete reservoir to be able to withstand a seismic event as identified in the Corps Seismic Reliability Study in 1997. Sierra Madre's project will provide for the portion of the construction cost for its Water Supply Well Project (\$250,000). This project will replace an existing well with a new high capacity well to provide for groundwater supply reliability. Each city will provide a 45% local match to the 55% EPA STAG funding, as required.

EARMARK DECLARATION

HON. LEONARD LANCE

OF NEW JERSEY

IN THE HOUSE OF REPRESENTATIVES Thursday, June~25,~2009

Mr. LANCE. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2647—National Defense Authorization Act for Fiscal Year 2010:

Authorized Amount: \$4,800,000.00

Project Name: Tactical Metal Fabrication (TacFab)

Funding Account/Service: RDA, Army

PE Number: 0602601A, Combat Vehicle and Automotive Technology Line Number: 13 Intended Recipient: SeaBox Inc., 450 Black

Horse Lane, No. Brunswick, NJ 08902

The TacFab system, which is currently development, will demonstrate a under tactically mobile rapid metal fabrication capability that will be a companion unit to the Mobile Parts Hospital to provide spare and replacement parts to our Warfighters in theater, and also as a stand-alone, metal casting resource provided to domestic organic Army depots and industrial facilities in support of RESET activities. This final increment for FY 2010 will result in a mobile, rapidly deployable asset, both in theater and within the U.S. in support of RESET operations. Once fully configured, the Army expects a 5x-10x reduction in delivery times for poured metal part base shapes using TacFab versus conventional procurement processes.

TacFab's containerized, mobile foundry to the U.S. Army allows deployed forces to produce spare and replacement parts in the field. This cuts the order time from weeks or months to 24 hours. Funding for this project will provide our troops with the parts they need to effectively complete their missions. Additionally, the system can be deployed at depots in CONUS assisting in RESET as currently exists. TacFab will reduce time waiting for parts and cut costs for DoD while ensuring our troops have the weapons they need as soon as they need them so they may effectively complete their missions.

IN HONOR OF DR. GOFF

HON. SAM FARR

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. FARR. Madam Speaker, I rise today to recognize the outstanding life-work of Dr. Lynda J. Goff. Dr. Goff has served with distinction as a Professor of Ecology and Evolutionary Biology at the University of California, Santa Cruz for more than 30 years. Dr. Goff has decided to take the next step in her life, and is retiring from the University of California. While she will no longer be a faculty member, her legacy of outstanding dedication to California and the scientific community at large shall be persistent.

Dr. Goff is a devoted and truly inspiring biology teacher. In the tenure of over three dec-

ades, she has taught 10,000 university students, and has supervised the research of more than 100 graduate students. Her noteworthy achievements include teaching and researching molecular plant and marine biology on all seven continents. She has the honor of having significantly contributed to seven expeditions to Antarctica and twenty in the Arctic. Her exemplary teaching led her to serve in the distinguished role of Vice Provost and Dean of Undergraduate Education from 1999 to 2004, and subsequently as the first director of the "California Teach" program. Dr. Goff played a pivotal role in creating this program, established to increase the number of highly trained K-12 science and mathematics teachers in California—something our nation desperately needs. She dedicated herself wholeheartedly to ensure that California, and indeed our great Nation, increases its competitiveness in math and science in the 21st Century.
Professor Goff has received national and

Professor Goff has received national and international recognition for her scientific research, much of which has centered on cellcell and genome interaction in algae and the evolution of parasitism. Dr. Goff has been a solid pillar in the Monterey Bay community for years; not only as a distinguished professor, but also as an elementary science teacher, a naturalist and photographer. Her work embodies what California's central coast prides: experiencing the beauty of nature, seeking to understand the mysteries of our oceans' flora and fauna and giving back to the community to ensure our posterity's brighter future.

I would like to thank her for her meritorious service to California and commend her for her many accomplishments.

EARMARK DECLARATION

HON. SHELLEY MOORE CAPITO

OF WEST VIRGINIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mrs. CAPITO. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2874, Commerce, Justice, Science, and Related Agencies Appropriations Act, 2010.

Awarded under: COPS TECH GRANT, Kanawha Prosecuters Case Management, Kanawha County Prosecuting Attorney, 700 Washington Street, East Charleston, WV 25301.

This project would allow for the cost of implementation of the case management system, integration of the system with law enforcement and hardware needed for both systems.

Awarded under: COPS TÉCH GRANT, Spencer PD Computer System, Spencer Police Department, 116 Court St., Spencer, WV 25276.

Funding will be used to purchase a computer system for processing criminals and case management.

Awarded under: COPS TECH GRANT, Weston Police Department Technology Upgrade, Weston Police Department, 102 West 2nd Street, Weston, WV 26452.

Funding would help establish a computer network in all police vehicles that is networked with the 911 center and the Weston Police Department and surrounding counties.

Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am

submitting the following information regarding earmarks I received as part of H.R. 2996 Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010.

Awarded under: U.S. Forest Service Land Acquisition, Nature Conservancy—Monongahela National Forest, U.S. Forest Service, 200 Sycamore Street, Elkins, WV 26241.

Funds would go towards the acquisition 1,210 acres within the Monongahela National Forest

Awarded under: Save America's Treasures, Claymont Court Claymont, Society for Continuous Education, 667 Huyett Road, Charles Town, WV 25414.

This funding will go to underwrite initial phases for restoration of Claymount Court, a national historic site of great significance.

EARMARK DECLARATION

HON. STEVEN C. LATOURETTE

OF OHIO

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. LATOURETTE. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, Department of the Interior, Environment and Related Agencies Appropriations Act, 2010:

Requesting Member: Mr. STEVEN C. LATOURETTE

Bill Number: H.R. 2996

Account: National Park Service, Construction Account

Legal Name of Requesting Entity: Cuyahoga Valley National Park

Address of Requesting Entity: 15610 Vaughn Rd., Brecksville, Ohio 44141

Description of Request: Provide an earmark in the amount of \$500,000 to carry out the Cuyahoga Valley National Park's Site and Structure Rehabilitation Program which is a component of its General Management Plan. With more than 250 historic structures, nearly 100 of which are on the National Register, the park will use the full amount for restoration, rehabilitation and stabilization of the buildings and the environment within the park. Protection of our nation's national parks and their facilities is a relevant use of taxpayer dollars.

Requesting Member: Mr. STEVEN C. LATOURETTE

Bill Number: H.R. 2996

Account: U.S. Environmental Protection Agency, State and Tribal Assistance Grants

Legal Name of Requesting Entity: The City of Stow, Ohio

Address of Requesting Entity: 3760 Darrow Road, Stow, Ohio 44224

Description of Request: Provide an earmark in the amount of \$500,000 for the construction of a sanitary sewer system within the City of Stow, Ohio. The full amount of the funding will be used for the construction and installation of the new system. The City of Stow will provide \$600,000 toward the total \$1.1 million cost of the project. Sanitary sewer systems protect human health and the environment.

EARMARK DECLARATION

HON. CANDICE S. MILLER

OF MICHIGAN

IN THE HOUSE OF REPRESENTATIVES $Thursday,\,June\;25,\,2009$

Mrs. MILLER of Michigan. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of HR 2892 the Department of Homeland Security Appropriations Act of 2010 Requesting Member: Congresswoman

CANDICE S. MILLER

Bill Number: HR2996

Account: STAG Water and Wastewater Infrastructure Project

Legal Name of Requesting Entity: The office of the Oakland County Water Resources Commissioner

Address of Requesting Entity: Oakland County Water Resources Commissioner 1 Public Works Dr. Building 95 West, Waterford, MI 48328

Description of Request: This request, in the amount of \$500,000.00, would be used to help rehabilitate the Oakland Macomb Interceptor. This is critical to the environment and health and safety of the region. This interceptor has experienced a catastrophic failure and is in need of major repairs.

IN RECOGNITION OF THE SONS OF THE PIONEERS 75TH ANNIVER-SARY

HON. ROY BLUNT

OF MISSOURI

IN THE HOUSE OF REPRESENTATIVES Thursday, June~25,~2009

Mr. BLUNT. Madam Speaker, I rise today to honor a legendary Ozarks western singing group—Sons of the Pioneers, who will celebrate their 75th anniversary of performing this year. They are known worldwide for their vocal blend, unique harmonies and special arrangements of their classic songs. Introduced in 1934, the Sons of the Pioneers are reputed to be the longest continually performing musical group in the history of western music.

After about 50 years of touring, the Sons of the Pioneers decided to make Branson their home. They settled at the Shepherd of the Hills, where they perform at the Sons of the Pioneers Pavilion. The six-member group entertains guests with western songs and stories.

The members have changed over the years, but they all continue to present the music in its original form for everyone to enjoy.

The founding members included Roy Rogers (Leonard Slye), Bob Nolan and Tim Spencer, who was born in Webb City, Missouri, which is now part of my congressional district. Their unique style of music became widely admired and copied. They composed many original songs, several of which have become true American classics. "Tumbling Tumbleweeds," "Cool Water," and "Riders in the Sky" were part of a unique sound and style, which became the traditional music of the American cowboy and the West.

The Sons of the Pioneers has had 33 members, and has never disbanded. The Sons of the Pioneers have performed in nearly 100

movies and have sung over 3,000 western songs. They have starred in movies with well known actors such as John Wayne, Gene Autry, Bing Crosby, and of course Roy Rogers

The Sons of the Pioneers has achieved many awards and accolades over their three-quarters of a century performing. They are considered "National Treasures" by the Smithsonian Institute. They have been inducted in several halls of fames including: Nashville Country Hall of Fame in 1978, Western Hero's Hall of Fame in 1984, Western Music Association Hall of Fame in 1990 and the National Cowboy Hall of Fame in 1995. The group won Vocal Group of the Year in 1970 and Band of the Year in 1978. In 1986, their popular song "Cool Water" was inducted into the Grammy Hall of Fame.

Sons of the Pioneers is truly a group who deserves significant credit for the music they have created, the standards they have set, the achievements they have accomplished, and all the generations they have touched.

This year celebrates the Sons of the Pioneers' 75th Anniversary of creating and preserving western music. It is truly an honor for Southwest Missouri to be the home of such a distinguished group. I wish Sons of the Pioneers continued success and many more years of keeping western music alive for future generations to enjoy.

EARMARK DECLARATION

HON. ROBERT B. ADERHOLT

OF ALABAMA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. ADERHOLT. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2847, the Commerce, Justice, and Science Appropriations Bill:

Requesting Member: ADERHOLT

Bill Number: H.R. 2296, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010

Account: National Park Service, Save America's Treasures

Legal Name of Requesting Entity: City of Fort Payne

Addréss of Requesting Entity: City of Fort Payne, 100 Alabama Ave., NW, Fort Payne, AL 35967

Description of Request: "Historic Fort Payne Coal and Iron Building Rehabilitation, \$150,000"

The funding would allow Fort Payne to create the construction documents, let bids, and begin the phased rehabilitation of an important landmark. The building will house a cultural center, which will serve the entire county. Taxpayer Justification: This building is located in the Fort Payne Boom Town Historical District (National Register #88000444), and upon completion of renovation, will be a valuable asset in stimulating cultural tourism and raising awareness of our heritage. \$150,000.00 appropriation will be applied to the project in the following manner: \$40,000 for the completion of the design phase (creation of construction documents): \$30,000 for the rehabilitation of the roof system; \$30,000 for the renovation of the exterior of the building; \$50,000 for the installation of HVAC, plumbing and electrical components.

Requesting Member: ADERHOLT

Bill Number: H.R. 2296, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010

Account: National Park Service, Save America's Treasures

Legal Name of Requesting Entity: University of Montevallo

Address of Requesting Entity: UM Station 6130, Montevallo, AL 35115

Description of Request: "Historic Montevallo Main Hall Renovation", \$150,000

Provide \$150,000 to fund interior and exterior renovation and an upgrade to existing safety codes. Priorities include upgrades to fire and life safety systems, HVAC systems, elevators, and toilet and shower rooms; enhancements to interior cosmetics and furnishings; and an exterior renovation. Taxpayer Justification: This building anchors the Montevallo campus and is a prominent feature of the Olmsted Brother's 1930 Master Plan. Main Hall was placed on the National Register of Historic Places in 1978. This project's budget is \$2.5 million. Within the budget is \$150,000 for stone and masonry work, \$300,000 for metal cornice repairs, \$250,000 for exterior painting, \$1,600,000 for windows, and \$200,000 for professional services. This request is consistent with the intended and authorized purpose of the National Park Service, Save America's Treasures account. The University of Montevallo will meet or exceed all statutory requirements for match funding where applicable.

Requesting Member: ADERHOLT

Bill Number: H.R. 2296, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010

Account: STAG, Water and Wastewater Infrastructure Project

Legal Name of Requesting Entity: City of Sulligent

Address of Requesting Entity: City of Sulligent, 5795 Highway 278, Sulligent, AL 35586

Description of Request: "Water Supply Project", \$500,000"

The funding would be used for the planning, design, and construction of an additional water supply well, an additional water storage tank, and a booster pumping station, all to provide an additional source of potable water and to increase system pressures. Taxpayer Justification: This funding will help meet the water needs of a growing population. The proposed project consists of the design and construction of a new water supply well and new water storage tank. The project budget includes \$315,000 for the construction of a new water supply well, \$600,000 for the construction of a new water storage tank, and \$75,000 for the construction of a booster pumping station. In addition, the budget includes \$110,000 for engineering services for a total estimated project cost of \$1,100,000.

EARMARK DECLARATION

HON. PETER T. KING

OF NEW YORK

IN THE HOUSE OF REPRESENTATIVES Thursday, June~25,~2009

Mr. KING of New York. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the fol-

lowing information regarding earmarks I received as part of H.R. 2996—the Department of Interior, Environment, and Related Agencies Appropriations Act. 2010:

Requesting Member: Congressman PETER KING

Bill Number: H.R. 2996

Account: Environmental Protection Agency—STAG

Legal Name of Requesting Entity: City of Glen Cove

Address of Requesting Entity: 9 Glen Street, Glen Cove, NY 11542

Description of Request: \$500,000 will be used to rehabilitate and obtain technology for failing drinking and storm water infrastructure that are critical to protection of the Long Island Sound, the community's sole source aquifer, and shoreline properties.

EARMARK DECLARATION

HON. DEAN HELLER

OF NEVADA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. HELLER. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010:

Requesting Member: Congressman DEAN HELLER

Bill Number: H.R. 2996

Account: Environmental Protection Agency—STAG Water and Wastewater Infrastructure Project

Legal Name of Requesting Entity: Lyon County Utilities

Address of Requesting Entity: 275 Main Street, Yerington, NV 89447

Description of Request: \$500,000. This project will expand the current wastewater treatment facility at Mound House to serve residents currently on septic. This will help remediate the groundwater contamination currently taking place downstream of the wastewater treatment plant's leach field. Through this project groundwater contamination can be reversed with improved wastewater treatment and by eliminating the existing septic system.

HICO POTHOLE PATCHING

HON. JOHN R. CARTER

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. CARTER. Madam Speaker, the residents of Hico, Texas deserve to be greatly commended for the service they provided to their own city through the Pothole Patching Project on March 7, 2009. One hundred and fifty dedicated and eager volunteers prepared for weeks for a long day of repairing the city's roads. These hardworking volunteers not only made their roads safer for residents and travelers, but nurtured a strong sense of community while doing it. The fellowship that this act of volunteerism illustrates is nothing short of honorable and I hope other cities can mirror this kind of community enthusiasm and resourcefulness.

EARMARK DECLARATION

HON. ROBERT E. LATTA

OF OHIO

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. LATTA. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2647, the National Defense Authorization Act for Fiscal Year 2010.

Requesting Member: Congressman ROBERT E. LATTA

Bill Number: H.R. 2647, National Defense Autorization Act for Fiscal Year 2010

Account: AirForce; Research, Development, Test & Evaluation, Air force (RDAF)

Legal Name of Requesting Entity: Metals Affordability Initiative (MAI)

Address of Requesting Entity: 1138 by-the-Shores Drive, Huron, OH 44839

Description of Request: \$10,000,000 for the initiation of 4 new, more immediate high-impact programs, as well as sustaining ongoing programs. These new industry-led programs will be directed at improvement in total systems cost, fuel savings/energy management, "green" (environmental impact), sustainment/ life extension, and access to space. The mission of MAI is to innovation to maintain leadership in the strategic aerospace metals industrial sector by using technology innovation to maintain global competitiveness while improving performance and increasing affordablity of weapons systems. MAI's main economic impact will be to maintain leadership in the strategic aerospace metals industrial sector by using technology innovation to maintain global competitiveness. This industrial sector continues to be under pressure by foreign manufacturers, and investing in technology will help sustain jobs. I certify that neither I nor my spouse has any financial interest in this project.

EARMARK DECLARATION

HON. SPENCER BACHUS

OF ALABAMA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. BACHUS. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information for publication in the CONGRESSIONAL RECORD regarding funding that I requested as part of H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010.

Requesting Member: Congressman SPEN-CER BACHUS

Bill Number: H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010

Account: National Park Service, Save America's Treasures

Legal Name of Requesting Entity: University of Montevallo

Address of Requesting Entity: UM Station 6130, Montevallo, AL 35115

Description of Request: Provide \$150,000 to fund interior and exterior renovation and an upgrade to existing safety codes. The Main Hall renovation project will provide students

with safe, comfortable, and accessible housing in a building listed on the National Historic Registry. The projects will provide an enhanced environment for living and learning. This project's budget is \$2.5 million. Within the budget is \$150,000 for stone and masonry work, \$300,000 for metal cornice repairs, \$250,000 for exterior painting, \$1,600,000 for windows, and \$200,000 for professional services. This request is consistent with the intended and authorized purpose of the National Park Service, Save America's Treasures account. The University of Montevallo will meet or exceed all statutory requirements for match funding where applicable

HONORING THE 100TH ANNIVER-SARY OF JOHNSON MATTHEY INC.

HON. JIM GERLACH

OF PENNSYLVANIA
IN THE HOUSE OF REPRESENTATIVES
Thursday, June 25, 2009

Mr. GERLACH. Madam Speaker, I rise today to honor an outstanding southeastern Pennsylvania manufacturer celebrating its 100th anniversary.

Johnson Matthey Inc. was officially incorporated on June 30, 1909 and has grown from a platinum works shop in Philadelphia to a thriving business that employs approximately 8,700 workers at operations in more than 30 countries. The company's North America headquarters is in Wayne, Pennsylvania and several plants operate throughout the Commonwealth of Pennsylvania.

Johnson Matthey focuses on catalysis, precious metals, fine chemicals and process technology. While the company's roots extend back to the 19th Century, Johnson Matthey has continued to develop its technology, demonstrating the company's ability to maintain world leadership by adapting constantly to rapidly changing customer needs. While adhering to rigorous environmental standards itself, Johnson Matthey products have contributed greatly to a cleaner environment and have enhanced the quality of life for millions of people around the world.

Throughout the week of June 30, 2009, Johnson Matthey management, employees, affiliate companies, parent company, and communities will commemorate the company's centennial.

Madam Speaker, I ask that my colleagues join me today in congratulating everyone at Johnson Matthey for reaching this memorable milestone and in wishing the company continued success in creating jobs and improving the quality of life across the globe.

EARMARK DECLARATION

HON. JO BONNER

OF ALABAMA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. BONNER. Madam Speaker, I submit the following information:

Project Name: Washington County Commission Sewer Extension

Requesting Member: Congressman JO BONNER

Bill Number: H.R. 2996

Account: STAG Water and Wastewater Infrastructure Project

Legal Name of Requesting Entity: Washington County Commission

Address of Requesting Entity: 45 Court Street, P.O. Box 146, Chatom, Alabama 36518

Description of Request: Provide an earmark of \$500,000 for Phase II of an ongoing project for unincorporated areas of Washington County not currently served by sanitary sewers. The soils in some areas of the county are generally conducive to percolation and some areas are on soils that have higher water tables that absorb water very slowly. Approximately, \$500,000 [or 100%] of funding will be used for construction, labor and materials of a low pressure, decentralized sanitary sewer collection and treatment facility. The county is currently working on phase I of this project and phase II would construct a 30,000 GPD on-site treatment and disposal facility, collection mains, interceptor tanks and pumps to provide homes and businesses with sanitary sewer. Washington County, the most economically challenged county in the state of Alabama, is home to a new steel plant that is providing 25,000 new construction jobs and 2,000 fulltime jobs. This much needed project will allow the county to continue to grow and recruit even more industry. The Washington County Commission will provide dollar for dollar match for this project.

CARNEGIE MEDAL

HON. JOHN R. CARTER

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Thursday. June 25, 2009

Mr. CARTER. Madam Speaker, I would like to congratulate the family of Courtney E. Butler from Stephenville, who was presented with the Carnegie Medal for heroism for their daughter's bravery in attempting to save a civilian caught in a flood on a low water crossing. Miss Butler was only sixteen when she made her valiant attempt in May of last year, and was swept up and drowned in the process. It is citizens like this young girl who make me proud to serve the great people of Texas District 31 and continually inspire me, as they should everyone else who learned of her

EARMARK DECLARATION

HON. JOHN L. MICA

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. MICA. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding an earmark I received in the amount of \$500,000 as part of the Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010, Environmental Protection Agency, STAG Water and Wastewater Infrastructure Account for the South Seminole and North Orange County Wastewater Improvement Project. The entity to receive funding for this project is the Or-

ange County Wastewater Transmission Authority located at 410 Lake Howell Road, Maitland, Florida.

This project will replace wastewater pipes and mechanical equipment that are approaching the end of their service lives. Portions of the Force Main that will be replaced are under the travel lanes of Aloma Avenue. The roadway carries 33,000 vehicles per day and a collapse of the Aloma Avenue pipe and a resulting collapse of the road would be a major public health and safety liability.

EARMARK DECLARATION

HON. ZACH WAMP

OF TENNESSEE

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. WAMP. Madam Speaker, as a leader on earmark reform, I am committed to protecting taxpayers' money and providing greater transparency and a fully accountable process. H.R. 2996, The Fiscal Year 2010 Interior, Environment, and Related Agencies Appropriations Act contains the following funding that I requested:

Requesting Member: Rep. ZACH WAMP
Account: National Park Service—Construc-

Legal Name Entity Receiving Funding: Moccasin Bend National Archeological District

Address: Moccasin Bend Road, Chattanooga, Tennessee 37405

Description of Request: Moccasin Bend National Archeological District, a unit of the Chickamauga and Chattanooga National Military Park, has a rich and varied cultural history with evidence of occupation dating back to the earliest human cultures in North America. Moccasin Bend was designated as a unit of the National Park Service to preserve the area's rich heritage for future generations. There are no facilities for public enjoyment of these nationally significant resources. Moccasin Bend National Archeological District received \$500,000 for design and construction of an Interpretive Center and educational exhibits to promote awareness of the archeological district.

Distribution of funding:

Design development and construction 100% Requesting Member: Rep. ZACH WAMP

Account: Environmental Protection Agency-State and Tribal Assistance Grant

Legal Name Requesting Entity: City of Harrogate, Tennessee

Address: 138 Harrogate Crossing, Harrogate, Tennessee 37752

Description of Request: The Mayor and City Council of Harrogate requested funding to extend a wastewater collection system to the Tri-State Health and Rehabilitation Center, residences and businesses. Upgraded sewer capabilities are critical to support the increasing residential and commercial development in Harrogate. The proposed expansion will allow residents in the area to have safe, adequate wastewater service. The City of Harrogate received \$500,000 for the wastewater improvements.

Distribution of funding: Construction—83% Survey/Fees—1% Engineering—6% Inspection—3%

Project Contingency-4% Environment Review—1% Administration—2%

CELEBRATING THECITY OF ERBENDORF. GERMANY'S 900TH BIRTHDAY

HON. MICHAEL E. McMAHON

OF NEW YORK

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. McMAHON. Madam Speaker, I rise today to commemorate and honor the city of Erbendorf in the Oberpfalz region in the State of Bavaria in Germany as it celebrates its 900th Birthday.

Nine hundred years ago, this village was first mentioned as "Herbendorf' in the Establishment and Protection letters of Pope Paschalis II as he wrote to the monastery Weissenohe in Oberfranken. Although it appears that location is today what is known as Altenstadt, it is clear that the city we know today has enjoyed an existence for more than 900 years. And since history does not stand still, we are sure that someday an even earlier mention of this city will be found.

In its more than 900 year history, the city of Erbendorf has certainly changed and developed. Through the middle ages and modern times it has been beset by war, hunger, pestilence, and siege. However, this has given the city its inner strength and it has now grown into a beloved city with a wonderful quality of life, enviable infrastructure, and a strong economy.

Certainly some of its most prominent citizens include Buergermeister Hans Donko, Axel Baron von Stromberg, and Hilde and Fritz Kohr, who recently celebrated their 50th Wedding Anniversary and continue to operate one of the city's most beloved businesses, Konditorei Kohr. In addition the city was the birthplace of two of its most favorite daughters, Maria Schrebs Trottmann, who emigrated to Neustadt/Waldnaab, and my mother Meta Baronin von Stromberg McMahon, who emigrated to the United States where she had seven children who to this day consider themselves part of the Erbendorf family. For many years, her brother Doctor Nils Baron von Stromberg and his wife Charlotte served the city as family doctors.

Madam Speaker, the city of Erbendorf has had a front row seat to the turbulent course of European history. For nearly a millennium, her citizens have borne witness to the countless events-from the epic to the mundane which unfolded to shape the Europe and the world of today. I am proud to be a son of the city of Erbendorf and offer my congratulations on its 900th anniversary.

EARMARK DECLARATION

HON. HAROLD ROGERS

OF KENTUCKY

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. ROGERS of Kentucky. Madam Speaker, I submit the following:

Requesting Member: Congressman HAROLD ROGERS

Bill Number: H.R. 2647

Account: MILCON, Army National Guard Legal Name of Requesting Entity: Kentucky Department of Military Affairs

Address of Requesting Entity: Boone National Guard Center, 100 Minuteman Parkway, Frankfort, Kentucky 40601

Description of Request: Provide directed funding of \$1.805 million to complete construction of the Phase IV Aviation Operation Facility-London Joint Readiness Center located in Laurel County, Kentucky. The funding will be used for the construction of two additional (11,400 Sf) unheated aircraft storage buildings at the facility. The project is required to fully house the Joint Support Operations equipment and personnel in one facility located in the vicinity of operations. At the conclusion of this project, the unit will be able to respond quicker and in a much more efficient manner which will allow a greater return on investment funds spent on the operation.

TEMPLE TEACHER

HON. JOHN R. CARTER

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CARTER. Madam Speaker, congratulations to Temple High School German teacher Nella Spurlin who was recently honored as Regional Teacher of the Year by the Southwest Conference on Language Teaching. The hard work and passion that she was committed to distinguished her from educators of the nine other states in the region.

On behalf of Texas District 31, I would like to wish Ms. Spurlin the best of luck when she competes against other regional winners for the American Council on the Teaching of Foreign Language National Teacher of the Year award in November.

EARMARK DECLARATION

HON. C.W. BILL YOUNG

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. YOUNG of Florida. Madam Speaker, pursuant to the House Republican Standards on Congressional appropriations initiatives, I am submitting the following information regarding a project that was included at my request in H.R. 2647, The National Defense Authorization Act of Fiscal Year 2010:

Consolidate Communications Facility Account: Military Construction, U.S. Air

Legal name and address of requesting entity: MacDill Air Force Base, Tampa, Florida.

Description of request: \$21,000,000 for a Consolidated Communication Facility (Project Number NVZR033702). MacDill Air Force Base, Tampa, Florida does not have an adequate Consolidated Communication Facility for the Joint Components of USSOCOM and USCENTCOM forces. This Consolidated Communication Facility would provide for all communication circuits (both digital and analog) entering and exiting MacDill AFB. The Department of Defense Unified Facilities Criteria Anti-Terrorism and Force Protection guidance

requires that essential communication equipment be located in a secure environment. Base Network Control Center functions currently located in Blda 260 will be relocated to the new secure facility.

PERSONAL EXPLANATION

HON. MICHAEL E. CAPUANO

OF MASSACHUSETTS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CAPUANO. Madam Speaker, on June 24, 2009, due to a medical situation involving a member of my immediate family, I had to return to my district and was unable to participate in rollcall votes 435 through 452. Had I been present, I would have voted in the following manner:

"yes" on rollcall 435; "yes" on rollcall 436;

"no" on rollcall 437; "yes" on rollcall 438; "no" on rollcall 439; "no" on rollcall 440;

"no" on rollcall 441; "yes" on rollcall 442; "no" on rollcall 443; "no" on rollcall 444; "no" on rollcall 445; "no" on rollcall 446;

"no" on rollcall 447; "no" on rollcall 448;

"no" on rollcall 449; "yes" on rollcall 450; "yes" on rollcall 451; "yes" on rollcall 452.

EARMARK DECLARATION

HON. BRIAN P. BILBRAY

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. BILBRAY. Madam Speaker, I submit the following:

Bill Number: H.R. 2647—National Defense Authorization Act for Fiscal Year 2010

Account: OPAF, Line 12

Legal Name of Requesting Entity: California National Guard

Address of Requesting Entity: 9800 Goethe Road, Box 42, Sacramento, CA 95826

Description of Request: I received an earmark of \$4 million to upgrade the Eagle Vision III system which is operated by the 147th Combat Communications Squadron, in San Diego, California. In October of 2007, San Diego suffered through one of the worst wildfire disasters in California history. With thousands of homes lost and hundreds of thousands of lives changed, the California National Guard requested upgrades to Eagle Vision, the San Diego based system that has already proven itself as an asset for the Federal Emergency Management Agency, CAL Fires/OES, and the Army Strategic Command. The Eagle Vision III system directly and indirectly supported the 2008 Midwest Flooding, Hurricanes Fay, Gustav, and Ike and has participated in numerous military exercises. To augment the current system, this request seeks to provide resources for an increased imaging system that will provide higher resolution images, with more frequent access to images for first responders, while at the same time allowing for image data collection through clouds, haze and smoke. These capabilities are essential for the military and will be critical to the San Diego region for combating natural disasters such as wildfires, floods and hurricanes.

MARY HARDIN-BAYLOR CHANCELLOR

HON. JOHN R. CARTER

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CARTER. Madam Speaker, I would like to congratulate to Dr. Jerry G. Bawcom, President at the University of Mary Hardin-Baylor, in Belton Texas, as Dr. Bawcom transitions into the office of the Chancellor. As the 21st President of UMHB, he has served as President for 18 years and will become Chancellor on June 1, 2009. I would like to thank Dr. Bawcom for his leadership and service as well as congratulate him and wish him well in his new position as Chancellor.

EARMARK DECLARATION

HON. MICHAEL C. BURGESS

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. BURGESS. Madam Speaker, pursuant to the U.S. House of Representatives Republican Leadership standards on earmarks, I am submitting the following information regarding an earmark I received as part of H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010:

The City of Gainesville Water Treatment Plant Expansion Project, Gainesville, TX—\$500,000—STAG Water and Wastewater Infrastructure Project—Congressman MICHAEL C. BURGESS

The purpose of this project is to expand the water supply and distribution system to convey treated water to the City of Valley View, Bolivar Water Supply and other water users in Cooke County, Texas. The requested funding will be utilized for raw water pump station improvements, a treatment unit and backwash pump station, high service pump station expansion, and other appurtenances as necessary for the water treatment plant upgrade. Federal funding is necessary to allow the city to meet its obligation to provide a stable drinking water supply for residents of Gainesville and surrounding communities and to reduce the region's reliance on limited groundwater sources. The total project cost is \$2,533,007. Matching funds will be provided through inkind services and through city and state funds.

The City of Gainesville is located at 200 South Rusk, Gainesville, TX 76240.

THANKING LILLIAN BETHEA FOR HER SERVICE TO THE HOUSE

HON. ROBERT A. BRADY

OF PENNSYLVANIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. BRADY of Pennsylvania. Madam Speaker, on the occasion of her retirement on December 31, 2008, we rise to thank Mrs. Lilian Bethea for twelve years of distinguished service to the United States House of Representatives and 36 years of service in the United States Government. Lillian has served this great institution as a valuable employee of

House Information Resources, in the Office of the Chief Administrative Officer.

Lillian began her tenure with the United States House of Representatives in 1996 as a Systems Analyst working in the Member Information Network (MIN) Group and later for the Quality Assurance Team. Lillian specialized in the support and maintenance of in-House applications including but not limited to Federal Funds Reports. Grants and Contracts and Bulletin Board services. She became a Federal Funds Trainer based on her extensive knowledge and attention to detail on the project. Lillian has played an important role in many information technology projects including Quality Assurance and Integrated Services and Information Systems (ISIS) testing. During the Y2K remediation efforts, she played an instrumental role in quality assurance and data testing of systems resulting in the successful transfer of services from the mainframe to their new platforms.

Since 2004, Lillian has been a Team Leader for the Web Solutions Call Center. Her attention to detail and quality assurance experience were again highlighted as she managed the customer request tracking system, team assignments, and day to day customer requests for the Web Group. Her duties included managing customer requests for web services using the Customer Tracking System (CTS) and coordinating with external teams to process Secure ID Web Manager requests, establishing Listserv lists, and providing permissions and access to Web Site Statistic services. Again, her detail orientation and quality work ethic assured the security of the House Web infrastructure through oversight and management of the necessary processes involved. Lillian also played a vital role in the preparation of materials and coordination of efforts for the House Services Fair, ensuring the Web Solutions Branch was properly represented during the event.

On behalf of the entire House community, we extend congratulations to Lillian for many years of dedication and outstanding contributions to the United States House of Representatives. We wish Lillian many wonderful years in fulfilling her retirement dreams.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. CANDICE S. MILLER

OF MICHIGAN

IN THE HOUSE OF REPRESENTATIVES Wednesday, June 24, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2047) to authorize appropriation for fiscal year 2010 for military activities of the Department of Defense, to prescribe military personnel strength for fiscal yea 2010, and for other purposes:

Mrs. MILLER of Michigan. Mr. Chair, I rise today in strong support of National Defense Authorization Act of 2009.

The Department of Defense directed the Army to restructure its premier modernization program known as Future Combat Systems—FCS program—which includes a network of new sensors, radios, robotic vehicles and a fleet of new combat vehicles.

I personally commend the thousands of dedicated soldiers, department of defense civilians and their defense industry partners who worked on the project.

More than 1,000 of these dedicated men and women that do the engineering work for the FCS program live and work in my district. Some 10,000 employees in 74 Michigan companies worked to provide the Army a new ground combat vehicle fleet.

Many of them will be economically disadvantaged, despite their best efforts, by termination of the combat vehicle project.

Legislation passed by the Armed Services committee recognizes the restructuring of the FCS program and provides guidance on how the Army should proceed.

Providing for the national defense is in the preamble of the Constitution of the United States, it is this body's most solemn duty and responsibility. We must ensure that the men and women we send into harm's way have the very best training and equipment we can provide.

It's imperative that we move rapidly to provide the Army a new ground combat vehicle that protects American soldiers against IEDs, road side bombs and anti-tank munitions. We must not lose the momentum gained during six years of research and development and the multibillion dollar taxpayer investment on this project.

Any new program must consider both Army and Marine Corps needs for manned ground combat vehicles now and in the future. It must build on what we have learned from three separate FCS ground vehicle designs as well as lessons learned from combat operations in Iraq and Afghanistan.

We have the best trained and dedicated Armed Forces in the world. Will we ask them to go to combat with vehicles that are nearly two generations old, designed for a different enemy and more conventional warfare?

Instead, let's build on the work that has already been done; ensure that billions of tax-payer dollars already spent are not wasted by starting from scratch, and provide U.S. Soldiers and Marines vehicles and systems that provide increased situational awareness for the conflicts of the future.

I urge the members to make a new combat vehicle the centerpiece of Army's research and development efforts in a restructured program.

WILLIAMSON COUNTY JOP

HON. JOHN R. CARTER

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CARTER. Madam Speaker, I would like to congratulate The Honorable Judy Schier Hoobs, Justice of the Peace for Williamson County, Precinct 4, who was awarded "Judge of the Year" by the Central Texas Justices of the Peace and Constables Association (CTJPCA) on April 15, 2009. When the group held their first meeting in 1986, Judge Hobbs was elected as the first vice president and was later elected as president in 1987. A lifetime member of the CTJPCA, Judge Hobbs was chaplain in 2008 and chair of the Legislative Committee. I am truly proud to have Judge Hobbs serve in Texas District 31.

IN HONOR OF SENATOR THURMAN G. ADAMS, JR.

HON. MICHAEL N. CASTLE

OF DELAWARE

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. CASTLE. Madam Speaker, it is with a heavy heart but great honor that I rise today to pay tribute to the life of the Honorable Thurman G. Adams, Jr. A member of Delaware's State Senate for the past 37 years and owner of T.G. Adams & Sons Inc., Senator Adams is a man who has given much to his community and his state; a man who is to be recognized for all that he has done and a man who will truly be missed by me and Delawareans throughout our state.

Since his initial election in 1972, Senator Adams worked diligently as a representative of his constituents and as an advocate for progress, molding Delaware into the businessfriendly, agriculturally rich state that it is today. The longest serving State Senator in Delaware history, Thurman served in this capacity under eight Governors and was elected as the Senate Majority Leader in 1999 and as the President Pro Tempore in 2002. Regarding Thurman's dedication to our State and his strength of character, I cannot say enough. For nearly four decades now, there is hardly a bill that has come to pass in Delaware upon which Thurman's influence has not been felt. One of the most notable pieces of legislation that he sponsored and fought for was an enhanced 9-1-1 bill. Passed and currently in place, the bill created a system that automatically gives the address from which a 9-1-1 call originatesenabling a quicker, more accurate response time. A member of the Senate Executive Committee since his first term and later appointed as chairman, Thurman played a huge role in determining who served in the judiciary, cabinet and various other influential state posts. The strong, positive force which he brought to the legislature every day has helped to strengthen and solidify Delaware's courts and government for many decades.

In his capacity as a legislator and as a citizen. Thurman spent his life in service to the State of Delaware. Senator Adams graduated from the University of Delaware in 1950 with a B.S in agricultural education and went on to succeed his father as the President of T.G. Adams & Sons Inc., a feed and grain business in his hometown of Bridgeville. With a solid base in agriculture and the business world, Thurman was appointed to the State Highway Commission in 1961 and appointed as the chairman of the Governor's Safety Committee in 1966. Over the years, Senator Adams was recognized for many accomplishments. In 1996, he received the University of Delaware's "Medal of Distinction," an honor acknowledging his outstanding professional achievements. He and his wife Hilda also became very active in trying to make the process to receive organ transplants easier for individuals and their families after their own personal experience with their son Brent. In 2008. he was both inducted into the National 4-H Hall of Fame and awarded the "Order of the First State," the highest award our Governor can present in recognition of his many years of service

Senator Adams spent his life as an advocate for his Bridgeville district, for the county of Sussex, and for the State of Delaware. A believer in personal, deep-rooted relationships, Thurman was a respected and compassionate legislator and his passing will leave a void in Delaware's General Assembly and our state. During my time as a State Senator and in my role as Lt. Governor and Governor, I had the privilege of working with Senator Adams on many key legislative issues. Thurman is someone with whom I worked closely and confided in frequently and I feel confident in recognizing him for who he was—a man who was incredibly fair, a strong, trusted and great leader with devotion unequaled, and a sterling reputation for helping others.

Foremost in Thurman's life was his family. Thurman was a loving husband to his wife Hilda, a father who could bestow life's lessons as well as heartfelt love to his three children, Brent, Lynn, and Polly, a grandfather who adored his grandchildren, and a brother to Leon, Beatrice and his deceased brother Alvin. His family and grandchildren warmed his heart and he took great pride in watching them grow and mature over the years. While we will all miss him dearly, I take comfort in knowing that he, Hilda, and Brent have been reunited and I am sure are watching over all of us now.

He gave his time, his energy, and his heart in pursuit of comprehensive and useful measures, established and implemented for the benefit of his fellow Delawareans. Steadfast in his beliefs, Thurman once said, "I hope that every bill will make life better." I stand today to acknowledge and honor that he was a man dedicated to just that. Godspeed to my good friend, Senator Thurman G. Adams, Jr. and thank you for your guidance, support and friendship over the years.

EARMARK DECLARATION

HON. DENNY REHBERG

OF MONTANA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. REHBERG. Madam Speaker, I submit the following:

Requesting Member: Rep. DENNY REHBERG Bill Number: H.R. 2996

Account: STAG Water and Wastewater Infrastructure Project

Name and Address: Em-Kayan County Water and Sewer District, 910 Greers Ferry Road, Libby, Montana 59923.

Description: The Em-Kayan community water system consists of three springs, two wells, five steel storage tanks and a water distribution system inclusive of fire hydrants. The original water system was constructed in the 1960s. Funding would be used to replace badly corroded steel water main with PVC water main, install additional fire hydrants to meet fire flow requirements, install water meters to better account for the District's water resource and install a control system.

Requesting Member: Rep. DENNY REHBERG Bill Number: H.R. 2996

Account: National Park Service—Save America's Treasures

Name and Address: City of Bozeman, 121 North Rouse Avenue, Bozeman, Montana 59771

Description: Historic Downtown Bozeman suffered a devastating loss due to a natural

gas pipeline explosion in March, 2009. The explosion and subsequent fire destroyed four historic building, and significantly damaged three others. All building are in the Bozeman Main Street Historic District, which is on the National Register of Historic Places. The destroyed buildings covered 150 linear feet of historic streetscape.

Requesting Member: Rep. DENNY REHBERG Bill Number: H.R. 2996

Account: BLM—Land Acquisition

Name and Address: The Conservation Fund, 125 Bank Street, Suite #612, Missoula, Montana 59802.

Description: Funding would be used for the BLM to purchase Phase II of this project. Located in Carbon County, near Red Lodge, the wind-blasted stone pinnacles of the Meeteetse Spires reach hundreds of feet into the sky and provide a unique backdrop to a scenic hanging valley as part of the Meeteetse Spires Area of Critical Environmental Concern (ACEC). In partnership with the BLM, The Conservation Fund has reached an agreement to acquire a 560-acre private inholding from a willing seller within the ACEC with the goal of conveying the property to the BLM through an appropriation.

Requesting Member: Rep. DENNY REHBERG Bill Number: H.R. 2996

Account: U.S. Forest Service—Land Acquisition

Name and Address: The Nature Conservancy, 32 S. Ewing, Helena, Montana 59601.

Description: This funding would be used for the U.S. Forest Service to acquire lands critical for protecting the existing federal investment in the Blackfoot Community—Nora Gulch—project area, including wildlife habitat for grizzly bears, elk, and threatened trout species.

Requesting Member: Rep. DENNY REHBERG Bill Number: H.R. 2996

Account: EPA—Science and Technology

Name and Address: Consortium for Plant Biotechnology Research Inc., 100 Sylvan Drive, Suite #210, St. Simons Island, Georgia 31522.

Description: Partnering with Montana State University, this funding would be used to fund university research and technology transfer for phytoremediation and environmentally friendly industries. Working with The Consortium for Plant Biotechnology Research, Inc., it will develop new and improved technologies that range from "green" chemicals and industrial manufacturing processes to environmental remediation.

Requesting Member: Rep. DENNY REHBERG Bill Number: H.R. 2996

Account: EPA—Science and Technology

Name and Address: The Water Research Foundation, 6666 Quincy Street, Denver, Colorado 80235.

Description: Partnering with the Mountain Water Company of Missoula, Montana, this funding would be used to sponsor individual research projects that enable utilities to provide safe, affordable and sustainable water to their customers. These projects will help water utilities address challenges such as climate change impacts on water supply, pharmaceutical contaminants in drinking water, aging infrastructure, and protection of watersheds.

Requesting Member: Rep. DENNY REHBERG Bill Number: H.R. 2996

Account: U.S. Fish and Wildlife Service—Land Acquisition

Name and Address: The Nature Conservancy, 32 S. Ewing, Helena, Montana 59601.

Description: This funding will be used for the U.S. Fish and Wildlife Service to acquire conservation easements along the Montana's Rocky Mountain Front.

Requesting Member: Rep. DENNY REHBERG Bill Number: H.R. 2996

Account: BLM—Land Acquisition

Name and Address: The Nature Conservancy, 32 S. Ewing, Helena, Montana 59601.

Description: This funding will be used for acquiring lands for the Bureau of Land Management to protect the existing federal investment in the project area, including wildlife habitat for grizzly bears, elk, and threatened trout species near the Blackfoot River.

Requesting Member: Rep. DENNY REHBERG Bill Number: H.R. 2996

Account: U.S. Forest Service—Land Acquisition

Name and Address: The Trust for Public Land, 111 South Grand Avenue, Suite #203, Bozeman, Montana 59715.

Description: This funding will be used as an acquisition project for the United States Forest Service to purchase mining claims within the Yellowstone National Park ecosystem. These lands offer natural and recreational resources that will be protected by the United States Forest Service.

RECOGNIZING THE CREW OF THE RB-47H SHOT DOWN OVER INTER-NATIONAL WATERS BY THE SO-VIET UNION ON JULY 1, 1960

HON. ROBERT J. WITTMAN

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES $Thursday,\,June~25,\,2009$

Mr. WITTMAN. Madam Speaker, I rise today to recognize Major Willard Palm, Captain Freeman B. Olmstead, Captain John McKone, and the crew of the RB-47H shot down over international waters by the Soviet Union on July 1, 1960. This recognition is well-deserved and highlights the unending service and integrity of our men and women in uniform.

The plane was crewed by Major Willard Palm as aircraft commander; Captain Freeman B. Olmstead as pilot; Captain John McKone as navigator.

Freeman B. Olmstead was born in Elmira, New York, and brought up in a devout Episcopal family. He earned a bachelor's degree in history from Kenyon College, Gambier, Ohio. He entered active duty with the Air Force in 1957.

McKone was a native of Tonganoxie, Kansas, and he graduated from Kansas State University with a bachelor's degree in history in 1954. He entered active duty on March 15, 1955.

On July 1, 1960, a United States Air Force RB-47H based at Forbes Air Force Base, Kansas, departed from Brize-Norton Royal Air Force Base in England. The flight's planned route kept the plane over international waters.

A MiG-19 fighter intercepted the American bomber in the Barents Sea. The MiG eventually opened fire on the RB-47H. Olmstead and McKone successfully ejected and survived only to be picked up by a Soviet fishing vessel. The aircraft commander, however, perished in the Barents Sea.

Ten days after the shootdown, Soviet Premier Nikita Khrushchev announced that they had shot down the bomber and captured the two crewmen. The pair were imprisoned in Moscow's Lubyanka prison, and accused by the Soviets of espionage, punishable by death, for allegedly violating the Soviet Sea frontier.

Shortly after the inauguration of President John F. Kennedy, Premier Nikita Khrushchev extended an offer to free Olmstead and McKone quickly—but with three terms later agreed to.

After seven months of imprisonment and interrogation the guards drove Captain Freeman B. Olmstead and Captain John McKone to the American embassy. They were handed over to U.S. officials to be reunited with their families without having disclosed any information to the Soviet government.

Madam Speaker, as a member of the Committee on Armed Services, I am continuously struck by the integrity of our servicemembers. With examples like Captain Freeman B. Olmstead and Captain John McKone it is clear where this integrity comes from and I ask my colleagues to join me in honoring them.

TRIBUTE TO BEN SACCO

HON. KEVIN McCARTHY

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES Thursday, June~25,~2009

Mr. McCARTHY of California. Madam Speaker, I rise today to honor Bernard "Ben" Sacco, a longtime Bakersfield entrepreneur, community leader, and friend who passed away on Tuesday, June 23, 2009, at the age of 87.

Ben Sacco was born in a small town outside Salerno, Italy, and immigrated to the United States in 1935. Sacco moved to California after serving his country in the U.S. Army Air Corps during World War II, and worked in agriculture in Hanford. In 1947, he and Morris Rosenberg founded Sierra Bag Company in Bakersfield to produce containers for local growers.

A devoted recycling advocate, Ben also founded Sierra Iron and Metal Company to recycle salvaged metals in 1959. Eventually, it became Sierra Recycling and Demolition, which cleans up land for redevelopment. On a visit to Italy, Sacco visited a scrap yard near Venice and discovered a unique machine—a mobile baler that could process twice as much scrap metal in a day as its U.S. counterparts. He promptly bought one, and at an age when many are considering retirement, Sacco embarked on a new career equipment vendor. He introduced the combination shear/baler in the United States in 1987, and soon Sierra International Machinery expanded into a major industry. Earlier this year, the Institute of Scrap Recycling Industries honored Ben Sacco with a lifetime achievement award for his dedication to Sierra International Machinery, LLC. Adding to his list of accomplishments. Sacco founded the Italian Heritage Dante organization in 1996.

Ben Sacco is survived by his wife, Eunice Sacco; sons John, Anthony, and Phillip; daughters Angela, Aragon, and Laura; and six grandchildren. Devoted to serving his community in a variety of ways, Ben's death is a

great loss for the Bakersfield community, but his legacy of dedication to his family, friends, and businesses will always be remembered.

FEDERAL OFFSET PROGRAM

HON. JAMES P. MORAN

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. MORAN of Virginia. Madam Speaker, today I am proposing bipartisan legislation to establish a program that would mirror the existing law for states. The legislation, in which I am joined by my colleagues, Representatives WOLF, WITTMAN, and CONNOLLY, would allow certain types of delinquent local tax debt to be collected through the reduction of federal tax refunds. Providing local governments access to these needed and due funds is important both in principle and for budgetary purposes. In the middle of this recession, it is especially important to assist cities and counties to collect the taxes they are owed. The alternatives would be a reduction in vital services and jobs at a time when the government safety net for very poor families who lack jobs has weakened significantly and increases in deep poverty in this recession are likely to be severe. This will impose significantly higher demands on local governments for police, housing and shelter, food, and other vital services. This bill offers a unique opportunity not just to provide hundreds of millions of dollars of desperately needed assistance at no cost to federal taxpayers, but also to protect honest taxpayers from an increase in local property taxes. Under this legislation, the only cost is to the delinquent taxpayer, who would finally be made to pay his or her outstanding tax obliga-

This proposed program would have no additional cost to the federal government. Local governments would pay the federal government the fee of \$25 for each offset refund. It would alleviate the administrative burden to Department of the Treasury by requiring the state taxing authority to act as the clearing-house. Therefore, the client base for the Department of the Treasury would not increase.

This concept of an offset originated as a way to assist states with securing child support arrearages. It was expanded to allow states to submit other delinquent claims against an individual's federal tax return. This program has been very successful for the states. Now this bill would expand its successful idea and concept to local governments in several billion dollars annually for local governments by effecting the collection of delinquent taxes.

The bill would instruct the Secretary of the Treasury, upon receiving notice from any eligible state on behalf of a local government, that a named person owes such local government a past-due, legally enforceable tax obligation and provide, consequently, for the reduction of the federal tax refunds payable to such person by the amount of such debt. That amount would be remitted to the state for payment to the affected local government, provide for notification to the state of the taxpayer's name, taxpaver identification number, address, and the amount collected; and notification of the person due the refund that it has been reduced by an amount necessary to satisfy a past-due, legally enforceable tax obligation.

This bill offers a unique opportunity to provide hundreds of millions of dollars of desperately needed assistance at little cost to federal taxpayers. For Virginia localities, it is estimated that it will bring in between 65-70 million dollars in revenue during the first year in the program. From its participation in the Federal Offset Program, for FY 2008, the Commonwealth of Virginia received over \$17 million dollars in offsets of federal income tax refunds and an additional \$5 million in offsets of the tax stimulus checks. This legislation has the official support of the National Association of Counties, the Government Finance Officers Association, the National League of Cities, the Treasurers' Association of Virginia, the United States Conference of Mayors, the Association of Public Treasurers of the United States and Canada, and the Conference of State Court Administrators.

This concept of an offset originated as a way to assist states with securing child support arrearages. It was expanded to allow states to submit other delinquent claims against an individual's federal tax return. This program has been very successful for the states. Now this bill would expand its successful idea and concept to local governments in all states. Doing so could potentially result in several billion dollars annually for local governments by effecting the collection of delinquent taxes. Under this legislation, the following order of priority for payment of an offset would be: (1) past-due federal income tax, (2) past-due state child support, (3) past-due federal government agency debt, (4) past-due state income tax, and (5) local government tax. The state taxing authority for each state would act as the clearinghouse for the local government tax debts, so this will not be an additional burden to Financial Management Services (which is a division of the United States Department of the Treasury administers the Federal Offset Program).

This is a bipartisan, good-government bill. If the legislation is passed, it would allow federal, state, and local governments to work together. Good citizens, who pay their taxes, will appreciate that the federal government and the state government are assisting localities to help local government collect from the delinquents. Each citizen should share in paying his fair share of taxes.

CONGRATULATING TRIXIE JOHNSON ON HER RETIREMENT

HON. JAMES L. OBERSTAR

OF MINNESOTA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. OBERSTAR. Madam Speaker, I rise today to congratulate Ms. Trixie Johnson on her recent retirement and to commemorate her dedicated service to the Southern California and to the nation throughout her distinguished career. Johnson served as the Director of Research for the Mineta Transportation Institute ("MTI") and where she worked for ten years before retiring this past May.

MTI was established by Congress in 1991 as part of the Intermodal Surface Transportation Efficiency Act and is located at San Jose State University (SJSU). This institution conducts research, education, and information and technology transfers specializing in transportation policy and management.

Ms. Johnson led a research program at MTI that brought together faculty and student researchers from SJSU, along with other academic institutions around the country, and the private sector to advance the body of knowledge in transportation policy and management from an intermodal perspective. In addition to publishing innovative reports and research findings, Ms. Johnson was deeply committed to recruiting, engaging, and training the nation's next generation of transportation planners and leaders.

Before joining the Mineta Transportation Institute in July 1999, Trixie Johnson served the full limit of two terms on the San Jose City Council—from 1991 through 1998. Due to Ms. Johnson's extensive experience, she has been recognized as a land use and environmental specialist by her peers. Her council service included two years as Vice Mayor and several years as chairperson of the city's Transportation, Development and Environment Committee.

Ms. Johnson has a long record of public service that included serving as chair of the Environmental Quality Committee and member of the Board of Directors for the League of California Cities; vice-chair of the Energy, Environment and Natural Resources Committee of the National League of Cities; and member of the Bay Area Air Quality Management District Board.

While her passionate work on transportation issues throughout her career will surely be missed, the many students and colleagues she has inspired will carry on her work as the nation seeks solutions to the transportation challenges of the 21st century.

Therefore, Madam Speaker, I would like to congratulate Trixie Johnson on her retirement, and wish her and her family the best of luck in this next chapter of their lives.

EARMARK DECLARATION

HON. TODD RUSSELL PLATTS

OF PENNSYLVANIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. PLATTS. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Department of Interior, Environment and Related Agencies Appropriations

Requesting Member: Congressman TODD RUSSELL PLATTS (PA-19)

Bill Number: H.R. 2996—Department of the Interior, Environment and Related Agencies Appropriations Act

Account: STAG

Legal Name of Requesting Entity: York City Sewer Authority

Address of Requesting Entity: 1701 Blackbridge Road, York, PA 17402

Description of Request/Justification of Federal Funding: The York City Sewer Authority is a public, municipal authority providing wastewater services for residential, commercial, and industrial users in an eight municipality service area. The York City Sewer Authority would use this funding to construct a new headworks facility, which includes the replacement of the building's heating and ventilation system and replacement of the activated carbon bed in the

building's odor control system. This is a good use of taxpayer funds because the combined improvements provide the most cost effective solution for updating infrastructure for the authority's residents and businesses.

EARMARK DECLARATION

HON. BILL POSEY

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. POSEY. Madam Speaker, pursuant to the Republican Leadership standards on earmarks as well as in accordance with Clause 9 of Rule XXI, I am submitting the following information regarding earmarks I received as part of H.R. 2647, the National Defense Authorization Act of Fiscal Year 2010.

Requesting Member: Congressman BILL POSEY

Bill Number: H.R. 2647

Account: Research, Development, Test & Evaluation, Defensewide

Legal Name of Requesting Entity: Soneticom

Address of Requesting Entity: 1045 South John Rodes Boulevard, West Melbourne, Florida 32904

Description of Request: This technology is important to helping our military and would be used for enhancement of a currently installed system for continued operations. \$3 million is provided for this program.

EARMARK DECLARATION

HON. DANIEL E. LUNGREN

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. DANIEL E. LUNGREN of California. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I rise today to submit the following information regarding an earmark I received as part of the Interior-Environment Appropriation.

The following earmark was requested by my office and is listed for funding in this bill:

City of Galt Wastewater Treatment Plant Requesting Member: DANIEL E. LUNGREN Bill Number: HR 2996

Account: EPA/STAG Water and Wastewater Infrastructure Project

Requesting Agency: City of Galt

Agency Address: 495 Industrial Drive, Galt, CA 95632

Amount: \$500,000

Description: The City of Galt is being forced to upgrade their existing wastewater treatment facility as a result of increased Federal water quality mandates. The new wastewater treatment facility will put Galt in to compliance with the National Pollutant Discharge Elimination System (NPDES). NPDES is the Federal system for the issuance of permits under Section 402 of the Federal Water Pollution Control Act Amendments of 1972, and many of the stringent NPDES permit requirements are based on National Toxics Rule (NTR). The NTR is an Environmental Protection Agency regulation that established numeric water quality criteria for priority inorganic pollutants for fourteen States and jurisdictions, including California,

into compliance with Section 303 (c)(2)(b) of the Clean Water Act.

Federal mandates dictate an increased number of contaminants for which the City must treat wastewater. The existing WWTP was not designed to meet most of the new standards, and therefore must be upgraded. The City is subject to mandatory Environmental Protection Agency (EPA) fines until such time as the project is completed. This project will enable the City of Galt to come into compliance with these Federal mandates.

This project represents an appropriate use of taxpayer funds as it responds to EPA mandates to improve wastewater treatment, to provide mitigation against a wider array of water contaminants, in a community acutely impacted by the capital demands of such undertaking.

INTRODUCING LEGISLATION PRO-VIDING STRONG LAND PROTEC-TION INCENTIVES

HON. EARL BLUMENAUER

OF OREGON

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. BLUMENAUER. Madam Speaker, more than 2 million farms make up America's rural landscape. Ninety-eight percent of these farms are owned by individuals, family partnerships, and family corporations, producing about 86 percent of U.S. agricultural products sold.

The most significant asset held by many of these farmers is their land. In some cases, when the owner of the farm dies, surviving family members must sell portions of the farm to cover their estate tax costs. Today I am introducing legislation to help ensure that families are not forced to sell the farm and that their land resources are available for agricultural and conservation use by future generations.

In 1997, in order to encourage the conservation of sensitive lands and farms, Congress enacted an estate tax exclusion for land placed under a conservation easement. 26 USC 2031(c). That law caps the exclusion at \$500,000. Given the significant rise in land values over the past decade, especially for agricultural regions near urbanizing areas, that cap is now too low to provide a meaningful incentive to many farmers.

My legislation updates and increases the exclusion to \$5 million. By increasing the current cap on the property value that can be ex-

cluded from an estate when the land is protected by a conservation easement from \$500,000 to \$5,000,000 (and by raising the exclusion percentage from 40 percent to 50 percent, this bill will encourage significant additional protection of farmland across our country.

The voluntary placement of a conservation easement on private land is a very effective and successful tool for protecting and conserving our nation's open spaces and sensitive lands. As the American Farmland Trust has written, "We strongly believe that the proper incentives are the most effective way of encouraging landowners to conserve land." This legislation provides strong land protection incentives and will result in the preservation of America's vital farm and ranchlands.

HONORING MR. JOHN GAMBLE

HON. JOHN T. SALAZAR

OF COLORADO

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. SALAZAR. Madam Speaker, I rise today to pay tribute to a respected leader of Southwest Colorado, Mr. John Gamble of Durango. Mr. Gamble has served the community of Southwest Colorado with distinction for 24 years and is announcing his retirement this month.

In 1985, Mr. Gamble took over the new Southwest Colorado Volunteers of America in Durango, Colorado. Under his strong and steady leadership, the agency grew to provide many critical services to the community. At the beginning of his tenure, Mr. Gamble helped to open a domestic violence shelter to provide a safe haven for those in need. And, in the early 1990s, he led the effort to open a much needed homeless shelter. To fund all of these critical services, Mr. Gamble opened a very successful thrift store and led many colorful and profitable fundraising events. In his spare time, Mr. Gamble served on the Durango City Council, including a term as the mayor of that proud city.

Madam Speaker, I commend Mr. John Gamble for his outstanding service and dedication to the residents of Southwest Colorado. Mr. Gamble clearly has a heart for service and the skills to get the job done. His community is a better place due to his efforts. While we will all miss Mr. Gamble's service and leadership, I ask that you join me in wishing him well upon his retirement.

PRELIMINARY COST ESTIMATE [Tacoma Emergency Intertie Booster Station]

EARMARK DECLARATION

HON. DAVID G. REICHERT

OF WASHINGTON

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. REICHERT. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Fiscal Year 2010 Interior, Environment, and Related Agencies Appropriations Act.

(1) \$333,000 for the City of Buckley, WA for an emergency intertie booster station.

Requesting Entity: City of Buckley, PO Box 1960, 933 Main Street, Buckley, WA 98321

Agency: Environmental Protection Agency Account: STAG

Funding requested by: Rep. DAVE REICHERT

The City of Buckley will construct an emergency intertie booster station to allow the City to use water from the City of Tacoma in an emergency. The City of Tacoma water system in this area operates with a hydraulic grade line of 810 feet. The City of Buckley water system operates with a hydraulic grade line of 882 feet. Therefore the booster station is required to overcome a static head of approximately 72 feet. The City's largest water source is the S. Prairie Creek surface water source. The City's water right for this source is 900 gpm. To allow the system to operate effectively with the S. Prairie Creek source out of service, the booster station will have a capacity of 900 gpm. The booster station will be constructed in right-of-way in a location close to existing City of Buckley and City of Tacoma water infrastructure.

Finance Plan:

City of Buckley, Budget Details: This request is for federal funding in the amount of \$550,000 to construct an emergency water intertie and booster station between the City of Tacoma's transmission main and the City of Buckley's water system. As illustrated below in the engineering cost estimate, approximately, \$121,000 is for administration & engineering; and \$485,000 for construction. The City of Buckley is currently working on a major flood damaged repair to our primary transmission water main, but will be able to allocate \$57,000 as a match towards this project.

	Item	Quantity	Unit price	Amount
1. 2 3 4 5 6 7 8 9 10 11 12	Mobilization/Demobilization Site Work Erosion Control Locate Existing Utilities Intertie Booster Pumps (2 x 450 gpm) Booster Station Building (12" x 16") Pjinig, Valves, and Appurtenances Site Fencing Surface Restoration Electrical, Telemetry, and Instrumentation Primary Power Service Subtotal Sales Tax (8.4%)		\$34,000 15,000 2,500 2,000 32,000 52,000 80,000 28 5,000 105,000	\$34,000 15,000 2,500 2,000 32,000 52,000 80,000 5,600 5,000 105,000 173,100 373,100
	Subtotal Contingency (20%) TOTAL ESTIMATED CONSTRUCTION COST Engineering and Administrative Costs (25%) R.O.W., Easement and/Or Land Acquisition			404,440 81,060 485,500 121,000

CONGRESSIONAL RECORD — Extensions of Remarks

PRELIMINARY COST ESTIMATE—Continued [Tacoma Emergency Intertie Booster Station]

 Item
 Quantity
 Unit price
 Amount

 TOTAL ESTIMATED PROJECT COST (2008 Dollars)
 607,000

2) \$2,150,000 for Mt. Rainier National Park for Land Acquisition.

Requesting Entity: U.S. Department of Interior, National Park Service, 1849 C Street, NW, Room 7256, Washington, DC 20240

Agency: Department of Interior Account: National Park Service

Funding requested by: Rep. DAVE REICHERT, JIM MCDERMOTT

This land acquisition will ensure visitors' access to Mt. Rainier National Park at the northwest entrance. The Carbon River Road has frequently been washed out, preventing visitors from reaching the Ipsut Creek campground and picnic area, as well as day-use parking for access to the Carbon Glacier and Wonderland Trail. To address this problem, and to eliminate the considerable maintenance costs necessitated by the frequent flooding, Congress passed an expansion of the park's northwestern boundary three miles along the Carbon River Valley. The addition of these lands will allow the National Park Service to establish a new campground with associated roads and parking, new hiking trails, and riverfront fishing areas. The expansion will also afford much needed protection to the beautiful Carbon River Valley, conserving habitat for endangered and threatened species. The valley contains one of the last inland old-growth rainforests in the United States, and connects wildlife corridors from the park to Puget Sound. Among the property included within the newly expanded park boundary is the 240acre Carbon River Gateway. This parcel lies adjacent to Forest Service lands that link current Park Service lands with the privately owned parcels within the expansion area.

Finance Plan: The National Park Service will use these funds to cover the fair market value (FMV) of two properties located within the expanded boundaries of Mt. Rainier National Park in Washington State. The actual amount to be expended will depend on federally approved appraisals of the parcels. \$2,500,000 is the best estimate of the cost at this time. Due diligence costs for the Carbon River Gateway property will be borne by the The Trust for Public Land and the acquisition management account of the National Park Service. There is no cost-share requirement for this program. This request is consistent with the authorized purposes of the Land and Water Conservation Act and Public Law 108-312, which authorizes land acquisition in this area of the park.

This office conducted site visits to meet with representatives from both of the projects listed above.

EARMARK DECLARATION

HON. MIKE ROGERS

OF ALABAMA

IN THE HOUSE OF REPRESENTATIVES $Thursday,\,June\,\,25,\,2009$

Mr. ROGERS of Alabama. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the fol-

lowing information regarding earmarks I received as part of H.R. 2996—Interior, Environment, and Related Agencies Appropriations Act, 2010.

Requesting Member: Congressman MIKE ROGERS (AL)

Bill Number: H.R. 2996

Account: EPA. STAG account. \$275.000

Legal Name of Requesting Entity: East Alabama Water Sewer and Fire Protection District

Address of Requesting Entity: P.O. Box 37, Valley, Alabama 36855

Description of Request: "Wastewater System Planning" Taxpayer justification—It is my understanding that the funding would be used to map the District's entire sanitary sewer system, analyze specific areas within the existing sanitary sewer system and, identify areas within the system where modifications and upgrades must be performed.

Requesting Member: Congressman MIKE ROGERS (AL)

Bill Number: H.R. 2996

Account: NPS, Save America's Treasures account. \$100.000

Legal Name of Requesting Entity: Talladega College, Talladega, AL

Address of Requesting Entity: 627 West Battle Street, Talladega, Alabama 35160

Description of Request: "Swayne Hall Historic Restoration and Renovation" Taxpayer justification—It is my understanding that the funding would be used to restore and upgrade Swayne Hall, the original building that housed Talladega College (built in 1852–53).

EARMARK DECLARATION

HON. JOHN L. MICA

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. MICA. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information for publication in the CONGRESSIONAL RECORD regarding earmarks I received as part of H.R. 2996—Department of the Interior, Environment, and Related Agencies Appropriations Act. This legislation appropriates \$500,000 in the Department of the Interior, Environment, and Related Agencies Appropriations Bill, for land acquisition for the Florida Trail Association. The entity to receive this funding is the Florida Trail Association, 5415 SW 13th St., Gainesville, FL.

Funding will be used for the acquisition of land to protect 16 critical segments of the Florida National Scenic Trail. Designed by Congress in 1983, the Florida National Scenic Trail is an essential part of maintaining Florida's natural beauty for future generations and serves as an inspirational, educational tool for conservation efforts in the state.

BOULDER, COLORADO'S SESQUICENTENNIAL

HON. JARED POLIS

OF COLORADO

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. POLIS. Madam Speaker, I rise today in recognition of the 150th birthday of my home town, Boulder, Colorado.

Boulder is a special place. When I meet people from other parts of the country who have passed through our fair state, the very mention of Boulder always brings a smile to their face. On February 10, 1859, settlers from the Nebraska Territory (the beginnings of a world renowned college football rivalry perhaps) founded the "Boulder City Town Company." From its birth, our city has been a shining example of what is possible with a civic minded populace.

From our humble beginning as a supply town for miners, to the national leader in smart growth and environmental stewardship we are today, Boulder has always been dedicated to the careful balance of entrepreneurship and wise land use.

The beauty of our natural surroundings has caused generations of Boulderites to value our town and to embrace a life of grace rather than greed. Over the years, Boulder residents have taken extraordinary measures to mesh the human environment seamlessly with our natural environment. Through a citizen initiative, we brought Frederick Law Olmstead to Boulder at the beginning of the 20th century to craft a vision plan for our city designed to highlight our natural treasures such as Boulder Creek and the Flatirons. In 1959, our residents took action to create the "blue-line" to preserve the mountain backdrop, and made Boulder the first city in the nation to impose a tax for land conservation. We purchased the Arapahoe Glacier to ensure a source of drinking water for our residents and agricultural uses. Boulder was also the first community to adopt a "carbon tax" to deal with the crisis of climate change. Today, our open space program has made Boulder the envy of many an over-crowded community and is now a model duplicated state and nationwide.

Boulder's commitment to the environment is equaled by its commitment to the community and especially to education. The Colorado Territory's first class of high school seniors graduated in Boulder. When Colorado became a state in 1874, Boulder citizens pooled their resources and raised \$15,000, a fortune in those days, to build the state's first public university. The vibrant culture surrounding this top tier institution of higher learning—full of philosophical debate, football, and foreign exchange—has created the colorful lifestyle that makes our town unique.

Our highly skilled workforce has attracted world class employers, such as IBM, Ball Aerospace, and Roche Pharmaceuticals Boulder, as well as some of the nation's premier research institutes, such as the National Oceanic and Atmospheric Agency (NOAA), the

National Institute of Standards and Technology, and the National Center for Atmospheric Research (NCAR).

The heart of Boulder is our award winning Downtown. Boulder's small businesses are the life blood of our community and give Boulder the special sense of place that is loved by residents and visitors alike. For more than 50 years, Boulder residents have relied on the Boulderado, McGuckins Hardware, and The Sink. The Pearl Street Mall and our Downtown, both easily accessible by pedestrians, drivers and bicyclists, are national models of smart urban development. The eclectic mix of housing, independent retailers and commercial enterprises give Boulder an economic driver that many larger communities envy.

I congratulate my fellow Boulderites on 150 years of progress and prosperity, and look forward with great anticipation of what the future holds for our diverse and vibrant community. Happy Birthday, Boulder.

EARMARK DECLARATION

HON. FRANK A. LOBIONDO

OF NEW JERSEY

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. LoBIONDO. Madam Speaker, as per the requirements of the Republican Conference Rules on earmarks, I secured the following earmarks in H.R. 2996:

Requesting Member: Congressman FRANK LOBIONDO (NJ-02) (along with Reps. ADLER, SIRES and ROTHMAN)

Bill Number: HR 2996

Account: Fish and Wildlife Service, Land Acquisition

Legal Name of Requesting Entity: New Jersey Audubon Society

Address of Requesting Entity: 11 Hard-scrabble Road, Bernardsville, NJ 09724.

Description of Request: Provide an earmark of \$1,100,000 for a land acquisition project at Edwin B. Forsythe National Wildlife Refuge.

Requesting Member: Congressman FRANK LOBIONDO (NJ-02) (along with Reps. SIRES and ROTHMAN)

Bill Number: HR 2996

Account: Fish and Wildlife Service, Land Acquisition

Legal Name of Requesting Entity: New Jersey Audubon Society

Address of Requesting Entity: 11 Hard-scrabble Road, Bernardsville, NJ 09724.

Description of Request: Provide an earmark of \$2,000,000 for a land acquisition project at National Wildlife Refuge.

 $\begin{array}{c} \text{HOMAGE TO MR. GEORGE A.} \\ \text{DALLEY} \end{array}$

HON. YVETTE D. CLARKE

OF NEW YORK

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Ms. CLARKE. Madam Speaker, I rise today extremely humbled and privileged to pay homage to Mr. George A. Dalley, who will retire as

Counsel and Chief of Staff to the Honorable Charles B. Rangel of the 15th Congressional District of New York. Chairwoman, anyone who has worked with Mr. Dalley, knows that he is extremely fond of Congressional Records. So it is more than appropriate that I submit my sentiments and testimony about him into the Record for posterity.

George A. Dalley is not only a highly-successful leader and an amazing human being, he has been a true supporter and friend to all who have crossed his path. I especially feel blessed to have him serve as my mentor and advisor, who was integral in helping me acclimate and adapt to the rigors of Congress, even before I arrived in D.C. I am also blessed to share with Mr. Dalley a rich Jamaican heritage and common lineage. The pride he exhibits in heritage and his work with the Caribbean American community has truly been an inspiration and motivation for my advocacy on behalf of Caribbean Americans across this nation and their countries of origin.

General Douglas McArthur once said, "A true leader has the confidence to stand alone, the courage to make tough decisions, and the compassion to listen to the needs of others. He does not set out to be a leader, but becomes one by the quality of his actions and the integrity of his intent."

Mr. George A. Dalley, your example has been a guide to us here on Capitol Hill and your leadership is an example for generations to come. I wish you all the best in the next stage of your life. Your presence on the Hill will sorely be missed.

THE AMERICAN CLEAN ENERGY AND SECURITY ACT OF 2009

HON. NICK J. RAHALL II

OF WEST VIRGINIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. RAHALL. Madam Speaker, the Congress would be unwise to sit by and simply allow the Environmental Protection Agency to regulate a reduction in greenhouse gas emissions, as the agency has been mandated to do by the Supreme Court. Similarly, it would be a mistake to sit back and allow other countries to devise international rules that will affect America's economic and energy interests.

I do not agree with those who advocate for sitting on our hands and just saying NO to everything, sight unseen. The international community has no interest in protecting American businesses, and the Environmental Protection Agency is not required by the Supreme Court to consider the views of our constituents or the economic consequences to our communities

I believe America is the one nation best equipped to lead such a multinational effort and, in doing so, to strike a balance between environmental preservation and the preservation of jobs. The hands-off approach of recent years did nothing to help promote new energy technologies, or to advance carbon capture and sequestration, or to protect American jobs.

It is evident that wishing that this complex issue would simply go away will not lead to

better results for our Nation or the people we represent. And "just saying no" to any and all proposals, sight unseen, is unrealistic and irresponsible.

For those reasons, I chose to work with my colleagues and with numerous stakeholders—including the coal industry, manufacturers, and labor—to positively influence this bill and America's climate change strategies. And for those reasons our coal miners and responsible industry members have been at the table, too, rather than on the sidelines.

I thank Chairman WAXMAN, who has made many concessions in this bill, and I thank leadership for listening to my concerns about this legislation and moving to help address them.

As well, I commend my colleague RICK BOUCHER, from southwestern Virginia, who serves on the Energy and Commerce Committee and worked in determined fashion to make improvements to the bill that we both sought. I am grateful that he has been so welcoming of my views and supportive of our interests—such as ensuring the availability of \$10 billion to advance carbon capture and sequestration technologies and other changes that are beneficial to the people of our neighboring districts.

While this bill is greatly improved from the discussion draft that was first circulated in March of this year—and opponents were saying NO even before that draft was written—more improvements are needed to gain my support.

Coal does much more than keep the lights on in big cities across America. In my district, it covers the mortgage, puts food on the family dinner table, and keeps open the doors of small businesses. While the emissions target in the early years of this program has been lowered from the 20% cap initially contained in this bill, there remains widespread concern that even the reduced cap—17% in 2020—is still too high and too soon to incentivize rapid development and deployment of carbon capture and sequestration technologies, so as to ensure coal mining jobs for the future. We must allow time for expensive clean coal technologies to come on line.

These technologies are critical to lowering emissions across multiple sectors of our economy. And they are necessary for keeping hardworking coal miners in the jobs they want, providing power for the country they love.

Madam Speaker, today, I cannot cast my vote for this bill.

PERSONAL EXPLANATION

HON. JOSEPH CROWLEY

OF NEW YORK

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CROWLEY. Madam Speaker, on June 25, 2009, I was absent for eight rollcall votes because I was in a meeting at the White House with President Obama on immigration reform. If I had been here, I would like the RECORD to reflect that I would have voted:

Yes on rollcall vote 453, Yes on rollcall vote 454, No on rollcall vote 455, No on rollcall vote 456, Yes on rollcall vote 457, Yes on rollcall vote 458, No on rollcall vote 459, and Yes on rollcall vote 460.

EARMARK DECLARATION

HON. LEE TERRY

OF NEBRASKA

IN THE HOUSE OF REPRESENTATIVES Thursday, June~25,~2009

Mr. TERRY. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of the Department of the Interior, Environment and Related Agencies Appropriations Bill for Fiscal Year 2010 (H.R. 2998).

Congressional District received \$500,000 for the City of Omaha Public Works Department, located at 1819 Farnam Street, Suite 600, Omaha, NE 68183. This money is from the State and Tribal Assistance Grant (STAG) account, and will be used by the City of Omaha for the design and construction of improvements to portions of the City's combined sewer system. These projects will allow the City of Omaha to reduce the amount of sewage overflowing to receiving streams. These efforts are consistent with the latest requirements from the Environmental Protection Agency (EPA) and Nebraska Department of Environmental Quality (NDEQ) to achieve the goal of improved water quality in the United States.

A TRIBUTE TO MAJOR EARL G. ANDERSON, JR.

HON. DAN BURTON

OF INDIANA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. BURTON of Indiana. Madam Speaker, I rise today to honor the life and military service of Major Earl G. Anderson, Jr. who was recently named the 2009 Aviator of the Year at the Indianapolis Air Show.

Born in Rockford, Illinois in 1920, twenty-two-year old Earl Anderson, Jr. enlisted in the United States Army Air Corps in April of 1942 leaving behind his wife Geraldine to serve his country in its time of need. By September 1943, Aviation Cadet Anderson had completed his State-side training and was assigned to the United States 15th Air Force flying The Consolidated B–24 Liberator bomber over Europe. The B–24 was an American heavy bomber that still holds the record as the most produced U.S. military aircraft.

Between December 1943 and June 1944 Major Anderson flew fifty-one successful combat missions against enemy targets before being shot down. He spent the remainder of the war as a Prisoner of War (POW) in a camp outside Munich, Germany. For his heroic and courageous flying, Major Earl Anderson, Jr. was awarded by order of the President of the United States the Distinguished Flying Cross, the Air Medal with 6 clusters, and the Distinguished Unit Badge with one cluster.

Earl's prison camp was eventually liberated by allied troops in 1945 and after debriefing Earl was sent back to the United States to spend some time on furlough before returning to duty. Major Anderson continued serving both on active duty and as a member of the Reserves until he was Honorably Discharged in 1961.

Fortunately for all Hoosiers, Earl's passion for aviation stayed with him after he left the service and he's been an active part of Indiana's aviation community for many years. Earl and his wife Geraldine (Gerrie) have been married for 67 years. They have two daughters, Marilyn and Barbara, and five grand-children.

I ask all of my colleagues to join me now to thank Major Earl Anderson, Jr. for his service and his sacrifices for our country, and to congratulate him on being named the 2009 Indiana Aviator of the Year.

 $\begin{array}{c} \text{HONORING LT. COLONEL CHARLIE} \\ \text{PARNELL} \end{array}$

HON. JOHN T. SALAZAR

OF COLORADO

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. SALAZAR. Madam Speaker, I rise today to pay tribute to an unsung hero from Southwest Colorado; Lt. Colonel Charlie Parnell of Durango. Charlie Parnell has selflessly and tirelessly been serving the veterans of Southwest Colorado for many years and it is time that he is recognized for this service.

In 1988, Lt. Colonel Parnell retired from the United States Air Force after 26 years of honorable service, including tours of duty in Germany, Thailand, Vietnam, Korea, Turkey and Saudi Arabia. He is the proud recipient of the Bronze Star.

After struggling for 15 years to receive the disability benefits he had earned from the Department of Veterans Affairs, Lt. Colonel Parnell dedicated himself to helping his fellow veterans wade through the challenging VA benefits system so they too would receive the compensation they had earned. Since then, he has helped over 1000 veterans receive their benefits, and has done so completely at his own expense.

It is this type of above the call-of-duty service that makes this nation great. And it is this kind of service that deserves all of our recognition. When asked why he does what he does for his fellow disabled veterans, Lt. Colonel Parnell says simply, "Because I can."

Madam Speaker, today I rise to join the 1000 veterans in Colorado's Southwest region to thank and honor Charlie Parnell for his service to this country and to my constituents in the Third Congressional District.

Thank you, Lt. Colonel Parnell for your hard work and dedication to our nation.

EARMARK DECLARATION

HON. JOHN L. MICA

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. MICA. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding an earmark I received as part of H.R. 2996, the Interior, Environment and Related Agencies Appropriations Act. This legislation appropriates \$500,000 to the Department of the Interior National Park Service account for the Castillo de San Marco National Monument in the City of St. Augustine, Flor-

ida, which is in my district. The entity to receive this funding is the U.S. Department of Interior, National Park Service, Castillo de San Marco National Monument located at 1 South Castillo Drive, St. Augustine, FL 32084.

The City of St. Augustine, founded 444 years ago in 1565, is our nation's oldest enduring settlement of European design. Prominent within the Historic Spanish Colonial District, which features thirty-six original colonial buildings, is the majestic Castillo de San Marcos stone fortress that began construction in 1672.

As the only existing 17th century fort in North America, the Castillo de San Marcos is an important historical and cultural landmark that features the oldest surviving masonry in our nation. About 538,500 people visited the Castillo in 2008, hosting as many as 3,751 tourists in just one day.

Authorized by Public Law 108–480, this funding will be used for the planning and design phase of the Castillo de San Marcos National Monument Restoration Project, as outlined in Alternative C of the March 2007 Final General Management Plan and Environmental Impact Statement.

This planning will help preserve and expand the Castillo by constructing a visitor center in the Spanish Quarter of St. Augustine and removing a portion of the visitor parking lot to restore the glacis.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. BILL PASCRELL, JR.

OF NEW JERSEY

IN THE HOUSE OF REPRESENTATIVES

Wednesday, June 24, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2647) to authorize appropriations for fiscal year 2010 for military activities of the Department of Defense, to prescribe military personnel strengths for fiscal year 2010, and for other purposes:

Mr. PASCRELL. Mr. Chair, I would like to take this opportunity to thank Chairman SKELTON and his Committee for the important work they have done on this legislation and the strides they have made to ensure that individuals with traumatic brain injury (TBI) are identified and afforded the benefits that they deserve.

TBI is the signature injury of our current conflicts overseas. As many as 20 percent of the 1.8 million deployed troops—or an estimated 360,000 soldiers—have sustained traumatic brain injuries while in Iraq and Afghanistan. Unfortunately, many of these men and women in uniform are falling through the cracks. We must ensure that these individuals are properly identified and provided with the world class health care that they deserve. H.R. 2647 takes important steps to achieving both of these goals.

First, I applaud the inclusion of language submitted by myself and Congressman TODD PLATTS, who is both a member of the Armed Services Committee and serves as my Co-Chair on the Congressional Brain Injury Task Force, that calls on the branches of the Armed Services to implement long-term tracking for

blast exposures, as the Army National Guard (NG) has already done. The NG initiative records the exposure to blasts in troops' personnel records in order to document the incident in the event of problems associated with traumatic brain injury or exposure to contaminants. This database will help determine eligibility for appropriate treatment, care, and disability entitlements. A comprehensive blast tracking system will also assist in efforts to research blast injuries and mild TBI and improve outreach, education, and follow-up for injured personnel who might otherwise fall through the cracks.

Second, I am appreciative of the inclusion of language that I submitted regarding the awarding of the Purple Heart to individuals who have sustained traumatic brain injuries, which calls on the Secretary to review its policies and procedures for determining eligibility and awarding of the Purple Heart as it relates to TBI. Media reports and anecdotal evidence have suggested that Purple Hearts may have been awarded inconsistently to service personnel who have sustained combat-related TBIs, suggesting that individuals with more severe TBIs may be eligible for the distinguished Purple Heart while individuals with less severe ones often receive refusals.

We believe that the Purple Heart criteria set out in regulation encompass soldiers who sustain a TBI or concussion as the result of enemy action. The Department of Defense's own Legislative Affairs has, however, stated that a brain injury that requires minimal medical attention would not suffice. I would caution against the use of such absolutes in the face of uncertainty about the effects of blast-related TBIs. Because the field of science still knows relatively little about effective interventions and the long-term consequences of traumatic brain injuries, particularly mild ones and those caused by blasts, the Department of Defenses' interpretation of treatment should not preclude injured soldiers who fulfill all other Purple Heart criteria from receiving the recognition and benefits they deserve.

Third, I am pleased to see the inclusion of legislation introduced by Congressman WAL-TER JONES, of which I am an original co-sponsor. This important language permits separated service members to seek a review of their discharge if their post-traumatic stress disorder (PTSD) or TBI was not taken into consideration when determining their separation and mandates a physical exam for active duty service members before an administrative separation proceeding if the service member had been diagnosed with PTSD or TBI. The effects and prevalence of PTSD and TBI have become too harsh and too widespread for our military leaders to overlook, and ensuring that the full facts of soldiers' injuries are considered upon discharge is the least we can do to ensure these individuals receive the care and benefits they deserve.

Finally, I praise the Committee for its recognition of the need for civilian and military collaboration in the science of the brain by providing for a Visiting NIH Senior Neuroscience Fellowship Program. This will provide an important opportunity for the military to learn from the work occurring at the National Institutes of Health on neuroscience and vice versa.

Thank you again to Chairman SKELTON, and I look forward to continuing to work with the Committee as we make further improvements

to the care and benefits that we provide to the brave men and women that put their lives on the line for our freedom.

TRIBUTE TO LARRY E. REIDER

HON. KEVIN McCARTHY

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES Thursday, June~25,~2009

Mr. McCARTHY of California. Madam Speaker, I rise today to honor Dr. Larry E. Reider, a resident and community leader from Bakersfield, California, on his retirement as Kern County Superintendent of Schools and to recognize his remarkable and distinguished leadership while serving the students of Kern county. Over the last 44 years, Larry has been instrumental in advancing Kern County's public education system.

Larry was born in the State of Washington and was raised on his family's farm. In 1965, he earned his bachelor's degree from Central Washington State University and made the move to Kern County to teach in the Arvin Union School District. A dedicated math teacher, Larry spent 19 years in Arvin schools' classrooms and later as a school administrator. He also earned advanced degrees from the California Polytechnic State University, San Luis Obispo and the University of Southern California.

In 1984, Larry joined the Office of the Kern County Superintendent of Schools as a district advisory consultant. Recognizing his dedication and commitment to the schools, students, and parents of the community, the Kern County Board of Education tapped him to be the Kern County Superintendent of Schools in 1999.

Since becoming Kern County Superintendent of Schools, Larry has been integral to a plethora of local initiatives and projects designed to enhance the reading, writing, and mathematical skills of elementary school students in the county. For instance, he partnered with the Bakersfield Californian to develop the Community Reading Project, which places volunteer reading tutors throughout various classrooms in the county to aid second graders in becoming more proficient readers. Additionally, he developed the Kern Reading Collaborative, an association that analyzes which reading programs are productive and investigates ways those programs can reach more students. Larry also established the Do The Math program, a bi-weekly television homework help channel where teachers assist students in both English and Spanish with their math problems both on and off the air, as well as Ready to Start, a summer pilot program that prepares pre-kindergartners to learn more efficiently as they begin their academic career.

As a former teacher, Larry was always cognizant that highly qualified and effective teachers in the classroom are the best recipe for successful students. To that end, he cochaired a task force which formulated various approaches to recruit and retain highly qualified teachers in Kern County schools and get them in the classroom. This initiative has been highly successful, and our schools have some of the best and brightest teachers in the region. He also recognized that new generations of students are exceedingly technology savvy,

and so opened a learning center that helps teachers integrate technology into the class-room to better teach and engage their students. This not only helps teachers be more effective, it also helps ensure their students continue to develop the skills necessary to be successful in the technology-driven workplace of today.

Not only has Larry harnessed cutting-edge technology in the classroom, he has also been an advocate to use technology to help keep our environment clean. Under Larry's leadership, Kern County schools are in the process of converting their current diesel school bus fleet to clean burning Compressed Natural Gas (CNG). More than half of the diesel buses have already been replaced. As part of this initiative, in 2006, the Superintendent of Schools opened a CNG fueling station, which serves Kern County school buses and is open to the public. As Kern County unfortunately has some of the dirtiest air in the United States, this initiative is extremely important to helping clean the air in the Central Valley.

Larry is also active in several community organizations, including the Bakersfield Chamber of Commerce, Kern County Network for Children, United Way, Rotary Club of Bakersfield, and Vision 2020. He has also been honored by several local and state organizations over the years for his leadership by organizations such as the Community Action Partnership of Kern, California State University-Bakersfield School of Education, Association of California School Administrators, California Teachers Association, Kern Council of Governments, and Kern Reading Association.

Larry exemplifies how one can serve their community with great enthusiasm, fortitude, and dedication. Over the years, I have enjoyed working with Larry and always found his perpetual optimism infectious. There was never an obstacle he did not challenge headon in his amiable, but no-nonsense style, and fight for the best interests of the students of Kern County. After 44 years in public service, I know that Larry looks forward to spending more time with his wife, Sandy, a retired junior high language arts and drama teacher, and his daughter Mikhail. I know that Larry will be missed in the Kern County public education system, and I salute his lifetime of service and wish him the best as he begins this new chapter in his life.

EARMARK DECLARATION

HON. LEONARD LANCE

OF NEW JERSEY

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. LANCE. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, The FY 2010 Department of the Interior, Environment, and Related Agencies Appropriations Act:

Agency: Environmental Protection Agency Account: STAG Water and Wastewater Infrastructure Project

Amount: \$500,000

Project: Railroad Avenue/Main Street stormwater improvements, Borough of Califon, NJ

Recipient: Borough of Califon, 39 Academy Street, Califon, NJ 07830

The funding would be used for reconstruction of the storm water conveyance system to reduce flooding, meet storm water management standards, and to enhance storm water quality in the Borough of Califon, New Jersey.

Much of the historic core of the Borough of Califon was developed during the mid-late 19th century. Drainage systems were constructed to collect and deliver stormwater to waterpower sites. Considerable segments of the original drainage infrastructure remain and are antiquated. The current drainage ways are susceptible to frequent flooding. During flooding events, recharge to groundwater is reduced, suspended solids and floatables bypass normal catchments, and septic systems are inundated. The quality of receiving waters is degraded.

A reoccurring flooding problem exists along an unnamed tributary which traverses a natural, wooded area between Academy Street and Main St. Severe flooding occurs as flows overtop the existing channel and then sheet overland along Railroad Avenue and Main Street. Flooding along the area reoccurs on a regular basis and results in the degradation of water quality of the downstream receiving watercourses.

In general, the problem is inadequate capacity of the conveyance system of open channels, pipes and culverts. Reconstruction of the system is needed to reduce flooding, meet current stormwater management standards and to enhance stormwater quality.

This project is consistent with environmental criteria established by the State of New Jersey to improve stormwater systems and water quality. Since the stormwater from the area of this project enters the South Branch of the Raritan River, which flows directly through the center of the Borough of Califon, the benefits of this project are far reaching.

IN REMEMBRANCE AND RECOGNITION OF TIMOTHY MICHAEL ELLIOTT

HON. DENNIS J. KUCINICH

OF OHIO

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. KUCINICH. Madam Speaker, I rise today in remembrance of Timothy Michael Elliott and in recognition of his service to our country and his dedication to the City of Cleveland, Ohio. Tim lived and worked in the Detroit-Shoreway neighborhood of Cleveland's west side in my district. He sought to preserve Cleveland's historic housing one house at a time and devoted his time to ensuring the historic integrity of each home he restored.

As a young man, Tim served in the U.S. Army and worked as a draftsman for Hauserman Inc., and B.F. Goodrich. He also worked for Century 21 Real Estate and led the Nolasco Housing Corporation, a non-profit development organization affiliated with the neighborhood Catholic Church, Our Lady of Mount Carmel. In addition to his work, he dedicated his life to the City of Cleveland. He was proud of the west side neighborhood in which he lived and became concerned about deteriorating conditions. He began to buy and repair neighboring homes to improve the housing of the neighborhood. He rarely worked on houses he could not walk to from

his Herman Avenue home. "He could walk into a place that was falling apart and not see it as it was but what it could be," said Judge Ray Pianka, a neighbor and friend as well as Cleveland's municipal housing judge. "He has taken some homes that appeared to be beyond saving and made them showplaces."

Also within walking distance of their home was Edgewater State Park, a beautiful park along the Lake Erie shore with beaches, boating, picnic areas, and other recreational activities. Tim and his wife Mimi, along with other neighbors and local officials, started the Friends of Edgewater Park to promote and preserve this wonderful amenity in their neighborhood. Tim is survived by his wife Mimi, his son Timothy Michael Jr., his granddaughter Brooke Elliott, and his many friends.

Madam Speaker and colleagues, please join me in celebrating the life of Tim Elliott, and in recognizing his dedication to the betterment of our community. His service and leadership in the west side neighborhood of Cleveland inspired us all to work toward neighborhood preservation.

TIMOTHY ELLIOTT, 63, FIXED UP OLD HOMES ON THE WEST SIDE—OBITUARY

(By Grant Segall)

Tim Elliott helped to turn around the West Side. The painstaking renovator and Realtor helped revive Ohio City and Detroit-Shoreway in the past four decades, boosting a couple of hundred properties and winning over skeptical investors, bankers and officials.

Elliott died Friday in his West Side home, one of his pet projects, a 3,200-square-foot Italianate from the 1860s. He was 63 and had struggled for several years with strokes.

"He could walk into a place that was falling apart and not see it as it was but what it could be," said Raymond Pianka, Cleveland's housing judge, a neighbor and the employer of Elliott's widow, Mimi. "He has taken some homes that appeared to be beyond saving and made them showplaces."

Elliott liked not just walking into a place but walking to it. He'd turn down a project if he and his small crew couldn't walk there from their homes.

He hoped each project would ripple through the neighborhood. He preferred corner homes, helping two blocks instead of one

He liked to install modern conveniences such as whirlpools while highlighting history

tory.
"There's not a newer old house in the city," he boasted about one salvage job.

He bought homes suffering from water, waste and vandals and sold them for several times his purchase price. He'd comb rural Ohio for replacement parts or make them himself, from tiles to spindles.

Elliott said he'd decided at age 7 to spruce up old homes. He was born on the East Side, the seventh of eight children. His father was an engineer, and several brothers followed suit.

He left Cleveland at 12 and graduated from Willoughby South High School. He enlisted in the U.S. Army, making photographs and maps serving partly in South Korea

maps, serving partly in South Korea. Elliott returned to Cleveland in the early 1970s and helped Hauserman Inc. draft work for projects such as the Americana high-rise in Euclid. He later drafted pipes and buildings for Goodrich in Solon.

On the side, he got an associate's degree in arts at Cuyahoga Community College.

He started renovating West Side homes about 1978. He owned about 16 buildings over the years and handled many others as well.

He worked for Century 21 and led Nolasco Housing Corp., a development group affiliated with Our Lady of Mt. Carmel Church, in the 1980s.

Elliott was honored by Cleveland Magazine and the Cleveland Restoration Society.

On the side, he liked to bicycle, raise terriers and sail. He put together a 27-foot boat from a kit.

EARMARK DECLARATION

HON. JEFF MILLER

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. MILLER of Florida. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of the Fiscal Year 2010 Department of Interior and Environment Appropriations request.

Requesting Member: Congressman JEFF MILLER

Project Name: Santa Rosa County for Navarre Beach water clarifier

Account: STAG Water and Wastewater Infrastructure Project

Legal Name of Requesting Entity: Santa Rosa County, FL

Address of Requesting Entity: 6495 Caroline Street, Milton, FL 32570

Description of Request: \$220,000-Santa Rosa County for Navarre Beach Water Clarifier, Milton, Florida. I requested these funds to allow for Navarre Beach residents to have a safe and reliable source of water. Currently there is no reliable backup beyond three days for citizens. It would also increase compliance with both State and Federal regulations. The entity to receive funding for this project is Santa Rosa County, Florida, located at 6495 Caroline Street, Milton, FL 32570. The funding would be used to complete the Navarre Beach Water Reclamation Facility clarifiers to protect the area's water quality. I certify that this project does have a direct and foreseeable effect on the pecuniary interest of my spouse or me. Consistent with the Republican Leadership's policy on earmarks, I hereby certify that this request (1) is not directed to any entity or program named after a sitting Member of Congress; (2) is not intended for a "front" or "pass through" entity; and (3) meets or exceeds all statutory requirements for matching funds where applicable.

EARMARK DECLARATION

HON. TED POE

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. POE of Texas. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2892, Department of Homeland Security Appropriations Act, 2010:

Requesting Member: Congressman TED

Bill Number: H.R. 2892, Department of Homeland Security Appropriations Act, 2010

Account: FEMA, Predisaster Mitigation Legal Name of Requesting Entity: CHRISTUS St. Elizabeth Hospital Address of Requesting Entity: 2830 Calder Street, Beaumont, TX 77702

Description of Request: I have secured \$250,000 in funding under FEMA's Predisaster Mitigation account to allow for the purchase of a 2.5 megawatt diesel generating plant to ensure sanitary and safe conditions for both current and potential patients during disasters. Although the Hospital has basic generator capabilities to sustain life support, Hurricanes Rita and Ike have proved that this basic capacity is insufficient. During Hurricane Ike, 190 patients were unable to be evacuated and as commercial utilities were shut down, basic hospital operations were compromised. The generator will make certain that the Hospital remains serviceable by ensuring that power and water are functional; thus, allowing the Hospital to maintain its mission of providing essential medical care to the residents of southeast Texas.

EARMARK DECLARATION

HON. KEN CALVERT

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. CALVERT of California. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010.

Requesting Member: Congressman KEN CALVERT

Bill Number: H.R. 2996

Account: Environmental Protection Agency, STAG Water and Wastewater Infrastructure

Legal Name of Requesting Entity: Western Municipal Water District

Address of Requesting Entity: 450 Alessandro Boulevard, Riverside, CA 92508

Description of Request: H.R. 2996 provides \$500,000 for the Western Municipal Water District for Arlington Desalter Biodenitrification project. The funding will be used to build a biological denitrification facility for drinking water. The process, called "Fixed-Bed Biological Treatment" (FXB) uses an innovative bioreactor to remove multiple contaminants from groundwater. Western Municipal Water District has completed pilot testing of the FXB process at the Arlington Desalter and has already received conditional approval from the California Department of Public Health for a full scale facility. This new facility will consist of a series of large biofilter, polishing and backwash equalization tanks as well as supply pumps and a new groundwater well. It will be built at the site of the Arlington Desalter in Riverside, California. The project benefits the City of Norco, portions of the City of Riverside, unincorporated areas of Riverside County, and any entity within the Arlington Groundwater Basin by cleaning the area's water supply and creating up to 3.7 million-gallons-per-day of new water.

Requesting Member: Congressman KEN CALVERT

Bill Number: H.R. 2996

Account: Environmental Protection Agency, STAG Water and Wastewater Infrastructure

Legal Name of Requesting Entity: City of San Juan Capistrano

Address of Requesting Entity: 32400 Paseo Adelanto, San Juan Capistrano, CA 92675

Description of Request: H.R. 2996 provides \$500.000 to the City of San Juan Capistrano for ground water recovery plant expansion and regional distribution facility. The funding will allow the city to expand the current capacity of the existing treatment facility to 7.3 million-gallons-per-day from 5.6 million-gallons-per-day. During the ongoing drought, water that is produced locally can be conveyed to surrounding water agencies thereby reducing the demands placed on the Sacramento Bay Delta and the Colorado River. In the event of a natural disaster or other emergency, the treatment plant will have the ability to function as a regional distribution facility to neighboring water agencies and helping to provide a reliable source of safe drinking water.

EARMARK DECLARATION

HON. WALTER B. JONES

OF NORTH CAROLINA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. JONES. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Department of the Interior, Environment and Related Agencies Appropriations Bill, 2010:

Rep. WALTER B. JONES

Project: Rural Water Technical Assistance, National Rural Water Association

Recipient: National Rural Water Association, 2915 South 13th Street, Duncan, OK 74544

Account: Environmental Protection Agency, Environmental Programs and Management Amount: \$13,000,000

Explanation: The funding will be used to provide rural water technical assistance, including source water and ground water protection, to help small rural communities across the nation protect their drinking water quality and comply with federal mandates.

EARMARK DECLARATION

HON. SAM GRAVES

OF MISSOURI

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. GRAVES. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding an earmark I received as part of H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010:

Congressman SAM GRAVES, (MO-6), Department of the Interior, EPA/STAG Account—\$500,000 to the City of St. Joseph for Stormwater and Wastewater Infrastructure (1100 Frederick Avenue, St. Joseph, MO 64501)

The federal funding I obtained will be utilized by the City of St. Joseph, MO, to repair and update its aging stormwater and wastewater system. The community's sanitary and stormwater collection system is divided into two components: a large combined sewer system and a separated system. Specifically, the

funds will support the development and implementation of a county-wide Stormwater Management Plan to make improvements to the system to comply with EPA requirements and operational needs resulting from new regulations, system conditions and community growth in the City of St. Joseph and Buchanan County, MO. This federal funding has the potential to create new jobs with the increased sanitary waste capacity, as well as have a positive impact on ratepayers thanks to more efficient operations with improved water quality.

HONORING THE EFFORTS OF MR. RUSS DAVIDSON

HON. DENNY REHBERG

OF MONTANA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. REHBERG. Madam Speaker, I rise to honor Russ Davidson of Colstrip, Montana, for 25 years of dedicated service to the Close Up Foundation. On behalf of the U.S. House of Representatives and Montana, it's a privilege to thank Russ for his many years of services.

to thank Russ for his many years of service.
As a high school teacher of history and government, Russ has traveled to Washington, D.C. with his students many times over the course of his career. According to his students and all who know him, Russ is an excellent teacher with years of experience in the classroom. Each year, I enjoy meeting with hundreds of Close Up students in Washington, D.C., and I appreciate the extent to which Close Up sponsors promote informed participation in the democratic process. Close Up gives students the unique opportunity to learn about the democratic process as they are introduced to lawmakers, public interest groups and personnel from all branches of government.

Thanks to people like Russ, students from across America are able to meet with their elected leaders and understand how they can make a positive difference through democratic participation. Once again, I thank Russ for his dedication as an educator and Close Up sponsor, and it's a privilege to formally recognize his efforts.

CELEBRATION OF THE 100TH BIRTHDAY OF MARTHA POFFENBERGER McKINLEY

HON. GEORGE RADANOVICH

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. RADANOVICH. Madam Speaker, I rise today on behalf of my colleagues, Representative DEVIN NUNES and Representative JIM COSTA, to acknowledge, congratulate, and celebrate the 100th Birthday of Martha Poffenberger McKinley.

Martha has always been an active member of the Fresno community. She worked for the State of California Department of Industrial Welfare for many years, where she was involved with a number of business and professional organizations. She also founded and became the first president of the women's section of the Fresno County Chamber of Commerce.

Mrs. McKinley now lives with her daughter and son-in-law. She enjoys spending time with her three grandchildren, 8 great grandchildren, and is looking forward to the birth of her first great-great grandchild.

Martha has been a remarkable mother not only to her own daughter but also to her other daughter Sally Lewis. In 2000, Martha was recognized by the Fresno County Women's Chamber of Commerce as Mother of the Year. She is well-deserving of this award.

My colleagues and I want to take this opportunity to not only wish Martha a happy birthday, but to express our admiration and gratitude for her service to the people of Fresno County. It is truly an honor to celebrate such a remarkable lady.

Below is a letter submitted by her long time friend, Sally M. Lewis.

"On July 17th, a remarkable lady will celebrate her 100th birthday. Martha Poffenberger McKinley was born in Portsmouth, Ohio, on July 17, 1909, the only child of Edward Daniel and Claire Kennedy Poffenberger.

Her life is a long list of accomplishments, but most of all she was a loving wife to Pete before his death and she is a remarkable mom to her daughter Monna and a true blessing in my life for treating me as a daughter since I was a child.

After graduation from Ohio State, Martha began her professional life in Ohio as the private secretary to Governor Bricker. Following her marriage to Peter B. McKinley they moved to northern California. Not much for staving at home, she went to work at Mare Island Ship Yard and quickly moved up from secretarial pool to department head. The family moved to Fresno after Monna was born and once she started school Martha went to work for the state of California Department of Industrial Welfare. While working there she was active in many business and professional organizations. Among them she founded and was the first president of the women's section of the Fresno County Chamber of Commerce (now The Fresno County Women in Chambers of Commerce).

She lived in her own home and washed her own car until she lost her vision well into her 90's. She now enjoys living with her daughter and son-in-law surrounded by her three grandchildren, 8 great children and soon her first great-great grand child.

Even though she is now blind, she still keeps up on current events, manages her own investments and has voted in every election.

Martha has a wonderful mind and fantastic memory. She is never without a joke and a smile. Always the life of any gathering, Martha has always enjoyed her evening cocktail and visits with family and friends. An evening with Martha is one you're not likely to forget.

It's an honor and a privilege to have her as my "other mutter." From: Sally M. Lewis"

CENTENNIAL CELEBRATION OF OREGON STATE UNIVERSITY'S HERMISTON AGRICULTURAL RE-SEARCH AND EXTENSION CEN-TER

SPEECH OF

HON. GREG WALDEN

OF OREGON

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

Mr. WALDEN. Madam Speaker, I rise today to draw my colleagues' attention to the historic

June 30, 2009, centennial of Oregon State University's Hermiston Agricultural Research and Extension Center, located in the corner of northeast Oregon near the mighty Columbia River.

Few areas in the world can match the quantity or quality of crop production of the Columbia Basin region that straddles the Oregon-Washington border. This center has been in the middle of it all for 100 years, helping farmers, ranchers, and researchers find ways to better grow and steward crops ranging from dry land wheat to watermelons; from sugar beets to wine grapes; from beef cattle to dairy cows.

Established in 1909, the "Umatilla Experiment Farm" initially served farmers trying to make a living on 20,000 acres of semi-arid northern Oregon desert as part of a federal government reclamation program. By the 1930s, farming expanded to well over 160,000 acres and the demand for the center's research reached levels far surpassing its initial 40 acres. The center moved and expanded to its current 300-acre location to better serve the region's agricultural communities. Today, the work done at this center serves well over 500,000 acres of irrigated and non-irrigated crop land.

The West is dominated by nutrient-deprived, semi-desert soils. The Columbia Basin is no different. So at the beginning, the center set upon helping farmers and ranchers overcome the fundamental challenges posed by an annual rainfall rate of eight inches. Researchers determined which types of organic matter, when put into the soil, would produce the best crops. They worked with farmers, ranchers, and communities to identify more efficient water use, based on soil type, topography, and micro-climate.

Madam Speaker, it is summertime, and if you enjoy a refreshing slice of watermelon this time of year, chances are you have the great work at this center to thank for it. The Columbia Basin is renowned for its delicious watermelons, and the center's researchers helped increase their production from 30-tons per acre under center-pivot irrigation to 70-tons per acre with drip irrigation and weed control. In the process, they made more efficient use of the water and decreased the amount of herbicide needed during production of the watermelon crop.

The center's researchers are in the middle of the battle against crop disease. Tuber worm has emerged as a threat to root crops in recent years. Late blight, the same fungus that caused the great potato famine, has resurfaced. Researchers are on the cutting of edge of identifying new methods to fight diseases that cost producers thousands of dollars each year to control.

And if all that work were not enough, researchers at the center are helping improve the quality of the country's food supply. This is one of the only centers of its kind in America with a molecular biologist working to increase the nutritional quality of our food.

The center's research is so valuable to the region that the many producers who benefit from its research return their thanks generously, donating over \$1 million to the center in the past two decades. Growers also funded the building of two large insect houses at \$40,000 each that facilitate research on which pests carry crop damaging diseases.

Today's challenges require innovative thinking and solutions. New crop varieties devel-

oped at the center help overcome the present challenges facing old crops. Many of the solutions that producers and individuals in the region see as major milestones are all in a day's work for the researchers of the center. As described by the station superintendent, Philip Hamm, "Our staff are just doing their job, and looking for the next challenge."

Madam Speaker, this center has played a vital role in helping farmers, ranchers and agricultural communities thrive on the sandy soils that have presented many challenges over the past 100 years. Today, the region served by the center is one of the most important agriculture production areas in the Northwest and produces some of the highest yielding, highest quality crops in the United States.

I congratulate Oregon State University's Hermiston Agricultural Research and Extension Center leadership, its board members, area farmers and ranchers, and the community on reaching this remarkable milestone. I am confident the center's next 100 years will be as successful as 1909–2009 has been.

ON THE 150TH ANNIVERSARY OF FOURTH BAPTIST CHURCH

HON. ROBERT C. "BOBBY" SCOTT

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES Thursday, June 25, 2009

Mr. SCOTT of Virginia. Madam Speaker, I rise today to congratulate an institution in Richmond, the capital of the Commonwealth of Virginia. On Saturday, June 27, 2009, the members of Fourth Baptist Church are celebrating their 150th anniversary, and I would like to take a moment to highlight the rich history of this church and its contribution to our community.

Fourth Baptist Church, the first black Baptist church in the Church Hill community in Richmond, began in 1859 as a regular assembly of slaves for prayer. The group met regularly on Chimborazo Hill until the outbreak of the Civil War, when the white congregation of the Leigh Street Baptist Church granted permission for the slaves to hold their services in the church basement.

In 1865 the Reverend Scott Gwathmey, one of the group's prayer leaders, gained permission for the group to meet in a Union barracks on Chimborazo Hill. There, on December 2, 1865, the Fourth Baptist Church was formally organized, with Reverend Gwathmey serving as the first pastor.

The barracks were eventually demolished, but the congregation salvaged lumber from the debris and constructed their own church building. In 1875 this church was replaced by another one of frame, on the northern side of Church Hill, near what was to be the site of the present church. The present building was completed in 1884, three months after the former church was destroyed by fire.

The church has grown considerably from these humble beginnings. Major expansion was conducted under the direction of current Pastor Emeritus, Dr. Robert L. Taylor. Dr. Taylor served as Pastor of Fourth Baptist for 34 years. He was responsible for instituting many of the programs that still exist at the church, and oversaw the building of the addition to the church building now known as Taylor Hall.

Fourth Baptist has vibrant Men's and Women's programs that enlighten and assist the young people as they participate in the Boy Scouts, Girl Scouts, and the Youth Usher programs. Fourth Baptist also participates with the Baptist General Convention of Virginia to conduct outreach ministries throughout Greater Richmond and the Commonwealth of Vir-

I would like to congratulate Chairman of the Board of Deacons Gerard A. Dabney, Interim Pastor Dr. Marion Tapscott, and the entire congregation of Fourth Street Baptist on the occasion of their 150th anniversary. I would to wish them another 150 years of service to their community.

EARMARK DECLARATION

HON. GEOFF DAVIS

OF KENTUCKY

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. DAVIS of Kentucky. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I secured as part of H.R. 2996, the Department of Interior, Environment, and Related Agencies Appropriations Act, 2010.

Requesting Member: Congressman GEOFF DAVIS

Bill Number: H.R. 2996

Account: STAG

Legal Name of Requesting Entity: City of Wurtland

Address of Requesting Entity: 500 Wurtland Avenue, Wurtland, Kentucky 41144

of Description Request: Appropriate \$500,000 for the Wurtland/Greenup/Lloyd Regional Sewer project. This project will extend sewers to underserved areas and decommission one WWTP consolidating service with a more modern regional facility. The project serves approximately 3,200 people and will accommodate growth and expansion. Completion of the project will improve health and environmental conditions in the region. In addition, it will eliminate two package plants & approximately 520 septic systems. The Kentucky Infrastructure Authority and the Greenup County Fiscal Court have committed \$1.37 million to this project. This project is a valuable use of taxpayer funds because it will reduce pollution in local streams that flow into the Ohio River and will help the community comply with federal environmental standards.

IN RECOGNITION OF THE PASSING OF DAN MCKENZIE

HON. JEFF MILLER

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. MILLER of Florida. Madam Speaker, I rise today to recognize Dan McKenzie, a Northwest Florida community leader and businessman who passed away on June 22, 2009. Mr. McKenzie spent his entire life serving his community and family. I am proud to honor his life of dedication and service.

Mr. McKenzie grew up in Pineapple, Alabama, the son of a sawmill owner. He chose to branch out and not follow in the family business, instead trying his hand at ranching. As

a young man, continuing health issues forced him to seek medical care in Foley, Alabama where he was told he would have to leave the area completely in order to regain his health. He spent the night in Milton, Florida and said he was never sick again. Milton became his permanent home after his miraculous recovery, where he became entrenched in the local business community.

Upon settling in Milton, Mr. McKenzie began a new career in the automotive industry. His first day on the job, he sold a brand new Mercury sedan for \$3,000. From there, he built a family owned automotive business that still stands to this day. For over 40 years, McKenzie Pontiac GMC Buick has provided for the automotive needs of the people of Northwest Florida. Billing themselves as a hometown dealership, their motto of "We will treat you like family" was a promise and not iust a slogan.

Mr. McKenzie was not only a businessman, but a dedicated family man. In 1945, he married his childhood sweetheart, Mary Till, and often credited her as his inspiration. They were the parents of five daughters. Sadly, Dianne passed away at the age of 9, but left to cherish his memory are Janet, Linda, Lisa and Dana.

Madam Speaker, on behalf of the United States Congress, I am privileged to honor Mr. Dan McKenzie as a man reflective of the true spirit of Northwest Florida. Mr. McKenzie will be remembered by all as a loving husband and father, a successful businessman and an important part of our Northwest Florida community.

EARMARK DECLARATION

HON. K. MICHAEL CONAWAY

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. CONAWAY. Madam Speaker, pursuant to the House Republican standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996—FY 2010 Interior, Environment, and Related Agencies Appropriations Act.

In the Environmental Protection Agency STAG Water and Wastewater Infrastructure Project account, an earmark for the City of Andrews arsenic filtration pilot project was included on my behalf. The entity to receive this funding is the City of Andrews. Texas. Andrews City Hall is located at 111 Logsdon, Andrews, TX, 79714. The funding would create a pilot program for demonstrating an alternative method to achieve EPA mandates for arsenic mitigation in rural public drinking water systems through the use of under-the-counter reverse-osmosis filtration systems.

EARMARK DECLARATION

HON. JIM GERLACH

OF PENNSYLVANIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. GERLACH. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act of 2010.

City of Reading Wastewater Treatment Plant, Reading PA—\$500,000 for upgrades to address environmental issues as required by Department of Justice Consent Decree.

EARMARK DECLARATION

HON. DON YOUNG

OF ALASKA

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. YOUNG of Alaska. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the fiscal year 2010 Interior, Environment and Related Agencies Appropriations Bill:

Requesting Member: Congressman DON Young

Bill Number: H.R. 2996. FY10 Interior. Environment, and Related Agencies Appropriations

Account: Fish and Wildlife Services/Fish-

Legal Name of Requesting Entity: Alaska Sea Otter and Stellar Sea Lion Commission.

Address of Requesting Entity: P.O. Box 142, Old Harbor, Alaska 99643.

Description of Request: \$200,000 for the Alaska Sea Otter and Stellar Sea Lion Commission. The Alaska Sea Otter and Stellar Sea Lion Commission is an Alaska Native organization that works to ensure conservation, comanagement, education, and artistic development of sea otters and sea lions. It is my understanding that this funding would facilitate the development of a co-management plan for sea otters and sea lions by local communities in the interest of sustainable populations and increasing involvement in subsistence management.

Requesting Member: Congressman Don

Bill Number: H.R. 2996. FY10 Interior. Environment, and Related Agencies Appropriations

Account: Fish and Wildlife Service/Resource Management.

Legal Name of Requesting Entity: Alaska Sealife Center.

Address of Requesting Entity: P.O. Box 1329, Seward, Alaska 99664.

Description of Request: \$350,000 for the Sealife Center's Eider Research Program. It is my understanding that the funding for this project would be used to integrate the Sealife Center's marine research facilities with field research to help recover the Stellar and Spectacled Eider, and support the Recovery Team mandated by the Endangered Species Act.

IN RECOGNITION OF THE NORTHEAST OHIO SIERRA CLUB

HON. DENNIS J. KUCINICH

OF OHIO

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. KUCINICH. Madam Speaker, I rise today in recognition of the Northeast Ohio Sierra Club and applaud their efforts to raise awareness about the dangers of coal and its contributions to global warming. As the nation takes strides towards more environmentally sound ways of producing energy, it is important that we recognize the danger of trading one harmful fuel for another. If we hope to have a stable climate, we must refrain from the use of strong and toxic pollutants like coal.

Americans are known for their determination and innovation when faced with a challenge. Let us rely on these qualities in our transition to cleaner energy, rather than choosing an easy way out represented by coal. The health of our children and our planet is too big of a price to pay for our continued dependence on coal.

Madam Speaker and colleagues, please join me in recognizing the efforts that the Northeast Ohio Sierra Club has taken in raising awareness of the dangers of coal. As the nation works towards cleaner energy policies, organizations such as the Northeast Ohio Sierra Club are working tirelessly to keep the American public accurately informed on energy issues.

EARMARK DECLARATION

HON. TED POE

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. POE of Texas. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, Department of Interior, Environment, and Related Agencies Appropriations Act. 2010:

Requesting Member: Congressman TED POE

Bill Number: H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010

Account: Environmental Protection Agency's STAG Water and Wastewater Infrastructure Project

Legal Name of Requesting Entity: City of Baytown, TX

Address of Requesting Entity: 2401 Market Street, Baytown, TX 77522

Description of Request: I, and Rep. Ron Paul, have jointly secured \$500,000 in funding under the Environmental Protection Agency's STAG Water and Wastewater Infrastructure Project account for the city of Baytown, TX to help them fund a six-year, \$140 million Capital Improvement Project that will rehabilitate and upgrade the city's wastewater and water infrastructure to comply with increased federal and state regulations, maintain its condition and reliability and save costs. This project rehabilitates portions of the Central District Wastewater Treatment plant. The work includes redesign of critical components to elevate structures out of the floodway and to reduce the storm surge impacts suffered as was suffered during Hurricane Ike. These include the influent lift station, blower building, administration/ laboratory building, and grit removal process. The internal piping needs to be replaced to improve energy and operating efficiency, along with the chlorine contact basin and plant pumping/transfer systems. Installation of poststorm emergency power systems are also a part of this project.

EARMARK DECLARATION

HON. J. RANDY FORBES

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. FORBES. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010.

Requesting Member: Congressman J. RANDY FORBES

Bill Number: H.R. 2996

Account: Fish and Wildlife Service, Land Acquisition

Legal Name of Requesting Entity: The Conservation Fund, Chesapeake, VA

Address of Requesting Entity: US 17, Chesapeake, Virginia, 23323, USA

Description of Request: Provides \$150,000 to fund the acquisition of 50 acres that has been identified by the U.S. Fish and Wildlife Service as the preferred site for the construction of a new visitor's center for the Great Dismal Swamp National Wildlife Refuge.

Requesting Member: Congressman J RANDY FORBES

Bill Number: H.R. 2996

Account: National Park Service, Save America's Treasures

Legal name of Requesting Entity: Chester-field County, Chesterfield, VA

Address of Requesting Entity: 9901 Lori Rd, Chesterfield, VA, 23832, USA

Description of Request: Provides \$150,000 to repair and preserve five historical structures in Chesterfield County.

EARMARK DECLARATION

HON. BRETT GUTHRIE

OF KENTUCKY

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. GUTHRIE. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act of 2010.

Requesting Member: Congressman BRETT GUTHBIE

Bill Number: H.R. 2996

Account: STAG Water and Wastewater Infrastructure

Recipient: Owensboro-Daviess County Regional Water Resource Agency, 1722 Pleasant Valley Road, Owensboro, KY 42303

Description of Request: Provide \$220,000 to install a sewer system in the Locust Hill Sub-division, which is currently without sewer services.

DEPARTMENT OF HOMELAND SE-CURITY APPROPRIATIONS ACT 2010

SPEECH OF

HON. BOB ETHERIDGE

OF NORTH CAROLINA

IN THE HOUSE OF REPRESENTATIVES

Wednesday, June 24, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2892) making appropriations for the Department of Homeland Security for the fiscal year ending September 30, 2010, and for other purposes:

Mr. ETHERIDGE. Madam Chair, I rise today in support of H.R. 2892, the Department of Homeland Security Appropriations Act for Fiscal Year 2010.

This legislation provides \$44 billion for the Department of Homeland Security to continue its work to keep Americans safe, keep our borders secure, and ensure our communities are prepared for any disaster—whether natural or man-made.

At a time when our state and local governments are strained in the current economic downturn, this legislation continues our federal commitment to support local efforts that keep our communities safe. It provides \$3.55 billion for first responder grant initiatives, including \$810 million for Fire Grants, \$950 million for State Emergency Preparedness Grants, \$330 million for Emergency Management Performance Grants, and a total of \$90 million for interoperable communications and emergency response centers.

H.R. 2892 will help secure our border and improve the enforcement of our nation's immigration laws. The measure would fully fund 20.019 border patrol agents with \$3.5 billion and provide \$732 million for border fencing, infrastructure and technology. It would provide \$5.7 billion for Immigration and Customs Enforcement (ICE) to enhance our ability to identify and remove immigrants who have illegally entered the country, and \$248 million for the United States Citizenship and Immigration Services to improve the processing of visas for those eligible to enter the country. This funding includes \$112 million to operate and improve E-Verify, the DHS initiative that empowers businesses to screen potential employees' immigration status.

As North Carolina is a prime hurricane state, I am pleased that this bill makes important investments in all-hazards disaster preparedness. It provides \$2 billion for Disaster Relief, \$220 million to continue flood map modernization and to maintain modernized maps, and \$200 million to address the increasing needs for emergency food and shelter, recognizing that the current economic downturn is a disaster in its own right.

Madam Chair, this is a strong bill that enhances our ability to keep our nation secure and our citizens safe. I urge my colleagues to join me in supporting this legislation.

EARMARK DECLARATION

HON. AARON SCHOCK

OF ILLINOIS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. SCHOCK. Madam Speaker, in accordance with the Republican adopted standards

on earmarks, I submit the below detailed explanation of the Village of Hopedale, Village of Hopedale, IL.

Bill Number: H.R. 2996 Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010

Provisions/Account: STAG Water and Wastewater Infrastructure Project

Name and Address of Requesting Entity: entity to receive funding for this project is the Village of Hopedale, located at Box 387, Hopedale, IL 61747.

Description of Request: The funding would be used to conduct preliminary work on a new wastewater treatment plant.

DEPARTMENT OF THE INTERIOR, ENVIRONMENT, AND RELATED AGENCIES APPROPRIATIONS ACT, 2010

SPEECH OF

HON, RUSH D. HOLT

OF NEW JERSEY

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

The House in Committee of the Whole House on the State of the Union had under consideration the bill (H.R. 2996) making appropriations for the Department of the Interior, environment, and related agencies for the fiscal year ending September 30, 2010, and for other purposes:

Mr. HOLT. Madam Chair, I rise today in support of H.R. 2996, the Fiscal Year 2010 Interior Appropriations Act.

This bill provides the much needed funding to protect and preserve our natural resources for future generations.

I applaud the Chairman for providing robust funding for the Land and Water Conservation Fund in this legislation. I have long been a supporter and a leader in Congress for increasing the funding for the Land and Water Conservation Fund (LWCF). Since its creation in 1965, LWCF has provided funding to four federal agencies including the National Park Service, Bureau of Land Management, Fish and Wildlife Service and the Forest Service to acquire public lands.

In July of 1999 during my first term in Congress, I secured passage of a key amendment to resurrect the state-side portion of LWCF, providing funding for that program for the first time in five years. To date, the stateside program has preserved over 73,000 acres of land in my home state of New Jersey. I strongly support the Manager's amendment which would increase the funding for the state-side matching grants to \$40 million, which is over double the amount that it received in Fiscal Year 2009.

I strongly oppose the amendment of the gentleman from Utah, Mr. CHAFFETZ, that would strip funding from the state side portion of the LWCF. This amendment would be detrimental to the ability of states to preserve at risk open space and I urge my colleagues to oppose it.

TRIBUTE TO MARINE GUNNERY SERGEANT CHARLES "BRANDON" BAILEY

HON. GEOFF DAVIS

OF KENTUCKY

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. DAVIS of Kentucky. Madam Speaker, today I rise to pay tribute to Marine Gunnery Sergeant Charles "Brandon" Bailey from Florence, Kentucky, who was wounded in an improvised explosive device attack on January 23, 2009, while serving in Afghanistan.

Gunnery Sergeant Bailey is a true patriot. Having felt the call to serve his country since childhood, Brandon sold his small business and selflessly joined the Marine Corps when he was twenty-four years old. He served his first combat deployment in Iraq and was a member of the 22nd Marine Expeditionary Unit. In April, 2008, Brandon married his childhood friend, Kristie. He was deployed to Afghanistan as a member of the Marine Special Operations Command shortly after the wedding. Without any hesitation, he left his new wife to serve his country once more in harm's way, ultimately to be severely wounded in action.

Gunnery Sergeant Bailey is undergoing rehabilitation with recovery in the distant future. He and Kristie are expecting their first baby this December. Gunnery Sergeant Bailey stays positive and says he is happy he had the opportunity to do the job that he loved and serve his country. Brandon's life and character epitomize the Marine Corps Motto—Semper Fidelis, Always Faithful.

Gunnery Sergeant Bailey is an inspiration to us all. Today, Madam Speaker, I ask the House of Representatives to recognize Gunnery Sergeant Bailey's unwavering dedication to the Marine Corps and to thank him for his service to our great nation.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. J. GRESHAM BARRETT

OF SOUTH CAROLINA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2647) to authorize appropriations for fiscal year 2010 for military activities of the Department of Defense; to prescribe military personnel strengths for fiscal-year 2010, and for other purposes.

Mr. BARRETT of South Carolina. Mr. Chair, ensuring that our nation remains safe and strong is the top priority for this House. Because of the real and increasing nuclear threat from countries like North Korea and Iran, I agree with my colleagues who are offering this amendment that cutting funding for missile defense is the wrong choice for our country right now.

While I certainly support efforts to increase funding for missile defense, I am unable to support the amendment offered by my colleagues. The significant decrease in funding for the Environmental Management included

as an offset in the amendment will have a serious impact on the ability of our nation to fulfill its obligation to clean up our defense nuclear waste at several sites across the country, including one in my district, the Savannah River Site (SRS).

For over fifty years, sites like SRS have played an indispensible role in keeping our nation secure. Now, the federal government has the responsibility to fulfill the commitment it made to the communities and the states that have hosted these sites by cleaning up the legacy nuclear materials that remain and providing a safe environment for future generations. The cuts made by this amendment will significantly delay the progress being made in cleanup efforts at these sites and will undoubtedly impact the highest risk activities—processing and disposing of tank waste, special nuclear materials, and spent nuclear fuel—across the complex.

Additionally, failure to fully fund the Environmental Management program will result in missed regulatory milestones in many states where the sites are located, resulting in substantial fines and penalties from state and federal regulators. These fines will ultimately be paid by the American taxpayer.

During my time in the House, I have proudly worked alongside my Nuclear Cleanup Caucus colleagues as well as the entire South Carolina delegation to ensure the safe and timely cleanup of Cold War-era nuclear waste. And I will continue to advocate for full and stable funding for the Environmental Management Program to keep nuclear waste cleanup on track.

Consequently, even though I support my colleagues' efforts to restore funding for our nation's important missile defense program, I cannot support this amendment because of the detrimental effect the funding reduction will have on the Environmental Management program. We must remain committed to cleaning up our defense nuclear waste now for the benefit of generations to come.

EARMARK DECLARATION

HON. BRETT GUTHRIE

OF KENTUCKY

IN THE HOUSE OF REPRESENTATIVES Friday, $June\ 26$, 2009

Mr. GUTHRIE. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act of 2010.

Requesting Member: Congressman BRETT GUTHRIE

Bill Number: H.R. 2996

Account: Save America's Treasures

Recipient: Breckinridge County Fiscal Court, Hardinsburg, KY

Description of Request: Provide \$150,000 to help preserve the historic Holt House. Judge Joseph Holt served as Judge Advocate General, and then later as Secretary of the Interior and Attorney General in President Lincoln's administration. The house has been on the National Register since 1976, however has not been properly maintained. Restoring the home would be key to helping develop regional tourism.

RECOGNIZING FRANKIE BRETHE-RICK HONORING AMERICA'S FIRST FLY GIRLS

HON. SAM JOHNSON

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. SAM JOHNSON of Texas. Madam Speaker, Women Air Force Service Pilots (WASP) were the first women in American history to fly military aircraft. Between the years 1942-1944, women were recruited to fly noncombat missions, so that every male pilot could be deployed in combat. These women piloted every kind of military aircraft and logged 60 million miles flying missions across the United States. They were never awarded full military status and were not eligible for officer status. It was not till 1977 that the WASP pilots were granted veterans' status. Of the 1,102 WASP pilots, just under 300 are living today. One of these living legends resides in the Third Congressional District. Frankie Bretherick. I'd like to thank her personally for her service to this great nation for being a pioneer of flight.

Frankie Lovvorn was born September 19, 1914, in Cranfils Gap, Bosque County, Texas. Her parents were Francis Marion Lovvorn and Primrose Smith. She graduated from high school in Meridian, Bosque County, Texas. She graduated from Providence Hospital Nursing School in Waco, Texas, in 1937. She worked for five years at various veteran's hospitals in Texas and Louisiana. She began flying lessons at an airport south of Dallas, Texas.

By the time she applied and was accepted into the WASP program, Class of 44W–6, she had acquired a commercial pilot's license and had logged over 200 hours of flying time. While stationed in Greenville, Mississippi at Greenville Army Air Base until deactivated on December 20, 1944, she flew BT–13s and UC–78s and slow-timed repaired aircraft.

After deactivation, Frankie was asked to join the Army Nurse Corps in May 1945. She was sent to Mitchell Field, New York where she worked at a hospital for three weeks. She was then sent to Randolph Field in San Antonio, Texas to attend the School of Aviation Medicine where she received training to become an air evacuation nurse. After World War II, she went to business school and attended Southern Methodist University in Dallas, Texas. She also worked part-time as a nurse while in school.

Frankie met Joseph Harry Bretherick while both were stationed in Greenville, Mississippi. They married in 1949 and lived in Philadelphia, Pennsylvania for 19 years. Frankie continued working as a part-time nurse after their marriage

They moved to Sarasota, Florida in 1968. After moving to Sarasota, Florida, Frankie became involved with the Sarasota Garden Club. She also acquired her Real Estate license. Frankie's husband, Joe, died in 1999. About three years ago Frankie moved to Plano, Collin County, Texas, to be close to family.

Through their actions, Women Air Force Service Pilots were a catalyst for revolutionary reform in the integration of women pilots into the U.S. Armed Services. Just as the Navajo Code Talkers served with distinction and were awarded the Congressional Gold Medal, it is

also appropriate for Congress to recognize and honor the service of the WASP with the Congressional Gold Medal. The Congressional Gold Medal is the highest and most distinguished award that the U.S. Congress can award to a civilian. Finally, these women will receive that long-overdue recognition now that the House and the Senate have passed the bill granting these women.

This Congressional Gold Medal honors mothers, grandmothers, teachers, office workers, nurses, business women, photographers, dancers, one was even a nun. But before that, they were pilots for the US Army Air Corps during World War II. Finally, this Congress has recognized their sacrifice and considers them all heroes because these trailblazers and true patriots served our country without question and with no expectations of recognition or praise. That is what being a true hero is all about! The Congressional Gold Medals will be awarded to all 1,102 pilots and/or their surviving family members.

To the brave and selfless women like Frankie, our nation owes them a debt of gratitude for their service and sacrifice. I am so very proud of them. God bless them and God bless America! I salute them one and all.

DEPARTMENT OF HOMELAND SECURITY APPROPRIATIONS ACT, 2010

SPEECH OF

HON. JOSEPH CROWLEY

OF NEW YORK

IN THE HOUSE OF REPRESENTATIVES

Wednesday, June 24, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2892) making appropriations for the Department of Homeland Security for the fiscal year ending September 30, 2010, and for other purposes:

Mr. CROWLEY. Madam Chair, I rise in support of H.R. 2892, the Department of Homeland Security Appropriations Act of 2010.

The Department of Homeland Security Appropriations bill makes fundamental investments that are vital to our nation's security. It tightens our nation's borders, allows for installation of the latest explosive detection systems at airports nationwide, protects our ports and critical infrastructure, and provides grants to meet the needs of our first responders. It also increases funding for the Urban Areas Security Initiative, which is very important to my home city of New York, by almost \$50 million, matching the President's request, for a total allocation of \$887 million.

In the months following the September 11th attacks, I spearheaded the creation of the High Threat Urban Area Account Program, which later became the Urban Area Security Initiative (UASI). I undertook this effort because, at the time, there were no Federal domestic security grant programs that provided funding solely on the basis of threat and risk. While I recognize that the threat of terror lingers everywhere, there are, unfortunately, several cities and areas that are more vulnerable to attack. New York, my home city, is one of them.

This is not a distinction we are proud of, but it is a reality we face. Al-Qaeda has already attacked my city twice. And, for me, it became all the more personal when my cousin, a New York City fireman, died during the September 11, 2001 attacks trying to help people out of Tower 2 at the World Trade Center.

What happened on September 11th can never happen again, and that is what the UASI program is about. The grants go to cities and states under the greatest threat of attack. In New York City, the grants have been used to train and better equip first responders, and provide them with better communication systems to assure preparedness, in addition to improved monitoring of critical infrastructure.

Late last month, four men were arrested in a plot to bomb two Bronx synagogues. According to authorities, they had planted bombs in cars outside the two synagogues, and were planning to shoot down military planes at an Air National Guard base in upstate New York. New York's Office of Homeland Security later provided Urban Area Security Initiative Nonprofit Security Grant Program (NSGP) funds in order to resolve the vulnerabilities of the synagogues. Additionally, it was Federal homeland security dollars that assisted the New York Police Department in their excellent investigative work to stop this act of terror before it occurred.

Madam Speaker, the threat of terrorism remains very real, making it essential for cities that face the greatest risk to have the tools and resources necessary to stop attacks before they occur. Cities, like New York, remain a major target for terrorists, and programs like UASI help us fight terrorism and ensures that our first responders have the equipment they need to protect the American people.

I would like to thank the gentleman from North Carolina, Chairman of the Homeland Security Appropriations Subcommittee, for his leadership, hard work, and dedication to the urban area initiative and I urge adoption of the bill

HONORING THE MILITARY SERVICE OF THE LOTHSPEICH FAMILY

HON. EARL POMEROY

OF NORTH DAKOTA

IN THE HOUSE OF REPRESENTATIVES

 $Friday,\,June\,\,26,\,2009$

Mr. POMEROY. Madam Speaker, I rise today to honor the military service of the Lothspeich family of North Dakota. North Dakota has a proud military tradition and has sent many of its sons and daughters into the service of their country. Amongst this proud history and tradition the Lothspeich family is unique. Edward and Rose Lothspeich were the parents of nine boys and one girl. From this family all nine of the Lothspeich brothers have bravely answered the call of a grateful nation when it was sorely needed.

These brave men served across several critical periods in our nation's history. Eugene, Harold and Edward served at the height of World War II. Donald, Gerald, Lyle, Marlin served during the Korean War and the beginning of the Cold War. Franklin and Leon served in Germany during a period in which the Soviet Union was increasing the isolation of East Germany.

Next week as we gather to celebrate the birth of our nation, the City of Park River, North Dakota will be celebrating its 125th anniversary. As a part of that celebration, Park

with us, Edward, Lyle, and Marlin, and those who are not Eugene, Harold, Edward, Donald, Gerald, Franklin and Leon.

The United States is what it is today because of the sacrifices of families like the Lothspeich's who gave so selflessly and served so bravely. These brothers helped win World War II and kept watch during the coldest nights of the Cold War.

The sacrifices of the Lothspeich brothers are worthy of our highest respect and I can think of no greater duty of a member of Congress than to honor our nation's heroes. I stand today to honor their service as the city of Park River will next week.

RECOGNIZING RICHARD F. MELL

HON. MIKE QUIGLEY

OF ILLINOIS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. QUIGLEY. Madam Speaker, I rise today to recognize the long and distinguished career of Richard F. Mell. Alderman Mell, who is celebrating his 35th year of service, is a vital part of the Chicago community.

Born in Muskegon, Michigan, Dick Mell began his career in public service shortly after moving to Chicago, starting as a precinct captain with the 33rd Ward Regular Democratic Organization and working closely with a variety of neighborhood organizations. Knowing he could do more to help the community by taking on a larger role, in 1975, he ran to be Alderman of the 33rd Ward and won. A year later, he became the Ward Committeeman and took his seat on the Democratic Central Committee of Cook County, representing his community on Chicago's Northwest side.

Alderman Mell has continued to take on important and influential roles throughout his successful career. He held the office of Vice Mayor of the City of Chicago for eight years and currently serves as Chairman of the Committee on Committees, Rules and Ethics. He is also a member of the Committees on Budget and Governmental Operations, Finance, Health, Housing & Land Acquisition, Human Relations, and Traffic Control and Safety.

As Alderman, Mr. Mell has always put his community first, remaining accessible to his constituents with an open door policy and frequent attendance at community meetings. He celebrates his multi-ethnic, multi-racial community and understands that diversity stimulates growth in all of its residents. He consistently strives to protect his entire community and has helped make possible social programs to assist the less fortunate.

Alderman Mell's list of accomplishments is longer than this statement will allow and includes setting new ethic codes for elected officials, fighting absentee slum landlords in housing courts, initiating an Adjacent Neighborhood Program that rids the city of vacant lots, and fighting to decrease graffiti in the city by banning spray paint and passing an ordinance that allows judges to sentence graffiti vandals to community service work.

Madam Speaker, I ask my colleagues to join me in recognizing Alderman Richard Mell and his extraordinary career, and thank him for his many outstanding contributions to the City of Chicago and its citizens. His commitment to public service stands as an example to us all.

River will honor those brothers who are still DEPARTMENT OF THE INTERIOR, ENVIRONMENT, AND RELATED APPROPRIATIONS AGENCIES ACT. 2010

SPEECH OF

HON. GENE GREEN

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

The House in Committee of the Whole House on the State of the Union had under consideration the bill (H.R. 2996) making appropriations for the Department of the Interior, environment, and related agencies for the fiscal year ending September 30, 2010, and for other purposes:

Mr. GENE GREEN of Texas. Madam Chair. I rise today in support of H.R. 2996, the Interior, Environment, and Related Agencies Appropriations Act for FY2010.

This legislation provides a 17% increase over FY09 levels for critical programs that protect our public health and environment.

Among other provisions, the legislation provides \$605 million for the Superfund program which will assist sites across the country clean up hazardous substances, including potentially the San Jacinto River Waste Pits site.

It also provides \$3.3 million to help EPA monitor air toxics outside schools, which I hope will ultimately include schools in our district in East Houston, as well as \$5 million to fund four new centers of excellence to study toxin and chemical impacts on children.

Madam Speaker, I would also like to highlight two important projects I requested funding for in this bill, but did not receive funding.

The first is the Mickey Leland National Urban Air Toxics Research Center to continue air quality public health research on air toxics in urban areas as directed by the U.S. Congress. The Center is a 501(c)(3) institution authorized by Congress in the Clean Air Act Amendments of 1990.

Americans want to know whether they are at risk from pollutants in the air that they breathe. People who live near sources of air toxics such as major roadways, industrial facilities, or small businesses, are often especially concerned about their risk.

The purpose of air quality regulation and research is to protect public health. High quality air toxics research is the only way to assess peoples' risks and give policymakers the tools they need to protect public health. The Center develops and manages air toxics research with a focus on understanding the air toxics that people are exposed to in their daily activities, and how those compounds may impact their health

The Houston Exposure to Air Toxics Study (HEATS) is an on-going project designed to study the relationship between personal exposures-the air people breathe as they go about their daily activities-and fixed site monitored concentrations of air toxics by measuring personal, residential indoor, and outdoor concentrations.

HEATS studies residents who live in the 29th district of Texas, in close proximity to an industrial neighborhood near the Houston Ship Channel and a comparison group with similar demographics in Aldine. Because it has been conducted according to rigorous statistical principles, study results will be applicable to the study participants, their neighborhoods,

and other, similar neighborhoods in Houston and nationwide.

Federal support for this project is critical to ensure this research continues and I hope to work with the Chairman as this bill goes forward, and with EPA to get funding for this research in the budget as Congress intended when it created the Center.

We also sought funding funding for a a sixyear Capital Improvement Project that will rehabilitate and upgrade the City of Baytown, Texas's wastewater and water infrastructure to comply with federal and state regulations, maintain its condition and reliability and save costs. The City has implemented an asset management program to assess equipment condition, optimize work practices and ensure funding remains in place to sustain infrastructure improvements over time.

The funding we requested under the State and Tribal Assistance Grant would help rehabilitate portions of the Central District Wastewater Treatment Plant to include elevation of redesign of critical components to reduce the storm surge impacts suffered during Hurricane Ike. These include the influent lift station, blower building, administration/laboratory building, and grit removal process. The internal piping needs to be replaced to improve energy and operating efficiency, along with the chlorine contact basin and plant pumping/ transfer systems. Installation of post-storm emergency power systems are also a part of this effort.

This is an important project to help Baytown recover from damage caused by Hurricane Ike and overall to upgrade their wastewater system, and I look forward to working the Chair as we move forward to find assistance for this project.

I do have some concerns, however, with provisions of the bill and report language.

The bill defers \$50 million in funding from the Ultra-Deepwater Research Fund that was a part of the 2005 Energy Policy Act of 2005. The ultra deepwater fund provides \$50 million annually for research for recovering oil and gas from ultra-deepwaters in the Gulf of Mexico.

It also includes report language urging EPA to "review the risks that hydraulic fracturing poses to drinking water using the best available science, as well as independent sources of information.'

I understand the concerns and desire to adequately protect the environment when developing our domestic resources, but hydraulic fracturing is a well-tested technology that has been used to develop energy for over 60 vears.

First used in 1947, hydraulic fracturing has become a standard practice for improving the process of natural energy extraction. The practice involves the pumping of fluid into wells at high pressure to create fractures in rock formations that allow for complete production of oil. Hydraulic fracturing is responsible for about 30 percent of our domestic recoverable oil and natural gas. About 90 percent of currently operating wells use this technology. Hydraulic fracturing, as used to produce natural gas from shale formations, has created new opportunities for clean energy and employment without causing environmental damage.

Recent studies on fracturing conducted by the Environmental Protection Agency in 2004 found no confirmed evidence of contamination of drinking water. The study concluded that the injection of hydraulic fracturing fluids poses "little or no threat" to humans or the environment (EPA). The EPA did not find a single incident of the contamination of drinking water wells by hydraulic fracturing fluid injection.

The subject of hydraulic fracturing is adequately regulated by the states and needs no federal intervention. Hydraulic fracturing is a vital and safe technology that helps drive the United States towards energy security and independence. Congress should not restrict a technology that plays such an integral part of our nation's energy strategy.

H. RES. 543, DESIGNATING JUNE AS HOME SAFETY MONTH

HON. MAXINE WATERS

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Ms. WATERS. Madam Speaker, I am proud to be a consponsor of this of this legislation, which recognizes June as Home Safety Month.

I would like to thank Congresswoman HALVORSON for her leadership in introducing this resolution and her commitment to the safety of America's homeowners.

At a time when we are encouraging homeowners to stay in their homes and increasing our efforts to spur new homeownership, we must also recognize the importance of ensuring the safety of homeowners within their homes.

Each year, 20,000 deaths and an average of 21 million medical visits result from unintentional injuries in the home, according to the Home Safety Council. The top five causes of unintentional home injury deaths include, falls, poisoning, fires or burns, choking or suffocation, and drowning. Such home injuries can cost employers up to \$38 billion dollars a year.

Many of these deaths and injuries could have been prevented if homeowners were equipped with the knowledge of simple and inexpensive steps to reduce the injury of risk in each area of the home.

Furthermore, children and older adults have increased rates of unintentional home injury. We must encourage adults, parents, caregivers to take greater actions to reduce unintentional injuries to protect the most vulnerable family members.

H. Res. 543 encourages manufacturers to develop innovative safety products and features to help lessen home injuries and accidents and encourages all levels of government to support funding for critical home safety education programs to reduce the risks from home injuries.

I strongly support H. Res. 543 and cannot stress enough how home safety education and awareness can help saves lives and money.

I urge all of my colleagues to support this important resolution.

RECOGNIZING THE SERVICE OF COLONEL KIRK W. HYMES

HON. JOHN P. MURTHA

OF PENNSYLVANIA
IN THE HOUSE OF REPRESENTATIVES
Friday, June 26, 2009

Mr. MURTHA. Madam Speaker, I rise today to honor the service of Colonel Kirk W. Hymes, U.S.M.C., the director of the Joint Non-Lethal Weapons Directorate. After 26 years of honorable and distinguished service to our great nation, Colonel Hymes will be re-

Colonel Hymes is a native of Altoona, Pennsylvania and graduated from the United States Naval Academy. After attending the Basic School, he trained at the Field Artillery Officer Basic Course at Fort Sill, Oklahoma. He also attended the Amphibious Warfare School in Quantico, Virginia and the Industrial College of the Armed Forces.

Colonel Hymes served in a number of different places and in a variety of capacities, including the Recruiting Station in Harrisburg, Pennsylvania where he served as the Operations Officer and Executive Officer and Twentynine Palms, California where he served with the 5th Battalion, 11th Marines. He also carried out a Unit Deployment to Okinawa, Japan and deployed with the 31st MEU (SOC). Following his return he became the Director of the 11th Marines Artillery Training School.

Subsequently, Colonel Hymes became the Fire Support Operational Test Project Officer at the Marine Corps Operational Test and Evaluation Activity, Quantico, Virginia. After transferring to the 2d Marine Division, Camp Lejeune, North Carolina he served with the 10th Marine Regiment where he was the Operations Officer and Executive Officer for 2d Battalion, 10th Marines and then the Regimental Operations Officer.

After reporting to Okinawa for duty with III Marine Expeditionary Force, he served in the G-3 Exercise Branch as the South East Asia Exercise Branch Head and Tandem Thrust Exercise Planner. He then returned to Twentynine Palms, California for duty as the Commanding Officer, 3d Battalion, 11th Marines where he deployed the battalion to support Operation Enduring Freedom and then Operation Iraqi Freedom. Colonel Hymes was later assigned to the Expeditionary Force Development Center at the Marine Corps Combat Development Center as the Integration Branch Head and Deputy Director for Operations.

Madam Speaker, throughout his career, Colonel Hymes received many personal awards including the Bronze Star with Combat "V", the Meritorious Service Medal with four Gold Stars, the Navy Marine Corps Achievement Medal, and the Combat Action Ribbon. Upon his retirement, I commend him for his outstanding service and wish him the best of luck in all of his future endeavors.

EARMARK DECLARATION

HON. TODD TIAHRT

OF KANSAS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. TIAHRT. Madam Speaker, pursuant to the Republican Leadership standards on ear-

marks, I am submitting the following information regarding earmarks I received as part of H.R. 2996—the Department of Interior, Environment, and Related Agencies Appropriations Act. 2010:

H.R. 2996 includes \$500,000 for a State and Tribal Assistance Grant to the City of Rose Hill, Kansas, for improvements to the city drainage system. The entity to receive funding for this project is the City of Rose Hill, 125 W. Rosewood, PO Box 185, Rose Hill, Kansas 67133.

This funding will facilitate the installation of a 48-inch drainage pipe, which will allow the area to handle up to a 10-year storm event, protecting homes in the area.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. KURT SCHRADER

OF OREGON

IN THE HOUSE OF REPRESENTATIVES Wednesday, June 24, 2009

The House Is Committee of the Whole House on the State of the Union had under consideration the bill (H.R. 2647) to authorize appropriations for fiscal year 2010 for military activities of the Department of Defense; to prescribe military personnel strengths for fiscal year 2010, and for other purposes:

Mr. SCHRADER. Madam Speaker, I want to take a moment and thank Chairman SKELTON and Ranking Member MCHUGH for their tireless work on behalf of the men and women of our Armed Services. I would also like to congratulate Congressman MCHUGH and wish him luck as he transitions to his new post as Secretary of the Army.

Madam Speaker, I rise today in support of the Skelton en bloc amendment which includes legislation I introduced requiring the Department of Defense to notify any member of the Armed Forces who is exposed to a potentially harmful material or contaminant and inform them of the health risks associated with that exposure. In the case the exposed soldier is a member of a reserve component, the Secretary of Defense will be required to notify the State military department.

Back in March I spoke with one of my constituents, Larry Roberta, a member of the Oregon National Guard who is suffering the health effects of being exposed to toxic chemicals on the battlefield. In 2003, while serving in Iraq, Oregon National Guard Members like unknowingly Larry were exposed Hexavalent Chromium while assigned to protect contractors rebuilding a water treatment facility near Iraqi oil fields. The problem with chemicals like Hexavalent Chromium is they can cause severe illnesses that may not appear until months or years after the exposure.

Their exposure to this cancerous agent was withheld from them while they were in the theater, and many of our soldiers are still unaware the symptoms they are experiencing may be related to a toxic exposure. Fast forward six years and the Oregon Guard is still having a difficult time tracking down all the soldiers they feel may have been exposed.

The estimated number of exposed Oregon soldiers is in the hundreds—many of these soldiers are still unaware they may have been exposed to toxic substances that are impacting their health. Had there been a notification

requirement and protocol in place it is very likely these soldiers would be identified, aware of their situation, and able to seek the appropriate care they need.

We're within days of sending 3,000 of Oregon's finest to the Middle East. This amendment provides them with added security and protection they need, and frankly deserve. I'd like to thank Chairman SKELTON and Ranking Member MCHUGH for their support to address this critical issue that has impacted so many of Oregon's citizen soldiers, and I urge my colleagues to support the adoption of this important amendment.

EARMARK DECLARATION

HON. MICHAEL K. SIMPSON

OF IDAHO

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. SIMPSON. Madam Speaker, in accordance with the policies and standards put forth by the House Appropriations Committee and the GOP Leadership, I would like to list the congressionally-directed projects I requested in my home state of Idaho that are contained in the report of H.R. 2996, the FY2010 Interior, Environment, and Related Agencies Appropriations Bill.

Project Name: City of Buhl Wastewater System Improvements

Amount: \$500,000 Account: EPA/STAG Recipient: City of Buhl

Recipient's Address: 203 North Broadway,

Buhl, ID 83316

Description: The city is periodically exceeding the NPDES limitations under the Clean Water Act and was recently fined by EPA for non-compliance of their pH, Total Suspended Solids (TSS), and Biochemical Oxygen Demand (BOD) limitations. IDEQ and EPA have mandated that the city build a new wastewater treatment center. Buhl, a town of less than 5,000 residents, recently passed a bond election for \$15 million to help pay for the required improvements to their water system. The loan funds will be a burden to the residents-many of whom are elderly (19% of the community) and the majority of whom are low to moderate income-and will increase monthly water bills by over \$100, but even this will be unsustainable without additional assistance. Funding for this project will enable the city build a new wastewater treatment center that would meet the Federal and State mandates imposed on the community.

Project Name: Historic Old Pen Site Stabilization Project

Amount: \$150,000

Account: National Park Service/Save America's Treasures

Recipient: Idaho State Historical Society

Recipient's Address: 2205 Old Penitentiary Road, Boise, ID 83712

Description: This project will provide stabilization to the Old Idaho State Penitentiary historic site, which is operated by the Idaho State Historical Society. The Old Pen is one of the West's most significant prison sites and one of the most visited cultural facilities in Idaho. It thus plays a key role in the economic vitality of Boise and the Treasure Valley. Funding would be used for work needed immediately to stabilize the site. In addition,

funding would be used for a historic structures report to help better anticipate future maintenance and repair needs before they become emergency situations.

Project Name: Idaho Sage-Grouse Management Plan

Amount: \$500,000

Account: Fish and Wildlife Service/ESA Resource Management

Recipient: Idaho Governor's Office of Species Conservation

Recipient's Address: 300 N. 6th Street, Boise, ID 83702

Description: Sage-grouse are on the verge of being listed under the Endangered Species Act, with a decision on listing expected this spring. Idaho is taking proactive steps to recover this species before a listing is required. The management plan, which is a partnership with private landowners, is an attempt to be wise stewards of the nation's wildlife without being compelled to do so by law.

Project Name: Piva Parcel Land Acquisition Amount: \$400,000

Account: USFS/Land Acquisition

Recipient: U.S. Forest Service, Sawtooth National Recreation Area

Recipient's Address: 5 North Fork Canyon Road, Ketchum, ID 83340

Description: Funds will be used to enable the Forest Service to acquire the 160-acre Piva parcel from a willing seller so that it can be used for public recreation and access to the Redfish Lake recreation area from the town of Stanley. The Forest Service currently has a conservation easement on the property, but acquiring the land is necessary to carry out planned improvements.

Project Name: SNRA Trail Maintenance and Improvements

Amount: \$1,200,000

Account: Capital Improvements and Maintenance (Trail Construction)

Recipient: U.S. Forest Service, Sawtooth National Recreation Area

Recipient's Address: 5 North Fork Canyon Road, Ketchum, ID 83340

Description: Funds will be used for trail construction, maintenance, and improvement in the Sawtooth National Recreation Area. Of the funds appropriated for trail maintenance and improvement in the Sawtooth National Recreation Area, \$500,000 is for trail improvements; \$500,000 is for maintenance of existing motorized trails and areas; and \$200,000 is for the improvement of two existing trails to provide primitive wheelchair access at Murdock Creek and Phyllis Lake.

I appreciate the opportunity to provide a list of congressionally-directed projects in my district that have received funding in the Interior, Environment, and Related Agencies Appropriations Act for FY2010 and provide an explanation of my support for them.

IN RECOGNITION OF MR. SCOTT F. LARGE

HON. SILVESTRE REYES

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. REYES. Madam Speaker, I rise today to pay tribute to a man of great integrity, intelligence and insight, Mr. Scott F. Large, on the occasion of his retirement after 23 years of distinguished service to the Intelligence Community.

I have had the pleasure of working with Mr. Large throughout his tenure as the Director of the National Reconnaissance Office. When he assumed this role in 2007, the organization was undertaking significant transformation that he helped initiate in earlier leadership roles. He carefully guided changes to strengthen his organization's role as the nation's primary source of space reconnaissance for military and intelligence forces.

Mr. Large's prior assignments prepared him well for this leadership role. He served as the Principal Deputy Director of the National Reconnaissance Office from April, 2007 until his appointment as Director later that year. He also served as Director of the Imagery Systems Operations and Acquisition Directorate from 2003 to 2006, during a period of significant technological and programmatic challenges.

Mr. Large has carried out leadership assignments in two other intelligence community organizations. He was Director of the Source Operations and Management Directorate at the National Geospatial-Intelligence Agency. He also served in the Central Intelligence Agency's Directorate of Operations and as Associate Director of the Science and Technology directorate, leading technology development programs. Mr. Large made fundamental contributions to these programs and helped establish them as some of the nation's premier intelligence efforts.

Mr. Large's determination to lead fundamental changes in his organization, his willingness to assume leadership roles in other intelligence organizations, and his ability to facilitate collaborative partnerships with other elements of the Intelligence Community are testament to the quality of his leadership.

In announcing that he was stepping down as Director of the National Reconnaissance Office, Mr. Large reminded his workforce of the critical role of space reconnaissance to the nation: For nearly 50 years the NRO has provided this nation with an undeniable intelligence and operational advantage. Today the NRO continues to provide mission critical information to all of our end users. We are clearly on the verge of taking our mission to the next level and have set in motion strategic initiatives which will clearly demonstrate the importance of what you do.

The nation's space reconnaissance workforce and systems are better positioned to contribute to the nation's defenses as a result of the leadership of this public servant. For this, we thank Mr. Large and wish him continued success in all of his future endeavors.

PERSONAL EXPLANATION

HON. NEIL ABERCROMBIE

OF HAWAII

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. ABERCROMBIE. Madam Speaker, I regret that I missed rollcall vote No. 297, 389, 392, 394 and 405. Had I been present, I would have voted "yea" on all rollcall votes No. 297, 392, and 394. I would have voted "nay" on rollcall votes No. 389 and 405.

DEPARTMENT OF THE INTERIOR, ENVIRONMENT, AND RELATED AGENCIES APPROPRIATIONS ACT, 2010

SPEECH OF

HON. CHRIS VAN HOLLEN

OF MARYLAND

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

The House in Committee of the Whole House on the State of the Union had under consideration the bill (H.R. 2996) making appropriations for the Department of the Interior, environment, and related agencies for the fiscal year ending September 30, 2010, and for other purposes:

Mr. VAN HOLLEN. Madam Chair, I rise in support of this FY 10 Interior-Environment Appropriations bill for the investments it makes in our infrastructure, natural resources and cultural life—as well as its commitment to tackling the ongoing challenge of global climate change.

This legislation provides \$10.46 billion for the Environmental Protection Agency to safeguard our nation's land, air and water. Of that amount, \$2.3 billion will go to the Clean Water State Revolving Fund and \$1.4 billion will go to the Drinking Water State revolving fund to help over 1500 communities improve their wastewater and drinking water systems. One and a half billion dollars will go to clean up hazardous and toxic waste, including \$605 million for our nation's most toxic Superfund sites and \$100 million for brownfields cleanup and redevelopment. And \$601 million is provided at President Obama's request to enable the EPA to enforce our nation's environmental laws.

Our national parks receive \$2.7 billion, which includes \$100 million to support the park service's 10-year initiative to upgrade park facilities before the National Park System's Centennial Anniversary in 2016. Our national wildlife refuge system is provided \$503 million for its conservation efforts. And the U.S. Forest service is allocated \$2.77 billion to manage of (Air federal forests—including targeted support for the Legacy Road and Trail Remediation program protecting streams and water systems from damaged forest roads, as well as the Forest Legacy Land Conservation Program to help protect environmentally important, privately owned forest lands.

To support our nation's cultural heritage, this legislation invests \$340 million, split evenly between the National Endowment for the Arts and the National Endowment for the Humanities. And the Smithsonian will receive \$774 million for reducing its backlog of deferred maintenance and the planning and design of the new National Museum of African American History and Culture.

Finally, this bill provides a total of \$420 million on climate change related initiatives—including \$50 million for the EPA's Energy Star program, \$17 million for the development of a Greenhouse Gas Registry necessary for monitoring greenhouse gases and \$10 million for new grants to empower local communities to find innovative ways to cut their, greenhouse gas emissions.

Madam Chair, I commend Chairman DICKS, Ranking Member SIMPSON and the rest of the subcommittee for developing this thoughtful bill, and I urge my colleagues' support.

N RECOGNITION OF THE TENTH
ANNIVERSARY OF THE
OLMSTEAD DECISION SUPPORTING CIVIL RIGHTS FOR
PERSONS WITH DISABILITIES

HON. DANNY K. DAVIS

OF ILLINOIS

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. DAVIS of Illinois. Madam Speaker, I want to take this moment to recognize the tenth anniversary of a monumental United States Supreme Court decision that represented a great advance in our contemporary civil rights struggle. On June 22, 1999, the United States Supreme Court asserted the right of individuals with disabilities to reside in their community via a 6-3 ruling. The Olmstead v. L.C. decision stated that making services for disabled individuals available only in institutions, thereby forcing them out of their homes, went against the Americans with Disabilities Act. Essentially, the Olmstead decision clarified the fact that the Americans with Disabilities Act gives individuals with disabilities the right to choose to receive their care in the community rather than in an institutional setting. Provision of care within one's community via personal care assistants is cost-effective and improves the quality of life of persons with disabilities. Studies show the cost of providing services in the community is much lower than in institutionalized settings, thereby allowing more individuals to receive services for the same cost. In addition, the ability to receive community based services and supports improves the ability of persons with disabilities to lead independent lives, work, and participate in their communities.

The federal government bears the responsibility of restructuring our current health care system. The inequities that exist in our health care system are profoundly disturbing. It is essential that we take the steps necessary to create an overhaul of the health care system that is both moral and practical. As Reverend Dr. Martin Luther King, Jr., once said: "Of all the forms of inequality injustice, health care is the most shocking and inhumane." In this spirit, I urge concerned citizens to mobilize to help us create a system that best serves those in our society who have limited resources.

As a policymaker who is adamant about improving health care for persons with disabilities, I believe it is imperative that the health care reform legislation that Congress intends to enact this year take a substantial step forward in requiring that all Medicaid-eligible individuals with disabilities have a choice between receiving care at home or in an institution. The option to receive care in one's community is critical to conforming to the goal of the Americans with Disabilities Act and with the Olmstead decision.

The Olmstead decision was a great step forward in allowing persons with disabilities the option to receive care in their own community. The tenth anniversary of the Olmstead decision symbolizes the struggle to create more options in our current health care system. We must strive to include the tenets of the Olmstead decision in our health care reform plans. Including provisions that provide choice in location of care to Medicaid-eligible persons with disabilities in comprehensive health care reform legislation would be a wonderful way to

IN RECOGNITION OF THE TENTH mark the tenth anniversary of the Olmstead ANNIVERSARY OF THE decision.

INTRODUCTION OF THE COM-PREHENSIVE COMPARATIVE STUDY OF VACCINATED AND UNVACCINATED POPULATIONS ACT OF 2009

HON. CAROLYN B. MALONEY

OF NEW YORK

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mrs. MALONEY. Madam Speaker, today, I am reintroducing bipartisan legislation that I hope will resolve the question of whether there is any link between the increased incidence of neurological disorders, including autism, and the use of certain vaccines and/or multiple vaccine schedules. Vaccines have been instrumental in reducing the incidence of many once-common diseases. However, there continue to be guestions raised in numerous media reports, and by medical professionals, regarding the safety of vaccines and multiple vaccine schedules while there have been no comprehensive studies comparing the health outcomes hetween vaccinated unvaccinated populations.

We owe it to parents and children to study and resolve the question of a possible link between vaccines and neurological disorders. The comprehensive national study comparing between vaccinated outcomes unvaccinated children mandated by this legislation would help resolve this controversy once and for all. As the most scientifically advanced country in the world, we should be jumping at the chance to conduct a comprehensive national study and help ensure absolute trust in our nation's vaccine program. Parents deserve answers, and children deserve no less than absolute certainty and safety when it comes to their health, which is why I am pleased to reintroduce this legislation today.

DEPARTMENT OF HOMELAND SECURITY APPROPRIATIONS ACT 2010

SPEECH OF

HON. DENNIS J. KUCINICH

OF OHIO

IN THE HOUSE OF REPRESENTATIVES Wednesday, June 24, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2892) making appropriations for the Department of Homeland Security for the fiscal year ending September 30, 2010, and for other purposes:

Mr. KUCINICH. Madam Chair, I rise in support of the Department of Homeland Security Appropriations Act of 2009 and the employees of the Department of Homeland Security (DHS). The service and dedication of the men and women that work to ensure the safety of our country is admirable.

This bill responds to the public safety needs of our communities in a time of hardship by providing \$800 million in grants to fire departments, of which \$380 million is provided for the Assistance for Firefighters Grants program used to train, hire and retain our local firemen

and women. It funds an increase in the number of border patrol agents to 20,019, providing additional jobs and better national security. I also support the provisions requiring DHS to monitor the medical care of all detainees held in immigration detention facilities and to direct Immigration and Customs Enforcement (ICE) to report to Congress on steps it has taken to ensure that all detainees are receiving proper medical care and attention.

I remain concerned about provisions in the bill regarding prisoners held in the Guantanamo Bay detention facility. I commend President Obama's pledge to close Guantanamo Bay, but this bill fails to ensure that the rule of law and our commitment to universal human rights are being upheld for detainees.

Section 522(a) of the bill requires the Department of Homeland Security to conduct extensive threat assessments for all detainees held at the Guantanamo Bay detention facility as of April 20, 2009, and to place all detainees on the "no-fly" list unless there is Presidential Certification to exclude them on such a list. This section also prohibits any funds in the act from being used to provide detainees with any immigration benefits, including refugee or asylum classification. The treatment and detention of hundreds of foreign nationals held indefinitely and illegally without charge at Guantanamo Bay has violated our most basic democratic principles. The burden to right this wrong by ensuring due process for the remaining 245 falls on the U.S. The detainees held at Guantanamo Bay must be afforded habeas corpus protections. We must have the confidence in our own U.S. system of justice to try the detainees.

I will continue to work to ensure all have equal protection under the law. I urge my colleagues to support passage of this bill.

INTRODUCTION OF THE GLOBAL WILDLIFE CONSERVATION, CO-ORDINATION AND ENHANCEMENT ACT OF 2009

HON. MADELEINE Z. BORDALLO

OF GUAM

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Ms. BORDALLO, Madam Speaker, as our understanding of human impacts on the environment grows, so too, must our commitment to the protection and conservation of the world's fish and wildlife resources. The United States is largely regarded as the global frontrunner in international fish and wildlife conservation. Our nation has a longstanding history of sharing our knowledge, technical abilities, and experience gained through the North American Model of Wildlife Conservation to aid other countries in the conservation of their wildlife and wildlife habitat. Unfortunately, wildlife conservation resources, including trained wildlife professionals and basic logistical and communication tools, still commonly remain unavailable in many foreign range states that are home to globally significant species.

Notwithstanding the many successful conservation initiatives implemented by the United States Fish and Wildlife Service around the world through its programs such as Wildlife Without Borders Program, there remains a glaring need to improve coordination and col-

laboration within the Federal government. In addition, improving cooperation between the Federal Government and non-governmental organizations to increase public awareness about illegal and unsustainable wildlife trade, to raise awareness about the implications of global biodiversity loss, to enhance assistance to range states in the conservation of their wildlife, and to close existing gaps in current conservation activities, is necessary and long overdue.

The Global Wildlife Conservation, Coordination and Enhancement Act of 2009, which I have introduced today, would address these needs by consolidating and enhancing the authority of the Secretary of the Interior to specifically conduct fish and wildlife conservation activities internationally. This legislation reflects the solid input gained through two oversight hearings conducted by the Committee on Natural Resources during the 110th Congress. The bill also benefits from extensive dialogue with wildlife conservationists, zoo and aquarium professionals, law enforcement experts, animal health and welfare organizations, and other stakeholders.

Title I of the bill would create an Institute for International Wildlife Conservation within the United States Fish and Wildlife Service, through which the Department of the Interior's international conservation initiatives would be coordinated and collaborative partnerships built. The Institute, which would enhance and strengthen the Service's existing International Affairs Office, would have authority to carry out a targeted public education and awareness campaign to better inform U.S. consumers of the illegal trade in wildlife and wildlife products, and most important, what they can do to limit the United States as a market for illegal contraband.

The Institute also would be empowered to provide financial, educational and technical assistance to range states and other partner institutions to support capacity building, to create and enhance locally adapted wildlife management programs abroad, and to develop professional cadres of wildlife conservationists in the United States and abroad. In addition, the Institute, through its Center for International Wildlife Recovery Partnerships, would provide a forum for the active collaboration of federal, state, tribal, local, and non-governmental entities regarding wildlife conservation and the care, rehabilitation and recovery of threatened and endangered wildlife species.

Title II of this bill would create a Global Wildlife Coordination Council within the Executive Branch in recognition of the fact that international wildlife conservation is a multi-dimensional issue that requires the broad involvement of the Federal Government to be successful. This Council, which is patterned after the highly successful United States Coral Reef Task Force, would be comprised of various Federal agencies with a responsibility and stake in global wildlife conservation. To comprehensively address the myriad threats confronting global wildlife, this Council would be tasked to develop a cross-cutting strategy to better utilize existing resources to increase Federal coordination without creating new bureaucracy.

In closing, the illegal wildlife trade, which has received considerably less public attention than the illegal trade in narcotics and weapons, is an increasing challenge threatening not only the conservation of biodiversity but also the social, political and environmental stability of range states throughout the world. Congress must act to ensure that the Federal Government has the authority and tools it needs to promote the conservation of wildlife resources abroad, to protect the environmental health and security of the United States today, and ensure that we pass on those resources to future generations.

I look forward to working with my colleagues on both sides of the aisle to advance this legislation and to strengthen the abilities of the Federal Government to provide critical wildlife conservation support around the world and to maintain the United States' leadership role internationally in wildlife conservation.

TRIBUE TO FRANK REYES

HON. JOE BACA

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. BACA. Madam Speaker, I stand here today to honor the career and contributions of a longstanding community activist, dear friend, loving husband, and father—Frank Reyes.

After 32 years of loyal service to the Inland Empire of Southern California, Frank recently announced his retirement from his post as Executive Director of Governmental Relations for the San Bernardino City Community College District (SBCCD).

Frank has made San Bernardino, California, his home since first immigrating to the United States from Guadalajara, Mexico, at age 12. He attended San Bernardino High School and Valley College before earning his degree in business from Cal State San Bernardino.

While Frank's academic background is in business, his true passion lies in the field of education. Before joining SBCCD, Frank worked as both a professor and a student counselor. During his tenure at SBCCD, Frank's strong leadership helped secure over \$100 million in grant money for both Crafton Hills College and San Bernardino Valley College.

Frank has received numerous Community Awards, from myself and many others for his excellent work in the areas of education, county safety, and community leadership.

Frank has been an active member of many distinguished professional organizations, including, the Hispanic Association of Colleges and Universities, the California Teachers' Association, the California Community College Counselors Association, the Association of Mexican American Educators, and the Inland Empire Latino Business Council.

In addition, Frank has been involved in numerous philanthropic activities in the San Bernardino area. He is a board member with Hands of Mercy, which builds homes for the needy in Ensenada, is an active member of the Kiwanis Club of Greater San Bernardino, and has been very involved with the Jerry Lewis Fire Training Facility. I know Frank will continue to work tirelessly, even in retirement, to support the causes he believes in.

I have had the great privilege of becoming close, personal friends with Frank, his wonderful wife, Eloise, and their son Christopher. In addition to being an outstanding husband and father, Frank has always been a strong supporter to me and my family, and for that—I am forever grateful.

My wife Barbara and I, my sons Councilman Joe Baca Jr. and Jeremy, and my daughters Natalie and Jennifer cherish their friendship, and are appreciative of all they have done over the years to create positive change in the Inland Empire.

In fact, I gave Eloise Reyes a "Woman of the Year" award in 1993, when I was in the California State Legislature. She was recognized for all her great work in the community, and for being a true trailblazer as the first Hispanic, female attorney in the Inland Empire.

Madam Speaker, my good friend Frank Reyes has lived a true life of service. He is a perfect example of what one can achieve with hard work, dedication, faith in God, and love in family and friends. My family and I congratulate him on a wonderful career, and wish him nothing but the best in retirement.

WHITMAN HOSPITAL AND MEDICAL CENTER OF COLVILLE, WASHINGTON

HON. CATHY McMORRIS RODGERS

OF WASHINGTON

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mrs. McMORRIS RODGERS. Madam Speaker, I rise today to recognize Whitman Hospital and Medical Center in Colville, Washington. Whitman Hospital, founded in 1893, has carried out its mission of providing medical care to members of the rural community in Northeast Washington for over 115 years.

Whitman Hospital and Medical Center is dedicated to assuring medical service is provided in accordance with its core values of respect, compassion, teamwork, stewardship, and responsiveness to the community. In addition to emergency services and surgery, the Medical Center operates a variety of clinics to support non-critical community health, such as allergy, cardiology, neurology, and ear, nose and throat conditions. The Whitman Hospital and Medical Center also provides opportunities for health education through classes, programs, and training seminars. The hospital proved its resilience by winning the "Top 100 Benchmark Hospital" award in 1994 and 1995 despite nearly closing due to financial difficulties in the late 1980s. Whitman Hospital and Medical Center's employees have contributed to providing the rural counties of Northeast Washington the kinds of healthcare options often only available in large urban centers.

Currently in the second stage of a \$19 million building and expansion project, the hospital and medical center continues to strive to provide better and more varied healthcare options. In its first stage of construction, the hospital constructed a new facility to house a 25-bed inpatient center, labor and delivery rooms, and radiology clinic. The current construction stage, scheduled for completion in late summer, 2009, involves remodeling several current operations, such as the respiratory therapy clinic and pharmacy.

Madam Speaker, I believe the ongoing efforts to provide excellent medical assistance to the counties of Northeast Washington make the Whitman Hospital and Medical Center worthy of recognition before this body. I invite my colleagues to join me in honoring Whitman Hospital and Medical Center by observing over 115 years of continuing dedication to community health services and education.

DEPARTMENT OF THE INTERIOR, ENVIRONMENT, AND RELATED AGENCIES APPROPRIATIONS ACT. 2010

SPEECH OF

HON. PAUL E. KANJORSKI

OF PENNSYLVANIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

The House in Committee of the Whole House on the State of the Union had under consideration the bill (H.R. 2996) making appropriations for the Department of the Interior, environment, and related agencies for the fiscal rear ending September 30, 2010, and for other purposes:

Mr. KANJORSKI. Madam Chair, I rise today in support of the manager's amendment put forth by Chairman DICKS to H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010. This manager's amendment incorporates an amendment I offered to allow funds appropriated to the Office of Surface Mining (OSM) to be used as the non-Federal share of the cost of certain environmental restoration projects that repair acid mine drainage from coal abandoned mines.

For many years, the Interior Appropriations bill authorized OSM to provide matching funds for federally-funded projects related to treatment or abatement of acid mine drainage from abandoned mines. The language was inadvertently removed from the appropriations bill several years ago and today I am pleased that Chairman DICKS agreed to collect this oversight by restoring this important provision in the fiscal year 2010 legislation.

Communities that are impacted by environmental damage related to abandoned mines tend to be in economically distressed areas of the country. These communities have small budgets and little, if any, money for environmental restoration projects. Furthermore, the economic downtown has caused budget shortfalls for many municipalities and providing basic services such as police and fire protection takes precedent over environmental restoration

Permitting OSM to use these funds to serve as the local match will help meet the department's mission of ensuring that citizens and the environment are protected during mining and that the land is restored to beneficial use when mining is finished. This provision will not cost the federal government any additional dollars.

In closing, I would like to thank Chairman DICKS for including my amendment in this legislation and urge my colleagues to support this manager's amendment.

CELEBRATING THE 75TH ANNIVER-SARY OF BROOKFIELD ZOO, COOK COUNTY, IL

HON. DANIEL LIPINSKI

OF ILLINOIS

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. LIPINSKI. Madam Speaker, I rise to commemorate the Chicago Zoological Society's Brookfield Zoo, which is celebrating its 75th anniversary. Located in Cook County, just outside Chicago and in my district, Brookfield Zoo has consistently been a leader in cutting edge animal science, zoo management and education programs. The zoo has been and will continue to be a wonderful resource for the people of metropolitan Chicago, the State of Illinois and beyond. I ask my colleagues to join me today in honoring Brookfield Zoo on the occasion this distinguished anniversary.

Brookfield Zoo, owned by the Forest Preserve District of Cook County and managed by the Chicago Zoological Society, has a stated mission to "inspire conservation leadership by connecting people with wildlife." It plays host to 2.1 million visitors annually, and cares for 3000 animals representing 450 different animal species.

Brookfield Zoo first opened to the public in 1934. Following the overwhelming approval of a referendum by the people of Cook County, construction began on the Zoo in 1926. While the onset of the Great Depression hindered progress, the federal Civil Works Administration (CWA) assisted in completing construction of the Zoo, and today many of the original, historic CWA buildings remain in use at the Zoo.

Brookfield Zoo has been an innovative leader among zoos. Notably, the zoo was one of the first "bar-less" zoos in North America. A revolution among zoos began in Europe in 1900, where cramped cages were disdained in favor of spacious enclosures, surrounded by moats and landscaped in natural settings. This was based on the belief that 'animals should be exhibited in as near natural conditions as possible', for the benefit of both the animal and the viewing public. Brookfield Zoo was designed with this modern concept in mind, and creatively overcame the challenges involved in maintaining safe, cageless environments in the northern climate of Chicago. Today, exhibits maintain their modern approach through a focus on ecosystems, incorporating native plants into animals' habitats.

Another "first" was the creation of a specific Children's Playground at the Zoo in 1937, which was later formalized into the Children's Zoo in 1953. This facility provided children not only with a location to play, but also enabled them to interact with animals, including goats, ducks, and lambs. Following the successful development of these facilities, Brookfield Zoo became the first zoo in North America to exhibit giant pandas in 1937, to breed black rhinos (1941) and okapi (1959) in captivity, and created the first inland "Dolphinarium" in 1960. It was also among the first to open a zoo animal hospital and to launch animal nutrition programs.

Just like millions of others, I have fond memories of Brookfield Zoo from my childhood. Growing up in Chicago, I was a member of the zoo for many years when I was in grade school and high school. It was a fun and safe place to go at all times of the year. Although I did not think about it at the time, I received a great education at Brookfield Zoo, including learning about not only animals and habitats around the world, but also the environment and environmental stewardship.

Education is something that Brookfield Zoo is strongly committed to. Last year, 250,000 students participated in school field trips to Brookfield Zoo, and more than 1,700 teachers participated in training and certification programs there as well. Facilities such as Brookfield Zoo are important sources of informal

science education, which can develop interest among children in future technological and scientific scholarship and careers. Brookfield Zoo has a remarkable research and professional training program organized under the Center for the Science of Animal Well-Being. Through the Chicago Zoological Society, field programs are sponsored and undertaken, now including long-term research on bottle nose dolphins, western lowland gorillas, and African lions, among other species.

I would like to commend Brookfield Zoo, as well as the Chicago Zoological Society, on their successful completion of 75 years of operation, and their continuing efforts to promote conservation leadership through education, research and family enjoyment. Congratulations on this notable anniversary, and I wish Brookfield Zoo and its dedicated staff and leadership many more years of success, effective research, and valuable education and outreach.

STATEMENT ON JANE MARGARET O'BRIEN AND TORRE MERINGOLO

HON. STENY H. HOYER

OF MARYLAND

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. HOYER. Madam Speaker, I would like to recognize the efforts of two individuals who have been key in the success of St. Mary's College of Maryland. Unfortunately, both of them have chosen to move on to new challenges and will be leaving this summer, so I wanted to reflect on the incredible contributions they have both made to the College.

Jane Margaret O'Brien leaves as the president of St. Mary's College of Maryland, having served in that capacity since 1996. Maggie is a personal friend and I want to salute her years of leadership as President, along with Torre Meringolo, who has served during much of that time as Vice President for Development. Together, they brought to St. Mary's College a strong reputation for excellence in scholarship, research, and community engagement

Dr. O'Brien received her bachelor's degree from Vassar College in 1975 with a major in biochemistry. She completed a Ph.D. in chemistry at the University of Delaware in 1981. In her early academic career she was a member of the chemistry and biochemistry department at Middlebury College where she also served as dean of the faculty. She was president of Hollins University from 1991–96.

Dr. O'Brien received a Kellogg National Leadership Fellowship from 1989–92, served as an International Fellow with the American Association of Colleges and Universities in 1990–91, and was an Eisenhower Fellow to Malaysia and Hungary in 1999. She is a member of Phi Beta Kappa and the science honors society Sigma Xi. After stepping down as president, Dr. O'Brien will continue to work for the College with the Centre for Medieval and Renaissance Studies in Oxford, England.

Dr. O'Brien assumed her post in July 1996 and dedicated herself and the College to the newly adopted Honors College Curriculum. She provided critical guidance to the College's external relations and fundraising, which included the \$40 million Heritage Campaign in support of the faculty's academic leadership, the extension of the residential college, and

the enhancement of community programs. Fundraising during Dr. O'Brien's tenure reshaped the College's scholarships, professorships, lecture and learning series, and arts, athletic, and community programs. External support made possible the Paul H. Nitze Scholars Program, the annual River Concert Series, over 40 new scholarships, nine endowed professorships and chairs, and many student and faculty awards presented at the annual Awards Convocation.

The Center for the Study of Democracy was established with a \$2 million NEH grant and challenge matches. Private funds now support the William Donald Schaefer Internships, the Ben Bradlee Lectures, the Andrew Goodpaster Lecture Series and the Patuxent Defense Forum.

In honoring the successful accomplishments at St. Mary's College under Maggie's leadership, we should also recognize the accomplishments of Torre Meringolo, who has been instrumental in carrying out much of Maggie's vision for the College. Torre also leaves this month after serving most of his 15 years at St. Mary's College as the Vice President for Development. He has accepted the position of vice president for university advancement and external relations at the University of Mary Washington.

Torre leaves a proud record of accomplishment at St. Mary's. Hired originally as director of the library and information services, he directed a comprehensive modernization effort that encompassed library partnerships with the University of Maryland System, raised \$2 million for library endowment, and provided the foundation for a contemporary IT system. Torre's previous employment at the University of Massachusetts at Amherst, Penn State University, and UNC Charlotte brought a strong knowledge of information systems to St. Mary's, which he deftly adapted for a smaller-scale campus with modest resources.

In concert with Trustee Terry Rubenstein, chair of the board's development committee, Torre led a professional development team that successfully completed a \$40.4 million campaign. During his time, endowment funds at the College grew to over \$24 million. Torre worked to create a modern, professionally run Foundation, which granted over \$16 million for the College's programs over the past 10 years. His passion for supporting students with financial needs made possible the graduation of many alumni.

Under Torre's leadership, the Alumni Office now serves 11,000 proud alumni with regular events and mailings to keep alumni involved and informed. His work has led to the creation of major campus events such as Reunion Weekend, Governor's Cup, Madrigals, and now the River Concert Series on the Townhouse Greens, all successful programs that bring thousands of alumni and friends to the College annually.

As Maggie O'Brien and Torre Meringolo depart, St. Mary's College is today a nationally recognized leader. Newsweek has called it "an lvy-level College with a public-school price tag." It is now consistently ranked as one of the best liberal arts schools in the nation by U.S. News and World Report, and the Princeton Review named it a "best value college" this year.

I want to congratulate Maggie and Torre for their contributions to higher education. Their accomplishments at St. Mary's College of Maryland have greatly benefitted their community and our State of Maryland. Both of them will be sorely missed.

HONORING CAPTAIN MARK GINDA FOR HIS LEADERSHIP OF NAVAL SUBMARINE BASE NEW LONDON

HON. JOE COURTNEY

OF CONNECTICUT

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. COURTNEY. Madam Speaker, I rise today to honor Captain Mark S. Ginda, who, after three years of service as Commanding Officer at Naval Submarine Base New London, will be moving on to his new position at the Defense Liaison Division in Washington, DC

Captain Mark Ginda has served our nation through his service in the Submarine force since 1982, when he graduated from the United States Naval Academy. He went on to serve on the USS George C. Marshall (SSBN 654), USS Alexander Hamilton (SSBN 617), USS Sand Lance (SSN 660) and commanded the USS Pasadena (SSN 752). Back on shore, Captain Ginda served as an instructor at Naval Nuclear Power School, flag aide to the Commander of the Atlantic Fleet, directed readiness preparations at Submarine Squadron FIFTEEN in Guam, helped to coordinate intelligence, surveillance and reconnaissance (ISR) resources at the United States Strategic Command.

In August 2006, Captain Ginda became the 48th Commanding Officer of Naval Submarine Base New London. Since then, he has overseen one of our nations most historic and important naval bases, which covers 680 acres, serves as home to 70 tenant commands, and supports the officers and crew of nearly onequarter of our attack submarine fleet. He has done so with enthusiasm, with passion and with a dedication not only to strengthening the base for the future, but with a renewed commitment to our nation's most import asset: the young Americans who serve our nation.

In his three years there. Captain Ginda has overseen a flurry of activity unmatched in the recent history of SUBASE New London. From a new crane facility at the waterfront, to a long-needed renovation of the Liberty Center for bachelor sailors, the completion of an initiative to improve housing options and a number of other critical projects, there isn't a corner of the base where Captain Ginda hasn't had an impact. Under his leadership, SUBASE embarked on one of the most ambitious demolition projects in the Navy, pulling down more than 35 buildings and structures through a more than \$18 million undertaking of projects that will trim down the excess infrastructure at the base and lower operating costs. He's also been a commander who takes things into his own hands, and recently manned the controls of a backhoe and helped demolish buildings.

More important than the bricks and mortar, however, has been Captain Ginda's efforts to improve the quality of life for the sailors, and their families, stationed at SUBASE New London, and breath new life into the base not just as a military facility—but as a home to its residents and a contributing member of the southeastern Connecticut community.

Not too long ago SUBASE New London was threatened with closure. While advocates and

supporters from across the state joined together to reverse this decision and keep the base open, there hung over the base a sense that it was a "relic," that it was somehow an outdated and gloomy place in which to serve. Each and every day since arriving at the base, Captain Ginda worked to reverse that perception by reconnecting the base with the community around it, by looking forward at what the base could be, and by ensuring that the base is able to accomplish its most important goal—the support of the sailors and families who make up our submarine force.

Not too long after Captain Ginda took command of the base, I was honored to be elected as the representative of the second Congressional district of Connecticut. As a new member from the other side of the district, it was important for me to get up to speed fast on the needs of the base and the challenges it faced. From day one, Captain Ginda made sure to reach out to me, and take the time to walk me through his vision for the base and ensuring that no question of mine went unasked. His help, and counsel, was instrumental in making sure I had the knowledge I needed to come to Washington to advocate on behalf of the base and its importance to our nation. I am so grateful for his assistance and the close working relationship he has had with me and my office. I am also especially thankful for the warm friendship that he and his wife, Terry, have shown and their efforts to ensure that I felt at home as a member of the SUBASE New London community.

Madam Speaker, it has truly been an honor to work with Captain Ginda, and I have no doubt that his legacy will be felt at the base and in the region for some time to come. He has been a terrific resource for me and my office, a trusted advocate for his base, and a respected partner in the southeastern Connecticut community. I ask all my colleagues in joining me in thanking Captain Ginda for his service to the Navy, recognizing his tireless efforts at SUBASE New London, and in wishing he and Terry good luck as they prepare to move on to this next step in their lives.

TRIBUTE TO CHARLES PRATHER, FIRE CHIEF ORANGE COUNTY FIRE AUTHORITY

HON. KEN CALVERT

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. CALVERT. Madam Speaker, I rise today to honor and pay tribute to an individual whose dedication and contributions to the community of Orange County, California are exceptional. Orange County has been fortunate to have dynamic and dedicated community leaders who willingly and unselfishly give their time and talent and make their communities a better place to live and work. Fire Chief Charles "Chip" Prather is one of these individuals. Chief Prather is retiring from the Orange County Fire Authority (OCFA) and today I honor his years of public service.

Chief Prather became Fire Chief for the Orange County Fire Authority on October 1, 1997. In this capacity he is responsible for the daily operation of one of the largest fire organizations in the State of California. Under Chief Prather's direction are a total of 1,500

firefighters, reserves and professional staff. The OCFA serves 22 cities and unincorporated areas of Orange County, with a total population of more than 1,300,000, from 62 fire stations and has an annual operating budget of 260 million dollars.

In addition, Chief Prather currently serves on the Orange County Emergency Council, Chairs the Orange County Emergency Operational Area Council, Fire Scope Board of Directors, Co-chairs an Orange County Joint Law/Fire/Health anti-terrorism advisory committee and is a member of the California Fire Chiefs Association Executive Board of Directors. In 2002, Chip was appointed by Governor Davis to the State Emergency Council which advises the Governor on policy matters during times of disaster and served on the states 2003 Blue Ribbon Fire Commission.

Chief Prather is also is a member of The Raise Foundation's Advisory Board (formerly Prevent Child Abuse Orange County), serves as a member of the Salvation Army Advisory Board and the Trauma Intervention Program Advisory Board and numerous other boards and commissions. Chief Prather was honored as the recipient of the Boy Scouts Spurgeon Award 2000 for his involvement in Explorer Scouting and in 2002 was selected as the Fire Chief of the Year by the California Fire Chiefs Association.

Chief Prather is a member of the following organizations: Orange County Chambers of Commerce, International Association of Fire Chiefs, Metropolitan Fire Chiefs' Association, California Fire Chiefs' Association, California State Firefighters' Association, the Orange County Fire Chiefs' Association and the National Fire Protection Association.

Chip holds a Bachelor of Arts Degree in Management and has completed the Harvard University John F. Kennedy School of Government Program for Senior Executives in state and local government. He has also attended the United States Fire Administration National Fire Academy, completing the Executive Fire Officer Program.

Chief Prather and his wife Katie live in San Clemente California with their two children.

Chief Prather's tireless passion for community and public service has contributed immensely to the betterment of the community of Orange County, California. I am proud to call Chip a fellow community member, American and friend. I know that many community members are grateful for his service and salute him as he retires.

MT. CARMEL HOSPITAL OF COLVILLE, WASHINGTON CELE-BRATES 90TH ANNIVERSARY

HON. CATHY McMORRIS RODGERS

OF WASHINGTON

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mrs. McMORRIS RODGERS. Madam Speaker, I rise today to recognize Mt. Carmel Hospital in Colville, Washington. Mt. Carmel Hospital was founded in 1919 as a non-profit, critical access, Catholic hospital and is currently run by the Sisters of Providence. For 90 years, the hospital has carried out its mission of providing medical care to members of the rural community in the Stevens, Ferry, and Pend Oreille counties of Northeast Washington

Mt. Carmel Hospital is dedicated to assuring medical service is provided in accordance with its core values of respect, compassion, justice, excellence, and stewardship. In addition to its operating emergency services, a surgery center, rehabilitation, and diagnostic imaging, Mt. Carmel serves the community's underprivileged and provides education to professionals and laymen alike. Through their partnership with various other regional nonprofits, such as Christ Clinic and Project Access, Mt. Carmel compassionately reaches out to those who have limited or no health insurance. Additionally, the hospital's Resident Physician program offers training for new medical personnel while its Community Health Education Center provides classes and support groups on awareness and health improvement opportunities. The excellent care and community support contributed by Mt. Carmel Hospital offers the rural counties of Northeast Washington the kind of healthcare options often only available in large urban centers.

In early June, 2009, Mt. Carmel Hospital completed its renewal and expansion project, which doubled the hospital's size and renovated the existing building. Construction of the new hospital building will increase the hospital's area by 70,000 square feet, which will include a new inpatient facility and an expanded outpatient area, emergency room, and laboratory, as well as other additions.

Madam Speaker, I believe the ongoing efforts to provide excellent medical assistance to the counties of Northeast Washington make Mt. Carmel Hospital worthy of recognition before this body. I invite my colleagues to join me in honoring Mt. Carmel Hospital and the Sisters of Providence by observing and celebrating 90 years of dedication to wellness and health education in the community.

IN RECOGNITION OF THE THIRTY-SEVENTH ANNIVERSARY OF TITLE IX

HON. DANNY K. DAVIS

OF ILLINOIS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. DAVIS of Illinois. Madam Speaker, I wish to take a moment this week to recognize the thirty-seventh anniversary of Title IX. When I think of this historic legislation that champions equal rights for women, I am reminded of something Betty Friedan said in her book, the Feminine Mystique. She said, "The problem that has no name-which is simply the fact that American women are kept from growing to their full human capacities-is taking a far greater toll on the physical and mental health of our country than any known disease." Ms. Friedan-a leader of the women's rights movement and a founding member of the National Organization for Women-described an ongoing battle; a battle that has plagued our country for far too long.

Title IX was enacted with the purpose of removing the barriers that could negatively constrict the potential of over 50% of our population. This monumental advance in equal rights for women was passed on June 23, 1972, with the goal of prohibiting gender discrimination in education programs, especially concerning athletic opportunities for young men and women. I have time and time again

commended this milestone in U.S. legislation for empowering women to engage and contribute positively to society as well as for encouraging women to make responsible decisions

Upon celebrating the thirty-seventh anniversary of Title IX, it is only right to recognize what has thus far been accomplished since the enactment of Title IX in 1972. In the arena of athletics, we have seen tremendous increases in the participation of women in sports. In 1972, there were merely 294,000 female high school athletic participants, in contrast to the 3.6 million male participants; now, looking at 2006, there has been a 904% increase with just under 3 million female high school athletes. In 1972, only about 30,000 women continued on to collegiate athletic participation, compared to 170,000 male participants. But in 2006, that number also increased exponentially, by 456%, to 167,000 female collegiate participants. In the world of business, the percentage of women general counsels in Fortune 500 companies rose from 4% to 15% between 1994 and 2002. Within the legal profession, the percentage of women in tenured positions at law schools increased from 5.9% in 1994 to 25.1% in 2006. In addition, I am certain that Title IX laid the foundation for other advancements in equal rights for women, such as the Lilly Ledbetter Fair Pay Act of 2009 that President Obama signed into law this January and that I proudly co-sponsored.

Even with this progress, the United States still has quite a journey ahead toward the goal of equality for women. There still exists resistance to efforts to treat women and men equally. Even now there is still a remarkably large gap between the number of female and male high school and collegiate sports participants. Beyond athletics, there still exists gender inequality in the work force on multiple fronts, including: the ratio of male to female professionals; the difference in the earnings of male and female employees; and the ratio of male to female leadership positions in the workforce. It is true that in 2003 female professional earnings had risen to 76% of what their male counterparts were making; nevertheless, 76% is still far less than 100%.

So, I celebrate the advances made during the thirty-seven years since Title IX was enacted, and I promise to continue to dedicate my time and efforts to champion equal rights for women.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. BOB ETHERIDGE

OF NORTH CAROLINA

IN THE HOUSE OF REPRESENTATIVES

Wednesday, June 24, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2647) to authorize appropriations for fiscal year 2010 for military activities of the Department of Defense; to prescribe military personnel strengths for fiscal year 2010, and for other purposes:

Mr. ETHERIDGE. Mr. Chair, I rise today in support of H.R. 2647, the National Defense Authorization Act for FY 2010.

As the representative of Fort Bragg and Pope Air Force Base. I am pleased that this bill makes important investments to support our national security and recognize the contributions of not only our men and women in uniform but also the families that support them. It provides for a 3.4 percent pay raise for service members and authorizes \$1.95 billion for family housing programs. It expands support for those who are injured in battle, with enhancements for the medical "mission to heal" and funding to help friends and family visit or otherwise support recovering service members. It also expands TRICARE health coverage for reserve component members and their families.

H.R. 2647 improves military readiness and authorizes additional funds for equipment depleted by the war in Iraq and Afghanistan. It authorizes the president's request for 15,000 more Army troops, 8,000 more Marines, 14,650 more Air Force personnel, and 2,477 more Navy sailors, and also includes funding for force protection to keep those troops safe in theater. It recognizes the toll on our Army National guard and reserves by providing new battle gear and construction projects in our communities.

While I am pleased that this resolution provides authorization of \$50 million for Impact Aid funding, with additional \$15 million for BRAC-affected areas, these levels are inadequate for the pressing needs our school districts have as they care for military-connected students. As the former superintendent of North Carolina's schools, I know first-hand that we cannot provide a high-quality education without high-quality facilities. In North Carolina, the BRAC process has swelled enrollment in the counties around Fort Bragg-Cumberland, Harnett, Johnston, and Sampson-without increasing the tax base that supports the local schools. Impact Aid funding has barely increased in the last five years. We must renew our commitment to support these students and give local schools the support they need to provide them a quality education, especially in the current economic downturn that is straining state and local budgets.

Mr. Chair, despite this shortfall, this is a strong bill that supports our men and women in uniform, and their families, and enhances our national security. I urge my colleagues to join me in supporting this legislation.

VETERANS HEALTH CARE BUDGET REFORM AND TRANSPARENCY ACT OF 2009

SPEECH OF

HON. MAXINE WATERS

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Tuesday, June 23, 2009

Ms. WATERS. Mr. Speaker, I rise in support of H.R. 1016—To amend title 38, United States Code, to provide advance appropriations authority for certain medical care accounts of the Department of Veterans Affairs. This bill would ensure sufficient, timely, and

predictable veterans funding so that the Department of Veterans Affairs would have the federal funding to better serve veterans' medical needs and improve health care services. This is a very timely and important measure as many of our troops today are returning home in need of accessible and adequate health care services. Therefore I strongly commend my colleague BOB FILNER for bringing this measure before the floor.

This bill would authorize Congress to provide investments in the Department of Veterans Affairs medical care one year in advance so the department can have sufficient time to plan how to deliver the best care to an increasing number of veterans with increasingly complex medical conditions.

My military constituents often turn to me for support in confronting the many challenges they face when working with the Department of Veterans Affairs. We have come to understand, that many of the challenges in efficient health care services are attributable to the Department of Veterans Affairs' inadequate funding. For most of the past two decades, the appropriated funds for medical care have not been provided to the Department of Veterans Affairs in a timely manner. This has resulted in the department's problems in planning and managing care for enrolled veterans. Accordingly, this bill addresses this budgetary problem and allows for advance appropriations to ensure the department has the Federal backing to effectively address the medical needs of our nation's veterans.

As a vocal advocate for veterans' rights, I am pleased to add my voice of support for H.R. 1016. I look forward to working with my colleagues to ensure that we continue to provide the necessary resources towards improving our Department of Veterans Affairs' health care programs and administrative services.

IN RECOGNITION OF OFFICER GARLAND C. THOMPSON

HON. PETE SESSIONS

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. SESSIONS. Madam Speaker, I rise today to honor Officer Garland C. Thompson's retirement from the United States Capitol Police after thirty-five years of service.

Founded in 1828, the Capitol Police have protected countless lives and secured our nation's historic Capitol complex. Officer Thompson first joined the Capitol Police on June 6, 1975. His deep sense of patriotism and dedication to upholding the rule of law is evident to all. Known as a strict enforcer, Officer Thompson has ensured the safety of elected officials, staffers, journalists, and tourists allike and the corner of First and C Streets will not be the same without his friendly face. I have had the pleasure of knowing him and am proud to call him my friend. I know he will be greatly missed.

Madam Speaker, I ask my esteemed colleagues to join me in expressing our heartfelt gratitude for Officer Thompson's thirty-five years of dedicated service to the Capitol Police and this great Nation. I wish him and his family all my very best.

RECOGNIZING THE 20TH ANNIVER-SARY OF THE NATIONAL CEN-TER FOR BIOTECHNOLOGY IN-FORMATION

HON. DAVID R. OBEY

OF WISCONSIN

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. OBEY. Madam Speaker, I rise today, as a member of the House of Representatives who has been intimately involved with the area of biomedical research and health care, to draw the attention of the Congress and the nation to the 20th anniversary of the National Center for Biotechnology Information (NCBI), a national resource for molecular biology information located at the National Library of Medicine, National Institutes of Health (NIH).

I am reminded at this time of our late distinguished colleague Claude Pepper who, in 1987, introduced H.R. 393, a bill to establish a National Center for Biotechnology Information. As he eloquently described it, the Center would deal "with nothing less than the mystery of human life and the unfolding scroll of knowledge, seeking to penetrate that mystery, which is life itself." A quick study, Claude early on concluded there was a growing need to fit together the pieces of the genetic puzzle so as to benefit humankind. Although the term biotechnology was relatively new at that time, there was clear evidence that the whole biotechnology information infrastructure was overloaded and there was an urgent need for developing a central repository for storing and sharing the data resulting from the explosive growth of research in molecular biology. The information-handling organization envisioned in the bill, the National Center for Biotechnology Information, became a reality with the signing by President Reagan of the Health Omnibus Extension Act (P.L. 100-607) on November 4, 1988.

I remember well those early years when a group of Nobel Laureates appeared before the House Appropriations Subcommittee on Health and laid out a vision that revolutionized our understanding of biology and genomics. Chairman Bill Natcher and those of us on the subcommittee enthusiastically supported the Genome Project. Its magnitude was nothing short of President Kennedy's vision of landing a man on the moon for it launched a grand national challenge of utmost importance to health. NIH Director James human Wyngaarden testified that year that we had sequencing data on less than one-tenth of one percent of the human genome. He said then that while the pace of biology research was rapidly accelerating, the ability to analyze and share information was severely constrained and that if we were going to understand the disease process we would need new and better information approaches. Clearly, the organization defined in Claude's bill fit that need and so the Appropriations Committee readily provided the necessary funding for NCBI.

Today molecular biology and genomics are the primary drivers of medical progress. And, under the innovative leadership of Dr. David Lipman, NCBI's first and current director, NCBI's molecular biology information resources are empowering hundreds of thousands of researchers around the world to

identify disease-related genes and develop strategies for treating and preventing disease. It's amazing that each and every week researchers are downloading data from NCBI that is equivalent in size—I am told—to the entire contents of the Library of Congress.

The U.S. Congress has encouraged and generously supported the more than 40 database resources developed by the NCBI. The recent legislative requirement that the results of NIH-funded research be made available through NCBI's PubMed Central database will, we believe, accelerate scientific progress and the discovery of new treatments.

Over the past 20 years, the management of biological information has progressed rapidly and has become an integral part of the scientific process. It is now virtually impossible to think of an experimental strategy in biomedicine that does not rely heavily on the kind of resources and tools developed by the NCBI for analyzing molecular and genomic data.

In summary, Madam Speaker, under Dr. Lipman's careful planning and creative stewardship the NCBI has responded successfully to the challenge of the mandate of the 1988 legislation by effectively developing a major national resource for molecular biology information that is greatly benefiting medical researchers, practitioners, educators, and the general public.

I believe that the era of "personalized medicine"—including highly targeted individualized treatments— will soon be upon us, and NCBI clearly will be a driving force in making that a reality. So I want to offer my congratulations to NCBI's visionary leader, Dr. David Lipman, to NLM's excellent director, Dr. Donald A. B. Lindberg, and to the bright and dedicated staff of the NCBI for 20 years of outstanding public service to the nation and to the world.

HONORING MAYOR WILLIAM HICKS

HON. SHELLEY MOORE CAPITO

OF WEST VIRGINIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mrs. CAPITO. Madam Speaker, I rise to recognize the remarkable achievements of William "Bill" Hicks, the beloved mayor of Romney, West Virginia.

Bill is a veteran of the Second World War's Pacific Theater where he was involved in navigation and sighting for secret bombing missions. Just fifteen days after returning home from the war, he married Thelma Elizabeth Berg on December 27, 1945.

Together, they made Romney their home on July 1, 1964 and have lived there ever since. Bill worked for Western Union Telegraph Company where he played a key role in setting up the first transcontinental microwave relay communications in the U.S. His work involved implementing communications infrastructure for private and government entities located throughout West Virginia and the surrounding areas. Through his work, Bill also developed a passion for public service.

He was first elected to the Romney City Council in 1968 and later was elected as Mayor of Romney in 1991. After more than 40 years of service, Mayor Hicks recently stepped down, but still remains committed to serving his community. He has been involved in numerous community organizations. He also serves on the Hampshire County Development Authority, the Potomac Valley Transit Authority, the Romney VFW, and the American Boy Scout Committee, just to name a few.

Bill and his wife Thelma remain committed to their community and their family. They raised five children, boast eight grandchildren and now have five great-grandchildren.

Madam Speaker, I am proud to honor Romney's beloved Mayor and long-time distinguished public servant, William "Bill" Hicks for his years of service and contributions to Hampshire County and the State of West Virginia. Mayor Hicks is a friend and a fellow West Virginian. I wish him all the best in the years to come.

HONORING THE 100TH ANNIVER-SARY OF PETE'S HAMBURGERS

HON. RON KIND

OF WISCONSIN

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. KIND. Madam Speaker, I rise today to honor Pete's Hamburgers of Prairie du Chien, Wisconsin and to recognize their 100th anniversary.

It is reassuring to see that despite these tough economic times many American small businesses are still thriving. It was 100 years ago when Pete Gokey opened Pete's Hamburgers as a small, humble stand selling panfried hamburgers. Pete Gokey's life embodies the hard work, dedication, and commitment that have made our country great.

Although we recognize it today for achieving the feat of keeping its doors open for 100 years, the story of Pete's Hamburgers is one founded upon an individual's commitment to public service and hard work. Before opening his stand to sell hamburgers, Pete Gokey was a member of the volunteer fire department in Prairie du Chien. As fate would have it, Pete was selected to be the chef for one of the fire department's community events, at which he was expected to serve fried hamburgers with onions. The hamburgers were a huge success and became the catalyst for Pete Gokey's successful stand.

Gokey was able to turn his stand into a fixture of the Prairie du Chien community. Whether serving hamburgers or volunteering as a fire fighter, Pete Gokey was a man who lived a life based on hard work and service to his community.

Pete's Hamburgers and its quality product have stood the test of time and I proudly stand before this chamber to recognize the success of Pete and his family who have dedicated their lives to something they love: hamburgers.

I applaud the efforts of Pete Gokey and his family members who now run the business and I am proud to see their hard work rewarded by 100 years of business and 100 years of service to the Prairie du Chien community. May their success continue for many more years to come.

CONGRATULATING PAIGE EPLER
ON HER GRADUATION FROM THE
UNIVERSITY OF OKLAHOMA
HIGH SCHOOL

HON. GERALD E. CONNOLLY

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. CONNOLLY of Virginia. Madam Speaker, I rise today to recognize Paige Laura Epler from Woodbridge, Virginia, on her graduation from the University of Oklahoma High School. Twelve year old Paige graduated on June 5, 2009 as the youngest girl to earn a high school diploma from an accredited high school. Paige had a 4.0 grade point average; however, she excelled in other areas as well. An extremely accomplished violinist, in addition to playing at her graduation, she was the selected violinist for NASA's 50th Year celebration and at President Obama's Inaugural Luncheon.

My colleagues also may know Paige from her passionate efforts to Save the Sharks. Starting at age eight, she has worked to educate people about sharks and dispel the myths that have led to a number of species becoming endangered. Paige has given briefings at the Smithsonian Air and Space Museum, the Science Museum of Virginia, and to the United States Congress.

Madam Speaker, Paige Epler represents the best this country has to offer, and her dedication to her studies bespeaks of the bright future before her. I congratulate her on her wonderful accomplishment and wish her well in all of her future endeavors.

IN TRIBUTE TO THE LATE AUBREY EMMITT FALLIN

HON. JACK KINGSTON

OF GEORGIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. KINGSTON. Madam Speaker, I rise today to honor the life and service of a truly great American, Aubrey Emmitt Fallin. Aubrey was a courageous veteran, a dedicated citizen, and a fiercely loyal friend and father.

Aubrey was a patriot by anybody's definition. He served as a marine during WWII, landing on Iwo Jima February 19, 1945. He demonstrated indestructible bravery and strength, enduring a grueling 24 hours in which 2,721 of his fellow patriots lost their lives. Within the following 36 days, over 7,000 American soldiers were killed in action. His presence during this historic struggle put him in one of the bloodiest battles in World history. If it were not for brave men like Aubrey the war would have been lost. Risking and overcoming much, Aubrey emerged from the war with deeply rooted pride, admiration, respect, and love for his America.

After his completion of service, Aubrey was not only a veteran, he was a veteran's veteran. Beyond his recollection and stories of this era he would also give lectures on how to apply yesterday's lessons to today and tomorrow. In peacetime, he was just as fierce of a freedom fighter as he was when bullets were flying all around him. Even as his health failed him, he kept a vigilant eye out for the best in-

terest of America. He used his devotion to our great nation to spur and awaken that very same passion within every individual he knew.

Beyond the battlefield, Aubrey served on the front lines of his local political community through his active leadership. He was a member of Coffee County Board of Registrars, The American Legion and Veterans of Foreign War, past chairman of The Coffee County Republican Party, former president of Douglas Hobos & Shriner Clowns, a member of the Masons and Shriners, and a past president of the Exchange Club. He manifested his faithful love for our country through continuing to sacrifice his time and serve his fellow citizens. His unwavering service, vigilance, and outspoken nature secured freedom for all.

Aubrey was an unquestionably loyal friend. I never left Coffee County without at least one bag of peanut brittle. Enjoying a treat made by such patriotic and loving hands was an honor. We will miss Aubrey as a friend and companion, and we will always be appreciative of the freedom we enjoy because of his and others' sacrifice. His life undoubtedly impacted all who came in contact with him for the better. Aubrey has left a lasting legacy of compassion, strength, and service. May God bless his memory forever!

IN REMEMBRANCE OF THOMAS RAE

HON. DENNIS J. KUCINICH

OF OHIO

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. KUCINICH. Madam Speaker, I rise today in remembrance of Thomas Rae and in recognition of his dedication to his family and country.

Thomas was born on March 2, 1930 in Cleveland Ohio as one of five siblings. Upon graduating from high school, Thomas joined and served in the United States Army for three years before being honorably discharged. After returning to Ohio, he married Mildred Dziak, and they had four daughters who were raised in Strongsville, Ohio. While raising a family, Thomas worked as an inspector for Terex General Motors and later as a supervisor at NASA. Thomas enjoyed his later years in the company of his children and their families. He was fortunate enough to spend time with all thirteen of his grandchildren and especially enjoyed watching them participate in sports. Thomas also took pleasure in the outdoors, playing golf, and handy-work after retirement.

Madam Speaker and colleagues, please join me in remembrance of Thomas Rae, who lived his life with the enduring support of his family and in recognition to his dedicated service to our country. I offer my deepest sympathies to his wife, Mildred; children, Denise Kucinich, Karen Vraja, Arleen Miciunas and Cheryl Vanderwyst; and grandchildren, Gary, Matt, Ryan and Michael Kucinich, Amanda, Samantha and Tommy Vraja, Lukas, Alyssa and Alec Miciunas, Lindsey, David and Nicole Vanderwyst.

PERSONAL EXPLANATION

HON. BEN RAY LUJAN

OF NEW MEXICO

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. LUJÁN. Madam Speaker, due to scheduling conflicts, I was unable to be present for rollcall vote No. 431. Had I been present, I would have voted "no."

RECOGNIZING EUROPE'S BLACK POPULATION

HON. ALCEE L. HASTINGS

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. HASTINGS of Florida. Madam Speaker, I rise today to introduce a resolution recognizing Europe's Black population and expressing solidarity with their struggle.

Last year, on April 29, 2008, I chaired the U.S. Helsinki Commission hearing entitled, "The State of (In)visible Black Europe: Race, Rights, and Politics" which focused on the more than 7 million people who make up Europe's Black or Afro-descendant population.

Despite their numerous contributions to European society, like African-Americans here, many Black Europeans face the daily challenges of racism and discrimination.

This includes being the targets of violent hate crimes, many of which have resulted in death. Existing inequalities in education, housing, and employment remain a problem and racial profiling is a norm. Few Black Europeans are in leadership positions and political participation is also limited for many, providing obstacles for addressing these problems.

In an effort to raise public awareness of these issues at the national and international level, the Black European Women's Council (BEWC) was launched on September 9, 2008 at the European Union's headquarters. More than 130 Black women from across Europe came to "insist on the recognition and inclusion of Black Europeans economically, politically, and culturally."

This resolution supports BEWC's fight for equality and urges European governments to implement anti-discrimination legislation and other plans of action, including a fund for victims incapacitated as a result of a hate crime.

Given the history of our own country, an increase in transatlantic cooperative efforts between our government and European governments, U.S. and European based civil rights groups, and within the private sector would also provide useful partnerships and assistance in combating racism and discrimination abroad and at home.

This resolution therefore also calls on the U.S. Government to increase support for public and private sector initiatives focused on combating racism and discrimination in Europe as part of our efforts to support global human rights.

It is for this reason that on April 15–16, 2009, I also co-hosted the "Black European Summit: Transatlantic Dialogue on Political Inclusion" at the European Parliament in Brussels with Black and other European minority parliamentarians to exchange information on the roles of racial and ethnic minority policymakers in developing and supporting policies

and initiatives to address racism, discrimination, and inequality.

As I continue to work on these initiatives, I urge my colleagues to join me in supporting this Resolution Recognizing Black Europeans and encourage them to review the statements and submissions from the Helsinki Commission's Black Europe Hearing at www.csce.gov.

EARMARK DECLARATION

HON. MARY FALLIN

OF OKLAHOMA

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Ms. FALLIN. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of H.R. 2647, "The National Defense Authorization Act for Fiscal Year 2010."

Title of Project: Advanced Autonomous Robotic Inspections for Aging Aircraft

Amount of Project: \$2,000,000

Account: Air Force, Operations & Maintenance

Project Recipient: Veracity Technology Solutions, LLC 2701 Liberty Parkway, Suite 311, Midwest City, OK 73001

At my request, \$2,000,000 was included in the FY10 NDAA, H.R. 2647, for Veracity Solutions in Midwest City, OK, to implement a fully automated autonomous robotic vehicle that has the capability to inspect for corrosion, as well as crack detection around fasteners for the KC-135 aircraft. Current inspection methods are both antiquated and time consuming, which has increased maintenance downtime and unnecessary refurbishment. A state-ofthe-art nondestructive inspection system and training, which decreases maintenance costs and improves safety, will have the ability to detect corrosion and cracking on the KC-135 wing skins (and other aging aircraft). This system will allow for condition assessment of aircraft structures, as well as continuous assessment through the historical comparison of pervious and present inspection results.

Specifically, the funding will be used for the technical personnel, facilities, and equipment required to develop an integrated system that includes a medical grade ultrasonic inspection system, an advanced impedance plane analysis eddy current unit, and an autonomous inspection vehicle that will allow engineers and depot crews to accurately and instantly identify defects and that are currently undetectable with traditional nondestructive inspection methods. The end product will provide a permanent record of the structural member which can be stored on the network for future comparison.

Title of Project: E–6B Strategic Communications Upgrade Block 1A (VLF–TX & HPTS) Amount of Project: \$4,000,000

Account: Navy, Research, Development, Test & Evaluation

Project Recipient: Rockwell Collins, 400 Collins Road, Cedar Rapids, Iowa 52498

At my request, \$4,000,000 was included in the FY10 NDAA, H.R. 2647, to provide modifications to the Navy's E-6B Mercury TACAMO. The E-6B Mercury TACAMO is a manned airborne communications relay platform designed to provide a survivable, reliable, endurable airborne Command and Control communications link between the President,

Secretary of Defense, and U.S. strategic and non-strategic forces, especially in the time of crisis or national emergency. In performing the TACAMO mission, the platform's primary purpose is the relay of messages via survivable Very Low Frequency transmission (VLF-TX).

This funding will provide for the modification of the VLF-TX, in addition to the High Power Transmit Set (HPTS) subsystem. The current VLF-TX is becoming unsupportable for the mission at hand. The money requested would provide for an encryption function which extends the development cycle for deployment of new equipment. In addition, it would be used to upgrade improvement in the HPTS system and improve the wire control system and operational availability.

These upgrades are critical to the E-6B execution of the TACAMO mission located at Tinker AFB and provide communications to the nation's strategic ballistic missile submarine force as a part of the Minimum Essential Emergency Communication Network (MEECN).

Title of Project: FIDO EXPLOSIVE DETECTOR

Amount of Project: \$7,000,000 Account: Army, Other Procurement Line Number: 135

Project Recipient: ICx Nomadics, 1024 S. Innovation Way, Stillwater, OK 74074

At my request, \$7,000,000 was included in the FY10 NDAA, H.R. 2647, for the FIDO Explosive Detector, which will provide soldiers in combat theater the ability to identify and disable explosive devices and those who manufacture these devices by detecting explosive vapors and residues. Over 1,500 FIDO systems have been fielded in support of current military operations.

The small, lightweight, handheld devices provide the soldier the ability to screen persons, packages, cargo, equipment, vehicles, and buildings and report vapor detections in real time with audio and visual feedback to the operator. The small detection devices can be mounted onto a unit's organic Unmanned Ground Vehicle (UGV) to provide additional force protection, while protecting the safety of the unit. Current FIDO systems have been successful in the field, and advances have been made to increase the ability of the sensor to detect additional substances in use today and into the future. This funding will accelerate the fielding of FIDO's in combat theater and providing explosive detection and protection to men and women in uniform.

Title of Project: Joint Fires and Effects
Trainer System Enhancements

Amount of Project: \$2,500,000

Account: Army, Research, Development, Test & Evaluation

Project Recipient: Creative Technologies, 6255 West Sunset Boulevards, Suite 716, Los Angeles, CA

At my request, \$2,500,000 was included in the FY10 NDAA, H.R. 2647, to provide upgrades to the Joint Fires and Effects Trainer System (JFETS) located at Fort Sill, Oklahoma. The current immersive simulation training capability suffers from one significant drawback—the one-to-one instructor/student requirement. The funding provided for this project would increase the ability for this program to upgrade the voice recognition technology of JFETS and allow a single instructor to manage nine concurrent call for fire training sessions in the Open Terrain module simulta-

neously and improve efficiency by 800%. Additionally, the project will develop an interactive application to drill soldiers in the five essential elements of accurate predictive fires to prepare them before they train in the immersive environment and reinforce the training before the deploy.

Title of Project: T-9 Noise Suppressor Support

Amount of Project: \$5,100,000 Account: Air Force, Military Construction Project Recipient: Tinker Air Force Base, 3001 Staff Drive, Tinker AFB, OK 73145

At my request, \$5,100,000 was included in the FY10 NDAA, H.R. 2647, to fund the construction of foundations and supporting facilities for two T–9 noise suppression systems at Tinker AFB, Oklahoma. This project would consist of the construction of reinforced concrete footings and slabs capable of supporting T–9 style engine testing facilities, a 20,000 gallon jet engine fuel storage and delivery system, utilities, access driveways, and a small office/restroom/break facility. Current engine test facilities are aging and unable to support the current test mission.

With the completion of the new Tinker Aerospace Complex (TAC) and the transfer of engine maintenance to this facility, construction of these test cells near the TAC will allow contiguous support of military jet engine repair, decrease maintenance downtime, and associated cost. This will allow the 76th Maintenance Wing and the 76th Propulsion Maintenance Group the capabilities to meet its mission of delivering engines on time and on cost and position Tinker AFB for increased mission capabilities in the future.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. MELISSA L. BEAN

OF ILLINOIS

IN THE HOUSE OF REPRESENTATIVES Wednesday, $June\ 24$, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2047) to authorize appropriations for fiscal year 2010 for military activities of the Department of Defense; to prescribe military personnel strengths for fiscal year 2010, and for other purposes:

Ms. BEAN. Mr. Chair, I rise in support of H.R. 2647, the National Defense Authorization Act and encourage its passage. Earlier this Congress I introduced H.R. 1267, "Captain James A. Lovell Federal Health Care Act of 2009, which provides legislative authority to the Navy and the Department of Veterans Affairs (VA) to jointly operate the new "Captain James A. Lovell Federal Health Care Center." In the other body, Senator DICK DURBIN has been working to include similar language in the Senate version of the National Defense Authorization Act.

After completion, the Lovell Federal Health Care Center will be the first health care facility in the nation to be operated jointly between the VA and the Navy saving taxpayers millions of dollars that would otherwise have been needed to rebuild or renovate the Navy's nearby hospital. Without this legislation, the Center will not be able to provide essential services to

thousands of military beneficiaries in the region. Beneficiaries who had previously received care at the Naval Health Clinic Great Lakes would either be ineligible for care or would charged a significant co-pay for certain care, including emergency, hospitalization, outpatient, and behavioral health services. The facility is scheduled to begin joint operations on October 1, 2010.

While my legislation was not included in the underlying bill, it is my understanding that Senator Durbin will be able to include similar language in the Senate NDAA. I will continue to work with my colleagues in the Senate on its inclusion, and encourage passage of the underlying bill.

"A VISION FOR HEALTH CARE" COMMENCEMENT ADDRESS BY SENATOR RICHARD T. MOORE

HON. MICHAEL E. CAPUANO

 $\label{eq:ofmassachusetts}$ IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. CAPUANO. Madam Speaker, my friend, Senator Richard T. Moore was honored recently at the commencement of the New England College of Optometry. I wanted to share his remarks, as his address justly paid tribute to the school, its faculty, and graduates for their commitment to public service.

A VISION FOR HEALTH CARE

President Chen, Chairman Manfredi, Vice Chairman Ferrucci (my friend and personal Optometrist), Members of the Board of Trustees, parents, alumni, friends, and most especially, my fellow graduates of the Class of 2009... I'm honored to share in your celebration today and to receive a degree from this prestigious institution with its well-deserved reputation for improving access to care, enhancing the quality of life by preventing blindness, and developing innovative. economically viable models of eve care.

Visus per mentem, vision through the mind, has long been the motto of this great College. It is a phrase that reflects a sincere commitment to learn the skills and knowledge necessary to serve others, as well as a deeply felt belief that you can help people to see the world with more clarity and purpose—to give in a way, the gift of sight—or at least improved vision. Hopefully, your clinical experience working at the New England Eye Institute and in community health centers and school or elderly vision clinics, has kindled in you to a desire to devote some portion of your time, treasure and talent to bring quality eye care to the underserved of our society.

Few, if any of you, in the Class of 2009 could have attended New England College of Optometry for four or more years without deriving from your studies, from your outstanding instructors and most of all from your own inner hearts some sense of inspiration and idealism as well as an appreciation of your social responsibility as a newlyminted health care professional.

CONTINUE THE LEGACY OF COMMUNITY SERVICE

Graduates of New England College of Optometry who preceded you have blazed a trail of community service through vision research and care that is almost legendary! They left an inspiring legacy upon which you and your classmates can now build. With your OD degree in hand, challenge yourselves to follow in the footsteps of exemplary alumni such as Charlie Mullen OD "69 (who

addressed you a few moments ago) and Kenneth Myers OD "74, who firmly established vision care as a focus of the U.S. Veterans Administration. Their pioneering work is, today, helping wounded veterans of the wars in Iraq and Afghanistan to see beyond the trauma of war and return to productive lives in our communities.

Then, there's Edward Goodnig OD "76. He brought his knowledge and skills to underserved regions expanding primary care opportunities for Alaska's Native American settlements and schools. You may also know of Frank Thorn OD "79, today's Commencement Marshal and an expert on the causes and development of Myopia, who has shared his professional knowledge and restless energy from this campus on the banks of the Charles River to remote villages in the Amazon Rain Forest and-in Marco Polo fashion—from Europe to China. Their exciting and fulfilling careers, chronicled in the College's 2008 Annual Report, offer a glimpse of the potential that awaits you as today's graduates.

Such stories of successful graduates can teach, they can offer hope, they can provide inspiration. But they cannot supply the courage to follow your own path. For that each of you must look into your own hearts. Accept your degrees today with the same pride, enthusiasm, and commitment that launched those pioneers of Optometry into rewarding lives of caring service.

CONTINUE TO LEARN AND SHARE KNOWLEDGE

Never be too busy to keep from learning how to better serve your patients. That includes sharing your real world knowledge of your patients and the condition of their eyes with those involved in academic research here at New England College of Optometry and elsewhere. It also means staying informed about the rapidly changing science of your profession. Each of you, my fellow graduates, as our newest health care professionals, have a responsibility to continue your education by maintaining competency in vision care and in the technology necessary to deliver the best quality of care to all who seek better vision.

Whether your career takes you to remote regions of America or the world, or takes you back to wherever you may call "home," remember one of the basic concepts that you learned here in the Back Bay, that eye care professionals are an integral part of the team of primary care providers, and deserve to be treated with the same degree of professional respect as any other health care professional! In this era of health care reform, each of you will play an essential role in not only diagnosing and treating conditions of the eye, but you will also serve as part of the team of professional caregivers who assist and support each other for the benefit of every patient.

MASSACHUSETTS AS A MODEL FOR THE NATION

For the past four years, as each of you have been immersed in becoming competent, dedicated vision care professionals in the classrooms at 424 Beacon Street, I've been learning the lessons of health care reform about a mile away in the State House meeting rooms at 24 Beacon Street. The grades are now in, and the results are clearly informing the growing national debate on health care. Massachusetts is leading the way in health care reform! We are:

First in the nation in health care access. First in electronic health records and e-prescribing.

In the forefront of patient safety, quality improvement, and cost containment.

Leading the way in prescription drug ethics.

In just three years, 432,000 Massachusetts residents, who were previously un-insured,

have gained access to health care and the many stories of lives saved or improved are truly heart-warming.

OPTOMETRY'S CONTRIBUTION TO HEALTH REFORM

One of the challenges facing Massachusetts and the Nation in fully realizing the health improvement and cost savings benefits of health care reform is the need to expand patient access to primary care. It is just as important—and less expensive—to keep people healthy, as well as to treat those who are ill. We have made great progress in expanding access to health insurance for the people of Massachusetts, but there is still an unmet need for easy access to primary care providers. I believe that optometrists, such as each of you, are ready—even anxious—to help to fill some of that void.

To address this challenge, those who pay for health care need to embrace new payment models that support wellness as well as coordinating care for those who suffer from illness, injury or less than good health. Any such wellness effort needs to include regular screening—such as vision screening—and be coordinated with health information technology such as through a centralized vision care registry.

Major stakeholders in health care reform obviously include the physician community. The Massachusetts Medical Society, the oldest, continuously operating state medical society in the United States, is the primary voice of physicians in the development of public policy. However, it sometimes seems to me that the society's policy positions have evolved far more slowly than the progress of science itself.

An old baseball player once said, "I don't question the integrity of an umpire, just his eyesight." Similarly, I don't question the integrity of our state medical society, just their vision! As fewer medical doctors enter the field of primary care, the medical profession needs to embrace other health professionals who, with appropriate training such as that provided by the New England College of Optometry, can do much to provide safe, cost-effective care for patients needing attention.

It's high time for all Massachusetts physicians to rise above the tradition-bound guildmentality that confounds health care progress, and respect the education and experience of all health professions in treating the whole person. It's time for Massachusetts to embrace treatment regimens for optometrists that are already fully accepted in 49 other states, if we are to offer quality care that is convenient and affordable for patients. You, the Class of 2009, must make your voices heard as that debate unfolds!

It was Robert Kennedy who once challenged an earlier graduating class at another college—"to decide, as Goethe put it, whether you will be a hammer—or an anvil. The question is whether you are to be a hammer—whether you are to give to the world in which you were reared and educated, the broadest possible benefits of that education." So I challenge you to get involved in writing the health care policy of your generation—be a hammer!

A VISION FOR HEALTH CARE IN AMERICA

You are graduating at a most exciting time in health care! As you begin your professional careers in vision care, health reform is about to take center stage in the national arena. National health reform is likely to include minimum standards for benefits, an individual insurance mandate, a guaranteed issue requirement for health insurance, a prohibition on excluding coverage of pre-existing conditions, the creation of an insurance exchange where people can sign up for coverage—all factors that are included in the Massachusetts health reform effort.

If we view health reform through the lens of the ongoing Massachusetts experiment, there are some fundamental principles to anchor the national effort.

- 1. Each of us has an individual responsibility to take care of our health—including screenings and check-ups, as well as maintaining health insurance to help pay for our care and that of our families.
- 2. Each of us has a collective responsibility, as citizens of a caring society, to support public policies that guarantee access to safe, high quality, affordable and patient-centered health care for everyone in society.
- 3. Each of us, in the field of health care, has a professional responsibility to strive for the highest level of competency, to ensure that we, and our colleagues in the patient care team, deliver the right care at the right time and in the right place.

These principles can serve as a shining beacon for health reform in the nation, much as this Commonwealth led the nation in propagating the principles of democratic government, social progress, and educational excellence throughout its proud history.

Massachusetts" first Governor, John Winthrop, wrote in 1630 about the social experiment being launched in this New World. He called upon his Puritan brethren and all their descendants to share their resources and gifts with others, "rejoice together, mourn together, labor and suffer together so that—"the world will say of succeeding plantations, may the Lord make it like that of New England . . . we shall be as a city upon a hill. The eyes of all people are upon us." Sharing our gifts with others is the cornerstone of health care reform in Massachusetts and, I hope, it will be your personal cornerstone in your health care careers as well.

Truly, the eyes of all people in America are focused on the Massachusetts health reform experience as a framework for bringing expanded access to quality care to all Americans. But that's not all we're contributing to health care. This morning, Massachusetts is sending forth from this city upon a hill, a new class of highly skilled, and energized health care professionals with their degree in optometry in hand!

While past experience may teach us to be skeptical of the promises of any politician, to those of you who will dedicate your health care careers to the betterment of your state and all her people—I can promise a lifetime of challenge and opportunity, sometimes exciting and rewarding, sometimes slow and difficult, but always, always worthwhile.

And let me add one final bit of parting wisdom: No one ever injured his or her eyesight by looking on the bright side of things! The economy will improve! You'll earn a good living! And those of us in government can't wait to share in your success every April 15th!

IN HONOR OF CAPTAIN MICHAEL T. DOYLE

HON. DENNIS J. KUCINICH

OF OHIO

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. KUCINICH. Madam Speaker, I rise today in honor of Captain Michael T. Doyle, upon his retirement from the Cleveland Police Department, following thirty years of dedicated service to the citizens of Cleveland.

Captain Doyle graduated from Normandy High School in Parma, Ohio, then went on to graduate with honors from Cleveland State University. Shortly thereafter, Captain Doyle accepted a position in law enforcement as the Assistant Deputy Sherriff for Medina County. After four years, in 1981, he began his service to the City of Cleveland as a Cleveland Police officer.

Captain Doyle's service to our community extended across nearly every police district in the City and included work as patrol officer, detective, sergeant, lieutenant and captain. Throughout his tenure, Captain Doyle fostered trust, communication and cooperation among individuals throughout our community, from neighborhood block club members to elected officials at Cleveland City Hall.

Madam Speaker and colleagues, please join me in honoring Captain Michael T. Doyle for his unwavering dedication to protecting the citizens of Cleveland, Ohio.

EARMARK DECLARATION

HON, GARY G. MILLER

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. GARY G. MILLER of California. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of the FY 2010 Homeland Security Appropriations Bill.

Requesting Member: Congressman GARY G. MILLER

Bill Number: H.R. 2892

Account: FEMA, State and Local Programs Legal Name of Requesting Entity: City of La Habra

Address of Requesting Entity: 201 E. La Habra Blvd., La Habra, CA 90631

Funding Secured: \$254,500

Description of Request: Currently, the City of La Habia's Emergency Operations Center (EOC) is a very small conference room within the Police Station. The maximum occupancy is less than a dozen individuals, and there is not adequate space or equipment to serve as an Emergency Operations Center, particularly if there were a large-scale emergency such as an earthquake, wildfires, act of terrorism, etc. During the recent "Golden Guardian" earthquake exercise in California, the team evaluating the City's performance noted the inadequacy of the facility and its hindrance to the exercise. The problems would be even more pronounced should there be an actual emergency requiring the mobilization of our first responders and emergency personnel. This project would provide for necessary equipment and modifications to establish the various reguired components of an EOC (Planning and Intelligence, Operations, Communications, Public Information, etc.). I believe that it is critical for Congress to use taxpayer dollars responsibly by investing in Southern California communities to prevent, combat, and contain the devastating threat of fire and natural disasters that routinely ravage the Southern California landscape

TRIBUTE TO REVEREND DR. DAVID GORDON PERSONS

HON. BRIAN HIGGINS

OF NEW YORK

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. HIGGINS. Madam Speaker, I rise today to honor Reverend Doctor David Gordon Persons on the occasion of his retirement from Wayside Presbyterian Church after thirty three years of leadership. It is my pleasure to recognize Reverend Dr. Persons and acknowledge him as an influential role model in the Western New York area.

Reverend Dr. Persons' leadership abilities were apparent at an early age. As a student of Sherman High School, he was lettered in both basketball and track and he was a member of the Top Math Team to represent Western New York at Boys Town. Upon graduating from Sherman High School in 1961, he received the American Legion Citizen of the Year award.

Reverend Dr. Persons' commitment to the Western New York community is evident by his leadership, devotion and dedication to the people in our community. His community service extended to the Lake Shore Volunteer Fire Department, where he served as Chaplain and Life Member for over thirty years. He was also a member of the Kiwanis Club from 1979 to 1986.

His belief that understanding and reaching out to the world can make a difference led to his co-founding of the Task Force to Reduce the Nuclear Arms Race at the United Nations, which later became the Peace Committee of Western New York. He has been a major influence and inspiration in the lives of young people. From 1979 to 1986, he led yearly youth group bike tours in Western New York and Southern Pennsylvania. Reverend Dr. Persons also led a youth group to the 20th Anniversary of Martin Luther King's speech.

Foremost, Reverend Dr. Persons has been integral to the life of his congregation. Over his religious career, he has officiated at some six hundred funerals, six hundred weddings and one thousand baptisms. His skills were recognized by his colleagues, and from 1965 to 1967, Reverend Dr. Persons was President of the Preaching Association in Seminary. In 1987, he was awarded grants to study meditation in ashrams in India. He is currently Moderator of Wright's Memorial Presbyterian Church—Native American Church in Irving, New York as well as Moderator of Presbytery of Western New York. He also holds the positions of the Chair of Presbytery Church and Society Committee as well as the Head of Presbytery Worship Committee.

Madam Speaker, along with his family, friends and great admirers who will join together today at the Wanakah Country Club, I am honored to pay tribute to the admirable accomplishments of Reverend Dr. Persons. His life of leadership, compassion and service to others is truly an example for us all on the enormous difference one person can make. I wish him all the best in his retirement.

WEB SITE INCLUSION OF VA SCHOLARSHIPS

SPEECH OF

HON. MAXINE WATERS

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Tuesday, June 23, 2009

Ms. WATERS. Mr. Speaker, I rise in support of H.R. 1172-to direct the Secretary of Veterans Affairs to include on the Internet website of the Department of Veterans Affairs a list of organizations that provide scholarships to veterans and their survivors. This important measure would provide an invaluable resource for our veterans and their survivors. In an effort to increase information accessibility, this bill would create a convenient section within the Veterans Affairs Department website for veterans and/or their survivors to view all available veteran scholarship opportunities that various public and private organizations sponsor throughout the year. I commend Rep. JOHN BOOZMAN for bringing this measure before the floor.

My veteran constituents frequently contact me with reports on the many administrative failures and shortcomings of the Department of Veterans Affairs. Slow processes and backlogs have become the expectation rather than an exception in the level of service our veterans receive. This is unfortunate as we send these brave men and women to armed conflict, and yet, we cannot provide them with the necessary tools and resources to become reoriented with society. This bill provides one solution to a relatively simple problem. I have no doubt, however, that many veterans and their families will appreciate this information, especially in light of the economic recession.

Mr. Speaker, I am pleased to add my voice of support for H.R. 1172. I look forward to working with my colleagues to ensure that we continue to provide the necessary resources towards improving our Department of Veterans Affairs' administration and services.

RECOGNIZING THE FIRST BAPTIST CHURCH OF DANVILLE, VIRGINIA

HON. THOMAS S.P. PERRIELLO

OF VIRGINIA

IN THE HOUSE OF REPRESENTATIVES Friday, June~26,~2009

Mr. PERRIELLO. Madam Speaker, today I recognize the First Baptist Church of Danville, Virginia, which celebrates its 175th anniversary on June 28, 2009. Since its founding in 1834, the First Baptist Church has been a source of fellowship, education, and service in its community and beyond.

Although the First Baptist Church has suffered from a terrible fire, moved its location several times, seen the town it serves grow from 1,000 to almost 50,000, and faced countless other changes throughout its long history, it remains true to its founding principles. Under the leadership of Reverend Stephen Cook, today the church is a community of strong relationships, where individuals bond over worship, meals, study, and music. Their affinity extends beyond just Sunday mornings to include weekly dinners, small group meetings, choirs and instrumental ensembles, programs for seniors and children, cultural outings, and

engagement in the larger community through service

I commend the First Baptist Church and its leadership on this commitment to hands-on service, whether locally, elsewhere in our nation, or abroad. The church has stated, "When our worship together ends, our service truly begins," and it has undoubtedly abided by this principle. The numerous organizations that have benefitted from the dedication and generosity of the church's congregants include Hope Harbor, Hope Tree Family Services, God's Storehouse, Klothes 4 Kids, the Danville Homeless Shelter, Habitat for Humanity, and Baptist World Aid. The efforts of the First Baptist Church to live out its mission in its works are an inspiring example: we should all strive to be so diligent in following the call to love and serve our fellow man.

The Book of Isaiah tells us, "And if you give yourself to the hungry, and satisfy the desire of the afflicted, then your light will rise in darkness, and your gloom will become like midday." I congratulate the First Baptist Church on its tireless efforts to meet both the physical and spiritual needs of the Danville community, and I hope that its light will continue to shine for many years to come.

ARMY RESERVE ASSOCIATION'S ENLISTED SCHOLARSHIP PROGRAM

HON. TODD TIAHRT

OF KANSAS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. TIAHRT. Madam Speaker, I am honored today to speak on a wonderful program that impacts the lives of many great heroes and their families. The Army Reserve Association's, ARA United States Army Reserve, USAR Enlisted Scholarship Program awards a \$500 scholarship to assist qualifying enlisted reservists or their dependents attend an insti-

tution of higher learning.

Started in 2000 as an initiative of Command Sergeant Major Ray Lackey, this program has awarded a total of \$225,500 in scholarships. Through the generosity of the United Services Automobile Association, USAA, the administrative efforts of the ARA, and the support of the USAR, these patriots have the opportunity to pursue their dreams. The opportunity to pursue their dreams. The opportunity to further their education not only benefits these heroes, but the Army Reserve and the country as a whole.

I applaud the Army Reserve Association and all those responsible for this effort on behalf of our Army Reserve soldiers and their families. Additionally, I request that the following two letters regarding this program be inserted into the record: a letter from the Army Reserve Association and a letter from Lieutenant General Jack C. Stultz, Chief of the Army Reserve.

THE ARMY RESERVE ASSOCIATION,
Fort McPherson, GA, March 3, 2009.
Subject ARA Enlisted Scholarship Program
Standards Approval.

Lieutenant General Jack C. Stultz, Commanding General,

U.S. Army Reserve

DEAR LIEUTENANT GENERAL STULTZ: This letter requests you approve the standards of the ARA Enlisted Scholarship Program listed below. Request approval of the following standards:

(1) a member of the USAR not under flag or pending disciplinary action;

(2) qualified in the MOS of their position of assignment:

(3) attending or entering an institution of higher learning (2 or 4 year college, vocational school, bible college, etc.) that is regionally or nationally accredited;

(4) military dependents must be registered In DEERS.

The applicant's chain of command CSM or SGM will certify that the applicant meets qualification standards (1) through (4), as applicable.

The ARA Enlisted Scholarships are for enlisted members of the United States Army Reserve and their dependent family members. Each year the ARA offers scholarships to each major command to which USAR members are assigned as designated by the Command Sergeant Major of the USAR. The annual goal of awarding fifty scholarships is predicated on the number of major commands participating and the number of scholarship applicants from each major command, as well as the amount of funds donated by the program cosponsor, the United Services Automobile Association (USAA).

The Army Reserve Association will create an announcement for the annual scholarship program and will transmit that announcement to the USARC G-1 with a request that the USARC G-1 forward the announcement to each major command. The announcement will include the approved standards and an application form that each command's applicants can use to apply for the scholarships. The calendar year program's closing date for receipt of all applications is 31 December, unless a waiver is granted.

We request the USARC G-1 to forward the

We request the USARC G-1 to forward the scholarship program announcement to USAR commands with instructions on submitting the applications to the USARC G-1 together with submission dates specified by the USARC G-1, so that applications can be forwarded to the ARA in time for evaluation and award of scholarships

and award of scholarships. The ARA will appoint a selection board with a board president from its existing association membership to select nominations for award of the ARA Enlisted Scholarship Award. Board members will serve in their private-citizen capacity and not in any military role and the board recorder may be a member of the Army Reserve Association. The selection list will be compiled, signed by the ARA enlisted scholarship selection board president and forwarded to the ARA for issuance of individual scholarship awards. The ARA may choose to either present or mail the awards to the Soldier's command or directly to the individual.

We appreciate your continued support and assistance in implementing this program.

MG KENT HILLHOUSE (R), President, Army Reserve Association. COL George M. Lind, (R) Director, ARA Field Support Services.

DEPARTMENT OF THE ARMY, OFFICE OF THE CHIEF, ARMY RESERVE, WASHINGTON, DC, APRIL 24, 2009. Major General KENT HILLHOUSE, RETIRED,

Winfield, Kansas.

DEAR GENERAL HILLHOUSE; This is to acknowledge receipt of your letter of March 3, 2009, requesting approval of the eligibility standards for the Army Reserve Association (ARA) Enlisted Scholarship Program. I approve the following eligibility standards:

a. an enlisted member of the U.S. Army Reserve not under flag or pending disciplinary action

b. qualified in the MOS of their position of assignment

higher learning (2 or 4 year college, vocational school, bible college, etc.) that is regionally or nationally accredited

d. Military dependents who are registered in DEERS

The ARA will submit any changes to the eligibility standards to this office for approval before implementation. It is understood that ARA is solely responsible for selection and notification of scholarship

The Army Reserve G-1 will make information available to the Army Reserve Major Subordinate Commands regarding the scholarships and forward all applications to ARA for processing as outlined in your letter.

If you have questions or concerns, please contact Sergeant Major Gary Martz of the Army Reserve G-1, at (404) 464-9011. Sincerely.

> JACK C. STULTZ. Lieutenant General, U.S. Army Chief, Army Reserve.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. DENNIS J. KUCINICH

OF OHIO

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2647) to authorize appropriations for fiscal year 2010 for military activities of the Department of Defense, to prescribe military personnel strengths for fiscal year 2010, and for other purposes:

Mr. KUCINICH. Mr. Chair, the amendment offered by Representative SCHIFF of California would allow a federally funded research and development center (FFRDC) under the National Aeronautics and Space Administration's (NASA) to apply for grants made available by the Department of Defense. Of NASA's ten field centers, there is only one FFRDC-the Jet Propulsion Laboratory (JPL)—in Pasadena, California. The amendment would allow this NASA center to do the "research, development, demonstration, or transfer of technology . . . for activities including, but not limited to, those conducted by the center under contact with or on behalf of the Department of Defense."

NASA is a civilian agency, doing civilian work that affects every American in various ways. It must not become too closely associated with the Department of Defense. NASA's mission is to pioneer scientific discovery, aeronautics research and space exploration, not to conduct research for the benefit of the Department of Defense.

At a time when these programs may be facing extensive funding cuts, allowing NASA's field centers to focus solely on carrying out NASA's mission could not be of more importance. Allowing JPL to apply for these grants would set a precedent that could pave the way for other NASA centers to follow suit. NASA is prohibited by law from accepting these grants from the Department of Defense for a reason. NASA should not be doing the work of the Department of Defense and should remain a distinct entity doing strictly civilian work for civilian benefits. It should be fully funded in order to allow it to do so.

c. attending or entering an institution of HONORING THE MINUTE MAN NA-TIONAL HISTORICAL PARK ON THE OCCASION OF ITS 50TH AN-NIVERSARY

HON. EDWARD J. MARKEY

OF MASSACHUSETTS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. MARKEY of Massachusetts. Madam Speaker, the resolution that I am introducing today with the gentlewoman from Massachusetts, Ms. TSONGAS, honors the Minute Man National Historical Park in Massachusetts on its upcoming 50th anniversary. Since being established in September 1959, the Minute Man National Historical Park has played a vital role in protecting and preserving the historic sites in the towns of Lexington, Lincoln, and Concord, where the American Revolution began. As the July 4th holiday approaches, it is fitting that we also have the opportunity to recognize Minute Man for its critical role in educating millions of Americans about the ideals of freedom and democracy that were embodied in the American Revolution and are the cornerstones of our Nation.

The Minute Man National Historical Park recognizes the people, places and events that have become enduring symbols of our shared American values. The park includes many important sites and landscapes along the historic 22-mile route from Boston to Concord, known as the "Battle Road" where British soldiers and American militia first clashed on April 19, 1775. The park includes the famed North Bridge in Concord, MA, where American militia were first ordered to return British fire. This heroic action was commemorated by the great American laureate Ralph Waldo Emerson in "The Concord Hymn" as "the shot heard round the world." The park commemorates Paul Revere's "midnight ride" on the night of April 18, 1775, to raise the alarm for the residents of Concord, Massachusetts, that the British were marching to destroy military stockpiles.

The Minute Man National Historical Park continues to serve as a vital and enduring educational resource not only to the American people, but also to people all around the globe. The Minute Man National Historical Park plays a vital role in protecting these special places in Massachusetts where the fight for our democracy began and providing a true benefit to our Nation.

A TRIBUTE TO FRANK REYES FOR A LIFETIME DEDICATION TO EDUCATION AND PUBLIC SERV-ICE

HON. JERRY LEWIS

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. LEWIS of California. Madam Speaker, I would like to pay tribute to my good friend Frank Reyes, an exceptional educator who has helped the San Bernardino Community College District become a national leader in programs designed to meet a diverse student hody.

Frank Reyes has been involved in education in San Bernardino County for more than three decades, beginning with receiving a bachelors and masters degree from California State University, San Bernardino, and culminating in his current position as Executive Director of Governmental Affairs for the 16,000-student San Bernardino Community College District.

Prior to joining the district management team, Frank worked as a counselor, professor, Director of Community Services and Director of the Counseling Department. He has shown a dedication to his hometown, and the students there, which has paid huge dividends for the community college district. He is part of the team that has helped keep costs down, while improving the campuses and their quality of education. This has helped make the two colleges—Crafton Hills College in Yucaipa. and Valley College in San Bernardino—among the most diverse in the Nation.

In his current role in administration, Frank has been extremely successful at winning competitive government grants for the community college district. After a major earthquake in 1992 made nearly all of the buildings at the Valley College campus unsafe. Frank led a team that secured Federal Emergency Management Agency funds to build a new library, health and human services building, administration and student services building. Most recently, the campus has added a 37,000square-foot campus center, a new art building and modern gallery.

I was proud to work closely with Frank in bringing funding to deserving projects for the colleges. Thanks largely to his hard work, the Federal Aviation Administration provided \$12.6 million for a new state-of-the-art fire academy that focuses on commercial aviation fires. Located at the San Bernardino International Airport, the facility attracts students from all over the country for real-life training on a jet fuselage. Most recently, I was delighted to work with Frank in winning the donation to Crafton Hills College of the swimming pool used in the 2004 Olympic Trials, which will be part of a recreation facility used by both the students and the community.

Frank has developed a national reputation for education excellence, serving on the International Development Team in Spain in May 2006, as well as the Defense Department's partnership with the Hispanic Associations of Colleges and Universities (HACU). Frank was also selected to be part of the U.S. Delegation to China in February 2006. The delegation continues its work on business, education and cultural exchanges. He has been a national leader with HACU, ensuring a significant federal funding increase for schools with significant Hispanic student bodies.

His community involvement beyond the colleges has been widely recognized—he has been listed in the Inland Empire Magazine as one of The Most Influential Hispanics and was named Latino of the Year by the Hispanic Chamber of Commerce. He has been Chairman of the Board for the Arrowhead Regional Medical Center Foundation for two years, and is an active Board member of the Hands of Mercy, an organization which builds loft houses for the indigent.

Madam Speaker, after three decades of service to the students and people of San Bernardino County, Frank Reves is retiring from the community college district. Please join me in thanking him for his hard work and dedication, and wish him well in his future enPERSONAL EXPLANATION

HON. LARRY KISSELL

OF NORTH CAROLINA

IN THE HOUSE OF REPRESENTATIVES

 $Friday,\,June\,\,26,\,2009$

Mr. KISSELL. Madam Speaker, on Wednesday, June 24, 2009, I missed two rollcall votes as I was attending a White House briefing on the Energy bill. Had I been present, I would have voted "aye" on rollcall number 428, and "no" on rollcall number 429.

PERSONAL EXPLANATION

HON. LUIS V. GUTIERREZ

OF ILLINOIS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. GUTIERREZ. Madam Speaker, due to a meeting at the White House, a Financial Services Committee Hearing and other commitments, I was unavoidably absent for certain votes this week. I would like the record to show that, had I been present, I would have voted "yea" on rollcall votes 419, 420, 421, 422, 423, 453, 454, 457, 458 and 460 and voted "nay" on rollcall votes 427, 455, 456, and 459.

A TRIBUTE TO THE LIFE OF DON GILKEY

HON. JIM COSTA

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. COSTA. Madam Speaker, I rise today to pay tribute to the life of an agricultural icon in California, Mr. Don Gilkey of Corcoran, California. Don passed away on May 24, 2009 at the age of 74. He is survived by his wife of 52 years, Moonyeen Gilkey, three children and several grandchildren.

Don Gilkey was born on February 3, 1935 in Corcoran, California to Margaret and Ralph Gilkey. Don graduated in 1952 from Corcoran High School. In 1953 he left for the University of California, Berkeley, where he played football and rugby all four years of college. Don was a lineman and punter for the Cal Berkeley Bears and in 1956 was voted the team captain. He was named First Team All Pacific Coast and Second Team A.P. All-American. In August 1956, during his senior year, Don married the love-of-his life, Moonyeen Apperson, and they spent their first year of marriage in Berkeley while Don finished college. After graduating from Cal, Don spent a short period of time as an officer with the U.S. Army. Upon returning, Don declined several offers to become a professional football player, deciding instead to return home to Corcoran where he would become an integral part of the family farming business.

In 1958, Don became a partner with his brother Charles and brothers-in-law Don Riddle and Ken DeVaney in the family farming operation. Soon thereafter, the family partnership grew to include another brother-in-law, Bill Bondurant. During his farming career, Don farmed cotton, grain, alfalfa and raised turkeys. In 1962, the family farming operation

was such a success they decided to build their own cotton gin and the company went on to successfully bale 30,000 to 60,000 bales per vear at their peak.

In 1966, one of Don's many community efforts became a reality when a new football stadium was built. In appreciation of Don's efforts, the following year the community of Corcoran overwhelmingly named Don Gilkey as their "Citizen of the Year". His community involvement was boundless. For many years, Mr. Gilkev served on the board of directors for Lakeland Dusters Aviation and Commercial Tire. He was a three-term board member and president of the Corcoran Unified School District board of trustees, president of the Corcoran Chamber of Commerce, member of the Corcoran Hospital Foundation, a lifelong member and trustee of the Corcoran First United Methodist Church, a long time member of Corcoran's Rotary Club, board member of the California Wheat Commission and the California Wheat Growers Association, past delegate to the National Cotton Council, member of Class V of the California Agricultural Leadership Program and for several years Don served as a board member of the California Ammonia Company. Don was honored as a member of the "65 Club", a select group of farmers chosen for their achievement in agriculture production, farm and community leadership. This special honor was given to him in 1982 in Washington, D.0 by then U.S. Secretary of Agriculture John R. Black during the National Agriculture Day ceremonies.

It goes without saying that Mr. Don "Donnie" Gilkey's dedication to his family, the family farm and his community have earned him a legacy of respect and enormous appreciation from Central Valley farmers, the Corcoran community and the agriculture industry. He will forever be remembered as "Don Gilkey, The Big Man with the Big Heart". I am honored and humbled to celebrate the life of this amazing man and agricultural icon.

NATIONAL DEFENSE AUTHORIZATION ACT FOR FISCAL YEAR 2010

SPEECH OF

HON. JOHN LEWIS

OF GEORGIA

IN THE HOUSE OF REPRESENTATIVES

Thursday, June 25, 2009

The House in Committee of the Whole House on the State of the Union had under consideration of the bill (H.R. 2647) to authorize appropriations for fiscal year 2010 for military activities of the Department of Defense, to prescribe military personnel strengths for fiscal year 2010, and for other purposes:

Mr. LEWIS of Georgia. Mr. Chair, I rise today as a cosponsor of this important amendment and urge of all of my colleagues to support it. I thank the Gentleman from Massachusetts (Mr. McGovern) for his tireless advocacy on addressing human rights issues, and I would like to recognize Cindy Buhl on his staff and Jamila Thompson in my office for their hard work on this issue.

The McGovern-Sestak-Bishop-Lewis amendment would allow public access to the names of graduates and instructors at the Western Hemisphere Institute for Security Cooperation formerly known as the School of the

Americas. This military institution, based at Ft. Benning in Georgia, is known throughout the region for its questionable teachings and record of its graduates.

This amendment is simply about transparency. By revealing the names of the Western Hemisphere Institute for Security Cooperation attendees, we can shine the light of accountability and truth on an institution that is unnecessarily shrouded in secrecy. We can show our regional neighbors that we seek to be their partners in peace, and not coconspirators of aggression.

I urge all of my colleagues to support the McGovern-Sestak-Bishop-Lewis amendment. Mr. Chair, with this amendment we can show that the intentions of the United States reflect a more cooperative foreign policy and a renewed commitment to international human rights standards.

PERSONAL EXPLANATION

HON. ALLEN BOYD

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. BOYD. Madam Speaker, I was unable to attend to a vote on May 20, 2009. Had I been present, my vote would have been "yea" on H.R. 2352, Job Creation Through Entrepreneurship Act.

IN RECOGNITION OF THE LA SAGRADA FAMILIA FESTIVAL

HON. DENNIS J. KUCINICH

OF OHIO

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. KUCINICH. Madam Speaker, I rise today in recognition of La Sagrada Familia Festival being held this June 26 through 28, 2009 and in remembrance of Reverend David F. Fallon, founding pastor of La Sagrada Familia Parish. This year's celebration is the twenty-fifth annual Latin American Festival and is being held at the Sagrada Familia Parish in Cleveland, Ohio.

The members of the La Sagrada Familia Parish in Cleveland have a long history of dedication to our community and to empowering Cleveland's diverse Latin American community. This year's celebration will feature live music, cultural dances, children's activities and a talent show that highlight the rich culture of the Latin American community. This year's honoree, Reverend David Fallon, became the founding pastor of Sagrada Familia on April 11, 1998 and continued in that role until his death on May I, 2009. Under his direction, La Sagrada Familia became a source of strength and support for people of all ethnic and religious backgrounds. Father Fallon initiated numerous programs and organized church volunteers to serve the community through social service, employment and education initiatives.

Madam Speaker and colleagues, please join me in recognition of the La Sagrada Familia Festival as they honor the memory of Reverend David F. Fallon at the 25th annual Latin American Festival. I offer my best wishes for a joyous celebration of culture and community.

TRIBUTE TO SGT. MIKE HEADRICK

HON. ZACH WAMP

OF TENNESSEE

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. WAMP. Madam Speaker, the Volunteer State has done it again! Today, I rise to honor Sgt. Mike Headrick, a Tennessee National Guard soldier from Dunlap, Tennessee, who will be among seven National Guardsmen from across the entire United States competing for the prestigious title of Non-Commissioned Officer (NCO) of the Year.

Sgt. Headrick has successfully competed against other highly talented National Guardsmen from our region for the opportunity to contend in the national finals. Competition begins in the hometown unit and becomes more difficult as the participant advances. In Sqt. Headrick's case, each unit in his Armored Cavalry Regiment squadron selected an NCO to compete at the Squadron level. Testing includes marksmanship, first aid, and warrior task training, along with proficiency on Army regulations and history. Squadron winners move up to regimental competition and face more difficult challenges including a physical fitness test, more warrior tasks, weapons qualification and a 10-mile road march. At the statewide competition, obstacles become even tougher with the addition of a land navigation course, another long road march and a mandatory appearance before a panel of Sergeant

The national competition begins at Fort Benning, Georgia, on July 30, and is packed with a grueling physical fitness test, five-mile run, day and night land navigation course, 12-mile road march with a 30 lb. rucksack, water survival, day and night weapons marksmanship, obstacle course, and hand-to-hand combat with little or no sleep. The competition concludes here in Washington, DC., one week later

Sgt. Headrick is a member of the 278th Armored Cavalry Regiment's Det. 1, Head-quarters Troop, 2nd Squadron, in Gallatin, Tennessee, and has proudly served in our National Guard for six years. He volunteered for military service at the age 33, just before the age-limit cutoff, because he wanted future generations to have the ability to live in freedom without the fear of terrorists attacks.

In civilian life, Sgt. Headrick is a Certified Master Auto Technician at Bavarian Auto in my hometown of Chattanooga. He has been married to his wife, Audrey, for 20 years and they have one son, Alex.

Tennessee is very proud of the accomplishments and service of Sgt. Mike Headrick, and I am honored to recognize him today in the U.S. House of Representatives. This friendly competition sharpens the skills of our service men and women and better prepares them for the intensities of combat. We wish all seven soldiers the very best as they prepare to win the coveted title of Non-Commissioned Officer of the Year, but it's no secret that I hope Sgt. Headrick brings it home to the great State of Tennessee!

EARMARK DECLARATION

HON. HAROLD ROGERS

OF KENTUCKY

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. ROGERS of Kentucky. Madam Speaker, pursuant to the House Republican standards on congressional-directed funding, I am submitting the following information regarding funding included in H.R. 2996, the Department of the Interior, Environment, and Related Agencies Appropriations Act of 2010.

Requesting Member: Congressman HAROLD ROGERS

Bill Number: H.R. 2996

Account: Department of the Interior—National Park Service—Land Acquisition

Legal Name of Recipient: Cumberland Gap National Historic Park

Address of Recipient: US 25E S, P.O. Box 1848, Middlesboro, KY 40965

Description of Request: Provide directed funding of \$500,000 for Cumberland Gap National Historical Park. P.L. 108-07 gave the National Park Service authority to acquire the historic and pristine Fern Lake and surrounding 4500 acre watershed incorporating this area into Cumberland Gap National Historical Park. Fern Lake will eventually serve as a clean and reliable water source for the city of Middlesboro, Kentucky as well as enhance recreational opportunities at Cumberland Gap. In May 2009, using previously secured federal funds, over 2000 acres of this property were conveyed to Cumberland Gap National Historical Park. To date, 4021 acres of the watershed have been added to the park, and the ultimate goal is to acquire 4500 acres within the sightline of the park's popular Pinnacle Overlook.

Requesting Member: Congressman HAROLD ROGERS

Bill Number: H.R. 2996

Account: Environmental Protection Agency—Science & Technology

Legal Name of Recipient: Consortium for Plant Biotechnology Research

Address of Recipient: 100 Sylvan Drive, Suite 210, St. Simons Island, GA 31522

Description of Request: Provide directed funding of \$1,000,000 for the Consortium for Plant Biotechnology Research, a non-profit organization whose membership includes 43 leading U.S. research universities and 39 agribusiness companies and trade associations. 92.6% of funding is utilized for researching plant biotechnologies that will improve the competitiveness of U.S. agriculture by developing technologies to lessen the country's dependence on foreign energy supplies. Federal funds are matched 130% on average. The University of Kentucky is a CPBR member.

Requesting Member: Congressman HAROLD ROGERS

Bill Number: H.R. 2996

Account: Environmental Protection Agency—Environmental Programs and Management—National Programs

Legal Name of Recipient: Rural Communities Assistance Partnership

Address of Recipient: 1522 K Street, NW., Suite 400. Washington DC 20005

Description of Request: Provide directed funding of \$2,500,000 for the Rural Communities Assistance Partnership with the EPA. RCAP service providers work with federal and

state agencies to help small communities address their drinking water and wastewater treatment concerns. While small, rural communities are home to less than 25% of the nation's population, they account for over 85% of the nation's community water systems. Problems with EPA clean water compliance may arise when small communities lack the oversight capacity and technical expertise to deal with the complexities of maintaining a safe and clean supply of water, and communities with fewer than 10.000 residents are more than twice as likely to violate drinking water standards as are larger systems. Each year. the RCAP network delivers services to more than 2,000 rural communities, 90% of which have populations of 2,500 or fewer, while leveraging an average of \$25 in additional funding for every \$1 in federal investment. FY10 funding will be equally divided between technical assistance activities related to drinking water and clean water compliance.

Requesting Member: Congressman HAROLD ROGERS

Bill Number: H.R. 2996

Account: Environmental Protection Agency—STAG Water & Wastewater Infrastructure Legal Name of Recipient: Perry County Sanitation District

Address of Recipient: P.O. Box 1615, Hazard, KY 41702

Description of Request: Provide directed funding of \$500,000 to support the Perry County Sanitation District's ongoing efforts to provide sanitary wastewater treatment services for residents in the Chavies area. Funds will support the Sanitation District in developing a 150,000 gallon per day wastewater treatment plant and an enhanced collection system, which will ultimately serve 502 households. The project will initially construct approximately 24,900 feet of gravity sewer, 3,500 feet of force main and two pump stations to serve 109 new customers. The wastewater treatment plant will be constructed to accommodate future expansions as collection lines are extended to serve additional customers. The Perry County Sanitation District received a grant from the U.S. Army Corps of Engineers for the design of the Wastewater Treatment Plant and Collection System, which covered the cost of a regional facilities plan, environmental assessment and design. An additional \$1.154 million in Environmental Protection Agency funds have also been secured to begin construction.

PERSONAL EXPLANATION

HON. BART STUPAK

OF MICHIGAN

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. STUPAK. Madam Speaker, on Wednesday, June 24, 2009, I could not be present for votes due to a family funeral back in Michigan. I rise today to enter into the RECORD how I would have voted had I been able to vote.

House rollcall vote No. 424. I would have voted no

House rollcall vote No. 425. I would have voted no.

House rollcall vote No. 426. I would have voted no.

House rollcall vote No. 427. I would have voted no.

House rollcall vote No. 428. I would have voted yes.

House rollcall vote No. 429. I would have voted no.

House rollcall vote No. 430. I would have voted yes.

House rollcall vote No. 431. I would have voted no.

House rollcall vote No. 432. I would have voted no.

House rollcall vote No. 433. I would have voted yes.

House rollcall vote No. 434. I would have voted no.

House rollcall vote No. 435. I would have voted yes.

House rollcall vote No. 436. I would have voted yes.

House rollcall vote No. 437. I would have

voted no.

House rollcall vote No. 437. I would have

voted yes.

House rollcall vote No. 439. I would have

voted yes.

House rollcall vote No. 440. I would have

voted no.

House rollcall vote No. 441. I would have

voted yes.

House rollcall vote No. 442. I would have

voted yes.

House rollcall vote No. 443. I would have voted no.

House rollcall vote No. 444. I would have voted no.

House rollcall vote No. 445. I would have voted no.

House rollcall vote No. 446. I would have voted no.

House rollcall vote No. 447. I would have voted no.

House rollcall vote No. 448. I would have voted no.

House rollcall vote No. 449. I would have voted yes.

House rollcall vote No. 450. I would have voted yes.

House rollcall vote No. 451. I would have voted yes.

House rollcall vote No. 452. I would have voted yes.

REGARDING THE AVAILABILITY OF THE CLASSIFIED ANNEX TO H.R. 2701, THE INTELLIGENCE AU-THORIZATION ACT FOR FISCAL YEAR 2010

HON. SILVESTRE REYES

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. REYES. Madam Speaker, I wish to inform my colleagues that the classified annex to H.R. 2701, the Intelligence Authorization Act for Fiscal Year 2010, will be available for review by members during regular Committee business hours, beginning on Monday, July 6th. 2009.

Members will be required to complete the appropriate security paperwork to view any classified information.

Staff are requested to contact the Committee to schedule a viewing appointment for members.

INTRODUCTION OF THE TRIBAL CHARITIES FAIRNESS ACT OF 2009

HON. XAVIER BECERRA

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. BECERRA. Madam Speaker, I rise to introduce the "Tribal Charities Fairness Act of 2009" with Representatives DEVIN NUNES, EARL BLUMENAUER, MICHAEL HONDA, DALE KILDEE, BEN RAY LUJÁN, BETTY MCCOLLUM, and JOHN OLVER. This legislation remedies an inequity in our tax code and will enhance the ability of tribal charities to provide essential services such as nutritional, educational and health care assistance for many in Indian country.

The economic and social needs of the Native American community are immense. Native American households are among the most economically disadvantaged in the United States. Over 25 percent live in poverty, with greater proportions of Native American children and seniors living in poverty compared with the general United States population. Health status is lower for Native Americans. who have a life expectancy that is 4.6 years shorter than all races considered together, and mortality rates from diabetes, tuberculosis, and alcoholism that are many times higher than in the general U.S. population. And although 76 percent of Native Americans have a high school diploma, just 13 percent go on to receive a bachelor's degree.

Tribal charities play an essential role in remedying these untenable circumstances by providing assistance to communities across Indian country. Their work and assistance ensure Native American children, working adults, and seniors have access to the same opportunities available to all Americans.

Unfortunately, the tax code currently treats tribes like corporations rather than like state and local governments when they provide support to charities that serve tribal members. This flawed tax treatment has significant implications, affecting tribal charities' ability to access tax-exempt financing, receive grants from private foundations, and operate in the governmental arena without being subject to additional tax rules and regulations.

The "Tribal Charities Fairness Act of 2009" will correct this inequity in the law by treating tribal governments the same as state and local governments when they provide support to charitable organizations. This simple change in our tax code will have far-reaching, positive effects for tribes and charities across the nation by increasing the availability of resources to address the poor economic and social conditions plaguing many in Indian country.

I encourage my colleagues to support this essential legislation that puts tribal charities on an equal playing field with other government-funded charities and increases their ability to carry out their necessary and important work.

TRIBUTE TO POLICE CHIEF WILLIAM "BILLY" WEBBER

HON. JAMES P. McGOVERN

OF MASSACHUSETTS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. McGOVERN. Madam Speaker, I proudly rise today to pay tribute to William "Billy" Webber, a revered Chief of Police of the Town of Southborough, Massachusetts, who died too early at the age of 53 on November 11, 2008 after a courageous 18 month battle with pancreatic cancer.

Earlier this week, family members, friends and colleagues held a golf tournament in honor of Chief Webber—"dedicated to his memory, to his kind heart and to the courage he has given all of us to rise above the sorrow." All proceeds from the event went to the Dana Farber Cancer Institute in Boston to support research efforts to fight the dreaded disease that claimed his life.

The son of proud parents, Harry and Claire Webber, Bill Webber grew up in Milford, Massachusetts and joined the Police Department in nearby Southborough in 1980, beginning an impressive and distinguished 28 year career in law enforcement. He received his Bachelor of Science in Criminal Justice from Northeastern University in 1983 and earned a Master's Degree in Public Administration from Clark University in Worcester in 2003. He was also a graduate of the State Police Academy where he was President of his class. In 2004 he was appointed as Southborough's Chief of Police.

Chief Webber's career with the Town of Southborough was characterized by honor, courage and commitment. His professionalism and integrity made him a great role model for his fellow officers and law enforcement colleagues. Town Planner Vera Kolias said "Chief Billy Webber had all of the qualities that you can only hope for in one person: an accomplished, intelligent and caring professional, and a consummate gentleman who displayed integrity and sensitivity at every turn."

With Chief Webber's death, the citizens of Southborough have suffered a tragic loss. The love and respect felt by his neighbors and members of the community is reflected by the Town's dedication of its 2008 Annual Report to him. In presenting copies of the Annual Report to his family at a recent Board of Selectmen meeting, Chairman Bill Boland expressed thanks to them "for sharing Billy with us; he was truly a remarkable person and a great representative of the Town of Southborough."

Chief Webber's Pastor, Reverend James Flynn of St. Matthew's Church in Southborough observed that he was a man of great compassion and said that "We of St. Matthews were awed with the example that Bill left for us, a man of faith who genuinely loved his neighbor."

Sadly, the record of impressive achievements and honorable service throughout Chief Webber's life came to an early end on November 11, 2008. As noted by Vanessa Hale, Assistant Town Administrator of Southborough, "It was providential that he left us on Veterans Day—a proud, patriotic American who loved his family, God and Country to the end."

On behalf of the residents of the Third Massachusetts District, I extend our deep sympathy to his loving wife Kathy (Carmody) Webber, his children Kathleen and Kevin, his

siblings Patricia and Stephen, their family members and the legion of friends who will always remember Billy Webber and the cherished part he played in their lives.

PERSONAL EXPLANATION

HON. JOHN LEWIS

OF GEORGIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. LEWIS of Georgia. Madam Speaker, on June 8, 2009, I underwent surgery and have been recuperating for the past 3 weeks. In my 24 years in Congress, I have missed very few votes and have taken pride in having a voting record of over 90%. This is the first time I've missed this many votes. Had I been here, I would have cast the following votes:

```
On rollcall 311, I would have voted yes.
On rollcall 312, I would have voted yes.
On rollcall 313, I would have voted yes.
On rollcall 314, I would have voted yes.
On rollcall 315, I would have voted yes. On rollcall 316, I would have voted yes.
On rollcall 317, I would have voted ves.
On rollcall 318, I would have voted yes.
On rollcall 319, I would have voted yes.
On rollcall 320, I would have voted yes.
On rollcall 321, I would have voted no.
On rollcall 322, I would have voted yes.
On rollcall 323, I would have voted yes.
On rollcall 324, I would have voted no.
On rollcall 325, I would have voted no.
On rollcall 326, I would have voted yes.
On rollcall 327, I would have voted no.
On rollcall 328, I would have voted yes.
On rollcall 329, I would have voted no.
On rollcall 330, I would have voted yes.
On rollcall 331, I would have voted no.
On rollcall 332, I would have voted no.
On rollcall 333, I would have voted no.
On rollcall 334, I would have voted yes.
On rollcall 335, I would have voted yes.
On rollcall 336, I would have voted yes.
On rollcall 337, I would have voted yes.
On rollcall 338, I would have voted ves.
On rollcall 339, I would have voted yes.
On rollcall 340, I would have voted yes.
On rollcall 341, I would have voted yes.
On rollcall 342, I would have voted yes.
On rollcall 343, I would have voted ves.
On rollcall 344, I would have voted yes.
On rollcall 345, I would have voted yes.
On rollcall 346, I would have voted yes.
On rollcall 347, I would have voted yes.
On rollcall 348, I would have voted no.
On rollcall 349, I would have voted yes.
On rollcall 350, I would have voted yes.
On rollcall 351, I would have voted yes.
On rollcall 352, I would have voted yes.
On rollcall 353, I would have voted yes.
On rollcall 354, I would have voted yes.
On rollcall 355, I would have voted yes.
On rollcall 356, I would have voted no.
On rollcall 357, I would have voted yes.
On rollcall 358, I would have voted yes.
On rollcall 359, I would have voted no.
On rollcall 360, I would have voted no.
On rollcall 361, I would have voted no.
On rollcall 362, I would have voted no.
On rollcall 363, I would have voted yes.
On rollcall 364, I would have voted no.
On rollcall 365, I would have voted yes.
On rollcall 366, I would have voted no.
```

On rollcall 367, I would have voted no.

```
On rollcall 368, I would have voted no.
On rollcall 369, I would have voted no.
On rollcall 370, I would have voted no.
On rollcall 371, I would have voted yes.
On rollcall 372, I would have voted no.
On rollcall 373, I would have voted no.
On rollcall 374, I would have voted no.
On rollcall 375, I would have voted no.
On rollcall 376, I would have voted no.
On rollcall 377, I would have voted no.
On rollcall 378, I would have voted no.
On rollcall 379, I would have voted no.
On rollcall 380, I would have voted no.
On rollcall 381, I would have voted no.
On rollcall 382, I would have voted no.
On rollcall 383, I would have voted no.
On rollcall 384, I would have voted yes.
On rollcall 385, I would have voted no.
On rollcall 386, I would have voted no.
On rollcall 387, I would have voted no.
On rollcall 388, I would have voted no.
On rollcall 389, I would have voted no.
On rollcall 390, I would have voted yes.
On rollcall 391, I would have voted no.
On rollcall 392, I would have voted yes.
On rollcall 393, I would have voted no.
On rollcall 394, I would have voted yes.
On rollcall 395, I would have voted no.
On rollcall 396, I would have voted yes.
On rollcall 397, I would have voted no.
On rollcall 398, I would have voted yes.
On rollcall 399, I would have voted no.
On rollcall 400, I would have voted yes.
On rollcall 401, I would have voted no.
On rollcall 402, I would have voted yes.
On rollcall 403, I would have voted no.
On rollcall 404, I would have voted no.
On rollcall 405, I would have voted no.
On rollcall 406, I would have voted no.
On rollcall 407, I would have voted no.
On rollcall 408, I would have voted yes.
On rollcall 409, I would have voted yes.
On rollcall 410, I would have voted yes.
On rollcall 411, I would have voted yes.
On rollcall 412, I would have voted yes.
On rollcall 413, I would have voted yes.
On rollcall 414, I would have voted present.
On rollcall 415, I would have voted yes.
On rollcall 416, I would have voted ves.
On rollcall 417, I would have voted yes.
On rollcall 418, I would have voted yes.
On rollcall 419, I would have voted yes.
On rollcall 420, I would have voted yes.
On rollcall 421, I would have voted ves.
On rollcall 422, I would have voted yes.
On rollcall 423, I would have voted yes.
On rollcall 424, I would have voted no.
On rollcall 425, I would have voted no.
On rollcall 426, I would have voted no.
On rollcall 427, I would have voted no.
On rollcall 428, I would have voted yes.
On rollcall 429, I would have voted no.
On rollcall 430, I would have voted yes.
On rollcall 431, I would have voted no.
On rollcall 432, I would have voted no.
On rollcall 433, I would have voted yes.
On rollcall 434, I would have voted no.
On rollcall 435, I would have voted yes.
On rollcall 436, I would have voted no.
On rollcall 437, I would have voted no.
On rollcall 438, I would have voted yes.
On rollcall 439, I would have voted no.
On rollcall 440, I would have voted no.
On rollcall 441, I would have voted no.
On rollcall 442, I would have voted no.
On rollcall 443, I would have voted no.
On rollcall 444, I would have voted no.
```

On rollcall 445, I would have voted no.

```
On rollcall 446, I would have voted no.
On rollcall 447, I would have voted no.
On rollcall 448, I would have voted no.
On rollcall 449, I would have voted no.
On rollcall 450, I would have voted yes.
On rollcall 451, I would have voted yes.
On rollcall 452, I would have voted yes.
On rollcall 453, I would have voted yes.
On rollcall 454, I would have voted yes.
On rollcall 455, I would have voted no.
On rollcall 456, I would have voted no.
On rollcall 457, I would have voted no.
On rollcall 458, I would have voted yes.
On rollcall 459, I would have voted no.
On rollcall 460, I would have voted no.
On rollcall 461, I would have voted yes.
On rollcall 462, I would have voted yes.
On rollcall 463, I would have voted yes.
On rollcall 464, I would have voted yes.
On rollcall 465, I would have voted ves.
```

IN RECOGNITION OF JIM BOREN'S 40 YEARS OF SERVICE

HON. JIM COSTA

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. COSTA. Madam Speaker, I rise today to give recognition to James V. "Jim" Boren, the Editorial Page Editor/Vice President of the Fresno Bee newspaper as he prepares to celebrate four decades of dedicated service to the Fresno Bee.

A native of Fresno, California, Jim attended Hoover High School, where his talent for using written words to convey specific imagery and captivate a reader's interest, officially began. While at Hoover, Boren became actively involved in the school's newspaper, the Hoover Patriot, and continued as a school reporter until his graduation in 1967. Following graduation, Boren attended Fresno City College where he earned his AA degree and became engaged with the official news publication of Fresno City College, the Rampage. His strong interest in journalism continued during his tenure at California State University, Fresno, where he graduated in 1972 with a bachelor's degree in journalism.

While still in college, on June 9, 1969, at the age of 19, Jim Boren was hired as a vacation relief reporter for the Valley Department of the Fresno Bee and with that position, Boren's illustrious journalism career officially began. During his 40-year tenure at the Bee, Boren has covered almost every beat at the paper. In 1980, Jim Boren quickly became known as "The Bee's Political Guru," as he continued to report exclusively on politics for nearly 15 years. During that time, Boren covered every level of politics, including city council elections, gubernatorial races, and presidential campaigns, joining the press pool of national campaigns to see, hear and report first-hand the events and progress surrounding those cam-

In 1995, Jim became the Editorial Page Editor of the Bee, one of the positions he still enjoys today. Boren has received a variety of journalism awards, including an investigative reporting award from the Society of Professional Journalists and in 2004, Boren earned recognition as the winner of the Jim Tucker Journalism Award presented by the Mass Communications and Journalism Department

of his alma mater, California State University, Fresno.

Always dedicated to helping prevent hunger for Valley residents, Boren's volunteer advocacy on behalf of the Community Food Bank continues to aid those less fortunate. Additionally, his volunteer efforts on behalf of Children's Hospital of Central California, resulted in significant funds being raised for the annual Kids Day event, where he has raised tens of thousands of dollars for those seeking medical care at the valley's only children's hospital. Boren is a founding board member and remains active on the board of the Kenneth L. Maddy Institute at California State University, Fresno.

A proud father, Marissa Boren continues in her father's footsteps and is dedicated to education and the community. She has just completed her education at the University of California at San Diego.

Boren, in his current role as Editorial Page Editor/Vice President, continues to write a weekly column on politics and public policy in addition to his duties overseeing the Bee's opinion pages. He is also a member of the Operating Committee, which is the senior management group of the newspaper.

On behalf of all those who have read his words, it is with great pleasure that I congratulate Jim Boren for 40 years of providing interesting informative stories, columns and opinions to Fresno Bee readers everywhere.

THE TRUE IMPORTANCE OF INDEPENDENCE DAY

HON. GABRIELLE GIFFORDS

OF ARIZONA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Ms. GIFFORDS. Madam Speaker, I rise today to encourage all citizens to take a moment during the upcoming Independence Day weekend to reflect on what the United States and the ideals of our Republic mean to them.

America's experiment with democracy represents the origins of a new outlook and new system of governance. Our founders dared to challenge history. The principles of personal liberty and collective justice—exercised daily across our country—were once little more than the lofty goals of our ancestors. Today, we have come a long way. We have struggled and continue to struggle, to achieve the true spirit of freedom for every American and every citizen of humanity.

When I reflect on the ideals of our nation and consider the significance of our shining example of freedom to the world, I think not only of our deep-rooted principle of self-determination but the basic liberties set forth by the Declaration of Independence and our Bill of Rights. These two great doctrines lay a foundation for all free nations.

But I believe freedom is more than words. Freedom is a society in which all have an

equal opportunity to succeed.

A free society is one in which citizens are not burdened by a perpetual cycle of poverty that breeds crime, violence and chronic dis-

A free society is one in which the people are not crushed into bankruptcy by the weight

of growing medical costs that seem without bounds.

Citizens of a free society need not choose between buying food and affording care.

A free society educates all of its children and provides vast opportunity for betterment beyond the classroom.

A free society ought not be bound by the shackles of oppression, be it physical restraints or the restraints imposed by a dependence on foreign assets.

A free society puts its stock in innovation, tapping into its own financial and human capital to grow a smarter economy and a safer future that doesn't poison our air, water and land or tie self determination to the foreign resources of another land's oppressor.

In our still pioneering young republic, we refuse to cede the initiative to innovate.

In our pursuit of freedom we agree to forgo some of our individual interests and intemperance to allow the space for open dialogue, debate and discussion.

Our society and all free societies must be open to compromise without bias to age, color or creed.

So as I stand here on the eve of our 233rd Independence Day, I am grateful for our founding fathers and their quest for democracy. While I value the vast distances we have traveled since Philadelphia, I remain mindful of the long journey yet to perfection.

On this Independence Day, I urge my fellow Arizonans and all Americans to endeavor to renew and revive the spirit of liberty that launched this great nation, and strive to seek a more perfect Union.

CONGRATULATING THE SOCORRO BULLDOGS BASEBALL TEAM

HON. SILVESTRE REYES

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. REYES. Madam Speaker, I rise today to congratulate the Socorro High School baseball team for winning the 2009 Texas 5A State Baseball Championship. The Socorro High Bulldogs ended their championship season with an impressive record, becoming the second team in El Paso history to bring home the coveted state title.

The team was tested by fierce competitors from across the great State of Texas, one of the most competitive states in the entire nation for high school baseball. As the post-season progressed, the Bulldogs fended off tough challengers and finished with an impressive 35–4 record.

On Saturday, June 20th, the Bulldogs had their toughest test this year when they faced the Lufkin Panthers in the state championship game at the Dell Diamond in Round Rock, Texas, and were down 2–0 in the game's early innings. The talented young men on the Socorro Bulldog team never waivered and forged an impressive come-from-behind victory.

I am extremely proud of the dedication, determination, sportsmanship, and discipline of this talented baseball team and their Coach Chris Forbes. The members of this champion-

ship team are to be commended for their drive and perseverance. The 2009 team members include: Tavi Amparan, Chuy Diaz, Cory Falvey, Roger Favela, Chris Guzman, Eric Herrera, Bobby Mares, Sergio Mendoza, Marcus Molina, Armando Muniz, Jessirey Navarrete, Aaron Olivas, Josh Rodriguez, Rene Rodriguez, Oscar Sandate, Ivan Sigala, Angel Soria, George Stoltz, and Luis Yanez.

Head Coach Chris Forbes and his great team of assistant coaches, Joe Alvarez, Adrian Garcia, Federico Contreras, and Herbert Reyes, were the masterminds behind the team's success. Coach Forbes, in particular, instilled a sense of hard work and discipline that kept the players motivated throughout the regular season and post-season. As part of his 25—year career in coaching, the former Austin High School baseball player has taken Socorro to 20 playoff appearances. Coach Forbes also boasts the most wins (576) of any varsity baseball coach in El Paso.

The Bulldogs' championship title energized El Paso sports fans, as over a thousand parents and members of the community made the long journey to Round Rock to cheer the team to victory. This team will forever be remembered for its historic victory that brought the State Championship Trophy to El Paso, 60 years after the storied Bowie Bears baseball team achieved the same feat in 1949. I am proud to join my constituents from the 16th District of Texas in commending the Socorro Bulldogs baseball team for a job well done.

RENEWABLE ENERGY DEVELOP-MENT AND TRANSMISSION ISSUES

HON. JAY INSLEE

OF WASHINGTON

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. INSLEE. Madam Speaker, I greatly appreciate the sentiments expressed in the attached letter from Carl Zichella, and I intend to work with these groups to achieve strong environmental protections in areas affected by transmission line siting.

SIERRA CLUB, Sacrementa, CA, June 26, 2009.

Hon. JAY INSLEE,

House of Representatives,

Washington, DC.

DEAR REPRESENTATIVE INSLEE: I write to thank you for your leadership on renewable energy development and transmission issues. The Sierra Club, The Wilderness Society and NRDC have concerns about the presidential override provision of the manager's transmission amendment. We recognize that it was not the intention of the amendment's author to, in any way, undermine environmental protection. We would like to work with Congressman Inslee and the Energy and Commerce Committee to help ensure that public land protection measures in transmission policy reforms are as strong as possible, as reflected in HR 2211 and to clarify the role of public stakeholders in the planning process the amendment establishes.

We are at your service in the coming days and weeks to address these issues.

Sincerely,

CARL ZICLIELLA, Western Renewable Projects Director. VETERANS HEALTH CARE BUDGET REFORM AND TRANSPARENCY ACT OF 2009

SPEECH OF

HON. SHEILA JACKSON-LEE

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES Tuesday, June 23, 2009

Ms. JACKSON-LEE of Texas. Mr. Speaker. I rise today in strong support of H.R. 1016, "Veterans Health Care Budget Reform and Transparency Act of 2009." I would like to thank my colleague, Congressman BOB FILNER, for introducing this bill, and providing leadership on this important issue.

Today I will defer to Thomas Jefferson who so auspiciously stated, "The care of human life and happiness and not their destruction is the first and only legitimate object of good government." We must call attention as both the House and Senate discuss health care reform. Today, in the midst of two wars and an economic crisis, I know in this 111th Congress and with the 44th President of the United States, our government is now in the position of necessity where we must work to ensure comprehensive health care reform to all citizens.

The Veterans Health Care Budget Reform and Transparency Act of 2009 will ensure that one community who gave the ultimate measure for their country will have a quality health care system. I urge members of Congress to put away the partisan bickering and come together to support those who have given their lives for the country they love. There should be no reason why our veterans should not receive the adequate health care they deserve.

For 19 out of the past 22 fiscal years, appropriated funds for medical care were not provided to the Department of Veterans Affairs before the commencement of its new fiscal year, causing the Department great challenges in planning and managing care for enrolled veterans. Appropriation levels for health care programs in the Department have too often proven insufficient over the past decade, requiring the Secretary of Veterans Affairs to ration health care and Congress to approve supplemental appropriations. Medical technology available on the battlefields and in U.S. medical facilities are saving the lives of a high percentage of severely wounded soldiers, but they then often face long-term recovery and rehabilitation challenges.

By providing sufficient, timely and predictable funding we would ensure that we meet the vital obligation to provide health care to all veterans. Congress must take action in ensuring our veterans who return home sick, injured, or even healthy will receive the quality health care they deserve. As Congress begins to swiftly act in an unprecedented time, I urge my colleagues to put away partisan bickering and act as a single non-partisan government to ensure our citizens' happiness in a quality health care system.

EARMARK DECLARATION

HON. ROBERT E. LATTA

OF OHIO

IN THE HOUSE OF REPRESENTATIVES Friday, June~26, 2009

Mr. LATTA. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information for publication in the CONGRESSIONAL RECORD regarding earmarks I received as part of H.R. 2996, the Fiscal Year 2010 Interior, Environment, and Related Agencies Appropriations Act.

Requesting Member: Congressman ROBERT E. LATTA

Bill Number: H.R. 2996, Fiscal Year 2010 Interior, Environment, and Related Agencies Appropriations Act

Account: EPA; STAG Water and Waste-water Infrastructure Project

Legal Name of Requesting Entity: Village of Tiro, Ohio

Address of Requesting Entity: P.O. Box 31, Tiro, OH 44887

Description of Request: \$500,000 for the Village of Tiro Water Distribution System. This project consists of purchasing treated water from the City of Shelby and transporting it to Tiro via 32,500 ft. of water main. 10,700 ft. of water main will be constructed in the Village for distribution of water. A booster pumping station, storage tower, and fire hydrants will be included. The Village of Tiro currently has no municipal water system. Water is collected or hauled into shallow wells or cisterns. The Village has tried for several years to secure a source of water and funding. The current project is the closest this village has come for a safe water supply. I certify that neither I nor my spouse has any financial interest in this project.

TRIBUTE TO FRANCISCO "PACO" SALDANA

HON. ANDER CRENSHAW

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. CRENSHAW. Madam Speaker. I rise today to congratulate one of my constituents Francisco "Paco" Saldana who as the Director of Guest Services, The Ritz-Carlton, Amelia Island is the winner of the "Faces of Travel" award granted on an annual basis by the U.S. Travel Association to an employee in the travel business who exemplifies the travel industry and what makes it a unique employment opportunity for 7.7 million Americans.

After months of searching and thousands of votes by industry members, Francisco "Paco" Saldana, a resident of Fernandina Beach, Florida, will be announced as the winner of the "Faces of Travel Contest."

As the winner of this award, Francisco "Paco" Saldana who is a proud employee at the Ritz-Carlton on Amelia Island will help communicate the critical role travel plays in the lives of working Americans across our great country.

Mr. Saldana is the embodiment of the American Dream and what is possible in this great land of opportunity, having emigrated to the United States in 1995 from Mexico City and rising up the ranks at The Ritz-Carlton. Mr. Saldana's dedication to hard work and his positive attitude over the last 14 years have propelled him to become the Director of Guest Services.

Mr. Saldana's work in the travel industry not only had a positive impact on his professional life, but also his personal life. Mr. Saldana met his wife, Christina, who also happened to work at The Ritz-Carlton, Amelia Island. They were married in September 2002. Mr. and Mrs. Saldana have three children, Isabella Grace, Nikolas Valentino and Sophia Claire.

SUPPORT OF: H.R. 1511, THE "TORTURE VICTIMS RELIEF REAUTHORIZATION ACT OF 2009"

HON. SHEILA JACKSON-LEE

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Ms. JACKSON-LEE of Texas. Madam Speaker, I support H.R. 1511, the "Torture Victims Relief Reauthorization Act of 2009." This bill was sponsored by Representative CHRISTOPHER SMITH of New Jersey. The bill's purpose is to amend the Torture Victims Relief Act of 1998 to authorize appropriations for FY2010–FY2011 which will provide assistance for domestic and foreign programs and centers for the treatment of victims of torture. I support this bill and I urge my colleagues to support this bill as it provides needed rehabilitation treatment to those who have been impacted by the effects of torture.

H.R. 1511, the Torture Victims Relief Reauthorization Act of 2009, authorizes appropriations for the Department of Health and Human Services (HHS) to provide grants to programs in the United States to cover the costs of services provided by domestic treatment centers in the rehabilitation of victims of torture (including treatment of the physical and psychological effects of torture). It will also allow the centers to provide social and legal services as well as research and training of health care providers outside of treatment centers or programs to enable them to provide such services. It authorizes the President to provide grants to treatment centers and programs in foreign countries that carry out projects and activities specifically designed to treat victims of torture for the physical and psychological effects of torture. In addition, it provides grants to the United Nations Voluntary Fund for Victims of Torture.

This bill is not only important, it is necessary. The Abu Ghraib prisoner abuse scandal and the myriad of consequential allegations of prisoner abuse across both Iraq and Afghanistan have cast a heavy shadow over our role in Iraq and our country as a whole. Under the Bush Administration, evidence indicates that torture was conducted on prisoners included methods such as: waterboarding, weeklong sleep deprivation, forced nudity, use of painful positions, bellyslap and the exploitation of prisoner's fears of animals or insects. President Obama has since denounced these inhumane integration practices and has vowed that the United States does not condone torture. H.R. 1511 supports the President's vow by providing treatment to victims which is designed to enable the victim to step back from the trauma, learn to identify and accept it and gradually become reintegrated into society and/or the working world. This treatment will also serve a social purpose in that it will enable the victim to restore ties that were severed by an array of clinical symptoms caused by being tortured.

In the wake of the Abu Ghraib scandal, the U.S. has gone to great pains to persuade the world that U.S. policy does not condone torture. If Congress enacts this legislation, it

would reaffirm America's commitment to a world without torture and show the rest of the world that the U.S. is committed to rehabilitating those who have suffered at the hands of torture.

We as a nation must set a clear example that we do not support torture, nor do we condone such practices. For the benefit or our troops, for the good of Iraq, for the good of America, and for the safety of the World, we must heal the wounds caused by torture to those victims domestic and foreign. A strong bipartisan message of support needs to be displayed by this body to right the wrongs and send a message to the world that America is committed to ending what President Obama called a "dark and painful chapter in our history," by providing treatment to the victims of torture. I invite my colleagues to stand with me today and support this important legislation.

TAX AND CAP A JOB KILLER

HON. JOHN L. MICA

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. MICA. Madam Speaker, the U.S. House of Representatives today passed H.R. 2454, the so-called Cap and Trade bill. I noted in opposition to that measure and offer the following statement.

The Cap and Tax bill could not come at a worse time and could be a job killer. The 1,200 page measure will impose a national tax on ALL energy and lead to higher energy prices for ALL American households, Most families cannot afford the estimated \$1,400 yearly increase in energy costs. With the economy struggling, this bill, with its increased expense to industry, will cause additional unemployment by sending jobs overseas where doing business is cheaper. This bill also further expands the role of government by imposing new restrictions and requirements on everything from light bulbs to water disnensers

As the Republican Leader of the Transportation and Infrastructure Committee, I want to point out that Transportation accounts for 30% of greenhouse gas emissions. This legislation contains significant provisions in the committee's jurisdiction, yet we held no hearings on this massive tax increase, and willingly surrendered our responsibility to consider any amendments to try to improve the bill.

According to the Heritage Foundation, by 2035 this Cap and Trade bill would: reduce aggregate gross GDP by \$9.4 trillion (or reduce Florida gross state product by \$28 billion); raise electricity rates 90 percent; raise gasoline prices by 58 percent; raise residential natural gas prices by 55 percent; and Increase inflation-adjusted federal debt by 26 percent, or \$28,728 additional federal debt per person.

For this any significant other reasons I voted against passage or H.R. 2454.

COMMEMORATING THE FIRST BUR-ATBAKERSFIELD TALS NA-TIONAL CEMETARY

HON. JIM COSTA

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Mr. COSTA. Madam Speaker, I rise today to give tribute and honor to the brave men and women of Kern County who have proudly served their country in the United States Armed Forces. As a nation, one of our most vital duties is to ensure we are committed to providing for our military veterans. This includes providing a final resting place for the honored to be recognized. Thus, today, I would like to commemorate the first burials at the new Bakersfield National Cemetery.

The Bakersfield National Cemetery is a 500-acre site located approximately 25 miles outside of Bakersfield nestled in the Tehachapi Mountains. Surrounded by golden scenery, crushed red rock and drought resistant plants, the newly developed cemetery is furnished with a memorial walkway, committal service shelter, internet areas and administrative and maintenance buildings. Upon project completion, the cemetery will be equipped to serve 200,000 Central California veterans, their spouses and children.

The first cremation and casket burials will take place on July 1 and July 2, 2009, respectively. On July 1, the cremated remains of nine soldiers and one spouse from the Bakersfield and surrounding area will be lowered in unison. The casket burial ceremony on July 2 will commemorate the life of Iragi veteran Army Reserve Maj. Jason E. George, a fallen soldier killed in action.

"A Place of Honor, For Those Who Served With Honor." These patriotic words to be inscribed at Bakersfield's National Cemetery demonstrate the overwhelming pride we have for our soldiers. Veterans in Kern County and surrounding areas take comfort in knowing their undying pledge and sacrifice to protect America's freedom is not forgotten. Having our own national shrine allows us to properly honor the fallen soldiers, veterans from generations past, and soldiers who are currently fighting overseas from the Kern County area.

On behalf of our veterans, I hereby express my high admiration and appreciation for all those who are currently serving our nation and commemorate those who have given the ultimate sacrifice. Let today's ceremony be a perpetual reminder of honor for all of America's men and women of valor.

SUPPORT OF H. CON. RES. 127, "RECOGNIZING SIGNIFI-THE CANCE OF NATIONAL CARIB-BEAN-AMERICAN HERITAGE MONTH

HON. SHEILA JACKSON-LEE

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Ms. JACKSON-LEE of Texas. Madam Speaker, I rise today to express my support of H. Con. Res 127, which recognizes the significance of National Caribbean-American Heritage Month.

As a child of Jamaican grandparents, I understand the importance of recognizing the influence Caribbean cultures continues to have on all facets of these United States. Growing up, my grandmother who hails from Jamaica. instilled in me a strong appreciation for her Caribbean values. As a result of my upbringing, I have adopted a strong work ethic and tremendous pride in my heritage. As a parent, I have passed on these same values to my own children, so they will develop a sense of pride in their Caribbean heritage and acknowledge the many roles Caribbean people play in shaping this nation. I whole-heartedly support this resolution that commemorates Caribbean heritage, history, culture and contributions to the United States.

In her 1970 autobiography, Shirley Chislom, the first black woman elected to Congress, credited her success to the education she received while attending school in Barbados. She wrote, "Years later I would know what an important gift my parents had given me by seeing to it that I had my early education in the strict, traditional, British-style schools of Barbados. If I speak and write easily now, that early education is the main reason."

This is a nation built by immigrants. From as early as the 17th century there have been individuals from the Caribbean Islands, working here in the United States as indentured servants in the colony of Jamestown, Virginia. They worked in fields picking cotton, tobacco and crops just as the slaves did.

Caribbean immigrants have been contributing to the well-being of American society since its founding. Alexander Hamilton, the First Secretary of the Treasury, was from the Caribbean island of St. Kitts. We count among our famous sons and daughters. Secretary of State Colin Powell, Cicely Tyson, W.E.B. Dubois, James Weldon Johnson, Harry Belafonte and Sidney Poitier to name a few.

H. Con. Res. 127 recognizes the significance of Caribbean people and their descendants in the history and culture of the United States. Our nation would not be what it is today without these significant contributions of the Caribbean people and we should honor these accomplishments with the passing of this legislation. The contributions of Caribbean-Americans are a significant part of the history, progress, and heritage of the United States and play an important role in shaping the ethnic and racial diversity of the United States, which ultimately enriches and strengthens our nation.

By passing this legislation we continue to honor the friendship between the United States and Caribbean countries. We are united by our common values and shared history, and we should celebrate the rich Caribbean Heritage and the many ways in which Caribbean Americans have helped shape this

I urge my colleagues to support this resolution to pay tribute to the common culture and bonds of friendship that unite the United States and the Caribbean countries.

TRIBUTE TO JAMES R. KIRBY

HON. JAMES P. McGOVERN

OF MASSACHUSETTS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. McGOVERN. Madam Speaker, I rise today to pay tribute to the James R. Kirby

American Legion Post 50 of Clinton, Massachusetts for its generous contributions to the people of my district. The American Legion is a not-for-profit organization that seeks to advocate for our distinguished veterans and to also promote community involvement. This weekend, the James R. Kirby Post 50 will be celebrating its 90th year of service to the community.

For the past 90 years, the James R. Kirby Legion Post has helped friends and neighbors in Clinton. MA in a variety of ways. Allow me to provide some background on the organization. James R. Kirby, for whom the post is named, was born on July 18th, 1876. He graduated from Clinton High School and joined the military soon afterward. He attended the College of the Holy Cross to pursue a career in medicine. He later attended Baltimore Medical College and began his own practice. Kirby was one of the first veterans of World War I from Clinton. He signed up for the Draft at the age of 42 and tragically died shortly after on September 29th, 1918 of influenza. In his memory, the citizens of Clinton chose to name the new American Legion Post 50 in Kirby's honor. Over the past 90 years, the current members of the Legion Post have continued to honor and serve veterans.

The American Legion Post will celebrate its founding at an event being held on Saturday, June 27th, 2009. The goal of this event is to honor the contributions of the Legion Post and the veterans it has worked hard to represent over the past 90 years. The event will also serve as a day of enjoyment for the community it serves so well. Members of the Legion Post and their families as well as state and local representatives will pay tribute to the service of this American Legion Post to the community of Clinton over the past 90 years. The Legion Post's passion for serving the common good of the community through veteran's advocacy and community involvement continues to demonstrate the service that the James R. Kirby Legion Post 50 has provided for the past 90 years.

Madam Speaker, I commend this group for its dedication to the Town of Clinton and the veteran community. I congratulate the Clinton James R. Kirby Post 50 for its 90 years of service, and I ask my colleagues to join me in paying tribute to its unyielding dedication to community involvement.

EARMARK DECLARATION

HON. GARY G. MILLER

OF CALIFORNIA

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. GARY G. MILLER of California. Madam Speaker, pursuant to the Republican Leadership standards on earmarks, I am submitting the following information regarding earmarks I received as part of the FY 2010 Defense Authorization Bill.

Requesting Member: Congressman GARY G. MILLER

Bill Number: H.R. 2647

Account: Navy-Research, Development, Test, and Evaluation

Legal Name of Requesting Entity: General Dynamics

Address of Requesting Entity: 180 North Riverview Drive, Suite 300, Anaheim Hills, California 92808

Funding Authorized: \$3,600,000

Description of Request: The Deployable Autonomous Distributed System (DADS) is the future of Network-Centric Anti-Submarine Warfare. The DADS program integrates and demonstrates an autonomous undersea sensor system, deployable from multiple platforms, to improve the Navy's capability to conduct effective anti-submarine warfare and intelligence, surveillance and reconnaissance operations in the littoral environment. DADS enhances the automation and connectivity between sensors, operators, and weapons and feeds the network-centric antisubmarine warfare picture. DADS utilizes multiple, cutting edge sensor technologies to increase the probability of detecting threats and to reduce the false alarm rate. With a goal to be deployable by any available asset, DADS will serve as an unmanned, autonomous reporting entity, freeing surveillance platforms for other missions. This funding will help the Navy in developing a system small enough to support deployability goals and in the development of compact power sources.

Requesting Member: Congressman GARY G. MILLER

Bill Number: H.R. 2647

Account: Navy-Research, Development, Test, and Evaluation

Legal Name of Requesting Entity: L-3 Power Paragon

Address of Requesting Entity: 901 E. Ball Road Anaheim, California 92805,

Funding Authorized: \$5,000,000

Description of Request: This project is a design build prototype for a hybrid electric drive (HED) for the CG 47 Class Cruisers for the US Navy. This project contributes to the future of environmentally sound, fuel-efficient propulsion. The Navy believes that this improvement would realize a significant savings per year per ship. This HED for surface combatants such as the CG 47 would significantly reduce fuel costs, increase ship endurance and range, produce less environmental emissions, increase ship survivability through reduce signatures, and provide increased overall ship electric power generation capacity. This installation would leverage advances in lighter weight and more efficient electric propulsion technologies that have resulted from the Office of Naval Research investments over the last several years.

COMMENDING THE CONGRESS OF LEADERS OF WORLD AND TRADI-TIONAL RELIGIONS FOR CALL-ING UPON ALL NATIONS TO LIVE IN PEACE AND MUTUAL UNDER-STANDING

HON. SHEILA JACKSON-LEE

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Ms. JACKSON-LEE of Texas. Madam Speaker, I rise today in support of H. Res. 535, to commend the Congress of Leaders of World and Traditional Religions for their call to action for the nations of our world to work toward peace and mutual understanding. Established in 2003, the Congress of Leaders of World and Traditional Religions is comprised of our world's major religions, including Buddhism, Christianity, Hinduism, Islam, Judaism,

Shinto, and Taoism. Since its founding, the Congress has promulgated the tenet that religion should not be seen as a divisive limitation within the global community, but rather world religions should be the benchmark and arbiter for resolving ongoing international political conflicts. Accordingly, we turn to our global religious leaders to be the driving force in main-

As a Member of Congress from Houston, Texas, my district is one of religious diversity. I represent constituents from all faiths and religious beliefs, and I stand here before you Madam Speaker to say that as a Representative of the 18th District of Texas, I am a humanitarian first and foremost. I believe in celebrating our differences in global theology, and in utilizing these differences as the basis of tolerance as we engage in multilateral interfaith dialogue.

As a Member of the Foreign Affairs Committee. I have worked hard to pass legislation in the foreign affairs arena which speaks to the importance of tolerance and recognizes the need for multilateralism. With respect to Pakistan and Afghanistan, I have worked to pass H.R. 2410 and H.R. 1886 which allocate U.S. support for both Afghanistan and Pakistan respectively. In turn, H.R. 2410 and H.R. 1886 emphasize the necessity of ongoing multilateral engagement with the U.S. in order to forge strong and enduring partnerships with these countries in a united effort to bridge global security disparity.

In his internationally esteemed doctrine on nonviolent protest, Mahatma Gandhi so eloquently stated, "All faiths constitute a revelation of Truth, but all are imperfect and liable to error. Reverence to other faiths need not blind us to their faults. We must be keenly alive to the defects of our own faith, and must not leave it on that account but try to overcome those defects. Looking at all religions with an equal eye, we would not only not hesitate but would think it our duty to adopt into our faith every acceptable feature of other faiths." In deference to Gandhi's wisdom, we must work toward our own "Revelation of Truth," in an international context. Despite the imperfections within every world religion, we must turn to our religious leaders to set the tone for understanding. We must work in concert to engage in interfaith dialogue to maintain peace and security in the world.

H. Res. 535 applauds the Congress of Leaders of World and Traditional Religions for regularly holding forums that address the need for religious freedom. Its inclusion of more than 26 nations, such as Israel, Egypt, Pakistan, Saudi Arabia, Libya, Armenia, South Korea, China, India, and the United States as its representatives is to be commended. The third Congress will be held in Astana, Kazakhstan, July 1-2, 2009, and I would like to recognize Kazakhstan for having been selected by the Secretariat to host the second and third Congress. As we move forward to promote freedom of religion and engage in interfaith dialogue as the foundation to global security, we turn to the Congress of Leaders of World and Traditional Religions to guide us in multilateral reform. I urge passage of this important resolution.

IN HONOR AND RECOGNITION OF KEN WARREN

HON. DENNIS J. KUCINICH

OF OHIO

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. KUCINICH. Madam Speaker, I rise today in honor and recognition of Ken Warren, on the occasion of his retirement as director of the Lakewood Library after 25 years of dedicated service to our community. In his capacity as director of the Lakewood Library, Ken worked to promote and develop innovative projects and programs hosted at the Lakewood Library and throughout the Lakewood community.

Ken Warren has maintained an enthusiasm for books and the power of the written word since his childhood. His interest in community issues began when he was a teen, as editor of an underground paper at his parochial high school. He is founding member of the Lakewood Observer and has made the publication a critical instrument of exchange of ideas and opinions on important civic and community issues.

During his tenure as director, the Lakewood Library underwent major expansions and improvements, including the complete interior and exterior renovation of the main library building, the development of a new technology center, public auditorium, a children's wing, and an inspiring display of murals that grace the walls throughout the facility. Ken has consistently reached out to the citizens, agencies and community leaders of Lakewood creating strong working relationships and friendships throughout the city. His legacy is highlighted by his unwavering advocacy and innovation in promoting and implementing literacy and learning programs, connecting the library to the public schools.

Madam Speaker and colleagues, please join me in honor and recognition of Ken Warren, whose tenure at the Lakewood Library is framed by integrity, kindness, love for learning, passion for the written word, and above all, an unbridled commitment to the betterment of the entire Lakewood community.

WOMEN VETERANS HEALTH CARE IMPROVEMENT ACT

SPEECH OF

HON. SHEILA JACKSON-LEE

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES Tuesday, June 23, 2009

Ms. JACKSON-LEE of Texas. Mr. Speaker, I rise today in strong support of H.R. 1211, "Women Veterans Health Care Improvement Act." I would like to thank my colleague, Congresswoman HERSETH SANDLIN, for introducing this bill, and providing leadership on this important issue.

In the wake of the recent Democratic Presidential victory, we witnessed an historic time in our electoral system. Now is the time to address the major ongoing disparities that exist for our minority and women. Secretary of State Hillary Rodham Clinton once said, "There cannot be true democracy unless women's voices are heard. There cannot be true democracy unless women are given the

opportunity to take responsibility for their own lives. There cannot be true democracy unless all citizens are able to participate fully in the lives of their country." And today, there cannot be true democracy unless women receive the same care and treatment in the military as their male counterparts. In addition to the health care reform debate, H.R. 1211 "Women's Veterans Health Care Improvement Act" will be an essential piece to the health care reform bill.

As the 111th Congress and 44th President of the United States undergo swift actions to reform our health care system it's important we get reform right! It will be a long-term problem if we don't implement the right kind of change now, which needs to include all Americans of every race, every gender, and in every condition. Without comprehensive reform, our government will have failed to serve our people in a time when the people elected for change.

This legislation will expand and improve health care services available to women veterans, especially those serving in Operation Enduring Freedom and Operation Iraqi Freedom. Women Veterans Health Care Improvement Act requires the Secretary of Veterans Affairs to: (1) study barriers encountered by women veterans to the provision by the Department of Veterans Affairs (VA) of comprehensive health care; (2) assess all health care services and programs provided by the VA for women veterans; (3) provide graduate education, training and certification for mental health professionals who provide counseling, care, and services to women veterans suffering from sexual trauma and post-traumatic stress disorder (PTSD); and (4) carry out a pilot program of child care for certain women veterans receiving health care from VA facilities.

For 19 out of the past 22 fiscal years, appropriated funds for medical care were not provided to the Department of Veterans Affairs before the commencement of its new fiscal year, causing the Department great challenges in planning and managing care for enrolled veterans.

By providing the access and care for women in the military, we will meet the vital obligation to provide health care to all veterans. Congress must take action in ensuring our veterans who return home sick, injured, or even healthy will receive the quality health care they deserve. As acts in an unprecedented time, I urge my colleagues to set aside the bickering and come together on a united front to ensure all of our citizen's happiness in a quality health care system. Only then can we live out the true meaning of our country, democracy.

RECOGNIZING BLACK EUROPEAN SUMMIT: TRANSATLANTIC DIA-LOGUE ON POLITICAL INCLUSION

HON. ALCEE L. HASTINGS

OF FLORIDA

IN THE HOUSE OF REPRESENTATIVES Friday, June 26, 2009

Mr. HASTINGS of Florida. Madam Speaker, I rise today to introduce a resolution recognizing the first "Black European Summit: Transatlantic Dialogue on Political Inclusion" and ensuing Brussels Declaration.

The Black European Summit (BES) was held in Brussels, Belgium at the European Parliament on April 15th and 16th. The historic 2-day Summit brought together political and intellectual minority leaders from the United States and Europe to exchange information on the roles of racial and ethnic minority policymakers in developing and supporting policies and initiatives to address racism, discrimination, and inequality.

The event was hosted and organized by myself, Harlem Desir, Member of the European Parliament; Joe Frans, President of the United Nations Working Group of Experts on People of African Descent and a former Swedish Parliamentarian; Claude Moraes, Member of the European Parliament and President of the European Parliament All Party Group on Anti-Racism and Diversity; and Glyn Ford, former Member of the European Parliament.

Participants included Parliamentarians, Congressional representatives, local and nationally elected officials, academics, representatives from European and international institutions, civil society, the private sector, and media from Black and other minority backgrounds.

During the Summit we exchanged information and best practices on addressing structural barriers that impact minority political participation, including implementing initiatives that address racism and discrimination.

Like in the United States, it was noted that despite the numerous contributions of minorities to European society, minorities still face the daily challenges of racism and discrimination. This includes being the targets of violent hate crimes, many of which in recent years have resulted in death. Existing inequalities in education, housing, and employment remain a problem and racial profiling is often a norm. Obstacles for addressing these problems, include the lack of minorities in leadership positions and the rise of racist and xenophobic political parties seeking to implement non-inclusive policies.

Summit participants committed to addressing these issues by adopting the Brussels Declaration, which calls for: (1) concrete action to assist ethnic and racial minorities in obtaining full access to participation in the political sphere and relevant areas of decision making, especially in the development and implementation of policy initiatives to address racial and ethnic discrimination and inequality; and (2) to support future opportunities to exchange and share perspectives in these areas through a sustained transatlantic dialogue.

As I continue to work on these initiatives, I urge my colleagues to join me in supporting this Resolution Recognizing both the Black European Summit and Brussels Declaration and encourage them to review the statements and submissions from the Helsinki Commission's Black Europe and Racism in the 21st Century Hearings at www.csce.gov and recently introduced Resolution on Black Europeans. Additionally, I would like to submit the following background materials on the Brussels Declaration and Black Europeans for the official record.

BLACK EUROPEAN SUMMIT—TRANSATLANTIC DIALOGUE ON POLITICAL INCLUSION BRUSSELS DECLARATION

Preamble

We, as members of the public, private, and voluntary sectors from Europe and the United States of America convening in Brussels, Belgium from the 15 to 16 of April for

the Black European Summit: Transatlantic Dialogue on Political Inclusion, draw attention to the need for coordinated strategies to address racism and discrimination;

We recognize the democratic, multi-ethnic and multi-racial nature of our countries' diverse societies;

We reaffirm the principles of equal rights and self-determination of peoples and recalling that all individuals are born equal in dignity and rights;

We remain concerned that the political and legal systems in some of our societies do not reflect the racial and ethnic diversity within our societies, which then contributes to the continuation of racism and discrimination:

We recognize that the full access of racial and ethnic minorities to participate in the political sphere and relevant areas of decision making at the levels of national, regional, and locally elected government appropriate to each nation is critical to combating racism and inequality and ensuring our democratic societies;

We therefore note the need for concrete strategies to: increase the representation and influence of racial and ethnic minority policymakers; jointly seek solutions to racial and ethnic minorities increased participation in decision-making in the development and implementation of policy initiatives to address discrimination and inequality; and support opportunities to exchange and share perspectives in these areas through the continuance of a transatlantic dialogue to realize these goals.

We today resolve that we will endeavor to enact initiatives to eradicate racial and ethnic discrimination through:

Continuing a transatlantic dialogue that: includes cultural exchanges between American and European racial and ethnic minority groups, including youth; focuses on the development of opportunities for racial and ethnic minority political leadership and participation in the policymaking process; and fosters the exchange of information on best practices to implement and enforce antidiscrimination measures and achieve racial equality:

Joining forces over the coming months to develop common goals and objectives in each of our decision-making bodies to recognize Europe's Black and racial and ethnic minority populations for their historical and present-day contributions and acknowledge past injustices;

Promoting racial and ethnic minority participation at all levels of national, regional, and local government through the education of civil and political rights, including the legislative process and advocacy of legislative issues relevant to racial and ethnic minority communities, development of targeted professional development and hiring strategies, increased youth and community outreach, and self-organization and other empowerment initiatives;

Reaffirming our continued cooperation and commitment to work with our governments, international institutions, civil society, private sector, and other partners to improve institutions so that they are fully participatory and reflect the democratic principles of equality, justice, and celebration of the strengths of our countries' diversity.

As Europe Veers Right, Minority Parliamentarians Counter

Washington—With far-right and anti-immigrant parties making worrying advances in recent elections across Europe, minority lawmakers and leaders called today for the political process to be more inclusive of minorities.

Following April's "Black European Summit: Transatlantic Dialogue on Political In-

clusion" in Brussels, Belgium, minority political and intellectual leaders today adopted a declaration calling for increased efforts to include racial and ethnic minorities in the political process. (Please find attached a copy of the Brussels Declaration).

I was very pleased to have the opportunity to work on these initiatives with my European colleagues," said U.S. Congressman and Helsinki Commission Co-Chairman Alcee L. Hastings (D-FL). "Whether speaking about voting and civil rights, increasing minority elected officials and diversity in policy staff, or responding to discriminatory policies, we have common issues. While I have been able to share the many successes we have had in the United States in terms of minority political participation, most recently evidenced by President Obama, one need only look at the lack of diversity in the U.S. Senate and staff in Congressional offices and many government agencies to know that we can be doing more. It is one reason I fully support this transatlantic declaration.'

"Despite the global significance of President Obama's historic election, the reality is that our elected leadership does not reflect the diversity of origins of people in our nations" said Summit co-organizer Harlem Desir, Member of the European Parliament (MEP). "This has contributed to a lack of inclusion of minorities in the planning and implementation of the very policies that impact us. Despite some successes, the overall results of recent elections are simply further evidence that we must do more to ensure the representation of the diversity of our society."

"In Britain we had never elected fascists in a national election until now. Whilst in the past there have been far-right MEPs from other countries, such as France, this election saw new groups gaining seats across Europe, and thus a worrying threshold has been said Summit co-organizer and crossed." President of the European Parliament All Party Group on Anti-Racism and Diversity, Claude Moraes MEP. "We will have to tackle the pernicious growth of far-right racist parties head-on, at both the grass-roots and parliamentary levels, and an integral part of this lies in encouraging the full inclusion of minorities in the political process.

U.S. Helsinki Commissioner Congressman G.K. Butterfield (D-NC), a former Judge known for his work supporting voting rights, who participated in the Summit, added, "it is clear by the outcome of the European elections that too few people are taking part in the political process at a potentially great risk to democracy. As I have learned from my work in the U.S., it is critical to remedy this situation rather than preserve a status quo that repeatedly elects lawmakers who do not represent the diverse interests of the population."

"These concerns for minority representation are exactly why we adopted the Brussels Declaration," said Summit co-organizer Joe Frans, Vice President of the United Nations Working Group on Experts of People of African Descent. "The declaration calls for the full and equal participation of non-White citizens of Europe with African, migrant, and other backgrounds in our countries' democracies. With more racist, xenophobic, and anti-Muslim parties making political gains, immigration and anti-discrimination policies are going to be further scrutinized, which will impact how persons of different races, ethnicities, and religions, are viewed and treated. Implementation of the Brussels declaration in this current climate is of the utmost importance.'

THE DEATH OF FARRAH FAWCETT

HON. SHEILA JACKSON-LEE

OF TEXAS

IN THE HOUSE OF REPRESENTATIVES

Friday, June 26, 2009

Ms. JACKSON-LEE of Texas. Madam Speaker, thank you for letting me stand before you today in order to mourn a great American icon, Farrah Fawcett. She died today, Thursday, June 25, 2009, shortly before 9:30 a.m. after battling cancer. She was 62.

I would also like to express and send my condolences to her family and friends. I know the actress fought a very public battle with cancer and I am proud to say that this beautiful, talented and courageous woman was an American legend, icon and a TEXAN.

Mary Farrah Leni Fawcett was born on Feb. 2, 1947, in Corpus Christi, Texas. Her father, James William Fawcett, was an oil pipefitter who later founded a pipeline construction company and a custodial service. She enrolled at the University of Texas in Austin, where she initially planned to study microbiology but later switched her major to art.

Farrah Fawcett is a true Hollywood success story. Winning a campus beauty contest got her noticed by an agent, who encouraged her to pursue acting. After graduating, she moved to Los Angeles and her healthy style and beauty was immediately noticed. She quickly got roles in various television commercials and also made appearances in some TV series.

Eventually, she came to the attention of the highly successful producer Aaron Spelling, who was impressed by her beauty and vivacious personality which won her a role in the TV series "Charlie's Angels" (1976). She played a private investigator who worked for a wealthy and mysterious businessman, along with two other glamorous female detectives. The show immediately became the most popular series on television, earning record ratings and a huge audience. All three actresses became very popular, but Farrah became by far the best known.

She was America's sweetheart, and found herself on every celebrity magazine and pursued by photographers and fans. While she enjoyed the success and got along well with her co-stars (both of whom were also of Southern origin), she found the material lightweight. Also, the long hours she worked were beginning to take a toll on her marriage so the following year, when the show was at its peak, she left to pursue a movie career.

September 2006, Fawcett, who at 59 still maintained a strict regimen of tennis and paddleball, began to feel strangely exhausted. She underwent two weeks of tests and was told the devastating news: She had anal cancer. Farrah fought a long, difficult brave battle against the cancer for three years and we must admire her determination and strength through it all. According to the American Cancer Society, an estimated 5,290 Americans, most of them adults over 35, will be diagnosed with that type of cancer this year, and there will be 710 deaths. She was able to give many people hope for a cure while documenting her own personal battle, so we must continue to search for a cure for this abhorrent disease that is cancer.

I would just like to leave her friends and family and all Americans who have lost a loved one with this poem by Henry Van Dyke: GONE FROM MY SIGHT (By Henry Van Dyke)

I am standing upon the seashore. A ship, at my side, spreads her white sails to the moving breeze and starts for the blue ocean. She is an object of beauty and strength.

I stand and watch her until, at length, she hangs like a speck of white cloud just with each other.

Then, someone at my side says, "There, she is gone"

Gone where?

Gone from my sight. That is all. She is just as large in mast, hull and spar as she was when she left my side.

where the sea and sky come to mingle And, she is just as able to bear her load of living freight to her destined port.

Her diminished size is in me—not in her.

And, just at the moment when someone says, "There, she is gone," there are other eyes watching her coming, and other voices ready to take up the glad shout, "Here she comes!"

And that is dying. . .

Daily Digest

HIGHLIGHTS

The House passed H.R. 2996, Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010.

The House passed H.R. 2454, American Clean Energy and Security Act of 2009.

Senate

Chamber Action

The Senate was not in session today. It will next meet at 2 p.m., on Monday, July 6, 2009.

(Unless the House of Representatives fails to adopt S. Con. Res. 31, Adjournment Resolution; if the House of Representatives fails to act, Senate convenes at 2 p.m., on Monday, June 29, 2009.)

Committee Meetings

(Committees not listed did not meet)

No committee meetings were held.

House of Representatives

Chamber Action

Public Bills and Resolutions Introduced: 44 public bills, H.R. 3065–3080, 3083–3110; 2 private bills, H.R. 3111–3112; and 20 resolutions, H. Con. Res. 160; and H. Res. 588–606 were introduced.

Pages H7703-05

Additional Cosponsors:

Pages H7705-07

Reports Filed: Reports were filed today as follows: H.R. 2701, to authorize appropriations for fiscal year 2010 for intelligence and intelligence-related activities of the United States Government, the Community Management Account, and the Central Intelligence Agency Retirement and Disability System, with an amendment (H. Rept. 111–186);

H.R. 3081, making appropriations for the Department of State, foreign operations, and related programs for the fiscal year ending September 30, 2010 (H. Rept. 111–187);

H.R. 3082, making appropriations for military construction, the Department of Veterans Affairs, and related agencies for the fiscal year ending September 30, 2010 (H. Rept. 111–188);

H. Res. 537, requesting that the President and directing that the Attorney General transmit to the House of Representatives all information in their possession relating to specific communications regarding detainees and foreign persons suspected of terrorism, adversely (H. Rept. 111–189); and

H.R. 2965, to amend the Small Business Act with respect to the Small Business Innovation Research Program and the Small Business Technology Transfer Program, with an amendment (H. Rept. 111–190, Pt. 1).

Journal: The House agreed to the Speaker's approval of the Journal by voice vote. Pages H7449, H7686

Committee Resignation: Read a letter from Representative Tauscher, wherein she resigned from the Committee on Transportation and Infrastructure, effective today.

Page H7451

Adjournment Resolution: The House agreed to S. Con. Res. 31, providing for a conditional adjournment or recess of the Senate, and a conditional adjournment of the House of Representatives, by a yea-and-nay vote of 243 yeas to 180 nays, Roll No. 464.

Page H7461

Moment of Silence: The House observed a moment of silence in honor of Michael Jackson. Page H7462

Department of the Interior, Environment, and Related Agencies Appropriations Act, 2010: The House passed H.R. 2996, making appropriations for the Department of the Interior, environment, and related agencies for the fiscal year ending September 30, 2010, by a yea-and-nay vote of 254 yeas to 173 nays, Roll No. 475. Consideration of the measure began on Thursday, June 25th. Pages H7463-71

Agreed to:

Dicks manager's amendment (No. 1 printed in part A of H. Rept. 111-184) that was debated on June 25th that allows the abandoned mine land funding to be used for the non-Federal share of the cost of certain environmental restoration projects funded by the Federal Government that repair acid mine drainage from coal abandoned mines; increases funding for the Saving America's Treasures Account, offset by reducing funding from the Construction account of the National Park Service; and increases the allocation for the Land and Water Conservation Fund Stateside program from \$30 million to \$40 million, by reducing the allocation for the Department of Interior, Working Capital Fund by \$10 million (the request for a recorded vote was withdrawn, and pursuant to the voice vote, the amendment was adopted). Page H7463

Rejected:

Heller amendment (No. 3 printed in part B of H. Rept. 111–184) that was debated on June 25th and sought to prohibit funds made available by this Act from being spent to build an interagency facility in one specific location in Carson City, Nevada (by a recorded vote of 202 ayes to 225 noes, Roll No. 467);

Page H7464

Jordan (OH) amendment (No. 4 printed in part B of H. Rept. 111–184) that was debated on June 25th and sought to reduce overall spending in the bill by \$5.75 billion to reflect FY2008 spending levels (by a recorded vote of 169 ayes to 259 noes, Roll No. 468);

Pages H7465–66

Stearns amendment (No. 6 printed in part B of H. Rept. 111–184) that was debated on June 25th and sought to decrease the funding included in the Interior and Environment Appropriations Act for the Environmental Protection Agency by 38% to reduce spending to 2009 levels (by a recorded vote of 170 ayes to 261 noes, Roll No. 469);

Page H7466

Campbell amendment (No. 1 printed in part C of H. Rept. 111–184) that was debated on June 25th and sought to strike \$1 million in funding for the "Restore Good Fellow Lodge, Indiana Dunes National Lakeshore" and reduce the overall cost of the

bill by a commensurate amount (by a recorded vote of 123 ayes to 305 noes, Roll No. 470);

Pages H7466-67

Campbell amendment (No. 3 printed in part D of H. Rept. 111–184) that was debated on June 25th and sought to strike the \$150,000 earmark for Traditional Arts in Upstate New York in Canton, New York (by a recorded vote of 122 ayes to 309 noes, Roll No. 471);

Pages H7467–68

Campbell amendment (No. 3 printed in part C of H. Rept. 111–184) that was debated on June 25th and sought to strike the \$150,000 in funding for the Tarrytown Music Hall Restoration and reduce the overall cost of the bill by a commensurate amount (by a recorded vote of 122 ayes to 301 noes, Roll No. 472);

Pages H7468–69

Campbell amendment (No. 1 printed in part E of H. Rept. 111–184) that was debated on June 25th and sought to strike the earmark for the Angel Island State Park Immigration Station Hospital Rehabilitation project (by a recorded vote of 131 ayes to 296 noes, Roll No. 473); and

Page H7469

Campbell amendment (No. 4 printed in part C of H. Rept. 111–184) that was debated on June 25th and sought to strike the \$150,000 in funding for the Historic Fort Payne Coal and Iron Building Rehabilitation and reduce the overall cost of the bill by a commensurate amount (by a recorded vote of 114 ayes to 317 noes, Roll No. 474). Pages H7469–70

H. Res. 578, the rule providing for consideration of the bill, was agreed to on Thursday, June 25th.

American Clean Energy and Security Act of 2009: The House passed H.R. 2454, to create clean energy jobs, achieve energy independence, reduce global warming pollution and transition to a clean energy economy, by a recorded vote of 219 ayes to 212 noes, Roll No. 477.

Pages H7451-61, H7462-63, H7471-7686

Pursuant to the rule, the amendment in the nature of a substitute consisting of the text of H.R. 2998, modified by the amendment printed in part A of H. Rept. 111–185, shall be considered as adopted, in lieu of the amendment recommended by the Committee on Energy and Commerce now printed in the bill.

Page H7471

Rejected:

Forbes amendment in the nature of a substitute (No. 1 printed in part B of H. Rept. 111–185) that sought to strike all and insert the text of H.R. 513, the "New Manhattan Project for Energy Independence" (by a recorded vote of 172 ayes to 256 noes, Roll No. 476).

Pages H7672–86

H. Res. 587, the rule providing for consideration of the bill, was agreed to by a recorded vote of 217 ayes to 205 noes, Roll No. 466, after agreeing to

order the previous question by a yea-and-nay vote of 232 yeas to 189 nays, Roll No. 465. Pages H7462-63

Supporting the goals and objectives of the Prague Conference on Holocaust Era Assets: The House agreed to discharge and agree to H. Con. Res. 89, to support the goals and objectives of the Prague Conference on Holocaust Era Assets. Pages H7687–88

Member Resignation: Read a letter from Representative Tauscher, wherein she resigned as Representative for the 10th Congressional District of California, effective immediately.

Page H7690

Whole Number of the House: The Speaker announced to the House that, in light of the resignation of the gentlewoman from California, Mrs. Tauscher, the whole number of the House is adjusted to 433.

Page H7690

Quorum Calls—Votes: Three yea-and-nay votes and 11 recorded votes developed during the proceedings of today and appear on pages H7461, H7462, H7462–63, H7464, H7465–66, H7466, H7467, H7467–68, H7468–69, H7469, H7470, H7470–71, H7685, H7686. There were no quorum calls.

Adjournment: The House met at 9 a.m. and adjourned at 9:21 p.m.

Committee Meetings

BRIEFING—HOT SPOTS

Permanent Select Committee on Intelligence: Met in executive session to hold a briefing on Hot Spots (N. Korean and Afghanistan Issues). Testimony was heard from Departmental witnesses.

Next Meeting of the SENATE 2 p.m., Monday, July 6

(Unless the House of Representatives fails to adopt S. Con. Res. 31, Adjournment Resolution; if the House of Representatives fails to act, Senate convenes at 2 p.m., on Monday, June 29, 2009.)

Senate Chamber

Program for Monday: Senate will resume consideration of H.R. 2918, Legislative Branch Appropriations Act, and vote on or in relation to McCain Amendment No. 1366 (to Amendment No. 1365), at 5:30 p.m.

Next Meeting of the HOUSE OF REPRESENTATIVES 2 p.m., Tuesday, July 7

House Chamber

Program for Tuesday: To be announced.

Extensions of Remarks, as inserted in this issue

HOUSE

Abercrombie, Neil, Hawaii, E1611 Aderholt, Robert B., Ala., E1589 Akin, W. Todd, Mo., E1584 Baca, Joe, Calif., E1613 Bachus, Spencer, Ala., E1590 Barrett, J. Gresham, S.C., E1607 Bean, Melissa L., Ill., E1620 Becerra, Xavier, Calif., E1627 Bilbray, Brian P., Calif., E1584, E1592 Blumenauer, Earl, Ore., E1575, E1597 Blunt, Roy, Mo., E1589 Bonner, Jo, Ala., E1591 Bono Mack, Mary, Calif., E1578 Bordallo, Madeleine Z., Guam, E1613 Boustany, Charles W., Jr., La., E1578 Boyd, Allen, Fla., E1625 Brady, Robert A., Pa., E1578, E1593 Burgess, Michael C., Tex., E1593 Burton, Dan, Ind., E1600 Calvert, Ken. Calif., E1603, E1616 Capito, Shelley Moore, W.Va., E1588, Capuano, Michael E., Mass., E1592, Carter, John R., Tex., E1580, E1590, E1591, E1592, E1593, E1593

Castle, Michael N., Del., E1594 Clarke, Yvette D., N.Y., E1599 Cohen, Steve, Tenn., E1574 Cole, Tom, Okla., E1576 Conaway, K. Michael, Tex., E1605 Connolly, Gerald E., Va., E1573, E1574, E1575, E1576, E1578, E1579, E1619 Costa, Jim, Calif., E1625, E1628, E1631 Courtney, Joe, Conn., E1615 Crenshaw, Ander, Fla., E1630

Crowley, Joseph, N.Y., E1599, E1608 Davis, Danny K., Ill., E1612, E1616 Davis, Geoff, Ky., E1605, E1607 Dent, Charles W., Pa., E1586 Dingell, John D., Mich., E1584 Dreier, David, Calif., E1588 Duncan, John J., Jr., Tenn., E1576 Etheridge, Bob, N.C., E1606, E1617 Fallin, Mary, Okla., E1620 Farr, Sam, Calif., E1588 Forbes, J. Randy, Va., E1606 Frelinghuysen, Rodney P., N.J., E1586 Gerlach, Jim, Pa., E1591, E1605 Giffords, Gabrielle, Ariz., E1629 Gingrey, Phil, Ga., E1576, E1583 Graves, Sam, Mo., E1603 Green, Al, Tex., E1573 Green, Gene, Tex., E1609 Guthrie, Brett, Ky., E1606, E1607 Gutierrez, Luis V., Ill., E1625 Hastings, Alcee L., Fla., E1619, E1633 Heller, Dean, Nev., E1590 Higgins, Brian, N.Y., E1622 Holt, Rush D., N.J., E1607 Hoyer, Steny H., Md., E1615 Hunter, Duncan, Calif., E1577 Inslee, Jay, Wash., E1629 Jackson-Lee, Sheila, Tex., E1630, E1630, E1631, E1632, E1633, E1634 Johnson, Eddie Bernice, Tex., E1577 Johnson, Sam, Tex., E1608 Johnson, Timothy V., Ill., E1588 Jones, Walter B., N.C., E1603 Kanjorski, Paul E., Pa., E1614 Kildee, Dale E., Mich., E1586 Kind, Ron, Wisc., E1618 King, Peter T., N.Y., E1590 Kingston, Jack, Ga., E1619

Kissell, Larry, N.C., E1625 Kucinich, Dennis J., Ohio, E1602, E1605, E1612, E1619, E1622, E1624, E1625, E1633 Lance, Leonard, N.J., E1588, E1601 Langevin, James R., R.I., E1580 LaTourette, Steven C., Ohio, E1589 Latta, Robert E., Ohio, E1590, E1630 Lewis, Jerry, Calif., E1624 Lewis, John, Ga., E1625, E1628 Lipinski, Daniel, Ill., E1614 LoBiondo, Frank A., N.J., E1599 Luján, Ben Ray, N.M., E1619 Lungren, Daniel E., Calif., E1596 McCarthy, Kevin, Calif., E1595, E1601 McGovern, James P., Mass., E1627, E1631 Michael M. McMahon, N.Y., E1592 McMorris Rodgers, Cathy, Wash., E1614, E1616 Maloney, Carolyn B., N.Y., E1612 Manzullo, Donald A., Ill., E1586 Markey, Edward J., Mass., E1624 Mica, John L., Fla., E1591, E1598, E1600, E1631 Miller, Candice S., Mich., E1589, E1593 Miller, Gary G., Calif., E1622, E1632 Miller, Jeff, Fla., E1581, E1602, E1605 Moran, James P., Va., E1595 Moran, Jerry, Kans., E1573 Murphy, Tim, Pa., E1575 Murtha, John P., Pa., E1610 Nadler, Jerrold, N.Y., E1580 Neugebauer, Randy, Tex., E1575 Oberstar, James L., Minn., E1596 Obey, David R., Wisc., E1618 Pascrell, Bill, Jr., N.J., E1600 Perriello, Thomas S.P., Va., E1623 Platts, Todd Russell, Pa., E1596

Poe, Ted, Tex., E1602, E1606 Polis, Jared, Colo., E1598 Pomeroy, Earl, N.D., E1608 Posey, Bill, Fla., E1596 Quigley, Mike, Ill., E1609 Radanovich, George, Calif., E1603 Rahall, Nick J., II, W.Va., E1599 Rehberg, Denny, Mont., E1594, E1603 Reichert, David G., Wash., E1597 Reyes, Silvestre, Tex., E1611, E1627, E1629 Rogers, Harold, Ky., E1592, E1626 Rogers, Mike, Ala., E1598 Rooney, Thomas J., Fla., E1579 Roskam, Peter J., Ill., E1581 Roybal-Allard, Lucille, Calif., E1581 Salazar, John T., Colo., E1597, E1600 Schock, Aaron, Ill., E1606 Schrader, Kurt, Ore., E1610 Schwartz, Allyson Y., Pa., E1574 Scott, Robert C. "Bobby", Va., E1604 Sessions, Pete, Tex., E1617 Simpson, Michael K., Idaho, E1611 Stark, Fortney Pete, Calif., E1587 Stupak, Bart, Mich., E1626 Terry, Lee, Nebr., E1600 Tiahrt, Todd, Kans., E1610, E1623 Van Hollen, Chris, Md., E1612 Walden, Greg, Ore., E1604 Wamp, Zach, Tenn., E1591, E1626 Waters, Maxine, Calif., E1610, E1617, E1623 Wilson, Joe, S.C., E1574 Wittman, Robert J., Va., E1595 Woolsey, Lynn C., Calif., E1587

Young, C.W. Bill, Fla., E1592

Young, Don. Alaska, E1605

Young, Don. Alaska, E1605



Congressional Record (USPS 087-390). The Periodicals postage is paid at Washington, D.C. The public proceedings of each House of Congress as reported by the Official Reporters through and of Congress, as reported by the Official Reporters thereof, are printed pursuant to directions of the Joint Committee on Printing as authorized by appropriate provisions of Title 44, United

States Code, and published for each day that one or both Houses are in session, excepting very infrequent instances when two or more unusually small consecutive issues are printed one time. Public access to the Congressional Record is available online through GPO Access, a service of the Government Printing Office, free of charge to the user. The online database is updated each day the Congressional Record is published. The database includes both text and graphics from the beginning of the 103d Congress, 2d session (January 1994) forward. It is available through GPO Access at www.gpo.gov/gpoaccess. Customers can also access this information with WAIS client software, via telnet at swais.access.gpo.gov, or dial-in using communications software and a modem at 202-512-1661. Questions or comments regarding this database or GPO Access can be directed to the GPO Access User Support Team at: E-Mail: gpoaccess@gpo.gov; Phone 1-888-293-6498 (toll-free), 202-512-1530 (D.C. area); Fax: 202-512-1262. The Team's hours of availability are Monday through Friday, 7:00 a.m. to 5:30 p.m., Eastern Standard Time, except Federal holidays. ¶The Congressional Record paper and 24x microfiche edition will be furnished by mail to subscribers, free of postage, at the following prices: paper edition, \$252.00 for six months, \$503.00 per year, or purchased as follows: less than 200 pages, \$10.50; between 200 and 400 pages, \$21.00; greater than 400 pages, \$31.50, payable in advance; microfiche edition, \$146.00 per year, or purchased for \$3.00 per issue payable in advance. The semimonthly Congressional Record Index may be purchased for the same per issue prices. To place an order for any of these products, visit the U.S. Government Online Bookstore at: bookstore.gpo.gov. Mail orders to: Superintendent of Documents, P.O. Box 371954, Pittsburgh, PA 15250-7954, or phone orders to 866-512-1800 (toll free), 202-512-1800 (D.C. area), or fax to 202-512-2250. Remit check or money order, made payable to the Superintendent of Documents, or use VISA, MasterCard, Discover, American Express, or GPO Deposit Account. \(\) Following each session of Congress, the daily Congressional Record is revised, printed, permanently bound and sold by the Superintendent of Documents in individual parts or by sets. With the exception of copyrighted articles, there are no restrictions on the republication of material from the Congressional Record.

POSTMASTER: Send address changes to the Superintendent of Documents, Congressional Record, U.S. Government Printing Office, Washington, D.C. 20402, along with the entire mailing label from the last issue received.