# Chapter – 6 Fire Fighting Equipment

#### A. Introduction

BIA wildland fire program equipment resources include engines, dozers, water tenders, and other motorized equipment for fire operations.

BIA policy will comply with established standards for training, equipment, communications, organization, and operating procedures required to effectively perform arduous duties in multi-agency environments and various geographic areas.

Approved foam concentrate may be used to improve the efficiency of water, except near waterways where accidental spillage or over spray of the chemical could be harmful to the aquatic ecosystem, or other identified resource concerns.

## B. National Model 52 Wildland Engine Program

The Model 52 Wildland Engine program was created by the BIA in 1996. The objective of the program is to provide a centralized process for replacement parts refurbishing, training and fabrication of Model 52 pumping systems. Detailed information on the program can be found in the BIA *National Model 52 Wildland Engine Program Operations Guide*.

## C. Mission/Policy

- Provide a standardized Model 52 engine for the participating Agency or Tribal organization.
- Provide an opportunity to supply trucks for Model 52 pumping systems.
- Provide refurbishment and repair services for Fire Management Planning Analysis (FMPA) approved number of engines.
- Provide training in the use and maintenance of the Model 52 pumping systems.
- Evaluate new equipment and Model 52 improvements to meet the wildland fire program needs.
- Provide emergency repair or replacement for Model 52 pumping systems.

#### D. Model 52 Replacement Guidelines

BIA Model 52 replacement schedule (funding pending) is set as follows:

Model 52 Type 6
 Model 52 Type 4
 Years
 100,000 Miles
 12 Years
 100,000 Miles

# E. Organization

The program is organized into three geographical areas.

- Northwest Center (Missoula, MT) services the Northwest, Rocky Mountain and north half of the Pacific Region.
- Northern Center (Eagle Butte, SD) services the Great Plains and Midwest Regions.
- Southwest Center (Dulce, NM) services the Southwest, Western, Navajo, Eastern Oklahoma, and Southern Plains, Eastern and south half of the Pacific Region.

#### 1. Administration

- The program is administered through the Operations Group at the National Interagency Fire Center, Boise, Idaho.
- A Model 52 Oversight Group has been established to plan, develop and budget for the annual operations of the program. The Group is comprised of the Model 52 Program Leads at each center and the Deputy, Fire Operations.
- Trucks and fabrication orders for the Model 52 are procured nationally through the BIA-National Interagency Fire Center office.

# 2. Emergency Repairs

Emergency fire related repairs to a BIA Model 52 pumping package will be requested through the assigned user area Model 52 Center. The request will be reviewed and approved by the Center Manager before a Service Truck is dispatched or replacement parts are sent to the requesting agency.

#### 3. Non-Emergency/Non-Suppression Repairs

Non-Emergency Repairs shall be charged to the identified agency account. The account will be approved by an agency official (example; FMO, Forest Manager, Superintendent) before requested action is taken.

Authorization of account will be sent by email or signed fax identifying account and name and title of authorizing official. Initial request for all non-emergency repairs will be requested through the assigned user area Model 52 Center. The request will be reviewed and approved by the Center Manager before a Service Truck is dispatched or replacement part is mailed to the requesting agency

All Emergency and Non- Emergency repair expenditures shall be charged to an appropriate account.

# F. Operational Procedures

All engines will be equipped, operated, and maintained within guidelines established by the Department of Transportation (DOT). All personnel assigned to agency fire engines will meet all gear weight, cube, and manifest requirements specified in the *National Mobilization Guide* (NFES 2902).

All employees driving Wildland Engines are responsible for the proper care, operation, maintenance and protection of the vehicle. The use of government owned, rented, or leased motor vehicles is for official business only. Unauthorized use is prohibited.

# G. Engine Crew Staffing

 Type 6 and 7 engines will have a minimum crew of two - an engine boss (ENGB) and a firefighter Type II (FFT2).

# 2. Type 3, 4 or 5 engines will have a minimum crew size of three:

- Single resource engines will be comprised of an ENGB, and two or more FFT2s.
- Task force engines will have an ENGB and the appropriate number of FFT2s as required by engine type. For more information refer to NWCG Fireline Handbook, 410-1.

## H. Driving Standards

Refer to Chapter 9 Motor Vehicle Policy.

## I. Commercial Drivers License (CDL)

BIA and DOI policy requires all personnel who operate a vehicle with a Gross Vehicle Weight (GVW) over 26,000 pounds to have a valid CDL.

## J. Casuals Hired as Drivers When Employed By BIA

Refer to Chapter 10 Business Management and Administration.

# K. Standards for Wildland Engines

#### 1. Engine Water Reserve

Engine Operators will maintain at least 10 percent of the pumpable capacity of the water tank for emergency engine protection and drafting.

#### 2. Chocks

At least one set of wheel chocks will be carried on each engine and will be properly utilized whenever the engine is parked or left unattended. This includes engine operation in a stationary mode without a driver "in place."

#### 3. Fire Extinguisher

All engines will have at least one 5 lb. ABC rated (minimum) fire extinguisher, either in full view or in a clearly marked compartment.

#### 4. First Aid Kit

Each engine shall carry, in a clearly marked compartment, a fully equipped 10-person first aid kit.

#### 5. Gross Vehicle Weight (GVW)

Each engine will have an annually certified weight slip in the vehicle at all times. Weight slip will show individual axle weights and total GVW. Operators of engines and water tenders must ensure that the maximum certified gross vehicle and axle weight ratings are never exceeded, including gear, personnel and fuel.

National Fire Protection Association (NFPA) 1906 standard, *Carrying Capacity*, section 5.1.2 (4) recommends fire apparatus have an estimated in service weight of 200 lbs for each seating position, and 70 lbs of personal gear for each sitting position, section 5.1.2(5).

Miscellaneous equipment allowance, section 5.1.2(8), has incorporated the following weight limits as the standard for equipment on fire apparatus with the corresponding vehicle weights:

Chassis GVRW	Equipment Weight
10,001 – 15,000	500
15,001 – 20,000	1,000
20,001 – 26,000	1,500
Greater than 26,000	2,000

# L. Speed Limits

Posted speed limits will not be exceeded.

## M. Lighting

Headlights and taillights shall remain illuminated at all times while the vehicle is in motion. Lighting packages will meet NFPA 1906, *Standard for Wildland Fire Apparatus 2006 Edition*, section 6.8.12, Color of Warning Lights, and Zone Colors as listed in section 6.8.12.1. A red, white, and yellow combination is the accepted color scheme for fire. Lighting packages containing blue lights are reserved for law enforcement and are not allowed on fire vehicles.

It is recommended all engines currently in service with lighting packages meet NFPA standards. All new vehicles with lighting packages will be required to meet the NFPA standard. Fire Management personnel may retrofit lighting packages to meet the standard.

## N. Emergency Light Use

Emergency lighting will be used only during on site wildland fire operations or to mitigate serious safety hazards. Overhead lighting and other emergency lighting must meet state code requirements, and will be illuminated whenever the visibility is reduced to less than 300 feet.

## O. Fuel Use, Storage and Transportation

Guidance and direction for the use, storage, and transportation of fuel can be found in the *Interagency Transportation Guide for Gasoline, Mixed Gas, Drip Torch Fuel, and Diesel*, PMS-442, <a href="http://www.nwcg.gov/pms/pubs/442/pms442.pdf">http://www.nwcg.gov/pms/pubs/442/pms442.pdf</a>

## P. Fire Engine Maintenance Procedure and Record

Apparatus safety and operational inspections will be accomplished either on a post-fire or daily basis. Offices are required to document these inspections. Periodic maintenance (as required by the manufacturer) shall be performed at the intervals recommended and properly documented.

## Q. Vehicle Repairs Maintenance

The cost of all vehicle repairs and maintenance is the responsibility of the individual Agency unless the damage is directly attributable to operations on a wildfire. In that case, with written documentation, approval from the host Agency (BIA, FS, BLM, NPS, and FWS), and the damages may be paid for under the wildland fire's suppression account.

# R. Engine Inventories

An inventory of supplies and equipment carried on each vehicle is required to maintain accountability and to obtain replacement items lost or damaged on incidents. The standard inventory for engines is found in Appendix 6-1.

#### S. Water Tenders

Water Tender Staffing Standards

#### 1. Water Tender (Non-Tactical)

- Qualifications: CDL (tank endorsement).
- Staffing: A water tender (non-tactical) may be staffed with a crew
  of one driver/operator when it is used in a support role as a fire
  engine refill unit or for dust abatement. These operators do not
  have to pass the Work Capacity Test (WCT) but are required to
  take annual refresher training.

#### 2. Water Tender (Tactical)

Tactical use is defined as "direct fire suppression missions such as pumping hoselays, live reel use, running attack, and use of spray bars and monitors to suppress fires."

- Qualifications: Engine Operator (ENOP), CDL (tank endorsement)
- Staffing: Tactical water tenders will carry a minimum crew of two:
  - One ENOP
  - One Engine Module Member

#### T. Dozer/Tractor Plows

#### 1. Dozer/Tractor Plow Training and Qualifications

Agency personnel assigned as dozer/tractor plow operators will meet the training standards for a Firefighter 2 (FFT2). This includes all safety and annual refresher training. While on fire assignments, all operators and support crew will meet PPE requirements including the use of aramid fiber clothing, hard hats, fire shelters, boots, etc.

#### 2. Dozer/Tractor Plow Physical Fitness Standards

All employee dozer/tractor plow operators will meet the WCT requirements at the Moderate level before accepting fire assignments.

#### 3. Dozer/Tractor Plow Operational Procedures

- Agency owned and operated dozer/tractor plows will be equipped with programmable two-way radios, configured to allow the operator to monitor radio traffic.
- Agency dozer/tractor plows with non-red carded operators and all contract dozer/tractor plows will have agency supplied supervision when assigned to any suppression operations.
- Contract or offer-for-hire dozers must also be provided with radio communications, either through a qualified dozer/tractor plow boss or an agency-supplied radio. Contract dozer/tractor plows will meet the specifications identified in their agreement/contract.
- Operators of dozer/tractor plows and transport equipment will meet DOT certifications and requirements regarding the use and movement of heavy equipment, including driving limitations, CDL requirements, and pilot car use.

# U. All Terrain Vehicles (ATV)/ Utility Terrain Vehicles (UTV)

The operation of ATV/UTVs can be high risk. The use of ATV/UTVs should be evaluated to ensure that use is essential to accomplish the mission, rather than for convenience.

Because of the high risk nature, each agency needs to develop a specific operational and safety policy. Common policy requirements for wildland fire operations are highlighted below:

- A JHA must be completed by Fire/Fuels Management personnel and approved by the Agency Administrator prior to ATV/UTV operations.
- All personnel authorized to operate an ATV/UTV must first complete agency specific or manufacturer/industry-provided training in safe operating procedures and appropriate PPE.
- Re-evaluation/Re-certification Operators shall be re-evaluated every three years. Infrequent users (less than 16 hours of riding a year) shall have a check ride prior to scheduled use of an ATV/UTV.
   Documentation of certification/re-certification will be documented in IQCS, and printed on Red Card for wildland fire operations.

- Specific authorization for ATV/UTV use is required -- all ATV/UTV operators must hold a valid Motor Vehicle Operator's Identification Card, and ATV/UTV certification must be documented on card.
- ATVs can only have a single rider passengers are prohibited even if ATV is designed for two riders.
- UTVs passengers are limited to the number of seats installed by manufacturer. The operator and passenger(s) must use seatbelts while the vehicle is in motion.
- Operators must use required PPE while loading/unloading ATV/UTV.
- Cargo loads shall be loaded and secured as to not affect the vehicle's center of gravity and shall not exceed manufacturer's recommendations for maximum carrying capacity.
- When transporting external fuel containers with a UTV, a 5 lb class BC fire extinguisher must be secured to the UTV.

#### V. Required PPE

# 1. ATV Head Protection for Wildland Fire Operations:

- ATV Helmets must meet Snell SA2005 or SA2010 certification
- A <sup>3</sup>⁄<sub>4</sub> face model meeting Snell SA2005 or SA2010 certification is acceptable for use.
- Use of half "shorty" helmets requires a JHA for fireline use and must include justification for its use. Refer to MTDC Tech Tip publication, A Helmet for ATV Operators with Fireline Duties (0651-2350-MTDC).

# 2. UTV Head Protection – Helmets must meet DOT, ANSI Z90.1; or Snell SA2005 or SA2010 unless:

- UTV is used for low speeds and smooth travel surfaces, administrative use (e.g., campgrounds, incident base camps) UTV operators are not required to wear hardhats or helmets.
- UTV is equipped with approved Rollover Protection System (ROPS).

 A comprehensive and properly prepared JHA of the specific conditions demonstrates no more than a minimal risk, then a hard hat meeting NFPA 1977 or ANSI Z 89.1 standards may be worn with chin straps secured in place under chin.

# 3. Eye protection (goggles, face shield, or safety glasses) based upon JHA.

Eye protection is not required for a UTV equipped with an original manufacturer windshield that protects the face from branches, flying debris, etc., unless otherwise required by an associated industrial use activity or JHA.

# 4. If operating ATV/UTV on the fireline, the following are required:

- Leather or leather/flame resistant combination gloves. Flight gloves are not approved for fireline use.
- Yellow aramid shirt
- Aramid trousers
- Wildland fire boots

ATV/UTV operator shall carry a personal communication device (e.g. two-way radio, cellular phone, or satellite phone).

# W. Operational Guidelines for Invasive Species

To reduce the transport, introduction, and establishment of noxious weeds or other invasive species biological contaminants on the landscape due to fire suppression activities, all fire suppression and support vehicles, tools, and machinery should be cleaned at a designated area prior to arriving and leaving the incident. Onsite fire equipment should be used to thoroughly clean the undercarriage, fender wells, tires, radiator, and exterior of the vehicle. Firefighter personnel should clean personal equipment, boots, clothing, etc. for weed materials or other invasive species, including visible plant parts, soil and other materials as identified by the fire resource advisor. The cleaning area should also be clearly marked to identify the area for post fire control treatments, as needed.

In order to prevent the spread of aquatic invasive species, it is important that fire personnel not only recognize the threat aquatic invasive species pose to ecological integrity, but how our fire operations and resulting actions can influence their spread. Each local land management unit may have specific guidelines related to aquatic invasive species. Therefore, it is recommended that you consult established local jurisdictional guidelines for minimizing the spread of aquatic invasive species and for equipment cleaning guidance specific to those prevalent areas and associated species. To minimize the potential transmission of aquatic invasive species, it is recommended that you:

- Consult with local biologists, resource advisers (READ) and fire
  personnel for known aquatic invasive species locations in the area and
  avoid them when possible.
- Avoid entering (driving through) water bodies or saturated areas whenever possible.
- Avoid transferring water between drainages or between unconnected waters within the same drainage when possible.
- Use the smallest screen possible that does not negatively impact operations and avoid sucking organic and bottom substrate material into water intakes when drafting from a natural water body.
- Avoid obtaining water from multiple sources during a single operational period when possible.
- Remove all visible plant parts, soil and other materials from external surfaces of gear and equipment after an operational period. If possible, power-wash all accessible surfaces with clean, hot water (ideally > 140° F) in an area designated by a local READ.

# X. Aerial Ignition Devices

Information on types of aerial ignition devices, operational guidelines and personnel qualifications may be found in the *Interagency Aerial Ignition Guide*, http://www.blm.gov/nifc/st/en/prog/fire/Aviation/Airops/iaig.html

# Y. Ground Ignition Devices

Guidance and direction for use of approved ground ignition equipment and the transportation and dispensing of drip torch fuel can be found in the *Interagency Transportation Guide for Gasoline, Mixed Gas, Drip Torch Fuel, and Diesel* at: http://www.nwcg.gov/pms/pubs/442/pms442.pdf.

**BLANK PAGE** 

# APPENDIX 6-1 Engine Equipment Inventory

Category	Item Description	NFES	Type	
		#	3,4&5	6
	McLeod	0296	1	1
	Combination Tool	0346	1	1
	Shovel	0171	3	2
	Pulaski	0146	3	2
	Backpack Pump	1149	3	2
	Fusees (case)	0105	1	1/2
Fire Tools &	Foam, concentrate, Class A (5-gallon)	1145	1	1
Equipment	Chain Saw (and Chaps)		1	1
	Chain saw Tool Kit	0342	1	1
	Drip Torch	0241	2	1
	Portable Pump		*	*
	First Aid Kit, 10-Person	0068	1	1
	Burn Kit		1	1
Medical	Body Fluid Barrier Kit	0640	1	1
	Flashlight, general service	0069	1	1
	Chock blocks		1	1
	Tow Chain or Cable	1856	1	1
	Jack, hydraulic (comply w/GVW)		1	1
	Lug Wrench		1	1
	Pliers, fence		1	1
	Food (48 hour supply)	1842	1	1
	Rags	3309	*	*
0	Rope/Cord (feet)		50	50
General Supplies	Sheeting, plastic, 10' x 20'	1287	1	1
	Tape, Duct	0071	1	1
	Tape, filament (roll)	0222	2	2
	Water (gallon/person) minimum		2	2
	Bolt Cutters		1	1
	Toilet Paper (roll)	0142	*	*
	Cooler or Ice Chest	0557	*	*
	Hand Primer, Mark III	0145	*	*
	Hose Clamp	0046	2	2
	Gaskets (set)		1	1
	Pail, collapsible	0141	1	1
	Hose Reel Crank		*	*

6-13

Category	Item Description	NFES #	Туре	
			3,4&5	6
Safety	Fire Extinguisher	2143	1	1
	Flagging, lime green (roll)	0258	*	*
	Flagging, yellow w/black stripes (roll)	0267	*	*
	Fuel Safety Can (OSHA, metal 5 gallon)	1291	*	*
	Reflector Set		*	*
	General Tool Kit (5180-00-177-7033/GSA)		1	1
	Oil, automotive, quart		4	2
	Oil, penetrating can		1	1
	Oil, automatic transmission, quart		1	1
Vehicle &	Brake Fluid, pint		1	1
Pump	Filter, gas		1	1
Support	Fan belts		1	1
	Spark plugs		1	1
	Hose, air compressor w/adapters		1	0
	Fuses (set)		1	1
	Tire Pressure Gauge		1	1
	Jumper Cables		1	1
	Battery Terminal Cleaner		*	*
	Tape, electrical, plastic	0619	1	1
	Tape, Teflon		1	1
Radio	Portable		1	1
	Mobile		1	1
	Batteries (for portable radio)		2	2
	File, mill bastard	0060	*	*
	Head Lamp	0713	1	1
	Hard Hat	0109	1	1
	Goggles	1024	2	2
	Gloves		*	*
	First Aid Kit, individual	0067	1	1
Personal	Fire Shirt		*	*
Gear	Fire Shelter w/case & liner	0169	2	1
(Extra	Packsack	0744	2	1
Supply)	Batteries, headlamp (pkg)	0030	6	4
	Ear Plugs (pair)	1027	3	3
	Dust Mask	0131	6	4

0-1	Maria Danastatian	NFES	Тур	e
Category	Item Description	#	3,4&5	6
Hose	Booster (feet/reel)	1220	100	100
	Suction (length, 8' or 10')		2	2
	1" NPSH (feet)	0966	300	300
	1½ " NH (feet)	0967	300	300
	3/4 " NH, garden (feet)	1016	300	300
	11/2 " NH, engine protection (feet)		20	20
	1½ "NH, refill (feet)		15	15
	Forester, 1" NPSH	0024	3	2
	Adjustable, 1" NPSH	0138	4	2
	Adjustable, 1½ " NH	0137	5	3
	Adjustable, 3/4" NH	0136	4	2
	Foam, 3/4" NH	0627	1	1
Nozzle	Foam, 11/2 " NH	0628	1	1
	Mopup Wand	0720	2	1
	Tip, Mopup Wand	0735	4	2
	Tip, forester nozzle, fog	0903	*	*
	Tip, forester nozzle, straight stream	0638	*	*
	1" NPSH, Two-Way Gated	0259	2	1
Wye	1½ " NH. Two-Way Gated	0231	4	2
	3/4" NH w/Ball Valve, Gated	0739	6	4
	1" NPSH-F to 1" NH-M	0003	1*	1*
	1" NH-F to 1" NPSH-M	0004	1	1
Adapters	1½ " NPSH-F to 1½ " NH-M	0007	1	1
	1½ " NH-F to NH-F to 1½ " NPSH-M	0006	*	*
	3/4" NH-F to 1" NPSH-M	2235	1	1
Increasers	1" NPSH-F to 1½ " NH-M	0416	2	1
	1" NPSH, Double Female	0710	1	1
Coupling	1" NPSH, Double Male	0916	1	1
	1½" NH, Double Female	0857	2	2
	1½" NH, Double Male	0856	1	1
	1" NPSH-F to 3/4" NH-M	0733	3	3
l <u>.</u>	1½" NH-F to 1" NPSH-M	0010	6	4
Reducer/ Adapters	2" NPSH-F to 11/2" NH-M	0417	1	1
Adapters	21/2" NPSH-F to 11/2" NH-M	2229	*	*
Reducer	1½" NH-F to 1" NH-M	0009	1	1
	2.5" NH-F to 11/2" NH-M	2230	1	1
	1" NPSH-F x 1" NPSH-M x 1" NPSH-M	2240	2	2
Tee	w/cap			
	1½" NH-F x 1½" NH-M x 1" NPSH-M w/cap	0731	2	2
	1½" NH-F x 1½" NH-M x 1" NPSH-M w/valve	0230	2	2

Catamami	egory Item Description	NFES #	Type	
Category			3,4&5	6
	1½" NH-F, Automatic Check and Bleeder	0228	1	1
	3/4" NH, Shut Off	0738	5	5
Valve	1" Shut Off	1201	1	1
valve	11/2" Shut Off	1207	1	1
	Foot w/strainer		1	1
Ejector	1" NPSH x 1½" NH x 1½" NH, Jet Refill	7429	*	*
	Hydrant, adjustable, 8"	0688	1	1
Wrench	Spanner, 5", 1" to 11/2" hose size	0234	4	1
	Spanner, 11", 11/2" to 21/2" hose size	0235	2	2
	Pipe, 14"	0934	1	1
	Pipe, 20"		1	1
Engine	Fireline Handbook	0065	1	1
	Belt Weather Kit	1050	1	1
	Binoculars		1	1
	Map Case w/map		1	1
	Inventory List		1	1
	Standards for Fire and Aviation Operations		1	1

<sup>\*</sup> No minimums - carried by engine as an option, within weight limitations.