## **Look Up, Down and Around**

Fire Environment Factors	Indicators
Fuel Characteristics (assess)	"Continuous fine fuels"     Heavy loading of dead and down     Ladder fuels     Tight crown spacing     Special Conditions:     Firebrand sources     Numerous snags     Preheated canopy     Frost and/or bug kill     Unusual fine fuels     High dead to live fuel ratio
<u>Fuel Moisture</u> (feel and measure)	<ul> <li>"Low RH (&lt;25%)"</li> <li>Low 10 hr FMC (&lt;6%)</li> <li>Drought conditions</li> <li>Seasonal stage of drying</li> </ul>
<u>Fuel Temperature</u> (feel and measure)	<ul> <li>"High temperatures (&gt;85F)"</li> <li>High % of fuels w/direct sunlight</li> <li>Aspect fuel temperature increasing</li> </ul>
<u>Terrain</u> (scout)	<ul> <li>"Steep slopes (&gt;50%)"</li> <li>Chutes and chimneys</li> <li>Box canyons</li> <li>Saddles</li> <li>Narrow canyons</li> </ul>
Wind (observe)	<ul> <li>"Surface winds &gt; 10 mph"</li> <li>"Shifting winds"</li> <li>Lenticular clouds</li> <li>High, fast moving clouds</li> <li>Approaching cold front</li> <li>Cumulonimbus cloud development</li> <li>Sudden calm</li> </ul>
<u>Stability</u> (observe)	Good visibility Gusty winds and dust Cumulus clouds Castellatus clouds in the a.m. Smoke rises straight up Inversion beginning to lift Thermal belt
<u>Fire Behavior</u> (watch)	<ul> <li>"Well developed smoke column"</li> <li>"Trees torching"</li> <li>"Frequent spot fires"</li> <li>Leaning smoke column</li> <li>Sheared smoke column</li> <li>Changing smoke column</li> <li>Smoldering fires picking up</li> <li>Small fire whirls beginning</li> </ul>