Open Access

Research **Automatic inference of indexing rules for MEDLINE** Aurélie Névéol^{*1}, Sonya E Shooshan¹ and Vincent Claveau²

Address: ¹National Library of Medicine, 8600 Rockville Pike, Bethesda, MD 20894, USA and ²IRISA – CNRS, Campus de Beaulieu, 35042 Rennes, France

Email: Aurélie Névéol* - neveola@nlm.nih.gov; Sonya E Shooshan - sonya@nlm.nih.gov; Vincent Claveau - vincent.claveau@irisa.fr * Corresponding author

from Natural Language Processing in Biomedicine (BioNLP) ACL Workshop 2008 Columbus, OH, USA. 19 June 2008

Published: 19 November 2008

BMC Bioinformatics 2008, 9(Suppl 11):S11 doi:10.1186/1471-2105-9-S11-S11

This article is available from: http://www.biomedcentral.com/1471-2105/9/S11/S11

© 2008 Névéol et al; licensee BioMed Central Ltd.

This is an open access article distributed under the terms of the Creative Commons Attribution License (<u>http://creativecommons.org/licenses/by/2.0</u>), which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Abstract

Background: Indexing is a crucial step in any information retrieval system. In MEDLINE, a widely used database of the biomedical literature, the indexing process involves the selection of Medical Subject Headings in order to describe the subject matter of articles. The need for automatic tools to assist MEDLINE indexers in this task is growing with the increasing number of publications being added to MEDLINE.

Methods: In this paper, we describe the use and the customization of Inductive Logic Programming (ILP) to infer indexing rules that may be used to produce automatic indexing recommendations for MEDLINE indexers.

Results: Our results show that this original ILP-based approach outperforms manual rules when they exist. In addition, the use of ILP rules also improves the overall performance of the Medical Text Indexer (MTI), a system producing automatic indexing recommendations for MEDLINE.

Conclusion: We expect the sets of ILP rules obtained in this experiment to be integrated into MTI.

Background

Information retrieval in either specialized or general databases calls for the *indexing* of documents. The index generated for each document is then used to match users' queries against the collection. Text documents are usually indexed using either *free-text indexing*, which consists of freely assigning sequences of words to the documents, or *controlled indexing*, which consists of assigning concepts available from a controlled list of terms; our work employs the latter. In the biomedical domain, the Medical Subject Headings (MeSH[®]) thesaurus developed by the U.S. National Library of Medicine (NLM) is a widely used tool for indexing the literature. The MEDLINE database comprises more than 16 million biomedical articles. Each document referenced in MEDLINE is described by about a dozen keywords representing the subject matter of the article. These keywords are selected among the more than 24,000 MeSH main headings (e.g. *Aphasia, Patient Care, Hand...*). If appropriate, subheadings (or qualifiers) such as *surgery* or *pharmacology* chosen from a set of 83 may be attached to the main headings in order to refer to a more specific

aspect of the concept. For each main heading, MeSH defines a subset of "allowable qualifiers", so that only certain pairs can be used as indexing terms. For example, the pairs *aphasia/metabolism* and *hand/surgery* are allowable, but *hand/metabolism* is not.

The steady increase of publications to be indexed in MEDLINE (about 2,500 per day) has led to the development of automatic tools such as the Medical Text Indexer (MTI) [1] intended to assist NLM indexers with indexing recommendations.

The complexity of the indexing task and the increasing amount of data to be processed make it necessary to improve existing tools. For automatic indexing in particular, the attachment of subheadings to the main heading recommendations produced automatically is a significant help to indexers. Recent work [2] in the context of the "Indexing 2015" project at NLM showed that the use of indexing rules applied to stand-alone main headings was a good method to produce pair recommendations. The use of qualifiers in the description of articles' subject matter usually follows implicit rules involving the main headings assigned to the paper. Sets of manual rules developed for a few subheadings show good performance in terms of precision but are often lacking in terms of recall. In addition, the development of new rules is a complex, timeconsuming task.

The objective of the work presented here is to supplement the manual rules available with a set of automatically inferred rules to be used in MTI's Subheading Attachment module. We investigate a novel approach adapting Inductive Logic Programming (ILP) to the specific context of MEDLINE data, which requires efficient processing of large amounts of data. The rules that need to be obtained are similar to the following example: *If* a main heading from the "Anatomy" tree and a "Carboxylic Acids" term are recommended for indexing, *then* the pair " [Carboxylic Acids]/pharmacology" should also be recommended.

Related work

The automatic indexing of the biomedical literature using MeSH indexing terms has been investigated by several researchers working on text in English as well as other European languages such as French, German and Portuguese. Indexing approaches include Natural Language Processing (NLP) [3], machine learning [4-6] or a combination of both [1,7]. However, due to the large number of indexing terms and even larger number of possible combinations most of these efforts, even the most recent [6], focus on stand-alone main headings and do not take subheadings into account. The experiments reported in this paper build on earlier work [2,3] addressing the issue of

automatic indexing with MeSH main heading/subhead-ing pairs.

To our knowledge, there has been no effort to automatically produce MeSH indexing rules. Related work [8] investigated the discovery of MeSH association rules to be used for query expansion in health information retrieval. However, few rules could be obtained because of the complexity of the problem description using usual machine learning techniques (see next section). The machine learning approach we chose to use, viz. ILP, is able to overcome these issues. ILP has been previously used for several machine-learning problems including NLP applications; for instance, it was used to infer extraction patterns [9], alignment rules [10], tagging and other tasks [11]. In these cases the expressiveness of ILP was found to be very useful; specifically, ILP was able to provide simple representations for relational problems and produce rules that can be easily interpreted. The ability of the method to accommodate complex representations usually translates into high computational complexity, which can result in prohibitive computation delays on large-scale problems. Therefore, special attention must be given to this issue as detailed in the next section.

Methods

Use of inductive logic programming

In this section, we briefly introduce the basic principles of ILP; a more comprehensive description can be found in [12]. After stressing the advantages of this method for MeSH indexing, we describe how it was adapted to accommodate our specific context.

Principles of inductive logic programming

ILP is a supervised machine learning technique used to infer rules that are expressed with logical clauses (Prolog clauses) based on a set of examples also represented using Prolog.

Let us consider a set of positive examples E^+ , a set of negative examples E^- , and a background knowledge *B*. An ILP program aims at finding a set of rules *H* so that:

 $B \land H \land E^- \neq \Box$ and $B \land H \models E^+$, where \Box represents false and \models represents a logical implication.

In practice, these two conditions can be relaxed so that, in fact, the set of rules explains (covers) most of the positive examples while rejecting most of the negative examples. This way, sparse or noisy data (frequently found in realworld applications) can be processed in order to obtain general rules that bear some exceptions.

Most ILP algorithms deal with rule inference within a hypothesis space (\mathcal{E}_H) as illustrated by Figure 1; the ILP

Iteration until $E^+ = \emptyset$

- 1. randomly choose a positive example e^+ in E^+
- 2. build the most specific clause \perp covering e^+
- 3. go through hypothesis space \mathscr{E}_H based on \perp seeking a clause h maximizing score function Sc
- 4. add h to set H and remove examples covered by h from E^+

End iteration

Figure I

ALEPH Algorithm.

tool that we used for our experiments, ALEPH [13], is based on this very algorithm. The method of exploring the hypothesis space \mathcal{E}_H while constructing clauses is key for the inference phase (see last sub-section of this section).

Description of examples

In our context, ILP is used to infer rules describing the attachment of MeSH subheadings based on sample MEDLINE citations containing sets of MeSH indexing terms. For each subheading, we are expecting to find rules providing indications such as which main heading the subheading should be attached to, given the specific context the main heading appears in.

It may be argued that this problem can be addressed by a less complex method than ILP, such as association rules discovery [14]. However, methods for association rules discovery such as APRIORI would require describing each example as a tuple comprising the relevant main heading (that to which the subheading of interest may be attached) and the other main headings occurring in the citation. Basically, this would result in a tuple of dimension $24,000+ \times 24,000+$. Even less complex representations fail to account for the fact that a different number of

main headings may be assigned to each citation and for the hierarchical structure of MeSH [8].

These issues, typical of propositional methods (i.e. methods describing problems as attribute/value tuples), are however naturally resolved by ILP. The expressiveness of Prolog allows for a simple description of relational problems. Let us consider the sample citation shown in Table 1. Occurrences of main headings to which the focus subheading is attached constitute positive examples. For example, let us take pharmacology as our focus subheading; according to the citation shown in Table 1 the following example E⁺ will be constructed to indicate that *pharmacol*attached Acrylamide: ogy was to qualif(mh16179550_1,"pharmacology"). Occurrences of main headings to which the focus subheading is not attached, although it is allowable for this main heading (such as Astrocytes in our sample citation), constitute negative examples. Contextual information for this occurrence (i.e. the other main headings assigned to the same citation) is accounted for in the background knowledge as shown in the table. The MeSH hierarchy is also included in the background knowledge in this way, with W representing a term:

Table I: ILP representation	of a MEDLINE citation
-----------------------------	-----------------------

Excerpt of a sample citation	Excerpt of ILP representation in B		
PMID – 16179550	in_article(pmid16179550, mh16179550_1).		
MH – Acrylamide/*pharmacology	hierarchy(mh16179550_1,"Acrylamide").		
MH – Animals	in_article(pmid16179550, mh16179550_2).		
MH – Astrocytes/drug effects	hierarchy(mh16179550_2,"Animals").		
MH – Histidine/physiology	in_article(pmid16179550, mh16179550_3).		
MH – Amino Acid Transport	hierarchy(mh16179550_3,"Astrocytes").		
Systems/*biosynthesis	in_article(pmid16179550, mh16179550_4).		

hierarchy(W, "Neuroglia") :- hierarchy(W, "Astrocytes").

hierarchy(W,"Nervous System") :- hierarchy(W,"Neuroglia").

hierarchy(W,"Anatomy") :- hierarchy(W,"Nervous System").

•••

This indicates that the main heading *Astrocytes* is a descendant of main heading *Neuroglia* in the MeSH hierarchy, which is, in turn, a descendant of *Nervous System*. MeSH hierarchical information described in this way can be exploited in the inference process. The construction of example clauses is fully automated. The rules that are then inferred use the various predicates described above. Below is a sample rule that could have been inferred from the example qualif(mh16179550_1,"pharmacology")., with *W* representing a term and *A* an article:

 $qualif(W_1, "pharmacology") :- hierarchy(W_1, "Carboxylic Acids"), in_article(A, W_1), in_article(A, W_2), hierarchy(W_2, "Anatomy"). In fact, it corresponds to the rule that we presented in the background section.$

Optimizing the performance of the inference process

The consequence of the expressiveness of ILP is the complexity of rule inference. The hypothesis space \mathcal{E}_H is usually very large, or even non-finite in some cases. Moreover, the computation of score *Sc* depends on the number of positive and negative examples covered (explained) by the hypothesis being tested, which implies checking every single example against the clause. This is the most costintensive aspect of ILP. It is necessary to handle it carefully in order to ensure reasonable computation times while producing relevant rules.

Luckily, \mathcal{E}_H can be structured and inheritance properties can be taken into account while going through rules; this is commonly achieved using a θ -subsumption relation [15].

Definition 1 (θ **-subsumption)** A clause $C_1 \theta$ -subsumes (is more general than) a clause $C_2(C_1 "_{\theta} C_2)$ if and only if (iff) a substitution θ so that $C_1 \theta \subseteq C_2$ exists (considering clauses as literal sets).

For example, the clause $C_2 = p(a, b) \leftarrow r(b, a)$ (i.e. p(a, b) := r(b, a) in the standard Prolog format) is subsumed by $C_1 = p(Y_1, Y_2) \leftarrow r(Y_2, Y_1)$ since we have $\{p(Y_1, Y_2), \neg r(Y_2, Y_1)\} \theta_1 \subseteq \{p(a, b), \neg r(b, a)\}$ with $\theta = \{Y_1/a, Y_2/b\}$.


Because of this hierarchical relationship between rules, the hypothesis space can be explored efficiently, for instance by moving from the most generic clause to the most specific one (\perp) . From a clause such as C_1 , it is possible to generate more specific clauses covering only subsets of the examples covered by C_1 . This process contributes to speed up score computation for clauses that are more specific than C_1 . Similarly, it is possible to avoid generating a clause that will not cover enough examples as soon as it appears that an ancestor clause does not cover enough examples itself.

However, θ -subsumption is not a perfect fit for our problem as it does not account for hierarchical relationships between MeSH main headings. Indeed, clause qualif(W₁,"genetics") :- in _article(A, W₁), in_article(A, W2), hierarchy(W2, "Frameshift Mutation") is not subsumed by qualif(W₁,"genetics") :- in_article(A, W₁), in_article(A, W₂), hierarchy(W₂,"Mutation") even though Mutation is an ancestor for Frameshift Mutation in the MeSH hierarchy. Figure 2 shows an excerpt of a lattice resulting from the organization of the search space with standard θ -subsumption. The very same problem appears since the clauses containing Carboxylic Acids, Organic Chemicals and Chemical and Drugs, are considered independantly although the main headings are related in the MeSH hierarchy. These hypotheses are thus evaluated independantly, and given the number of examples and possible hypotheses in the lattices, it results in very high computation times.

For this reason, we are introducing a new definition of subsumption based on work by Buntine [16] about *Generalized subsumption*:

Definition 2 A clause $C_1 \quad \theta_{hier}$ -subsumes a clause $C_2(C_1 "_{hier} C_2)$ with respect to background knowledge B iff there exist a substitution θ and a function f_D such that $f_D(C)\theta \subseteq D$, where f_D is such that $\forall l \in C$, B, $f_D(l) \mid = l$, with $f_D(\{l_1, l_2, ..., l_m\})$ meaning $\{f_D(l_1), f_D(l_2), ..., f_D(l_m)\}$.

Function f_D accounts for information contained in the background knowledge, i.e. hierarchical relationships between MeSH terms in our case. This subsumption, implemented by modifying ALEPH, is consistent with the notion of coverage. It is easy to show that, given our background knowledge, this subsumption induces a partial order between clauses and thus also structures \mathcal{E}_H as a lattice. Figure 3 shows the same excerpt as the one in Figure 2. Yet, with the use of the generalized subsumption, the lattice takes into account the relations described in the MeSH hierarchies. The lattice contains the same hypothe-



ses as the one structured by standard *A*-subsumption, but it is reorganized in a more hierarchical way. Thanks to the inheritance properties, it makes the computation of the score much more efficicent. This new subsumption is completely adapted to our context and allows us to efficiently infer rules from large sets of positive and negative examples (see "'Results"' section) while avoiding the computational pitfall of considering each of the 24,000 MeSH main headings independently. Note that, interestingly, this type of subsumption is in fact suitable for any rule inference problem involving structured knowledge as described in ontologies.

Baseline method


Since association rules discovery methods are not completely adequate for our data, we have devised a simple baseline method for results comparisons. The baseline consists of random main heading/subheading attachments based on the statistical distribution of MeSH pairs in MEDLINE. The probability *P* of a main heading/subheading pair was computed as the number of occurrences of the pair in MEDLINE divided by the total number of occurrences of the corresponding main heading in MEDLINE, whether alone or attached to one or more subheadings. Table 2 presents the complete distribution for the main heading *Irritable Mood* and an excerpt of the distribution for *Lung*.

Training and test corpora

ILP rules were induced using a training corpus comprising 100,000 citations randomly chosen from MEDLINE 2006. The statistical distribution of MeSH indexing terms used in the baseline method was derived from the 15,433,668 citations referenced in MEDLINE at the end of 2005 [17]. Finally, we also used a test corpus comprising 100,000 citations randomly chosen from MEDLINE 2006. Note that this corpus had no common citation with the training corpora mentioned above.

Assessment of rules in a production indexing environment In practice, as can be seen from the sample indexing rule

in the introduction section, stand-alone main headings are used as trigger terms for applying the rules. For English, MTI[1], a tool developed at NLM, is able to retrieve stand-alone main heading indexing recommendations. On the test corpus, note that MTI retrieves about 45% of the main headings selected by NLM indexers for MEDLINE. For this reason, we anticipate that theoretical performance of ILP rules assessed directly on MEDLINE citations will be higher than the practical performance obtained by applying the rules to sets of terms retrieved by MTI, i.e. in a real production automatic indexing environment. The index-



Excerpt of a search space structured by generalized subsumption.

ing rules inferred using ILP are assessed on the test corpus using MEDLINE indexing as a gold standard. ILP performance is then compared to that of manual rules produced by a domain expert and to the baseline described above.

For each method, (ILP, manual, baseline) only the pairs formed using a main heading recommended by MTI and also selected in MEDLINE are considered. The performance measures we used are precision, recall and balanced Fmeasure [18]. The significance of the differences in performance observed with the different methods was assessed with a pairwise T-test using an online analysis tool [19].

Table 2: MeSH subheading distr	ibution in MEDLINE
--------------------------------	--------------------

<i>Irritable Mood</i> 5 allowable qualifiers		<i>Lung</i> (excerpt) 26 allowable qualifiers		
subheading		subheading	Р	
no subheading	0.758	no subheading	0.047	
classification	0.008	classification	0	
drug effect	0.129	drug effect	0.082	
ethics	0	metabolism	0.117	
physiology	0.101	pathology	0.171	
radiation effect 0.004		radiation effect	0.011	

Possible improvements on ILP rules

Preliminary experiments with producing ILP rules suggested that improvement could be achieved in two ways: (1) by filtering out rules that showed a comparatively low precision on the training corpus when applied to main headings retrieved by MTI; and (2) by having an indexing expert review the rules to improve their readability and reduce possible bias due to the training corpus. We report results of both improvement methods below.

Results and discussion

Table 3 presents the theoretical performance for ILP rules (assessed on different MEDLINE citations than the ones used to infer the rules). In addition we also show the number of examples and the processing time on a desktop computer (Linux Intel Xeon 3 GHz).

Table 4 presents the performance on the test corpus for the ILP rules, compared to rules obtained manually (when available) and through the baseline method. We also show the performance obtained by ILP rules after filtering out rules that obtained a precision of less than 35% on the training corpus (ILP-filtered) and after review by a domain expert (ILP-reviewed). Here, the main headings triggering the application of rules were retrieved by MTI.

Subheading	E +	E -	Computing time	Precision (%)	Recall (%)	F-measure (%)
Administration & dosage	5,300	40,000	75 mn	41.4	53.0	46.5
Genetics	5,700	30,500	51 mn	50.4	59.4	54.5
Metabolism	4,500	21,000	37 mn	42.4	60.2	49.7
Pharmacology	5,000	22,000	45 mn	48.8	53.9	51.2
Physiology	5,200	34,000	46 mn	41.4	41.5	41.5

Table 3: Performance of ILP	rule inference on MEDLINE citations
	The mich chief on medeline creations

Table 5 presents the performance on the test corpus for MTT's subheading attachment module performing subheading attachment by combining four methods, including the use of post-processing rules. The other methods (dictionary method, MTI method and PubMed Related Citations) are detailed in [20]. Here, we compare the overall performance of the module using post-processing rules obtained manually, through ILP out-of-the-box and with a combination of manual and ILP rules, manual rules being used only when ILP rules were not available for a given subheading. Results for this last configuration are not shown because they were almost identical to those obtained with ILP. In table 4 and 5, the best performance for each subheading is bolded.

General performance of ILP rules

As expected, the use of MTI to produce main heading recommendations used as triggers for the rules results in comparable precision but significantly lower recall compared to the theoretical assessment (p = 0.001). In spite of this, the performance obtained by ILP rules is statistically superior to the baseline and shows the best F-measure (p = 0.001). The precision obtained by the manual rules, when they exist, is higher (p = 0.007), but they produce a recall inferior to ILP (p = 0.007) and even to the baseline method, although in this case the difference was not statistically significant. It is important to note that our results compare favorably with the consistency between human

Subheading	Method	No. rules	Precision (%)	Recall(%)	F-measure(%)
Administration & dosage	ILP	166	38	29	33
	Manual	I	54	I	I
	ILP-filtered	95	45	25	32
	ILP-reviewed	124	37	29	33
	Baseline	-	26	9	13
Genetics	ILP	200	55	39	46
	Manual	226	65	28	39
	ILP-filtered	181	55	39	46
	ILP-reviewed	172	55	39	46
	Baseline	-	33	10	15
Metabolism	ILP	134	49	38	43
	Manual	61	58	20	30
	ILP-filtered	123	49	38	43
	ILP-reviewed	73	49	38	43
	Baseline	-	37	12	18
Pharmacology	ILP	217	47	28	35
	Manual	7	67	3	5
	ILP-filtered	183	48	28	35
	ILP-reviewed	74	47	28	35
	Baseline	-	28	12	17
Physiology	ILP	70	46	24	32
	Manual	0	-	-	-
	ILP-filtered	64	46	24	32
	ILP-reviewed	70	46	24	32
	Baseline	-	28	10	15

Subheading	PP rules	Precision (%)	Recall(%)	F-measure(%)
Administration & dosage	ILP	48	27	35
-	Manual	48	17	25
Genetics	ILP	55	39	46
	Manual	56	38	45
Metabolism	ILP	51	47	49
	Manual	56	33	42
Pharmacology	ILP	50	38	43
	Manual	55	24	33
Physiology	ILP	45	32	37
,	Manual	44	23	30
MeSH descriptors (83 Subheadings)	ILP	49	26	34
	Manual	50	23	32

Table 5: Performance of MTI's subheading attachment module using Manual vs. ILP post-processing rules

indexers assigning MeSH pairs to articles referenced in MEDLINE, which was reported to be 33.8% [21].

ILP vs. manual rules

A detailed analysis of the rules obtained with ILP shows that, while some rules are easily understood by indexers: *If* a main heading from the "Neoplasms" subtree and a "Chromosomes" term are recommended for indexing, *then* the pair " [Chromosomes]/genetics" should also be recommended., others are not: *If* a main heading from the "Persons" subtree and a "Food and Beverages" term are recommended for indexing, *then* the pair " [Food and Beverages]/administration and dosage" should also be recommended.

This is due to some unexpected regularities which do not seem to be relevant but nonetheless achieved good results on the training data used to infer rules.

Furthermore, we noticed that while most rules typically contain a "trigger term" (e.g. *Persons* in our previous example) and a "target term" (e.g. *Food and Beverages* above), in some rules the target term can also serve as the trigger term. That is the case for example in *If* a main heading from the "Chemicals and Drugs" tree and an "Enzymes and Coenzymes" term are recommended for indexing, *then* the pair " [Enzymes and Coenzymes]/metabolism" should also be recommended., where *Enzymes and Coenzymes* is a descendant of *Chemicals and Drugs*. These rules may be explained by looking at the distribution of subheadings for the terms involved. For example, for *DNA Ligases*, a descendant of *Enzymes and Coenzymes* with 32 allowable qualifiers, *P(metabolism)* = 0.45. Some changes

in the ILP inferring process are planned in order to prevent the production of such rules.

Rule filtering vs. manual review

The filtering process had the biggest impact on *administration and dosage* where 71 rules out of 166 had a precision lower than 35% on the training corpus. As a result, the precision on the test corpus improved by 7 points with only a 3 point decrease in recall and no impact on the Fmeasure. For the other subheadings studied here, filtering had little impact but generally tended to improve precision while F-measure stayed the same, which was our goal. On the other hand, the manual review of the rules seemed to degrade the performance obtained with the original ILP. Furthermore, the manual review of the rules is more costly than filtering, which can be done automatically. However, the differences in performance between ILP, ILP-reviewed and ILP-filtered were not statistically significant.

Integrating ILP rules into a subheading attachment feature for MTI

Considerations for rule integration

One issue with the integration of ILP rules into MTI's subheading attachment feature is the fusion of ILP rule sets with the manual rule sets when they exist. Manual rules yield very good precision; therefore we may want ILP rules to *supplement* the manual sets instead of replacing them. However, while ILP rules and manual rules are generally distinct (only 6 rules were strictly identical), some cases of partial overlap were found. For example, the manual rule: *If* a main heading from the "Drug Resistance" subtree and a "Chemical Actions and Uses" term are recommended for indexing, *then* the pair "[Chemical Actions and Uses]/ pharmacology" should also be recommended. and the ILP rule: *If* a main heading from the "Chemical and Pharmacologic Phenomena" subtree and a "Anti-Infective Agents" term are recommended for indexing, *then* the pair "[Anti-Infective Agents]/pharmacology" should also be recommended. are partially overlapping as *Anti-Infective Agents* is a descendant of *Chemical Actions and Uses* while *Chemical and Pharmacologic Phenomena* is an ancestor of *Drug Resistance*. We need to decide how these cases should be handled (i.e., keep both rules in final set or select manual or ILP rule).

Performance of rules in an indexing system

As shown in Table 5, the performance observed on the rules alone have a similar impact on the overall performance of MTI's subheading attachment module. Recall is higher (p = 0.008) when ILP rules are used (*vs.* manual rules), while there is no statistical difference in precision. We also compared these results to the performance obtained when all rules (manual and ILP) are applied, and there was no statistical difference with the use of ILP rules only. Therefore, in the final system, for each subheading, it seems sound to use whichever set of rules (Manual or ILP) yields the best results as this strategy will ensure the best performance is obtained with minimal integration effort.

Conclusion

We have shown that it is possible to exhibit and exploit the regularities in the descriptions of biomedical articles indexed for MEDLINE to make automatic recommendations for the attachment of subheadings to main headings in new articles to be processed. Subheading attachment has been performed manually until now and the automation of this complex and time-consuming task has not received much attention in the past. However, the use of ILP provided us with a suitable representation thanks to the use of a form of subsumption specifically tailored to the MEDLINE context. This particular feature enabled the processing of large amounts of data to produce relevant indexing rules with reasonable computation times. This approach may also be applied to rule discovery in other large-scale datasets involving structured data (e.g., ontologies).

In the ILP experiments presented in this paper, the score *Sc* used to choose the best hypotheses in the search spaces was such that it gave the same weight to precision and recall. Different score functions are currently under study in order to favor more precise rules (yet keeping good F-measure); thus, it would make the post-filtering step superfluous. From a practical point of view, further work will be necessary in order to obtain rules for all 83 MeSH subheadings. In any case, we anticipate that the subhead-

ing attachment rule sets produced will be integrated into MTI's subheading attachment module.

Competing interests

The authors declare that they have no competing interests.

Authors' contributions

AN designed the study, prepared the data, performed the evaluation of the rules and of the subheading attachment module including the rules, and prepared the first draft of this manuscript. SES produced the manual rules, analyzed and reviewed the ILP rules and resulting indexing recommendations. VC implemented the ILP-based inference of the rules using the generalized subsumption operator, generated the rules and provided theoretical results on the performances and efficiency of the inference process. All authors read and approved the final manuscript.

Acknowledgements

This study was supported in part by the Intramural Research Programs of the National Institutes of Health, National Library of Medicine (NLM). A. Névéol was supported by an appointment to the NLM Research Participation Program administered by ORISE through an inter-agency agreement between the U.S. Department of Energy and NLM. The authors would like to thank L. Tanabe for preliminary discussions on ILP, AR. Aronson and JG. Mork for their comments and feedback on this work and BT. McInnes for her help with the statistical analysis of the results.

This article has been published as part of *BMC Bioinformatics* Volume 9 Supplement 11, 2008: Proceedings of the BioNLP 08 ACL Workshop: Themes in biomedical language processing. The full contents of the supplement are available online at http://www.biomedcentral.com/1471-2105/9?issue=S11

References

- Aronson AR, Mork JG, Gay CW, Humphrey SM, Rogers WJ: The NLM Indexing Initiative's Medical Text Indexer. Stud Health Technol Inform 2004, 107(Pt 1):268-272.
- Névéol Á, Shooshan SÈ, Rindflesh TC, Aronson AR: Multiple approaches to fine-grained indexing of the biomedical literature. Pac Symp Biocomput 2007:292-303.
- Névéol A, Rogozan A, Darmoni SJ: Automatic indexing of online health resources for a French quality controlled gateway. Information Processing and Management 2006, 42(3):695-709.
- Lin J, Wilbur WJ: PubMed related articles: a probabilistic topicbased model for content similarity. BMC Bioinformatics 2007, 8:423.
- Rak R, Kurgan LA, Reformat M: Multilabel associative classification categorization of MEDLINE articles into MeSH keywords. *IEEE Eng Med Biol Mag* 2007, 2(26):47-55.
 Sohn S, Kim W, Comeau DC, Wilbur WJ: Optimal Training Sets
- Sohn S, Kim W, Comeau DC, Wilbur WJ: Optimal Training Sets for bayesian prediction of MeSH assignment. J Am Med Inform Assoc 2008, 15(4):546-53.
- Markó K, Daumke P, Schulz S, Hahn U: Cross-language MeSH indexing using morpho-semantic normalization. AMIA Annu Symp Proc 2003:425-429.
- Soualmia LF: Étude et évaluation d'approches multiples de projection de requêtes pour une recherche d'information intelligente. Application au domaine de la Santé sur l'Internet. In PhD thesis INSA de Rouen, France; 2004.
- 9. Claveau V, Sébillot P, Fabre C, Bouillon P: Learning Semantic Lexicons from a Part-of-Speech and Semantically Tagged Corpus using Inductive Logic Programming. Journal of Machine Learning Research (JMLR), special issue on ILP 2003, 4:493-525.
- Ozdowska S, Claveau V: Inférence de règles de propagation syntaxique pour l'alignement de mots. TAL (Traitement Automatique des Langues) 2006, 47:167-186.

- 11. Cussens J, Džeroski S, (Eds): Learning Language in Logic 2000 [http:// www.springer.com/computer/artificial/book/978-3-540-41145-1]. Lecture Notes in Artificial Intelligence, Springer Verlag
- 12. Muggleton S, Raedt LD: Inductive Logic Programming: Theory and Methods. Journal of Logic Programming 1994, 19/20:629-679 [http://citeseerx.ist.psu.edu/viewdoc/summary?doi=10.1.1.36.8300]. 13. Srinivasan A: The ALEPH manual Machine Learning at the Computing Lab-
- oratory, Oxford University; 2001.
- 14. Agrawal R, Imielinski T, Swami A: Mining Association Rules Between Sets of Items in Large Databases. Proceedings of the SIGMOD Conference, Washington, DC, USA 1993:207-216.
- 15. Plotkin GD: A Note on Inductive Generalization. In Machine Intelligence Volume 5. Edited by: Meltzer B, Michie D. Edinburgh: Edinburgh University Press; 1970:153-163.
- 16. Buntine WL: Generalized Subsumption and its Application to Induction and Redundancy. Artificial Intelligence 1988, 36:375-399.
- 17. MEDLINE Baseline Repository [http://mbr.nlm.nih.gov/Refer ence/MEDLINE_Baseline_Repository_Detail.pdf]
- 18. Manning CD, Shütze H: Foundations of Statistical Natural Language Processing Cambridge, Massachusetts: MIT Press; 2000. Uitenbroek DG: Simple Interractive Statistical Analysis.
- 19. [http://www.quantitativeskills.com/sisa/statistics/pairwise.htm]
- Névéol A, Shooshan SE, Mork JG, Aronson AR: Fine-Grained 20. Indexing of the Biomedical Literature: MeSH Subheading Attachment for a MEDLINE Indexing Tool. AMIA Annu Symp Proc 2007:553-557.
- 21. Funk ME, Reid CA: Indexing consistency in MEDLINE. Bull Med Libr Assoc 1983, 71(2):176-183.

