


What I need to know about Physical Activity and Diabetes



U.S. Department
of Health and
Human Services

NATIONAL INSTITUTES OF HEALTH

NIDDK NATIONAL INSTITUTE OF
DIABETES AND DIGESTIVE
AND KIDNEY DISEASES

National Diabetes Information Clearinghouse

What I need to know about Physical Activity and Diabetes



U.S. Department
of Health and
Human Services

NATIONAL INSTITUTES OF HEALTH

NIDDK | NATIONAL INSTITUTE OF
DIABETES AND DIGESTIVE
AND KIDNEY DISEASES

National Diabetes Information Clearinghouse

Contents

How can I take care of my diabetes?	1
What can a physically active lifestyle do for me?	1
What kinds of physical activity can help me?	3
Can I exercise any time I want?	8
Are there any types of physical activity I shouldn't do?	9
Can physical activity cause low blood glucose?	10
What should I do before I start a physical activity program?	13
What can I do to make sure I stay active?	14
For More Information	15
Acknowledgments	16

How can I take care of my diabetes?

Diabetes means your blood glucose, also called blood sugar, is too high. Your body uses glucose for energy. But having too much glucose in your blood can hurt you.

When you take care of your diabetes, you'll feel better. You'll reduce your risk for problems with your kidneys, eyes, nerves, feet and legs, and teeth. You'll also lower your risk for a heart attack or a stroke. You can take care of your diabetes by

- being physically active
- following a healthy meal plan
- taking medicines, if prescribed by your doctor

What can a physically active lifestyle do for me?

Research has shown that physical activity can

- lower your blood glucose and your blood pressure
- lower your bad cholesterol and raise your good cholesterol
- improve your body's ability to use insulin
- lower your risk for heart disease and stroke
- keep your heart and bones strong
- keep your joints flexible

- lower your risk of falling
- help you lose weight
- reduce your body fat
- give you more energy
- reduce your stress levels

Physical activity also plays an important part in preventing type 2 diabetes. A major Government study, the Diabetes Prevention Program (DPP), showed that modest weight loss of 5 to 7 percent—for example, 10 to 15 pounds for a 200-pound person—can delay and possibly prevent type 2 diabetes. People in the study used diet and exercise to lose weight.

For more information about the study, read the DPP fact sheet online. Go to www.diabetes.niddk.nih.gov/intro and click on *Diabetes Prevention Program* under “Prediabetes.” Or call the National Diabetes Information Clearinghouse (NDIC) at 1-800-860-8747 to request a printed copy.

What kinds of physical activity can help me?

Four kinds of activity can help. You can

- be extra active every day
- do aerobic exercise
- do strength training
- stretch

Be Extra Active Every Day

Being extra active can increase the number of calories you burn. Try these ways to be extra active, or think of other things you can do.

- Walk around while you talk on the phone.
- Play with the kids.
- Take the dog for a walk.
- Get up to change the TV channel instead of using the remote control.
- Work in the garden or rake leaves.
- Clean the house.
- Wash the car.
- Stretch out your chores. For example, make two trips to take the laundry downstairs instead of one.

- Park at the far end of the shopping center parking lot and walk to the store.
- At the grocery store, walk down every aisle.
- At work, walk over to see a co-worker instead of calling or emailing.
- Take the stairs instead of the elevator.
- Stretch or walk around instead of taking a coffee break and eating.
- During your lunch break, walk to the post office or do other errands.
- Other things I can do: _____



Do Aerobic Exercise

Aerobic exercise is activity that requires the use of large muscles and makes your heart beat faster. You will also breathe harder during aerobic exercise. Doing aerobic exercise for 30 minutes a day at least 5 days a week provides many benefits. You can even split up those 30 minutes into several parts. For example, you can take three brisk 10-minute walks, one after each meal.

If you haven't exercised lately, see your doctor first to make sure it's OK for you to increase your level of physical activity. Talk with your doctor about how to warm up and stretch before you exercise and how to cool down after you exercise. Then start slowly with 5 to 10 minutes a day. Add a little more time each week, aiming for at least 150 minutes per week. Try

- walking briskly
- hiking
- climbing stairs
- swimming or taking a water-aerobics class
- dancing
- riding a bicycle outdoors or a stationary bicycle indoors
- taking an aerobics class
- playing basketball, volleyball, or other sports
- in-line skating, ice skating, or skate boarding
- playing tennis
- cross-country skiing
- other things I can do: _____



The National Institute on Aging offers a free booklet, *Exercise & Physical Activity: Your Everyday Guide from the National Institute on Aging*. To read it online, go to www.nia.nih.gov/HealthInformation/Publications and click on “Healthy Aging.” Or call 1-800-222-2225 to request a printed copy.

Do Strength Training

Doing exercises with hand weights, elastic bands, or weight machines three times a week builds muscle. When you have more muscle and less fat, you’ll burn more calories because muscle burns more calories



than fat, even between exercise sessions. Strength training can help make daily chores easier, improving your balance and coordination, as well as your bones' health. You can do strength training at home, at a fitness center, or in a class. Your health care team can tell you more about strength training and what kind is best for you.

Stretch

Stretching increases your flexibility, lowers stress, and helps prevent muscle soreness after other types of exercise. Your health care team can tell you what kind of stretching is best for you.

The Weight-control Information Network, a service of the National Institute of Diabetes and Digestive and Kidney Diseases, has information about exercise. Call 1-877-946-4627, toll-free, to request free copies of the following publications, or read them online.

- *Active at Any Size*
www.win.niddk.nih.gov/publications/active.htm
- *Walking: A Step in the Right Direction*
www.win.niddk.nih.gov/publications/walking.htm
- *Physical Activity and Weight Control*
www.win.niddk.nih.gov/publications/physical.htm

Can I exercise any time I want?

Your health care team can help you decide the best time of day for you to exercise. Together, you and your team will consider your daily schedule, your meal plan, and your diabetes medicines.


If you have type 1 diabetes, avoid strenuous exercise when you have ketones in your blood or urine. Ketones are chemicals your body might make when your blood glucose level is too high and your insulin level is too low. Too many ketones can make you sick. If you exercise when you have ketones in your blood or urine, your blood glucose level may go even higher.

If you have type 2 diabetes and your blood glucose is high but you don't have ketones, light or moderate exercise will probably lower your blood glucose. Ask your health care team whether you should exercise when your blood glucose is high.

Are there any types of physical activity I shouldn't do?

If you have diabetes complications, some kinds of exercise can make your problems worse. For example, activities that increase the pressure in the blood vessels of your eyes, such as lifting heavy weights, can make diabetic eye problems worse. If nerve damage from diabetes has made your feet numb, your doctor may suggest that you try swimming instead of walking for aerobic exercise.

When you have numb feet, you might not feel pain in your feet. Sores or blisters might get worse because you don't notice them. Without proper care, minor foot problems can turn into serious conditions, sometimes leading to amputation. Make sure you exercise in cotton socks and comfortable, well-fitting shoes designed for the activity you are doing. After you exercise, check your feet for cuts, sores, bumps, or redness. Call your doctor if any foot problems develop.



Can physical activity cause low blood glucose?

Physical activity can cause low blood glucose, also called hypoglycemia, in people who take insulin or certain types of diabetes medicines. Ask your health care team whether your diabetes medicines can cause low blood glucose.

Low blood glucose can happen while you exercise, right afterward, or even up to a day later. It can make you feel shaky, weak, confused, grumpy, hungry, or tired. You may sweat a lot or get a headache. If your blood glucose drops too low, you could pass out or have a seizure.

However, you should still be physically active. These steps can help you be prepared for low blood glucose:

Before Exercise

- Ask your health care team whether you should check your blood glucose level before exercising.
- If you take diabetes medicines that can cause low blood glucose, ask your health care team whether you should
 - change the amount you take before you exercise
 - have a snack if your blood glucose level is below 100

During Exercise

- Wear your medical identification (ID) bracelet or necklace or carry your ID in your pocket.
- Always carry food or glucose tablets so you'll be ready to treat low blood glucose.
- If you'll be exercising for more than an hour, check your blood glucose at regular intervals. You may need snacks before you finish.

After Exercise

- Check to see how exercise affected your blood glucose level.



Treating Low Blood Glucose

If your blood glucose is below 70, have **one** of the following right away:

- 3 or 4 glucose tablets
- 1 serving of glucose gel—the amount equal to 15 grams of carbohydrate
- 1/2 cup (4 ounces) of any fruit juice
- 1/2 cup (4 ounces) of a regular—**not diet**—soft drink
- 1 cup (8 ounces) of milk
- 5 or 6 pieces of hard candy
- 1 tablespoon of sugar or honey

After 15 minutes, check your blood glucose again. If it's still too low, have another serving. Repeat until your blood glucose is 70 or higher. If it will be an hour or more before your next meal, have a snack as well.

What should I do before I start a physical activity program?

Check with your doctor. Always talk with your doctor before you start a new physical activity program. Ask about your medicines—prescription and over-the-counter—and whether you should change the amount you take before you exercise. If you have heart disease, kidney disease, eye problems, or foot problems, ask which types of physical activity are safe for you.

Decide exactly what you'll do and set some goals.

Choose

- the type of physical activity you want to do
- the clothes and items you'll need to get ready
- the days and times you'll add activity
- the length of each session
- your plan for warming up, stretching, and cooling down for each session
- a backup plan, such as where you'll walk if the weather is bad
- your measures of progress

Find an exercise buddy. Many people find they are more likely to do something active if a friend joins them. If you and a friend plan to walk together, for example, you may be more likely to do it.

Keep track of your physical activity. Write down when you exercise and for how long in your blood glucose record book. You'll be able to track your progress and see how physical activity affects your blood glucose.

Decide how you'll reward yourself. Do something nice for yourself when you reach your activity goals. For example, treat yourself to a movie or buy a new plant for the garden.

What can I do to make sure I stay active?

One of the keys to staying on track is finding some activities you like to do. If you keep finding excuses not to exercise, think about why. Are your goals realistic? Do you need a change in activity? Would another time be more convenient? Keep trying until you find a routine that works for you. Once you make physical activity a habit, you'll wonder how you lived without it.

For More Information

To find diabetes teachers—nurses, dietitians, and other health professionals—near you, call the American Association of Diabetes Educators toll-free at 1-800-TEAMUP4 (1-800-832-6874). Or visit www.diabeteseducator.org and click on “Find a Diabetes Educator.”

For additional information about diabetes, contact

American Diabetes Association

1701 North Beauregard Street
Alexandria, VA 22311

Phone: 1-800-DIABETES (1-800-342-2383)
or 703-549-1500

Fax: 703-549-6995

Email: AskADA@diabetes.org

Internet: www.diabetes.org

Juvenile Diabetes Research Foundation International

26 Broadway, 14th Floor
New York, NY 10004

Phone: 1-800-533-CURE (1-800-533-2873)

Fax: 212-785-9595

Email: info@jdrf.org

Internet: www.jdrf.org

Acknowledgments

Publications produced by the Clearinghouse are carefully reviewed by both NIDDK scientists and outside experts. The NDIC would like to thank the following individuals for assisting with the scientific and editorial review of the original version of this publication:

Andrea Kriska, Ph.D.

University of Pittsburgh, Department of Epidemiology

David G. Marrero, Ph.D.

Indiana University School of Medicine, Division of Endocrinology

Susan Yanovski, M.D.

NIDDK, Division of Digestive Diseases and Nutrition, Obesity and Eating Disorders Program

Thank you also to Sally A. Stacey, R.N., C.D.E., at the Regional Diabetes Center, Home Hospital, Lafayette, IN, for facilitating field-testing of the original version of this publication.

National Diabetes Information Clearinghouse

1 Information Way
Bethesda, MD 20892-3560
Phone: 1-800-860-8747
TTY: 1-866-569-1162
Fax: 703-738-4929
Email: ndic@info.niddk.nih.gov
Internet: www.diabetes.niddk.nih.gov

The National Diabetes Information Clearinghouse (NDIC) is a service of the National Institute of Diabetes and Digestive and Kidney Diseases (NIDDK). The NIDDK is part of the National Institutes of Health of the U.S. Department of Health and Human Services. Established in 1978, the Clearinghouse provides information about diabetes to people with diabetes and to their families, health care professionals, and the public. The NDIC answers inquiries, develops and distributes publications, and works closely with professional and patient organizations and Government agencies to coordinate resources about diabetes.

This publication is not copyrighted. The Clearinghouse encourages users of this publication to duplicate and distribute as many copies as desired.

This publication is available at www.diabetes.niddk.nih.gov.

This publication may contain information about medications. When prepared, this publication included the most current information available. For updates or for questions about any medications, contact the U.S. Food and Drug Administration toll-free at 1-888-INFO-FDA (1-888-463-6332) or visit www.fda.gov. Consult your health care provider for more information.



U.S. DEPARTMENT OF HEALTH
AND HUMAN SERVICES
National Institutes of Health

NIDDK | NATIONAL INSTITUTE OF
DIABETES AND DIGESTIVE
AND KIDNEY DISEASES

NIH Publication No. 08-5180
March 2008



The NIDDK prints on recycled paper with bio-based ink.