Economic Impacts Associated with the U.S. West Coast Critical Habitat Designation for the Leatherback Sea Turtle

January 2012

Prepared by: NOAA's National Marine Fisheries Service

Primary Authors: NMFS Southwest Regional Office NMFS Southwest Fisheries Science Center

		BLES URES	
EXE	CUTIVE	E SUMMARY	ES-1
<u>Introc</u>	luction		1
SECT	FION 1:	FRAMEWORK FOR THE ANALYSIS	1
<u>1.1</u>	Ir	ntroduction	1
1.2	<u>G</u>	eneral Framework for the Economic Analysis	1
	1.2.1	Benefit-Cost Analysis and Cost-Effectiveness Analysis	1
1.3	<u>I</u> 1	npacts that are the Focus of this Analysis	3
	1.3.1	Baseline for the Economic Analysis	4
	1.3.2	Types of Economic Impacts of Critical Habitat Designation	5
1.4	<u>A</u>	pproach to Analysis	10
	1.4.1	Define Geographic Study Area	10
	1.4.2	Identify PCEs & Potentially Affected Economic Activities	13
	1.4.3	Estimate the Baseline Level of Protection Afforded Leatherbacks by Area and Activ	vity
		Туре	14
	1.4.4	Establish Existing/Expected Level of Economic Activity Likely to be Affected by	
		Critical Habitat	17
	1.4.5	Estimate Potential Economic Impacts by Area	18
	1.4.6	Calculate Total Impacts by Area	19
	1.4.7	Analytical Time Frame	19
<u>1.5</u>	<u>R</u>	eport Organization	19
SECT	FION 2:	ECONOMIC IMPACTS BY ACTIVITY	21
2.1	E	conomic Impacts of Critical Habitat Designation on National Pollutant Discharge &	
	E	limination System (NPDES) Facilities	21
	2.1.1	Description of Threat	21
	2.1.2	Regulatory Environment & Extent of Activity	21
	2.1.3	Impacts of Critical Habitat Designation on NPDES Permitted Facilities	23
	2.1.4	Summary of Economic Impacts to NPDES Facilities by Area	
2.2	E	conomic Impacts of Critical Habitat Designation on Agricultural Pesticide Application.	
	2.2.1	Description of Threat	25
	2.2.2	Regulatory Environment & Extent of Activity	25
	2.2.3	Impacts of Critical Habitat Designation on Agricultural Pesticide Application	25
	2.2.4	Summary of Economic Impacts to Agricultural Pesticide Application by Area	27
<u>2.3</u>	E	conomic Impacts of Critical Habitat Designation on Oil Spill Response	28
	2.3.1	Description of Threat	28
	2.3.2	Regulatory Environment & Extent of Activity	28
	2.3.3	Impacts of Critical Habitat Designation on Oil Spill response	34

TABLE OF CONTENTS

	2.3.4	Summary of Economic Impacts to Oil Spill Response Activities by Area	34
<u>2.4</u>	•	Economic Impacts of Critical Habitat on Power Plants	37
	2.4.1	Description of Threat	37
	2.4.2	Regulatory Environment and Extent of Activity	37
	2.4.3	Impacts of Critical Habitat Designation on Power Plants	41
	2.4.4	Summary of Economic Impacts to Power Plants by Area	42
2.5	•	Economic Impacts of Critical Habitat Designation on Desalination Plants	42
	2.5.1	Description of Threat	42
	2.5.2	Regulatory Environment & Extent of Activity	43
	2.5.3	Impacts of Critical Habitat Designation on Desalination Plants	45
	2.5.4	Summary of Economic Impacts to Desalination Plants by Area	47
2.6	•	Economic Impacts of Critical Habitat Designation on Tidal, Wave, and Wind Energy	
	•	Projects	47
	2.6.1	Description of Threat	47
	2.6.2	Regulatory Environment & Extent of Activity	48
	2.6.3	Impacts of Critical Habitat Designation on Tidal, Wave, and Wind Energy Project	s50
	2.6.4	Summary of Economic Impacts to Tidal, Wave, and Wind Energy Projects by Are	a51
2.7	•	Economic Impacts of Critical Habitat Designation on Liquefied Natural Gas Projects	52
	2.7.1	Description of Threat	52
	2.7.2	Regulatory Environment & Extent of Activity	52
	2.7.3	Impacts of Critical Habitat Designation on Liquefied Natural Gas Projects	55
	2.7.4	Summary of Economic Impacts to Liquefied Natural Gas Projects by Area	56
2.8	•	Economic Impacts of Critical Habitat Designation on Aquaculture	56
SEC	TION 3	: SUMMARY OF RESULTS	57
REF	ERENC	ES	63
		A: NON-COST SUMMARY INFORMATION	
APP	ENDIX	B: LAWS AND REGULATIONS THAT MAY PROVIDE BASELINE PROTECTIO	Ν
		FOR LEATHERBACK SEA TURTLES	B-1
APP	ENDIX	C: INCREMENTAL SCORE SENSITIVITY ANALYSIS	C-1
APP	ENDIX	D: DISCOUNT RATE SENSITIVITY ANALYSIS	D-1
APP	ENDIX	E: FINAL REGULATORY FLEXIBILITY ANALYSIS	E-1
APP	ENDIX	F: ENERGY IMPACTS ANALYSIS	F-1

LIST OF TABLES

Table ES-1:	Summary of Annualized Impacts by AreaE	S-2
Table 1.3-1:	Example Range of Administrative Consultation Costs)	7
Table 1.4-1:	Estimated Baseline Level of Protection Error! Bookmark not defin	ned.
Table 1.4-2:	Incremental Scores, Baseline Protection and Associated Costs Error! Bookmark	not
defined.		
Table 2.1-1:	NPDES Permits	22
Table 2.2-1:	Estimate of Acres under Farming in Areas Potentially Affected	27
Table 2.2-2:	Estimated per Acre Impacts by Area	27
Table 2.3-1:	U.S. National Oil Spill Data	31
Table 2.3-2:	Summary of Economic Impacts from Oil Spill Cleanup by Area	36
Table 2.5-1:	Number of Desalination Plants in California Affected Areas	44
Table 2.5-2:	Estimated Costs of Alternative Method of Brine Disposal	47
Table 2.6-1:	Issued and Pending Preliminary Permits Issued by FERC for Tidal and Wave	
	Energy Projects	49
	Environmental Measures for Example Wave Energy Project	51
Table 2.6-3:	Summary of Economic Impacts to Tidal, Wave, and Wind Energy Projects by	
	Area	
	LNG Terminals by Area	55
Table 3-1:	Summary of Potential Threats within Areas Considered for Leatherback Critical	
	Habitat Designation*	
Table 3-2:	Activities Count*	58
Table 3-4:	Incremental Scores	
	Total Impacts (Activities with Quantitative Costs)	
Table 3-5b:	Total Impacts (Activities with Qualitative Discussion)	
Table A-1:	Summary of Activities: Threat, Section 7 Nexus & Possible Modifications	
	Summary of Annualized Impacts by Area*, ranked from highest to lowest	
Table C-2:	Summary of Economic Impacts to NPDES Facilities by Area	
Table C-4:	Summary of Economic Impacts of Desalination Projects by Area	3
Table C-5:	Summary of Economic Impacts to Tidal, Wave, and Wind* Energy Projects by	
	Area	3
Table E-1:	Major Relevant Activities and a Description of the Industry Sectors Engaged in those	
	Activities	
Table E-2:	Socioeconomic profile of counties bordering potential leatherback critical habitat	5
Table E-3a:	Estimated Number of Regulated Entities that are Small, with Employee Constraints	
	(by area, county, and activity type)	7
Table E-3b:	Estimated Number of Regulated Entities that are Small, with Revenue Constraints	_
	(by area, county, and activity type)	8
Table E-3c:	Estimated Number of Regulated Entities that are Small, with Capacity Constraints	-
	(by area, county, and activity type)	
Table E-4:	Estimated Number of Regulated Entities Classified as Small (by area and activity)	
Table E-5:	Percentage of Businesses that are Classified as Small (by area and activity type)	
Table E-6:	Estimated Annualized Impacts per Small Entity by area and activity type	12

Table F-1:	Summary of Capacity of Power Plants	. 2
	Summary of Capacity at Proposed Tidal, Wave, and Wind Energy Projects	
Table F-3:	Summary of Economic Impacts to LNG Projects	.5

LIST OF FIGURES

Final Leatherback Critical Habitat Areas	
Washington volume of oil spilled (gallons)	
Vessel incident rate and vessel inspections from 1998-2006	
Vessel incident rate from 1998-2006 for all Washington waters	
Volume of California oil spills (1990-1999)	
Proposed Desalination Plants in California (2006)	45
Proposed North American LNG Import Terminals	53
Potential North American LNG Import Terminals	60
	Final Leatherback Critical Habitat Areas Washington volume of oil spilled (gallons) Vessel incident rate and vessel inspections from 1998-2006 Vessel incident rate from 1998-2006 for all Washington waters Volume of California oil spills (1990-1999) Proposed Desalination Plants in California (2006) Proposed North American LNG Import Terminals Potential North American LNG Import Terminals

EXECUTIVE SUMMARY

Introduction

The purpose of this report is to identify and analyze the potential economic impacts associated with the designation of critical habitat for the leatherback sea turtle (hereafter, "leatherback") under the Endangered Species Act (ESA). The analysis examines the potential impacts of restricting or modifying specific water and land uses to avoid adverse modification or destruction of leatherback critical habitat.

Approach

This analysis examines the state of the world with and without the designation of critical habitat for leatherbacks. The "without critical habitat" scenario represents the baseline for the analysis, considering habitat protections already afforded leatherbacks under its Federal listing and under other Federal, State, and local regulations, including protections afforded leatherbacks from other listed species, such as green sturgeon, West Coast salmon and steelhead, delta smelt, and marine mammal species, and their designated critical habitat. The "with critical habitat" scenario attempts to describe the incremental impacts associated specifically with the designation of critical habitat for leatherbacks. This analysis does provide an overview of costs that may be considered coextensive with the listing of leatherbacks and other baseline protections. The focus of the analysis, however, is determining the incremental costs, attributable to critical habitat designation of leatherbacks.

To quantify the economic impacts of modifications to water and land uses that result from critical habitat designation, the analysis employs the following five steps:

- Define the geographic area for the analysis; identify physical and biological features and the primary constituent elements (hereafter "PCEs"); and then identify the specific areas (i.e., areas that contain the PCEs) to be analyzed for purposes of this designation. The biological report to designate leatherback critical habitat analyzes how each of three identified specific areas meets the definition of critical habitat set forth in section 3 of the ESA.
- Identify economic activities that may have an impact on the PCEs.
- Estimate the baseline level of protection afforded leatherback critical habitat by area and activity type.
- For each economic activity, establish the existing and expected level of economic activity that may be affected by leatherback critical habitat in each area.
- Estimate potential economic impacts of leatherback critical habitat conservation by economic activity type and sum these impacts by area.

These steps are described in greater detail in Section 1 of this report.

Results

Seven categories of economic activities were identified as being potentially affected by the designation of leatherback critical habitat. Because a large degree of uncertainty exists with regard to future actions likely to be undertaken specifically for the conservation of leatherbacks and their habitat as a result of these identified activities, this analysis presents a range of possible impacts. This range is based on lowend and high-end impact scenarios developed for five activities: National Pollutant Discharge Elimination System (NPDES) facilities, desalination plants, and tidal & wave energy projects. These scenarios are discussed further in Section 2. The remaining activity categories for which data limitations

precluded a quantitative assessment of economic effects, including power plants, wind energy, oil spill response, agricultural pesticide application, and liquefied natural gas terminals.¹

The annualized impacts by area are presented below in table ES-1 for both low, mid, and high scenarios. In the low-end scenario, estimated annualized impacts by area range from \$126,000 to \$1.1 million. In the high-end scenario, estimated annualized impacts by area vary from \$2.0 million to \$23.0 million. Area 1 is estimated to incur the highest impacts.

	Annualize	d Impacts		A stinition with only a qualitating analysis (NOT	
Area	Low	Mid	High	Activities with only a qualitative analysis (NOT included in the estimated costs)	
1	\$94,000	\$4,125,000	\$8,157,000	Power plants, oil spill response, agricultural pesticides	
2	\$16,000	\$238,000	\$460,000	Wind energy, LNG and oil spill response, agricultural pesticides	
7	\$78,000	\$276,000	\$475,000	Power plants, oil spill response, agricultural pesticides	
Total	\$188,000	\$4,639,000	\$9,092,000	Power plants, wind energy, LNG and oil spill response, agricultural pesticides	

Table ES-1: Summary of Annualized Impacts by Area*

* Note: These costs are reported in annual terms, Section 2 of the report present results of the analysis in more detail (refer to Section 3 for present discounted values). NMFS received numerous comments on the area boundaries and PCE's. Based on the comments received, the CHRT reevaluated the specific areas identified in the proposed rule. Several boundary adjustments were made, including adjusting the boundary between Areas 2 and 3, moving the offshore boundary of Area 7 to the 3000 meter isobath, and creating a 9th area in the southern portion of area 7. Areas 3, 4, 5, 6, 8 and 9 were also found to no longer meet the definition of critical habitat following a revision of the PCEs.

¹ Note that while aquaculture was previously included in our analysis, with the removal of the passage PCE, it is no longer considered as an activity that may impact leatherback critical habitat.

SECTION 1: FRAMEWORK FOR THE ANALYSIS

<u>1.1</u> Introduction

The purpose of this report is to identify and analyze the potential economic impacts associated with the designation of critical habitat for the leatherback. The analysis examines the potential impacts of restricting or modifying specific water and land uses to avoid adverse modification or destruction of critical habitat. This chapter presents the framework applied to analyze the economic impacts of critical habitat designation.

<u>1.2</u> General Framework for the Economic Analysis

Similar to our analysis of critical habitat designation for West Coast salmon and steelhead and Southern Distinct Population Segment (DPS) of North American Green Sturgeon, we, the National Oceanic and Atmospheric Administration's (NOAA) National Marine Fisheries Service (NMFS), are applying a cost-effectiveness framework to analyze the designation of critical habitat for leatherbacks. This framework supports the section 4(b)(2) decision-making process by allowing us to compare an estimate of the economic "benefits of exclusion" against an indicator of the biological "benefits of designation" for any particular area.² For this analysis, the cost-effectiveness framework has been modified, given the general uncertainty about specific management actions likely to be undertaken. This economic analysis addresses the economic "benefits of exclusion" portion of the weighing process, while the biological report and the ESA section 4(b)(2) report address and compare our results to the conservation "benefits of designation" for each particular area considered. These other reports also present more detailed information regarding presence of leatherbacks and the identified PCE in areas under consideration for critical habitat designation.

Note: Information, where appropriate, was taken from the "Economic Analysis of the Impacts of Designating Critical Habitat for the Threatened Southern Distinct Population Segment of North American Green Sturgeon (2008), prepared by Industrial Economics, Inc. for NMFS. Also, information, where appropriate, was taken from the "Final Economic Analysis of Critical Habitat Designation for Seven West Coast Salmon and Steelhead ESUs (2005)," prepared by NMFS.

1.2.1 Benefit-Cost Analysis and Cost-Effectiveness Analysis

When economic activities have biological effects or other consequences for conservation, analyses of the impacts of regulating those activities can take a number of approaches. Two possible approaches are benefit-cost analysis and cost-effectiveness analysis. Each of these approaches has strong scientific support as well as support from the Office of Management and Budget (OMB) through its guidelines on regulatory analysis.³ Each also has well known drawbacks, both theoretical and practical, as discussed in the following section in the context of critical habitat designation.

² National Marine Fisheries Service (NMFS). *Final Economic Analysis of Critical Habitat Designation for 12 West Coast Salmon and Steelhead ESUs*. August 2005. Section 1.2.1 of this report is a reduced form of the framework discussion provided in the West Coast salmon critical habitat analysis by the Northwest Fisheries Science Center.

³ U.S. Office of Management and Budget. "Circular A-4," September 17, 2003. Accessed at: http://www.whitehouse.gov/sites/default/files/omb/assets/omb/circulars/a004/a-4.pdf.

Benefit-cost analysis (BCA) is the first choice for analyzing the consequences of a regulatory action such as critical habitat designation.⁴ BCA is a well-established procedure for assessing the "best" course or scale of action, where "best" is that course which maximizes net benefits.⁵ Because BCA assesses the value of an activity in net benefit terms, it requires that a single metric, most commonly dollars, be used to gauge both benefits and costs. Although the data and economic models necessary to estimate costs may be difficult or costly to gather and develop, expressing costs in dollars is straightforward for most regulatory actions. This is often the case for critical habitat designation, which has direct impacts on activities carried out, funded, or permitted by the Federal government. However, as discussed below, a large degree of uncertainty exists with regard to potential economic impacts of critical habitat designation for the leatherbacks. (Conceptually, the "benefits of exclusion," which is the language used in section 4(b)(2) of the Endangered Species Act (ESA), are identical to the "costs of designation," and so estimates of these costs could be used in a benefit-cost framework.)

Assessing the benefits of critical habitat designation in a BCA framework is straightforward in principle but much more difficult in practice. To the extent that the critical habitat provisions of the ESA increase the protections afforded the leatherbacks and their habitat, they produce real benefits to the species. In principle, these benefits can be measured first by a biological metric, and then by a dollar metric. A biological metric could take the form of the expected decrease in extinction risk, increase in the annual population growth rate, and so forth. A BCA would then use this metric to assess the state of the species with and without critical habitat designation. This assessment would reveal the biological impact of designation, quantified in terms of the metric. However, the available data are insufficient to quantify the benefits of designating critical habitat for leatherbacks, particularly with respect to discrete geographical areas.

Recognizing the difficulty of estimating economic values in cases like this one, OMB has recently acknowledged cost-effectiveness analysis (CEA) as an appropriate alternative to BCA:

Cost-effectiveness analysis can provide a rigorous way to identify options that achieve the most effective use of the resources available without requiring monetization of all of the relevant benefits or costs. Generally, cost-effectiveness analysis is designed to compare a set of regulatory actions with the same primary outcome (e.g., an increase in the acres of wetlands protected) or multiple outcomes that can be integrated into a single numerical index (e.g., units of health improvement).⁶

Ideally, CEA quantifies both the benefits and costs of a regulatory action but uses different metrics for each. A common application of this method is to health care strategies, where the benefits of a strategy are quantified in terms of lives saved, additional years of survival, or some other quantitative, health-related measure.

In principle, conducting a CEA of critical habitat designation proceeds along the same lines identified above for BCA, except that the last step of assigning economic (dollar) values to biological benefits is not

⁴ Ibid.

⁵ Zerbe, R., and D. Dively, 1994. Benefit Cost Analysis in Theory and Practice, New York: HarperCollins.

⁶ Ibid.

taken. Different configurations of critical habitat could be gauged by both metrics, with the costeffectiveness (ratio of units of biological benefits to monetized cost) evaluated in each case. If alternatives have the same level of biological benefits, the most cost-effective is the one with the highest ratio of biological benefits to cost (either in the form of monetized costs or some other cost metric or cost ranking).

Standard CEA presumes that benefits and costs can be measured with a cardinal or even continuous measure. For critical habitat designations in general, however, constructing such a measure for biological benefits is problematic. Although protecting habitat for leatherbacks is likely to have benefits, it is not yet possible to quantify the benefits reliably with a single biological metric given the state of the science. In addition, there is general uncertainty about specific management actions likely to be undertaken on behalf of this species. Thus, applying CEA in its standard form is not possible.

The alternative form of CEA being applied to the leatherback analysis is one that develops an ordinal measure of the benefits of critical habitat designation. Although it is difficult to monetize or quantify benefits of critical habitat designation, it is possible to differentiate among habitat areas based on their estimated relative need for special management. For example, habitat areas can be rated as having a high, medium, or low biological value. The output (a qualitative ordinal ranking) may better reflect the state of the science for the geographic scale considered here than a quantified output, and can be done with available information.

Individual habitat areas can be assessed using both their biological evaluation and economic impact assessments, so that areas with high conservation value and lower economic impacts have a higher priority for designation, and areas with a low conservation value and higher economic impacts have a higher priority for exclusion. Again, these analyses are discussed in the Biological Report and the ESA section 4(b)(2) report for this rule.

By proceeding in order of these priorities (either in terms of designation or exclusion), the critical habitat will minimize, or at least (in practice) reduce, the overall economic cost of achieving any given level of conservation. This form of CEA has two limitations, one of which it shares with the standard form of CEA. First, because CEA does not evaluate benefits and costs in the same metric, the analysis cannot assess whether a given change has benefits that, in monetary terms, are greater than costs. Although this analysis arrives at estimated economic impacts on a cost per area basis, a large degree of uncertainty exists with regard to these costs. However, because the biological values are classified into high, medium, and low values, the coarseness of the available cost information should suffice to produce an effective tool for balancing costs and benefits. A second limitation of the modified form of CEA is the inability to discern variation in benefits among those areas assigned the same conservation value (i.e., the same ordinal ranking). A likely outcome is that using the modified CEA will lead to an outcome with higher expected costs of achieving any given level of conservation than one produced with standard CEA or BCA. This limitation, however, should be compared to the greater feasibility of the modified CEA.

1.3 Impacts that are the Focus of this Analysis

This analysis examines the state of the world with and without the designation of critical habitat for the leatherback. The "without critical habitat" scenario represents the baseline for the analysis, considering

habitat protections already afforded leatherbacks under its Federal listing and under other Federal, State, and local regulations, including protections afforded leatherbacks resulting from protections afforded other listed species, such as West Coast salmon and steelhead, delta smelt, green sturgeon and marine mammals. The "with critical habitat" scenario attempts to describe the incremental impacts associated specifically with the designation of critical habitat for the leatherbacks.⁷ This analysis does provide an overview of costs that may be considered coextensive with the listing of leatherbacks and other baseline protections. The focus of the analysis, however, is determining the increment of costs that is attributable to critical habitat.

The social welfare impacts of critical habitat designation generally reflect "opportunity costs" associated with the commitment of resources required to accomplish species and habitat conservation. For example, if a set of activities that may take place on a parcel of land is limited as a result of the designation or the presence of the species, and thus the market value of that land is reduced, this reduction in value represents one measure of opportunity cost. Similarly, the costs incurred by a Federal action agency to consult with NMFS under section 7 represent opportunity costs related to leatherback conservation, as the time and effort associated with those consultations would have been spent on other endeavors absent the listing of the species or critical habitat designation.

At the guidance of the Office of Management and Budget (OMB) and in compliance with Executive Order 12866, "Regulatory Planning and Review," Federal agencies measure changes in economic efficiency in order to understand how society, as a whole, will be affected by a regulatory action. Economists generally characterize opportunity costs in terms of changes in producer and consumer surpluses (i.e., social welfare impacts) in affected markets.⁸

1.3.1 Baseline for the Economic Analysis

The first step in the economic analysis is to identify the baseline level of protection afforded the leatherbacks and their habitat. This section provides a description of the methodology used to identify baseline conditions and incremental impacts stemming from the designation of critical habitat for the leatherbacks.

The baseline for this analysis is the existing state of regulation prior to the designation of critical habitat that provides protection to the species under the ESA and other Federal, State and local laws and regulations. The baseline includes the protections of sections 7, 9, and 10 of the ESA, and economic impacts resulting from these protections to the extent that they are expected to occur absent the designation of critical habitat for the species.

⁷ We note that although the focus of this analysis is on the incremental effects of the designating critical habitat, due to uncertainties with regard to future management actions associated with leatherback critical habitat, it was difficult in some cases to exclude potential impacts that may already occur under the baseline. Thus, the analysis may include some costs which would have occurred under the baseline regardless of designating critical habitat.

⁸ For additional information on the definition of "surplus" and an explanation of consumer and producer surplus in the context of regulatory analysis, see: Gramlich, Edward M. *A Guide to Benefit-Cost Analysis (2nd Ed.)*. Prospect Heights, Illinois: Waveland Press, Inc., 1990; and U.S. Environmental Protection Agency, "Guidelines for Preparing Economic Analyses," EPA 240-R-00-003, September 2000. Accessed at: http://yosemite.epa.gov/ee/epa/eed.nsf/ webpages/Guidelines.html.

Section 7 of the ESA, absent critical habitat designation, requires Federal agencies to consult with NMFS to ensure that any action authorized, funded, or carried out will not likely jeopardize the continued existence of any endangered or threatened species. The portion of the administrative costs of consultations under the jeopardy standard, along with the impacts of project modifications resulting from consideration of this standard, are considered baseline impacts.

Section 9 defines the actions that are prohibited by the ESA. In particular, it prohibits the "take" of endangered wildlife, where "take" means to "harass, harm, pursue, hunt, shoot, wound, kill, trap, capture, or collect, or to attempt to engage in any such conduct."⁹ The economic impacts associated with this section manifest themselves in sections 7 and 10.

The protection of listed species and habitat is not limited to the ESA. Other Federal agencies, as well as State and local governments, may also seek to protect the natural resources under their jurisdiction. If compliance with the Clean Water Act or State environmental quality laws, for example, protects habitat for the species, such protective efforts are considered to be baseline protections and costs associated with these efforts are not quantified as impacts of critical habitat designation. As noted above, where uncertainty exists as to whether particular costs would have already occurred under the baseline, this analysis conservatively includes those costs. Many of the relevant existing regulations are discussed in Appendix B.

1.3.2 Types of Economic Impacts of Critical Habitat Designation

This analysis focuses on the incremental impacts of the critical habitat designation. The purpose of the analysis is to determine the impacts on water and land uses from the designation of critical habitat that are above and beyond those impacts due to existing or planned conservation efforts being undertaken due to other Federal, State, and local regulations or guidelines.

When critical habitat is designated, section 7 of the ESA requires Federal agencies to ensure that their actions will not result in the destruction or adverse modification of critical habitat (in addition to ensuring that the actions are not likely to jeopardize the continued existence of the species). The added administrative costs of including consideration of critical habitat in section 7 consultations and the additional impacts of implementing project modifications to protect critical habitat are the direct result of the designation of critical habitat. These costs are not in the baseline, and are considered incremental economic impacts of the rulemaking.

Incremental impacts may include the direct costs associated with additional effort for future consultations, reinitiated consultations, and new consultations occurring specifically because of the designation, and additional project modifications that would not have been otherwise required to avoid jeopardizing the continued existence of the species. Additionally, incremental impacts may include indirect impacts resulting from reaction to the potential designation of critical habitat, triggering of additional requirements under. State or local laws intended to protect sensitive habitat, and uncertainty and perceptional effects on markets. The nature of these impacts is described in greater detail below.

⁹ 16 U.S.C. 1532.

Direct Impacts

The direct incremental impacts of critical habitat designation stem from the consideration of the potential for destruction or adverse modification of critical habitat during section 7 consultations. The two categories of direct incremental impacts of critical habitat designation are: 1) the administrative costs of conducting section 7 consultations; and 2) implementation of any project modifications requested by NMFS through section 7 consultation to avoid destruction or adverse modification of critical habitat.

Administrative Section 7 Consultation Costs

Parties involved in section 7 consultations for leatherbacks include NMFS, a Federal action agency (The Federal agency that funds, authorizes, or carries out the program or project), and in some cases, a private entity involved in the project or activity. NMFS could also serve as the Federal action agency, in which case the consultation would be conducted internally between regions, divisions, or offices. While consultations are required for activities that involve a Federal nexus and may affect the species, regardless of whether critical habitat is designated, the designation may increase the effort for consultations where the project or activity in question may adversely modify critical habitat. Administrative efforts for consultation may therefore result in both baseline and incremental impacts.

The geographic scope of the leatherback critical habitat being considered and the nature of the available data preclude unit-by-unit accounting of these costs. First, a single consultation can cover more than one project. While the majority of consultations cover a single project, the exceptions are important. For example, programmatic consultations determine how a type or types of project, not the projects themselves, can be modified to ensure they comply with section 7. As a result, these consultations can cover large numbers of projects. While programmatic consultations are likely to be more costly, the cost per project is likely to be significantly lower than the per-project cost for non-programmatic consultations. For that reason, applying a constant per-project cost estimate would significantly inflate the estimated level of consultation cost. Moreover, when multi-project consultations occur, they are likely to cover a wide geography. This makes it difficult to attribute those consultation costs to a particular area. Due to the uncertainties regarding the specific location, type, and frequency of future consultations, the current analysis does not project total administrative costs associated with this designation.

For contextual purposes, Table 1.3-1 presents generalized per-consultation administrative costs of consultations. In general, three different scenarios associated with the designation of critical habitat may trigger incremental administrative consultation costs:

- New Consultation Initiated to address both adverse modification or destruction of critical habitat and jeopardy to the species New consultations taking place after critical habitat designation may require additional effort to address critical habitat above and beyond addressing the listed species. In this case, only the additional administrative effort required to consider critical habitat is considered an incremental impact of the designation.
- **Re-initiation of consultation to address adverse modification or destruction of critical habitat**-Consultations that have already been completed on a project or activity may require re-initiation to address critical habitat. In this case, the costs of reinitiating the consultation, including all

associated administrative and project modification costs are considered incremental impacts of the designation.

• **Consultation resulting entirely from the critical habitat designation -** Critical habitat designation may trigger additional consultations that may not occur absent the designation (e.g., for an activity for which adverse modification may be an issue, while adverse impact to the species are not). All associated administrative and project modification costs are considered incremental impacts of the designation.

The administrative costs of these consultations vary depending on the specifics of the project. One way to address this variability is to show a range of possible costs of consultation. Table 1.3-1 provides estimated consultation costs representing effort required for all types of consultation, including those that consider both adverse modification and jeopardy. To estimate the fractions of the total administrative consultation costs that are baseline and incremental, the following assumptions were applied:

- Costs associated with an incremental consultation (one occurring because of the designation of critical habitat) would be attributed wholly to critical habitat;
- Incremental costs of a re-initiation of a consultation, because of the critical habitat designation, are assumed to be approximately half the cost of the original consultation that considered only adverse effects to the listed species. This assumes that re-initiations are less time-consuming as the groundwork for the project has already been considered in terms of its effect on the species;
- Efficiencies exist when considering both jeopardy and adverse modification at the same time (e.g., in staff time saved for project review and report writing), and therefore incremental administrative costs of considering adverse modification in consultations that will already be required to consider jeopardy result in the least incremental effort of these three consultation categories, roughly half that of a re-initiation.

Importantly, the estimated costs represent the midpoint of a potential range of impacts to account for variability regarding levels of effort of specific consultations.

Consultation	Service	Federal	Third Party	Biological	Total Costs	
Туре		Agency		Assessment		
New consultation	ons addressing a	dverse modification	on only		·	
Technical	\$530	n/a	\$1,050	n/a	\$1,500	
Assistance						
Informal	\$2,300	\$2,900	\$2,050	\$2,000	\$9,500	
Formal	\$5,150	\$5,800	\$3,500	\$4,800	\$19,500	
Programmatic	\$15,500	\$13,000	n/a	\$5,600	\$34,100	
Re-initiation of	existing consul	tation to address a	dverse modification		•	
Technical	\$265	n/a	\$525	n/a	\$750	
Assistance						

 Table 1.3-1: Example Range of Administrative Consultation Costs (Per Consultation), \$2007

Informal	\$1,150	\$1,450	\$1,030	\$1,000	\$4,750
Formal	\$2,580	\$2,900	\$1,750	\$2,400	\$9,750
Programmatic	\$7,750	\$6,480	n/a	\$2,800	\$17,000
Additional effort	in new consultati	ons addressing jeo	pardy and adverse	modification.	
Technical	\$133	n/a	\$263	n/a	\$375
Assistance					
Informal	\$575	\$725	\$513	\$500	\$2,380
Formal	\$1,290	\$1,450	\$875	\$1,200	\$4,880
Programmatic	\$3,880	\$3,240	n/a	\$1,400	\$8,510

Source: Adapted from the IEc (2009).

Note: 1. IEc analysis of full administrative costs is based on data from the Federal Government Schedule Rates, Office of Personnel Management, 2007, and a review of consultation records from several Fish and Wildlife Service field offices across the country conducted in 2002; this is the based on a national level sample and is the best available data at this time.

2. Totals may not sum due to rounding.

3. Estimates reflect average hourly time required by staff.

Section 7 Project Modification Impacts

Section 7 consultation considering critical habitat may also result in additional project modification recommendations specifically addressing potential destruction or adverse modification of critical habitat. For consultations that consider jeopardy and adverse modification, and for re-initiations of past consultations to consider critical habitat, the economic impacts of project modifications undertaken to avoid or minimize adverse modification are considered incremental impacts of critical habitat designation. For consultations that are forecast to occur specifically because of the designation (incremental consultations), impacts of all associated project modifications are assumed to be incremental impacts of the designation.

Indirect Impacts

The designation of critical habitat may, under certain circumstances, affect actions that do not have a Federal nexus and thus are not subject to the provisions of section 7 of the Act. Indirect impacts are those unintended changes in economic behavior that may occur outside of the Act, through other Federal, State, local, or private actions that are caused by the designation of critical habitat. Below common types of indirect impacts that may be associated with the designation of critical habitat are identified. These types of impacts are not always considered incremental. If these types of conservation efforts and economic effects would occur regardless of critical habitat designation, they are appropriately considered baseline impacts.

Other State and Local Laws

Under certain circumstances, critical habitat designation may provide new information to a State or local government about the sensitive ecological nature of a geographic region, potentially triggering additional economic impacts under other State or local laws. In cases where these impacts would not have been triggered absent critical habitat designation, they are considered indirect, incremental impacts of the designation.

Additional Indirect Impacts

In addition to the indirect effects noted above, project proponents, land managers and landowners may face additional indirect impacts, including the following:

Time Delays - Both public and private entities may experience incremental delays for projects and other activities due to requirements associated with the need to reinitiate the section 7 consultation process and/or compliance with other laws triggered by the designation. To the extent that delays result from the designation, they are considered indirect, incremental impacts of the designation.

Regulatory Uncertainty - NMFS conducts each section 7 consultation on a case-by-case basis and issues a biological opinion on formal consultations based on species-specific and site-specific information. As a result, government agencies and affiliated private parties who consult with NMFS under section 7 may face uncertainty concerning whether project modifications will be recommended by NMFS and what the nature of these modifications will be. This uncertainty may diminish as consultations are completed and additional information becomes available on the effects of critical habitat on specific activities. Where information suggests that regulatory uncertainty stemming from the designation may affect a project or economic behavior, associated impacts are considered indirect, incremental impacts of the designation.

Stigma - In some cases, the public may perceive that critical habitat designation may result in limitations on private property uses above and beyond those associated with anticipated project modifications or regulatory uncertainty. Public attitudes about the limits or restrictions that critical habitat may impose can cause real economic effects, regardless of whether such limits are actually imposed. All else equal, a property that is adjacent to the designated critical habitat may have a lower market value than an identical property that is not adjacent to the boundaries of the critical habitat due to perceived limitations or restrictions. The converse may also be true. As the public becomes aware of the true regulatory burden imposed by critical habitat, the impact of the designation on property markets may decrease. To the extent that potential stigma effects on markets are probable and identifiable, these impacts are considered indirect, incremental impacts of the designation.

These potential impacts are not explicitly addressed in this analysis, but were considered during the development of cost estimates.

1.4 Approach to Analysis

To quantify the economic impacts of modifications to land and water uses that result from critical habitat designation, the analysis employs the following five steps:

- 1. Define the geographic area for the analysis, and identify the geographic areas occupied, identify specific areas to be analyzed for purposes of this designation. The final rule to designate critical habitat analyzes how each of these areas meets the definition of critical habitat set forth in section 3 of the ESA.
- 2. Identify the PCEs that are found in each of the specific areas and the potentially affected economic activities (e.g., liquid natural gas or tidal, wave, or wind projects).
- 3. Estimate the baseline level of protection afforded leatherbacks by area and activity type.
- 4. For each economic activity, establish the existing and expected level of economic activity that may be affected by leatherback conservation efforts in each critical habitat area.
- 5. Estimate potential economic impacts of leatherback management by economic activity type and sum by area.

These steps are described in greater detail below.

1.4.1 Define Geographic Study Area

The geographic study area spans from the California-Mexico border to Cape Flattery in Washington. NMFS divided this study area into nine individual areas to be considered for critical habitat designation (hereafter, "areas"), as shown in Figure 1.4-1. Based on subsequent analysis and review, NMFS arrived at a leatherback critical habitat designation in the final rule, which is limited to areas 1, 2 and 7 of those initially considered. The draft economic report included all the eight areas identified in the proposed rule in the analysis. An initial revised report prepared thereafter addressed the additional ninth area. The CHRT, in response to public comments and further deliberation, determined that three of the nine areas

qualified as critical habitat. This final version of the analysis only includes areas 1, 2 and 7 as those are the only areas eligible for designation and thus potential exclusion under section 4(b)(2).

Below is the description of the nine study areas which were considered in a preliminary draft of the report prepared after publication of the proposed rule.¹⁰

- Area 1: Neritic waters between Point Arena and Point Sur, California extending offshore to the 200 meter isobath.
- Area 2: Nearshore waters between Cape Flattery, Washington, and Cape Blanco, Oregon extending offshore to the 2000 meter isobath.
- Area 3: Nearshore waters between Cape Blanco, Oregon and Point Arena, California extending offshore to the 2000 meter isobath.
- Area 4: Offshore area west and adjacent to area 2 (see above). Includes waters west of the 2000 meter isobath.
- Area 5: Offshore area west of Cape Blanco upwelling plume (warm water side of steep sea surface temperature gradient). Area is south and adjacent to area 4 (see above). Includes waters outside of the 2000 meter isobath west of Umpqua River, Oregon to the US EEZ limit (approximately), south to offshore waters west of Oregon/California border
- Area 6: Offshore area extending from waters west of California/Oregon border, outside of area 3 (see above), south to Point Arena, California at the 200 meter isobath. Western border extends from US EEZ limit west of the California/Oregon border southeast to point west of Point Arena, California.
- Area 7: Offshore waters between the 200 3000 meter isobaths from Point Arena to Point Sur, California and waters between the coastline and the 3000 meter isobath from Point Sur to Point Arguello, California.
- Area 8: Offshore waters west and adjacent to area 6, and west of the 3000 meter isobath adjacent to areas 7 and 9 between Point Arena, California and the U.S. EEZ/Mexico maritime border.
- Area 9: Southern California Bight waters extending from the coast to the 3000 meter isobath between Point Arguello and Point Vicente, and from Point Vicente to N32.589/W117.463 extending to the 3000 meter isobath.

While NMFS provided study area boundaries in ocean waters based on the presence of leatherbacks and their PCEs, the economic analysis at times uses county data to describe the presence and extent of some activities, due to data availability. Where this occurs, we approximated to which study areas the coastal county data would be attributed.

¹⁰ NMFS received numerous comments on the area boundaries. Based on the comments received, the CHRT reevaluated the specific areas identified in the proposed rule. Several boundary adjustment were made including: the boundary between Areas 2 and 3, moving the offshore boundary of Area 7 to the 3000 meter isobath, and the creation of a 9th area in the southern portion of area 7.




Figure 1.4-1 Final Leatherback Critical Habitat Areas

1.4.2 Identify PCEs & Potentially Affected Economic Activities

Joint NMFS-U.S. Fish and Wildlife Service regulations at 50 CFR 424.12(b) state that in determining what areas are critical habitat, the agencies "shall consider those physical and biological features that are essential to the conservation of a given species and that may require special management considerations or protection." Features to consider may include, but are not limited to:

(1) Space for individual and population growth, and for normal behavior;

(2) Food, water, air, light, minerals, or other nutritional or physiological requirements;

(3) Cover or shelter;

(4) Sites for breeding, reproduction, rearing of offspring, germination, or seed dispersal; and generally;

(5) Habitats that are protected from disturbance or are representative of the historic geographical and ecological distributions of a species.

ESA regulation also require agencies to "focus on the principle biological or physical constituent elements" (hereafter referred to as "Primary Constituent Elements" or PCEs) within the specific areas considered for designation. NMFS identified one PCE essential for the conservation of leatherbacks in marine waters of the U.S. West Coast (see Critical Habitat for Leatherback Sea Turtle Biological Report for more information on this PCE)¹¹:

Occurrence of prey species, primarily Scyphomedusae of the order Semaeostomeae (Chrysaora, Aurelia, Phacellophora, and Cyanea) of sufficient condition, distribution, diversity, abundance and density to support individual as well as population growth, reproduction, and development of leatherbacks

NMFS then identified seven categories of economic activity that may have an effect on the prey PCE described above. These activities may require modification to avoid destruction or adverse modification of leatherback critical habitat. These "activities" include the operation of some facilities, such as water temperature control, where modifications may be required as a result of this designation. The following are the economic activities assessed in this analysis¹²:

- NPDES permit activities
- Agricultural pesticides
- Oil spill response
- Power plants
- Desalination plants
- Tidal, wave, and wind energy projects
- Liquefied natural gas (LNG) projects

Using maps and data, this analysis first assesses the level of current and expected economic activity for each affected industry. The analysis then scales this level of activity to the number of projects expected

¹¹ Note that the draft economic analysis for the proposed rule, originally considered two PCEs, prey and passage. Based on the comments received and our review of the proposed rule, migratory pathway conditions to allow for safe and timely passage and access to/from/within high use foraging areas has been eliminated as a PCE.

¹² Note that while aquaculture was previously included in our analysis, with the removal of the passage PCE, it is no longer considered as an activity that may require special management.

to be affected annually by leatherback critical habitat designation (e.g., the number of proposed tidal, wave, and wind energy projects).

1.4.3 Estimate the Baseline Level of Protection Afforded Leatherbacks by Area and Activity Type

Upon final designation of critical habitat, activities affecting leatherback critical habitat may require modification to avoid destruction or adverse modification of the critical habitat. This analysis aims to understand the economic impacts of avoiding adverse impacts to leatherback critical habitat over and above other baseline protections that may already be in place. Because of the close relationship in terms of management requirements under the ESA for a species and its critical habitat, protections for the leatherback itself will likely provide the strongest baseline protections to leatherback critical habitat. In addition, protections already in place for National Marine Sanctuaries and critical habitat. The following paragraphs provide a level of baseline protection for leatherback critical habitat. The following paragraphs provide additional detail regarding baseline protections that comprised a substantial part of the baseline analysis for one or more of the three specific areas evaluated. A number of other regulations, laws, and initiatives that have been created specifically to address human-induced impacts on marine species are summarized in Appendix B and were also considered part of the baseline when relevant to the specific area being analyzed.

National Marine Sanctuaries

There are four National Marine Sanctuaries (NMS) along the California and Washington coasts that overlap with leatherback critical habitat; the Monterey Bay NMS, Cordell Bank NMS, Gulf of the Farallones NMS and Olympic Coast NMS. All Sanctuaries have implemented regulations designed to protect habitat and resources within the Sanctuaries. For example, the Monterey Bay NMS, which runs from Rocky Point to Cambria, California (Area 1), restricts the alteration of or construction on the seafloor and the discharging or depositing of any materials into the Sanctuary.¹³ These protections to the bottom habitat will likely provide protection for the benthic polyp stage of jellyfish reproduction.

Green Sturgeon Critical Habitat

Green sturgeon critical habitat includes marine waters within 60 fm depth including Monterey Bay, north to Cape Flattery, Washington. Thus, this critical habitat overlaps with portions of the critical habitat being considered for leatherbacks. NMFS identified several activities that would affect green sturgeon critical habitat in marine coastal waters, including oil spills, and wave energy projects (73 FR 52084 September 8, 2008). These categories of activities have also been identified as special management concerns for critical habitat being considered for leatherbacks. Modifications to these types of activities to prevent adverse modification of green sturgeon critical habitat, which includes water quality and food resources, would potentially benefit the leatherback critical habitat prey PCE.

Salmon and Steelhead Critical Habitat

Salmon and steelhead critical habitats are almost exclusively riverine and do not overlap with critical habitat for leatherbacks. However, some modifications to upland and riverine activities (e.g., restrictions

¹³ Marine Conservation Biology Institute. *Monterey Bay National Marine Sanctuary*. Accessed at: <u>http://www.mcbi.org/what/what_pdfs/Monterey_Bay.pdf</u>, on May 2010.

to pesticide use) may affect water quality and prey in the critical habitat areas for leatherbacks. . NMFS identified agriculture as an activity that may impact salmon and steelhead critical habitat (70 FR 52630, September 2, 2005). Agriculture, in particular the use of pesticides, was also identified as an activity that may require special management for leatherback critical habitat. A number of initiatives have been undertaken to address human induced impacts on salmon and steelhead critical habitat, including impacts to habitat features such as water quality, water quantity and salinity. Improvements to these features for purposes of salmon and steelhead critical habitat will likely also provide benefits to leatherback prey species.

Black Abalone Critical Habitat

Critical habitat for black abalone has been designated within marine waters along the west coast from the mean higher high water (MHHW) line onshore to 6 meters depth offshore, which overlaps with coastal portions of the leatherback critical habitat, therefore consultations on these two critical habitat designations will likely overlap. NMFS identified several activities that may affect the proposed black abalone critical habitat in marine coastal waters, including NPDES, agricultural pesticide application, oil spills, power plants, desalination plants, and tidal and wave energy projects (76 FR 66806 October 27, 2011). These categories of activities have also been identified as special management concerns for leatherback critical habitat. Activities with the potential to impact black abalone also have the potential to impact leatherback prey species during their benthic development stage. Therefore, while the black abalone critical habitat designation looked specifically at these activity types from the perspective of an invertebrate species and necessary water quality, there are similar concerns and potential project modifications that may be required for the protection of all life stages of the leatherback prey PCE.

Marine Mammals

The analysis also considers baseline protections to leatherback critical habitat resulting from the presence of ESA listed marine mammals such as Southern Resident killer whales and Steller sea lions, as well as non-ESA listed marine mammals that are afforded protections through the Marine Mammal Protection Act (MMPA). Due to the presence of MMPA and ESA listed marine mammals along the U.S. West Coast, many activities must consider both direct and indirect effects to marine mammals. Indirect effects include impacts to marine mammal prey and water quality, which would likely result in a measure of protection for leatherback prey. Additionally, many activities identified in the leatherback critical habitat designation will also be evaluated for impacts to marine mammals, such as tidal, wave, and wind energy projects, therefore, any modifications required for marine mammals may provide a measure of protection for leatherbacks and their habitat.

Assigning Baseline Protections within the Specific Areas

In order to determine the incremental scores associated with possible changes to activities, we first considered the existing or baseline protections in each specific area and relative to the associated economic activities. To determine the baseline for each area and economic activity we considered three major factors: 1) the overlap of previously designated critical habitat for other species within leatherback critical habitat, 2) the presence of other listed species and protected marine mammals within leatherback critical habitat, and 3) the Federal, state and local protections already in place to conserve and protect marine resources. In conducting this evaluation, we considered whether protections provided by these three factors would benefit the leatherback prey PCE. Below we summarize information regarding the

baseline protections in each of the three specific areas, and we present the baseline ratings for each area and activity type in Table 1.4-1.

- Area 1: This area consists of the nearshore waters between Point Arena and Point Sur, California extending offshore to the 200 meter isobath. This area contains 6 activity types that were identified as requiring special management: NPDES permitting, agricultural pesticides, oil spill response, power plants, desalination, and tidal, wave and wind energy projects. This area encompasses three U.S. West Coast national marine sanctuaries (Monterey Bay NMS, Cordell Bank NMS, and Gulf of the Farallones NMS), marine protection areas, essential fish habitats, and contains various ESA listed species for which section 7consultations have occurred. Further, given the proximity to the coast, these areas receive additional conservation benefit from protections required under the Coastal Zone Management Act and state and regional policies and regulations. This area also overlaps with critical habitat for black abalone and green sturgeon. When evaluating this area for the baseline protections already afforded to leatherback critical habitat, we concluded that this area has an overall high level of baseline protections relative to the economic activities of NPDES permitting, agricultural pesticides, oil spill response, power plants and desalination plants. Tidal, wave and wind energy projects were rated as having medium baseline protections due to a higher degree of uncertainty regarding modifications that would be required for these types of projects as a result of existing protections. For alternative energy projects, we also have a more limited section 7 consultation history to use to consider possible project modifications and potential benefits to leatherback critical habitat.
- Area 2: This area consists of nearshore waters between Cape Flattery, Washington, and Cape Blanco, Oregon extending offshore to the 2000 meter isobath. This area contains 5 activity types that were identified as requiring special management, NPDES permitting, agricultural pesticides, oil spill response, tidal, wave and wind energy projects, and LNG. This area is located in the coastal neritic environment of Oregon and Washington, and encompasses one U.S. West Coast national marine sanctuary, the Olympic Coast NMS, marine protection areas, essential fish habitats, and contain various ESA listed species for which section 7 consultations have occurred. Further, given the proximity to the coast, these areas receive additional conservation benefit from protections required under the Coastal Zone Management Act and state and regional policies and regulations. This area also overlaps with critical habitat for salmon/steelhead and green sturgeon. When evaluating this area for the baseline protections already afforded to leatherback critical habitat, we concluded that this area has a high level of baseline protections for NPDES, agricultural pesticides and oil spill response activities. Tidal, wave and wind energy projects and LNG terminals were rated as having medium baseline protections due to a higher degree of uncertainty regarding modifications that would be required for these types of projects as a result of existing protections. For alternative energy and LNG projects, we also have a more limited section 7 consultation history to use to consider possible project modifications and potential benefits to leatherback critical habitat.
- Area 7: This area consists of the offshore waters between the 200 3000 meter isobaths from Point Arena to Point Sur, California and waters between the coastline and the 3000 meter isobath from Point Sur to Point Arguello, California. This area contains 5 activity types that were

identified as requiring special management: NPDES permitting, agricultural pesticides, oil spill response, power plants, and desalination. This area is located in both coastal and offshore environment and encompasses essential fish habitats, contains various ESA listed species for which section 7 consultations have occurred, and this area overlaps with critical habitat designated for black abalone. Further, given the proximity to the coast in the lower portion of this area, it receives additional conservation benefit from protections required under the Coastal Zone Management Act and state and regional policies and regulations. When evaluating this area for the baseline protections already afforded to leatherback critical habitat, we concluded that this area has a high level of baseline protections relative to each of the 5 activity types.

Table 1.4-1 below shows the baseline protection rating for each activity within each specific area. Dashes indicate that the activity does not occur in the specific area, based upon the information currently available, or that it will not affect the corresponding area.

		Agricultural	Oil Spills	Power		Tidal, Wave, & Wind	
Area	NPDES	Pesticides	Response	Plants	Desalination	Energy	LNG
1	high	high	high	high	high	med	-
2	high	high	high	-	-	med	med
7	high	high	high	high	high	-	-

 Table 1.4-1: Estimated Baseline Level of Protection¹⁴

1.4.4 Establish Incremental Scores and the Existing/Expected Level of Economic Activity Likely to be Affected by Critical Habitat

After establishing the level of baseline protections that exist, we determined an incremental score for each activity in each area. We reviewed previous critical habitat designations to compare methods for estimating economic costs associated with the designations. We found that several different methods have been used, but most used an incremental scoring process to account for the existing protections afforded to the species, which then apportion a percentage of project modification costs to existing baseline protections and a percentage to the critical habitat designation. We adopted this approach for leatherback critical habitat.

We assigned incremental scores based on the qualitative baseline ratings. In areas where baseline protections were considered to be high, the portion of project modification costs attributable to leatherback critical habitat designation should be low, and thus the assigned incremental score should be low. For these areas, we assigned an incremental score of 0.3, meaning 30% of project modification costs would be attributable to leatherback critical habitat. Areas rated as having a medium level of baseline protections were assigned an incremental score of 0.5, meaning 50% of any project modification costs

¹⁴ Note that while aquaculture was previously included in our analysis, with the removal of the passage PCE, it is no longer considered as an activity that may require special management.

would be attributed to leatherback critical habitat. In areas where lower baseline protections exist, it is expected that the majority of any project modification costs would be associated with the leatherback critical habitat designation; thus, the assigned incremental score should be high. For these areas, we assigned an incremental score of 0.7, meaning 70% of project modifications and associated costs would be attributable to leatherback critical habitat. Areas with no identified baseline protections would receive an incremental score of 1.0. Table 1.4-2 presents baseline ratings and their associated incremental scores.

Once incremental scores were determined for each activity in each area, we used these incremental scores to adjust the potential costs for this critical habitat designation. Because there is uncertainty associated with assigning incremental scores, a sensitivity analysis of the incremental scoring was conducted and is provided in Appendix C. Table C-1 of Appendix C presents total area costs with and without the incremental score calculations. The ranking of total area impacts does not change for the low, midpoint, and high cost scenarios when comparing costs that incorporate incremental scores to costs without incremental scores. When incremental scores were not applied, the overall cost of designation does not include other conservation efforts in place and are thus much higher per area. The total annual area costs calculated using the incremental scores are the cost evaluated in the ESA section 4(b)(2) process when evaluating exclusions based on economic impacts.

Table 1.4-2 summarizes the systematic approach that was used to assign incremental scores to areas and activities given direct or indirect benefits expected from existing protections or designated critical habitat.

Baseline Protection Rating	Incremental Score	Relative Cost Associated with Leatherback Critical Habitat
High	0.3	Low
Medium	0.5	Medium
Low	0.7	High
None	1.0	All Costs

 Table 1.4-2: Incremental Score Based on Review of Existing Regulations and Designated Critical

 Habitat

1.4.5 Estimate Potential Economic Impacts by Area

For each potentially affected economic activity, we identify project modifications that may be necessary to avoid destruction or adverse modification of the critical habitat being considered for leatherbacks. Because a large degree of uncertainty exists with regard to future actions likely to be undertaken specifically for the benefit of leatherbacks, this analysis begins by estimating economic impacts of likely management actions that may take into account leatherbacks as well as other listed species.

1.4.6 Calculate Total Impacts by Area

To create a total impact estimate for each critical habitat area, we multiplied the number of affected projects by the annualized costs per project and the incremental score for each area and economic activity type, then summed these activity scores in each area.

This process is summarized in the following equation:

$$C_U = \sum_U N_{i,U} * C_{i,U} * I_{i,U}$$

Where

 C_U = Total annualized economic impacts (costs) for area 'U' (2009 dollars)

 $N_{i,U}$ = Annual number of affected projects for activity 'i' in area 'U'

 $C_{i,U}$ = Annualized economic impacts (costs) on activity 'i' in area 'U' (2009 dollars)

 $I_{i,U}$ = Incremental impact of leatherback critical habitat on activity 'i' in area 'U' (0.3 – 0.7)

The final estimates of the total impacts by area are presented in Section 3 of this analysis.

1.4.7 Discount Rate

OMB Circular A-94 states that a 7 percent discount rate should be used as a base-case for regulatory analysis to approximate the marginal pre-tax rate of return on an average investment in the private sector in recent years (before 1992).¹⁵ OMB Circular A-4 adds that estimates using a 3 percent discount rate should also be provided for regulatory analyses.¹⁶ Thus, this analysis provides present discounted values using discount rates of 3 and 7 percent. Given the present low interest rate environment, we consider the present values discounted at 3 percent to better reflect current economic conditions. Appendix D presents a sensitivity analysis of our assumptions by comparing the present values discounted at 3 and 7 percent with those discounted at 2.1 percent.

1.4.8 Analytical Time Frame

The analysis estimates impacts based on activities that are reasonably foreseeable, including activities that are currently authorized, permitted, or funded, or for which proposed plans are currently available to the public. In general, the time frame over which data are available to project land uses in the study area is 20 years. In most cases, therefore, the analysis estimates economic impacts from 2010 to 2029 (20 years from the expected year of a critical habitat designation).

<u>1.5</u> Report Organization

The remainder of this report proceeds through three sections, including:

¹⁵ U.S. Office of Management and Budget. 1992. "Circular A-94: Guidelines and Discount Rates for Benefit-Cost Analysis of Federal Programs." October 29, 1992. Accessed at: http://www.whitehouse.gov/omb/assets/a94/a094.pdf.

¹⁶ U.S. Office of Management and Budget. 2003. "Circular A-4." September 17, 2003. Accessed at: http://www.whitehouse.gov/sites/default/files/omb/assets/omb/circulars/a004/a-4.pdf.

- Section 2 describes the seven categories of economic activity that may require modification to avoid destruction or adverse modification of leatherback critical habitat.
- Section 3 discusses the results of the analysis by area and activity. These results are derived from the activity counts and related cost estimates presented in earlier sections.
- Appendix A summarizes threats to leatherback critical habitat identified by NMFS.
- Appendix B summarizes laws and regulations that may provide baseline protection to leatherback critical habitat.
- Appendix C provides a sensitivity analysis testing the degree to which leatherback critical habitat drive the costs in particular areas.
- Appendix D tests the sensitivity of the discount rate by applying a 1 and 5 percent discount rate.
- Appendix E presents a Final Regulatory Flexibility Analysis.
- Appendix F analyzes energy impacts.

SECTION 2: ECONOMIC IMPACTS BY ACTIVITY

NMFS identified seven categories of economic activity that may require modification to avoid destruction or adverse modification of leatherback critical habitat. This section describes each activity in terms of their threat to leatherbacks, extent of occurrence within critical habitat, specific baseline elements that may provide protection to leatherbacks, and potential economic impacts of leatherback conservation efforts. Five categories discussed: National Pollutant Discharge Elimination System (NPDES) facilities, , , desalination plants, and tidal & wave energy projects all have a quantitative assessment with specific cost estimates presented for each activity type. The remaining activities: power plants, wind energy, and liquefied natural gas projects, are discussed qualitatively due to uncertainty of project modifications and/or lack of cost data.¹⁷

It is important to note here that the critical habitat review team also considered impacts to the prey PCE from ocean acidification and commercial fishing activities. Due to a lack of data and uncertainty regarding the impacts from ocean acidification, the team was unable to fully consider potential impacts, therefore this activity was not included in this analysis. When considering impacts to the prey PCE from commercial fishing activities, the team looked at potential fisheries that would target jellyfish, but no such fishery was anticipated in the foreseeable future. The bycatch of jellyfish in existing commercial fisheries was also considered, but it was determined that the level of bycatch was limited. Additionally, the direct take of the species in fishing gear is more appropriately considered under the jeopardy standard in ESA section 7 consultations. For these reasons, commercial fishing activities were excluded from this analysis.

2.1 Economic Impacts of Critical Habitat Designation on National Pollutant Discharge & Elimination System (NPDES) Facilities

2.1.1 Description of Threat

NMFS has identified point source pollution, particularly NPDES facilities as a threat to leatherback critical habitat in all areas; however, pollution would be found primarily in the three coastal areas under consideration: Areas 1, 2, and 7. This activity may affect prey resources, through contamination of all stages of jellyfish, including bioaccumulation of toxins through small prey ingestion. Limited studies have shown that jellyfish may concentrate higher levels of metals (e.g., cadmium) proportionately than fish, and given the likely low energetic value of jellyfish and the fact that leatherbacks must consume large quantities to meet their needs, leatherbacks may be exposed to high levels of metals, particularly in coastal areas (Caurant *et al.* 1999).

2.1.2 Regulatory Environment & Extent of Activity

Under the NPDES program, the Environmental Protection Agency (EPA) sets pollutant-specific limits on the point source discharges for major industries and provides permits to individual point sources that apply to these limits. According to a 2001 Memorandum of Agreement between the EPA, National

¹⁷ Note that while aquaculture was previously included in our analysis, with the removal of the passage PCE, it is no longer considered as an activity that may require special management.

Marine Fisheries Service (NMFS), and the U.S. Fish and Wildlife Service (USFS), the EPA has provided States and Tribes authority over their Clean Water Act permitting when appropriate.¹⁸

Although development and implementation of State water quality standards are subject to a section 7 consultation between NMFS and the EPA, as an added precaution, NMFS may review each individual NPDES permit application to confirm that listed species are not adversely affected by water quality impacts. If the proposed permit does not appear to meet State water quality standards, NMFS may object to issuance of the permit, and the State may ask the applicant to alter the permit to meet the standards. Although the State Agencies themselves issue the vast majority of NPDES permits, the EPA issues federal NPDES permits for tribal lands and for any discharges into federal ocean waters beyond state boundaries.

The NPDES contains general and individual permits. General permits cover multiple facilities within a specific category; whereas, individual permits are tailored for a specific discharge and analyzed on a caseby-case basis. The EPA developed a major/minor classification system for individual industrial and municipal NPDES permits to provide an initial framework for setting permit issuance priorities during the first and second rounds of NPDES permit issuance. Major permits almost always have the capability to impact receiving waters if not controlled. Minor permits may or may not, adversely impact receiving waters if not controlled. There are approximately 65,000 dischargers in the United States which have been issued NPDES permits. Currently, 7,500 of these, due to size or composition of wastewater or both are termed "major" permits. The remainder are termed "minor" permits.¹⁹

	Miles from mean low	Estimated Number of Facilities			
Area	water line	Minor	Major		
1	1	3	6		
1	5	5	11		
2	1	16	1		
2	5	47	6		
7	1	3	5		
/	5	5	6		
Source: 1	US EPA Water Discharge Pe	ermit Complianc	e System (PCS)		

 Table 2.1-1:
 NPDES Permits

Table 2.1-1 above presents the number of current NPDES permits for outfalls within one and 5 miles from the mean lower low water (MLLW) line within the identified critical habitat areas, which are most likely to have an effect on potential critical habitat. NPDES permitted outfalls are facilities holding

¹⁸ U.S. Environmental Protection Agency, Department of the Interior, and the Department of Commerce, Memorandum of Agreement Between the Environmental Protection Agency, Fish and Wildlife Service and National Marine Fisheries Service Regarding Enhanced Coordination Under the Clean Water Act and Endangered Species Act; Notice, Federal Register Vol. 66, No. 36, February 22, 2001.

¹⁹ USEPA, Office of Water. "National NPDES Minor Permit Issuance Strategy," Office of Water Enforcement and Permits, Permits Division, Technical Support Branch. January, 1986.

permits to discharge municipal and industrial wastes to surface water. While these amounts represent active past and present permit locations, we assume the general pattern of permitting locations is likely to continue into the future.

Section 403 of the Clean Water Act requires that NPDES permits for dischargers into the territorial seas, the contiguous zone and the oceans be issued in compliance with EPA's guidelines for determining the degradation of marine waters. Changes to the NPDES regulations on September 1, 1983, also provide that the Regional Administrator shall issue general permits covering discharges from offshore oil and gas facilities within the Region's jurisdiction. Ocean discharge criteria guidelines set forth criteria for determinations of unreasonable degradation and irreparable harm which must be addressed prior to the issuance of a NPDES permit. Some factors considered in a determination of unreasonable degradation are: The composition and vulnerability of biological communities, which may be exposed to such pollutants including threatened or endangered species; the importance of receiving water area to the surrounding biological community, including forage areas and migratory pathways; the existence of special aquatic sites, including marine sanctuaries and refuges, etc.; and marine water quality criteria developed pursuant to Section 304(a)(1) of the Clean Water Act.²⁰

2.1.3 Impacts of Critical Habitat Designation on NPDES Permitted Facilities

Leatherback critical habitat could impose modifications on NPDES permitted facilities, such as:

- Where federal permits are necessary, ensure discharge meets standards other than existing federal standards and regulations (EPA, CWA).
- Require measures to prevent or respond to a catastrophic event (i.e., using best technology to avoid unnecessary discharges).

Changes to discharge permits that may be required to accommodate leatherback critical habitat are unknown at this time. However, if changes were imposed, the goals would likely be to reduce the concentrations/levels/types of toxins into the environment inhabited by jellyfish species favored by leatherbacks.

Although there have been no formal consultations regarding water quality issues associated with leatherbacks to date, a number of such consultations have occurred with regard to other species that could be related to leatherback critical habitat, such as Pacific salmon species. NOAA Fisheries has consulted with EPA on various aspects of its approval of State Water Quality Standards, including development of Total Maximum Daily Loads (TMDLs), review of non-temperature related Water Quality Standards and cleanup of Superfund sites.

In general, the only project modification resulting from consultation for salmon or steelhead species pertained to water temperature controls. While NPDES-permitted facilities have always been required to adhere to certain temperature criteria associated with effluent discharge, the 2003 guidance has led to stricter standards where salmon and steelhead are known to spawn or rear. As a result, this analysis focuses on costs associated with the temperature criteria.

²⁰ USEPA, "The NPDES Permitting Process for Oil and Gas Activities on the Outer Continental Shelf." June 18, 1985.

The EPA and NOAA Fisheries authored guidance to States and tribes in 2003 on the development of temperature criteria deemed protective of salmon and steelhead. As a result, NPDES-permitted facilities in the Pacific Northwest are required to ensure effluent discharge does not raise the temperature in receiving waters above site-specific minimum temperature standards.²¹

This analysis estimates that if modifications to pollution discharge operations are required to comply with the temperature control criteria, NPDES-permitted facilities may identify and employ a number of temperature control procedures through Temperature Management Plans (TMPs). Control efforts may include process optimization, pollution prevention, land application, and/or cooling towers. The analysis estimates the operations and maintenance (O&M) costs and capital expenditures necessary to comply with the temperature control criteria.

Using EPA data, major facilities are assumed to require significant capital expenses to comply with the temperature criteria, while minor facilities are assumed only to require O&M expenditures. This analysis assumes that minor facilities will incur costs of \$0 to \$14,800 annually (2009\$) to comply with temperature control criteria, while major facilities will incur \$5,650 to \$37,000 annually in O&M costs.²² In addition, major facilities are assumed to incur capital costs of \$46,390 annually.²³ Based on EPA's sample of facilities all costs are assumed to incur uniformly over a 20-year period.

2.1.4 Summary of Economic Impacts to NPDES Facilities by Area

Table 2.1-2 presents a summary of our findings regarding the economic impacts arising out of special management considerations for NPDES-permitted facilities as a result of this designation. While NMFS consults on all federal and tribal permits, it does not necessarily consult on every state permit; however, for purposes of this analysis we assumed consultation on all permits. Therefore, these estimated costs are likely to be an overestimate of the true costs. With regard to minor facilities, Area 2 is estimated to be associated with the highest economic impacts related to management of pollutant discharge into water bodies.

²¹ U.S. Environmental Protection Agency (EPA). "Region 10 Guidance For Pacific Northwest State and Tribal Temperature Water Quality Standards." EPA 910-B-03-002, April 2003.

²² This analysis applied EPA's economic impact assessment to estimate modification costs for NPDES permitted facilities. See NMFS August, 2005 for more information.

²³ Science Applications International Corporation. 2003. *Economic Analysis of the Proposed Water Quality Standards Rule for the State of Oregon*. Reston, VA. EPA No. 68-C-99-252.; Adjusted to 2009 dollars using the U.S. Bureau of Economic Analysis, National Economic Accounts, National Income and Product Accounts table, 2009.

		Estimat	ed		Total Annualized Costs							
	D CC	Number of				T (1				Matan		
	Buffer	Facilitie		Incremental	Mino		TT: -1	Major	Ma	TT: -1-		
Area	Zone	Minor	Major	Score	Low	Mid	High	Low	Mid	High		
1	<1	3	6	0.3	\$0	\$7,000	\$13,000	\$94,000	\$122,000	\$150,000		
1	<5	5	11		\$0	\$11,000	\$22,000	\$172,000	\$223,000	\$275,000		
2	<1	16	1	0.3	\$0	\$36,000	\$71,000	\$16,000	\$20,000	\$25,000		
2	<5	47	6	0.5	\$0	\$104,000	\$209,000	\$94,000	\$122,000	\$150,000		
7	<1	3	5	0.3	\$0	\$7,000	\$13,000	\$78,000	\$102,000	\$125,000		
/	<5	5	6	0.5	\$0	\$11,000	\$22,000	\$94,000	\$122,000	\$150,000		
Total	<1				\$0	\$50,000	\$97,000	\$188,000	\$244,000	\$300,000		
Total	<5				\$0	\$126,000	\$253,000	\$360,000	\$467,000	\$575,000		

Table 2.1-2: Summary of Economic Impacts to NPDES Facilities by Area

2.2 Economic Impacts of Critical Habitat Designation on Agricultural Pesticide Application

2.2.1 Description of Threat

NMFS has identified agricultural pesticide application as a specific non-point source pollution activity as a potential threat to leatherback critical habitat in the three coastal areas under consideration: Areas 1, 2, and 7. This activity may affect prey resources through contamination of all stages of jellyfish, including bioaccumulation of toxins through small prey ingestion. Pesticide application could affect water quality and prey resources available within some of the areas being considered for critical habitat.

2.2.2 Regulatory Environment & Extent of Activity

Many common pesticides have carcinogenic/mutagenic properties (USEPA, 2005). Pesticides are also known to cause adverse effects in wildlife by disrupting endocrine systems (Kavlock *et al.*, 1996). Even at levels below those expected to result in direct mortality, exposure to these compounds may have unknown mutagenic, developmental and reproductive effects through consumption of contaminated prey. Unlike direct toxicity effects, the dose response relationship for carcinogenicity and endocrine disruption for many pesticides is not known and therefore the spatial extent from shore where these exposures would be discountable cannot be determined. Although pesticides are likely to be extremely diluted by the time they disperse into the open, marine environment, contaminants can be collected in nearshore areas driven by bathymetry or orography (submerged physical features).²⁴ As a result, any exposure to these compounds could conceivably result in adverse impacts to prey consumed by leatherbacks in an area concentrated by pesticides. Therefore, it is reasonable to assume that there may potentially be adverse impacts to leatherbacks and their habitat in any nearshore waters receiving runoff from lands where pesticides are used.

2.2.3 Impacts of Critical Habitat Designation on Agricultural Pesticide Application

In July 2002, a federal court ordered EPA to consult with the USFWS and NMFS to ensure that the registration of 54 pesticide active ingredients under the Federal Insecticide, Fungicide, and Rodenticide

²⁴ Personal communication with Steve Bograd, NMFS SWFSC (2009).

Act (FIFRA) complies with section 7 of the ESA. In January 2004, the EPA was enjoined from authorizing the application of a set of pesticides within certain distances from "salmon-supporting waters."²⁵ The EPA was required to consult with NMFS concerning possible adverse effects of pesticide applications on salmon and steelhead protected under the ESA. The court imposed two types of restrictions on application of pesticides covered in the lawsuit. For aerial applications, no pesticides can be applied within 100 yards of "salmon-supporting waters"; for ground applications, the distance is 20 yards.²⁶ Although unknown at the present time, given the primarily marine environment inhabited by leatherbacks, some management measures could be placed on the application to restrict pesticides to protect leatherback critical habitat in the future.

NMFS has now completed 4 consultations on registration of 24 of 37 pesticide active ingredients that were part of the litigation. NMFS concluded that the registration of these pesticides was likely to jeopardize most listed salmon populations and was likely to adversely modify critical habitat. In one consultation, NMFS identified reasonable and prudent alternatives that included, among other things, buffers of 1000 feet for aerial application and 500 feet for ground applications. EPA has not yet implemented these restrictions.

This analysis assumes that the court-ordered injunction restricting pesticide use for the protection of salmon and steelhead species, will provide some protection in leatherback critical habitat areas, depending on the pesticide and degree of dispersal (e.g., pesticides that are carcinogenic or disrupt the endocrine system may pose a risk throughout the critical habitat area). Of the 24 pesticides NMFS have consulted on, only one thus far has had endocrine disrupting potential.

To the extent that management actions are needed for herbicide use, they could include similar best management practices for application of herbicides that were outlined in a consultation on salmon and steelhead species through minimizing the amount and type of pesticide that enters estuarine and marine waters.²⁷ The following measures may or may not be appropriate for reducing impacts to coastal waters designated as critical habitat:

- All vegetation removal will be restricted to above the ground surface, thus leaving the root systems intact and retaining bank stability.
- Within 100 ft of each side of any waterway vegetation taller than 15 ft may be cut to the 15 ft level.
- No garlon will be applied with a 100-foot buffer on either side of all streams with ESA-listed fish. Rodeo may be used within this area.
- Trained individuals will apply herbicides using only low pressure spot spray and direct wicking application methods. All herbicide applications will be conducted in accordance with label instructions.

²⁵ Washington Toxics Coalition, et al. v. EPA, C01-0132 (W.D. WA), 22 January 2004.

²⁶ Ibid.

²⁷ NMFS, Northwest Region, Endangered Species Act Section 7 Formal Consultation and Magnuson-Stevens Fishery Conservation and Management Act Essential Fish Habitat Consultation on the Port of St. Helens Industrial Outfall and Portland General Electric Power Plant, Port Westward Industrial Park, Columbia River, Columbia County, Oregon (Corps No. 200200448), August 1, 2003.

- Spray activities will only occur during dry, calm weather conditions to prevent drift and runoff. No spraying will occur during winds greater than five mph or during rain events. No spraying of the herbicide will occur if rain is forecast within 24 hours.
- Spill response procedures have been developed and reviewed with each applicator before commencing herbicide application operations.
- All chemical storage, chemical mixing, and post-application equipment cleaning is completed in such a manner as to prevent the potential contamination of any perennial or intermittent water body, unprotected ephemeral waterway, or wetland.
- Use only those sprayers with a single nozzle, such as backpack or hand sprayers, to spray the herbicide in the riparian zone.
- All hand operated application equipment is leak and spill proof.

Table 2.2-1: Estimate of Acres under Farming in Areas Potentially Affected

	Estimated Prime Acres of Farmland	
	1 mile from MLLW & 100 yards from water	5 miles from MLLW & 100 yards from
Area	body (acres)	water body (acres)
1	6,289	22,462
2	4,913	26,411
7	1,027	2,755
Source: USDA NRCS Soil Survey Geographic Database (SSURGO)		

Values of cropland in the form of market value of crops sold were estimated using county data from the 2007 Census of Agriculture (USDA, NASS 2009). The analysis determined a foregone value from sales of crops due to pesticide restrictions.

Table 2.2-2: Estimated per Acre Impacts by Area

Area	Estimated Value of Cropland per Acre
1	\$2,200
2	\$300
7	\$1,900

2.2.4 Summary of Economic Impacts to Agricultural Pesticide Application by Area

In our proposed economic report and proposed rule, we provided a summary of potential impacts to agricultural pesticide application within one and 5 miles of the MLLW within critical habitat areas. Through consulting NMFS Biological Opinions issued since the publication of the proposed rule, these costs were found to be overestimated. We originally assumed the prohibition of pesticides would result in total crop loss, however, it is possible that the farmland may be used for other purposes, and the proposed analysis did not include alternative uses of the farmland. Further, it has been stated by NMFS that the total crop loss is not expected to occur, even with pesticide prohibitions. Given the uncertainty of the impact of restricted or prohibited pesticide use, we have determined that a direct cost analysis of the impacts of this critical habitat designation on the agricultural industry is not possible at this time, therefore, the analysis in our final economic report removed these costs entirely.

2.3 Economic Impacts of Critical Habitat Designation on Oil Spill Response

2.3.1 Description of Threat

NMFS has identified oil spill response as a potential threat to the essential features of the areas being considered for leatherback critical habitat in all nine areas. Oil spills may have localized impacts affecting prey (toxicity of oil on coelenterates and/or the use of chemical dispersants, *in situ* burning to respond to the spill). Oil spills most often result from vessels, i.e., vessels grounding, collisions with another vessel or a structure, sinking. Oil spills can also be the result of oil exploration activities, drilling or operations at oil rigs. The type of response is dependent on a number of factors including the type of oil spilled, the trajectory of the oil and threats to the shoreline and species, and ocean conditions at the spill site. The three types of response are the use of dispersants, *in-situ* burning, and skimming. Dispersants are chemicals that reduce the oil/water interfacial tension, thereby decreasing the energy needed for the slick to break into smaller droplets and mix into the water column. Dispersants are generally applied within the first hours of the spill, via aircraft or vessel, and are intended to reduce the amount of oil on the surface. Dispersed oil generally does not penetrate below approximately 10 meters in measurable concentrations. The dispersants allowed along the West Coast (Corexit 9500 and Corexit 9527) may be toxic to jellyfish and the prev they depend on such as the sensitive life stages of zooplankton, although most studies have been conducted on juvenile fish and invertebrates. Dispersing oil into the water column may increase its availability and impact to jellyfish below the water surface, but this is expected to be localized. Sub lethal effects to jellyfish by use of dispersants could include depressed reproductive success and growth, but this is unknown and therefore speculative.

In situ burning removes oil from the water surface by burning it in place and typically the oil is contained with a fire-resistant U-shaped boom, towed from the main spill and burned. As with dispersants, burning oil at sea is most effective when it is conducted early in a spill and in calm seas (seas greater than a meter) since the natural emulsification and evaporation will confine the oil less. Burn residue is produced, and responders attempt to collect as much as possible before it sinks. Any jellyfish in the surface or uppermost layers of the water column in the area of a burn may be vulnerable, although it would be likely localized and the surface area is likely to be very small relative to the total surface area and depth of a given body of water. Field and laboratory studies have shown that, because almost all of the heat during a burn is directed upward and currents and waves continuously exchange the water beneath the burn, inhabitants of the underlying water column are not adversely affected (Hoff and Shigenaka 2003). The effects of oil on jellyfish are largely unknown, but Milton *et al.* (2003) notes that leatherbacks may be less at risk than hard-shelled turtles that feed on species that are known to bioaccumulate petroleum hydrocarbons such as crustaceans and mollusks.

2.3.2 Regulatory Environment & Extent of Activity

The United States Coast Guard (USCG) has the authority to respond to all oil and hazardous substance spills in the offshore/coastal zone, while the EPA has the authority to respond in the inland zone. The EPA and the USCG oversee the Oil Pollution Prevention regulations promulgated under the authority of the Federal Water Pollution Control Act (also known as the Clean Water Act). Among other issues, these regulations address requirements for Spill Prevention, Control and Countermeasure Plans and Facility

Response Plans for offshore and onshore oil producers and carriers. The Facility Response Plans are submitted to the USCG for the transportation-related portion of the facility and to EPA for the non-transportation portions. The National Oil and Hazardous Substances Pollution Contingency Plan (or National Contingency Plan), is the Federal government's guideline for responding to both oil spills and hazardous substance releases. Regional Response Team IX (RRT-IX) is a formal organization of tribal, state and federal agencies as defined by the National Contingency Plan. Co-chaired by the EPA and the USCG, RRT-IX is responsible for ensuring that state and federal resources are available when needed for emergency response within the states of Arizona, California and Nevada and the 146 tribal nations, and that the multi-agency relationships and coordination systems exist to support these emergency response efforts (The Regional Contingency Plan for federal region IX).²⁸ One of the key responsibilities of the RRT is development of dispersant use plans. The RRT is responsible for conducting the net environmental benefit analysis on the use of dispersants which is, in turn, used by the USCG and EPA during development of a response.

Across the West Coast, Area Contingency Plans provide guidelines and information to be used during response. The Northwest Area Contingency Plan (NWACP), developed by the Northwest Area Committee, serves as the primary guidance document for responders in Washington, Oregon, and Idaho to oil spills and hazardous materials spills. Under the NWACP, the USCG has the authority to respond to all oil and hazardous substance spills in the coastal zone, the EPA has authority to respond in the inland zone, and the States, themselves, respond within state boundaries. The NWACP also contains the "Northwest Area Shoreline Countermeasures Manual and Matrices," which describes northwest area-specific habitat and response strategies that should be recommended or conditionally recommended in case of an oil spill.²⁹ In California, there are three ACP's that cover the six USCG areas in the state; San Diego, Los Angeles/Long Beach and San Francisco.

NOAA's Emergency Response Division (ERD), part of NOAA's Office of Response and Restoration facilitates spill prevention, preparedness, response, and restoration at national and local levels. Information on present and past spills and summary documents are provided on their website and serve as a communications tool to various responders, federal and local planners (http://www.incidentnews.gov). The ERD has responded to nearly every major marine spill in the United States over the last 25 years.

Because oil spill response is a Federal activity, it is subject to ESA section 7. In 2001, an "Inter-agency Memorandum of Agreement (MOA) Regarding Oil Spill Planning and Response Activities under the FWPCA's National Oil and Hazardous Substances Pollution Contingency Plan and the Endangered Species Act" was signed by NOAA, USFWS, EPA, and USCG. The purpose of the MOA is to increase cooperation and understanding among agencies involved in ESA compliance at every stage in oil spill planning and response. The MOA outlines procedures to streamline the ESA compliance process before, during, and after an incident.

²⁸ California Department of Fish and Game. *The Regional Contingency Plan for federal region IX*. Accessed at: http://www.dfg.ca.gov/ospr/response/acp/marine/2005RCP/RCP102405.pdf.

²⁹ NOAA Fisheries, Endangered Species Act Section 7 Programmatic Formal Consultation and Magnuson- Stevens Fishery Conservation and Management Act Essential Fish Habitat Consultation for the Oil Spill Response Activities Conducted Under the Northwest Area Contingency Plan (NWACP), November 6, 2003.

Responses to spills vary greatly depending on variables that cannot be predicted in advance, thus spill response is subject to emergency section 7 consultation. However, in November 2003, NOAA issued a programmatic biological opinion to EPA and USCG that addressed most response actions undertaken by these agencies to limit or prevent oil discharges and their effects on listed species and their habitats in the Pacific Northwest. This consultation included sea turtle species along with numerous salmon species, whale species, and Steller sea lion. The consultation found that many oil spill response activities could be treated programmatically, but that some actions which were "less predictable" were identified as potentially requiring individual consultation.³⁰ The biological opinion expired and has not been re-initiated.

Many oil spills are the result of ship groundings or collisions. Following the grounding of the *Exxon Valdez* in 1989, which spilled 11 million gallons of water in Prince William Sound, Alaska, Congress passed the Oil Pollution Act (OPA) of 1990. The OPA addresses oil pollution liability and compensation, international oil pollution prevention and removal and an oil pollution research and development program. Following passages of OPA, the U.S. unilaterally imposed a double hull requirement for both new and existing oil tankers, according to the vessels' age limits and according to deadlines imposed for phasing out single-hulled tankers. Through the International Convention for the Prevention of Pollution from Ships (MARPOL), the International Maritime Organization established double hull standards for all Member States, requiring all oil tankers with a deadweight tonnage of 600 tons be constructed with double hulls or an equivalent design. Existing single hull tankers also had requirements imposed on them to reduce the risk of oil spills from collisions or groundings. A review of oil spills suggests that the passage of regulations and an International Convention is likely a large reason for a reduction in offshore oil spills.

The extent of oil spills can be determined by the occurrence of oil spills and the quantity of oil spilled. The USCG records indicate that nationally, 95 percent of oil spills are spills of less than 1,000 gallons.³¹ "Major" spills are 10,000 gallons or more. "Serious" spills are 25-10,000 gallons.³² National data from 1992-2001 on oil spills is presented in Table 2.3-1. The data shows that the number of spills and amount of oil spilled has generally decreased since 1997.

³⁰ NOAA Fisheries, Endangered Species Act Section 7 Programmatic Formal Consultation and Magnuson- Stevens Fishery Conservation and Management Act Essential Fish Habitat Consultation for the Oil Spill Response Activities Conducted Under the Northwest Area Contingency Plan (NWACP), November 6, 2003.

³¹ National Marine Fisheries Service (NMFS). *Economic Impacts Associated with Potential Critical Habitat Designation for the Southern Resident Population of Killer Whales*. November 7, 2006.


³² Puget Sound Water Quality Action Team. *State of the Sound 2004.* Accessed at:


http://www.psparchives.com/publications/puget_sound/sos/04sos/PSATSOS2004.pdf on June 9, 2009.

Year	Number of Spills	Gallons Spilled				
1992	708	1,585,955				
1993	618	2,060,422				
1994	662	3,945,487				
1995	505	1,899,525				
1996	521	3,146,931				
1997	395	1,019,809				
1998	436	798,832				
1999	367	1,315,204				
2000	353	838,044				
2001	253	501,045				
Source: U.S. C	oast Guard (USCG). "Oil	Spill Response Research				
& Development	Program, A Decade of Ac	chievement." U.S. Coast				
Guard Research	Guard Research & Development Center, Groton, CT 06340-6048,					
Report No. CG	Report No. CG-D-07-03. Accessed at:					
http://www.uscg	g.mil/hq/cg9/rdc/Reports/2	003/CGD0703Report.pdf				

Table 2.3-1: U.S. National Oil Spill Data

In Washington, between 2001 and 2006, there were 5 oil spills, totaling about 100,000 gallons of oil spilled. This is a significant decrease from previous years: 1996-2000 had about 13 such oil spills totaling almost 800,000 gallons of oil; 1991-1995 had 6 oil spills that totaled about 1.25 million gallons of oil and 1986-1990 had 14 oil spills totaling about 1.0 million gallons of oil (see figure 2.3-1, where each colored band indicates a distinct spill over 10,000 gallons in five year periods).





³³ Washington State Department of Ecology. 2006 Annual Report of Spill Prevention, Preparedness and Response Program. Accessed at: http://www.ecy.wa.gov/pubs/0708002.pdf on April 2009.

In Washington, vessel inspections occur to check vessel compliance with state spill prevention regulations and to provide technical assistance. Investigations are also conducted to determine causes of incidents. In 2006, there were 1,587 vessel inspections (see figure 2.3-2). The figure shows a trend over the years of increased inspections correlating with a decrease in incident rates. Some of the recent drop in oil spill incidents can be attributed to a rise in the frequency and quality of inspections.





Figure 2.3-2 Vessel incident rate and vessel inspections from 1998-2006

Figure 2.3-3 shows vessel incident rates. Incident rates were calculated as the percentage of trips in which large commercial vessels experience significant problems, such as an oil spill or a loss of propulsion or steering, out of the total number of transits in state waters. The incident rate has been around one percent from 2004-2006. There were 30 spills from large commercial ships during 2006. Improved compliance by large vessels has led to a statewide drop in oil spills and near misses

Figure 2.3-3 Vessel incident rate from 1998-2006 for all Washington waters



In California, total gallons of oil spills have been less than 100,000 gallons per year from 1995-1999 (see Figure 2.3-4).




Figure 2.3-4 Volume of California oil spills (1990-1999)³⁴

In Washington, the Department of Ecology (DOE) has a Spill Prevention, Preparedness and Response Program, which spends \$14.0+ million/year, with most going to salaries, etc., and approximately \$8.0 million/year covering spill prevention, preparedness, response, and damage assessment. In 2006, the DOE and their partners/contractors responded to over 40 spills, and monitored three disabled container ships in the marine environment, none of which spilled oil. Over the years, the number of spills has decreased, likely due to stricter regulations and requirements as well as better preparedness. Oregon's Department of Environmental Quality has a similar program to handle minor and major spills and levies annually per vessel, dredge, or facility to pay for their marine spill response program. In California, the Office of Spill Prevention and Response (OSPR) was created after the Exxon Valdez spilled in 1989 and then another large vessel spilled 300,000 gallons of crude oil off Southern California in 1990. OSPR has the California Department of Fish and Game's public trustee and custodial responsibilities for protecting, managing and restoring the State's fish, wildlife, and plants. It is one of the few State agencies in the nation that has both major pollution response authority and public trustee authority for wildlife and habitat. This mandate ensures that prevention, preparedness, restoration and response will provide the best protection for California's natural resources. In the last few years, the largest oil spill took place in San Francisco Bay when a container ship, the M/V Cosco Busan collided with a pier and dumped 50,000+ gallons of heavy fuel oil in November, 2007.

³⁴ Natural Resource Defense Council (NRDC). *Oil Spills*. Accessed at: http://www.nrdc.org/greengate/wildlife/oilf.asp, on September 15, 2008.

2.3.3 Impacts of Critical Habitat Designation on Oil Spill response

Designation of leatherback critical habitat could impose modifications related to oil spill response, such as:

- Conduct surveys prior to oil spill response (e.g., use of boom, sorbents, skimmers, dispersants, *in situ* burning), to minimize impacts to leatherback prey.
- Modify the response to oil spills (e.g., boom, dispersants, *in situ* burning) in areas where leatherback prey are found to be present in significant quantities and condition (e.g., preferred prey, such as *Chrysaurus fusescens*)

Impacts from modifications are difficult to quantify due to the unpredictability of oil spills but may include costs from training and contingency planning requirements, which already take place to a large degree, as well as surveys (aerial, vessel, etc.) prior to or during oil spill response to minimize impacts to leatherback critical habitat. Costs could also be incurred from use of an alternate oil spill response methodology to minimize impacts to the leatherback prey PCE.

There are many factors that influence the decision to respond to an oil spill, including whether it may or may not be possible to physically respond to a spill, particularly in offshore areas, depending on weather and other factors. A number of factors are considered, but generally, the most common method for controlling and eliminating surface oil is the use of vessels with oil skimming capabilities, referred to as mechanical recovery. In rare cases where the seas are relatively flat, in-situ burning may be employed. The effectiveness of both mechanical recovery and in-situ burning operations dramatically decreases with sea states above a 2 foot chop or 5 to 6 foot swell. Sea states off the West Coast, particularly in the offshore areas, preclude the use of mechanical clean-up techniques, thus the use of chemical dispersants is the only option offshore. As noted previously, the impact of dispersants and dispersed oil on jellyfish is not well known, but putting oil into the water column via dispersants may actually be more detrimental to jellyfish than leaving it at the surface and relying on natural cause evaporation of the oil (i.e., not responding to a spill). In the draft economic report, we considered the possible effect of oil on leatherback passage, but our analysis is limited to the prey PCE and it is difficult to determine what, if any, special management may be necessary for spill response. In terms of the prev PCE, at this time, NMFS could not identify alternative methods that may be necessary to protect the prev PCE during a response to an oil spill.

2.3.4 Summary of Economic Impacts to Oil Spill Response Activities by Area

In our proposed rule and proposed economic report, we made the assumption that if critical habitat were designated, then the USCG may be more likely to launch a response to clean up the oil using chemical dispersants or other response techniques, and we developed associated costs for response based on this assumption. However, after additional research on oil spill response as well as firsthand experience in spill response and drills, we have determined that making this assumption does not accurately reflect what is likely to occur in the event of an oil spill. That is, the existence of leatherback critical habitat is likely to play a small part in the decision making on whether to respond and how to respond. Each spill is unique, and response is determined based on the type of oil, sea state, availability of mechanical or chemical materials, and risk to resources, particularly shoreline resources. Along the U.S. West Coast, NMFS is becoming more actively engaged in oil spill response planning and is reviewing ACPs and

RCPs and providing information on protected species, including leatherbacks. Oil spill response is not like other Federal activities considered in this final rule. The ESA section 7 occurs after the Federal activity (spill response) has occurred, so there is limited opportunity to change activities during a response. NMFS' engagement at the ACP and RCP level is likely the optimal means of raising awareness of leatherback critical habitat and working within the spill response community to make changes to response protocols to protect critical habitat. At this time, we do not know what types of activities we would request that USCG modify to protect critical habitat during an oil spill response; therefore we cannot assign a dollar value to this activity.

Although we have determined to qualitatively, rather than quantitatively assess impacts of an oil spill response, we feel compelled to revise information that was published in the proposed rule to reflect what was learned from the multi-agency response to the Deepwater Horizon (DWH) oil spill. Table 2.3-2 below presents a summary of potential impacts from the cleanup of oil spills within the critical habitat areas. Because all areas used the assumptions for number of occurrences and quantity of spill, the results are similar, although costs may be higher if a spill were to occur along the western portion of areas 2 and 7 as these areas are farther from shore and may be less accessible than the nearshore areas.

	Estimated # of	Incremental	Total Annu	Total Annualized Impacts			
Area	gallons/year	Score	Low	Mid	High		
1	20,000	0.3	\$221,000	\$444,000	\$667,000		
2	20,000	0.3	\$221,000	\$444,000	\$667,000		
7	20,000	0.3	\$221,000	\$444,000	\$667,000		
Total			\$663,000	\$1,332,000	\$2,001,000		

Table 2.3-2: Summary of Economic Impacts from Oil Spill Cleanup by Area

The cost estimates in this final economic report are higher than those presented in the proposed rule and draft economic report. The proposed rule and draft economic report included costs associated with spill response based upon a model developed and published by Dagmar Etkin (1999). The costs associated with spill clean-up using the model were quite low, less than \$100,000. Since publication of the proposed rule, two members of the CHRT have been deployed to the Gulf of Mexico to help in the multi-agency response to the Deepwater Horizon (DWH) oil spill. This experience brought invaluable insight into the nature of oil spill response and the costs associated with response and prompted us to review the oil spill response and costs and engage the USCG and staff from NOAA's Emergency Response Division and Office of Response and Restoration to determine if the costs from the model were reasonable. Through this review it was determined that the costs were too low. We worked with staff from the Incident Management Division of Sector Los Angeles and Long Beach of the USCG to develop more reasonable cost estimates and those are provided in this economic analysis. The costs provided do not include the total costs, but only the expenses for USCG assets to respond. Additional costs not captured would include survey planes, vessels, staff on the water and coordinating operations on land, and waste management. Thus the costs are a minimum estimate based upon the different methods used and the assumptions made in terms of spilled oil. The cost estimates range from over \$662,400 to over \$2,000,000. Again, it is important to note that these are not the total costs, but do indicate that the figure used in the proposed rule were indeed off by at least one order of magnitude.

As noted above, these estimated costs are provided to update work presented in the draft economic report. NMFS has determined that these costs are not a reasonable means of measuring the economic costs of oil

spill response as they are based on the faulty assumption that the designation of leatherback critical habitat would compel the USCG to take action, respond to an oil spill, that they may otherwise not do. Instead, we must consider what changes the USCG may need to make during a spill response in order to protect leatherback critical habitat. That is, the response would be an action that they would take regardless of leatherback critical habitat and our task is to identify how that activity may need to be modified. At this time, we do not have sufficient information on the effects of oil spill response to speculate on the types of changes and associated costs that may be required. Because there is a high level of uncertainty associated with the types of changes to oil spill response that may be the result of leatherback critical habitat, this analysis can present only a qualitative discussion.

Caveats

In general, cleanup costs decrease significantly on a per-ton basis; that is, a larger spill will be much less expensive per ton than a smaller spill, given the costs associated with setting up the response, bringing in equipment, labor, etc. In addition, use of dispersants offshore to prevent impacts to the shoreline is typically less expensive than shoreline cleanup (Etkin 1999).

2.4 Economic Impacts of Critical Habitat on Power Plants

2.4.1 Description of Threat

NMFS has identified power plants as a potential threat to leatherback critical habitat in two study areas: Areas 1 and 7. One potential threat from power plants to prey resources of leatherbacks is the plants' use of coastal waters for cooling and subsequently discharging heated water back into the marine environment. This may involve the discharge of up to one million gallons of heated sea water into the receiving waters. This water may be warmer than the ambient water temperatures and therefore may affect jellyfish survivability, recruitment into benthic habitat, and development, as well as prey resources (e.g., mesozooplankton, fish larvae, etc.). The impacts of power plant discharge of higher water temperature (and potentially treated water) are unclear. The release of thermal effluents that may raise water temperature in leatherback habitat has also been shown to cause jellyfish blooms (see Purcell *et al.* 2007), which may be a positive effect on the prey PCE and therefore leatherback habitat.

Power plants may also entrain jellyfish through their intake system, although because entrainment may be detrimental to the operation of the plant, power plants likely have methods to reduce or remove jellyfish (e.g., see write-up on individual power plant operations below). The effects of entrainment on prey resources are likely very localized and affect a small proportion of the coastal population of jellies. The effects of power plants is unclear, as Purcell *et al.* (2007) report that structures associated with coastal power plants may serve as substrate for the polyp stage of jellyfish, which may contribute to increases in jellies, thus a benefit to the prey PCE in leatherback habitat.

Most plants do have a spill prevention control and countermeasure plan so concerns over possible oil spills or pollution into the water are minimal.

2.4.2 Regulatory Environment and Extent of Activity

The Nuclear Regulatory Commission regulates commercial nuclear power plants and other uses of nuclear materials, such as in nuclear medicine, through licensing, inspection and enforcement of its requirements. The California Energy Commission has multiple duties, such as: licensing thermal power plants 50 megawatts or larger and planning for and directing state response to energy emergencies.

Section 316(a) of the CWA requires the thermal component of a discharge be limited, taking into account the interaction of this thermal component with other pollutants, to assure the protection and propagation of balanced, indigenous populations of shellfish, fish, and wildlife in the receiving water. California State's Water Quality Control Plan for the control of temperature in coastal waters requires that elevated temperature effluent from existing discharges, "shall comply with limitations necessary to assure protection of the beneficial uses and areas of special biological significance."³⁵

³⁵ State Water Resources Control Board. Water Quality Control Plan for the control of temperature in the coastal and interstate waters and enclosed bays and estuaries of California. Available online at: http://www.swrcb.ca.gov/water_issues/programs/ocean/docs/wqplans/thermpln.pdf

Section 316(b) of the CWA requires that the location, design, construction, and capacity of cooling water intake structures, such as for DCNPP, must reflect the best technology available to protect aquatic life for large power utilities through the 316(b) Phase II regulation, promulgated in 2004. In 2007, EPA suspended the requirements of the 316(b) Phase II regulation because of the decision issued by the U.S. Court of Appeals for the Second Circuit, Riverkeeper, Inc. v. EPA, 475 F.3d 83 (2nd Cir. 2007). In November 2010, EPA signed a Settlement Agreement with Riverkeeper regarding rulemaking dates for EPA to set technology standards for cooling water intake structures for existing facilities under Section 316(b) of the CWA. EPA agreed to propose standards by March 14, 2011, and after considering public comments, to take final action by July 27, 2012. On March 11, 2011, the parties agreed to an amendment to the settlement agreement to extend the date for the proposed rule to March 28, 2011.

The State of California has adopted a "Policy on the Use of Coastal and Estuarine Waters for Power Plant Cooling,"³⁶ which establishes clear standards to implement the Clean Water Act in a consistent manner and thereby reduce the harmful effects associated with the cooling water intakes on life in the ocean and estuaries. Although entrainment is addressed by provisions of the statute other than critical habitat, these studies are relevant because a reduction in intake will result in an equivalent reduction in outflow, which contributes to addressing the 316(a) thermal discharge requirement.

This analysis uses data provided by the California Energy Commission, to identify power plants that could be affected by the critical habitat designation.³⁷ There are 7 power plants within the critical habitat areas. The Diablo Canyon Power Plant, which is located in San Luis Obispo County, CA near Avila Beach, is the only nuclear power plant within the area of critical habitat (Area 7). The activities of non-nuclear power plants, while not managed by a federal agency, may still be subjected to a section 7 consultation. For example, the 11 non-nuclear power plants off the coast of California have applied for a "Letter of Authorization" under the MMPA to take pinnipeds incidental to their operations (entrainment of marine mammals in their intake structures, causing serious injury/mortality). In addition, these power plants may entrain sea turtles, and as such, 7 of these power plants have already applied for a section 10 permit under the ESA to take sea turtles. Because NMFS has proposed to issue these permits to the non-nuclear power plants, a section 7 consultation with NMFS is underway. At this point, whether this section 7 consultation would include an analysis of the effects of the cooling water discharge on potential leatherback critical habitat is unclear, but because there is a potential federal nexus, we are including non-nuclear coastal power plants in this analysis.

The following is a list and brief description of the coastal power plants in California. There are no power plants located along the coasts of Oregon and Washington.

AREA 1 Moss Landing Power Plant (MLPP)

```
http://www.swrcb.ca.gov/water_issues/programs/ocean/cwa316/docs/policy100110.pdf.
```

³⁶ SWRCB. 2010. Statewide water quality control policy on the use of coastal and estuarine waters for power plant cooling. October 1, 2010. Available online at:

³⁷ California Energy Commission. *California Statewide Plants map*. Accessed at: http://www.energy.ca.gov on April 20, 2008.

The MLPP is a 2,590-MW facility located on the eastern shoreline of Moss Landing Harbor in Monterey County, California, about 177 km south of San Francisco. Moss Landing Harbor is located approximately midway between the cities of Santa Cruz and Monterey and is open to Monterey Bay. The MLPP has two separate intake structures in Moss Landing Harbor for withdrawal of cooling water that is necessary to remove excess heat from the power generating process. The intake that services the newly operational Units 1 and 2 (2002) was modernized from its original configuration after the original Units 1 through 5 were retired (1995). A second intake structure services operating Units 6 and 7. The total flow of cooling water is approximately 850,000 gpm. Discharge from all the Units is carried out of the plant in two 3.66-m ID subsurface conduits located in Monterey Bay 731 m from the plant, about 183 m offshore.

AREA 7

Diablo Canyon Power Plant (DCPP)

DCPP is owned and operated by Pacific Gas and Electric Company (PG&E), and is a nuclear-powered, steam-turbine power plant with a rated output of 2,200 MW of electricity. The power plant draws in seawater from a constructed intake cove through a cooling water system to provide cooling for power plant operations. Four circulating water pumps combine to produce a cooling water flow of 1,704,000 gpm. On the ocean side of the intake structure, a concrete curtain wall extends approximately 2.4 m below mean sea level to prevent floating debris from entering the structure. Seawater entering the intake structure passes through one of 16 sets of bars racks designed to exclude large debris from the forebays. The bar racks consist of vertical rows of steel bars placed about 8.0 cm apart. The underwater portion of the bar racks is approximately 10 m high depending on tide. Two of the bar racks are 1.5 m wide (ASW bar racks), while the other 14 are 3.1 m wide (CWP bar racks). The cooling water is returned to the ocean via stair-step weir structure that opens on the eastern end of Diablo Cove.

This power plant may affect prey resources due to discharges of 1,704,000 gallons per minute (gpm) of sea water into Diablo Cove. The cooling water discharge is into Diablo Cove. In order to control biofouling, part of the auxiliary salt water system may be taken out of service and filled with "firewater" (approximately 40,000 gallons), which will be discharged – this takes place approximately once per month for approximately 9 hours – effects on the receiving water, etc. are being monitored. In addition, the plant may discharge low levels of chemical wastes, low-level radioactive wastes (treated and sampled for compliance with discharge limits) and storm water runoff. Leakages could occur from operation, maintenance and testing. The plant does have a spill prevention control and countermeasure plan.

Morro Bay Power Plant (MBPP)

The MBPP is a 1,030-MW facility owned located within the city of Morro Bay, San Luis Obispo County, California, near the eastern shore of Morro Bay Harbor. MBPP is proposed for modernization involving the replacement of the existing four steam-electric generation units (Units 1 through 4) with two state of the art combined cycle systems composed of two gas turbines and a steam turbine each. The modernized facility will have a smaller physical footprint, will utilize substantially less cooling water, and will produce more electrical power than the existing facility. The CWS for the plant consists of an intake structure which draws water from Morro Bay and an outfall structure which discharges water into Estero Bay (Pacific Ocean). The existing seawater intake structure located on the east shore of Morro Bay Harbor houses 8 cooling water pumps (two pumps per unit) and related auxiliary equipment and provides cooling water to the condensers of the four existing units. The current capacity of the CWS is 464,000

gpm, which would be reduced to 330,000 gpm following modernization. Should the plant be modernized in the future as proposed, the combined cycle units will utilize the existing intake structure though the traveling screens and pumps will be reconfigured.

Cooling water is returned to the ocean via a canal supplied by three separate underground tunnels. Units 1 and 2 share a common cooling water discharge tunnel that runs about 1,080 m from the condensers to a short 84 m outfall canal on Estero Bay just north of Morro Rock. Units 3 and 4 each have separate, parallel 1,230 m long discharge tunnels that also discharge into the outfall canal on Estero Bay.

Reliant Energy Mandalay Generating Station (REMGS)

REMGS is a 577 MW-facility owned located on the southern California coast approximately 4.8 km west of the city of Oxnard. The plant consists of two steam-electric generating units, each rated at 215 MW, and one gas turbine unit rated at 147 MW.

Ocean water for cooling purposes is supplied via a single cooling water system. Cooling water is drawn into the plant through Edison Canal, which originates approximately 4.2 km away at the northern end of Channel Islands Harbor in Oxnard, California. The capacity of the CWS is 176,000 gpm. Four circulating water pumps with a total capacity of 176,000 gpm direct cooling water flow to a screening facility within the plant. Water passes through trash bars and vertical sliding screens which prevent debris, fish, and invertebrates from entering the CWS. The trash bars consist of vertical steel bars with 5.7 cm openings which prevent large debris from moving further through the CWS. Beyond the trash racks, the water is conveyed through two sets of vertical sliding screens with 0.95 cm mesh for removal of small debris, fish, and macro-invertebrates.

The cooling water is then pumped to four horizontal centrifugal circulating pumps set in a dry well. Leaving the pumps, water flows to the main condensers through four 1.4 m ID pipes. Flows from the condensers are then joined in a 2.7 m ID discharge pipe, and then into a 61.0 m long rock-lined canal, where it flows across the beach at a velocity of 0.8 m/s into the ocean. Products of other plant systems join the cooling water stream prior to discharge.

Reliant Energy Ormond Beach Generating Station (OBGS)

Reliant Energy Ormond Beach Generating Station (OBGS) is a two-unit, 1,500 MW gas-fueled, steamelectric generating facility located near Oxnard, California. Ocean water for cooling purposes is supplied via a single cooling water system. The facility consists of two gas-fueled steam-electric units fed with cooling water via the CWS. Four circulating water pumps operate with a total capacity of 476,000 gpm.

The intake structure is located 631 m offshore at a depth of 10.7 m. Once the ocean cooling water enters the intake tunnel, the flow velocity is about 2.1 m/s (4.1 knots) during normal plant power operations. The cooling water is then directed through trash bars and vertical traveling screens which prevent debris, fish, and invertebrates from entering the CWS. The trash bars consist of vertical steel bars with 11.4 cm openings. Beyond the trash racks, the water is conveyed through four traveling screens with 1.6 cm mesh for removal of small debris, fish, and macro-invertebrates. Debris, fish, and invertebrates are removed from the screens by high-pressure sprays and conveyed to trash baskets for disposal.

Warmed cooling water is discharged offshore the generating station approximately 174 m inshore of the intake structure. The discharge structure is located in approximately 9.0 m of water. Products of other plant systems join the cooling water stream prior to discharge.

El Segundo Generating Station (ESGS)

ESGS is a 1,020 MW facility located in the City of El Segundo and utilizes two intake structures (individual structures for Units 1 and 2 and for Units 3 and 4) as part of the facility's once through cooling system. The intake structures consist of two pipes that extend 790 m offshore into Santa Monica Bay and are each topped with a velocity cap. The maximum flow through the intake for Units 1 and 2 is 144,000 gpm and the maximum for Units 3 and 4 is 276,000 gpm.

There are also two separate outfall pipes (one for Units 1 and 2 and one for Units 3 and 4) located in Santa Monica Bay with the depth of the outfall for Units 1 and 2 at 8.5 m and the depth for Units 3 and 4 at 9.1 m (both measured at a tide level of mean lower low water).

Redondo Beach Generating Station (RBGS)

RBGS is a 1,310-MW facility located in the city of Redondo Beach and consists of 8 fossil-fueled steamelectric generating units. There are three intake structures which provide cooling water to the 8 units. In 1987, four of the units and one of the intake structures were taken offline. The two remaining intakes supply Units 5 and 6 and Units 7 and 8, respectively, and draw in approximately 176,000 – 468,000 gallons of sea water per minute (gpm). After reaching the forebay the cooling water is directed through trash bars and vertical traveling screens with 0.95 cm mesh, which prevents debris, fish, and invertebrates from progressing further through the CWS. The warmed cooling water is joined with products of other plant systems and returned to the ocean via discharge conduits. The discharge for Units 5 and 6 is located 445 m offshore, just outside the King Harbor breakwater. Units 7 and 8 discharge effluents 45 m ` within King Harbor.

2.4.3 Impacts of Critical Habitat Designation on Power Plants

As noted above, thermal effluent from power plants may affect jellyfish survivability, recruitment into benthic habitat, and development, as well as prey resources (e.g., mesozooplankton, fish larvae, etc.) although there is some evidence of warmer water causing increases in jellyfish blooms, so the effect of the warmed water may be either negative or positive for jellyfish that are the primary prey of leatherbacks.

Designation of leatherback critical habitat could, through a section 7 consultation, result in the imposition of modifications related to power plant operations, such as:

- Require cooling of thermal effluent before release to the environment (may require use of different technology).
- Require treatment of any contaminated waste materials.
- Modifications associated with permit issued under NPDES (any updates from current early 1990s issuance).

2.4.4 Summary of Economic Impacts to Power Plants by Area

The costs associated with power plants, in the proposed rule, were reanalyzed based on public comments. A comment by Pacific Gas and Electric recommended that we assess costs associated with cooling of thermal effluent before release to the environment and that may more accurately reflect what modifications are likely to occur.³⁸ The costs found in these documents are associated with drastic transformation of the facilities. Following our review we concluded that drastic transformations of facilities will not likely be imposed on the plants during consultation. NMFS has decided the impacts to the prey PCE, as a result of changes in water temperature, are uncertain at this time and therefore we cannot conclude that the project modifications suggested by PG&E cannot reasonably be attributed to leatherback critical habitat. Thus, NMFS was unable to present a quantitative assessment for possible power plant modifications for this analysis.

The areas most likely to be affected due to potential power plant modifications are areas 1 and 7. Due to regulations already in place and the likelihood of modifications, it is estimated that incremental costs solely attributed to leatherback critical habitat would be about 30 percent.

2.5 Economic Impacts of Critical Habitat Designation on Desalination Plants

2.5.1 Description of Threat

NMFS has identified desalination plants as a potential threat in two areas: Areas 1 and 7. Desalination plants may pose a threat to leatherback critical habitat by affecting jellyfish prey. It is possible for "…marine life to become trapped on screens at the feed water intake (impingement) or sucked into the feed water system (entrainment)."³⁹ Impingement or entrainment of jellyfish could result in localized and temporary detrimental impacts on this PCE. Also, the discharge of hypersaline water could affect jellyfish; however, any effects would likely be localized due to dilution and may have both beneficial and detrimental impacts.

The California Coastal Commission has found that the desalination process results in an effluent that is high in salts and may contain various contaminants such as chemicals or cleaning compounds.⁴⁰ The discharge also carries with it what may be a large volume of biomass made up of the entrained organisms that were drawn through the facility. There are also likely to be other types of impacts when desalination discharges are combined with other discharge from coastal power plants, wastewater treatment facilities, or others types of facilities. However, there have been known beneficial impacts from desalination plants on jellyfish. Xian *et al.* (2005) has noted "At the water storage stage, the discharge of water and sediments into estuary is greatly reduced, making the saltwater intrusion appear earlier and the duration of intrusion longer. The increase of water temperature and salinity, the high level of nutrients, and the

³⁸ Public comments of Diane Ross-Leech, Director, Environmental Stewardship, Pacific Gas and Electric Company, April 22, 2010.

³⁹California American Water. *Seawater Desalination: White Paper*. September 2004. Accessed at: http://www.coastalwaterproject.com/pdf/WhitePaper_SeawaterDesalination.pdf on April 1, 2009.

⁴⁰ California Coastal Commission. *Seawater Desalination and the California Coastal Act*. Accessed at: http://www.coastal.ca.gov/energy/14a-3-2004-desalination.pdf on April 1, 2009.

abundance of zooplankton has stimulated the expansion of Cyanea capillata, from a prevalence of 0.41% in 1998 to 85.47% of the total samplings for fisheries in November 2003."⁴¹

2.5.2 Regulatory Environment & Extent of Activity

The USCG is responsible for approving structures in navigable waters, such as intake and outfall pipelines, to ensure they don't adversely affect navigation. The Coast Guard may also require buoys or markers to be maintained over the structures. The applicant may also be required to submit information about the structures to include on nautical charts.

U.S. Army Corps of Engineers: A desalination facility may require a Section 404 permit from the U.S. Army Corps of Engineers if it involves placing fill in navigable waters, and a Section 10 permit if the proposal involves placing a structure in a navigable waterway. Facilities may require review from NMFS and/or U.S. Fish and Wildlife Service for their potential effects on endangered threatened or other sensitive species. They may also require review for effects on EFH, protected marine mammals, and migratory birds. Other permits may also be required from the Federal Bureau of Reclamation, Environmental Protection Agency (e.g., NPDES permit), Bureau of Ocean Energy Management (BOEM), etc.

The available consultation data upon which we based our analysis does not indicate that NMFS or the Fish and Wildlife Service had consulted on past desalination projects regarding impacts on listed marine species. Further, existing desalination plants do not appear to have implemented measures to manage the discharge of hypersaline effluent for human protection or otherwise, to date. Discharges from desalination plants are subject to Clean Water Act (CWA) requirements, but because there is no past consultation history, it is not clear whether CWA requirements adequately address hypersaline effluent in marine waters for jellyfish.


There are nineteen existing coastal desalination plants located within the critical habitat area (see Table 2.5-1). Two of these plants are not currently operating and the City of Morro Bay has a temporary emergency desalination plant that is not currently in operation.⁴² Because water produced via desalination tends to be more expensive than water from other sources, the operating status of a plant is highly dependent on prevailing drought conditions and local water prices. As water from other sources becomes scarce, desalination becomes a more viable source of drinking water, and desalination plants may be brought online. Sixteen additional desalination plants have been proposed but have not yet been constructed (see Table 2.5-1 and Figure 2.5-1). Generally, the proposed plants have greater capacities than existing plants, suggesting that these plants may produce a greater quantity of hypersaline effluent. Similar to LNG terminals and tidal, wave, and wind energy projects, it is unclear how many projects may ultimately reach construction stage.


⁴¹ Xian et al. 2005. "Jellyfish Blooms in the Yangtze Estuary," <u>Science</u>, vol. 307.

⁴² California Coastal Commission. *Chapter Two: Coastal Desalination Projects in California*. Accessed at: http://www.coastal.ca.gov/desalrpt/dchap2.html.

Area	Project Name/(Ownership)	Capacity (MGD)	Status
Existi	ng	•	•
1	Duke Energy/Moss Landing/(Private)	0.5	Active
1	Marina Coast Water District/(Public)	0.3	Temporarily idle
1	Monterey Bay Aquarium/(Non-profit)	0.04	Active
7	City of Morro Bay/(Public)	0.6	Intermittent use
7	Duke Energy/Morro Bay/(Private)	0.4	Not known
7	PG&E/Diablo Canyon/(Private)	0.6	Not known
Some	Oil and gas companies -located at offshore oil and gas	0.002-	Active
in 1, 7, and 9	platforms/(Private)	0.03	
Propo	sed		
1	California American Water Company	11-12	
1	City of Sand City	0.3	
1	City of Santa Cruz	2.5-4.5	
1	East Bay Municipal Utility District	1.5	
1	Marin Municipal Water District	10-15	
1	Marina Coast Water District	1.3	
1	Montara Water and Sanitary District	N/A	
1	Monterey Peninsula Water Management District	7.5	
1	Ocean View Plaza	0.05	
1	Pajaro-Sunny Mesa/Poseidon	20-25	
1	San Francisco Public Utilities Commission/ Contra Costa Water District/ Santa Clara Valley Water District	20-80	
7	Arroyo Grande/Grover Beach/ Ocean Community Services District	1.9	
7	Cambria Community Services District/ Department of the Army	0.4	

 Table 2.5-1: Number of Desalination Plants in California Affected Areas





Source: Cooley, Heather, Peter H. Gleick, and Gary Wolff. 2006. "Desalination, with a Grain of Salt: *A California Perspective*." Pacific Institute for Studies in Development, Environment, and Security. Accessed at: www.pacinst.org/reports/desalination/desalination_report.pdf on March 24, 2009.

2.5.3 Impacts of Critical Habitat Designation on Desalination Plants

Leatherback critical habitat could impose modifications related to desalination plants, such as:

- Avoiding or minimizing entrainment and impingement impacts. The California Coastal Commission (2004) lists ways this can be accomplished:
 - Use alternative designs and mitigation measures to avoid intake.
 - By using a subsurface intake, such as a beach well or infiltration gallery, which would allow these impacts to be avoided entirely.
 - Where subsurface intakes are infeasible, open water intakes may be designed and located so that entrainment and impingement are reduced, but usually not entirely eliminated.
- Avoid or minimize adverse effects caused by desalination discharges. Yet again, The California Coastal Commission (2004) lists ways this can be accomplished:
 - Proper location
 - Subsurface outfalls
 - o Structural measures diffusers or multiport outfalls
 - o Minimizing chemical use or using alternative treatments
 - o Wastewater treatment systems or on-land disposal

o Co-located or combined outfalls

Under Clean Water Act requirements, desalination plants require Federal permits from USACE, EPA, or both. Therefore, when critical habitat is designated for leatherbacks in areas where these plants operate, a section 7 consultation may be required to determine impacts. Potential conservation efforts to mitigate desalination impacts are likely to include the treatment of hypersaline effluent to ensure that salinity levels are restored to normal values. The costs of treating hypersaline effluent or finding an alternate manner of brine disposal can vary widely across plants depending on plant capacity and design. Therefore, this analysis presents a range of possible impacts.

At the low end, this analysis assumes that the cost of reducing salinity levels will be minimal. For example, desalination plants may be co-located with power plants. If co-located, the effluent can be mixed with the power plants' wastewater to reduce salinity at minimal cost. Many desalination plants already choose to be co-located with power plants because co-location can result in construction and energy cost savings.⁴³

At the high end, it assumes that desalination plants would utilize alternate methods of brine disposal. These alternate methods can include using injection wells, evaporation ponds, or crystallizers. The estimated costs of brine disposal using injection wells (the least cost alternative at approximately \$0.63 per kilogallon in \$2009⁴⁴) are presented in Table 2.5-2.

⁴³ Poseidon Resources, "Desal 101." Accessed at: http://www.poseidonresources.com/desal_101.html on June 1, 2009.

⁴⁴U.S. Department of the Interior Bureau of Reclamation. 2006. *Desalination and Water Purification Research and Development Program Report No. 111: Zero Discharge Seawater Desalination: Integrating the Production of Freshwater, Salt, Magnesium, and Bromine*. Reclamation: Managing Water in the West. University of South Carolina Research Foundation Agreement No. 98-FC-81-0054; adjusted for inflation using Bureau of Labor Statistics "Inflation Calculator." Accessed at: http://www.bls.gov on May 4, 2009.

	Number Capacity			Average Annual Cost per
Area	of Plants	(kgal/year)	Annual Cost	Plant
1	17	40,869,000	\$25,748,000	\$1,515,000
7	8	1,599,000	\$1,007,000	\$126,000

Table 2.5-2: Estimated Costs of Alternative Method of Brine Disposal

Notes: Assumes brine is disposed in injection wells. Assumes, on average, costs of \$0.63/kgal for alternative brine disposal.

Source: U.S. Department of the Interior Bureau of Reclamation. 2006. *Desalination and Water Purification Research and Development Program Report No. 111: Zero Discharge Seawater Desalination: Integrating the Production of Freshwater, Salt, Magnesium, and Bromine.* Reclamation: Managing Water in the West. University of South Carolina Research Foundation Agreement No. 98-FC-81-0054.

2.5.4 Summary of Economic Impacts to Desalination Plants by Area

As discussed above, potential impacts on desalination plants are subject to high levels of uncertainty for the following reasons:

- The number of future desalination plants is speculative
- Future management and required project modifications for desalination are uncertain and could vary depending on the location and size of the plant.

Table 2.5-3 presents a summary of our findings. Area 1 has the highest impact due to the number of existing and proposed facilities identified in the area.

Table 2.5-3: Summary of Economic Impacts of Desalination Projects by Area

	Number of Affected					
	Plants		Incremental	Total Annualized Costs		
Description	Existing Proposed		Score	Low	Mid	High
1	6	11	0.3	\$0	\$3,862,000	\$7,724,000
7	6 2		0.3	\$0	\$151,000	\$302,000
Total				\$0	\$4,013,000	\$8,026,000

2.6 Economic Impacts of Critical Habitat Designation on Tidal, Wave, and Wind Energy <u>Projects</u>

2.6.1 Description of Threat

NMFS has identified tidal, wave, and wind energy projects as potentially affecting areas considered for leatherback critical habitat in two coastal areas included in the final rule: Areas 1 and 2. Tidal, wave, and wind energy projects are designed to harness the kinetic energy of waves, currents, tides, or wind to generate electricity. These projects typically involve placement of structures, such as buoys, cables, and turbines, in the water column. Projects can vary greatly in terms of size and design, and most are not yet fully developed. The exact nature of habitat impacts is difficult to predict; however, possible impacts to the feature of the leatherback critical habitat include disturbance to prey species during their benthic,

polyp stage.⁴⁵ Effects on the habitat features as a result of project construction and operation will undoubtedly vary based on the particular project and project location.

2.6.2 Regulatory Environment & Extent of Activity

Because tidal, wave, and wind energy projects in leatherback habitat on the West Coast are in the preliminary stages of development, NMFS has yet to make specific recommendations about project modifications that may be required to mitigate potential adverse impacts on listed species and/or their designated critical habitat. Tidal, wave, and wind energy projects have the potential to affect the habitat of a wide range of species, including green sturgeon, Pacific salmon and steelhead, and marine mammal species. Again, due to the preliminary stages of permitting for most projects, NMFS has made few conservation recommendations related to these projects for these species. Nonetheless, some level of baseline protection is thought to exist for these species under the ESA.

Tidal and wave energy projects are subject to FERC permitting and licensing requirements, and thus may require section 7 consultations on impacts to listed species and critical habitat. The BOEM is responsible for projects on the outer continental shelf (in Federal waters).⁴⁶ Both NMFS and the U.S. Fish and Wildlife Service have commented on several of the preliminary permit applications for these projects. In its comments, NMFS noted affected areas that represent essential fish habitat (EFH) for federally managed species under the Magnuson Stevens Fishery Management Act, but indicated that the breadth and magnitude of potential adverse impacts on this habitat are unknown and cannot be evaluated without further information on and analysis of the specific projects at issue.⁴⁷ Among other environmental statutes applicable to proposed or pilot projects are section 401 of the Clean Water Act and the Marine Mammal Protection Act. A proposed project would also likely require a finding of consistency by the relevant state under section 307 (c) of the Coastal Zone Management Act to ensure the project complies with the state's coastal zone management plan.

⁴⁵ Note safe passage was previously considered for inclusion as a PCE; however based on the comments received and our review of the proposed rule, migratory pathway conditions to allow for safe and timely passage and access to/from/within high use foraging areas has been eliminated as a PCE.

⁴⁶ PFMC. Habitat and Communities: Wave, Tidal, and Offshore Wind Energy. Accessed at:

http://www.pcouncil.org/habitat-and-communities/wave-tidal-and-offshore-wind-energy/. Page last updated on November 29, 2010.

⁴⁷ See, for example, National Marine Fisheries Service. *Comments on San Francisco Bay Tidal Energy Project* (FERC No. 12585), August 12, 2005.

Tidal and Wave Energy

To date, six projects within the identified areas have received preliminary permits from the Federal Energy Regulatory Commission (FERC). Preliminary permits are issued for up to three years and allow the permit-holder priority to develop that site for the duration of the permit. Preliminary permits, however, do not authorize any construction. In order to construct and operate a hydrokinetic facility, a license must be issued by FERC. A list of hydrokinetic projects proposed within the study area is presented in Table 2.6-1 and is based on review of information posted at www.ferc.gov as of December 2, 2011:

Table 2.6-1: Issued and Pending Preliminary Permits Issued by FERC for Tidal and Wave Energy
Projects

Are				Issue/Filing	Expiration	Projec
a	Docket #	Project Name	Applicant	Date	Date	t Type
Issued	d and Pendir	ng Preliminary Permits	·	·		
		Del Mar Landing Project	Sonoma County Water			
1	P-13376		Agency	07/09/09	06/30/12	Wave
		Fort Ross North Project	Sonoma County Water			
1	P-13378		Agency	07/09/09	06/30/12	Wave
		Fort Ross South Project	Sonoma County Water			
1	P-13377		Agency	07/09/09	06/30/12	Wave
		San Francisco Bay Tidal	Golden Gate Energy			
1	P-12585	Energy Project	Company	02/04/10	01/31/13	Tidal
		Coos Bay OPT Wave	Oregon Wave Energy			
2	P-12749	Park	Partners I, LLC	08/10/10	07/31/13	Wave
		Douglas County Wave &				
2	P-12743	Tidal Energy	Douglas County, OR	10/06/10	09/30/13	Wave
		San Onofre OWEG				
2	P-13678	Electricity Farm	JD Products, LLC	10/29/2010	pending	Wave
Sourc	e: FERC. I	ssued and Valid Hydrokineti	c Projects Preliminary Per	mit. Accessed at:		•

http://www.ferc.gov/industries/hydropower/gen-info/licensing/hydrokinetics.asp#skipnavas of December 2, 2011; FERC. *Pending Hydrokinetic Projects Preliminary Permits*. Accessed at:

http://www.ferc.gov/industries/hydropower/gen-info/licensing/hydrokinetics.asp#skipnavUpdated as of December 2, 2011;

Wind Energy

To date, there is one project, the Principle Power Offshore Wind Project, which is currently being proposed in Oceanside & Netarts, OR (Area 2). If approved, the plant will require the installation of a floating deepwater offshore wind facility with access to the ports of Tillamook and/or Garibaldi along the north central coast, about 10 miles from port. In 2008, the Tillamook Intergovernmental Development

Agency and Principle Power signed a MOU for phased development off offshore wind plant.⁴⁸ Working closely with the local public utility and community leaders, the project will be built in two phases:

Phase I will see installation of a 5MW floating offshore turbine to demonstrate the viability, reliability and economics of Principle Power's WindFloat technology. The development will expand to its full nameplate capacity of 150 MW during Phase II, targeted to begin in 2012, providing clean renewable energy to the Northwest's Columbia Grid and beyond.⁴⁹

2.6.3 Impacts of Critical Habitat Designation on Tidal, Wave, and Wind Energy Projects

The technology for hydrokinetic projects is relatively new and is still being actively developed. It is not yet known what number of the proposed projects will be constructed and become operational. Thus the ultimate design, location, and impacts of these projects are difficult to predict. Project modifications that would be required to minimize impacts to leatherback critical habitat are similarly difficult to predict and quantify. Based on NMFS consultations on several pilot projects, project modifications could include installation of covers on turbines, installation of sampling gear, and biological monitoring. In the absence of specific conservation efforts recommended for listed species, the potential impact of leatherback critical habitat on tidal, wave, and wind energy project remains uncertain.

Data on the costs of these measures were not widely available. To develop an estimate of potential costs, this analysis relies on the estimated costs of environmental measures for a single project, and assumes that these costs will be incurred by all tidal and wave energy projects (see Table 2.6-2). We recognize that this sample is small, and thus large uncertainties exist with respect to estimated potential impacts to these projects. In addition, FERC points out in the "Economic Analysis of the Impacts of Designating Critical Habitat for the Threatened Southern Distinct Population Segment of North American Green Sturgeon (NMFS 2008)" that license application costs and costs related to environmental review of the projects may increase due to critical habitat designation. While costs of section 7 consultation are discussed in Section 1 of this report, other environmental review costs are not explicitly captured in current estimates. To the extent that future projects require more or fewer project modifications than have been included in this example, these costs may over- or underestimate economic effects.

Modification costs for wind energy are currently unknown at this time.

⁴⁸ PFMC. *Active West Coast Hydrokinetic Projects*. Report developed by the Pacific Fishery Management Council. August 23, 2010. Accessed online at: http://www.pcouncil.org/wp-

content/uploads/INFO_RPT1_ACTIVEHYDRO_SEPT2010BB.pdf.

⁴⁹ Principle Power, Inc. Site Development: Oregon. Accessed online at: http://www.principlepowerinc.com/sitedev/oregon.html.

		Annual				
	Capital	O&M	Total 30			
Project Modification	Cost	Cost	yr Cost			
Use horizontal directional drilling to deploy transmission cable from						
shore station under beach and intertidal area, out to depth of 10 to 30 ft						
below mean lower low tide (2005\$)	\$500,000	\$0	\$500,000			
Design features to achieve a closed-loop system to prevent any marine						
life entering pressurized water flow (2005\$)	\$500,000	\$20,000	\$1,100,000			
Design features to minimize scale of anchor devices, project footprint						
on seafloor, and chain/cable sweep of seafloor (2005\$)	\$250,000	\$0	\$250,000			
Develop a schedule of regular system maintenance that minimizes site						
visits, disturbance to marine growth, and activity at the site. (2005\$)	\$2500	\$500	\$18,000			
Total			\$1,868,000			
Total (2009\$)			\$2,029,000			
Annual Cost \$68						
Source: Cost estimates from Economic Analysis of the Impacts of Designating Critical Habitat for the						
Threatened Southern District Population Segment of North American G	reen Sturgeo	n, August	27, 2008,			
prepared for NMFS and adjusted for inflation using the Bureau of Labor	Statistics In	flation Cal	culator.			

Table 2.6-2: Environmental Measures for Example Wave Energy Project

2.6.4 Summary of Economic Impacts to Tidal, Wave, and Wind Energy Projects by Area

As discussed above, potential impacts on tidal, wave, and wind energy projects are subject to high levels of uncertainty for the following reasons:

- The number of future tidal, wave, and wind energy projects is speculative.
- Future management and required project modifications for leatherback critical habitat related to tidal and wave energy projects are uncertain and could vary in scope from project to project.

Table 2.6-3 presents a summary of our findings. Area 1 has the highest costs due to the number of issued preliminary permits.

Area	Issued Preliminary Permits	Pending Projects	Incremental Score	Total Annualized Costs
1	4	0	0.5	\$135,000
2*	2	2	0.5	\$101,000
Total			·	\$236,000

Table 2.6-3: Summary of Economic Impacts to Tidal, Wave, and Wind Energy Projects by Area

* Note that while the wind energy project has been identified as a "Pending Project" under Area 2, the costs associated with modifications to wind energy projects is currently unknown. Thus, is not reflected in the costs.

2.7 Economic Impacts of Critical Habitat Designation on Liquefied Natural Gas Projects

2.7.1 Description of Threat

NMFS identified the construction and operation of LNG projects as a potential threat to leatherback critical habitat. While there are no identified LNG facilities within the specific areas, the development of future projects may still pose a threat. NMFS identified proposed liquefied natural gas (LNG) projects as a potential threat to leatherback critical habitat in one area, Area 2.

Several environmental issues have been identified with the construction and operation of LNG terminals, including cold water discharge, leaks and spills, release of anti-fouling chemicals into the water, disturbance of benthic habitat and noise. Cold water discharge associated with regasification could have impacts on prey resources if the discharge is significantly cooler than ambient water. LNG terminals may be located onshore or offshore, including offshore floating terminals, offshore oil platform terminals, and gravity-based offshore ports.⁵⁰ One concern for offshore facilities is that construction of pipelines to transport LNG onshore may affect leatherback critical habitat by impacting the benthic habitat which may impact jellyfish reproduction and development. For onshore LNG terminals, construction of breakwaters, jetties, or other shoreline structures and the activities associated with construction (e.g., dredging) may affect leatherback habitat for similar reasons as mentioned above. Another concern is the increased potential for oil spills and potential effects on water quality from the presence of vessels transporting and offloading LNG at the terminals.

2.7.2 Regulatory Environment & Extent of Activity

Under the Energy Policy Act of 2005, FERC has exclusive authority to issue licenses for the siting, construction, operation, and modification of LNG import terminals onshore and in state waters. The Maritime Administration (MARAD) and the USCG have siting and permitting jurisdiction for "deepwater ports" in Federal waters, defined as "any fixed or floating man-made structures other than a vessel…located beyond the territorial sea and off the coast of the United States …"⁵¹ Approved LNG

⁵⁰ Surfrider Foundation. Coastal A-Z, *LNG*. Accessed at: <u>http://www.surfrider.org/a-z/LNG.php</u>.

⁵¹ 33 U.S.C.S. § 1502(10)

terminal projects must also obtain Coastal Zone Management Act, Section 404 (under the CWA) water quality certificate, and Section 404 (under the CWA) dredging permits.⁵²

Therefore, depending on the proximity of the facility to shore, LNG projects are subject to either FERC or Coast Guard permitting and licensing requirements and thus may require ESA section 7 consultations. During operations, LNG facilities must comply with federal safety standards (49 CFR 193) and regulations for waterfront facilities (33 CFR 127).

Based on review of FERC's database,⁵³ updated as of December 2, 2011, there are no approved, one proposed, and one potential LNG facilities within the study areas. These projects are still in the development stages, and are awaiting approval from FERC and/or the U.S. Coast Guard (depending on their location). The potential project along the California coast is also being discussed by the industry; however, this project may never be proposed to FERC (see figures 2.7-1, 2.7-2, and table 2.7-1 below for more details).


It is difficult to predict the number and location of LNG facilities that will be built within the areas being considered for critical habitat of leatherbacks. In addition to a rigorous approval process, many of these projects face significant local opposition as has been witnessed in the Pacific Northwest or are abandoned during the development stages for various reasons. FERC's website indicates that market forces will ultimately dictate the number of facilities constructed; analysts project that about 30% (12) of the 40 LNG terminals currently being considered, nationally, will ever be built (www.ferc.gov).


Figure 2.7-1 Proposed North American LNG Import Terminals⁵⁴

⁵² FERC. *LNG Projects*. Accessed at: http://www.ferc.gov/industries/lng.asp. Updated as of February 6, 2010.

⁵³ FERC, accessed online December 20, 2011 at http://www.ferc.gov/industries/hydropower/gen-info/licensing/prepermits.asp. Page updated as of December 2, 2011.

⁵⁴ FERC, accessed online December 20, 2011 at http://www.ferc.gov/industries/hydropower/geninfo/licensing/pre-permits.asp Updated as of December 2, 2011.





Potential North American LNG Import Terminals⁵⁵ **Figure 2.7-2**

Table 2.7-1: LNG Terminals by Area

Area	Location	Applicant	Capacity			
Proposed LNG In	Proposed LNG Import Terminals					
2	Astoria, OR	Oregon LNG	1.5 Bcfd			

2.7.3 Impacts of Critical Habitat Designation on Liquefied Natural Gas Projects

Based on available data, this analysis cannot forecast how many projects may or may not ultimately be constructed. Because there are no LNG projects under consideration in this analysis, NMFS has yet to make specific recommendations about any project modifications that might be required to mitigate potential adverse impacts on leatherback critical habitat. Until specific plans for the LNG projects are made available, their potential impact on habitat will remain uncertain, as will the nature of any project modifications that might be requested to mitigate adverse impacts. Potential modifications may include biological monitoring and specific measures to prevent or respond to catastrophes. While LNG projects on the West Coast are still in the preliminary stages, NMFS has consulted on several projects on the East Coast, and has not yet required project modifications to mitigate adverse impacts to an aquatic species.⁵⁶ Because there is a high level of uncertainty associated with anticipating future management efforts for leatherback critical habitat as a result of LNG projects, this analysis presents only a qualitative discussion.

⁵⁵ FERC, accessed online December 20, 2011 at http://www.ferc.gov/industries/hydropower/gen-info/licensing/prepermits.asp Updated as of December 2, 2011. ⁵⁶ NMFS (2007), Personal communication with NMFS on July 17, 2008.

2.7.4 Summary of Economic Impacts to Liquefied Natural Gas Projects by Area

As discussed above, potential impacts on LNG terminals are subject to high levels of uncertainty for the following reasons:

- The number of future LNG projects likely to reach the construction stage within critical habitat areas is speculative.
- Future management and required project modifications for LNG terminals are uncertain and could vary in scope from project to project.

NMFS was unable to present a quantitative assessment for possible LNG modifications for this analysis. Although the economic analysis for green sturgeon included possible modification costs for LNG facilities in overlapping areas, those costs were attributed to potential site limitations or site relocation of facilities which is not applicable to this designation. It is not anticipated that leatherback sea turtle essential feature or PCE will be affected by proposed or potential LNG siting. The area most likely to be affected due to potential LNG modifications is area 2. Currently, there is one proposed project in area 2. Due to regulations already in place and the likelihood of modifications, it is estimated that incremental costs solely attributed to leatherback critical habitat (excluding re-siting costs) would be about 50 percent.

Potential modification costs for future onshore LNG facilities might include costs similar to those for inwater construction (i.e., coastal armoring, breakwater, etc.) and dredging. Potential modification costs for future offshore LNG facilities might include the costs associated with installing pipelines to avoid jellyfish benthic habitat. Additional modifications that may incur a cost include a requirement that each LNG carrier maintain a shipboard oil pollution plan containing measures to be implemented in the event of a spill or release of oil, as well as a prohibition on liquid transfer and refueling of vehicles and equipment within 100 ft of water bodies.⁵⁷ However, in the absence of specific information about the extent of the modification costs and modification requirements for leatherback critical habitat, we cannot at this time present a quantitative assessment for possible LNG modifications that can be used in the 4(b)(2) analysis.

2.7.5 Summary of Economic Impacts to Liquefied Natural Gas Projects by Specific Area

As discussed above, potential impacts on LNG terminals are subject to high levels of uncertainty for the following reasons:

- The number of future LNG projects likely to reach the construction stage within the specific areas is speculative.
- Future management and required project modifications for LNG terminals are uncertain and could vary in scope from project to project.

⁵⁷ FERC. 2008. Final EIS for the construction and operation of the Bradwood Landing Project. June 6, 2008. Accessed at: <u>http://www.ferc.gov/industries/lng/enviro/eis/2008/06-06-08-eis.asp</u>.

NMFS was unable to present a quantitative assessment for possible LNG modifications for this analysis because there are currently no LNG projects or structures associated with LNG projects (i.e., pipelines to transport the LNG onshore) existing or proposed within the specific areas.

2.8 Economic Impacts of Critical Habitat Designation on Aquaculture

In the proposed rule and supporting economic analysis, aquaculture was evaluated as an activity type that may impact the PCE passage. Any potential effects on prey PCE are addressed within the NPDES effects since aquaculture facilities require permits to manage discharge into the water. The PCE passage has been removed from analysis based on public comments and CHRT review, therefore aquaculture is no longer an activity that will trigger the need for special management through the designation of leatherback critical habitat.

SECTION 3: SUMMARY OF RESULTS

3.1 Summary of Results

This section presents seven tables that summarize the results of this analysis.

Table 3-1 shows the economic activities, by area, that may trigger the need for special management consideration or protection to accommodate leatherback critical habitat and are thus activities that may be impacted by the designation. The "Y" stands for yes, that activity is present in the respective area.

Activity Area	1	2	7		
NPDES	Y	Y	Y		
Agricultural Pesticides	Y	Y	Y		
Oil Spill Response	Y	Y	Y		
Power Plants	Y		Y		
Desalination Plants	Y		Y		
Tidal, Wave, & Wind Energy	Y	Y			
LNG		Y			

Table 3-1: Summary of Potential Threats within Areas Considered for Leatherback Critical Habitat Designation*

Table 3-2 presents the level of economic activity by area and by threat. The metric used to estimate the level of activity varies by threat. For example, an approximate number of facilities currently in place are used to estimate the number or power plants, while the potential number of projects is used to estimate the number of LNG facilities.

	NPDES:	NPDES:		Oil Spill Respo	Power		Tidal, Wave, & Wind		
	Minor	Major		nse	Plants	Desalination	Energy	LNG	
	# of	# of							
	facilities	facilities		#					
	(<5 miles	(<5 miles		actual					
	from	from		gallons	# of		# of	# of	
Area	coast)	coast)		spilled	plants	# of plants	projects	facilities	
1	5	11		20,000	1	17	4		
2	47	6		20,000			4	1	
7	5	6		20,000	2	8			
* Note	* Note that while aquaculture was previously included in the analysis, with the removal of the passage								
PCE, it	is no longer	considered	as an activity tha	at may req	uire speci	al management.			

Table 3-2: Activities Count*

Table 3-3 presents the estimated annualized cost and present discounted values by activity, in 2009 dollars, discounted at 3 percent and 7 percent rates. The "Annualized Costs" column summarizes the costs used throughout Section 2. The "Present Value" column is then calculated based on the annualized cost, across the indicated timeframe, and discounted at a 3 percent rate.⁵⁸ Appendix D tests the sensitivity of this assumption by comparing present values computed at 0 percent, 3 percent and 7 percent discount rates.

⁵⁸ The economic analysis in the proposed rule originally utilized a 7 percent discount rate. Public comment caused NMFS to reanalyze the rates used. The U.S. Office of Management and Budget has reiterated their guidance to use either a 3 percent or a 7 percent discount rate to calculate present values for regulatory impact analysis. The 3 percent rate used in Table 3-3 better reflects current economic conditions. See OMB Circular A-4, September 17, 2003. Available online at: http://www.whitehouse.gov/sites/default/files/omb/assets/omb/circulars/a004/a-4.pdf.

Activity	Cost Category	Metric	Annualized Costs	Timeframe (years)	Present Value (Discounted at 3%)	Present Value (Discounted at 7%)
NPDES:	Low		\$0		\$0	\$0
Minor	Midpoint	per plant	\$7,000	20	\$104,000	\$74,000
Facilities	High		\$15,000		\$223,000	\$159,000
NPDES:	Low		\$52,000		\$774,000	\$551,000
Major	Midpoint	per plant	\$68,000	20	\$1,012,000	\$720,000
Facilities	High		\$83,000		\$1,235,000	\$879,000
	Low: Area 1	per unit	\$0		\$0	\$0
Develingtion	High: Area 1	based on	\$1,515,000	- 20	\$22,539,000	\$16,050,000
Desalination	Low: Area 7	plant	\$0		\$0	\$0
	High: Area 7	capacity	\$126,000		\$1,875,000	\$1,335,000
Tidal, Wave, & Wind Energy	N/A	per project	\$68,000	30	\$1,333,000	\$844,000

 Table 3-3: Present Discounted Value of Annualized Costs by Activity, in 2009 dollars

*Wind energy is not included here since costs could not be quantified.

Table 3-4 presents the incremental score by area and by activity. The incremental score is used to develop an estimate of the share of impacts that may be attributed to leatherback critical habitat. The scores vary both by activity and by area depending on the level of baseline protection provided by Federal, State and local regulations as well as the presence of other listed species, other listed critical habitat, etc. The incremental scores range from 0.3 for activities that exist in areas with a large amount of current protections, such as marine sanctuary areas and areas with critical habitat designations for other species to 0.5 for activities that have moderate protection, such as protection of listed leatherbacks and EPA regulations. The dashes indicate that the activity does not exist or will not affect the corresponding area.

		Agricultural	Oil Spill	Power		Tidal, Wave, &	
Area	NPDES	Pesticides	Response	Plants	Desalination	Wind Energy	LNG
1	0.3	0.3	0.3	0.3	0.3	0.5	-
2	0.3	0.3	0.3	-	-	0.5	0.5
7	0.3	0.3	0.3	0.3	0.3	-	-

Table 3-4: Incremental Scores

Table 3-5a presents total estimated impacts (costs) by area and by activity for both the low and high scenarios for the 6 activity types where a quantitative assessment was possible.

Area			1	2	7
		Low	\$0	\$0	\$0
NPDES:	<1 mile	High	\$13,000	\$71,000	\$13,000
Minor		Low	\$0	\$0	\$0
	<5 miles	High	\$22,000	\$209,000	\$22,000
		Low	\$94,000	\$16,000	\$78,000
NPDES:	<1 mile	High	\$150,000	\$25,000	\$125,000
Major		Low	\$172,000	\$94,000	\$94,000
	<5 miles	High	\$275,000	\$150,000	\$150,000
Desalination	Low		\$0	\$0	-
Plants	High		\$12,874,000	\$7,724,000	-
Tidal &	Low		\$0	\$0	-
Wave					
Energy*	High		\$135,000	\$135,000	-

 Table 3-5a:
 Total Impacts (Activities with Quantitative Costs)

*Wind energy is not included here since costs could not be quantified.

Table 3-5b provides a summary of possible impacts and costs for the three activities (power plants, wind energy, and LNG projects) in which only a qualitative assessment was possible.⁵⁹ "Impacts" refers to the types of modifications that those activities may have to implement due to leatherback critical habitat and the cost range was determined from the incremental scores. Therefore, for power plants, it is expected that these facilities may have small, minor modifications due to leatherback critical habitat in the future (low impacts) and it was deemed that power plants and the areas shown below already have a high amount of regulations in place and hence, if a modification took place, the costs attributed solely to leatherback critical habitat is expected to be 30 percent (low costs). The possible modifications for both wind energy and LNG projects are extremely speculative and no projects are currently in place on the West Coast, the impacts that may occur in the future were given a medium rating. If a modification does occur to future wind energy or LNG projects because of leatherback critical habitat, it is expected that about 50 percent (medium costs) would be attributed solely to the leatherback critical habitat.

Table 5-55. Total impacts (Activities with Quantative Discussion)								
Area	Power Plants	Wind Energy	LNG	Oil Spill Response	Agricultural pesticide use			
	Low impacts			Uncertain impacts	Unknown			
1	with low costs							
		Medium impacts	Medium impacts	Uncertain impacts	Unknown			
		with medium	with medium					
2		costs	costs					
	Low impacts			Uncertain impacts	Unknown			
7	with low costs							

 Table 3-5b:
 Total Impacts (Activities with Qualitative Discussion)

⁵⁹ Note that while aquaculture was previously included in the analysis, with the removal of the passage PCE, it is no longer considered as an activity that may require special management.

REFERENCES

16 U.S.C. 1532.

- ABSG Consulting. LNG Receiving Terminal Offshore Oregon as an Alternative to the Land-Based Bradwood Facility. Prepared for: Northern Star Natural Gas. Project No.: 1495888, January 7, 2006.
- Bureau of Ocean Energy Management (BOEM). Pacific Region: Pacific OSC Region. Accessed at: http://www.boemre.gov/omm/pacific/index.htm, on November 2010.
- CalFish. Fish Barrier Data. Accessed at: http://www.calfish.org/ on August 21, 2007.
- California American Water. *Seawater Desalination: White Paper*. September 2004. Accessed at: http://www.coastalwaterproject.com/pdf/WhitePaper_SeawaterDesalination.pdf on April 1, 2009.
- California Coastal Commission. *Chapter Two: Coastal Desalination Projects in California*. Accessed at: http://www.coastal.ca.gov/desalrpt/dchap2.html.
- California Coastal Commission. *Seawater Desalination and the California Coastal Act*. Accessed at: http://www.coastal.ca.gov/energy/14a-3-2004-desalination.pdf on April 1, 2009.
- California Coastal Commission. *Seawater Desalination in California*. Accessed at: http://www.coastal.ca.gov/desalrpt/dsynops.html on April 14, 2009.
- California Department of Fish and Game. 2009 Registered Aquaculturists. Accessed at: http://www.nrm.dfg.ca.gov/FileHandler.ashx?DocumentID=3265 updated through March 5, 2009.
- California Department of Fish and Game. *The Regional Contingency Plan for federal region IX*. Accessed at: http://www.dfg.ca.gov/ospr/response/acp/marine/2005RCP/RCP102405.pdf.
- California Energy Commission. *California Statewide Plants map*. Accessed at: http://www.energy.ca.gov on April 20, 2008.
- California Environmental Protection Agency (CalEPA). *California Impaired Water Segments*. State Water Resources Control Board. Accessed at: http://www.swrcb.ca.gov/water_issues/programs/tmdl/docs/303dlists2006/epa/state_06_303dlist.xls on August 2008.
- California Environmental Protection Agency (CalEPA). *California Integrated Water Quality System Project (CIWQS), Regulated Facilities Report Form.* State Water Resources Control Board, Water Quality. Accessed at: http://ciwqs.waterboards.ca.gov/ciwqs/readOnly/ciwqsReportRegulatedFacilitiesCriteria.jsp?comman

http://ciwqs.waterboards.ca.gov/ciwqs/readOnly/ciwqsReportRegulatedFacilitiesCriteria.jsp?comman d=resetCriteria on July 30, 2008.

- California Environmental Protection Agency (CalEPA), State Water Resources Control Board. Accessed at: http://ciwqs.waterboards.ca.gov/ciwqs/readOnly/ciwqsReportRegulatedFacilitiesCriteria.jsp? command=resetCriteria on July 30, 2008.
- Caurant, F., P. Bustamante, M. Bordes, and P. Miramand. 1999. "Bioaccumulation of Cadmium, Copper and Zinc in some Tissues of Three Species of Marine Turtles Stranded Along the French Atlantic Coasts." *Marine Pollution Bulletin*, vol. 38, no. 12, pp. 1085-1091.

- Cooley, Heather, Peter H. Gleick, and Gary Wolff. 2006. "Desalination, with a Grain of Salt: *A California Perspective*." Pacific Institute for Studies in Development, Environment, and Security. Accessed at: www.pacinst.org/reports/desalination/desalination_report.pdf on March 24, 2009.
- Etkin, Dagmar Schmidt. 1999. "Estimating Cleanup Costs for Oil Spills." Oil Spill Intelligence Report, Cutter Information Corp., Arlington, MA. International Oil Spill Conference, #168.
- Federal Energy Regulatory Commission (FERC). *Issued and Valid Hydrokinetic Projects Preliminary Permit*. <u>http://www.ferc.gov/industries/hydropower/gen-info/licensing/hydrokinetics.asp#skipnav</u> on December 20, 2011.
- Federal Energy Regulatory Commission (FERC). Pending Hydrokinetic Projects Preliminary Permits. <u>http://www.ferc.gov/industries/hydropower/gen-info/licensing/hydrokinetics.asp#skipnav</u> on December 20, 2011.
- Gramlich, Edward M. A Guide to Benefit-Cost Analysis (2nd Ed.). Prospect Heights, Illinois: Waveland Press, Inc., 1990.
- Hoff, Rebecca Z. and Shigenaka, Gary. 2003. "Chapter 5 Response Considerations for Sea Turtles." Oil and Sea Turtles: Biology, Planning, and Response. NOAA's National Ocean Service/Office of Response and Restoration/Hazardous Materials Response Division, August 2003.
- Industrial Economics, Inc. (IEc), prepared for NMFS. *Economic Analysis of the Impacts of Designating Critical Habitat for the Threatened Southern Distinct Population Segment of North American Green Sturgeon.* September 28, 2009.
- Milton, S., P. Lutz y G. Shigenaka. 2003. Oil Toxicity and Impacts on Sea Turtles, capítulo 4 de *Oil and Sea Turtles, Biology, Planning and Response*. NOAA Office of Response and Restoration.
- National Association of State Fire Marshals. Liquefied Natural Gas: An Overview of the LNG Industry for Fire Marshals and Emergency Responders, 2005.
- National Marine Fisheries Service (NMFS). *Comments on San Francisco Bay Tidal Energy Project* (FERC No. 12585), August 12, 2005.
- National Marine Fisheries Service (NMFS). *Designation of Critical Habitat for the Leatherback Sea Turtle, Section 4(b) (2) Report.* December 2009.
- National Marine Fisheries Service (NMFS) (prepared by Industrial Economics, Inc.), *Economic Impacts* Associated with Potential Critical Habitat Designation for the Southern Resident Population of Killer Whales. November 7, 2006.
- National Marine Fisheries Service (NMFS). *Final Economic Analysis of Critical Habitat Designation for Seven West Coast Salmon and Steelhead ESUs.* Long Beach, CA, August 2005.
- Natural Resource Defense Council (NRDC). *Oil Spills*. Accessed at: http://www.nrdc.org/greengate/wildlife/oilf.asp.
- National Response Center, accessed at: http://www.nrc.uscg.mil/foia.html on July 2008.
- NOAA Fisheries, Endangered Species Act Section 7 Programmatic Formal Consultation and Magnuson-Stevens Fishery Conservation and Management Act Essential Fish Habitat Consultation for the Oil

Spill Response Activities Conducted Under the Northwest Area Contingency Plan (NWACP), November 6, 2003.

- Oregon Department of Environmental Quality. *Water Quality, Wastewater Permits, Water Quality Permitted Facilities.* Accessed at: http://www.deq.state.or.us/wq/sisdata/facilitylist.asp on July 24, 2008.
- Pacific Fishery Management Council (PFMC). Active West Coast Hydrokinetic Projects. Report developed by the Pacific Fishery Management Council. August 23, 2010. Accessed online at: http://www.pcouncil.org/wp-content/uploads/INFO_RPT1_ACTIVEHYDRO_SEPT2010BB.pdf.
- Pacific Fishery Management Council (PFMC). Habitat and Communities: Wave, Tidal, and Offshore Wind Energy. Accessed at: http://www.pcouncil.org/habitat-and-communities/wave-tidal-andoffshore-wind-energy/. Page last updated on November 29, 2010.
- Personal communication with K. Baker, NMFS Southeast Region in April 2009.
- Personal communication with USCG in March 2011.
- Public comments of Diane Ross-Leech, Director, Environmental Stewardship, Pacific Gas and Electric Company, April 22, 2010.
- Poseidon Resources, "Desal 101." Accessed at: http://www.poseidonresources.com/desal_101.html on June 1, 2009.
- Principle Power, Inc. Site Development: Oregon. Accessed online at: http://www.principlepowerinc.com/sitedev/oregon.html.
- Puget Sound Water Quality Action Team. *State of the Sound 2004*. Accessed at: http://www.psparchives.com/publications/puget_sound/sos/04sos/PSATSOS2004.pdf on June 9, 2009.
- Purcell, Jennifer E., Shin-ichi Uye, Wen-Tseng Lo. 2007. "Anthropogenic causes of jellyfish blooms and their direct consequences for humans: a review." Marine Ecology Progress Series, vol. 350, pp. 153–174.
- San Francisco Bay Conservation and Development Commission. *San Francisco Bay Dredging Environmental Work Windows*. Accessed at: http://www.bcdc.ca.gov/pdf/Dredging/D_EWW.xls.
- Science Applications International Corporation. 2003. *Economic Analysis of the Proposed Water Quality Standards Rule for the State of Oregon*. Reston, VA. EPA No. 68-C-99-252.
- U.S. Census Bureau. *County Business Patterns*. Accessed at: http://censtats.census.gov/cbpnaic/cbpnaic.shtml on September 2008.
- U.S. Census Bureau. North American Industry Classification System (NAICS). Accessed at: http://www.census.gov/cgi-bin/sssd/naics/naicsrch?chart=2007.
- U.S. Census Bureau. Number of Firms, Number of Establishments, Employment, Annual Payroll, and Receipts by Receipt Size of the Enterprise for the United States, All Industries -2002. Accessed at: http://www2.census.gov/csd/susb/2002/usalli_r02.xls.
- U.S. Census Bureau. State and County QuickFacts, Census 2006. Accessed at: http://quickfacts.census.gov/qfd on July 2008.

- U.S. Coast Guard (USCG). "Oil Spill Response Research & Development Program, A Decade of Achievement." U.S. Coast Guard Research & Development Center, Groton, CT 06340-6048, Report No. CG-D-07-03. Accessed at: http://www.uscg.mil/hq/cg9/rdc/Reports/2003/CGD0703Report.pdf
- U.S. Department of Agriculture. 2005 Census of Agriculture. Accessed at: http://www.agcensus.usda.gov/Publications/2002/Aquaculture/AQUACEN.pdf, on October 17, 2008.
- U.S. Department of the Interior, Bureau of Reclamation. 2006. Desalination and Water Purification Research and Development Program Report No. 111: Zero Discharge Seawater Desalination: Integrating the Production of Freshwater, Salt, Magnesium, and Bromine. Reclamation: Managing Water in the West. University of South Carolina Research Foundation Agreement No. 98-FC-81-0054.
- U.S. Environmental Protection Agency (EPA). "Guidelines for Preparing Economic Analyses," EPA 240-R-00-003, September 2000. Accessed at: http://yosemite.epa.gov/ee/epa/eed.nsf/ webpages/Guidelines.html.
- U.S. EPA, Office of Water. "National NPDES Minor Permit Issuance Strategy," Office of Water Enforcement and Permits, Permits Division, Technical Support Branch. January, 1986.
- U.S. EPA, "The NPDES Permitting Process for Oil and Gas Activities on the Outer Continental Shelf." Prepared by the Permits Division Office of Water Enforcement and Permits USEPA under the memorandum of understanding between EPA and the Minerals Management Service of the Department of the Interior. June 18, 1985.
- U.S. Environmental Protection Agency (EPA). "Region 10 Guidance For Pacific Northwest State and Tribal Temperature Water Quality Standards." EPA 910-B-03-002, April 2003.
- U.S. Environmental Protection Agency (EPA). *Region 10: the Pacific Northwest, Current EPA NPDES Permits in Oregon and Washington.* Accessed at: http://yosemite.epa.gov/r10/water.nsf/NPDES+Permits/CurrentOR&WA821 on July 2008.
- U.S. Environmental Protection Agency (EPA). *Region 9: Water Program, NPDES Permits and Stormwater, California.* Accessed at: http://www.epa.gov/region09/water/npdes/permits.html#epaissued. Web site accessed July 2008.
- U.S. Environmental Protection Agency, Department of the Interior, and the Department of Commerce, Memorandum of Agreement Between the Environmental Protection Agency, Fish and Wildlife Service and National Marine Fisheries Service Regarding Enhanced Coordination Under the Clean Water Act and Endangered Species Act; Notice, Federal Register Vol. 66, No. 36, February 22, 2001.
- U.S. Fish and Wildlife Service. *Endangered Species and Habitat Conservation Planning*. Accessed at: http://endangered.fws.gov/hcp/ in October 2008.
- U.S. Geological Survey. "Mission." Accessed at: http://www.usgs.gov/aboutusgs/ on May 2009.
- U.S. Office of Management and Budget. "Discount Rates for Cost-Effectiveness, Lease Purchase, and Related Analyses." Appendix C Revised December 2009. Available online at: http://www.whitehouse.gov/omb/circulars_a094_a94_appx-c/.

- U.S. Office of Management and Budget. "Circular A-4," September 17, 2003. Accessed at: http://www.whitehouse.gov/sites/default/files/omb/assets/omb/circulars/a004/a-4.pdf.
- U.S. Office of Management and Budget. 1992. "Circular A-94: Guidelines and Discount Rates for Benefit-Cost Analysis of Federal Programs." October 29, 1992. Accessed at: http://www.whitehouse.gov/omb/assets/a94/a094.pdf.
- U.S. Small Business Administration. Table of Small Business Size Standards Matched to North American Industry Classification System Codes. Accessed at: http://www.sba.gov/idc/groups/public/documents/sba_homepage/serv_sstd_tablepdf.pdf.
- Washington Department of Ecology. *Ground and Surface Water Quality Information, Water Quality Standards for Surface Waters, Washington.* Accessed at: http://www.ecy.wa.gov/programs/wq/links/standards.html on July 2008.
- Washington Department of Environmental Quality. Information on Ecology's Water Quality Permit Life Cycle System (WPLCS). Accessed at: http://www.ecy.wa.gov/programs/wq/permits/wplcs/index.html on July 30, 2008.
- Washington State Department of Ecology. 2006 Annual Report of Spill Prevention, Preparedness and Response Program. Vol. 10, No. 1, February 2007. WDOE Publication: 07-08-002. Accessed at: http://www.ecy.wa.gov/pubs/0708002.pdf
- Xian et al. (Jan. 2005), "Jellyfish Blooms in the Yangtze Estuary," Science, vol. 307.
- Zerbe, R., and D. Dively. 1994. "Benefit Cost Analysis in Theory and Practice," New York: HarperCollins.

APPENDIX A: NON-COST SUMMARY INFORMATION

Appendix A provides a table showing non-cost summary information for the seven categories identified in the report.⁶⁰ The information provided is: the areas the activity is located in, the PCE the activity could affect and the nature of that threat, the Section 7 nexus for that activity and the possible modifications that activity may have to implement due to leatherback critical habitat.

Activity	Areas	PCE and Nature of the threat	Section 7 nexus	Possible change to activity
NPDES	1,2,7	Prey PCE - may cause contamination of all stages of	Issuance of CWA	Where federal permits are necessary,
		jellyfish, including bioaccumulation of toxins	permits. State water	ensure discharge meets other federal
		through small prey ingestion. Limited studies have	quality standards are	standards and regulations (EPA,
		shown that jellyfish may concentrate higher levels of	subject to a section 7	CWA).
		metals (e.g., Cadmium) proportionately than fish, and	consultation between	Require measures to prevent or
		given the likely low energetic value of jellyfish and	NOAA and the EPA	respond to a catastrophic event (i.e.,
		the fact that leatherbacks therefore must consume	and NOAA can	using best technology to avoid
		large quantities to meet their needs, imply that they	review individual	unnecessary discharges.
		may be exposed to high levels of metals, particularly	NPDES permit	
		in coastal areas (Caurant et al. 1999). However the	applications for	
		effects of these levels on jellyfish or leatherbacks are	impacts on listed	
		unknown. Aquaculture facilities will also need	species.	
		NPDES permits, so impacts on prey from aquaculture		
		would be addressed here. Use of aquatic pesticides		
		also requires NPDES permits.		
		Impact on quantity of prey unknown.		
Agriculture	1,2,7	Prey PCE - Pesticide application is believed to affect	EPA consultation on	It is not known if or how agriculture
Pesticide		water quality, and prey resources available within the	FIFRA, pesticide	use of pesticides would need to be
Application		critical habitat areas. Agriculture and development	registration program,	modified as impacts on prey are
		increase nitrate loads, which are associated with	and NPDES permits	unknown. Existing biological

 Table A-1:
 Summary of Activities:
 Threat, Section 7 Nexus & Possible Modifications

⁶⁰ Note that while aquaculture was previously included in the analysis, with the removal of the passage PCE, it is no longer considered as an activity that may require special management.

			c : : : : :	
		eutrophication and increased scyphomedusae blooms	for aquatic pesticides	opinions require modifications of
		(Purcel et al. 2007). Blooms can disrupt the natural	(see National Cotton	pesticide use around salmon
		abundance, distribution, and availability of the	Council vs. EPA).	producing streams. It is assumed that
		primary food that leatherbacks forage on. It is	Also with USFS and	these protections are sufficient to
		difficult to characterize this threat since the effects of	BLM.	protect leatherback prey.
		pesticides on jellyfish and rate of diffusion within		
		marine waters is unknown.		
Oil spill	1,2,7	Prey PCE – spills or clean up may kill or compromise	Emergency	Unknown at this time, possible
		condition of prey (use of chemical dispersants, in situ	consultation with	changes include conducting surveys,
		burning). ⁶¹	USCG during and	changes in dispersants used, and use
			following oil spill	of in-situ burning in areas where
			USCG. Regulations	leatherback prey are found to be
			under the Water	present.
			Pollution Control Act	*
Power plants	1,7	Prey PCE – discharge of warm water may affect	License through the	Require cooling of thermal effluent
		health of jellyfish prey, although evidence that this	Nuclear Regulatory	before release to the environment
		may cause jellyfish blooms. The effects of	Commission	(may require use of different
		entrainment on prey resources are likely very		technology) and treatment of any
		localized and affect a small proportion of the coastal		contaminated waste materials.
		population of jellies. Purcell <i>et al.</i> (2007) report that		
		structures associated with coastal power plants may		
		serve as substrate for the polyp stage of jellyfish.		
Desalination	1,7	Prey PCE - Impingement or entrainment of jellyfish	A desalination	Potential conservation efforts to
plants		could result in localized and temporary detrimental	facility may require a	mitigate desalination impacts may
		impacts on the prey PCE. Also, the discharge of	Section 404 permit	include the treatment of hypersaline
		hypersaline water could affect jellyfish; however, this	from the U.S. Army	effluent to ensure that salinity levels
		is speculative and may have both beneficial and	Corps of Engineers if	are restored to normal values. The
		detrimental impacts.	it involves placing fill	costs of treating hypersaline effluent
		1	in navigable waters,	or finding an alternate manner of
			<i>o</i> ,	0

⁶¹ Note the safe passage was previously considered, however based on the comments received and our review of the proposed rule, migratory pathway conditions to allow for safe and timely passage and access to/from/within high use foraging areas has been eliminated as a PCE.

Tidal, wave, and wind energy projects	1,2	Prey PCE – possible disturbance to prey species during their benthic, polyp stage (although the location of the polyp fields are unknown). ⁶²	and a Section 10 permit if the proposal involves placing a structure in a navigable waterway. Tidal, wave, and wind energy projects are subject to FERC permitting and licensing requirements. The BOEM is responsible for projects on the outer continental shelf (in Federal waters). Section 401 of the Clean Water	brine disposal can vary widely across plants depending on plant capacity and design. Based on NMFS consultations on several pilot projects, project modifications could include installation of covers on turbines, installation of sampling gear, and biological monitoring. Potential modifications to these projects to mitigate adverse impacts may include spatial or temporal restrictions on project installation, operation, and maintenance.
LNG facilities	2	Prey PCE - Cold-water discharge, leaks and spills, release of anti-fouling chemicals into the water, disturbance of benthic habitat and noise could impact prey. Dredging and filling associated with construction and maintenance (to allow tanker passage) could have impacts on benthic habitat and possibly the early life stages of leatherback prey resources, although the location of polyp fields is not known. ⁶³	Act. Clean Water Act permits under section 401 (water quality certificate) and/or section 404 (a dredge and fill permit) and Clean Air Act permits under section 502 may be required	Potential modifications may include biological monitoring, spatial restrictions on project installation, and specific measures to prevent or respond to catastrophes. While LNG projects on the West Coast are still in the preliminary stages, NMFS has consulted on several projects on the East Coast, and has not yet required project modifications to mitigate adverse impacts to an aquatic species

	habitat.

APPENDIX B: LAWS AND REGULATIONS THAT MAY PROVIDE BASELINE PROTECTION FOR LEATHERBACK SEA TURTLES

Clean Water Act (33 U.S.C. 1251 ET SEQ. 1987)

The Clean Water Act (CWA) establishes the basic structure for regulating discharges of pollutants into the waters of the United States. It gives the Environmental Protection Agency (EPA) the authority to implement pollution control programs such as setting wastewater standards for industry. The CWA also continued requirements to set water quality standards for all contaminants in surface waters.

Pursuant to Section 404 of the CWA, it is unlawful for any person to dredge, dispose of dredge material, or discharge a pollutant from a point source into navigable waters, unless a permit is obtained from the U.S. Army Corps of Engineers (USACE). As part of pollution prevention activities, the USACE may limit activities in waterways through the Section 404 permitting process, independent of leatherback concerns. These reductions in pollution may benefit leatherback critical habitat.

Pursuant to Section 402 of the CWA and under the National Pollutant Discharge Elimination System (NPDES) program, EPA sets pollutant-specific limits on the point source discharges for major industries and provides permits to individual point sources that apply to these limits. Under the water quality standards program, EPA, in collaboration with States, establishes water quality criteria to regulate ambient concentrations of pollutants in surface waters.

Under section 401 of the CWA, all applicants for a Federal license or permit to conduct activity that may result in discharge to navigable waters are required to submit a State certification to the licensing or permitting agency. For example, the 1995 Bay-Delta Water Quality Control Plan and Water Right Decision 1641 incorporates objectives such as providing water for fish and wildlife, including anadromous fish. Costs associated with this and other existing water control plans are considered baseline protection in this analysis.

Magnuson-Stevens Fishery Conservation and Management Reauthorization Act 2006

This law signed by the President in January, 2007, amends the older Magnuson-Stevens Fishery Conservation and Management Act (as amended through 1996) that included bycatch reduction standards, and provision for the description of essential fish habitat in fishery management plans and consideration of actions to ensure the conservation and enhancement of habitat. The newer Magnuson-Stevens Reauthorization Act mandates the use of annual catch limits and accountability measures to end overfishing, provides for widespread market-based fishery management through limited access programs, and calls for increased international cooperation. This act may provide protection to leatherbacks by imposition of stringent bycatch measures.

Marine Mammal Protection Act of 1972 as Amended 2007

The Marine Mammal Protection Act (MMPA) was enacted in response to increasing concerns among scientists and the public that significant declines in some species of marine mammals were caused by human activities. The MMPA established a moratorium on the taking of marine mammals in U.S. waters.

Exceptions can only be made through permits/regulations for take incidental to commercial fishing, nonfishing activities (e.g., military exercises), scientific research, and public display.

Marine Protection, Research, and Sanctuaries Act of 1972

This Act authorizes the Secretary of Commerce to designate and manage areas of the marine environment with special national significance due to their conservation, recreational, ecological, historical, scientific, cultural, archeological, educational, or esthetic qualities as national marine sanctuaries. The Act also directs the Secretary to facilitate all public and private uses of those resources that are compatible with the primary objective of resource protection. Five sanctuaries have been designated within the leatherback critical habitat area: In California—Channel Islands, Cordell Bank, Gulf of Farallones, Monterey Bay; in Washington—Olympic Coast.

Federal Power Act (16 U.S.C. § 800 1920, as amended)

The Federal Power Act (FPA) was promulgated to establish the Federal Energy Regulatory Commission (FERC) to oversee non-Federal hydropower generation. The FERC is an independent Federal agency governing approximately 2,500 licenses for non- Federal hydropower facilities, has responsibility for national energy regulatory issues. This Act may provide protection to leatherback habitat from hydropower activities. Section 10(j) of the Federal Power Act (FPA) was promulgated to ensure that FERC considers both power and non-power resources during the licensing process. More specifically, section 18 of the FPA states that FERC shall require the construction, operation, and maintenance by a licensee at its own expense of a fish way if prescribed by the Secretaries of Interior (delegated to the Fish and Wildlife Service) and Commerce (NOAA).

Fish and Wildlife Coordination Act (16 U.S.C.§§ 661-666 1934, as amended)

This law provides that, whenever the waters or channels of a body of water are modified by a department or agency of the U.S. government, the department or agency must first consult with the U.S. Fish and Wildlife Service and with the head of the agency exercising administration over the wildlife resources of the State where modification will occur with a view to the conservation of wildlife resources. The purpose of this Act is to ensure that fish and wildlife resources are equally considered with other resources during the planning of water resources development projects by authorizing FWS to provide assistance to Federal and State agencies in protecting game species and studying the effects of pollution on wildlife. This Act may offer protection to leatherback habitat by requiring consultation concerning the species with FWS for all in stream activities with a Federal nexus.

Rivers and Harbors Act (33 USC §§ 401 ET SEQ. 1938)

The Rivers and Harbors Act (RHA) places Federal improvements of rivers, harbors and other waterways under the jurisdiction of the Department of the Army, USACE and requires that all improvements include due regard for wildlife conservation. This Act may provide protection to the leatherback critical habitat related to activities in bays and estuarine navigable waters. Under sections 9 and 10 of the RHA, the USACE is authorized to regulate the construction of any structure or work within navigable waterways. This includes, for example, bridges and docks.

National Environmental Policy Act (42 USC §§ 4321-4345 1969)

The National Environmental Policy Act (NEPA) requires that all Federal agencies conduct a detailed environmental impact statement (EIS) in every recommendation or report on proposals for legislation and other major Federal actions significantly affecting the quality of the human environment. The NEPA process may provide protection to the leatherback critical habitat for activities that have Federal involvement, if alternatives are considered and selected that are less harmful to leatherback critical habitat than other alternatives.

The Sikes Improvements Act (16 USC §670 1997)

The Sikes Improvement Act (SIA) requires military installations to prepare and implement an Integrated Natural Resources Management Plan (INRMP). The purpose of the INRMP is to provide for:

- The conservation and rehabilitation of natural resources on military installations;
- The sustainable multipurpose use of the resources, which shall include hunting, fishing, trapping, and nonconsumptive uses; and
- Subject to safety requirements and military security, public access to military installations to facilitate the use of the resources.

INRMPs developed in accordance with SIA may provide protection to leatherback critical habitat within military training ranges.

California Environmental Quality Act (CEQA) (California Natural Resources Code §15065(A))

CEQA is a California State statute that requires State and local agencies (known as "lead agencies") to identify the significant environmental impacts of their actions and to avoid or mitigate those impacts, if feasible. Projects carried out by Federal agencies are not subject to CEQA provisions. CEQA instructs the lead agency (typically a county or city community development or planning department in the case of land development projects) to examine impacts from a broad perspective, taking into account the value of species' habitats that may be impacted by the project in an Environmental Impact Report (EIR). The lead agency must determine which, if any, project impacts are potentially significant and, for any such impacts identified, whether feasible mitigation measures or feasible alternatives will reduce the impacts to a level less than significant. It is within the power of a lead agency to decide that negative impacts are acceptable in light of economic, social, or other benefits generated by the project.

Long-term Management Strategy (LTMS) for the Placement of Dredged Material in the San Francisco Bay Region

The LTMS is a multi-agency effort on the part of the USACE, EPA, NOAA and others to eliminate unnecessary dredging and maintain in an economically and environmentally sound manner those channels necessary for navigation in San Francisco Bay and Estuary. The LTMS also establishes dredging windows for salmon and other aquatic species. These seasonal limitations on dredging are intended to accommodate salmon spawning, which may have ancillary benefits for leatherback critical habitat.

The Comprehensive Conservation and Management Plan for the San Francisco Bay-delta Estuary

The Comprehensive Conservation and Management Plan for the San Francisco Bay-Delta Estuary helps to restore and maintain the estuary's water quality and natural resources. This plan is jointly sponsored by the EPA and the State of California, and is considered to be a blueprint for restoring and maintaining the chemical, physical, and biological integrity of the Bay and Delta. Many of the recommended actions may improve leatherback prey distribution, diversity, and abundance by improving water quality.

Keene-Nielsen Fisheries Restoration Act of 1985

This Act states that California intends to make reasonable efforts to prevent further declines in fish and wildlife, restore fish and wildlife to historic levels where possible, and enhance fish and wildlife resources where possible. Just over \$15 million were initially authorized in approved legislation; however, only \$11.3 million were actually appropriated between 1985 and 1987. The Act was reworded through 1990 legislation to closely tie expenditures from this account to projects called for under the Salmon, Steelhead Trout, and Anadromous Fisheries Program Act of 1988. However, the legislation provided no funding to the Keene-Nielsen account, nor have the budgets of subsequent governors.

Other Statues and Regulations that Apply to Land Use Activities

While the following statutes and regulations may apply to lands and waters that fall within leatherback habitat areas, they are unlikely to provide significant baseline protections and are not considered in the analysis.

• North American Wetland Conservation Act (16 USC § 4401 et seq. 1989) - NAWCA encourages partnerships among public agencies and other interests to protect, enhance, restore and manage an appropriate distribution and diversity of wetland ecosystems and other habitats for migratory birds and other fish and wildlife.

• *Executive Order 11988 and 11990 (1977)* – These Executive Orders require, to the extent possible, prevention of long and short term adverse impacts associated with the occupancy and modification of floodplains and prevention of direct or indirect support of floodplain development wherever there is a practicable alternative.

• *Coastal Zone Management Act (16 USC §§ 1451 et seq. 1972)* – CZMA establishes an extensive Federal grant program to encourage coastal States to develop and implement coastal zone management programs to provide for protection of natural resources, including wetlands, flood plains, estuaries, beaches, dunes, barrier islands, coral reefs, and fish and wildlife and their habitat.

• *California Endangered Species Act (California Fish and Game Code §§ 2050, et seq.)* - The CESA parallels the main provisions of the Federal Endangered Species Act and is administered by the California Department of Fish and Game (DFG). CESA prohibits the "taking" (the California Fish and Game Code defines "take" as "hunt, pursue, catch, capture, or kill, or attempt to hunt, pursue, catch, capture, or kill") of listed species except as otherwise provided in State law. The CESA also applies the take prohibitions to species petitioned for listing ("candidate species").

APPENDIX C: INCREMENTAL SCORE SENSITIVITY ANALYSIS

Section 2 of this analysis presents estimated annualized impacts by area and economic activity. These estimated impacts assume that a certain baseline level of protection is afforded leatherbacks from 1) the overlap of previously designated critical habitat for other species within leatherback critical habitat, 2) the presence of other listed species and protected marine mammals within leatherback critical habitat, and 3) the Federal, state and local protections already in place to conserve and protect marine resources. However, a degree of uncertainty exists regarding this level of baseline protection and future actions likely to be undertaken specifically for the benefit of the leatherbacks and their habitat.

Because of this level of uncertainty, this appendix presents impacts without applying the "incremental scores," in order to inform decision-makers about the range of potential impacts. Table C-1 presents total un-scaled impacts by area, as well as the difference between these impacts and those estimated in previous chapters, which applied incremental scores. The ranking of total area impacts does not change for the low, midpoint, and high scenarios, when comparing costs that incorporate incremental scores compared to costs without incremental scores.

	No Incren	No Incremental Scores			With Incremental Scores			Difference		
Area	Low*	Mid	High**	Low*	Mid	High**	Low*	Mid	High**	
1	\$312,000	\$13,751,000	\$27,190,000	\$94,000	\$4,125,000	\$8,157,000	\$218,000	\$9,626,000	\$19,03	
2	\$52,000	\$793,000	\$1,534,000	\$16,000	\$238,000	\$460,000	\$36,000	\$555,000	\$1,074,	
7	\$260,000	\$921,000	\$1,582,000	\$78,000	\$276,000	\$475,000	\$182,000	\$645,000	\$1,107,	
Total	\$624,000	\$15,465,000	\$30,306,000	\$188,000	\$4,639,000	\$9,092,000	\$436,000	\$10,826,000	\$21,214	

Table C-1: Summary of Annualized Impacts by Area

**where applicable, < 1 mile buffer use

*where applicable, < 5 miles used

	Annualize	ed Impacts		A stivition with order a smalitation analysis
Area	Low	Mid	High	 Activities with only a qualitative analysis (NOT included in the estimated costs)
				Power plants, oil spill response, agricultural
1	\$94,000	\$4,125,000	\$8,157,000	pesticides
				Wind energy, LNG and oil spill response,
2	\$16,000	\$238,000	\$460,000	agricultural pesticides
				Power plants, oil spill response, agricultural
7	\$78,000	\$276,000	\$475,000	pesticides
				Power plants, wind energy, LNG and oil
Total	\$188,000	\$4,639,000	\$9,092,000	spill response, agricultural pesticides

Table C-2: Summary of Economic Impacts to NPDES Facilities by Area

		Total Annu	Total Annualized Costs				
	Buffer	Minor			Major		
Area	Zone	Low	Mid	High	Low	Mid	High
1	<1	\$0	\$22,000	\$44,000	\$312,000	\$406,000	\$500,000
1	<5	\$0	\$37,000	\$74,000	\$572,000	\$745,000	\$917,000
2	<1	\$0	\$118,000	\$237,000	\$52,000	\$68,000	\$83,000
2	<5	\$0	\$348,000	\$696,000	\$312,000	\$406,000	\$500,000
7	<1	\$0	\$22,000	\$44,000	\$260,000	\$339,000	\$417,000
/	<5	\$0	\$37,000	\$74,000	\$312,000	\$406,000	\$500,000
Total	<1	\$0	\$163,000	\$326,000	\$624,000	\$813,000	\$1,001,000
Total	<5	\$0	\$422,000	\$844,000	\$1,197,000	\$1,558,000	\$1,918,000

		Total Annualized Costs					
A	rea	Low	Mid	High			
1		\$0	\$12,874,000	\$25,748,000			
7		\$0	\$504,000	\$1,007,000			
Т	'otal	\$0	\$13,377,000	\$26,755,000			

Table C-4: Summary of Economic Impacts of Desalination Projects by Area

Table C-5: Summary of Economic Impacts to Tidal, Wave, and Wind* Energy Projects by Area

Area	Total Annualized Costs
1	\$270,000
2	\$270,000
Total	\$541,000

*Wind energy is not included here since costs could not be quantified.

APPENDIX D: DISCOUNT RATE SENSITIVITY ANALYSIS

Appendix D provides a discount rate sensitivity analysis for present discounted values of annualized costs by activity, in 2009 dollars, shown in Table 3-3. The "Annualized Costs" column summarizes the costs used throughout Section 2. The "Present Value" columns are calculated based on the annualized cost, across the indicated timeframe, and discounted using a 0, 3, and 7 percent discount rates. The 0 and 7 percent discount rate present values are used to test the sensitivity of the 3 percent rate used in Table 3-3. Table D-1 shows the present discounted value cost estimates, in 2009 dollars, by activity, comparing calculations at all three discount rates.

					Present Value	Present Value
	Cost		Annualized	Timeframe	(Discounted	Value (Discounted
Activity	Category	Metric	Costs	(years)	at 3%)	at 7%)
NPDES:	Low		\$0		\$0	\$0
Minor	Midpoint	per plant	\$7,000	20	\$104,000	\$74,000
Facilities	High	plant	\$15,000		\$223,000	\$159,000
NPDES:	Low		\$52,000		\$774,000	\$551,000
Major	Midpoint	per plant	\$68,000	20	\$1,012,000	\$720,000
Facilities	High	plant	\$83,000		\$1,235,000	\$879,000
	Low: Area 1	per unit	\$0		\$0	\$0
Desalination	High: Area 1	based	\$1,515,000	20	\$22,539,000	\$16,050,000
Desamation	Low: Area 7	on plant	\$0	20	\$0	\$0
	High: Area 7	capacity	\$126,000		\$1,875,000	\$1,335,000
Tidal,						
Wave, &		per		30		
Wind		project		30		
Energy	N/A		\$68,000		\$1,333,000	\$844,000

 Table 3-3: Present Discounted Value of Annualized Costs by Activity, in 2009 dollars

APPENDIX E: FINAL REGULATORY FLEXIBILITY ANALYSIS

This analysis considers the extent to which the potential economic impacts associated with the designation of critical habitat for the leatherback sea turtle could be borne by small businesses. The analysis presented is conducted pursuant to the Regulatory Flexibility Act (RFA) as amended by the Small Business Regulatory Enforcement Fairness Act (SBREFA) of 1996. Information for this analysis was gathered from the Small Business Administration (SBA) and U.S. Census Bureau.

Introduction

First enacted in 1980, the RFA was designed to ensure that the government considers the potential for its regulations to unduly inhibit the ability of small entities to compete. The goals of the RFA include increasing the government's awareness of the impact of regulations on small entities and to encourage agencies to exercise flexibility to provide regulatory relief to small entities.

When a Federal agency proposes regulations, the RFA requires the agency to prepare and make available for public comment an analysis that describes the effect of the rule on small entities (i.e., small businesses, small organizations, and small government jurisdictions). For this rulemaking, this analysis takes the form of a final regulatory flexibility analysis (FRFA). Under 5 U.S.C., Section 603(b) of the RFA, an FRFA is required to contain:

- i. A description of the reasons why action by the agency is being considered;
- ii. A succinct statement of the objectives of, and legal basis for, the final rule;
- iii. A description of and, where feasible, an estimate of the number of small entities to which the final rule will apply;
- iv. A description of the projected reporting, recordkeeping and other compliance requirements of the final rule, including an estimate of the classes of small entities which will be subject to the requirement and the type of professional skills necessary for preparation of the report or record;
- v. An identification, to the extent practicable, of all relevant Federal rules which may duplicate, overlap or conflict with the final rule;
- vi. Each final regulatory flexibility analysis shall also contain a description of any significant alternatives to the final rule which accomplish the stated objectives of applicable statutes and which minimize any significant economic impact of the final rule on small entities.

Needs and Objective of the Rule

The leatherback sea turtle was listed as endangered throughout its range under the Endangered Species Act (ESA) on June 2, 1970 (35 FR 8491). Section 4(b)(2) of the ESA requires NOAA to designate critical habitat for threatened and endangered species "on the basis of the best scientific data available and after taking into consideration the economic impact, impact on national security, and any other relevant impact, of specifying any particular area as critical habitat." The ESA defines critical habitat under Section 3(5) (A) as:

"(i) the specific areas within the geographical area occupied by the species, at the time it is listed..., on which are found those physical or biological features (I) essential to the conservation of the species and (II) which may require special management considerations or protection; and (ii) specific areas outside the geographical area occupied by the species at the time it is listed...upon a determination by the Secretary that such areas are essential for the conservation of the species."

DESCRIPTION AND ESTIMATE OF THE NUMBER OF SMALL ENTITIES TO WHICH THE RULE APPLIES

Definition of a Small Entity

Three types of small entities are defined in the RFA:

- i. Small Business. Section 601(3) of the RFA defines a small business as having the same meaning as small business concern under section 3 of the Small Business Act. This includes any firm that is independently owned and operated and is not dominant in its field of operation. The U.S. Small Business Administration (SBA) has developed size standards to carry out the purposes of the Small Business Act, and those size standards can be found in 13 CFR 121.201. The size standards are matched to North American Industry Classification System (NAICS) industries. The SBA definition of a small business applies to a firm's parent company and all affiliates as a single entity.
- ii. **Small Governmental Jurisdiction.** Section 601(5) defines small governmental jurisdictions as governments of cities, counties, towns, townships, villages, school districts, or special districts with a population of less than 50,000. Special districts may include those servicing irrigation, ports, parks and recreation, sanitation, drainage, soil and water conservation, road assessment, etc. Most tribal governments will also meet this standard. When counties have populations greater than 50,000, those municipalities of fewer than 50,000 can be identified using population reports. Other types of small government entities are not as easily identified under this standard, as they are not typically classified by population.
- iii. **Small Organization.** Section 601(4) defines a small organization as any not-for-profit enterprise that is independently owned and operated and not dominant in its field. Small organizations may include private hospitals, educational institutions, irrigation districts, public utilities, agricultural co-ops, etc. Depending upon state laws, it may be difficult to distinguish whether a small entity is a government or non-profit entity. For example, a water supply entity may be a cooperative owned by its members in one case and in another a publicly chartered small government with the assets owned publicly and officers elected at the same elections as other public officials.

Description of Economic Activities for which Impacts are Most Likely

Any activity conducted by a small entity that affects the habitat or habitat features essential to the leatherback sea turtle has the potential to be affected by the critical habitat designation. As described in the main text of this analysis, NMFS identified seven categories of economic activity as potentially requiring modification to avoid destruction or adverse modification of the leatherback sea turtle critical habitat. These "activities" include the operation of some facilities, such as water temperature controls, where special management of operations may be required for the leatherback sea turtle. The following are the economic activities assessed in this FRFA:⁶⁴

- i. NPDES permit activities
- ii. Agricultural pesticides
- iii. Oil spills
- iv. Power plants
- v. Desalination plants
- vi. Tidal, wave, and wind energy projects
- vii. Liquefied natural gas (LNG) projects

As discussed earlier in this report, a great deal of uncertainty exists with regard to how potentially regulated entities will attempt to avoid the destruction or adverse modification of critical habitat. This is because relatively little data exist on the effects to leatherback sea turtles and their prey from aspects of the activities identified (i.e., water quality, water temperature, etc.) In addition, while baseline protections are expected to be afforded due to current listing-related conservation measures, the economic analysis estimates the incremental impacts resulting specifically from the critical habitat designation. This FRFA estimates the potential number of small businesses that may be affected by this rule, and the average annualized impact per entity for a given area and activity type. Specifically, based on an examination of the North American Industry Classification System (NAICS), this analysis classifies the potentially affected economic activities into industry sectors and provides an estimate of the number of small businesses affected in each sector based on the applicable NAICS codes. Table E-1 presents a list of the major relevant activities and descriptions of the industry sectors involved in those activities, including NAICS codes, and the SBA thresholds for determining whether a business is small.

This FRFA does not consider all types of small businesses that could be affected by the critical habitat designation due to lack of information.

Impacts to small businesses involved in the remaining 6 activities are discussed below.

⁶⁴ Note that while aquaculture was previously included in the analysis, with the removal of the passage PCE, it is no longer considered as an activity that may require special management.

Activity	Description of included industry sectors	NAICS code	SBA size standard
	Water Supply and Irrigation Systems This industry comprises establishments primarily engaged in operating water treatment plants and/or operating water supply systems. The water supply system may include pumping stations, aqueducts, and/or distribution mains. The water may be used for drinking, irrigation, or other uses.	221310	\$7.0 million average annual receipts
	Sewage Treatment Facilities This industry comprises establishments primarily engaged in operating sewer systems or sewage treatment facilities that collect, treat, and dispose of waste.		\$7.0 million average annual receipts
NPDES	Food Manufacturing Industries in this sector transform livestock and agricultural products into products for intermediate or final consumption. The industry groups are distinguished by the raw materials (generally of animal or vegetable origin) processed into food products.	311	500 employees
	Wood Product Manufacturing Industries in this sector manufacture wood products, such as lumber, plywood, veneers, wood containers, wood flooring, wood trusses, manufactured homes (i.e., mobile home), and prefabricated wood buildings.	321	500 employees
	Paper and Pulp Mills This industry comprises establishments primarily engaged in manufacturing paper and/or pulp.	322	750 employees
Agricultural Pesticides	Farm Supplies Merchant Wholesalers This industry comprises establishments primarily engaged in the merchant wholesale distribution of farm supplies, such as animal feeds, fertilizers, agricultural chemicals, pesticides, plant seeds, and plant bulbs.	424910	100 employees
Oil Spills	Deep Sea, Coastal, and Great Lakes Water Transportation This industry comprises establishments primarily engaged in providing deep sea, coastal, Great Lakes, and St. Lawrence Seaway water transportation. Marine transportation establishments using the facilities of the St. Lawrence Seaway Authority Commission are considered to be using the Great Lakes Water Transportation System.	48311	500 employees
	Marinas This industry comprises establishments, commonly known as marinas, engaged in operating	713930	\$7.0 million average annual

Table E-1: Major Relevant Activities and a Description of the Industry Sectors Engaged in those Activities

		NAICS	SBA size
Activity	Description of included industry sectors	code	standard
	docking and/or storage facilities for pleasure craft owners, with or without one or more related		receipts
	activities, such as retailing fuel and marine supplies; and repairing, maintaining, or renting pleasure		
	boats.		
	Fossil Fuel Electric Power Generation		
	This U.S. industry comprises establishments primarily engaged in operating fossil fuel powered		4 million
	electric power generation facilities. These facilities use fossil fuels, such as coal, oil, or gas, in	221112	megawatts for
	internal combustion or combustion turbine conventional steam process to produce electric energy.	221112	the preceding
	The electric energy produced in these establishments is provided to electric power transmission		year ¹
	systems or to electric power distribution systems.		
	Nuclear Electric Power Generation		4 million
	This U.S. industry comprises establishments primarily engaged in operating nuclear electric power		megawatts for
Power Plants	generation facilities. These facilities use nuclear power to produce electric energy. The electric	221113	the preceding
rower rialits	energy produced in these establishments is provided to electric power transmission systems or to		year ¹
	electric power distribution systems.		year
	Electric Power Transmission, Control, and Distribution		
	This industry comprises establishments primarily engaged in operating electric power transmission		4 million
	systems, controlling (i.e., regulating voltages) the transmission of electricity, and/or distributing		megawatts for
	electricity. The transmission system includes lines and transformer stations. These establishments	22112	the preceding
	arrange, facilitate, or coordinate the transmission of electricity from the generating source to the		year1
	distribution centers, other electric utilities, or final consumers. The distribution system consists of		year r
	lines, poles, meters, and wiring that deliver the electricity to final consumers.		
	Hydroelectric Power Generation		4 million
	This U.S. industry comprises establishments primarily engaged in operating hydroelectric power		megawatts for
Tidal, Wave,	generation facilities. These facilities use water power to drive a turbine and produce electric	221111	the preceding
and Wind	energy. The electric energy produced in these establishments is provided to electric power		year1
	transmission systems or to electric power distribution systems.		yearr
Energy	Other Electric Power Generation		4 million
	This U.S. industry comprises establishments primarily engaged in operating electric power	221119	megawatts for
	generation facilities (except hydroelectric, fossil fuel, nuclear). These facilities convert other forms		the preceding

		NAICS	SBA size
Activity	Description of included industry sectors	code	standard
	of energy, such as solar, wind, or tidal power, into electrical energy. The electric energy produced		year ¹
	in these establishments is provided to electric power transmission systems or to electric power		
	distribution systems.		
	Natural Gas Liquid Extraction		
LNG	This U.S. industry comprises establishments primarily engaged in the recovery of liquid	211112	500 employees
LNG	hydrocarbons from oil and gas field gases. Establishments primarily engaged in sulfur recovery		500 employees
	from natural gas are included in this industry.		

Note:

(1) All entities in the Electric Services Sectors are assumed to be small entities. Consequently, the number for small entities in these sectors represents an upper bound estimate. The number of small entities in the hydroelectric power generation and electrical services industries is unknown because of the unavailability of data related to small business thresholds. For both of these industry sectors the SBA defines a firm as "small" if, including its affiliates, it is primarily engaged in the generation, transmission, and/or distribution of electric energy for sale, and its total electric output for the preceding fiscal year did not exceed 4 million megawatt hours. It was not possible to locate a source that provides this information for all regulated entities within these sectors.

Sources:

Definitions complied from U.S. Census Bureau. North American Industry Classification System (NAICS). Accessed at:

http://www.census.gov/cgi-bin/sssd/naics/naicsrch?chart=2007; SBA size standards complied from U.S. Small Business Administration. Table of Small Business Size Standards Matched to North American Industry Classification System Codes. Accessed at:

http://www.sba.gov/idc/groups/public/documents/sba homepage/serv sstd tablepdf.pdf.

ESTIMATE OF THE NUMBER OF SMALL ENTITIES TO WHICH THE RULE WILL APPLY

Approach for Estimating the Number of Small Entities

The occupied areas considered for designation of critical habitat, and hence the action area for this rule, spans from Northern Washington to Southern California. NMFS defined the potential critical habitat areas in Section 1 and identified activities in Section 2, both water and land based, that could be affected by the designation. Although the critical habitat areas include marine areas off the coast, the small business analysis is focused on land based areas, which is consistent with Section 2, where most economic activities occur and which could be affected by the designation.

Ideally, this analysis would directly identify the number of small entities that are located within the coastal areas adjacent to the designated critical habitat areas. However, it is not possible to directly determine the number of firms in each industry sector within these areas because business activity data is maintained at the county level. Therefore, this analysis provides a maximum number of small businesses that could be affected. This number is most likely inflated since all of the identified small businesses are unlikely to be located in close proximity of the critical habitat areas.

After determining the number of small entities, this analysis estimates the impact per entity for each area and industry sector. The following steps were used to provide these estimates:

- Total impact for every area and activity type is determined based on the results presented earlier in this report (see Executive Summary);
- The proportion of businesses that are small is calculated for every area for every activity type;
- The impact to small businesses for every area and activity type is estimated by multiplying the total impacts estimated for all businesses with the proportion of businesses that are determined to be small;
- The average impact per small businesses is estimated by taking the ratio of the total estimated impacts to the total number of small businesses.

Discussion of Results

The twenty-six counties that make up the West Coast and may be affected by leatherback sea turtle critical habitat designation represent a range of urban and rural environments. The list of counties, industry sectors (identified by NAICS codes), and the SBA-specified small business size thresholds was used to search the U.S. Census Bureau database.⁶⁵ The states of Washington, Oregon, and California respectively include 4, 7, and 15 of these counties. An estimate of the total number of small entities that could be potentially affected by the designation is summarized in Tables E-2, E-3a, E-3b, E-3c, and E-4.

Demographic Data

Table E-2 shows the socioeconomic profile of the applicable West Coast Counties. Los Angeles County is the most populous county of the twenty-six with a population of nearly 10 million in 2006, representing about 27.3 percent of the population of California. Orange County has the second largest population of

⁶⁵ NAICS codes can be accessed from the US Census Bureau website:

http://www.census.gov/epcd/www/naics.html; and the U.S. Census Bureau. *Number of Firms, Number of Establishments, Employment, Annual Payroll, and Receipts by Receipt Size of the Enterprise for the United States, All Industries -2002.* Accessed at: http://www2.census.gov/csd/susb/2002/usalli_r02.xls.

the twenty-six counties, with a little over 3 million people in 2006. Orange County contained 8.2 percent of California's population. Pacific and Curry Counties have the smallest populations of the twenty-six counties with 21,735 and 22,358 people, respectively, in 2006.

The populations in all West Coast Counties in the states of Washington and Oregon, and most of the counties in California have been growing. Between 2000 and 2006, the largest growth has been in Jefferson County where population increased 11.3 percent. San Francisco, Santa Cruz, and San Mateo Counties were the only counties to have negative growths between 2000 and 2006. Their growth rates were -4.2, -2.3, and -0.2 percent, respectively.

Median per capita income in 18 of the 26 counties is lower than median per capita income for their respective state. The poverty rate in thirteen of the twenty-six counties exceeds the poverty rate of their respective state. In Del Norte County, the poverty rate is the highest among the twenty-six counties with 19.2 percent of residents below the poverty threshold.

Thirteen of these counties are more densely populated compared to the statewide population density. Notice that San Francisco County has a large population density of nearly 10,000 people per square mile, but only holds 2 percent of the population of California. In short, the counties bordering critical habitat for the leatherbacks range from rural, lightly populated counties with as few as 13 persons per square mile to urban, heavily populated counties with as many as 10,000 persons per square mile. The spectrum of economic welfare across the twenty-six counties is equally diverse encompassing counties with median per capita income of about 14,000 in Del Norte County to Marin County with per capita income over \$44,000.

		_			%	Per		Population
				% of	Change	Capita	Poverty	Density
			Population	Statewide	(2000-	Income	Rate	(persons/sq
Area	State	County	(2006)	Population	2006)	(1999)	(2004)	mi)
1	California	Sonoma	466,891	1.30%	1.80%	25,724	8.40%	291
1	California	Marin	248,742	0.70%	0.60%	44,962	7.00%	475.6
1	California	San Francisco	744,041	2.00%	-4.20%	34,556	11.60%	9,999.90
1	California	San Mateo	705,499	1.90%	-0.20%	36,045	6.60%	1,575.00
1	California	Santa Cruz	249,705	0.70%	-2.30%	26,396	10.80%	574.4
1&7	California	Monterey	410,206	1.10%	2.10%	20,165	12.90%	120.9
2	Washington	Clallam	70,400	1.10%	9.70%	19,517	12.30%	37.1
2	Washington	Jefferson	29,279	0.50%	11.30%	22,211	10.90%	14.3
2	Washington	Grays Harbor	71,587	1.10%	6.50%	16,799	15.80%	35.1
2	Washington	Pacific	21,735	0.30%	3.60%	17,322	14.50%	22.5
2	Oregon	Clatsop	37,315	1.00%	4.70%	19,515	13.00%	43.1
2	Oregon	Tillamook	25,380	0.70%	4.60%	19,052	12.90%	22
2	Oregon	Lincoln	46,199	1.20%	3.90%	18,692	15.30%	45.4

Table E-2: Socioeconomic profile of counties bordering potential leatherback critical habitat

2	Oregon	Lane	337,870	9.10%	4.60%	19,681	14.90%	70.9		
7	California	San Luis Obispo	257,005	0.70%	4.20%	21,864	10.40%	74.7		
7	California	Santa Barbara	400,335	1.10%	0.20%	23,059	12.50%	145.9		
7	California	Ventura	799,720	2.20%	6.20%	24,600	9.30%	408.2		
7	California	Los Angeles	9,948,081	27.30%	4.50%	20,683	16.70%	2,344.10		
Source: U.S. Census Bureau. State and County QuickFacts, Census 2006. Accessed at:										
http://	quickfacts.censu	http://quickfacts.census.gov/qfd on July 2008.								

Small Business Analysis

Tables E-3a, E-3b, and E-3c present the distribution of small businesses by area and by county for businesses with employee, revenue, and capacity constraints, respectively. There is a maximum of 3,458 small businesses involved in activities most likely to be affected by the final rule.⁶⁶ Of these small businesses, 3,022 (87 percent) are located in California, 301 in Oregon (9 percent), and 134 (4 percent) in Washington. Thus, a majority of the impacts is expected to be concentrated in California. Los Angeles County in California has the maximum number (1,853) of the estimated small affected businesses. Lane County in Oregon and Sonoma, San Francisco, San Mateo, and Ventura counties of California contain about 140 or more small businesses that may be affected by this rule.

⁶⁶ This is based on the assumption that all small businesses counted across units and activity types are separate entities. However, it is likely that a particular small business may appear multiple times as being affected by conservation measures for multiple units and activity types. Hence, total small business estimates across units and activity types are likely to be overestimated.

Max.	# of employees to						
be cor	sidered small:	500	500	500	750	100	500
						424910 – Farm	48311 – Deep
		211112 -				Supplies	Sea, Coastal, and
		Natural Gas		321 – Wood	322 -	Merchant	Great Lakes
	NAICS Code –	Liquid	311 – Food	Product	Paper and	Wholesalers	Water
	Category	Extraction	Manufacturing	Manufacturing	Pulp Mills	(Agricultural	Transportation
Area	(Activity)	(LNG)	(NPDES)	(NPDES)	(NPDES)	Pesticides)	(Oil Spills)
2	Clallam	0	3	20	1	2	1
2	Jefferson	0	5	2	1	0	2
2	Grays Harbor	0	9	36	4	0	2
2	Pacific	0	15	6	0	1	0
2	Clatsop	0	17	3	0	0	1
2	Tillamook	0	8	5	1	1	0
2	Lincoln	0	11	5	1	1	0
2	Lane	0	52	77	5	11	0
2	Douglas	0	5	34	1	0	0
2	Coos	0	11	19	0	0	3
1	Sonoma	N/A	82	40	1	10	1
1	Marin	N/A	26	11	1	4	2
1	San Francisco	N/A	116	11	6	7	4
1	San Mateo	N/A	91	11	11	3	2
1	Santa Cruz	N/A	41	13	1	5	0
1&7	Monterey	0	70	10	4	25	1
7	San Luis Obispo	N/A	27	3	3	8	0
Total	1	0	589	306	41	78	19

 Table E-3a: Estimated Number of Regulated Entities that are Small, with Employee Constraints (by area, county, and activity type)

Max. a	mount of				
revenu	e to be				
conside	ered small:	\$7.0 million	\$7.0 million	\$7.0 million	
		221310 –Water			
		Supply and	221320 -		
	NAICS Code –	Irrigation	Sewage	713930 -	
	Category	Systems	Treatment Plant	Marinas (Oil	
Area	(Activity)	(NPDES)	(NPDES)	Spills)	
2	Clallam	9	0	2	
2	Jefferson	3	2	4	
2	Grays Harbor	2	0	0	
2	Pacific	3	0	0	
2	Clatsop	6	0	0	
2	Tillamook	2	0	2	
2	Lincoln	1	0	0	
2	Lane	3	1	2	
2	Douglas	3	0	0	
2	Coos	0	0	2	
1	Sonoma	11	0	2	
1	Marin	2	0	11	
1	San Francisco	2	0	4	
1	San Mateo	10	2	6	
1	Santa Cruz	4	0	1	
1&7	Monterey	12	1	3	
7	San Luis Obispo	13	0	3	
Total		86	6	42	

 Table E-3b:
 Estimated Number of Regulated Entities that are Small, with Revenue Constraints (by area, county, and activity type)

Max. a	amount of		4 million	4 million	4 million	
	ty to be	4 million	megawatts	megawatts	megawatts	4 million
-	ered small:	megawatts for	for the	for the	for the	megawatts for
		the preceding	preceding	preceding	preceding	the preceding
		year ¹				
					221119 -	
			221112 -	221113 -	Other	
		221111 -	Fossil Fuel	Nuclear	Electric	22112 -
		Hydroelectric	Electric	Electric	Power	Electric Power
		Power	Power	Power	Generation	Transmission,
	NAICS Code –	Generation	Generation	Generation	(Tidal,	Control, and
	Category	(Tidal, Wave,	(Power	(Power	Wave, and	Distribution
Area	(Activity)	and Wind)	Plants)	Plants)	Wind)	(Power Plants)
2	Clallam	0	N/A	N/A	0	N/A
2	Jefferson	0	N/A	N/A	0	N/A
2	Grays Harbor	0	N/A	N/A	0	N/A
2	Pacific	0	N/A	N/A	0	N/A
2	Clatsop	0	N/A	N/A	0	N/A
2	Tillamook	0	N/A	N/A	0	N/A
2	Lincoln	0	N/A	N/A	0	N/A
2	Lane	2	N/A	N/A	0	N/A
2	Douglas	0	N/A	N/A	0	N/A
2	Coos	0	N/A	N/A	0	N/A
1	Sonoma	0	0	0	0	1
1	Marin	0	0	0	2	1
1	San Francisco	0	0	0	0	5
1	San Mateo	0	0	0	0	2
1	Santa Cruz	0	1	0	0	1
1&7	Monterey	2	2	0	0	2
	San Luis					
7	Obispo	N/A	1	0	N/A	1
Total		4	4	0	2	13

 Table E-3c:
 Estimated Number of Regulated Entities that are Small, with Capacity Constraints (by area, county, and activity type)

Table E-4 sums the information displayed in Tables E-3a, E-3b, and E-3c, and presents the total number of small businesses by area. Efforts associated with Areas 1 and 2 are expected to impact a maximum of 632 and 430 small entities, respectively

Small businesses receiving National Pollutant Discharge Elimination System (NPDES) permits represent the largest number (2,908) of the potentially affected small entities. This group includes the manufacturing sector (e.g., food processing facilities, paper and pulp mills or sewage treatment plants). Another 179 and 170 small businesses involved in agricultural pesticide use and oil spills, respectively, are also expected to be affected by the final rule. Thus, water quality concerns are expected to be the reason that 96 percent of the small entities will be affected. As identified in the final rule, States and the Environmental Protection Agency (EPA) have already established acceptable levels of contaminants in waterways. Entities are already required to obtain the National Pollutant Discharge Elimination System (NPDES) permits to discharge contaminants. In cases where NPDES permits are not required, monitoring and compliance with the clean water standards set by the EPA and the States may be required to avoid the destruction or adverse modification of critical habitat for leatherback sea turtle.

Area	NPDES ¹	Agricultural Pesticides	Oil Spills ²	Power Plant	Tidal, Wave, and Wind Energy	LNG	Total
1	541	42	34	13	3		632
2	391	16	21		2	0	430
7	122	31	6	5			163
Total	1,054	89	61	18	5	0	1,225
small b <i>Employ</i>	usinesses. S ment, Annue	Source: U.S. Ce al Payroll, and I	nsus Bureau. Receipts by Re	Number of F ceipt Size of	vas used to attribut Firms, Number of E The Enterprise for sd/susb/2002/usall	Establishn the Unite	nents, ed States,

Table E-4: Estimated Number of Regulated Entities Classified as Small (by area and activity)

Table E-5 estimates for every activity type the proportion of businesses that are small within an area. As can be seen, the proportion of businesses that are small in most areas and for most activity types are 97 percent and above. Thus, the considered activity types, most businesses in the study area can be considered to be small.

Table F-5. Percentage o	f Rusingsos that are	Classified as Small	(by area and activity type))
Table E-5. Tercentage 0	Dusinesses that are	Classified as Sillali	(by area and activity type)	,

					Tidal, Wave,		
		Agricultural		Power	& Wind		
Area	NPDES ¹	Pesticides	Oil Spills	Plant	Energy	LNG	Total

1	99%	100%	97%	100%	100%		99%		
2	99%	100%	100%		100%	N/A*	99%		
7	99%	100%	100%	100%			99%		
¹ Note t	¹ Note that the number of small businesses for NAICS code 221320 is too small to have any								
impact	impact on the total percentage of NPDES businesses classified as small.								
* N/A -	* N/A - there are no entities classified as small in the respective areas and activities.								

Table E-6 combines information from Tables E-4 and E-5, and annualized cost estimates from previous sections of this report to generate for every area and activity type the potential annualized impact to a typical small business. As explained above, this estimate is generated by taking the ratio of total business impacts, and the total number of small businesses estimated, multiplied by the proportion of businesses that are small, as presented in Table E-4.

	NPDES	NPDES: Minor		Major	Tidal &
					Wave
Area	<1	<5	<1	<5	Energy*
1	\$20	\$35	\$375	\$700	\$22,500
2	\$90	\$265	\$50	\$300	\$25,350
7	\$90	\$150	\$1,400	\$1,650	

 Table E-6: Estimated Annualized Impacts per Small Entity by area and activity type

Evaluation of Alternatives

In accordance with the requirements of the RFA (as amended by SBREFA, 1996) this analysis considered various alternatives to the critical habitat designation for the leatherback. The alternative of not designating critical habitat for the leatherback was considered and rejected because such an approach does not meet the legal requirements of the ESA. Should NMFS determine to exercise its discretion to designate all areas, the Final Regulatory Flexibility Analysis will address the appropriate impacts.

An alternative to designating critical habitat within all nine areas is the designation of critical habitat within a subset of these areas. This approach would help to reduce the number of small businesses potentially affected. The extent to which the economic impact to small entities would be reduced depends on how many, and which areas would be excluded.

APPENDIX F: ENERGY IMPACTS ANALYSIS

Introduction

Pursuant to Executive Order No. 13211, "Actions Concerning Regulations that Significantly Affect Energy Supply, Distribution, or Use," issued May 18, 2001, Federal agencies must prepare and submit a "Statement of Energy Effect" for all "significant energy actions." The purpose of this requirement is to ensure that all Federal agencies "appropriately weight and consider the effects of the Federal Government's regulations on the supply, distribution, and use of energy."

The Office of Management and Budget provides guidance for implementing this Executive Order, outlining nine outcomes that may constitute "a significant adverse effect" when compared with the regulatory action under consideration:

- Reductions in crude oil supply in excess of 10,000 barrels per day (bbls);
- Reductions in fuel production in excess of 4,000 barrels per day;
- Reductions in coal production in excess of 5 million tons per year;
- Reductions in natural gas production in excess of 25 million Mcf per year;
- Reductions in electricity production in excess of 1 billion kilowatts-hours per year or in excess of 500 megawatts of installed capacity;
- Increases in energy use required by the regulatory action that exceed the thresholds above;
- Increases in the cost of energy production in excess of one percent;
- Increases in the cost of energy distribution in excess of one percent; or
- Other similarly adverse outcomes.⁶⁸

Of these, the most relevant criteria to this analysis are potential changes in natural gas and electricity production, as well as changes in the cost of energy production. Possible energy impacts may occur as the result of requested project modifications to power plants, tidal, wave, and wind energy projects, and LNG facilities. The following sections describe the potential for these impacts in greater detail.

Power Plants

As discussed in Section 2.4, there are currently seven power plants located within areas that could be affected by leatherback critical habitat. Out of the seven power plants, one is a nuclear power plant. Descriptions of each power plant can be found in section 2.4.2. Future management and required project modifications for leatherback critical habitat related to power plants include: cooling of thermal effluent before release to the environment, treatment of any contaminated waste materials and modifications associated with permits issued under NPDES.

These modifications could affect energy production; however, the potential impact of possible leatherback conservation efforts on the project's energy production and the associated cost is unknown.

⁶⁷ Memorandum For Heads of Executive Department Agencies, and Independent Regulatory Agencies, Guidance for Implementing E.O. 13211, M-01-27, Office of Management and Budget, July 13, 2001, http://www.whitehouse.gov/omb/memoranda/m01-27.html.

⁶⁸ Ibid.

As shown in Table F-1, power plants within the study area have a combined production capacity of 10,227 megawatts and therefore, if about half of this capacity is affected by leatherback critical habitat, it would be higher than the 500 megawatts of installed capacity threshold. It is unlikely that any project modifications would have a large impact on the amount of electricity produced. It is more likely that any additional cost of leatherback conservation efforts would be passed on to the consumer in the form of slightly higher energy prices. Without information about the effect of power plants on future electricity prices and more specific information about how recommended conservation measures for leatherback would affect electricity production, this analysis is unable to forecast potential energy impacts resulting from changes to power plants.

Area	Estimated number of affected power plants	Capacity (MW)
1	Moss Landing Power Plant	2,590
7	Diablo Canyon Power Plant	2,200
7	Morro Bay Power Plant	1,030
Total C	apacity	5,820

Table F-1: Summary of Capacity of Power Plants

Tidal, Wave, and Wind Energy Projects

As discussed in Section 2.6, the number of future tidal, wave, and wind energy projects that will be constructed within critical habitat is unknown. Currently there are no actively generating tidal, wave or wind energy projects located within the critical habitat area. However, as described in Section 2.6, six tidal, wind or wave projects have received preliminary permits from the Federal Energy Regulatory Commission (FERC) and 1 project has a pending preliminary permit.⁶⁹

Future management and required project modifications for leatherback critical habitat related to tidal, wave, and wind energy projects are uncertain and could vary widely in scope from project to project. Moreover, because the proposed projects are still in the preliminary stages, the potential impact of possible leatherback conservation efforts on the project's energy production and the associated cost of that energy are unclear.

As shown in Table F-2, proposed tidal, wave, and wind energy projects within the study area have a combined production capacity of 474 megawatts. If the potential cost of leatherback conservation results in *all* projects not being constructed, then reductions in electricity production in excess of the 500 megawatts of installed capacity threshold are possible. However, this represents a worst case scenario.

It is more likely that any additional cost of leatherback conservation efforts would be passed on to the consumer in the form of slightly higher energy prices. That said, any increase in energy prices as a result of leatherback conservation would have to be balanced against changes in energy price caused by the development of these projects. That is, the construction of tidal, wave, and wind energy projects may

⁶⁹ FERC. Issued and Valid Hydrokinetic Projects Preliminary Permit. Accessed at: http://www.ferc.gov/industries/hydropower/gen-info/licensing/pre-permits.aspon December 20, 2011; FERC. Pending Hydrokinetic Projects Preliminary Permits http://www.ferc.gov/industries/hydropower/geninfo/licensing/pre-permits.aspon December 20, 2011

result in a general reduction in energy prices in affected areas. Without information about the effect of these projects on future electricity prices and more specific information about recommended conservation measures for leatherback, this analysis is unable to forecast potential energy impacts resulting from changes to tidal, wave, and wind energy projects.

				Capacity			
Area	Docket #	Project Name	Classification	(MW)			
Issued	Issued Preliminary Permits						
		San Francisco Bay Tidal					
1	P-12585	Energy Project	Tidal	10			
1	P-13376	Del Mar Landing Project	Wave	5			
1	P-13377	Fort Ross South Project	Wave	5			
1	P-13378	Fort Ross North Project	Wave	5			
		Douglas County Wave &					
2	P-12743	Tidal Energy	Wave	3			
		Coos Bay OPT Wave					
2	P-12749	Park	Wave	100			
Pending Preliminary Projects							
	P-14292	Green Wave San Luis					
7		Obisbo Wave Park	Wave	100			
Source	Source: FERC. Issued and Valid Hydrokinetic Projects Preliminary Permit.						
Access	Accessed at: http://www.ferc.gov/industries/hydropower/gen-						
info/licensing/hydrokinetics.asp#skipnav on December 20, 2011.; FERC.							
Pendin	Pending Hydrokinetic Projects Preliminary Permits.						
Access	Accessed at: <u>http://www.ferc.gov/industries/hydropower/gen-</u>						
info/lic	info/licensing/hydrokinetics.asp#skipnav on December 20, 2011.						

Table F-2: Summary of Capacity at Proposed Tidal, Wave, and Wind Energy Projects

LNG Projects

Similar to tidal, wave, and wind energy projects, the number of future LNG projects that will be built within critical habitat is unknown. As described in Section 2.7, many LNG projects are likely to be abandoned during the development stages for reasons unrelated to leatherback critical habitat. In addition, the potential impact of LNG facilities on leatherback habitat remains uncertain, as is the nature of any project modifications that might be requested to mitigate adverse impacts. Because these LNG projects are still in the development stages, the potential impact of possible leatherback conservation efforts on the project's energy production and the associated cost of that energy are unclear.

Proposed LNG terminals within the study area have a combined natural gas production capacity of 2.7 Bcfd, which is in excess of the 25 million Mcf per year threshold (see Table F-2). As discussed in Section 2, project modifications may include biological monitoring, spatial restrictions on project installation, and specific measures to prevent or respond to catastrophes.

Out of the project modifications listed above, spatial restrictions on project installation could have effects on energy production. This modification could increase LNG construction costs, which may result in higher natural gas costs. However, the construction of LNG facilities and associated increased energy supplies to consumers aim to generally result in lower energy prices than would have otherwise been expected. Therefore, this analysis is unable to forecast potential energy impacts resulting from changes to LNG projects without specific information about recommended leatherback conservation measures or future forecasts of energy prices that reflect future markets with increased energy supplies from LNG projects.

Area	Location	Applicant	Capacity				
Proposed LNG Import Terminals							
2	Astoria, OR	Oregon LNG	1.5 Bcfd				
Total Cap	1.5 Bcfd						
Sources: FERC, accessed online December 20, 2011 at							
http://www.ferc.gov/industries/hydropower/gen-info/licensing/pre-permits.asp . Updated as of							
December 2, 2011; FERC, accessed online December 20, 2011 at							
http://www.ferc.gov/industries/hydropower/gen-info/licensing/pre-permits.asp . Updated as of							
December	2, 2011						

 Table F-3: Summary of Economic Impacts to LNG Projects