
 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 1 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

Sections Included in this Document and Change History


1. Purpose
 2. Scope
 3. Responsibilities
 4. Background
 5. References
 6. Procedure
 7. Definitions/(Changed Analytical Batch to Batch and revised definition)
 8. Records
 9. Supporting Documents
 10. Attachments
- Document History

1. Purpose	This procedure describes the monitoring activities in a laboratory quality control (QC) program to ensure the quality of test results.
2. Scope	This procedure is applicable to Office of Regulatory Affairs (ORA) laboratories performing chemical, biological, microbiological and physical testing.
3. Responsibilities	ORA laboratories are responsible for establishing a laboratory quality control program. Laboratory Supervisors are responsible for ensuring that quality control is performed and for reviewing quality control data for acceptability. Analysts are responsible for conducting quality control analyses in accordance with the laboratory quality control program.
4. Background	None
5. References	Taylor, J. K. (1993). <i>Handbook for SRM users</i> . Gaithersburg, MD: National Institute of Standards and Technology
6. Procedure	<p>A. Laboratory Quality Control Program</p> <p>Laboratory quality control is an essential aspect of ensuring that data released is fit for the purpose determined by the quality objectives (i.e. accuracy and precision).</p> <p>When properly executed, quality control samples can monitor the various aspects of data quality on a routine basis. In instances where performance falls outside acceptable limits, the data produced can be questioned and, after investigation, a determination made as to its validity. With professional experience and a <i>common sense</i> approach quality control is the principal recourse available for ensuring that only quality data is</p>

 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 2 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10


released. The dual foundations of the laboratory quality control program is its internal quality control, composed of day-to-day and sample-set to sample-set monitoring of analytical performance, and its external QC, based on the laboratory's performance in proficiency testing programs. The QC data generated is recorded in such a manner to detect trends.

1. Internal quality control: QCs are used to measure accuracy, precision, contamination, and matrix effects. Generally, QCs are run per batch or set of samples at a frequency of 5% or one every twenty samples. This level sufficiently demonstrates the validity of results. The laboratory determines, where feasible, the accuracy and precision of all analyses performed.
 - a. QC schemes utilized for chemistry consist of:
 - *Blanks*, either matrix or reagent, to determine and measure contamination and interferences - The results of blanks should be compared with the sample analyzed per analysis to determine whether the source of any analyte present is due to sample or laboratory contamination, interferences, the sample matrix, or the actual analyte in the samples. Blanks should be below the method detection limit where possible. Blank results are evaluated and corrected where possible. If blank results are consistently above the method detection level (MDL) established, the MDL should be re-established. High blank results may also indicate contamination either from the solvent, laboratory equipment or laboratory environment.
 - *Matrix spikes* - Matrix spikes measure the effects the sample matrix may have on the analytical method, usually the analyte recovery. Method accuracy is documented and controlled based on the percent recovery of matrix spikes for quantitative analysis and the positive response of the analyte for qualitative analysis.
 - *Duplicate samples or matrix spike duplicates* - Duplicate sample or matrix spike duplicates measure precision of the analytical process. Duplicate analysis usually involves a replicate sample, sub-sampled in the laboratory, but for some methods it is in the form of a matrix spike duplicate. Method precision is documented and controlled based on the relative

 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 3 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

percent difference (RPD) or the positive response for qualitative analysis.

- *Quality control samples* - Quality control samples (QCS) measure method performance. The matrix of the QCS should match the matrix of the samples being analyzed and should pass through the entire sample preparation process. The QCS, therefore, measures both the sample preparation process and the analytical process.
 - *Standards* - Calibration check standards referred to as initial calibration verification (ICV) and continuing calibration verification (CCV) are used to determine whether an analytical procedure is in control and stays within control. They are used to detect analytical method errors from procedural or operator errors or contamination from laboratory sources.
 - *Accuracy and precision control charts*
- b. QC schemes utilized for microbiology include running QC controls concurrently with each sample batch or set. They are:
- *positive and negative culture controls* - positive and negative controls give correct response,
 - *system and collector controls*,
 - *applicable kit controls* (positive and negative),
 - *media quality* - the culture controls additionally verify the acceptability of the media,
 - *un-inoculated media* – un-inoculated media control reveals no visible growth, and
 - *accuracy and precision control charts*.
- c. QC schemes utilized for miscellaneous testing (i.e. microscopic) includes QC samples for:

 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 4 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

- accuracy – a known or reference sample,
- precision – a duplicate sample, and
- blank – a system control, reagent blank to check for environmental or laboratory contamination.


B. External Quality Control Program

Participation in proficiency testing is an important means of quality control and assessing laboratory performance. Accrediting agencies require laboratories to participate in programs relevant to the laboratory's scope of testing. The ORA laboratories participate in the Association of Official Analytical Chemists (AOAC) Standard Microbiology Proficiency Program and the FDA National Check Sample Program (NCSP) for foods, drugs, colors, metals, nutrition, sulfites, and filth. The Division of Field Science (DFS) has the principal responsibility for managing the NCSP. Proficiency surveys are used as a tool to assist personnel in the identification of laboratory problems that may exist and that have eluded the internal quality control program. Therefore, it is essential that proficiency testing samples are treated as routine samples to the extent possible. Analyses of proficiency samples should not be repeated, unless it is necessary to repeat the entire procedure or the data on those specific samples exceed the method's linearity. Samples should be run in duplicate *only* in those procedures where samples are normally analyzed in duplicate. Supervisors are individually responsible to ensure that the performance and evaluation of proficiency samples are submitted within the designated time frame. The Laboratory Director reviews all data and forwards the packet to DFS by the date defined when issued. In addition, for the Microbiology Proficiency Program, the AOAC forms are completed and faxed to AOAC. Copies are retained in the laboratory. The results are reviewed upon receipt of the DFS report. A corrective action is initiated if necessary according to the laboratory's corrective action process. All unacceptable results are investigated and the cause or causes identified for the unacceptable performance, and corrective action implemented.

C. Other Quality Control Monitoring Activities

There are other QC procedures that may be occasionally used. These are:

- a. *Replicate testing* - Replicate testing may be performed on samples which are found to be violative. The original sample results are verified

 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 5 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

by using an alternative method or by rechecking results by the same method. A violative chemistry result may be verified by a second instrument, another method, a second analyst or repeated by the same analyst. A violative microbiology result by a rapid screening method is verified by a culture method.


- b. *Retesting of retained items* - Retained samples can be re-introduced into the workload as regular samples in order to assess laboratory performance.
- c. *Correlation* - Checking for correlation means evaluating the interrelated characteristics (analytes) of the sample. By comparing results from different analyses on the same test item, one checks for reasonableness (i.e. Does the data make sense or correspond as anticipated?). Certain characteristics within the sample will maintain an analogous relationship to one another with regard to the type of test being performed. If one characteristic is dependent on or at all indicative of another characteristic, they should be compared for consistency. The supervisor or designated reviewer should be able to anticipate and recognize an analogous relationship with different characteristics of the same sample. Any deviation such as the absence of expected primary characteristics or the sudden appearance of previously unobserved characteristics of the sample, signals the probability of error.

D. Evaluation of Quality Control Data

All worksheets are submitted to the supervisor or designee for review. The QC range of each quality control data is evaluated for acceptability. Data that fall inside established control limits are judged to be acceptable, while data lying outside of the control interval are considered suspect. Control limits established by the laboratory are not be exceeded except as resolved under a documented corrective action process. This planned action includes the checking of results for calculation or transcription errors, preparation or use of new standards, recalibration of instrument, reanalysis of all samples with new controls or reagents, use of alternate system, repeating analysis.

E. Quality Control Charts


- 1. Accuracy and precision control charts are used to determine if the measurement system process is in control and whether the results

 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 6 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

generated by the measurement system are acceptable. The control chart provides the tool for distinguishing the pattern of indeterminate (random) variation from the determinate (assignable cause) variation. This technique displays the test data from a process or method in a form which graphically compares the variability of all test results with the average or expected variability of small groups of data, in effect, a graphical analysis of variance. The average or mean value is calculated and the spread (dispersion or range) is established. Common practice sets the warning limits at ± 2 standard deviations while control limits are set at ± 3 standard deviations on each side of the mean. Since the distribution of averages exhibits a normal form, the probability of results exceeding the control limits is readily calculated. The control chart is actually a graphical presentation of QC efficiency. If the procedure is *in-control*, the results will almost always be within established control limits. Further, the chart will disclose trends and cycles from assignable causes which can be corrected. It is emphasized that there is absolutely no substitute for sound judgment based on an appreciation of the analytical system, the technique, the quality control materials utilized, and the analytical interpretation of the data generated by the procedure.

- a. Accuracy charts (other names are Mean Chart, Levy (Levey)-Jennings or Shewhart Control Chart) - The data from a series of analytical tests are plotted with the vertical scale in units such as percent (percent recovery), and the horizontal scale in units of batch number or time. The mean and standard deviation is calculated on the data. Upper and lower control limits are established at the mean $\pm 3X$ the calculated standard deviation. Upper and lower warning limits are established at the mean $\pm 2X$ the calculated standard deviation.
- b. Precision charts (other names are Range Chart or R-chart) – The data from duplicates are plotted with the vertical scale in units such as percent (RPD), and the horizontal scale in units of batch number or time. The mean and standard deviation is calculated on the data. The upper control limit is established at the mean $X 3.27$ and the upper warning limit is established at the mean $X 2.51$. Precision control charts do not have a lower warning and control limit.

F. Statistical Process Control

 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 7 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

Statistical limits are determined at the 99% confidence interval. The evaluation of control limits is made after no less than seven to ten points are accumulated.

1. Accuracy is expressed as percent recovery of spiked samples.
 - a. Percent recovery is calculated as follows for spikes in solvent or standard spikes:

$$\% \text{ Recovery} = 100 \times \frac{X}{K}$$

where:

X = observed value

K = known value

- b. Accuracy is calculated for spikes into natural matrices as follows:

$$\text{Recovery} = 100 \times \frac{X_s - X_u}{K}$$

where:

X_s = measured value for spiked sample

X_u = measured value for unspiked sample

K = known value of the spike in the sample

- c. For accuracy this interval is computed as :

$$\text{Accuracy Interval} = \text{Mean Recovery} \pm 3 \times S$$


where: S = Standard deviation for individual values

$$\sigma = \sqrt{\frac{\sum (X_i - X)^2}{N - 1}}$$

where:

X_i = value of individual measurement

X = arithmetic mean of the measurements

 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 8 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

N = number of the measurements

- d. For qualitative analysis, accuracy expressed as positive (presence) or negative (absence).
2. Precision is expressed as relative standard deviation (RSD) or relative percent difference (RPD) of duplicate samples.
 - a. RSD is calculated from standard deviation and mean recovery, when the standard deviation is derived from multiple recovery results as follows:

$$RSD = CV = 100 \times \frac{\sigma}{X}$$

where:

RSD = relative standard deviation

CV = coefficient of variation

σ = standard deviation

X = arithmetic mean of the measurements

- b. RPD is calculated when only two sample results are available as follows:

$$RPD = \frac{|R_1 - R_2|}{R} \times 100$$

where:

$|R_1 - R_2|$ = absolute difference between the determinations


R = arithmetic mean of the two values

- c. For precision based on RPD of duplicate samples this limit is computed as:

$$Upper\ Control\ Limit = 3.27 \times RPD$$

where: RPD = mean relative percent difference

- d. For qualitative analysis, precision is expressed as true and false positive rates; and true and false negative rates.


 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 9 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

$$\% \text{ false positive} = \frac{\# \text{ falsepositives}}{\text{total}\#\text{knownnegatives}} \times 100$$

$$\% \text{ false negative} = \frac{\# \text{ falsenegatives}}{\text{total}\#\text{knownpositives}} \times 100$$

3. Treatment of Outliers and Trends

- a. An outlier is a datum that is different from the main data pattern, and/or is not representative of the data set. Outliers are extreme cases of one variable, or a combination of variables, which have a strong influence on the calculation or statistics. The principal safeguards against obtaining or using an outlier are vigilance during all operations and visual inspection of data before performing statistical analyses. Each suspected outlier is evaluated and rejected if found to be unrepresentative, or to have a high probability of being unrepresentative. Rejection for a reason is referred to as rejection for assignable cause.
- b. A plotting outside of the control limits may be an indication of an assignable cause. If a quality control result falls above or below the control limits (3 SD) of the control chart, the value is investigated. The investigation is a planned action to correct the problem and to prevent the reporting of incorrect results. Sometimes the investigation will reveal a recording or computational mistake that can be revised to obtain the correct value. If the investigation reveals an assignable cause, i.e. deterioration of reagents, improperly prepared reagents, inadequate storage of reagents or standards, the analysis is repeated. When outliers are found, all analytical results for that analytical batch are inspected to ensure that erroneous results are not reported.
- c. Quality control data outside of the control limits (3SD) rejected due to assignable cause remain in the permanent records of the laboratory, for example, on QC charts. However, a datum so determined to be an outlier will be flagged as such and is excluded from the data set before statistical calculations are made. Control limits calculated from data sets containing outliers are not valid.
- d. The chart will disclose trends and shifts from assignable causes

 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 10 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

which can be corrected. A trend will show a tendency or movement in a particular direction. If a series of consecutive plottings move steadily either upward or downward, a trend is indicated. If a series of consecutive plottings fall either above or below the center line, a shift is indicated. When a trend or shift is detected, it is annotated as such on the chart and reviewed to the extent possible to identify if a significant concern is indicated. If the review indicates a significant concern, a corrective action is initiated to determine the cause.

7. Definitions

Accuracy – Accuracy is the nearness of a measurement or the mean of a set of measurements to the true value. Accuracy is assessed in terms of percent recovery for quality control check samples and matrix spikes.


Analytical solution – An analytical solution is the sample in the form as introduced to an instrument. The analytical solution is the end result of the sample preparation, extraction, and digestion procedures.

Analytical spike – An analytical spike is a sample made by spiking an analytical solution after the sample preparation or digestion process.

Batch - A batch is the basic unit of measure by which the number of quality control samples needed is determined. The analytical batch is those samples, sample extracts, or sample digestates that are analyzed together with the same method sequence, the same lots of reagents, and manipulations common to each sample within the same time period or in continuous sequential time periods. The extraction batch is those samples extracted or digested using the same techniques. Samples in each analytical or extraction batch should be of similar composition.

Calibration blank – A calibration blank is usually an organic or aqueous solution that is as free of analyte as possible and prepared with the same volume of chemical reagents used in the preparation of the calibration standards and diluted to the same volume with the same solvent (water or organic) used in the preparation of the calibration standard. The calibration blank is used to give the null reading for the calibration curve. For methods in which the calibration solutions receive the full sample preparation treatment, the calibration blank is identical to, and becomes referred to as, the method blank.

Continuing Calibration Verification (CCV) – A CCV is a standard solution used to verify freedom of excessive instrument drift. The CCV is a periodic

 <p style="text-align: center;">ORA LABORATORY PROCEDURE Food and Drug Administration</p>	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 11 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

check of the calibration.

Control charts – This is a chart consisting of an expected value (typically the mean) and an acceptable range of occurrences expressed as control limits. The values obtained from measurements versus the time sequence of entries are plotted to produce control charts.

Duplicate samples – Duplicate samples are two separate samples taken from the same source (i.e. samples in separate containers and analyzed independently).

Initial Calibration Verification (ICV) – This is an independent standard solution used to verify the calibration standard level. An independent standard solution is defined as a standard solution composed of the analyte of interest from a separate (different) source, a different lot or a separately prepared set of two primary standards may be used.


Matrix spike sample – A matrix spike sample is prepared by adding a predetermined quantity of stock solution of representative analytes to an actual sample matrix (as opposed to an ideal matrix, e.g. reagent water, or site blanks, etc.) prior to sample extraction/digestion and analysis. The matrix spike is used to measure accuracy of the method in the sample matrix.

Matrix spike duplicate analysis - Equal and predetermined quantities of stock solutions of certain analytes are added to each of two aliquots of a sample prior to extraction or digestion and analysis. Matrix spike duplicates can be used to measure precision.

Method detection limit (MDL) – The MDL is the minimum concentration of a substance that can be measured and reported with 99% confidence that the analyte concentration is greater than zero. It is determined from the analysis of replicates of a sample containing the analyte at very low concentration.

Monitor – To monitor is to observe and record activity to measure compliance with a specific standard of performance; routine and ongoing collection of data about the indicator.

Precision – Precision is the agreement between a set of replicate measurements without assumption or knowledge of the true value. Analytical precision is assessed by means of laboratory duplicate or replicate or duplicate matrix spike analysis. The most commonly used estimates of precision are the relative standard deviation (RSD) or the coefficient of variation (CV).

 ORA LABORATORY PROCEDURE Food and Drug Administration	Document No.: ORA-LAB.5.9	Version No.: 1.5
		Page 12 of 12
ASSURING THE QUALITY OF TEST RESULTS		Effective Date: 10-01-03 Revised: 09-08-10

Quality Assurance – Quality assurance is an integrated system of management activities involving planning, implementation, assessment, reporting, and quality improvement to ensure that a process, item, or service is the type and quality needed and expected by the client.

- | | |
|--------------------------------|---|
| 8. Records | Control charts for accuracy and precision
Proficiency test results |
| 9. Supporting Documents | Laboratory Corrective Action procedure
DFS.2 Standard Operating Procedures National Check Sample Program
ORA-LAB 1 Standard Operating Procedure (SOP): Microbiological Controls for Sample Analysis |
| 10. Attachments | None |

Document History					
Version No.	Status (I, R, C)	Date Approved	Location of Change History	Name & Title	
				Author	Approving Official
1.2	R	12/06/06	In Document	LMEB	LMEB
1.3	R	04/03/07	In Document	LMEB	LMEB
1.4	R	11/15/07	In Document	LMEB	LMEB
1.5	R	09/14/10	In Document	LMEB	LMEB

Approving Official's signature: _____ Date: _____