

Applicability: Model A330 and A340 series airplanes, certificated in any category, except those airplanes on which Airbus Modification 47433 (Airbus Service Bulletin A330-27-3075 or A340-27-4081) or Airbus Modification 45512 (Airbus Service Bulletin A330-27-3054 or A340-27-4062) has been installed.

Note 1: This AD applies to each airplane identified in the preceding applicability provision, regardless of whether it has been modified, altered, or repaired in the area subject to the requirements of this AD. For airplanes that have been otherwise modified, altered, or repaired so that the performance of the requirements of this AD is affected, the owner/operator must request approval for an alternative method of compliance in accordance with paragraph (e) of this AD. The request should include an assessment of the effect of the modification, alteration, or repair on the unsafe condition addressed by this AD; and, if the unsafe condition has not been eliminated, the request should include specific proposed actions to address it.

Compliance: Required as indicated, unless accomplished previously. To detect and correct excess backlash of the spherical bearing of the active aileron servo-controls, which could result in failure of the active aileron servo-control and consequent reduced controllability of the airplane, accomplish the following:

Inspection

(a) Perform an inspection to check for backlash of the spherical bearing of the active aileron servo-controls, in accordance with Airbus Service Bulletin A330-27-3073, Revision 01 (for Model A330 series airplanes), or A340-27-4079, Revision 01 (for Model A340 series airplanes), each dated January 18, 2000; as applicable; at the applicable time specified in paragraph (a)(1) or (a)(2) of this AD.

(1) For airplanes that, as of the effective date of this AD, have accumulated 13,000 total flight hours or less: Perform the inspection within 6 months after the effective date of this AD, or within 6 months after accumulating 9,000 total flight hours, whichever occurs later.

(2) For airplanes that, as of the effective date of this AD, have accumulated more than 13,000 total flight hours: Perform the inspection within 3 months after the effective date of this AD.

Repetitive Inspections

(b) If, during the inspection required by paragraph (a) of this AD, no backlash is detected, or if any backlash is detected that is less than or equal to 0.2 millimeter (mm) (0.0078 inch) on all active aileron servo-controls, repeat the inspection required by paragraph (a) of this AD thereafter at intervals not to exceed 15 months or until the actions of paragraph (d) of this AD are accomplished on all active aileron servo-controls.

Corrective Actions

(c) If, during any inspection required by paragraph (a) or (b) of this AD, any backlash is detected that is more than 0.2 mm (0.0078 inch), prior to further flight, accomplish the

requirements of either paragraph (c)(1) or (c)(2) of this AD, in accordance with Airbus Service Bulletin A330-27-3073, Revision 01 (for Model A330 series airplanes), or A340-27-4079, Revision 01 (for Model A340 series airplanes); each dated January 18, 2000; as applicable.

(1) Replace discrepant active aileron servo-controls with new ECP7 standard servo-controls in accordance with the applicable service bulletin, and repeat the inspection required by paragraph (a) of this AD thereafter at intervals not to exceed 15 months or until the requirements of paragraph (d) of this AD are accomplished; or

(2) Replace discrepant active servo-controls with ECP8 or ECP9 standard servo-controls, in accordance with the applicable service bulletin.

Note 2: Any inspection or replacement accomplished prior to the effective date of this AD, in accordance with Airbus Service Bulletin A330-27-3073 (for Model A330 series airplanes) or A340-27-4079 (for Model A340 series airplanes), each dated August 31, 1999, is considered acceptable for compliance with the applicable requirement specified by this AD.

Optional Terminating Action

(d) Replacement of all active servo-controls with ECP8 or ECP9 standard servo-controls, in accordance with Airbus Service Bulletins A330-27-3075, dated September 24, 1999, and A330-27-3054, Revision 01, dated November 8, 1999 (for Model A330 series airplanes); or A340-27-4081, dated September 24, 1999, and A340-27-4062, Revision 01, dated November 8, 1999 (for Model A340 series airplanes); as applicable; constitutes terminating action for the requirements of this AD.

Alternative Methods of Compliance

(e) An alternative method of compliance or adjustment of the compliance time that provides an acceptable level of safety may be used if approved by the Manager, International Branch, ANM-116, FAA Transport Airplane Directorate. Operators shall submit their requests through an appropriate FAA Principal Maintenance Inspector, who may add comments and then send it to the Manager, International Branch, ANM-116.

Note 3: Information concerning the existence of approved alternative methods of compliance with this AD, if any, may be obtained from the International Branch, ANM-116.

Special Flight Permits

(f) Special flight permits may be issued in accordance with sections 21.197 and 21.199 of the Federal Aviation Regulations (14 CFR 21.197 and 21.199) to operate the airplane to a location where the requirements of this AD can be accomplished.

Note 4: The subject of this AD is addressed in French airworthiness directives 2000-014-108(B) and 2000-017-134(B), each dated January 12, 2000.

Issued in Renton, Washington, on June 7, 2000.

Donald L. Riggan,

Acting Manager, Transport Airplane Directorate, Aircraft Certification Service.

[FR Doc. 00-14955 Filed 6-13-00; 8:45 am]

BILLING CODE 4910-13-P

FEDERAL TRADE COMMISSION

16 CFR Part 250

Extension of Time for Comments Concerning the Guides for the Household Furniture Industry

AGENCY: Federal Trade Commission.

ACTION: Notice of extension of comment period.

SUMMARY: The Federal Trade Commission (the "Commission") has extended the date by which comments must be submitted concerning the review of its Guides for the Household Furniture Industry ("Household Furniture Guides" or the "Guides"). The Commission solicited comments until June 9, 2000. In response to a request from an industry trade association, the Commission grants an extension of the comment period until July 10, 2000.

DATES: Written comments will be accepted until July 10, 2000.

ADDRESSES: Written comments should be submitted to Office of the Secretary, Federal Trade Commission, Room H-159, 600 Pennsylvania Ave., NW., Washington, DC 20580. Comments should be identified as "Household Furniture Industry Guides, 16 CFR Part 250—Comment." If possible, submit comments both in writing and on a personal computer diskette in Word Perfect or other word processing format (to assist in processing, please identify the format and version used). Written comments should be submitted, when feasible and not burdensome, in five copies.

FOR FURTHER INFORMATION CONTACT:

Ingrid Whittaker-Ware, Attorney, Southeast Region, Federal Trade Commission, 60 Forsyth Street, SW., Atlanta, Georgia 30303, telephone number (404) 656-1364. E-mail address (for questions or information only): "Furniture@FTC.gov".

SUPPLEMENTARY INFORMATION: On April 10, 2000, the Commission published in the *Federal Register* a request for public comments on the overall costs, benefits and the continuing need for its Guides for the Household Furniture Industry 16 CFR part 250, as part of its regulatory review program, 65 FR 18933. The Guides are voluntary guidelines issued

by the Commission to assist members of the furniture industry in complying with section 5 of the FTC Act. The **Federal Register** Notice ("notice") posed eleven questions in all; some were general regulatory review questions, while others asked about material issues that are specific to the household furniture industry. Pursuant to the **Federal Register** notice, the comment period relating to the Household Furniture Guides currently ends on June 9, 2000.

The Commission received a request for an extension of the comment period from the American Furniture Manufacturers Association ("AFMA"). AFMA has indicated that additional time is required so that its members can prepare thorough, thoughtful responses to the proposals and questions contained in the **Federal Register** notice.

The Commission is mindful of the need to deal with this matter as expeditiously as possible. However, the Commission is also aware that some of the issues raised by the **Federal Register** notice may be complex and it welcomes as much substantive input as possible to facilitate its decisionmaking process. Accordingly, in order to provide sufficient time for these and other interested parties to prepare useful comments, the Commission has decided to extend the deadline for comments until July 10, 2000.

Authority: 15 U.S.C. 41–58.

List of Subjects in 16 CFR Part 250

Forest and forest products, Furniture industry, Trade practices.

By direction of the Commission.

Donald S. Clark,
Secretary.

[FR Doc. 00–14975 Filed 6–13–00; 8:45 am]

BILLING CODE 6750–01–M

CONSUMER PRODUCT SAFETY COMMISSION

16 CFR Part 1211

Safety Standard for Automatic Residential Garage Door Operators

AGENCY: Consumer Product Safety Commission.

ACTION: Notice of proposed rulemaking.

SUMMARY: The Consumer Product Safety Commission is proposing to amend regulations on the Safety Standard for Automatic Residential Garage Door Operators to reflect changes made by Underwriters Laboratories, Inc. in its standard UL 325.

DATES: The Office of the Secretary must receive comments by August 28, 2000.

ADDRESSES: Comments may be mailed to the Office of the Secretary, Consumer Product Safety Commission, Washington, DC 20207 or delivered to the Office of the Secretary, Consumer Product Safety Commission, Room 502, 4330 East-West Highway, Bethesda, Maryland 20814–4408, telephone (301) 504–0800. Comments may also be filed by telefacsimile to (301) 504–0127 or e-mailed to cpsc-os@cpsc.gov.

FOR FURTHER INFORMATION CONTACT: John Murphy, Directorate for Engineering Sciences, Consumer Product Safety Commission, Washington, DC 20207, telephone 301–504–0494.

SUPPLEMENTARY INFORMATION: The Commission issued part 1211 on December 21, 1992 to minimize the risk of entrapment by residential garage door openers. As mandated by section 203 of Public Law 101–608, subpart A of part 1211 codifies garage door operator entrapment provisions of Underwriter Laboratories, Inc. ("UL") standard UL 325, third edition, "Door, Drapery, Louver and Window Operators and Systems." Subparagraph (c) of section 203 of Pub. L. 101–608 also required the Commission to incorporate into part 1211 any revisions that UL proposed to the entrapment protection requirements of UL 325, unless the Commission notified UL that the revision does not carry out the purposes of Pub. L. 101–608.

UL proposed revisions to UL 325 on June 30, 1998 and made them final on September 18, 1998. The Commission determined that the entrapment related revisions do carry out the purposes of Public Law 101–608. This proposed rule would incorporate into subpart A of part 1211 those revisions that relate to entrapment by residential automatic garage door operators. It would also correct a few typographical errors in part 1211.

The changes to the UL standard allow for advances in the state of the art in garage door safety. Some new garage door operators have an inherent entrapment protection system that can continuously monitor the position of the door. The UL revisions add requirements for this type of system. Some new garage door operators have an inherent secondary door sensor that is independent of the primary entrapment protection system. The UL revisions add requirements for this type of new system. Finally, the UL standard adds some new and revised provisions concerning instructions and field installed labels. The proposed rule

would incorporate these changes into the CPSC mandatory standard.

Pursuant to section 605(b) of the Regulatory Flexibility Act, 5 U.S.C. 605(b), the Commission certifies that this rule will not have a significant impact on a substantial number of small entities. Most of the changes are editorial and minor. The substantive changes only affect the few companies that are developing the new type of garage door operators discussed above. Moreover, UL has already made these changes to its UL 325 standard which is widely followed by the industry. The Commission also certifies that this rule will have no environmental impact. The Commission's regulations state that safety standards for products normally have little or no potential for affecting the human environment. 16 CFR 1021.5(c)(1). Nothing in this proposed rule alters that expectation.

Public Law 101–608 contains a preemption provision. It states: "those provisions of laws of States or political subdivisions which relate to the labeling of automatic residential garage door openers and those provisions which do not provide at least the equivalent degree of protection from the risk of injury associated with automatic residential garage door openers as the consumer product safety rule" are subject to preemption under 15 U.S.C. 2075. Pub. L. 101–608, section 203(f).

List of Subjects in 16 CFR Part 1211

Consumer protection, Imports, Labeling, Reporting and recordkeeping requirements.

Accordingly, 16 CFR part 1211 is proposed to be amended as follows:

PART 1211—SAFETY STANDARDS FOR AUTOMATIC RESIDENTIAL GARAGE DOOR OPENERS

1. The authority citation for part 1211 is revised to read as follows:

Authority: Sec. 203 of Pub. L. 101–608, 104 Stat. 3110; 15 U.S.C. 2063 and 2065.

2. In § 1211.2(c) remove the word "1993" and add, in its place "1999".

3. In the first sentence of § 1211.3 remove the words "as given in these requirements" and "an equivalent" and add the word "a" between the words "by" and "value".

4. Section 1211.4 is amended as follows:

a. In § 1211.4(c) remove the words "1st ed., dated July 19, 1991" and add, in their place "second edition, dated June 23, 1995".

b. In § 1211.4(c) add "5" before "U.S.C.".

5. Section 1211.5 is amended as follows: