

U.S. DEPARTMENT OF HEALTH AND HUMAN SERVICES National Institutes of Health National Heart, Lung, and Blood Institute



Sickle Cell Research for Treatment and Cure

Research

Treatment

Cure

NATIONAL INSTITUTES OF HEALTH NATIONAL HEART, LUNG, AND BLOOD INSTITUTE







To surent the Public Health Surviva Act to provide for the count, of siction

United States of America in Congress assembled.

Be if enouted by the Sennis and House of Representatives of the

An Act

Secrets 1. This Art shall be gitted as the "National Sieble Cell SAMEDLINES THE RECTURATION OF SAMEDINE Suc. 2. (a) 'The Congress funds and declares in a delalitating inheritable discussion (1) (but middle cell anomic is a delalitating behavior of the succession of the successi Annala Control Act". that affire a systematical two million American chinese and

(2) that the disease is a deadly and traffic burden which i likely to strike one-tourth of the children been to payed wh has been largely realested; (3) that efforts to prevent within cell amount must be directly their designation of the range and tricking of the both bear the striple sell trait; disperse and the phrecient at tending and controlling of carrie

(a) that simple and increasing serening tests have be desired which will identify these who have the disease of the of the slode oil train; (5) that programs to control sinkle call someth must be be

anticely signs the spinning engineering of the indical statement of battle methods of coulon, diag-

## Sickle Cell Research for Treatment and Cure



National Institutes of Health National Heart, Lung, and Blood Institute



SOUTHER, SAMPHERS & DESCRIPT L.L.P.

1291 Pennsylvania Avenue, N.W. 160, New 407 Washington, D.C. 20040-0407

Office 11,707,676,6600

Fee: +1.202.626.6780

Direct Dial: +1.202.626.6687 htmlcre@real.com

August 22, 2002

Claude Lenfant, M.D. National Heart, Lung, and Blood Institute National Institutes of Health 31 Center Drive Bethesda, MD 20692

Dogr Dr. Lenfant:

The National Sickle Cell Disease Program, which began in 1972, coincided with all but the first two years of my 30-year service in the United States House of Representatives. As a long-term member of the Committee on Appropriations and its Subcommittee on Labor, Health and Human Services, Education, and Related Agencies, I was privileged to receive regular updates from you as the Director of the National Heart, Lung, and Blood Institute on the program and in the prevention, diagnosis, and treatment of sickle cell disease. The advances that have been made since the inception of the program and the resultant improvement in both the quality and length of the lives of parsons with sickle cell disease in the United States are cause for recognition and oelebration.

We now know that treating infants with sickle cell disease prophylactically with pericillin can markedly reduce their incidence of life-threatoning infactions and that treatment can be safely discontinued at the age of five. We now know that the incidence of progress strokes can be dramatically reduced in children with sickle cell disease through regular transfusions. We now know that giving hydroxyures to selected patients with sickle cell disease can reduce by half their frequency of painful crises and occurrences of acute chart syndrome.

We also know that the future offers great promise for further advances that will improve the quality of life and increase the life expectancy of those with sickle cell disease. We have already seen that a cure is possible for some. I realize that much remains to be done before it is a reality for all. However, I believe that recognizing 30 years of accomplishment is both justified and appropriate. I extend to you and your colleagues my thanks for your dedication and my congratulations on your success.

Sincerely, Louis Stoten

Louis Stokes

Caramana - Caramana - Catandra - Hardeson - Jacobson - Los Jacobson - Ware - Mare York - Product - Profession - See Hardeson
Tarres - Troppe Carama - Westerna and DC | Baressan - Bernald - Bernald - Respect - Resp - Jordon - Marine - Malan
Mineral - Professi | Jacobs - Bernald - Howe Bone - Tarres - Troppe | Americania - Catalog Childs

monhowe



### MOREHOUSE SCHOOL OF MEDICINE

August 19, 2002

Director National Heart Lung and Blood Institute National Institute of Health 31 Center Dr., Rm. 5AS2 Berlenda, MIS 20092

### Dear Claude:

I constrain his ven, the NBLBI staff, the Advisory Connell and the national network of Sickle Cell Centers and recombant, on reaching this M-year aminumary of the National Sickle Cell Discove Program.

It is only because of a conflict in my subsidale that I am not with you in person, to join in the celebrations and recognitions.

As you are aware, I was pleased to serve as a revealed of the original National Sickle Disease Advisory Controlled to the Secretary of Heilth Education and Weller. This advisory committee belood to define the stope of this testional programs, which included basic and climical revearch, protection, obscience and sentence required to the desired or 400000.

This new initiative of NIII and III will led to the catabilitizated of two competitionine States of exacting a readomic medical content around the country. I was pleased and howeved to nave as Associate Districts, then Districts of the State Cell Content as Beston City Hangilat, one of the first NIII-depted notional content. The Boston State of Cell Center included health profunctionals and passacts of eventues from medical schools at Harvard, Boston University, Taffe University and the University of Manuschapetts — a truly collaborative offset in Manuschapetts.

Over the thirty-year period of the National Sickle Cell Program, much has been ecomophished, including a number of successful eliminal trials; resulting in new protocol for periodille prophylazis, here favian therapy in chaldren, use of hydrony with that other thempers.

NMLBI has expended atmost \$1.0 billion to support those studies. As a count of this investment over the past there decodes, we have extensive in insteads in increase life expectancy for those with sick is cell discuss, from ten than 30 years in 1972 to more than 45 years today, and an improvement in the quality of life for those with sockle cell discuss. For our notion's efforts this is a way close trains from their investment of scientific and medical solont and of their fature for forces are considered.

Most important is the reality that these afflicted with sickle cell discoverted have a brighter fister than was the case thirty years ago.

Again, congratulations to you, to NILLHI, and to our nation's biomedical research community on this happy occasion.

Sincerely

Louis W. Sullivan, M.D. President Fracritos

### Sickle Cell Research for Treatment and Cure

### Introduction


In his "Special Message to the Congress Proposing a National Health Strategy" of February 18, 1971, President Nixon made research on sickle cell anemia a national priority:

"A... targeted disease for concentrated research should be sickle-cell anemia - a most serious childhood disease which almost always occurs in the black population. It is estimated that one out of every 500 black babies actually develops sickle-cell disease.

"It is a sad and shameful fact that the causes of this disease have been largely neglected throughout our history. We cannot rewrite this record of neglect, but we can reverse it. To this end, this administration is increasing its budget for research and treatment of sickle-cell anemia . . ."

Legislation was subsequently introduced in both the House and the Senate to provide for the control of sickle cell anemia, and only 14 months later, on May 16, 1972, the National Sickle Cell Anemia Control Act (P.L. 92–294) was signed into law. P.L. 92–294 provided for the establishment of voluntary sickle cell anemia screening and counseling programs; information and education programs for health professionals and the public; and research and research training in the diagnosis, treatment, and control of sickle cell anemia.

Shortly after the act was passed, the Secretary of the Department of Health, Education, and Welfare responded by establishing a National Sickle Cell Disease Program and by assigning to the National Heart, Lung, and Blood Institute (NHLBI, then the National Heart and Lung Institute) the responsibility for developing and supporting a program of research in sickle cell disease and for coordinating the overall program. The extent of the Institute's commitment to improving the lives of persons with sickle



Since 1972, the NHLBI has invested over \$923 million in sickle cell disease research.

cell disease is reflected in the size of its research investment, which totaled \$923 million during the years 1972–2001.

The return on this public investment in sickle cell disease research has been impressive. Unlike the situation 30 years ago, babies born today with sickle cell disease have available to them a number of treatment options that can mediate, and in some cases even prevent, complications of the disease. They also have before them the


promise that research will continue to increase our understanding of the disease and its complications, to expand and improve upon the options for treatment, and to develop a safe and effective cure.

### Sickle Cell Disease

Sickle cell disease is a genetic blood disorder that affects about 72,000 Americans, predominantly those of African ancestry. It occurs when a child inherits from each parent

# North America South America Africa Australia

Many Africans and people of African descent have the gene for sickle hemoglobin.



Red blood cells containing sickle hemoglobin can assume a variety of distorted shapes.

## **Harvesting the Fruits of Earlier Research**

Here are some examples of how basic laboratory results from years ago have provided a basis for lifesaving advances against sickle cell disease and offer hope for future progress.

- Early laboratory tests that could distinguish blood from people with sickle cell disease and other blood disorders served as a foundation for the widespread screening of newborns. (See page 4, "The CSSCD and PROPS—Identifying a Problem, Finding a Solution.")
- Awareness of the existence of multiple types of hemoglobin (e.g., epsilon and zeta [embryonic] hemoglobins; gamma [fetal] hemoglobin; alpha, beta, and delta [adult] hemoglobins), and realization that both gamma and beta hemoglobin are capable of binding with alpha hemoglobin to form the complete, four-part hemoglobin protein that allows red blood cells to carry oxygen, paved the way for treatments based on reactivation of fetal hemoglobin synthesis. (See page 6, "Hope Through Fetal Hemoglobin.")
- A basic understanding of blood typing and transfusion medicine enabled patients with sickle cell disease to benefit from prophylactic and therapeutic transfusions. (See page 9, "Stopping Stroke.")
- Experiments in the 1950s demonstrating that mice whose bone marrow had been destroyed by irradiation could be rescued via infusions of bone marrow from healthy mice constituted one step in a chain of discoveries that set the stage for bone marrow transplants to cure human diseases. (See page 10, "Transplantation.")

a gene that makes an altered form of hemoglobin, the protein that carries oxygen throughout the body. This genetic alteration often causes the red blood cells to assume the crescent or sickle shape that gives the disease its name. Unlike normal red cells that pass smoothly through the blood vessels, sickle cells tend to become entangled and to obstruct blood flow.



Sickle cell disease has affected this infant's spleen and liver.


The result is episodes of extreme pain ("crises"), as well as chronic damage to vital organs. Two of the organs most susceptible to damage are the brain and the lung, and strokes and a life-threatening respiratory problem, known as acute chest syndrome, are frequent complications for sickle cell disease patients. The disease also destroys the spleen at

a very early age, which impairs the body's immune system and renders youngsters extremely vulnerable to overwhelming bacterial infections. Although there is much variability in the severity of the disease, many with sickle cell disease face a shortened life expectancy and a host of troubling, debilitating, and expensive health problems.


### The CSSCD and PROPS—Identifying a Problem, Finding a Solution

In the 1970s, federally funded research in laboratories throughout the country brought about a revolution in our understanding of sickle cell disease - it was the first human disease to be fully characterized at the DNA and RNA levels. And yet, little was known about the clinical course of the disease. The medical literature carried reports of only the sickest patients, and information about the typical course of the disease and likely response to therapeutic and preventive approaches was lacking.

The NHLBI responded to this need in 1978 by launching the multicenter, 4,000-patient, Cooperative Study of Sickle Cell Disease (CSSCD). In addition to collecting important epidemiological data, the study sites provided the basic infrastructure for one of the first major clinical trials to address sickle cell disease. Pneumococcal infection had been identified as a threat to infants and young children with sickle cell disease as early as 1966. In 1983, 12 of the CSSCD sites joined forces with 11 other centers to test the effectiveness of penicillin in preventing the deadly Streptococcus pneumoniae sepsis in infants and toddlers. In 1986, the study, called the Penicillin Prophylaxis in Sickle Cell Disease Study (PROPS), was terminated 8 months early because it had already produced some remarkable results: researchers found that daily administration of oral penicillin to children aged 3 months to 3 years could reduce the incidence of infection by 84 percent. The impact of the PROPS results was pronounced. They not only established a new standard of care for infants with sickle cell anemia, but also brought about a widespread change in policy regarding the screening of newborns. Although the technology for screening newborns for sickle cell disease had been available since the early 1970s, it was not generally employed because an early diagnosis offered no advantage. Without an effective treatment, nothing could be done to decrease







The 23 sites of the Cooperative Study of Sickle Cell Disease were located in major metropolitan centers.

morbidity or mortality. PROPS changed all that, providing indisputable evidence that early diagnosis of sickle cell disease and the subsequent administration of prophylactic penicillin could save children's lives. Due largely to those results, the Consensus Development Conference on Newborn Screening for Sickle Cell Disease and Other Hemoglobinopathies, convened by the National Institutes of Health (NIH) in 1987, recommended that "every child should be screened for hemoglobinopathies to prevent the potentially fatal complications of sickle cell disease during infancy."

With the prestige of the Consensus Development Conference recommendations added to the strength of the

### Conclusions From the NIH Consensus Statement "Newborn Screening for Sickle Cell Disease and Other Hemoglobinopathies."


(NIH Consensus Statement Online 1987 Apr 6–8 [cited 2002 Aug 15];6(9):1–22.)

- Effective intervention in children with sickle cell disease provides a major impetus for neonatal screening. Prophylactic penicillin therapy provided in a setting of comprehensive care has been found to significantly reduce the morbidity and mortality of patients with pneumococcal sepsis.
- Reliable, simple, and cost-effective techniques for mass screening of neonates are available and have demonstrated validity.
- The benefits of screening are so compelling that universal screening should be provided. State law should mandate the availability of these services while permitting parental refusal.
- 4. Centralization of laboratory services improves efficiency and decreases the probability of error.
- 5. To be effective, neonatal screening must be part of a comprehensive program for the care of sickle cell patients and their families. These services must include a network of providers who ensure optimal medical care, psychosocial support, and genetic counseling. Such followup capabilities should be in place before screening is instituted.
- 6. Further research should focus on the following: improving and evaluating the technology for screening; defining the impact of screening on the physical, social, cognitive, and emotional development on the child and on family members; assessing other methods of management of infection; and providing optimal education of individuals and families at risk.

In summary, the panel concludes that every child should be screened for hemoglobinopathies to prevent the potentially fatal complications of sickle cell disease during infancy.

cell disease.

The NHLBI invited researchers to submit grant applications on the topic "Synthesis of Fetal Hemoglobin in Human Erythroid Cells." Leading molecular biologists responded and began investigating ways that fetal hemoglobin production could be increased as a therapy for sickle cell disease.



Results from PROPS show that 125 mg of penicillin twice daily prevents infection in children less than 3 years old.



In 1987, the NIH held a consensus development conference on Newborn Screenina for Sickle Cell Disease and Other Hemoglobinopathies.

PROPS findings, the public health community quickly responded. Whereas before the Conference. fewer than 14 States offered/provided neonatal screening for sickle cell disease, today 44 States, the District of Columbia. Puerto Rico. and the Virgin Islands provide universal screening for sickle cell disease, and screening is available by request in the other 6 States.

Of course, the logical next question was, When, if ever, can we safely discontinue the penicillin regimen for those babies found to have sickle cell disease? That question was answered in 1995 by the NHLBI-sponsored PROPS II, which demonstrated that once a child reaches 5 years of age, penicillin prophylaxis can be safely stopped.

### Hope Through Fetal Hemoglobin

The hemoglobin molecule in the red blood cells of children and adults differs from its counterpart in the red blood cells of fetuses. For most people, the process of replacing red blood cells that contain the fetal form of hemoglobin with red blood cells that contain the postnatal form, a process that begins around birth, is of no consequence. However, for those with sickle cell disease this replacement makes a profound difference because it is their altered postnatal form of hemoglobin that causes their red blood cells to sickle.

As early as 1948, researchers noted that the adverse effects of sickle cell disease were reduced in very young infants who continued to show circulating red cells with fetal hemoglobin. Yet it was not until decades later, when researchers supported by the CSSCD and others noted milder symptoms in those adults with sickle cell disease who had circulating blood cells containing fetal hemoglobin, that the search for ways to stimulate fetal hemoglobin production as a treatment for sickle cell disease began in earnest.

A combination of basic research advances provided the first hint that drugs could be developed to stimulate the production of fetal hemoglobin in sickle cell disease patients. Researchers had previously determined that the genes involved in hemoglobin are located on chromosomes 11 and 16 and had characterized the pattern by which they are activated to produce hemoglobin during fetal and neonatal development. Others discovered that an anticancer drug, 5-azacytidine, was capable of reactivating the production of fetal hemoglobin after birth. Once researchers established that it stimulated the production of fetal-like hemoglobin in chickens and baboons, the NHLBI began a collaboration between investigators in its Comprehensive Sickle Cell Centers and others located at the NIH Clinical Center to determine the effect of the drug in terminally ill patients with sickle cell disease. The results were dramatic in that the drug ameliorated most of their symptoms.


Yet, despite its favorable properties, 5-azacytidine will never be an acceptable therapy because it is also a toxic carcinogen. Fortunately, it was not the only potential stimulant of fetal hemoglobin being studied. Preliminary studies on butyrate, a fatty acid that binds to DNA and occurs naturally in humans, showed that it also had promise, although its use continues to be experimental. Meanwhile, other researchers focused on another cancer drug, hydroxyurea, that they believed could affect fetal hemoglobin production in a way similar to the effect of 5-azacytidine.

### **How Does Fetal Hemoglobin Help?**

The basic pathogenesis of sickle cell disease is the formation of sickled cells. Within the cells, the sickle hemoglobin molecules combine to form fibers, which then combine with other fibers to form a rigid gel that is responsible for the deformation, or sickling, of the cells. Fetal hemoglobin disrupts fiber formation to the extent that a rigid gel does not form

One study showed that a fetal hemoglobin concentration of 25 percent essentially eliminates gelling under physiologic conditions. This finding is of great clinical importance, because drugs such as hydroxyurea and butyrate may be capable of increasing fetal hemoglobin to these levels. The NHLBI also supports studies of how hydroxyurea and other agents may influence hemoglobin gene expression and how gene expression is regulated during development. A thorough understanding of how hemoglobin genes are switched on and off should lead to new therapeutic approaches that enhance fetal hemoglobin synthesis.


Understanding fetal hemoglobin's role in the gelling process also has opened other potential avenues of treatment. Researchers are working to develop compounds that interrupt the gelling process as another treatment approach for patients with sickle cell disease.



Unlike hemoglobin in children and adults without sickle cell disease, the hemoglobin of sickle cell patients sticks together and forms a fibrous gel that gives the sickled red blood cells their rigid structure.

## epsilon (embryonic) (fetal) hemoglobin dene Cluster on Chromosome 11 Hemoglobin 2 copies of gamma delta (adult) hemoglobin hemoglobin hemoglobin Hemoglobin Gene Cluster on Chromosome 16 2 copies of zeta (embryonic) 2 copies of alpha (fetal and adult) hemoglobin

Multiple types of hemoglobin are found on chromosomes 11 and 16 in approximately the order in which they are expressed during development.



Hemoglobin genes are expressed at specific times during human development.

By 1991, with numerous studies indicating that hydroxyurea could indeed be a valuable treatment, the NHLBI began its Multicenter Study of Hydroxyurea in Sickle Cell Anemia (MSH). The trial, which was scheduled to run until May 1995, was brought to an end 4 months early because of the compelling results. Hydroxyurea treatment reduced by half all of the following sickle cell symptoms or complications:

- Painful sickle cell episodes or crises
- Hospitalizations for painful episodes
- Episodes of acute chest syndrome (a life-threatening condition similar to pneumonia)
- Units of blood that patients needed to receive

The MSH results figured prominently in the 1998 decision by the Food and Drug Administration (FDA) to make hydroxyurea the first agent approved for the prevention of painful episodes in adult patients with sickle cell disease.

Because fetal hemoglobin levels in most people disappear entirely after the first few months of life, researchers suspected that hydroxyurea could also help pediatric patients with sickle cell disease. But they also had a serious concern: Could hydroxyurea be safely given to children? Another NHLBI-supported study tested the safety and efficacy of hydroxyurea in patients aged 5 to 15. That study not only confirmed the efficacy of hydroxyurea in

children, showing results similar to those in adults (i.e., hydroxyurea increased fetal hemoglobin and total hemoglobin levels and decreased complications associated with sickle cell disease), but also demonstrated its safety. Hydroxyurea showed no adverse effect on growth or development.

The NHLBI is now evaluating whether hydroxyurea can benefit even younger patients. A pilot study of hydroxyurea given to children between ages 6 and 24 months demonstrated that the drug is well tolerated and stimulates fetal hemoglobin expression; an additional study is scheduled to begin this year.

Further analysis of data from MSH has shown that hydroxyurea therapy reduces health care costs. Currently, investigators are monitoring volunteers from MSH to determine how long-term hydroxyurea therapy affects their quality of life, morbidity, and mortality.

### Stopping Stroke

One of the important findings of the CSSCD was that pediatric patients with sickle cell anemia have rates of stroke in the range of 0.5–1 percent per year. In an attempt to find a strategy that would prevent first-time stroke, the NHLBI initiated the Stroke Prevention Trial in Sickle Cell Anemia (STOP) to identify children between the ages of 2 and 16 who were at risk for first-time stroke and to determine whether periodic blood transfusions were more effective at preventing stroke than standard supportive care.

In September 1997, STOP followed the pattern established by PROPS and MSH, in that it too was terminated early because of favorable results. Study participants who received regular prophylactic transfusions experienced a 90-percent reduction in their stroke rate compared with those who did not. With the completion of STOP, we now know that we can effectively prevent the two leading causes of death in children with sickle cell disease: pneumococcal sepsis and stroke.

As with the prophylactic penicillin regimen, however, STOP left unanswered the logical followup questions: Must the transfusions be continued indefinitely? Could they be stopped after some period of time, and if so, when? The NHLBI is currently supporting another study, called STOP II. to address these issues.

Stroke prevention is a major reason for transfusing sickle cell patients, but it is not the only one. Transfusions are an effective treatment for patients with chronic debilitating pain, pulmonary hypertension, and anemia associated with chronic renal failure. However, chronic transfusions invariably cause iron concentrations to increase throughout the body, and high iron concentrations result in damage to vital organs, especially the liver, heart, and pancreas. The NHLBI continues to support research

### Stroke Risk Factors Identified by the CSSCD, STOP, and Other Studies

### All pediatric patients

- Prior transient ischemic attack
- Low steady-state hemoglobin
- Rate and recency of acute chest syndrome
- Elevated systolic blood pressure
- Stroke in a sibling
- Subtle neurological abnormalities
- Severe anemia
- High leukocyte count
- Genotype
- Transcranial doppler (TCD) ultrasound reading ≥ 200 cm/sec



Dactylitis (painful swelling of hands and feet) indicates that a child is at increased risk of pain crises, stroke, acute chest syndrome, and death.

efforts to reduce the adverse effects associated with chronic transfusion therapy by finding safe and effective ways to remove excess iron.

### **Transplantation**

Although bone marrow transplantation had been used for some time to treat leukemias and other fatal disorders of the blood, no one had pursued it as a potential therapy for sickle cell disease until 1984, when a bone marrow transplant performed to treat a pediatric patient with leukemia was reported to have also cured the child's sickle cell disease.

That bone marrow transplantation was overlooked as a possible treatment approach for sickle cell disease is not at all surprising. It is a serious procedure that entails substantial risk to the patient. Prior to the transplant itself, patients must undergo a chemotherapeutic regimen to destroy their own bone marrow and immune system. Some patients do not survive the chemotherapy. Others suffer from life-threatening infections before their bone marrow and immune systems are sufficiently regenerated. Some bone marrow transplants simply do not work. Still others seem to work initially but then fail because the immune cells produced by the transplanted marrow attack the tissues and organs of the patient (graft-versushost disease) or because the patient succumbs to other complications, such as hemorrhage.

### A Summary of the Bone Marrow **Transplant Process**

- The patient and his or her family and physicians determine that bone marrow transplant is worth the risks.
- A suitable donor is found.
- The patient undergoes a toxic preparative conditioning regimen of chemotherapy and/or radiation to destroy existing bone marrow.
- Special precautions are taken to shield the patient from infection, since his or her immune system has been destroyed by the preparative regimen.
- The patient receives the transplant.
- In the weeks to months following the transplant but before total engraftment occurs, the patient and medical team are vigilant about preventing, detecting, and treating complications, including
  - Infection
  - · Acute graft-versus-host disease
  - Bleeding
  - Damage to heart, kidneys, liver, lungs
  - Graft failure
- After patient is discharged from hospital, followup care begins. It includes treatment of
  - Long-term effects of preparative regimens (cataracts, infertility)
  - Severe fatigue, which may require treatment with medication or red blood cell transfusions
  - Chronic graft-versus-host disease
  - Side effects of medications used to treat transplant complications

Today, transplants are considered only for sickle cell patients whose disease is severe enough to justify the risk. However, the NHLBI currently is supporting a range of research programs to reduce the risk by improving the likelihood of a successful transplantation. Umbilical-cord blood is one promising area of investigation. Increasing evidence suggests that donors of umbilical-cord blood do not need to match recipients as closely as bone marrow donors do. In addition to indicating that use of cord blood may reduce the risks of rejection and graft-versushost disease, this also suggests that transplantation of unrelated cord blood may provide a source of stem cells for children with hard-to-match tissue types. Investigators are also exploring an approach in which a patient's bone marrow is only partially destroyed before performing a transplant. This "mixed-chimerism" protocol, which

### **Examples of Diseases That Can Be** Treated by Bone Marrow Transplant

- Acute Myelogenous Leukemia
- Acute Lymphoblastic Leukemia
- Chronic Myelogenous Leukemia
- Congenital Thrombocytopenia
- Hodgkin's Lymphoma
- Multiple Myeloma
- Myelodysplastic Disorder Syndromes
- Non-Hodgkin's Lymphoma
- Severe Aplastic Anemia
- Sickle Cell Anemia

leaves the patient with components of two immune systems, would be especially attractive for children, because it would entail a less toxic chemotherapeutic regimen to be used before the transplant. It would not only further decrease the chance of death, but also reduce the likelihood of permanent infertility. Mixed-chimerism protocols are also being explored as a possible treatment approach for adults.


## Clinical Severity, Genetic Modifiers, and Gene Therapy

Despite a detailed body of knowledge about sickle cell disease at the molecular level, researchers do not yet know why sickle cell patients show such extreme variability in disease severity. Individuals with sickle cell disease all have the same defect in the gene that produces betahemoglobin, yet some of them are subject to strokes, others are subject to frequent painful episodes, and still others show minimal symptoms.

Researchers examining the region of the chromosome *nearby* the gene for beta-hemoglobin noted variations in the sequence among individuals. The variations followed four major patterns, or haplotypes. This suggests that the genetic mutation that causes sickle hemoglobin is associated with at least four different genetic backgrounds. Recent studies have shown that clinical

differences may exist among the haplotypes and that the differences may serve as predictors of disease severity. For example, people who have the Arab-Indian variation tend to have a milder form of sickle cell anemia, sometimes with no symptoms.

Some clues to the causes of variability in disease severity are provided by the beneficial effects of elevated levels of fetal hemoglobin. Elevated levels of fetal hemoglobin are associated with fewer painful crises, a reduced frequency of acute chest syndrome, a delayed onset of damage to the spleen, and a slower rate of degeneration of the hip and shoulder joints, which is another frequent complication.



The four major sickle hemoglobin haplotypes are associated with different geographic regions.

In 2001, the NHLBI began an effort to stimulate research examining the genetic elements that modulate the severity of sickle cell disease. Identification of other, as yet unknown, genetic modifiers of the clinical severity of sickle cell disease may help physicians determine which pediatric patients are likely to experience more severe disease and initiate targeted therapies to extend and improve the quality of their lives.

For years, one of the greatest impediments to research on sickle cell disease was the lack of a useful animal model of the disease. This hurdle was overcome in 1997, when two groups of NHLBI-supported investigators inserted the human gene responsible for sickle cell disease into mice, thereby creating transgenic models of the human disease. The two models differ slightly; one produces both human sickle hemoglobin and human fetal hemoglobin and displays mild symptoms, whereas the other, which produces only sickle hemoglobin, closely mimics severe sickle cell disease.

That advance is critical to researchers who are seeking a gene-therapy cure for sickle cell disease. Their ultimate objective is to correct the defective gene and then insert it into the bone marrow of sickle cell patients to stimulate the production of normal hemoglobin. Recent experiments show promise. In December 2001, NHLBI-supported scientists announced that they had corrected sickle cell disease in two mouse models of the disease using gene

therapy. Scientists are hopeful that their approach can be applied to human patients by removing some of a patient's own bone marrow cells, genetically correcting them, and then infusing the corrected cells back into the patient.

### Deformed Membranes and Dehydrated Cells

A large body of evidence suggests that abnormalities of the red cell membrane contribute to the pathophysiology of sickle cell disease. The defective hemoglobin in sickle cell disease also weakens the membranes of the red cells and ultimately causes them to fail from repeated sickling. The changes in cell shape that occur during sickling include the appearance of long protrusions from the red cell surface. Unlike their normal counterparts, the hemoglobin molecules in sickle cell disease tend to bind to one another, especially after they have delivered their oxygen to the surrounding tissues. Investigators have observed that as they bind together, they push through the membrane, causing it to deform and then fail. These alterations of the membrane during sickling increase the tendency of the red cells to adhere to the linings of blood vessels. Clinical investigators have begun to evaluate membrane-active drugs as possible treatments for patients who have sickle cell disease. Agents that have been studied include clortrimazole, magnesium compounds, glutamine, and omega-3 fatty acids. Since not all patients

### A Framework for the Future: **Towards Improved Treatment and Cure**

The NHLBI has adopted and already begun to implement a strategic plan for progressing to improved treatments and ultimately a cure. It consists of two components:

### Improved treatment

- Facilitate the development of more effective inducers of fetal
- Test the new inducers of fetal hemoglobin in large animals
- Initiate carefully devised clinical investigations with human patients of those approaches found to be safe and effective in animal studies

### Gene therapy for a cure

- Facilitate the development of improved technologies for hemoglobin gene transfer
- Test the new gene transfer approaches in large animal studies
- Initiate carefully devised clinical investigations with human patients of those approaches found to be safe and effective in animal studies

respond to or can take hydroxyurea, it is hoped that these alternatives will lead to new approaches to treat patients with sickle cell disease

Red blood cells have a finite lifespan; as they fail, they must be replaced. Sickle cell patients have unusually high concentrations of newly formed red cells, known as reticulocytes, because their red blood cells have a shorter lifespan than normal red blood cells. In sickle cell disease, reticulocytes not only are inordinate in number, but also have unique properties that make them particularly susceptible to dehydration. As red cells become dehydrated,

their concentration of hemoglobin increases, thereby increasing the proximity of hemoglobin molecules to one another so that they have more opportunity to bind together. In addition, the dehydrated cells are much less flexible. They are, therefore, more likely to lodge in small blood vessels, where they contribute to such characteristic manifestations of sickle cell disease as pain crises. An increased understanding of the dehydration process has led to pilot clinical studies of potential therapeutic agents to regulate red blood cell hydration.


### A Disease of the Blood Vessels Too?

Like their red blood cells, the blood vessels of sickle cell. patients differ from those of people who produce normal hemoglobin. One of the most prominent differences is that endothelial cells from patients with sickle cell disease appear to enter into the circulation at an unusually high rate. In addition, mere contact between the red blood cells and the endothelial cells is sufficient to stimulate an immune response in sickle cell patients. The immune response causes an inflammation, which further reduces the space available for blood to flow and thereby increases the likelihood of blockage formation.

Findings related to blood vessel constriction in general also have applicability in sickle cell disease. Much research has been conducted over the past several years on nitric oxide and its role in regulating blood pressure. One of its functions is to keep blood vessels open so that blood can flow freely; nitric oxide also suppresses the proteins that help blood cells to stick to the vessel walls. These observations, combined with the knowledge that patients with sickle cell disease have abnormally low levels of nitric oxide, provide important insights and research opportunities regarding how red blood cell "stickiness," vessel inflammation, and vasoconstriction all combine to disrupt blood flow.

### Summary

The story of the National Sickle Cell Disease Program is a story of progress and promise. The progress is reflected in a doubling of the life expectancy for patients with sickle cell disease since 1970, with patients now living on average into their mid-forties. It is reflected in the successful conclusion of a number of major clinical trials and in the three revisions of the NHLBI publication on managing sickle cell disease that have been necessitated by the trial





The NHLBI recently released a new guide to the management of sickle cell disease (available online at www.nhlbi.nih.gov/health/prof/blood/sickle/index.htm).

findings since the document was first published in 1982. It is reflected in the routine screening of infants for sickle cell disease and in the routine administration shortly after birth of antibiotic treatment to those infants identified with the

disease. And it is reflected in the FDA approval of hydroxyurea as a proven therapy to reduce the painful, debilitating, and damaging sickle cell crises in adults.

The promise is that the NHLBI will continue to support and encourage research to improve the lives of persons with sickle cell disease. We will support and encourage new basic research studies to advance our fundamental understanding of the disease that will provide the insight needed to develop new approaches to treatment and cure. We will support and encourage followup clinical investigations of basic science advances to determine whether they are likely to benefit sickle cell patients. We will support and encourage efforts to ensure that proven treatments are rapidly disseminated and applied to improve the health of sickle cell patients. And we will not consider the National Sickle Cell Disease Program to be a complete

success until babies born with sickle cell disease enjoy the same life expectancy and the same quality of life as everyone else.

