Records Management Guidance For PKI-Unique Administrative Records
Final
March 14, 2003

Table of Contents

DOCUMENT STATUS	1
1. INTRODUCTION	2
2. BACKGROUND	4
3. PURPOSE AND SCOPE	
3. PURPOSE AND SCOPE	0
4. PKI RECORDS PRODUCING FUNCTIONS AND ACTIVITIES	10
5. PKI-UNIQUE RECORDS MANAGEMENT GUIDANCE	14
5.1 GUIDANCE FOR OPERATIONAL SYSTEMS	16
5.2 GUIDANCE FOR RECORDKEEPING SYSTEMS	24
APPENDIX A. GLOSSARY, ACRONYMS AND ABBREVIATIONS	32
APPENDIX B. EXAMPLE PKI-UNIQUE ADMINISTRATIVE RECORDS SERIES	38

Document Status

This final version of the *Records Management Guidance for PKI-Unique Administrative Records* has been produced for the CIO Council and records management community by the Federal Public Key Infrastructure Steering Committee's Legal/Policy Working Group and the National Archives and Records Administration. It addresses the following sets of received comments.

		Distribution	Comments
Draft Number	For Review by	Date	Date
One	Legal and Policy Working Group, FPKISC	6/21/02	7/17/02
Two	Federal PKI Steering Committee	7/29/02	8/9/02
Three	NARA, DOJ	8/19/02	9/27/02
Four	Federal PKI Steering Committee (final review)	10/15/02	10/29/02
Five	CIO Council	11/5/02	12/16/02
Final	Final	03/14/03	03/01/03

1. Introduction

A public key infrastructure (PKI) is defined as "a set of policies, processes, server platforms, software and workstations used for the purpose of administering certificates and public-private key pairs, including the ability to issue, maintain, and revoke public key certificates." A PKI is also an asymmetric cryptography security environment that is built on a set of standards and guidelines that require the production, receipt, and maintenance of certain administrative records during the planning, implementation, operation, auditing/monitoring and reorganization or termination of the infrastructure.

Regulatory, legal or audit issues could arise during the operation of PKIs in the conduct of business by federal agencies that require the retrieval and delivery of PKI-unique administrative records. Retrieval may also be required in the course of subsequent agency business transactions. Therefore, retaining and managing records according to regulations and good practices for the authorized retention period should be fundamental elements of a PKI. With the understanding that a record file copy is established as soon as data content or document content is finalized or received, this fundamental need for records management is an integral part of a PKI and applies whether the records are being retained and managed in an operational system², or in a recordkeeping system³.

As a means to assist agencies in the management of PKI-unique administrative records, the development of this guidance was jointly initiated by NARA and the Legal and Policy Working Group [LPWG] of the Federal Public Key Infrastructure Steering Committee [FPKISC], which operates under the mandate of the Chief Information Officers' [CIO] Council.

The target audience for this guidance includes federal agency information technology, records management and operations personnel responsible for planning, implementing, operating or otherwise documenting and managing records produced by PKI administrative activities. Other entities, such as state and local government agencies, as well as commercial entities interacting with government agencies may find this guidance document useful and may adopt and or modify it to suit their specific needs.

The remaining content of this guidance is organized as follows:

Section 2. Background, discusses the situation with respect to existing records management guidance and articulates specific questions that need to be answered when developing guidance unique to a PKI.

¹ Introduction to Public Key Technology and the Federal PKI Infrastructure, 26 February 2001, National Institute of Standards and Technology

² The software and hardware system that performs the day-to-day activities of running and maintaining a PKI, such as a CA (see Appendix A).

³ A manual or automated system in which records are collected, organized, and categorized to facilitate their preservation, retrieval, use, and disposition for the authorized retention period (see Appendix A).

Section 3. Purpose and Scope, presents the key considerations that form the basis for the records management guidance.

Section 4. PKI Records Producing Functions and Activities, describes the various processes and activities, including example records inherent in a PKI environment and categorizes them as either PKI-unique or PKI-supporting.

Section 5. PKI-Unique Records Management Guidance, delineates the guidance for the management of PKI-unique administrative records and is segmented into two areas: "operational" and "recordkeeping" systems.

There are two supporting appendices: Appendix A – Glossary, Acronyms and Abbreviations; Appendix B – Example PKI-unique Administrative Records Series, which presents an example of how PKI-unique records can be logically categorized by activity.

2. Background

Currently, there are several general sources of guidance for managing records generated in an electronic application environment. In response to requirements stated in the Government Paperwork Elimination Act (GPEA), NARA issued a document entitled "Records Management Guidance for Agencies Implementing Electronic Signature Technologies" dated October 18, 2000 (transmitted as part of Bulletin 2001-02 on October 19, 2000). NARA also has promulgated regulations in 36 CFR Part 1234 that provide general guidance for the management of electronic records. The Department of Defense (DOD) 5015.2 Design Criteria Standard for Electronic Records Management Software Applications, Version 2, delineates comprehensive guidance for the management of electronic records in general. OMB Circular A-130 contains general guidance in Appendix III related to the need for the management of records created in a security infrastructure. However, A-130 does not specifically address the management of records unique to a PKI.

Current guidance that addresses PKI-specific records is at a very high level (CARAT⁴) or only provides discussion of issues (PAG⁵), rather than setting forth specific requirements. Section 4.5.5 Records Archival of the X.509 Certificate Policy and Certificate Practices Framework (RFC 2527) dated January 3, 2002 (X.509 CP/CPS Framework), only suggests a framework for managing records and appears to relate exclusively to an operational system environment. This framework does not provide specific guidance for managing records during the authorized retention period, nor does it address the management of other PKI-unique administrative records that are created outside of the operational system, such as a Certificate Policy (CP), Certification Practice Statement (CPS), or subscriber agreement.

Statements made in Section 4.5.5 Records Archival of the latest X.509 CP/CPS Framework and in several certificate policy drafts, such as from the Federal Bridge Certification Authority (FBCA), Digital Signature Trust (now part of Identrus) and VeriSign, suggest that government agencies and PKI software vendors primarily are interpreting the term "records archival" as meaning "backup" of the records in a PKI operational system. This interpretation does not reflect the meaning of "archival" and "archiving" as understood by records managers: a trustworthy logical or physical repository of records that is protected from loss, alteration, and deterioration for the full duration of the authorized retention period. Satisfying various requirements for protecting records as trustworthy evidence means that they should be managed in an environment that supports the functionality required of a recordkeeping system.

In essence, the current guidance and framework are either too general or too narrowly focused to address the specific requirements for managing PKI-unique administrative records, particularly

⁴ CARAT Guidelines for Constructing Policies Governing the Use of Identity-Based Public Key Certificates; National Automated Clearing House Association (NACHA), The Internet Council Certification Authority Rating and Trust (CARAT) Task Force, January 14, 2000

⁵ *PKI Assessment Guidelines (PAG)*, *v0.30*, Information Security Committee, Section of Science and Technology, American Bar Association, June 18, 2001

regarding higher level certificate environments where retention periods can run from ten to twenty-plus years. Examples of key questions left unanswered by current guidance are:

- Since the X.509 CP/CPS Framework, Section 4.5.5 Records Archival appears to focus on operational PKI systems, what guidance is needed to manage records that are created or received outside of the operational system, such as paper records or records created and stored in electronic form by an office productivity application?
- If the data that underlies records are being retained in database tables on the operational system and also being retained as the record file copy for the full retention period, what is needed on the operational system to manage the disposition of the records according to the authorized retention schedule?
- What data elements (metadata) should be available on the operational system to allow for either:
 - Managing the disposition of database records when the authorized retention period expires?
 - Transferring database records to a recordkeeping system for management during longer term retention periods?
- Should non-current or non-active PKI-unique records (e.g., expired digital certificates) be transferred from an operational system to a recordkeeping system and, if so, when and using what methods?
- If records are transferred from an operational system to a recordkeeping system, what practices should be in place to ensure a complete and accurate transfer?
- If the record file copy is maintained in a recordkeeping system, what practices need to be followed to preserve it for a long term retention period? The retention periods of each agency will vary according to their needs and should be developed by each agency and approved by NARA.

This guidance document is aimed at providing answers to these questions in the form of perspectives, examples and guidance for managing PKI-unique administrative records.

In an effort to determine the areas and issues that should be considered when developing more detailed PKI-unique administrative records management guidance, two Focus Groups sessions with participants from multiple federal agencies were conducted on March 18 and 20, 2002. Key issues identified in these Focus Groups have been addressed, as appropriate, in Section 5. PKI-unique Records Management Guidance.


3. Purpose and Scope

This document provides records management guidance for both operational and recordkeeping environments that will assist federal agencies in the management of administrative records produced or received during the planning, implementation, operation, audit or monitoring and reorganization or termination of a PKI. This guidance supplements the general electronic signature records management guidance issued by NARA on October 18, 2000 entitled "Records Management Guidance for Agencies Implementing Electronic Signature Technologies."

The focus of this guidance is on PKI-unique administrative records (as opposed to transaction records that incorporate the use of a public key certificate or cryptographic key). This guidance may apply to both classified and unclassified PKI-unique administrative records. PKI-unique records are specific to the administrative functions related to planning, implementing, operating, auditing or monitoring, and reorganizing or terminating a PKI and are generally appraised as temporary. Records that are not unique to a PKI are called "supporting records." Supporting records are data or documents that are produced in most implementations of a computer or communications security infrastructure and are covered by existing records schedules or other guidance. Examples of supporting records are hardware/software documentation, training records, and personnel records (which are specifically covered in a General Records Schedule). While this document identifies both the unique and supporting functions and activities that are part of a PKI, this guidance focuses specifically on records that are unique to the PKI.

The following diagram delineates the specific group of records, namely PKI-unique records (in the bolded box), that are the subject of this guidance.

Figure 1. Relationship of PKI-unique Records



Several additional considerations define the scope of this guidance document:

- PKI records in general do not constitute a unique body of records although they are becoming of central importance to modern electronic business practices; nonetheless, basic records management regulations, standards and good practices all apply equally to records created or received in a PKI environment.
- This guidance addresses the need for records management according to the particular mode within which the PKI-unique records are being or will be retained. Guidance is provided for two basic modes:
 - Operational System: The need for records management guidance is especially critical for operational systems because little if any guidance exists and operational systems typically do not provide the functionality that is necessary for managing records. Operational systems maintain records in such a way that they can be accessed rapidly in the day-to-day activities of running a PKI, and potentially for a shorter time period than the authorized retention period. Many of the records that are required to establish the validity of a certificate or the operational integrity of the PKI at a given point in time are created or received and maintained on an operational system, such as the system operated by a Certification Authority (CA) or Registration Authority (RA). Since these records may be the official and possibly the only source of this information during part if not all of the authorized retention period, the operational system can be said to contain the "record file copy" of that information. Operational systems must ensure that the integrity of the records they manage is protected which may entail transferring records to a recordkeeping system before they are changed or replaced. Operational systems that currently do not meet the guidance outlined in Section 5.1 should be modified to conform.
 - Recordkeeping System: A recordkeeping system typically does not "create" records, rather it receives electronic records from an operational PKI system or from an office productivity application (e.g., word processing) or tracks paper records, or scanned, digital images of paper records for the purpose of providing retention and disposition management as well as long term retrieval and reproduction of the record file copy for the authorized retention period. Guidance for a recordkeeping system is required in order to allow for operational records to be transferred to a long-term records management environment and for the management of records created or received outside of the operational system.

Although the distinction between an operational system and a recordkeeping system is useful in this document, the professional community of PKI-system implementers should think through the implications of using the preceding definition as the working definition of recordkeeping system in other environments

⁶ A "record file copy" is the final or "official" copy that is retained according to a NARA-authorized retention schedule.

- Furthermore, records management guidance is considered in the context of the following sources for a record file copy:
 - Operational system: A record file copy of a specific record (e.g., a digital certificate) can be derived from relational database tables that have been populated from content submitted or entered via an Internet form or otherwise key-entered by a subscriber or administrative person, as well as automatically generated event log information.
 - Office productivity application: Text-based documents that do not require a handwritten signature to be complete could be retained as the record file copy.
 - Paper: Represents the record file copy when received into a PKI activity in paper form (such as documents from an applicant or other entity used for identity proofing) or if handwritten signatures need to be affixed to finalize the document or content, e.g., subscriber agreement, Certificate Policy (CP) or Certification Practice Statement (CPS). The documents may be printed from an operational system (such as from a database form or template) or from an office productivity application in order to apply handwritten signatures.
 - *Digital Images*: A paper record also may be scanned and converted to a digital image that is retained and tracked in electronic form.

These 'sources' highlight the diversity of record copies for PKI-unique administrative records. This is not intended as a recommendation to use these source systems as recordkeeping systems. PKI-unique administrative records should be separated from these source systems into recordkeeping systems, whenever possible.

 This guidance assumes that the implementation, operation and management of a PKI may involve disparate technology platforms and architectures that can change over time.
 Therefore, the requirements and good practices delineated in this guidance are technology independent.

This guidance is limited to defining and describing the requirements (or "what" is needed) for meeting records management regulations and good recordkeeping practices for PKI-unique administrative records. It does not define or suggest "how", i.e., which technology or products should be employed to implement the guidance.

This guidance does not define or recommend retention periods. The retention periods for each agency may vary considerably based on the needs and requirements of the agency. Records schedules should be developed to meet the specific needs of each agency's PKI implementation and then approved by NARA. PKI-unique administrative records that are created or received in the course of government business may only be disposed of in accordance with instructions articulated in an approved records schedule. Agencies may contact their NARA appraisal staff for more information on scheduling PKI administrative records.

This guidance does not address the area of records confidentiality since the requirements for the level and duration of confidentiality is very specific to the needs of each agency.

Although individual PKI subscribers may be government employees, private citizens, or both; this guidance only addresses the maintenance of records by individual government subscribers. This guidance does not cover the maintenance of transaction records generated by such, as those records are not administrative in nature

This guidance is not intended to be a primer or educational tool for understanding cryptography or the technical details of how a PKI functions or operates. To adequately apply this guidance in planning for appropriate records management of PKI-unique administrative records there should be close cooperation between records management personnel and personnel implementing the PKI. Please refer to the Web site of the National Institute of Standards and Technology (NIST) for information related to cryptography and PKI technology in the form of Federal Information Processing Standards and informational NIST publications – http://csrc.nist.gov/pki/documents/.

4. PKI Records Producing Functions and Activities

The objective of this section is to present a functional view of a PKI administrative environment where records are created or received and managed.

In the overall context of information resource management systems or information technology, a PKI primarily is a cryptographic security architecture and infrastructure and should be treated as such in the planning, documentation, implementation and management of the PKI. Certain functions and activities of a PKI generate records that may entail unique management requirements. However, there are many activities that merely support a PKI and produce records that are found in other security infrastructures. In this context, the general policies, procedures and requirements defined in Appendix III, Security of Federal Automated Information Resources of OMB Circular No. A-130, should be considered and applied, where applicable, in the management of administrative records produced in conjunction with a PKI.

The major sources used in developing this overview of PKI functions and activities are:


- Introduction to Public Key Technology and the Federal PKI Infrastructure, 26 February 2001, National Institute of Standards and Technology
- Federal Agency Use of Public Key Technology for Digital Signatures and Authentication, NIST Special Publication 800-25, October 2000, National Institute of Standards and Technology, Federal Public Key Infrastructure Steering Committee, Kathy Lyons-Burke
- Internet X.509 Public Key Infrastructure Certificate Policy and Certification Practices Framework, July 2001
- ITU-T Recommendation X.509 ISO/IEC 9594-8: "Information technology Open systems interconnection The directory: Public-key and attribute certificate frameworks"
- X.509 Certificate Policy For The Federal Bridge Certification Authority (FBCA), June 18, 2002
- CARAT Guidelines for Constructing Policies Governing the Use of Identity-Based Public Key Certificates; National Automated Clearing House Association (NACHA), The Internet Council Certification Authority Rating and Trust (CARAT) Task Force, January 14, 2000
- *PKI Assessment Guidelines (PAG), v0.30*, Information Security Committee, Section of Science and Technology, American Bar Association, June 18, 2001
- WebTrust Program for Certification Authorities, AICPA/CICA, August 25, 2000, Version 1.0
- Access Certificates for Electronic Services (ACES) Request for Proposal, General Services Administration, Amendment 00046, August 27, 1999.

The remainder of this section presents an overview of the PKI administrative record processes with examples of activities and related records.

Figure 2 below broadly depicts the administrative functional processes of a PKI and identifies example activities and example records produced from these activities. These examples of activities and records are not intended to be all inclusive, rather only to provide a perspective (see Table 1. for a more comprehensive listing of PKI administrative activities).

Bolded example activities and records represent the PKI-unique activities that are the focus of this guidance.

Figure 2. PKI Administrative Processes – Example Activities and Records



Bolded = PKI-unique Activities & Records

Table 1 presents a more complete list of example functions and activities of a PKI and differentiates them as being either unique or supporting a PKI environment. However, there may be other activities that are unique to a particular PKI application or to a particular CA's implementation. The records management guidance defined in Section 5 is designed for the PKI-unique activities identified in this table and the activities and records identified in Appendix B. Example PKI-unique Administrative Records Series.

Table 1. PKI Functions/Activities Differentiated As Either PKI-Unique or Supporting

EXAMPLE RECORDS-GENERATING FUNCTIONS/ACTIVITIES	PKI – UNIQUE	PKI SUPPORTING
Plan and Define PKI Environment		
Develop business case and requirements		X
 Perform risk/cost analysis (determine level vs. cost of security infrastructure) 		X
Authorize project		X
 Develop project plan 		X
• Develop certificate policy (CP) ⁷	X	
• Develop certification practice statement (CPS) ⁸	X	
Define certificate profile	X	
 Concept of operations 	X	
 Develop PKI SOPs per CP and CPS 	X	
 Develop recordkeeping strategy and procedures per CP and CPS 	X	
 Conduct insource/outsource (third-party) analysis 		X
Establish personnel requirements		X
Establish/Install/Start Up		
 Select CA (internal or third party) 	X	
 Select RA (internal or third party) 	X	
 Review and approve third-party CA, RA CPS (as required) 	X	
Conduct CA/RA accreditation	X	
Select/Establish certificate repository	X	
Establish certificate archive	X	
Internal Install		
 Acquire software and hardware 		X

⁷ The Certificate Policy should delineate the policies for operational and record keeping systems.

Final 03/14/2003

_

⁸ The Certification Practice Statement should state the practices that will be employed to manage PKI-unique records.

EXAMPLE RECORDS-GENERATING		PKI
FUNCTIONS/ACTIVITIES	PKI – UNIQUE	SUPPORTING
Install software		X
Install hardware		X
Test and validate hardware and software		X
Test security procedures		X
Create CA public key pair (Key Ceremony)	X	
Third Party Execution		
Develop/Execute third-party contractor		X
agreement		
Develop contractual recordkeeping agreement	X	
Validate third-party systems		X
Operate		
Personnel: Clear (background checks), hire, and		X
train		Λ
Identity proofing	X	
Register users	X	
Issue digital certificate (implicitly includes	X	
generate keys, deliver public or private key,	11	
Prove possession of private key and verify public		
key)		
Establish Certificate Revocation List (CRL)	X	
Maintain CRL	X	
Maintain CARL (CA Revocation List – FBCA)	X	
Renew certificates	X	
Revoke/suspend certificates	X	
Install HW/SW updates		X
Interoperate (FBCA)		
CA identity proofing	X	
Policy mapping	X	
Technical interoperability testing	X	
Cross certification agreements	X	
Border directory technical specifications	X	
Audit/Monitor		
Create audit trail data of PKI events, e.g.		
certificate revocation, certificate renewal, etc.	X	
Monitor external security		X
Investigate internal fraud or misconduct		X
Internal audit of SW and security		X
Internal audit of records management practices		X
External audit of HW/SW and security		X
Cross certification audits	X	

EXAMPLE RECORDS-GENERATING FUNCTIONS/ACTIVITIES	PKI – UNIQUE	PKI SUPPORTING
Reorganize or Terminate Operations		
Plan to terminate, consolidate or reorganize	X	
• Approval	X	
 Notify subscribers 	X	
Transfer inactive keys and CRL to storage	X	
Transfer consenting subscribers certificates to new CA for reissuance	X	
Revoke all certificates	X	
Shut down and dispose of RA and CA HW/SW		X
Destroy CA private keys	X	

5. PKI-Unique Records Management Guidance

The PKI-unique records management guidance is segmented into two areas, one for operational systems and one for recordkeeping systems (as identified and previewed in Section 3. Purpose and Scope). Since a record file copy is established as soon as data content or document content is finalized or received, both the operational and recordkeeping systems will have obligations for managing the records during the authorized retention period. However, operational and recordkeeping systems have fundamentally different purposes and require different approaches for managing records:

1) Guidance for Operational Records, Section 5.1: In most PKI operational systems, the active content (such as public key certificate data elements) and event information (audit log) typically are stored in relational database tables. While the data may be backed up for disaster recovery purposes, operational systems typically do not provide the necessary functionality to effectively manage records disposition nor other traditional records management functions. For example, a PKI system periodically may create a backup copy of "auditable events," but only the most recent three or four copies are kept because older copies are overwritten by the newer copies.

Since little if any records management guidance exists for operational systems and they typically do not provide the functionality that is necessary for records management, the need for guidance is especially critical.

In order to emphasize the necessity for implementing records management functionality in operational systems, the guidance for operational systems is intentionally kept separate from that of recordkeeping systems (even though there is some overlap in the individual guidance points).

Records Management Guidance for PKI-Unique Administrative Records

2) Guidance for Recordkeeping Systems, Section 5.2: The basis of the guidance for recordkeeping systems is to ensure that all trustworthy PKI-unique records are preserved as evidence for the authorized retention period. Guidance for a recordkeeping system is required for the following reasons:

15

- To manage PKI-unique administrative records (and possibly other supporting PKI administrative records) that are not created or received by the operational system, such as paper records and electronic records that are created on office productivity applications or are scanned images of paper documents. The guidance for recordkeeping systems applies to all PKI-unique records independent of the media on which they are stored.
- To provide for the transfer of operational system records to a recordkeeping system when the status of the record changes (no longer current or active) or certain events related to one or more records occur (e.g., expiration of a public key certificate).

A key premise for this guidance is that PKI-unique administrative records do not constitute a new category of records that require a total "reinvention" of life cycle records management policies and guidance. While the records a PKI produces may be unique in their content and application, the records management practices, as already embodied in certain federal statutes, regulations, guidance and standards, still apply.

The guidance tables in Sections 5.1 and 5.2 have two columns, 'Guidance' and 'Source'. It is important to note, however, that the portions of the *Code of Federal Regulations* cited in the 'Source' column do <u>not</u> articulate specific PKI-unique recordkeeping requirements. In no cases should *CFR* citations in the 'Source' column be an indication of a mandatory requirement; rather, one of potential applicability warranting further examination. In all cases, potential applicability of the cited sources should be discussed between the Agency Records Officer and the NARA Appraisal Archivist. A source for each guidance is cited and is drawn from the following references:

- NARA "Records Management Guidance for Agencies Implementing Electronic Signature Technologies"
- NARA 36 CFR 1234 Regulations
- DoD 5015.2 Standard, Version 2
- ITU-T Recommendation X.509 ISO/IEC 9594-8
- FBCA X.509 Certificate Policy
- GSA ACES Certificate Policy
- Good practice

As a first consideration, existing regulations are cited as the source. Where specific regulations currently do not exist to support the guidance, then existing records management guidance or standard, such as DoD 5015.2, is cited. Good practice is cited only in those instances where no specific regulatory source or other official guidance, standard or framework can be identified, yet where the guidance point is very important to ensure proper management of records for the

authorized retention period. This is particularly the case in defining certain records management guidance for operational systems and for the transfer of records from an operational to a recordkeeping system. Good practice guidance is derived from various records management studies and reports and from knowledge and experience derived in the process of applying good records management practices in commercial and public entities.

This guidance applies whether the PKI operational system and recordkeeping system are controlled internally by an agency, by a contractor or some mix of the two.

This guidance takes into account the stipulation to avoid "undue or excessive recordkeeping requirements" as mandated by the Paperwork Reduction Act and the CARAT Guidelines. In other words, this guidance is kept to a minimum with the goal of achieving good records management while allowing federal agencies as well as PKI operational system vendors and recordkeeping system vendors to implement the guidance without undue cost.

While intended to be comprehensive, this guidance may not have identified all example PKI-unique functions, activities and example records, nor have defined every element of guidance that will be required in every agency PKI implementation. It is the responsibility of each agency to ensure that they are retaining the appropriate PKI-unique administrative records and are employing all necessary records management guidance required to meet their regulatory, legal and business needs. Once again, if you require assistance in applying this guidance, contact your agency's NARA Appraisal Archivist in the Life Cycle Management Division.

5.1 Guidance for Operational Systems

The guidance in this section is organized into thirteen separate categories that encompass the PKI-unique activities identified in the operations and audit components of Table 1. PKI Functions/Activities Differentiated As Either PKI-Unique or Supporting.

A key operational systems requirement is to determine whether and when PKI-unique administrative records will be transferred from an operational system environment to a recordkeeping system environment. If this is not immediately the case, at the very least the operational system must ensure the integrity and authenticity of the information it produces which is eventually to be transferred to a recordkeeping system. As the operational system begins to provide some or all of the functions of an recordkeeping system it will need to implement the same guidance articulated here that applies to a stand-alone recordkeeping system. Neither the FBCA X.509 CP nor 36 CFR specifically address this point because in most instances the transfer may depend upon the operational status of the records or the length of the retention period. NARA regulations refer to "current" and "non-current records." The latter includes records that are no longer required for current agency business. ¹⁰ From the perspective

 ^{9 &}quot;CARAT Guidelines, Guidelines for Constructing Policies Governing the Use of Identity-Based Public Key Certificates," (National Automated Clearing House Association – NACHA, January 14, 2000): p. 113.
 10 NARA regulations do not specifically define when current (active) records become non-current (inactive) records because this is largely seen as a records disposition issue that is determined by the business needs and legal

of PKI-unique records, one instance of non-current records would be expired digital certificates. Nonetheless, this section assumes that, at some point in time during the authorized retention period, many PKI-unique administrative records will be transferred from an operational system environment to a recordkeeping system environment.

requirements of each agency. The notion of current v. non-current records is rooted in the management of paper records where, after some elapse of time, records that were infrequently accessed could be moved from costly office space to less costly storage areas. There is a parallel with electronic records stored in an operational system where, after a period of time when the records are no longer frequently accessed or when they expire (such as an expired digital certificate), they could be moved to a recordkeeping system for longer term management and access.

5.1 Guidance for Operational Systems Guidance Source 1. Records Capture 1.1 NARA "Records 1.1 Enable the capture, automatically where possible, of Management accurate and complete records at or near the time of an Guidance for Agencies administrative event (e.g., issuance of a digital certificate, **Implementing** Electronic Signature certificate renewal, certificate revocation, etc.) Technologies" 1.2 Support automatic tracking of all activities relating to the 1.2 FBCA X.509 CP, 4.51 capture of records in an audit trail or event log, including identification of the individual initiating the activity and the time and date of the activity 1.3 Enable the population, automatically where possible, of records series title, retention period, and vital records 1.3 DoD 5015.2¹¹ status Record Metadata¹² 2.1 DoD 5015.2¹³ 2.1 The minimum attributes to be captured for each PKIunique event (both for audit log and event data records, e.g., certificate issuance, CRL entries) to facilitate records management are: For Retrieval: - Common Name - Certificate Number - Date of Event - Distinguished Name (when available) For Retention and Business Resumption Management - Records Series Title - Records Series Retention Period - Vital records status 2.2 DoD 5015.2 2.2 Restrict changes in metadata to authorized users

¹¹ DoD 5015.2 C2.2.3.10 establishes the precedent for the concept of population of metadata elements relevant for record capture.

19

3. Records Retrieval	
3.1 Support searching and retrieving of records based upon one or more record metadata elements (e.g., common name or retention period)	3.1 DoD 5015.2
3.2 Support the presentation and interpretation (i.e., rendering) of any retrieved record (e.g., a digital certificate composed of multiple database attributes) in a usable form	3.2 DoD 5015.2
3.3 Support browsing and graphical navigation of retrieved records	3.3 Good Practice
4. Records Disposition	
4.1 Provide a means to identify the retention status of records using the Record Series and/or Retention period attributes identified in 2.1 above	4.1 Good Practice
4.2 Enable time, event, and time-event dispositions ¹⁴	4.2 DoD 5015.2
4.3 Provide a means to delete individual records based on their retention status	4.3 Good Practice
4.4 Restrict the capability of defining the record series title and retention period to authorized individuals	4.4 Good Practice
4.5 Enable changes in record series titles and retention periods by authorized individuals	4.5 Good Practice
4.6 Restrict records destruction commands and instructions to authorized users	4.6 FBCA X.509 CP, 4.6.3
4.7 Enable identification of records that have no assigned disposition (e.g., the Records Series Title or Records Retention attributes are missing or null value) including the ability to produce a list of such records	4.7 Good Practice

¹² These metadata attributes are intended to provide a means for managing retention in the operational environment, or to ensure that these critical records management attributes are available should the operational records be transferred at a later date to a recordkeeping environment.

¹³ DoD 5015.2 C2.2.3.2 establishes a precedent of specifying mandatory recordkeeping metadata elements.

¹⁴ Time disposition occurs when records are immediately available for disposition after the conclusion of a fixed period of time. Event disposition is when records are eligible for disposition immediately after the conclusion of an event (e.g., destroy when superseded). Time-event disposition occurs when a retention period is triggered by an event (e.g. transfer digital certificates to a recordkeeping system 60 days after expiration of the certificate).

nal -- 20

5.	Records Integrity	
	5.1 Prevent unauthorized access to records	5.1 36 CFR 1234.28
	5.2 Prevent any changes to stored records – protect the record for as long as it resides in the system	5.2 DoD 5015.2
	5.3 Ensure that an auditable entry is captured for all events associated with extending the usability of records over time through media renewal or migration	5.3 Good Practice
	5.4 Prevent modification to or deletion of event log entries	5.4 FBCA X.509 CP, 4.5.4
	5.5 Maintain at least one up-to-date copy of all records and associated metadata off site in the event one or more records is corrupted or otherwise becomes unreadable	5.5 36 CFR 1234.28
6.	Records Storage (Operational)	
	6.1 Prevent unauthorized physical access to records	6.1 36 CFR 1234.28
	6.2 Support the backup of records with a frequency that assures complete recovery	6.2 FBCA X.509 CP, 4.6.2
	6.3 Maintain duplicate or back-up copies of records in geographically separate repositories from the record copy	6.3 36 CFR 1234.30
	6.4 Use external labels with removable storage media to provide unique identification for the records, including date of creation	6.4 36 CFR 1234.30
	6.5 Store records in a stable environment where the temperature and relative humidity are maintained at	6.5 36 CFR 1234.30
	62° to 68° Fahrenheit and 35% to 45% Relative Humidity	6.6 36 CFR 1234.30
	6.6 Implement a comprehensive disaster recovery plan	
7.	Vital Records	
	7.1 Identify records that are essential to resumption of business if there is a natural disaster or system failure (see recommendation for including a Vital Record attribute in 2.1 above)	7.1 36 C FR 1236.22
	7.2 Ensure that vital records can be quickly and fully recovered	7.2 36 CFR 1236.24

Records Management Guidance for PKI-Unique Administrative Records

7.3 Support the authorized destruction of vital records	7.3 36 CFR 1236.28
8. Records Audit Trail	
8.1 Ensure that all actions related to records retention and disposition are recorded as auditable events	8.1 Good Practice
8.2 For each records retention or disposition event, capture the following attributes as an auditable event log record:	8.2 FBCA X.509 CP, 4.5.1
Common Name	
Distinguished Name (when available)	
Certificate Serial Number	
A success or failure indicator	
Type of actionable event	
 Identity or entity or operator that caused the event 	
Date and time	8.3 Good Practice
8.3 Support the transfer of event log records to a recordkeeping system	
9. Records Privacy ¹⁵	
9.1 Physical and electronic security methods must protect against unauthorized access to records and associated metadata that are covered by [or subject to] the Privacy Act	9.1 GSA ACES CP, 2.8
9.2 Protect the privacy of records collected during identity proofing and applicant registration	9.2 GSA ACES CP, 2.8
9.3 Support authorized revision or correction of any subscriber record or metadata information that is not correct	9.3 GSA ACES CP, 2.8
9.4 Ensure that subscriber records are used only for the purposes for which they were collected	9.4 GSA ACES CP, 2.8

¹⁵ GSA ACES CP, Section 2.8 states: "The Authorized CA shall protect the confidentiality of personal information regarding Subscribers that is collected during the applicant registration, ACES Certification application, authentication, and certificate status checking processes in accordance with the Privacy Act of 1974, and Appendix

22

10 D 1 C 2	
10. Records Security	
10.1 Protect records from unauthorized physical and electronic access	10.1 FBCA X.509 CP, 4.6.3 10.2 FBCA X.509 CP, 5.1.2
10.2 Maintain controlled access to the repository where records are physically stored	10.3 FBCA X.509 CP, 5.1.2 10.4 Good Practice
10.3 Maintain a physical access log that is inspected periodically	10.4 Good Fractice
10.4 Support the use of techniques to detect unauthorized changes in records	
11. Record Freezes/Holds	
11.1 Check records against existing hold or freeze orders prior to authorized destruction of records to ensure that they are not inadvertently deleted	11.1 36 CFR 1228.54
11.2 Optionally, extract records that have been identified as part of a hold or freeze order from the operational system and move to a recordkeeping system for management during the hold or freeze period	11.2 36 CFR 1228.54
11.3 Ensure that only authorized users may implement the guidance identified in 11.1 and 11.2 above	11.3 Good Practice
12. Records Transfer to a Recordkeeping System	
 12.1 Support transfer of records and associated metadata to an electronic recordkeeping system on fulfillment of specified criteria, that may include: Cut-off date for non-current or non-active records such as the end of a quarter, the calendar year, fiscal year, or other defined cycle 	12.1 Good Practice
 Elapsed time since the occurrence of a specified event such as the expiration of a digital certificate 	
 Cut-off based upon the database supporting the 	

(I and) III to OMB Circular A-130." The Department of Justice is the designated lead agency in the interpretation of Privacy Act requirements.

Records Management Guidance for PKI-Unique Administrative Records

12.3	PKI reaching a certain percentage of total storage capacity Generate an auditable event that documents the date of transfer of records to the recordkeeping system Confirm the integrity of transferred records by verifying that no record was altered during their transfer to a recordkeeping system All of the documentation and metadata (including the record series title, retention period, and vital records status) associated with the transferred records must be transferred to the recordkeeping system.	12.2 Good Practice12.3 Good Practice12.4 Good Practice
	Term Retention (Operational System)	
13.1	Ensure that records can be retrieved, viewed, reproduced, and processed during the authorized retention period	13.1 36 CFR 1234.30
13.2	Adopt a storage medium that has both a life expectancy of at least 20 years and multi-vendor support	13.2 Good Practice
13.3	Migrate records from old storage media to new storage media every ten years	13.3 36 CFR 1234.30
13.4	Transfer records to an electronic recordkeeping system as appropriate (see 12.1)	13.4 36 CFR 1234.24 (c) ¹⁶
13.5	Validate the integrity of electronic records after every preservation activity by confirming that no record has been changed	13.5 Good Practice
13.6	Maintain a preservation history file that documents all actions taken to preserve records	13.6 Good Practice

 $^{^{16}}$ This guidance is based upon the precedent of 36 CFR 1234.24 for transferring scheduled e-mail messages from an operational e-mail system to recordkeeping system.

5.2 Guidance for Recordkeeping Systems

This guidance is organized into eleven separate categories that encompass the PKI-unique activities identified in the example functions and activities identified in Table 1. PKI Functions/Activities Differentiated As Either PKI-Unique or Supporting.

The guidance for recordkeeping systems provides for the situation whereby records being managed in an operational system that are no longer considered current or active, or for other valid purposes, will be transferred to a recordkeeping system in order to ensure that records are preserved as evidence in a trustworthy and usable manner for the authorized retention period. The recordkeeping system guidance also applies to records that are not created or received by a PKI operational system, such as paper records and electronic records that are created on office productivity applications or are scanned images of paper documents.

This recordkeeping guidance applies to all PKI-unique administrative records independent of the media on which they are stored.

An example of a recordkeeping system is a Records Management Application that has been certified under DoD 5015.2.

5.2	5.2 Guidance for Recordkeeping Systems			
Gı	uidance	Source		
1.	Records Capture			
	1.1 Receive records from an operational system according to the following guidance:	1.1 CFR 1234.22, 1234.24 ¹⁷ ; NARA "Records		
	For records received where the origination source is database tables or proprietary or raw data formats:	Management Guidance for Agencies Implementing Electronic Signature		
	- Transfer sufficient metadata to support retrieval and retention management	Technologies"		
	 Preferably be in or be converted to a technology neutral format (e.g. XML, RTF) 			
	 If not in a technology neutral format, then operational system software in which the tables resided during the retention period to enable 			

¹⁷ This guidance is based upon the precedent of 36 CFR 1234.24 for transferring scheduled e-mail messages from an operational e-mail system to a recordkeeping system.

5.2 Guidance for Recordkeeping Systems Guidance Source restoration and rendering for reproduction must also be retained For records received in "as-rendered-for-viewing" format: - Be in a technology neutral format (e.g. XML, RTF) - Provide metadata sufficient to support retrieval and retention management in the form of a file that can be automatically loaded or manually entered into the recordkeeping system 1.2 Good Practice 1.2 Accept import of PKI-unique record file copy in technology neutral formats (e.g., XML, RTF) from office productivity systems 1.3 36 CFR 1234.22¹⁸ 1.3 Support management of records in paper format, e.g., a CP or CPS that contains handwritten signatures 1.4 Good Practice 1.4 Maintain an event log that documents the date of 1.5 Good Practice transfer from an operational system to a recordkeeeping system 1.5 Confirm integrity of records by verifying that no 1.6 36 CFR 1234.32¹⁹ changes have occurred in records received from an operational system 1.6 Ensure that all of the metadata, supporting event log data, and information associated with a record are completely and accurately transferred 2. Records Metadata 2.1 Transfer the minimum attributes specified in the 2.1 Good Practice guidance for Operational Systems to the recordkeeping system 2.2 Good Practice

2.2 For electronic records created in an office productivity

¹⁸ Citation of 36 CFR 1234.22 is based on its providing guidance for creating and managing text documents in an electronic recordkeeping system.

¹⁹ Citation of 36 CFR 1234.32 is based on its providing guidance for the retention and disposition of electronic records.

5.2 Guidance for Recordkeeping Systems Guidance Source system or for paper records or scanned images of paper records, metadata should be captured that is consistent with the minimum requirements stated in Section 5.1.2 Metadata. This is required in order to be able to retrieve all records related to a subscriber (e.g., using common name) or to an auditable event. Metadata in addition to the operational metadata may be required such as for a CP or CPS that cannot be identified with a common name or certificate number. Identification using PKIunique attributes, such as the associated ObjectID of the record, may be required. 2 3 DoD 5015 2 2.3 Support the capability to view and print complete record metadata or user-specified portions of the metadata 2.4 DoD 5015.2 2.4 Support assignment of a unique computer-generated record identifier for each record (electronic or paper) 2.5 Good Practice regardless of where the record is stored 2.5 Support identification of record location in terms of the 2.6 DoD 5015.2 hard copy file or electronic location (system, path, and media) 2.7 Good Practice 2.6 Support generation of a human readable and computer readable label to be attached to all paper records 2.7 Restrict changes to records, files, sub-series, and series to authorized individuals 3. Records Classification 3.1 Support a classification scheme that can represent 3.1 DoD. 5015.2 records, files, sub-series, and series organized in a hierarchy with a minimum of four levels. 3.2 36 CFR 1234.24²⁰ 3.2 Logically aggregate individual records into files (folders) 3.3 36 CFR 1234.24 3.3 Logically aggregate files into records sub-series 3.4 36 CFR 1234.24 3.4 Logically aggregate records sub-series into records 3.5 Good Practice series

²⁰ Citation of 36 CFR 1234.24 is based on its providing standards for the management of email records.

27

5.2	2 Gu	idance for Recordkeeping Systems	
Gı	ıidaı	ıce	Source
	3.5	Support browsing and graphical navigation of the files and classification scheme structure; and the selection, retrieval and display of electronic records and their contents through this mechanism.	3.6 Good Practice
	3.6	Maintain an audit trail of any records, files, sub-series, and series that are reclassified so that their entire history can be reconstructed	
4.	Reco	ords Retrieval	
	4.1	Support retrieval and viewing or reproduction of records based upon one or more metadata attributes (e.g. common name, date-range, records series, etc)	4.1 DoD 5015.2
	4.2	Support retrieval, and rendering of a specific PKI- unique record (e.g., digital certificate or multiple digital certificates	4.2 Good Practice 4.3 36 CFR 1234.24
	4.3	Support the rendering of any retrieved record (e.g., a digital certificate) in a form that is usable by humans	4.4 Good Practice
	4.4	Restrict retrieval of records based upon user access permissions	4.5 DoD 5015.2
	4.5	Support browsing and graphical navigation of retrieved records	
5.	Reco	ords Disposition	
	5.1	Restrict the capability for defining retention periods, disposition actions, and the changing of retention periods to authorized individuals	5.1 DoD 5015.2
	5.2	Enable time, event, and time-event disposition	5.2 DoD 5015.2
	5.3	Enable automatic calculation of destruction date where appropriate	5.3 DoD 5015.2
	5.4	Support authorized changes in the disposition of records, files, records sub-series, and records series	5.4 DoD 5015.2
	5.5	Support authorized individuals to enter data indicating	5.5 DoD 5015.2

5.2 Guidance for Recordkeeping Systems Guidance Source when a specified event or time-event has occurred that affects the authorized retention of records 5.6 Good Practice 5.6 Support authorized individuals to view the disposition attributes for each record, file, record sub-series, or records series 5.7 DoD 5015.2 5.7 Support the identification and rendering of records, including associated metadata, that are eligible for destruction 5.8 DoD 5015.2 5.8 Support the requirement for a second confirmation from an authorized user before deleting records 5.9 DoD 5015.2 5.9 Produce documentation related to all authorized record destruction 6. Records Integrity 6.1 Prevent unauthorized access to records 6.1 36 CFR 1234.28 6.2 Prevent any changes to stored records – protect the 6.2 DoD 5015.2 record for as long as it resides in the system 6.3 Prevent modification or deletion to records history log 6.3 FBCA X.509 CP 4.5.4 entries 6.4 Maintain a second up-to-date copy of all records and 6.4 36 CFR 1234.30 associated metadata, including history log entries, off site for records recovery 7. Records History Log 7.1 Good Practice 7.1 Ensure that all activities taken to ensure the continued usability of records through media renewal or migration to a new technology platform are fully documented in a records history log

5.2 Guidance for Recordkeeping Systems Guidance Source 8. Records Privacy²¹ 8.1 Physical and electronic security methods must protect 8.1 GSA ACES CP, 2.8 against unauthorized access to records and associated metadata that are covered by [or subject to] the Privacy Act 8.2 Protect the privacy of records collected during identity 8.2 GSA ACES CP, 2.8 proofing and applicant registration 8.3 Support authorized revision or correction of any 8.3 GSA ACES CP, 2.8 subscriber record or metadata information that is not correct 8.4 Ensure that subscriber records are used only for the 8.4 GSA ACES CP, 2.8 purposes for which they were collected 9. Records Security 9.1 36 CFR 1234.28 9.1 Protect records from unauthorized deletion 9.2 FBCA X.509 CP, 5.1.2 9.2 Maintain controlled access to the repository where records are stored 9.3 Maintain an access log that is inspected periodically 9.3 FBCA X.509 CP, 5.1.2 9.4 Block external access to electronic records through an 9.4 Good Practice electronic "firewall" 9.5 Use techniques to detect attempted or unauthorized 9.5 Good Practice changes or modifications to electronic records 9.6 36 CFR 1234.30 9.6 Store duplicate or back-up copies of records in a geographically separate archives or recordkeeping storage facility 9.7 Implement a comprehensive disaster recovery plan 39.7 6 CFR 1236.26 10. Record Freezes/Holds 10.1 Provide the capability for authorized individuals to 10.1 36 CFR 1228.54 identify records that are subject to a "hold" or "freeze" order 10.2 Provide the capability to extend or suspend 10.2 36 CFR 1228.54

²¹ See footnote 15

5.2	Guid	lance for Recordkeeping Systems	
Gu	idano	ee	Source
		(freeze/hold) the retention period of records beyond their scheduled disposition	
	10.3	Provide the capability for authorized individuals to "unfreeze" records	10.3 36 CFR 1228.54
11.	Reco	rds Preservation	
	11.1	Support the capability to ensure the usability and trustworthiness of records throughout their authorized retention through migration to new software recordkeeping system applications, new storage media, or new vendor technology neutral formats	11.1 FBCA X.509 CP 4.62
		OR	
	11.2	Where achieving the guidance in 11.1 is not possible, then retain PKI software and hardware necessary to read, search, retrieve, and render records	11.2 DoD 5015.2
	11.3	Prevent unauthorized physical/electronic access to the facility where the records are stored	11.3 36 CFR 1234.28
	11.4	Adopt a storage medium that has a predicted life expectancy of at least 20 years and has multi-vendor support	11.4 Good Practice
	11.5	Renew storage media through copying (exact duplication of the bit stream) or reformatting records from old storage media to new storage media (e.g., 3480 tape to 3490 tape) every ten years	11.5 36 CFR 1234.30
	11.6	Confirm after each media renewal activity (e.g., copy) that no record has changed	11.6 Good Practice
	11.7	Migrate records to a technology neutral file format (e.g., XML, RTF) that has substantial vendor support	11.7 Good Practice
	11.8	Store records in a stable environment where the temperature and humidity are maintained at 62° to 68° Fahrenheit and 35% to 45% Relative Humidity	11.8 36 CFR 1234.30
	11.9	Annually inspect a statistical sample of records in the	

31

5.2 Guidance for Recordkeeping Systems	
Guidance	Source
storage facility to confirm that no catastrophic loss has occurred or may be impending 11.10 Create and maintain a preservation history log that documents all actions taken to extend the usability of storage media	36 CFR 1234.30 11.10 Good Practice

Appendix A. Glossary, Acronyms and Abbreviations

Definitions

These definitions are derived from a variety of sources, including the NARA GPEA guidance, DoD 5015.2, X.509 PKIX, X.509 Certificate Policy for the Federal Bridge Certification Authority (FBCA), and glossaries in several books relating to PKI and digital signatures.

As-rendered-for-viewing record. A Logical PKI Record (see definition) that has been rendered in a human-readable, reproducible format, and then saved in that format as the record file copy. For example, a single event, such as a certificate revocation, would be rendered as viewable and usable by inserting the appropriate data elements into a database form or template, then reproducing that representation in a format that could be preserved as the record file copy (such as on paper or in XML format)

Archives. A physical or logical space independent of a production environment where records are protected from loss, alteration, and deterioration so that they may be used as trustworthy evidence for as far into the future as is necessary.

Certification Authority. A trusted organization that can accept certificate applications from subscribers, issues digital certificates, and either maintains status information about certificates or arranges for a trust third party to perform these services. Note: in some cases, a CA may be defined in a more narrow sense, such as "The CA is collection of computer hardware, software and the people who operate it" (Housley and Polk, p44).

Certificate Policy. A written document that identifies the applicability of a class of certificates with common security requirements and sets forth the requirements that are appropriate for applications or uses. PKIX has created an outline and guidance for the content of certificate policy documents.

Certification Practice Statement. A written document that articulates the practices that a Certification Authority employs in issuing, managing, revoking, and renewing certificates. PKIX has created an outline and guidance for the content of certificate practice statements.

Certificate Revocation List. This is a Certificate Authority's listing of unexpired certificates that cannot be trusted, i.e., revoked certificates.

Classification. The systematic identification and arrangement of business activities and/or *records* into categories according to logically structured conventions, methods, and procedural rules represented in a classification scheme that meets the specific business needs of the agency. A PKI classification scheme could be designed that defines records, record files or folders,

records sub-series, and records series for each of the primary PKI administrative functions.

Common Name. The given name of an individual or organization that corresponds to its real world identity.

Content. The information that a record is meant to convey that may consist of words, phrases, numbers, symbols, and so on.

Context. The organizational, functional, and operational circumstances in which documents are created and/or received and used. The placement of records within a larger records classification system providing cross-references to other related records.

Current Records. Records that are necessary to conduct the current business of an office and therefore are readily available for consultation and reference.

Cut off. Breaking, or ending, files at regular intervals, usually at the close of a fiscal or calendar year, to permit their disposal or transfer in complete blocks or segments.

Disposition. Actions taken regarding records after they are no longer required to conduct current Agency business. (See Non-current record)

Distinguished Name. A unique name or character string for each individual in a CA directory that unambiguously identifies each subscriber.

Emergency Operating Records. (See Vital Records)

Event Disposition. A disposition instruction in which a record is eligible for the specified disposition (transfer or destroy) upon or immediately after the specified event occurs. No retention is applied and there is no fixed waiting period as with the "timed" or combination "time-event" dispositions. An example of event disposition would be "Destroy when no longer needed for current operations".

Freeze. The suspension or extension of the disposition of temporary records that cannot be destroyed on schedule because of special circumstances, such as a court order or an investigation, that requires a temporary extension of the approved retention period.

Good Practice. Good practice indicates that no specific regulatory or other official standard or framework can be cited, yet where the guidance point is very important to ensure proper management of records for the authorized retention period. The good practice guidance cited in this document is derived from various records management studies and reports and from knowledge and experience derived from the application of records management practices in commercial and public entities.

Individual Subscriber. A subscriber is an individual who has generated a private/public key pair and has been issued a digital certificate after being appropriately identified and authenticated as part of a registration process.

Integrity. The integrity of a record refers to its being complete and unaltered over time.

Legal and Financial Rights Records. (see Vital Records)

Logical PKI Record. A logical PKI record consists of data content stored in relational database tables or other proprietary or raw data format that exists as a physical record only at the time of rendering for viewing, printing, or saving. If the rendered physical record is not printed or saved then it ceases to exist as a physical entity. If the data content has not changed then a specific logical record can be retrieved and accurately rendered innumerable times. As an example, the data representing the content of a digital certificate may exist in two or more database tables but the digital certificate exists as a physical entity only at the time that the data content is retrieved and used to populate a digital certificate template. This digital certificate may then be printed or saved as a physical entity.

Metadata. Data describing stored data, that is, data describing the structure, content, and context, and other characteristics of electronic records. Record profile data.

Non-current Record. Records that are no longer required to conduct agency business and therefore are ready for final disposition. (See also Current Record)

Object ID. A unique identifier for a Certificate Policy that is registered with the American National Standards Institute so that a certificate issuer and a certificate users (subscriber) can both recognize and reference the policy.

Office Productivity. Applications. Software packages that perform a variety of office support functions, such as word processing, desktop publishing, spreadsheet calculations, electronic mail, facsimile transmission and receipt, document imaging, optical character recognition (OCR), work flow, and data management. These applications are generally those used to generate, convert, transmit, or receive business documents.

Operational System. The software and hardware system that performs the day-to-day activities of running and maintaining a PKI, such as a CA. In an operational system, the active content (such as public key certificate data elements) and event information (audit log) typically are stored in relational database tables. Since this content or event data may be the official and possibly the only source of this information for a period of time, the operational system can be said to contain the "record file copy" of that information. While the data may be backed up for disaster recovery purposes, operational systems typically do not provide the functionality that is necessary to effectively manage records disposition nor other traditional records management functions.

PKI Administrative Record. PKI records that are created, used, maintained, and preserved to support on-going management and operation. They do not include subscriber transactions where a public key has been used for signing or for another purpose.

PKI Event. Any administrative transaction conducted as part of a PKI, such as: the issuance of a digital certificate, certificate renewal, certificate revocation, etc.

PKI Transaction Record. A record that is created by the actual use of a public key pair to digitally sign an electronic document or consummate an electronic commerce transaction. This PKI-unique administrative records management guidance does not cover PKI transaction records.

Record File Copy. A "record file copy" is the final or "official" copy that is retained according to a NARA-authorized retention schedule.

Recordkeeping System. A manual or automated system in which records are collected, organized, and categorized to facilitate their preservation, retrieval, use, and disposition for the authorized retention period.

Records Schedule. A document that provides mandatory instructions for what to do with records (and nonrecord materials) no longer needed for current Government business.

Record Series. File units or documents arranged in accordance with a filing system or maintained as a unit because they result from the same accumulation or filing process, the same function, or the same activity; have a particular form; or because of some other relationship arising out of their creation, receipt, or use.

Registration Authority. An entity that is responsible for identification and authentication of certificate subjects prior to the issuance of certificates, but which does not sign or issue certificates (i.e., a Registration Authority is delegated certain tasks on behalf of an authorized CA).

Retention Period. The length of time that records must be kept before they are destroyed. Records not authorized for destruction have a retention period of "permanent." A retention period is sometimes referred to as "Authorized Retention" because NARA has approved the disposition of the records.

Structure. The physical and logical format of a record and the relationships between the data elements

Technology Neutral Format. An openly published file format that supports data interchange and interoperability across heterogeneous product lines, media, devices, and systems.

Time Disposition. A disposition instruction that specifies when a record shall be cut off and when the fixed retention period is applied. The retention period does not begin until after the records have been cut off. Example: "Destroy after two years – cut off at the end of the calendar (or fiscal) year; hold for two years; then destroy".

Time-Event Disposition. A disposition instruction that specifies that a record shall be disposed of a fixed period of time after a predictable or specified event. Once the specified event has occurred, then the retention period is applied. Example: "Destroy three years after close of case".

Vital Records. Essential records that are needed to meet operational responsibilities under national security emergencies or other emergency or disaster conditions (emergency operating records) or to protect the legal and financial rights of the Government and those affected by Government activities (legal and financial rights records). Emergency operating records are the type of vital records essential to the continued functioning or reconstitution of an organization during and after an emergency (a vital record may be both an emergency operating record and a financial rights record).

Acronyms and Abbreviations

ACES. Access Certificates for Electronic Services (General Services Administration)

CA. Certification Authority

CARAT. Internet Council Certification Authority Rating and Trust (CARAT) Task Force

CFR. Code of Federal Regulations

CMM. Capability Maturity Model

CP. Certificate Policy

CPS. Certification Practice Statement

CRL. Certificate Revocation List

ERM. Electronic Records Management

FPKISC. Federal Public Key Infrastructure Steering Committee

FBCA. Federal Bridge Certification Authority

Final -- 37

Records Management Guidance for PKI-Unique Administrative Records

LPWG. Legal and Policy Working Group of the Federal Public Key Infrastructure Steering Committee

OID. Object Identifier

PAG. PKI Assessment Guidelines (American Bar Association)

PKIX. Public Key Infrastructure (X.509) (Internet Engineering Task Force Working Group)

RA. Registration Authority

Final – Records Management Guidance for PKI-Unique Administrative Records

Appendix B. Example PKI-unique Administrative Records Series

EXAMPLE ACTIVITIES 1.1 Determine that a PKI is to be established and create a project implementation plan	IQUE EXAMPLE PKI-UNIQUE RECORDS BY ACTIVITY
TTIES a PKI is to be established and create a project	UE AMPLE PKI-UNIQUE RECORDS BY ACTIVITY
TTIES a PKI is to be established and create a project	AMPLE PKI-UNIQUE RECORDS BY ACTIVITY
a PKI is to be established and create a project	
	1.1 Authorizing documentation and project implementation plan
1.2 Designate the entity to serve as Certification Authority (CA) 1.2 Decision available CAs	1.2 Decision approval records, selection criteria, assessment of available CAs
1.3 Create Certificate Policy (CP), Certification Practice 1.3 Approv Statement(CPS), and other key operating documents Statement, a	1.3 Approval of Certificate policy and Certification Practice Statement, and key operating documents
1.4 Develop operating procedures in accordance with Certificate 1.4 Operation Policy and Certificate Practice Statement	1.4 Operating procedures manual
1.5 Conduct a risk cost analysis as required by GPEA and OMB 1.5 Risk and Implementation Guidelines	1.5 Risk analysis studies, recommendations, guidelines, implementation procedures
1.6 Develop records management policy, including migration 1.6 Record strategy for records retained for a long time to be implen	1.6 Records management policy, plans, and migration strategies to be implemented
1.7 Select the entity to serve as Registration Authority (RA) 1.7 Decision existing RAs	1.7 Decision approval records, selection criteria, assessment of existing RAs
PKI-SUPPORTING	TING
EXAMPLE ACTIVITIES EXAMPLE	EXAMPLE PKI-SUPPORTING RECORDS BY ACTIVITY

Final – Records Management Guidance for PKI-Unique Administrative Records

d checks	
, backgroun	
equirements.	
s, training re	
scriptions	
8 Job de	
ıts	
personnel requirement	
1.8 Establish p	

Series 2: Launch/Install A Public Key Infrastructure	cture
PKI-UNIQUE	IQUE
EXAMPLE ACTIVITIES	EXAMPLE PKI-UNIQUE RECORDS BY ACTIVITY
2.1 Install and validate Certification Authority hardware and software	2.1 Installation records, testing procedures
2.2 Install and validate Registration Authority hardware and software	2.2 Installation Record, testing procedures
2.3 Obtain final approval from oversight or authorizing body	2.3 Approval/rejection documents
2.4 Create CA signature key	2.4 Signature key creation record and signature key use/ validity requirements
PKI-SUPPORTING	ORTING
EXAMPLE ACTIVITIES	EXAMPLE PKI-SUPPORTING RECORDS BY ACTIVITY
2.5 Test security procedures	2.5 Test results and sample certificates
2.6 Validate certification revocation procedure	2.6 Procedures to follow in revoking certificates and maintenance of a certification revocation list
2.7 Establish backup and storage	2.7 Overall storage policies and practices, including backup procedures and data restoration

Final – Records Management Guidance for PKI-Unique Administrative Records

Series 3: Operate a Public Key Infrastructure	
PKI-U	PKI-UNIQUE
EXAMPLE ACTIVITIES	EXAMPLE PKI-UNIQUE RECORDS BY ACTIVITY
3.1 Certification Application	3.1 Verification of identity, identity documentation
3.2 Certificate Issuance and Key Generation	
	NCY.
3.3 Certificate Acceptance	3.3 Subscriber acknowledgement of acceptance of conditions of use of the certificate, including subscriber obligations
3.4 Certificate Validation	3.4 Identity of requester, identity of certificate, verification or denial, Online Certificate Status Protocol, reason for denial, time/date stamp
3.5 Certificate Revocation	3.5 Confirmation that conditions that merit revocation have been met, Certificate Revocation List, update frequency, individual performing update
3.6 Certificate Suspension	3.6 Confirmation that conditions that merit certificate suspension have been met. Reasons for the suspension, individual performing update
3.7 Certificate Replacement	3.7 Confirmation that conditions which merit certificate replacement have been met and subscriber acknowledgement of receipt of certificate replacement
3.8 Certificate Renewal	3.8 Confirmation that the subscriber has met the CP/CPS conditions for renewal as well as subscriber authorization to

¹ This process may include the generation of an encryption key by the CA which is escrowed. This escrowed key may be maintained as an administrative record as part of the key history file.

Final – Records Management Guidance for PKI-Unique Administrative Records

	renew a certificate that has not been revoked, suspended, or
	expired
3.9 Create and maintain an event log	3.9 Auditable events specified in FBCA X.509 Certificate Policy

Final – Records Management Guidance for PKI-Unique Administrative Records

Series 3: Operate a Public Key Infrastructure	
PKI-SUP	PKI-SUPPORTING
EXAMPLE ACTIVITIES	EXAMPLE PKI-SUPPORTING RECORDS BY ACTIVITY
3.10 Hire and train personnel	3.10 Job applications, training records, background checks
3.11 Install and validate software updates	3.11 Decision documents, installation and test records
3.12 Notify users of new software	3.12 Notification to affected users, contingency plan if new
	software does not replicate the functionality of old software

EXAMPLE ACTIVITIESEXAMPLE ACTIVITIESEXAMPLE PKI-UNIQUE RECORDS BY ACTIVITIES4.1.1 Periodic internal review of auditable events specified in X.509 ACES Policy4.1.1 Audit report, reports on compliance/non-compliance/non-compliance with security requirements specified in X.5094.1.2 Audit report, reports on compliance/non-compliance/non-compliance with security requirements specified in X.5094.1.2 External review of auditable events specified in X.5094.1.2 Audit report, reports on compliance/non-compliance/non-compliance with security requirements specified in 4.1.3 Reports on compliance audits, remedial actions4.1.3 Monitor compliance with security requirements specified in X.5094.1.3 Reports on compliance audits, remedial actions4.1.1 Monitor compliance with security requirements specified in X.5094.1.3 Reports on compliance audits, remedial actions4.1.2 Investigate internal fraud or misconductEXAMPLE PKI-SUPPORTING RECORDS BY ARAMPLE ACTIVITIES4.2.1 Investigate internal fraud or misconduct4.2.1 Investigation reports, disciplinary actions, remedial actions, remedial actions	Series 4: Audit and Monitor a Public Key Infrastructure	tructure
onduct	PKI-UN	IIQUE
onduct	EXAMPLE ACTIVITIES	EXAMPLE PKI-UNIQUE RECORDS BY ACTIVITY
ts specified in X.509 requirements specified in PKI-SUPP onduct	4.1.1 Periodic internal review of auditable events specified in X.509 ACES Policy	4.1.1 Audit report, reports on compliance/non-compliance, remedial actions
requirements specified in PKI-SUPP onduct	4.1.2 External review of auditable events specified in X.509 ACES Policy	4.1.2 Audit report, reports on compliance/non-compliance, remedial actions
PKI-SUPP	4.1.3 Monitor compliance with security requirements specified in the CPS and other operating procedures	4.1.3 Reports on compliance audits, remedial actions
	PKI-SUPP	ORTING
	EXAMPLE ACTIVITIES	EXAMPLE PKI-SUPPORTING RECORDS BY ACTIVITY
taken	4.2.1 Investigate internal fraud or misconduct	4.2.1 Investigation reports, disciplinary actions, remedial actions taken

Final – Records Management Guidance for PKI-Unique Administrative Records

4.2.2	Internal audit of software and systems security	4.2.2 Audit report, reports on compliance with recommendations
		in audit report
4.2.3	External audit of software and system security	4.2.3 Audit reports based upon PAG guidance, reports on
		compliance with recommendations in audit report

Series 5: Terminate/Consolidate/Reorganize A	te/Reorganize A Public Key Infrastructure
PKI-U	PKI-UNIQUE
EXAMPLE ACTIVITIES	EXAMPLE PKI-UNIQUE RECORDS BY ACTIVITY
5.1 Determine that PKI is to be terminate, consolidate, or reorganized	5.1 Studies, reports, recommendation, and action documents
5.2 Obtain approval (if required) from appropriate entities to terminate, consolidate, or reorganize	5.2 Decision documents
5.3 Notify subscribers	5.3 List of individuals/organizations to whom notice has been
	given, several examples of notices, identification of new CA, and option for subscribers to elect or reject the CA
5.4 Transfer inactive keys and revocation certificate list to	5.4 Transfer document attesting to legal custody along with
storage repository	access rights
5.5 Transfer consenting subscribers' certificates and related	5.5 Transfer notices, list of subscribers who have agreed to use
material to new Certificate Authority	the new Certificate Authority
5.6 Destroy sensitive records involving privacy	5.6 Approved disposal of records in accordance with an
	authorized records schedule
5.7 Shutdown and disposal of RA hardware and CA software	5.7 Shutdown report with signoffs from appropriate individuals