HIGHLIGHTS OF PRESCRIBING INFORMATION

These highlights do not include all the information needed to use GARDASIL safely and effectively. See full prescribing information for GARDASIL.

GARDASIL

[Human Papillomavirus Quadrivalent (Types 6, 11, 16, and 18) Vaccine. Recombinant1

Suspension for intramuscular injection

Initial U.S. Approval: 2006

------RECENT MAJOR CHANGES ------

Indications and Usage (1)
Girls and Women (1.1)

n (1.1)

12/2010

Boys and Men (1.2) 12/2010 Limitations of GARDASIL Use and Effectiveness (1.3) XX/XXXX

----INDICATIONS AND USAGE ----

GARDASIL is a vaccine indicated in girls and women 9 through 26 years of age for the prevention of the following diseases caused by Human Papillomavirus (HPV) types included in the vaccine:

- Cervical, vulvar, vaginal, and anal cancer caused by HPV types 16 and 18
- Genital warts (condyloma acuminata) caused by HPV types 6 and 11

And the following precancerous or dysplastic lesions caused by HPV types 6, 11, 16, and 18:

- Cervical intraepithelial neoplasia (CIN) grade 2/3 and Cervical adenocarcinoma in situ (AIS)
- · Cervical intraepithelial neoplasia (CIN) grade 1
- Vulvar intraepithelial neoplasia (VIN) grade 2 and grade 3
- Vaginal intraepithelial neoplasia (VaIN) grade 2 and grade 3
- Anal intraepithelial neoplasia (AIN) grades 1, 2, and 3

GARDASIL is indicated in boys and men 9 through 26 years of age for the prevention of the following diseases caused by HPV types included in the vaccine:

- Anal cancer caused by HPV types 16 and 18
- Genital warts (condyloma acuminata) caused by HPV types 6 and

And the following precancerous or dysplastic lesions caused by HPV types 6, 11, 16, and 18:

Anal intraepithelial neoplasia (AIN) grades 1, 2, and 3. (1)

Limitations of GARDASIL Use and Effectiveness:

- GARDASIL does not eliminate the necessity for women to continue to undergo recommended cervical cancer screening. (1.3) (17)
- Recipients of GARDASIL should not discontinue anal cancer screening if it has been recommended by a health care provider. (1.3) (17)
- GARDASIL has not been demonstrated to provide protection against disease from vaccine and non-vaccine HPV types to which a person has previously been exposed through sexual activity. (1.3) (14.4) (14.5)
- GARDASIL is not intended to be used for treatment of active external genital lesions; cervical, vulvar, vaginal, and anal cancers; CIN; VIN; VaIN, or AIN. (1.3)
- GARDASIL has not been demonstrated to protect against diseases due to HPV types not contained in the vaccine. (1.3) (14.4) (14.5)

- Not all vulvar, vaginal, and anal cancers are caused by HPV, and GARDASIL protects only against those vulvar, vaginal, and anal cancers caused by HPV 16 and 18. (1.3)
- GARDASIL does not protect against genital diseases not caused by HPV. (1.3)
- Vaccination with GARDASIL may not result in protection in all vaccine recipients. (1.3)
- GARDASIL has not been demonstrated to prevent HPV-related CIN 2/3 or worse in women older than 26 years of age. (14.7)

----- DOSAGE FORMS AND STRENGTHS ----

 0.5-mL suspension for injection as a single-dose vial and prefilled syringe. (3) (11)

-----CONTRAINDICATIONS -----

 Hypersensitivity, including severe allergic reactions to yeast (a vaccine component), or after a previous dose of GARDASIL. (4) (11)

------WARNINGS AND PRECAUTIONS-----

 Because vaccinees may develop syncope, sometimes resulting in falling with injury, observation for 15 minutes after administration is recommended. Syncope, sometimes associated with tonic-clonic movements and other seizure-like activity, has been reported following vaccination with GARDASIL. When syncope is associated with tonic-clonic movements, the activity is usually transient and typically responds to restoring cerebral perfusion by maintaining a supine or Trendelenburg position. (5.1)

--- ADVERSE REACTIONS---

The most common adverse reaction was headache. Common adverse reactions (frequency of at least 1.0% and greater than AAHS control or saline placebo) are fever, nausea, dizziness; and injection-site pain, swelling, erythema, pruritus, and bruising. (6.1)

To report SUSPECTED ADVERSE REACTIONS, contact Merck Sharp & Dohme Corp., a subsidiary of Merck & Co., Inc., at 1-877-888-4231 or VAERS at 1-800-822-7967 or www.vaers.hhs.gov.

-----DRUG INTERACTIONS ---

GARDASIL may be administered concomitantly with RECOMBIVAX HB (7.1) or with Menactra and Adacel. (7.2)

------USE IN SPECIFIC POPULATIONS ---

Safety and effectiveness of GARDASIL have not been established in the following populations:

- Pregnant women. Physicians are encouraged to register pregnant women exposed to GARDASIL by calling 1-800-986-8999 so that Merck Sharp & Dohme Corp., a subsidiary of Merck & Co., Inc., can monitor maternal and fetal outcomes. (8.1)
- Children below the age of 9 years. (8.4)
- Immunocompromised individuals. Response to GARDASIL may be diminished. (8.6)

See 17 for PATIENT COUNSELING INFORMATION and FDA-approved patient labeling.

Revised: XX/XXXX

FULL PRESCRIBING INFORMATION: CONTENTS*

1 INDICATIONS AND USAGE

- 1.1 Girls and Women
- 1.2 Boys and Men
- 1.3 Limitations of GARDASIL Use and Effectiveness

2 DOSAGE AND ADMINISTRATION

- 2.1 Dosage
- 2.2 Method of Administration
- 3 DOSAGE FORMS AND STRENGTHS

4 CONTRAINDICATIONS

5 WARNINGS AND PRECAUTIONS

5.1 Syncope

5.2 Managing Allergic Reactions

6 ADVERSE REACTIONS

6.1 Clinical Trials Experience

6.2 Postmarketing Experience DRUG INTERACTIONS

7.1 Use with RECOMBIVAX HB

7.2 Use with Menactra and Adacel

- 7.3 Use with Hormonal Contraceptives
- 7.4 Use with Systemic Immunosuppressive Medications

8 USE IN SPECIFIC POPULATIONS

- 8.1 Pregnancy
- 8.3 Nursing Mothers
- 8.4 Pediatric Use
- 8.5 Geriatric Use
- 8.6 Immunocompromised Individuals
- 10 OVERDOSAGE
- 11 DESCRIPTION
- 12 CLINICAL PHARMACOLOGY
 - 12.1 Mechanism of Action
- 13 NONCLINICAL TOXICOLOGY
 - 13.1 Carcinogenesis, Mutagenesis, Impairment of Fertility
- 14 CLINICAL STUDIES

1

4

5

6

7

9

10

12

15

16 17

18 19

20

21

22

23

24

25

26

27

28 29

30

31

32

33

34

- 14.1 Prophylactic Efficacy HPV Types 6, 11, 16, and 18 in Girls and Women 16 Through 26 Years of Age
- 14.2 Prophylactic Efficacy HPV Types 6, 11, 16, and 18 in Boys and Men 16 Through 26 Years of Age

- 14.3 Prophylactic Efficacy Anal Disease Caused by HPV Types 6, 11, 16, and 18 in Boys and Men 16 Through 26 Years of Age in the MSM Sub-study
- 14.4 Population Impact in Girls and Women 16 Through 26 Years of Age
- 14.5 Population Impact in Boys and Men 16 Through 26 Years of Age
- 14.6 Overall Population Impact
- 14.7 Studies in Women 27 Through 45 Years of Age
- 14.8 Immunogenicity
- 14.9 Studies with RECOMBIVAX HB [hepatitis B vaccine (recombinant)]
- 14.10 Studies with Menactra [Meningococcal (Groups A, C, Y and W-135) Polysaccharide Diphtheria Toxoid Conjugate Vaccine] and Adacel [Tetanus Toxoid, Reduced Diphtheria Toxoid and Acellular Pertussis Vaccine Adsorbed (Tdap)]
- 16 HOW SUPPLIED/STORAGE AND HANDLING
- 17 PATIENT COUNSELING INFORMATION
- *Sections or subsections omitted from the full prescribing information are not listed.

FULL PRESCRIBING INFORMATION

2 1 INDICATIONS AND USAGE

3 1.1 Girls and Women

GARDASIL®¹ is a vaccine indicated in girls and women 9 through 26 years of age for the prevention of the following diseases caused by Human Papillomavirus (HPV) types included in the vaccine:

- Cervical, vulvar, vaginal, and anal cancer caused by HPV types 16 and 18
- Genital warts (condyloma acuminata) caused by HPV types 6 and 11

8 And the following precancerous or dysplastic lesions caused by HPV types 6, 11, 16, and 18:

- Cervical intraepithelial neoplasia (CIN) grade 2/3 and Cervical adenocarcinoma in situ (AIS)
- Cervical intraepithelial neoplasia (CIN) grade 1
- Vulvar intraepithelial neoplasia (VIN) grade 2 and grade 3
 - Vaginal intraepithelial neoplasia (VaIN) grade 2 and grade 3
- Anal intraepithelial neoplasia (AIN) grades 1, 2, and 3

14 1.2 Boys and Men

GARDASIL is indicated in boys and men 9 through 26 years of age for the prevention of the following diseases caused by HPV types included in the vaccine:

- Anal cancer caused by HPV types 16 and 18
- Genital warts (condyloma acuminata) caused by HPV types 6 and 11
- And the following precancerous or dysplastic lesions caused by HPV types 6, 11, 16, and 18:
 - Anal intraepithelial neoplasia (AIN) grades 1, 2, and 3

1.3 Limitations of GARDASIL Use and Effectiveness

The health care provider should inform the patient, parent, or guardian that vaccination does not eliminate the necessity for women to continue to undergo recommended cervical cancer screening. Women who receive GARDASIL should continue to undergo cervical cancer screening per standard of care. [See Patient Counseling Information (17).]

Recipients of GARDASIL should not discontinue anal cancer screening if it has been recommended by a health care provider. [See Patient Counseling Information (17).]

GARDASIL has not been demonstrated to provide protection against disease from vaccine and non-vaccine HPV types to which a person has previously been exposed through sexual activity. [See Clinical Studies (14.4, 14.5).]

GARDASIL is not intended to be used for treatment of active external genital lesions; cervical, vulvar, vaginal, and anal cancers; CIN; VIN; VaIN; or AIN.

GARDASIL has not been demonstrated to protect against diseases due to HPV types not contained in the vaccine. [See Clinical Studies (14.4, 14.5).]

GARDASIL®

[Human Papillomavirus Quadrivalent (Types 6, 11, 16, and 18) Vaccine, Recombinant]

Not all vulvar, vaginal, and anal cancers are caused by HPV, and GARDASIL protects only against those vulvar, vaginal, and anal cancers caused by HPV 16 and 18.

GARDASIL does not protect against genital diseases not caused by HPV.

Vaccination with GARDASIL may not result in protection in all vaccine recipients.

GARDASIL has not been demonstrated to prevent HPV-related CIN 2/3 or worse in women older than 26 years of age. [See Clinical Studies (14.7).]

2 DOSAGE AND ADMINISTRATION

2.1 Dosage

GARDASIL should be administered intramuscularly as a 0.5-mL dose at the following schedule: 0, 2 months, 6 months. [See Clinical Studies (14.8).]

2.2 Method of Administration

For intramuscular use only.

Shake well before use. Thorough agitation immediately before administration is necessary to maintain suspension of the vaccine. GARDASIL should not be diluted or mixed with other vaccines. After thorough agitation, GARDASIL is a white, cloudy liquid. Parenteral drug products should be inspected visually for particulate matter and discoloration prior to administration. Do not use the product if particulates are present or if it appears discolored.

GARDASIL should be administered intramuscularly in the deltoid region of the upper arm or in the higher anterolateral area of the thigh.

Syncope has been reported following vaccination with GARDASIL and may result in falling with injury; observation for 15 minutes after administration is recommended. [See Warnings and Precautions (5.1).] Single-Dose Vial Use

Withdraw the 0.5-mL dose of vaccine from the single-dose vial using a sterile needle and syringe and use promptly.

Prefilled Svringe Use

This package does not contain a needle. Shake well before use. Attach the needle by twisting in a clockwise direction until the needle fits securely on the syringe. Administer the entire dose as per standard protocol.

3 DOSAGE FORMS AND STRENGTHS

GARDASIL is a suspension for intramuscular administration available in 0.5-mL single dose vials and prefilled syringes. See *Description (11)* for the complete listing of ingredients.

4 CONTRAINDICATIONS

Hypersensitivity, including severe allergic reactions to yeast (a vaccine component), or after a previous dose of GARDASIL. [See Description (11).]

5 WARNINGS AND PRECAUTIONS

5.1 Syncope

Because vaccinees may develop syncope, sometimes resulting in falling with injury, observation for 15 minutes after administration is recommended. Syncope, sometimes associated with tonic-clonic movements and other seizure-like activity, has been reported following vaccination with GARDASIL. When syncope is associated with tonic-clonic movements, the activity is usually transient and typically responds to restoring cerebral perfusion by maintaining a supine or Trendelenburg position.

5.2 Managing Allergic Reactions

Appropriate medical treatment and supervision must be readily available in case of anaphylactic reactions following the administration of GARDASIL.

6 ADVERSE REACTIONS

Overall Summary of Adverse Reactions

Headache, fever, nausea, and dizziness; and local injection site reactions (pain, swelling, erythema, pruritus, and bruising) occurred after administration with GARDASIL.

Syncope, sometimes associated with tonic-clonic movements and other seizure-like activity, has been reported following vaccination with GARDASIL and may result in falling with injury; observation for 15 minutes after administration is recommended. [See Warnings and Precautions (5.1).]

Anaphylaxis has been reported following vaccination with GARDASIL.

6.1 Clinical Trials Experience

Because clinical trials are conducted under widely varying conditions, adverse reaction rates observed in the clinical trials of a vaccine cannot be directly compared to rates in the clinical trials of another vaccine and may not reflect the rates observed in practice.

Studies in Girls and Women (9 Through 45 Years of Age) and Boys and Men (9 Through 26 Years of Age)

In 7 clinical trials (5 Amorphous Aluminum Hydroxyphosphate Sulfate [AAHS]-controlled, 1 saline placebo-controlled, and 1 uncontrolled), 18,083 individuals were administered GARDASIL or AAHS control or saline placebo on the day of enrollment, and approximately 2 and 6 months thereafter, and safety was evaluated using vaccination report cards (VRC)-aided surveillance for 14 days after each injection of GARDASIL or AAHS control or saline placebo in these individuals. The individuals who were monitored using VRC-aided surveillance included 10,088 individuals 9 through 45 years of age at enrollment who received GARDASIL and 7,995 individuals who received AAHS control or saline placebo. Few individuals (0.2%) discontinued due to adverse reactions. The race distribution of the 9- through 26-year-old girls and women in the safety population was as follows: 62.3% White; 17.6% Hispanic (Black and White); 6.8% Asian; 6.7% Other; 6.4% Black; and 0.3% American Indian. The race distribution of the 24- through 45-year-old women in the safety population of Study 6 was as follows: 20.6% White; 43.2% Hispanic (Black and White); 0.2% Other; 4.8% Black; 31.2% Asian; and 0.1% American Indian. The race distribution of the 9- through 26-year-old boys and men in the safety population was as follows: 42.0% White; 19.7% Hispanic (Black and White); 11.0% Asian; 11.2% Other; 15.9% Black; and 0.1% American Indian.

Common Injection-Site Adverse Reactions in Girls and Women 9 Through 26 Years of Age

The injection site adverse reactions that were observed among recipients of GARDASIL at a frequency of at least 1.0% and also at a greater frequency than that observed among AAHS control or saline placebo recipients are shown in Table 1.

Table 1
Injection-Site Adverse Reactions in Girls and Women 9 Through 26 Years of Age*

Adverse Reaction (1 to 5 Days Postvaccination)	GARDASIL (N = 5088) %	AAHS Control** (N = 3470) %	Saline Placebo (N = 320) %
Injection Site			
Pain	83.9	75.4	48.6
Swelling	25.4	15.8	7.3
Erythema	24.7	18.4	12.1
Pruritus	3.2	2.8	0.6
Bruising	2.8	3.2	1.6

^{*}The injection-site adverse reactions that were observed among recipients of GARDASIL were at a frequency of at least 1.0% and also at a greater frequency than that observed among AAHS control or saline placebo recipients.

Common Injection-Site Adverse Reactions in Boys and Men 9 Through 26 Years of Age

The injection site adverse reactions that were observed among recipients of GARDASIL at a frequency of at least 1.0% and also at a greater frequency than that observed among AAHS control or saline placebo recipients are shown in Table 2.

^{**}AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

Table 2
Injection-Site Adverse Reactions in Boys and Men 9 Through 26 Years of Age*

Adverse Reaction (1 to 5 Days Postvaccination)	GARDASIL (N = 3093)	AAHS Control ** (N = 2029) %	Saline Placebo (N = 274) %
Injection Site			
Pain	61.4	50.8	41.6
Erythema	16.7	14.1	14.5
Swelling	13.9	9.6	8.2
Hematoma	1.0	0.3	3.3

^{*}The injection-site adverse reactions that were observed among recipients of GARDASIL were at a frequency of at least 1.0% and also at a greater frequency than that observed among AAHS control or saline placebo recipients.

122123

124

Evaluation of Injection-Site Adverse Reactions by Dose in Girls and Women 9 Through 26 Years of Age
An analysis of injection-site adverse reactions in girls and women by dose is shown in Table 3. Of
those girls and women who reported an injection-site reaction, 94.3% judged their injection-site adverse
reaction to be mild or moderate in intensity.

Table 3
Postdose Evaluation of Injection-Site Adverse Reactions in Girls and Women 9 Through 26 Years of Age
(1 to 5 Days Postvaccination)

	GARDASIL (% occurrence)			AAHS Control* (% occurrence)			Saline Placebo (% occurrence)		
Adverse Reaction	Post- dose 1 N** = 5011	Post- dose 2 N = 4924	Post- dose 3 N = 4818	Post- dose 1 N = 3410	Post- dose 2 N = 3351	Post- dose 3 N = 3295	Post- dose 1 N = 315	Post- dose 2 N = 301	Post- dose 3 N = 300
Pain	63.4	60.7	62.7	57.0	47.8	49.6	33.7	20.3	27.3
Mild/Moderate	62.5	59.7	61.2	56.6	47.3	48.9	33.3	20.3	27.0
Severe	0.9	1.0	1.5	0.4	0.5	0.6	0.3	0.0	0.3
Swelling***	10.2	12.8	15.1	8.2	7.5	7.6	4.4	3.0	3.3
Mild/Moderate	9.6	11.9	14.2	8.1	7.2	7.3	4.4	3.0	3.3
Severe	0.6	0.8	0.9	0.2	0.2	0.2	0.0	0.0	0.0
Erythema***	9.2	12.1	14.7	9.8	8.4	8.9	7.3	5.3	5.7
Mild/Moderate	9.0	11.7	14.3	9.5	8.4	8.8	7.3	5.3	5.7
Severe	0.2	0.3	0.4	0.3	0.1	0.1	0.0	0.0	0.0

^{*}AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

125 126

127 128

129

Evaluation of Injection-Site Adverse Reactions by Dose in Boys and Men 9 Through 26 Years of Age
An analysis of injection-site adverse reactions in boys and men by dose is shown in Table 4. Of those
boys and men who reported an injection-site reaction, 96.4% judged their injection-site adverse reaction
to be mild or moderate in intensity.

^{**}AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

^{**}N = Number of individuals with follow-up

^{***}Intensity of swelling and erythema was measured by size (inches): Mild = 0 to ≤1; Moderate = >1 to ≤2; Severe = >2.

133

134 135

136

137

138 139

140

Table 4
Postdose Evaluation of Injection-Site Adverse Reactions in Boys and Men 9 Through 26 Years of Age
(1 to 5 Days Postvaccination)

(1 to 3 Days 1 Ostvaccination)										
		GARDASII (% occurrence		AAHS Control* (% occurrence)			Saline Placebo (% occurrence)			
Adverse Reaction	Post- dose 1 N** = 3003	Post- dose 2 N = 2898	Post- dose 3 N = 2826	Post- dose 1 N = 1950	Post- dose 2 N = 1854	Post- dose 3 N = 1799	Post- dose 1 N = 269	Post- dose 2 N = 263	Post- dose 3 N = 259	
Pain	44.7	36.9	34.4	38.4	28.2	25.8	27.5	20.5	16.2	
Mild/Moderate	44.5	36.4	34.1	37.9	28.2	25.5	27.5	20.2	16.2	
Severe	0.2	0.5	0.3	0.4	0.1	0.3	0.0	0.4	0.0	
Swelling*** Mild/Moderate Severe	5.6	6.6	7.7	5.6	4.5	4.1	4.8	1.5	3.5	
	5.3	6.2	7.1	5.4	4.5	4.0	4.8	1.5	3.1	
	0.2	0.3	0.5	0.2	0.0	0.1	0.0	0.0	0.4	
Erythema***	7.2	8.0	8.7	8.3	6.3	5.7	7.1	5.7	5.0	
Mild/Moderate	6.8	7.7	8.3	8.0	6.2	5.6	7.1	5.7	5.0	
Severe	0.3	0.2	0.3	0.2	0.1	0.1	0.0	0.0	0.0	

^{*}AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

Common Systemic Adverse Reactions in Girls and Women 9 Through 26 Years of Age

Headache was the most commonly reported systemic adverse reaction in both treatment groups (GARDASIL = 28.2% and AAHS control or saline placebo = 28.4%). Fever was the next most commonly reported systemic adverse reaction in both treatment groups (GARDASIL = 13.0% and AAHS control or saline placebo = 11.2%).

Adverse reactions that were observed among recipients of GARDASIL, at a frequency of greater than or equal to 1.0% where the incidence in the GARDASIL group was greater than or equal to the incidence in the AAHS control or saline placebo group, are shown in Table 5.

Table 5
Common Systemic Adverse Reactions in Girls and Women 9 Through 26 Years of Age
(GARDASIL ≥Control)*

Adverse Reactions (1 to 15 Days Postvaccination)	GARDASIL (N = 5088) %	AAHS Control** or Saline Placebo (N = 3790)
(1 to 15 Days Postvaccination)	/0	(N = 3790) %
Pyrexia	13.0	11.2
Nausea	6.7	6.5
Dizziness	4.0	3.7
Diarrhea	3.6	3.5
Vomiting	2.4	1.9
Cough	2.0	1.5
Toothache	1.5	1.4
Upper respiratory tract infection	1.5	1.5
Malaise	1.4	1.2
Arthralgia	1.2	0.9
Insomnia	1.2	0.9
Nasal congestion	1.1	0.9

^{*}The adverse reactions in this table are those that were observed among recipients of GARDASIL at a frequency of at least 1.0% and greater than or equal to those observed among AAHS control or saline placebo recipients.

141 142

143

144

Common Systemic Adverse Reactions in Boys and Men 9 Through 26 Years of Age

Headache was the most commonly reported systemic adverse reaction in both treatment groups (GARDASIL = 12.3% and AAHS control or saline placebo = 11.2%). Fever was the next most commonly

^{**}N = Number of individuals with follow-up

^{***}Intensity of swelling and erythema was measured by size (inches): Mild = 0 to ≤1; Moderate = >1 to ≤2; Severe = >2.

^{**}AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

150

151 152

153

154

155 156

157 158

reported systemic adverse reaction in both treatment groups (GARDASIL = 8.3% and AAHS control or saline placebo = 6.5%).

Adverse reactions that were observed among recipients of GARDASIL, at a frequency of greater than

Adverse reactions that were observed among recipients of GARDASIL, at a frequency of greater than or equal to 1.0% where the incidence in the group that received GARDASIL was greater than or equal to the incidence in the AAHS control or saline placebo group, are shown in Table 6.

Table 6

Common Systemic Adverse Reactions in Boys and Men 9 Through 26 Years of Age
(GARDASIL ≥Control)*

	GARDASIL	AAHS Control** or Saline
Adverse Reactions	(N = 3093)	Placebo
(1 to 15 Days Postvaccination)	%	(N = 2303)
		%
Headache	12.3	11.2
Pyrexia	8.3	6.5
Oropharyngeal pain	2.8	2.1
Diarrhea	2.7	2.2
Nasopharyngitis	2.6	2.6
Nausea	2.0	1.0
Upper respiratory tract infection	1.5	1.0
Abdominal pain upper	1.4	1.4
Myalgia	1.3	0.7
Dizziness	1.2	0.9
Vomiting	1.0	0.8

^{*}The adverse reactions in this table are those that were observed among recipients of GARDASIL at a frequency of at least 1.0% and greater than or equal to those observed among AAHS control or saline placebo recipients.

Evaluation of Fever by Dose in Girls and Women 9 Through 26 Years of Age An analysis of fever in girls and women by dose is shown in Table 7.

Table 7
Postdose Evaluation of Fever in Girls and Women 9 Through 26 Years of Age (1 to 5 Days Postvaccination)

1: :: : = :: ; : : : : : : : : : : : : :								
	GARDASIL (% occurrence)						Placebo	
Temperature (°F)	Postdose 1 N** = 4945	Postdose 2 N = 4804	Postdose 3 N = 4671	Postdose 1 N = 3681	Postdose 2 N = 3564	Postdose 3 N = 3467		
≥100 to <102	3.7	4.1	4.4	3.1	3.8	3.6		
≥102	0.3	0.5	0.5	0.2	0.4	0.5		

^{*}AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

Evaluation of Fever by Dose in Boys and Men 9 Through 26 Years of Age An analysis of fever in boys and men by dose is shown in Table 8.

Table 8
Postdose Evaluation of Fever in Boys and Men 9 Through 26 Years of Age

(1 to 5 Days Postvaccination) GARDASIL **AAHS Control* or Saline Placebo** (% occurrence) (% occurrence) Temperature Postdose 1 Postdose 2 Postdose 3 Postdose 1 Postdose 2 Postdose 3 $N^{**} = 2972$ N = 2849N = 2792N = 2194N = 2079N = 2046(°F) 2.5 2.3 2.2 ≥100 to <102 2.4 2.1 1.6 ≥102 0.6 0.5 0.5 0.3 0.3

159

^{**}AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

^{**}N = Number of individuals with follow-up

^{*}AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

^{**}N = Number of individuals with follow-up

163 164

165

166

167

168

169 170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186 187

188

189

190

191

192 193

194

195

196

197

198 199

200

201

202

203

204 205

160 Serious Adverse Reactions in the Entire Study Population

Across the clinical studies, 258 individuals (GARDASIL N = 128 or 0.8%; placebo N = 130 or 1.0%) out of 29,323 (GARDASIL N = 15,706; AAHS control N = 13,023; or saline placebo N = 594) individuals (9- through 45-year-old girls and women; and 9- through 26-year-old boys and men) reported a serious systemic adverse reaction.

Of the entire study population (29,323 individuals), 0.04% of the reported serious systemic adverse reactions were judged to be vaccine related by the study investigator. The most frequently (frequency of 4 cases or greater with either GARDASIL, AAHS control, saline placebo, or the total of all three) reported serious systemic adverse reactions, regardless of causality, were:

Headache [0.02% GARDASIL (3 cases) vs. 0.02% AAHS control (2 cases)],

Gastroenteritis [0.02% GARDASIL (3 cases) vs. 0.02% AAHS control (2 cases)],

Appendicitis [0.03% GARDASIL (5 cases) vs. 0.01% AAHS control (1 case)],

Pelvic inflammatory disease [0.02% GARDASIL (3 cases) vs. 0.03% AAHS control (4 cases)],

Urinary tract infection [0.01% GARDASIL (2 cases) vs. 0.02% AAHS control (2 cases)],

Pneumonia [0.01% GARDASIL (2 cases) vs. 0.02% AAHS control (2 cases)],

Pyelonephritis [0.01% GARDASIL (2 cases) vs. 0.02% AAHS control (3 cases)],

Pulmonary embolism [0.01% GARDASIL (2 cases) vs. 0.02% AAHS control (2 cases)].

One case (0.006% GARDASIL; 0.0% AAHS control or saline placebo) of bronchospasm; and 2 cases (0.01% GARDASIL; 0.0% AAHS control or saline placebo) of asthma were reported as serious systemic adverse reactions that occurred following any vaccination visit.

In addition, there was 1 individual in the clinical trials, in the group that received GARDASIL, who reported two injection-site serious adverse reactions (injection-site pain and injection-site joint movement impairment).

Deaths in the Entire Study Population

Across the clinical studies, 40 deaths (GARDASIL N = 21 or 0.1%; placebo N = 19 or 0.1%) were reported in 29,323 (GARDASIL N = 15,706; AAHS control N = 13,023, saline placebo N = 594) individuals (9- through 45-year-old girls and women; and 9- through 26-year-old boys and men). The events reported were consistent with events expected in healthy adolescent and adult populations. The most common cause of death was motor vehicle accident (5 individuals who received GARDASIL and 4 individuals who received AAHS control), followed by drug overdose/suicide (2 individuals who received GARDASIL and 6 individuals who received AAHS control), gun shot wound (1 individual who received GARDASIL and 3 individuals who received AAHS control), and pulmonary embolus/deep vein thrombosis (1 individual who received GARDASIL and 1 individual who received AAHS control). In addition, there were 2 cases of sepsis, 1 case of pancreatic cancer, 1 case of arrhythmia, 1 case of pulmonary tuberculosis, 1 case of hyperthyroidism, 1 case of post-operative pulmonary embolism and acute renal failure, 1 case of traumatic brain injury/cardiac arrest, 1 case of systemic lupus erythematosus, 1 case of cerebrovascular accident, 1 case of breast cancer, and 1 case of nasopharyngeal cancer in the group that received GARDASIL; 1 case of asphyxia, 1 case of acute lymphocytic leukemia, 1 case of chemical poisoning, and 1 case of myocardial ischemia in the AAHS control group; and 1 case of medulloblastoma in the saline placebo group.

Systemic Autoimmune Disorders in Girls and Women 9 Through 26 Years of Age

In the clinical studies, 9- through 26-year-old girls and women were evaluated for new medical conditions that occurred over the course of follow-up. New medical conditions potentially indicative of a systemic autoimmune disorder seen in the group that received GARDASIL or AAHS control or saline placebo are shown in Table 9. This population includes all girls and women who received at least one dose of GARDASIL or AAHS control or saline placebo, and had safety data available.

Table 9
Summary of Girls and Women 9 Through 26 Years of Age Who Reported an Incident Condition
Potentially Indicative of a Systemic Autoimmune Disorder After Enrollment in Clinical Trials of
GARDASIL. Regardless of Causality

Conditions	GARDASIL (N = 10,706)	AAHS Control* or Saline Placebo (N = 9412)
	n (%)	n (%)
Arthralgia/Arthritis/Arthropathy**	120 (1.1)	98 (1.0)
Autoimmune Thyroiditis	4 (0.0)	1 (0.0)
Celiac Disease	10 (0.1)	6 (0.1)
Diabetes Mellitus Insulin-dependent	2 (0.0)	2 (0.0)
Erythema Nodosum	2 (0.0)	4 (0.0)
Hyperthyroidism***	27 (0.3)	21 (0.2)
Hypothyroidism [†]	35 (0.3)	38 (0.4)
Inflammatory Bowel Disease [‡]	7 (0.1)	10 (0.1)
Multiple Sclerosis	2 (0.0)	4 (0.0)
Nephritis ¹	2 (0.0)	5 (0.1)
Optic Neuritis	2 (0.0)	0 (0.0)
Pigmentation Disorder [§]	4 (0.0)	3 (0.0)
Psoriasis [#]	13 (0.1)	15 (0.2)
Raynaud's Phenomenon	3 (0.0)	4 (0.0)
Rheumatoid Arthritis ^{††}	6 (0.1)	2 (0.0)
Scleroderma/Morphea	2 (0.0)	1 (0.0)
Stevens-Johnson Syndrome	1 (0.0)	0 (0.0)
Systemic Lupus Erythematosus	1 (0.0)	3 (0.0)
Uveitis	3 (0.0)	1 (0.0)
All Conditions	245 (2.3)	218 (2.3)

^{*}AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

NOTE: Although an individual may have had two or more new Medical Conditions, the individual is counted only once within a category. The same individual may appear in different categories.

207 208

209

210 211

212

213

Systemic Autoimmune Disorders in Boys and Men 9 Through 26 Years of Age

In the clinical studies, 9- through 26-year-old boys and men were evaluated for new medical conditions that occurred over the course of follow-up. New medical conditions potentially indicative of a systemic autoimmune disorder seen in the group that received GARDASIL or AAHS control or saline placebo are shown in Table 10. This population includes all boys and men who received at least one dose of GARDASIL or AAHS control or saline placebo, and had safety data available.

^{**}Arthralgia/Arthritis/Arthropathy includes the following terms: Arthralgia, Arthritis, Arthritis reactive, and Arthropathy

^{***}Hyperthyroidism includes the following terms: Basedow's disease, Goiter, Toxic nodular goiter, and Hyperthyroidism

[†]Hypothyroidism includes the following terms: Hypothyroidism and thyroiditis

[‡]Inflammatory bowel disease includes the following terms: Colitis ulcerative, Crohn's disease, and Inflammatory bowel disease

Nephritis includes the following terms: Nephritis, Glomerulonephritis minimal lesion, Glomerulonephritis proliferative

[§]Pigmentation disorder includes the following terms: Pigmentation disorder, Skin depigmentation, and Vitiligo

^{*}Psoriasis includes the following terms: Psoriasis, Pustular psoriasis, and Psoriatic arthropathy

^{††}Rheumatoid arthritis includes juvenile rheumatoid arthritis. One woman counted in the rheumatoid arthritis group reported rheumatoid arthritis as an adverse experience at Day 130.

N = Number of individuals enrolled

n = Number of individuals with specific new Medical Conditions

Table 10
Summary of Boys and Men 9 Through 26 Years of Age Who Reported an Incident Condition
Potentially Indicative of a Systemic Autoimmune Disorder After Enrollment in Clinical Trials of
GARDASIL. Regardless of Causality

Orthoria, regulation of Gaudanty							
Conditions	GARDASIL (N = 3093)	AAHS Control* or Saline Placebo (N = 2303)					
	n (%)	n (%)					
Alopecia Areata	2 (0.1)	0 (0.0)					
Ankylosing Spondylitis	1 (0.0)	2 (0.1)					
Arthralgia/Arthritis/Reactive Arthritis	30 (1.0)	17 (0.7)					
Autoimmune Thrombocytopenia	1 (0.0)	0 (0.0)					
Diabetes Mellitus Type 1	3 (0.1)	2 (0.1)					
Hyperthyroidism	0 (0.0)	1 (0.0)					
Hypothyroidism**	3 (0.1)	0 (0.0)					
Inflammatory Bowel Disease***	1 (0.0)	2 (0.1)					
Myocarditis	1 (0.0)	1 (0.0)					
Proteinuria	1 (0.0)	0 (0.0)					
Psoriasis	0 (0.0)	4 (0.2)					
Skin Depigmentation	1 (0.0)	0 (0.0)					
Vitiligo	2 (0.1)	5 (0.2)					
All Conditions	46 (1.5)	34 (1.5)					

^{*}AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

Safety in Concomitant Use with RECOMBIVAX HB [hepatitis B vaccine (recombinant)] in Girls and Women 16 Through 23 Years of Age

The safety of GARDASIL when administered concomitantly with RECOMBIVAX HB^{®1} [hepatitis B vaccine (recombinant)] was evaluated in an AAHS-controlled study of 1871 girls and women with a mean age of 20.4 years [see Clinical Studies (14.9)]. The race distribution of the study individuals was as follows: 61.6% White; 23.8% Other; 11.9% Black; 1.6% Hispanic (Black and White); 0.8% Asian; and 0.3% American Indian. The rates of systemic and injection-site adverse reactions were similar among girls and women who received concomitant vaccination as compared with those who received GARDASIL or RECOMBIVAX HB [hepatitis B vaccine (recombinant)].

Safety in Concomitant Use with Menactra [Meningococcal (Groups A, C, Y and W-135) Polysaccharide Diphtheria Toxoid Conjugate Vaccine] and Adacel [Tetanus Toxoid, Reduced Diphtheria Toxoid and Acellular Pertussis Vaccine Adsorbed (Tdap)]

The safety of GARDASIL when administered concomitantly with Menactra [Meningococcal (Groups A, C, Y and W-135) Polysaccharide Diphtheria Toxoid Conjugate Vaccine] and Adacel [Tetanus Toxoid, Reduced Diphtheria Toxoid and Acellular Pertussis Vaccine Adsorbed (Tdap)] was evaluated in a randomized study of 1040 boys and girls with a mean age of 12.6 years [see Clinical Studies (14.10)]. The race distribution of the study subjects was as follows: 77.7% White; 1.4% Multi-racial; 12.3% Black; 6.8% Hispanic (Black and White); 1.2% Asian; 0.4% American Indian, and 0.2% Indian.

There was an increase in injection-site swelling reported at the injection site for GARDASIL (concomitant = 10.9%, non-concomitant = 6.9%) when GARDASIL was administered concomitantly with Menactra and Adacel as compared to non-concomitant (separated by 1 month) vaccination. The majority of injection-site swelling adverse experiences were reported as being mild to moderate in intensity. Safety in Women 27 Through 45 Years of Age

The adverse reaction profile in women 27 through 45 years of age was comparable to the profile seen in girls and women 9 through 26 years of age.

^{**}Hypothyroidism includes the following terms: Hypothyroidism and Autoimmune thyroiditis

^{***}Inflammatory bowel disease includes the following terms: Colitis ulcerative and Crohn's disease

N = Number of individuals who received at least one dose of either vaccine or placebo

n = Number of individuals with specific new Medical Conditions

NOTE: Although an individual may have had two or more new Medical Conditions, the individual is counted only once within a category. The same individual may appear in different categories.

6.2 Postmarketing Experience

The following adverse events have been spontaneously reported during post-approval use of GARDASIL. Because these events were reported voluntarily from a population of uncertain size, it is not possible to reliably estimate their frequency or to establish a causal relationship to vaccine exposure.

Blood and lymphatic system disorders: Autoimmune hemolytic anemia, idiopathic thrombocytopenic purpura, lymphadenopathy.

Respiratory, thoracic and mediastinal disorders: Pulmonary embolus.

Gastrointestinal disorders: Nausea, pancreatitis, vomiting.

General disorders and administration site conditions: Asthenia, chills, death, fatigue, malaise.

Immune system disorders: Autoimmune diseases, hypersensitivity reactions including anaphylactic/anaphylactoid reactions, bronchospasm, and urticaria.

Musculoskeletal and connective tissue disorders: Arthralgia, myalgia.

Nervous system disorders: Acute disseminated encephalomyelitis, dizziness, Guillain-Barré syndrome, headache, motor neuron disease, paralysis, seizures, syncope (including syncope associated with tonic-clonic movements and other seizure-like activity) sometimes resulting in falling with injury, transverse myelitis.

Infections and infestations: cellulitis.

Vascular disorders: Deep venous thrombosis.

7 DRUG INTERACTIONS

7.1 Use with RECOMBIVAX HB

Results from clinical studies indicate that GARDASIL may be administered concomitantly (at a separate injection site) with RECOMBIVAX HB [hepatitis B vaccine (recombinant)] [see Clinical Studies (14.9)].

264 7.2 Use with Menactra and Adacel

Results from clinical studies indicate that GARDASIL may be administered concomitantly (at a separate injection site) with Menactra [Meningococcal (Groups A, C, Y and W-135) Polysaccharide Diphtheria Toxoid Conjugate Vaccine] and Adacel [Tetanus Toxoid, Reduced Diphtheria Toxoid and Acellular Pertussis Vaccine Adsorbed (Tdap)] [see Clinical Studies (14.10)].

7.3 Use with Hormonal Contraceptives

In clinical studies of 16- through 26-year-old women, 13,912 (GARDASIL N = 6952; AAHS control or saline placebo N = 6960) who had post-Month 7 follow-up used hormonal contraceptives for a total of 33,859 person-years (65.8% of the total follow-up time in the studies).

In one clinical study of 24- through 45-year-old women, 1357 (GARDASIL N = 690; AAHS control N = 667) who had post-Month 7 follow-up used hormonal contraceptives for a total of 3400 person-years (31.5% of the total follow-up time in the study). Use of hormonal contraceptives or lack of use of hormonal contraceptives among study participants did not impair the immune response in the per protocol immunogenicity (PPI) population.

7.4 Use with Systemic Immunosuppressive Medications

Immunosuppressive therapies, including irradiation, antimetabolites, alkylating agents, cytotoxic drugs, and corticosteroids (used in greater than physiologic doses), may reduce the immune responses to vaccines [see Use in Specific Populations (8.6)].

282 8 USE IN SPECIFIC POPULATIONS

8.1 Pregnancy

Pregnancy Category B:

Reproduction studies have been performed in female rats at doses equivalent to the recommended human dose and have revealed no evidence of impaired female fertility or harm to the fetus due to GARDASIL. There are, however, no adequate and well-controlled studies in pregnant women. Because animal reproduction studies are not always predictive of human responses, GARDASIL should be used during pregnancy only if clearly needed.

An evaluation of the effect of GARDASIL on embryo-fetal, pre- and postweaning development was conducted using rats. One group of rats was administered GARDASIL twice prior to gestation, during the period of organogenesis (gestation Day 6) and on lactation Day 7. A second group of pregnant rats was administered GARDASIL during the period of organogenesis (gestation Day 6) and on lactation Day 7 only. GARDASIL was administered at 0.5 mL/rat/occasion (120 mcg total protein which is equivalent to the recommended human dose) by intramuscular injection. No adverse effects on mating, fertility, pregnancy, parturition, lactation, embryo-fetal or pre- and postweaning development were observed. There were no vaccine-related fetal malformations or other evidence of teratogenesis noted in this study. In addition, there were no treatment-related effects on developmental signs, behavior, reproductive performance, or fertility of the offspring.

Clinical Studies in Humans

In clinical studies, women underwent urine pregnancy testing prior to administration of each dose of GARDASIL. Women who were found to be pregnant before completion of a 3-dose regimen of GARDASIL were instructed to defer completion of their vaccination regimen until resolution of the pregnancy.

GARDASIL is not indicated for women 27 years of age or older. However, safety data in women 16 through 45 years of age was collected, and 3819 women (GARDASIL N = 1894 vs. AAHS control or saline placebo N = 1925) reported at least 1 pregnancy each.

The overall proportions of pregnancies that resulted in an adverse outcome, defined as the combined numbers of spontaneous abortion, late fetal death, and congenital anomaly cases out of the total number of pregnancy outcomes for which an outcome was known (and excluding elective terminations), were 22.6% (446/1973) in women who received GARDASIL and 23.1% (460/1994) in women who received AAHS control or saline placebo.

Overall, 55 and 65 women in the group that received GARDASIL or AAHS control or saline placebo, respectively (2.9% and 3.4% of all women who reported a pregnancy in the respective vaccination groups), experienced a serious adverse reaction during pregnancy. The most common events reported were conditions that can result in Caesarean section (e.g., failure of labor, malpresentation, cephalopelvic disproportion), premature onset of labor (e.g., threatened abortions, premature rupture of membranes), and pregnancy-related medical problems (e.g., pre-eclampsia, hyperemesis). The proportions of pregnant women who experienced such events were comparable between the groups receiving GARDASIL and AAHS control or saline placebo.

There were 45 cases of congenital anomaly in pregnancies that occurred in women who received GARDASIL and 34 cases of congenital anomaly in pregnancies that occurred in women who received AAHS control or saline placebo.

Further sub-analyses were conducted to evaluate pregnancies with estimated onset within 30 days or more than 30 days from administration of a dose of GARDASIL or AAHS control or saline placebo. For pregnancies with estimated onset within 30 days of vaccination, 5 cases of congenital anomaly were observed in the group that received GARDASIL compared to 1 case of congenital anomaly in the group that received AAHS control or saline placebo. The congenital anomalies seen in pregnancies with estimated onset within 30 days of vaccination included pyloric stenosis, congenital megacolon, congenital hydronephrosis, hip dysplasia, and club foot. Conversely, in pregnancies with onset more than 30 days following vaccination, 40 cases of congenital anomaly were observed in the group that received

GARDASIL®

[Human Papillomavirus Quadrivalent (Types 6, 11, 16, and 18) Vaccine, Recombinant]

- GARDASIL compared with 33 cases of congenital anomaly in the group that received AAHS control or saline placebo.
- 334 Pregnancy Registry for GARDASIL

Merck Sharp & Dohme Corp., a subsidiary of Merck & Co., Inc., maintains a Pregnancy Registry to monitor fetal outcomes of pregnant women exposed to GARDASIL. Patients and health care providers are encouraged to report any exposure to GARDASIL during pregnancy by calling (800) 986-8999.

8.3 Nursing Mothers

339 Women 16 Through 45 Years of Age

It is not known whether GARDASIL is excreted in human milk. Because many drugs are excreted in human milk, caution should be exercised when GARDASIL is administered to a nursing woman.

GARDASIL or AAHS control were given to a total of 1133 women (vaccine N = 582, AAHS control N = 551) during the relevant Phase III clinical studies.

Overall, 27 and 13 infants of women who received GARDASIL or AAHS control, respectively (representing 4.6% and 2.4% of the total number of women who were breast-feeding during the period in which they received GARDASIL or AAHS control, respectively), experienced a serious adverse reaction.

In a post-hoc analysis of clinical studies, a higher number of breast-feeding infants (n = 7) whose mothers received GARDASIL had acute respiratory illnesses within 30 days post vaccination of the mother as compared to infants (n = 2) whose mothers received AAHS control.

8.4 Pediatric Use

Safety and effectiveness have not been established in pediatric patients below 9 years of age.

8.5 Geriatric Use

The safety and effectiveness of GARDASIL have not been evaluated in a geriatric population, defined as individuals aged 65 years and over.

8.6 Immunocompromised Individuals

The immunologic response to GARDASIL may be diminished in immunocompromised individuals [see Drug Interactions (7.4)].

10 OVERDOSAGE

There have been reports of administration of higher than recommended doses of GARDASIL.

In general, the adverse event profile reported with overdose was comparable to recommended single doses of GARDASIL.

11 DESCRIPTION

GARDASIL, Human Papillomavirus Quadrivalent (Types 6, 11, 16, and 18) Vaccine, Recombinant, is a non-infectious recombinant quadrivalent vaccine prepared from the purified virus-like particles (VLPs) of the major capsid (L1) protein of HPV Types 6, 11, 16, and 18. The L1 proteins are produced by separate fermentations in recombinant *Saccharomyces cerevisiae* and self-assembled into VLPs. The fermentation process involves growth of *S. cerevisiae* on chemically-defined fermentation media which include vitamins, amino acids, mineral salts, and carbohydrates. The VLPs are released from the yeast cells by cell disruption and purified by a series of chemical and physical methods. The purified VLPs are adsorbed on preformed aluminum-containing adjuvant (Amorphous Aluminum Hydroxyphosphate Sulfate). The quadrivalent HPV VLP vaccine is a sterile liquid suspension that is prepared by combining the adsorbed VLPs of each HPV type and additional amounts of the aluminum-containing adjuvant and the final purification buffer.

GARDASIL is a sterile suspension for intramuscular administration. Each 0.5-mL dose contains approximately 20 mcg of HPV 6 L1 protein, 40 mcg of HPV 11 L1 protein, 40 mcg of HPV 16 L1 protein, and 20 mcg of HPV 18 L1 protein.

Each 0.5-mL dose of the vaccine contains approximately 225 mcg of aluminum (as Amorphous Aluminum Hydroxyphosphate Sulfate adjuvant), 9.56 mg of sodium chloride, 0.78 mg of L-histidine, 50 mcg of polysorbate 80, 35 mcg of sodium borate, <7 mcg yeast protein/dose, and water for injection. The product does not contain a preservative or antibiotics.

After thorough agitation, GARDASIL is a white, cloudy liquid.

12 CLINICAL PHARMACOLOGY

12.1 Mechanism of Action

HPV only infects human beings. Animal studies with analogous animal papillomaviruses suggest that the efficacy of L1 VLP vaccines may involve the development of humoral immune responses. Human beings develop a humoral immune response to the vaccine, although the exact mechanism of protection is unknown.

13 NONCLINICAL TOXICOLOGY

13.1 Carcinogenesis, Mutagenesis, Impairment of Fertility

GARDASIL has not been evaluated for the potential to cause carcinogenicity or genotoxicity.

GARDASIL administered to female rats at a dose of 120 mcg total protein, which is equivalent to the recommended human dose, had no effects on mating performance, fertility, or embryonic/fetal survival.

The effect of GARDASIL on male fertility has been studied in male rats at an intramuscular dose of 0.5 mL/rat/occasion (120 mcg total protein which is equivalent to the recommended human dose). One group of male rats was administered GARDASIL once, 3 days prior to cohabitation, and a second group of male rats was administered GARDASIL three times, at 6 weeks, 3 weeks, and 3 days prior to cohabitation. There were no treatment-related effects on reproductive performance including fertility, sperm count, and sperm motility. There were no treatment-related gross or histomorphologic and weight changes on the testes.

14 CLINICAL STUDIES

CIN 2/3 and AIS are the immediate and necessary precursors of squamous cell carcinoma and adenocarcinoma of the cervix, respectively. Their detection and removal has been shown to prevent cancer; thus, they serve as surrogate markers for prevention of cervical cancer. In the clinical studies in girls and women aged 16 through 26 years, cases of CIN 2/3 and AIS were the efficacy endpoints to assess prevention of cervical cancer. In addition, cases of VIN 2/3 and VaIN 2/3 were the efficacy endpoints to assess prevention of HPV-related vulvar and vaginal cancers, and observations of external genital lesions were the efficacy endpoints for the prevention of genital warts.

In clinical studies in boys and men aged 16 through 26 years, efficacy was evaluated using the following endpoints: external genital warts and penile/perineal/perianal intraepithelial neoplasia (PIN) grades 1/2/3 or penile/perineal/perianal cancer. In addition, cases of AIN grades 1/2/3 and anal cancer made up the composite efficacy endpoint used to assess prevention of HPV-related anal cancer.

Anal HPV infection, AIN, and anal cancer were not endpoints in the studies conducted in women. The similarity of HPV-related anal disease in men and women supports bridging the indication of prevention of AIN and anal cancer to women.

Efficacy was assessed in 6 AAHS-controlled, double-blind, randomized Phase II and III clinical studies. The first Phase II study evaluated the HPV 16 component of GARDASIL (Study 1, N = 2391 16-through 26-year-old girls and women) and the second evaluated all components of GARDASIL (Study 2, N = 551 16- through 26-year-old girls and women). Two Phase III studies evaluated GARDASIL in 5442 (Study 3) and 12,157 (Study 4) 16- through 26-year-old girls and women. A third Phase III study, Study 5, evaluated GARDASIL in 4055 16- through 26-year-old boys and men, including a subset of 598 (GARDASIL = 299; placebo = 299) men who self-identified as having sex with men (MSM population). A fourth Phase III study, Study 6, evaluated GARDASIL in 3817 24- through 45-year-old women. Together, these six studies evaluated 28,413 individuals (20,541 girls and women 16 through 26 years of age at

enrollment with a mean age of 20.0 years, 4055 boys and men 16 through 26 years of age at enrollment with a mean age of 20.5 years, and 3817 women 24 through 45 years of age at enrollment with a mean age of 34.3 years). The race distribution of the 16- through 26-year-old girls and women in the clinical trials was as follows: 70.4% White; 12.2% Hispanic (Black and White); 8.8% Other; 4.6% Black; 3.8% Asian; and 0.2% American Indian. The race distribution of the 16- through 26-year-old boys and men in the clinical trials was as follows: 35.2% White; 20.5% Hispanic (Black and White); 14.4% Other; 19.8% Black; 10.0% Asian; and 0.1% American Indian. The race distribution of the 24- through 45-year-old women in the clinical trials was as follows: 20.6% White; 43.2% Hispanic (Black and White); 0.2% Other; 4.8% Black; 31.2% Asian; and 0.1% American Indian.

The median duration of follow-up was 4.0, 3.0, 3.0, 3.0, 2.3, and 4.0 years for Study 1, Study 2, Study 3, Study 4, Study 5, and Study 6, respectively. Individuals received vaccine or AAHS control on the day of enrollment and 2 and 6 months thereafter. Efficacy was analyzed for each study individually and for all studies in girls and women combined according to a prospective clinical plan.

Overall, 73% of 16- through 26-year-old girls and women, 67% of 24- through 45-year-old women, and 83% of 16- through 26-year-old boys and men were naïve (i.e., PCR [Polymerase Chain Reaction] negative and seronegative for all 4 vaccine HPV types) to all 4 vaccine HPV types at enrollment.

A total of 27% of 16- through 26-year-old girls and women, 33% of 24- through 45-year-old women, and 17% of 16- through 26-year-old boys and men had evidence of prior exposure to or ongoing infection with at least 1 of the 4 vaccine HPV types. Among these individuals, 74% of 16- through 26-year-old girls and women, 71% of 24- through 45-year-old women, and 78% of 16- through 26-year-old boys and men had evidence of prior exposure to or ongoing infection with only 1 of the 4 vaccine HPV types and were naïve (PCR negative and seronegative) to the remaining 3 types.

In 24- through 45-year-old individuals, 0.4% had been exposed to all 4 vaccine HPV types.

In individuals who were naïve (PCR negative and seronegative) to all 4 vaccine HPV types, CIN, genital warts, VIN, VaIN, PIN, and persistent infection caused by any of the 4 vaccine HPV types were counted as endpoints.

Among individuals who were positive (PCR positive and/or seropositive) for a vaccine HPV type at Day 1, endpoints related to that type were not included in the analyses of prophylactic efficacy. Endpoints related to the remaining types for which the individual was naïve (PCR negative and seronegative) were counted.

For example, in individuals who were HPV 18 positive (PCR positive and/or seropositive) at Day 1, lesions caused by HPV 18 were not counted in the prophylactic efficacy evaluations. Lesions caused by HPV 6, 11, and 16 were included in the prophylactic efficacy evaluations. The same approach was used for the other types.

14.1 Prophylactic Efficacy – HPV Types 6, 11, 16, and 18 in Girls and Women 16 Through 26 Years of Age

GARDASIL was administered without prescreening for presence of HPV infection and the efficacy trials allowed enrollment of girls and women regardless of baseline HPV status (i.e., PCR status or serostatus). Girls and women with current or prior HPV infection with an HPV type contained in the vaccine were not eligible for prophylactic efficacy evaluations for that type.

The primary analyses of efficacy with respect to HPV types 6, 11, 16, and 18 were conducted in the per-protocol efficacy (PPE) population, consisting of girls and women who received all 3 vaccinations within 1 year of enrollment, did not have major deviations from the study protocol, and were naïve (PCR negative in cervicovaginal specimens and seronegative) to the relevant HPV type(s) (Types 6, 11, 16, and 18) prior to dose 1 and through 1 month Postdose 3 (Month 7). Efficacy was measured starting after the Month 7 visit.

GARDASIL was efficacious in reducing the incidence of CIN (any grade including CIN 2/3); AIS; genital warts; VIN (any grade); and VaIN (any grade) related to vaccine HPV types 6, 11, 16, or 18 in those who were PCR negative and seronegative at baseline (Table 11).

In addition, girls and women who were already infected with 1 or more vaccine-related HPV types prior to vaccination were protected from precancerous cervical lesions and external genital lesions caused by the other vaccine HPV types.

Table 11
Analysis of Efficacy of GARDASIL in the PPE* Population** of 16- Through 26-Year-Old Girls and Women for Vaccine HPV Types

Daniel attan	GARDASIL		A	AHS Control	0/ Est (0 = 0/ O)	
Population	N	Number of cases	N	Number of cases	% Efficacy (95% CI)	
HPV 16- or 18-related CIN	2/3 or AIS			•		
Study 1***	755	0	750	12	100.0 (65.1, 100.0)	
Study 2	231	0	230	1	100.0 (-3744.9, 100.0)	
Study 3	2201	0	2222	36	100.0 (89.2, 100.0)	
Study 4	5306	2	5262	63	96.9 (88.2, 99.6)	
Combined Protocols [†]	8493	2	8464	112	98.2 (93.5, 99.8)	
HPV 16-related CIN 2/3 or	AIS					
Combined Protocols [†]	7402	2	7205	93	97.9 (92.3, 99.8)	
HPV 18-related CIN 2/3 or	AIS					
Combined Protocols [†]	7382	0	7316	29	100.0 (86.6, 100.0)	
HPV 16- or 18-related VIN	2/3					
Study 2	231	0	230	0	Not calculated	
Study 3	2219	0	2239	6	100.0 (14.4, 100.0)	
Study 4	5322	0	5275	4	100.0 (-50.3, 100.0)	
Combined Protocols [†]	7772	0	7744	10	100.0 (55.5, 100.0)	
HPV 16- or 18-related Vall	l 2/3					
Study 2	231	0	230	0	Not calculated	
Study 3	2219	0	2239	5	100.0 (-10.1, 100.0)	
Study 4	5322	0	5275	4	100.0 (-50.3, 100.0)	
Combined Protocols [†]	7772	0	7744	9	100.0 (49.5, 100.0)	
HPV 6-, 11-, 16-, or 18-rela	ted CIN (CIN 1	, CIN 2/3) or AIS				
Study 2	235	0	233	3	100.0 (-138.4, 100.0)	
Study 3	2241	0	2258	77	100.0 (95.1, 100.0)	
Study 4	5388	9	5374	145	93.8 (88.0, 97.2)	
Combined Protocols [†]	7864	9	7865	225	96.0 (92.3, 98.2)	
HPV 6-, 11-, 16-, or 18-rela	ted Genital W	arts				
Study 2	235	0	233	3	100.0 (-139.5, 100.0)	
Study 3	2261	0	2279	58	100.0 (93.5, 100.0)	
Study 4	5404	2	5390	132	98.5 (94.5, 99.8)	
Combined Protocols [†]	7900	2	7902	193	99.0 (96.2, 99.9)	
HPV 6- and 11-related Ger	nital Warts					
Combined Protocols [†]	6932	2	6856	189	99.0 (96.2, 99.9)	

^{*}The PPE population consisted of individuals who received all 3 vaccinations within 1 year of enrollment, did not have major deviations from the study protocol, and were naïve (PCR negative and seronegative) to the relevant HPV type(s) (Types 6, 11, 16, and 18) prior to dose 1 and through 1 month postdose 3 (Month 7).

478

479

480 481 Note 1: Point estimates and confidence intervals are adjusted for person-time of follow-up.

Note 2: The first analysis in the table (i.e., HPV 16- or 18-related CIN 2/3, AIS or worse) was the primary endpoint of the vaccine development plan.

Note 3: Table 11 does not include cases due to non-vaccine HPV types.

AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

Prophylactic efficacy against overall cervical and genital disease related to HPV 6, 11, 16, and 18 in an extension phase of Study 2, that included data through Month 60, was noted to be 100% (95% CI: 12.3%, 100.0%) among girls and women in the per protocol population naïve to the relevant HPV types.

GARDASIL was efficacious against HPV disease caused by HPV types 6, 11, 16, and 18 in girls and women who were naïve for those specific HPV types at baseline.

^{**}See Table 14 for analysis of vaccine impact in the general population.

^{***}Evaluated only the HPV 16 L1 VLP vaccine component of GARDASIL

[†]Analyses of the combined trials were prospectively planned and included the use of similar study entry criteria.

N = Number of individuals with at least 1 follow-up visit after Month 7

CI = Confidence Interval

Age

482

483 484

485 486 487 488 489 490 491

492 493

The primary analyses of efficacy were conducted in the per-protocol efficacy (PPE) population. This population consisted of boys and men who received all 3 vaccinations within 1 year of enrollment, did not have major deviations from the study protocol, and were naïve (PCR negative and seronegative) to the relevant HPV type(s) (Types 6, 11, 16, and 18) prior to dose 1 and through 1 month postdose 3 (Month 7). Efficacy was measured starting after the Month 7 visit.

14.2 Prophylactic Efficacy – HPV Types 6, 11, 16, and 18 in Boys and Men 16 Through 26 Years of

GARDASIL was efficacious in reducing the incidence of genital warts related to vaccine HPV types 6 and 11 in those boys and men who were PCR negative and seronegative at baseline (Table 12). Efficacy against penile/perineal/perianal intraepithelial neoplasia (PIN) grades 1/2/3 or penile/perineal/perianal cancer was not demonstrated as the number of cases was too limited to reach statistical significance.

Table 12 Analysis of Efficacy of GARDASIL in the PPE* Population of 16- Through 26-Year-Old Boys and Men for Vaccine **HPV Types**

111 V 13 POO						
Endpoint	GARDASIL		A	AHS Control	% Efficacy (95% CI)	
Enapoint	N**	Number of cases	N	Number of cases	/8 Efficacy (95 /8 CI)	
External Genital Lesions HPV 6-, 11-, 16-, or 18- related						
External Genital Lesions	1394	3	1404	32	90.6 (70.1, 98.2)	
Condyloma	1394	3	1404	28	89.3 (65.3, 97.9)	
PIN 1/2/3	1394	0	1404	4	100.0 (-52.1, 100.0)	

^{*}The PPE population consisted of individuals who received all 3 vaccinations within 1 year of enrollment, did not have major deviations from the study protocol, and were naïve (PCR negative and seronegative) to the relevant HPV type(s) (Types 6, 11, 16, and 18) prior to dose 1 and through 1 month postdose 3 (Month 7).

494 495

496

497

498

499

500

501

502 503

14.3 Prophylactic Efficacy - Anal Disease Caused by HPV Types 6, 11, 16, and 18 in Boys and Men 16 Through 26 Years of Age in the MSM Sub-study

A sub-study of Study 5 evaluated the efficacy of GARDASIL against anal disease (anal intraepithelial neoplasia and anal cancer) in a population of 598 MSM. The primary analyses of efficacy were conducted in the per-protocol efficacy (PPE) population of Study 5.

GARDASIL was efficacious in reducing the incidence of anal intraepithelial neoplasia (AIN) grades 1 (both condyloma and non-acuminate), 2, and 3 related to vaccine HPV types 6, 11, 16, and 18 in those boys and men who were PCR negative and seronegative at baseline (Table 13).

Table 13 Analysis of Efficacy of GARDASIL for Anal Disease in the PPE* Population of 16- Through 26-Year-Old Boys and Men in the MSM Sub-study for Vaccine HPV Types

HPV 6-, 11-, 16-, or 18- related	GARDASIL		A/	AHS Control	% Efficacy (95% CI)	
Endpoint	N**	Number of cases	N	Number of cases	/8 Lilicacy (95 /8 Ci)	
AIN 1/2/3	194	5	208	24	77.5 (39.6, 93.3)	
AIN 2/3	194	3	208	13	74.9 (8.8, 95.4)	
AIN 1	194	4	208	16	73.0 (16.3, 93.4)	
Condyloma Acuminatum	194	0	208	6	100.0 (8.2, 100.0)	
Non-acuminate	194	4	208	11	60.4 (-33.5, 90.8)	

^{*}The PPE population consisted of individuals who received all 3 vaccinations within 1 year of enrollment, did not have major deviations from the study protocol, and were naïve (PCR negative and seronegative) to the relevant HPV type(s) (Types 6, 11, 16, and 18) prior to dose 1 and through 1 month postdose 3 (month 7).

^{**}N = Number of individuals with at least 1 follow-up visit after Month 7

CI = Confidence Interval

AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

^{**}N = Number of individuals with at least 1 follow-up visit after Month 7

CI = Confidence Interval

AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

14.4 Population Impact in Girls and Women 16 Through 26 Years of Age

Effectiveness of GARDASIL in Prevention of HPV Types 6-, 11-, 16-, or 18-Related Genital Disease in Girls and Women 16 Through 26 Years of Age, Regardless of Current or Prior Exposure to Vaccine HPV Types

The clinical trials included girls and women regardless of current or prior exposure to vaccine HPV types, and additional analyses were conducted to evaluate the impact of GARDASIL with respect to HPV 6-, 11-, 16-, and 18-related cervical and genital disease in these girls and women. Here, analyses included events arising among girls and women regardless of baseline PCR status and serostatus, including HPV infections that were present at the start of vaccination as well as events that arose from infections that were acquired after the start of vaccination.

The impact of GARDASIL in girls and women regardless of current or prior exposure to a vaccine HPV type is shown in Table 14. Impact was measured starting 1 month Postdose 1. Prophylactic efficacy denotes the vaccine's efficacy in girls and women who are naïve (PCR negative and seronegative) to the relevant HPV types at Day 1. Vaccine impact in girls and women who were positive for vaccine HPV infection, as well as vaccine impact among girls and women regardless of baseline vaccine HPV PCR status and serostatus are also presented. The majority of CIN and genital warts, VIN, and VaIN related to a vaccine HPV type detected in the group that received GARDASIL occurred as a consequence of HPV infection with the relevant HPV type that was already present at Day 1.

There was no clear evidence of protection from disease caused by HPV types for which girls and women were PCR positive regardless of serostatus at baseline.

Table 14

Effectiveness of GARDASIL in Prevention of HPV 6, 11, 16, or 18-Related Genital Disease in Girls and Women
16 Through 26 Years of Age, Regardless of Current or Prior Exposure to Vaccine HPV Types

Endneint	Analysia		IL or HPV 16	AAHS Control		% Reduction	
Endpoint	Analysis	N Cases		N Cases		(95% CI)	
HPV 16- or 18-	Prophylactic Efficacy*	9346	4	9407	155	97.4 (93.3, 99.3)	
related CIN 2/3 or	HPV 16 and/or HPV 18 Positive at Day 1**	2870	142	2898	148***	†	
AIS	Girls and Women Regardless of Current or Prior Exposure to HPV 16 or 18 [‡]	9836	146	9904	303	51.8 (41.1, 60.7)	
HPV 16- or 18-	Prophylactic Efficacy*	8642	1	8673	34	97.0 (82.4, 99.9)	
related VIN 2/3 or	HPV 16 and/or HPV 18 Positive at Day 1**	1880	8	1876	4	_ _†	
ValN 2/3	Girls and Women Regardless of Current or Prior Exposure to HPV 16 or 18 [‡]	8955	9	8968	38	76.3 (50.0, 89.9)	
HPV 6-, 11-, 16-,	Prophylactic Efficacy*	8630	16	8680	309	94.8 (91.5, 97.1)	
18-related CIN (CIN 1, CIN 2/3) or	HPV 6, HPV 11, HPV 16, and/or HPV 18 Positive at Day 1**	2466	186 [#]	2437	213#	[†]	
AIS	Girls and Women Regardless of Current or Prior Exposure to Vaccine HPV Types [‡]	8819	202	8854	522	61.5 (54.6, 67.4)	
	Prophylactic Efficacy*	8761	10	8792	252	96.0 (92.6, 98.1)	
HPV 6-, 11-, 16-, or 18-related	HPV 6, HPV 11, HPV 16, and/or HPV 18 Positive at Day 1**	2501	51 [§]	2475	55 [§]	†	
Genital Warts	Girls and Women Regardless of Current or Prior Exposure to Vaccine HPV Types [‡]	8955	61	8968	307	80.3 (73.9, 85.3)	
HPV 6- or 11-	Prophylactic Efficacy*	7769	9	7792	246	96.4 (93.0, 98.4)	
related Genital	HPV 6 and/or HPV 11 Positive at Day 1**	1186	51	1176	54	t	
Warts	Girls and Women Regardless of Current or Prior Exposure to Vaccine HPV Types [‡]	8955	60	8968	300	80.1 (73.7, 85.2)	

^{*}Includes all individuals who received at least 1 vaccination and who were HPV-naïve (i.e., seronegative and PCR negative) at Day 1 to the vaccine HPV type being analyzed. Case counting started at 1 month postdose 1.

N = Number of individuals who have at least one follow-up visit after Day 1

Note 1: The 16- and 18-related CIN 2/3 or AIS composite endpoint included data from studies 1, 2, 3, and 4. All other endpoints only included data from studies 2, 3, and 4.

Note 2: Positive status at Day 1 denotes PCR positive and/or seropositive for the respective type at Day 1.

Note 3: Table 14 does not include disease due to non-vaccine HPV types.

AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

526 527

528

529 530

531 532

533

534

535

536

537

Effectiveness of GARDASIL in Prevention of Any HPV Type Related Genital Disease in Girls and Women 16 Through 26 Years of Age, Regardless of Current or Prior Infection with Vaccine or Non-Vaccine HPV Types

The impact of GARDASIL against the overall burden of dysplastic or papillomatous cervical, vulvar, and vaginal disease regardless of HPV detection, results from a combination of prophylactic efficacy against vaccine HPV types, disease contribution from vaccine HPV types present at time of vaccination, the disease contribution from HPV types not contained in the vaccine, and disease in which HPV was not detected.

Additional efficacy analyses were conducted in 2 populations: (1) a generally HPV-naïve population (negative to 14 common HPV types and had a Pap test that was negative for SIL [Squamous Intraepithelial Lesion] at Day 1), approximating a population of sexually-naïve girls and women and (2)

^{**}Includes all individuals who received at least 1 vaccination and who were HPV positive or had unknown HPV status at Day 1, to at least one vaccine HPV type. Case counting started at Day 1.

^{***}Out of the 148 AAHS control cases of 16/18 CIN 2/3, 2 women were missing serology or PCR results for Day 1.

[†]There is no expected efficacy since GARDASIL has not been demonstrated to provide protection against disease from vaccine HPV types to which a person has previously been exposed through sexual activity.

[‡]Includes all individuals who received at least 1 vaccination (regardless of baseline HPV status at Day 1). Case counting started at 1 month postdose 1.

^{*}Includes 2 AAHS control women with missing serology/PCR data at Day 1.

[§]Includes 1 woman with missing serology/PCR data at Day 1.

CI = Confidence Interval

the general study population of girls and women regardless of baseline HPV status, some of whom had HPV-related disease at Day 1.

Among generally HPV-naïve girls and women and among all girls and women in the study population

Among generally HPV-naïve girls and women and among all girls and women in the study population (including girls and women with HPV infection at Day 1), GARDASIL reduced the overall incidence of CIN 2/3 or AIS; of VIN 2/3 or VaIN 2/3; of CIN (any grade) or AIS; and of Genital Warts (Table 15). These reductions were primarily due to reductions in lesions caused by HPV types 6, 11, 16, and 18 in girls and women naïve (seronegative and PCR negative) for the specific relevant vaccine HPV type. Infected girls and women may already have CIN 2/3 or AIS at Day 1 and some will develop CIN 2/3 or AIS during follow-up, either related to a vaccine or non-vaccine HPV type present at the time of vaccination or related to a non-vaccine HPV type not present at the time of vaccination.

Table 15

Effectiveness of GARDASIL in Prevention of Any HPV Type Related Genital Disease in Girls and Women 16
Through 26 Years of Age. Regardless of Current or Prior Infection with Vaccine or Non-Vaccine HPV Types

Through 26 Years of Age, Regardless of Current or Prior Infection with Vaccine or Non-Vaccine HPV Types									
Endpoints Caused by Vaccine or	Analysis	GAR	DASIL	AAHS Control		% Reduction			
Non-vaccine HPV Types	Allalysis	N	Cases	N	Cases	(95% CI)			
	Prophylactic Efficacy*	4616	77	4680	136	42.7 (23.7, 57.3)			
CIN 2/3 or AIS	Girls and Women Regardless of Current or Prior Exposure to Vaccine or Non- Vaccine HPV Types**	8559	421	8592	516	18.4 (7.0, 28.4)			
	Prophylactic Efficacy*	4688	7	4735	31	77.1 (47.1, 91.5)			
VIN 2/3 and VaIN 2/3	Girls and Women Regardless of Current or Prior Exposure to Vaccine or Non- Vaccine HPV Types**	8688	30	8701	61	50.7 (22.5, 69.3)			
	Prophylactic Efficacy*	4616	272	4680	390	29.7 (17.7, 40.0)			
CIN (Any Grade) or AIS	Girls and Women Regardless of Current or Prior Exposure to Vaccine or Non- Vaccine HPV Types**	8559	967	8592	1189	19.1 (11.9, 25.8)			
	Prophylactic Efficacy*	4688	29	4735	169	82.8 (74.3, 88.8)			
Genital Warts	Girls and Women Regardless of Current or Prior Exposure to Vaccine or Non- Vaccine HPV Types**	8688	132	8701	350	62.5 (54.0, 69.5)			

^{*}Includes all individuals who received at least 1 vaccination and who had a Pap test that was negative for SIL [Squamous Intraepithelial Lesion] at Day 1 and were naïve to 14 common HPV types at Day 1. Case counting started at 1 month postdose 1.

**Includes all individuals who received at least 1 vaccination (regardless of baseline HPV status or Pap test result at Day 1). Case counting started at 1 month postdose 1.

AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

14.5 Population Impact in Boys and Men 16 Through 26 Years of Age

Effectiveness of GARDASIL in Prevention of HPV Types 6-, 11-, 16-, or 18-Related Anogenital Disease in Boys and Men 16 Through 26 Years of Age, Regardless of Current or Prior Exposure to Vaccine HPV Types

Study 5 included boys and men regardless of current or prior exposure to vaccine HPV types, and additional analyses were conducted to evaluate the impact of GARDASIL with respect to HPV 6-, 11-, 16-, and 18-related anogenital disease in these boys and men. Here, analyses included events arising among boys and men regardless of baseline PCR status and serostatus, including HPV infections that

CI = Confidence Interval

GARDASIL®

 [Human Papillomavirus Quadrivalent (Types 6, 11, 16, and 18) Vaccine, Recombinant]

were present at the start of vaccination as well as events that arose from infections that were acquired after the start of vaccination.

The impact of GARDASIL in boys and men regardless of current or prior exposure to a vaccine HPV type is shown in Table 16. Impact was measured starting at Day 1. Prophylactic efficacy denotes the vaccine's efficacy in boys and men who are naïve (PCR negative and seronegative) to the relevant HPV types at Day 1. Vaccine impact in boys and men who were positive for vaccine HPV infection, as well as vaccine impact among boys and men regardless of baseline vaccine HPV PCR status and serostatus are also presented. The majority of anogenital disease related to a vaccine HPV type detected in the group that received GARDASIL occurred as a consequence of HPV infection with the relevant HPV type that was already present at Day 1.

There was no clear evidence of protection from disease caused by HPV types for which boys and men were PCR positive regardless of serostatus at baseline.

Table 16
Effectiveness of GARDASIL in Prevention of HPV Types 6-, 11-, 16-, or 18-Related Anogenital
Disease in Boys and Men 16 Through 26 Years of Age, Regardless of Current or Prior Exposure to
Vaccine HPV Types

	Vaccine HPV Types AAHS % Reduction							
Endpoint	Analysis	GAR	DASIL		ntrol	(95% CI)		
Liiapoint	Analysis	N	Cases	N	Cases	(3070 01)		
	Prophylactic Efficacy*	1775	13	1770	54	76.3 (56.0, 88.1)		
External	HPV 6, HPV 11, HPV 16, and/or HPV 18 Positive at Day 1**	460	14	453	26	_***		
Genital Lesions	Boys and Men Regardless of Current or Prior Exposure to Vaccine or Non-Vaccine HPV Types [†]	1943	27	1937	80	66.7 (48.0, 79.3)		
	Prophylactic Efficacy*	1775	10	1770	49	80.0 (59.9, 90.9)		
	HPV 6, HPV 11, HPV 16, and/or HPV 18 Positive at Day 1**	460	14	453	25	***		
Condyloma	Boys and Men Regardless of Current or Prior Exposure to Vaccine or Non-Vaccine HPV Types [†]	1943	24	1937	74	68.1 (48.8, 80.7)		
	Prophylactic Efficacy*	1775	4	1770	5	20.7 (-268.4, 84.3)		
	HPV 6, HPV 11, HPV 16, and/or HPV 18 Positive at Day 1**	460	2	453	1	***		
PIN 1/2/3			6	1937	6	0.3 (-272.8, 73.4)		
	Prophylactic Efficacy*	259	9	261	39	76.9 (51.4, 90.1)		
	HPV 6, HPV 11, HPV 16, and/or HPV 18 Positive at Day 1**	103	29	116	38	***		
AIN 1/2/3	Boys and Men Regardless of Current or Prior Exposure to Vaccine or Non-Vaccine HPV Types [†]	275	38	276	77	50.3 (25.7, 67.2)		
	Prophylactic Efficacy*	259	7	261	19	62.5 (6.9, 86.7)		
	HPV 6, HPV 11, HPV 16, and/or HPV 18 Positive at Day 1**	103	11	116	20	_***		
AIN 2/3	Boys and Men Regardless of Current or Prior Exposure to Vaccine or Non-Vaccine HPV Types [†]	275	18	276	39	54.2 (18.0, 75.3)		

^{*}Includes all individuals who received at least 1 vaccination and who were HPV-naïve (i.e., seronegative and PCR negative) at Day 1 to the vaccine HPV type being analyzed. Case counting started at Day 1.

AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

571 572

573

574 575

576

577

578

579

580

Effectiveness of GARDASIL in Prevention of Any HPV Type Related Anogenital Disease in Boys and Men 16 Through 26 Years of Age, Regardless of Current or Prior Infection with Vaccine or Non-Vaccine HPV Types

The impact of GARDASIL against the overall burden of dysplastic or papillomatous anogenital disease regardless of HPV detection, results from a combination of prophylactic efficacy against vaccine HPV types, disease contribution from vaccine HPV types present at time of vaccination, the disease contribution from HPV types not contained in the vaccine, and disease in which HPV was not detected.

Additional efficacy analyses from Study 5 were conducted in 2 populations: (1) a generally HPV-naïve population that consisted of boys and men who are seronegative and PCR negative to HPV 6, 11, 16,

^{**}Includes all individuals who received at least 1 vaccination and who were HPV positive or had unknown HPV status at Day 1, to at least one vaccine HPV type. Case counting started at Day 1.

^{***}There is no expected efficacy since GARDASIL has not been demonstrated to provide protection against disease from vaccine HPV types to which a person has previously been exposed through sexual activity.

¹Includes all individuals who received at least 1 vaccination. Case counting started at Day 1.

CI = Confidence Interval

and 18 and PCR negative to HPV 31, 33, 35, 39, 45, 51, 52, 56, 58 and 59 at Day 1, approximating a population of sexually-naïve boys and men and (2) the general study population of boys and men regardless of baseline HPV status, some of whom had HPV-related disease at Day 1.

Among generally HPV-naïve boys and men and among all boys and men in Study 5 (including boys and men with HPV infection at Day 1), GARDASIL reduced the overall incidence of anogenital disease (Table 17). These reductions were primarily due to reductions in lesions caused by HPV types 6, 11, 16, and 18 in boys and men naïve (seronegative and PCR negative) for the specific relevant vaccine HPV type. Infected boys and men may already have anogenital disease at Day 1 and some will develop anogenital disease during follow-up, either related to a vaccine or non-vaccine HPV type present at the time of vaccination or related to a non-vaccine HPV type not present at the time of vaccination.

Table 17
Effectiveness of GARDASIL in Prevention of Any HPV Type Related Anogenital Disease in Boys and Men 16 Through 26 Years of Age, Regardless of Current or Prior Infection with Vaccine or Non-Vaccine HPV Types

Non-vaccine nev Types							
Endpoint	Analysis	GARDASIL		AAHS Control		% Reduction (95% CI)	
		N	Cases	N	Cases	(33 % 01)	
	Prophylactic Efficacy*	1275	7	1270	37	81.5 (58.0, 93.0)	
External Genital Lesions	Boys and Men Regardless of Current or Prior Exposure to Vaccine or Non-Vaccine HPV Types**	1943	38	1937	92	59.3 (40.0, 72.9)	
	Prophylactic Efficacy*	1275	5	1270	33	85.2 (61.8, 95.5)	
Condyloma	Boys and Men Regardless of Current or Prior Exposure to Vaccine or Non-Vaccine HPV Types**	1943	33	1937	85	61.8 (42.3, 75.3)	
	Prophylactic Efficacy*	1275	2	1270	4	50.7 (-244.3, 95.5)	
PIN 1/2/3	Boys and Men Regardless of Current or Prior Exposure to Vaccine or Non-Vaccine HPV Types**	1943	8	1937	7	-13.9 (-269.0, 63.9)	
	Prophylactic Efficacy*	129	12	126	28	54.9 (8.4, 79.1)	
AIN 1/2/3	Boys and Men Regardless of Current or Prior Exposure to Vaccine or Non-Vaccine HPV Types**	275	74	276	103	25.7 (-1.1, 45.6)	
	Prophylactic Efficacy*	129	8	126	18	52.5 (-14.8, 82.1)	
AIN 2/3	Boys and Men Regardless of Current or Prior Exposure to Vaccine or Non-Vaccine HPV Types**	275	44	276	59	24.3 (-13.8, 50.0)	

^{*}Includes all individuals who received at least 1 vaccination and who were seronegative and PCR negative at enrollment to HPV 6, 11, 16 and 18, and PCR negative at enrollment to HPV 31, 33, 35, 39, 45, 51, 52, 56, 58 and 59. Case counting started at Day 1.

AAHS Control = Amorphous Aluminum Hydroxyphosphate Sulfate

14.6 Overall Population Impact

The subject characteristics (e.g. lifetime sex partners, geographic distribution of the subjects) influence the HPV prevalence of the population and therefore the population benefit can vary widely.

The overall efficacy of GARDASIL will vary with the baseline prevalence of HPV infection and disease, the incidence of infections against which GARDASIL has shown protection, and those infections against which GARDASIL has not been shown to protect.

The efficacy of GARDASIL for HPV types not included in the vaccine (i.e., cross-protective efficacy) is a component of the overall impact of the vaccine on rates of disease caused by HPV. Cross-protective

^{**}Includes all individuals who received at least 1 vaccination. Case counting started at Day 1.

CI = Confidence Interval

601 efficacy was not demonstrated against disease caused by non-vaccine HPV types in the combined 602 database of the Study 3 and Study 4 trials. 603 GARDASIL does not protect against genital disease not related to HPV. One woman who received

GARDASIL does not protect against genital disease not related to HPV. One woman who received GARDASIL in Study 3 developed an external genital well-differentiated squamous cell carcinoma at Month 24. No HPV DNA was detected in the lesion or in any other samples taken throughout the study.

In 18,150 girls and women enrolled in Study 2, Study 3, and Study 4, GARDASIL reduced definitive cervical therapy procedures by 23.9% (95% CI: 15.2%, 31.7%).

14.7 Studies in Women 27 Through 45 Years of Age

Study 6 evaluated efficacy in 3253 women 27 through 45 years of age based on a combined endpoint of HPV 6-, 11-, 16- or 18-related persistent infection, genital warts, vulvar and vaginal dysplastic lesions of any grade, CIN of any grade, AIS, and cervical cancer. These women were randomized 1:1 to receive either GARDASIL or AAHS control. The efficacy for the combined endpoint was driven primarily by prevention of persistent infection. There was no statistically significant efficacy demonstrated for CIN 2/3, AIS, or cervical cancer. In post hoc analyses conducted to assess the impact of GARDASIL on the individual components of the combined endpoint, the results in the population of women naïve to the relevant HPV type at baseline were as follows: prevention of HPV 6-, 11-, 16- or 18-related persistent infection (80.5% [95% CI: 68.3, 88.6]), prevention of HPV 6-, 11-, 16- or 18-related CIN (any grade) (85.8% [95% CI: 52.4, 97.3]), and prevention of HPV 6-, 11-, 16- or 18-related genital warts (87.6% [95% CI: 7.3, 99.7]).

Efficacy for disease endpoints was diminished in a population impact assessment of women who were vaccinated regardless of baseline HPV status (full analysis set). In the full analysis set (FAS), efficacy was not demonstrated for the following endpoints: prevention of HPV 16- and 18-related CIN 2/3, AIS, or cervical cancer and prevention of HPV 6- and 11-related condyloma. No efficacy was demonstrated against CIN 2/3, AIS, or cervical cancer in the general population irrespective of HPV type (FAS any type analysis).

14.8 Immunogenicity

Assays to Measure Immune Response

The minimum anti-HPV titer that confers protective efficacy has not been determined.

Because there were few disease cases in individuals naïve (PCR negative and seronegative) to vaccine HPV types at baseline in the group that received GARDASIL, it has not been possible to establish minimum anti-HPV 6, anti-HPV 11, anti-HPV 16, and anti-HPV 18 antibody levels that protect against clinical disease caused by HPV 6, 11, 16, and/or 18.

The immunogenicity of GARDASIL was assessed in 23,951 9- through 45-year-old girls and women (GARDASIL N = 12,634; AAHS control or saline placebo N = 11,317) and 5417 9- through 26-year-old boys and men (GARDASIL N = 3109; AAHS control or saline placebo N = 2308).

Type-specific immunoassays with type-specific standards were used to assess immunogenicity to each vaccine HPV type. These assays measured antibodies against neutralizing epitopes for each HPV type. The scales for these assays are unique to each HPV type; thus, comparisons across types and to other assays are not appropriate.

Immune Response to GARDASIL

The primary immunogenicity analyses were conducted in a per-protocol immunogenicity (PPI) population. This population consisted of individuals who were seronegative and PCR negative to the relevant HPV type(s) at enrollment, remained HPV PCR negative to the relevant HPV type(s) through 1 month postdose 3 (Month 7), received all 3 vaccinations, and did not deviate from the study protocol in ways that could interfere with the effects of the vaccine.

Immunogenicity was measured by (1) the percentage of individuals who were seropositive for antibodies against the relevant vaccine HPV type, and (2) the Geometric Mean Titer (GMT).

In clinical studies in 16- through 26-year-old girls and women, 99.8%, 99.8%, 99.8%, and 99.4% who received GARDASIL became anti-HPV 6, anti-HPV 11, anti-HPV 16, and anti-HPV 18 seropositive, respectively, by 1 month postdose 3 across all age groups tested.

660

661

662

In clinical studies in 27- through 45-year-old women, 98.2%, 97.9%, 98.6%, and 97.1% who received GARDASIL became anti-HPV 6, anti-HPV 11, anti-HPV 16, and anti-HPV 18 seropositive, respectively, by 1 month postdose 3 across all age groups tested.

In clinical studies in 16- through 26-year-old boys and men, 98.9%, 99.2%, 98.8%, and 97.4% who received GARDASIL became anti-HPV 6, anti-HPV 11, anti-HPV 16, and anti-HPV 18 seropositive, respectively, by 1 month postdose 3 across all age groups tested.

Across all populations, anti-HPV 6, anti-HPV 11, anti-HPV 16, and anti-HPV 18 GMTs peaked at Month 7 (Table 18 and Table 19). GMTs declined through Month 24 and then stabilized through Month 36 at levels above baseline. Tables 20 and 21 display the persistence of anti-HPV cLIA geometric mean titers by gender and age group. The duration of immunity following a complete schedule of immunization with GARDASIL has not been established.

Table 18
Summary of Month 7 Anti-HPV cLIA Geometric Mean Titers in the PPI* Population of Girls and Women

Population	N**	n***	% Seropositive (95% CI)	GMT (95% CI) mMU [†] /mL
Anti-HPV 6			(0070 0.)	(0070 01) 111110 71112
9- through 15-year-old girls	1122	917	99.9 (99.4, 100.0)	929.2 (874.6, 987.3)
16- through 26-year-old girls and women	9859	3329	99.8 (99.6, 99.9)	545.0 (530.1, 560.4)
27- through 34-year-old women	667	439	98.4 (96.7, 99.4)	435.6 (393.4, 482.4)
35- through 45-year-old women	957	644	98.1 (96.8, 99.0)	397.3 (365.2, 432.2)
Anti-HPV 11				
9- through 15-year-old girls	1122	917	99.9 (99.4, 100.0)	1304.6 (1224.7, 1389.7)
16- through 26-year-old girls and women	9859	3353	99.8 (99.5, 99.9)	748.9 (726.0, 772.6)
27- through 34-year-old women	667	439	98.2 (96.4, 99.2)	577.9 (523.8, 637.5)
35- through 45-year-old women	957	644	97.7 (96.2, 98.7)	512.8 (472.9, 556.1)
Anti-HPV 16				
9- through 15-year-old girls	1122	915	99.9 (99.4, 100.0)	4918.5 (4556.6, 5309.1)
16- through 26-year-old girls and women	9859	3249	99.8 (99.6, 100.0)	2409.2 (2309.0, 2513.8)
27- through 34-year-old women	667	435	99.3 (98.0, 99.9)	2342.5 (2119.1, 2589.6)
35- through 45-year-old women	957	657	98.2 (96.8, 99.1)	2129.5 (1962.7, 2310.5)
Anti-HPV 18				
9- through 15-year-old girls	1122	922	99.8 (99.2, 100.0)	1042.6 (967.6, 1123.3)
16- through 26-year-old girls and women	9859	3566	99.4 (99.1, 99.7)	475.2 (458.8, 492.1)
27- through 34-year-old women	667	501	98.0 (96.4, 99.0)	385.8 (347.6, 428.1)
35- through 45-year-old women	957	722	96.4 (94.8, 97.6)	324.6 (297.6, 354.0)

^{*}The PPI population consisted of individuals who received all 3 vaccinations within pre-defined day ranges, did not have major deviations from the study protocol, met predefined criteria for the interval between the Month 6 and Month 7 visit, and were naïve (PCR negative and seronegative) to the relevant HPV type(s) (types 6, 11, 16, and 18) prior to dose 1 and through 1 month Postdose 3 (Month 7).

CI = Confidence Interval

GMT = Geometric Mean Titers

[†]mMU = milli-Merck Units

663

^{**}Number of individuals randomized to the respective vaccination group who received at least 1 injection.

^{***}Number of individuals contributing to the analysis.

cLIA = Competitive Luminex Immunoassay

Table 19 Summary of Month 7 Anti-HPV cl IA Geometric Mean Titers in the PPI* Population of Boys and Men

Summary of Month? Anti-HPV CLIA Geometric Mean Titlers in the PPT Population of Boys								
Population	N**	n***	% Seropositive (95% CI)	GMT (95% CI) mMU [†] /mL				
	14	- 11	(93 /6 CI)	(95% CI) IIIMO /IIIL				
Anti-HPV 6								
9- through 15-year-old boys	1072	884	99.9 (99.4, 100.0)	1037.5 (963.5, 1117.3)				
16- through 26-year-old boys and men	2026	1093	98.9 (98.1, 99.4)	447.8 (418.9, 478.6)				
Anti-HPV 11	Anti-HPV 11							
9- through 15-year-old boys	1072	885	99.9 (99.4, 100.0)	1386.8 (1298.5, 1481.0)				
16- through 26-year-old boys and men	2026	1093	99.2 (98.4, 99.6)	624.3 (588.4, 662.3)				
Anti-HPV 16								
9- through 15-year-old boys	1072	882	99.8 (99.2, 100.0)	6056.5 (5601.3, 6548.7)				
16- through 26-year-old boys and men	2026	1136	98.8 (97.9, 99.3)	2403.3 (2243.4, 2574.6)				
Anti-HPV 18								
9- through 15-year-old boys	1072	887	99.8 (99.2, 100)	1357.4 (1249.4, 1474.7)				
16- through 26-year-old boys and men	2026	1175	97.4 (96.3, 98.2)	402.6 (374.6, 432.7)				

^{*}The PPI population consisted of individuals who received all 3 vaccinations within pre-defined day ranges, did not have major deviations from the study protocol, met predefined criteria for the interval between the Month 6 and Month 7 visit, and were naïve (PCR negative and seronegative) to the relevant HPV type(s) (types 6, 11, 16, and 18) prior to dose 1 and through 1 month Postdose 3 (Month 7).

665

^{**}Number of individuals randomized to the respective vaccination group who received at least 1 injection.

^{***}Number of individuals contributing to the analysis. cLIA = Competitive Luminex Immunoassay

CI = Confidence Interval

GMT = Geometric Mean Titers

[†]mMU = milli-Merck Units

Table 20
Persistence of Anti-HPV cLIA Geometric Mean Titers in 9- Through 45-Year-Old Girls and Women

1 013131	J55 0			<u>ic Mean Titers in 9-</u> 26-Year-Old Girls		to 34-Year-Old		to 45-Year-Old
	9- to	15-Year-Old Girls			21-		35-	
A (-1.1A)/		(N* = 1122)		and Women		Women		Women
Assay (cLIA)/		· ·		(N* = 9859)		(N* = 667)		(N* = 957)
Time Point		GMT	4.4	GMT		GMT		GMT
	n**	(95% CI)	n**	(95% CI)	n**	(95% CI)	n**	(95% CI)
		mMU***/mL		mMU***/mL		mMU***/mL		mMU***/mL
Anti-HPV 6		1		T		T		
Month 07	917	929.2	3329	545.0	439	435.6	644	397.3
		(874.6, 987.3)		(530.1, 560.4)		(393.4, 482.4)		(365.2, 432.2)
Month 24	214	156.1	2788	109.1	421	70.7	628	69.3
		(135.6, 179.6)		(105.2, 113.1)		(63.8, 78.5)		(63.7, 75.4)
Month 36 [†]	356	129.4	-	-	399	79.5	618	81.1
-		(115.6, 144.8)				(72.0, 87.7)		(75.0, 87.8)
Month 48 [‡]	-	-	2514	73.8	391	58.8	616	62.0
				(70.9, 76.8)		(52.9, 65.3)		(57.0, 67.5)
Anti-HPV 11								
Month 07	917	1304.6	3353	748.9	439	577.9	644	512.8
		(1224.7, 1389.7)		(726.0, 772.6)		(523.8, 637.5)		(472.9, 556.1)
Month 24	214	218.0	2817	137.1	421	79.3	628	73.4
		(188.3, 252.4)		(132.1, 142.3)		(71.5, 87.8)		(67.4, 79.8)
Month 36 [†]	356	148.0	-	-	399	81.8	618	77.4
		(131.1, 167.1)				(74.3, 90.1)		(71.6, 83.6)
Month 48 [‡]	-	-	2538	89.4	391	67.4	616	62.7
				(85.9, 93.1)		(60.9, 74.7)		(57.8, 68.0)
Anti-HPV 16								
Month 07	915	4918.5	3249	2409.2	435	2342.5	657	2129.5
		(4556.6, 5309.1)		(2309.0, 2513.8)		(2119.1, 2589.6)		(1962.7, 2310.5)
Month 24	211	944.2	2721	442.6	416	285.9	642	271.4
		(804.4, 1108.3)		(425.0, 460.9)		(254.4, 321.2)		(247.1, 298.1)
Month 36 [†]	353	642.2	-	-	399	291.5	631	276.7
		(562.8, 732.8)				(262.5, 323.8)		(254.5, 300.8)
Month 48 [‡]	-	-	2474	326.2	394	211.8	628	192.8
				(311.8, 341.3)		(189.5, 236.8)		(176.5, 210.6)
Anti-HPV 18								
Month 07	922	1042.6	3566	475.2	501	385.8	722	324.6
		(967.6, 1123.3)		(458.8, 492.1)		(347.6, 428.1)		(297.6, 354.0)
Month 24	214	137.7	3002	50.8	478	31.8	705	26.0
		(114.8, 165.1)		(48.2, 53.5)		(28.1, 36.0)		(23.5, 28.8)
Month 36 [†]	357	87.0	-	-	453	32.1	689	27.0
		(74.8, 101.2)				(28.5, 36.3)		(24.5, 29.8)
Month 48 [‡]	-	-	2710	33.2	444	25.2	688	21.2
*A1 - A1				(31.5, 35.0)		(22.3, 28.5)		(19.2, 23.4)

^{*}N = Number of individuals randomized in the respective group who received at least 1 injection.

^{**}n = Number of individuals in the indicated immunogenicity population.

^{***}mMU = milli-Merck Units

[†]Month 37 for 9- to 15-year-old girls. No serology samples were collected at this time point for 16- to 26-year-old girls and women. [‡]Month 48/End-of-study visits for 16- to 26-year-old girls and women were generally scheduled earlier than Month 48. Mean visit timing was Month 44. The studies in 9- to 15-year-old girls were planned to end prior to 48 months and therefore no serology samples were collected.

cLIA = Competitive Luminex Immunoassay

CI = Confidence Interval

GMT = Geometric Mean Titers

Table 21
Persistence of Anti-HPV cLIA Geometric Mean Titers in 9- Through 26-Year-Old Boys and Men

Assay (cLIA)/ Time Point	9	- to 15-Year-Old Boys (N* = 1072)	16- to 26-Year-Old Boys and Men (N* = 2026)			
Assay (CLIA)/ Time Form	n**	GMT (95% CI) mMU***/mL	n**	GMT (95% CI) mMU***/mL		
Anti-HPV 6						
Month 07	884	1037.5 (963.5, 1117.3)	1094	447.2 (418.4, 477.9)		
Month 24	323	134.1 (119.5, 150.5)	907	80.3 (74.9, 86.0)		
Month 36 [†]	342	126.6 (111.9, 143.2)	654	72.4 (68.0, 77.2)		
Month 48 [‡]	-	-	-	-		
Anti-HPV 11			. "			
Month 07	885	1386.8 (1298.5, 1481.0)	1094	624.5 (588.6, 662.5)		
Month 24	324	188.5 (168.4, 211.1)	907	94.6 (88.4, 101.2)		
Month 36 [†]	342	148.8 (131.1, 169.0)	654	80.3 (75.7, 85.2)		
Month 48 [‡]	-	-	-	-		
Anti-HPV 16						
Month 07	882	6056.5 (5601.4, 6548.6)	1137	2401.5 (2241.8, 2572.6)		
Month 24	322	938.2 (825.0, 1067.0)	938	347.7 (322.5, 374.9)		
Month 36 [†]	341	708.8 (613.9, 818.3)	672	306.7 (287.5, 327.1)		
Month 48 [‡]	-	-	-	-		
Anti-HPV 18						
Month 07	887	1357.4 (1249.4, 1474.7)	1176	402.6 (374.6, 432.6)		
Month 24	324	131.9 (112.1, 155.3)	967	38.7 (35.2, 42.5)		
Month 36 [†]	343	113.0 (94.7, 135.0)	690	33.4 (30.9, 36.1)		
Month 48 [‡]	-	-	-	-		

^{*}N = Number of individuals randomized in the respective group who received at least 1 injection.

GMT = Geometric Mean Titers

669 670

671

672

673 674

675

676

677

678

679

680

Tables 18 and 19 display the Month 7 immunogenicity data for girls and women and boys and men. Anti-HPV responses 1 month postdose 3 among 9- through 15-year-old adolescent girls were non-inferior to anti-HPV responses in 16- through 26-year-old girls and women in the combined database of immunogenicity studies for GARDASIL. Anti-HPV responses 1 month postdose 3 among 9- through 15-year-old adolescent boys were non-inferior to anti-HPV responses in 16- through 26-year-old boys and men in Study 5.

On the basis of this immunogenicity bridging, the efficacy of GARDASIL in 9- through 15-year-old adolescent girls and boys is inferred.

GMT Response to Variation in Dosing Regimen in 18- Through 26-Year-Old Women

Girls and women evaluated in the PPE population of clinical studies received all 3 vaccinations within 1 year of enrollment. An analysis of immune response data suggests that flexibility of ±1 month for Dose

^{**}n = Number of individuals in the indicated immunogenicity population.

^{***}mMU = milli-Merck Units

[†]Month 36 time point for 16- to 26-year-old boys and men; Month 37 for 9- to 15-year-old boys.

[‡]The studies in 9- to 15-year-old boys and girls and 16- to 26-year-old boys and men were planned to end prior to 48 months and therefore no serology samples were collected.

cLIA = Competitive Luminex Immunoassay

CI = Confidence Interval

2 (i.e., Month 1 to Month 3 in the vaccination regimen) and flexibility of ±2 months for Dose 3 (i.e., Month
 4 to Month 8 in the vaccination regimen) do not impact the immune responses to GARDASIL.
 Duration of the Immune Response to GARDASIL

The duration of immunity following a complete schedule of immunization with GARDASIL has not been established. The peak anti-HPV GMTs for HPV types 6, 11, 16, and 18 occurred at Month 7. Anti-HPV GMTs for HPV types 6, 11, 16, and 18 were similar between measurements at Month 24 and Month 60 in Study 2.

14.9 Studies with RECOMBIVAX HB [hepatitis B vaccine (recombinant)]

The safety and immunogenicity of co-administration of GARDASIL with RECOMBIVAX HB [hepatitis B vaccine (recombinant)] (same visit, injections at separate sites) were evaluated in a randomized, double-blind, study of 1871 women aged 16 through 24 years at enrollment. The race distribution of the girls and women in the clinical trial was as follows: 61.6% White; 1.6% Hispanic (Black and White); 23.8% Other; 11.9% Black; 0.8% Asian; and 0.3% American Indian.

Subjects either received GARDASIL and RECOMBIVAX HB (n = 466), GARDASIL and RECOMBIVAX HB-matched placebo (n = 468), RECOMBIVAX HB and GARDASIL-matched placebo (n = 467) or RECOMBIVAX-matched placebo and GARDASIL-matched placebo (n = 470) at Day 1, Month 2 and Month 6. Immunogenicity was assessed for all vaccines 1 month post completion of the vaccination series.

Concomitant administration of GARDASIL with RECOMBIVAX HB [hepatitis B vaccine (recombinant)] did not interfere with the antibody response to any of the vaccine antigens when GARDASIL was given concomitantly with RECOMBIVAX HB or separately.

14.10 Studies with Menactra [Meningococcal (Groups A, C, Y and W-135) Polysaccharide Diphtheria Toxoid Conjugate Vaccine] and Adacel [Tetanus Toxoid, Reduced Diphtheria Toxoid and Acellular Pertussis Vaccine Adsorbed (Tdap)]

The safety and immunogenicity of co-administration of GARDASIL with Menactra [Meningococcal (Groups A, C, Y and W-135) Polysaccharide Diphtheria Toxoid Conjugate Vaccine] and Adacel [Tetanus Toxoid, Reduced Diphtheria Toxoid and Acellular Pertussis Vaccine Adsorbed (Tdap)] (same visit, injections at separate sites) were evaluated in an open-labeled, randomized, controlled study of 1040 boys and girls 11 through 17 years of age at enrollment. The race distribution of the subjects in the clinical trial was as follows: 77.7% White; 6.8% Hispanic (Black and White); 1.4% Multi-racial; 12.3% Black; 1.2% Asian; 0.2% Indian; and 0.4% American Indian.

One group received GARDASIL in one limb and both Menactra and Adacel, as separate injections, in the opposite limb concomitantly on Day 1 (n=517). The second group received the first dose of GARDASIL on Day 1 in one limb then Menactra and Adacel, as separate injections, at Month 1 in the opposite limb (n=523). Subjects in both vaccination groups received the second dose of GARDASIL at Month 2 and the third dose at Month 6. Immunogenicity was assessed for all vaccines 1 month post completion of the vaccination series (1 dose for Menactra and Adacel and 3 doses for GARDASIL).

Concomitant administration of GARDASIL with Menactra [Meningococcal (Groups A, C, Y and W-135) Polysaccharide Diphtheria Toxoid Conjugate Vaccine] and Adacel [Tetanus Toxoid, Reduced Diphtheria Toxoid and Acellular Pertussis Vaccine Adsorbed (Tdap)] did not interfere with the antibody response to any of the vaccine antigens when GARDASIL was given concomitantly with Menactra and Adacel or separately.

16 HOW SUPPLIED/STORAGE AND HANDLING

- All presentations for GARDASIL contain a suspension of 120 mcg L1 protein from HPV types 6, 11, 16, and 18 in a 0.5-mL dose. GARDASIL is supplied in vials and syringes.
- 726 Carton of one 0.5-mL single-dose vial. **NDC** 0006-4045-00.
- 727 Carton of ten 0.5-mL single-dose vials. **NDC** 0006-4045-41.
- 728 Carton of six 0.5-mL single-dose prefilled Luer Lock syringes with tip caps. **NDC** 0006-4109-09.
- 729 Store refrigerated at 2 to 8°C (36 to 46°F). Do not freeze. Protect from light.

GARDASIL®

[Human Papillomavirus Quadrivalent (Types 6, 11, 16, and 18) Vaccine, Recombinant]

9883616

GARDASIL should be administered as soon as possible after being removed from refrigeration.

GARDASIL can be out of refrigeration (at temperatures at or below 25°C/77°F), for a total time of not more than 72 hours.

17 PATIENT COUNSELING INFORMATION

[See FDA-Approved Patient Labeling.]

Inform the patient, parent, or guardian:

- Vaccination does not eliminate the necessity for women to continue to undergo recommended cervical cancer screening. Women who receive GARDASIL should continue to undergo cervical cancer screening per standard of care.
- Recipients of GARDASIL should not discontinue anal cancer screening if it has been recommended by a health care provider.
- GARDASIL has not been demonstrated to provide protection against disease from vaccine and non-vaccine HPV types to which a person has previously been exposed through sexual activity.
- Since syncope has been reported following vaccination sometimes resulting in falling with injury, observation for 15 minutes after administration is recommended.
- Vaccine information is required to be given with each vaccination to the patient, parent, or guardian.
- Information regarding benefits and risks associated with vaccination.
- GARDASIL is not recommended for use in pregnant women.
- Importance of completing the immunization series unless contraindicated.
- Report any adverse reactions to their health care provider.

750 751

752 753 754

755

733

734

735

736

737

738

739 740

741

742

743

744 745

746 747

748

749

Manuf. and Dist. by: Merck Sharp & Dohme Corp., a subsidiary of

MERCK & CO., INC., Whitehouse Station, NJ 08889, USA

Printed in USA 9883616

_

¹ Registered trademark of Merck Sharp & Dohme Corp., a subsidiary of Merck & Co., Inc. Copyright © 2006, 2009, 2010 Merck Sharp & Dohme Corp., a subsidiary of Merck & Co., Inc. All rights reserved