

PRINCIPAL DEPUTY UNDER SECRETARY OF DEFENSE

3015 DEFENSE PENTAGON WASHINGTON, DC 20301-3015

JUL 1 8 2011

MEMORANDUM FOR SECRETARIES OF THE MILITARY DEPARTMENTS DIRECTORS OF THE DEFENSE AGENCIES

SUBJECT: Document Streamlining – Program Protection Plan (PPP)

The September 14, 2010, Better Buying Power memorandum directed a review of the documentation required by Department of Defense Instruction (DoDI) 5000.02 in support of the acquisition process. This is the second in a series of document streamlining memoranda, following my April 20, 2011, direction on the streamlined Technology Development Strategy/Acquisition Strategy (TDS/AS) and Systems Engineering Plan outlines. I am directing the following actions for the PPP:

<u>Document Streamlining</u>: The PPP will be streamlined consistent with the attached annotated outline. The outline is designed to guide both program protection management and document preparation. It increases emphasis on early-phase planning activity and is specifically focused on information central to the purpose of the document. The new PPP reflects the integration of the Acquisition Information Assurance (IA) Strategy and recognizes Program Protection as the Department's holistic approach for delivering trusted systems.

PPP Review and Approval: Every acquisition program shall submit a PPP for Milestone Decision Authority review and approval at Milestone A and shall update the PPP at each subsequent milestone and the Full-Rate Production decision. While some programs may not have Critical Program Information, every program, including those with special access content, shall address mission-critical functions and components requiring risk management to protect warfighting capabilities. Per the TDS/AS outline described above, Program Protection information is no longer included in the TDS. The Acquisition IA Strategy shall continue to be reviewed and approved in accordance with DoDI 8500.1 and shall be included as an appendix to the PPP.

These actions constitute expected business practice and are effective immediately. The revised outline will be documented in the Defense Acquisition Guidebook and referenced in the next update to DoDI 5000.02. My point of contact is the Mr. Stephen Welby, Deputy Assistant Secretary of Defense for Systems Engineering, at 703-695-7417.

Frank Kendall

cc:

All CAEs

DCMA

DCAA

DCMO

DASD(PSA)

ARA

DPAP

Program Protection Plan Outline & Guidance

- VERSION 1.0
 - July 2011 •



Deputy Assistant Secretary of Defense

Systems Engineering

Introduction

This document provides an outline, content, and formatting guidance for the Program Protection Plan (PPP) required by DoDI 5000.02 and DoDI 5200.39. The outline structure and tables are considered minimum content that may be tailored to meet individual program needs.

General Guidance:

- Program Protection is the integrating process for managing risks to advanced technology and mission-critical system functionality from foreign collection, design vulnerability or supply chain exploit/insertion, and battlefield loss throughout the acquisition lifecycle.
- The purpose of the PPP is to help programs ensure that they adequately protect their technology, components, and information. This includes information that alone might not be damaging and might be unclassified, but that in combination with other information could allow an adversary to clone, counter, or defeat warfighting capability.
- The process of preparing a PPP is intended to help program offices consciously think through what needs to be protected and to develop a plan to provide that protection. Once a PPP is in place, it should guide program office security measures and be updated as threats and vulnerabilities change or are better understood.
- It is important that an end-to-end system view be taken when developing and executing the PPP. External, interdependent, or government furnished components that may be outside a program managers' control must be considered.
- The PPP should be a useable reference within the program for understanding and managing the full spectrum of program and system security activities throughout the acquisition lifecycle. The PPP is a plan, not a treatise; it should contain the information someone working on the program needs to carry out his or her Program Protection responsibilities and it should be generated as part of the program planning process.
- At Milestone A, it's possible that not all Program Protection information will be available. Complete the tables/sections with the information that is available and document the plan to update this information as more details become available. At minimum, a Milestone A PPP should include an initial criticality analysis, candidate CPI, potential countermeasures, and the Information Assurance Strategy. The Milestone B PPP should be a comprehensive document.
- The Acquisition Information Assurance (IA) Strategy must now be appended to the PPP. Some sections (e.g. IA threats, MAC level)) have been moved to the body of the PPP for document streamlining. Other sections (e.g. Program Information, schedule) may be included in the Acquisition IA Strategy or referenced when other documents contain that information (e.g. Acquisition Strategy). The information must be available but does not need to be repeated in multiple documents if it is accessible to users of the PPP.
- If a topic/section can be sufficiently covered in a sentence instead of a paragraph, write a sentence.
- Wherever possible, reference or point to other documents containing relevant information rather than duplicating the information in the PPP unless that information would be valuable to users of the plan. Do not simply repeat general policies unless that information would be valuable to the user of the plan.

- Appendices are required where relevant and appropriate. For example, every acquisition program must have an Information Assurance Strategy but not all acquisition programs will have an Anti-Tamper plan.
- <u>Classification Guidance</u>: The PPP should be classified by content. Threat and vulnerability information is commonly classified at SECRET or above. Detailed descriptions of CPI and critical functions/components may also be classified. The program Original Classification Authority is responsible for determining appropriate classification of the PPP and related information. The program may opt to reference some tables (e.g. threats, vulnerabilities) as classified appendices.

The office of primary responsibility for this guide is the Deputy Assistant Secretary of Defense for Systems Engineering (DASD(SE)). This office will continue to develop and coordinate updates to the guide as required, based on any future policy changes and customer feedback. To provide feedback, send e-mail to <u>dasd-se@osd.mil</u>.

[PROGRAM NAME] – [ACAT LEVEL]

PROGRAM PROTECTION PLAN VERSION [#]

SUPPORTING MILESTONE [MS] AND [APPROPRIATE PHASE NAME]

[DATE]	
*************	********
Undersecretary of Defense	Date
Acquisition, Technology, and Logistics	Buto
or appropriate Milestone Decision Authority for non-	ACAT ID programs]
• • • •	1 U 1

SUBMITTED BY

Name Program Manager	Date
CO	NCURRENCE
Name Program Executive Officer or Equivalent	Date
	NENT APPROVAL OSD approval (ACAT ID, IAM, etc.)]
Name Component Acquisition Executive	Date

Contents

1.0. Introduction – Purpose and Update Plan	. 7
1.1. Technology/System Description	. 7
1.2. Program Protection Responsibilities	. 7
2.0. Program Protection Summary	. 8
2.1. Schedule	
2.2. CPI and Critical Functions and Components Protection	. 8
3.0. Critical Program Information (CPI) and Critical Components	10
3.1. Identification Methodology	
3.2. Inherited CPI and Critical Components	10
3.3. Organic CPI and Critical Components	11
4.0. Horizontal Protection	12
5.0. Threats, Vulnerabilities, and Countermeasures	13
5.1. Threats	13
5.2. Vulnerabilities	14
5.3. Countermeasures	15
6.0. Other System Security-Related Plans and Documents	19
7.0. Program Protection Risks	20
8.0. Foreign Involvement	21
8.1. Defense Exportability Features	
9.0. Processes for Management and Implementation of PPP	22
9.1. Audits/Inspections	22
9.2. Engineering/Technical Reviews	22
9.3. Verification and Validation	22
9.4. Sustainment	
10.0. Processes for Monitoring and Reporting Compromises	23
11.0. Program Protection Costs	24
11.1. Security Costs	24
11.2. Acquisition and Systems Engineering Protection Costs	24
Appendix A: Security Classification Guide	25
Appendix B: Counterintelligence Support Plan	
Appendix C: Criticality Analysis	
Appendix D: Anti-Tamper Plan	
Appendix E: Acquisition Information Assurance (IA) Strategy	30

1.0. Introduction - Purpose and Update Plan

- Who will use the PPP?
- What is the plan to align Prime Contractor Program Protection Implementation Plan(s) (PPIP) with this PPP if they are written? What aspects of Program Protection will you ask the contractor to do?
- Summarize how the PPP will be updated and the criteria for doing so to include:
 - o Timing of PPP updates (e.g. prior to milestone, prior to export decision, following Systems Engineering Technical Review),
 - o Update authority
 - o Approval authority for different updates

Table 1.0-1 PPP Update Record (mandated)

Revision Number	Date	Changes	Approved By		

1.1. Technology/System Description

• Reference and include a link/direction to the appropriate acquisition document (e.g. Technology Development Strategy, Acquisition Strategy) that describes the technology/system and the project/program for developing it

Table 1.1-1: Program Information

Program Name	ACAT Level	Mission Assurance Category (MAC)	Last Milestone

1.2. Program Protection Responsibilities

- Who is responsible for Program Protection on the program? The chain of responsibility for all aspects of Program Protection should be clear.
- Include contact information for Program Protection leads/resources/SMEs. What aspects are each of these resources responsible for?
- For every countermeasure being implemented, identify who is responsible for execution. Include relevant PEO/SYSCOM contacts as well.

Table 1.2-1: Program Protection Responsibilities (mandated)(sample)

Title/Role	Name	Location	Contact Info
Program Manager			
Lead Systems Engineer			
Program Protection Lead	•		
Anti-Tamper Lead			
Info. Assurance Lead			
Software Assurance Lead			
SCRM Lead			

2.0. Program Protection Summary

2.1. Schedule

- A Program Protection schedule overlaid onto the program's master schedule (milestones, systems engineering technical reviews, etc.) includes:
 - o CPI and critical function/component identification/updates
 - o Acquisition Security Database (ASDB) updates
 - o Threat assessment requests
 - o Vulnerability assessments, red teams, etc.
 - o Security Audits/Inspections
 - o Engagement with Systems Engineering Technical Reviews (e.g. subsystem Preliminary Design Reviews for critical components)
 - o Countermeasure (e.g. Anti-Tamper, Information Assurance) testing/verification events
 - o Foreign involvement events (Exportability likelihood assessment, Cooperative Development, License Requests, etc.)

Expectation: Program Protection activities and events should be integrated in overall program scheduling.

2.2. CPI and Critical Functions and Components Protection

- Over the lifecycle of the program list all CPI and critical functions and components (including inherited and organic) mapped to the security disciplines of the countermeasures being applied in Table 2.2-1 below.
- For each countermeasure being implemented, list who is responsible for execution in Section 1 above.
- Table 2.2-1 is meant to summarize the protection scheme/plan for the program. The detail supporting this summary assessment (including the threats and vulnerabilities the selected countermeasures apply to) is planned for and documented in the subsequent sections of the document.

Table 2.2-1: CPI and Critical Components Countermeasure Summary (mandated) (sample)

# Protected Item					Countermeasures														
		(Inherited a	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	
	1	Algorithm QP	1	Х	X	X	X	X	X	Х		X					X	X	
	2	System Secu Configuration												X			ı		
CPI	3	Encryption Ha	ardware	Х	X	X	X	X	X	Х	X				X		X		
	4	IDS Policy Co	onfiguration	Х	X	X	Х	X	X	X	X						X		
	5	IDS Collected	d Data	Х	X	X	X	X	X	1				<u> </u>				1	
	6	KGV-136B		X	X	X	X			1		1				1			
40	7	iDirect M1D1 Card	T Hub-Line	Х	X	X	X	X	X	X	X				X	X	Х		
Critical Components	8	Advance Security Option (ASO)		X	X	X	X	X	X								X		
S	9																		•
)al	10	·			<u> </u>														
riţi	11																		
ľ	12				<u> </u>														
<u> </u>	13																		
L			KEY [Exa	mpl	es l	nclu	ded	: UF	PDA	TE 1	THIS	LIS	TAC	CORL	ING	TO PR	OGRA	AM]	
			General	CM	S			Res					nolog IS	ЭУ	•	Truste	ed Sys	tems	Design CMs
	Key X = Implemented I = Denotes protection already implemented if CPI is inherited 1 Personnel Se 2 Physical Sec 3 Operations S 4 Industrial Sec 5 Training 6 Information S 7 Foreign Disclosure/Agr			urity Secu curit Secu	rity y rity		8 Transportation Mgmt 9 Anti-Tamper 10 Dial-down Functionality				11 IA/Network Security 12 Communication Security 13 Software Assurance 14 Supply Chain Risk Management 15 System Security Engineering (SSE) 16 Other								

3.0. Critical Program Information (CPI) and Critical Components

3.1. Identification Methodology

Describe the methodology that will be used to identify CPI and mission critical functions and components in accordance with DoDI 5200.39¹ and DoDI 5000.02². Include:

- CPI identification and criticality analysis participants
- Timing of identification and updates to CPI and mission critical functions and components
- Process for identifying CPI, including inherited CPI.
- Approach for performing criticality analysis

Expectations: The end-to-end system must be considered, including items such as mission packages, government furnished components, and interdependent systems that may be outside a program manager's control. CPI and mission critical functions and components must be identified by a multi-disciplined group. Criticality analysis should be led by systems engineers and mission/operator representatives. CPI identification should be led by technology protection and security specialists. Information regarding these components and/or technologies must be considered for protection. Criticality analysis updates should be tied to Systems Engineering Technical Reviews. Inherited CPI is CPI from other acquisition programs, subsystems, or projects that are being incorporated or implemented into this program. Early in the program this section will reflect intentions, in updates it will provide a record of what has been done and any remaining work.

3.2. Inherited CPI and Critical Components

For any inherited CPI or critical components identified, summarize the approach to identifying and managing Program Protection risks.

- Identify the system the inherited item comes from. Will it be protected in the same way it was originally? Indicate variances in usage and plans for adjusting countermeasures as appropriate
- Identify the POC for answering questions about the inherited system(s). How will the program interact with them to ensure horizontal protection?

...

¹ http://www.dtic.mil/whs/directives/corres/pdf/520039p.pdf

² http://www.dtic.mil/whs/directives/corres/pdf/500002p.pdf

Table 3.2-1: Inherited CPI and Critical Components (mandated)

	Inherited Critical Item	Parent Program	Original Use	Planned Use	Variation in CMs?	Inherited Program POC
CPI						
Critical Components						

3.3. Organic CPI and Critical Components

As CPI and Critical Components are identified, track them in Table 3.3-1 below.

- Identify CPI and critical components, and summarize the effects or consequences if they are compromised. Track any adds/changes/deletions from this list over the course of the program with rationale for the edit.
- Where will the CPI and critical components be physically located during the acquisition lifecycle? Indicate whether or not contractor PPIPs are in place to flow protection requirements to contractor locations.
- Show traceability from mission-level documents (JCIDS Key Performance Parameters, Key System Attributes, etc.) and Critical Technology Elements (CTE) to the system architecture.

Table 3.3-1: Organic CPI and Critical Components (mandated)

	Assessment Date(s): 22 December 2009							
	CPI/CC	Consequence of Compromise	Status/ Date & Justification for Status Change	Traceable CTEs, KPPs, etc.	Export Control Areas	Physical Location	System Location PPIP Exists?	
CPI								
mponents								
Critical Components								

4.0. Horizontal Protection

- Who is responsible for horizontal protection?
- What other programs or weapons systems have CPI similar to this program?
- How will the program align protection of horizontal CPI? How will issues/disagreements about protection of horizontal CPI be resolved?
- When will the program create/update its Acquisition Security Database (ASDB) record? Expectations: The ASDB and associated registration/help information is located on SIPRNET at https://asdb.strikenet.navy.smil.mil. The program ASDB record should be created as soon as CPI is identified and updated periodically, as changes occur and at each subsequent milestone. Critical Functions/Components are not identified in the ASDB. After creating an ASDB record, programs should use the search capabilities to identify other programs with potentially similar CPI and follow up with their POCs to ensure horizontal protection.

Table 4.0-1: Horizontal Protection Information (mandated)

Date of Last ASDB U	pdate: Date of Next	ASDB Update:
CPI	Other Programs With Same or Similar CPI	Pending Adjudications of CPI? (Y/N)

5.0. Threats, Vulnerabilities, and Countermeasures

- Summarize any identified threats and vulnerabilities to CPI and critical functions/components in Table 5.0-1 below. Also identify any countermeasures selected to mitigate risks of compromise.
- This table should be updated over time as the information is identified; early in the program, identify the plan for obtaining this information in Sections 5.1-5.3 below.
- The numbers in the threat and vulnerabilities tables should correspond to the numbered rows in the threat table (5.1-2) and vulnerability table (5.2-1) below. All CPI and critical functions/components should be reflected in the table.

Table 5.0-1: Summary of CPI Threat, Vulnerabilities, and Countermeasures (mandated) (sample)

	CPI/CC (and CC supplier) Section 2.0	Threats Section 5.1	Vulnerabilities Section 5.2	Countermeasures Section 5.3
	Algorithm	4, 5, 7, 13- 15	1, 2	Anti-Tamper, SSE, Supply Chain Risk Management
CPI	System/Security Configuration	1,9, 14, 15	1	Secure storage of configuration; Supplier Assurance
	Encryption Hardware	2, 9, 14	2	Supply Chain Risk Management, NSA encryption device
cal	iDirect M1D1T Hub-line Card	2, 8, 9, 14	3	Communication Security; Software Assurance; SCRM
Critical Components	Cisco Router IOS with ASO	2, 6, 8, 9, 14	4	Supply Chain Risk Management

5.1. Threats

- Who is responsible for requesting and receiving threat products, and when will they be requested? Who in the intelligence community is responsible for supporting these requests? Include these contacts in the table in Section 1.2.
- What threat products will be requested for the program, when, and how will they be used?
- How frequently will threat products be updated?
- For threat products that have been received, what threats were identified?

Table 5.1-1: Threat Product References (mandated) (sample)

Title of Program-Specific or Other Threat Products Used for PPP Threat Analysis	Classification	Document Date	Organization(s) Producing the Product	Reference/ Link to Product					
Formal Threat Reports									
AFOSI Counterintelligence Assessment/Report	s	Jul 2002	HQ Office of Special Investigations						
AFOSI Department of Defense Threat Assessment	S	Dec 2007	Office of Special Investigations						
Capstone Threat Assessment (CTA)	U-S	Dec 2002	Defense Intelligence Agency						
Foreign Technology Assessment	U	Feb 2004	Counterintelligence Service						
Integrated Threat Assessment (ITA)	U-S	Jan 2002	Service for Special Assess Programs						
Technology Targeting Risk Assessment (TTRA)	U-S	Mar 2006	Defense Intelligence Agency						
System Threat Assessment Report (STAR)	S	Jan 2007	Defense Intelligence Agency						
Supply	Chain Threat As	sessments							
iDirect M1D1T Hub-line Card Assessment	TS/SCI	Apr 2009	Defense Intelligence Agency						
Cisco Router IOS with ASO	TS/SCI	Apr 2009	Defense Intelligence Agency						
Other Threat Documents									
Technology Collection Trends in the U.S. Defense Industry	U	Oct 2006	Defense Security Service						
Targeting U.S. Technologies	U	Feb 2007	Defense Security Service						

Expectations: As threat products are received, reference these documents in Table 5.1-1. This table should be comprehensive by Milestone B. For the Supply Chain Threat Assessments, document each critical component supplier (or potential supplier) that has been assessed. Summarize the threats identified in Table 5.1-2 below.

Table 5.1-2: Identified Threats (mandated) (sample)

T#	Threat	Description	Consequence of threat realization
1	HUMINT Collection	Country X is actively targeting CPI #3 at Location B.	Compromise of U.S. technology lead
2	Malicious Code Insertion	Country Y is known to have inserted malware into the software that Critical Component #2 depends on	Degraded or untrustworthy performance of targeting module
3			
4			

5.2. Vulnerabilities

• What vulnerabilities have been identified to date?

- How will the program identify new vulnerabilities (both system-level and in the development environment) to the CPI and mission-critical functions and components? Who is responsible for doing this, and with what frequency? Include the responsible person in the table in Section 1.2.
- How often will vulnerabilities be re-assessed?
- How will identified vulnerabilities be mitigated?
- Summarize the results of any vulnerability assessments, red teams, etc. performed to date in Table 5.2-1 below.

Table 5.2-1: Potential CPI and Critical Component Vulnerabilities (mandated)

V#	CPI/Critical Components	Identified Vulnerabilities
1		
2		-
3		

5.3. Countermeasures

- How will countermeasures be selected to protect CPI and critical functions/components? Who has the responsibility for their implementation? Include in the table in Section 1.2.
- How will contracts supporting the acquisition program incorporate protection requirements? Indicate the RFP Contract Line Item Number (CLIN) or Data Item Description (DID) that will be used to ensure that CPI and critical functions/components are protected in the development environment and on the system
- Succinctly describe the implementation of each countermeasure used to protect CPI and critical functions and components. Be specific: If SCRM Key Practices apply, describe which ones; if using Software Assurance techniques, explain which ones.
- Indicate planned implementation and actual implementation as the PPP evolves. Explain deviations from the plan.
- At a minimum, address implementation of the countermeasures in Section 5.3.1-5.3.5 or rationale for not using them:

5.3.1. Anti-Tamper (AT)

- Who will identify AT requirements and who is responsible for developing an AT plan? When will the AT Plan be completed? Include plans for engaging with the Component AT lead and Executive Agent for AT.
- If an AT Plan or AT Plan Waiver has been developed, submit as an Appendix.

5.3.2. Information Assurance (IA)

- Who is responsible for assessing the adequacy of IA countermeasures for CPI? What are the key IA schedule milestones?
- How will the appropriate implementation of IA protections for DoD information systems (other than the system being acquired) hosting CPI be ensured?
- How will the appropriate implementation of IA protections for contractor-owned information systems (or other non-DoD information systems) hosting CPI be ensured?

- o How will IA controls be negotiated with contractors?
- Who will ensure these controls are flowed down to subcontractors?
- o Who will keep an inventory of CPI hosted on contractor information systems?
- How will the appropriate implementation of IA protections for the system being acquired (if it includes on-board CPI) be ensured?.
 - o Include the Component CIO approved Acquisition IA Strategy as an Appendix. (See Appendix E description in this document)

Expectation: IA countermeasures planning should account for the system being acquired and any support information systems that may contain or host CPI and critical functions and components. The Acquisition IA Strategy documents the plan for implementing IA specifically on the system being acquired. IA controls can also be applied to protect CPI and critical functions and components as they are handled/transmitted across contractor or partner systems. For example, contractor development environments may host CPI and should be evaluated for protection.

5.3.3. Software Assurance

- Who is responsible for Software Assurance?
- How will software be designed and tested to assure protection of critical functionality and CPI?
 - o How will software architectures, environments, designs, and code be evaluated with respect to CVE (Common Vulnerabilities and Exposures), CAPEC (Common Attack Pattern Enumeration and Classification), and CWE (Common Weakness Enumeration)?
 - CVE Used to identify and coordinate SW vulnerabilities that enable various types of attacks.
 - CAPEC Used for the analysis of common destructive attack patterns
 - CWE Used to examine software architecture/design and source code for weaknesses.
- How will COTS software and software of unknown pedigree (i.e., software from sources buried in the supply chain) be protected and tested/vetted?
- How will the critical functions and CPI be protected in the operational system?
- How will the development environment be protected?
 - o List the development environment tools
- Who has access to the development environment?
 - o Who will be responsible for maintaining a list of cleared, US citizens as well as foreign nations/nationals that have access?
 - o Where will the list be stored, and how often will it be updated?
- P/A indicates planned/actual explain any deviations from planned testing/evaluation rates. For further details see key practices 9, 11, 16,17,19,21 and 23 in the "Key Practices and Implementation Guide for DOD Comprehensive National Cyber Initiative 11 Supply Chain Risk Management Pilot Program."

Table 5.3.3-1: Application of Software Assurance Countermeasures (sample)

	3.3.3-1. Арриса							
Software (CPI, critical function components, other software)	Static Analysis p/a (%)	Developm Design Inspect	ent Process Code Inspect p/a (%)	CVE p/a (%)	CAPEC p/a (%)	CWE p/a (%)	Pen Test	Test Coverage p/a (%)
Developmental CPI SW	100/80	Two Levels	100/80	100/60	100/60	100/60	Yes	75/50
Developmental Critical Function SW	100/80	Two Levels	100/80	100/70	100/70	100/70	Yes	75/50
Other Developmental SW	none	One level	100/65	10/0	10/0	10/0	No	50/25
COTS CPI and Critical Function SW	Vendor SwA	Vendor SwA	Vendor SwA	0	0	0	Yes	UNK
COTS (other than CPI and Critical Function) and NDI SW	No	No	No	0	0	0	No	UNK
		Operatio	nal System					
	Failover Multiple Supplier Redundancy (%)	Fault Isolation	Least Privilege		rstem Element Ing chec Isolation valid		ng /	SW load key
Developmental CPI SW	30	All	all	v	es	All		All
Developmental Critical Function SW	50	All	All	у	es	All		all
Other Developmental SW	none	Partial	none	N	one	all		all
COTS (CPI and CF) and NDI SW	none	Partial	All		one	Wrappers/ all		all
)evelopmen	t Environme					
SW Product	Source	Release testing	Generate code inspectio p/a (%)					
C Compiler	No	Yes	50/20					
Runtime libraries	Yes	Yes	70/none					
Automated test system	No	Yes	50/none					
Configuration management system	No	Yes	NA					
Database	No	Yes	50/none					
Development Environment Access Controlled access; Cleared personnel only								

5.3.4. Supply Chain Risk Management

- How will the program manage supply chain risks to CPI and critical functions and components?
- Explain how supply chain threat assessments will be used to influence system design, development environment, and procurement practices. Who has this responsibility? When will threat assessments be requested?

5.3.4.1.Trusted Suppliers

- Will any ASICs require trusted fabrication?
- How will the program make use of accredited trusted suppliers of integrated circuitrelated services?

5.3.4.2.Counterfeit Prevention

• What counterfeit prevention measures will be in place? How will the program mitigate the risk of counterfeit insertion during Operations and Maintenance?

5.3.5. System Security Engineering

- Who is responsible for system security engineering?
- Describe the linkage between system security engineering and the Systems Engineering Plan. How will system security design considerations be addressed?

5.3.6. General Countermeasures

• Summarize generic countermeasures or security activities in place that will/do apply to all program information/facilities/personnel and contribute to the protection of CPI and critical functions and components.

Table 5.3.6-1: Generic Program Countermeasures/Security Activities (mandated) (sample)

Туре	Detail
COMSEC (Development Environment)	Program Office Policy XX-XXX details program COMSEC countermeasures that are implemented at each government facility.
OPSEC	 Program Management Directive XX-XXX, will be tailored to satisfy specific security requirements of individual PROGRAM XYZ activities. The PROGRAM XYZ effort will comply fully with AFI 10-701, Operations Security The 669 AESS OPSEC Plan identifies all PROGRAM XYZ critical information.
Foreign Visit Program	 Program office personnel, other government organizations and contractors will adhere to approved visit procedures for the facility being visited.
CPI Protection Training	 The PM has instituted a tiered training program. Tier 1 is for general training of what CPI is and Tier II is for personnel who actually handle, store, develop and/or maintain CPI. All industry partners who have this PPP, implemented via DD Form 254, DoD Contract Security Classification Specifications, will implement this tier training.
Information Assurance (Development Environment)	 Prime Contractor network security architecture and configuration will be managed by the CIO. Network security procedures and countermeasures applicable to subnets containing Government CUI are available upon request. The program will comply with DTM 08-027 "Security of Unclassified DoD Information on Non-DoD Information Systems".
Secure System Administration	System configuration will be managed remotely by the DISA GNSC/TNC administrators.
Personnel Security	 The 669 AESS/SF is responsible for reviewing personnel security procedures at all 669 AESS and PROGRAM XYZ industry locations. This will be coordinated with DSS for industry reviews.
Industrial Security	 Security protection requirements will be incorporated into all PROGRAM XYZ contracting activities. Government procedures and instructions for preparing DD Forms 254, Contract Security Classification Specifications, will ensure that contractors are provided quality acquisition security, Program Protection, and classification management guidance.

6.0. Other System Security-Related Plans and Documents

• Reference relevant acquisition or system security-related documents.

Table 6.0-1: Other System Security-Related Plans and Documents (mandated) (sample)

Plan	Organization	Link/POC
Counterintelligence Support Plan (CISP)	Service CI	
Test & Evaluation Master Plan	TEMP Approval Authority	
Systems Engineering Plan	SEP Approval Authority	
Software Secure Coding Standards	Contractor SW Design Lead	
Trusted Software Design Techniques	Contractor SW Design Lead	
Secure Software Process Standards	Contractor SW Design Lead	
Foreign Travel Training	Contractor FSO	
Foreign Visit Processes	Contractor FSO	

Expectation: If Technical Assistance Agreements, Memoranda of Agreement (MOA), Memoranda of Understanding (MOU), or other similar agreements have been signed, reference or link to them in an additional table with a description of the key commitments.

7.0. Program Protection Risks

- Describe how Program Protection risks (cost, schedule, technical) will be integrated with overall Program risk management.
- Discuss the approach to identifying residual risks of CPI and critical function and component compromise after countermeasure implementation. Are there any unmitigated risks?
- Include a risk cube and mitigation plan for the top Program Protection risks.

8.0. Foreign Involvement

- Summarize any international activities and any plans for, or known, foreign cooperative development or sales of the system.
- What are the applicable Technology Security and Foreign Disclosure (TS&FD) processes that will provide guidance to safeguard the sharing of program information with allies and friends?
- Have previous generations of this system been sold to foreign allies? Have similar systems been sold?
- How will export requirements/restrictions be addressed if a foreign customer/sale is identified? Who is responsible for implementing these requirements?

Table 8.0-1: Foreign Involvement Summary (mandated) (sample)

This system is US	This system is US ONLY (Yes, No, Unknown): Yes							
This system is intended for CONUS deployment only (Yes, No, Unknown): No. It is intended for global deployment.								
Approved Disclos	Approved Disclosures of CPI: TBD							
Technology Asses	Technology Assessment/Control Plan Exists (Y/N/Unknown): No							
Type of Foreign Involvement (IC/FMS/DCS) Likelihood of Foreign (Perceived/Established) Involvement (H, M, L) Status Agreements/Licenses in Place (if known) Involved?								
IC	М	Perceived	None	Pangaea				

8.1. Defense Exportability Features

- What are the impacts and risks to the program from foreign military sales and direct commercial sales? Who is responsible for managing these?
- Will the program be a viable DEF candidate to develop, plan, and design an export variant during the research and development phase?
- Include a hotlink to the relevant DEF discussion in the Technology Development Strategy and/or Acquisition Strategy.

9.0. Processes for Management and Implementation of PPP

There are several types of checking PPP implementation. Audits/inspections are used to ensure compliance with applicable laws, regulations, and policies. Engineering reviews are used to ensure that system security requirements are identified, traceable and met throughout the acquisition lifecycle.

9.1. Audits/Inspections

• Summarize the timing of security audits/inspections. How will contractor security requirements be enforced? Who is responsible for this?

9.2. Engineering/Technical Reviews

- How will system security requirements be addressed in Systems Engineering Technical Reviews, functional/physical configuration audits, etc? Who is responsible for this?
- What Program Protection entry/exit criteria will be used for these reviews?

9.3. Verification and Validation

- Explain how the program will integrate system security requirements testing into the overall test and evaluation strategy. Who is responsible for this?
- Link to relevant discussion in T&E documents.

9.4. Sustainment

- How will Program Protection requirements and considerations be managed in sustainment? Who is responsible for this?
- Link to the relevant Lifecycle Sustainment Plan (LCSP) language.

10.0. Processes for Monitoring and Reporting Compromises

- Summarize the plan/procedure for responding to a CPI compromise or a supply chain exploit.
- What constitutes a compromise or exploit? Who is notified if one occurs? Define what constitutes an Anti-Tamper event or a Supply Chain exploit.

11.0. Program Protection Costs

• Indicate where Program Protection costs are to be accounted for in the SCP and program budget. Who has the responsibility to ensure Program Protection costs are estimated and included in the programs budget and contracts?

11.1. Security Costs

Indicate/Estimate the security costs associated with Program Protection that exceed normal NISPOM costs.

- Will SCIFs or other secure facilities require construction specifically for CPI protection?
- If limited access rosters or other similar instruments will be used, how much will development and maintenance of the roster cost?

Table 11.1-1: Security Costs above NISPOM Requirements (mandated)

Cost Type	Activity	Responsibility	Cost
Total cost			\$\$

11.2. Acquisition and Systems Engineering Protection Costs

- Indicate/estimate the design, engineering, development, testing, and other costs related to Program Protection activities (e.g. CPI identification, criticality analysis, vulnerability assessment, countermeasure development, etc.).
- How will non-recurring engineering costs associated with Program Protection requirements be accounted for?
- Describe the programs approach to using projected cost-benefit tradeoffs in countermeasure selection.
- As costs are identified, summarize in table 11.2-1 below.

Table 11.2-1: Acquisition and Systems Engineering Protection Costs (mandated) (sample)

Cost Type	Activity	Responsibility	Cost	
Engineering	Incorporate CA, protection design alternative trade studies and system security requirements into RFP scope	PM	\$\$	
	CA and design alternative trade study	Prime Contractor	\$\$	
	Anti-tamper	Prime contractor	\$\$	
	Trusted Foundry	Supplier	\$\$	
Supply Chain Risk Management	Evaluate supplier lists	PM, DIA TAC	\$\$	
Verification &Validation	Software code analysis	PM, Gunter AFB	\$\$	
	V&V for anti-tamper architecture	AF AT	\$\$	
	Verify satisfaction of system security requirements	PM, verification team	\$\$	
Sustainment	Anti-counterfeit measures	Depot	\$\$	
Total			\$\$	

Appendix A: Security Classification Guide

The SCG may be referenced or pointed to rather than included in the document.

Appendix B: Counterintelligence Support Plan The CISP may be referenced or pointed to rather than included in the document.

Appendix C: Criticality Analysis

- Document the results of the most recent Criticality analysis in table C-1 below. The CA should be updated regularly (e.g. at each SE Technical Review)
- Early in the program lifecycle, the CA may only be able to identify missions or missions and critical functions.
- Criticality should be assessed in terms of relative impact on the system's ability to complete its mission if the component fails. Level I is total mission failure, Level II is significant/unacceptable degradation, Level III is partial/acceptable, and Level IV is negligible.

Table C-1: Criticality analysis Part 1 - Missions, Functions, and Components

Missions	Missions Critical Functions Supporting Logic-Bearing Comp (Include HW/SW/Firmware		System Impact (I, II, III, IV)
	Data Eurian	Processor X	II
	Data Fusion	SW Module Y	I
Mission 1		Database Z	III
WIISSIUII I	Fire Control	SW Module A	I
	Critical Function 3	Processor X	II
	Critical Function 5	Sensor A	IV
<u> </u>		Sensor B	I
	Critical Function 4	Radar A	I
Mission 2		Processor Y	II
Mission 2	Critical Function 5	SW Module B	II
	G.W. I.R. W. C	Database Y	Ш
	Critical Function 6	Integrated Circuit A	I
Missis 2	Data Paris	Processor X	II
Mission 3	Data Fusion	SW Module Y	I

The Level I and Level II components identified in Table C-1 were then prioritized for resources and attention based on a variety of factors. The results of this prioritization are in the table C-2 below.

Note: Additional blank columns are provided for program-specific analysis/prioritization variables. The program manager is ultimately responsible for prioritizing effort/resources against critical components, and the purpose of this table is to capture the rationale for that prioritization.

Table C-2: Critical Component Prioritization

Critical Components	Missions Supported (#)	Source of Item or Component		Integrated Circuit?	Specifically Designed	•••	•••	Overall CC Priority
(Level I/II from Part1)		COTS/GOTS/ Developmental Item	Legacy/ New	(Y/N If Y: what kind?)	for Military Use? (Y/N)			(H/M/L)
Processor X	2	Development	New	Y, ASIC	Y			Н
SW Module Y	2	Development	Legacy	N	Y			М
SW Module A	1	COTS	Legacy	N	N			М
Sensor B	1	GOTS	Legacy	N	Y			M
Radar A	1	GOTS	New	N	Y			M
Processor Y	1	Development	New	N	Y			Н
SW Module B	1	COTS	Legacy	N	N			M
Integrated Circuit A	1	Development	New	Y: ASIC	Y			Н

Appendix D: Anti-Tamper PlanNot all programs will require an Anti-Tamper plan. If an Anti-Tamper Plan is required, use the template developed by the Executive Agent for Anti-Tamper.

Appendix E: Acquisition Information Assurance (IA) Strategy Foreword

- 1. The reuse of existing documentation in preparing the Acquisition IA Strategy document is strongly encouraged where practicable. For example, the integrated schedule in the program's approved Acquisition Strategy may be referenced in the "program information" section. However, it is incumbent on the submitting PMO to ensure that any such information is readily available to the document review/approval chain by providing copies of the referenced documents in conjunction with the Acquisition IA Strategy document. References to draft documents are not sufficient to support approval of the Acquisition IA Strategy document.
- 2. In consideration of the different levels of maturity relative to acquisition phases, and to encourage brevity and focus, the following page limitations are imposed:
- Acquisition IA Strategies are not required for Material Development Decisions (MDD)
- Acquisition IA Strategies for Milestone A 7 pages
- Acquisition IA Strategies for Milestone B or C − 15 pages
- Acquisition IA Strategies for Full Rate Production (FRP) or Full Deployment Decision (FDD) - 15 pages

Tables of content, acronym lists, signature sheets and executive summaries are not required, but if included do not count against the page limitations.

- 3. As part of the Acquisition Documentation Streamlining effort, DOASD(I&IA) has reached agreement with DASD(SE) proposal that the Acquisition IA Strategy be included as an appendix to the Program Protection Plan. This does not affect the current review and approval process for the Acquisition IA Strategy document, since only documents that have been approved by the Component CIO and reviewed by the DoD CIO (with a formal review report issued by ODASD(I&IA)/DIAP)) will be appended to the PPP.
- 4. Program offices should utilize the template on the following page in the preparation of their Acquisition IA Strategy documents.
- 5. IA threats must be included in the PPP threat table.

(PROGRAM NAME) Acquisition IA Strategy

I. Program and System Description.

A. Program Information (Applicable to MS A, B, C, FRP/FDD)

Identify the Acquisition Category (ACAT) of the program. Identify current acquisition life-cycle phase and next milestone decision. Include a graphic representation of the program's schedule.

B. System Description (Applicable to MS A, B, C, FRP/FDD)

Include or reference a high-level overview of the specific system being acquired. Characterize the system as to type of DoD information system (AIS application, enclave, platform IT interconnection, outsourced IT-based process), or as Platform IT without a GIG interconnection. Include or reference a graphic (block diagram) that shows the major elements/subsystems that make up the system or service being acquired, and how they fit together. Describe or reference the system's function, and summarize significant information exchange requirements and interfaces with other IT or systems, as well as primary databases supported. Identify the primary network(s) to which the system will be connected (e.g. NIPRNET, SIPRNET, JWICS, etc.). Include a description or graphic defining the system's accreditation boundary.

II. Information Assurance Requirements.

A. Sources (Applicable to MS A, B, C, FRP/FDD)

1. Mission Assurance Category and Confidentiality Level

Identify the system's MAC and Confidentiality Level as specified in the applicable capabilities document, or as determined by the system User Representative on behalf of the information owner, in accordance with DoD Instruction 8500.2. If the system architecture includes multiple segments with differing MAC and CL combinations, include a table listing all segments and their associated MAC and CL designations, as well as a brief rationale for the segmentation.

2. Baseline IA Control Sets

Identify the applicable sets of Baseline IA Controls from DoD Instruction 8500.2 that will be implemented. A listing of individual controls is not required.

3. ICD/CDD/CPD specified requirements

List any specific IA requirements identified in the approved governing capability documents (e.g. Initial Capabilities Document, Capability Development Document or Capability Production Document).

4. Other requirements

List any IA requirements specified by other authority (i.e. Component mandated).

B. IA Budget (scope and adequacy) (Applicable to MS A, B, C, FRP/FDD)

Describe how IA requirements for the full life cycle of the system (including costs associated with certification and accreditation activities) are included and visible in the overall program budget. Include a statement of the adequacy of the IA budget relative to requirements.

III. System IA Approach (high level): (Applicable to MS B, C, FRP/FDD)

A. System IA technical approach

Describe, at a high level, the IA technical approach that will secure the system.

B. Protections provided by external system or infrastructure

List any protection to be provided by external systems or infrastructure (i.e. inherited control solutions).

IV. Acquisition of IA Capabilities and Support: (Applicable to MS B, C, FRP/FDD)

Describe how the program's contracting/procurement approach is structured to ensure each of the following IA requirements are included in system performance and technical specifications, RFPs and contracts (as well as other agreements, such as SLAs, MOAs, etc.) early in the acquisition life cycle.

- A. System IA capabilities (COTS or developmental contract)
- B. GFE/GFM (external programs)
- C. System IA capabilities as services (commercial or government)
- D. Information Systems Security Engineering (ISSE) services
- E. IA professional support services to the program (commercial or government, including C&A support)

Confirm that program contracts/agreements communicate the requirement for personnel performing IA roles to be trained and appropriately certified in IA in accordance with DoD Directive 8570.01.

V. System Certification and Accreditation:

- A. Process (DIACAP; DCID 6/3, etc) (Applicable to MS A, B, C, FRP/FDD) Identify the specific Certification and Accreditation (C&A) process to be employed (e.g., DoD Information Assurance Certification and Accreditation Process (DIACAP), NSA/CSS Information Systems Certification and Accreditation Process (NISCAP), DoD Intelligence Information System (DODIIS)). If the system being acquired is platform IT without a GIG interconnection, describe any Component level process imposed to allocate and validate IA requirements prior to operation.
- **B.** Key role assignments (Applicable to MS B, C, FRP/FDD)

 Include the name, title, and organization of the Designated Accrediting Authority,

 Certification Authority, and User Representative for each separately accreditable system being acquired by the program.
- C. C&A timeline (Applicable to MS B, C, FRP/FDD)

Include a timeline graphic depicting the target initiation and completion dates for the C&A process, highlighting the issuance of Interim Authorization to Test (IATT), Interim Authorization to Operate (IATO), and Authorizations to Operate (ATOs). Normally, it is expected that an ATO will be issued prior to operational test and evaluation.

D. C&A approach (Applicable to MS B, C, FRP/FDD)

If the program is pursuing an evolutionary acquisition approach, describe how each increment will be subjected to the certification and accreditation process. If the C&A process has started, identify significant activity completed, and whether an ATO or IATO was issued. If the system being acquired will process, store, or distribute Sensitive Compartmented Information, compliance with Intelligence Community Directive (ICD) 503 "Intelligence Community Information Technology Systems Security Risk Management, Certification and Accreditation" is required, and the plan for compliance should be addressed. Do not include reiterations of the generic descriptions of the C&A process (e.g. general descriptions of the DIACAP activities from DoDI 8510.01 and the DIACAP Knowledge Service).

VI. IA Testing:

A. Testing Integration (Applicable to MS A, B, C, FRP/FDD)

Confirm that all IA testing and C&A activities will be/has been integrated into the program's test and evaluation planning, and incorporated into program testing documentation, such as the Test and Evaluation Strategy and Test and Evaluation Master Plan.

B. Product Evaluation (e.g. IA/IA enabled products) (Applicable to MS B, C, FRP/FDD)

List any planned incorporation of IA products/IA enabled products into the system being acquired, and address any acquisition or testing impacts stemming from compliance with NSTISSP Number 11.

C. Cryptographic Certification (Applicable to MS B, C, FRP/FDD)

List any planned incorporation of cryptographic items into the system being acquired, and address any acquisition or testing impacts stemming from the associated certification of the items by NSA or NIST prior to connection or incorporation.

VII. IA Shortfalls: (Include as classified annex if appropriate) (Applicable to MS B, C, FRP/FDD)

A. Significant IA shortfalls

Identify any significant IA shortfalls, and proposed solutions and/or mitigation strategies. Specify the impact of failure to resolve any shortfall in terms of program resources and schedule, inability to achieve threshold performance, and system or warfighter vulnerability. If applicable, identify any Acquisition Decision Memoranda that cite IA issues. If no significant issues apply, state "None".

B. Proposed solutions and/or mitigation strategies

If the solution to an identified shortfall lies outside the control of the program office, include a recommendation identifying the organization with the responsibility and authority to address the shortfall.

VIII. Policy and Guidance: (Applicable to MS A, B, C, FRP/FDD)

List the primary policy guidance employed by the program in preparing and executing the Acquisition IA Strategy, including the DoD 8500 series, and DoD Component, Major Command/Systems Command, or program-specific guidance, as applicable. The Information Assurance Support Environment web site provides an actively maintained list of relevant statutory, Federal/DoD regulatory, and DoD guidance that may be applicable. Capsule descriptions of the issuances are not required.

IX. Point of Contact: (Applicable to MS A, B, C, FRP/FDD)

Include the name and contact information for the program management office individual responsible for the Acquisition IA Strategy document. It is recommended that the system's Information Assurance Manager (as defined in DoD Instruction 8500.2) be the point of contact.