Drug and Alcohol Services Information System

The DASIS Report

Treatment Admissions in Urban and Rural Areas Involving Abuse of Narcotic Painkillers: 2002 Update


In Brief

- Treatment admission rates for narcotic painkillers increased by 155 percent between 1992 and 2002
- Increases in treatment admission rates for abuse of narcotic painkillers occurred at all levels of urbanization and were greatest in more rural areas
- The proportions of narcotic painkiller treatment admissions taking the drugs orally or inhaling them increased while the proportion injecting them decreased

reatment admission rates involving abuse of narcotic painkillers increased in publicly funded substance abuse treatment facilities across the nation between 1992 and 2002. In 1992, the treatment admission rate for narcotic painkiller abuse in the United States was 14 admissions per 100,000 persons aged 12 or older. By 1997, the admission rate had increased by 12 percent, to 15 per 100,000, and by 2002, it had increased by another 129 percent, to 35 per 100,000.

This report examines narcotic pain-killer treatment admission rates per 100,000 persons aged 12 or older at five urbanization levels for 1992, 1997, and 2002. Data are from the Treatment Episode Data Set (TEDS), an annual compilation of data on the 1.9 million annual admissions to publicly funded substance abuse treatment.

The DASIS Report is published periodically by the Office of Applied Studies, Substance Abuse and Mental Health Services Administration (SAMHSA). All material appearing in this report is in the public domain and may be reproduced or copied without permission from SAMHSA. Additional copies of this report or other reports from the Office of Applied Studies are available on-line: http://www.oas.samhsa.gov. Citation of the source is appreciated.



Source: 2002 SAMHSA Treatment Episode Data Set (TEDS).

U.S. counties and county equivalents were assigned to one of five urbanization levels according to the classification scheme developed by the National Center for Health Statistics (NCHS):³

Large Central Metro—County in a Metropolitan Statistical Area (MSA) of 1 million or more population that contained all or part of the largest central city of the MSA

Large Fringe Metro—County in a large MSA (1 million or more population) that did not contain any part of the largest central city of the MSA

Small Metro—County in an MSA with less than 1 million population

Non-Metro with City—County not in an MSA but with a city of 10,000 or more population

Non-Metro without City— County not in an MSA and without a city of 10,000 or more population

TEDS records indicate where persons entered treatment, not their area of residence. As not all counties have substance abuse treatment facilities, people may seek treatment at an urbanization level different from where they live. Table 1 compares the levels of urbanization of all counties in the United States with that of counties with treatment facilities reporting narcotic painkiller admissions to TEDS.

Treatment Admission Rates for Narcotic Painkillers


Treatment admission rates for narcotic painkillers increased between 1992 and 2002 in the United States as a whole and at all levels of urbanization (Figure 1). Between 1992 and 2002, the narcotic painkiller treatment admission rate in the United States increased by 155 percent (Figure 2). The increase was smallest in large central metropolitan areas (58 percent), and greatest in the most rural areas, non-metropolitan areas without a city (269 percent).

Route of Administration

The route of administration among narcotic painkiller abusers entering treatment changed between 1992 and 2002. In 1992, 66 percent of admissions for narcotic painkiller abuse took the drugs orally, 25 percent injected them, and 3 percent inhaled them. By 2002, the proportion taking the drugs orally had increased to 77 percent, the

Table 1. County Urbanization in the United States and in Counties Reporting Narcotic Painkiller Admissions to TEDS

	United		
	States	TEDS	
No. of Counties	3,100	1,700	
	Percent		
Large Central Metro	2%	4%	
Large Fringe Metro	8%	12%	
Small Metro	17%	24%	
Non-Metro with City	15%	23%	
Non-Metro without City	58%	37%	



Large

Metro

Central Fringe

Small

Metro

Metro

with City

Metro

without

Table 2. Route of Administration of Narcotic Painkillers, by Urbanization: 1992 and 2002

	Total U.S.	Large Central Metro	Large Fringe Metro	Small Metro	Non-Metro with City	Non-Metro without City	
Percent							
1992							
Oral	66	61	74	64	71	76	
Injection	25	25	19	29	21	17	
Inhalatio	n 3	4	3	2	3	2	
Other	6	10	4	5	5	5	
Total	100	100	100	100	100	100	
2002							
Oral	77	82	83	74	71	69	
Injection	11	7	7	14	15	14	
Inhalatio	n 8	5	7	9	9	12	
Other	4	6	3	3	5	5	
Total	100	100	100	100	100	100	

proportion injecting had fallen to 11 percent, and the proportion inhaling had increased to 8 percent.

Total

U.S.

Large

Metro

In large central metropolitan areas, the proportion of narcotic painkiller treatment admissions injecting the drugs decreased by 18 percentage points and the proportion taking the drugs orally increased by 21 percentage points. In fringe and small metropolitan areas, the proportions injecting decreased by 12 and 15 percentage points, respectively. In these areas, the proportions taking narcotic painkillers orally and the proportions inhaling them increased by 4 to 10 percentage points. Nonmetropolitan areas with cities exhibited a 6-percentage point shift from injection to inhalation.

In the most rural areas (nonmetropolitan areas without cities), the proportions of narcotic painkiller treatment admissions who took the drugs orally or injected them both decreased (7 and 3 percentage points, respectively). In these areas, the proportion who inhaled the drugs increased from 2 percent in 1992 to 12 percent in 2002.

End Notes

Narcotic painkiller admissions include all admissions reporting primary, secondary, or tertiary abuse of narcotic painkillers such as codeine, hydrocodone, hydromorphone, meperidine, morphine, oxycodone, pentazocine, propoxyphene, and any other drug with morphine-like effects. Admissions involving abuse of heroin and/or methadone, unless reported in addition to abuse of narcotic painkillers, are excluded from this report.

- ² States continually review the quality of their data processing. When systematic errors are identified, States may revise or replace historical TEDS data files. While this process represents an improvement in the data system, the historical statistics in this report will differ slightly from those in earlier reports.
- ³ Eberhardt, M.S., Ingram, D.D., Makuc, D.M., et al. (2001). *Urban and Rural Health Chartbook. Health, United States, 2001*. Hyattsville, MD: National Center for Health Statistics.

The Drug and Alcohol Services Information System (DASIS) is an integrated data system maintained by the Office of Applied Studies, Substance Abuse and Mental Health Services Administration (SAMHSA). One component of DASIS is the Treatment Episode Data Set (TEDS). TEDS is a compilation of data on the demographic characteristics and substance abuse problems of those admitted for substance abuse treatment. The information comes primarily from facilities that receive some public funding. Information on treatment admissions is routinely collected by State administrative systems and then submitted to SAMHSA in a standard format. Approximately 1.9 million records are included in TEDS each year. TEDS records represent admissions rather than individuals, as a person may be admitted to treatment more than once.

The DASIS Report is prepared by the Office of Applied Studies, SAMHSA; Synectics for Management Decisions, Inc., Arlington, Virginia; and RTI, Research Triangle Park, North Carolina.

Information and data for this issue are based on data reported to TEDS through March 1, 2004.

Access the latest TEDS reports at: http://www.oas.samhsa.gov/dasis.htm

Access the latest TEDS public use files at: http://www.oas.samhsa.gov/SAMHDA.htm

Other substance abuse reports are available at: http://www.oas.samhsa.gov



U.S. DEPARTMENT OF HEALTH AND HUMAN SERVICES Substance Abuse and Mental Health Services Administration Office of Applied Studies www.samhsa.gov