




Department of the Treasury
Internal Revenue Service

Publication 721

Cat. No. 46713C

Tax Guide to U.S. Civil Service Retirement Benefits

For use in preparing
2011 Returns



**Get forms and other information
faster and easier by:**

Internet IRS.gov

Contents

What's New	1
Reminders	1
Introduction	2
Part I. General Information	3
Part II. Rules for Retirees	4
Part III. Rules for Disability Retirement and Credit for the Elderly or the Disabled	16
Part IV. Rules for Survivors of Federal Employees	18
Part V. Rules for Survivors of Federal Retirees	23
How To Get Tax Help	25
Simplified Method Worksheet	28
Lump-Sum Payment Worksheet	29
Index	30

What's New

The IRS has created a page on IRS.gov for information about Publication 721, at www.irs.gov/pub721. Information about any future developments affecting Publication 721 (such as legislation enacted after we release it) will be posted on that page.

Reminders

Disaster related tax relief. Special rules apply to the use of retirement funds by qualified individuals who suffered an economic loss as a result of the storms and tornadoes that began on May 4, 2007 in the Kansas disaster area and the severe storms in the Midwestern disaster areas. See Publication 575, for information on these special rules.

Rollovers. You can roll over certain amounts from the CSRS, FERS, or TSP, to a tax-sheltered annuity plan (403(b) plan) or a state or local government section 457 deferred compensation plan. See [Rollover Rules](#) in Part II.

Rollovers by surviving spouse. You may be able to roll over a distribution you receive as the surviving spouse of a deceased employee or retiree into a qualified retirement plan or an IRA. See [Rollover Rules](#) in Part II.

Thrift Savings Plan (TSP) beneficiary participant accounts. If you are the spouse beneficiary of a decedent's TSP account, you have the option of leaving the death benefit payment in a TSP account in your own name (a beneficiary participant account). The amounts in the beneficiary participant account are neither taxable or reportable until you choose to make a withdrawal, or otherwise receive a distribution from the account.

Benefits for public safety officer's survivors. A survivor annuity received by the spouse, former spouse, or child of a public safety officer killed in the line of duty generally will be excluded from the recipient's income. For more information, see [Dependents of public safety officers](#) in Part IV.

Uniformed services Thrift Savings Plan (TSP) accounts. If you have a uniformed services TSP account, it may include contributions from combat zone pay. This pay is tax-exempt and contributions attributable to that pay are tax-exempt when they are distributed from the uniformed services TSP account. However, any earnings on those contributions are subject to tax when they are distributed. The statement you receive from the TSP will separately state the total amount of your distribution and the amount of your taxable distribution for the year. If you have both a civilian and a uniformed services TSP account, you should apply the rules discussed in this publication separately to each account. You can get more information from the TSP website, www.tsp.gov, or the TSP Service Office.

Photographs of missing children. The Internal Revenue Service is a proud partner with the National Center for Missing and Exploited Children. Photographs of missing children selected by the Center may appear in this publication on pages that would otherwise be blank. You can help bring these children home by looking at the photographs and calling 1-800-THE-LOST (1-800-843-5678) if you recognize a child.

Introduction

This publication explains how the federal income tax rules apply to civil service retirement benefits received by retired federal employees (including those disabled) or their survivors. These benefits are paid primarily under the Civil Service Retirement System (CSRS) or the Federal Employees' Retirement System (FERS).

Tax rules for annuity benefits. Part of the annuity benefits you receive is a tax-free recovery of your contributions to the CSRS or FERS. The rest of your benefits are taxable. If your annuity starting date is after November 18, 1996, you must use the Simplified Method to figure the taxable and tax-free parts. If your annuity starting date is before November 19, 1996, you generally could have chosen to use the Simplified Method or the General Rule. See Part II, [Rules for Retirees](#).

Thrift Savings Plan. The Thrift Savings Plan (TSP) provides federal employees with the same savings and tax benefits that many private employers offer their employees. This plan is similar to private sector 401(k) plans. You can defer tax on part of your pay by having it contributed to your account in the plan. The contributions and earnings on them are not taxed until they are distributed to you. See [Thrift Savings Plan](#) in Part II.

Comments and suggestions. We welcome your comments about this publication and your suggestions for future editions.

You can write to us at the following address:

Internal Revenue Service
Individual and Specialty Forms and Publications
Branch
SE:W:CAR:MP:T:I
1111 Constitution Ave. NW, IR-6526
Washington, DC 20224

We respond to many letters by telephone. Therefore, it would be helpful if you would include your daytime phone number, including the area code, in your correspondence.

You can email us at taxforms@irs.gov. Please put "Publications Comment" on the subject line. You can also send us comments from www.irs.gov/formspubs/. Select "Comment on Tax Forms and Publications" under "Information About."

Although we cannot respond individually to each comment received, we do appreciate your feedback and will consider your comments as we revise our tax products.

Ordering forms and publications. Visit www.irs.gov/formspubs/ to download forms and publications, call 1-800-829-3676, or write to the address below and receive a response within 10 days after your request is received.

Internal Revenue Service
1201 N. Mitsubishi Motorway
Bloomington, IL 61705-6613

Tax questions. If you have a tax question, check the information available on IRS.gov or call 1-800-829-1040. We cannot answer tax questions sent to either of the above addresses.

Useful Items

You may want to see:

Publication

- 524** Credit for the Elderly or the Disabled
- 575** Pension and Annuity Income
- 590** Individual Retirement Arrangements (IRAs)
- 939** General Rule for Pensions and Annuities

Form (and Instructions)

- CSA 1099R** Statement of Annuity Paid
- CSF 1099R** Statement of Survivor Annuity Paid
- W-4P** Withholding Certificate for Pension or Annuity Payments
- 1099-R** Distributions From Pensions, Annuities, Retirement or Profit-Sharing Plans, IRAs, Insurance Contracts, etc.
- 5329** Additional Taxes on Qualified Plans (including IRAs) and Other Tax-Favored Accounts

See [How To Get Tax Help](#) near the end of this publication for information about getting publications and forms.

Part I

General Information

This part of the publication contains information that can apply to most recipients of civil service retirement benefits.

Refund of Contributions

If you leave federal government service or transfer to a job not under the CSRS or FERS and you are not eligible for an immediate annuity, you can choose to receive a refund of the money in your CSRS or FERS retirement account. The refund will include both regular and voluntary contributions you made to the fund, plus any interest payable.

If the refund includes only your contributions, none of the refund is taxable. If it includes any interest, the interest is taxable unless you roll it over directly into another qualified plan or a traditional individual retirement arrangement (IRA). If you do not have the Office of Personnel Management (OPM) transfer the interest to an IRA or other plan in a direct rollover, tax will be withheld at a 20% rate. See [Rollover Rules](#) in Part II for information on how to make a rollover.



Interest is not paid on contributions to the CSRS for service after 1956 unless your service was for more than 1 year but not more than 5 years. Therefore, many employees who withdraw their contributions under the CSRS do not get interest and do not owe any tax on their refund.

If you do not roll over interest included in your refund, it may qualify as a lump-sum distribution eligible for capital gain treatment or the 10-year tax option. If you separate from service before the calendar year in which you reach age 55, it may be subject to an additional 10% tax on early distributions. For more information, see *Lump-Sum Distributions and Tax on Early Distributions* in Publication 575.



A lump-sum distribution is eligible for capital gain treatment or the 10-year tax option only if the plan participant was born before January 2, 1936.

Tax Withholding and Estimated Tax

The CSRS or FERS annuity you receive is subject to federal income tax withholding, unless you choose not to have tax withheld. OPM will tell you how to make the choice. The choice for no withholding remains in effect until you change it. These withholding rules also apply to a disability annuity, whether received before or after minimum retirement age.

If you choose not to have tax withheld, or if you do not have enough tax withheld, you may have to make estimated tax payments.



You may owe a penalty if the total of your withheld tax and estimated tax does not cover most of the tax shown on your return. Generally, you will owe the penalty for 2012 if the additional tax you must pay with your return is \$1,000 or more and more than 10% of

the tax to be shown on your 2012 return. For more information, including exceptions to the penalty, see chapter 4 of Publication 505, Tax Withholding and Estimated Tax.

Form CSA 1099R. Form CSA 1099R is mailed to you by OPM each year. It will show any tax you had withheld. File a copy of Form CSA 1099R with your tax return if any federal income tax was withheld.



You also can view and download your Form CSA 1099R by visiting the OPM website at www.servicesonline.opm.gov. To log in, you will need your retirement CSA claim number and your personal identification number.

Choosing no withholding on payments outside the United States. The choice for no withholding generally cannot be made for annuity payments to be delivered outside the United States and its possessions.

To choose no withholding if you are a U.S. citizen or resident alien, you must provide OPM with your home address in the United States or its possessions. Otherwise, OPM has to withhold tax. For example, OPM must withhold if you provide a U.S. address for a nominee, trustee, or agent (such as a bank) to whom the benefits are to be delivered, but you do not provide your own U.S. home address.

If you do not provide a home address in the United States or its possessions, you can choose not to have tax withheld only if you certify to OPM that you are not a U.S. citizen, a U.S. resident alien, or someone who left the United States to avoid tax. But if you so certify, you may be subject to the 30% flat rate withholding that applies to nonresident aliens. For details, see Publication 519, U.S. Tax Guide for Aliens.

Withholding certificate. If you give OPM a Form W-4P-A, Election of Federal Income Tax Withholding, you can choose not to have tax withheld or you can choose to have tax withheld. The amount of tax withheld depends on your marital status, the number of withholding allowances, and any additional amount you designate to be withheld. If you do not make either of these choices, OPM must withhold as if you were married with three withholding allowances.



To change the amount of tax withholding or to stop withholding, call OPM's Retirement Information Office at 1-888-767-6738 (customers within the local Washington, D.C. calling area must call 202-606-0500). No special form is needed. You will need your retirement CSA or CSF claim number, your social security number, and your personal identification number (PIN) when you call. If you have TTY/TDD equipment call 1-877-255-7408. If you need a PIN, call OPM's Retirement Information Office.



You also can change the amount of withholding or stop withholding online by visiting the OPM website at www.servicesonline.opm.gov. You will need your retirement CSA or CSF claim number and your PIN.

Withholding from certain lump-sum payments. If you leave the federal government before becoming eligible to retire and you apply for a refund of your CSRS or FERS contributions, or you die without leaving a survivor eligible

for an annuity, you or your beneficiary will receive a distribution of your contributions to the retirement plan plus any interest payable. Tax will be withheld at a 20% rate on the interest distributed. However, tax will not be withheld if you have OPM transfer (roll over) the interest directly to your traditional IRA or other qualified plan. If you have OPM transfer (roll over) the interest directly to a Roth IRA, the entire amount will be taxed in the current year. However, for any rollover in 2010, there are special rules. See [Special rules for 2010 rollovers from qualified retirement plans to Roth IRAs](#) in Part II. Because no income tax will be withheld at the time of the transfer, you may want to increase your withholding or pay estimated taxes. See [Rollover Rules](#) in Part II. If you receive only your contributions, no tax will be withheld.

Withholding from Thrift Savings Plan payments. Generally, a distribution that you receive from the TSP is subject to federal income tax withholding. The amount withheld is:

- 20% if the distribution is an eligible rollover distribution, or
- 10% if it is a nonperiodic distribution other than an eligible rollover distribution, or
- An amount determined as if you were married with three withholding allowances, unless you submit a withholding certificate (Form W-4P), if it is a periodic distribution.

However, you usually can choose not to have tax withheld from TSP payments other than eligible rollover distributions. By January 31 after the end of the year in which you receive a distribution, the TSP will issue Form 1099-R showing the total distributions you received in the prior year and the amount of tax withheld.

For a detailed discussion of withholding on distributions from the TSP, see Important Tax Information About Payments From Your TSP Account, available from your agency personnel office or from the TSP.



The above document is also available in the "Forms & Publications" section of the TSP website at www.tsp.gov.

Estimated tax. Generally, you must make estimated tax payments for 2012 if you expect to owe at least \$1,000 in tax for 2012 (after subtracting your withholding and credits) and you expect your withholding and your credits to be less than the smaller of:

- 90% of the tax to be shown on your income tax return for 2012, or
- 100% of the tax shown on your 2011 income tax return (110% of that amount if the adjusted gross income shown on the return was more than \$150,000 (\$75,000 if your filing status for 2012 will be married filing separately)). The return must cover all 12 months.

You do not have to pay estimated tax for 2012 if you were a U.S. citizen or resident alien for all of 2011 and you had no tax liability for the full 12-month 2011 tax year.

Form 1040-ES contains a worksheet that you can use to help you figure your estimated tax payments. For more information, see chapter 2 in Publication 505.

Filing Requirements

If your gross income, including the taxable part of your annuity, is less than a certain amount, you generally do not have to file a federal income tax return for that year. The gross income filing requirements for the tax year are in the instructions to Form 1040, 1040A, or 1040EZ.

Children. If you are the surviving spouse of a federal employee or retiree and your monthly annuity check includes a survivor annuity for one or more children, each child's annuity counts as his or her own income (not yours) for federal income tax purposes.

If your child can be claimed as a dependent, treat the taxable part of his or her annuity as unearned income when applying the filing requirements for dependents.

Form CSF 1099R. Form CSF 1099R will be mailed to you by January 31 after the end of each tax year. It will show the total amount of the annuity you received in the past year. It also should show, separately, the survivor annuity for a child or children. Only the part that is each individual's survivor annuity should be shown on that individual's Form 1040 or 1040A.

If your Form CSF 1099R does not show separately the amount paid to you for a child or children, attach a statement to your return, along with a copy of Form CSF 1099R, explaining why the amount shown on the tax return differs from the amount shown on Form CSF 1099R.



You also can view and download your Form CSF 1099R by visiting the OPM website at www.servicessonline.opm.gov. To log in you will need your retirement CSF claim number and personal identification number.



You may request a Summary of Payments, showing the amounts paid to you for your child(ren), from OPM by calling OPM's Retirement Information Office at 1-888-767-6738 (customers within the local Washington, D.C. calling area must call 202-606-0500). You will need your CSF claim number and your social security number when you call.

Taxable part of annuity. To find the taxable part of a retiree's annuity when applying the filing requirements, see the discussion in Part II, [Rules for Retirees](#), or Part III, [Rules for Disability Retirement and Credit for the Elderly or the Disabled](#), whichever applies. To find the taxable part of each survivor annuity when applying the filing requirements, see the discussion in Part IV, [Rules for Survivors of Federal Employees](#), or Part V, [Rules for Survivors of Federal Retirees](#), whichever applies.

Part II Rules for Retirees

This part of the publication is for retirees who retired on nondisability retirement.



If you retired on disability before you reached your minimum retirement age, see Part III, [Rules for Disability Retirement and Credit for the Elderly or the Disabled](#). However, on the day after you reach your minimum retirement age use the rules in this section to report your disability retirement and begin recovering your cost.

Annuity statement. The statement you received from OPM when your CSRS or FERS annuity was approved shows the commencing date (the annuity starting date), the gross monthly rate of your annuity benefit, and your total contributions to the retirement plan (your cost). You will use this information to figure the tax-free recovery of your cost.

Annuity starting date. If you retire from federal government service on a regular annuity, your annuity starting date is the commencing date on your annuity statement from OPM. If something delays payment of your annuity, such as a late application for retirement, it does not affect the date your annuity begins to accrue or your annuity starting date.

Gross monthly rate. This is the amount you were to get after any adjustment for electing a survivor's annuity or for electing the lump-sum payment under the alternative annuity option (if either applied) but before any deduction for income tax withholding, insurance premiums, etc.

Your cost. Your monthly annuity payment contains an amount on which you have previously paid income tax. This amount represents part of your contributions to the retirement plan. Even though you did not receive the money that was contributed to the plan, it was included in your gross income for federal income tax purposes in the years it was taken out of your pay.

The cost of your annuity is the total of your contributions to the retirement plan, as shown on your annuity statement from OPM. If you elected the alternative annuity option, it includes any deemed deposits and any deemed redeposits that were added to your lump-sum credit. (See [Lump-sum credit](#) under *Alternative Annuity Option*, later.)

If you repaid contributions that you had withdrawn from the retirement plan earlier, or if you paid into the plan to receive full credit for service not subject to retirement deductions, the entire repayment, including any interest, is a part of your cost. You cannot claim an interest deduction for any interest payments. You cannot treat these payments as voluntary contributions; they are considered regular employee contributions.

Recovering your cost tax free. How you figure the tax-free recovery of the cost of your CSRS or FERS annuity depends on your annuity starting date.

- If your annuity starting date is before July 2, 1986, either the [Three-Year Rule](#) or the [General Rule](#) (both discussed later) applies to your annuity.
- If your annuity starting date is after July 1, 1986, and before November 19, 1996, you could have chosen to use either the [General Rule](#) or the [Simplified Method](#) (discussed later).
- If your annuity starting date is after November 18, 1996, you must use the [Simplified Method](#).

Under both the General Rule and the Simplified Method, each of your monthly annuity payments is made up of two parts: the tax-free part that is a return of your cost, and the taxable part that is the amount of each payment that is more than the part that represents your cost (unless such payment is used for purposes discussed under [Distributions Used To Pay Insurance Premiums for Public Safety Officers](#), later). The tax-free part is a fixed dollar amount. It remains the same, even if your annuity is increased. Generally, this rule applies as long as you receive your annuity. However, see [Exclusion limit](#), later.

Choosing a survivor annuity after retirement. If you retired without a survivor annuity and report your annuity under the Simplified Method, do not change your tax-free monthly amount even if you later choose a survivor annuity.

If you retired without a survivor annuity and report your annuity under the General Rule, you must figure the tax-free part of your annuity using a new exclusion percentage if you later choose a survivor annuity and take reduced annuity payments. To figure the new exclusion percentage, reduce your cost by the amount you previously recovered tax free. Figure the expected return as of the date the reduced annuity begins. For details on the General Rule, see Publication 939.

Canceling a survivor annuity after retirement. If you retired with a survivor annuity payable to your spouse upon your death and you notify OPM that your marriage has ended, your annuity might be increased to remove the reduction for a survivor benefit. The increased annuity does not change the cost recovery you figured at the annuity starting date. The tax-free part of each annuity payment remains the same.



For more information about choosing or canceling a survivor annuity after retirement, contact OPM's Retirement Information Office at 1-888-767-6738 (customers within the local Washington, D.C. calling area must call 202-606-0500).

Exclusion limit. Your annuity starting date determines the total amount of annuity payments that you can exclude from income over the years.

Annuity starting date after 1986. If your annuity starting date is after 1986, the total amount of annuity income that you (or the survivor annuitant) can exclude over the years as a return of your cost cannot exceed your total cost. Annuity payments you or your survivors receive after the total cost in the plan has been recovered are generally fully taxable.

Example. Your annuity starting date is after 1986 and you exclude \$100 a month under the Simplified Method. If your cost is \$12,000, the exclusion ends after 10 years (120 months). Thereafter, your entire annuity is generally fully taxable.

Annuity starting date before 1987. If your annuity starting date is before 1987, you can continue to take your monthly exclusion figured under the General Rule or Simplified Method for as long as you receive your annuity. If you chose a joint and survivor annuity, your survivor can continue to take that same exclusion. The total exclusion may be more than your cost.

Deduction of unrecovered cost. If your annuity starting date is after July 1, 1986, and the cost of your annuity has not been fully recovered at your (or the survivor annuitant's) death, a deduction is allowed for the unrecovered cost. The deduction is claimed on your (or your survivor's) final tax return as a miscellaneous itemized deduction (not subject to the 2%-of-adjusted-gross-income limit). If your annuity starting date is before July 2, 1986, no tax benefit is allowed for any unrecovered cost at death.

Simplified Method

If your annuity starting date is after November 18, 1996, you must use the Simplified Method to figure the tax-free part of your CSRS or FERS annuity. (OPM has figured the taxable amount of your annuity shown on your Form CSA 1099R using the Simplified Method.) You could have chosen to use either the Simplified Method or the General Rule if your annuity starting date is after July 1, 1986, but before November 19, 1996. The Simplified Method does not apply if your annuity starting date is before July 2, 1986.

Under the Simplified Method, you figure the tax-free part of each full monthly payment by dividing your cost by a number of months based on your age. This number will differ depending on whether your annuity starting date is before November 19, 1996, or after November 18, 1996. If your annuity starting date is after 1997 and your annuity includes a survivor benefit for your spouse, this number is based on your combined ages.

Worksheet A. Use [Worksheet A. Simplified Method](#) (near the end of this publication), to figure your taxable annuity. Be sure to keep the completed worksheet. It will help you figure your taxable amounts for later years.



Instead of Worksheet A, you generally can use the Simplified Method Worksheet in the instructions for Form 1040, Form 1040A, or Form 1040NR to figure your taxable annuity. However, you must use [Worksheet A](#) and [Worksheet B](#) in this publication if you chose the [alternative annuity option](#), discussed later.

Line 2. See [Your cost](#), earlier, for an explanation of your cost in the plan. If your annuity starting date is after November 18, 1996, and you chose the [alternative annuity option](#) (explained later), you must reduce your cost by the tax-free part of the lump-sum payment you received.

Line 3. The number you enter on line 3 is the number of monthly annuity payments under the plan. Find the appropriate number from one of the tables at the bottom of the worksheet. If your annuity starting date is after 1997, use:

- Table 1 for an annuity without a survivor benefit, or
- Table 2 for an annuity with a survivor benefit.

If your annuity starting date is before 1998, use Table 1.

Line 6. If you retired before 2011, the amount previously recovered tax free that you must enter on line 6 is the total amount from line 10 of last year's worksheet. If your annuity starting date is before November 19, 1996, and you chose the alternative annuity option, this amount includes the tax-free part of the lump-sum payment you received.

Example. Bill Smith retired from the Federal Government on March 31, 2011, under an annuity that will provide a survivor benefit for his wife, Kathy. His annuity starting date is April 1, 2011, the annuity is paid in arrears, and he received his first monthly annuity payment on May 1, 2011. He must use the Simplified Method to figure the tax-free part of his annuity benefits.

Bill's monthly annuity benefit is \$1,000. He had contributed \$31,000 to his retirement plan and had received no distributions before his annuity starting date. At his annuity starting date, he was 65 and Kathy was 57.

Bill's completed Worksheet A is shown on the next page. To complete line 3, he used Table 2 at the bottom of the worksheet and found that 310 is the number in the second column opposite the age range that includes 122 (his and Kathy's combined ages). Bill keeps a copy of the completed worksheet for his records. It will help him (and Kathy, if she survives him) figure the taxable amount of the annuity in later years.

Bill's tax-free monthly amount is \$100. (See line 4 of the worksheet.) If he lives to collect more than 310 monthly payments, he will generally have to include in his gross income the full amount of any annuity payments received after 310 payments have been made.

If Bill does not live to collect 310 monthly payments and his wife begins to receive monthly payments, she also will exclude \$100 from each monthly payment until 310 payments (Bill's and hers) have been collected. If she dies before 310 payments have been made, a miscellaneous itemized deduction (not subject to the 2%-of-adjusted-gross-income limit) will be allowed for the unrecovered cost on her final income tax return.

General Rule

If your annuity starting date is after November 18, 1996, you cannot use the General Rule to figure the tax-free part of your CSRS or FERS annuity. If your annuity starting date is after July 1, 1986, but before November 19, 1996, you could have chosen to use either the General Rule or the Simplified Method. If your annuity starting date is before July 2, 1986, you could have chosen to use the General Rule only if you could not use the Three-Year Rule.

Under the General Rule, you figure the tax-free part of each full monthly payment by multiplying the initial gross monthly rate of your annuity by an exclusion percentage. Figuring this percentage is complex and requires the use of actuarial tables. For these tables and other information about using the General Rule, see Publication 939.

Three-Year Rule

If your annuity starting date was before July 2, 1986, you probably had to report your annuity using the Three-Year Rule. Under this rule, you excluded all the annuity payments from income until you fully recovered your cost. After your cost was recovered, all payments became fully taxable. You cannot use another rule to again exclude amounts from income.

The Three-Year Rule was repealed for retirees whose annuity starting date is after July 1, 1986.

Worksheet A. Simplified Method for Bill Smith

See the instructions in Part II of this publication under [Simplified Method](#).

<p>1. Enter the total pension or annuity payments received this year. Also, add this amount to the total for Form 1040, line 16a; Form 1040A, line 12a; or Form 1040NR, line 17a</p>	<p>1. <u> </u> \$ 8,000</p>
<p>2. Enter your cost in the plan at the annuity starting date, plus any death benefit exclusion*. See Your cost in Part II, <i>Rules for Retirees</i>, earlier</p> <p>Note: If your annuity starting date was before this year and you completed this worksheet last year, skip line 3 and enter the amount from line 4 of last year's worksheet on line 4 below (even if the amount of your pension or annuity has changed). Otherwise, go to line 3.</p>	<p>2. <u> </u> 31,000</p>
<p>3. Enter the appropriate number from Table 1 below. But if your annuity starting date was after 1997 and the payments are for your life and that of your beneficiary, enter the appropriate number from Table 2 below.</p>	<p>3. <u> </u> 310</p>
<p>4. Divide line 2 by the number on line 3</p>	<p>4. <u> </u> 100</p>
<p>5. Multiply line 4 by the number of months for which this year's payments were made. If your annuity starting date was before 1987, enter this amount on line 8 below and skip lines 6, 7, 10, and 11. Otherwise, go to line 6</p>	<p>5. <u> </u> 800</p>
<p>6. Enter any amounts previously recovered tax free in years after 1986. This is the amount shown on line 10 of your worksheet for last year</p>	<p>6. <u> </u> 0</p>
<p>7. Subtract line 6 from line 2</p>	<p>7. <u> </u> 31,000</p>
<p>8. Enter the smaller of line 5 or line 7</p>	<p>8. <u> </u> 800</p>
<p>9. Taxable amount for year. Subtract line 8 from line 1. Enter the result, but not less than zero. Also, add this amount to the total for Form 1040, line 16b, or Form 1040A, line 12b. If you are a nonresident alien, also enter this amount on line 1 of Worksheet C. If your Form CSA 1099R or Form CSF 1099R shows a larger amount, use the amount figured on this line instead. If you are a retired public safety officer, see Distributions Used To Pay Insurance Premiums for Public Safety Officers in Part II before entering an amount on your tax return or Worksheet C, line 1</p>	<p>9. <u> </u> \$ 7,200</p>
<p>10. Was your annuity starting date before 1987?</p> <p><input type="checkbox"/> Yes. Do not complete the rest of this worksheet.</p> <p><input checked="" type="checkbox"/> No. Add lines 6 and 8. This is the amount you have recovered tax free through 2011. You will need this number if you need to fill out this worksheet next year</p>	<p>10. <u> </u> 800</p>
<p>11. Balance of cost to be recovered. Subtract line 10 from line 2. If zero, you will not have to complete this worksheet next year. The payments you receive next year will generally be fully taxable</p>	<p>11. <u> </u> \$ 30,200</p>

Table 1 for Line 3 Above

IF your age on your annuity starting date was	AND your annuity starting date was—	
	before November 19, 1996, THEN enter on line 3	after November 18, 1996, THEN enter on line 3
55 or under	300	360
56–60	260	310
61–65	240	260
66–70	170	210
71 or over	120	160

Table 2 for Line 3 Above

IF the annuitants' combined ages on your annuity starting date were	THEN enter on line 3
110 or under	410
111–120	360
121–130	310
131–140	260
141 or over	210

* A death benefit exclusion of up to \$5,000 applied to certain benefits received by survivors of employees who died before August 21, 1996.

Alternative Annuity Option

If you are eligible, you may choose an alternative form of annuity. If you make this choice, you will receive a lump-sum payment equal to your contributions to the plan and a reduced monthly annuity. You are eligible to make this choice if you meet all of the following requirements.

- You are retiring, but not on disability.
- You have a life-threatening illness or other critical medical condition.
- You do not have a former spouse entitled to court ordered benefits based on your service.

If you are not eligible or do not choose this alternative annuity, you can skip the following discussion and go to [Federal Gift Tax](#), later.

Lump-Sum Payment

The lump-sum payment you receive under the alternative annuity option generally has a tax-free part and a taxable part. The tax-free part represents part of your cost. The taxable part represents part of the earnings on your annuity contract. Your lump-sum credit (discussed later) may include a deemed deposit or redeposit that is treated as being included in your lump-sum payment even though you do not actually receive such amounts. Deemed deposits and redeposits, which are described later under *Lump-sum credit*, are taxable to you in the year of retirement. Your taxable amount may therefore be more than the lump-sum payment you receive.

You must include the taxable part of the lump-sum payment in your income for the year you receive the payment unless you roll it over into another qualified plan or an IRA. If you do not have OPM transfer the taxable amount to an IRA or other plan in a direct rollover, tax will be withheld at a 20% rate. See [Rollover Rules](#), later, for information on how to make a rollover.



OPM can make a direct rollover only up to the amount of the lump-sum payment. Therefore, to defer tax on the full taxable amount if it is more than the payment, you must add funds from another source.

The taxable part of the lump-sum payment does not qualify as a lump-sum distribution eligible for capital gain treatment or the 10-year tax option. It also may be subject to an additional 10% tax on early distributions if you separate from service before the calendar year in which you reach age 55, even if you reach age 55 in the year you receive the lump-sum payment. For more information, see *Lump-Sum Distributions and Tax on Early Distributions* in Publication 575.

Worksheet B. Use [Worksheet B. Lump-Sum Payment](#) (near the end of this publication), to figure the taxable part of your lump-sum payment. Be sure to keep the completed worksheet for your records.

To complete the worksheet, you will need to know the amount of your lump-sum credit and the present value of your annuity contract.

Lump-sum credit. Generally, this is the same amount as the lump-sum payment you receive (the total of your

contributions to the retirement system). However, for purposes of the alternative annuity option, your lump-sum credit also may include deemed deposits and redeposits that OPM advanced to your retirement account so that you are given credit for the service they represent. Deemed deposits (including interest) are for federal employment during which no retirement contributions were taken out of your pay. Deemed redeposits (including interest) are for any refunds of retirement contributions that you received and did not repay. You are treated as if you had received a lump-sum payment equal to the amount of your lump-sum credit and then had made a repayment to OPM of the advanced amounts.

Present value of your annuity contract. The present value of your annuity contract is figured using actuarial tables provided by the IRS.



If you are receiving a lump-sum payment under the Alternative Annuity Option, you can write to the address below to find out the present value of your annuity contract.

Internal Revenue Service
Attn: Actuarial Group 2
TE/GE SE:T:EP:RA:T:A2
NCA-629
1111 Constitution Ave., NW
Washington, DC 20224-0002

Example. David Brown retired from the federal government in 2011, one month after his 55th birthday. He had contributed \$31,000 to his retirement plan and chose to receive a lump-sum payment of that amount under the alternative annuity option. The present value of his annuity contract was \$155,000.

The tax-free part and the taxable part of the lump-sum payment are figured using Worksheet B, as shown on the next page. The taxable part (\$24,800) is also his net cost in the plan, which is used to figure the taxable part of his reduced annuity payments. See [Reduced Annuity](#), later.

Lump-sum payment in installments. If you choose the alternative annuity option, you usually will receive the lump-sum payment in two equal installments. You will receive the first installment after you make the choice upon retirement. The second installment will be paid to you, with interest, in the next calendar year. (Exceptions to the installment rule are provided for cases of critical medical need.)

Even though the lump-sum payment is made in installments, the overall tax treatment (explained at the beginning of this discussion) is the same as if the whole payment were paid at once. If the payment has a tax-free part, you must treat the taxable part as received first.

How to report. Add any actual or deemed payment of your lump-sum credit (defined earlier) to the total for Form 1040, line 16a; Form 1040A, line 12a; or Form 1040NR, line 17a. Add the taxable part to the total for Form 1040, line 16b; Form 1040A, line 12b; or Form 1040NR, line 17b, unless you roll over the taxable part to your traditional IRA or a qualified retirement plan.

Worksheet B. Lump-Sum Payment for David Brown

See the instructions in Part II of this publication under [Alternative Annuity Option](#).

1. Enter your lump-sum credit (your cost in the plan at the annuity starting date)	1.	\$	31,000
2. Enter the present value of your annuity contract	2.		155,000
3. Divide line 1 by line 2	3.		.20
4. Tax-free amount. Multiply line 1 by line 3. (<i>Caution: Do not include this amount on line 6 of Worksheet A in this publication.</i>)	4.	\$	6,200
5. Taxable amount (net cost in the plan). Subtract line 4 from line 1. Include this amount in the total on Form 1040, line 16b; Form 1040A, line 12b; or Form 1040NR, line 17b. Also, enter this amount on line 2 of Worksheet A in this publication.	5.	\$	24,800

If you receive the lump-sum payment in two installments, include any interest paid with the second installment on line 8a of either Form 1040 or Form 1040A, or on line 9a of Form 1040NR.

Reduced Annuity

If you have chosen to receive a lump-sum payment under the alternative annuity option, you also will receive reduced monthly annuity payments. These annuity payments each will have a tax-free and a taxable part. To figure the tax-free part of each annuity payment, you must use the Simplified Method (Worksheet A). For instructions on how to complete the worksheet, see [Worksheet A](#) under *Simplified Method*, earlier.

To complete Worksheet A, line 2, you must reduce your cost in the plan by the tax-free part of the lump-sum payment you received. Enter as your net cost on line 2 the amount from Worksheet B, line 5. Do not include the tax-free part of the lump-sum payment with other amounts recovered tax free (Worksheet A, line 6) when limiting your total exclusion to your total cost.

Example. The facts are the same as in the example for David Brown in the preceding discussion. In addition, David received 10 annuity payments in 2011 of \$1,200 each. Using Worksheet A, he figures the taxable part of his annuity payments. He completes line 2 by reducing his \$31,000 cost by the \$6,200 tax-free part of his lump-sum payment. His entry on line 2 is his \$24,800 net cost in the plan (the amount from Worksheet B, line 5). He does not include the tax-free part of his lump-sum payment on Worksheet A, line 6. David's filled-in Worksheet A is shown on the next page.



Reemployment after choosing the alternative annuity option. If you chose this option when you retired and then you were reemployed by the Federal Government before retiring again, your Form CSA 1099R may show only the amount of your contributions to your retirement plan during your reemployment. If the amount on the form does not include all your contributions, disregard it and use your total contributions to figure the taxable part of your annuity payments.

Annuity starting date before November 19, 1996. If your annuity starting date is before November 19, 1996, and you chose the alternative annuity option, the taxable and tax-free parts of your lump-sum payment and your annuity payments are figured using different rules. Under

those rules, you do not reduce your cost in the plan (Worksheet A, line 2) by the tax-free part of the lump-sum payment. However, you must include that tax-free amount with other amounts previously recovered tax free (Worksheet A, line 6) when limiting your total exclusion to your total cost.

Federal Gift Tax

If, through the exercise or nonexercise of an election or option, you provide an annuity for your beneficiary at or after your death, you have made a gift. The gift may be taxable for gift tax purposes. The value of the gift is equal to the value of the annuity.

Joint and survivor annuity. If the gift is an interest in a joint and survivor annuity where only you and your spouse can receive payments before the death of the last spouse to die, the gift generally will qualify for the unlimited marital deduction. This will eliminate any gift tax liability with regard to that gift.

If you provide survivor annuity benefits for someone other than your current spouse, such as your former spouse, the unlimited marital deduction will not apply. This may result in a taxable gift.

More information. For information about the gift tax, see Publication 950, Introduction to Estate and Gift Taxes, and Form 709, United States Gift (and Generation-Skipping Transfer) Tax Return, and its instructions.

Retirement During the Past Year

If you have recently retired, the following discussions covering annual leave, voluntary contributions, and community property may apply to you.

Annual leave. A payment for accrued annual leave received on retirement is a salary payment. It is taxable as wages in the tax year you receive it.

Voluntary contributions. Voluntary contributions to the retirement fund are those made in addition to the regular contributions that were deducted from your salary. They also include the regular contributions withheld from your salary after you have the years of service necessary for the maximum annuity allowed by law. Voluntary contributions are not the same as employee contributions to the Thrift Savings Plan. See [Thrift Savings Plan](#), later.

Worksheet A. Simplified Method for David Brown

See the instructions in Part II of this publication under [Simplified Method](#).

<p>1. Enter the total pension or annuity payments received this year. Also, add this amount to the total for Form 1040, line 16a; Form 1040A, line 12a; or Form 1040NR, line 17a.</p>	<p>1. \$ 12,000</p>
<p>2. Enter your cost in the plan at the annuity starting date, plus any death benefit exclusion*. See Your cost in Part II, <i>Rules for Retirees</i>, earlier</p> <p>Note: If your annuity starting date was before this year and you completed this worksheet last year, skip line 3 and enter the amount from line 4 of last year's worksheet on line 4 below (even if the amount of your pension or annuity has changed). Otherwise, go to line 3.</p>	<p>2. 24,800</p>
<p>3. Enter the appropriate number from Table 1 below. But if your annuity starting date was after 1997 and the payments are for your life and that of your beneficiary, enter the appropriate number from Table 2 below.</p>	<p>3. 360</p>
<p>4. Divide line 2 by the number on line 3</p>	<p>4. 68.89</p>
<p>5. Multiply line 4 by the number of months for which this year's payments were made. If your annuity starting date was before 1987, enter this amount on line 8 below and skip lines 6, 7, 10, and 11. Otherwise, go to line 6</p>	<p>5. 688.90</p>
<p>6. Enter any amounts previously recovered tax free in years after 1986. This is the amount shown on line 10 of your worksheet for last year</p>	<p>6. 0</p>
<p>7. Subtract line 6 from line 2</p>	<p>7. 24,800</p>
<p>8. Enter the smaller of line 5 or line 7</p>	<p>8. 688.90</p>
<p>9. Taxable amount for year. Subtract line 8 from line 1. Enter the result, but not less than zero. Also, add this amount to the total for Form 1040, line 16b, or Form 1040A, line 12b. If you are a nonresident alien, also enter this amount on line 1 of Worksheet C. If your Form CSA 1099R or Form CSF 1099R shows a larger amount, use the amount figured on this line instead. If you are a retired public safety officer, see Distributions Used To Pay Insurance Premiums for Public Safety Officers in Part II before entering an amount on your tax return or Worksheet C, line 1</p>	<p>9. \$ 11,311.10</p>
<p>10. Was your annuity starting date before 1987?</p> <p><input type="checkbox"/> Yes. Do not complete the rest of this worksheet.</p> <p><input checked="" type="checkbox"/> No. Add lines 6 and 8. This is the amount you have recovered tax free through 2011. You will need this number if you need to fill out this worksheet next year</p>	<p>10. 688.90</p>
<p>11. Balance of cost to be recovered. Subtract line 10 from line 2. If zero, you will not have to complete this worksheet next year. The payments you receive next year will generally be fully taxable</p>	<p>11. \$ 24,111.10</p>

Table 1 for Line 3 Above

IF your age on your annuity starting date was	AND your annuity starting date was—	
	before November 19, 1996, THEN enter on line 3	after November 18, 1996, THEN enter on line 3
55 or under	300	360
56–60	260	310
61–65	240	260
66–70	170	210
71 or over	120	160

Table 2 for Line 3 Above

IF the annuitants' combined ages on your annuity starting date were	THEN enter on line 3
110 or under	410
111–120	360
121–130	310
131–140	260
141 or over	210

* A death benefit exclusion of up to \$5,000 applied to certain benefits received by survivors of employees who died before August 21, 1996.

Additional annuity benefit. If you choose to receive an additional annuity benefit from your voluntary contributions, it is treated separately from the annuity benefit that comes from the regular contributions deducted from your salary. This separate treatment applies for figuring the amounts to be excluded from, and included in, gross income. It does not matter that you receive only one monthly check covering both benefits. Each year you will receive a Form CSA 1099R that will show how much of your total annuity received in the past year was from each type of benefit.

Figure the taxable and tax-free parts of your additional monthly benefits from voluntary contributions using the rules that apply to regular CSRS and FERS annuities, as explained earlier.

Refund of voluntary contributions. If you choose to receive a refund of your voluntary contributions plus accrued interest, the interest is taxable to you in the tax year it is distributed unless you roll it over to a traditional IRA or another qualified retirement plan. If you do not have OPM transfer the interest to a traditional IRA or other qualified retirement plan in a direct rollover, tax will be withheld at a 20% rate. See [Rollover Rules](#), later. The interest does not qualify as a lump-sum distribution eligible for capital gain treatment or the 10-year tax option. It also may be subject to an additional 10% tax on early distributions if you separate from service before the calendar year in which you reach age 55. For more information, see *Lump-Sum Distributions* and *Tax on Early Distributions* in Publication 575.

Community property laws. State community property laws apply to your annuity. These laws will affect your income tax only if you file a return separately from your spouse.

Generally, the determination of whether your annuity is separate income (taxable to you) or community income (taxable to both you and your spouse) is based on your marital status and domicile when you were working. Regardless of whether you are now living in a community property state or a noncommunity property state, your current annuity may be community income if it is based on services you performed while married and domiciled in a community property state.

At any time, you have only one domicile even though you may have more than one home. Your domicile is your fixed and permanent legal home that you intend to use for an indefinite or unlimited period, and to which, when absent, you intend to return. The question of your domicile is mainly a matter of your intentions as indicated by your actions.

If your annuity is a mixture of community income and separate income, you must divide it between the two kinds of income. The division is based on your periods of service and domicile in community and noncommunity property states while you were married.

For more information, see Publication 555, Community Property.

Reemployment After Retirement

If you retired from federal service and are later rehired by the Federal Government as an employee, you can continue to receive your annuity during reemployment. The employing agency usually will pay you the difference between your salary for your period of reemployment and your annuity. This amount is taxable as wages. Your annuity will continue to be taxed just as it was before. If you are still recovering your cost, you continue to do so. If you have recovered your cost, the annuity you receive while you are reemployed generally is fully taxable.

Nonresident Aliens

The following special rules apply to nonresident alien federal employees performing services outside the United States and to nonresident alien retirees and beneficiaries. A nonresident alien is an individual who is not a citizen or a resident alien of the United States.

Special rule for figuring your total contributions. Your contributions to the retirement plan (your cost) also include the government's contributions to the plan to a certain extent. You include government contributions that would not have been taxable to you at the time they were contributed if they had been paid directly to you. For example, government contributions would not have been taxable to you if, at the time made, your services were performed outside the United States. Thus, your cost is increased by these government contributions and the benefits that you, or your beneficiary, must include in income are reduced.

This method of figuring your total contributions does not apply to any contributions the government made on your behalf after you became a citizen or a resident alien of the United States.

Limit on taxable amount. There is a limit on the taxable amount of payments received from the CSRS, the FERS, or the TSP by a nonresident alien retiree or nonresident alien beneficiary. Figure this limited taxable amount by multiplying the otherwise taxable amount by a fraction. The numerator of the fraction is the retiree's total U.S. Government basic pay, other than tax-exempt pay for services performed outside the United States. The denominator is the retiree's total U.S. Government basic pay for all services.

Basic pay includes regular pay plus any standby differential. It does not include bonuses, overtime pay, certain retroactive pay, uniform or other allowances, or lump-sum leave payments.

To figure the limited taxable amount of your CSRS or FERS annuity or your TSP distributions, use the following worksheet. (For an annuity, first complete [Worksheet A](#) in this publication.)

Worksheet C. Limited Taxable Amount for Nonresident Alien

Keep for Your Records



1. Enter the otherwise taxable amount of the CSRS or FERS annuity (from line 9 of Worksheet A or from Forms CSA 1099R or CSF 1099R) or TSP distributions (from Form 1099R)	1.	_____
2. Enter the total U.S. Government basic pay other than tax-exempt pay for services performed outside the United States	2.	_____
3. Enter the total U.S. Government basic pay for all services	3.	_____
4. Divide line 2 by line 3	4.	_____
5. Limited taxable amount. Multiply line 1 by line 4. Enter this amount on Form 1040NR, line 17b	5.	_____

Example 1. You are a nonresident alien who performed all services for the U.S. Government abroad as a nonresident alien. You retired and began to receive a monthly annuity of \$200. Your total basic pay for all services for the U.S. Government was \$100,000. All of your basic pay was tax exempt because it was not U.S. source income.

The taxable amount of your annuity using Worksheet A in this publication is \$720. You are a nonresident alien, so you figure the limited taxable amount of your annuity using Worksheet C as follows.

Worksheet C. Limited Taxable Amount for Nonresident Alien — Example 1

1. Enter the otherwise taxable amount of the CSRS or FERS annuity (from line 9 of Worksheet A or from Forms CSA 1099R or CSF 1099R) or TSP distributions (from Form 1099R)	1.	\$ 720
2. Enter the total U.S. Government basic pay other than tax-exempt pay for services performed outside the United States	2.	0
3. Enter the total U.S. Government basic pay for all services	3.	100,000
4. Divide line 2 by line 3	4.	0
5. Limited taxable amount. Multiply line 1 by line 4. Enter this amount on Form 1040NR, line 17b	5.	0

Example 2. You are a nonresident alien who performed services for the U.S. Government as a nonresident alien both within the United States and abroad. You retired and began to receive a monthly annuity of \$240.

Your total basic pay for your services for the U.S. Government was \$120,000; \$40,000 was for work done in the United States and \$80,000 was for your work done in a foreign country. The part of your total basic pay for your work done in a foreign country was tax exempt because it was not U.S. source income.

The taxable amount of your annuity figured using Worksheet A in this publication is \$1,980. You are a nonresident alien, so you figure the limited taxable amount of your annuity using Worksheet C as follows.

Worksheet C. Limited Taxable Amount for Nonresident Alien — Example 2

1. Enter the otherwise taxable amount of the CSRS or FERS annuity (from line 9 of Worksheet A or from Forms CSA 1099R or CSF 1099R) or TSP distributions (from Form 1099R)	1.	\$ 1,980
2. Enter the total U.S. Government basic pay other than tax-exempt pay for services performed outside the United States	2.	40,000
3. Enter the total U.S. Government basic pay for all services	3.	120,000
4. Divide line 2 by line 3	4.	.333
5. Limited taxable amount. Multiply line 1 by line 4. Enter this amount on Form 1040NR, line 17b	5.	659

Thrift Savings Plan

All of the money in your TSP account is taxed as ordinary income when you receive it. (However, see *Uniformed services TSP accounts*, next.) This is because neither the contributions to your TSP account nor its earnings have been included previously in your taxable income. The way that you withdraw your account balance determines when you must pay the tax.

Uniformed services TSP accounts. If you have a uniformed services TSP account that includes contributions from combat zone pay, the distributions attributable to those contributions are tax exempt. However, any earnings on those contributions are subject to tax when they are distributed. The statement you receive from the TSP will separately state the total amount of your distribution and the amount of your taxable distribution for the year. You can get more information from the TSP website, www.tsp.gov, or the TSP Service Office.

Direct rollover by the TSP. If you ask the TSP to transfer any part of the money in your account to a traditional IRA or other qualified retirement plan, the tax on that part is deferred until you receive payments from the traditional IRA or other plan. See *Rollover Rules*, later.

Direct rollover by the TSP to a Roth IRA. If you ask the TSP to transfer any part of the money in your account to a Roth IRA, the amount transferred will be taxed in the current year. See *Rollovers to Roth IRAs* for more information, later.

TSP annuity. If you ask the TSP to buy an annuity with the money in your account, the annuity payments are taxed when you receive them. The payments are not subject to the additional 10% tax on early distributions, even if you are under age 55 when they begin.

Cash withdrawals. If you withdraw any of the money in your TSP account, it is generally taxed as ordinary income when you receive it unless you roll it over into a traditional IRA or other qualified plan. (See *Rollover Rules*, later.) If you receive your entire TSP account balance in a single tax year, you may be able to use the 10-year tax option to figure your tax. See *Lump-Sum Distributions* in Publication 575 for details.



To qualify for the 10-year tax option, the plan participant must have been born before January 2, 1936.

If you receive a single payment or you choose to receive your account balance in monthly payments over a period of less than 10 years, the TSP generally must withhold 20% for federal income tax. If you choose to receive your account balance in monthly payments over a period of 10 or more years or a period based on your life expectancy, the payments are subject to withholding as if you are married with three withholding allowances, unless you submit a withholding certificate. See also [Withholding from Thrift Savings Plan payments](#) earlier under *Tax Withholding and Estimated Tax in Part I*.

Tax on early distributions. Any money paid to you from your TSP account before you reach age 59½ may be subject to an additional 10% tax on early distributions. However, this additional tax does not apply in certain situations, including any of the following.

- You receive the distribution and separate from government service during or after the calendar year in which you reach age 55.
- You choose to receive your account balance in monthly payments based on your life expectancy.
- You are totally and permanently disabled.

For more information, see *Tax on Early Distributions* in Publication 575.

Outstanding loan. If the TSP declares a distribution from your account because money you borrowed has not been repaid when you separate from government service, your account is reduced and the amount of the distribution (your unpaid loan balance and any unpaid interest) is taxed in the year declared. The distribution also may be subject to the additional 10% tax on early distributions. However, the tax will be deferred if you make a rollover contribution to a traditional IRA or other qualified plan equal to the declared distribution amount. See [Rollover Rules](#), below. If you withdraw any money from your TSP account in that same year, the TSP must withhold income tax of 20% of the total of the declared distribution and the amount withdrawn.

More information. For more information about the TSP, see Summary of the Thrift Savings Plan, distributed to all federal employees. Also, see Important Tax Information About Payments From Your TSP Account and Tax Treatment of TSP Payments to Nonresident Aliens and Their Beneficiaries, which are available from your agency personnel office or from the TSP.



The above documents are also available on the TSP website at www.tsp.gov. Select “Forms & Publications.”

Rollover Rules

Generally, a rollover is a tax-free withdrawal of cash or other assets from one qualified retirement plan or traditional IRA and its reinvestment in another qualified retirement plan or traditional IRA. You do not include the amount rolled over in your income, and you cannot take a deduction for it. The amount rolled over is taxed later as the new

program pays that amount to you. If you roll over amounts into a traditional IRA, later distributions of these amounts from the traditional IRA do not qualify for the capital gain or the 10-year tax option. However, capital gain treatment or the 10-year tax option will be restored if the traditional IRA contains only amounts rolled over from a qualified plan and these amounts are rolled over from the traditional IRA into a qualified retirement plan.



To qualify for the capital gain treatment or 10-year tax option, the plan participant must have been born before January 2, 1936.

You can also roll over a distribution from a qualified retirement plan into a Roth IRA. Although the transfer of a distribution into a Roth IRA is considered a rollover for Roth IRA purposes, it is not a tax-free transfer. See [Rollovers to Roth IRAs](#), later, for more information.

Qualified retirement plan. For this purpose, a qualified retirement plan generally is:

- A qualified employee plan,
- A qualified employee annuity,
- A tax-sheltered annuity plan (403(b) plan), or
- An eligible state or local government section 457 deferred compensation plan.

The CSRS, FERS, and TSP are considered qualified retirement plans.

Distributions eligible for rollover treatment. If you receive a refund of your CSRS or FERS contributions when you leave government service, you can roll over any interest you receive on the contributions. You cannot roll over any part of your CSRS or FERS annuity payments.

You can roll over a distribution of any part of your TSP account balance except:

1. A distribution of your account balance that you choose to receive in monthly payments over:
 - a. Your life expectancy,
 - b. The joint life expectancies of you and your beneficiary, or
 - c. A period of 10 years or more,
2. A required minimum distribution generally beginning at age 70½,
3. A declared distribution because of an unrepaid loan, if you have not separated from government service (see [Outstanding loan](#) under *Thrift Savings Plan*, earlier), or
4. A hardship distribution.

In addition, a distribution to your beneficiary generally is not treated as an eligible rollover distribution. However, see [Qualified domestic relations order \(QDRO\)](#) and [Rollovers by surviving spouse](#), and [Rollovers by nonspouse beneficiary](#), later.

Direct rollover option. You can choose to have the OPM or TSP transfer any part of an eligible rollover distribution directly to another qualified retirement plan that accepts rollover distributions or to a traditional IRA or Roth IRA.

There is an automatic rollover requirement for mandatory distributions. A mandatory distribution is a distribution made without your consent and before you reach age 62 or normal retirement age, whichever is later. The automatic rollover requirement applies if the distribution is more than \$1,000 and is an eligible rollover distribution. You can choose to have the distribution paid directly to you or rolled over directly to your traditional or Roth IRA or another qualified retirement plan. If you do not make this choice, OPM will automatically roll over the distribution into an IRA of a designated trustee or issuer.

No tax withheld. If you choose the direct rollover option or have an automatic rollover, no tax will be withheld from any part of the distribution that is directly paid to the trustee of the other plan. However, if the rollover is to a Roth IRA, you may want to choose to have tax withheld since any amount rolled over is generally included in income. Any part of the eligible rollover distribution paid to you is subject to withholding at a 20% rate.

Payment to you option. If an eligible rollover distribution is paid to you, the OPM or TSP must withhold 20% for income tax even if you plan to roll over the distribution to another qualified retirement plan, traditional or Roth IRA. However, the full amount is treated as distributed to you even though you actually receive only 80%. You generally must include in income any part (including the part withheld) that you do not roll over within 60 days to another qualified retirement plan or to a traditional IRA. [Rollovers to Roth IRAs](#) are generally included in income.

If you leave government service before the calendar year in which you reach age 55 and are under age 59½ when a distribution is paid to you, you may have to pay an additional 10% tax on any part, including any tax withheld, that you do not roll over. See *Tax on Early Distributions* in Publication 575.

Exception to withholding. Withholding from an eligible rollover distribution paid to you is not required if the distributions for your tax year total less than \$200.

Partial rollovers. A lump-sum distribution may qualify for capital gain treatment or the 10-year tax option if the plan participant was born before January 2, 1936. See *Lump-Sum Distributions* in Publication 575. However, if you roll over any part of the distribution, the part you keep does not qualify for this special tax treatment.

Rolling over more than amount received. If you want to roll over more of an eligible rollover distribution than the amount you received after income tax was withheld, you will have to add funds from some other source (such as your savings or borrowed amounts).

Example. You left government service at age 53. On February 1, 2011, you receive an eligible rollover distribution of \$10,000 from your TSP account. The TSP withholds \$2,000, so you actually receive \$8,000. If you want to roll over the entire \$10,000 to postpone including that amount in your income, you will have to get \$2,000 from some other source and add it to the \$8,000 you actually received.

If you roll over only \$8,000, you must include in your income the \$2,000 not rolled over. Also, you may be subject to the 10% additional tax on the \$2,000.

Time for making rollover. You generally must complete the rollover of an eligible rollover distribution paid to you by

the 60th day following the day on which you receive the distribution.

The IRS may waive the 60-day requirement where the failure to do so would be against equity or good conscience, such as in the event of a casualty, disaster, or other event beyond your reasonable control. For more information on this waiver, see Revenue Procedure 2003-16, in Internal Revenue Bulletin 2003-4. If you need to apply for a waiver, you must request a letter ruling, which requires the payment of a user fee. See Revenue Procedure 2012-4, available at www.irs.gov/irb/2012-01_IRB/ar09.html, for information on letter rulings and Revenue Procedure 2012-8, available at www.irs.gov/irb/2012-01_IRB/ar13.html, for information on user fees. Both revenue procedures are in Internal Revenue Bulletin 2012-1.

A letter ruling is not required if a financial institution receives the rollover funds during the 60-day rollover period, you follow all procedures required by the financial institution, and, solely due to an error on the part of the financial institution, the funds are not deposited into an eligible retirement account within the 60-day rollover period.

Frozen deposits. If an amount distributed to you becomes a frozen deposit in a financial institution during the 60-day period after you receive it, the rollover period is extended. An amount is a frozen deposit if you cannot withdraw it because of either:

- The bankruptcy or insolvency of the financial institution, or
- Any requirement imposed by the state in which the institution is located because of the bankruptcy or insolvency (or threat of it) of one or more financial institutions in the state.

The 60-day rollover period is extended by the period for which the amount is a frozen deposit and does not end earlier than 10 days after the amount is no longer a frozen deposit.

Qualified domestic relations order (QDRO). You may be able to roll over tax free all or part of a distribution you receive from the CSRS, the FERS, or the TSP under a court order in a divorce or similar proceeding. You must receive the distribution as the government employee's spouse or former spouse (not as a nonspousal beneficiary). The rollover rules apply to you as if you were the employee. You can roll over the distribution if it is an eligible rollover distribution (described earlier) and it is made under a QDRO or, for the TSP, a qualifying order.

A QDRO is a judgment, decree, or order relating to payment of child support, alimony, or marital property rights. The payments must be made to a spouse, former spouse, child, or other dependent of a participant in the plan. For the TSP, a QDRO can be a qualifying order, but a domestic relations order can be a qualifying order even if it is not a QDRO. For example, a qualifying order can include an order that requires a TSP payment of attorney's fees to the attorney for the spouse, former spouse, or child of the participant.

The order must contain certain information, including the amount or percentage of the participant's benefits to be paid to each payee. It cannot require the plan to pay

benefits in a form not offered by the plan, nor can it require the plan to pay increased benefits.

A distribution that is paid to a child, dependent, or, if applicable, an attorney for fees, under a QDRO or a qualifying order is taxed to the plan participant.

Rollovers by surviving spouse. You may be able to roll over tax free all or part of the CSRS, FERS, or TSP distribution you receive as the surviving spouse of a deceased employee or retiree. The rollover rules apply to you as if you were the employee or retiree. You generally can roll over the distribution into a qualified retirement plan or an IRA. An amount rolled over to a Roth IRA is not tax free. See [Rollovers to Roth IRAs](#) later.

A distribution paid to a beneficiary other than the employee's surviving spouse is generally not an eligible rollover distribution. However, see *Rollovers by nonspouse beneficiary*, next.

Rollovers by nonspouse beneficiary. You may be able to roll over tax free all or a portion of a distribution you receive from the CSRS, FERS, or TSP of a deceased employee or retiree if you are a designated beneficiary (other than a surviving spouse) of the employee or retiree. The distribution must be a direct trustee-to-trustee transfer to your IRA that was set up to receive the distribution. The transfer will be treated as an eligible rollover distribution and the receiving plan will be treated as an inherited IRA. An amount rolled over to a Roth IRA is not tax free. See [Rollovers to Roth IRAs](#) later. For information on inherited IRAs, see Publication 590.

How to report. On your Form 1040, report the total distributions from the CSRS, FERS, or TSP on line 16a. Report the taxable amount of the distributions (total distribution less the amount rolled over) on line 16b. If you file Form 1040A, report the total distributions on line 12a and the taxable amount on line 12b. If you file Form 1040NR, report the total distributions on line 17a and the taxable amount on line 17b. Also, write "Rollover" next to line 16b, 12b, or 17b, whichever is applicable.

If the rollover was made to a Roth IRA, see [Rollovers to Roth IRAs](#) later for reporting the rollover on your return.

Written explanation to recipients. The TSP or OPM must provide a written explanation to you within a reasonable period of time before making an eligible rollover distribution to you. It must tell you about all of the following.

- Your right to have the distribution paid tax free directly to another qualified retirement plan or to a traditional IRA.
- The requirement to withhold tax from the distribution if it is not directly rolled over.
- The nontaxability of any part of the distribution that you roll over within 60 days after you receive the distribution.
- Other qualified retirement plan rules that apply, including those for lump-sum distributions, alternate payees, and cash or deferred arrangements.
- How the distribution rules of the plan to which you roll over the distribution may differ from the rules that apply to the plan making the distribution in their restrictions and tax consequences.

Note. Rollovers to Roth IRAs are not tax free and are included in income. See [Rollovers to Roth IRAs](#) later.

Reasonable period of time. The TSP or OPM must provide you with a written explanation no earlier than 90 days and no later than 30 days before the distribution is made. However, you can choose to have the TSP or OPM make a distribution less than 30 days after the explanation is provided, as long as the following two requirements are met.

- You have the opportunity to consider whether or not you want to make a direct rollover for at least 30 days after the explanation is provided.
- The information you receive clearly states that you have the right to have 30 days to make a decision.

Contact the TSP or OPM if you have any questions about this information.

Rollovers to Roth IRAs.

You can roll over distributions directly from the CSRS, FERS, and TSP to a Roth IRA.

You must include in your gross income distributions from the CSRS, FERS, and TSP that you would have had to include in income if you had not rolled them over into a Roth IRA. You do not include in gross income any part of a distribution that is a return of contributions that were taxable to you when paid. In addition, the 10% tax on early distributions does not apply.

Any amount rolled over to a Roth IRA is subject to the same rules for converting a traditional IRA into a Roth IRA. For more information, see *Converting From Any Traditional IRA Into a Roth IRA* in chapter 1 of Publication 590.

How to report. A rollover to a Roth IRA is not a tax-free distribution other than any after-tax contributions you made. Report a rollover from a qualified retirement plan to a Roth IRA on Form 1040, lines 16a and 16b; Form 1040A, lines 12a and 12b; or Form 1040NR, lines 17a and 17b.

Enter the total amount of the distribution before income tax or deductions were withheld on Form 1040, line 16a; Form 1040A, line 12a; or Form 1040NR, line 17a. This amount is shown in box 1 of Form 1099-R. From this amount, subtract any contributions (usually shown in box 5 of Form 1099-R) that were taxable to you when made. From that result, subtract the amount of any qualified rollover from a designated Roth account. Enter the remaining amount, even if zero, on Form 1040, line 16b; Form 1040A, line 12b; or Form 1040NR, line 17b.

Special rules for 2010 rollovers from qualified retirement plans to Roth IRAs. In 2010, you were able to rollover amounts from a qualified retirement plan to a Roth IRA. Special rules allowed you to include any amounts required to be included in income in equal amounts in 2011 and 2012. You could have also chosen to include the total amount in income in 2010. See your tax return instructions to figure the taxable amount for 2011.



If you must include any amount in your gross income, you may have to increase your withholding or make estimated tax payments. See Publication 505, Tax Withholding and Estimated Tax.

Choosing the right option. Table 1 may help you decide which distribution option to choose. Carefully compare the effects of each option.

Table 1. Comparison of Payment to You Versus Direct Rollover

Affected Item	Result of a Payment to You	Result of a Direct Rollover
Withholding	The payer must withhold 20% of the taxable part.	There is no withholding. However, you may want to choose withholding on a rollover to a Roth IRA.
Additional tax	If you are under age 59½, a 10% additional tax may apply to the taxable part (including an amount equal to the tax withheld) that is not rolled over.	There is no 10% additional tax. See Tax on early distributions , earlier.
When to report as income	Any taxable part (including the taxable part of any amount withheld) not rolled over is income to you in the year paid.	Any taxable part is not income to you until later distributed to you from the new plan or IRA. However, see Rollovers to Roth IRAs , earlier, for an exception.

Distributions Used To Pay Insurance Premiums for Public Safety Officers

If you are an eligible retired public safety officer (law enforcement officer, firefighter, chaplain, or member of a rescue squad or ambulance crew), you can elect to exclude from income distributions made from an eligible retirement plan that are used to pay the premiums for accident or health insurance or long-term care insurance. The premiums can be for coverage for you, your spouse, or dependents. The distribution must be made directly from the plan to the insurance provider. You can exclude from income the smaller of the amount of the insurance premiums or \$3,000. You can only make this election for amounts that would otherwise be included in your income. The amount excluded from your income cannot be used to claim a medical expense deduction.

For this purpose, an eligible retirement plan is a governmental plan that is:

- A qualified trust,
- A section 403(a) plan,
- A section 403(b) annuity, or
- A section 457(b) plan.

The CSRS and FERS are considered eligible retirement plans.

How to report. If you make this election, reduce the otherwise taxable amount of your annuity by the amount excluded. The taxable annuity shown on Form CSA 1099R does not reflect this exclusion. Report your total distributions on Form 1040, line 16a; Form 1040A, line 12a; or Form 1040NR, line 17a. Report the taxable amount on Form 1040, line 16b; Form 1040A, line 12b; or Form 1040NR, line 17b. Enter “PSO” next to the appropriate line on which you report the taxable amount.

If you are retired on disability and reporting your disability pension on line 7 of Form 1040 or Form 1040A, or line 8 of Form 1040NR, include only the taxable amount on that line and enter “PSO” and the amount excluded on the dotted line next to the applicable line.

How To Report Benefits

If you received annuity benefits that are not fully taxable, report the total received for the year on Form 1040, line 16a; Form 1040A, line 12a; or Form 1040NR, line 17a. Also, include on that line the total of any other pension plan payments (even if fully taxable, such as those from the TSP) that you received during the year in addition to the annuity. Report the taxable amount of these total benefits on line 16b (Form 1040), line 12b (Form 1040A), or line 17b (Form 1040NR). If you use Form 4972, Tax on Lump-Sum Distributions, however, to report the tax on any amount, do not include that amount on lines 16a and 16b, lines 12a and 12b, or lines 17a or 17b, instead follow the Form 4972 instructions.

If you received only fully taxable payments from your retirement, the TSP, or other pension plan, report on Form 1040, line 16b; Form 1040A, line 12b; or Form 1040NR, line 17b, the total received for the year (except for any amount reported on Form 4972); no entry is required on line 16a (Form 1040), line 12a (Form 1040A), or line 17a (Form 1040NR).

Part III Rules for Disability Retirement and Credit for the Elderly or the Disabled

This part of the publication is for federal employees and retirees who receive disability benefits under the CSRS, the FERS, or other federal programs. It also explains the tax credit available to certain taxpayers because of age or disability.

Disability Annuity

If you retired on disability, the disability annuity you receive from the CSRS or FERS is taxable as wages until you reach minimum retirement age, as explained in this section. However, beginning on the day after you reach [minimum retirement age](#), your payments are treated as a

retirement annuity and you can begin to recover the cost of your annuity under the rules discussed in [Part II, Rules for Retirees](#).

If you find that you could have started your recovery in an earlier year for which you have already filed a return, you can still start your recovery of contributions in that earlier year. To do so, file an amended return for that year and each succeeding year for which you have already filed a return. Generally, an amended return for any year must be filed within 3 years after the due date for filing your original return for that year.

Minimum retirement age. This is the age at which you first could receive an annuity were you not disabled. This generally is based on your age and length of service.

Retirement under the Civil Service Retirement System (CSRS). In most cases, under the CSRS, the minimum combinations of age and service for retirement are:

- Age 55 with 30 years of service,
- Age 60 with 20 years of service,
- Age 62 with 5 years of service, or
- For service as a law enforcement officer, firefighter, nuclear materials courier, or air traffic controller, age 50 with 20 years of covered service.

Retirement under the Federal Employees Retirement System (FERS). In most cases, the minimum age for retirement under the FERS is between ages 55 and 57 with at least 10 years of service. With at least 5 years of service, your minimum retirement age is age 62. Your minimum retirement age with at least 10 years of service is shown in Table 2.

Table 2. **FERS Minimum Retirement Age (MRA) With 10 Years of Service**

IF you were born in	THEN Your MRA is
1947 or earlier	55 years.
1948	55 years, 2 months.
1949	55 years, 4 months.
1950	55 years, 6 months.
1951	55 years, 8 months.
1952	55 years, 10 months.
1953 to 1964	56 years.
1965	56 years, 2 months.
1966	56 years, 4 months.
1967	56 years, 6 months.
1968	56 years, 8 months.
1969	56 years, 10 months.
1970 or later	57 years.

For service as a law enforcement officer, member of the Capitol or Supreme Court Police, firefighter, nuclear materials courier, or air traffic controller, the minimum retirement age is age 50 with 20 years of covered service or any age with 25 years of covered service.

How to report. You must report all your disability annuity payments received before minimum retirement age on Form 1040 or Form 1040A, line 7, or Form 1040NR, line 8. Disability annuity payments received after you reach that age are reported as discussed under [How To Report Benefits](#), earlier in Part II.

Withholding. For income tax withholding purposes, a disability annuity is treated the same as a nondisability annuity. This treatment also applies to disability payments received before minimum retirement age even though these payments are shown as wages on your return. See [Tax Withholding and Estimated Tax](#) in Part I.

Other Benefits

The tax treatment of certain other benefits is explained in this section.

Federal Employees' Compensation Act (FECA). FECA payments you receive for personal injuries or sickness resulting from the performance of your duties are like workers' compensation. They are tax exempt and are not treated as disability income or annuities. However, payments you receive while your claim is being processed, including pay while on sick leave and continuation of pay for up to 45 days, are taxable.

Sick pay or disability payments repaid. If you repay sick leave or disability annuity payments you received and included in income in an earlier year to be eligible for nontaxable FECA benefits for that period, you can deduct the amount you repay. You can claim the deduction whether you repay the amount yourself or have the FECA payment sent directly to your employing agency or the OPM.

Claim the deduction on Schedule A (Form 1040) as a miscellaneous itemized deduction, subject to the 2%-of-adjusted-gross-income limit. It is considered a business loss and may create a net operating loss if your deductions for the year are more than your income for the year. Get Publication 536, Net Operating Losses (NOLs) for Individuals, Estates, and Trusts, for more information. The repayment is not eligible for the special tax credit that applies to repayments over \$3,000 of amounts received under a claim of right.

If you repay sick leave or disability annuity payments in the same year you receive them, the repayment reduces your taxable sick leave pay or disability annuity. Do not deduct it separately.

Terrorist attack. Disability payments for injuries incurred as a direct result of a terrorist attack directed against the United States (or its allies) are not included in income. For more information about payments to survivors of terrorist attacks, see Publication 3920, Tax Relief for Victims of Terrorist Attacks.

Military actions. Disability payments for injuries incurred as a direct result of a military action involving the Armed Forces of the United States and resulting from actual or threatened violence or aggression against the United States or any of its allies, are not included in income.

Disability resulting from military service injuries. If you received tax-exempt benefits from the Department of Veterans Affairs for personal injuries resulting from active service in the U.S. Armed Forces and later receive a CSRS or FERS disability annuity for disability arising from the same injuries, you cannot treat the disability annuity payments as tax-exempt income. They are subject to the rules described earlier under [Disability Annuity](#).

Payment for unused annual leave. If you retire on disability, any payment for your unused annual leave is taxed as wages in the tax year you receive the payment.

Credit for the Elderly or the Disabled

You can take the credit for the elderly or the disabled if:

- You are a qualified individual, and
- Your income is not more than certain limits.

You are a qualified individual for this credit if you are a U.S. citizen or resident alien and, at the end of the tax year, you are:

1. Age 65 or older, or
2. Under age 65, retired on permanent and total disability, and
 - a. Received taxable disability income, and
 - b. Did not reach mandatory retirement age (defined later) before the tax year.

You are retired on permanent and total disability if:

- You were permanently and totally disabled when you retired, and
- You retired on disability before the close of the tax year.

Even if you do not retire formally, you may be considered retired on disability when you have stopped working because of your disability.

Permanently and totally disabled. You are permanently and totally disabled if you cannot engage in any substantial gainful activity because of your physical or mental condition. A physician must certify that the condition has lasted or can be expected to last continuously for 12 months or more, or that the condition can be expected to result in death. See *Physician's statement*, next. Substantial gainful activity is the performance of significant duties over a reasonable period of time while working for pay or profit, or in work generally done for pay or profit.

Physician's statement. If you are under 65, you must have your physician complete a statement certifying that you were permanently and totally disabled on the date you retired. You must keep this statement for your tax records. For this purpose, you can use the Physician's Statement in the Instructions for Schedule R (Form 1040A or 1040).

Mandatory retirement age. This is the age set by your employer at which you would have had to retire if you had not become disabled. There is no mandatory retirement age for most federal employees. However, there is a mandatory retirement age for the following federal employees.

- An air traffic controller appointed after May 15, 1972, by the Department of Transportation or the Department of Defense generally must retire by the last day of the month in which he or she reaches age 56.

- A federal firefighter, law enforcement officer, nuclear materials courier, or member of the Capitol or Supreme Court Police who is otherwise eligible for immediate retirement generally must retire by the last day of the month in which he or she reaches age 57 or, if later, completes 20 years of service.

Figuring the credit. If you figure the credit yourself, first fill out the front of Schedule R. Next, fill out Part III of the schedule.

If you want the Internal Revenue Service to figure your tax and credits, including the credit for the elderly or the disabled, see the Instructions for Schedule R (Form 1040A or 1040).

More information. For detailed information about this credit, get Publication 524, *Credit for the Elderly or the Disabled*.

Part IV Rules for Survivors of Federal Employees

This part of the publication is for survivors of federal employees. It explains how to treat amounts you receive because of the employee's death. If you are the survivor of a federal retiree, see [Part V](#).

Employee earnings. Salary or wages earned by a federal employee but paid to the employee's survivor or beneficiary after the employee's death are income in respect of the decedent. This income is taxable to the survivor or beneficiary. This treatment also applies to payments for accrued annual leave.

Dependents of public safety officers. The Public Safety Officers' Benefits program, administered through the Bureau of Justice Assistance (BJA), provides a tax-free death benefit to eligible survivors of public safety officers whose death is the direct and proximate result of a traumatic injury sustained in the line of duty. The death benefit is not includible in the decedent's gross estate for federal estate tax purposes or the survivor's gross income for federal income tax purposes.

A public safety officer is a law enforcement officer, firefighter, or member of a public rescue squad or ambulance crew. In certain circumstances, a chaplain killed in the line of duty is also a public safety officer. The chaplain must have been responding to a fire, rescue, or police emergency as a member or employee of a fire or police department.

This program can pay survivors an emergency interim benefit of up to \$3,000 if it finds that the death of the public safety officer is one for which a final benefit will probably be paid. If there is no final payment, the recipient of the interim benefit is liable for repayment. However, the BJA may not require all or part of the repayment if it will cause a hardship. If that happens, that amount is tax free.



For more information on this program, you may contact the BJA by calling 1-888-744-6513, or 202-307-0635 if you are in the metropolitan Washington, D.C., calling area.



Additional information about this program is also available on the BJA website at www.ojp.usdoj.gov/BJA.

FERS Death Benefit

You may be entitled to a special FERS death benefit if you were the spouse of an active FERS employee who died after at least 18 months of federal service. At your option, you can take the benefit in the form of a single payment or in the form of a special annuity payable over a 3-year period.

The tax treatment of the special death benefit depends on the option you choose and whether a FERS survivor annuity is also paid.

If you choose the single payment option, use the following rules.

- If a FERS survivor annuity is not paid, at least part of the special death benefit is tax free. The tax-free part is an amount equal to the employee's FERS contributions.
- If a FERS survivor annuity is also paid, all of the special death benefit is taxable. You cannot allocate any of the employee's FERS contributions to the special death benefit.

If you choose the 3-year annuity option, at least part of each monthly payment is tax free. Use the following rules.

- If a FERS survivor annuity is not paid, the tax-free part of each monthly payment is an amount equal to the employee's FERS contributions divided by 36.
- If a FERS survivor annuity is also paid, allocate the employee's FERS contributions between the 3-year annuity and the survivor annuity. Make the allocation in the same proportion that the expected return from each annuity bears to the total expected return from both annuities. Divide the amount allocated to the 3-year annuity by 36. The result is the tax-free part of each monthly payment of the 3-year annuity.

CSRS or FERS Survivor Annuity

If you receive a CSRS or FERS survivor annuity, you can recover the employee's cost tax free. The employee's cost is the total of the retirement plan contributions that were taken out of his or her pay.

How you figure the tax-free recovery of the cost depends on your annuity starting date. This is the day after the date of the employee's death. The methods to use are the same as those described near the beginning of Part II under [Recovering your cost tax free](#).

The following discussions cover only the Simplified Method. You can use this method if your annuity starting date is after July 1, 1986. You must use this method if your annuity starting date is after November 18, 1996. Under the Simplified Method, each of your monthly annuity payments is made up of two parts: the tax-free part that is a return of the employee's cost and the taxable part that is the amount of each payment that is more than the part that represents the employee's cost. The tax-free part remains

the same, even if your annuity is increased. However, see [Exclusion limit](#), later.

Surviving spouse with no children receiving annuities. Under the Simplified Method, you figure the tax-free part of each full monthly annuity payment by dividing the employee's cost by a number of months based on your age. This number will differ depending on whether your annuity starting date is before November 19, 1996, or after November 18, 1996. To use the Simplified Method, complete [Worksheet A](#). Specific instructions for [Worksheet A](#) are given in Part II under [Simplified Method](#).

Example. Diane Green, age 48, began receiving a \$1,500 monthly CSRS annuity in March 2011 upon the death of her husband. Her husband was a federal employee when he died. She received 10 payments in 2011. Her husband had contributed \$36,000 to the retirement plan.

Diane must use the Simplified Method. Her completed [Worksheet A](#) is shown on the next page. To complete line 3, she used Table 1 at the bottom of the worksheet and found that 360 is the number in the last column opposite the age range that includes her age. Diane keeps a copy of the completed worksheet for her records. It will help her figure her taxable annuity in later years.

Diane's tax-free monthly amount is \$100 (line 4 of her worksheet). If she lives to collect more than 360 payments, the payments after the 360th will be fully taxable. If she dies before 360 payments have been made, a miscellaneous itemized deduction (not subject to the 2%-of-adjusted-gross-income limit) will be allowed for the unrecovered cost on her final income tax return.

Surviving spouse with child. If the survivor benefits include both a life annuity for the surviving spouse and one or more temporary annuities for the employee's children, an additional step is needed under the Simplified Method to allocate the monthly exclusion among the beneficiaries correctly.

Figure the total monthly exclusion for all beneficiaries by completing lines 2 through 4 of [Worksheet A](#) as if only the surviving spouse received an annuity. Then, to figure the monthly exclusion for each beneficiary, multiply line 4 of the worksheet by a fraction. For any beneficiary, the numerator of the fraction is that beneficiary's monthly annuity and the denominator is the total of the monthly annuity payments to all the beneficiaries.

The ending of a child's temporary annuity does not affect the total monthly exclusion figured under the Simplified Method. The total exclusion merely needs to be reallocated at that time among the remaining beneficiaries. If only the surviving spouse is left drawing an annuity, the surviving spouse is entitled to the entire monthly exclusion as figured in the worksheet.

Example. The facts are the same as in the example for Diane Green in the preceding discussion except that the Greens had a son, Robert, who was age 15 at the time of his father's death. Robert is entitled to a \$500 per month temporary annuity until he reaches age 18 (age 22, if he remains a full-time student and does not marry).

In completing [Worksheet A](#) (not shown), Diane fills out the entries through line 4 exactly as shown in the filled-in worksheet for the earlier example. That is, she includes on line 1 only the amount of the annuity she herself received

and she uses on line 3 the 360 factor for her age. After arriving at the \$100 monthly exclusion on line 4, however, Diane allocates it between her own annuity and that of her son.

To find how much of the monthly exclusion to allocate to her own annuity, Diane multiplies the \$100 monthly exclusion by the fraction \$1,500 (her monthly annuity) over \$2,000 (the total of her \$1,500 and Robert's \$500 annuities). She enters the result, \$75, just below the entry space for line 4. She completes the worksheet by entering \$750 on lines 5 and 8 and \$14,250 on line 9.

A second Worksheet A (not shown) is completed for Robert's annuity. On line 1, he enters \$5,000 as the total annuity received. Lines 2, 3, and 4 are the same as those on his mother's worksheet. In allocating the \$100 monthly exclusion on line 4 to his annuity, Robert multiplies it by the fraction \$500 over \$2,000. His resulting monthly exclusion is \$25. His exclusion for the year (line 8) is \$250 and his taxable annuity for the year (line 9) is \$4,750.

Diane and Robert only need to complete lines 10 and 11 on a single worksheet to keep track of their unrecovered cost for next year. These lines are exactly as shown in the filled-in Worksheet A for the earlier example.

When Robert's temporary annuity ends, the computation of the total monthly exclusion will not change. The only difference will be that Diane will then claim the full exclusion against her annuity alone.

Surviving child only. A method similar to the Simplified Method also can be used to figure the taxable and nontaxable parts of a temporary annuity for a surviving child when there is no surviving spouse annuity. To use this method, divide the deceased employee's cost by the number of months from the child's annuity starting date until the date the child will reach age 22. The result is the monthly exclusion. (However, the monthly exclusion cannot be more than the monthly annuity payment. You can carry over unused exclusion amounts to apply against future annuity payments.)

More than one child. If there is more than one child entitled to a temporary annuity (and no surviving spouse annuity), divide the cost by the number of months of payments until the date the youngest child will reach age 22. This monthly exclusion must then be allocated among the children in proportion to their monthly annuity payments, like the exclusion shown in the previous example.

Disabled child. If a child otherwise entitled to a temporary annuity was permanently disabled at the annuity starting date (and there is no surviving spouse annuity), that child is treated for tax purposes as receiving a lifetime annuity, like a surviving spouse. The child must complete line 3 of Worksheet A using a number in Table 1 at the bottom of the worksheet corresponding to the child's age at the annuity starting date. If more than one child is entitled to a temporary annuity, an allocation like the one shown under [Surviving spouse with child](#), earlier, must be made to determine each child's share of the exclusion.

Exclusion limit. If your annuity starting date is after 1986, the most that can be recovered tax free is the cost of the annuity. Once the total of your exclusions equals the cost, your entire annuity is taxable. If your annuity starting date is before 1987, the tax-free part of each whole monthly payment remains the same each year you receive payments—even if you outlive the number of months used on

line 3 of the Simplified Method Worksheet. The total exclusion may be more than the cost of the annuity.

Deduction of unrecovered cost. If the annuity starting date is after July 1, 1986, and the annuitant's death occurs before all the cost is recovered tax free, the unrecovered cost can be claimed as a miscellaneous itemized deduction (not subject to the 2%-of-adjusted-gross-income limit) for the annuitant's last tax year.

Survivors of Slain Public Safety Officers

Generally, if you receive survivor annuity payments as the spouse, former spouse, or child of a public safety officer killed in the line of duty, you can exclude the payments from your income. The annuity is excludable to the extent that it is due to the officer's service as a public safety officer. Public safety officers include law enforcement officers, firefighters, chaplains, ambulance crew members, and rescue squad members. The provision applies to a chaplain killed in the line of duty after September 10, 2001. The chaplain must have been responding to a fire, rescue, or police emergency as a member or employee of a fire or police department.

The exclusion does not apply if your actions were a substantial contributing factor to the death of the officer. It also does not apply if:

- The death was caused by the intentional misconduct of the officer or by the officer's intention to cause his or her own death,
- The officer was voluntarily intoxicated at the time of death, or
- The officer was performing his or her duties in a grossly negligent manner at the time of death.



The special death benefit paid to the spouse of a FERS employee (see [FERS Death Benefit](#), earlier) is not eligible for this exclusion.

Lump-Sum CSRS or FERS Payment

If a federal employee dies before retiring and leaves no one eligible for a survivor annuity, the estate or other beneficiary will receive a lump-sum payment from the CSRS or FERS. This single payment is made up of the regular contributions to the retirement fund plus accrued interest, if any, to the extent not already paid to the employee.

The beneficiary is taxed, in the year the lump sum is distributed or made available, only on the amount of any accrued interest. The taxable amount, if any, generally cannot be rolled over into an IRA or other plan and is subject to federal income tax withholding at a 10% rate. However, a nonspousal beneficiary making a transfer described under [Rollovers by nonspouse beneficiary](#) under [Rollover Rules](#) in Part II, can roll over any taxable amount. In addition, the payment may qualify as a lump-sum distribution eligible for capital gain treatment or the 10-year tax option if the plan participant was born before January 2, 1936. If the beneficiary also receives a lump-sum payment of unrecovered voluntary contributions plus interest, this treatment applies only if the payment is received within the

Worksheet A. Simplified Method for Diane Green

See the instructions in Part II of this publication under [Simplified Method](#).

<p>1. Enter the total pension or annuity payments received this year. Also, add this amount to the total for Form 1040, line 16a; Form 1040A, line 12a; or Form 1040NR, line 17a.</p>	<p>1. <u> \$ 15,000</u></p>
<p>2. Enter your cost in the plan at the annuity starting date, plus any death benefit exclusion*. See Your cost in Part II, Rules for Retirees, earlier</p> <p>Note: If your annuity starting date was before this year and you completed this worksheet last year, skip line 3 and enter the amount from line 4 of last year's worksheet on line 4 below (even if the amount of your pension or annuity has changed). Otherwise, go to line 3.</p>	<p>2. <u> 36,000</u></p>
<p>3. Enter the appropriate number from Table 1 below. But if your annuity starting date was after 1997 and the payments are for your life and that of your beneficiary, enter the appropriate number from Table 2 below.</p>	<p>3. <u> 360</u></p>
<p>4. Divide line 2 by the number on line 3</p>	<p>4. <u> 100</u></p>
<p>5. Multiply line 4 by the number of months for which this year's payments were made. If your annuity starting date was before 1987, enter this amount on line 8 below and skip lines 6, 7, 10, and 11. Otherwise, go to line 6</p>	<p>5. <u> 1,000</u></p>
<p>6. Enter any amounts previously recovered tax free in years after 1986. This is the amount shown on line 10 of your worksheet for last year</p>	<p>6. <u> 0</u></p>
<p>7. Subtract line 6 from line 2</p>	<p>7. <u> 36,000</u></p>
<p>8. Enter the smaller of line 5 or line 7</p>	<p>8. <u> 1,000</u></p>
<p>9. Taxable amount for year. Subtract line 8 from line 1. Enter the result, but not less than zero. Also, add this amount to the total for Form 1040, line 16b, or Form 1040A, line 12b. If you are a nonresident alien, also enter this amount on line 1 of Worksheet C. If your Form CSA 1099R or Form CSF 1099R shows a larger amount, use the amount figured on this line instead. If you are a retired public safety officer, see Distributions Used To Pay Insurance Premiums for Public Safety Officers in Part II before entering an amount on your tax return or Worksheet C, line 1</p>	<p>9. <u> \$ 14,000</u></p>
<p>10. Was your annuity starting date before 1987?</p> <p><input type="checkbox"/> Yes. Do not complete the rest of this worksheet.</p> <p><input checked="" type="checkbox"/> No. Add lines 6 and 8. This is the amount you have recovered tax free through 2011. You will need this number if you need to fill out this worksheet next year</p>	<p>10. <u> 1,000</u></p>
<p>11. Balance of cost to be recovered. Subtract line 10 from line 2. If zero, you will not have to complete this worksheet next year. The payments you receive next year will generally be fully taxable</p>	<p>11. <u> \$ 35,000</u></p>

Table 1 for Line 3 Above

IF your age on your annuity starting date was	AND your annuity starting date was—	
	before November 19, 1996, THEN enter on line 3	after November 18, 1996, THEN enter on line 3
55 or under	300	360
56–60	260	310
61–65	240	260
66–70	170	210
71 or over	120	160

Table 2 for Line 3 Above

IF the annuitants' combined ages on your annuity starting date were	THEN enter on line 3
110 or under	410
111–120	360
121–130	310
131–140	260
141 or over	210

* A death benefit exclusion of up to \$5,000 applied to certain benefits received by survivors of employees who died before August 21, 1996.

same tax year. For more information, see *Lump-Sum Distributions* in Publication 575.

Lump-sum payment at end of survivor annuity. If an annuity is paid to the federal employee's survivor and the survivor annuity ends before an amount equal to the deceased employee's contributions plus any interest has been paid out, the rest of the contributions plus any interest will be paid in a lump sum to the employee's estate or other beneficiary. Generally, this beneficiary will not have to include any of the lump sum in gross income because, when it is added to the amount of the annuity previously received that was excludable, it still will be less than the employee's total contributions.

Any unrecovered cost is allowed as a miscellaneous itemized deduction on the final return of the annuitant. This deduction is not subject to the 2%-of-adjusted-gross-income limit.



To figure the taxable amount, if any, use the following worksheet.

Worksheet D. Lump-Sum Payment at End of Survivor Annuity

Keep for Your Records



1. Enter the lump-sum payment	1. _____
2. Enter the amount of annuity previously received tax free	2. _____
3. Add lines 1 and 2	3. _____
4. Enter the employee's total cost	4. _____
5. Taxable amount. Subtract line 4 from line 3. Enter the result, but not less than zero	5. _____

The taxable amount, if any, generally cannot be rolled over into an IRA or other plan and is subject to federal income tax withholding at a 10% rate. However, a non-spousal beneficiary making a transfer described under [Rollovers by nonspouse beneficiary](#) under *Rollover Rules* in Part II, can roll over any taxable amount. In addition, the payment may qualify as a lump-sum distribution eligible for capital gain treatment or the 10-year tax option if the plan participant was born before January 2, 1936. If the beneficiary also receives a lump-sum payment of unrecovered voluntary contributions plus interest, this treatment applies only if the payment is received within the same tax year. For more information, see *Lump-Sum Distributions* in Publication 575.

Example. At the time of your brother's death in December 2010, he was employed by the Federal Government and had contributed \$45,000 to the CSRS. His widow received \$6,600 in survivor annuity payments before she died in 2011. She had used the Simplified Method for reporting her annuity and properly excluded \$1,000 from gross income.

Only \$6,600 of the guaranteed amount of \$45,000 (your brother's contributions) was paid as an annuity, so the balance of \$38,400 was paid to you in a lump sum as your brother's sole beneficiary. You figure the taxable amount of this payment as follows.

Worksheet D. Lump-Sum Payment at End of Survivor Annuity — Example

1. Enter the lump-sum payment	1. \$ 38,400
2. Enter the amount of annuity previously received tax free	2. 1,000
3. Add lines 1 and 2	3. 39,400
4. Enter the employee's total cost	4. 45,000
5. Taxable amount. Subtract line 4 from line 3. Enter the result, but not less than zero	5. 0

Voluntary contributions. If a CSRS employee dies before retiring from government service, any voluntary contributions to the retirement fund cannot be used to provide an additional annuity to the survivors. Instead, the voluntary contributions plus any accrued interest will be paid in a lump sum to the estate or other beneficiary. The beneficiary generally must include any interest received in income for the year distributed or made available. However, if the beneficiary is the employee's surviving spouse (or someone other than the employee's spouse making a transfer described under [Rollovers by nonspouse beneficiary](#) under *Rollover Rules* in Part II), the interest can be rolled over. See also [Rollovers by surviving spouse](#) under *Rollover Rules* in Part II.

The interest, if not rolled over, generally is subject to federal income tax withholding at a 20% rate (or 10% rate if the beneficiary is not the employee's surviving spouse). It may qualify as a lump-sum distribution eligible for capital gain treatment or the 10-year tax option if:

- The plan participant was born before January 2, 1936,
- Regular annuity benefits cannot be paid under the retirement system, and
- The beneficiary also receives a lump-sum payment of the regular contributions plus interest within the same tax year as the voluntary contributions.

For more information, see *Lump-Sum Distributions* in Publication 575.

Thrift Savings Plan

The payment you receive as the beneficiary of a decedent's Thrift Savings Plan (TSP) account is fully taxable. However, if you are the decedent's surviving spouse (or someone other than the employee's spouse making a transfer described under [Rollovers by nonspouse beneficiary](#) in Part II under *Rollover Rules*), you generally can roll over the payment tax free. If you do not choose a direct rollover of the decedent's TSP account, mandatory 20% income tax withholding will apply. For more information, see *Rollover Rules* in Part II. If you are neither the surviving spouse nor someone other than the employee's spouse making a transfer described above, the payment is not eligible for rollover treatment. The TSP will withhold 10% of the payment for federal income tax, unless you gave the TSP a Form W-4P to choose not to have tax withheld.

If the entire TSP account balance is paid to the beneficiaries in the same calendar year, it may qualify as a

lump-sum distribution eligible for the 10-year tax option if the plan participant was born before January 2, 1936. See *Lump-Sum Distributions* in Publication 575 for details. Also, see Important Tax Information About Thrift Savings Plan Death Benefit Payments, which is available from the TSP.

Beneficiary participant account. A beneficiary participant account will be established for a spouse beneficiary. The money in the account is not subject to Federal income tax until it is withdrawn. For more information on beneficiary participant accounts, see Death Benefits, Information for Beneficiaries, available from the TSP.



Both of the above TSP documents are available on the TSP website at www.tsp.gov. Select “Forms & Publications.”



If you receive a payment from a uniformed services TSP account that includes contributions from combat zone pay, see [Uniformed services Thrift Savings Plan \(TSP\) accounts](#), under Reminders near the beginning of this publication.

Federal Estate Tax

Form 706, United States Estate (and Generation-Skipping Transfer) Tax Return, must be filed for the estate of citizen or resident alien of the United States who died in 2011 if the gross estate is more than \$5,000,000. Included in this \$5,000,000 are any adjusted taxable gifts made by the decedent after 1976 and the specific exemption allowed for gifts by the decedent after September 8, 1976, and before 1977.

The gross estate generally includes the value of all property beneficially owned by the decedent at the time of death. Examples of property included in the gross estate are salary or annuity payments that had accrued to an employee or retiree, but which were not paid before death, and the balance in the decedent’s TSP account.

The gross estate also usually includes the value of the death and survivor benefits payable under the CSRS or the FERS. If the federal employee died leaving no one eligible to receive a survivor annuity, the lump sum (representing the employee’s contribution to the retirement system plus any accrued interest) payable to the estate or other beneficiary is included in the employee’s gross estate.

Marital deduction. The estate tax marital deduction is a deduction from the gross estate of the value of property that is included in the gross estate but that passes, or has passed, to the surviving spouse. Generally, there is no limit on the amount of the marital deduction. Community property passing to the surviving spouse qualifies for the marital deduction.

More information. For more information, get Publication 950, Introduction to Estate and Gift Taxes, and Publication 559, Survivors, Executors, and Administrators.

Part V Rules for Survivors of Federal Retirees

This part of the publication is for survivors of federal retirees. It explains how to treat amounts you receive because of the retiree’s death. If you are the survivor of a federal employee, see [Part IV](#).

Decedent’s retirement benefits. Retirement benefits accrued and payable to a CSRS or FERS retiree before death, but paid to you as a survivor, are taxable in the same manner and to the same extent these benefits would have been taxable had the retiree lived to receive them.

CSRS or FERS Survivor Annuity

CSRS or FERS annuity payments you receive as the survivor of a federal retiree are fully or partly taxable under either the General Rule or the Simplified Method.

Cost recovered. If the retiree reported the annuity under the Three-Year Rule and recovered all of the cost tax free, your survivor annuity payments are fully taxable. This is also true if the retiree had an annuity starting date after 1986, reported the annuity under the General Rule or the Simplified Method, and had fully recovered the cost tax free.

General Rule. If the retiree was reporting the annuity under the General Rule, figure the tax-free part of the annuity using the same exclusion percentage that the retiree used. Apply the exclusion percentage to the amount specified as your survivor annuity at the retiree’s annuity starting date. Do not apply the exclusion percentage to any cost-of-living increases made after that date. Those increases are fully taxable. For more information about the General Rule, get Publication 939.

Simplified Method. If the retiree was reporting the annuity under the Simplified Method, your tax-free monthly amount is the same as the retiree’s monthly exclusion (Worksheet A, line 4). This amount remains fixed even if the monthly payment is increased or decreased. A cost-of-living increase in your survivor annuity payments does not change the amount you can exclude from gross income.

Exclusion limit. If the retiree’s annuity starting date was before 1987, you can exclude the tax-free amount from all the annuity payments you receive. This includes any payments received after you recover the cost tax free.

If the retiree’s annuity starting date is after 1986, you can exclude the tax-free amount only until you recover the cost tax free. The annuity payments you receive after you recover the annuity cost tax free are fully taxable.

Deduction of unrecovered cost. If the annuity starting date is after July 1, 1986, and the survivor annuitant’s death occurs before all the cost is recovered tax free, the unrecovered cost can be claimed as a miscellaneous itemized deduction (not subject to the 2%-of-adjusted-gross-income limit) for the annuitant’s last tax year.

Surviving spouse with child. If the survivor benefits include both a life annuity for the surviving spouse and one or more temporary annuities for the retiree's children, the tax-free monthly amount that would otherwise apply to the life annuity must be allocated among the beneficiaries. To figure the tax-free monthly amount for each beneficiary, multiply it by a fraction. The numerator of the fraction is the beneficiary's monthly annuity and the denominator of the fraction is the total of the monthly annuity payments to all the beneficiaries.

Example. John retired in 2009 and began receiving a \$1,147 per month CSRS retirement annuity with a survivor annuity payable to his wife, Kate, upon his death. He reported his annuity using the Simplified Method. Under that method, \$150 of each payment he received was a tax-free recovery of his \$45,000 cost. John received a total of 22 monthly payments and recovered \$3,300 of his cost tax free before his death in 2011. At John's death, Kate began receiving an annuity of \$840 per month and their children, Sam and Lou, began receiving temporary annuities of \$330 each per month. Kate must allocate the \$150 tax-free monthly amount among the three annuities.

To find how much of the monthly exclusion to allocate to her own annuity, Kate multiplies the \$150 tax-free monthly amount by the fraction \$840 (her monthly annuity) over \$1,500 (the total of her \$840, Sam's \$330, and Lou's \$330 monthly annuities). Her resulting monthly exclusion is \$84. In allocating the \$150 monthly exclusion to each child's annuity, the \$150 is multiplied by the fraction \$330 (each child's monthly annuity) over \$1,500. Each child's resulting monthly exclusion is \$33.

Beginning with the month in which either child is no longer eligible for an annuity, Kate will reallocate the \$150 monthly exclusion to her own annuity by multiplying the \$150 by the fraction \$840 over \$1,170 (the total of her \$840 and her other child's \$330 monthly annuities). Her resulting monthly exclusion is \$108. In reallocating the \$150 monthly exclusion to the other child's annuity, the \$150 is multiplied by the fraction \$330 over \$1,170. The other child's resulting monthly exclusion is \$42.

Surviving child only. If the survivor benefits include only a temporary annuity for the retiree's child, allocate the unrecovered cost over the number of months from the date the annuity started until the child reaches age 22. If more than one temporary annuity is paid, allocate the cost over the number of months until the youngest child reaches age 22, and allocate the tax-free monthly amount among the annuities in proportion to the monthly annuity payments.

Lump-Sum CSRS or FERS Payment

If a deceased retiree has no beneficiary eligible to receive a survivor annuity, and the deceased retiree's annuity ends before an amount equal to the deceased retiree's contributions plus any interest has been paid out, the rest of the contributions plus any interest will be paid in a lump sum to the estate or other beneficiary. The estate or other beneficiary rarely will have to include any part of the lump sum in gross income. The taxable amount is figured as follows.

Worksheet E. Lump-Sum Payment at End of Retiree's Annuity (With No Survivor Annuity)

Keep for Your Records



1. Enter the lump-sum payment	1.	_____
2. Enter the amount of annuity received tax free by the retiree	2.	_____
3. Add lines 1 and 2	3.	_____
4. Enter the total cost	4.	_____
5. Taxable amount. Subtract line 4 from line 3. Enter the result, but not less than zero	5.	_____

The taxable amount, if any, generally cannot be rolled over into an IRA or other plan and is subject to federal income tax withholding at a 10% rate. However, a non-spousal beneficiary making a transfer described under [Rollovers by nonspouse beneficiary](#) under *Rollover Rules* in Part II, can roll over any taxable amount. In addition, the payment may qualify as a lump-sum distribution eligible for capital gain treatment or the 10-year tax option if the plan participant was born before January 2, 1936. If the beneficiary also receives a lump-sum payment of unrecovered voluntary contributions plus interest, this treatment applies only if the payment is received within the same tax year. For more information, see *Lump-Sum Distributions* in Publication 575.

Voluntary Contributions

If you receive an additional survivor annuity benefit from voluntary contributions to the CSRS, treat it separately from the annuity that comes from regular contributions. Each year you will receive a Form CSF 1099R that will show how much of your total annuity received in the past year was from each type of benefit.

Figure the taxable and tax-free parts of your additional survivor annuity benefit from voluntary contributions using the same rules that apply to regular CSRS and FERS survivor annuities, as explained earlier under [CSRS or FERS Survivor Annuity](#).

Lump-sum payment. Figure the taxable amount, if any, of a lump-sum payment of the retiree's unrecovered voluntary contributions plus any interest using the rules that apply to regular lump-sum CSRS or FERS payments, as explained earlier under [Lump-Sum CSRS or FERS Payment](#).

Thrift Savings Plan

If you receive a payment from the TSP account of a deceased federal retiree, the payment is fully taxable. However, if you are the retiree's surviving spouse (or someone other than the retiree's spouse making a transfer described under [Rollovers by nonspouse beneficiary](#) in Part II earlier under *Rollover Rules*), you generally can roll over the otherwise taxable payment tax free. If you do not choose a direct rollover of the TSP account, mandatory 20% federal income tax withholding will apply. For more information, see [Rollover Rules](#) in Part II. If you are neither the surviving spouse nor someone other than the retiree's spouse making a transfer described above, the payment is

not eligible for rollover treatment. The TSP will withhold 10% of the payment for federal income tax, unless you gave the TSP a Form W-4P to choose not to have tax withheld.

If the retiree chose to receive his or her account balance as an annuity, the payments you receive as the retiree's survivor are fully taxable when you receive them, whether they are received as annuity payments or as a cash refund of the remaining value of the amount used to purchase the annuity.

Beneficiary participant account. A beneficiary participant account will be established for a spouse beneficiary. The money in the account is not subject to Federal income tax until it is withdrawn. For more information on beneficiary participant accounts, see Death Benefits, Information for Beneficiaries, available from the TSP.



If you receive a payment from a uniformed services TSP account that includes contributions from combat zone pay, see [Uniformed Services Thrift Savings Plan \(TSP\) accounts](#), under Reminders near the beginning of this publication.

Federal Estate Tax

A federal estate tax return may have to be filed for the estate of the retired employee. See [Federal Estate Tax](#) in Part IV.

Income Tax Deduction for Estate Tax Paid

Any income that a decedent had a right to receive and could have received had death not occurred and that was not properly includible in the decedent's final income tax return is treated as income in respect of a decedent. This includes retirement benefits accrued and payable to a retiree before death, but paid to you as a survivor.

If the federal estate tax was paid on the decedent's estate and you are required to include income in respect of a decedent in your gross income for any tax year, you can deduct the portion of the federal estate tax that is from the inclusion in the estate of the right to receive that amount. For this purpose, if the decedent died after the annuity starting date, the taxable portion of a survivor annuity you receive (other than a temporary annuity for a child) is considered income in respect of a decedent.

For more information, see *Income in Respect of a Decedent* in Publication 559.

How To Get Tax Help

You can get help with unresolved tax issues, order free publications and forms, ask tax questions, and get information from the IRS in several ways. By selecting the method that is best for you, you will have quick and easy access to tax help.

Free help with your return. Free help in preparing your return is available nationwide from IRS-certified volunteers. The Volunteer Income Tax Assistance (VITA) program is designed to help low-moderate income taxpayers and the Tax Counseling for the Elderly (TCE) program is

designed to assist taxpayers age 60 and older with their tax returns. Most VITA and TCE sites offer free electronic filing and all volunteers will let you know about credits and deductions you may be entitled to claim. To find the nearest VITA or TCE site, visit [IRS.gov](#) or call 1-800-906-9887 or 1-800-829-1040.

As part of the TCE program, AARP offers the Tax-Aide counseling program. To find the nearest AARP Tax-Aide site, call 1-888-227-7669 or visit AARP's website at [www.aarp.org/money/taxaide](#).

For more information on these programs, go to [IRS.gov](#) and enter keyword "VITA" in the upper right-hand corner.



Internet. You can access the IRS website at [IRS.gov](#) 24 hours a day, 7 days a week to:

- Check the status of your 2011 refund. Go to [IRS.gov](#) and click on *Where's My Refund*. Wait at least 72 hours after the IRS acknowledges receipt of your e-filed return, or 3 to 4 weeks after mailing a paper return. If you filed Form 8379 with your return, wait 14 weeks (11 weeks if you filed electronically). Have your 2011 tax return available so you can provide your social security number, your filing status, and the exact whole dollar amount of your refund.
- *E-file* your return. Find out about commercial tax preparation and *e-file* services available free to eligible taxpayers.
- Download forms, including talking tax forms, instructions, and publications.
- Order IRS products online.
- Research your tax questions online.
- Search publications online by topic or keyword.
- Use the online Internal Revenue Code, regulations, or other official guidance.
- View Internal Revenue Bulletins (IRBs) published in the last few years.
- Figure your withholding allowances using the withholding calculator online at [www.irs.gov/individuals](#).
- Determine if Form 6251 must be filed by using our Alternative Minimum Tax (AMT) Assistant available online at [www.irs.gov/individuals](#).
- Sign up to receive local and national tax news by email.
- Get information on starting and operating a small business.



Phone. Many services are available by phone.

- *Ordering forms, instructions, and publications.* Call 1-800-TAX-FORM (1-800-829-3676) to order current-year forms, instructions, and publications, and prior-year forms and instructions. You should receive your order within 10 days.

- **Asking tax questions.** Call the IRS with your tax questions at 1-800-829-1040.
- **Solving problems.** You can get face-to-face help solving tax problems every business day in IRS Taxpayer Assistance Centers. An employee can explain IRS letters, request adjustments to your account, or help you set up a payment plan. Call your local Taxpayer Assistance Center for an appointment. To find the number, go to www.irs.gov/localcontacts or look in the phone book under *United States Government, Internal Revenue Service*.
- **TTY/TDD equipment.** If you have access to TTY/TDD equipment, call 1-800-829-4059 to ask tax questions or to order forms and publications.
- **TeleTax topics.** Call 1-800-829-4477 to listen to pre-recorded messages covering various tax topics.
- **Refund information.** You can check the status of your refund on the new IRS phone app. Download the free IRS2Go app by visiting the iTunes app store or the Android Marketplace. IRS2Go is a new way to provide you with information and tools. To check the status of your refund by phone, call 1-800-829-4477 (automated refund information 24 hours a day, 7 days a week). Wait at least 72 hours after the IRS acknowledges receipt of your e-filed return, or 3 to 4 weeks after mailing a paper return. If you filed Form 8379 with your return, wait 14 weeks (11 weeks if you filed electronically). Have your 2011 tax return available so you can provide your social security number, your filing status, and the exact whole dollar amount of your refund. If you check the status of your refund and are not given the date it will be issued, please wait until the next week before checking back.
- **Other refund information.** To check the status of a prior-year refund or amended return refund, call 1-800-829-1040.

Evaluating the quality of our telephone services. To ensure IRS representatives give accurate, courteous, and professional answers, we use several methods to evaluate the quality of our telephone services. One method is for a second IRS representative to listen in on or record random telephone calls. Another is to ask some callers to complete a short survey at the end of the call.



Walk-in. Many products and services are available on a walk-in basis.

- **Products.** You can walk in to many post offices, libraries, and IRS offices to pick up certain forms, instructions, and publications. Some IRS offices, libraries, grocery stores, copy centers, city and county government offices, credit unions, and office supply stores have a collection of products available to print from a CD or photocopy from reproducible proofs. Also, some IRS offices and libraries have the Internal Revenue Code, regulations, Internal Revenue Bulletins, and Cumulative Bulletins available for research purposes.

- **Services.** You can walk in to your local Taxpayer Assistance Center every business day for personal, face-to-face tax help. An employee can explain IRS letters, request adjustments to your tax account, or help you set up a payment plan. If you need to resolve a tax problem, have questions about how the tax law applies to your individual tax return, or you are more comfortable talking with someone in person, visit your local Taxpayer Assistance Center where you can spread out your records and talk with an IRS representative face-to-face. No appointment is necessary—just walk in. If you prefer, you can call your local Center and leave a message requesting an appointment to resolve a tax account issue. A representative will call you back within 2 business days to schedule an in-person appointment at your convenience. If you have an ongoing, complex tax account problem or a special need, such as a disability, an appointment can be requested. All other issues will be handled without an appointment. To find the number of your local office, go to www.irs.gov/localcontacts or look in the phone book under *United States Government, Internal Revenue Service*.



Mail. You can send your order for forms, instructions, and publications to the address below. You should receive a response within 10 days after your request is received.

Internal Revenue Service
1201 N. Mitsubishi Motorway
Bloomington, IL 61705-6613

Taxpayer Advocate Service. The Taxpayer Advocate Service (TAS) is your voice at the IRS. Our job is to ensure that every taxpayer is treated fairly, and that you know and understand your rights. We offer free help to guide you through the often-confusing process of resolving tax problems that you haven't been able to solve on your own. Remember, the worst thing you can do is nothing at all.

TAS can help if you can't resolve your problem with the IRS and:

- Your problem is causing financial difficulties for you, your family, or your business.
- You face (or your business is facing) an immediate threat of adverse action.
- You have tried repeatedly to contact the IRS but no one has responded, or the IRS has not responded to you by the date promised.

If you qualify for our help, we'll do everything we can to get your problem resolved. You will be assigned to one advocate who will be with you at every turn. We have offices in every state, the District of Columbia, and Puerto Rico. Although TAS is independent within the IRS, our advocates know how to work with the IRS to get your problems resolved. And our services are always free.

As a taxpayer, you have rights that the IRS must abide by in its dealings with you. Our tax toolkit at www.TaxpayerAdvocate.irs.gov can help you understand these rights.

If you think TAS might be able to help you, call your local advocate, whose number is in your phone book and on our website at www.irs.gov/advocate. You can also call our toll-free number at 1-877-777-4778.

TAS also handles large-scale or systemic problems that affect many taxpayers. If you know of one of these broad issues, please report it to us through our Systemic Advocacy Management System at www.irs.gov/advocate.

Low Income Taxpayer Clinics (LITCs). Low Income Taxpayer Clinics (LITCs) are independent from the IRS. Some clinics serve individuals whose income is below a certain level and who need to resolve a tax problem. These clinics provide professional representation before the IRS or in court on audits, appeals, tax collection disputes, and other issues for free or for a small fee. Some clinics can provide information about taxpayer rights and responsibilities in many different languages for individuals who speak English as a second language. For more information and to find a clinic near you, see the LITC page on www.irs.gov/advocate or IRS Publication 4134, *Low Income Taxpayer Clinic List*. This publication is also available by calling 1-800-829-3676 or at your local IRS office.

Free tax services. Publication 910, *IRS Guide to Free Tax Services*, is your guide to IRS services and resources. Learn about free tax information from the IRS, including publications, services, and education and assistance programs. The publication also has an index of over 100 TeleTax topics (recorded tax information) you can listen to on the telephone. The majority of the information and services listed in this publication are available to you free of charge. If there is a fee associated with a resource or service, it is listed in the publication.

Accessible versions of IRS published products are available on request in a variety of alternative formats for people with disabilities.



DVD for tax products. You can order Publication 1796, *IRS Tax Products DVD*, and obtain:

- Current-year forms, instructions, and publications.
- Prior-year forms, instructions, and publications.
- Tax Map: an electronic research tool and finding aid.
- Tax law frequently asked questions.
- Tax Topics from the IRS telephone response system.
- Internal Revenue Code—Title 26 of the U.S. Code.
- Links to other Internet based Tax Research materials.
- Fill-in, print, and save features for most tax forms.
- Internal Revenue Bulletins.
- Toll-free and email technical support.
- Two releases during the year.
 - The first release will ship the beginning of January 2012.
 - The final release will ship the beginning of March 2012.

Purchase the DVD from National Technical Information Service (NTIS) at www.irs.gov/cdorders for \$30 (no handling fee) or call 1-877-233-6767 toll free to buy the DVD for \$30 (plus a \$6 handling fee).

Worksheet A. Simplified Method

Keep for Your Records



See the instructions in Part II of this publication under [Simplified Method](#).

<p>1. Enter the total pension or annuity payments received this year. Also, add this amount to the total for Form 1040, line 16a; Form 1040A, line 12a; or Form 1040NR, line 17a.</p> <p>2. Enter your cost in the plan at the annuity starting date, plus any death benefit exclusion*. See Your cost in Part II, Rules for Retirees, earlier</p> <p>Note: If your annuity starting date was before this year and you completed this worksheet last year, skip line 3 and enter the amount from line 4 of last year's worksheet on line 4 below (even if the amount of your pension or annuity has changed). Otherwise, go to line 3.</p> <p>3. Enter the appropriate number from Table 1 below. But if your annuity starting date was after 1997 and the payments are for your life and that of your beneficiary, enter the appropriate number from Table 2 below.</p> <p>4. Divide line 2 by the number on line 3</p> <p>5. Multiply line 4 by the number of months for which this year's payments were made. If your annuity starting date was before 1987, enter this amount on line 8 below and skip lines 6, 7, 10, and 11. Otherwise, go to line 6</p> <p>6. Enter any amounts previously recovered tax free in years after 1986. This is the amount shown on line 10 of your worksheet for last year</p> <p>7. Subtract line 6 from line 2</p> <p>8. Enter the smaller of line 5 or line 7</p> <p>9. Taxable amount for year. Subtract line 8 from line 1. Enter the result, but not less than zero. Also, add this amount to the total for Form 1040, line 16b, or Form 1040A, line 12b. If you are a nonresident alien, enter this amount on line 1 of Worksheet C. If your Form CSA 1099R or Form CSF 1099R shows a larger amount, use the amount figured on this line instead. If you are a retired public safety officer, see Distributions Used To Pay Insurance Premiums for Public Safety Officers in Part II before entering an amount on your tax return or Worksheet C, line 1</p> <p>10. Was your annuity starting date before 1987?</p> <p><input type="checkbox"/> Yes. STOP Do not complete the rest of this worksheet.</p> <p><input type="checkbox"/> No. Add lines 6 and 8. This is the amount you have recovered tax free through 2011. You will need this number if you need to fill out this worksheet next year</p> <p>11. Balance of cost to be recovered. Subtract line 10 from line 2. If zero, you will not have to complete this worksheet next year. The payments you receive next year will generally be fully taxable</p>	<p>1. _____</p> <p>2. _____</p> <p>3. _____</p> <p>4. _____</p> <p>5. _____</p> <p>6. _____</p> <p>7. _____</p> <p>8. _____</p> <p>9. _____</p> <p>10. _____</p> <p>11. _____</p>
---	---

Table 1 for Line 3 Above

IF your age on your annuity starting date was	AND your annuity starting date was—	
	before November 19, 1996, THEN enter on line 3	after November 18, 1996, THEN enter on line 3
55 or under	300	360
56–60	260	310
61–65	240	260
66–70	170	210
71 or over	120	160

Table 2 for Line 3 Above

IF the annuitants' combined ages on your annuity starting date were	THEN enter on line 3
110 or under	410
111–120	360
121–130	310
131–140	260
141 or over	210

* A death benefit exclusion of up to \$5,000 applied to certain benefits received by survivors of employees who died before August 21, 1996.

Worksheet B. **Lump-Sum Payment**

See the instructions in Part II of this publication under Alternative Annuity Option.

Keep for Your Records



1. Enter your lump-sum credit (your cost in the plan at the annuity starting date)	1.	_____
2. Enter the present value of your annuity contract	2.	_____
3. Divide line 1 by line 2.	3.	_____
4. Tax-free amount. Multiply line 1 by line 3. (<i>Caution: Do not include this amount on line 6 of Worksheet A in this publication.</i>)	4.	_____
5. Taxable amount (net cost in the plan). Subtract line 4 from line 1. Include this amount in the total on Form 1040, line 16b; Form 1040A, line 12b; or Form 1040NR, line 17b. Also, enter this amount on line 2 of Worksheet A in this publication.	5.	_____



A		Free tax services 25	Refund of contributions 3
Alternative annuity option:			Retirees, rules for 4
How to report 8		Retirement during the past
Lump-sum payment 8	G	year 9
Annual leave 9	General Rule 6 , 23	Rollovers:
Annuity:		Gift tax 9	Nonspouse beneficiary 15
Starting date 5	H	Rollover rules 13
Statement 5	Help (<i>See Tax help</i>)	To Roth IRAs 15
With survivor benefit 19		
Without survivor benefit 5	I	S
Assistance (<i>See Tax help</i>)	Income in respect of a	Simplified Method 6 , 23
		decedent 25	Substantial gainful activity 18
		Income tax withholding 3 , 17	Survivor annuity 5 , 19 , 23
			Survivors of federal
			employees 18
			Survivors of federal retirees 23
B		L	T
Benefits, how to report 16	Lump-sum CSRS or FERS	Tax help 25
		payment 20 , 24	Taxpayer Advocate 26
		Lump-sum payment:	Thrift Savings Plan 2 , 12
		Alternative annuity option	TTY/TDD information 25
	 8	
		Installments	
	 8	
		Withholding	
	 3	
		M	U
		Mandatory retirement age 18	Uniformed services Thrift Savings
		Marital deduction 23	Plan 2
		Minimum retirement age 17	Unused annual leave 18
		More information (<i>See Tax help</i>)	
		N	V
		Nonresident alien retiree 11	Voluntary contributions 9 , 22 , 24
		P	W
		Permanently and totally	Withholding certificate 3
		disabled 18	Withholding of income tax 3 , 17
		Physician’s statement 18	
		Public safety officers:	Worksheets:
		Dependents 18	Lump-sum payment at end of
		Insurance premiums 16	survivor annuity 22
		Survivors 20	Lump-sum payment to the estate or
			other beneficiary 24
		Publications (<i>See Tax help</i>)	Nonresident alien retiree 11
			Simplified Method 28
		Q	
		Qualified domestic relations order	
		(QDRO) 14	
		R	
		Reemployment after	
		retirement 11	
E			
Estate tax 23 , 25		
Estimated tax 3 , 4		
F			
Federal Employees’ Compensation			
Act (FECA) 17			
Filing requirements 4		
Form:			
1099-R 4		
CSA 1099R 3		
CSF 1099R 4		
W-4P-A 3		

Tax Publications for Individual Taxpayers

See *How To Get Tax Help* for a variety of ways to get publications, including by computer, phone, and mail.

General Guides		Specialized Publications	
1	Your Rights as a Taxpayer	531	Reporting Tip Income
17	Your Federal Income Tax For Individuals	535	Business Expenses
334	Tax Guide for Small Business (For Individuals Who Use Schedule C or C-EZ)	536	Net Operating Losses (NOLs) for Individuals, Estates, and Trusts
509	Tax Calendars for 2012	537	Installment Sales
910	IRS Guide to Free Tax Services	541	Partnerships
3	Armed Forces' Tax Guide	544	Sales and Other Dispositions of Assets
54	Tax Guide for U.S. Citizens and Resident Aliens Abroad	547	Casualties, Disasters, and Thefts
225	Farmer's Tax Guide	550	Investment Income and Expenses (Including Capital Gains and Losses)
463	Travel, Entertainment, Gift, and Car Expenses	551	Basis of Assets
501	Exemptions, Standard Deduction, and Filing Information	554	Tax Guide for Seniors
502	Medical and Dental Expenses (Including the Health Coverage Tax Credit)	555	Community Property
503	Child and Dependent Care Expenses	556	Examination of Returns, Appeal Rights, and Claims for Refund
504	Divorced or Separated Individuals	559	Survivors, Executors, and Administrators
505	Tax Withholding and Estimated Tax	561	Determining the Value of Donated Property
514	Foreign Tax Credit for Individuals	570	Tax Guide for Individuals With Income From U.S. Possessions
516	U.S. Government Civilian Employees Stationed Abroad	571	Tax-Sheltered Annuity Plans (403(b) Plans) For Employees of Public Schools and Certain Tax-Exempt Organizations
517	Social Security and Other Information for Members of the Clergy and Religious Workers	575	Pension and Annuity Income
519	U.S. Tax Guide for Aliens	584	Casualty, Disaster, and Theft Loss Workbook (Personal-Use Property)
521	Moving Expenses	587	Business Use of Your Home (Including Use by Daycare Providers)
523	Selling Your Home	590	Individual Retirement Arrangements (IRAs)
524	Credit for the Elderly or the Disabled	594	The IRS Collection Process
525	Taxable and Nontaxable Income	596	Earned Income Credit (EIC)
526	Charitable Contributions	721	Tax Guide to U.S. Civil Service Retirement Benefits
527	Residential Rental Property (Including Rental of Vacation Homes)	901	U.S. Tax Treaties
529	Miscellaneous Deductions	907	Tax Highlights for Persons with Disabilities
530	Tax Information for Homeowners	908	Bankruptcy Tax Guide
		915	Social Security and Equivalent Railroad Retirement Benefits
		925	Passive Activity and At-Risk Rules
		926	Household Employer's Tax Guide For Wages Paid in 2012
		929	Tax Rules for Children and Dependents
		936	Home Mortgage Interest Deduction
		946	How To Depreciate Property
		947	Practice Before the IRS and Power of Attorney
		950	Introduction to Estate and Gift Taxes
		969	Health Savings Accounts and Other Tax-Favored Health Plans
		970	Tax Benefits for Education
		971	Innocent Spouse Relief
		972	Child Tax Credit
		1542	Per Diem Rates (For Travel Within the Continental United States)
		1544	Reporting Cash Payments of Over \$10,000 (Received in a Trade or Business)
		1546	Taxpayer Advocate Service – Your Voice at the IRS
		Spanish Language Publications	
		1SP	Derechos del Contribuyente
		17(SP)	El Impuesto Federal sobre los Ingresos Para Personas Físicas
		547(SP)	Hechos Fortuitos Desastres y Robos
		584(SP)	Registro de Pérdidas por Hechos Fortuitos (Imprevistos), Desastres y Robos (Propiedad de Uso Personal)
		594SP	El Proceso de Cobro del IRS
		596SP	Crédito por Ingreso del Trabajo
		850(EN/SP)	English-Spanish Glossary of Words and Phrases Used in Publications Issued by the Internal Revenue Service
		1544 (SP)	Informe de Pagos en Efectivo en Exceso de \$10,000 (Recibidos en una Ocupación o Negocio)

Commonly Used Tax Forms

See *How To Get Tax Help* for a variety of ways to get forms, including by computer, phone, and mail.

Form Number and Title		Form Number and Title	
1040	U.S. Individual Income Tax Return	2441	Child and Dependent Care Expenses
Sch A	Itemized Deductions	2848	Power of Attorney and Declaration of Representative
Sch B	Interest and Ordinary Dividends	2848(SP)	Poder Legal y Declaración del Representante
Sch C	Profit or Loss From Business	3903	Moving Expenses
Sch C-EZ	Net Profit From Business	4562	Depreciation and Amortization
Sch D	Capital Gains and Losses	4868	Application for Automatic Extension of Time To File U.S. Individual Income Tax Return
Sch E	Supplemental Income and Loss	4868(SP)	Solicitud de Prórroga Automática para Presentar la Declaración del Impuesto sobre el Ingreso Personal de los Estados Unidos
Sch EIC	Earned Income Credit	4952	Investment Interest Expense Deduction
Sch F	Profit or Loss From Farming	5329	Additional Taxes on Qualified Plans (Including IRAs) and Other Tax-Favored Accounts
Sch H	Household Employment Taxes	6251	Alternative Minimum Tax—Individuals
Sch J	Income Averaging for Farmers and Fishermen	8283	Noncash Charitable Contributions
Sch R	Credit for the Elderly or the Disabled	8582	Passive Activity Loss Limitations
Sch SE	Self-Employment Tax	8606	Nondeductible IRAs
1040A	U.S. Individual Income Tax Return	8812	Additional Child Tax Credit
Sch B	Interest and Ordinary Dividends	8822	Change of Address
1040EZ	Income Tax Return for Single and Joint Filers With No Dependents	8829	Expenses for Business Use of Your Home
1040-ES	Estimated Tax for Individuals	8863	Education Credits (American Opportunity, and Lifetime Learning Credits)
1040X	Amended U.S. Individual Income Tax Return	8949	Sales and Other Dispositions of Capital Assets
2106	Employee Business Expenses	9465	Installment Agreement Request
2106-EZ	Unreimbursed Employee Business Expenses	9465(SP)	Solicitud para un Plan de Pagos a Plazos
2210	Underpayment of Estimated Tax by Individuals, Estates, and Trusts		