

**MINIMUM CREW STANDARDS FOR NATIONAL MOBILIZATION**

Minimum Standards	Type 1	Type 2 with IA Capability	Type 2
<b>Fireline Capability</b>	Initial attack/can be broken up into squads, fire line construction, complex firing operations(backfire)	Initial attack/can be broken up into squads, fireline construction, firing to include burnout	Initial attack, fireline construction, firing as directed
<b>Crew Size</b>	18-20		
<b>Leadership Qualifications</b>	Permanent Supervision Supt: TFLD, ICT4,FIRB Asst Supt: STCR, ICT4 3 Squad Bosses: ICT5 2 Senior Firefighters: FFT1	Crew Boss: CRWB 3 Squad Bosses: ICT5	Crew Boss: CRWB 3 Squad Bosses: FFT1
<b>Language Requirement</b>	All senior leadership including Squad Bosses and higher must be able to read and interpret the language of the crew as well as English.		
<b>Experience</b>	80% 1 season	60% 1 season	20% 1 season
<b>Full Time Organized Crew</b>	Yes (work and train as a unit 40 hrs per week)	No	No
<b>Communications</b>	5 programmable radios	4 programmable radios	
<b>Sawyers</b>	3 agency qualified	3 agency qualified	None
<b>Training</b>	As required by the Interagency Hotshot Crew Guide or agency policy prior to assignment	Basic firefighter training and/or annual firefighter safety refresher prior to assignment	Basic firefighter training and/or annual firefighter safety refresher prior to assignment
<b>Logistics</b>	Crew level agency purchasing authority	No purchasing authority	No purchasing authority
<b>Maximum Weight</b>	5100 lbs		
<b>Dispatch Availability</b>	Available nationally	Available nationally	Variable
<b>Production Factor</b>	1.0	.8	.8
<b>Transportation</b>	Own transportation	Transportation needed	Transportation needed
<b>Tools &amp; Equipment</b>	Fully equipped	Not equipped	Not equipped
<b>Personal Gear</b>	Arrives with: Crew First Aid kit, personal first aid kit, headlamp, 1 qt canteen, web gear, sleeping bag		
<b>PPE</b>	All standard designated fireline PPE		
<b>Certification</b>	Must be annually certified by the local host unit agency administrator or designee prior to being made available for assignment.	N/A	N/A