

## 12 - Wildland/Urban Firefighting

## Wildland/Urban Interface

The wildland/urban interface is more than a geographic area or zone where structures meet or intermingle with wildland fuels. It is a set of conditions where flammable structures exist within the reach of ignition sources, primarily firebrands, from burning wildland and structural fuels. Often, as severe wildland fires meet structural developments, vegetation ceases to burn but catastrophic fire continues, sustained by structures igniting and perpetuating these events even a mile or more from wildland fuels. The potential exists in areas of wildland/urban interface conditions for extremely dangerous and complex fire conditions which pose a tremendous threat to public and firefighter safety.

## Structural & Vehicle Firefighting

#### Policy

Fire protection agreements specify responsibilities of partners, including funding. For more information on BLM policy, refer to *BLM Manual 9200* and the *Federal Wildland Fire Management Final Report*, December 1995.

For additional fire service and homeowner information regarding wildland/urban fire refer to FIREWISE.ORG on the web.

on safety hazards associated with suppression around developments and transportation systems.

### Clarification

- 1) BLM resources will not be planned, nor dispatched as normal response for structure or vehicle fires, except in those cases where these fires pose significant threat to BLM-administered lands. In these situations, BLM resources should only be used in wildland protection. BLM employees may only take action on structure or vehicle fires when adequate local firefighting forces are not yet present. Actions will be limited to the exterior of the structure or vehicle unless there is immediate threat to human life. Employees must not knowingly be exposed to noxious gases or chemicals or other situations that require the use of self-contained breathing apparatus. BLM units will withdraw from structural fire suppression and protect adjoining wildland resources when local fire agency units arrive in sufficient force.
- 2) The number, type, and location of bureau firefighting resources will not be based on, nor justified by, structure or vehicle firefighting needs.

Release Date: 4/99

- 3) No bureau employee should respond to a structure or vehicle fire prior to receiving specialized training in hazard awareness and unique safety considerations associated with structure and vehicle protection. In most cases, a local fire department with responsibility for structure and vehicle fire protection will provide this training.
- 4) BLM employees, in interagency dispatch centers, should not provide dispatch service for cooperating agencies with structure fire, vehicle fire, or emergency medical responsibility unless (1) a current interagency agreement is in effect, (2) the bureau dispatcher has been trained the same as the cooperating agency dispatchers, and (3) the bureau employee has been given a delegation of authority for those activities outside the normal scope of the bureau. In these instances, BLM employees will be acting as agents of that agency and will only communicate information contained in that agency's dispatch plan or as directed by an official from that agency.

#### **Protection Agreements and Planning**

Managers must ensure that all wildland/urban interface areas are covered by fire protection agreements or renegotiate existing agreements to reflect federal policy and to ensure state and local responsibilities are apportioned appropriately. Incorporate wildland/urban interface considerations into all agreements, operating plans, land and fire management plans.

### Safety

#### Wildland/Urban Watch Outs

- Wooden construction and wood shake roofs
- Poor access and narrow one-way roads Observe bridge limits when using heavy equipment
- Inadequate water supply
- Natural fuels 30 feet or closer to structure
- Extreme fire behavior
- Strong winds
- Evacuation of public (panic) and pets (horses, dogs)
- Structures located in chimneys, box canyons, narrow canyons, or on slopes of

30 percent or more in flashy or heavy brush fuel types

- Power lines and poles Watch for both overhead and fallen lines
- Propane and above ground fuel tanks with nearby vegetation or wooden improvements
- Local citizens attempting suppression actions
- Airtanker retardant drops and helicopter bucket operations

## Sizeup

Release Date: 4/99

210

#### CHAPTER 12

The primary considerations are firefighter safety, public safety, potential fire behavior, access, egress, nature of the threat, hazardous materials, and water supplies. The following checklists are designed for incidents that BLM normally does not respond to unless specifically trained. Distribute these checklists only to those who are trained and qualified to perform these tasks and assessments.

#### Structure Assessment

#### Address/Property Name

- Numerical street address, ranch name, etc.
- Residents on site?

#### **Road Access**

- Paved, gravel, dirt
- Number of lanes, vegetation clearance, defensible space, safety zones
- Undercarriage problems, 4x4 only?
- Turnouts, turnarounds
- Bridges adequate support structure?
- Creek Crossings approach angle, crossing surface
- Terrain road slope, position on slope, near chimneys, saddles, canyon bottom
- Grade greater or less than 15 percent

#### Structure/Building

- Single residence, multiple occupancy, barn, fuel storage, unknown storage.
- Exterior walls stucco or other non-combustible, wood frame, wood shake, or other combustible. Large unprotected windows facing heat source?
- Roof asphalt or fiberglass shingle, tile, rock, metal or other low combustible material; wood shake or other easily combustible material?
- Eaves covered and little overhang; exposed with large overhang exposure?
- Other exposed wooden structural elements, overhangs slope, attached wood deck, firewood piles, wooden patio furniture, wooden fences attached to house.

Release Date: 4/99

#### Clearances/Exposures/Defensible Space

- 100' vegetation clearance, max. 18" high, 15 percent or less slope, good ground clearance, vegetation is low combustible type, or is clearance less than described?
- Predominant fuel bed in area surrounding structure is light, medium, heavy, continuous, non-continuous?
- Flammable trees adjacent to structure?
- Other combustibles adjacent to structure?
- High voltage lines or transformers near apparatus placement areas?
- Structure located on narrow ridge, knoll, narrow canyon, chimney, mid-slope; defensible space less than 200 feet?
- Propane and above ground fuel tanks with nearby vegetation

#### Hazardous Materials

Pesticides, herbicides, DOT/NFPA/UN symbols, propane, oil, fuels, paints

#### Available Water

Hydrant or standpipe, water storage tank with valve, swimming pool with access

#### **Evacuation Needs**

Describe

#### Estimated Resources for Protection

Number and type engines, number water tenders, number crews, number dozers?

#### **Structure Triage**

There are three categories of structures: those that are threatened; those that are not threatened; and those that are lost or too dangerous to protect.

Factors that may make an attempt to save a structure hopeless or too dangerous are:

- Fire is making a sustained run and there is little or no clearance.
- 12
- Fire behavior is extreme; spot fires are numerous and out pacing control.
- Water supply will not last as long as the threat.
- Fire's intensity dictates you leave the area NOW.
- Roof is more than one-quarter involved.
- There is fire inside the structure or windows are broken.

212

Release Date: 4/99

 You cannot safely remain at the structure and your escape route could become unusable.

## **Initial Action**

The following checklists are designed to guide responses to situations. The checklists provide factors to consider for a safe and effective response.

#### **Structure Protection Checklist**

- Always stay mobile.
- Back equipment in for quick escape.
- Coil a short 1½" charged line with fog nozzle on your engine for safety and quick knock down.
- Don't make long hose lays.
- Know bridge limits, alternate access, and turnarounds for you and support vehicles.
- Keep at least 100 gallons of water reserve in your tank.
- Check roads before the fire hits.
- Check each home for defense. Use Structure Assessment Checklist.
- Determine if residents are home. Leave home lights on inside and out, day and night.
- Close garage door.
- Place owner's ladder at a corner of home on least fire threat side.
- Coil and charge garden hoses.
- Check and mark HazMat, i.e., LPG, pesticides, paint storage.
- Don't enter a burning structure unless you are trained, equipped, and authorized.
- If a home becomes well involved, leave it. Move on to one you can save.
- Always wear your safety gear, all of it.
- Firefighter safety and survival is the number one priority.

A course, Introduction to Wildland Firefighting for the Structural Company Officer, has been developed by the National Fire Academy and will be available July 1998. The course covers two primary areas. The first is what a company officer can expect when assigned to a wildland fire incident, and the second is the basics of wildland firefighting. The course is designed to have a wildland fire instructor participate. It is highly recommended that bureau fire managers participate in the local instruction of this course whenever possible.

Release Date: 4/99

## **Hazardous Materials**

All individuals responding to wildland fire incidents should be familiar with the current publication of the Department of Transportation's *Emergency Response Guidebook* DOT P 5800.7 1996, its purpose and use.

It is required that all employees receive hazardous materials awareness training (BLM H-1112-2). This training is available either through agency HazMat coordinators or local fire departments.

#### IC HazMat Checklist

Approach cautiously	Resist the urge to rush in; you cannot help others until you know what you are facing. Stay upwind and uphill.
Identify the Hazards Pla	acards, container labels, shipping papers and or knowledgeable persons on the scene are valuable information sources. Evaluate all of them and then consult the recommended guide page before you place yourself or others at risk.
Secure the Scene W	ithout entering the immediate hazard area, do what you can to isolate the area and assure the safety of individuals and the environment. Move and keep individuals away from the scene and the perimeter. Allow room enough to move and remove your own equipment.
Obtain Help	Advise dispatch to notify responsible agencies and call for assistance from trained experts through CHEMTREC and the National Response Center.
Decide on Site Entry	Any efforts you make to rescue persons, protect property or the environment must be weighed against the possibility that you could become part of the problem.

**Above All** - Do not walk into or touch spilled material. Avoid inhalation of fumes, smoke and vapors, even if no hazardous materials are known to be involved. Do not assume that gasses or vapors are harmless because of lack of smell–odorless gasses or vapors may be harmful.

**1-800-424-9300** CHEMTREC (Chemical Transportation Emergency Center) – for immediate information about a chemical or to seek assistance from a manufacturer

214

Release Date: 4/99

#### 1-800-424-8802 National Response Center – To report spills of oil and hazardous materials

#### HazMat Checklist

#### Assume role of IC until relieved by responsible agency

- Assign safety officer
- . Develop action plan for area security and evacuation. Advise dispatcher.
- Advise all units of changes in situation.
- Document all actions taken and contacts.
- Document employee exposure.

#### **Rules for Isolation Distances**

- Minor event (1 drum, 1 bag, etc.) = 150 feet •
- Major event (1 drum or more, etc.) = 500 feet
- Residential and light commercial = 300 feet •
- Open areas = 1000 feet •
- BLEVE (Boiling Liquid Expanding Vapor Explosion) potential = 2500 feet (one-half mile)
- Stage arriving units 2500 feet upwind.
- Position vehicles headed out.

#### **Think Safety**

- Safe approach, upwind/upgrade/upstream
- Identify, isolate and deny entry
- Notify agency dispatcher
- Request needed assistance via safe route

#### Scene Management

- Goal is to protect life, environment and property
- Attempt to identify substance using DOT Emergency Response Guide. occupancy/location, placards/labels, container shapes/colors, Material Safety Data Sheets (MSDS), shipping papers. Use binoculars!
- Assess situation exact location, identity and quantity of material involved, exposures and hazards

# 12 HazMat Response Acronyms Reference: NFES 2148

- S afety Responder safety is #1 priority.
- I solation & Deny Entry Isolate material and don't let anyone enter hazard area.
- N otifications Local, state, and federal responders and regulators.

Release Date: 4/99

- C ommand/Management Implement command. IC must be identified/assigned.
- I dentification & Assessment ID material and hazards associated with it.
- A ction Planning State law requires written action plan. ICS 201 will work.
- P rotective Equipment Determine appropriate level for responders.
- **C** ontainment & Control Mitigate hazardous material involved only if you are trained, equipped, and authorized.
- P rotective Actions Secure area, evacuate or shelter in place.
- D econtamination & Cleanup Up to responsible party or local health department.
- D isposal Very expensive. Special permits required for hauling.
- D ocumentation Document everything!

12

216

Release Date: 4/99