Chapter 18 Prescribed Fire

2

Introduction

The Interagency Prescribed Fire Planning and Implementation Procedures
Reference Guide (IA RX Fire Guide) was signed by the National Fire and
Aviation Executive Board (NFAEB) on September 1, 2006. The IA RX Fire
guide provides consistent interagency policy, establishes common terms and
definitions, and identifies planning and implementation processes for prescribed
fire. These procedures meet all policy requirements described in the 2003
Interagency Strategy for the Implementation of Federal Wildland Fire
Management Policy. The 2006 guide provides unified direction and guidance
for prescribed fire planning and implementation for the Department of the
Interior's Bureau of Indian Affairs (BIA), Bureau of Land Management (BLM),
the National Park Service (NPS), the United States Fish and Wildlife Service
(USFWS) and the United States Department of Agriculture Forest Service
(USDA FS).

18

The guide can be obtained electronically at the National Fire and Aviation Executive Boards (NFAEB) website: http://www.nifc.gov/fire_policy/ and at the

National Interagency Fuels Management Website:

http://www.nifc.gov/fuels/index.html. Access the 'Direction and Guidance'

23 link.

24

The IA RX Fire Guide describes what is minimally acceptable for prescribed fire planning and implementation. All personnel involved in the prescribed fire planning and implementation process must ensure that specific agency additional standards and or supplemental guidance are followed.

29

Purpose

The purpose of this guide is to provide consistent interagency policy, establish common terms and definitions, and identify planning and implementation processes for prescribed fire.

33 34

The guide describes what is minimally acceptable for prescribed fire planning and implementation. Agencies may choose to provide more restrictive standards and policy direction, but must adhere to these minimums.

38

Scope

This guide provides policy and direction to implement existing federal policy and has been developed with tribal, state, county, and local cooperators in mind.
While some of these guidelines will not fit all non-federal cooperators, the intent is to include everyone by establishing a planning and implementation guide that might result in that outcome.

45 46

Release Date: January 2007

18-1

Prescribed Fire Program Goals

Interagency Prescribed Fire Program goals are to:

- Provide for firefighter and public safety as the first priority.
- Ensure that risk management is incorporated into all prescribed fire planning and implementation.
- Use prescribed fire in a safe, carefully planned, and cost-efficient manner.
- Reduce wildfire risk to communities, municipal watersheds and other values and to benefit, protect, maintain, sustain, and enhance natural and cultural resources.
- Utilize prescribed fire to restore natural ecological processes and functions, and to achieve land management objectives.

11 12

14

10

Authorities

All use of prescribed fire will be supported by a Land/Resource Management Plan (L/RMP) and/or Fire Management Plan (FMP). Prescribed fire projects can only be implemented through an approved Prescribed Fire Plan. Specific authorities exist for each agency to utilize prescribed fire (See Appendix A of the *Interagency Prescribed Fire Planning and Implementation Procedures Reference Guide*). All project decisions to use prescribed fire are subject to the agency's analysis, documentation, and disclosure requirements for complying with the National Environmental Policy Act (NEPA).

21 22

24

During prescribed fire planning and operations, all federal agencies will accept each other's standards for qualifications. The minimum qualifications standard is the National Wildland Fire Coordinating Group (NWCG) *Wildland and Prescribed Fire Qualifications System Guide*, 2000 (PMS 310-1). State, local cooperators and contractors working on federal agency prescribed fires must meet the NWCG PMS 310-1 standards unless local agreements specify otherwise.

29 30 31

> 32 33

The main reference glossary for this guide is the NWCG glossary, which is updated periodically: http://www.nwcg.gov/.

3

This guide is not intended to address interagency business rules. Reference individual agency's business rules for direction.

36 37

39

40

41

42

43

Prescribed Fire Planning Process

Common planning documents to ensure quality prescribed fire plans include:

- Land/Resource Management Plan (L/RMP)
- Overall direction is provided to the Wildland Fire Management Program by L/RMP. These plans serve as the document to initiate, analyze, and provide the basis for using prescribed fire to meet resource management objectives.

44 45

> 6 18-2

Fire Management Plan (FMP)

- All burnable acres will be covered by a Fire Management Plan (FMP). The FMP
- is the cornerstone plan for managing a Wildland Fire Management Program and
- should flow directly from the L/RMP. FMPs may be developed for a Fire
- Planning Unit (FPU) that crosses jurisdictional boundaries. Where the Wildland
- Fire Management Program crosses jurisdictional boundaries, or where program
- coordination is essential, the FMP will require interagency coordination. Most
- FMPs are anticipated to fall into this category.

National Environmental Policy Act (NEPA) 10

Resource and prescribed fire objectives for specific prescribed fire projects are 11

derived from the NEPA analysis. The entire prescribed fire project area must be 12

analyzed under NEPA. NEPA documents that identify and analyze the effects

of using or not using prescribed fire treatment projects may include

Environmental Impact Statements (EIS), Environmental Assessments (EA), and

Categorical Exclusion (CE). 16

Other authorities that may be utilized to guide analysis and determination of 18

NEPA compliance are the Healthy Forest Restoration Act (HFRA), the Healthy 19

Forest Initiative (HFI), and the Tribal Forest Protection Act (TFPA).

21

Prescribed fire planning and related NEPA analysis should always occur at the 22 23 largest possible spatial and temporal scales.

24

35 36

37

Implementation Organization and Qualifications

During prescribed fire planning and operations, all federal agencies will accept 26 each other's standards for qualifications. The minimum qualifications standard is the National Wildland Fire Coordinating Group (NWCG) Wildland and Prescribed Fire Qualifications System Guide, 2000 (PMS 310-1). State, local 29 cooperators, and contractors working on federal agency prescribed fires must meet the NWCG PMS 310-1 standards unless local agreements specify otherwise. No less than the organization described in the approved Prescribed

Fire Plan may be used for implementation. The complexity of each prescribed fire or phase of fire(s) determines the organization(s) needed to safely achieve

the objectives specified in the Prescribed Fire Plan.

Minimum Supervisory Qualifications Determined By Prescribed Fire **Complexity:**

	Complexity		
Position	High	Moderate-low	Low
RXM1	Optional	Optional	Optional
RXM2	Not Allowed	Optional	Optional
RXB1	Required	Optional	Optional
RXB2	Not Allowed	Required	Optional
RXB3	Not Allowed	Not Allowed	Required
FIRB	Optional	Optional	Optional

Holding Specialist

2 Holding functions will be managed by personnel qualified at the appropriate ICS

- wildland fire operations position as required by complexity, assigned resources
- 4 and operational span of control. For some projects, there may be no holding
- requirements or the holding duties are assumed by the Burn Boss.

requirements or the noiding duties are assumed by th

High, Moderate, and Low complexity prescribed fires are determined through the required NWCG *Prescribed Fire Complexity Rating System Guide*.

9

Prescribed Fire Burn Boss Type 3 (RXB3)

Adoption of the RXB3 position is up to each agency. Non-federal RXB3s must meet the qualifications as listed in the table below unless local agreements specify otherwise.

14

An RXB3 will only be allowed to implement low complexity prescribed fires where the possibility of spread or spotting outside the project area is negligible to non-existent; multiple fuel models are not involved; and aerial operations are not involved.

19

Requirements for Prescribed Fire Burn Boss Type 3

Requirements for Trescribed Fire Duri Boss Type 3		
Training	Required: S-290 Intermediate	
	Wildland Fire Behavior	
	Suggested: S-234 Ignition Operations	
Prerequisite Experience	Incident Commander, Type 5	
	OR	
	Advanced Firefighter/Squad Boss	
	AND	
	Satisfactory position performance as a	
	Prescribed Fire Burn Boss Type 3	
Physical Fitness	Moderate	
Other Position Assignments that will	Prescribed Fire Burn Boss Type 2	
Maintain Currency	Prescribed Fire Burn Boss Type 1	
	Fire Use Manager	
	Prescribed Fire Manager Type 1	
	Prescribed Fire Manager Type 2	

21

Responsibilities

Prior to prescribed fire implementation, thorough planning and review processes

must be conducted. All prescribed fire actions must be developed from

resource/fire management objectives carried forward from FMP's and L/RMP's.

A specific implementation plan for each prescribed fire must be completed,

reviewed, and approved before ignition can begin.

28

The agency administrator has final approval authority for all Prescribed Fire

Plans, unless special circumstances warrant higher review and concurrence

31 (such as may occur during higher Preparedness Levels or for extremely large,

```
complex projects). Although the agency administrator has final approval
authority for the Prescribed Fire Plan and the agency administrator Pre-Ignition
Approval Checklist, the Prescribed Fire Burn Boss has the responsibility to
make the on-site tactical "GO/NO-GO" decision. The Prescribed Fire Burn
Boss ensures that all prescription, staffing, equipment, and other plan
specifications are met before, during, and after the prescribed fire.
```

Every Prescribed Fire Plan must receive a technical review. The Technical Reviewer and Prescribed Fire Plan Preparer must be qualified or have been previously qualified as a Prescribed Fire Burn Boss at an experience level equal to or higher than the complexity being reviewed. Either the Prescribed Fire Plan 12

Preparer or Technical Reviewer must be currently qualified.

13

Only a RXB1 can review plans at high complexity. An RXB2 can review plans of moderate to low complexity. An RXB3 is not allowed to function as a 15 Prescribed Fire Plan Preparer (see Chapter 3, section C of the Interagency Prescribed Fire Planning and Implementation Procedures Reference Guide) or Technical Reviewer. 18

19

Agency or individual unit policy may dictate additional reviews. Interagency Prescribed Fire Plans require approval from all appropriate agency administrators and a technical review. Listed below are the prescribed fire and 23 implementation position roles and responsibilities.

24

Agency Administrator

For the purposes of this document, the agency administrator is defined as the 26 Line Officer (or designee) of the agency or jurisdiction that has responsibility for the prescribed fire. These usually include the: NPS Park Superintendent, BIA Agency Superintendent, USFS Forest Supervisor, BLM District/Field 29 Office Manager, FWS Project Leader, State Forest Officer, and/or Fire Chief.

31 32

34

35

36

The agency administrator is responsible to:

- Approve Prescribed Fire Plans. When approving a plan, understand the risks associated with it. Ensure that the plan has been reviewed and recommended for approval by the Technical Reviewer who was not the primary preparer of the plan.
- Ensure that only trained and qualified personnel participate in the 37 implementation portion of the prescribed fire. 38
- Ensure that projects are monitored, evaluated, and documented in the 39 project file.
- Sign, date, and provide an expiration date for the approval to burn on the 41 agency administrator Pre-Ignition Approval Checklist (Reference Burn Plan Template, Appendix B of the Interagency Prescribed Fire Planning 43 and Implementation Procedures Reference Guide). 44
- Understand and approve the Complexity Analysis (PMS 424 January 45 2004).

 Ensure that all prescribed fires are conducted in accordance with the approved implementation plan and established standards and guidelines.

- Ensure that periodic reviews and inspections of the Prescribed Fire Program are completed.
- Determine if and when the agency administrator is to be notified that contingency actions are being taken.
- Report all wildfires resulting from prescribed fires through the chain of command.
- Declare an escaped prescribed fire a wildfire (if responsibility is assigned in the plan).
- Ensure that escaped prescribed fires are reviewed according to established guidelines.

Technical Reviewer

13

14

33

41

42

The Technical Reviewer is responsible for reviewing each Prescribed Fire Plan element for content as well as evaluating the risk and Complexity Analysis to ensure that the stated goals and objectives can be safely and successfully 17 achieved when properly implemented. The Technical Reviewer shall be qualified or previously qualified as a Burn Boss at or above the level of project 19 complexity. At a minimum, NWCG qualifications will be accepted. The Technical Reviewer should have local knowledge of the area, experience burning in similar fuel types, and/or conduct an on-site review. The Technical Reviewer must be someone other than the primary preparer of the plan. An off-23 unit technical review is encouraged to provide an additional independent 24 perspective. It is acceptable for other specialists to review certain portions of 25 the plan however; a primary Technical Reviewer must be designated as technical review signatory. For example, a fire behavior analyst may review the fire behavior calculations; the aviation manager may review the air operations plan; and/or a resource specialist may review impacts to their resource of interests. It is recommended that at least once every year, each unit should send a moderate or high complexity Prescribed Fire Plan off-unit for technical 31 review. The Technical Reviewer is responsible to:

- Ensure that Prescribed Fire Plans meet agency policy and direction.
- Ensure that the Complexity Analysis accurately represents the project, so the agency administrator understands the identified risks and the mitigating measures enacted. This may require on-site review in Wildland Urban Interface (WUI) or high complexity situations by the Technical Reviewer.
- Check the prescription parameters against the fuel types to ensure that the project as planned has a reasonable chance of meeting the resource management objectives.
 - Ensure that the fire behavior calculations and/or prescription parameters are appropriate and within the acceptable range.
- Ensure that the ignition, holding and contingency plans are consistent with the predicted fire behavior.

Prescribed Fire Chapter 18

• Complete and sign the Technical Review Checklist (See Burn Plan Template, Appendix B of the *Interagency Prescribed Fire Planning and Implementation Procedures Reference Guide*) and the Prescribed Fire Plan signature page.

5

Prescribed Fire Plan Preparer

- For the purpose of this document, the Prescribed Fire Plan Preparer is defined as the individual responsible for the preparation of the Prescribed Fire Plan.
- 9 Several people may be involved in the preparation of the Prescribed Fire Plan,
- but the Prescribed Fire Plan Preparer is responsible for the final plan content.
- The primary preparer of the Prescribed Fire Plan will sign the signature page.
 The preparer is responsible to:
- Prepare the Prescribed Fire Plan in accordance with this guide's policy and
- direction.

 Coordinate with the resource management and/or technical specialists to
- ensure that the plan meets management and operational objectives.

 Interact with the Technical Reviewer to ensure that all plan elements are
- adequately addressed.
 Complete and sign the Complexity Analysis.

20 21

26

27

Prescribed Fire Burn Boss (RXB1/RXB2/RXB3)

- The Prescribed Fire Burn Boss is responsible to the agency administrator, Prescribed Fire Manager, or FMO/local fire management organization for implementing the Prescribed Fire Plan. The Prescribed Fire Burn Boss is responsible to:
 - Review the Prescribed Fire Plan prior to implementation and ensure all required elements and objectives are addressed.
- Inspect the burn unit to validate Prescribed Fire Plan elements including areas of special concern as well ensuring that holding/contingency plans adequately address expected fire behavior outside the unit(s).
- Obtain current weather and smoke management forecasts, updates, and special advisories from a meteorologist.
- Maintain communication with the agency administrator, Prescribed Fire Manager, or FMO/local fire management organization.
- Ensure that the agency administrator Pre-Ignition Approval Checklist is valid (See Burn Plan Template, Appendix B of the *Interagency Prescribed Fire Planning and Implementation Procedures Reference Guide*)
- Take to the field those portions of the Prescribed Fire Plan necessary for completing the briefing and safe project implementation.
- Complete and sign the Prescribed Fire GO/NO-GO Checklist (See Burn
 Plan Template, Appendix B of the *Interagency Prescribed Fire Planning* and *Implementation Procedures Reference Guide*).
- Ensure availability of any contingency resources and management of those resources if deployed.

Ensure that all operations are conducted in a safe manner and in accordance with the approved plan and established standards and guidelines.

- Verify qualifications of all assigned personnel. Conduct the personnel /safety briefing to ensure a safe operation.
- Conduct the test fire and document the results.
- Supervise assigned personnel and direct the ignition, holding and monitoring operations. The Prescribed Fire Burn Boss will be responsible for implementation including mop-up and patrol unless otherwise assigned to other qualified personnel. 10
- Declare the prescribed fire out unless the responsibility for it is formally 11 passed to another Prescribed Fire Burn Boss, Prescribed Fire Manager or 12 the local fire management organization.
- Determine when the prescribed fire is not within prescription parameters 14 (both short and long term) or is not meeting objectives. 15
- Declare an escaped prescribed fire a wildfire (if responsibility is assigned 16 in the plan). 17
- Manage the incident or oversee the transition to another Incident 18 Commander if an escape occurs. 19
- Ensure that reports are completed. • 20
- Coordinate with adjacent landowners, cooperators and permittees as 21 designated in the Prescribed Fire Plan. 22

23

24

Fire Management Officer (FMO)/ Fire Program Manager

The Fire Management Officer (FMO)/Fire Program Manager is responsible to the agency administrator for planning, implementing and monitoring of the Prescribed Fire Program in accordance with policy and direction. The 27 FMO/Fire Program Manager is responsible to: 28

- Ensure compliance with national, regional, tribal and local fire policy and 29 direction, as well as applicable state and local laws. 30
- Ensure that Preparedness Level Restrictions are adhered to. At National 31 Preparedness Levels Four and Five, prescribed fire implementation is 32 restricted. See the National Interagency Mobilization Guide for details. 33
- Ensure that both the Prescribed Fire Plan Preparer and the Technical 34 Reviewer are qualified or qualified less currency at the level of complexity or higher. 36
- Ensure that trained and qualified personnel are available to participate in 37 the Prescribed Fire Program. 38
- Assign the Prescribed Fire Burn Boss.
- Ensure a Prescribed Fire Plan with written approval exists for each 40 prescribed fire project. 41
- Review the Prescribed Fire Plan to assess the impact of the project on the 42 unit's workload; include the project in the unit's Annual Work Plan; assess 43 the unit's ability to implement the project; and assess the need for 44 additional implementation resources. 45

 Ensure that all prescribed fires are conducted in accordance with the approved Prescribed Fire Plan and established standards and guidelines.

- Declare an escaped prescribed fire a wildfire (if responsibility is assigned in the plan).
- Act as liaison/coordinator to the agency administrator, Prescribed Fire Manager and/or Prescribed Fire Burn Boss, local dispatch office, other units, other agencies, air quality authorities, news media, transportation agencies, and safety officials.
- Ensure that projects are reported through the local office and comply with national reporting guidelines.
- Ensure that fuels management projects and interagency support actions are reported through the proper reporting systems.
- Ensure that periodic reviews and inspections of the Prescribed Fire Program are completed.
- Update agency administrator on the progress of the prescribed fire (as necessary).
- Ensure that projects are monitored, evaluated and documented as a part of the project file.

20 Prescribed Fire Manager (RXM1/RXM2)

The Prescribed Fire Manager is responsible for implementing and coordinating assigned prescribed fire activities. A Prescribed Fire Manager may be assigned during periods when multiple simultaneous prescribed fires are being conducted; when multiple prescribed fires will be conducted within a short time frame; or where there is complex interagency involvement. The Prescribed Fire Manager is responsible to:

- Review Prescribed Fire Plans prior to implementation.
- Monitor all prescribed fire operations.
- Ensure that all operations are conducted in a safe manner and in accordance with the approved plan(s) and established standards and guidelines.
- Act as coordinator/liaison between the burn organization(s) and other offices, agencies, air quality authorities, news media, transportation agencies, safety officials, and interested public.
- Declare an escaped prescribed fire a wildfire (if responsibility is assigned in the plan).
- Obtain and interpret long-term weather information.
- Brief the Burn Bosses and direct operational assignments according to policies, priorities, and standards.
- Set priorities for allocation of resources.
- Ensure the completion of all required documentation including the evaluation and documentation of accomplishments, fire behavior and fire effects, operation procedures, and cost summaries.

44 45

19

Release Date: January 2007 18-9

Firing Boss (FIRB)

The Firing Boss reports to the Prescribed Fire Burn Boss and is responsible for supervising and directing ground and/or aerial ignition operations according to established standards in the Prescribed Fire Plan. The Firing Boss is responsible to:

- Review the Prescribed Fire Plan and the burn unit prior to implementation.
- Brief personnel on project objectives and ignition operations.
- Complete the test fire according to the ignition plan at the direction of the Prescribed Fire Burn Boss.
- Conduct ignition operations in a safe manner according to the ignition plan.
- Identify the impacts of ignition on the control and desired fire effects.
- Coordinate ignition operations with the Holding Specialist.

14

Holding Specialist

The supervisory position in charge of the holding forces reports to the
Prescribed Fire Burn Boss. There is no specific NWCG approved prescribed
fire position for this function. This position is assigned by name and title using
PMS 310-1 mnemonics. Holding functions will be managed by personnel
qualified at the appropriate Incident Command System (ICS) wildland fire
operations standard and as required by the prescribed fire complexity, assigned
resources, and operational span of control. The Holding Specialist is
responsible to:

- Review the Prescribed Fire Plan and the burn unit prior to implementation.
 - Brief holding personnel on project objectives and holding operations.
- Conduct holding operations in a safe manner according to the holding plan.
- Coordinate holding operations with the Firing Boss.
 - Confine the fire to a predetermined area, mop up, and patrol.
- Maintain communication with Burn Boss on holding progress and/or problems.
- For some prescribed fires, there may be no holding requirements or the holding duties are assumed by the Prescribed Fire Burn Boss.

33

28

34 Fire Effects Monitor (FEMO)

The Fire Effects Monitor (FEMO) is responsible for collecting the onsite weather, fire behavior, and fire effects information needed to assess whether the fire is achieving established resource management objectives. The FEMO is responsible to:

- Review the monitoring plan prior to implementation.
- Monitor, obtain, and record weather data.
- Monitor and record fire behavior data throughout the burn operations.

Release Date: January 2007

- Recon the burn unit/area assigned.
- Plot the burn area and perimeter on a map.
- Monitor and record smoke management information.
- Monitor first order fire effects.

18-10

Prescribed Fire Chapter 18

- Provide monitoring summary of the fire.
- Provide fire behavior and weather information to burn personnel as appropriate.

3

Helitorch Manager (HTMG)

6 The Helitorch Manager is responsible to manage the helitorch operation,

supervise the mixing operation, and provide technical assistance to the

Prescribed Fire Burn Boss/Ignition Specialist. The HTMG may also serve as

Helicopter Manager and Helitorch Manager or Helicopter Parking Tender (but not both).

11

Plastic Sphere Dispenser Operator (PLDO)

The Plastic Sphere Dispenser Operator (PLDO) is responsible for the preparation, operation, maintenance, and care of the dispenser. The PLDO reports to the Ignition Specialist.

16

Helitorch Mixmaster (HTMM)

The Helitorch Mixmaster (HTMM) is responsible for supervising the mixing/filling operations. The HTMM may also serve as Helitorch Manager or Helicopter Manager.

21 22

30

31

32

Resource Specialist or Resource Advisor (READ)

The Resource Specialist/READ is responsible for ensuring the prescribed fire project is planned and implemented in a manner supporting the unit's resource management goals and objectives. The Resource Specialist/READ is responsible to the agency administrator. The Resource Specialist/READ is responsible to:

- Ensure resource management representation in the preparation of the Prescribed Fire Plan.
 - Ensure a review of Prescribed Fire Plans is conducted before each plan is submitted for approval.
 - Evaluate the prescribed fire project in terms of meeting objectives.
- Provide resource information and direction to the Prescribed Fire Burn Boss.
- Present information at briefings on resources, priorities, and issues of concern.
 - Coordinate with adjacent landowners, cooperators and permittees as designated in the Prescribed Fire plan or by the Burn Boss.

39 40

37

38

Amendments

There may be a need to make amendments to the Prescribed Fire Plan. These are changes to the Prescribed Fire Plan that require an agency administrator signature. When changes are necessary, plans must be amended to identify the affected sections; the reason for the change(s); and have the changes clearly

identified. For amendments, the same standards for Prescribed Fire Plan preparation, review, and approval apply.

Common reasons for amending the Prescribed Fire Plan may include:

- Changes to objectives.
- Changes to complexity.

10

11

12

13 14

18

19

20

21

22

33

34

35

36 37

38

44 45

- Changes to fire behavior prescription parameters.
- Changes to project area boundaries resulting in either an increase or decrease in area.
- Reduction in resource capabilities identified as required in the plan.
- Major changes to ignition methods including ground ignition to aerial
 ignition; aerial ignition to hand ignition; hand drip torch ignition to use of
 terra torch ignition (includes ATV mounted ignition devices); and/or hand
 ignition from roadways to hand ignition from boats or other watercraft.

To avoid having to amend the Prescribed Fire Plan, flexibility should be built into the plan that will allow for a range of adjustments during the prescribed fire. When building flexibility, the range of identified options must remain within the scope of the Complexity Analysis. Examples of flexibility that can be built into a prescribed fire plan:

- The Prescribed Fire Plan may state that on burn day and subsequent days
 of the prescribed fire, a mix of the number and kinds of hand crews and
 engines may be modified as long as stated production capabilities are not
 compromised.
- As the prescribed fire progresses from ignition to holding to mop up and patrol, specified capabilities and/or types of resources may be adjusted. If these flexibilities are built into the Prescribed Fire Plan, there must be a clear statement as to the work capability requirements of the resources at the various stages of the prescribed fire.
- Minor changes in burn unit boundaries to facilitate holding and/or ignition, as long as the area in question has been in the NEPA document, requires no change in holding or ignition resources and is within the project boundaries.
 - Additional resources may be assigned to the project without amending the burn plan if the addition of these resources does not change the complexity of the burn or require additional supervisory positions. These changes must be documented in the daily briefing.

Safety

The Federal Wildland Fire Policy states that firefighter and public safety is first priority. Prescribed Fire Plans and activities must reflect this commitment. Every person involved in a prescribed fire is responsible for identifying safety issues and concerns. It is the responsibility of each individual participating in prescribed fire activities to notify immediate supervisor of any possible misunderstanding of assigned tasks or safety concerns related to the assignment.

```
NWCG established Work/Rest Guidelines and span of control apply equally to
  wildland and prescribed fire operations. The management of crew, overhead,
  and support personnel rest to assure safe, productive fire operations is the
  responsibility of all supervisory fire management personnel (refer to NWCG
   Interagency Incident Business Management Handbook, PMS 902, NFES 3139).
  Exposure to smoke during prescribed fire operations can be a significant safety
   concern. Research has shown that exposure to smoke on prescribed fires,
   especially in holding and ignition positions, often exceeds that on wildfire. At a
  minimum, smoke exposure must be addressed in the Job Hazard Analysis (JHA)
   and smoke management element. Public safety impacts from smoke should be
   addressed in the Smoke Management and Air Quality Element as well as the
   Public, Personnel Safety, and Medical Element.
13
   Transportation and use of any product containing chemicals (drip torch fuel,
15
   aviation gas, sphere dispensers, fusees, fuel thickener, etc.) must be in
   compliance with the Occupational Safety and Health Administration's (OSHA)
   Hazard Communication Standard (29 CFR 1910.1200) and Department of
   Transportation Regulations (49 CFR Part 171), and agency specific guidance.
   Material Safety Data Sheets (MSDS) for hazardous materials used on projects
   should be consulted in developing the JHA.
21
22
23
   The SAFENET form and process is designed for reporting and correcting unsafe
   situations and is applicable to prescribed fire applications.
24
25
   The risk management process identified in the NWCG Incident Response Pocket
26
   Guide (IRPG, PMS 410-1) helps ensure that critical factors and risks associated
27
   with prescribed fire operations are considered during decision making. This
   process should be applied to all prescribed fire planning and operations.
29
30
   Consider using a Safety Officer on high complexity prescribed fires and others
   where the complexity analysis shows the need or indicates a higher than normal
32
  hazard.
33
   A qualified Safety Officer is defined as a currently qualified Safety Officer, at
35
   any Type level (Types 1, 2 or 3), as defined by the NWCG, Wildland and
   Prescribed Fire Qualification System Guide (PMS 310-1).
38
   Prescribed Fire Plan
   The Prescribed Fire Plan is the site-specific implementation document. It is a
   legal document that provides the agency administrator the information needed to
  approve the plan and the Prescribed Fire Burn Boss with all the information
  needed to implement the prescribed fire. Prescribed fire projects must be
```

implemented in compliance with the written plan.

45

Release Date: January 2007 18-13

```
Prescribed Fire Plans will vary in their degree of detail. The size and complexity of the prescribed fire project will determine the level of detail required. The Prescribed Fire Plan Template (Appendix B of the Interagency Prescribed Fire Planning and Implementation Procedures Reference Guide) must be utilized. Each element must be addressed and then assembled in the sequence identified in the template. Should an element not apply to a specific prescribed fire plan, not applicable (N/A) may be utilized. Programmatic plans for multiple units under like conditions may be appropriate. Additional
```

10

If an interagency mixed ownership Prescribed Fire Plan is being prepared, the
development of all appropriate elements within the plan will be conducted in an
interagency setting. Interagency agreements and Memorandums of
Understanding (MOU) and/or private land owner agreements are required to
implement prescribed fire on multiple ownerships.

16

Listed below are the planning explanations of each individual element required as part of a complete Prescribed Fire Plan and implementation policy related to the element.

20 21

Prescribed Fire Plan Elements

information may be added as appendices.

22 23

1. Signature Page

24 The following information must be included on the signature page:

- Administrative unit name.
- Prescribed Fire Unit (burn unit)/Project name.
- At a minimum, three dated signatures are required: a Prescribed Fire Plan Preparer, a Technical Reviewer, and an agency administrator. Additional signatures may be included as required by the individual unit.
- Final determined complexity rating(s).
- If the plan needs to be amended, the signed and dated amendments must be attached to the Prescribed Fire Plan (see Chapter 4 of the *Interagency Prescribed Fire Planning and Implementation Procedures Reference Guide*).

34 Guide

36

37

2. GO/NO-GO Checklists

Agency Administrator Pre-Ignition Approval Checklist

The Agency Administrator's Pre-Ignition Approval Checklist (Burn Plan 38 Template, Appendix B of the Interagency Prescribed Fire Planning and 39 Implementation Procedures Reference Guide) is required to be completed. 40 The Agency Administrator's Pre-Ignition Approval Checklist evaluates 41 whether compliance requirements, Prescribed Fire Plan's elements, and 42 internal and external notification(s) have been completed and expresses the 43 agency administrator's intent to implement the Prescribed Fire Plan. The 44 checklist establishes the expiration date for the implementation of the 45 Prescribed Fire Plan. If ignition of the prescribed fire is not initiated prior

Prescribed Fire Chapter 18

to expiration date determined by the agency administrator, a new approval is required. An 'acting' agency administrator may sign the Agency
Administrator Pre-Ignition Approval Checklist if authority to do so has been delegated. If the Prescribed Fire Plan is amended, a review and revalidation of the Agency Administrator Pre-Ignition Approval Checklist would be required and included in the Project File.

Prescribed Fire GO/NO-GO Checklist

Prior to all ignition operations, the assigned Prescribed Fire Burn Boss will complete and sign the Prescribed Fire GO/NO-GO Checklist (Burn Plan Template, Appendix B of the *Interagency Prescribed Fire Planning and Implementation Procedures Reference Guide*). This checklist is a minimum standard and agencies may elect to add questions and/or approval signatures. For each day of active ignition on a prescribed fire, a separate daily GO/NO-GO Checklist is required.

15

10

11

12

13

14

17

21

23

28

32

33

3. Complexity Analysis

Risk management is a foundation for all prescribed fire activities. Risks and uncertainties relating to prescribed fire activities must be understood, analyzed, communicated, and managed as they relate to the cost of either doing or not doing an activity. At a minimum, those risks from the Complexity Analysis that are rated high and can not be mitigated will be identified with a discussion of the risks associated in the Summary Complexity Rating Rationale. This discussion will also be included in the Complexity Analysis Summary page (Burn Plan Template, Appendix B of the *Interagency Prescribed Fire Planning and Implementation Procedures Reference Guide*).

The Prescribed Fire Complexity Rating must be completed utilizing the *Prescribed Fire Complexity Rating System Guide, NWCG, January, 2004* (or current version). The purpose of the complexity rating process is to provide:

- Assignment of a complexity rating of high, moderate, or low to the prescribed fire.
 - Management and implementation personnel a relative ranking as to the overall complexity of a specific prescribed fire project.
- A process that can be used to identify Prescribed Fire Plan elements or characteristics that may pose special problems or concerns.
- A process that identifies mitigation activities needed to reduce the risk/hazard to the implementation personnel and public as well as mitigating potential resource damage.
- A preliminary rating will be completed early in the Prescribed Fire Plan development stage. This will identify potential concerns that may be mitigated during the plan preparation process. Once the Prescribed Fire Plan is near completion, the final complexity rating is made. The final complexity rating will be used as a basis for determining prescribed fire organization, Prescribed Fire Burn Boss level, and mitigation measures.

45

Release Date: January 2007 18-15

The Summary Complexity Rating Rationale will clearly justify the summary rating for prescribed fire organization and Prescribed Fire Burn Boss level. It must also identify those risks from the Complexity Analysis that are rated high and can not be mitigated and will provide a discussion of the risks associated. The Complexity Analysis must be signed by the Prescribed Fire Plan Preparer and the agency administrator and attached as an appendix to the Prescribed Fire Plan. The Complexity Analysis Summary will be attached to the Prescribed Fire Plan following the GO/NO-GO Checklists.

9 10

Separate prescriptions and/or burn organizations for different stages of implementation may result in multiple Complexity Analyses and ratings. For example, a plan may have separate prescriptions for spring and fall burning which may require different organizations and constitute the need for additional complexity analyses.

15

12

13

If a prescribed fire complexity changes which results in different Prescribed Fire
Burn Boss qualifications, a separate complexity analysis is required. For
example, for certain prescribed fires conducted over time, progressive or
sequential actions may reduce complexity, organization, and Prescribed Fire
Burn Boss qualifications (e.g. a large scale, high complexity prescribed fire has
been black-lined, portions burned and operations suspended for a period of time
then resumed to continue or finish the prescribed fire). In this case, a separate
Complexity Analysis will be developed to reflect the reduced complexity rating
and will be included in the appendix of the Prescribed Fire Plan.

25 26

29

30

31

32

4. Description of the Prescribed Fire Area Physical Description

This section of the plan will describe the physical features of the prescribed fire area.

- Location Narrative description of the location of the prescribed fire project including a legal description, UTM and/or latitude/longitude (decimal degrees; NAD83 preferred), county, and state.
- Size Area, in acres, of the prescribed fire project with a breakdown by prescribed fire unit and/or ownership if applicable.
- Topography Identify the upper and lower range of elevation, slope(s) maximum/minimum and average, and aspect(s) of the prescribed fire project.
- Project Boundary The project boundary defines that area where fire will be ignited and may be allowed to burn (some agencies previously called this Maximum Management Area or Allowable Area). Describe the physical, natural and/or human made boundaries (including multiple units) of the prescribed fire project. This will be done through maps and may include narratives. The entire prescribed fire project area must be analyzed under NEPA.

45

Vegetation/Fuels Description

This is a description of current vegetation and fuels in the project area and should discuss history including past environmental effects or land management practices and how they have impacted the fuel characteristics. Identify any reference material used.

- Describe the structure and composition of the vegetation type(s) and fuel characteristics. This description may include natural or activity fuels, total fuel load (both live and dead) in tons/acre, dead fuel load by time-lag size classes, live fuel load (woody/herbaceous), fuel bed depth, and vertical and horizontal arrangement within the project boundary.
- Describe the percent of the unit composed of each vegetative type and the corresponding fuel model(s).
- Identify conditions (fuels, slope, and aspect) in and adjacent to boundaries that may be a potential threat for escaped fire.
- Identify any abiotic conditions like airshed, climate, soils, etc. as
 appropriate.

17 18

6

10

Description of Unique Features and Resources

List and discuss special features, hazards, regulations, issues, constraints, etc. Examples may include: fences to protect, power poles, historical/cultural sites, threatened and endangered species or habitat, etc.

22 23

24

29

31

32

33

Maps

Maps will be developed and included in the Prescribed Fire Plan. At a minimum, the plan will include a vicinity and project map. The number of maps, map size and scale, legend and level of detail should be appropriate for the complexity of the project. All maps will include the standard mapping elements: title, name of preparer(s), date, north arrow, scale, and legend.

- Vicinity Map Shows prominent features including roads, streams, water sources, towns, structures, and the proximity of the burn unit(s) to these features. Transportation route(s) will be identified. Map scale will be such that the burn units can be located on the ground and in sufficient detail to guide implementation.
- Project Map(s) The project map(s) identify features in sufficient detail to 34 guide and assist in operational implementation of the prescribed fire. 35 Topographic, vegetative, or aerial photo maps should be used as the base 36 map. ICS map display symbols, identified in the Fireline Handbook PMS 37 410-1 will be used as appropriate. Examples of features that should be 38 included on the project map(s) are: project boundary, individual unit 39 boundaries, ownership, fireline locations, natural barriers, fuel model 40 locations, proposed ignition patterns and sequence, critical holding points, 41 hazards, safety zones, escape routes, helispots, areas of special concern, 42 smoke management issues (predicted plume dispersion, sensitive receptors, 43 etc), escaped fire contingency actions (primary and secondary control lines, 44 trigger points, etc), water sources, location of treatment monitoring plots, 45 etc., if these are significant in communicating project implementation.

Release Date: January 2007 18-17

5. Goals and Objectives

A short summary description will be developed that identifies the purpose of the prescribed fire and the resource management goals from the supporting L/RMPs and/or NEPA documents. The summary will identify desired future conditions of the prescribed fire project. This should be consistent with the appropriate land management goals. Include a discussion of future Fire Regime Condition

7 Class (FRCC) post-treatment conditions if applicable.

Describe in clear, concise statements the specific measurable resource and fire objectives for this prescribed fire. Objectives will be measurable and quantifiable so prescription elements can be developed to meet those objectives and the success of the project can be determined following implementation.

12 13

6. Funding

Identify the funding source(s) and estimated cost(s) of the prescribed fire.
Itemize by phase if desired.

7. Prescription

Prescription is defined as the measurable criteria that define a range of conditions during which a prescribed fire may be ignited and held as a prescribed fire.

21 22 23

24

18

The plan prescription will describe a range of low to high limits for the environmental (weather, topography, fuels, etc.) and fire behavior (flame lengths, rate of spread, spotting distance, etc.) parameters required to meet Prescribed Fire Plan objectives while meeting smoke management and control objectives. Parameters are quantitative variables expressed as a range that result in acceptable fire behavior and smoke management.

29

The range of prescribed fire behavior characteristics (outputs such as: flame lengths, rates of spread, scorch heights, mortality, spotting, etc.) identified in the plan will help determine the acceptable combination of environmental parameters (inputs such as: weather, topography and fuels) under which the prescribed fire can be conducted. In many cases, burning under the extremes of all prescriptive parameters would not meet or possibly exceed the desired prescribed fire behavior characteristics and are therefore out of prescription. The Prescribed Fire Burn Boss must ensure that the prescriptive parameters and fire behavior characteristics as identified in the Prescribed Fire Plan are not exceeded. Empirical evidence (historical evidence or researched data) and judgment may be utilized to identify or calibrate prescriptions. Weaknesses in modeling can be overridden, but must be justified with empirical evidence and/or verified actual fire behavior.

43

Separate prescriptions may be needed for multiple fuel model conditions to address seasonal differences and/or types of ignition (black lining, aerial ignition, etc). Separate prescriptions may result in multiple complexity ratings

and burn organizations. For example, a separate prescription is needed for black-lining operations if conditions will be significantly different from the

primary prescription or if the holding resources differ from those identified for ignition and holding phases. Separate prescriptions may result in the need to identify multiple levels of management, organizational structures, implementation measures, and pre-burn considerations. Holding and contingency plans must be developed with the consideration of the predicted fire behavior outside the project boundary(s). Fire behavior characteristics for fuel models within the maximum spotting distance and/or adjacent to the project boundaries must be considered and modeled using worstcase fire behavior predictions. These predictions will be identified from fire 12 behavior model runs or empirical evidence of the hottest, driest, and windiest prescription limits identified in the Prescribed Fire Plan, along with the most extreme environmental conditions (slope, aspect) identified. 15 A short fire behavior narrative that summarizes the fire behavior identified in the

16 17

prescription and discusses how it will achieve the desired treatment objectives may be included.

20 21

When used, fire behavior calculations must be developed using an appropriate fire behavior modeling program. Include modeling and/or empirical evidence documentation as an appendix or in the fire behavior narrative.

23 24

8. Scheduling

Identify the general ignition time frame(s) (i.e. time of day, duration of ignition) 26 or season(s) and note any dates when the project may not be conducted. For prescribed fires with multiple ignitions or burn days, list projected duration.

29

At National Preparedness Levels Four and Five, prescribed fire implementation is restricted. See National Interagency Mobilization Guide for details.

32 33

9. Pre-burn Considerations

Describe on and off-site actions and considerations that need to be conducted prior to implementation. Examples include clearances; line to be built; preparation of critical holding points; snags to be felled or protected; equipment to be pre-positioned; special features to be protected; warning signs to be placed; weather recording; fuels condition sampling; monitoring needs; responsibility; and timeframes. 39

40

Describe any fuel sampling and weather data that may need to be obtained (See Element 14: Test Fire). This data should be taken at the project site. If this is not possible, use the closest representative site.

43

The plan will include a list of organizations (including media) and individuals that are to be notified prior to ignition, with information necessary to make the

18-19

```
contacts. Reasonable efforts will be made to notify adjacent land owners (or
their agents) and other potentially impacted publics. Attempts and/or actual
notifications will be documented with date and method and placed in the Project
```

Identify in the burn plan the method and frequency for obtaining weather and smoke management forecast(s).

Spot weather or local area forecasts are required prior to ignition, on all ignition days and any days the fire is actively spreading. A copy of the forecast will be included in the Project File. The Prescribed Fire Burn Boss or other person in charge of mop-up and patrol will also obtain and review the spot weather or area forecast to determine if mop up and patrol resources are adequate.

15

22

27

10. Briefing

All assigned personnel must be briefed at the beginning of each operational period to ensure personnel safety considerations (including the JHA) and prescribed fire objectives and operations are clearly defined and understood. Briefing checklists are required to be included in the Prescribed Fire Plan and will include the following elements:

- Burn Organization and Assignments 21
 - Burn Objectives and Prescription
- Description of the Prescribed Fire Area
- Expected Weather & Fire Behavior 24
- Communications 25
- **Ignition Plan**
- Holding Plan
- Contingency Plan and Assignments 28
- Wildfire Conversion 29
- Safety and Medical Plan 30

The briefing checklist should list briefing topics only, not re-state what is listed 31 in the Prescribed Fire Plan for that element.

33

The Prescribed Fire Burn Boss will ensure that any new personnel arriving to the prescribed fire receives a briefing prior to assignment. 35

An Incident Action Plan (IAP) is optional, it is recommended for large multiday or high complexity prescribed fires. 38

39

If aerial ignition devices will be used, include an Aerial Ignition Briefing.

41

11. Organization & Equipment

The complexity of each prescribed fire determines the organization capabilities

Release Date: January 2007

- needed to safely achieve the objectives specified in the Prescribed Fire Plan.
- Specify the minimum required implementation organization to meet the

18-20

capabilities (line production rates, etc.) by position, equipment, and the supplies needed for all phases of the prescribed fire until declared out. At a minimum, a Prescribed Fire Burn Boss will be assigned to every prescribed fire. Positions that may not be filled as collateral duty will be identified in the organization chart of the Prescribed Fire Plan.

chart of the Prescribed

Standard ICS fire management principles for span of control and length of
 assignments will be adhered to when developing burn implementation
 organization(s) and used in managing prescribed fires. On prescribed fires with
 large organizations, use the ICS organization and staffing commensurate with
 the level of complexity. Consider the use of a Prescribed Fire Manager in
 conducting multiple prescribed fires.

13

Before implementation (all phases) of the prescribed fire, documentation in the form of an organization chart must be completed. Any changes to the organization during implementation must be documented. Any changes that reflect modification of the capabilities, equipment or supplies will require an amendment. Different organizations may be identified for different phases of implementation (i.e. holding v. mop-up and patrol, different ignition operations, different prescriptions).

21

Multiple prescriptions for one Prescribed Fire Plan are permissible and in some cases required (Element 7). Multiple prescriptions may require identifying and developing multiple organizations.

25 26

The Prescribed Fire Burn Boss is responsible for implementation including mopup and patrol until the responsibility is formally passed to a Prescribed Fire Burn Boss, Prescribed Fire Manager or the local fire management organization.

29

12. Communication

Develop communications plan specific to the project's implementation to address safety and tactical resource management needs. Identify and assign command, tactical, and air operations frequencies as needed. Also include any required telephone numbers. Cover under an Incident Action Plan, if utilized.

35

13. Public & Personnel Safety, Medical

Describe provisions to be made for public and personnel safety. All personnel who are within the active burn area are required to wear personal protective equipment. Identify and analyze the safety hazards unique to the individual prescribed fire project and specify personnel safety and emergency procedures. Include safety hazards (including smoke exposure and impacts) and measures taken to reduce those hazards. Specify emergency medical procedures, evacuation methods, and emergency facilities to be used. A Job Hazard Analysis (JHA) is required for each prescribed fire project and will be attached to the Prescribed Fire Plan as an appendix.

46

Release Date: January 2007 18-21

14. Test Fire

Provisions for a test fire are required and results must be recorded. The test fire must be ignited in a representative location and in an area that can be easily controlled. The purpose of the test fire is to verify that the prescribed fire

behavior characteristics will meet management objectives and to verify

predicted smoke dispersion. In many applications, analysis of the initial

7 ignitions may provide adequate test fire results. On multiple-day projects,

8 evaluation of current active fire behavior, in lieu of a test fire, may provide a

o comparative basis for continuing and must be documented. If in doubt however,

initiate a separate test fire and evaluate results.

11

Prior to ignition of both the test fire and ignition operations, compare the
Prescribed Fire Plan prescription elements, both individually and collectively,
against local area or spot weather forecasts, other predicted conditions, and the
actual conditions onsite (See element 9: Pre-Burn Considerations) to ensure that
predicted fire behavior will take place and/or weather parameters will not
change to the point of the burn going out of prescription.

18

15. Ignition Plan

Describe planned ignition operations including firing methods, devices, techniques, sequences, patterns, and ignition staffing for single or multiple unit operations. Maps showing proposed firing patterns may be included. If aerial ignition (or other aerial operations) is planned, cover aviation operations, organization, and safety within the Prescribed Fire Plan, Aerial Ignition Plan, or in an agency specific Aviation Operating Plan (Refer to the *Interagency Helicopter Operations Guide*, {NFES #1885} and the *Interagency Aerial Ignition Guide* {NFES #1080} for more detailed information on this topic).

Multiple prescriptions and ignition operations (blackline, primary, aerial, etc.) may require identifying and developing multiple ignition organizations.

30 31

16. Holding Plan

Describe general procedures to be used for operations to maintain the fire within the project area and meet project objectives until the fire is declared out. This may include mop-up and/or patrol procedures. Describe critical holding points (if any) and mitigation actions. Critical holding points will be identified on the project map. Describe minimum capabilities needed for all phases of implementation (see Element 11: Organization and Equipment). If used, attach or reference modeling outputs or worksheets (i.e. Fireline Handbook production rates, BEHAVE, etc.) and/or documented empirical evidence to justify minimum holding resources required.

41

Different organizations may be identified for different phases of implementation (i.e. holding, mop-up and patrol, different ignition operations, different prescriptions). Multiple prescriptions may require identifying multiple complexity ratings and developing multiple holding organizations.

46

```
If onsite resources are insufficient to meet the prescribed fire plan objectives,
then the Burn Boss should implement the Contingency Plan or Wildfire
Conversion.
```

17. Contingency Plan

"...If the objectives are not being met the Contingency Plan, a required component of the Prescribed Fire Burn Plan, is implemented. If the Contingency Plan is successful at bringing the project back within the scope of the Prescribed Fire Burn Plan the project continues. If contingency objectives are not met the prescribed fire is converted to a wildfire and Extended Attack is undertaken." 11

12

Interagency Strategy for the Implementation of Federal Wildland Fire 13 Management Policy, June 20, 2003, page 12.

15

Contingency planning is intended for more than just a response to an escaped fire. The contingency plan is the portion of the Prescribed Fire Plan that considers possible but unlikely events and the contingency resources and actions needed to mitigate those events.

20

24

25

- Contingency planning is the determination of initial actions and additional 21 resources needed if the prescribed fire is not meeting, exceeds, or threatens to 23 exceed:
 - Project or unit boundary
 - Objectives
- Prescription parameters 26
- Minimum implementation organization 27
- Smoke impacts 28
- Other Prescribed Fire Plan elements 29

30

The contingency plan will establish trigger points or limits that indicate when 31 additional holding resources and actions are needed.

32

33 Contingency planning includes the additional resources required, and the 35 maximum acceptable response time for those resources. Resource needs should be based on fire behavior outputs tied to the worst case fire behavior scenario (as modeled in Element 7: Prescription). Separate contingency plans may be necessary and appropriate to address seasonal differences, types of ignitions or phases of the burn implementation as described in the prescriptions and ignition and holding plans developed for the burn.

41

Verify and document availability of identified contingency resources and response time on day of implementation. If contingency resources availability falls below plan levels, actions must be taken to secure operations until identified contingency resources are replaced.

The same contingency resource can be identified for multiple prescribed fire projects. When specific contingency resources are identified for more than one prescribed fire, the local fire management organization(s) must evaluate and document adequacy of all contingency resources within the area. This evaluation must consider:

- Local, current, and predicted fire danger
- Local and regional wildland fire activities.

8

11

Once a contingency resource is committed to a specific wildland fire action (wildfire, wildland fire use or prescribed fire), it can no longer be considered a contingency resource for another prescribed fire project and a suitable replacement contingency resource must be identified or the ignition halted.

13

The agency administrator will determine if and when they are to be notified that contingency actions are being taken.

16 17

If the contingency actions are successful at bringing the project back within the scope of the Prescribed Fire Plan, the project may continue. If contingency actions are not successful by the end of the next burning period, then the prescribed fire will be converted to a wildfire.

20 21 22

18. Wildfire Conversion

The Prescribed Fire Plan will specify who has the authority to declare a wildfire. A prescribed fire must be declared a wildfire by those identified in the plan when that person(s) determines that the contingency actions have failed or are likely to fail and cannot be mitigated by the end of the next burning period by on-site holding forces and any listed contingency resources. In addition, an escaped prescribed fire must be declared a wildfire when the fire has spread outside the project boundary, or is likely to do so, and cannot be contained by the end of the next burning period. A prescribed fire can be converted to a wildfire for reasons other than an escape.

32 33

37

39

Describe the actions to be taken when a prescribed fire is declared a wildfire (refer to Wildland Fire and Aviation Program Management and Operations Guide {BIA--Blue Book} and Interagency Standards for Fire and Aviation {Red Book}). Description will include:

- Wildfire declaration (by whom)
- IC assignment
 - Notifications: dispatch, agency administrator, adjacent land owners, etc.
- Extended attack actions and opportunities to aid in suppression efforts.
- After a wildfire declaration, an escaped prescribed fire cannot be returned to prescribed fire status. A WFSA will define appropriate future management actions.

44 45

18-24

19. Smoke Management & Air Quality

- 2 Describe how the project will comply with local community, county, state,
- tribal, and federal air quality regulations. Identify what permits, if any, need to
- be obtained. Identify smoke sensitive areas including population centers,
- recreation areas, hospitals, airports, transportation corridors, schools, non-
- 6 attainment areas, Class I air sheds, and restricted areas that may be impacted.
- 7 Include modeling outputs and mitigation strategies and techniques to reduce the
- 8 impacts of smoke production, if required by State Implementation Plans (SIPs)
- 9 and/or State or local regulations. Reference the Smoke Management Guide for
- Prescribed and Wildland Fire 2001 Edition for other smoke management
- planning suggestions and smoke management techniques for reducing or
- redistributing emissions.

13

Special considerations must be taken to address smoke when the project is in a non-attainment area for a National Ambient Air Quality Standards including insuring compliance with SIP/TIP provisions and addressing Conformity.

Projects which will potentially impact Class I areas should address any efforts to minimize smoke impacts on visibility. Comply with all local, state, tribal and federal pre-burn and post-burn data reporting requirements.

20 21

20. Monitoring

Prescribed fire monitoring is defined as the collection and analysis of repeated observations or measurements to evaluate changes in condition and progress toward meeting a management objective. Describe the monitoring that will be required to ensure that Prescribed Fire Plan objectives are met. For the prescribed fire, at a minimum specify the weather, fire behavior and fuels information (forecast and observed) and smoke dispersal monitoring required during all phases of the project and the procedures for acquiring it, including who and when.

30 31

21. Post-burn Activities

Describe the post-burn activities that must be completed. This may include post-burn report, safety mitigation measures, and rehabilitation needs including those as a result of pre-burn activities undertaken.

35

38

Appendices

Include all the required appendices.

- Maps
- Technical Review Checklist
 - Complexity Analysis
- Job Hazard Analysis
- Fire Behavior Modeling Documentation or Empirical Documentation

43 44

45

Release Date: January 2007

18-25

Project file

- All prescribed fire Project Files will contain the following information.
- Agencies and/or administrative units may require additional information.
- Prescribed Fire Plan
- Monitoring data including weather, fire behavior, fire effects and smoke dispersal observations
- Weather forecasts
- Notifications
- Documented prescribed fire organization(s)
- Any agreements related to implementation
- Multiple day GO/NO-GO checklist(s), if applicable
- Re-validation of the Agency Administrator Pre-Ignition Approval
 Checklist

14

- 15 Depending on the scope and complexity of the prescribed fire, optional
- information and/or further documentation that may be included in the Project

17 File include:

- After Action Review (see Chapter 8 of the *Interagency Prescribed Fire Planning and Implementation Procedures Reference Guide*)
- o Incident Action Plans, Unit Logs
- Press releases, etc
- Implementation costs
- Actual ignition patterns and sequences used
- Smoke management information
- Agency individual fire occurrence form
- Detailed Post Burn Report
- 27 NEPA documentation
- 28 Permits

29

30 After Action Review (AAR)

- Each operational shift on a prescribed fire should have an informal After Action Review (AAR). Certain events or a culmination of events that may affect future prescribed fire implementation and/or policy should be submitted via the Rollup documentation (Found at http://www.wildfirelessons.net). The questions to
- up documentation (Found at http://www.wildfirelessons.net). The questions to answer in conducting an AAR are:
- What did we set out to do (what was planned)?
- What actually happened?
- Why did it happen that way?
- What should be sustained? What can be improved?

40

41 Escaped Fire Reviews

- The agency administrator will be notified of an escaped fire. The agency
- administrator is required to make the proper notifications. All prescribed fires
- declared a wildfire will have an investigative review initiated by the agency
- 45 administrator. The level and scope of the review will be determined by policy
 18-26 Release Date: January 2007

and procedures in Wildland Fire and Aviation Program Management and

- Operations Guide (BIA--Blue Book) or Interagency Standards for Fire and
- Aviation (Red Book).

10

11

19

22

23

32

- The goal of the escaped prescribed fire review process is to guide future
- program actions by minimizing future resource damage and/or preventing future
- escapes from occurring by gathering knowledge and insight for incorporation
- into future resource management and prescribed fire planning. The objectives of the review are to:
- Determine if the Prescribed Fire Plan was adequate for the project and complied with policy and guidance related to prescribe fire planning and implementation.
- Determine if the prescription, actions, and procedures set forth in the 12 Prescribed Fire Plan were followed.
 - Describe and document factual information pertaining to the review.
- Determine if overall policy, guidance, and procedures relating to 15 prescribed fire operations are adequate. 16
- Determine the level of awareness and the understanding of the personnel 17 involved, in regard to procedures and guidance. 18

At a minimum, the escaped fire review report will include the following 20 elements: 21

- An analysis of seasonal severity, weather events, and on-site conditions leading up to the wildfire declaration.
- An analysis of the actions taken leading up to the wildfire declaration for 24 consistency with the Prescribed Fire Plan. 25
- An analysis of the Prescribed Fire Plan for consistency with policy. 26
- An analysis of the prescribed fire prescription and associated 27 environmental parameters. 28
- A review of the approving line officer's qualifications, experience, and 29 involvement. 30
- A review of the qualifications and experience of key personnel involved. 31
 - A summary of causal agents contributing to the wildfire declaration.
- Document the incident, including all actions prior to and after the escape. Set up
- a file that includes all pertinent information, i.e., the Prescribed Fire Plan; a
- chronology of events including the prescribed fire report; unit logs and
- individual statements; weather forecasts including any spot forecasts; weather
- information taken on site and Remote Automated Weather Station (RAWS) and 37
- National Fire Danger Rating System (NFDRS) data for the day of the escape
- from the nearest station(s); photos; and all other pertinent information. Since all
- prescribed fires are planned management actions, an escape may lead to a Tort 40
- Claim and liability issues. Special attention to documentation is critical. 41

42

- An independent review team is recommended for conducting escaped fire
- reviews. The number of individuals assigned to the team and their functional

expertise should be commensurate with the scope and focus of the review.

² Interagency participation is highly recommended for all prescribed fire reviews.