Avionics Requirements Matrix for Light Fixed Wing Aircraft*

January 18, 2012

January 18, 2012	Reconnaissance							Air Tactical								
	Resource				Fire (FS Only)		Тур	e 1	Тур	e 2						
Equipment	Recon I (DOI)	Recon II (DOI)	Any c	olumı	n is ac	cceptable (FS)		ny co accep			Eith colur accep	nn is	Eitl colur accep	nn is	Type 3	Type 4 (FS Only)
Accessory Power Source Connector				1				1								1
ELT ^A				1					1		1	L		l	1	1
720 Channel VHF AM Transceiver		1									720	chanr	iel radi	os as th cificatio	pical ervice contraction ne #2 COMM on will be pha acts expire.	. The 720
760 Channel VHF AM Transceiver					1			:	1		1 - On	ly thos	2 - Typical se Forest Service contracts still allowing a 720 channel #2 COMM			still allowing
P25 Digital VHF- FM Transceiver						1 - Typical 1 - See Note B (FHP)				1	2	3	1	2	1	
Analog VHF-FM Transceiver						1 - See Note B (FHP)										
AUX-FM Provisions					1				2		1,C		1,C			
VHF-FM Antenna	1		1	1			2	1								2
Space for Portable Radio Kit				1				1								1
Automated Flight Following				1				:	1		1	L	1	1	1	1
GPS (Panel Mount) GPS (Portable)	1		1			1			1		1	L	<u>:</u>	L	1	1
Static System											1	L		L	1	1
Transponder												L	- 1	L	1	1
TAS											1 - See D (T					
Audio Control System				1	1	1		1	1	1	2			2	1	1
#3 Audio Control System											1 - See E		1 - See E			
ICS System											1	L	- :	L	1	

This matrix shows the minimum required contracted avionics items on typical contracts. Contracts are often modified to meet local needs. The contract language an aircraft is contracted under is the final determining factor on applicability and requirements.

^{*} Helicopters performing Air Tactical missions shall meet these specifications.

Notes

А	I FIT	Many DOI Bureaus require C-126 (406 MHz) ELTs for Exclusive Use contracts. New DOI Exclusive Use contract require C-126 (406 MHz) ELTs on all fixed wing aircraft.		
В	IEHD Analog VHE-	Only Forest Service Forest Health Protection (FHP) non-fire reconnaissance aircraft may utilize specific analog VHF-FM radios for specific missions in lieu of P25 Digital VHF-FM Transceivers.		
С	ATGS #3 VHF- FM	Many BLM Exclusive Use contracts require a #3 VHF-FM in lieu of AUX-FM provisions.		
D	I IAS	TAS is required on all DOI Type 1 Air Tactical aircraft while the Forest Service does not. Therefore, DOI considers all Forest Service non-TAS equipped Type 1 aircraft to be a Type 2 aircraft.		
Е		Air Tactical Type 1 and 2 aircraft must have either a #3 Audio Control System or audio jacks with a radio PTT for the ATGS Instructors position.		

Avionics Requirements Matrix for Helicopters

January 5, 2012

	Fire Helicopter ^A									
Equipment	Hea	avy		lium	Light					
	Either column	is acceptable	Either column	is acceptable	Either column is acceptable					
Accessory Power Source Connector				tegory Medium ers only	1					
9 Pin Remote Cargo Hook Connector			:	1	<u>:</u>	l				
ELT ^B		1		1	<u>:</u>	1				
760 Channel	1 - Ty	/pical	1 - T _\	/pical	1 - Typical					
VHF-AM	2	2 - Any helicopter c	arded for Air Tactic	al must have a 2nd	VHF-AM transceiver					
Transceiver	2 - 1	All Forest Service Ex	xclusive Use helicop	ter contracts requi	re a 2nd VHF-AM ra	dio				
P25 Digital VHF-	1 - Typical 2 - Most Forest	1 - KMAX & Cobra	1 - Typical 2 - Most Forest	2 - Not common (1 required + 1	1 - Typical 2 - Most Forest	2 - Not common (1 required + 1				
FM Transceiver	Service Exclusive Use contracts require a 2nd VHF- FM radio	(1 required + 1 not contractually required)	Service Exclusive Use contracts require a 2nd VHF- FM radio	not contractually required)	Service Exclusive Use contracts require a 2nd VHF- FM radio	not contractually required)				
	1 - Typical	0 - Not required on KMAX or Cobra helicopters	1 - Typical	0 - When a 2nd	1 - Typical	0 - When a 2nd				
AUX-FM Provisions	1 - An AUX-FM is required on all Forest Service Exclusive Use contracts because a 2nd P25 Digital VHF-FM transceiver is also required	0 - When a 2nd P25 Digital VHF- FM Transceiver is provided and not contractually required	1 - An AUX-FM is required on all Forest Service Exclusive Use contracts because a 2nd P25 Digital VHF-FM transceiver is also required	P25 Digital VHF- FM Transceiver is provided and not contractually required.	1 - An AUX-FM is required on all Forest Service Exclusive Use contracts because a 2nd P25 Digital VHF-FM transceiver is also required	P25 Digital VHF- FM Transceiver is provided and not contractually required				
Automated Flight Following	1		1		<u>:</u>	l				
Public Address System	Heavy helicopters	rvice Exclusive Use	0 - Typical 1 - Some Forest Service Exclusive Use Medium helicopters require an external PA with siren							
GPS		1		1		1				
Static System		1		1		1				
Transponder		1		1		1				
TAS			0 - Typical 1 - Some Forest Service Exclusive Use contracts in Region 5 require TAS							

	Fire Helicopter ^A								
Equipment	Heavy	Medium	Light						
	Either column is acceptable	Either column is acceptable	Either column is acceptable						
	0 - Typical								
CVR	1 - A CVR is required on Heavy standard category helicopters used to transport personnel								
#1 & #2 Audio	2 - Typical	2	2						
Control Systems	1 - KMAX & Cobra	2							
		0 - Typical	0 - Typical						
#3 Audio Control System		1 - Required in Medium Rappel helicopters	Light Rappel helicopters may utilize the #2 system for the spotter if it can be accomplished safely. AMD Short Haul Light helicopters require the use of the #2 Audio Control System.						
ICS System	1	1	1						

This matrix shows the minimum required contracted avionics items on typical contracts. Contracts are often modified to meet host base needs. The contract language a helicopter is contracted under is the final determining factor on applicability and requirements.

Notes

А	'	Requirements for restricted helicopters are somewhat different than those for standard category helicopters. For example, restricted aircraft do not need passenger drop cords.
В	ELT	Many DOI Bureaus require C-126 (406 MHz) ELTs for Exclusive Use contracts

Avionics Requirements Matrix for Large Aircraft

January 5, 2012

Equipment	Airtanker	SEAT	Smokejumper
ELT ^A	1	1	1
760 Channel VHF- AM Transceiver	2	Non-BLM contracts require 1 VHF- AM transceiver. BLM SEAT contracts require 2 VHF-AM transceivers.	2
P25 Digital VHF- FM Transceiver	1	1	2
Automated Flight Following	1	1	1
Public Address System			1
GPS	1	1	1
Static System	1	1	1
Transponder	1	1	1
VOR System	2		2
ILS System	1		2
Marker Beacon	1		1
DME or IFR GPS	1		1
ADF or IFR GPS			1
Weather Detection System			1
Radar Altimeter	1		
TAS	1		1
CVR	1		1
FDR			Per 14 CFR 135 (+20 PAX seats a FDR is required)
Audio Control System	At least 2. The pilot inspector's position must have a #3 Audio Control System or provisions to monitor the SICs radio RX along with ICS capability.	1	At least 3. A 4th and 5th Audio Control System is required in CASA 212, DC3-TP, and Shorts C23A/SD3- 30 aircraft.
ICS System	1		1

This matrix shows the minimum required contracted avionics items on typical contracts. Contracts are often modified to meet host base needs. The contract language an aircraft is contracted under is the final determining factor on applicability and requirements.

Notes

		Many DOI Bureaus require C-126 (406 MHz) ELTs for Exclusive Use
Α	ELT	contracts. New DOI Exclusive Use contracts require C-126 (406 MHz)
		ELTs on all fixed wing aircraft.