Drug and Alcohol Services Information System

The DASIS Report

December 7, 2001

Older Adults in Substance Abuse Treatment

In Brief

- In 1999, 50,700 persons aged 55 or older were admitted to publicly funded substance abuse treatment
- Alcohol was the primary substance of abuse among older adults
- Alcohol abuse admissions among older adults declined between 1994 and 1999, but illicit drug admissions increased

his report examines trends in admissions of adults aged 55 or older to publicly funded substance abuse treatment facilities. In 1999, this age group comprised approximately 58 million people in the United States. The aging of the baby boom generation (those born between 1946 and 1964) will cause that number to almost double by 2030, reaching 108 million.

If the relatively low rates of substance abuse among older adults were to remain the same as in 1995, treatment need would be 1½ times greater in 2030 because of this population growth.¹ However, the baby boom generation has higher rates of lifetime alcohol and drug use than did the previous generation, and evidence suggests that these higher rates will persist as the group ages.²,³ Thus, the need for substance abuse treatment among older adults is expected to increase.

The Treatment Episode Data Set (TEDS) permits monitoring of trends among older adults admitted to substance abuse treatment in publicly funded facilities.

The DASIS Report is published periodically by the Office of Applied Studies, Substance Abuse and Mental Health Services Administration (SAMHSA). All material appearing in this report is in the public domain and may be reproduced or copied without permission from SAMHSA. Additional copies of this report may be downloaded from http://www.samhsa.gov/oas/facts.cfm. Citation of the source is appreciated. Other reports from the Office of Applied Studies are also available on-line: http://www.DrugAbuseStatistics.samhsa.gov/.

Table 1. Admissions Aged 55 or Older, by Primary Substance at Admission: 1994-1999

1994	1995	1996	1997	1998	1999
52.2	50.3	51.3	46.8	49.9	50.7
Primary Substance		Percent			
82.0	80.9	81.0	79.1	78.3	76.1
9.7	10.3	10.0	11.4	11.0	12.6
2.6	3.0	3.2	3.6	4.2	4.5
0.7	8.0	0.9	1.0	1.1	1.3
0.9	0.8	0.9	1.0	0.8	0.7
0.3	0.3	0.3	0.4	0.5	0.6
3.8	3.9	3.5	3.7	4.1	4.1
	52.2 ce 82.0 9.7 2.6 0.7 0.9 0.3	52.2 50.3 ce 82.0 80.9 9.7 10.3 2.6 3.0 0.7 0.8 0.9 0.8 0.3 0.3	52.2 50.3 51.3 ce	52.2 50.3 51.3 46.8 ce	52.2 50.3 51.3 46.8 49.9 Percent 82.0 80.9 81.0 79.1 78.3 9.7 10.3 10.0 11.4 11.0 2.6 3.0 3.2 3.6 4.2 0.7 0.8 0.9 1.0 1.1 0.9 0.8 0.9 1.0 0.8 0.3 0.3 0.3 0.4 0.5

Figure 1. Admissions Aged 55 or Older, by Age Group: 1994-1999

60
50
40
20
1994 1995 1996 1997 1998 1999
55-59 60-64 65-69
70-74

Source: 1999 SAMHSA Treatment Episode Data Set (TEDS).

In 1999, there were 50,700 admissions aged 55 or older to publicly funded substance abuse treatment (Table 1). The majority (81 percent) were male. The admission rate for adults aged 55 or older was 88 per 100,000, which was considerably lower than the rate of 719 admissions per 100,000 for the population aged 12 or older (data not shown).

Trends in Treatment Admissions

Between 1994 and 1999, annual substance abuse treatment admissions among persons aged 55 or older decreased by 3 percent, from 52,200 to 50,700 (Table 1). This decrease was similar to that shown in the total treatment population.

Adults aged 55 to 59 made up the largest part of the older adult treatment population. This proportion increased from 49 percent in 1994 to 55 percent in 1999 (Figure 1).

Alcohol was the primary substance of abuse at admission for all age groups, including individuals aged 55 or older (Table 1). However, alcohol admissions declined by 9 percent between 1994 and 1999 both for men and for women in that age group (Figure 2). Among older adults, admissions for illicit drugs increased by 25 percent for men and 43 percent for women over this time period, although overall admissions remained low.

Referral Source

Older adults were more likely than younger adults to be referred to treatment by health care providers and less likely to enter treatment through the criminal justice system (data not shown). Among adults aged 55 or older, 13 percent were referred by health care providers, compared with 7 percent of admissions under age 55. Thirty percent of adults aged 55 or older were


referred through the criminal justice system, compared with 37 percent of younger admissions.


Age at First Use

First use of drugs or first alcohol intoxication occurred at a younger age among men aged 55 or older than among women in that age group (Figure 3). Fifty percent of the men in this age group had initiated drug or alcohol use by the age of 17. Women in this group, however, were generally older when they began their drug and alcohol use, with more than one quarter reporting that their first use occurred after age 30.

Admissions by State

In 1999, the most populous States tended to have the largest numbers of older adults entering substance abuse treatment, but not necessarily the highest





admission rates (Table 2). Admission rates among adults aged 55 or older tended to be highest in northern and northeastern States.

End Notes

Gfroerer, J.C., & Epstein, J.F. (1999). Marijuana initiates and their impact on future drug abuse treatment need. *Drug and Alcohol Dependence* 54, 229-237.

²Substance Abuse and Mental Health Services Administration. (2000). *Summary of findings from* the 1999 National Household Survey on Drug Abuse (NHSDA Series: H-12, DHHS Publication No. SMA 00-3466). Rockville, MD: Author.

³Center for Substance Abuse Treatment. (1998). Substance abuse among older adults (DHHS Publication No. SMA 98-3179). Rockville, MD: Substance Abuse and Mental Health Services Administration.

Table 2. States with Largest Numbers and Highest Rates of Admissions Aged 55 or Older, by Rank: 1999

			Rate per 100,000
State	Number	State	Aged 55 or Older
New York	7,026	Alaska	378
California	6,063	Colorado	335
Florida	2,782	Oregon	225
Colorado	2,631	Connecticut	214
Massachusetts	2,218	Minnesota	185
Minnesota	1,820	District of Columbia	179
Oregon	1,737	New York	177
Maryland	1,636	Vermont	171
Connecticut	1,605	South Carolina	170
Washington	1,491	South Dakota	167
New Jersey	1,421	Massachusetts	163
Michigan	1,416	Utah	163
South Carolina	1,387	Maryland	160
Indiana	1,304	Montana	139
Pennsylvania	1,276	Maine	136

The Drug and Alcohol Services Information System (DASIS) is an integrated data system maintained by the Office of Applied Studies, Substance Abuse and Mental Health Services Administration (SAMHSA). One component of DASIS is the Treatment Episode Data Set (TEDS), a national-level dataset comprising State administrative data from treatment facilities receiving public funds. The TEDS system includes records for some 1.6 million substance abuse treatment admissions annually. TEDS records represent admissions rather than individuals, as a person may be admitted to treatment more than once.

The DASIS Report is prepared by the Office of Applied Studies, SAMHSA; Synectics for Management Decisions, Inc., Arlington, Virginia; and RTI, Research Triangle Park, North Carolina.

Information and data for this issue are based on data reported to TEDS through April 16, 2001.

Access the latest TEDS reports at: www.DrugAbuseStatistics.SAMHSA.gov

Access the latest TEDS public use files at: www.icpsr.umich.edu/SAMHDA/teds.html