

Grain Handling

U.S. Department of Labor Occupational Safety and Health Administration

OSHA 3103 1996 (Revised)

This informational booklet is intended to provide a generic, non-exhaustive overview of a particular standards-related topic. This publication does not itself alter or determine compliance responsibilities, which are set forth in OSHA standards themselves and the Occupations Safety and Health Act. Moreover, because interpretations and enforcement policy may change over time, for additional guidance on OSHA compliance requirements, the reader should consult current administrative interpretations and decisions by the Occupational Safety and Health Review Commission and the courts.

Material contained in this publication is in the public domain and may be reproduced, fully or partially, without permission of the Federal Government. Source credit is requested but not required.

This information will be made available to sensory impaired individuals upon request. Voice phone (202) 219-8615; Telecommunications Device for the Deaf (TDD) message referral phone: 1-800-326-2577.



Grain Handling

U.S. Department of Labor Robert B. Reich, Secretary

Occupational Safety and Health Administration Joseph A. Dear, Assistant Secretary

OSHA 3103 1996 (Revised)

Contents

Introduction1Scope and Application1Provisions of the Standard2Hot Work2	
Entry Into Bins, Silos, Tanks, and Other Storage Structures 2	
Inside Bucket Elevator Legs	
Preventive Maintenance	
Housekeeping4	
Emergency Action Plan	
Training and Education	
Other Sources of OSHA Assistance6Safety and Health Program Management Guidelines.6State Programs.7Consultation Services7Voluntary Protection Programs (VPPs)8Training and Education.8Electronic Information.9Emergencies9	
OSHA Related Publications	
States with Approved Plans	
OSHA Consultation Project Directory14	
OSHA Area Offices	

Page

Introduction

The Occupational Safety and Health Administration (OSHA) issued its Grain Handling Standard. *Title 29. Code of Federal Regulations* (CFR). Part 1910.272. in 1987 to protect workers exposed to fires and explosions. Excessive amounts of grain dust was one of the major causes of these devastating catastrophes that killed or maimed hundreds of workers.

The standard protects workers from hazards faced while walking on or underneath accumulations of grain within a grain storage facility. These hazards include engulfment and entrapment in grain and grain handling equipment, which can result in asphyxiations, crushing injuries, and amputations.

In 1996, OSHA further amended the standard¹ to protect employees whenever they enter a "flat storage structure"² regardless of their point of entry. "walk down" grain to make it flow within or outside of a grain storage structure or stand on grain at a depth that poses an engulfment hazard.

OSHA believes that this technical amendment will prevent from 2 to 4 additional fatalities annually and a similar number of traumatic injuries caused by mechanical devices such as augers.

Employers and employees covered by an OSHA-approved state safety and health plan should check with their state agency. which may be enforcing standards and other procedures " at least as effective as," but not always identical to. federal requirements. See list of state plans at end of this publication.

This publication serves as a guide to the standard, discusses the causes of grain dust explosions, and provides the information needed to train employees on ways to eliminate related hazards.

Scope and Application

The requirements of the standard apply to more than 250,000 workers at 24,000 grain elevators and mills that have been and continue to be exposed to fires, explosions, engulfment, and entrapment hazards. Engulfment and entrapment hazards have killed or maimed hundreds of workers.

¹ Fed Reg 61 (47):9578-9584, March 8, 1996. Part 1910.272

² A "flat storage structure" means a grain storage building or structure that will not empty completely by gravity, has an unrestricted ground level opening for entry, and must be entered to reclaim the residual grain by using pwered equipment or manual means.

According to the bureau of Labor Statistcs³. In 1993 and 1994 OSHA estimates that there have been more than 45 workers engulfed in gain and asphyxiated or crushed to death by grain augers.

Provisions of the Standard

There are several provisions employers must follow to comply with the grain handling standard. including a requirements for hot work: entering bins, silos, tanks, and other storage structures: inside bucket elevator legs: preventive maintenance. housekeeping, handling emergencies, and training.

Hot Work

A permit system is required for employees performing hot work. Hot work includes electric or gas welding, cutting , brazing, or similar flame-producing operations.

The permit is to ensure that the employer is aware of the hot work being performed—particularly, when performed by contractors—and that appropriate safety precautions have been taken prior to beginning the work.

The standard does not require a work permit if the hot work is performed in the presence of the employer or the employer's authorized representative. in an employer-authorized welding shop. or when work is conducted out of doors and away from the grain facility.

Entry into Bins, Silos. Tanks, and Other Storage Structures

Employees must be given a work permit before they enter bins, silos. or tanks unless the employer or the employer's representative is present. Such permits will help employers maintain control over employee entry into these areas.

In addition to the permit-system, employees should be thoroughly informed of the hazards associated with entry into bins, silos, tanks, and other structures. For example employees should never enter these areas from the bottom when grain or other agricultural products are hung-up or stuck to the sides. Employees should be made aware that the atmosphere in bins. silos and tanks can be oxygen deficient or toxic. Consequently, employees must be trained in the proper method of testing, the atmosphere procedures to take if the atmosphere is

³ U.S. Department of Labor, Bureau of Labor Statistics, *Census of Fatal Occupational Injuries*. Washington. DC, 1993-1994.

to take if the atmosphere is found to be hazardous. The air inside the enclosure must be tested for oxygen content both before and during employee entrance, unless there is continuous natural air movement or forced-air ventilation in the space.

Provide ventilation. supplemented by the use of appropriate respirators. if necessary. If oxygen levels are less than 19.5 percent if concentrations of toxic agents present in the air either exceed ceiling limits in OSHA's health standards or will have health affects that restrict an employee's abilities to effect self-rescue or obtain assistance: or, if there is a combustible gas or vapor concentrations in excess of 10 percent of the lower flammable limit. Ventilation must be provided until the unsafe condition is eliminated and must be continued as long as there is a possibility of recurrence of the unsafe condition while the bin, silo, or tank is occupied by employees.

An employee must wear a body harness with a lifeline or use a boatswain's chair whenever entering a grain storage structure at or above the level of stored grain and the depth of stored grain poses an engulfment hazard. If the employer can demonstrate that the lifeline or boatswain's chair is not feasible or creates a greater hazard the employer must provide an alternative means of protection. Where employees work in a bin, silo, or tank, a trained and equipped observer must be present on the outside maintain communication with employees and provide help if needed.

The standard prohibits "walking down grain" to make it flow within or outside of the storage structure. or standing on moving grain. Also, all mechanical, electrical. and pneumatic equipment that presents a danger to employees inside grain storage structures must be deenergized and disconnected, locked-out and tagged, blocked-off, or otherwise stopped by other equally effective means or methods.

In addition, no employee is permitted to be in any location where an accumulation of grain on the sides of the storage structure or elsewhere could fall and engulf him or her.

Inside Bucket Elevator Legs

Inside bucket elevators are well recognized as potential ignition sources for primary explosions. To lessen these hazards, the standard requires that belts purchased after March 30, 1988, have a surface electrical resistance not exceeding 300 megohms. Bucket elevators must have an opening to the head pulley section and boot section to allow for inspection, maintenance, and cleaning; bearings must be mounted externally to the leg casing or the employer must provide vibration, temperature, or other monitoring of the conditions of the bearings if bearings are mounted inside or partially inside the leg casing.

Also, elevator legs must be equipped with a motion-detection device that will shut down the leg when the belt speed is reduced by 20 percent or more of the normal operating speed. A belt-alignment monitoring device with an alarm to alert employees when the belt is not tracking properly is also required: alternatively, employers must provide a means to keep the belt tracking properly.

Bearing monitors, motion detection devices, and belt-alignment devices need not be installed if the employer equips bucket elevators with a fire and explosion suppression system capable of protecting the head and boot sections of the leg, or with a pneumatic dust control system: that will keep the dust concentrations inside the leg casing 25 percent below the lower explosive limit during operation.

Preventive Maintenance

Preventive maintenance is a very important aspect of any grain industry safety and health program. It is a must for controlling fuel and ignition sources and for keeping equipment functioning properly and safely.

The OSHA standard does not require the employer to have a written preventive maintenance program but states that all mechanical and electrical equipment must be kept in proper operating condition. To do this the employer must annually inspect the mechanical and safety control equipment associated with dryers, grain stream processing equipment, dust collection equipment, including filter collectors, and bucket elevators.

This equipment must be lubricated and maintained according to the manufacturers' recommendations, or as determined necessary by prior operating records. Equipment that malfunctions or operates below designed efficiency must be promptly repaired or removed from service. Inspected or repaired equipment must how the date of inspection.

The standard also requires procedures for locking out and tagging equipment to prevent the inadvertent application of energy or motion to equipment being repaired. serviced, or adjusted. All employees who repair, service. and operate the equipment must be familiar with the employer's locking out and tagging procedures.

Housekeeping

Housekeeping is an important part of any safety and health program especially in facilities where combustible material might accumulate. The standard request the employer to develop and implement a written housekeeping program to help eliminate these dangers.

The program must include instructions for reducing dust accumulations on ledges, floors, equipment, and other exposed surfaces, and must

identify "priority" areas in grain elevators that are known to be potential sources of ignition. These include floor areas within 35 feet (10.9728 meters) of inside bucket elevator legs, enclosed areas containing grinding equipment. and enclosed areas containing grain dryers located inside the facility. The housekeeping program also must address the methods for removing grain spills from work areas. The use of compressed air to remove dust is permitted only when all machinery that presents a source of ignition in the area is shutdown. and all other known potential ignition sources are removed or controlled.

Because grain dust is the main source of fuel for explosions in grain handling facilities, the standard allows a maximum accumulation of more than an 1/8-inch (0.3175 centimeters) in priority housekeeping areas of grain elevators, if dust accumulations exceed the 1/8-inch (0.3175 Centimeters) action level in priority housekeeping areas designated means or methods must be initiated immediately to remove such accumulations. The standard also provides for the employer to use alternative means to the 1/8-inch (0.3175 centimeters) action level where the alternative can be demonstrated to provide equivalent protection from explosions. This may involve additional treatment of the dust and/or the area of dust accumulation, such as spraying with oil or water. In addition, the use of oil additives such as white mineral oil in the grain flow, and changes in materials handling processes can also help reduce the accumulation of dust and make the dust less explosive.

Emergency Action Plan

Employers must develop and implement a written emergency action plan. The plan does not have to be written if there are fewer than 10 employees. This plan must include a distinguishable and distinct alarm system (especially for those employees who work indoors) and evacuation procedures, and must include employee training in emergency procedures.

Employees must know where the nearest escape routes are and must be familiar with workplace maps that clearly show these emergency escape routes. In addition, at least two means of emergency escape from galleries (bin decks) are required in grain elevators.

The employer must also designate a safe area outside the facility where employees can congregate after evacuation and must implement procedures to account for all employees after emergency evacuation has been completed. It is recommended that employers seek the assistance of local fire departments to preplan for emergencies and designate a means of contacting fire and rescue agencies under emergency conditions.

Training and Education

Training employees to recognize hazards associated with their jobs is an effective method for increasing overall safe operations. Employers are required to train employees in their work tasks annually or whenever changes in job assignments expose them to new hazards. New employees are to be trained prior to starting work. Employees assigned special or infrequent tasks, such as bin entry and the handling of flammable or toxic substances, must also be trained to perform these tasks safely.

Training must include the following:

- General safety precautions associated with the grain facility as well as the recognition and prevention of hazards related to engulfment, mechanical devices, dust accumulations, and common ignition sources such as smoking.
- Specific procedures and safety practices applicable to the job tasks including, but not limited to, clearing choked legs, and performing housekeeping, hot work, preventive maintenance, and lockout/tagout. and
- Training in emergency procedures.

Other Sources of OSHA Assistance

Safety and Health Program Management Guidelines

Effective management of worker safety and health protection is a decisive factor in reducing the extent and severity of work-related injuries and illnesses and their related costs. To assist employers and employees in developing effective safety and health programs, OSHA published recommended *Safety and Health Program Management Guidelines (Federal Register 34 (18):3908-3916, January 36, 1989)*. These voluntary guidelines apply to all places of employment covered by OSHA..

The guidelines identify four general elements that are critical to the development of a successful safety and health management program:

- Management commitment and employee involvement,
- Worksite analyses,
- Hazard prevention and control, and
- Safety and health training

The guidelines recommend specific actions under each of these general elements to achieve an effective safety and health program. A single free copy of the guidelines can be obtained from the U.S. Department of Labor,

Publications, P.O. Box 37535, Washington, DC 20013-7535, by sending a self-addressed mail label with your request.

State Programs

The Occupational Safety and Health Act of 1970 encourages states to develop and operate their own job safety and health plans. States with plans approved under section 18(b) of the Act must adopt standards and enforce requirements that. are at least as effective as federal requirements. There are currently 25 state plan states and territories: 23 covering both private and public (state and local government) employees and 2 covering public sector employees only. Plan states must adopt standards comparable (but not necessarily identical) to the federal within 6 months of a federal standard's promulgation. Until a state standard is promulgated, OSHA provides interim enforcement assistance, as appropriate, in these states. A listing of approved state plans appears at the end of this publication.

Consultation Services

Free onsite safety and health consultation services are available in all states to employers who warn help in establishing and maintaining a safe and healthful workplace. Primarily developed for smaller employers with more hazardous operations, the OSHA Consultation Service is largely funded by OSHA and is delivered by state governments employing professional safety and health consultants. The full service assistance that is offered includes an appraisal of all mechanical systems, physical work practices, occupational safety and health hazards of the workplace, and all aspects of the employer's present job safety and health program. In addition, the service offers assistance to employers in developing and implementing an effective workplace safety and health program that corrects and continuously addresses safety and health concerns.

The program is separate tom OSHA's inspection efforts. No penalties are proposed or citations issued for any safety or health problems identified by the consultant The service is confidential. The employer's name, and the firm's name, and any information about the workplace, plus any unsafe or unhealthful working conditions that the consultant uncovers will not be reported routinely to the OSHA inspection staff.

The only obligation is the employer's commitment to correct serious job safety and health hazards in a timely manner. The employer is asked to make this commitment prior to the actual visit.

For more information concerning consultation services, see the list of consultation projects at the end of this publication.

Voluntary Protection Programs (VPPs)

The Voluntary Protection Programs are designed to recognize and promote effective safety and health program management. In the VPP, management, labor, and OSHA establish cooperative relationships at workplaces that have implemented strong programs.

Sites approved for VPP's Star, Merit and Demonstration programs have met. and must continue to meet rigorous participation standards. Benefits of VPP participation include improved employee motivation to work safely, leading to better quality and productivity: lost workday case rates that generally are 60 to 80 percent below industry aver-ages; reduced workers' compensation and other injury- and illness-related costs: positive community recognition and interaction: further improvement and revitalization of already good safety and health programs; and partnership with OSHA.

Voluntary Protection Programs and onsite consultation services, when coupled with an effective enforcement program. expand worker protection to help meet the goals of the *Occupational Safety and Health Act*.

For additional information about the VPP, contact the VPP manager in your OSHA regional office listed at the end of this publication.

Training and Education

OSHA's area offices offer a variety of informational services, such as publications, audiovisual aids, technical advice, and speakers for special engagements. OSHA's Training Institute in Des Plaines, IL, provides basic and advanced courses in safety and health for federal and state compliance officers, state consultants, federal agency personnel, and private sector employers, employees, and their representatives.

Tile OSHA Training institute also has established OSHA Training Institute Education Centers to address the increased demand for its courses from the private sector and from other federal agencies. These centers include nonprofit colleges, universities, and other organizations that have been selected after a competition for participation in the program.

OSHA also provides funds to nonprofit organizations, through grants, to conduct workplace training and education in subjects where OSHA believes there is a lack of workplace training.

Grants are awarded annually and grant recipients are expected to contribute at least 20 percent of the total grant cost.

For more information on grants, courses, and education centers, contact the OSHA Training Institute, Office of Training, and Education, 1555 Times Drive. Des Plaines, IL 60018, (847) 297-4810, fax (847) 297-4874.

For further information on any OSHA program, contact your nearest OSHA area or regional office listed at the end of this publication.

Electronic Information

Labor News Bulletin Board -- OSHA news releases. recent Federal Register notices. fact sheets, and other information are available by modem by dialing (202) 219-4734. Callers should set the modem at 300, 1,200, 2,400, 9,600, or 14,400 BAUD: Parity: None: Data Bias=8: Stop Bit=1. Voice phone (202) 219-5831.

Internet -- OSHA standards, interpretations, directives, and additional information are now on the World Wide Web at http://www.osha.gov/ and http://www.osba-slc.gov/.

CD-ROM -- A wide variety of OSHA materials including standards, interpretations. directives, and more can be purchased on CD-ROM from the Government Printing Office. To order, write to Superintendent of Documents, P.O. Box 371954.Pittsburgh,PA 15250-795. Specify OSHA Regulations, Documents and Technical Information on CD-ROM, (ORDT), S/N 729-031-000005. The price is \$88 per year (\$ 110.00 foreign); single copy \$30.00 (\$37.50 foreign).

Emergencies

To report life-threatening situations, catastrophes, or fatalities call (800) 3 21-OSHA. Complaints will go immediately to the nearest OSHA area or state office for help.

For further information on any OSHA program, contact your nearest OSHA -area or regional office listed at the end of this publication.

OSHA Related Publications

Single, free copies of the following publications can be obtained from the U.S. Department of Labor, OSHA Publications. P.O. Box 37535, Washington, DC 20013-7535, (202) 219-1667 (202) 219-9266 (fax), or from the nearest OSHA regional area office listed at the end of this publication. Send a self-addressed mailing label with your request.

Consultation Services for the Employer - OSHA 3047

Control of Hazardous Energy (Lockout/Tagout) - OSHA 3120

Employer Rights and Responsibilities Following an OSHA Inspection - OSHA 3000

Employee Workplace Rights - OSHA 3021

How to Prepare for Workplace Emergencies - OSHA 3088

OSHA Inspections - OSHA 2098

Personal Protective Equipment – OSHA 3077

Respiratory Protection - OCHA 3079

The following publications are available from the Superintendent of Documents, U.S. Government Printing Office Washington, DC 20402, (202) 512-1800. Include GPO Order No. and make checks payable to Superintendent of Documents.

Construction Industry Digest - OSHA 2202 Order No. 029-016-00151-4. Cost \$2.25.

Hazard Communication--A Compliance Kit - OSHA 3704 Order No. 029-016-00127-1. Cos1\$18.00 (Foreign \$22.50)

Hazard Communication Guidelines for Compliance - OSHA 3111 Order No.029-016-00127-I. Cost \$1.00

Job Hazard Analysis - OSHA 3071 Order No.029-016-00143-3. Cost \$1.00

Principal Emergency Response and Preparedness Requirements in OSHA Standards and Guidance for Safety and Health Programs - OSHA 3122 Order No. 029-O16-00136-1. Cost \$2.50

Training Requirements in OSHA Standards and Training Guidelines OSHA 2254 Order No.029-016-00137-9. Cost \$4.25

States with Approved Plans

Commissioner

Alaska Department of Labor 1111 West 8th Street Room 306 Juneau AK 99801 (907) 465-2700

Director

Industrial Commission of Arizona 800 W. Washington Phoenix, AZ 85007 (602) 542-5795

Director

California Department of Industrial Relations 45 Fremont Street San Francisco, CA 94105 (415) 972-8835

Commissioner

Connecticut Department of Labor 200 Folly Brook Boulevard Wethersfield, CT 06109 (203) 566-5123

Director

Hawaii Department of Labor and Industrial Relations 830 Punchbowl Street Honolulu, HI 96813 (808) 586-8844

Commissioner

Indiana Department of Labor State Office Building 402 West Washington Street Room W195 Indianapolis, IN 46204 (307) 232-2378

Commissioner

Iowa Division of Labor Services 1000 E. Grand Avenue Des Moines, IA 50319 (515) 281-3447

Secretary

Kentucky Labor Cabinet 1049 U.S. Highway, 127 South Frankfort, KY 40601 (502) 564-3070

Commissioner

Maryland Division of Labor and Industry Department of Labor Licensing and Regulation 501 St. Paul Place, 2nd Floor Baltimore, MD 21202-2272 (410) 333-4179

Director

Michigan Department of Labor Victor Office Center 201 N. Washington Square P.O. Box 30015 Lansing, MI 48933 (517) 373-9600

Commissioner

Minnesota Department of Labor and industry 443 Lafayette Road St. Paul, MN 55155 (612) 296-2342

Director

Nevada Division of Industrial Relations 400 West King Street Carson City, NV 97502 (702) 687-3032

Secretary

New Mexico Environmental Department 1190 St. Francis Drive P.O. Box 26110 Santa Fe, NM 87502 (505) 827-7850

Commissioner

New York Department of Labor W. Averell Harriman State Office Building – 12, Room 500 Albany, NY 12240 (518) 457-2741

Commissioner

North Carolina Department of Labor 319 Chapanoke Road Raleigh, NC 27603 (919) 662-4585

Administrator

Department of Consumer & Business Services, Labor and Industries Building Room 430 Salem, OR 97310 (503) 378-3272

Secretary

Puerto Rico Department of Labor and Human Resources Prudencio Rivera Martinez. Building 505 Munoz Rivera A-venue Hato Rey, PR 00918 (809) 754-2119

Commissioner

South Carolina Department of Labor 3600 Forest Drive P.O. Box 11329 Columbia, SC 29211-1329 (803) 734-9594

Commissioner

Tennessee Department of Labor Attention: Robert Taylor 710 James Robertson Parkway Nashville, TN 37243-0659 (615) 741-2582

Commissioner

Industrial Commission of Utah 160 East 300 South, 3rd Floor P.O. Box 146600 Salt Lake City, UT 84114-6600 (801) 530-6898

Commissioner

Vermont Department of Labor and Industry National Life Building – Drawer 20 120 State Street Montpelier, VT 05620 (802) 828-2788

Commissioner

Virgin Islands Department of Labor and Industry Powers- Taylor Building 13 South 13th Street Richmond, VA 23219 (804) 786-2377

Commissioner

Virgin Islands Department of Labor 2131 Hospital Street, Box 890 Christiansted St. Croix, VI 00820—1666 (809) 773-1994

Director

Washington Department of Labor and industries P.O. Box 44000 Olympia, WA 98504-4000 (360) 902-4200

Administrator

Worker's Safety and Compensaation Divison (WSC) Wyoming Department of Employment Herschler Building, 2nd Floor East 122 West 25th Street Cheyenne, WY 82002 (307) 777-7786

OSHA Consultation Project Directory

State

Telephone

Alabama	(205) 348-3033
Alaska	
Arizona	
Arkansas	
California	
Colorado	
Connecticut	
Delaware	
District of Columbia	
Florida	
Georgia	
Guam	
Hawaii	
Ida ho Illinois	
	. ,
Indiana	
Iowa	
Kansas	
Kentucky	
Louisiana	
Maine	
Maryland	
Massachusetts	
Michigan	
Minnesota	
Mississippi	
Missouri	
Montana	
Nebraska	
Nevada	
New Hampshire	
New Jersey	
New Mexico	
New York	
North Carolina	
North Dakota	
Ohio	
Oklahoma	. (405) 528-1500

Oregon	(503) 378-3272
Pennsylvania	
Puerto Rico	
Rhode Island	
South Carolina	(803) 734-9599
South Dakota	
Tennessee	(615) 741-7036
Texas	(512) 440-3834
Utah	
Vermont	
Virginia	(804) 786-8707
Virgin Islands	
Washington	
West Virginia	(304) 558-7890
Wisconsin	(608) 266-8579(H)
	(414) 521-5063(S)
Wyoming	

(H)-Health (S)- Safety

15

OSHA Area Offices

Area

Telephone

Albany, NY
Albuquerque, N M
Allentown, PA
Anchorage, AK
Appleton, WI
Augusta, ME
Austin, TX
Avenel, NJ
Baltimore, MD
Baton Rouge, LA
Bayside, NY
Bellevue, WA
Billings, MT
Birmingham, AL
Bismarck, ND
Boise, ID
Bowmansville, NY
Braintree, MA
Bridgeport, CT
Calumet City, IT
Carson City, NV
Charleston, WV
Cincinnati, OH
Cleveland, OH
Columbia, SC
Columbus, OH
Concord, NH
Corpus Christi, TX (512) 884-2694
Dallas, TX
Denver, CO
Des Plaines IT (708) 803-4800
Des Moines, I A (515) 284-4794
Englewood, CO
Erie, PA
Fort Lauderdale, FL
Fort Worth, TX
Frankfort, KY (502) 227-7024
Harrisburg, PA

Headford OT	(202) 240 2152
Hartford, CT	
Hasbrouck Heights, NJ	
Honolulu, HI	
Houston, TX	
Houston; TX	
Indianapolis, IN	
Jackson, MS	· · ·
Jacksonville, FL	
Kansas City, MO	
Lansing, MI	
Little Rock, AR	. ,
Lubbock, TX	· · ·
Madison, WI	
Marlton, NJ	. ,
Methuen, MA	
Milwaukee, WI	
Minneapolis, MN	
Mobile, AL	
Nashville, TN	. ,
New York, NY	. ,
Norfolk, VA	. ,
North Aurora, IL	
Oklahoma City, OK	
Omaha, NE	(402) 221-3182
Parsippany, NJ	(201) 263-1003
Peoria, IL	(309) 671-7033
Philadelphia, PA	(215) 597-4955
Phoenix, AZ	(602) 640-2007
Pittsburgh, PA	(412) 644-2903
Portland, OR	(503) 326-2251
Providence, RI	(401) 528-4669
Raleigh, NC	(919) 856-4770
Salt Lake City, UT	(801) 524-5080
San Francisco, CA	(415) 744-7120
Savannah, GA	(912) 652-4393
Smyrna, GA	(404) 984-8700
Springfield, MA	
St. Louis, MO	(314) 425-4249
Syracuse, NY	(315) 451-0808
Tampa, FL	
Tarrytown, NY	
Toledo, OH	
Tucker, GA	
Westbury, NY	
Wichita, KS	
Wilkes-Barre, PA	

U.S. Department of Labor Occupational Safety and Health Administration Regional Offices

Region I

(CT,* MA, ME, NH, RI, VT*) 133 Portland Street 1st Floor Boston, MA 02114 Telephone: (617) 565-7164

Region II

(**NJ**, **NY**, * **PR**,* **VI***) 201Varick Street Room 670 New York, 10014 Telephone: (212) 337-2378

Region III

(**DC**, **DE**,**MD**,* **PA**, **VA**,* **WV**) Gateway Building, Suite 2100 3535 AM Street Philadelphia, PA 19104 Telephone:(215) 596-1201

Region IV

(AL, FL, GA, KY,*MS, NC, SC,* TN*) 1375 Peachtree Street, N.E. Suite 587 Atlanta, GA 30367 Telephone: (404) 347-3573

Region V

(**IL**, **IN**,* **MI**,* **OH**, **WI**) 230 South Dearborn Street Room 3244 Chicago, IL 60604 Telephone: (312) 353-2220

Region VI (AR, ILA, NM,*OK, TX) 525 Griffin Street Room 602 Dallas, TX 75202 Telephone: (214) 767-4731

Region VII

(IA,* KS, MO, NE) City Center Square 110 Main Street, Suite 8 00 Kansas City, MO 64105 Telephone: (816)426-5861

Region VIII (CO, MT,ND,SD,UT,* WY*) Federal Building, Room 1576 1999 Broadway Denver, CO 8002-5716 Telephone: (303) 391-5858

Region IX American Samoa, AZ,* CA,* Guam, HI,*NV,*Trust Territories of the Pacific) 71 Stevenson Street, Room 420 San Francisco, CA 94105 Atlanta, GA 30367 Telephone: (415) 744-6670

Region X

(**AK**, *** ID**, **OR**, *** WA***) 1111 Third Avenue Suite 715 Seattle, WA 98101-3212 Telephone: (206) 553-5930

* These states and territories operate their own OSHA-approved job safety and health programs (Connecticut and New York plans cover public employees only). States with approved programs must have a standard that is identical to, or at least as effective, as the federal standard.