HIGHLIGHTS OF PRESCRIBING INFORMATION

These highlights do not include all the information needed to use Fluzone safely and effectively. See full prescribing information for Fluzone.

Fluzone (Influenza Virus Vaccine) Suspension for Intramuscular Injection 2012-2013 Formula Initial US Approval 1980

-----INDICATIONS AND USAGE-----

Fluzone is indicated for active immunization against influenza disease caused by influenza virus subtypes A and type B contained in the vaccines. (1) **Fluzone** is approved for use in persons 6 months of age and older. (1)

-----DOSAGE AND ADMINISTRATION-----

• For intramuscular use only

Age	Dose	Schedule
6 months through 35	One or two doses a, 0.25 mL	If 2 doses, administer at
months	each	least 1 month apart
36 months through 8	One or two doses a, 0.5 mL	If 2 doses, administer at
years	each	least 1 month apart
9 years and older	One dose, 0.5 mL	-

^a1 or 2 doses depends on vaccination history as per Advisory Committee on Immunization Practices annual recommendations on prevention and control of influenza with vaccines.

-----DOSAGE FORMS AND STRENGTHS-----

Suspension for injection supplied in 4 presentations: prefilled syringe (pink plunger rod), 0.25 mL; prefilled syringe (clear plunger rod), 0.5 mL; single-dose vial, 0.5 mL; multi-dose vial, 5 mL. (3)

-----CONTRAINDICATIONS-----

Severe allergic reaction to any component of the vaccine, including egg protein, or after previous dose of any influenza vaccine. (4)

-----WARNINGS AND PRECAUTIONS-----

• If Guillain-Barré syndrome (GBS) has occurred within 6 weeks of previous influenza vaccination, the decision to give Fluzone should be based on careful consideration of the potential benefits and risks. (5.1)

-----ADVERSE REACTIONS-----

- In children 6 months through 8 years of age, the most common injectionsite reactions were pain or tenderness (>50%) and redness (>25%); the most common solicited systemic adverse events were irritability and drowsiness (>25% of children 6 months through 35 months) and myalgia (>20% of children 3 years through 8 years). (6.1)
- In adults 18 through 64 years of age, the most common injection-site reaction was pain (>50%); the most common solicited systemic adverse events were headache and myalgia (>30%). (6.1)
- In adults ≥65 years of age, the most common injection-site reaction was pain (>20%); the most common solicited systemic adverse events were headache, myalgia, and malaise (>10%). (6.1)

To report SUSPECTED ADVERSE REACTIONS, contact Sanofi Pasteur Inc., Discovery Drive, Swiftwater, PA 18370 at 1-800-822-2463 (1-800-VACCINE) or VAERS at 1-800-822-7967 or www.vaers.hhs.gov.

-----USE IN SPECIFIC POPULATIONS-----

- Safety and effectiveness of Fluzone has not been established in pregnant women. (8.1).
- Antibody responses to Fluzone are lower in persons ≥65 years of age than in younger adults. (8.5)

See 17 PATIENT COUNSELING INFORMATION and FDA - approved patient labeling.

Revised: May 2012

FULL PRESCRIBING INFORMATION: CONTENTS*

- 1 INDICATIONS AND USAGE
- 2 DOSAGE AND ADMINISTRATION
 - 2.1 Dose and Schedule
 - 2.2 Administration
- 3 DOSAGE FORMS AND STRENGTHS
- 4 CONTRAINDICATIONS
- 5 WARNINGS AND PRECAUTIONS
 - 5.1 Guillain-Barré Syndrome
 - 5.2 Preventing and Managing Allergic Reactions
 - 5.3 Altered Immunocompetence
 - 5.4 Limitations of Vaccine Effectiveness
- 6 ADVERSE REACTIONS
 - 6.1 Clinical Trials Experience
 - 6.2 Post-Marketing Experience
- 7 DRUG INTERACTIONS

8 USE IN SPECIFIC POPULATIONS

- 8.1 Pregnancy
- 8.3 Nursing Mothers
- 8.4 Pediatric Use
- 8.5 Geriatric Use
- 11 DESCRIPTION
- 12 CLINICAL PHARMACOLOGY
 - 12.1 Mechanism of Action
- 13 NON-CLINICAL TOXICOLOGY
 - 13.1 Carcinogenesis, Mutagenesis, Impairment of Fertility

14 CLINICAL STUDIES

- 14.1 Immunogenicity of Fluzone in Children 6 Months through 8 Years of Age
- 14.2 Immunogenicity of Fluzone in Adults
- 14.3 Immunogenicity of Fluzone in Geriatric Adults
- 15 REFERENCES

16 HOW SUPPLIED/STORAGE AND HANDLING

- 16.1 How Supplied
- 16.2 Storage and Handling

17 PATIENT COUNSELING INFORMATION

*Sections or subsections omitted from the full prescribing information are not listed.

[&]quot;-" indicates information is not applicable

5

7

10

FULL PRESCRIBING INFORMATION:

2 1 INDICATIONS AND USAGE

- 3 Fluzone® is an inactivated influenza virus vaccine indicated for active immunization against
- 4 influenza disease caused by influenza virus subtypes A and type B contained in the vaccine.
- 6 Fluzone is approved for use in persons 6 months of age and older.

8 2 DOSAGE AND ADMINISTRATION

9 • For intramuscular use only

2.1 Dose and Schedule

11 The dose and schedule for Fluzone is presented in Table 1.

12 Table 1: Fluzone

Age	Dose	Schedule
6 months through 35 months	One or two doses ^a , 0.25 mL each	If 2 doses, administer at least
		1 month apart
36 months through 8 years	One or two doses ^a , 0.5 mL each	If 2 doses, administer at least
		1 month apart
9 years and older	One dose, 0.5 mL	-

^a1 or 2 doses depends on vaccination history as per Advisory Committee on Immunization Practices annual recommendations on prevention and control of influenza with vaccines.

2.2 Administration

- 18 Inspect Fluzone visually for particulate matter and/or discoloration prior to administration. If
- either of these conditions exist, the vaccine should not be administered.

20

13

14

15

16

[&]quot;-" indicates information is not applicable

- 1 Before administering a dose of vaccine, shake the prefilled syringe or single-dose or multi-dose
- 2 vial. Withdraw a single dose of vaccine using a sterile needle and syringe. Use a separate sterile
- 3 needle and syringe for each dose withdrawn from the multi-dose vial.

- 5 The preferred sites for intramuscular injection are the anterolateral aspect of the thigh in infants 6
- 6 months through 11 months of age, the anterolateral aspect of the thigh (or the deltoid muscle if
- 7 muscle mass is adequate) in persons \geq 12 months through 35 months of age, or the deltoid muscle
- 8 in persons \geq 36 months of age. The vaccine should not be injected into the gluteal area or areas
- 9 where there may be a major nerve trunk.

10

11 Do not administer this product intravenously or subcutaneously.

12

13 Fluzone vaccine should not be combined through reconstitution or mixed with any other vaccine.

14

15

3 DOSAGE FORMS AND STRENGTHS

16 Fluzone is a suspension for injection.

- 18 Fluzone is supplied in 4 presentations:
- 1) Prefilled syringe (pink syringe plunger rod), 0.25 mL, for persons 6 months through 35 months
- of age.
- 21 2) Prefilled syringe (clear syringe plunger rod), 0.5 mL, for persons 36 months of age and older.
- 22 3) Single-dose vial, 0.5 mL, for persons 36 months of age and older.
- 4) Multi-dose vial, 5 mL, for persons 6 months of age and older.

1	
2	4 CONTRAINDICATIONS
3	A severe allergic reaction (e.g., anaphylaxis) to any component of the vaccine [see <i>Description</i>
4	(11)], including egg protein, or to a previous dose of any influenza vaccine is a contraindication to
5	administration of Fluzone.
6	
7	5 WARNINGS AND PRECAUTIONS
8	5.1 Guillain-Barré Syndrome
9	The 1976 swine influenza vaccine was associated with an elevated risk of Guillain-Barré
10	syndrome (GBS). Evidence for a causal relation of GBS with other influenza vaccines is
11	inconclusive; if an excess risk exists, it is probably slightly more than 1 additional case per 1
12	million persons vaccinated (1). If GBS has occurred within 6 weeks of previous influenza
13	vaccination, the decision to give Fluzone should be based on careful consideration of the potential
14	benefits and risks.
15	
16	5.2 Preventing and Managing Allergic Reactions
17	Appropriate medical treatment and supervision must be available to manage possible anaphylactic
18	reactions following administration of the vaccine.
19	
20	5.3 Altered Immunocompetence
21	If Fluzone is administered to immunocompromised persons, including those receiving
22	immunosuppressive therapy, the expected immune response may not be obtained.
23	

1 **5.4 Limitations of Vaccine Effectiveness** Vaccination with Fluzone may not protect all recipients. 2 3 6 **ADVERSE REACTIONS** 4 5 6.1 Clinical Trials Experience 6 Because clinical trials are conducted under widely varying conditions, adverse event rates 7 observed in the clinical trials of a vaccine cannot be directly compared to rates in the clinical trial 8 of another vaccine, and may not reflect the rates observed in practice. 9 10 Children 6 Months through 8 Years of Age 11 In a multi-center study conducted in the US, children 6 months through 35 months of age received 12 two 0.25 mL doses of Fluzone, and children 3 years through 8 years of age received two 0.5 mL 13 doses of Fluzone, irrespective of previous influenza vaccination history. The two doses (year 14 2006-2007 formulation) were administered 26 to 30 days apart. The safety analysis set included 15 97 children 6 months through 35 months of age and 163 children 3 years through 8 years of age. 16 Table 2 and Table 3 summarize solicited injection site reactions and systemic adverse events 17 reported within 7 days post-vaccination via diary cards.

1 Table 2: Frequency of Solicited Injection Site Reactions and Systemic Adverse Events

2 Within 7 Days After Vaccination with Fluzone, Children 6 Through 35 Months of Age

	Dose 1 (N ^a =90-92) Percentage		Dose 2 (N ^a =86-87) Percentage			
	Any	Moderate ^b	Severec	Any	Moderate ^b	Severe ^c
Injection-Site Tenderness	47.3	8.8	0.0	56.3	3.4	1.1
Injection-Site Erythema	29.3	0.0	0.0	32.2	1.1	0.0
Injection-Site Swelling	16.7	0.0	0.0	14.9	0.0	0.0
Injection-Site Induration	14.4	0.0	0.0	16.1	0.0	0.0
Injection-Site Ecchymosis	14.4	1.1	0.0	14.9	2.3	0.0
Fever ^d	11.0	4.4	0.0	10.3	3.4	1.1
Vomiting	6.6	1.1	0.0	8.1	5.8	0.0
Crying Abnormal	31.9	11.0	0.0	18.6	7.0	2.3
Drowsiness	26.4	1.1	0.0	26.7	4.7	0.0
Appetite Lost	23.1	8.8	0.0	19.8	5.8	1.2
Irritability	42.9	19.8	1.1	34.9	17.4	4.7

³ and is the number of vaccinated subjects with available data for the events listed.

- 4 b Moderate Injection-site tenderness: cries and protests when injection site is touched; Injection-site erythema,
- 5 Injection-site swelling, Injection-site induration, and Injection-site ecchymosis: \geq 2.5 cm to \leq 5 cm; Fever: \geq 101.3°F
 - to ≤103.1°F; Vomiting: 2 to 5 episodes per 24 hours; Crying abnormal: 1 to 3 hours; Drowsiness: not interested in
- 7 surroundings or did not wake up for a meal; Appetite lost: missed 1 or 2 feeds completely; Irritability: requiring
- 8 increased attention

- 9 ° Severe Injection-site tenderness: cries when injected limb is moved or the movement of the injected limb is
- reduced; Injection-site erythema, Injection-site swelling, Injection-site induration, and Injection-site ecchymosis: ≥5
- 11 cm; Fever: >103.1°F; Vomiting: ≥6 episodes per 24 hours or requiring parenteral hydration; Crying abnormal: >3
- hours; Drowsiness: sleeping most of the time or difficulty to wake up; Appetite lost: refuses ≥3 feeds or refuses
- most feeds; Irritability: inconsolable

- 1 d Fever Any Fever indicates ≥100.4°F. The percentage of temperature measurements that were taken by rectal,
- 2 axillary, or oral routes, or not recorded were 69.2%, 17.6%, 13.2%, and 0.0%, respectively for Dose 1; and 69.0%,
- 3 13.8%, 16.1%, and 1.1%, respectively for Dose 2

4 Table 3: Frequency of Solicited Injection Site Reactions and Systemic Adverse Events

5 Within 7 Days After Vaccination with Fluzone, Children 3 Through 8 Years of Age

	Dose 1 (N ^a =150-151) Percentage		Dose 2 (N ^a =144-145) Percentage			
	Any	Any Moderate ^b Severe ^c		Any	Moderate ^b	Severe ^c
Injection-Site Pain	59.3	8.0	0.0	62.1	9.7	0.7
Injection-Site Erythema	27.8	3.3	0.7	27.6	2.1	0.7
Injection-Site Swelling	19.9	5.3	0.0	14.5	2.8	0.0
Injection-Site Induration	16.6	2.0	0.0	11.7	1.4	0.0
Injection-Site Ecchymosis	12.6	0.7	0.7	15.2	0.7	0.0
Injection-Site Pruritus	7.3	-	-	13.2	-	-
Fever ^d	11.9	2.6	2.0	9.7	1.4	1.4
Headache	16.7	2.0	0.7	11.8	1.4	1.4
Malaise	20.0	2.7	1.3	14.6	4.2	0.7
Myalgia	28.0	5.3	0.0	17.4	4.2	0.0

- 6 aN is the number of vaccinated subjects with available data for the events listed.
- 7 b Moderate Injection-site pain: sufficiently discomforting to interfere with normal behavior or activities; Injection-
- 8 site erythema, Injection-site swelling, Injection-site induration, and Injection-site ecchymosis: ≥2.5 cm to <5 cm;
- 9 Fever: >100.4°F to ≤102.2°F; Headache, Malaise, and Myalgia: interferes with daily activities
- 10 ° Severe Injection-site pain: incapacitating, unable to perform usual activities, may have/or required medical care or
- absenteesim; Injection-site erythema, Injection-site swelling, Injection-site induration, and Injection-site
- 12 ecchymosis: ≥5 cm; Fever: >102.2°F; Headache, Malaise, and Myalgia: prevents daily activities
- d Fever Any Fever indicates ≥99.5°F. The percentage of temperature measurements that were taken by oral or
- axillary routes, or not recorded were 93.4%, 6.6%, and 0.0%, respectively for Dose 1; and 93.1%, 6.2%, and 0.7%,
- respectively for Dose 2

"-" indicates information was not collected

2

1

- 3 During the period from the first vaccination through 6 months following the second vaccination,
- 4 there were no serious adverse events considered to be caused by vaccination and no deaths
- 5 reported in this study.

6

7

Adults

- 8 Adults 18 through 64 years of age received Fluzone (year 2008-2009 formulation) in a multi-
- 9 center trial conducted in the US. The safety analysis set included 1421 Fluzone recipients. Table 4
- summarizes solicited injection-site reactions and systemic adverse events reported within 7 days
- post-vaccination via diary cards.

12 Table 4: Frequency of Solicited Injection-Site Reactions and Systemic Adverse Events

13 Within 7 Days After Vaccination with Fluzone, Adults 18 Through 64 Years of Age

	(N ^a =1392-1394) Percentage		
	Any	Grade 2 ^b	Grade 3 ^c
Injection-Site Erythema	13.2	2.1	0.9
Injection-Site Induration	10.0	2.3	0.5
Injection-Site Swelling	8.4	2.1	0.9
Injection-Site Pain	53.7	5.8	0.8
Injection-Site Pruritus	9.3	0.4	0.0
Injection-Site Ecchymosis	6.2	1.1	0.4
Headache	30.3	6.5	1.6
Myalgia	30.8	5.5	1.4
Malaise	22.2	5.5	1.8
Shivering	6.2	1.1	0.6
Fever ^d	2.6	0.4	0.2

1 ^aN is the number of vaccinated subjects with available data for the events listed. 2 ^b Grade 2 - Injection-site erythema, Injection-site induration, Injection-site swelling, and Injection-site ecchymosis: \geq 3 2.5 cm to <5 cm; Injection-site pain and Injection-site pruritus: sufficiently discomforting to interfere with normal 4 behavior or activities; Fever: >100.4°F to ≤102.2°F; Headache, Myalgia, Malaise, and Shivering: interferes with 5 daily activities 6 ^c Grade 3 - Injection-site erythema, Injection-site induration, Injection-site swelling, and Injection-site ecchymosis: ≥5 7 cm; Injection-site pain: incapacitating, unable to perform usual activities; Injection-site pruritus: incapacitating, 8 unable to perform usual activities, may have/or required medical care or absenteeism; Fever: >102.2°F; Headache, 9 Myalgia, Malaise, and Shivering: prevents daily activities ^d Fever - Any Fever indicates ≥99.5°F. The percentage of temperature measurements that were taken by oral or 10 11 axillary routes, or not recorded were 99.6%, 0.0%, and 0.4%, respectively 12 13 Within 28 days and six months post-vaccination, a serious adverse event was reported by 5 (0.4%) 14 and 20 (1.4%) Fluzone recipients, respectively. No serious adverse event was considered to be 15 caused by vaccination. No deaths were reported during the 6 months post-vaccination. 16 17 **Geriatric Adults** 18 Adults 65 years of age and older received Fluzone (year 2006-2007 formulation) in a multi-19 center, double-blind trial conducted in the US. The safety analysis set included 1260 Fluzone 20 recipients. 21 22 Table 5 summarizes solicited injection-site reactions and systemic adverse events reported within 23 7 days post-vaccination via diary cards. Onset was usually within the first 3 days after vaccination 24 and a majority of the reactions resolved within 3 days.

1 Table 5: Frequency of Solicited Injection-Site Reactions and Systemic Adverse Events

2 Within 7 Days After Vaccination with Fluzone, Adults 65 Years of Age and Older

		N ^a =1258-1260 Percentage		
	Any	Moderate ^b	Severe ^c	
Injection-Site Pain	24.3	1.7	0.2	
Injection-Site Erythema	10.8	0.8	0.6	
Injection-Site Swelling	5.8	1.3	0.6	
Myalgia	18.3	3.2	0.2	
Malaise	14.0	3.7	0.6	
Headache	14.4	2.5	0.3	
Fever ^d	2.3	0.2	0.1	

³ aN is the number of vaccinated subjects with available data for the events listed

- 4 bModerate Injection-site pain: sufficiently discomforting to interfere with normal behavior or activities; Injection-
- 5 site erythema and Injection-site swelling: ≥2.5 cm to <5 cm; Fever: >100.4°F to ≤102.2°F; Myalgia, Malaise, and
- 6 Headache: interferes with daily activities
- 7 Severe Injection-site pain; incapacitating, unable to perform usual activities; Injection-site erythema and Injection-
- 8 site swelling: \geq 5 cm; Fever: \geq 102.2°F; Myalgia, Malaise, and Headache: prevents daily activities
- d Fever –Any Fever indicates \geq 99.5°F. The percentage of temperature measurements that were taken by oral route or
- not recorded were 98.6% and 1.4%, respectively

11

12

- Within 6 months post-vaccination, 93 (7.4%) Fluzone recipients experienced a serious adverse
- event (N=1260). No deaths were reported within 28 days post-vaccination. A total of 7 deaths
- were reported during the period Day 29-180 post-vaccination: 7 (0.6%) among Fluzone recipients
- 15 (N=1260). The majority of these participants had a medical history of cardiac, hepatic, neoplastic,
- renal, and/or respiratory diseases. No deaths were considered to be caused by vaccination.

6.2 Post-Marketing Experience

- 2 The following events have been spontaneously reported during the post-approval use of Fluzone.
- 3 Because these events are reported voluntarily from a population of uncertain size, it is not always
- 4 possible to reliably estimate their frequency or establish a causal relationship to vaccine exposure.
- 5 Adverse events were included based on one or more of the following factors: severity, frequency
- 6 of reporting, or strength of evidence for a causal relationship to Fluzone.

7

- 8 Blood and Lymphatic System Disorders: Thrombocytopenia, lymphadenopathy
- Immune System Disorders: Anaphylaxis, other allergic/hypersensitivity reactions (including
- 10 urticaria, angioedema)
- Eye disorders: Ocular hyperemia
- Nervous System Disorders: Guillain-Barré syndrome (GBS), convulsions, febrile
- convulsions, myelitis (including encephalomyelitis and transverse myelitis), facial palsy
- 14 (Bell's palsy), optic neuritis/neuropathy, brachial neuritis, syncope (shortly after vaccination),
- dizziness, paresthesia
- Vascular Disorders: Vasculitis, vasodilatation/flushing
- Respiratory, Thoracic and Mediastinal Disorders: Dyspnea, pharyngitis, rhinitis, cough,
- wheezing, throat tightness
- Skin and Subcutaneous Tissue Disorders: Stevens-Johnson syndrome
- General Disorders and Administration Site Conditions: Pruritus, asthenia/fatigue, pain in
- 21 extremities, chest pain
- Gastrointestinal Disorders: Vomiting

1	
2	7 DRUG INTERACTIONS
3	Data evaluating the concomitant administration of Fluzone with other vaccines are not available.
4	
5	8 USE IN SPECIFIC POPULATIONS
6	8.1 Pregnancy
7	Pregnancy Category C: Animal reproduction studies have not been conducted with Fluzone. It is
8	also not known whether Fluzone can cause fetal harm when administered to a pregnant woman or
9	can affect reproduction capacity. Fluzone should be given to a pregnant woman only if clearly
10	needed.
11	
12	8.3 Nursing Mothers
13	It is not known whether Fluzone is excreted in human milk. Because many drugs are excreted in
14	human milk, caution should be exercised when Fluzone is administered to a nursing woman.
15	
16	8.4 Pediatric Use
17	Safety and effectiveness of Fluzone in children below the age of 6 months have not been
18	established. Safety and immunogenicity of Fluzone was evaluated in children 6 months through 8
19	years of age. [See Adverse Reactions (6.1) and Clinical Studies (14.1).]
20	
21	8.5 Geriatric Use

1 Safety and immunogenicity of Fluzone was evaluated in adults 65 years of age and older. See 2 Adverse Reactions (6.1) and Clinical Studies (14.3).] Antibody responses to Fluzone are lower in 3 persons \geq 65 years of age than in younger adults. 4 11 DESCRIPTION 5 6 Fluzone (Influenza Virus Vaccine) for intramuscular injection, is an inactivated influenza virus 7 vaccine, prepared from influenza viruses propagated in embryonated chicken eggs. The virus-8 containing allantoic fluid is harvested and inactivated with formaldehyde. Influenza virus is 9 concentrated and purified in a linear sucrose density gradient solution using a continuous flow 10 centrifuge. The virus is then chemically disrupted using a non-ionic surfactant, Octylphenol Ethoxylate (Triton® X-100), producing a "split virus". The split virus is further purified and then 11 12 suspended in sodium phosphate-buffered isotonic sodium chloride solution. 13 14 Fluzone suspension for injection is clear and slightly opalescent in color. 15 16 Antibiotics are not used in the manufacture of Fluzone. 17 18 No presentation of Fluzone contains latex. 19 20 Fluzone is standardized according to United States Public Health Service requirements and is 21 formulated to contain HA of each of the following three influenza strains recommended for the 22 2012-2013 influenza season: A/California/07/2009 NYMC X-179A (H1N1), A/Victoria/361/2011

- 1 IVR-165 (H3N2) and B/Texas/6/2011 (a B/Wisconsin/1/2010-like virus). The amounts of HA and
- 2 other ingredients per dose of vaccine are listed in Table 6.

3 Table 6: Fluzone Ingredients

Ingredient	Quantity (per dose)		
	Fluzone 0.25 mL Dose	Fluzone 0.5 mL Dose	
Active Substance: Split influenza virus, inactivated strains ^a :	22.5 mcg HA total	45 mcg HA total	
A (H1N1)	7.5 mcg HA	15 mcg HA	
A (H3N2)	7.5 mcg HA	15 mcg HA	
В	7.5 mcg HA	15 mcg HA	
Other:			
Sodium phosphate-buffered isotonic sodium chloride solution	QS ^b to appropriate volume	QS ^b to appropriate volume	
Formaldehyde	≤50 mcg	≤100 mcg	
Octylphenol Ethoxylate	≤75 mcg	≤150 mcg	
Gelatin	0.05%	0.05%	
Preservative			
Single-Dose Presentations	None	None	
Multi-Dose Presentation (Thimerosal)	N/A	25 mcg mercury	

- 4 aper United States Public Health Service (USPHS) requirement
- 5 ^bQuantity Sufficient
- 6 N/A not applicable

7

8

12 CLINICAL PHARMACOLOGY

- 9 12.1 Mechanism of Action
- 10 Influenza illness and its complications follow infection with influenza viruses. Global surveillance
- of influenza identifies yearly antigenic variants. For example, since 1977, antigenic variants of
- influenza A (H1N1 and H3N2) viruses and influenza B viruses have been in global circulation.

1 Specific levels of hemagglutination inhibition (HI) antibody titer post-vaccination with inactivated influenza virus vaccines have not been correlated with protection from influenza virus 2 3 infection. In some human studies, antibody titers ≥1:40 have been associated with protection from 4 influenza illness in up to 50% of subjects. (2) (3) 5 6 Antibodies against one influenza virus type or subtype confer limited or no protection against 7 another. Furthermore, antibodies to one antigenic variant of influenza virus might not protect 8 against a new antigenic variant of the same type or subtype. Frequent development of antigenic 9 variants through antigenic drift is the virologic basis for seasonal epidemics and the reason for the 10 usual change of one or more new strains in each year's influenza vaccine. Therefore, influenza 11 vaccines are standardized to contain the hemagglutinins of influenza virus strains, representing the 12 influenza viruses likely to be circulating in the US in the upcoming winter. 13 14 Annual vaccination with the current vaccine is recommended because immunity during the year 15 after vaccination declines, and because circulating strains of influenza virus change from year to 16 year. 17 13 NON-CLINICAL TOXICOLOGY 18 19 13.1 Carcinogenesis, Mutagenesis, Impairment of Fertility 20 Fluzone has not been evaluated for carcinogenic or mutagenic potential, or for impairment of 21 fertility. 22 **CLINICAL STUDIES** 14 23

1 14.1 Immunogenicity of Fluzone in Children 6 Months through 2 8 Years of Age 3 In a multi-center study conducted in the US, 68 children 6 months through 35 months of age 4 given two 0.25 mL doses of Fluzone and 120 children 3 years through 8 years of age given two 5 0.5 mL doses of Fluzone were included in the per-protocol analysis set. The two doses (year 2006-2007 formulation) were administered 26 to 30 days apart. Females accounted for 42.6% of 6 7 the participants in the 6 months through 35 months age group and 53.3% of the participants in the 8 3 years through 8 years age group. Most participants in the 6 months through 35 months and 3 9 years through 8 years age groups, respectively, were Caucasian (70.6% and 79.2%), followed by 10 Hispanic (19.1% and 13.3%), and Black (7.4% and 4.2%). 11 12 The percentage of participants who received influenza vaccination during the previous influenza 13 season was 54.4% for the 6 months through 35 months age group and 27.5% for the 3 years 14 through 8 years age group. Table 7 shows seroconversion rates and the percentage of participants 15 with an HI titer ≥1:40 pre-vaccination and one month following the second dose of Fluzone. 16

- 1 Table 7: Percentage (%) with Pre and Post-Vaccination HI Titers ≥1:40 and Seroconversion
- 2 Following the Second Vaccine Injection with Fluzone^a in Children 6 Months Through 35
- 3 Months and 3 Years Through 8 Years of Age

Antigen	Age Group	Pre-Vaccination Titer ≥1:40 % (95% CI)	Post-Vaccination ^b Titer ≥1:40 % (95% CI)	Seroconversion ^c % (95% CI)
		N=68 (6 to 35 i	months); N=120 (3 th	rough 8 years)
A (H1N1)	6 through 35 months	11.8 (5.2; 21.9)	92.6 (83.7; 97.6)	88.2 (78.1; 94.8)
	3 through 8 years	40.0 (31.2; 49.3)	99.2 (95.4; 100.0)	78.3 (69.9; 85.3)
A (H3N2)	6 through 35 months	29.4 (19.0; 41.7)	100.0 (94.7; 100.0)	91.2 (81.8; 96.7)
	3 through 8 years	80.0 (71.7; 86.7)	100.0 (97.0; 100.0)	61.7 (52.4; 70.4)
В	6 through 35 months	1.5 (0.0; 7.9)	20.6 (11.7; 32.1)	20.6 (11.7; 32.1)
	3 through 8 years	3.3 (0.9; 8.3)	58.3 (49.0; 67.3)	53.3 (44.0; 62.5)

- 4 a Children received two doses of Fluzone administered 26 to 30 days apart, irrespective of previous influenza
- 5 vaccination history

10

- 6 ^bPost-vaccination HI titers drawn at 28 days post-dose
- 7 °Seroconversion: Paired samples with pre-vaccination HI titer <1:10 and post-vaccination (28 days post-dose 2) titer
- ≥ 1.40 or a minimum 4-fold increase for participants with pre-vaccination titer ≥ 1.10

14.2 Immunogenicity of Fluzone in Adults

- Adults 18 through 64 years of age received Fluzone (year 2008-2009 formulation) in a multi-
- center trial conducted in the US. For immunogenicity analyses, there were 1287 participants who
- received Fluzone in the per-protocol analysis set. There were fewer males (35.8%) than females.
- The mean age was 42.6 years (ranged from 18.2 through 65.0 years). Most participants were
- 15 Caucasian (80.0%), followed by Hispanic (11.0%), and Black (6.3%). Table 8 shows

10

12

- seroconversion rates at 28 days following vaccination and the percentage of participants with an
- 2 HI titer ≥1:40 prior to vaccination and 28 days following vaccination.

4 Table 8: Percentage (%) with Pre and Post-Vaccination HI Titers ≥1:40 and Seroconversion

5 in Adult Fluzone Recipients 18 through 64 Years of Age

Antigen	Pre-Vaccination Titer ≥1:40 % (95% CI) N ^c =1285-1286	Post-Vaccination ^a Titer ≥1:40 % (95% CI) N ^c =1283-1285	Seroconversion ^b % (95% CI) N ^c =1283-1285
A (H1N1)	39.1 (36.4;41.8)	91.7 (90.0;93.1)	60.5 (57.7;63.2)
A (H3N2)	33.6 (31.0; 36.2)	91.4 (89.8;92.9)	74.8 (72.3;77.1)
В	41.2 (38.5;44.0)	89.3 (87.4;90.9)	54.2 (51.4;56.9)

^{6 &}lt;sup>a</sup> Post-vaccination HI titers drawn at 28 days post-dose

11 14.3 Immunogenicity of Fluzone in Geriatric Adults

- Adults 65 years of age and older received Fluzone (year 2006-2007 formulation) in a multi-center
- trial conducted in the US. For immunogenicity analyses, there were 1,275 participants who
- received Fluzone in the immunogenicity analysis set. Females accounted for 54.7% of
- participants. The mean age was 72.9 years (ranged from 65 through 94 years of age); 36% of
- participants were 75 years of age or older. Most participants were Caucasian (92.9%), followed by
- Hispanic (3.7%), and Black (2.7%). Table 9 shows seroconversion rates at 28 days following

⁷ b Seroconversion: Paired samples with pre-vaccination HI titer <1:10 and post-vaccination (28 days post-dose) titer

 $^{8 \}ge 1:40$ or a minimum 4-fold increase for participants with pre-vaccination titer $\ge 1:10$

^{9 °}N is the number of vaccinated subjects with available data for the immunologic endpoint listed

- 1 vaccination and the percentage of participants with an HI titer ≥1:40 prior to vaccination and 28
- 2 days following vaccination.

- 4 Table 9: Percentage (%) with Pre and Post-Vaccination HI Titers ≥1:40 and Seroconversion
- 5 in Adult Fluzone Recipients 65 Years of Age and Older

Antigen	Pre-Vaccination HI Titer ≥1:40%(95% CI) N ^c =1267-1268	Post-Vaccination ^a Titer ≥1:40 %(95% CI) N ^c =1252	Seroconversion ^b %(95% CI) N ^c =1248-1249
A (H1N1)	45.9 (43.2;48.7)	76.8 (74.3;79.1)	23.1 (20.8;25.6)
A (H3N2)	68.6 (66.0;71.2)	96.5 (95.3;97.4)	50.7 (47.9;53.5)
В	27.3 (24.9;29.9)	67.6 (64.9;70.2)	29.9 (27.4;32.6)

^{6 &}lt;sup>a</sup> Post-vaccination HI titers drawn at 28 days post-dose

- 8 \geq 1:40 or a minimum 4-fold increase for participants with pre-vaccination titer \geq 1:10
- 9 °N is the number of vaccinated subjects with available data for the immunologic endpoint listed
- 10

⁷ b Seroconversion: Paired samples with pre-vaccination HI titer <1:10 and post-vaccination (28 days post-dose) titer

15 REFERENCES 1 2 3 Lasky T, Terracciano GJ, Magder L, et al. The Guillain-Barre' syndrome and the 1992-1993 1 4 and 1993-1994 influenza vaccines. N Engl J Med 1998;339(25):1797-802. 5 2 Hannoun C, Megas F, Piercy J. Immunogenicity and protective efficacy of influenza 6 vaccination. Virus Res 2004;103:133-138. 7 3 Hobson D, Curry RL, Beare AS, Ward-Gardner A. The role of serum haemagglutination-8 inhibiting antibody in protection against challenge infection with influenza A2 and B 9 viruses. J Hyg Camb 1972;767-777. 10 11 12

17

16 HOW SUPPLIED/STORAGE AND HANDLING 1 2 16.1 How Supplied 3 Single-dose, prefilled syringe, without needle, 0.25 mL, package of 10 (does not contain latex) – 4 NDC 49281-112-25. 5 6 Single-dose, prefilled syringe, without needle, 0.5 mL, package of 10 (does not contain latex) – 7 NDC 49281-012-50. 8 9 Single-dose vial, 0.5 mL, package of 10 (does not contain latex) – NDC 49281-012-10. 10 11 Multi-dose vial, 5 mL, package of one (does not contain latex). The vial contains ten 0.5 mL 12 doses – NDC 49281-390-15. 13 14 16.2 Storage and Handling Store all Fluzone presentations refrigerated at 2° to 8°C (35° to 46°F). DO NOT FREEZE. 15 16 Discard if vaccine has been frozen. 17 Between uses, return the multi-dose vial to the recommended storage conditions at 2° to 8°C (35° 18 19 to 46°F). 20 21 Do not use after the expiration date shown on the label. 22 PATIENT COUNSELING INFORMATION

- 1 See FDA-approved patient labeling (Patient Information).
- Inform the patient or guardian that Fluzone contains killed viruses and cannot cause influenza.
- Fluzone stimulates the immune system to produce antibodies that help protect against
- 4 influenza, but does not prevent other respiratory infections.
- Annual influenza vaccination is recommended.
- Instruct vaccine recipients and guardians to report adverse reactions to their healthcare
- 7 provider and/or to the Vaccine Adverse Event Reporting System (VAERS).
- 9 Fluzone is a registered trademark of Sanofi Pasteur Inc.
- 11 Manufactured by:
- 12 Sanofi Pasteur Inc.
- 13 Swiftwater PA 18370 USA

8

1	Patient Information Sheet
2	Fluzone®
3	Influenza Virus Vaccine
5 6 7 8	Please read this information sheet before getting Fluzone® vaccine. This summary is not intended to take the place of talking with your healthcare provider. If you have questions or would like more information, please talk with your healthcare provider.
9	What is Fluzone vaccine?
10	Fluzone is a vaccine that helps protect against influenza illness (flu).
11	Fluzone vaccine is for people who are 6 months of age and older.
12 13	Vaccination with Fluzone vaccine may not protect all people who receive the vaccine.
14	Who should not get Fluzone vaccine?
15	You should not get Fluzone vaccine if you:
16	• ever had a severe allergic reaction to eggs or egg products.
17	• ever had a severe allergic reaction after getting any flu shot.
18	• are younger than 6 months of age.
19	
20	Tell your healthcare provider if you or your child have or have had:
21	• Guillain-Barré syndrome (severe muscle weakness) after getting a flu shot.
22 23	• problems with your immune system as the immune response may be diminished.
24	How is the Fluzone vaccine given?
25	Fluzone vaccine is a shot given into the muscle of the arm.
26 27	For infants, Fluzone vaccine is a shot given into the muscle of the thigh.

1	What are the possible side effects of Fluzone vaccine?
2	The most common side effects of Fluzone vaccine are:
3	• pain, redness, swelling, bruising and hardness where you got the shot
4	• muscle aches
5	• tiredness
6	• headache
7	• fever
8	
9 10	These are not all of the possible side effects of Fluzone vaccine. You can ask your healthcare provider for a list of other side effects that is available to healthcare professionals.
11	
12 13 14	Call your healthcare provider for advice about any side effects that concern you. You may report side effects to the Vaccine Adverse Event Reporting System (VAERS) at 1-800-822-7967 or http://vaers.hhs.gov .
15	
16	What are the ingredients in Fluzone vaccine?
17	Fluzone vaccine contains 3 killed flu virus strains.
18 19	Inactive ingredients include formaldehyde, octylphenol ethoxylate, and gelatin. The preservative thimerosal is only in the 10 dose (multi-dose) vial of Fluzone vaccine.
20	
21	Manufactured by: Sanofi Pasteur Inc.
22	Swiftwater, PA 18370 USA