

Food Safety and Inspection Service Office of Public Health Science Laboratory QA/QC Division 950 College Station Road Athens, GA 30605

## Laboratory Guidebook Notice of Change

Chapter new, **revised**, or archived: MLG 8A.04

Title: FSIS Procedure for the Use of a *Listeria monocytogenes* Polymerase Chain

Reaction (PCR) Screening Test

Effective Date: 8/3/09

Description and purpose of change(s):

The more accurate term "Primary Enrichment plating" replaced "Direct plating" throughout the chapter.

The methods described in this guidebook are for use by the FSIS laboratories. FSIS does not specifically endorse any of the mentioned test products and acknowledges that equivalent products may be available for laboratory use.

Effective: 5/29/07

Issuing Authority: Laboratory Quality Assurance Division (LQAD)

MLG 8A.04		Page 1 of 4		
Title: FSIS Procedure for the Use of a Listeria monocytogenes Polymerase Chain Reaction (PCR) Screening Test				
Revision: 04	Replaces: 03	Effective: 8/3/09		

#### **Procedure Outline**

- 8A.1 Introduction
- 8A.2 Safety Precautions
- 8A.3 Quality Control Procedures
  - 8A.3.1 Culture Controls
  - 8A.3.2 Sterility Control
- 8A.4 Equipment, Reagents, and Media
- 8A.5 Sample Preparation and Primary Enrichment
- 8A.6 Secondary Enrichment and Primary Enrichment Plating
- 8A.7 The BAX® System for Screening L. monocytogenes Test Procedure
- 8A.8 Cultural Confirmation
- 8A.9 Interpretation of Results
- 8A.10 Completion of Testing if BAX® Unavailable
- 8A.11 Selected References

#### 8A.1 Introduction

This method describes the use of a commercial PCR based screening procedure as described in MLG 8 Section 8.4.5 to screen-test processed meat, poultry, pasteurized liquid egg products and environmental sponge samples for the presence of *Listeria monocytogenes*. All samples identified as presumptively positive for *Listeria monocytogenes* by these tests are subject to cultural confirmation.

### **8A.2** Safety Precautions

CDC guidelines for the handling of BioSafety Level 2 organisms should be followed whenever live cultures of *Listeria monocytogenes* are used. All available Material Safety Data Sheets (MSDS) must be obtained from the manufacturer for the media, chemicals, reagents, and microorganisms used in the analysis. The personnel who will handle the material should read all MSDS sheets, and all MSDS requirements should be followed.

Pregnant women and potentially immunocompromised individuals should be prohibited from laboratory rooms or areas where *L. monocytogenes* isolation or identification procedures are in progress. Although a properly sanitized laboratory area should not harbor *L. monocytogenes* or other pathogens, supervisors should use their own discretion in allowing high-risk individuals into these areas when not in use for these activities.

MLG 8A.04		Page 2 of 4		
Title: FSIS Procedure for the Use of a Listeria monocytogenes Polymerase Chain Reaction (PCR) Screening Test				
Revision: 04	Replaces: 03	Effective: 8/3/09		

### **8A.3** Quality Control Procedures

#### **8A.3.1** Culture Controls

- a. At least one *L. monocytogenes* positive control strain is required. Appropriate cultures include ATCC® 19111, NCTC 7973 or other *L. monocytogenes* cultures validated to perform in an equivalent manner.
- b. At least one *L. innocua* negative control culture is required. Appropriate cultures include *L. innocua* strain ATCC® 33090 or other *L. innocua* strains validated to perform in an equivalent manner.

## **8A.3.2** Sterility Control

Prepare one "blank" (incubated but un-inoculated pre-enrichment/ enrichment broth) to provide a sterility control for the process.

#### 8A.4 Equipment, Reagents, and Media

In addition to equipment, reagents, and media used in analysis of samples as described in MLG 8, the following materials will be needed.

- a. PCR tube holder (Qualicon)
- b. Cell Lysis Tube Cooling Block (Qualicon) held at  $4 \pm 2$ °C
- c. Techne DB-2A Heating block set at  $55 \pm 2^{\circ}$ C
- d. Techne DB-2A Heating block set at  $95 \pm 3$ °C
- e. Eppendorf Repeater Plus Pipettor (or equivalent) set at 200:1 μl, and tips
- f. Corning Lambda 20 Pipettor (or equivalent) set at  $5 \pm 1 \mu l$ , and tips
- g. Corning Lambda 200 Pipettor (or equivalent) set at  $150 \pm 1 \,\mu$ l, and tips
- h. 12 X 75 mm (Falcon 352063, or equivalent) tubes
- i. Cell Lysis Tubes and Caps, Cell Lysis Tube Rack and box (Genemate 8 strip tubes, ISC Bioexpress, T-3120-5)
- j. Pipettor and 5 ml pipettes
- k. BAX® Assay for Screening *L. monocytogenes* (Qualicon # 17710609) held at  $4 \pm 2$ °C
- 1. Morpholinepropanesulfonic acid-buffered *Listeria* enrichment broth (MOPS-BLEB) medium:

MLG 8A.04		Page 3 of 4		
Title: FSIS Procedure for the Use of a Listeria monocytogenes Polymerase Chain Reaction (PCR) Screening Test				
Revision: 04	Replaces: 03	Effective: 8/3/09		

BBL Listeria enrichment broth (BBL #12333, or equivalent) MOPS free acid (Sigma #1254, or equivalent) MOPS sodium salt (Sigma #M9381, or equivalent)

## 8A.5 Sample Preparation and Primary Enrichment

Perform sample preparation and pre-enrichment in as described in MLG 8, Section 8.5.1 and 8.5.2.

### 8A.6 Secondary Enrichment and Primary Enrichment Plating

- a. Transfer  $0.1 \pm 0.02$  ml of the UVM enrichment to  $10 \pm 0.5$  ml of MOPS-BLEB. Incubate inoculated MOPS-BLEB tubes at  $35 \pm 2^{\circ}$ C for 18-24 h.
- b. Streak a MOX plate. Streak a loopful or a drop approximating 0.1 ml of the UVM over the surface of the plate. Alternatively, dip a sterile cotton-tipped applicator or equivalent into the UVM and swab 25-50% of the surface of a MOX plate. Use a loop to streak for isolation from the swabbed area onto the remainder of the plate. Incubate the MOX at  $35 \pm 2^{\circ}$ C for  $26 \pm 2$  h.

# 8A.7 The BAX® System for Screening L. monocytogenes Test Procedure

Follow the current BAX® User's Guide for preparing reagents, performing the test, and reading the results. The equipment must be set up, and operated, and all records must be documented, according to laboratory work instructions.

### **8A.8** Cultural Confirmation

- a. Streak a MOX plate using a loopful of the MOPS-BLEB, or by streaking a drop approximating 0.1 ml or aseptically dip a sterile cotton-tipped applicator or equivalent into the MOPS-BLEB and swab 25-50% of the surface of a MOX plate. Use a loop to streak for isolation from the swabbed area onto the remainder of the plate. Incubate the MOX at  $35 \pm 2^{\circ}$ C for  $26 \pm 2$  h.
- b. Proceed with all isolation and purification procedures as per MLG 8, Sections 8.5.4.a.i, 8.5.6, and 8.6.

MLG 8A.04		Page 4 of 4		
Title: FSIS Procedure for the Use of a Listeria monocytogenes Polymerase Chain Reaction (PCR) Screening Test				
Revision: 04	Replaces: 03	Effective: 8/3/09		

## **8A.9** Interpretation of Results

- Samples that test BAX®-negative will be reported as negative if the concurrent 24h Primary Enrichment Plating is also negative. Cultural analysis will continue on samples that are BAX®-negative but have typical colonies on the 24 h Primary Enrichment Plating MOX plates, or have a BAX®-positive, BAX®-indeterminate or have an invalid result. Or based on the findings of a cause analysis, the laboratory may analyze the indeterminate or invalid result samples by:
  - repeating the BAX® analysis from the rack loading step or
  - preparing new BAX® tubes and repeating the analysis.
- b. In analytical runs where the positive control tests negative, either the reserve samples will be retested or the laboratory shall complete the cultural method by streaking all samples and controls from MOPS-BLEB medium onto MOX plates. Proceed with all isolation and purification procedures as per MLG 8, Sections 8.5.6 and 8.6.

# **8A.10** Completion of Testing if BAX® Unavailable

If circumstances (e.g. a power outage or equipment failure) do not allow testing using the BAX<sup>®</sup> system, the laboratory shall complete the cultural method by streaking all samples and controls from MOPS-BLEB medium onto MOX plates. Proceed with all isolation and purification procedures as per MLG 8, Sections 8.5.6 and 8.6.

### **8A.11 Selected References**

Centers for Disease Control and Prevention and National Institutes of Health (CDC/NIH). 2007. BioSafety in Microbiological and Biomedical Laboratories, 5<sup>th</sup> ed. U.S. Government Printing Office, Washington, D.C. (also found on the internet at:

http://www.cdc.gov/od/ohs/biosfty/bmbl5/bmbl5toc.htm

 $\mathsf{BAX}^{\text{\tiny{\$}}}$  System PCR Automated Detection for Bacterial Screening User Guide, Dupont Qualicon.