

CPSC Fact Sheet

CHILD SAFETY PROTECTION ACT FACT SHEET

- Effective January 1, 1995 products that are manufactured in or imported into the United States on or after that date must comply with the Child Safety Protection Act (CSPA).
- Any ball with a diameter of 1.75 inches (44.4mm) or less that is intended for use by children younger than 3 years of age is banned.
- Any ball with a diameter of 1.75 inches (44.4mm) or less that is intended for use by children 3 years or older must be labeled:

/!\ WARNING:

CHOKING HAZARD-This toy is a small ball. Not for children under 3 yrs.

 Any toy or game intended for children 3 years or older but less than 8 years that contains a small ball shall bear the following cautionary label:

/!\ WARNING:

CHOKING HAZARD-Toy contains a small ball.

Not for children under 3 yrs.

 Toys and games with small parts intended for use by children at least 3 years old but under 6 years must be labeled as follows:

/!\ WARNING:

CHOKING HAZARD - Small parts. Not for children under 3 yrs.

Any latex balloon, or toy or game that contains a latex balloon, shall be labeled as follows:

/!\ WARNING:

CHOKING HAZARD-Children under eight yrs. can choke or suffocate on uninflated or broken balloons.

Adult supervision required.

Keep uninflated balloons from children.
Discard broken balloons at once.

• Any marble intended for children 3 years or older shall be labeled:

/!\ WARNING:

CHOKING HAZARD - This toy is a marble. Not for children under 3 yrs.

Any toys and games intended for children at least 3 years old but less than 8 years which contain a marble shall be labeled:

/!\ WARNING:

CHOKING HAZARD - Toy contains a marble. Not for children under 3 yrs.

Publication 282