# Composition of Foods Raw, Processed, Prepared USDA National Nutrient Database for Standard Reference, Release 25

September 2012

U.S. Department of Agriculture Agricultural Research Service Beltsville Human Nutrition Research Center Nutrient Data Laboratory 10300 Baltimore Avenue Building 005, Room 107, BARC-West Beltsville, Maryland 20705

## **Suggested Citation:**

U.S. Department of Agriculture, Agricultural Research Service. 2012. USDA National Nutrient Database for Standard Reference, Release 25. Nutrient Data Laboratory Home Page, <a href="http://www.ars.usda.gov/ba/bhnrc/ndl">http://www.ars.usda.gov/ba/bhnrc/ndl</a>

### **Disclaimers:**

Mention of trade names, commercial products, or companies in this publication is solely for the purpose of providing specific information and does not imply recommendation or endorsement by the U.S. Department of Agriculture over others not mentioned.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410, or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Issued September 2012

The USDA National Nutrient Database for Standard Reference, Release 25 was prepared by the following staff members of the Nutrient Data Laboratory, Beltsville Human Nutrition Research Center, Agricultural Research Service, U.S. Department of Agriculture:

Coordinator David B. Haytowitz Senior Scientists Jaspreet K.C. Ahuja

Jacob Exler

David B. Haytowitz Pamela R. Pehrsson

Janet Roseland

Scientists Mona Khan

Melissa Nickle Kris Patterson Bethany Showell Robin Thomas Juhi Williams

Research Leader Paul Cotton (Acting)

Joanne Holden (Ret.)

IT Support Kim Klingenstein

Cevon McLean

Administrative Support Carole Miller

**Acknowledgements:** The authors gratefully acknowledge the constructive contributions of the peer reviewers: Carol J. Boushey, University of Hawaii Cancer Center and Diane C. Mitchell, Department of Nutritional Sciences, Pennsylvania State University.

## Contents

Introduction	
Specific Changes for SR25	1
Database Reports	4
Database Content	4
Food Descriptions	4
Food Group	5
LanguaL	6
Nutrients	
Nutrient Retention and Food Yield	
Proximates	11
Minerals	13
Vitamins	
Lipid Components	
Amino Acids	
Weights and Measures	
Sources of Data	
Explanation of File Formats	
Relational Files	
Food Description File	
Food Group Description File	
LanguaL Factor	
LanguaL Factors Description File	
Nutrient Data File	
Nutrient Definition File	
Source Code File	
Data Derivation Code Description File	
Weight File	
Footnote File	
Sources of Data Link File	
Sources of Data File	
Abbreviated File	
Update Files	
Summary	
References Cited in the Documentation	42

## **Contents (Continued)**

Notes on Foods	49
Introduction	
National Food and Nutrient Analysis Program	
Identify Key Foods and critical nutrients for sampling and analysis	
Evaluate existing data for scientific quality	
Devise and implement a probability-based sampling survey of U.S. foods	
Analyze sampled foods under USDA-supervised laboratory contracts	
Compile newly generated data to update the National Nutrient Databank	
Beef Products (Food Group 13)	
Breakfast Cereals (Food Group 08)	
Cereal Grains and Pasta (Food Group 20)	
Eggs (Food Group 01)	
Legumes and Legume Products (Food Group 16)	
Nut and Seed Products (Food Group 12)	
Pork Products (Food Group 10)	
Poultry Products (Food Group 05)	
Vegetable and Vegetable Products (Food Group 11)	
Appendix A. Abbreviations Used in Short Descriptions	
Appendix B. Other Abbreviations	

### Introduction

The USDA National Nutrient Database for Standard Reference (SR) is the major source of food composition data in the United States. It provides the foundation for most food composition databases in the public and private sectors. As information is updated, new versions of the database are released. This version, Release 25 (SR25), contains data on 8,194 food items and up to 146 food components. It replaces SR24 issued in September 2011.

Updated data have been published electronically on the USDA Nutrient Data Laboratory (NDL) web site since 1992. SR25 includes composition data for all the food groups and nutrients published in the 21 volumes of "Agriculture Handbook 8" (U.S. Department of Agriculture 1976-92), and its four supplements (U.S. Department of Agriculture 1990-93), which superseded the 1963 edition (Watt and Merrill, 1963). SR25 supersedes all previous releases, including the printed versions, in the event of any differences.

In July 2001, when NDL converted to a new version of its Nutrient Databank System (NDBS), formats were changed and fields added to improve the descriptive information for food items and the statistical information about the nutrient values. While data in previous releases have been moved to the new NDBS, they may not have been updated through the complete system. Therefore, many of these new fields contain data only for those items that have been processed through the new NDBS and it will take a number of years before they are populated for all food items in the database.

Data have been compiled from published and unpublished sources. Published data sources include the scientific literature. Unpublished data include those obtained from the food industry, other government agencies, and research conducted under contracts initiated by USDA's Agricultural Research Service (ARS). These contract analyses are currently conducted under the National Food and Nutrient Analysis Program (NFNAP), in cooperation with the National Cancer Institute (NCI) and other offices and institutes of the National Institutes of Health (Haytowitz *et al.*, 2008). Data from the food industry represents the nutrient content of a specific food or food product at the time the data is sent to NDL. The values may change due to reformulations or other processing changes by individual companies between the time that SR is released and the next update of SR. Values in the database may be based on the results of laboratory analyses or calculated by using appropriate algorithms, factors, or recipes, as indicated by the source code in the Nutrient Data file. Every food item does not contain all of the nutrients/components released in SR.

## **Specific Changes for SR25**

The major changes to the database since the last release are listed below.

 Nutrient profiles were added for new foods and existing nutrient profiles were updated for SR25 using data generated by USDA through the NFNAP or submitted

by the food industry. Foods added or updated include: Greek yogurt, taco shells, canned spaghetti and meatballs, frozen chicken tenders, barbecue rotisserie chicken (breast, drumstick, thigh, wing, and back (with and without skin)), sliced ready-to-eat luncheon meats (bologna, chicken, and salami), and bacon (regular, low-sodium and pre-cooked), frozen meat and cheese lasagna, pot pie, dried and frozen egg products, protein shakes, regular and light mayonnaise, regular and light Italian dressing, lightly salted mixed nuts, and iced tea. A major focus of this effort was to expand and monitor those foods which are major contributors of sodium to the diet, as well as to provide data on formulated foods, produced by the food industry to replace food items in the Food and Nutrient Database for Dietary Studies (FNDDS) which previously relied on home-prepared recipes. Nutrient data for other food items were updated and expanded in response to specific requests from the Food Surveys Research Group (FSRG) to support future releases of the FNDDS. A complete list of the added food items can be found in the ADD FOOD file and the updated nutrients in the CHG NUTR file. The formats of these files can be found on p. 40.

- Over 200 food industry items for baked products and mixed dishes have been added for SR 25. Several generic items have been updated, as well. Sodium values have been reviewed and updated for over 100 foods in these groups.
- Cultivar-specific profiles have been added for fresh apples and pears sold in the U.S.
- A study was conducted to obtain nutrient values for specific cuts of raw Australian beef, veal, and lamb. Australian scientific collaborators sent samples to Texas Tech University, where they were homogenized, composited, and analyzed for nutrients needed for labeling. Beef cuts from grass-fed beef and from Wagyu beef (from cattle breeds originating in Japan) were analyzed. The grass-fed beef cuts were: boneless tenderloin, boneless top loin, boneless top sirloin cap-off, boneless ribeye roast cap-on, boneless bottom round, boneless top round cap-off, and 85% lean ground beef. The Wagyu beef cuts, from two different Australian yield grades (yield grade 4/5 and yield grade 9), were: boneless tenderloin, boneless top loin, and small end rib roast. The veal cuts analyzed were rib roast, fore shank, and hind shank. Ground lamb sold as 85% lean was also analyzed.
- A study was conducted to determine the nutrient composition of whole turkey. Whole turkeys, enhanced with added water, salt, and sodium phosphate, were obtained from 11 different retail locations according to the NFNAP nationwide sampling plan. Measurements of weight of meat, with and without skin, were determined. Samples were homogenized, composited, and analyzed at commercial laboratories for nutrient content in both raw and roasted forms. As a result of this study, data has been generated to create new SR items for these enhanced whole turkey items: light meat (with and without skin), dark meat (with and without skin), gizzard, heart, liver, neck, and skin. Nutrient profiles for many

turkey items such as "fryer-roaster", "hen", and "tom" have been removed. This change has been made since the new SR25 turkey values represent one or more unidentified market classes.

- A study of non-enhanced/natural whole turkeys was also conducted. Since non-enhanced turkeys were not readily available in the NFNAP national retail locations, samples were obtained locally. Measurements of weight of meat, with and without skin, were determined. Samples of whole turkeys from 4 different retail outlets were homogenized, composited, and analyzed at commercial laboratories for nutrient content in both raw and roasted forms. As a result of this study data has been generated to update existing SR items, which are from non- enhanced whole turkey, for these items: light meat (with and without skin), dark meat (with and without skin), gizzard, heart, liver, neck, and skin.
- Products, such as mixed dishes and breakfast cereals no longer on the market or without current data, have been removed. A complete list of deleted food items can be found in the DEL\_FOOD file. The format of the file is given on p. 40.
- The food group, "Ethnic Foods" has been renamed "American Indian/Alaska Native Foods" to better reflect its contents. Food Groups are described in greater detail below (p. 5).
- A section on Notes on Foods has been added to the documentation and placed after the references. When the earlier paper copies of Agriculture Handbook No. 8, Composition of Foods: Raw, Processed, Prepared were released in separate sections by food group there was a section for each food group called Notes on Foods. The Notes gave additional information about the foods, such as the definitions of lean and fat for meats or enrichment for grain products. For some food groups, a brief description of research projects conducted to generate nutrient data were described. In this release Notes on Foods were added for Breakfast Cereals and Poultry Products. When applicable, "Notes on Foods" released earlier have been updated to include new information.

### **Data Files**

The data files for SR25 are available in ASCII format and as a Microsoft Access 2003 database. A description of each field in these files and the relationships between each begins on p. **Error! Bookmark not defined.**. The Access database contains all the SR25 files and relationships, with a few sample queries and reports. An abbreviated file (p. 37), with fewer nutrients (46) but all the food items, is also included. A Microsoft Excel 2003 spreadsheet of this file is also provided. These database and spreadsheet files are generally compatible with later releases of the same software package or with other software packages released at the same time.

## **Database Reports**

The data in SR25 are available as reports in two different presentations. The first presents items in SR25 as page images containing all the data for each food. These data are separated into files by food groups. The second presentation contains selected foods and nutrients in SR25. Those reports are sorted either alphabetically by food description or in descending order by nutrient content in terms of common household measures. The food items and weights in these reports are adapted from those in the "U.S. Department of Agriculture Home and Garden Bulletin 72, Nutritive Value of Foods" (Gebhardt and Thomas, 2002).

Adobe Reader is needed to see these files. There is a link from the NDL web site to Adobe's web site where it can be downloaded at no charge.

## **Database Content**

The database consists of several sets of data: food descriptions, nutrients, weights and measures, footnotes, and sources of data. The sections below provide details about the information in each. More extensive details on many specific foods are available in the printed "Agriculture Handbook 8" sections (U.S. Department of Agriculture, 1976-92).

## **Food Descriptions**

This file includes descriptive information about the food items. For more details on the format of the Food Description file, see "Food Description File Formats" (p. **Error! Bookmark not defined.**). A full description (containing the name of the food with relevant characteristics, e.g., raw or cooked, enriched, color) and a short description (containing abbreviations) are provided. Abbreviations used in creating short descriptions are given in Appendix A. In creating the short description, the first word in the long description is not abbreviated. In addition, if the long description is 25 characters or less, the short description contains no abbreviations. Abbreviations used elsewhere are given in Appendix

B. Brand names used in food descriptions are in upper case. Scientific names, common names, manufacturers' names, amounts of refuse, and refuse descriptions are provided where appropriate. The common name field includes alternative names for a product, e.g., soda or pop, for a carbonated beverage. In addition this field also includes Uniform Retail Meat Identity Standard (URMIS) identification numbers and USDA commodity codes as appropriate. The food group to which the food item belongs is also indicated. A code is also provided indicating if the item is used in the Food and Nutrient Database for Dietary Studies (FNDDS; USDA, ARS, 2012). The factors used to calculate protein from nitrogen are included, as well as those used to calculate kilocalories. There are no factors for items prepared using the recipe program of the NDBS or for items where the manufacturer calculates protein and kilocalories.

The refuse and refuse description fields contain amounts and descriptions of inedible

material (for example, seeds, bone, and skin) for applicable foods. These amounts are expressed as a percentage of the total weight of the item as purchased, and they are used to compute the weight of the edible portion. Refuse data were obtained from NFNAP and other USDA-sponsored contracts and U.S. Department of Agriculture Handbooks 102 (Matthews and Garrison, 1975) and 456 (Adams, 1975). To calculate the "amount of nutrient in edible portion of 1 pound (453.6 grams) as purchased," use the following formula:

Y = V\*4.536\*[(100-R)/100]

## where

Y = nutrient value per 1 pound as purchased,

V = nutrient value per 100 g (Nutr Val in the Nutrient Data file), and

R = percent refuse (Refuse in the Food Description file).

For meat cuts containing bone and connective tissue, the amount of connective tissue is included in the value given for bone. Separable fat is not shown as refuse if the meat is described as separable lean and fat. Separable fat generally refers to seam fat and external trim fat. Separable lean refers to muscle tissue that can be readily separated from fat, bone, and connective tissue in the intact cut; it includes any fat striations (marbling) within the muscle. For boneless cuts, the refuse value applies to connective tissue or connective tissue plus separable fat. The percentage yield of cooked, edible meat from 1 pound of raw meat with refuse can be determined by using the following formula:

 $Y = (W_c/453.6)*100$ 

#### where

 $Y = percentage yield of cooked edible meat per 1 pound as purchased, and <math>W_c = weight of cooked$ , edible meat in grams.

**Food Group**. To facilitate data retrieval the food items in SR are organized into food groups. Currently there are 25 food groups, which are listed in the FD\_GROUP file. For more details on the format of the Food Group Description file, see "Food Group Data File Formats" (p. 29). Starting with SR25, the food group, "Ethnic Foods" has been renamed "American Indian/Alaska Native Foods" to better reflect its contents. Data on other ethnic foods are contained in their respective food groups, for example data on plantains, a Latino ethnic food are in food group 9 (Fruit and Fruit Juices, while the Asian foods, miso and natto, are entered in food group 16 (Legumes and Legume Products). Food group 36 contains foods sampled at various restaurants (not fast food, which are in food group 21), and are different from the home prepared items or prepared frozen entrees included in Food Group 22, Meals, Entrees, and Sidedishes Some food items, such as beverages and rice, though obtained at restaurants are included in their respective food groups. At this time Restaurant Foods contains food items obtained from family-style restaurants, Latino restaurants, and Chinese restaurants.

Langual. To address the needs of diverse users of the USDA food composition databases in addition to the food descriptions, starting with SR23 NDL is providing an expanded standardized food description for selected food groups (spices and herbs, fruits and fruit juices, pork products, vegetables and vegetable products, and beef products) based on the Langual Thesaurus (Moeller and Ireland, 2009). The use of this multi-hierarchical food classification system will permit the harmonization of food description terms and definitions across many cultures and languages to support food research, food safety, nutrition monitoring, and food marketing.

LanguaL stands for "Langua aLimentaria" or "language of food". The work on LanguaL was started in the late 1970's by the Center for Food Safety and Applied Nutrition (CFSAN) of the United States Food and Drug Administration as an ongoing cooperative effort of specialists in food technology, information science, and nutrition.

Since then, LanguaL has developed in collaboration with the NCI, and, more recently, its European partners, notably in France, Denmark, Switzerland, and Hungary. Since 1996, the European LanguaL Technical Committee has administered the thesaurus.

The thesaurus provides a standardized language for describing foods, specifically for classifying food products for information retrieval. LanguaL is based on the concept that:

- Any food (or food product) can be systematically described by a combination of characteristics or facets
- These characteristics can be categorized into viewpoints and coded for computer processing
- The resulting viewpoint/characteristic codes can be used to retrieve data about the food from external databases

The current facets for foods in SR25 include: product type; food source; part of plant or animal; physical state, shape or form; extent of heat treatment; cooking method; treatment applied; preservation method; packing medium; container or wrapping; food contact surface; consumer group/dietary use/label claim; geographic places and regions; and adjunct characteristics of food.

The specific tables added to SR are the LanguaL Factor File (p. 29) and the LanguaL Factors Description File (p. 30). For more information on LanguaL, see the web site: <a href="https://www.langual.org">www.langual.org</a>

### **Nutrients**

The Nutrient Data file contains mean nutrient values per 100 g of the edible portion of food, along with fields to further describe the mean value. The following statistical attributes are provided to better describe the data:

- Nutrient value the mean of the data values for a specific parameter. Nutrient values have been rounded to the number of decimal places for each nutrient as specified in the Nutrient Definition file (p. 32).
- Number of data points the number of data points used to estimate the mean.
- Standard error the standard error of the mean: a measure of variability of the mean value as a function of the number of data points.
- Number of studies—the number of analytical studies used to generate the mean.
   A study is a discrete research project conducted or reported for a specific food. A study can be the analysis of one nutrient in one food, one nutrient in many foods, or many nutrients in many foods.
- Minimum value—the smallest observed value in the range of values.
- Maximum value—the largest observed value in the range of values.
- Degrees of freedom—the number of data values that are free to vary after certain restrictions are placed on the estimates; used in probability calculations.
- Lower- and upper-error bounds—represents a range of values within which the population mean is expected to fall, given a pre-specified confidence level. For SR25 and related releases, the confidence level is 95 percent.
- Statistical comments—provide additional details about certain assumptions made during statistical calculations. The definition of each comment is given after the description of the Nutrient Data file under "File Formats" (p. 29).

Other fields provide information on how the values were generated, as follows:

- Derivation code—gives more information about how a value was calculated or imputed. Procedures used to impute a nutrient value are described by Schakel et al. (1997).
- Reference NDB number—indicates the NDB number of the food item that was
  used to impute a nutrient value for another food. This field is only populated for
  items which have been added or updated since SR14 for which an imputed value
  is provided.
- Added nutrient marker—a "Y" indicates that a mineral or vitamin was added for enrichment or fortification. This field is populated for ready-to-eat breakfast cereals and many brand-name hot cereals in food group 08. In future releases, this field will be populated for other food groups, where applicable.
- AddMod\_Date—indicates when a value was either added to the database or last modified. This field was first added with SR24. Data, which have not been updated since SR14 (2001) carry the date when that section of AH-8 was published. When the nutrient values are reviewed, but not modified, there is no change in the AddMod\_Data. Hence, the field may not accurately reflect the currency of the data. Dates associated with calculated values (carbohydrate by difference, energy, vitamin A (IU and RAE), and folate DFE) may carry newer dates reflecting their recalculation when other values in the profile of a particular food item were updated, though the values from which the specific value was calculated may not have changed. Only values added or modified since SR14 will have newer dates. To determine if the date has changed the values between the

current and preceding releases are compared to the number of decimal places specified in the Nutr\_Def table. The date associated with the source documents used to determine the mean can be found in the Src\_Data file. The description of this file can be found on p. 35.

• Confidence code—indicates the relative quality of the data. This code is derived using the data quality criteria first described by Mangels *et al.* (1993). These criteria have been expanded and enhanced for the NDBS (Holden *et al.*, 2002). This field is included as a placeholder for future releases.

For more details on the Nutrient Data file, see "Nutrient Data File Formats" (p. 29). Nutrient values indicate the total amount of the nutrient present in the edible portion of the food, including any nutrients added in processing. Table 1 gives an idea of the comprehensiveness of the database by listing for each nutrient the number of food items that contain data.

In general, levels of fortified nutrients are the values calculated by the manufacturer or by NDL, based on the Nutrition Labeling and Education Act (NLEA) label declaration of % Daily Value (DV) (CFR, Title 21, Pt. 101) (U.S. Food and Drug Administration—Department of Health and Human Services, 2012). Such values represent the minimum nutrient level expected in the product. If analytical values were used to estimate levels of added nutrients, a number is present in the sample count field for these nutrients.

**Nutrient Retention and Food Yield.** When nutrient data for prepared or cooked products are unavailable or incomplete, nutrient values are calculated from comparable raw items or by recipe. When values are calculated in a recipe or from the raw item, appropriate nutrient retention (USDA, 2007) and food yield factors (Matthews and Garrison, 1975) are applied to reflect the effects of food preparation on food weights and nutrient content. To obtain the content of nutrient per 100 g of cooked food, the nutrient content per 100 g of raw food is multiplied by the nutrient retention factor and, where appropriate, adjustments are made for fat and moisture gains and losses.

Nutrient retention factors are based on data from USDA research contracts, research reported in the literature, and USDA publications. Most retention factors were calculated by the True Retention Method (%TR) (Murphy *et al.*, 1975). This method, as shown below, accounts for the loss or gain of moisture and the loss of nutrients due to heat or other food preparation methods:

$$%TR = (N_c * G_c) / (N_r * G_r) * 100$$

#### Where

TR = true retention

 $N_c$  = nutrient content per g of cooked food,

 $G_c = g$  of cooked food,

 $N_r$  = nutrient content per g of raw food, and

 $G_r = g$  of food before cooking.

Table 1.—Number of Foods in the Database (n = 8,194) Containing a Value for the Specified Nutrient

<u> 2be</u>	ecified Nutrient				
Nutr.		Number	Nutr.		Number
No.	Nutrient	of Foods	No.	Nutrient	of Foods
255	Water	8188	418	Vitamin B-12	6966
208	Energy	8194	578	Vitamin B-12, added	4257
203	Protein	8194	320	Vitamin A, RAE	6674
204	Total lipid (fat)	8194	319	Retinol	6360
207	Ash	7855	321	Carotene, beta	4827
205	Carbohydrate, by difference	8194	322	Carotene, alpha	4740
291	Fiber, total dietary	7498	334	Cryptoxanthin, beta	4731
269	Sugars, total	6139	318	Vitamin A, IU	7479
210	Sucrose	1373	337	Lycopene	4705
211	Glucose (dextrose)	1376	338	Lutein + zeaxanthin	4681
212	Fructose	1375	323	Vitamin E (alpha-	5054
213	Lactose	1355		tocopherol)	
214	Maltose	1343	573	Vitamin E, added	4082
287	Galactose	1225	341	Tocopherol, beta	1509
209	Starch	895	342	Tocopherol, gamma	1504
301	Calcium, Ca	7830	343	Tocopherol, delta	1489
303	Iron, Fe	8047	328	Vitamin D (D2 + D3)	4763
304	Magnesium, Mg	7451	325	Vitamin D2 (ergocalciferol)	52
305	Phosphorus, P	7570	326	Vitamin D3 (cholecalciferol)	1373
306	Potassium, K	7732	324	Vitamin D	4761
307	Sodium, Na	8111	430	Vitamin K (phylloquinone)	4620
309	Zinc, Zn	7437	429	Dihydrophylloquinone	1299
312	Copper, Cu	6977	428	Menaquinone-4	477
315	Manganese, Mn	6159	606	Fatty acids, total saturated	7855
317	Selenium, Se	6425	607	4:0	5072
313	Fluoride, F	552	608	6:0	5117
401	Vitamin C, total ascorbic	7395	609	8:0	5361
	acid		610	10:0	5755
404	Thiamin	7473	611	12:0	6021
405	Riboflavin	7495	696	13:0	238
406	Niacin	7468	612	14:0	6395
410	Pantothenic acid	6179	652	15:0	1801
415	Vitamin B-6	7201	613	16:0	6608
417	Folate, total	7042	653	17:0	2012
431	Folic acid	6391	614	18:0	6596
432	Folate, food	6590	615	20:0	2108
435	Folate, DFE	6381	624	22:0	1751
421	Choline, total	4192	654	24:0	1480
454	Betaine	1848	645	Fatty acids, total	7491
				monounsaturated	
			`		

Nutr.		Number	Nutr.		Number
No.	Nutrient	of Foods	No.	Nutrient	of Foods
625	14:1	2010	858	22:4	630
697	15:1	1497	631	22:5 n-3 (DPA)	5136
626	16:1 undifferentiated	6359	621	22:6 n-3 (DHA)	5139
673	16:1 c	686	605	Fatty acids, total trans	2606
662	16:1 t	566	693	Fatty acids, total trans-	1156
687	17:1	1704		monoenoic	
617	18:1 undifferentiated	6624	695	Fatty acids, total trans-	906
674	18:1 c	1171		polyenoic	
663	18:1 t	1185	601	Cholesterol	7834
859	18:1-11t (18:1t n-7)	154	636	Phytosterols	514
628	20:1	5750	638	Stigmasterol	128
630	22:1 undifferentiated	5169	639	Campesterol	127
676	22:1 c	604	641	Beta-sitosterol	128
664	22:1 t	488	501	Tryptophan	4797
671	24:1 c	788	502	Threonine	4843
646	Fatty acids, total	7498	503	Isoleucine	4847
	polyunsaturated		504	Leucine	4846
618	18:2 undifferentiated	6642	505	Lysine	4860
675	18:2 n-6 c,c	1129	506	Methionine	4857
670	18:2 CLAs	782	507	Cystine	4786
669	18:2 t,t	216	508	Phenylalanine	4843
666	18:2 i	60	509	Tyrosine	4812
665	18:2 t not further defined	651	510	Valine	4847
619	18:3 undifferentiated	6540	511	Arginine	4832
851	18:3 n-3 c,c,c (ALA)	1308	512	Histidine	4840
685	18:3 n-6 c,c,c	1113	513	Alanine	4789
856	18:3i	126	514	Aspartic acid	4792
627	18:4	5101	515	Glutamic acid	4792
672	20:2 n-6 c,c			Glycine	4789
689	20:3 undifferentiated		517	Proline	4780
852	20:3 n-3	487	518	Serine	4790
853	20:3 n-6	568	521	Hydroxyproline	1175
620	20:4 undifferentiated	5761	221	Alcohol, ethyl	4887
855	20:4 n-6	7	262	Caffeine	4657
629	20:5 n-3 (EPA)	5183	263	Theobromine	4633
857	21:5	102			

<sup>\*</sup>Indicates the 65 nutrients included in the USDA Food and Nutrient Database for Dietary Studies (FNDDS).

† Nutrients included in the Abbreviated file (p. 37).

**Proximates.** The term proximate component refers to those macronutrients that include water (moisture), protein, total lipid (fat), total carbohydrate, and ash. To be included in the database, a nutrient profile must have values for the proximate components and at least one other nutrient.

<u>Protein.</u> The values for protein were calculated from the amount of total nitrogen (N) in the food, using the specific conversion factors recommended by Jones (1941) for most food items. The analytical methods used to determine the nitrogen content of foods are AOAC 968.06 (4.2.04), 992.15 (39.1.16), and 990.03 (combustion); and 991.20 (Kjeldahl) (AOAC, 2010). The specific factor applied to each food item is provided in the N\_Factor field in the Food Description file. The general factor of 6.25 is used to calculate protein in items that do not have a specific factor. When the protein content of a multi-ingredient food (e.g., beef stew) is calculated using the recipe program of the NDBS the specific nitrogen to protein conversion factors are applied at the ingredient level. Therefore, the N-factor field will remain empty. When the manufacturer calculates protein the N-factor field will also be empty.

Protein values for chocolate, cocoa, coffee, mushrooms, and yeast were adjusted for non-protein nitrogenous material (Merrill and Watt, 1973). The adjusted protein conversion factors used to calculate protein for these items are as follows:

4.74
5.3
4.38
5.7

When these items are used as ingredients, such as chocolate in chocolate milk or yeast in bread, only their protein nitrogen content was used to determine their contribution to the calculated protein and amino acid content of the food. Protein calculated from total nitrogen, which may contain non-protein nitrogen, was used in determining carbohydrate by difference. This unadjusted protein value is not given in the Nutrient Data file for SR25; rather, it was previously included as a footnote in printed sections of "Agriculture Handbook 8."

For soybeans, nitrogen values were multiplied by a factor of 5.71 (Jones, 1941) to calculate protein. The soybean industry, however, uses 6.25 to calculate protein. To convert these values divide the proteins value by 5.71, and then multiply the resulting value by 6.25. It will also be necessary to adjust the value for carbohydrate by difference (Nutr. No. 205).

<u>Total Lipid.</u> The total lipid (fat) content of most foods obtained through NFNAP are determined by gravimetric methods, including acid hydrolysis (AOAC 922.06, 925.12, 989.05, or 954.02) and extraction methods using a mixed solvent system of chloroform and methanol (AOAC 983.25 or Folch *et al.*). Older values may have been obtained by ether extraction (AOAC 920.39, 933.05, or 960.39). Total lipid determined by extraction is reported as Nutrient No. 204. It is sometimes referred to as "crude fat" and includes

the weight of all lipid components, including glycerol, soluble in the solvent system. Nutrient No. 204 may not be identical to the fat level declared on food labels under the NLEA, where fat is expressed as the amount of triglyceride that would produce the analytically determined amount of lipid fatty acids and does not include other lipid components not soluble in the solvent system. The term "NLEA fat" is commonly referred to as "total fatty acids expressed as triglycerides."

<u>Ash</u>. The ash content of foods is determined by gravimeteric methods (AOAC 923.03, 942.05, or 945.46).

Moisture. The moisture (or water) content of foods is determined by vacuum oven (AOAC 934.01, 934.06, 964.22) or forced air (AOAC 950.46).

Carbohydrate. Carbohydrate, when present, is determined as the difference between 100 and the sum of the percentages of water, protein, total lipid (fat), ash, and, when present, alcohol. Total carbohydrate values include total dietary fiber. Available carbohydrate, which is used in some countries, can be calculated if desired by the user, by subtracting the sum of the percentages of water, protein, total lipid (fat), ash, total dietary fiber, and, when present, alcohol from 100. Carbohydrate in beer and wine is determined by methods 979.06 (27.1.21) and 985.10 (28.1.18) of AOAC International (AOAC, 2010), respectively. Total dietary fiber content is determined by enzymaticgravimetric methods 985.29 or 991.43 of the AOAC (2010). Total sugars is the term used for the sum of the individual monosaccharides (galactose, glucose, and fructose) and disaccharides (sucrose, lactose, and maltose). Analytical data for individual sugars obtained through NFNAP were determined by liquid chromatography (AOAC 982.14). Earlier values were also determined using AOAC methods (2010), with either highperformance liquid chromatography (HPLC) or gas-liquid chromatography (GLC). When analytical data for total sugars are unavailable for items in the FNDDS, values are imputed or obtained from manufacturers and trade associations. Starch is analyzed using the AOAC method 966.11 (2010) or by a polarometric method (The Feedings Stuffs Regulations 1982). Because the analyses of total dietary fiber, total sugars, and starch are performed separately and reflect the analytical variability inherent to the measurement process, the sum of these carbohydrate fractions may not equal the carbohydrate-by-difference value.

<u>Food Energy</u>. Food energy is expressed in kilocalories (kcal) and kilojoules (kJ). One kcal equals 4.184 kJ. The data represent physiologically available energy, which is the energy value remaining after digestive and urinary losses are deducted from gross energy. Energy values, with the exception of multi-ingredient processed foods, are based on the Atwater system for determining energy values. Derivation of the Atwater calorie factors is discussed in "Agriculture Handbook 74" (Merrill and Watt, 1973). For multi-ingredient processed foods, kilocalorie values (source codes 8 or 9; for more information on source codes, see p. 33) generally reflect industry practices (as permitted by NLEA) of calculating kilocalories as 4, 4, or 9 kilocalories per gram of protein, carbohydrate, and fat, respectively, or as 4, 4, or 9 kilocalories per gram of protein, carbohydrate minus insoluble fiber, and fat. The latter method is often used for

high-fiber foods.

Calorie factors for protein, fat, and carbohydrates are included in the Food Description file. For foods containing alcohol, a factor of 6.93 is used to calculate kilocalories per gram of alcohol (Merrill and Watt, 1973). No calorie factors are given for items prepared using the recipe program of the NDBS. Instead, total kilocalories for these items equal the sums of the kilocalories contributed by each ingredient after adjustment for changes in yield, as appropriate. For multi-ingredient processed foods, if the kilocalories calculated by the manufacturer are reported, no calorie factors are given.

Calorie factors for fructose and sorbitol, not available in the Atwater system, are derived from the work of Livesay and Marinos (1988). Calorie factors for coffee and tea are estimated from those for seeds and vegetables, respectively.

*Minerals*. Minerals included in the database are calcium, iron, magnesium, phosphorus, potassium, sodium, zinc, copper, manganese, selenium, and fluoride. Levels of minerals for most foods are determined by methods of the AOAC (2010). Calcium, iron, magnesium, phosphorus, sodium, potassium, zinc, copper, and manganese are usually determined by inductively coupled plasma emission spectrophotometry (AOAC 984.27) or, except for phosphorus, by atomic absorption (AOAC 985.35) with phosphorus determined colorimetrically by AOAC 2.019, 2.095 and 7.098.

Analytical data for selenium were published earlier by USDA (1992) and were determined by the modified selenium hydride and fluorometric methods. Selenium values for foods analyzed between 1998 and 2008 for NFNAP are determined by either the modified selenium hydride (AOAC 986.15) or stable isotope dilution gas chromatography-mass spectrometry (Reamer and Veillon, 1981) methods. The selenium content of plants, in particular cereal grains, is strongly influenced by the quantity of biologically available selenium in the soil in which the plants grow, that is, by their geographical origin (Kubota and Allaway, 1972). The values given are national averages and should be used with caution when levels of selenium in locally grown foods are of interest or concern.

Beginning with SR19 (2006), Values for fluoride, previously released in the USDA National Fluoride Database of Selected Beverages and Foods, Release 2 (USDA, 2005), are included in SR. Other analyzed values in the Fluoride Database, including regional values, are not included in SR. Samples are analyzed using a fluoride ion-specific electrode, direct read method (VanWinkle, 1995) for clear liquids and a micro-diffusion method (VanWinkle, 1995) for other food samples. As with selenium, the values for fluoride are national averages and should be used with caution when levels of fluoride in locally produced foods and beverages are of interest or concern.

**Vitamins.** Vitamins included in the database are ascorbic acid (vitamin C), thiamin, riboflavin, niacin, pantothenic acid, vitamin  $B_6$ , vitamin  $B_{12}$ , folate, total choline and betaine, vitamin A (individual carotenoids, and retinol), vitamin E (tocopherol), vitamin K (phylloquinone, dihydrophylloquinone and menaquinone-4), and vitamin D ( $D_2$  and  $D_3$ ).

Ascorbic acid. In the current database system, nearly all data for ascorbic acid listed under Nutrient No. 401, total ascorbic acid, have been determined by the microfluorometric method (AOAC 967.22). Older values which have not been updated are primarily for reduced ascorbic acid and were determined by the dichloroindophenol method (AOAC 967.21)

Thiamin, Riboflavin, and Niacin. Thiamin is determined chemically by the fluorometric method (AOAC 942.23). Fluorometric (AOAC 970.65) or microbiological (AOAC 940.33) methods are used to measure riboflavin. Niacin is determined by microbiological methods (AOAC 944.13). The values for niacin are for preformed niacin only and do not include the niacin contributed by tryptophan, a niacin precursor. The term "niacin equivalent" applies to the potential niacin value; that is, to the sum of the preformed niacin and the amount that could be derived from tryptophan (the mean value of 60 mg tryptophan is considered equivalent to 1 mg niacin (IOM, 1998)). Although not included in SR, niacin equivalents can be estimated for those foods where amino acids are given:

mg Niacin equivalents = mg niacin + (mg tryptophan / 60)

Pantothenic acid, Vitamins  $B_6$ , and  $B_{12}$ . Pantothenic acid (AOAC 945.74 or 992.07), vitamin  $B_6$  (AOAC 961.15), and vitamin  $B_{12}$  (AOAC 952.20) are determined by microbiological methods. Vitamin  $B_{12}$  is found intrinsically in foods of animal origin or those containing some ingredient of animal origin, e.g., cake that contains eggs or milk. For foods that contain only plant products, the value for vitamin  $B_{12}$  is assumed to be zero. Some reports contain values for vitamin  $B_{12}$  in certain fermented foods (soy sauce and miso). It is believed that this  $B_{12}$  is synthesized not by the microorganisms responsible for the fermentation of the food, but rather by other contaminating microorganisms. Therefore, one should not consider these foods to be a consistent source of vitamin  $B_{12}$  (Liem *et al.*, 1977) and these values are not included in the database.

The Dietary Reference Intakes (DRI) report on vitamin  $B_{12}$  recommended that people older than 50 years meet their Recommended Dietary Allowances (RDA) mainly by consuming foods fortified with vitamin  $B_{12}$  or a vitamin  $B_{12}$ -containing supplement (IOM, 1998). Since vitamin  $B_{12}$  added as a fortificant may provide a significant source of the vitamin in the diet, a nutrient number (#578) for "added vitamin  $B_{12}$ " has been added to the database. In this release, there are about 260 foods fortified with vitamin  $B_{12}$ . The vast majority are breakfast cereals, infant formulas, and plant-based meat substitutes. For these foods, the value for total vitamin  $B_{12}$  is used for "added vitamin  $B_{12}$ ." Only a few cereals containing a milk ingredient would contain any intrinsic vitamin  $B_{12}$ . Milk-based infant formulas should contain intrinsic vitamin  $B_{12}$ . However, infants are not the population of concern for intake of fortified vitamin  $B_{12}$ . Plant-based meat substitutes should not contain intrinsic vitamin  $B_{12}$ .

Folate. Values are reported for folic acid (Nutr. No. 431), food folate (Nutr. No. 432), and

total folate reported in  $\mu$ g (Nutr. No. 417) and as dietary folate equivalents (DFEs) (Nutr. No. 435). These varied folate forms are included and defined as described in the DRI report on folate (IOM, 1998). RDAs for folate are expressed in DFEs, which take into account the greater bioavailability of synthetic folic acid compared with naturally occurring food folate.

To calculate DFEs for any single food, it is necessary to have separate values for naturally occurring food folate and added synthetic folic acid in that item.

 $\mu g$  DFE =  $\mu g$  food folate + (1.7 \*  $\mu g$  folic acid)

Folate values for foods analyzed through NFNAP are generated using the trienzyme microbiological procedure (Martin *et al.*, 1990). For a small number of foods, total folate was determined as the sum of one or more individual folate vitamers (5-methyltetrahydrofolate, 10-formyl folic acid, 5-formyltetrahydrofolic acid, and tetrahydrofolic acid); these are indicated in the footnotes. Microbiological methods measure µg total folate; for enriched foods, folic acid and food folate are not distinguished from each other. Therefore, to be able to calculate DFE, multi-ingredient enriched foods are analyzed by an additional microbiological procedure without enzymes to estimate the amount of added folic acid (Chun *et al.*, 2006). Food folate is then calculated by difference.

The addition of folic acid to enriched cereal-grain products subject to standards of identity began in the United States on January 1, 1998 (CFR, Title 21, Pts. 136B137). These products include flour, cornmeal and grits, farina, rice, macaroni, noodles, bread, rolls, and buns. Folic acid may continue to be added (with some restrictions on amounts) to breakfast cereals, infant formulas, medical foods, food for special dietary use, and meal replacement products.

For unenriched foods, food folate would be equivalent to total folate since folic acid (pteroylmonoglutamic acid) occurs rarely in foods. Therefore, the same value with its number of data points and standard error, if present, is used for total folate and food folate. The folic acid value is assumed to be zero.

For enriched cereal-grain products with standards of identity (flour, cornmeal and grits, farina, rice, macaroni, noodles, bread, rolls, and buns), the folic acid value is calculated by subtracting the analytical folate value before fortification from the analytical value for the fortified product.

Enriched ready-to-eat (RTE) cereals have generally included folic acid fortification for over 25 years. Therefore, food folate values (before fortification) were not readily available for these products. Food folate was estimated by means of the NDBS formulation program for a variety of high-consumption cereals. Mean folate values were calculated for categories of RTE cereals based on grain content. Added folic acid was then calculated by subtracting estimated food folate from the total folate content. Generally, food folate values represent a small proportion of the total folate in the

fortified products.

<u>Choline</u>. Beginning with SR19 (2006), total choline and betaine values from the USDA Database for the Choline Content of Common Foods (USDA, 2004) have been incorporated into SR. Values for the individual metabolites have not been added to SR, but are available in the USDA Database for the Choline Content of Common Foods.

For analysis, choline compounds are extracted, partitioned into organic and aqueous phases using methanol and chloroform, and analyzed directly by liquid chromatography-electrospray ionization-isotope dilution mass spectrometry (LC-ESI-IDMS) (Koc *et al.*, 2002). Samples are analyzed for betaine and these choline-contributing compounds: free choline (Cho), glycerophosphocholine (GPC), phosphocholine (Pcho), phosphatidylcholine (Ptdcho), and sphingomyelin (SM).

Because there are metabolic pathways for the interconversion of Cho, GPC, Pcho, PtdCho, and SM (Zeisel *et al.*, 1994), total choline content is calculated as the sum of these choline-contributing metabolites. Betaine values are not included in the calculation of total choline since the conversion of choline to betaine is irreversible (Zeisel *et al.*, 2003).

<u>Vitamin A</u>. Beginning with SR15 (2002) values for vitamin A in  $\mu$ g of retinol activity equivalents (RAEs) and  $\mu$ g of retinol are reported. At the same time, values in  $\mu$ g of retinol equivalents (REs) were dropped from the database.

This change responded to new reference values for vitamin A in the DRI report issued by the Institute of Medicine of the National Academies (IOM, 2001). The report recommended changing the factors used for calculating vitamin A activity from the individual provitamin A carotenoids and introduced RAE as a new unit for expressing vitamin A activity. One  $\mu g$  RAE is equivalent to 1  $\mu g$  of all-trans-retinol, 12  $\mu g$  of all-trans- $\beta$ -carotene, or 24  $\mu g$  of other provitamin A carotenoids. The RAE conversion factors are based on studies showing that the conversion of provitamin A carotenoids to retinol was only half as great as previously thought.

Vitamin A is also reported in international units (IU), and will continue to be reported because it is still the unit used for nutrition labeling in the U.S. One IU is equivalent to 0.3  $\mu$ g retinol, 0.6  $\mu$ g  $\beta$ -carotene, or 1.2  $\mu$ g other provitamin-A carotenoids (NAS/NRC, 1989) and thus over-estimates bioavailabilty.

Individual carotenoids ( $\beta$ -carotene,  $\alpha$ -carotene,  $\beta$ -cryptoxanthin, lycopene, and lutein+zeaxanthin) are reported. The analytical data are from NFNAP, generated using HPLC methodology (AOAC 941.15 or Craft, 2001). Most analytical systems do not separate lutein and zeaxanthin, so these carotenoids are shown combined. These values supersede those in Holden *et al.*, 1999. Vitamin A activity values in RAE and IU were calculated from the content of individual carotenoids ( $\beta$ -carotene,  $\alpha$ -carotene, and  $\beta$ -cryptoxanthin) using the appropriate factors. For food items used in the FNDDS, carotenoid values are imputed if analytical data are not available. For many of these

items data are only available for vitamin A in IU. The variability in carotenoid levels due to cultivar, season, growing area, etc., as well as rounding within the NDBS, increases the difficulty in matching the calculated vitamin A activity values from imputed individual carotenoids to the existing IU values. As a result, the vitamin A IU value agrees within ±15 IU of the value calculated from individual carotenoids.

When individual carotenoids are not reported for plant foods (i.e. fruits, vegetables, legumes, nuts, cereal grains, and spices and herbs), µg RAE are calculated by dividing the IU value by 20. In foods of animal origin, such as eggs, beef, pork, poultry, lamb, veal, game, and fish (except for some organ meats and dairy), all of the vitamin A activity is contributed by retinol. For these foods, where analytical data are not available, µg RAE and µg of retinol are calculated by dividing the IU value by 3.33.

In foods that contain both retinol and provitamin A carotenoids, the amount of each of these components must be known to calculate RAE. Previously, most of the vitamin A data in the database were received as IU. Therefore, the amounts of the provitamin A carotenoids and retinol were then estimated from the ingredients. Once the components had been estimated, µg RAE were calculated as (IU from carotenoids/20) + (IU from retinol/3.33). Micrograms of retinol were calculated as IU from retinol/3.33.

<u>Vitamin D</u> Due to considerable public health interest in vitamin D, a multi-year project was undertaken by NDL to expand and update the relatively small existing dataset of vitamin D values in SR. Much of the original data for vitamin D had been published earlier in USDA's Provisional Table (PT-108) (Weihrauch and Tamaki, 1991), with values for fortified foods updated as needed with data received from the food industry. Earlier data collected between 1999 and 2008 utilized AOAC methods 982.29 or 992.26.

The availability of vitamin D data for foods permitting subsequent dietary intake assessment is expected be a useful tool in investigating dietary requirements of vitamin D in vulnerable groups, one of the specific research recommendations of the 2005 Dietary Guidelines Committee (DGAC. 2004). An Institute of Medicine Committee to Review Dietary Reference Intakes for Vitamin D and Calcium was convened in 2009 to assess current relevant data and revise, as appropriate, the DRIs for vitamin D and calcium. Their report was issued in 2011 (IOM).

Before foods could be analyzed for vitamin D for inclusion in SR, analytical methodology had to be developed that could be used for a variety of food matrices (Byrdwell, 2008). Although a single method is not required for USDA-sponsored analyses, all participating laboratories must demonstrate that their analysis of quality control materials falls within an acceptable range of values. For vitamin D, all methods involved extraction with solvent(s), cleanup steps, and quantification by HPLC or by HPLC and LC/MS. In the absence of certified quality control materials for vitamin D, NDL, in collaboration with Virginia Tech, developed five matrix-specific materials, one of which was sent with every batch of foods to be analyzed. The materials were: vitamin D<sub>3</sub> fortified fluid milk, a vitamin D<sub>3</sub> fortified multigrain ready-to-eat cereal, orange juice fortified with calcium and

vitamin D<sub>3</sub>, pasteurized process cheese fortified with vitamin D<sub>3</sub>, and canned red salmon, a natural source of D<sub>3</sub> (Phillips *et al.* 2008). Vitamin D may also be present as 25-hydroxycholecalciferol in some foods such as fish, meat, and poultry. At this point the analytical methodology used to determine this metabolite of vitamin D has not been sufficiently validated; when work on this validation is completed 25-hydroxycholecalciferol values will be provided in future releases of SR.

Once an improved method of analysis was developed (Byrdwell, 2008), and the laboratories certified, a selection of foods, representing natural vitamin D sources and fortified sources, were chosen for sampling and analysis under the NFNAP (Haytowitz et al. 2008). Analyses have been completed for raw eggs and the following fortified products: fluid milk at 4 fat levels, reduced fat chocolate milk, fruit yogurt, and orange juice. Current analytical values for fish are based on limited analyses; additional samples are being analyzed and values will be updated in future SR releases. Vitamin D analyses have also been completed for selected cuts/pieces of chicken, pork, and beef. These data have been determined by a new LC/MS/MS method (Huang and Winters, 2011).

Cholecalciferol (vitamin  $D_3$ ; Nutr. No. 326) is the form naturally occurring in animal products and the form most commonly added to fortified foods. Ergocalciferol (vitamin  $D_2$ ; Nutr. No. 325) is the form found in plants and is sometimes added to fortified foods, such as soy milk. In SR25, vitamin D (Nutr. No. 328) is defined as the sum of vitamin  $D_2$  and vitamin  $D_3$ .

Vitamin D values in SR25 are provided in both micrograms ( $\mu$ g) and International Units (IU) to support both the analytical unit ( $\mu$ g) and the unit (IU) that is currently used in nutrient labeling of foods in the U.S. The biological activity of vitamin D is given as 40 IU/ $\mu$ g. Where available, specific isomers of vitamin D are reported only in  $\mu$ g. Calculations for vitamin D in SR include:

```
Vitamin D, \mug (Nutr. No. 328) = vitamin D<sub>2</sub>, \mug + vitamin D<sub>3</sub>, \mug Vitamin D, \mug (Nutr. No. 324) = vitamin D, \mug x 40
```

Vitamin D values in  $\mu$ g (Nutr. No. 328) are provided for all items in SR25 used to create the FNDDS.

In some cases, it was possible to identify food groups for which the foods do not provide or only contain trace amounts of vitamin D. Values for those foods were set to zero. For example, except for mushrooms, plant foods are not expected to contain any appreciable levels of vitamin D. In order to provide vitamin D estimates for the rest of the foods provided to create the FNDDS, data for other foods have been taken from the scientific literature or from other food composition databases, calculated from industry-declared % DV fortification levels, determined by formulation/recipe techniques, or estimated by other USDA imputation methods.

Fluid milk available at the retail level is fortified. The dairy industry provided guidance

that most dairy products used as ingredients in formulated (commercial multi-ingredient) food, are not likely to be fortified with vitamin D. Likewise, margarine used in commercial products is generally not vitamin D-fortified; a relatively low percentage of vitamin D-fortified margarines and spreads are available in the retail market. For ingredients that could be fortified at the retail level, but generally are not fortified at the food processing level, two related profiles are available in SR – one with added vitamin D and one without. When estimates were calculated for formulated foods, the unfortified profile was used. For home-prepared foods, such as pudding prepared with milk, the fortified ingredient(s) was selected for use in the recipe calculation of vitamin D. In the case of margarine, a market-share blend of fortified and unfortified product was used.

For some retail products, such as yogurt, there is considerable brand-to-brand difference in vitamin D fortification practices. One brand or line of products may be fortified with vitamin D, whereas another brand may not. Both types are included in the database. The market changes quickly and consumers concerned about vitamin D intake should always confirm vitamin D content by checking the product label.

<u>Vitamin E.</u> The DRI report (IOM, 2000) defines vitamin E as the naturally occurring form (*RRR*-α-tocopherol) and three synthetic forms of α-tocopherol. Since the release of SR16-1 (2003), NDL has reported vitamin E as mg of α-tocopherol (Nutr. No. 323) in accordance with the DRI report. Analytical values for tocopherols found in the database are determined by gas-liquid chromatography (GLC) or high-performance liquid chromatography (HPLC; Ye *et al.*, 2000). Although  $\beta$ ,  $\gamma$ , and  $\delta$ -tocopherol do not contribute to vitamin E activity, they are included in the database when analytical data are available

In the 2000 DRI report, a revised factor was recommended for calculation of the milligram amounts of  $\alpha$ -tocopherol contributed by synthetic forms of vitamin E, since *all rac*- $\alpha$ -tocopherol contains 2R-stereoisomeric and 2S-stereoisomeric forms in equal amounts. Vitamin E activity is limited to the 2R-stereoisomeric forms of  $\alpha$ -tocopherol to establish recommended intakes (IOM, 2000).

However, the unit for vitamin E required by the NLEA is IU and is based on the 1968 RDA definitions for vitamin E (CFR, Title 21, Pt. 101) (U.S. Food and Drug Administration—Department of Health and Human Services, 2004).

When NDL receives vitamin E data from the food industry expressed as IU, the values are converted to mg amounts based on the conversions of vitamin E in IU to mg as defined by the DRI report:

One mg of  $\alpha$ -tocopherol = IU of the *all rac*- $\alpha$ -tocopherol compound  $\times$  0.45; and One mg of  $\alpha$ -tocopherol = IU of the *RRR*- $\alpha$ -tocopherol compound  $\times$  0.67.

The basis of the vitamin E tolerable upper intake level (UL), another important reference value defined in the DRI report, was established using all forms of supplemental α-

tocopherol (IOM, 2000). Although the 2*S*-stereoisomers do not contribute to dietary requirements for vitamin E (IOM, 2000), they do contribute to the total intake relative to the UL. Nutrient number 573 is used to identify quantities of "added vitamin E." In this release, there are about 140 food items that have values for added vitamin E greater than 0. For the majority of these food items, the form added is *all rac*- $\alpha$ -tocopherol; these values should be multiplied by 2 to relate intakes of this form to the UL. Items that are fortified with *RRR*- $\alpha$ -tocopherol are identified by a footnote and the added vitamin E value can be used directly to estimate its contribution to the UL.

<u>Vitamin K.</u> Much of the data for vitamin K has been generated under NFNAP and supersedes the values in the USDA Provisional Table (PT-104) (Weihrauch and Chatra, 1994). Vitamin K is extracted with hexane, purified with solid phase extraction using silica columns, and quantitated using HPLC with chemical reduction and fluorescence detection. Losses are corrected using vitamin  $K_{1(25)}$  as the internal standard (Booth *et al.* 1994). Starting with SR23, in addition to data on vitamin  $K_1$  (Nutr. No. 430), data on dihydrophylloquinone (Nutr. No.429) and menaquinone-4 (Nutr. No. 428) are also released. Dihydrophylloquinone is created during the commercial hydrogenation of plant oils. Menaquinone-4 is formed from vitamin  $K_1$  and/or the synthetic form of vitamin K found in animal feed, and is found primarily in meats and meat products.

**Lipid Components.** Fatty acids are expressed as the actual quantity of fatty acid in g per 100 g of food and do not represent fatty acids as triglycerides. Historically, most fatty acid data were obtained as the percentage of fatty acid methyl esters and determined by GLC analyses (AOAC 996.06). These data were converted to g fatty acid per 100 g total lipid using lipid conversion factors and then to g fatty acid per 100 g edible portion of food using the total lipid content. Details of the derivation of lipid conversion factors were published by Weihrauch *et al.*, 1977.

In the redesigned NDBS, fatty acid data may be imported in a variety of units and converted within the system. No conversions are required if data are received as g fatty acid per 100 g edible portion of food. Data received as fatty acid esters and as triglycerides are converted to fatty acids using Sheppard conversion factors. Sheppard conversion factors are based on the molecular weights of the specific fatty acid and its corresponding esters (butyl or methyl) and triglyceride (Sheppard, 1992). When fatty acid data are received as percentages of fatty acid methyl esters, methyl esters are converted to fatty acids using Sheppard conversion factors and then multiplied by total lipid (Nutrient No. 204) to give g fatty acid per 100 g edible portion of food. Occasionally, total lipid values are available from a variety of data sources, but individual fatty acids are available from fewer sources. In those cases, it may be necessary to normalize the individual fatty acids to the mean fat value of the food item. In the case of normalized fatty acids, the sum of the individual fatty acids will equal the mean fat value multiplied by the Weihrauch (1977) lipid conversion factor for that food item. No statistics of variability are reported for normalized fatty acids.

<u>Individual Fatty Acids</u>. The basic format for describing individual fatty acids is that the number before the colon indicates the number of carbon atoms in the fatty acid chain,

and the number after the colon indicates the number of double bonds. For unsaturated fatty acids, additional nutrient numbers have been added to accommodate the reporting of many specific positional and geometric isomers. Of the specific isomers, there are two basic classifications considered: omega double bond position and *cis/trans* configuration of double bonds.

Omega-3 (n-3) and omega-6 (n-6) isomers are denoted in shorthand nomenclature as n-3 and n-6. The n- number indicates the position of the first double bond from the methyl end of the carbon chain. The letter *c* or *t* indicates whether the bond is *cis* or *trans*. For polyunsaturated fatty acids, *cis* and *trans* configurations at successive double bonds may be indicated. For example, linoleic acid is an 18 carbon omega-6 fatty acid with 2 double bonds, both in *cis* configuration. When data are isomer specific, linoleic acid is described as 18:2 n-6 *c,c*. Other isomers of 18:2, for which nutrient numbers have now been assigned, include 18:2 *c,t*, 18:2 *t,t*; 18:2 *t* not further defined; and 18:2 *i*. 18:2 *i* is not a single isomer but includes isomers other than 18:2 n-6 *c,c* with peaks that cannot be easily differentiated in the particular food item. Systematic and common names for fatty acids are given in Table 2.

Table 2 is provided for the convenience of users in attaching common names or systematic names to fatty acids in this database. Though individual fatty acids are more specific than in past releases, it is not possible to include every possible geometric and positional isomer. Where specific isomers exist for a fatty acid, the common name of the most typical isomer is listed for the undifferentiated fatty acid and an asterisk (\*) designates the specific isomer by that name. For example, the most typical isomer for 18:1 is oleic. Thus, the specific isomer by that name, 18:1 c, is designated in Table 2 as oleic.

Table 2.—Systematic and Common Names for Fatty Acids

Fatty acid	Systematic name	Common name of most typical isomer	Nutrient number
Saturated fatty acids			
4:0	butanoic	butyric	607
6:0	hexanoic	caproic	608
8:0	octanoic	caprylic	609
10:0	decanoic	capric	610
12:0	dodecanoic	lauric	611
13:0	tridecanoic		696
14:0	tetradecanoic	myristic	612
15:0	pentadecanoic	•	652
16:0	hexadecanoic	palmitic	613
17:0	heptadecanoic	margaric	653
18:0	octadecanoic	stearic	614
20:0	eicosanoic	arachidic	615
22:0	docosanoic	behenic	624
24:0	tetracosanoic	lignoceric	654

Fatty acid	Systematic name	Common name of	Nutrient
		most typical isomer	number
Monounsaturated fatty acids			
14:1	tetradecenoic	myristoleic	625
15:1	pentadecenoic		697
16:1 undifferentiated	hexadecenoic	palmitoleic	626
16:1 <i>cis</i>			673*
16:1 <i>trans</i>			662
17:1	heptadecenoic		687
18:1 undifferentiated	octadecenoic	oleic	617
18:1 <i>ci</i> s			674*
18:1 <i>trans</i>			663
20:1	eicosenoic	gadoleic	628
22:1 undifferentiated	docosenoic	erucic	630
22:1 <i>ci</i> s			676*
22:1 <i>trans</i>			664
24:1 <i>cis</i>	cis-tetracosenoic	nervonic	671
Polyunsaturated fatty acids			
18:2 undifferentiated	octadecadienoic	linoleic	618
18:2 <i>trans</i> not further defined			665
18:2 <i>i</i> (mixed isomers)			666
18:2 n-6 <i>cis, ci</i> s			675*
18:2 trans, trans			669
18:2 conjugated linoleic acid (CLAs)			670
18:3 undifferentiated	octadecatrienoic	linolenic	619
18:3 n-3 <i>cis, cis, cis</i>		alpha-linolenic	851*
18:3 n-6 <i>cis, cis, ci</i> s		gamma-linolenic	685
18:3 trans (other isomers)			856
18:4	octadecatetraenoic	parinaric	627
20:2 n-6 <i>cis, cis</i>	eicosadienoic	·	672
20:3 undifferentiated	eicosatrienoic		689
20:3 n-3			852
20:3 n-6			853
20:4 undifferentiated	eicosatetraenoic	arachidonic	620
20:4 n-6			855
20:5 n-3	eicosapentaenoic (EPA)	timnodonic	629
21:5	. , ,		857
22:4			858
22:5 n-3	docosapentaenoic (DPA)	clupanodonic	631
22:6 n-3	docosahexaenoic (DHA)	•	621

<sup>\*</sup> Designates the specific isomer associated with the common name; the typical isomer is listed for the undifferentiated fatty acid.

<u>Fatty acid totals</u>. Only a small portion of the fatty acid data received for release in SR25 contains specific positional and geometric isomers. Therefore, it has been necessary to maintain the usual nutrient numbers corresponding to fatty acids with no further differentiation other than carbon length and number of double bonds. To aid users of our data, specific isomers are always summed to provide a total value for the undifferentiated fatty acid. For example, mean values for the specific isomers of 18:2 are summed to provide a mean for 18:2 undifferentiated (Nutrient No. 618). Other fatty acid totals provided are (1) the sum of saturated, monounsaturated, and polyunsaturated fatty acids and (2) the sum of *trans*-monoenoic, the sum of *trans*-polyenoic, and the sum of all *trans* fatty acids.

Values for total saturated, monounsaturated, and polyunsaturated fatty acids may include individual fatty acids not reported; therefore, the sum of their values may exceed the sum of the individual fatty acids. In rare cases, the sum of the individual fatty acids may exceed the sum of the values given for the total saturated fatty acids (SFA), monounsaturated fatty acids (MUFA), and polyunsaturated fatty acids (PUFA). These differences are generally caused by rounding and should be relatively small.

For multi-ingredient processed brand-name foods, industry data are often available for fatty acid classes (SFA, MUFA, and PUFA) but are lacking for individual fatty acids. In these cases, individual fatty acids are calculated from the fatty acids of the individually listed ingredients and normalized to the total fat level. A best-fit approximation has been made to fatty acid classes, but unavoidably, calculated sums of individual fatty acid totals do not always match industry data for fatty acid classes. Zero values for individual fatty acids should be understood to mean that trace amounts may be present. When g fatty acids per 100 g of total lipid are converted to g fatty acids per 100 g of food, values of less than 0.0005 are rounded to 0.

<u>Cholesterol</u>. Cholesterol values are generated primarily by gas liquid chromatographic procedures (AOAC 994.10). Recent meat data has been determined by a GC method without derivitization (Dinh *et al.* 2008). It is assumed that cholesterol is present only in foods of animal origin and foods containing at least one ingredient of animal origin (for example, cake that contains eggs). For mixtures containing ingredients derived from animal products, the cholesterol value may be calculated from the value for those ingredients. For foods that contain only plant products, the value for cholesterol is assumed to be zero.

<u>Plant sterols</u>. Data on plant sterols (campesterol, stigmasterol, and β-sitosterol) are obtained by gas-chromatographic procedures (AOAC 967.18) and summed to calculate total phytosterols (Nutr. No. 636). Plant sterols for a number of nuts, seeds, mushrooms, and other food items were determined by a gas-chromatographic method developed by Phillips *et al.* (2005) which includes an acid hydrolysis step. These data include additional sterols such as ergosterol or delta-5-avenasterol and various stanols plus some minor sterols that are not disseminated in SR. When available, data on these phytosterols are provided in a footnote for the specific food item. In these cases, Nutrient No. 636, total phytosterols, is not disseminated for these food items.

Amino Acids. Amino acid data for a class or species of food are aggregated to yield a set of values that serve as the pattern for calculating the amino acid profile of other similar foods. The amino acid values for the pattern are expressed on a per-gram-of-nitrogen basis. Amino acids are extracted in three groups—tryptophan, sulfur-containing amino acids (methionine and cystine), and all others. Tryptophan is determined by alkaline hydrolysis/HPLC (AOAC 988.15), methionine and cystine by performic oxidation/HPLC (AOAC 994.12) and all others by acid hydrolysis/HPLC (AOAC 982.30). Hydroxyproline in meats has been determined using a colorimetric method (AOAC 990.26). The amino acid patterns and the total nitrogen content are used to calculate the levels of individual amino acids per 100 g of food, using the following formula:

$$AA_f = (AA_n * V_p)/N_f$$

## Where:

 $AA_f$  = amino acid content per 100 g of food,  $AA_n$  = amino acid content per g of nitrogen,  $V_p$  = protein content of food, and  $N_f$  = nitrogen factor.

For foods processed in the NDBS since SR14 (2001), the number of observations used in developing an amino acid pattern will be released only with the pattern. The amino acid profiles calculated from these patterns will show the number of data points to be zero. In the past, the number of data points appeared only for the food item for which the amino acid pattern was developed, not on other foods that used the same pattern. It referred to the number of observations used in developing the amino acid pattern for that food.

If amino acid values are presented for an item with more than one protein-containing ingredient, the values may be calculated on a per-gram-of-nitrogen basis from the amino acid patterns of the various protein-containing ingredients. Then the amino acid contents for an item on the 100-g basis are calculated as the sum of the amino acids in each protein-containing ingredient multiplied by total nitrogen in the item. The number of data points for these values is given as zero.

## **Weights and Measures**

Information is provided on household measures for food items (for example, 1 cup, 1 tablespoon, 1 fruit, 1 leg). Weights are given for edible material without refuse, that is, the weight of an apple without the core or stem, or a chicken leg without the bone, and so forth. The Weight file contains the gram weights and measure descriptions for each food item. This file can be used to calculate nutrient values for food portions from the values provided per 100 g of food. The following formula is used to calculate the nutrient content per household measure:

N = (V\*W)/100

#### Where:

N = nutrient value per household measure.

V = nutrient value per 100 g (Nutr Val in the Nutrient Data file), and

W = g weight of portion (Gm\_Wgt in the Weight file).

The Weight file can be used to produce reports showing the household measure and nutrient values calculated for that portion. The weights are derived from published sources, industry files, studies conducted by USDA (Adams, 1975; Fulton *et al.*, 1977), and the weights and measures used in the FNDDS (2012). However, weight information is not available for all food items in the database. Though special efforts have been made to provide representative values, weights and measures obtained from different sources vary considerably for some foods. The format of this file is described on p. 34.

## **Footnotes**

Footnotes are provided for a few items where information about food description, weights and measures, or nutrient values could not be accommodated in existing fields. For example, if citric acid is added to a juice drink, this is indicated in the footnote. The format of this file is described on p. 35.

## **Sources of Data**

The Sources of Data file (previously called References) was first added with SR14 (2001). The name of the file and fields reflect the fact that not all sources are journals or published literature, but also include the results of unpublished data from USDA-sponsored research and from research sponsored by others either separately or in collaboration with USDA. It contains data sources for the nutrient values and links to an identification number on each nutrient record. Since some of the data in this release were carried forward from SR13 (1999), nutrient-specific source documentation is not electronically available. As new data for these foods are generated and as additional documentation is entered into the new NDBS, data source information will increase in future releases. The format of this file is described on p. 35.

A file, the Sources of Data Link file, is provided to allow users to establish a relationship between the Sources of Data file and the Nutrient Data file. This lets the user identify specific sources of data for each nutrient value. For example, the user can use these files to determine the dates associated with source documents for a particular data value. These files can also be used to determine values obtained from a particular data source, for example where NFNAP data is used in the database. The format of this file is described on p.35.

## **Explanation of File Formats**

The data appear in two different organizational formats. One is a relational format of four principal and six support files making up the database. The relational format is complete and contains all food, nutrient, and related data. The other is a flat abbreviated file with all the food items, but fewer nutrients, and not all of the other related information. The abbreviated file does not include values for starch, individual sugars, fluoride, betaine, vitamin  $D_2$  or  $D_3$ , added vitamin E, added vitamin  $B_{12}$ , alcohol, caffeine, theobromine, phytosterols, individual amino acids, or individual fatty acids. See p. 37 for more information on this file.

## **Relational Files**

The four principal database files are the Food Description file, Nutrient Data file, Gram Weight file, and Footnote file. The six support files are the Nutrient Definition file, Food Group Description file, Source Code file, Data Derivation Code Description file, Sources of Data file, and Sources of Data Link file. Table 3 shows the number of records in each file. In a relational database, these files can be linked together in a variety of combinations to produce queries and generate reports. Figure 1 provides a diagram of the relationships between files and their key fields.

Table 3. – Number of Records in Principal and Support Files

File name	Table name	Number of records
Principal files		
Food Description	FOOD_DES	8,194
Nutrient Data	NUT_DATA	595,359
Weight	WEIGHT	14,162
Footnote	FOOTNOTE	525
Support files		
Food Group Description	FD_GROUP	25
LanguaL Factor	LANGUAL	39,085
LanguaL Factors Description	LANGDESC	774
Nutrient Definition	NUTR_DEF	146
Source Code	SRC_CD	10
Data Derivation Description	DERIV_CD	54
Sources of Data	DATA_SRC	610
Sources of Data Link	DATSRCLN	187,720

The relational files are provided in both ASCII format and a Microsoft Access 2003 database. Tables 4 through 13 describe the formats of these files. Information on the relationships that can be made among these files is also given. Fields that always contain data and fields that can be left blank or null are identified in the "blank" column; N indicates a field that is always filled; Y indicates a field that may be left blank (null) (Tables 4-13). An asterisk (\*) indicates primary key(s) for the file. Though keys are not identified for the ASCII files, the file descriptions show where keys are used to sort and manage records within the NDBS. When importing these files into a database management system, if keys are to be identified for the files, it is important to use the keys listed here, particularly with the Nutrient Data file, which uses two.

Food Description File Food Group Description File NDB No. Food Group Code Food Group Code Nutrient Definition File Footnote File Nutrient No. NDB No. Source Code File Source Code Nutrient Data File NDB No. Nutrient No. Data Derivation File Source Code Data Derivation Code **Derivation Code** Sources of Data Link File NDB No. Gram Weight File DataSrc ID NDB No. Sources of Data File DataSrc ID LanguaL Factor File LanguaL Factors Description File NDB No Factor Code Factor Code

Figure 1. Relationships among files in the USDA National Nutrient Database for Standard Reference \*

<sup>\*</sup> Underlined items denote key fields.

ASCII files are delimited. All fields are separated by carets (^) and text fields are surrounded by tildes (~). A double caret (^^) or two carets and two tildes (~~) appear when a field is null or blank. Format descriptions include the name of each field, its type [N = numeric with width and number of decimals (w.d) or A = alphanumeric], and maximum record length. The actual length in the data files may be less and most likely will change in later releases. Values will be padded with trailing zeroes when imported into various software packages, depending on the formats used.

**Food Description File** (file name = FOOD\_DES). This file (Table 4) contains long and short descriptions and food group designators for 8,194 food items, along with common names, manufacturer name, scientific name, percentage and description of refuse, and factors used for calculating protein and kilocalories, if applicable. Items used in the FNDDS are also identified by value of "Y" in the Survey field.

- Links to the Food Group Description file by the FdGrp Cd field
- Links to the Nutrient Data file by the NDB\_No field
- · Links to the Weight file by the NDB No field
- Links to the Footnote file by the NDB\_No field
- Links to the Langual Factor file by the NDB No field

**Table 4.—Food Description File Format** 

Field name	Туре	Blank	Description
NDB_No	A 5*	N	5-digit Nutrient Databank number that uniquely identifies a food item. If this field is defined as numeric, the leading zero will be lost.
FdGrp_Cd	A 4	N	4-digit code indicating food group to which a food item belongs.
Long_Desc	A 200	N	200-character description of food item.
Shrt_Desc	A 60	N	60-character abbreviated description of food item. Generated from the 200-character description using abbreviations in Appendix A. If short description is longer than 60 characters, additional abbreviations are made.
ComName	A 100	Y	Other names commonly used to describe a food, including local or regional names for various foods, for example, "soda" or "pop" for "carbonated beverages."
ManufacName	A 65	Υ	Indicates the company that manufactured the product, when appropriate.

Field name	Туре	Blank	Description
Survey	A 1	Y	Indicates if the food item is used in the USDA Food and Nutrient Database for Dietary Studies (FNDDS) and thus has a complete nutrient profile for the 65 FNDDS nutrients.
Ref_desc	A 135	Υ	Description of inedible parts of a food item (refuse), such as seeds or bone.
Refuse	N 2	Υ	Percentage of refuse.
SciName	A 65	Y	Scientific name of the food item. Given for the least processed form of the food (usually raw), if applicable.
N_Factor	N 4.2	Υ	Factor for converting nitrogen to protein (see p. 11).
Pro_Factor	N 4.2	Υ	Factor for calculating calories from protein (see p. 12).
Fat_Factor	N 4.2	Υ	Factor for calculating calories from fat (see p. 12).
CHO_Factor	N 4.2	Υ	Factor for calculating calories from carbohydrate (see p. 12).

<sup>\*</sup> Primary key for the Food Description file.

**Food Group Description File** (file name = FD\_GROUP). This file (Table 5) is a support file to the Food Description file and contains a list of food groups used in SR25 and their descriptions.

• Links to the Food Description file by FdGrp\_Cd

**Table 5.—Food Group Description File Format** 

Field name	Туре	Blank	Description
FdGrp_Cd	A 4*	N	4-digit code identifying a food group. Only the first 2 digits are currently assigned. In the future, the last 2 digits may be used. Codes may not be consecutive.
FdGrp_Desc	A 60	N	Name of food group.

<sup>\*</sup> Primary key for the Food Group Description file.

**Langual Factor File** (File name = LANGUAL). This file (Table 6) is a support file to the Food Description file and contains the factors from the Langual Thesaurus used to code a particular food.

- Links to the Food Description file by the NDB\_No field
- Links to Langual Factors Description file by the Factor Code field

**Table 6.—Langual Factor File Format** 

Field name	Type	Blank	Description
NDB_No	A 5*	N	5-digit Nutrient Databank number that uniquely identifies a food item. If this field is defined as numeric, the leading zero will be lost.
Factor_Code	A 5*	N	The LanguaL factor from the Thesaurus

<sup>\*</sup> Primary key for the Langual Factor file.

**Langual Factors Description File** (File name = LANGDESC). This file (Table 7) is a support file to the Langual Factor file and contains the descriptions for only those factors used in coding the selected food items codes in this release of SR.

Links to the Langual Factor File by the Factor\_Code field

**Table 7.—Langual Factors Description File Format** 

Field name	Type	Blank	Description
Factor_Code	A 5*	N	The LanguaL factor from the Thesaurus. Only those codes used to factor the foods contained in the
Description	A 140	N	LanguaL Factor file are included in this file The description of the LanguaL Factor Code from the thesaurus

<sup>\*</sup> Primary key for the Langual Factor Description file.

**Nutrient Data File** (file name = NUT\_DATA). This file (Table 8) contains the nutrient values and information about the values, including expanded statistical information.

- Links to the Food Description file by NDB No.
- Links to the Food Description file by Ref\_NDB\_No.
- Links to the Weight file by NDB No.
- Links to the Footnote file by NDB\_No and when applicable, Nutr\_No.
- Links to the Nutrient Definition file by Nutr No.
- Links to the Source Code file by Src Cd
- Links to the Derivation Code file by Deriv Cd

**Table 8.—Nutrient Data File Format** 

Field name	Туре	Blank	Description
NDB_No	A 5*	Ν	5-digit Nutrient Databank number.
Nutr_No	A 3*	Ν	Unique 3-digit identifier code for a nutrient .
Nutr_Val	N 10.3	Ν	Amount in 100 grams, edible portion †.
Num_Data_Pts	N 5.0	N	Number of data points (previously called Sample_Ct) is the number of analyses used to calculate the nutrient value. If the number of data points is 0, the value was calculated or imputed.
Std_Error	N 8.3	Υ	Standard error of the mean. Null if cannot be calculated. The standard error is also not given if the number of data points is less than three.
Src_Cd	A 2	Ν	Code indicating type of data.
Deriv_Cd	A 4	Υ	Data Derivation Code giving specific information on how the value is determined
Ref_NDB_No	A 5	Y	NDB number of the item used to impute a missing value. Populated only for items added or updated starting with SR14.
Add_Nutr_Mark	A 1	Y	Indicates a vitamin or mineral added for fortification or enrichment. This field is populated for ready-to-eat breakfast cereals and many brand-name hot cereals in food group 8.
Num_Studies	N 2	Υ	Number of studies.
Min	N 10.3	Υ	Minimum value.
Max	N 10.3	Υ	Maximum value.
DF	N 4	Υ	Degrees of freedom.
Low_EB	N 10.3	Υ	Lower 95% error bound.
Up_EB	N 10.3	Υ	Upper 95% error bound.
Stat_cmt	A 10	Υ	Statistical comments. See definitions below.
AddMod_Date	A10	Υ	Indicates when a value was either added to the database or last modified.

Field name	Туре	Blank	Description
CC	A 1	Y	Confidence Code indicating data quality, based on evaluation of sample plan, sample handling, analytical method, analytical quality control, and number of samples analyzed. Not included in this release, but is planned for future releases.

<sup>\*</sup> Primary keys for the Nutrient Data file.

Definitions of each statistical comment included in the Nutrient Data table follow:

- 1. The displayed summary statistics were computed from data containing some less-than values. Less-than, trace, and not-detected values were calculated.
- 2. The displayed degrees of freedom were computed using Satterthwaite's approximation (Korz and Johnson, 1988).
- 3. The procedure used to estimate the reliability of the generic mean requires that the data associated with each study be a simple random sample from all the products associated with the given data source (for example, manufacturer, variety, cultivar, and species).
- 4. For this nutrient, one or more data sources had only one observation. Therefore, the standard errors, degrees of freedom, and error bounds were computed from the between-group standard deviation of the weighted groups having only one observation.

**Nutrient Definition File** (file name = NUTR\_DEF). This file (Table 9) is a support file to the Nutrient Data file. It provides the 3-digit nutrient code, unit of measure, INFOODS tagname, and description.

Links to the Nutrient Data file by Nutr No.

**Table 9.—Nutrient Definition File Format** 

Field name	Туре	Blank	Description
Nutr_No	A 3*	N	Unique 3-digit identifier code for a nutrient.
Units	A 7	N	Units of measure (mg, g, µg, and so on).
Tagname	A 20	Y	International Network of Food Data Systems (INFOODS) Tagnames.† A unique abbreviation for a nutrient/food component developed by INFOODS to aid in the interchange of data.
NutrDesc	A 60	N	Name of nutrient/food component.

<sup>†</sup> Nutrient values have been rounded to a specified number of decimal places for each nutrient. Number of decimal places is listed in the Nutrient Definition file.

Field name	Туре	Blank	Description
Num_Dec	A 1	N	Number of decimal places to which a nutrient value is rounded.
SR_Order	N 6	N	Used to sort nutrient records in the same order as various reports produced from SR.

<sup>\*</sup> Primary key for the Nutrient Definition file.

**Source Code File** (file name = SRC\_CD). This file (Table 10) contains codes indicating the type of data (analytical, calculated, assumed zero, and so on) in the Nutrient Data file. To improve the usability of the database and to provide values for the FNDDS, NDL staff imputed nutrient values for a number of proximate components, total dietary fiber, total sugar, and vitamin and mineral values.

Links to the Nutrient Data file by Src Cd

**Table 10.—Source Code File Format** 

Field name	Type	Blank	Description
Src_Cd	A 2*	N	2-digit code.
SrcCd_Desc	A 60	N	Description of source code that identifies the type of nutrient data.

<sup>\*</sup> Primary key for the Source Code file.

**Data Derivation Code Description File** (file name = DERIV\_CD). This file (Table 11) provides information on how the nutrient values were determined. The file contains the derivation codes and their descriptions.

Links to the Nutrient Data file by Deriv Cd

**Table 11.—Data Derivation Code File Format** 

Field name	Type	Blank	Description
Deriv_Cd	A 4*	N	Derivation Code.
Deriv_Desc	A 120	N	Description of derivation code giving specific information on how the value was determined.

<sup>\*</sup> Primary key for the Data Derivation Code file.

For example, the data derivation code that indicates how  $\alpha$ -tocopherol (Nutrient No. 323) in Emu, fan fillet, raw (NDB. No. 05623) was calculated is BFSN. The breakdown

<sup>†</sup> INFOODS, 2009.

of the code is as follows:

B = based on another form of the food or a similar food;

F = concentration adjustment used;

S = solids, the specific concentration adjustment used; and

N = retention factors not used

The Ref\_NDB\_No is 05621 Emu, ground, raw. This means that the analytical  $\alpha$ -tocopherol value in the total solids of emu, ground, raw is used to calculate the  $\alpha$ -tocopherol in the total solids of emu, fan fillet, raw.

$$N_t = (N_s * S_s)/S_t$$

### where

 $N_t$  = the nutrient content of the target item,

N<sub>s</sub> = the nutrient content of the source item,

For NDB No. 05621,  $\alpha$ -tocopherol = 0.24 mg/100 g

 $S_s$  = the total solids content of the source item, and

For NDB No. 05621, solids = 27.13 g/100 g S<sub>t</sub> = the total solids content of the target item.

For NDB No. 05623, solids = 2538 g/100 g

So, using this formula for the above example:

 $N_t = (0.24 \times 25.38)/27.13 = 0.22 \text{ mg}/100 \text{ g} \alpha\text{-tocopherol in Emu, fan fillet, raw}$ 

Only items that were imputed starting with SR14 (2001) will have both derivation codes and reference NDB numbers. Other items that have been imputed outside the NDBS will have data derivation codes, but the Ref\_NDB\_No field will be blank.

**Weight File** (file name = WEIGHT). This file (Table 12) contains the weight in grams of a number of common measures for each food item.

- Links to Food Description file by NDB\_No.
- Links to Nutrient Data file by NDB No.

**Table 12.— Weight File Format** 

Field name	Type	Blank	Description
NDB_No	A 5*	N	5-digit Nutrient Databank number.
Seq	A 2*	Ν	Sequence number.
Amount	N 5.3	N	Unit modifier (for example, 1 in "1 cup").
Msre_Desc	A 84	N	Description (for example, cup, diced, and 1-inch pieces).

Field name	Туре	Blank	Description
Gm_Wgt	N 7.1	N	Gram weight.
Num_Data_Pts	N 3	Υ	Number of data points.
Std_Dev	N 7.3	Υ	Standard deviation.

<sup>\*</sup> Primary key for the Weight file.

**Footnote File** (file name = FOOTNOTE). This file (Table 13) contains additional information about the food item, household weight, and nutrient value.

- Links to the Food Description file by NDB\_No.
- Links to the Nutrient Data file by NDB No and when applicable, Nutr No.
- Links to the Nutrient Definition file by Nutr No, when applicable.

**Table 13.—Footnote File Format** 

Field name	Type	Blank	Description
NDB_No	A 5	N	5-digit Nutrient Databank number.
Footnt_No	A 4	N	Sequence number. If a given footnote applies to more than one nutrient number, the same footnote number is used. As a result, this file cannot be indexed.
Footnt_Typ	A 1	N	Type of footnote: D = footnote adding information to the food description;
			M = footnote adding information to measure description;
			N = footnote providing additional information on a nutrient value. If the Footnt_typ = N, the Nutr_No will also be filled in.
Nutr_No	A 3	Υ	Unique 3-digit identifier code for a nutrient to which footnote applies.
Footnt_Txt	A 200	N	Footnote text.

**Sources of Data Link File** (file name = DATSRCLN). This file (Table 14) is used to link the Nutrient Data file with the Sources of Data table. It is needed to resolve the many-to-many relationship between the two tables.

- Links to the Nutrient Data file by NDB No. and Nutr\_No.
- Links to the Nutrient Definition file by Nutr No
- Links to the Sources of Data file by DataSrc ID.

**Table 14.—Sources of Data Link File Format** 

Field name	Type	Blank	Description
NDB_No	A 5*	N	5-digit Nutrient Databank number.
Nutr_No	A 3*	N	Unique 3-digit identifier code for a nutrient.
DataSrc_ID	A 6*	N	Unique ID identifying the reference/source.

<sup>\*</sup> Primary key for the Sources of Data Link file.

**Sources of Data File** (file name = DATA\_SRC). This file (Table 15) provides a citation to the DataSrc ID in the Sources of Data Link file.

• Links to Nutrient Data file by NDB No. through the Sources of Data Link file

**Table 15.—Sources of Data File Format** 

Field name	Type	Blank	Description
DataSrc_ID	A 6*	Ν	Unique number identifying the reference/source.
Authors	A 255	Υ	List of authors for a journal article or name of sponsoring organization for other documents.
Title	A 255	N	Title of article or name of document, such as a report from a company or trade association.
Year	A 4	Υ	Year article or document was published.
Journal	A 135	Υ	Name of the journal in which the article was published.
Vol_City	A 16	Υ	Volume number for journal articles, books, or reports; city where sponsoring organization is located.
Issue_State	A 5	Υ	Issue number for journal article; State where the sponsoring organization is located.
Start_Page	A 5	Υ	Starting page number of article/document.
End_Page	A 5	Υ	Ending page number of article/document.

<sup>\*</sup> Primary key for the Sources of Data file.

### **Abbreviated File**

The Abbreviated file (file name = ABBREV) is available in ASCII format and as a Microsoft Excel spreadsheet. It contains all the food items found in the relational database, but with fewer nutrients and other related information. The abbreviated file does not include values for starch, fluoride, betaine, vitamin D<sub>2</sub> and D<sub>3</sub>, added vitamin E, added vitamin B<sub>12</sub>, alcohol, caffeine, theobromine, phytosterols, individual amino acids, individual fatty acids, or sugars. Table 16 lists all the nutrients included in the abbreviated file. Starting with SR22 (2009), Vitamin D in µg and IU was added to the Abbreviated file. The ASCII file (Table 16) is in delimited format. Fields are separated by a caret (^) and text fields are surrounded by tildes (~). Data refer to 100 g of the edible portion of the food item. Decimal points are included in the fields. Missing values are denoted by the null value of two consecutive carets (^^) or two carets and two tildes (~~). The file is sorted in ascending order by the NDB number. Two common measures are provided, which are the first two common measures in the Weight file for each NDB number. To obtain values per one of the common measures, multiply the value in the desired nutrient field by the value in the desired common measure field and divide by 100. For example, to calculate the amount of fat in 1 tablespoon of butter (NDB No. 01001),

 $V_{H}=(N*CM)/100$ 

#### where:

Vh = the nutrient content per the desired common measure N = the nutrient content per 100 g
For NDB No. 01001, fat = 81.11 g/100 g
CM = grams of the common measure
For NDB No. 01001, 1 tablespoon = 14.2 g

So using this formula for the above example:

Vh = (81.11\*14.2)/100 = 11.52 g fat in 1 tablespoon of butter

This file is a flat file and is provided for those users who do not need a relational database. It contains the information in one record per food item and is suitable for importing into a spreadsheet. The data file has been imported into a Microsoft Excel 2003 spreadsheet for users of that application. Users of other software applications can import either the Microsoft Excel 2003 spreadsheet or the ASCII files. If additional information is needed, this file can be linked to the other SR files by the NDB number.

**Table 16.—Abbreviated File Format** 

Field name	Type	Description
NDB_No.	A 5*	5-digit Nutrient Databank number.
Shrt_Desc	A 60	60-character abbreviated description of food item.†

Field name	Type	Description
Water	N 10.2	Water (g/100 g)
Energ_Kcal	N 10	Food energy (kcal/100 g)
Protein	N 10.2	Protein (g/100 g)
Lipid_Tot	N 10.2	Total lipid (fat)(g/100 g)
Ash	N 10.2	Ash (g/100 g)
Carbohydrt	N 10.2	Carbohydrate, by difference (g/100 g)
Fiber_TD	N 10.1	Total dietary fiber (g/100 g)
Sugar_Tot	N 10.2	Total sugars (g/100 g)
Calcium	N 10	Calcium (mg/100 g)
Iron	N 10.2	Iron (mg/100 g)
Magnesium	N 10	Magnesium (mg/100 g)
Phosphorus	N 10	Phosphorus (mg/100 g)
Potassium	N 10	Potassium (mg/100 g)
Sodium	N 10	Sodium (mg/100 g)
Zinc	N 10.2	Zinc (mg/100 g)
Copper	N 10.3	Copper (mg/100 g)
Manganese	N 10.3	Manganese (mg/100 g)
Selenium	N 10.1	Selenium (µg/100 g)
Vit_C	N 10.1	Vitamin C (mg/100 g)
Thiamin	N 10.3	Thiamin (mg/100 g)
Riboflavin	N 10.3	Riboflavin (mg/100 g)
Niacin	N 10.3	Niacin (mg/100 g)
Panto_acid	N 10.3	Pantothenic acid (mg/100 g)
Vit_B6	N 10.3	Vitamin B <sub>6</sub> (mg/100 g)
Folate_Tot	N 10	Folate, total (µg/100 g)
Folic_acid	N 10	Folic acid (µg/100 g)
Food_Folate	N 10	Food folate (µg/100 g)
Folate_DFE	N 10	Folate (µg dietary folate equivalents/100 g)
Choline_Tot	N 10	Choline, total (mg/100 g)
Vit_B12	N 10.2	Vitamin B <sub>12</sub> (μg/100 g)
Vit_A_IU	N 10	Vitamin A (IU/100 g)

Field name	Туре	Description
Vit_A_RAE	N 10	Vitamin A (µg retinol activity equivalents/100g)
Retinol	N 10	Retinol (μg/100 g)
Alpha_Carot	N 10	Alpha-carotene (μg/100 g)
Beta_Carot	N 10	Beta-carotene (µg/100 g)
Beta_Crypt	N 10	Beta-cryptoxanthin (µg/100 g)
Lycopene	N 10	Lycopene (µg/100 g)
Lut+Zea	N 10	Lutein+zeazanthin (µg/100 g)
Vit_E	N 10.2	Vitamin E (alpha-tocopherol) (mg/100 g)
Vit_D_mcg	N 10.1	Vitamin D (μg/100 g)
Vit_D_IU	N 10	Vitamin D (IU/100 g)
Vit_K	N 10.1	Vitamin K (phylloquinone) (μg/100 g)
FA_Sat	N 10.3	Saturated fatty acid (g/100 g)
FA_Mono	N 10.3	Monounsaturated fatty acids (g/100 g)
FA_Poly	N 10.3	Polyunsaturated fatty acids (g/100 g)
Cholestrl	N 10.3	Cholesterol (mg/100 g)
GmWt_1	N 9.2	First household weight for this item from the Weight file.‡
GmWt_Desc1	A 120	Description of household weight number 1.
GmWt_2	N 9.2	Second household weight for this item from the Weight file.‡
GmWt_Desc2	A 120	Description of household weight number 2.
Refuse_Pct	N 2	Percent refuse.§

<sup>\*</sup> Primary key for the Abbreviated file.

## **Update Files**

The update files contain changes made between SR24 (2011) and SR25 (2012). Update files in ASCII are provided for those users who reformatted previous releases for their systems and wish to do their own updates. If a release earlier than SR24 is used, it is necessary to first obtain the update files for that release through SR24, update the database to SR24, and then use the update files provided with SR25. The

<sup>†</sup> For a 200-character description and other descriptive information, link to the Food Description file.

<sup>‡</sup> For the complete list and description of the measure, link to the Weight file.

<sup>§</sup> For a description of refuse, link to the Food Description file.

earlier update files are available on NDL's web site: http://www.ars.usda.gov/nutrientdata.

New data added to SR25 are given in the following files:

- ADD\_FOOD for descriptions of the new items,
- ADD NUTR for added nutrient data,
- ADD\_WGT for added weight and measure data,
- ADD FTNT for added footnotes,

These files are in the same formats as the Food Description file, the Nutrient Data file, the Weight file, and the Footnote file.

Five files contain changes made since SR24 (2011):

- CHG\_FOOD contains records with changes in the descriptive information for a food item.
- CHG\_NUTR contains changes to the following fields: nutrient values, standard errors, number of data points, source code, and data derivation code. CHG\_WGT contains records with changes to the gram weights or measure information.
- CHG FTNT contains records with changes to footnotes.
- CHG NDEF contains records with changes to the nutrient definitions.
- CHG FDGP contains records with changes to the food group descriptions.

If the values in any fields have changed, the entire record is included for that file. These files are in the same format as the Food Description, Nutrient Data, Weight, Nutrient Definition and Food Group files.

Four files contain records that were deleted since SR24 (2011):

- DEL\_FOOD file (Table 17) lists those food items that were deleted from the database.
- DEL\_NUTR file (Table 18) lists those nutrient values that were removed from the database.
- DEL\_WGT contains any gram weights that were removed. These records are in the same format as the Weight file (Table 12).
- DEL\_FTNT contains any footnotes that were removed from the database (Table 19).
   Starting with SR19, if a given footnote applied to more than one nutrient number, the same footnote number can be used. When these footnote numbers are updated, the extra footnotes are deleted.

**Table 17.—Foods Deleted Format** 

Field name	Type	Blank	Description
NDB_No	A 5*	N	Unique 5-digit number identifying deleted item.
Shrt_Desc	A 60	N	60-character abbreviated description of food item.

<sup>\*</sup> Primary key for Foods Deleted file.

Table 18. —Nutrients Deleted Format

Field name	Type	Blank	Description
NDB_No	A 5*	N	Unique 5-digit number identifying the item that contains the deleted nutrient record.
Nutr_No	A 3	N	Nutrient number of deleted record.

<sup>\*</sup> Primary key for Nutrients Deleted file.

**Table 19.—Footnotes Deleted Format** 

Field name	Туре	Blank	Description
NDB_No	A 5*	N	Unique 5-digit number identifying the item that contains the deleted nutrient record.
Footnt_No	A 4	N	Sequence number.
Footnt_Typ	A 1	N	Type of footnote of deleted record.

<sup>\*</sup> Primary key for Footnotes Deleted file.

Update files in ASCII are also provided for the Abbreviated file:

- CHG\_ABBR file contains records for food items where a food description, household weight, refuse value, or nutrient value have been added, changed, or deleted since SR24. This file is in the same format as the Abbreviated file (Table 16).
- DEL\_ABBR contains food items that have been removed from the database; it is in the same format as DEL\_FOOD.
- ADD\_ABBR contains food items added since SR24; it is also in the same format as the Abbreviated file.

# **Summary**

A number of food items have been added to the database using new data from NFNAP, the food industry, and other sources. Other foods have had nutrient values updates. In particular, the sodium content of those foods which are major contributors of sodium to the diet—primarily processed foods— has been targeted for nutrient analysis. A number of food items, no longer on the market, such as certain processed foods, have been removed. These are described in "Specific Changes for SR25" (p. 1). The next release, SR26, available during summer 2013, will contain additional items and updates.

## **References Cited in the Documentation**

Adams, C.F. 1975. Nutritive Value of American Foods in Common Units. U.S. Department of Agriculture, Agricultural Handbook 456.

AOAC International. 2010. Official Methods of Analysis, 18th ed., AOAC International, Gaithersburg, MD. http://www.aoac.org

Booth, S.L., K.W. Davidson, and J.A. Sadowski. 1994. Evaluation of an HPLC method for the determination of phylloquinone (vitamin  $K_1$ ) in various food matrices. Journal of Agricultural and Food Chemistry 42:295-300.

Byrdwell, W. C., J. Devries, J. Exler, J.M. Harnly, J.M. Holden, M.F. Holick, B.W. Hollis, R.L. Horst, M. Lada, L.E. Lemar, K.Y. Patterson, K.M. Philips, M.T. Tarrago-Trani, W.R. Wolf. 2008. Analyzing vitamin D in foods and supplements: methodologic challenges. American Journal of Clinical Nutrition. 88(2):554S-557S.

Chun, J., Martin, J.A., Chen, L., Lee, J., Ye, L., Eitenmiller, R. 2004. A differential assay of folic acid and total folate in foods containing enriched cereal-grain products to calculate µg dietary folate equivalents (µg DFE). Journal of Food Composition and Analysis 19(2-3):182-187.

Craft, N. 2001. Chromatographic techniques for carotenoid separation. *In* Current Protocols Food Analytical Chemistry. F2.3.1–F2.3.15. Wrolstad, R. E., Acree, T. E., Decker, E. A., Penner, M. H., Reid, D. S., Schwartz, S. J., Shoemaker, C. F., Sporns, P., Editors. Wiley.. New York.

Dietary Guidelines Advisory Committee (DGAC). 2004. The Report of the Dietary Guidelines Advisory Committee on Dietary Guidelines for Americans, 2005. Available from http://www.health.gov/dietaryguidelines/dga2005/report/default.htm (accessed 07/06/2012).

Dinh, T.T.N., Blanton Jr., J.R., Brooks, J.C., Miller, M.F., Thompson, L.D. 2008. A simplified method for cholesterol determination in meat and meat products. Journal of Food Composition and Analysis 21:306-314.

Fulton, L., E. Matthews, and C. Davis. 1977. Average Weight of a Measured Cup of Various Foods. U.S. Department of Agriculture, Home Economics Research Report 41.

Gebhardt, S.E., and R.G. Thomas. 2002. Nutritive Value of Foods. U.S. Department of Agriculture, Home and Garden Bulletin 72.\*

Haytowitz, D.B., P.R. Pehrsson, and J.M Holden. 2008. The national food and nutrient analysis program: a decade of progress. Journal of Food Composition and Analysis 21(Supp. 1):S94-S102.\*

Holden, J.M., S.A. Bhagwat, and K.Y. Patterson. 2002. Development of a multi-nutrient data quality evaluation system. Journal of Food Composition and Analysis 15(4):339–348.\*

Holden, J.M., A.L. Eldridge, G.R. Beecher, Buzzard, I.M. Bhagwat, S.A., Davis, C.S., Douglass, Larry W., Gebhardt, S.E., Haytowitz, D.B., and Schakel, S.. 1999. Carotenoid content of U.S. foods: An update of the database. Journal of Food Composition and Analysis 12:169–196.\*

Huang M., Winters, D. 2011. Application of Ultra-Performance Liquid Chromatography/Tandem Mass Spectrometry for the Measurement of Vitamin D in Foods and Nutritional Supplements. Journals of AOAC International 94:211-223.

INFOODS. 2012. Tagnames for Food Components. INFOODS web site. http://www.fao.org/infoods/tagnames\_en.stm. (Accessed 7/6/2012).

Institute of Medicine. 1998. Dietary reference intakes for thiamin, riboflavin, niacin, vitamin B<sub>6</sub>, folate, vitamin B<sub>12</sub>, pantothenic acid, biotin, and choline. National Academy Press, Washington, DC.

Institute of Medicine. 2000. Dietary reference intakes for vitamin C, vitamin E, selenium, and carotenoids. National Academy Press, Washington, DC.

Institute of Medicine. 2001. Dietary reference intakes for vitamin A, vitamin K, arsenic, boron, chromium, copper, iodine, iron, manganese, molybdenum, nickel, silicon, vanadium, and zinc. National Academy Press, Washington, DC.

Institute of Medicine. 2011. Dietary reference intakes for vitamin D and Calcium. National Academy Press, Washington, DC.

Jones, D.B. 1941. Factors for Converting Percentages of Nitrogen in Foods and Feeds into Percentages of Protein. U.S. Department of Agriculture, Circular 83, slight revision.\*

Koc, H., Mar, M. H., Ranasinghe, A., Swenberg, J. A., and Zeisel, S. H. 2002. Quantitation of choline and its metabolites in tissues and foods by liquid chromatography/electrospray ionization-isotope dilution mass spectrometry. Analytical Chemistry 74:4734-4740.

Korz, S., and N.L. Johnson. 1988. Encyclopedia of Statistical Sciences. Vol. 8, pp. 261–262, John Wiley and Son, New York, NY.

Kubota, J., and W.H. Allaway. 1972. Geographic distribution of trace element problems. *In* J.J. Mortvedt, ed., Micronutrients in Agriculture: Proceedings of Symposium held at Muscle Shoals, Alabama, pp. 525–554. Soil Science Society of America, Madison, WI.

Leonard, S.W., C.K. Good, E.T. Gugger, and M.G. Traber. 2004. Vitamin E bioavailability from fortified breakfast cereal is greater than that from encapsulated supplements. American Journal of Clinical Nutrition 79:86–92.

Liem, I.I.H., K.H. Steinkraus, and J.C. Cronk. 1977. Production of vitamin B<sub>12</sub> in tempeh: A fermented soybean food. Applied Environmental Microbiology 34:773–776.

Livesay, G., and E. Marinos. 1988. Estimation of energy expenditure, net carbohydrate utilization, and net fat oxidation and synthesis by indirect calorimetry: Evaluation of errors with special reference to the detailed composition of fuels. American Journal of Clinical Nutrition 47:608–628.

Mangels, A.R., J.M. Holden, G.R. Beecher, et al. 1993. Carotenoid content of fruits and vegetables: An evaluation of analytic data. Journal of the American Dietetic Association 93:284–296.

Martin, J.I., W.O. Landen, A.M. Soliman, and R.R. Eitenmiller. 1990. Application of a trienzyme extraction for total folate determination in foods. Journal of the Association of Analytical Chemistry 73:805–808.

Matthews, R.H., and Y.J. Garrison. 1975. Food Yields Summarized by Different Stages of Ppreparation. U.S. Department of Agriculture, Agriculture Handbook 102.\*

Merrill, A.L., and B.K. Watt. 1973. Energy Value of Foods: Basis and Derivation, revised. U.S. Department of Agriculture, Agriculture Handbook 74.\*

Møller A., and Ireland J. 2009. LanguaL 2009 – The LanguaL thesaurus. EuroFIR Technical Report D1.8.43. Danish Food Information. LanguaL Web site: http://www.langual.org/langual\_literature.asp (Accessed 7/6/2012)

Murphy, E.W., P.E. Criner, and B.C. Gray. 1975. Comparison of methods for determining retentions of nutrients in cooked foods. Journal of Agriculture and Food Chemistry 23:1153.\*

National Research Council. 1989. Recommended dietary allowances, 10th ed. National Academy Press, Washington, DC.

Phillips, K.M., Ruggio, D.M., and Ashraf-Khorassani, M. 2005. Phytosterol composition of nuts and seeds commonly consumed in the United States. Journal of Agricultural and Food Chemistry 53(24): 9436-9445.

Phillips K.M., W.C. Byrdwell, J. Exler, J.M. Harnly, J.M. Holden, M.F. Holick, B.W. Hollis, R.L. Horst, L.E. Lemar, K.Y. Patterson, M.T.Tarrago-Trani, and W.R. Wolf. 2008. Development and validation of control materials for the measurement of vitamin D<sub>3</sub> in selected US foods. Journal of Food Composition and Analysis 21:527-534.

- Reamer, D.C., and C. Veillon. 1981. Determination of selenium in biological materials by stable isotope dilution gas chromatography-mass spectrometry. Analytical Chemistry 53(14):2166–2169.
- Schakel, S.F., I.M. Buzzard, and S.E. Gebhardt. 1997. Procedures for estimating nutrient values in food composition databases. Journal of Food Composition and Analysis 10:102–114.\*
- Sheppard, A.J. 1992. Lipid Manual: Methodology Suitable for Fatty acid-Cholesterol Analysis. William C. Brown Publishers, Dubuque, IA.
- U.S. Department of Agriculture, Agricultural Research Service. 1976. Composition of Foods: Dairy and Egg products; raw, processed, prepared. Agriculture Handbook 8–1.
- U.S. Department of Agriculture, Agricultural Research Service. 1977. Composition of Foods: Spices and herbs; raw, processed, prepared. Agriculture Handbook 8–2.
- U.S. Department of Agriculture, Agricultural Research Service. 1978. Composition of Foods: Baby foods; raw, processed, prepared. Agriculture Handbook 8–3.
- U.S. Department of Agriculture, Agricultural Research Service. 1979. Composition of Foods: Fats and oils; raw, processed, prepared. Agriculture Handbook 8–4.
- U.S. Department of Agriculture, Agricultural Research Service. 1979. Composition of Foods: Poultry products; raw, processed, prepared. Agriculture Handbook 8–5.
- U.S Department of Agriculture, Agricultural Research Service. 1980. Composition of Foods Soups, sauces, and gravies; raw, processed, prepared. Agriculture Handbook 8–6.
- U.S. Department of Agriculture, Agricultural Research Service. 1980. Composition of Foods Sausages and luncheon meats; raw, processed, prepared. Agriculture Handbook 8–7.
- U.S. Department of Agriculture, Agricultural Research Service. 1982. Composition of Foods Breakfast cereals; raw, processed, prepared. Agriculture Handbook 8–8.
- U.S. Department of Agriculture, Agricultural Research Service. 1982. Composition of Foods Fruits and fruit juices; raw, processed, prepared. Agriculture Handbook 8–9.
- U.S. Department of Agriculture, Agricultural Research Service. 1992. Composition of Foods Pork products; raw, processed, prepared. Agriculture Handbook 8–10.
- U.S. Department of Agriculture, Agricultural Research Service. 1984. Composition of Foods Vegetables and vegetable products; raw, processed, prepared. Agriculture Handbook 8–11.

- U.S. Department of Agriculture, Agricultural Research Service. 1984. Composition of Foods Nut and seed products; raw, processed, prepared. Agriculture Handbook 8–12.
- U.S. Department of Agriculture, Agricultural Research Service. 1990. Composition of Foods Beef products; raw, processed, prepared. Agriculture Handbook 8–13.
- U.S. Department of Agriculture, Agricultural Research Service. 1986. Composition of Foods Beverages; raw, processed, prepared. Agriculture Handbook 8–14.
- U.S. Department of Agriculture, Agricultural Research Service. 1987. Composition of Foods Finfish and shellfish products; raw, processed, prepared. Agriculture Handbook 8–15.
- U.S. Department of Agriculture, Agricultural Research Service. 1986. Composition of Foods Legumes and legume products; raw, processed, prepared. Agriculture Handbook 8–16.
- U.S. Department of Agriculture, Agricultural Research Service. 1989. Composition of Foods Lamb, veal, and game products; raw, processed, prepared. Agriculture Handbook 8–17.
- U.S. Department of Agriculture, Agricultural Research Service. 1992. Composition of Foods Baked products; raw, processed, prepared. Agriculture Handbook 8–18.
- U.S. Department of Agriculture, Agricultural Research Service. 1991. Composition of Foods Snacks and sweets; raw, processed, prepared. Agriculture Handbook 8–19.
- U.S. Department of Agriculture, Agricultural Research Service. 1989. Composition of Foods Cereal grains and pasta; raw, processed, prepared. Agriculture Handbook 8–20.
- U.S. Department of Agriculture, Agricultural Research Service. 1988. Composition of Foods Fast foods; raw, processed, prepared. Agriculture Handbook 8–21.
- U.S. Department of Agriculture, Agricultural Research Service. 1990. Composition of Foods Raw, processed, prepared. Agriculture Handbook 8, 1989 Supplement.
- U.S. Department of Agriculture, Agricultural Research Service. 1991. Composition of Foods Raw, processed, prepared. Agriculture Handbook 8, 1990 Supplement.
- U.S. Department of Agriculture, Agricultural Research Service. 1992. Composition of Foods Raw, processed, prepared. Agriculture Handbook 8, 1991 Supplement.
- U.S. Department of Agriculture, Agricultural Research Service. 1993. Composition of Foods Raw, processed, prepared. Agriculture Handbook 8, 1992 Supplement.

- U.S. Department of Agriculture, Agricultural Research Service. 1992. Provisional Table on the Selenium Content of Foods. USDA, HNIS, PT–109.
- U.S. Department of Agriculture. 2007. USDA Table of Nutrient Retention Factors, Release 6. Nutrient Data Laboratory Home Page at http://www.ars.usda.gov/Main/docs.htm?docid=9448. (Accessed 7/6/2012)\*
- U.S. Department of Agriculture, Agricultural Research Service. 2004. USDA Database for the Choline Content of Common Foods. Nutrient Data Laboratory web site: http://www.ars.usda.gov/nutrientdata/choline. (Accessed 7/6/2012)\*
- U.S. Department of Agriculture, Agricultural Research Service. 2005. USDA National Fluoride Database of Selected Beverages and Foods Release 2. Nutrient Data Laboratory web site: http://www.ars.usda.gov/nutrientdata/fluoride. (Accessed 7/6/2012)\*
- U.S. Department of Agriculture, Agricultural Research Service. 2012. USDA Food and Nutrient Database for Dietary Studies (release 5.0) [database]. Food Surveys Research Group web site: http://www.ars.usda.gov/ba/bhnrc/fsrg (Accessed 7/6/2012)
- U.S. Food and Drug Administration, Department of Health and Human Services. 2012. Food Labeling. Code of Federal Regulations, Title 21, Pt. 101. U.S. Government Printing Office web site: http://www.gpo.gov/fdsys/browse/collectionCfr.action?collectionCode=CFR (Accessed

http://www.gpo.gov/fdsys/browse/collectionCfr.action?collectionCode=CFR (Accessed 7/6/2012).

Van Winkle S, Levy S.M., Kiritsy M.C., Heilman J.R., Wefel J.S., Marshall T. 1995. Water and formula fluoride concentrations: Significance for infants fed formula. Pediatric Dentistry. 17(4):305-310.

Watt, B.K., and A.L. Merrill. 1963. Composition of Foods Raw, Processed, Prepared. U.S. Department of Agriculture, Agriculture Handbook 8.

Weihrauch, J.L., and A.S. Chatra. 1994. Provisional Table on the Vitamin K Content of Foods, Revised. USDA, HNIS, PT–104.\*

Weihrauch, J.L., L.P. Posati, B.A. Anderson, and J. Exler. 1977. Lipid conversion factors for calculating fatty acid content of foods. Journal of the American Oil Chemists Society 54:36–40.

Weihrauch, J.L., and J. Tamaki. 1991. Provisional Table on the Vitamin D Content of Foods. USDA, HNIS, PT–108.\*

Williams, J., Patterson, K., Howe, J. (Retired), Snyder, C., Boillot, K., Lofgren, P., Thompson, L., Luna, A., Nalawade, A., Douglass, L., Holden, J. 2009. Nutrient Composition in Ground Pork using Regression Techniques (Poster). Institute of Food Technologists Annual Meeting + Food Expo. Anaheim, CA. June 6-9, 2009, http://www.ars.usda.gov/SP2UserFiles/Place/12354500/Articles/IFT09\_GrdPork.pdf (Accessed 7/6/2012) \*

Ye, L., Landen, W.O., and Ronald R. Eitenmiller, R.R. 2000. Ye, Landen, Eitenmiller Liquid Chromatographic Analysis of *all-trans*-Retinyl Palmitate, β-Carotene, and Vitamin E in Fortified Foods and the Extraction of Encapsulated and Nonencapsulated Retinyl Palmitate. Journal of Agricultural and Food Chemistry. 48(9):4003-8.

Zeisel, S. H., and Blusztajn, J. K. 1994. Choline and human nutrition. Annual Reviews of Nutrition. 14:269-296

Zeisel, S.H., Mar, M.H., Howe, J. C., Holden, J. M. 2003. Concentrations of choline – containing compounds and betaine in common foods. Journal of Nutrition 133:1302-1307; Erratum. 2003. Journal of Nutrition. 133:2918-2919

<sup>\*</sup> Available on NDL's web site: http://www.ars.usda.gov/nutrientdata

### **Notes on Foods**

### Introduction

The information contained in "Notes on Foods" was initially published in printed copies of Agriculture Handbook No. 8 (AH-8), which were presented as individual sections by food groups. In addition to a description of the tables and how nutrient values were determined, each food group section included a portion, called "Notes on Foods" with information specific to each food group. The information on the database, nutrient values and formats has been published separately as the documentation accompanying each release of the USDA National Nutrient Database for Standard Reference (SR; NDL, 2011). At this time, "Notes on Foods" are included in this document for only some of the sections previously available in the printed copies. It is anticipated that this document will expand, as information for the remaining food groups is added.

Data are obtained from a variety of sources. These include the scientific literature, data provided by food companies and trade associations, other government agencies and USDA-sponsored contracts. In a number of cases, various trade associations have worked with the Nutrient Data Laboratory (NDL) to design analytical studies to obtain new data on various food items. These studies are described in greater detail in their respective sections below. Since 1997, USDA-sponsored contracts have been conducted under the aegis of the National Food and Nutrient Analysis Program (NFNAP), which is described below.

## National Food and Nutrient Analysis Program

In 1997, the NDL, in cooperation with the National Heart Lung and Blood Institute and other Institutes and Offices of the National Institutes of Health (NIH), instituted the National Food and Nutrient Analysis Program. In 2005, The National Cancer Institute took over the lead role in coordinating the program at NIH. The goals of NFNAP are to improve the quantity and quality of data in the USDA National Nutrient Databank which has resulted in annual updates of the USDA National Nutrient Database for Standard Reference (NDL, 2011) and a number of Special Interest Databases: isoflavones (NDL, 2008), choline (NDL, 2004a), proanthocyanidins (NDL, 2004b), fluoride (NDL, 2005), and flavonoids (NDL, 2011). To achieve these goals, five principle aims were established:

- 1. Identify and rank foods and nutrients for analysis
- 2. Evaluate existing data for foods and nutrients
- 3. Develop strategies for sampling
- 4. Process and analyze foods
- 5. Review and disseminate results

Since its inception in 1997, over 1,900 food items have been sampled and analyzed under NFNAP. To date, values for over 1,600 of these food items have been

incorporated into SR. The process of acquiring, evaluating, and disseminating food composition data is continuous. At any time, new samples are being collected, prepared and analyzed and data for samples already analyzed are being revised and processed through NDL's Nutrient Data Bank System (NDBS). Details of these studies are described in specific chapters on each food group, which follow this section. A number of trade associations in the food industry, such as the National Cattleman's Beef Association, the National Pork Board, the Produce for Better Health Foundation, the Mushroom Council, the American Egg Board and others have worked with NDL to analyze food items in their product category sectors, using protocols adapted as part of NFNAP. Details of each of these studies are described in the specific chapter for each food group.

### Identify Key Foods and critical nutrients for sampling and analysis

To identify and rank foods and nutrients for analysis, the Key Foods approach (Haytowitz et al., 2000; Haytowitz et al., 2002) was used. Key Foods are those foods which in aggregate contribute 75% of the nutrient intake for selected nutrients of public health importance from the diet. The most current Key Foods list was generated using weighted data for two-day food consumption data from the National Health and Nutrition Examination Survey (NHANES) 2007-08 Data Files (NCHS, 2010) and food composition data from SR22 (issued in 2009). For the current Key Foods list, targeted nutrients (total fat, food energy, total sugar, total dietary fiber, calcium, iron, potassium, sodium, β-carotene, α-tocopherol, vitamin C, vitamin B<sub>12</sub>, choline, cholesterol and saturated fatty acids) were those identified in the Dietary Guidelines Advisory Committee Report on the Dietary Guidelines for Americans, 2010 (DGAC, 2010) and the Dietary Guidelines for Americans, 2010 (USDA & USDHHS, 2010) as "shortfall" nutrients (limited in the diet) or nutrients of excess consumption, in particular those associated with poor health outcomes. Other nutrients of concern such as trans fatty acids and added sugar were considered but not included in the Key Foods algorithm as only those nutrients included in the Food and Nutrient Database for Dietary Surveys (FNDDS), 5.0 (USDA-ARS, 2012) can be used. The Key Foods approach has allowed NDL to concentrate analytical resources on those foods that contribute significant amounts of nutrients of public health interest to the diet.

### Evaluate existing data for scientific quality

At the initiation of NFNAP in 1997, the food composition values in SR were reviewed for scientific quality by NDL staff. Data for many of the foods in the database at that time were found to be more than 10 years old, based on a limited number of values, lacking in complete and accurate documentation, and including some samples of uncertain origin. To assess the quality of existing data and to improve the level of documentation, NDL scientists developed an expert system for evaluating data quality (Holden *et al.*, 2002; Holden *et al.*, 2005). The expert system focuses on evaluation and documentation of five data quality indicators: 1) sampling plan; 2) sample handling; 3) number of samples analyzed; 4) analytical methodology; and 5) analytical quality control. This system has been used in the production of a number of special interest

databases including isoflavones (NDL, 2008), choline (NDL, 2004a), proanthocyanidins (NDL, 2004b), fluoride (NDL, 2005), and flavonoids (NDL, 2007). This process is used to provide information on the data quality assessment for all of the analytical nutrient profiles for foods in SR. Many of the food profiles in the database lacked some or all of the data quality information. For these reasons, and to establish a core set of data of known sampling, analytical methodology, and quality control, NDL determined that comprehensive updates of the food items on the Key Foods list would be needed.

Devise and implement a probability-based sampling survey of U.S. foods

A probability-proportional-to-size (PPS) food sampling plan was developed by NDL staff in collaboration with statisticians from the National Agricultural Statistics Service, USDA (Pehrsson et al., 2000). This approach allows the development of nationally representative data for a given food. The original NFNAP food product sampling design was based on a stratified design including each of four regions across the 48 conterminous states of nearly equal in population size. A revised PPS sampling design was developed with 2000 U.S. Census data (Perry et al., 2003) and was based on a stratified three-stage design using 2001 Census Bureau projected state population sizes and Census regions (U.S. Census Bureau, 2002). Forty-eight geographically dispersed counties were selected at the first stage, supermarket outlets at the second stage, and specific food products at the third stage. Subsets of these locations can be selected according to the requirements of the specific food item and nutrients, weighing variability vs. reliability. Multiples of these geographic locations can also be employed for studies requiring more samples, i.e., where wide variability in a nutrient is expected and/or existing data are limited or nonexistent. Fluoride, for example, is highly variable in drinking water; in a national USDA study, drinking water was sampled in 144 locations and over two seasons (Pehrsson et al., 2006). Another consideration in designing the sampling strategy was that fewer samples would be analyzed for lower consumption foods as identified during the Key Foods process or for nutrients in foods which were not significant contributors to the diet or present in low or trace concentrations. Details of the sampling design are discussed in Perry et al. (2003). This sampling plan will be updated in the future to use data from the 2010 U.S. Census.

Specific food products were selected according to a sampling approach based on market share. For example, after examining the Key Foods list, it was determined that pizza was a major contributor of many nutrients. However, the FNDDS does not differentiate between pizzas purchased from a fast food pizza restaurant vs. those purchased frozen and heated and served at home. Consequently, NDL undertook the analysis of both types. Several different types (e.g., cheese, pepperoni, pepperoni and sausage, and meat/vegetable combinations) and brands (e.g., major national brands and store brands) were purchased in supermarkets as described above. Later, several different types (e.g., cheese, pepperoni, and deluxe) of fast food restaurant pizza from major national chains were purchased from individual restaurants. For frozen pizzas, national composites of each type and brand were prepared. For the fast food restaurant pizzas, four composites of three randomly drawn samples of each type and brand were

## prepared.

Foods were purchased under contract by a USDA-directed professional product pickup company using tested selection protocols in retail outlets. The foods were shipped to the Food Analysis Laboratory Control Center (FALCC) at Virginia Polytechnic Institute and State University in Blacksburg, Virginia for sample preparation. Procedures were developed for sample unit receipt, preparation, and storage which can be modified as needed for new food samples. FALCC continuously develops protocols for homogenizing and compositing samples based on instructions from NDL. FALCC also collects relevant weights and dissection information for edible and non-edible portions as required, and documents processing and preparation procedures. Processed samples are shipped to USDA-qualified analytical laboratories for analysis as directed by NDL. Reserve and archive samples of each food are maintained at FALCC.

The sampling plan can be modified to meet the requirements of a specific study of specific nutrients or unique foods, e.g., the sampling of tap water in homes to determine fluoride levels. With modifications, the sampling plan can be used for special population groups located in geographically distinct areas (e.g., American Indians and Alaska Natives on reservations, and Hispanic Americans (Perry *et al.* 2002)).

Analyze sampled foods under USDA-supervised laboratory contracts

NDL employs a two-step process for awarding contracts for analysis of foods. The first step requires prospective contractors to submit a formal proposal. Prospective contractors are asked to include a study plan in their proposal with detailed plans and procedures for conducting the nutrient analysis of Key Foods, as well as identifying the analytical methods and procedures they will use to complete each task. The description of analytical methods includes sample handling and storage, extraction or digestion, analysis, and quantification steps performed as part of the analysis. The laboratories propose specific analytical methods, based on their expertise, which are examined by NDL during the review of the proposals. A detailed discussion of day-to-day quality control (QC) procedures is requested to facilitate the assessment of accuracy and precision for the unknown samples. The commercial laboratory proposals are evaluated by a panel consisting of NDL and other ARS staff members. The proposals are reviewed and scored against criteria delineated in the Request for Proposals.

Those offerors whose proposals are deemed technically acceptable are sent "check" samples by FALCC for analysis. These are Certified Reference Materials (CRMs) procured from a variety of sources, both in the U.S. and at the global level. Nutrient-specific analytical results generated by offerors for these samples are evaluated against acceptable ranges prepared by NDL. Offerors with the best written proposals and analytical results on the check samples may be awarded a contract for specific nutrients. Specific work orders under each contract are awarded such that contractors will not be given analytical work for nutrients where results for the check samples were outside the acceptable range.

Aliquots of each food composite are sent to the laboratories by FALCC for analysis according to the work plans developed by NDL. The methods of analysis employed by the various analytical laboratories are given in Table 20. Along with the samples, FALCC includes a QC material, which is either a control composite developed at FALCC or a CRM purchased from a certifying organization (Phillips *et al.*, 2006). The laboratories are required to provide the results of their in-house quality control runs with the results for the analytical samples. The results from the laboratories are then reviewed by a quality control committee comprised of NDL and FALCC staff. The QC data for CRMs are compared to the certificate values for the material and the results for control composites are compared to a database of all results obtained for the particular control composites. Analytical data for food samples are compared to existing data for that food or a similar food. Questions are referred to the laboratories, and, if necessary, the analyses are repeated.

Table 20. Methods of analysis used by NFNAP laboratories

Nutrient	Technique	Methods Identification		
Protein (Nitrogen)	Combustion	AOAC 968.06 (4.2.04) Protein (Crude) in Animal Feed		
	Combustion	AOAC 990.03 Protein (Crude) in Animal Feed		
	Combustion	AOAC 992.15 (39.1.16) Crude Protein in Meat and Meat Products		
		Including Pet Foods		
	Kjeldahl	AOAC 991.20 Nitrogen (Total) in Milk		
Total Fat	Acid hydrolysis	AOAC 989.05 (33.2.26) Fat in Milk, Mojo, Acid Hydrolysis		
	Acid hydrolysis	AOAC 922.06 (32.1.14) Fat in Flour, Acid Hydrolysis Method		
	Acid hydrolysis	AOAC 925.12 (32.5.05) Fat in Macaroni Products		
	Acid hydrolysis	AOAC 954.02 (4.5.02 or 7.063) Fat (Crude) or Ether Extract in Pet		
		Food		
	Extraction	AOAC 920.39 Fat (Crude) or Ether Extract in Animal Feed		
	Extraction	AOAC 933.05 Fat in Cheese		
	Extraction	AOAC 960.39 (39.1.05) Fat (Crude) or Ether Extract in Meat		
	Extraction	AOAC 983.23 (45.4.02) Fat in Foods, Chloroform-Methanol		
		Extraction Method		
	Extraction Folch <i>et al.</i> , (1957) J. Biol. Chem., 226; 497-509.			
	Extraction	Phillips et al. Simplified Gravimetric Determination of Total Fat in		
		Mixed Food Composites After Chloroform/Methanol Extraction J.		
		Amer. Oil Chem. Soc., 74 (1997)p. 137-142		
	Extraction	AOAC 989.05 Fat in Milk		
Ash	Gravimetric	AOAC 923.03 (32.1.05 or 14.006) Ash of Flour		
	Gravimetric	AOAC 942.05 (4.1.10) Ash of Animal Feed		
	Gravimetric	AOAC 945.46 Ash of Milk		
Moisture	Vacuum oven	AOAC 934.01 (4.1.03) Moisture in Animal Feed		
	Vacuum oven	AOAC 934.06 (37.1.10) Moisture in Fruits, Vegetables, and their		
		Products		
	Vacuum oven	AOAC 964.22 (42.1.05) Solids (Total) in Canned Vegetables:		
		Gravimetric Method		
	Forced air	AOAC 950.46 (39.1.02) Moisture in Meat		
Fiber	Enzymatic-	AOAC 991.43 (32.1.17) Total, Soluble, and Insoluble Dietary Fiber in		
	gravimetric	Foods		
	Enzymatic-	AOAC 985.29 (45.4.07) Total Dietary Fiber in Foods		
	gravimetric			
Starch	Enzymatic-	AOAC 979.10 (32.2.05) Starch in Cereals, Glucoamylase Method		
	colorimetric			
·	·	53		

Nutrient	Technique	Methods Identification
	Polarimetric	The Feedings Stuffs (Sampling and Analysis) Regulations 1982 No. 1144, Agriculture, London
Sugars	LC	AOAC 982.14 (32.2.07) Glucose, Fructose, Sucrose, and Maltose in Presweetened Cereals
Minerals	ICP	AOAC 984.27 Ca, Cu, Fe, Mg, Mn, P, K, Na and Zn in Infant Formula
Willicials	Atomic	Laboratory modified AOAC 968.08 (4.8.02) + 985.35 (50.1.14) +
	absorption	965.05 (2.6.01) Metals in Food by AAS
	ICP	Laboratory modified AOAC 985.01 (3.2.06) + 984.27 (50.1.15) Metals in Food by ICP
Selenium	Isotope dilution GC/MS	Reamer & Veillon, Anal. Chem., 53, (1981) 2166
	Hydride	AOAC 986.15 (9.1.01) Arsenic, Cadmium, Lead, Selenium and Zinc
	generation	in Human and Pet Foods
Retinol	HPLC	AOAC 974.29 (modified for HPLC) Vitamin A in Mixed Feeds, Premixes, and Foods and Int'l Vitamin Nutrition (1992) (modified for HPLC determination) or a laboratory modified method with UV & fluorescent detection
Fluoride	Specific ion electrode	VanWinkle, Levy et al., Pediatr. Dent., 17 (1995) p305 (direct-read)
	Microdiffusion	VanWinkle, Levy <i>et al.</i> , Pediatr. Dent., 17 (1995) p305 (microdiffusion)
Vitamin E	GC	Cort <i>et al.</i> , J Agr Food Chem (1983) 31:1330-1333 + Speek <i>et al.</i> , J Food Sci (1985) 50:121-124 + McMurray <i>et al.</i> , J AOAC (1980) 63:1258-1261
	LC	Ye, Landen, Eitenmiller J Agric Food Chem. 2000 Sep;48(9):4003-8.
Carotenoids	HPLC	AOAC 941.15 (45.1.03) modified by Quackenbush, J. Liq. Chroma. (1987) 10:643-653
	HPLC	Craft, N. 2001. Chromatographic techniques for carotenoid separation. <i>In</i> Current Protocols in Food Analytical Chemistry. F2.3.1–F2.3.15. Wrolstad, R. E., Acree, T. E., Decker, E. A., Penner, M. H., Reid, D. S., Schwartz, S. J., Shoemaker, C. F.,
Thispasia	Fluence at at a	Sporns, P., Editors. Wiley New York.
Thiamin	Fluorometric	AOAC 942.23 Thiamine (B1) in Foods
Riboflavin	Microbiological	Laboratory modified AOAC 940.33 (45.2.06) Riboflavin (Vitamin B2) in Vitamin Preparations
	Fluorometric	AOAC 970.65 Riboflavin (Vitamin B2) in Foods and Vitamin Preparations (Fluorometric)
Niacin	Microbiological	Laboratory modified AOAC 944.13 (45.2.04) Niacin and Niacinamide (Nicotinic Acid and Nicotinamide) in Vitamin Preparations
Pantothenic acid	Microbiological	AOAC 945.74 (45.2.05) Pantothenic Acid in Vitamin Preparations
	Microbiological	AOAC 992.07 (50.1.22) Pantothenic Acid in Milk-Based Infant Formula
Vitamin B6	Microbiological	AOAC 961.15 (45.2.08) Vitamin B6 (Pyridoxine, Pyridoxal, and Pyridoxamine) in Food Extracts (Microbiological)
Vitamin B12	Microbiological	AOAC 952.20 (45.2.02) Cobalamin (Vitamin B12 Activity) in Vitamin Preparations
Total folate	Microbiological	Martin et al. J Assoc Off Anal Chem. 1990 Sep-Oct;73(5):805-8.
Choline	LC/ESI/MS	Koc et al. (Zeisel), Quantitation of Choline and its Metabolites in Tissues and Foods by LC/ESI/MS. Anal. Chem. (2002) 74:4734-4740

Nutrient	Technique	Methods Identification		
Vitamin D	LC	AOAC 995.05 (50.1.23) Vitamin D in Infant Formulas and Enteral		
		Products		
	HPLC	AOAC 982.29 (45.1.22) Vitamin D in Mixed Feeds, Premixes, and		
		Pet Foods		
	HPLC	Birdwell et al. Am J Clin Nutr 88 (2008) 554S-557S		
	LC/MS/MS	Huang, Luzerne, Winters & Sullivan, JAOAC Int., 92 (2009) p1327- 1335		
Vitamin C	Microfluorometric	AOAC 967.22 (45.1.15) Vitamin C (Total ) in Vitamin Preparations		
Vitamin K	HPLC	Booth & Sadowski, Methods Enzymol., (1997) 282:446 (HPLC)		
Cholesterol	GC/Direct saponification	AOAC 994.10 (45.4.10) Cholesterol in Foods		
	GC/Direct	Dinh et al. J Food Comp Anal, 21 (2008) p306-314		
	saponification			
	Acid Hydrolysis-	AOAC 982.30 (45.3.05) (modified) Protein Efficiency Ratio (Ninhydrin		
	HPLC	post column)		
	Alk. hydrolysis-	AOAC 988.15 (modified) Tryptophan in Foods and Food and Feed		
	HPLC	Ingredients		
	Colorimetric	990.26 (39.1.27) Hydroxyproline in Meat and Meat products		
	Performic	994.12 (4.1.11) (modified) Amino Acids in Feed (OPA post column)		
	oxidation-HPLC			
Amino acids	Alk. hydrolysis-	AOAC 988.15 (modified) Tryptophan in Foods and Food and Feed		
	HPLC	Ingredients		
	Performic	AOAC 994.12 (4.1.11) (modified) Amino Acids in Feed (OPA post		
	oxidation-HPLC	column)		
	Acid Hydrolysis-	AOAC 982.30 (45.3.05) (modified) Protein Efficiency Ratio (Ninhydrin		
	HPLC	post column)		
	Colorimetric	AOAC 990.26 (39.1.27) Hydroxyproline in Meat and Meat products		
Fatty acids	GLC	CE 1-62 (1997) Fatty Acid Composition by Gas Chromatography		
	GLC	AOCS Ce 1-62 for GC, and Ce 2-66 for prep of methyl esters		
	GLC	AOAC 996.06 (41.1.28A) Fat (Total, Saturated and		
		Monounsaturated) in Foods		
	GLC	AOAC 996.06 (41.1.28A) Fat (Total, Saturated, and Unsaturated) in		
		Foods & AOCS Ce 1c-89 Fatty Acid Composition by Gas		
		Chromatography (modified)		

## Compile newly generated data to update the National Nutrient Databank

The acceptable data from the analytical laboratories are then combined with the descriptive information collected on the sample units and are migrated to NDL's Nutrient Databank System, which was designed with three levels (Initial, Aggregated, and Compiled) to manage and process food composition data (Haytowitz *et al*, 2009). In the Initial step, all the individual data points are maintained along with complete information on methods of analysis, analytical quality control, sample handling, common measures, component and refuse data, and the source and sampling information for each sample unit. Information is also retained on how individual sample units are composited. Values are converted to standard units of measure per 100 g, but the "as received" data values are also retained. In the Aggregated step, NDL scientists make decisions on how to group the data (e.g., combining data from different sources or a single source), weight the data (usually by market share or production information), and/or handle new

data when data already exist for a food item (i.e., replace the old data or combine it with new data). Specialized statistical procedures are used to aggregate the groups of data and generate descriptive statistics which take into consideration the grouping and nature of the data. NDL scientists also use statistical procedures within the NDBS to compare sets of data and test for outliers. For food items used in the FNDDS, missing data are imputed according to scientific principles (Schakel et al., 1998) at the Compiled step. Missing values can be calculated using the recipe or formulation modules within the databank system. These modules are based on linear regression and are often used to generate a few missing values for some foods and complete nutrient profiles for other foods. The formulation regression program uses nutrient values and ingredients (in a specified order) from product labels. The recipe program uses known amounts from authoritative sources to generate a specific food nutrient profile. Finally, the name of the food item is finalized, common measures are selected and ranked, and the item is approved for release. Prior to release, the data are sent to experts for review; brand name items are sent to food companies or appropriate trade associations, and other foods are sent to analysts or other specialists familiar with the food and its nutrient content. The experts indicate if the data are acceptable based on their knowledge of the products and if any changes are recommended. If changes are made, the data are disseminated in annual releases of the SR database.

# References for Notes on Foods – National Food and Nutrient Analysis Program

Dietary Guidelines Advisory Committee (DGAC). 2010. Report of the Dietary Guidelines Advisory Committee on the *Dietary Guidelines for Americans*, 2010. <a href="http://www.cnpp.usda.gov/DGAs2010-DGACReport.htm">http://www.cnpp.usda.gov/DGAs2010-DGACReport.htm</a> (Accessed 7/6/2012).

- U.S. Department of Agriculture (USDA) and U.S. Department of Health and Human Services (USDHHS). *Dietary Guidelines for Americans*, 2010. 7<sup>th</sup> Edition. http://www.cnpp.usda.gov/DGAs2010-PolicyDocument.htm (Accessed 7/6/2012).
- U.S. Department of Agriculture, Agricultural Research Service. 2012. USDA Food and Nutrient Database for Dietary Studies (release 5.0) [database]. Food Surveys Research Group web site: http://www.ars.usda.gov/ba/bhnrc/fsrg (Accessed 7/6/2012)

Haytowitz, D.B., Pehrsson, P.R., Holden, J.M. 2000. Setting Priorities for Nutrient Analysis in Diverse Populations. Journal of Food Composition and Analysis 13, 425-433.

Haytowitz, D.B., Pehrsson, P.R., Holden, J.M. 2002. The Identification of Key Foods for Food Composition Research. Journal of Food Composition and Analysis 15, 183-194.

Haytowitz, D.B., Lemar, L.E., Pehrsson, P.R. 2009. USDA's Nutrient Databank System—A tool for handling Data from Diverse Sources. Journal of Food Composition

and Analysis. 22, 433-441.

Holden, J.M., Bhagwat, S.A, Patterson, K.Y. 2002. Development of a Multi-Nutrient Data Quality Evaluation System. Journal of Food Composition and Analysis 15, 339-348.

Holden, J.M., Bhagwat, S.A., Haytowitz, D., Gebhardt, S., Dwyer, J., Peterson, J., Beecher, G.R., Eldridge, A.L. 2005. Development of a database of critically evaluated flavonoid data: application of USDA's data quality evaluation system. Journal of Food Composition and Analysis 18, 829-844.

National Center for Health Statistics (NCHS), Center for Disease Control and Prevention (CDC), Department of Health and Human Services (DHHS). 2010. National Health and Nutrition Examination Survey 2007-2008 Data Files. http://www.cdc.gov/nchs/nhanes/nhanes2007-2008/nhanes07\_08.htm (Accessed 7/6/2012).

Nutrient Data Laboratory (NDL), Agricultural Research Service (ARS), U.S. Department of Agriculture (USDA). 2004a. USDA Database on the Choline Content of Common Foods - 2004. http://www.ars.usda.gov/nutrientdata. (Accessed 7/6/2012).

Nutrient Data Laboratory (NDL), Agricultural Research Service (ARS), U.S. Department of Agriculture (USDA). 2004b. USDA Database for the Proanthocyanidin Content of Foods - 2004. <a href="http://www.ars.usda.gov/nutrientdata">http://www.ars.usda.gov/nutrientdata</a>. (Accessed 7/6/2012).

Nutrient Data Laboratory (NDL), Agricultural Research Service (ARS), U.S. Department of Agriculture (USDA). 2005. USDA National Fluoride Database of Selected Beverages and Foods, Release 2 (2005). <a href="http://www.ars.usda.gov/nutrientdata">http://www.ars.usda.gov/nutrientdata</a>. (Accessed 7/6/2012).

Nutrient Data Laboratory (NDL), Agricultural Research Service (ARS), U.S. Department of Agriculture (USDA). 2011. National Nutrient Database for Standard Reference, Release 24. http://www.ars.usda.gov/Services/docs.htm?docid=8964 (Accessed 7/6/2012).

Nutrient Data Laboratory (NDL), Agricultural Research Service (ARS), U.S. Department of Agriculture (USDA). 2011. USDA Database on the Flavonoid Content of Foods, Release 3.0 – 2011. <a href="http://www.ars.usda.gov/nutrientdata">http://www.ars.usda.gov/nutrientdata</a> (Accessed 7/6/2012).

Nutrient Data Laboratory (NDL), Agricultural Research Service (ARS), U.S. Department of Agriculture. 2008. USDA for the Isoflavone Content of Selected Foods, Release 2.0. <a href="http://www.ars.usda.gov/nutrientdata">http://www.ars.usda.gov/nutrientdata</a>. (Accessed 7/6/2012).

Nutrient Data Laboratory (NDL), Agricultural Research Service (ARS), U.S. Department of Agriculture (USDA). 2010. National Nutrient Database for Standard Reference, Release 23. http://www.ars.usda.gov/Services/docs.htm?docid=22115. (Accessed 7/6/2012).

Pehrsson PR, Haytowitz DB, Holden JM, Perry CR, Beckler DG. 2000. USDA's National Food and Nutrient Analysis Program: Food Sampling. Journal of Food Composition and Analysis 12, 379-89.

Pehrsson, P.R., Perry, C.R., Cutrufelli, R.L., Patterson, K.Y., Wilger, J., Haytowitz, D.B., Holden, J.M., Day, C.D., Himes, J.H., Harnack, L., Levy, S., Wefel, J., Heilman, J., Phillips, K., Rasor, A. 2006. Sampling and initial findings for a national study of fluoride in drinking water. Journal of Food Composition and Analysis 19, S45-S52.

Perry, C.P., Beckler, D.G., Bellow M.E., Gregory L.G., Pehrsson, P.R. 2002. Alaska Native and American Indian Tribe Sampling Frame Construction and Sample Design for the National Food and Nutrient Analysis Program. 2001. 2001 Proceedings of the American Statistical Association

http://www.amstat.org/sections/srms/proceedings/y2001f.html (Accessed 7/6/2012)

Perry, C.R, Pehrsson P.R., Holden J. 2003. A Revised Sampling Plan for Obtaining Food Products for Nutrient Analysis for the USDA National Nutrient Database. 2003 Proceedings of the American Statistical Association (CD-ROM). http://www.amstat.org/sections/srms/proceedings/y2003f.html. (Accessed 7/6/2012)

Phillips, K.M, Wunderlich, K.M, Holden, J.M., Exler, J., Gebhardt, S.E., Haytowitz, D., Beecher, G.R., Doherty, R.F. 2005. Stability of 5-methyltetrahydrofolate in frozen fresh fruits and vegetables. *Food Chem.* 92:587-595.

Phillips, K.M., Patterson, K.Y., Rasor, A.S., Exler, J., Haytowitz, D.B., Holden, J.M., Pehrsson, P.R. 2006. Quality-control materials in the USDA National Food and Nutrient Analysis Program (NFNAP). *Anal. Bioanal. Chem.* 384(6):1341-1355.

Schakel, S.F., Buzzard, I.M., Gebhardt, S.E. 1998. Procedures for Estimating Nutrient Values for Food Composition Databases. *J. Food Comp. Anal.* 10:102-114.

U.S. Census Bureau. 2002. U.S. Census Bureau Population Estimates 2001. http://www.census.gov/popest/data/historical/2000s/vintage\_2002/index.html (Accessed 7/11/2012)

## **Beef Products (Food Group 13)**

## Introduction

Data for beef products are presented in the USDA National Nutrient Database for Standard Reference. For most retail cuts, nutrient values are presented for cuts trimmed to 1/8-inch and 0-inch fat and for Choice or Select quality grades. Nutrient values reported as "All Grades" were estimated by combining the nutrient values for Choice and Select grades, weighted by their market proportions. A few Prime cuts trimmed at 1/8 inch external fat are also included.

The data in SR represent the amount of each constituent in 100 grams of edible portion. The edible portion in beef may be represented as "separable lean and fat" or as "separable lean only". In both cases, bone and connective tissue are removed from the cut and reported as refuse. In the case of "separable lean and fat", it is assumed that all fat present is consumed. For items described as "separable lean only", all external trim fat and seam fat are removed from the cut, weighed, and included in the reported refuse. Weights are determined for the whole retail cut as purchased, and for each component (e.g., separable lean, separable fat, refuse, etc.). Nutrient analyses are conducted on the separable lean and the separable fat. The external trim fat and the seam fat are combined for analyses and reported as separable fat. The nutrient values for separable lean and separable fat are weighted for their respective contributions to the whole retail cut and reported as "separable lean and fat". For cooked beef cuts, the cuts are cooked with the separable fat intact. Nutrient data for separable fat, separable lean only, and separable lean and fat of cooked cuts are analyzed or calculated as described above.

The analytical nutrient data include the mean nutrient value, the standard error given to three decimal places, and the number of observations on which the values are based. For many food items, mean values are given without an accompanying standard error and number of samples. These values are either calculated by pooling data by or by weighting means (e.g. All Grades), by applying cooking yields or nutrient retention factors, or by imputation from a different, closely related food. For raw beef items and unheated cured items, nutrient values are estimated on the known content of that nutrient in the lipid (fatty acids), total solids (cholesterol), moisture-free, fat-free solids (minerals), or protein (water-soluble vitamins) fraction of a similar food.

### **Nutrients**

Nutrient information for SR can be found under "File Content" in the documentation. However, some nutrient information specific to beef products are included here. Nutrient data are obtained for moisture, protein, ash and total fat. The values for protein are calculated from the content of total nitrogen (N) in the food using the conversion factor recommended by Jones (Jones, D.B., 1941). The specific factor applied to beef items is 6.25. The carbohydrate content of uncured products (except some organ meats)

consisting entirely of beef is negligible. For such foods, the carbohydrate content is assigned a zero value. The sum of the percentages of water, protein, total lipid, and ash may not necessarily equal 100 percent for those foods showing zero carbohydrate because the amounts of each of these constituents are determined independently.

For heart, liver, kidney, tongue, and cured products (foods expected to contain carbohydrate), the carbohydrate value is calculated as the difference between 100 and the sum of the percentages of water, protein, total lipid, and ash. If the total of these constituents for any item is more than 100 due to analytical variation, the carbohydrate content is assigned a zero value.

Food energy is expressed in terms of both kilocalories and kilojoules. (One kilocalorie equals 4.184 kilojoules.) The data are for physiologic energy values remaining after losses due to digestion and metabolism have been deducted. Further discussions on energy and caloric factors used in SR can be found in the "Food Description File" of the general documentation.

The specific calorie factors used for calculating energy values in beef products are:

	<u>Kcal/g</u>
Protein	4.27
Fat	9.02
Carbohydrate	3.87

The carbohydrate factor of 3.87 is used for some organ meats and some cured products. The factor of 4.11 is used for tongue. The factors are based on the Atwater system for determining energy values. Details of the derivation of these factors are outlined in Agriculture Handbook No. 74 (Merrill, A.L. and Watt, B.K., 1973). Because the level of carbohydrate in separable lean and separable fat is insignificant, no carbohydrate factor is needed for most beef products.

# **Description of Projects**

The studies documented in these notes on beef represent only data collected since 1998.

## Selected cuts, 1/8 inch external trim fat.

A collaborative study was funded by the Beef Checkoff Program and conducted by USDA, America's Beef Producers, and Texas A&M University to determine the food and nutrient composition of 13 raw and cooked retail cuts for inclusion in the USDA National Nutrient Database for Standard Reference.

**Sampling and fabrication.** Carcasses (n=20) were selected from two packing plants, one in the Texas Panhandle and the other in Nebraska. Ten USDA Choice and ten USDA Select carcasses (yield grade 2 and 3) were selected for the study. These

carcasses represented the approximate distribution found in the US beef supply according to the National Quality Beef Audit – 1998 (Boleman, S.L. et al., 1998). All carcasses were shipped to Texas A&M University for fabrication of the following retail cuts: arm roast, bottom round roast, bottom round steak, brisket - flat half, eye of round roast, flank steak, round tip roast, small-end rib steak, tenderloin steak, tri-tip (bottom sirloin butt) roast (boneless and defatted), top loin steak, top round steak, and top sirloin steak. Cuts were assigned randomly to the following external fat trim levels: 0.0 cm (0 inch trim), 0.3 cm (1/8 inch trim), or 0.6 cm (1/4 inch trim). External fat was measured at five points, the points connected, and with a scalpel, the fat was removed half the thickness of the cut. This procedure was repeated on the other side, thus removing the excess fat completely. One additional steak was assigned to a raw treatment and trimmed to 0.3 cm. Three of the cuts (flank steak, round tip roast, and tri-tip roast) had no external fat and were therefore assigned to the 0.0 cm group for both preparations (raw and cooked). Dried surfaces, extending chine bones, minor muscles, and muscle pieces were trimmed from all cuts. All cuts were vacuum packed individually, labeled, and frozen at -23°C for further dissection and cooking. Additional details on fabrication have been previously published (Wahrmund-Wyle, J.L. et al., 2000).

**Cooking procedures.** (Wahrmund-Wyle, J.L. *et al.*, 2000). Retail cuts destined for cooking were thawed overnight in a cooler at 5°C, weighed, and cooked as follows: arm roast, bottom round steak, and brisket were braised; bottom round roast, eye of round roast, round tip roast, and tri-tip roast were roasted; and flank steak, small-end rib steak, tenderloin steak, top loin steak, top round steak, and top sirloin steak were broiled.

For braising, cuts were browned for 4-8 min (time being size-dependent) in a preheated Farberware Dutch Oven placed on top of a conventional range. After browning, the cuts were covered with 90-180ml distilled water, placed in a preheated conventional gas oven at 325°F (163°C) and simmered in a covered vessel to an internal temperature of 185°F (85°C).

Cuts for roasting were placed on wire racks with the fat side up, when possible, and cooked in a conventional gas oven (preheated to 325°F (163°C) to an internal temperature of 140°F (60°C). For broiling, cuts were cooked on electric Farberware Open-Hearth Broilers (model 350A) to an internal temperature of 149°F (65°C). The internal temperature of each retail cut was monitored by inserting copper constantan thermocouples into the geometric center of the cut and recording the data on Honeywell recorders. After cooking, cuts were wrapped in plastic wrap and chilled (2-3°C) overnight (Jones, D.K. *et al.*, 1992). Each cut was weighed prior to and after cooking for calculation of cooking yield.

**Sample preparation.** Individual samples from all cuts, both raw and cooked, were carefully dissected to separate and weigh the various cut components. These components included separable lean, external fat, seam fat, and waste such as bone and heavy (non-edible) connective tissue. The separable lean included muscle, intramuscular fat, and connective tissue that would be considered edible. External fat is the fat on the outside of the cut. Seam fat included intermuscular fat depots within the

cut. Separable fat from all cuts was pooled to form raw and cooked composites. Separable fat included both external and seam fat in these composites. Separable lean was placed in a Cuisinart® food processor and homogenized for 35 seconds. Sample aliquots were frozen at -10°C until analysis.

**Sample analyses.** Proximate nutrients (moisture, total fat, ash, and protein) were determined on individual samples and composites of the separable fat. Raw and cooked samples of separable fat and the separable lean from the arm roast, bottom round steak, and top loin steak, trimmed to 1/8 inch external fat, were also analyzed for minerals (calcium, copper, iron, magnesium, manganese, phosphorus, potassium, selenium, sodium, and, zinc) and vitamins (niacin, thiamin, riboflavin, vitamins  $B_6$  and  $B_{12}$ ). Samples from the raw and cooked arm roast and separable fat were analyzed for vitamins A and E, total folate, and pantothenic acid. Raw samples from the arm roast were analyzed for amino acids. Data were released in SR16 (2003).

## **Grass-fed Beef**

A collaborative study (Leheska, J.M. *et al.*, 2008) was funded by the Beef Checkoff Program and conducted by America's Beef Producers, Texas Tech University, and USDA to determine the nutrient composition of grass-fed beef in the United States for inclusion in SR. The demand for grass-fed products has increased in recent years due to increased public interest in grass-fed production practices and nutrition. Crop variety, season, and geographic location can have an affect on the nutrient content of feedstuffs. In turn, the different types of feed given to cattle can affect weight gain, carcass characteristics, and nutrient content.

**Sampling.** Ground beef and strip steaks were collected on 3 separate occasions from 15 producers of grass-fed beef, representing 13 different states (Alabama, Arkansas, California, Colorado, Georgia, Idaho, Kentucky, Minnesota, Missouri, Montana, New Mexico, Texas, and Virginia). The sample collection protocol required that 2 steaks from 3 different animals be collected by each producer on each of the 3 separate occasions. The steaks were cut 2.54 cm thick from the 13<sup>th</sup> rib position of the strip loin. Similarly, 454 g of ground beef targeting 85% lean and 15% fat was collected by each producer from 3 different carcasses on each of 3 different occasions. When the specified lean to fat ratio (85/15) was not available they were asked to provide the next leanest ground beef (e.g., 88/12). The samples were then packaged appropriately and shipped frozen to Texas Tech University.

**Sample preparations, grass-fed ground beef samples.** After the ground beef samples had thawed properly they were frozen in liquid nitrogen and homogenized. Once homogeneity was reached aliquots of the samples were double bagged in labeled Whirl-Pak bags and stored at -80°C until subsequent analysis.

**Sample preparations grass-fed strip steak samples**: After proper thawing, the strip steak samples were weighed and dissected. The lean, fat, and refuse (connective tissue

and scrap) of each steak was separated and weighed individually. Samples of cubed strip steak were frozen in liquid nitrogen and homogenized using the same protocol as ground beef samples. Aliquots of the homogenized samples were double bagged in labeled Whirl-Pak bags and stored at -80°C until subsequent analyses.

**Chemical Analysis.** Analyses of proximate nutrients were performed at Texas Tech University. Following ether extraction, fat was determined in each sample using the Soxhlet method according to Official Method 991.36. Percent protein was determined by combustion using a LECO FP 2000 following AOAC Official Method 992.15. Percent moisture of the samples was analyzed by oven drying according to AOAC Official Method 8.2.1.1 and percent ash was determined by difference. Fatty acid analysis and cholesterol content was performed by a commercial laboratory using gas chromatography according to AOAC Official Methods 963.22 and 994.15. The University of North Carolina analyzed the grass-fed beef samples for choline by extracting choline compounds and quantifying by liquid chromatography-electrospray ionization-isotope dilution mass spectrometry. Total choline content of the samples was calculated as the sum of choline-contributing metabolites. Total fat, thiamin, vitamin B<sub>12</sub>, and minerals (calcium, copper, iron, magnesium, manganese, phosphorus, potassium, selenium, sodium, and, zinc) were analyzed by a commercial laboratory using AOAC Official Methods. To validate all analytical procedures, quality control was monitored by insertion of certified reference materials and blind duplicates into the sampling course. Data on Grass-fed beef was released with SR21 (2008).

## **Ground Beef Products.**

The USDA, in collaboration with America's Beef Producers and the University of Wisconsin, undertook a study funded by the Beef Checkoff Program to update the nutrient composition data for ground beef products in SR. None of the ground beef products contained extenders. According to Federal regulations, ground beef has no added water, phosphates, binders, or extenders, and shall not contain more than 30 percent fat (USDA, FSIS, Code of Federal Regulations). Ground beef is a unique meat product in that a wide range of formulations for this product are available in most US retail stores. In order to provide consumers and industry with the nutrient composition information for this variable product, the study was designed to establish the mathematical relationship between the various nutrients and the total fat content of raw ground beef through regression techniques. The ultimate aim was to use these relationships for predicting the nutrient composition for raw and prepared ground beef.

**Sampling**. Ground beef samples for each of three fat categories (label declarations of <12% fat, 12-22% fat, or >22% fat) were purchased from 24 retail outlets nationwide. In this sampling plan developed for the NFNAP (Pehrsson, P.R. *et al.*, 2000), the country was divided into 4 regions, with 3 consolidated metropolitan statistical areas (CMSA) within each region; 2 retail stores were selected within each CMSA.

**Sample preparation.** Ground beef products were analyzed in raw and cooked form. To achieve uniform sizing for broiled and pan-broiled patties, 112 g of ground beef were

pressed into a patty mold. Patties were broiled in a preheated conventional oven for 8.7 min (final internal temperature of 160°F (71°C). Pan-broiled patties were broiled in a pre-heated Westbend electric skillet for 11.75 min (final internal temperature of 160°F (71°C). Patties were cut in half to evaluate degree of doneness based on color. Ground beef crumbles were cooked in a pre-heated Westbend electric skillet for 5.3 min (final internal temperature of 160°F (71°C)), and drained in a colander. The loaf was baked in a conventional oven at 325°F (163°C) for 41 min (final internal temperature of 160°F (71°C)). No fat was added during cooking. After cooking, all samples were stored at –24°C in sealed vacuum bags until homogenization and analysis.

Sample analyses. Raw samples and broiled patties from each location and for each fat level (n=72) were analyzed for moisture, nitrogen, total fat, ash, and selenium. Samples were pooled based on CMSA (n=36) for analyses of minerals (calcium, copper, iron, magnesium, manganese, phosphorus, potassium, sodium, and, zinc), niacin, thiamin, riboflavin, vitamins B<sub>6</sub> and B<sub>12</sub> and cholesterol; twelve samples (pooled by region) were analyzed for total choline, vitamin K, amino acids (raw samples only), and fatty acids (C8 - C22); composites of 12 locations (n=6) were analyzed for folate, pantothenic acid, retinol, and vitamin E. Proximate components for pan-broiled patties and pan-browned crumbles were analyzed on the samples pooled by CMSA; minerals, including selenium, niacin, thiamin, riboflavin, vitamins B<sub>6</sub> and B<sub>12</sub> and cholesterol were analyzed in samples pooled by region; fatty acids, folate, pantothenic acid, retinol, and vitamin E and were analyzed on the 6 composites of 12 locations each. For the baked loaf samples, proximate components, minerals, including selenium, niacin, thiamin, riboflavin, vitamins B<sub>6</sub> and B<sub>12</sub>, and cholesterol were analyzed on regional composites; fatty acids, folate, pantothenic acid, retinol, and vitamin E were analyzed on the 6 composites of 12 locations each.

Nutrient analyses were conducted at either University laboratories or at a commercial testing laboratory using AOAC methods. Quality control measures included duplicate sampling, and the use of control composites and NIST certified reference materials (SRM 1546: Meat Homogenate).

**Statistics.** Data were analyzed using mixed model regression analysis to obtain a regression equation for each nutrient and preparation method (SAS, 2004).

Nutrient values were released in SR15 (2002) for ground beef products containing 5%, 10%, 15%, 20%, 25%, and 30% fat. The prepared ground beef values included raw samples, broiled patties, pan-broiled patties, pan-browned crumbles, and baked loaf. The ground beef calculator, released on the NDL web site in 2006, computes the nutrient profile for raw and prepared ground beef products of intermediate fat content.

### **Beef Value Cuts**

A new line of single–muscle roasts and steaks, fabricated from the outside round, the knuckle, and the chuck shoulder clod, were introduced to the retail market in 2001-2002. These cuts, the top blade steak (Infraspinatus), shoulder top and center steaks

(Triceps brachii), shoulder tender (Teres major), tip center (Rectus femoris), tip side (Vastus lateralis), and bottom round (Biceps femoris), were tested for palatability and functionality. Furthermore, five of the six major cuts met the USDA definition of lean or extra-lean. USDA, in collaboration with America's Beef Producers and the University of Wisconsin, conducted a study funded by the Beef Checkoff Program to determine the nutrient profile of the Beef Value Cuts for inclusion in SR.

**Sampling.** Animal products were obtained from an IBP (Tyson) plant near Sioux City, lowa. This plant draws cattle from a large number of feedlots and has nationwide product distribution. Twelve carcasses were identified by quality grade (high choice, average choice, and select) with yield grades of 2 or 3. Two carcasses were used for reserves and for training the meat cutting staff. There was sufficient product from 1 knuckle, 1 outside round, and 1 chuck clod to sample, prepare, and analyze five of the cuts. The Teres major is a very small muscle (~8 oz from 1 side) and would not provide a sufficient amount for all analyses. Therefore, one 15 pound box of choice (quality grade unknown) and one box of select Teres major muscles were purchased from the same plant. Removed beef value muscles were trimmed free of all external fat and heavy connective tissue. The denuded muscles were vacuum packaged and stored at -20°F until steak preparation.

**Sample preparation.** Muscles were cut into 1-inch thick steaks and weighed. Steaks were removed in pairs, one steak for raw analyses, the other to be cooked and analyzed in the cooked state. Steaks were cooked by grilling over a preheated portable gas grill. Steaks were turned when the internal temperature reached the midway point between the starting temperature and the final internal temperature (including post-cooking temperature rise) of 160°F (71°C) (medium degree of doneness). Steaks were placed on a wire rack for 3 min and then weighed to obtain the cooked weight. Raw and cooked steaks were stored at -20°F (-29°C) until time for nutrient analyses.

**Sample analyses.** Proximate nutrients (moisture, total fat, ash, and protein) and cholesterol were determined on individual muscle samples from the chuck clod, bottom round, and the knuckle, both raw and cooked. Composites of three samples from each of these muscle groups were pooled into composites and analyzed for fatty acid content. Individual samples from the knuckle muscles were also analyzed for of minerals (calcium, copper, iron, magnesium, manganese, phosphorus, potassium, selenium, sodium, and, zinc) and vitamins (niacin, riboflavin, thiamin, vitamins  $B_6$  and  $B_{12}$ ). Samples from the raw and cooked knuckle muscles were also analyzed for vitamins A and E. No vitamins or minerals were analyzed on samples from the chuck clod or bottom round; NDL imputed these values based on nutrient values from the arm roast and bottom round. Cooking yields calculations were based on initial (raw) and final cooked weights from all samples. These data were disseminated in SR18 (2005).

## **Beef Nutrient Database Improvement Study:**

A collaborative research study was undertaken by NDL with scientists at the National Cattlemen's Beef Association (NCBA), Colorado State University (CSU), Texas A & M

University (TAMU), and Texas Tech University (TTU) to update nutrient information in the USDA National Nutrient Database for Standard Reference (SR). This entailed updating the food and nutrient composition for beef cuts currently in SR, and adding new cuts, which had been introduced in the market place. The first phase of this study involved cuts from the chuck: Brisket, Mock Tender Steaks, Top Blade Steaks, Shoulder Steaks Boneless, Shoulder Clod Roasts, Boneless Chuck Short Ribs, Denver Steaks, Chuck Eye Steaks, Country Style Ribs, America's Beef Roast, Underblade Steaks and Roasts, and Beef for Stewing. Most of these cuts are new with the exception of the Shoulder Steaks which replaced the older Clod Steak data (NDB#s 23533, 13943, 23536, 13946, 23554, 23516). The second phase of this study involved cuts from the rib and plate: Back Ribs, Rib Eye Roast, Rib Eye Steak, Outside Skirt, and Inside Skirt. During the second phase of NDI, a separate study on Beef Alternative Merchandising (BAM) beef cuts was also conducted. BAM cuts were developed by the beef industry to utilize all the potential meat from today's larger subprimals and traditional subprimals, and to respond to customers' desire for leaner, more health-conscious portions. BAM cuts are leaner and smaller than more traditional cuts. The boneless beef cuts added to SR from the BAM study were: Ribeye Filet, Ribeye Petite Roast, Ribeye Cap Steak, Top Loin Filet, Top Loin Petite Roast, Top Sirloin Filet, Top Sirloin Cap Steak, and Top Sirloin Petite Roast.

**Sampling**: Beef carcasses for the study were selected from six different major packing plants, representing the different regions of the U.S. Each university was assigned two different packing plants. The sampling plan was developed for 36 animals. In order to get true retention and yield data, an A and a B side of the animal carcass was needed; thus the total animal count came to 72. When selecting the carcasses certain properties were considered as part of the sampling plan protocol: quality grade (upper choice, lower choice, select), yield grade (YG2, YG3), gender (steer or heifer), and genetics (dairy or non-dairy). Each university was responsible for identifying and obtaining beef chucks that fit into the sampling matrix. The universities assessed and recorded carcass data at the packing plants, properly identified each selected cut and shipped the product back to their respective meat laboratories. Products were fabricated into the needed retail cuts for this study within 14-21 days postmortem. Retail cuts were properly identified and vacuum packaged and held frozen until cooking or dissection. The retail product was cooked according to protocols developed for each cut. Cooked and raw products were dissected; weights for each component (separable lean, separable fat, and refuse) were obtained. Total weights of raw and cooked (prior to and after cooking) cuts were obtained. Samples were then homogenized and composited.

The compositing plan was developed to establish an effective and efficient statistical design for nutrient analyses of the beef cuts. The plan consisted of 4 different compositing levels: an animal level (36 animals) where all the samples were analyzed; a six composite level; a three composite level; and a national composite level. This was done for both raw and cooked samples. Different nutrients were analyzed at each composite level.

**Sample preparation:** The various beef cuts were analyzed in raw and cooked form. The following cooking methods were used: grilling, roasting, and oven-braising. Frozen raw samples were tempered under refrigeration (0-4°C) for 24-48 h based on the appropriate size and weight of the cut. The appropriate temperatures and weights were recorded prior to cooking. The thermocouple was placed in the geometric center or thickest portion of the meat piece. The probe positioning did not affect the product's contact with the cooking surface. For small or thin beef cuts, the thermocouple was used periodically to check the internal temperature of samples throughout the cooking process.

## **Cooking Procedure:**

**Grilling -** The grill was pre-heated to  $195^{\circ}$ C. The beef samples were evenly spaced in center of cooking grate. The grill lid was closed and the sample was cooked to an internal temperature of  $70^{\circ}$ C. Tongs or spatulas were used to remove samples from the grill. Beef samples were allowed to stand while monitoring the internal temperature rise until temperatures began to decline. The point right before the temperature declines (highest temperature reached) was considered the final internal temperature of the cooked sample. Beef samples were then chilled uncovered in the refrigerator (2-4° C) for  $24 \pm 1$  hr before dissection.

**Roasting** - The oven was pre-heated to  $160^{\circ}\text{C}$  ( $325^{\circ}\text{F}$ ). The beef sample(s) were positioned in the center of the rack in the roasting pan, no oil or water was added, and the pan was not covered. The roasting pan with the beef sample was positioned on the oven rack in center of oven and roasted to an internal temperature of  $60^{\circ}\text{C}$ . The beef samples were removed from the oven. The thermocouple probe remained in place and samples were allowed to stand while monitoring the internal temperature rise until temperatures began to decline. The point right before the temperature declines (highest temperature reached) was considered the final internal temperature of the cooked sample. The beef samples were then chilled uncovered in refrigeration (2-4° C) for 24  $\pm$  1 hr before dissection.

Oven-Braising - The beef samples were placed in a pre-heated pan and were "browned/seared", turning as needed for even browning on all sides. The pan drippings were poured off and the volume (mL) of drippings was measured. The thermocouple was then applied in the geometric center or thickest portion of the meat piece. A small amount of distilled, deionized water was added until the water reached one third-the thickness of the meat. The liquid was held at a simmer, the pan was covered with a lid, and placed in the Dutch oven. The Dutch oven was then placed in a preheated 120°C (250°F) oven. The beef samples simmered and cooked until an internal temperature of 85°C was reached. The samples were removed from the oven keeping the thermocouple probe in place and were allowed to stand while monitoring the internal temperature rise until temperatures began to decline. The point right before the temperature declines (highest temperature reached) was considered the final internal temperature of the cooked sample. The beef sample(s) were removed from the cooking liquid and the cooking liquid yield and volume were documented. The beef samples

were then chilled uncovered in the refrigerator  $(2-4^{\circ} \text{ C})$  for  $24 \pm 1$  hr before dissection. In phase two, the Back Ribs were oven-braised and the "browned/seared" step was not performed.

### **Nutrient Analysis:**

At the animal level only proximates were analyzed. At the next level, the six composite level, the following nutrients were analyzed: Proximates (fat, moisture, protein, and ash), fatty acids including long-chain fatty acids and CLAs, total cholesterol, minerals (Ca, Fe, Mg, P, K, Na, Zn, Cu and Mn), selenium, vitamin E, vitamin D and the B-vitamins including B12, B6, riboflavin, and niacin. At the 3 composite level amino acids and retinol were analyzed. At the final National composite level total choline and the other B-vitamins, thiamin and pantothenic acid, were analyzed. The pooled fat samples, both raw and cooked, from all the cuts were analyzed for all nutrients.

The techniques for analyzing the proximate nutrients are as follows: Protein by combustion, total fat by extraction and acid hydrolysis, ash by gravimetric, and moisture by forced air. For the minerals calcium, magnesium, iron, zinc, copper, and manganese, they were analyzed by atomic absorption spectroscopy (AAS), potassium and sodium by emission spectrometry, and selenium by hydride generation. Retinol, vitamin E, and vitamin D were analyzed by high-performance liquid chromatography (HPLC) methods. Choline was analyzed by liquid chromatography-electrospray ionization-isotope dilution mass spectrometry (LC/ESI/IDMS). B-vitamins such as thiamin and riboflavin were analyzed by fluorometric methods and niacin, pantothenic acid, vitamin B6, and vitamin B12 by microbiological methods. Amino acids such as tryptophan were analyzed by alkaline hydrolysis-HPLC, cystine and methionine by performic oxidation-HPLC, and all other amino acids by acid hydrolysis-HPLC. Hydroxyproline was analyzed using a colorimetric method, cholesterol by a gas chromatographic (GC)/direct saponification method not using derivativation, and fatty acids by gas-liquid chromatography (GLC).

#### References for Notes on Foods – Beef Products

Boleman, S.L., S.J. Boleman, W.W. S.J., Morgan, D.S. W.W., Hale, D.B. D.S., Griffin, J.W. D.B., Savell, R.P. J.W., Ames, M.T. R.P., Smith, J.D. M.T., Tatum, T.G. J.D., Field, G.C. T.G., Smith, B.A. G.C., Gardener, J.B. B.A., Morgan, S.L. J.B., Northcutt, H.G. S.L., Dolezal, D.R. H.G., Gill, D.R., and F.K. Ray., F.K. 1998 National Beef Quality Audit- 1995: Survey of producer-related defects and carcass quality and quality attributes. J. Anim. Sci. 76:96-103.

Code of Federal Regulations. Animals and Animal Products; Food Safety and Inspection Service, Meat and Poultry Inspection, U.S. Department of Agriculture; Definitions and Standards of Identity. 9 CFR 319.

Jones, D.B. 1941. Factors for Converting Percentages of Nitrogen in Foods and Feeds into Percentages of Protein. Rev. U.S. Dept. of Agric., Circ. 183, 22 pp.

Jones, D.K., J.W. Savell, J.W., and H.R. Cross., H.R. 1992. Effects of fat trim on the composition of beef retail cuts – 1. Separate tissue components. J. Muscle Foods 3: 45-56.

Leheska, J.M., L.D. Thompson, J.C. L.D., Howe, E. J.C., Hentges, J. E., Boyce, J.C. J., Brooks, B. J.C., Shriver, L. B., Hoover, L., and M.F. Miller., M.F. 2008. Effects of conventional and grass feeding systems on the nutrient composition of beef. J Animal Sci

Merrill, A.L., and B.K. Watt. 1973. Energy Value of Foods—Basis and Derivation. Rev. U.S. Dept. of Agric., Agric. Handb. No. 74, 105 pp.

Pehrsson, P. R., D.B. Haytowitz, J.M. D.B., Holden, C.R. J.M., Perry, C.R. and D.G. Beckler., D.G. 2000. USDA's National Food and Nutrient Analysis Program: food sampling. Journal of Food Composition and Analysis 13:379-389.

SAS, 2004 - SAS Institute Inc. 2004. SAS OnlineDoc® 9.1.2. Cary, NC: SAS Institute Inc.

Wahrmund-Wyle, J.L., K.B. Harris, K.B., and J.W. Savell., J.W. 2000. Beef Retail Cut Composition: 1. Separable Tissue Components. J. Food Comp. and Anal. :13:, 233-242.

# **Breakfast Cereals (Food Group 08)**

### Introduction

Food Group 08 foods are identified as breakfast cereals to clearly distinguish them from cereal products used mainly as ingredients or typically consumed at meals other than breakfast (see Food Group 20 Cereal Grains and Pasta). The Breakfast Cereals group of about 370 items includes two major sections: ready-to-eat (RTE) and to-be-cooked (hot) cereals. The majority of breakfast cereals are listed by brand name. The number and level of fortification nutrients differ appreciably between breakfast cereals, resulting in many unique products that can't adequately be described generically. The majority of major brand breakfast cereals are included in SR, accounting for over 80% of the retail market.

Breakfast cereals generally consist of one or more cereal grains, either as whole grains or milled portions, as a major constituent. The continuum of grain content goes from less than 50% for some presweetened RTE cereals and approaches 100% for hot cereals. The predominant grains for RTE cereals are corn, wheat, oats and rice. Additional ingredients such as sweeteners, flavoring or texturizing macroingredients (including fruit, nuts, and oil), microingredient flavors or colors, and nutritional fortificants and shelf life preservatives may be added (Caldwell, 2000). Manufacturing processes generally used for RTE cereals include: flaked, extruded flakes, gun-puffed whole grains, extruded gun-puffed, oven-puffed, shredded whole grains, and extruded shredded methods.

<u>Fortification</u>: Addition of vitamins and/or minerals to grain products began in the late 1930's with selected nutrients (primarily thiamin, riboflavin, niacin, iron, and calcium) being added in amounts to restore the natural content of the grain which may have been modified during processing (enrichment). A standard of identity, effective in 1942. established standards for unenriched and enriched farina. Enrichment standards were developed for corn grits in 1947 (Park, 2001; FDA 2012). In 1955, nutrients were first added to breakfast cereals in amounts higher than those of the whole grain itself. By 1969 many RTE cereals were fortified with 25% of the U.S. RDA for thiamin, riboflavin. niacin, vitamin B6, vitamin B12, A, C, and folic acid; with iron at 10 to 25% RDA; and some cereals with vitamin D at 10% RDA (Steele, 1976). A recognition of the importance of folate in prevention of neural tube defects led to an FDA regulation, effective in 1998, requiring folate fortification of specific flours and grains (see Table of Standards of Enrichment, in Notes on Foods for Cereal Grains and Pasta), including enriched farina, which is used as a hot cereal (Phillips, 2010; Rader, 2000). Ready-toeat cereals were not affected by the regulation. Today, nearly all processed ready-toeat breakfast cereals are fortified with vitamins and/or minerals at varying levels.

Addition of nutrients presents technological problems – some vitamins are not heat stable; others are affected by pressure; and some can produce undesirable tastes and odors (Steele, 1976). Incorporation of fortificants before processing provides uniform distribution of the nutrients, but may lead to undesirable loss of nutrients and flavor

changes. Thus, some cereals are exposed to multiple coating processes for topical application of the added nutrients. A phase 1 coating may include vitamin addition, then phase 2 may include coating with slurries of sugars, honey and flavoring agents. Coatings may be applied by spraying the product as it passes down a conveyer belt or may be added by means of a coating drum (Burns, 2000). Manufacturers generally add nutrients at a higher level than labeled to compensate for possible losses during processing, thus ensuring that content of fortification nutrients in the packaged cereal meets or exceeds the declared level (FDA, 2010).

Nutrient data: Due to the frequency of reformulations of breakfast cereals and brand name specificity of most items in this food group, the Nutrient Data Laboratory relies heavily on the cereal industry to provide current nutrient data for breakfast cereals in SR. Kellogg and General Mills typically supply data each year, while Quaker and Post contribute data some years. Breakfast cereal manufacturers generally can provide data for proximates, all fortification vitamins and minerals and some non-fortification vitamins and minerals. Data for fatty acid classes (total saturated, monounsaturated and polyunsaturated fatty acids) are generally provided, but individual fatty acids rarely so. Industry-provided fortification nutrient values are based on the label-declared values, representing the minimum amount of that fortified nutrient that should be present in the cereal. Although industry does not provide values for all non-fortification vitamins and minerals, a portion of these nutrients (e.g., magnesium and vitamin C) are generally industry-supplied. Some nutrient values are derived from the product's nutrition facts label, as well.

Every few years, beginning in 2002, various RTE cereals with a high market share have been selected for statistically representative nationwide sampling and nutrient analysis as part of the USDA National Food and Nutrient Analysis Program (NFNAP). Regular and instant oatmeal, corn grits, and cream of wheat were sampled through NFNAP, as well. The NFNAP sampling method is described in detail elsewhere (p. 49). The most recent sampling was for Kellogg's Rice Krispies, Frosted Flakes, and Raisin Bran; General Mills Lucky Charms and Cheerios; and Post Honey Bunches of Oats. Regular, cinnamon and spice, and raisin spice instant oatmeal were sampled, as well. The results are in SR25.

Approximately 200 breakfast cereals are included in a subset of foods supplied for the Food and Nutrient Database for Dietary Studies, which is used for national nutrition monitoring. For these products, there is a list of mandatory nutrients for which values must be provided. A variety of standard imputing methods are available in NDL's databank system for estimating missing nutrient values. The predominant imputation method for RTE cereals is by NDL's formulation estimation procedures. These estimation procedures were incorporated into the databank system; they include linear programming techniques to estimate ingredient proportions by weight and calculate a full nutrient profile based on this estimated commercial recipe (i.e. formulation) (Haytowitz, 2009). Individual fatty acids, choline, vitamin K, carotenoids, caffeine and theobromine are generally derived by the formulation method. In the absence of analytical data, added folic acid is calculated by subtracting estimated natural food

folate from the total folate value provided by the manufacturer.

In general, a profile is calculated by recipe for the cooked version of hot cereals that are sold in bulk, such as rolled oats or farina. The yield and retention factors are applied to the recipe to estimate the effects of cooking on moisture and nutrient levels. For brand name instant hot cereals sold in single serve packets, a nutrient profile is generally provided only for the dry cereal, since there will be practically no difference between the nutrients contained in one packet of the dry cereal and the nutrients in one packet prepared by adding hot water.

Food Group 08 items in SR include data for both ready-to-eat and hot breakfast cereals that are derived from cereal manufacturers, food labels, lab analyses, formulation and other estimations. Recent trends show a decrease in sugar and sodium levels and increase in fiber levels. NDL will continue to monitor these and other changes.

### References for Notes on Foods – Breakfast Cereals

Burns, R.E., Caldwell, E.F., Fast, R.B., and Jones, W.H. 2000. Ch. 7 in: Breakfast Cereals and How They Are Made, 2<sup>nd</sup> ed. R.B. Fast, R.B. and E. F. Caldwell, eds. American Association of Cereal Chemists: St. Paul, MN.

Caldwell, E.F., Johnson, L.E. and Labuza, T.P. 2000. Ch. 10 in: Breakfast Cereals and How They Are Made, 2<sup>nd</sup> ed. R.B. Fast and E. F. Caldwell, eds. American Association of Cereal Chemists: St. Paul, MN.

Haytowitz, D.B., Lemar, L.E., and Pehrsson, P.R. (2009). USDA's Nutrient Databank System – A tool for handling data from diverse sources. Journal of Food Composition and Analysis. 22:433-441.

Park, Y.K. 2001. History of cereal-grain product fortification in the United States. Nutrition Today 36(3) 124-137.

Phillips, K.M., Ruggio, D.M., Ashraf-Khorassani, M., Eitenmiller, R.E., Cho, S., Lemar, L.E., Perry, C.R., Pehrsson, P.R., and Holden, J.M. 2010. Folic Acid Content of Ready-to-Eat Cereals Determined by Liquid Chromatography-Mass Spectrometry: Comparison to Product Label and to Values Determined by Microbiological Assay. Cereal Chem. 87(1):42–49.

Rader, J.I., Weaver, C.M., and Angyal, G. 2000. Total folate in enriched cereal-grain products in the United States following fortification. Food Chem. 70: 275-289.

Steele, C.J. 1976. Cereal fortification – technological problems. Cereal Foods World 21(10) 538-540.

- U.S. Food and Drug Administration (FDA), Department of Health and Human Services. 2012. Cereal Flours and Related Products. Code of Federal Regulations, 21 CFR 137, U.S. Government Printing Office, Washington, DC.
- U.S. Food and Drug Administration (FDA), Department of Health and Human Services. 2010. Nutrition labeling of food. Code of Federal Regulations, 21 CFR 101, U.S. Government Printing Office, Washington, DC.

# **Cereal Grains and Pasta (Food Group 20)**

There are over 180 food items in the Cereal Grains and Pasta food group in the SR. The sources of nutrient data for these items are mainly analytical obtained from the scientific literature or analytical studies. These include data collected by nationwide sampling under NDL's NFNAP program, described earlier.

Federal Definitions and Standards of Identity have been published for a number of cereal grain and pasta products appearing on the market today (FDA, 2008a, 2008b). Federal Enrichment Standards exist for wheat flour, cornmeal, rice, and macaroni and noodle products (FDA, 2008a, 2008b). These standards do not mandate the enrichment of the products, but if it is labeled as "enriched," specified nutrient levels must be present. Federal standards specify enrichment levels or ranges for thiamin, riboflavin, niacin, iron, and folic acid in most enriched products. The Federal Enrichment Standard for riboflavin in enriched rice has been stayed since 1958, and hence riboflavin is not currently added to enriched rice. The standards for enriched grain products were amended to require the addition of folic acid beginning in 1998. Addition of calcium to most enriched products is optional, but if added must meet specified levels. However, consistency in levels of enrichment may be an issue (Guerrero et al, 2009). The current Federal Enrichment Standards are listed in Table 21.

In the Cereal Grains and Pasta food group, data are presented for the enriched and unenriched forms of commonly enriched products.

Table 21. Standards for Enrichment<sup>1</sup>

Table 21. Otandards for Enrichment						
Food Item	Thiamin	Riboflavin	Niacin	Iron	Folic Acid	Calcium <sup>2</sup>
	milligrams per pound					
Wheat flour	2.9	1.8	24	20	0.7	960
Self-rising	2.9	1.8	24	20	0.7	960
wheat flour						
Cornmeal	2.0-3.0	1.2-1.8	16-24	13-26	0.7-1.0	500-750
Self-rising	2.0-3.0	1.2-1.8	16-24	13-26	0.7-1.0	500-750
cornmeal						
Rice	2.0-4.0	1.2-2.4 <sup>3</sup>	16-32	13-16.5	0.7-1.4	500-1,000
Macaroni and	4.0-5.0	1.7-2.2	27-34	13-16.5	0.9-1.2	500-625
noodle products						

A range of figures indicates minimum and maximum levels. A single figure is the minimum level, with overages left to good manufacturing practice.

In 2010, the U.S. Departments of Agriculture and Health and Human Services released the seventh edition of the Dietary Guidelines for Americans, which set evidence-based recommendations for the public to help prevent disease (U.S. Departments of

<sup>&</sup>lt;sup>2</sup> Calcium enrichment is optional in these products.

The enrichment standard for riboflavin in enriched rice has been stayed since 1958.

Agriculture and Health and Human Services, 2010). The guidelines emphasize consumption of whole grain foods, stating at least half of an individual's recommended total grain intake should be whole grains to reduce the risk of several chronic diseases and help with weight maintenance.

The AACC International definition of whole grains is "Whole grains shall consist of the intact, ground, cracked or flaked caryopsis, whose principal anatomical components - the starchy endosperm, germ and bran - are present in the same relative proportions as they exist in the intact caryopsis."

In 2006, FDA issued draft guidance for Industry and FDA Staff on Whole Grain Label Statements. It can be accessed at:

http://www.fda.gov/Food/GuidanceComplianceRegulatory Information/GuidanceDocuments/FoodLabelingNutrition/ucm059088.htm.

<u>Cereal grains</u>.—The majority of the cereal grains included in Food Group 20 are cultivated grasses belonging to the Poaceae (alt.Gramineae) family and are thus true cereals. Amaranth, buckwheat, and quinoa differ botanically from true cereals, and are referred to as pseudo cereals because they are grown and used like cereal grains (Brouk, 1975). Arrowroot flour is derived from arrowroot and tapioca is produced from cassava root, which are both non-cereal-grain plants, but used in ways similar to cereal grains.

The scientific name is given for the most unprocessed form of the cereal grain in the database. The Germplasm Resources Information Network (GRIN) was used as the basic reference for the scientific names and preferred common names (USDA, 2011).

With the exception of corn (maize), which is native to the Americas, nearly all true cereal grains originated in Europe and Asia (Brouk, 1975). Buckwheat is native to central Asia. Amaranth and quinoa are native to Central and South America, respectively.

Kasha, a buckwheat product, originated in Russia. Buckwheat groats, which are roasted to develop a distinctive nutty flavor, may be packaged in the whole form or milled to either coarse, medium, or fine granulations. Kasha is usually cooked as a hot cereal or prepared in combination with other foods and ingredients.

Corn and corn products appearing in Food Group 20 are restricted to field corn varieties and do not represent the varieties (sweet corn) used mainly as a vegetable. Corn and cornmeal products are available in white, yellow, and blue varieties. Yellow corn varieties have higher vitamin A values due to the presence of the provitamin-A carotenoids, alpha- and beta-carotene. Yellow corn also has much higher levels of lutein + zeaxanthin. With the exception of these nutrients, the composition profiles of white and yellow corn are similar.

Self-rising cornmeals and wheat flours have more calcium, phosphorus, and sodium

due to the addition of chemical leavening agents and salt. Sodium bicarbonate, monocalcium phosphate, sodium acid pyrophosphate, and sodium aluminum phosphate are the most commonly used leavening agents. Salt is also usually added to self-rising products for flavor. Bolted cornmeal has had most of the bran removed during milling, but contains most of the germ present in the whole-grain corn.

Masa corn flour is milled from corn which has been steeped in a lime (calcium hydroxide) solution. This is done both to facilitate the removal of the outer hull of the corn grain and to impart the characteristic flavor of authentic corn tortillas and other related products. As a result of the use of lime in processing, masa corn flour is higher in calcium than other corn products.

Brown rice has the bran layers intact. Rice that has been milled to remove the bran layers is referred to as white rice in this database.

Bulgur, a wheat product, has been produced in the Middle East and northern Africa since ancient times. Bulgur is produced by parboiling, drying, and then cracking wheat kernels. It is usually consumed as a cooked cereal or as an ingredient in other dishes.

Couscous is coarse-ground wheat endosperm made from durum wheat or another hard wheat variety. Couscous is a popular food in northern Africa and in the Middle East. It is usually eaten as a hot cereal or combined with other foods.

Wheat flour tortilla mix is used for making flour tortillas and other related products. This product is higher in calcium than other wheat flour products because calcium carbonate is added.

Bread flour, approximately 13% protein, is milled primarily from hard wheats. Cake flour, approximately 9% protein, is milled from soft wheats. Semolina is coarse-ground endosperm from durum wheat, and is used chiefly for making pasta.

Teff is an ancient crop believed to have been domesticated in the northern highlands of Ethiopia. It is used alone or in combination with sorghum to prepare the fermented flat bread, injera (Dendy, 1995).

Corn grits, farina, rolled oats or oatmeal, and toasted wheat germ are included in Food Group 08, Breakfast Cereals.

Nutrient data for different forms and products of each cereal grain were not obtained from the same sample or source. For example, a single source of wheat was not processed to all forms given in the database: whole-grain, bran, germ, and various flour products. The data were obtained from many sources at different times for analysis and are affected by different variables: growing locations, crop years, cultivars, natural variability, milling and processing techniques, laboratories, and possibly methods of analysis. Therefore, in a comparison of different forms and products of a cereal grain, nutritional differences may not measure precisely the effect of processing or preparation

methods.

<u>Pasta</u>.—Under Federal Standards of Identity, there are two broad categories of pasta products: macaroni and noodle products (FDA, 2008b). Macaroni products are formed by extrusion of the pasta dough into a variety of shapes and sizes including elbows, spirals, shells, twists, wheels, etc. Specific shapes of macaroni products have unique names such as rigatoni, manicotti, ziti, linguini, and spaghetti which are recognized by the consumer.

Although spaghetti is defined under Federal standards as a macaroni product, it is included as a separate category due to its unique market identity. However, the nutrient composition of spaghetti and that of other forms of macaroni products are the same on an equal weight basis.

Noodle products are also available in a variety of sizes and shapes. Federal Standards of Identity specify that noodle products must contain not less than 5.5 percent by weight of the solids of egg or egg yolk (FDA, 2008b).

Various forms of vegetable macaroni and noodle products are available today. Federal standards specify that these products must contain a minimum of 3 percent by weight of the solids of tomatoes (red varieties), artichoke, beet, carrot, parsley, or spinach ((FDA, 2008b). Spinach noodles and tricolor-type (red, green, and regular) macaroni are the most commonly available products of this type on the market.

Protein-fortified macaroni products, both with and without added vegetable solids, are also available. These products usually contain wheat germ, dried yeast, or other ingredients which increase the protein content of the product. If a macaroni product is labeled as "with Fortified Protein," under Federal standards it must have a protein content of at least 20 percent on a 13-percent moisture basis and protein quality not less than 95 percent of that of casein (FDA, 2008b).

Corn pasta is available on the market to meet the needs of those who are allergic to wheat and hence must avoid foods containing wheat ingredients. Corn pasta is made exclusively from corn flour. Since it contains no wheat flour ingredients, corn pasta is not required to meet Federal standards for macaroni or noodle products.

Fresh-refrigerated pasta has a higher moisture content than dry pasta and must be kept under refrigeration until prepared. Data are presented for plain and spinach types, both of which contain egg. Stuffed pasta such as ravioli and tortellini are listed in Food Group 22, Meals, Entrees, and Side Dishes.

Data are presented for the cooked forms of both egg-containing and non-egg-containing homemade pasta. The recipe used for each item is footnoted.

Oriental noodles do not fall under Federal Standards of Identity. Although these products may be labeled as noodles, they usually do not contain eggs. Chinese-style

pasta products currently in SR include rice noodles, chow mein noodles, and fried flat noodles. Two Japanese noodles are currently in SR: soba noodles are made with buckwheat flour; somen is a thin wheat flour noodle. Chinese cellophane noodles, also called long rice noodles, are made from mung bean flour and are included in Food Group 16, Legumes and Legume Products.

### References for Notes on Foods – Cereal Grains and Pasta

AACC International. 1999. Definition of Whole Grains. Retrieved July 10, 2011 from http://www.aaccnet.org/definitions/wholegrain.asp.

Dendy, D.A.V., ed. 1995 Sorghum and Millets: Chemistry and Technology. American Association of Cereal Chemists, Minnesota, 406 pp.

Guerrero, R., Gebhardt, S.E., Holden, J.M., Kretsch, M., Todd, K., Novotny, R., Murphy, S. 2009. White rice sold in Hawaii, Guam, and Saipan often lacks nutrient enrichment. Journal of American Dietetic Association. 109(10):1738:1743.

- U.S. Department of Agriculture, Agricultural Research Service, National Genetic Resources Program. 2011. *Germplasm Resources Information Network (GRIN)* [Online Database]. National Germplasm Resources Laboratory, Beltsville, Maryland. http://www.ars-grin.gov/cgi-bin/npgs/html/tax\_search.pl (Accessed 7/11/2012)
- U.S. Departments of Agriculture and Health and Human Services. 2010. Dietary Guidelines for Americans, 7<sup>th</sup> Edition. http://www.cnpp.usda.gov/DietaryGuidelines.htm. (Accessed 7/11/2012)
- U.S. Food and Drug Administration (FDA), Department of Health and Human Services. 2008a. Cereal Flours and Related Products. Code of Federal Regulations, 21 CFR 137, U.S. Government Printing Office, Washington, DC.
- U.S. Food and Drug Administration (FDA), Department of Health and Human Services. 2008b. Macaroni and Noodle Products. Code of Federal Regulations, 21 CFR 139, U.S. Government Printing Office, Washington, DC.
- U.S. Food and Drug Administration (FDA), Department of Health and Human Services. 2006. "Whole Grain Label Statements." Docket 2006D-0066. http://www.fda.gov/Food/GuidanceComplianceRegulatoryInformation/GuidanceDocuments/FoodLabelingNutrition/UCM059088. (Accessed 7/11/2012)

# Eggs (Food Group 01)

Recently, NDL arranged to have regular large, whole eggs picked up in a nationwide sampling as part of NFNAP. Notes on other food items in this food group will be included at a later time.

Sampling and analysis. Whole egg samples of regular large eggs were picked up in March/April 2010 at the 12 NFNAP sampling locations. The sample units were sent to the Food Analysis Laboratory Control Center (FALCC) at Virginia Tech for preparation of analytical samples to be sent to the qualified analytical laboratories. Individual samples from each of the 12 locations were prepared for the determination of proximates (moisture, protein and fat), fatty acids, and cholesterol. Samples units from the 12 locations were paired, using randomization, to create six city-pair analytical composites for analysis of vitamins, minerals, and sugars. FALCC also sent quality control (QC) samples to the analytical laboratories to monitor accuracy and precision of measurements.

**Results**. The analytical and QC data received from the analytical laboratories were reviewed. The QC results were found to be acceptable, and the analytical data for most nutrients were comparable to the current data in the National Nutrient Database for Standard Reference, Release 22 (SR22). Values for cholesterol, vitamin D, and vitamin  $B_{12}$  were significantly different from the older values which were based on analyses from eggs sampled in 2002.

Cholesterol was determined by gas chromatography; the new value for cholesterol is 372 mg/100g compared to the SR22 value of 423 mg/100g. This estimate was based on the analysis of the 12 individual samples by each of three independent qualified laboratories. The results for QC materials from all three laboratories were also acceptable.

Vitamin D was determined by HPLC-UV for the six city-pair composites. The results for the QC material were within the acceptable range. Two of the city-pair composites were analyzed by another lab using HPLC-MS/MS to double check the data. The inter-lab results were in good agreement.

Values for four of the six city-pair composites for Vitamin D averaged 1.2  $\mu$ g (49.2 IU)/100g (with a range of 1  $\mu$ g (39 IU) – 1.8  $\mu$ g (71 IU)/100g), compared to the SR22 value of 1.2  $\mu$ g (49.6 IU)/100g. However, the values for the other two city-pairs were 3.8  $\mu$ g (150 IU)/100g and 8.7  $\mu$ g (348 IU)/100g. Each city-pair with a higher vitamin D value contained samples of eggs for a specific brand picked up in two non-contiguous states from the same grocery store chain, and those cartons were labeled as follows: 5X MORE VITAMIN D PER EGG.

Reserve samples for the four individual cities that were part of the two city-pairs with higher vitamin D were sent to the laboratory to be analyzed for vitamin D. One of the city values was within the expected range  $(1 \mu g (39 IU) - 1.8 \mu g (71 IU)/100g)$  of the

data for the current estimate. The other three city values were much higher and fell between 7.1  $\mu$ g (284 IU)/100g and 12.1  $\mu$ g (483 IU)/100g. Two of these three samples were from the same store brand, and their respective cartons were labeled as indicated above, and thus higher in vitamin D. The third of the three was obtained from a store brand that had no vitamin D statement on the carton. Additional samples of that brand were sampled, analyzed, and confirmed.

To calculate the final estimate of vitamin D in large, whole eggs, all values from samples which had no vitamin D claims were averaged together to yield a value of 2.0  $\mu$ g (82 IU)/100g with a range of 1.0  $\mu$ g (39 IU)/100g to 9.2  $\mu$ g (368 IU)/100g. The new value is 64% higher than the SR22 value of 1.2  $\mu$ g (50 IU)/100g.

The values for the store brand which contained a vitamin D claim were not used. NDL staff decided that the presence of a claim could influence the selection of that brand by the consumer and may bias the representativeness of the sample set. However, it is clear that some eggs in the marketplace now contain higher levels of vitamin D. It is likely that this change is due to the fortification of specific feeds given to the laying hens. More research will be needed to assess the impact on vitamin D levels in eggs nationwide.

The new value for vitamin  $B_{12}$  (0.89  $\mu$ g/100g) is 31% lower than the value in SR22 (1.29  $\mu$ g/100g). The values for the QC samples were satisfactory.

**Impact**. All egg products that contain egg yolk, where the fat soluble cholesterol and vitamin D are found, were updated to reflect the change in values. NDL food specialists, who use whole eggs and other egg products as ingredients in formulations and recipes, will use these cholesterol and vitamin D values to calculate the composition of those food items. NDL plans to follow up on the sampling and analysis of whole eggs in one to two years to monitor levels of vitamin D in samples nationwide.

# **Legumes and Legume Products (Food Group 16)**

The legumes included in this food group are restricted to the mature, dry seeds of the family Fabaceae or Leguminosae, as well as products made from them. The immature seeds or pods and other parts of the plant, such as leaves, tubers, and sprouted seeds are included in Food Group 11, Vegetables and Vegetable Products, when appropriate.

The sources of nutrient data include the scientific literature, analytical studies conducted by NDL and other government agencies, and the food industry. Since the inception of NFNAP (p. 49) in 1997, a few legumes and legume products (common beans, baked beans, refried beans, chickpeas, peanut butter, and tofu,) have been sampled and analyzed. Data for commonly consumed raw and cooked legumes were obtained by a comprehensive study conducted in the 1980's at the University of Idaho. Data on other raw and cooked legumes, for the most part, have been obtained from the scientific literature. In most cases, data for other processed legumes were supplied by the food industry or obtained from the scientific literature.

Data are presented for raw, cooked, and canned legumes. Legume products, such as fermented legumes, e.g. soy sauce, tempeh, and natto, and other products manufactured from legumes, e.g. peanut butter, tofu and soy milk are also included in this food group. If appropriate, data are presented for both the unprepared and the prepared forms of the food.

Nutrient data for different forms of the same legumes and the legume products were not necessarily derived from the same sample. That is, a single sample of kidney beans was not analyzed in all forms given in the database: raw, cooked, and canned. The data were obtained from many sources and most likely represent different crop years, growing areas, cultivars, processing techniques, lengths and conditions of storage, and possibly different methods of analysis. Therefore, in a comparison of different forms of a legume, nutritional differences should not be ascribed solely to the effect of processing or preparation methods.

Raw legumes.--Although nutrient data were available for several cultivars of some legumes, the data base for any one cultivar was too small to justify giving separate entries by cultivar. Mature legumes are not eaten raw because toxic factors, such as hemaglutinins and trypsin inhibitors (Akroyd and Doughty, 1982), are present. Raw, mature legumes are also unpalatable and hard to digest. The usual processing or preparation methods, such as cooking and canning, remove or inactivate these toxic factors. Cooking or other processing of legumes also makes them more palatable by reducing the beany flavor that some find objectionable.

Prepared legumes.--Nutrient data for cooked legumes were sometimes unavailable or incomplete. In these cases, nutrient values for the cooked form were calculated from data for the raw form of the same legume. For example, nutrient data for boiled peanuts were calculated from data for raw peanuts.

Appropriate true nutrient retention factors were used to calculate the nutrient content of the cooked foods after adjusting for moisture changes. These are presented in the USDA Table of Nutrient Retention Factors, Release 6 (2007) The percentage yields for cooked legumes prepared from raw legumes are given in Table 22. The increased moisture content for cooked legumes leads to the average yield factor of about 2.5.

Table 22. Yields Factors for Selected Cooked Legumes

Legume	Yield Factor Ratio of Weights <sup>1</sup>
Beans:	
Black	2.3
Cranberry	2.3
Great northern	2.5
Navy	2.3
Pink	2.3
Pinto	2.4
Red kidney	2.4
Small red	2.3
Small white	2.3
Broadbeans	2.8
Chickpeas	2.1
Cowpeas	2.6
Lima beans:	
Baby	2.4
Large	2.6
Lentils	2.7
Mung beans	3.2
Peas, split	2.5
Pigeon peas	2.6

<sup>&</sup>lt;sup>1</sup> Ratio of Weights = (Weight of legume cooked / Weight of legume, uncooked)

Sodium values for cooked legumes are relatively low because no salt was added. Since the sodium content of tap water varies according to location (0-39 mg/100g), the sodium value of cooked legumes may be underestimated if the water supply naturally contains significant amounts of sodium. Sodium content of cooked legumes will depend on the amount of salt used in cooking and can be as high as that of canned legumes. Sodium values for cooked legumes with added salt were calculated by adding the sodium content of approximately 1/8 of a teaspoon of salt per 100 grams of legumes or 236 mg of sodium to the sodium naturally occurring in the cooked vegetable with no salt added. Tap water also contains other dissolved minerals. The content varies considerably depending on the source and treatment of the local water supply.

Retention values are generally based on cooking methods that minimize the loss of nutrients, particularly the water-soluble vitamins, primarily due to leaching into the

cooking water. Nutrient values of cooked legumes obtained by these procedures tend to be higher than those values for the same legumes cooked by less-than-optimum methods. Some conditions that affect the retention of nutrients in legumes include cooking method, size and shape of the legumes or amount of surface area, maturity, condition of the legume, proportion of broken seeds, amount of cooling water and cooking time.

Nutrient values for multi-ingredient mixtures such as home-prepared Boston baked beans were calculated from recipes developed by the U.S. Department of Agriculture. Values for each nutrient provided by the ingredients used in the recipe were totaled. Nutrient values were adjusted by using appropriate nutrient retention values to account for any changes caused by evaporation or hydration and heat destruction due to cooking procedures.

Data for canned legumes were often developed for the purpose of nutritional labeling; therefore data are presented for the total can contents. During the canning process, and sometimes during cooking, the cotyledons of legumes rupture, releasing starch into the brine; therefore, draining of the liquid medium is difficult. However, cooks do generally drain these products. Some packers may add sugar to certain canned legumes and this may also affect the nutrient content.

Nomenclature.--To aid in identifying individual legumes listed in the tables, the scientific name of the legume is included in the food description file, usually on the raw form of the legume. The USDA Germplasm Resources Information Network (GRIN), (USDA, 2011) was used as the basic reference for the scientific and preferred common names.

Identifying legumes by their common names, however, is often confusing because these names are not always applied to the same food in different geographical locations. Some names of legumes in common use or unique to one region of the country have been included in the common name filed of the food description file. Additional descriptions of legumes and legume products are provided in the following paragraphs.

In other countries and among immigrants to the United States, various terms are often substituted for "legume." The term "pulse" is sometimes used for a legume having a low fat content. Pulses include common beans, broadbeans, peas, and lentils. Soybeans and peanuts are sometimes referred to as leguminous oilseeds (Akroyd and Doughty, 1982). Data on oils derived from these sources, are found in Food Group 4, Fats and Oils.

"Dhal" or "dal" are legumes that have been dehulled and split. This practice is common in India to shorten the cooking time. "Gram" is a term sometimes used in India for the whole seed of any legume (Yamaguchi, 1983) and sometimes used as another name for the chickpea (Duke, 1981). There are a number of other "grams." For example, red gram refers to pigeon peas, green gram to mung beans, and Bengal gram to chickpeas.

Adzuki beans (*Vigna angularis*) are grown primarily in East Asia, but have been introduced into the southern United States and Hawaii. These beans are eaten either boiled or fried. Adzuki beans ground into a fine paste are used in some confections, such as yokan. Canned adzuki beans, sweetened with sugar, are commonly sold in Hawaii (Duke, 1981).

Common beans (*Phaseolus vulgaris*) are native to the tropical areas of Central and South America. They include black, black turtle soup, cranberry, French, great northern, kidney, navy, pink, pinto, and white beans, which are widely grown in many areas around the world. White beans are commonly used to prepare many types of baked beans. Pinto beans are used in many Mexican recipes (Akroyd and Doughty, 1982, Duke, 1981). Data were combined for several types of kidney beans to produce an overall figure for kidney beans.

The broadbean (*Vicia faba*) has been cultivated in the Mediterranean region and the Near East since ancient times. It was the only bean known to Europeans until the common bean (*P. vulgaris*) was introduced from the New World. There are two major subspecies of broadbeans. Var. <u>major</u>, which has large flat seeds, is usually consumed by humans. Var. <u>equina</u>, which has small, globular seeds and commonly called field bean or horse bean, is used for feeding livestock. Broadbeans are used in many dishes in the Mediterranean region, such as falafel (Akroyd and Doughty, 1982).

Carob flour or powder (*Ceratonia siliqua*), also called St. John's bread, is found in many "health foods" as a chocolate replacement. The seeds are ground to extract a gum, known as locust bean gum, which is used in many food and industrial products. The pods are ground to produce carob flour. Vegetable oil or other fats are frequently added to the raw carob flour to make confectionary coatings or candy bars. The carob tree is native to the eastern Mediterranean region and has been introduced to California and other areas (Akroyd and Doughty, 1982, Duke, 1981).

Chickpeas (*Cicer arietinum*) or garbanzo beans are one of the most commonly consumed legumes in India and in the Near East (Akroyd and Doughty, 1982). In the United States, canned or cooked chickpeas are a common item at many salad bars. In the Near East chickpeas are used in many dishes such as hummus and falafel. These items have become more popular in the United States.

Cowpeas (*Vigna unguiculata*), or black-eyed peas, are cultivated in the southern United States and in many tropical areas. There are three major subspecies: *Vigna unguiculata unguiculata* is the common cowpea or black-eyed pea; *Vigna unguiculata cylindrica*, or catjang, is used whole or split but is more frequently used as forage; *Vigna unguiculata sesquipedalis*, or yardlong bean, has pods that may grow to 36 inches in length and is commonly used in the Orient as a vegetable. The mature seeds are also used (Akroyd and Doughty, 1982).

Hyacinth beans (*Dolichos purpurens*), also known as lablab, are native to Asia and have been cultivated in India for centuries. The mature seeds are eaten as a dahl.

Lentils (*Lens culinaris*) originated in the Near East and Mediterranean areas. The seeds are usually boiled and served in soups and stews (Akroyd and Doughty, 1982).

Lima beans (*Phaseolus lunatus*) originated in tropical regions of the Americas and are now grown in tropical and subtropical areas around the world. Baby lima beans grow in most areas of the United States (Duke, 1981). There are two major subgroupings of lima beans: the small or baby type and the large lima beans.

Lupins (*Lupinus* spp.) are found in the Americas and in the Mediterranean region. There are four major species. White or Egyptian lupins (*Lupinus albus*) are common in the Mediterranean region and were cultivated by the Romans. Seeds are treated by soaking, then boiling, and sometimes additional soaking. Sweet strains with less alkaloids have been developed.

Blue lupin (*Lupinus angustifolius*) originated in northern Europe and is grown primarily for animal feed. Yellow lupin (*Lupinus luteus*) is native to southern Europe and the Mediterranean. Low-alkaloid varieties have been developed. Tarwi or pearl lupin (*Lupinus mutabilis*) has been grown in South America for centuries. Special preparation methods are required to remove the alkaloids. Low-alkaloid types are being developed (Akroyd and Doughty, 1982, Duke, 1981). Because of limited data, nutrient values for all four subspecies have been combined in the tables.

Mothbeans (*Vigna aconitifolia*) are native to India and are eaten whole or as a dhal. The seeds are also used as a source of flour (Duke, 1981).

Mung beans (*Vigna radiata*), also called green gram in India, are native to tropical areas of Asia and are widely grown there. Recently, mung beans have been introduced to the United States. In China and the United States mung beans are commonly grown for sprouting and are consumed as a vegetable. The mature seeds can be boiled and eaten. They can also be ground into a flour for use in bakery products and fried snack foods (Akroyd and Doughty, 1982). Mung beans are also made into a noodle-like product called long rice. A similar product made from mung bean flour is cellophane noodles.

Mungo beans (*Vigna mungo*), sometimes called black gram, originated in India and are also grown in the West Indies (Vaughan and Geisler, 1997). Mungo beans are eaten either whole or as a dhal. They also can be boiled or roasted and ground into flour for use in cakes and breads.

Peas (*Pisum sativum*), or field peas, originated in southwest Asia and are now grown in temperate areas around the world (Akroyd and Doughty, 1982). They were once named as different species—garden peas and field peas—but are now classified together. Field peas are hardier, have smaller seeds, and are usually grown for the mature seeds.

Peanuts (*Arachis hypogaea*), native to Latin America, are now grown in tropic, subtropic and warm-temperate areas of the world. In the United States over 50 percent of the peanuts are processed into peanut butter, about 21 percent are roasted, and about 16 percent are used in confections (Duke, 1981). In other countries, peanuts are produced primarily for their oil and the remaining peanut cake is used for livestock feed. The three main types of peanuts are Virginia, Spanish, and Valencia. Virginia peanuts have large seeds and usually contain two seeds per pod. Spanish peanuts have small seeds and their pods also contain two seeds. Valencia peanuts also have small seeds and the pods contain two to five seeds (Brouk, 1975). Nutrient data on the different cultivars of peanuts were combined to generate overall values for peanuts: Virginia (including runner), 90.6 percent; Spanish type, 8.5 percent; and Valencia type, 0.9 percent. By federal regulation (21 CFR 164.150), peanut butter must contain at least 90 percent peanuts, and not more than 10 percent seasonings (including sugar, salt, and oil), and stabilizing ingredients.

Pigeon peas (*Cajanus cajan*), or red gram, were probably native to Africa, spreading in prehistoric times to Asia (Vaughan and Geisler, 1997). In India, pigeon peas are usually consumed as a dahl.

Soybeans (*Glycine max*) are among the most important sources of protein and oil known to man. Indigenous to eastern Asia, where they have been used in myriad ways for centuries, soybeans are now cultivated in eastern and southeastern Asia as well as in the Americas, predominately in the United States and Brazil (Akroyd and Doughty, 1982, Duke, 1981, Vaughan and Geisler, 1997). A number of fermented soybean products are known in the Orient, and in recent years these have attracted a following in the United States.

Shoyu (Japanese soy sauce) is made from equal parts soybeans and cracked, roasted wheat, plus salt and water. The mixture is inoculated with *Aspergillus soyae* mold and fermented from 6 months to as long as 5 years. Tamari is a different product made with little or no wheat. In the United States a non-fermented, synthetic product known as soy sauce is prepared from hydrolyzed soy protein, caramel coloring, corn syrup, salt, and water (Shurtleff and Aoyagi, 1979a) rather than using the traditional fermentation method. Soy sauces are commonly used as condiments in east and southeastern Asian style cooking. It is also used in western cuisines and prepared foods.

Miso, or soy paste, is made from soybeans, a grain (either rice or barley), salt, and water. The mold *Aspergillus oryzae* is introduced for fermentation (Shurtleff and Aoyagi, 1976). Many different types of miso are marketed and rarely are identified in the scientific literature. Data for a number of market samples have been combined in the database, which explains the somewhat large variation in some nutrient values.

Natto is made from whole, cooked soybeans, which are inoculated with the bacterium *Bacillus subtiis*. Natto is often served over rice or noodles as a main dish or used in soups and salads (Shurtleff and Aoyagi, 1979a).

Tempeh, from Indonesia, is made from cooked soybeans bound together with the mycellia of the mold *Rhizopus mycellius*. The product is made into cakes or patties and often sliced and fried (Shurtleff and Aoyagi, 1979b).

Tofu, another soy product, is prepared by precipitating the protein of soy milk with any of several coagulants. Tofu is prepared by soaking the whole soybeans overnight and later grinding them with water before draining. The resulting soy milk is pressed from the cooked, ground soybeans, leaving a white or yellowish pulp consisting of the insoluble parts of the soybean. This pulp is known as okara, and can be used in many recipes (Shurtleff and Aoyagi, 1979a). Any of several coagulants is then added to precipitate the protein and form the curds. Nigari, the traditional coagulant used in Japan, contains primarily magnesium chloride. Calcium chloride, calcium sulfate, seawater, lemon juice and vinegar can also be used. As expected, the composition of the coagulant affects the calcium and magnesium content of the finished product. Excess liquid is pressed from the curd, which in turn affects the firmness of the tofu (Shurtleff and Aoyagi, 1979a). Tofu is available in a number of "firmness" types, i.e. soft, silken, medium, firm, extra firm, and others reflecting the amount of water pressed from the curd. The amount of water pressed from the tofu, reflected in the firmness term used, will also have concomitant effect on the nutrient content—firm tofu with less water will have a higher nutrient content than soft types with more water. However, there is no standard for these terms, and one company's tofu using a particular term, may be more similar to another company's product using a different term.

Soy milk is a beverage produced commercially from soybeans. In the United States, soy milk may be used by individuals who choose not to consume animal products, are allergic to cow's milk or who are lactose intolerant. Some infant formulas are based on soy milk. Soy milk can be processed in many of the same ways as cow's milk and can be substituted for it in many recipes.

In the United States and in other countries, soybeans are utilized as a source of oil, and the resulting defatted meal was formerly used for animal feed. In recent years, however, the defatted soy meal has been used in the preparation of many soy-based products. Soy flour and soy grits can also be prepared from the defatted meal. Soy flour is used in many foods as is or may be extruded into various soy-based products. Soy protein concentrates are processed to remove most of the non-protein compounds, primarily soluble sugars, from the defatted soy flour by wet extraction. Concentrates are often extruded in the preparation of many products.

Soy protein isolates have had nearly all the non-protein constituents removed. The soy extract can be either spray-dried or extruded into an acid medium to form fibers resembling meat, which are marketed as textured vegetable protein. Soy protein isolates are also used as an ingredient in a number of food products, both as a protein extender and for their functional properties.

Modern processing methods have been used experimentally on a number of other legumes, but none have reached large—scale commercial production or have gained

the commercial acceptance of soy products.

Winged beans (*Psophocarpus tetragonolobus*) are native to southeast Asia and have been introduced to tropical areas of the United States, such as Hawaii, Puerto Rico, and southern Florida. The pods, leaves, stems, and tubers of this plant are all edible and are included in Food Group 11, Vegetable and Vegetable Products.. Only data on the mature seeds, however, are reported here. The mature seeds can be steamed, boiled, roasted, fermented, or processed into milk or into products such as tofu or tempeh (BOSTID, 1981).

# References for Notes on Foods – Legumes and Legume Products

Akroyd, W.E. and Doughty, J. 1982. Legumes in Human Nutrition. FAO Food and Nutrition Paper No. 20. Food and Agricultural Organization of the United Nations. Rome, Italy. 152 pp.

Board on Science and Technology for International Development (BOSTID), National Research Council. 1981. The winged Bean – A High Protein Crop for the Tropics. National Academy Press. Washington, D.C. 46 pp.

Brouk, B. 1975. Plants Consumed by Man. Academic Press. New York. 479 pp.

Duke, J.A. 1981. Handbook of Legumes of Economic Importance. Plenum Press. New York. 345 pp.

Shurtleff, W. and Aoyagi, A. 1976. The book of Miso. Ballantine Books. New York, 618 pp.

Shurtleff, W. and Aoyagi, A. 1979a. The book of Tofu. Ballantine Books. New York, 433 pp.

Shurtleff, W. and Aoyagi, A. 1979b. The book of Tempeh. Ballantine Books. New York, 247 pp.

U.S. Department of Agriculture, Agricultural Research Service, National Genetic Resources Program. 2011. *Germplasm Resources Information Network - (GRIN)* [Online Database]. National Germplasm Resources Laboratory, Beltsville, Maryland. http://www.ars-grin.gov/cgi-bin/npgs/html/tax\_search.pl (Accessed 7/11/2012)

Vaughan, J.G. and Geisler, C.A. 1997. The New Oxford Book of Food Plants. Oxford University Press. New York. 239 pp

Yamaguchi, M. 1983. World Vegetables – Principles, Production and Nutritive Values. Avi Publishing Company. Westport, Ct. 415 pp.

# **Nut and Seed Products (Food Group 12)**

### Introduction

There are currently 127 food items in the Nut and Seed Products food group within the USDA National Nutrient Database for Standard Reference (SR). The sources of nutrient data for these items released in SR include the scientific literature, analytical studies, and food industry. In 1999 the International Tree Nut Council (INC) collaborated with the Nutrient Data Laboratory (NDL) to sample and analyze almonds, hazelnuts, macadamias, pecans, pistachios, and English walnuts. Since 2002, additional data were obtained via NDL's National Food and Nutrient Analysis Program (NFNAP) (p. 49) for those nuts as well as almond butter, Brazil nuts, cashews, and pine nuts; and flaxseed, pumpkin, sesame and sunflower seeds. The Almond Board of California provided data on many varieties of almonds commonly grown in California. The Western Pistachio Association (now called American Pistachio Growers) provided data on both raw and dry roasted pistachio nuts. These industry data were then aggregated with the INC and NFNAP data. The remaining nut and seed nutrient data were derived primarily from the scientific literature.

Apparent nutritional differences in estimates for different forms of nuts and seeds are not necessarily due to the effects of processing or preparation methods. Different forms of nuts and seeds (e.g., raw, oil roasted and dry roasted) usually were not of a common sample origin. Data were obtained from many sources and may represent different growing years, growing areas, cultivars, processing techniques, lengths and conditions of storage, laboratories, and possibly different methods of analysis. The above factors, together with natural variability, may lead to difference in nutrient content not related to the processing or preparation methods. The USDA ARS Germplasm Resources Information Network (GRIN) database (USDA, 2012) was used as the basic reference for scientific names and preferred common names.

### Nuts

Several tree nuts which are grown in the United States and are commercially important in the food supply are: almonds, black walnuts, English walnuts, hazelnuts (filberts), macadamia nuts, pecans, pinyon, and pistachio nuts. In fact, the United States produces over one-tenth of the world's tree nuts and provides about a quarter of world exports (USDA, 2011). Most coconuts consumed in the United States are imported, but in some tropical areas, coconuts are readily available from the coconut palm tree. Other nuts must be imported, such as Brazilnuts, cashew nuts, European chestnuts, ginkgo nuts, and pine nuts. Detailed information about tree nut imports and exports can be found through the USDA's Economic Research Service at www.ers.usda.gov. Relatively small amounts of nuts are gathered by the consumer, either from the woodlands or from trees used to landscape property. Nuts in this category are acorns, beechnuts, butternuts, Chinese and Japanese chestnuts, and hickorynuts. Black walnuts are gathered by families across 16 states and bought by nut companies to be shelled and packaged for sale to consumers (Hammons, 2007). Botanically, peanuts

and soybeans are legumes, not tree nuts. Thus, they are found in the Legume and Legume Products Food Group 16. Nearly all nuts must be dried or cured prior to being consumed. Drying nuts to a low moisture content—either by sun drying or by mechanical drying—prevents deterioration of the nut and protects its quality during storage (California Walnut Board, 2011). Although coconuts can be eaten raw, directly from the tree, harvested green coconuts are partially dried or seasoned in the field (Grimwood, 1975). According to USDA's Economic Research Service (2010), the per capita consumption of tree nuts has increased from 2-1/4 pounds in the 1980's and 1990's to 3 ½ pounds as of 2009.

**Almonds** (*Prunus dulcis*) make up over 1/3 of the per capita consumption of tree nuts in the U.S. (USDA, 2010). About 80% of the world's supply and approximately 100% of the domestic supply are grown in the Central Valley of California. The market forms available include inshell almonds; shelled almonds in many unblanched and blanched forms (whole, sliced, slivered, chopped, and ground); almond paste made from ground unblanched or blanched almonds blended with sugar; almond butter made from ground dry roasted almonds blended with salt and a stabilizer; almond meal; and almond powder or flour (Almond Board of California, 2010).

**Brazilnuts** (*Bertholletia excelsa*) come from large trees that grow in the tropical jungles of the Amazon Basin. They are produced mainly in Bolivia, Brazil, and Peru. Both inshell and shelled Brazilnuts are marketed (INC, 2008). These nuts are known for their very high selenium content, which is highly variable, depending on the geographic location where the nuts are found (Chang, 1995).

**Cashew nuts** (*Anacardium occidentale*), which are native to Brazil, are cultivated in many tropical countries, especially India, Vietnam, Mozambique and Brazil (INC, 2008). Before the cashew nuts are eaten, the corrosive liquid between the shells must be removed by some form of heat treatment (Woodroof, 1979), generally roasting. Raw cashews have been heat-treated to safely remove the kernel from the shell, but have not been further roasted.

Most **coconuts** (*Cocos nucifera*) eaten in the United States are consumed as dried (desiccated) coconut, a form of coconut meat that has been shredded, disintegrated, and then thoroughly dried in hot air driers (Grimwood, 1975). Unsweetened and sweetened coconut comes in many forms, called cuts. The two types of coconut cuts most often found in retail markets are flaked and shredded desiccated sweetened coconut (General Foods, 1982). Another type of desiccated coconut is toasted coconut which may be either unsweetened or sweetened (Ruehrmund, 1974).

**HazeInut** and filbert are names used interchangeably for species of the genus *Corylus* (HazeInut Council, 2008; Woodroof, 1979). HazeInuts are grown commercially in Oregon and Washington, but filberts are also imported from Turkey, Italy, France, and Spain to meet the demand for this nut (Woodroof, 1979; INC, 2008). These nuts are marketed in-shell and shelled, roasted or salted, and used for the preparation of several food products such as candy and ice cream (INC, 2008).

**Macadamia nuts** (*Macadamia integrifolia, M. tetraphylla*) are native to Australia. The *M. tetraphylla* variety has a rough shell which is not as good for roasting. The largest producers of macadamia nuts are Hawaii, Australia, South Africa, and Guatemala (INC, 2008). Dry roasted, salted macadamia nuts are readily available throughout the United States.

**Pecans** (*Carya illinoinensis*) are native to temperate North America, originating in central and eastern areas. The leading producers of pecans are Georgia and Texas, but they are also grown in several other states including Arizona, the Carolinas, Florida, and New Mexico, as well as Mexico. Over 80% of pecans sold have been shelled (NPSA, 2008).

One **pine nut** species, pinyon (*Pinus edulis*), is an important source of food and revenue for Native Americans in the Southwest. Very little recent information on the nutrient content of pinyons is available, except for the unpublished data of Lanner (1975) and Weber (1983). Most pine nuts (*Pinus* spp.) are imported from Italy, Spain, China, Portugal, and Turkey (INC, 2008). Pine nuts are marketed in shelled form and are generally used in the confectionery industry (INC, 2008) and as an ingredient in recipes.

**Pistachio nuts** (*Pistacia vera*) are cultivated in the United States, Iran, Turkey, Greece, Syria, and Italy. California is the major producer of pistachios in the U.S., with Arizona and New Mexico as additional sources. Pistachios are marketed primarily roasted and salted in their shell, but are also available unsalted and shelled (INC, 2008). Natural ivory-shelled and red-dyed pistachio nuts are available, but the percentage of dyed nuts is currently very small (American Pistachio Growers, 2011).

**English walnuts** (*Juglans regia*), which are often just called "walnuts," originated in Persia (now known as Iran). Thus, they were first called Persian walnuts (Woodroof, 1979). After these walnuts were introduced to England and then brought to America they were called English walnuts (Brouk, 1975; Woodroof, 1979). Today, the Central Valley of California is the center of commercial production in the United States: 78% of the world's supply and nearly all of the U.S. production (California Walnut Board, 2011).

**Black walnuts** (*Juglans nigra*), are native to North America (Brouk, 1975). These walnuts, which are very hard to crack, are harvested wild from woodlands and from cultivated trees (Brouk, 1975, Woodroof, 1979) in the Midwest and East-Central part of the United States (Hammons, 2007).

#### Less Common Nuts

**Acorns** (*Quercus* spp.) are eaten raw, dried, or roasted in many parts of the world. American pioneers and native Americans ground acorns into meal to make bread or to thicken soups (Millikan, 1979). Most acorns contain potentially toxic tannins which must be leached out of the acorns before they are eaten. The literature contains very little recent information on the nutritive value of acorns. Weber, however, has made

unpublished data available on the nutrient content of dried acorn kernels and full-fat acorn flour both of which are used by the White Mountain Apache Indians (Weber, 1983). Also see NDB No. 35182 for acorn stew which is an Apache dish.

Although **beechnut** trees (*Fagus spp.*) are found in many wooded areas, very few produce beechnuts that have a sweet flavor (Millikan, 1979). Beechnuts from these trees are difficult to gather for food because of their small size and poor nutmeat development.

**Butternuts** are another species of *Juglans* (*Juglans cinerea*). The trees are native to the Eastern United States and adjacent areas of Canada (USDA NRCS, 2011). The number of butternut trees in North America has decreased dramatically due to a canker fungal disease and other factors. The tree is considered an endangered species in Canada (Ministry of Natural Resources, 2009) and a species of special concern in all United States National Forests (Woeste and Pijut, 2009). Butternuts are used in baked products and candies due to their oily texture and nice flavor (Woeste and Pijut, 2009).

Almost all of the trees of the American **chestnut** (*Castanea dentata*) have been destroyed by fungus blight. Today, Chinese chestnut (*Castanea mollissima*) trees, which are blight resistant, are sold in place of the American chestnut for yard and orchard culture (Jaynes, 1979). Some Japanese chestnuts (*Castanea crenata*) are imported from Japan and some are grown in the United States, although these chestnuts are not as well adapted to the North American climate as the Chinese chestnuts (Jaynes, 1979). European or Italian chestnuts (*Castanea sativa*) are available in markets around the holiday season and are also sold roasted on street corners of some cities.

Dried **ginkgo nuts** (*Ginkgo biloba*) resemble almonds but are whiter, fuller, and rounder (Hedrick, 1972). Canned ginkgo nuts imported from Japan are readily available in Asian markets in the United States.

**Hickorynuts**, which are native to the woodlands of the United States, belong to the *Carya* species (Woodroof, 1979). Shagbark hickorynuts (*Carya ovata*) are moderate in size and thin shelled, while shellbark hickorynuts (*Carya laciniosa*) are larger nuts with a thick shell (Woodroof, 1979).

**Pilinuts** (*Canarium ovatum*) are imported from the Philippines. In the United States, markets featuring Philippine foods stock candied pilinuts.

#### Seeds

Seeds are grown primarily for their edible oils, because they have a very high fat content. Some seeds are eaten with very little home or commercial processing. Like nuts, some of the seeds are commercially important and can be easily purchased in retail or wholesale markets. Other seeds are available only to those having access to the growing plants or trees.

Both **pumpkin and squash seeds** (*Cucurbita* spp.) are consumed in the United States. Dried pumpkin and squash seeds and roasted pumpkin seeds are available in retail markets. Whole squash seeds are eaten roasted and salted by the Navajo Indians (Weber, 1983). Safflower seed (*Carthamus tinctorius*) is grown in the United States – primarily California – as well as in Mexico, India, and the Middle East (U.S. ITC, 2003). Although there has been some interest in using safflower seed meal and flour, safflower is cultivated primarily for oil in the seeds.

During the Civil War, **cottonseed** (*Gossypium* spp.) was parched and ground as a coffee substitute in the South (Hedrick, 1972). Today, glandless cottonseed products such as roasted kernels, flour, and meal are used as ingredients in a variety of products (Simmons, 1980) such as candy and baked products.

**Sesame seed** (*Sesamum indicum*) is native to East Africa and is grown in China, India, Ethiopia, Sudan, Nicaragua, Mexico, Guatemala, and the United States (Brouk, 1975). A paste form of sesame butter, is made from the whole seed, while tahini, another type of sesame butter, is made from the kernel.

In the summer, **watermelon seeds** (*Citrullus lanatus*) are readily available from raw watermelons, but are probably seldom eaten from this source. Dried watermelon seeds, imported from Thailand and Taiwan, can be found in Asian markets in the United States.

**Breadfruit** trees (*Artocarpus altilis*) are found throughout the Tropics. Although most breadfruit trees bear fruit that is seedless, some cultivars contain seeds. In the seeded cultivars, the fruit pulp is almost nonexistent and the breadfruit seeds take up almost all the space inside the fruit (Brouk, 1975). Breadfruit seeds are boiled, roasted, or fried as a snack. They can also be ground into flour or used as nuts in baked products (FAO, 1989, South Pacific Commission, 1983). In the American Tropics and Mexico, the breadnut tree (*Brosimum alicastrum*) produces yellow fruit with single seeds, also called ramóns (Peters and Pardo-Tejeda, 1982). The seeds are eaten raw or boiled and can be toasted and ground into a meal to make flatbread or a coffee-type beverage (Rocas, 2003).

One of the species of **Sisymbrium** (*Sisymbrium* spp.) is also known as tumble mustard. Native Americans of the Navajo nation use these dry ground seeds, which they call "k'ostse," as an ingredient of cornbread (Weber, 1983). Small-seeded plants that differ botanically from cereals, but that are cultivated like cereals in fields and ground into flour to make bread and similar products, are called pseudo-cereals (Brouk, 1975).

One of these pseudo-cereals is **chia seed** (*Salvia hispanica*) which is native to Mexico (Brouk, 1975).

The sacred **lotus** (*Nelumbo* spp.) is an aquatic plant found in China and India (Brouk, 1975). In the United States, Asian markets stock the dried, whole lotus seed which is

imported from China. Traditionally, the seeds are roasted, candied, cooked in soup, and made into a paste for sauces and moon cakes (Dharmananda, 2002).

Cultivars of the confectionery type of **sunflower seeds** (*Helianthus annuus*) are generally black with white stripes and are larger than oilseed type cultivars (Adams, 1982). Whole sunflower seeds, sunflower kernels, and sunflower butter are sold.

### References for Notes on Foods – Nuts and Seeds

Adams, J., ed. 1982. Sunflower. The National Sunflower Association, Bismark, ND.

Almond Board of California. 2010. Almond technical information kit. www.almondboard.com. (Accessed 5/16/2012)

American Pistachio Growers (formerly Western Pistachio Association). 2011. Personal communication, Richard Matoian, Executive Director, July 27, 2011. Brouk, B. 1975. Plants consumed by man. Academic Press, New York, NY.

California Walnut Board. 2011. California walnut history, cultivation & processing. www.walnuts.org. (Accessed 5/16/2012)

Chang, J.C., W.H. Gutenmann, C.M. Reid, and D.J. Lisk. 1995. Selenium content of Brazil nuts from two geographic locations in Brazil. Chemosphere 30:801-802.

Dharmananda, S. 2002. Lotus seed: food and medicine. Institute for Traditional Medicine, Portland, OR. http://www.itmonline.org/arts/lotus.htm. (Accessed 5/16/2012)

Food and Agriculture Organization (FAO). 1989. Utilization of tropical foods: trees. http://books.google.com (Accessed 7/18/2012)

General Foods Corporation. 1982. Tarrytown, NY. (Unpublished data; personal communication).

Grimwood, B.E. 1975. Coconut palm products: Their processing in developing countries. Rome: Food and Agriculture Organization of the United Nations, (FAO Agricultural Development Paper No. 99).

Hammons Products Company. 2007. Taste the Wild Side of the Black Walnut. http://www.hammonsproducts.com. (Accessed 5/16/2012)

Hazelnut Council. 2008. www.hazelnutcouncil.org. Hedrick, U.P., ed. 1972. Sturtevant's edible plants of the world. Dover Publications, Inc., New York, NY. International Tree Nut Council (INC), Nutrition Research & Education Foundation. 2008. www.nuthealth.org.

Jaynes, R.A. 1979. Chestnuts. <u>In Nut tree culture in North America (ed. R.A. Jaynes)</u>. Northern Nut Growers Association, Inc., Hamden, CN.

Lanner, R.M. 1975. Department of Forestry and Outdoor Recreation, Utah State University, Logan. (Unpublished data).

Millikan, D.F. 1979. Beeches, oaks, pines, and ginkgo. <u>In Nut tree culture in North America</u> (ed. R.A. Jaynes). Northern Nut Growers Association, Inc., Hamden, CN.

Ministry of Natural Resources, Ontario. 2012. Butternut (Juglans cinerea). http://www.mnr.gov.on.ca/stdprodconsume/groups/lr/@mnr/@species/documents/document/stdprod 070895.pdf (Accessed 5/16/2012).

National Pecan Shellers Assocation (NPSA). 2008. www.ilovepecans.org (Accessed 5/16/2012)

Peters, C.M. and E. Pardo-Tejeda. 1982. <u>Brosimum alicastrum</u> (Moraceae): Uses and potential in Mexico. Economic Botany 36:166-175.

Rocas, A.N. 2003. <u>Brosimum alicastrum</u> Sw. In: Tropical Tree Seed Manual. Reforestation, Nurseries, & Genetics Resources, <a href="http://www.rngr.net">http://www.rngr.net</a> (Accessed 5/16/2012).

Ruehrmund, M.E. 1974. "Golden Toasted Coconut" in candies and cookies. Confectionary Production 40:402-404.

Simmons, R.G. 1980. Glandless cottonseed—A new food crop. Texas Agricultural Progress, Winter.

South Pacific Commission. 1983. Leaflet No. 9 - 1983 – Breadfruit. http://www.fao.org/WAIRdocs/x5425e/x5425e09.htm (Accessed 5/16/2012).

- U.S. Department of Agriculture, Agricultural Research Service. 2012. Germplasm Resources Information Network (GRIN) website. http://www.ars-grin.gov (Accessed 5/16/2012).
- U.S. Department of Agriculture, Economic Research Service. 2010. Fruit and tree nuts situation and outlook yearbook. www.ers.usda.gov (Accessed 5/16/2012).
- U.S. Department of Agriculture, Economic Research Service. 2011. Briefing Rooms. Fruit and Tree Nuts: Trade. www.ers.usda.gov/briefing/fruitandtreenuts/trade.htm (Accessed 5/16/2012).

USDA, NRCS. 2011. The PLANTS Database (http://plants.usda.gov, 1 June 2011). National Plant Data Team, Greensboro, NC 27401-4901 USA.

U.S. International Trade Commission (U.S. ITC). 2003. USITC Publication 3576. Industry & Trade Summary: Oilseeds. Office of Industries, Washington, DC 20436.

Weber, C.W. 1983. Department of Nutrition and Food Science, University of Arizona, Tucson. (Unpublished data).

Woeste, K. and Pijut, P.M. 2009. The peril and potential of butternut. http://www.agriculture.purdue.edu/fnr/htirc/pdf/publications/Arnoldia%202009.pdf (Accessed 5/16/2012)

Woodroof, J.G. 1979. Tree nuts: Production, processing, products. 2<sup>nd</sup> ed., AVI Publishing Co., Westport, CN.

# **Pork Products (Food Group 10)**

### Introduction

Nutrient and food composition data for pork products are presented in the USDA National Nutrient Database for Standard Reference (SR). The data in SR represent the amount of each constituent in 100 grams of edible portion. The edible portion of pork may be represented as "separable lean and fat" or as "separable lean only". In each case, bone and connective tissue are removed from the cut and reported as refuse. In the case of "separable lean and fat", it is assumed that all fat present is consumed. For items described as "separable lean only", all external trim fat as well as trimmable seam fat are removed from the cut, and included in the reported refuse. Weights are determined for the whole retail cut as purchased, and for each component (e.g. refuse, separable lean, etc). The external trim fat and the seam fat are combined for analyses. weighed, and reported as separable fat. Nutrient analyses are conducted on the separable lean and the separable fat. The nutrient values for separable lean and separable fat are combined and weighted for their respective contributions to the whole retail cut; the resulting food items are reported as "separable lean and fat". For cooked pork cuts, the cuts are cooked with the separable fat intact. Nutrient data for separable fat, separable lean only, and separable lean and fat of cooked cuts are analyzed or calculated as described above.

The analytical nutrient data includes the mean nutrient value, the standard error given to three decimal places, and the number of observations on which the values are based. For many food items, mean values are given without an accompanying standard error and number of samples. These values are either calculated by pooling data or by weighting means, by applying cooking yields or nutrient retention factors to derive values for some cooked foods, or by imputation from a different, closely related food. For raw pork items and unheated cured items, nutrient values were calculated based on known content of the nutrient in the lipid (fatty acids), total solids (cholesterol), moisture-free, fat-free solids (minerals), or protein (water-soluble vitamins) fractions.

#### **Nutrients**

Nutrient information for SR can be found under "File Content" in the documentation. However, some nutrient information specific to pork products are included here. Nutrient values are obtained for moisture, protein, ash, and total fat. The values for protein are calculated from the content of total nitrogen (N) in the food using the conversion factor recommended by Jones (1941). The specific factor for protein applied to pork items is 6.25. The carbohydrate content of uncured products (except for some organ meats) consisting entirely of pork is negligible, and the carbohydrate content is thus assigned a zero value. The sum of the percentages of water, protein, total lipid, and ash do not necessarily equal 100 percent for those foods showing zero carbohydrate because the amounts of each of these constituents were determined independently.

Food energy is expressed in terms of both kilocalories and kilojoules and represents the physiological energy value remaining after losses in digestion and metabolism have been deducted. (One kilocalorie equals 4.184 kilojoules). A broader discussion on energy and calorie factors used in SR can be found under "Food Description" file in the documentation. The specific calorie factors used for calculating energy values in pork products are:

	<u>kcal/g</u>
Protein	4.27
Fat	9.02
Carbohydrate	3.87

The carbohydrate factor of 3.87 is used for estimating energy values for some organ meats and some cured products. The factors are based on the Atwater system for determining energy values. Details of the derivation of these factors are outlined in Agriculture Handbook No. 74 (1973). Because the level of carbohydrate in separable lean and separable fat is insignificant, no carbohydrate factor is needed for these products.

# **Description of Projects**

A series of projects have been conducted to update the pork cuts in the USDA National Nutrient Database for Standard Reference (SR). The studies documented in these notes on pork represent only data collected since 2005. These projects are described in detail below:

# **Natural Fresh Pork Cuts**

Nutrient composition data for fresh pork products in the SR had not been updated since 1991. Since that time, changes in animal husbandry practices and industry procedures led to the availability of leaner cuts. In order to provide up-to-date nutrient information on fresh pork products in SR, the NDL, in collaboration with scientists at the University of Wisconsin and the National Pork Board, conducted a study to determine the nutrient composition of nine (9) fresh pork cuts. This study was funded in part by the National Pork Board. The cuts chosen for evaluation were bone-in shoulder blade steak, boneless tenderloin roast, boneless top loin chop, boneless top loin roast, bone-in sirloin roast, bone-in center loin chop, bone-in center rib chop, bone-in country-style ribs, and bone-in spare ribs. Data from this project were disseminated in a separate report on the NDL web site titled "The Revised USDA Nutrient Data for Fresh Pork" in 2006 and were later incorporated in SR20 (2007).

**Sampling**: Nine fresh pork cuts were pre-ordered and purchased from 12 retail outlets using the nationwide sampling plan developed for NFNAP (Perry *et al.*, 2003) and shipped frozen to the University of Wisconsin for trimming and preparation. Products from each location were assigned randomly to either raw or cooked preparation. For roasts and spare ribs, each roast or rack of ribs was randomly assigned to either raw or

cooked preparation.

# <u>Preparation - Cooking procedures:</u>

**Broiling** (Center Loin Chops, Center Rib Chops, Top Loin Chops). Chops were grilled on a pre-heated George Foreman<sup>™</sup> Indoor/Outdoor Electric Barbeque Grill for 10 minutes, setting "4". External fat thickness and chop thickness were measured prior to cooking; weights of raw cuts were obtained. Two (2) thermocouples were placed into one (1) or two (2) chops, as needed. Chops were turned over when the internal temperature reached 100°-105°F (38°-41°C). Chops were removed from the grill to attain a final internal temperature of 160°F/71°C (chops were taken off the grill at approximately 155°F/68°C internal temperature). Chops were cooled on a wire rack for 5 minutes and the highest internal temperature attained during the standing period was recorded. After standing for 5 minutes, chops were re-weighed.

**Roasting** (Top Loin, Tenderloin, and Sirloin Roasts). Oven was pre-heated to 325°F/163°C (425°F/218°C for tenderloin roast). Top loin, tenderloin, and sirloin roasts were weighed raw, and placed on a rack in a pan for cooking. Top loin roasts (boneless) were roasted as "single" loin roasts (one loin muscle only). If the purchased product was "double top loin roast (boneless)", i.e. two single top loin roasts backed and tied together, the strings were removed, and each half of the double top loin roast was processed as a single top loin roast. Roasts were cooked uncovered. An oven-durable meat thermometer was placed into the geometric center of the roast. Roasts were removed when they achieved an internal temperature of ~150°F/65°C; the target final internal temperature was approximately 160°F/71°C. Roasts were allowed to stand 15 minutes; the final internal temperature was determined during this period. The cooked weight of the roast was obtained and the cooking yield calculated.

**Roasting** (Spareribs). The oven was pre-heated to 325°F/163°C. No external fat measurements were collected, but any gross physical fat (loosely attached) from the raw ribs were removed before cooking. The raw weight of the spareribs was obtained. The number of ribs in the product being cooked was recorded. Spareribs were placed on a rack in a pan, but were not covered during cooking. Ribs were roasted for 1 hour and 45 minutes. Ribs were then removed from the oven; the temperature in the intercostal muscles was immediately taken. Ribs were cooled for 10 minutes, and then re-weighed. When cool enough to process, edible lean was separated from bone/cartilage. Trimmable fat and connective tissue are not an issue in cooked ribs, since it is assumed that, with this product, all soft tissues are consumed.

**Braising** (Shoulder Blade Steaks and Country-Style Ribs). Oven was pre-heated to 325°F/163°C. The raw blade steaks and/or country-style ribs were weighed. The thickness of the external fat around the outer surface of the cuts was measured. Blade steaks or country-style ribs were placed on a rack in a roasting pan. Distilled water (100 ml) was added to the roasting pan, which was covered tightly and placed in the center of the oven. Cooking time was determined from initial trials. Initial cooking time

estimates were: 45 minutes for blade steaks; 1 hour and 15 minutes for country-style ribs. The internal temperature was determined with an electronic digital thermometer. Steaks and/or ribs were allowed to cool for 5 minutes and then re-weighed and the weight was recorded.

# Sample preparation - raw and cooked products:

**Measurement of external trim (separable) fat.** For all chops, blade steaks, and country-style ribs, external fat at the  $\frac{1}{4}$ ,  $\frac{1}{2}$ , and  $\frac{3}{4}$  points along the external fat surface of the product were measured in millimeters. External fat thickness was measured at each of these points. For top loin and sirloin roasts, fat thickness measurements were taken over the center of the exposed fat at the  $\frac{1}{4}$ ,  $\frac{1}{2}$ , and  $\frac{3}{4}$  points along the length of the roast. External fat measurements were not determined on tenderloin roast or spareribs.

**Separation of lean meat, separable fat, connective tissue, and bone**. Dissection of pork cuts was performed from the perspective of a "careful consumer", who conscientiously separates these tissues. The most difficult separation is between the trimmable (separable) fat and connective tissue, which lies in the "seams" between muscles. The separation was accomplished by "scraping" the co-mingled tissues with a knife blade, such that the soft fat was separated from the tougher, stringy connective tissue. Separable lean tissue should be relatively free of trimmable fat, while the trimmable fat should be reasonably free of connective tissue.

Separable lean meat, separable fat, and connective tissue were removed from bones as cleanly as possible. Separable fat (i.e., external trim fat and seam fat), bone, and connective tissue were removed from raw and cooked products and weighed to determine the relative amounts of separable fat and separable lean meat. Component weights (i.e., weights of separable lean, separable fat, bone, and connective tissue) were reported in SR; weights of connective tissue and bone were combined and reported as "refuse". For food items listed "lean only", the separable fat associated with that cut is considered "refuse"; for food items listed "lean and fat", the separable fat is considered edible and contributes to the nutrient profile.

### Sample composites and nutrient analyses:

**Shoulder blade steak, tenderloin roast, and top loin chops**. Shoulder blade steak, tenderloin roast, and top loin chops represent different areas of the pig and are most commonly cooked by grilling, roasting, and braising, respectively. For purposes of this study, these were referred to as the primary cuts since complete nutrient profiles were obtained for both the raw and cooked preparations of these cuts. For each cut, the lean tissue cuts purchased from an individual location were combined into individual composites for homogenization and nutrient analysis; for some nutrients (proximates, minerals, cholesterol, thiamin, niacin, and riboflavin), the number of observations (n) = 12. For pantothenic acid, vitamin  $B_6$ , and vitamin  $B_{12}$ , samples from the three locations were combined to form regional composites (n = 4). One of these composites was randomly chosen and analyzed for retinol (Vitamin A); n = 1. Separable fat from all cuts

were combined to form raw and cooked composites. Complete nutrient profiles were determined for each of these composites (raw and cooked).

**Top loin roasts, sirloin roasts, center loin chops, center rib chops, country-style ribs, and spare ribs.** Proximate nutrients and minerals were analyzed from individual composites for both the raw and cooked preparations of top loin roasts, sirloin roasts, center loin chops, center rib chops, country-style ribs, and spare ribs. For these cuts, cholesterol, thiamin, niacin, and riboflavin were determined from the regional composites of the cooked samples. For some nutrients, values were imputed using established NDL procedures described above. Nutrient values for pantothenic acid, vitamin  $B_6$ , and vitamin  $B_{12}$  for these cooked cuts were imputed from the primary cuts prepared (cooked) in the same manner. Nutrient values (cholesterol, thiamin, niacin, and riboflavin, pantothenic acid, vitamin  $B_6$  and vitamin  $B_{12}$ ) for the raw preparations were imputed from their cooked counterparts. A commercial laboratory, whose analytical procedures were evaluated through the NFNAP process and found to be acceptable, performed tissue homogenization and nutrient analyses.

# **Enhanced Pork Cuts**

Enhanced pork is the process of adding non-meat ingredients to fresh pork to improve the eating quality of the final product where eating quality is defined as the juiciness, tenderness, and flavor of pork (National Pork Board, 1998). As meat producers increasingly raise leaner animals that contain significantly less fat, alternative processes are being developed to replace the flavor loss due to fat reduction and reduce moisture loss resulting from cooking. Enhancing the meat is one such process. It is estimated that 45% of fresh pork cuts are enhanced. Since SR did not provide data for the nutrient content of enhanced meat, a collaborative study was conducted by scientists at USDA, the University of Wisconsin, and the National Pork Board to determine the nutrient profile of the following enhanced products: shoulder blade steak, tenderloin, and top loin chops. This project was funded in part by the National Pork Board.

**Sampling.** Three fresh, enhanced pork cuts were pre-ordered and purchased from 12 retail outlets using the nationwide sampling plan developed for NFNAP (Perry *et al.*, 2003) and shipped frozen to the University of Wisconsin for trimming and preparation.

**Preparation and analysis.** Preparation, compositing, and nutrient analyses for enhanced versions of the shoulder blade steak, tenderloin, and top loin chops were similar to those described for natural fresh pork cuts (see above). Data for enhanced pork cuts were disseminated in SR20 (2007).

# Pork Value Cuts

USDA, in collaboration with the National Pork Board and University of Wisconsin, conducted a study to determine the nutrient profile of four new pork value cuts. This project was funded in part by the National Pork Board. These cuts were introduced to the retail market in 2008-2009. Pork value cuts are individual muscles chosen from the

shoulder and the leg. These cuts were selected for their strong marketability, consistency in flavor and tenderness, availability, and economic feasibility for food chains and consumers. The common names of the four new cuts selected, the scientific name for the muscle, and the part of the carcass from which they originate are as follows:

- Pork Shoulder Breast Boneless (Pectoralis profundi) shoulder
- Pork Shoulder Petite Tender Boneless (Teres major) shoulder
- Pork Leg Cap Steak Boneless (Gracilis) leg
- Pork Leg Sirloin Tip Roast Boneless (Vastus lateralis and Rectus femoris) knuckle and leg.

The nutrient profiles of these four new cuts were released in SR21 (2008).

**Sampling.** A total of 14 paired cuts for each pork value cut were obtained from pork production plants in North Carolina and Iowa. At each plant, both shoulder and hams from 7 randomly selected pork carcasses were obtained. Carcasses were of average weight or slightly heavier to ensure an adequate amount of sample. Proper cut identification of each ham and shoulder from each plant was maintained throughout the fabrication process. Each muscle was denuded, trimmed free of all external fat and connective tissue, and frozen prior to shipment to the University of Wisconsin.

**Sample Preparation.** Among the 7 paired products from each of the two locations, 6 pairs were randomly selected for use in the study. One member of each pair was prepared as raw and the other was cooked either by broiling or braising to a desired internal temperature or time end-point. After a designated cooling period, the cooked product was cubed, hand mixed, and divided into individual carcass samples, and composites of two or three carcasses.

The designated cooking method for each pork value cut were:

- Pectoralis profundi broiled
- Teres major broiled
- Gracilis broiled
- Rectus femoris braised

Cooking methods, broiling. Cuts were grilled on a pre-heated George Foreman™ Indoor/Outdoor Electric Barbeque Grill for 10 minutes on setting "4". Raw cuts were weighed prior to cooking. Internal cooking temperatures were determined by insertion of thermocouples. Cuts were turned-over when the internal temperature reached 100°-105°F (71°-41°C). Cuts were removed from the grill to attain a final internal temperature of 160°F/71°C (cuts were taken off the grill at approximately 155°F/68°C internal temperature). After standing 5 minutes, cuts were re-weighed and the highest internal temperature was attained during the standing period and recorded.

**Cooking methods, braising**. Oven was pre-heated to 325°F/163°C. Temperature was monitored with an oven thermometer. The cuts were weighed prior to cooking and then placed on a rack in a roasting pan. Distilled water (100 ml) was added to the roasting pan, which was covered tightly and placed in the center of the oven. Cuts were braised

until reasonably tender. Cooking time was determined from initial trials. Initial cooking time estimates were: 45 minutes for blade steaks; 1 hour and 15 minutes for country-style ribs. Immediately after removal from the oven, the product was placed on a wire rack. The internal temperature was determined with an electronic digital thermometer. Cuts were allowed to cool for 5 minutes and then weighed.

**Sample analyses.** Proximate nutrients (moisture, total fat, ash, and protein) and cholesterol were determined on individual muscle samples from the shoulder, leg and knuckle, both raw and cooked. For each cut, three samples were pooled into composites and analyzed for fatty acids. Vitamins and minerals were analyzed on samples from the two-carcass composites. Choline and folate analyses were done on the three-carcass composites, raw and cooked. Amino acids were also analyzed on the three-sample composites - raw samples only.

### **Cured Hams**

A new study on cured ham products was conducted by the NDL in collaboration with the University of Wisconsin to update the nutrient profile of various cured ham products in the SR. The word Ham refers to pork meat from the hind leg of a hog. Ham products were available in bone-in or boneless forms.

Cured hams are classified into four categories (USDA-FSIS, 2007):

- Ham at least 20.5% protein in the lean area with no water added;
- Ham with Natural Juices (HNJ) at least 18.5% protein with a small addition of water when cured:
- Ham Water added (HWA) at least 17% protein with no more than 10% added solution:
- Ham and Water Product (HWP) less than 17% protein and contains any amount of water but labeling must indicate percentage of "added ingredients".

"Added ingredients" may vary for each ham product. These solutions, flavorings or "added ingredients" may include water, sugar, salt, sodium erythrobate, sodium nitrite, potassium, and magnesium leading to flavor enhancement. Binders such as soy or milk proteins may also be added to help hold water in the ham. These additions of water and flavor enhancers in ham affect its taste and texture.

**Sampling.** The sampling plan used for the study was developed for NFNAP (Pehrsson *et al.*, 2000). The country was divided into four regions, with three consolidated metropolitan statistical areas (CMSA) within each region; two retail stores were selected within each CMSA. Eight different types of ham products were picked up from 12 retail outlets nationwide: 1) ham, bone-in whole; 2) ham, bone-in, shank half; 3) ham with natural juices, bone-in rump; 4) ham with natural juices, bone-in spiral sliced; 6) ham, water added, bone-in, slice; 7) boneless hams (many shapes and sizes); and 8) ham and water product, boneless slices, any type, and/or glazed with sugar, honey, and other ingredients. The sampling procedure

for each category of bone-in hams was to select two half-hams. One of those was a shank-half portion and the other a rump-half portion. It was preferable that the two halves should come from the same manufacturer and from the same category. Pairs of selected, branded, bone-in hams (Maple, Haen, and Brandon) were picked-up for retention studies. All products were vacuum packaged, individually labeled, and sent frozen to University of Wisconsin for further cooking and dissection.

**Sample preparation.** All hams (bone-in and boneless; heated and unheated) were weighed, measured for thickness, and dissected to separate external fat and seam fat. Bone-in hams were further dissected for removal of bone and connective tissue prior to nutrient analyses. Branded hams or paired bone-in whole hams were cut into shank, butt, and slices. One portion from each pair (rumps and shanks) was analyzed "as purchased" and the other roasted to an internal temperature >160°F (71°C). Slices were weighed and measured for thickness prior to being pan-fried to an internal temperature of 64-82°F (18°-28°C). All other types of bone-in and boneless hams were either roasted in a 325°F (163°C) convection oven or pan-broiled to the internal temperature specified on the label. No fat was added during any cooking preparation.

**Sample analyses.** Proximate nutrients (moisture, total fat, ash, and protein) cholesterol, vitamins, and minerals were determined on all categories of bone-in and boneless hams, both heated and unheated. Total sugars and fatty acids were analyzed on all bone-in and boneless forms of "Ham", "Ham with natural juices" and "Ham and water product". Two pairs of "Ham" types, heated and unheated, were analyzed for vitamin K, retinol, choline, and amino acids (unheated only).

#### References for Notes on Foods – Pork Products

Jones, D.B. 1941. Factors for Converting Percentages of Nitrogen in Foods and Feeds into Percentages of Protein. Rev. U.S. Dept. of Agric., Circ. 183, 22 pp.

Merrill, A.L. and B.K. Watt. 1973. Energy Value of Foods—Basis and Derivation. Rev. U.S. Dept. of Agric., Agric. Handb. No. 74, 105 pp.

National Pork Board. 1998. Functionality Of Non-Meat Ingredients Used In Enhanced Pork. National Pork Board Web site:

http://www.pork.org/filelibrary/Factsheets/PorkScience/functionalitynonmeat04527.pdf (Accessed 7/11/2012)

Perry C.R., P.R. Pehrsson, and J. Holden 2003. A Revised Sampling Plan for Obtaining Food Products for Nutrient Analysis for the USDA National Nutrient Database 2003. Proceedings of the American Statistical Association, Section on Survey Research Methods [CD-ROM], Alexandria, VA: American Statistical Association, San Francisco

Pehrsson, P. R., D.B. Haytowitz, J.M. Holden, C.R. Perry, and D.G. Beckler, 2000. USDA's National Food and Nutrient Analysis Program: food sampling. Journal of Food Composition and Analysis 13:379-389.

U.S. Department of Agriculture, Food Safety and Inspection Service. 2007. Ham Glossary – Ham and food safety fact sheet: 2007. Home page: http://www.fsis.usda.gov/factsheets/ham/ (Accessed 7/11/2012)

#### **Poultry Products (Food Group 05)**

#### Introduction

Data for poultry products including chicken, turkey, and other fowl are presented in the USDA National Nutrient Database for Standard Reference (SR). For most listings of fresh chicken or turkey, nutrient values are given either for specific market types such as broiler or fryer chicken, young tom turkey, young hen turkey, or as "all classes" to indicate that the values represent one or more unidentified market types for the species.

The data in SR represent the amount of each constituent in 100 grams of edible portion. Edible portion for poultry may be represented as "meat and skin" or as "meat only". In both cases, bone, cartilage, and separable fat are removed from the meat and reported as refuse. Weights are determined for the whole bird as purchased and as parts (breast, thigh, wing, drumstick, back), skin, and refuse (bone and cartilage). Refuse is reported as percentages in the SR Full Report format.

Nutrient analyses are conducted for meat and for skin in both raw and cooked forms. Nutrient values for meat only and skin only are weighted for their respective contributions to each intact bird part (as purchased), or part of the whole bird, and then reported as "meat and skin." Cooked poultry has been cooked with the skin intact, unless otherwise indicated.

The analytical nutrient data include the mean nutrient value, the standard error given to three decimal places, and the number of observations on which the values are based. For many food items, mean values are given without an accompanying standard error and number of samples. These values are either calculated by pooling data by or by weighting means, by applying cooking yields and/or nutrient retention factors, or by imputation from a different, closely related food. For poultry, nutrient estimates are based on the nutrient value for lipid (e.g., fatty acids), total solids (e.g., cholesterol), moisture-free, fat-free solids (e.g., minerals), or protein (e.g., water-soluble vitamins) fraction of a similar food.

#### **Nutrients**

Nutrient information for SR can be found under "File Content" in the documentation. In addition, some nutrient information specific to poultry products are included here. Nutrient data are obtained for moisture, protein, ash and total fat. The values for protein are calculated from the content of total nitrogen (N) in the food using the conversion factor recommended by Jones (Jones, 1941). The specific factor for protein applied to poultry items is 6.25. The carbohydrate content of uncured products consisting entirely of poultry (except some organ meats) is negligible. For such foods, the carbohydrate content is assumed to be zero.

For heart, liver, giblets, and cured products (foods expected to contain carbohydrate),

the carbohydrate value is calculated as the difference between 100 and the sum of the percentages of water, protein, total lipid, and ash. If the total of these constituents for any item is more than 100 due to analytical variation, the carbohydrate content is assigned a zero value.

Food energy is expressed in terms of both kilocalories and kilojoules. (One kilocalorie equals 4.184 kilojoules.) The data are for physiologic energy values remaining after losses due to

digestion and metabolism have been deducted. Further discussions on energy and caloric factors

used in SR can be found in the "Food Description File" of the general documentation.

The specific calorie factors used for calculating energy values in poultry products are:

	rcai/g
Protein	4.27
Fat	9.02
Carbohydrate	3.87

The carbohydrate factor of 3.87 is used for some organ meats and some cured products. Because the level of carbohydrate in poultry meat and skin is insignificant, no carbohydrate factor is needed for most poultry products. The factors are based on the Atwater system for determining energy values. Details of the derivation of these factors are outlined in Agriculture Handbook No. 74 (Merrill, 1973).

## **Description of Projects**

The studies documented in these poultry notes represent data collected since 2008.

#### Rotisserie chicken

In collaboration with Texas Tech University, the USDA conducted studies to determine the nutrient composition of commercially prepared rotisserie BBQ chicken (released in SR 21 and SR 25). The studies were conducted because rotisserie chicken has become a popular ready-to-serve poultry item in the retail market.

<u>Sampling</u>: Rotisserie chicken samples were procured nationwide from 12 retail locations using the National Food and Nutrient Analysis Program (NFNAP) nationwide sampling plan developed for the USDA (Perry et al., 2003).

**Sample preparation:** Samples were purchased whole and dissected into separate parts: breast, thigh, wing, drumstick, and back. Each bird was weighed whole. After dissection, parts were weighed separately, with and without skin. Refuse including drippings, bone, subcutaneous fat, and cartilage was also weighed. Samples were homogenized and composited.

**Sample analysis:** Samples were chemically analyzed by qualified laboratories for nutrient content for the breast, drumstick, thigh, wing, back, and skin. Since rotisserie

chicken as purchased is already cooked, samples were analyzed only as cooked, not raw. To validate all analytical procedures, quality control was monitored by use of duplicate sampling, in-house control materials, and certified reference materials.

The rotisserie chicken purchased at each individual location was used to create individual composites for analyses of proximate nutrients (moisture, total fat, ash, and protein), minerals, niacin, vitamin B6, thiamin, riboflavin, pantothenic acid, vitamin B12, cholesterol, and fatty acids. Composite samples from individual locations were grouped for analyses of selenium, folate, choline, vitamin E, amino acids, carotenoids, retinol, vitamin D, vitamin C, and vitamin K.

### Whole turkey

USDA conducted a study in collaboration with Texas Tech University to determine the nutrient composition of raw and roasted whole turkey for inclusion in the USDA National Nutrient Database for Standard Reference. The study was initiated due to changes occurring in the industry. For example, during sampling and market checks done by the Nutrient Data Laboratory, most whole turkeys found in retail outlets were labeled as enhanced with sodium-containing solutions, while non-enhanced whole turkeys were relatively uncommon. Therefore, due to the relatively common and recent availability of enhanced whole turkey, data for this product were needed in SR.

Samples of whole enhanced turkeys were procured from 11 retail locations, using the nationwide sampling plan developed for the USDA's National Food and Nutrient Analysis Program (NFNAP). Due to unavailability of non-enhanced turkeys in the NFNAP retail locations, samples of non-enhanced turkeys were obtained through 4 different local retail sources. Two turkeys per location were purchased—one to be dissected and analyzed raw and the other to be dissected and analyzed after roasting. All of the turkeys were shipped to Texas Tech University for processing. Weights of meat, skin, and other components were obtained in order to determine cooking yields. Samples of meat, skin and offal (gizzard, heart, and liver) were homogenized, composited, and chemically analyzed for nutrient content.

**Cooking Procedure:** Roasting -Thawed turkeys were unwrapped and the weight of the drippings, neck, organ meats, and packaging were measured. Oven was preheated to 325°F/163°C. The turkeys were placed on a wire rack in a shallow roasting pan, with ½ cup water added in the bottom of the pan. Turkeys were roasted until they achieved an internal temperature of 165°F/74°C, when they were removed from the oven. After 20 minutes at room temperature, the cooked weight of each whole turkey was obtained.

<u>Sample preparation:</u> Separation of meat, skin, separable fat, cartilage, and bone: Each turkey was cut into parts: breast, wings, drumsticks, thighs, and back including the tail. Each part was weighed and refrigerated for up to 24 hours. Dissection of each turkey part was performed by carefully "scraping" the co-mingled parts with a knife blade, so that the separable fat, bone, and cartilage were separated from the meat as closely as possible, then weighed, to measure the relative amount of each component.

Component weights (i.e., weights of meat, skin, separable fat, bone, and cartilage) were reported in SR. Weights of bone and cartilage were combined and reported as "refuse". For food items listed as "meat only", the skin associated with those cuts is included in the "refuse". For food items listed "meat and skin", the skin is considered edible and contributes to the nutrient profile and is not included in the refuse.

<u>Sample composites and nutrient analyses:</u> For each analytical sample, the turkeys purchased at each individual location were used to create an individual composite. For the enhanced turkey data, a composite of light meat and a composite of dark meat from each location were paired (n=6), then homogenized and analyzed in both raw and cooked forms. For the non-enhanced turkey data, each location was analyzed separately (n=4) for both the raw and cooked forms. Skin samples from the entire bird were pooled and analyzed both in raw and cooked forms. At this level, these nutrients were analyzed: proximate nutrients (moisture, total fat, ash, and protein), minerals, cholesterol, fatty acids, thiamin, niacin, riboflavin, vitamin B6, and vitamin B12.

Samples from two or more locations were combined to form regional or national composites for enhanced and non-enhanced turkey for these nutrients: amino acids, choline, vitamin K, folate, and retinol. Values for vitamin D, including 25-hydroxy vitamin D, were also obtained from regional composites. Nutrient analyses were performed by TTU and a commercial laboratory, whose analytical procedures were evaluated and validated through the NFNAP process. Regional composites of enhanced turkey were also analyzed for sugar and starch.

In SR, turkey listings are described as light meat, dark meat, or by specific parts. Listings in previous versions of SR also included turkey classes such as fryer, hen, or tom in some of the descriptions. However, terms used to identify specific turkey classes are no longer included in SR 25, since turkeys sold in the current market are not consistently identified with this information.

As a result of this study, data have been generated to create new SR items for these enhanced whole turkey items: light meat (with and without skin), dark meat (with and without skin), gizzard, heart, liver, neck, and skin. Data have been generated to update these non- enhanced whole turkey items: light meat (with and without skin), dark meat (with and without skin), gizzard, heart, liver, neck, and skin.

#### References for Notes on Foods – Poultry Products

Jones, D.B. 1941. Factors for Converting Percentages of Nitrogen in Foods and Feeds into Percentages of Protein. Rev. U.S. Dept. of Agriculture, Circ. 183, 22 pp.

Merrill, A.L. and B.K. Watt. 1973. Energy Value of Foods—Basis and Derivation. Rev. U.S. Dept. of Agriculture, Agriculture Handbook. No. 74, 105 pp.

Perry, C.R., Pehrsson, P.R., and Holden, J.M. 2003. A Revised Sampling Plan for Obtaining Food Products for Nutrient Analysis for the USDA National Nutrient Database 2003. Proceedings of the American Statistical Association, Section on Survey Research Methods [CD-ROM], Alexandria, VA: American Statistical Association, San Francisco.

## **Vegetable and Vegetable Products (Food Group 11)**

The sources of nutrient data for this food group include the scientific literature, analytical studies conducted by NDL and other government agencies, and the food industry. Since the inception of NFNAP (p. 49) in 1997, a few canned and frozen vegetables have also been sampled and analyzed. Data for raw and cooked vegetables, with the exception of the studies described below, for the most part, come from the scientific literature. In most cases, data for other canned and frozen vegetables were supplied by the food industry.

In 2000 and 2001 the Produce for Better Health Foundation collaborated with the Nutrient Data Laboratory (NDL) to sample and analyze 16 vegetables utilizing NFNAP protocols (p. 49). For most vegetables, samples were collected from retail outlets in 12 major metropolitan areas, once during the peak market season for the particular vegetable and once during the low market season. Four composites comprised of sample units from three locations each were prepared, and sent to the lab for analysis. A number of vegetables (tomatoes, potatoes, broccoli, and broccoli raab) were also analyzed both raw and prepared. In most cases, vegetables in the retail market are not identified by cultivar. However, for lettuce, red leaf, green leaf, iceberg, romaine, and butterhead types were sampled; for potatoes, russet, red and white types were sampled. Since 2002, additional data were obtained via NFNAP for other vegetables on FDA's list of the 20 most commonly consumed fruits, nuts and vegetables (FDA/DHHS, 2011).

In 2004 the Mushroom Council collaborated with NDL to update the data on several types of mushrooms (white, maitake, oyster, enoki, shiitake, crimini and portabella). These samples were also collected from retail outlets in 12 major metropolitan areas. They were composited into four composites of samples from three locations each, and sent to the labs for analysis. Samples of white and portabella mushrooms were also cooked before analysis. In 2009 additional analyses were conducted for vitamin D in the above listed mushrooms. Samples of morel and chanterelle mushrooms were also collected for the first time.

Data are presented for raw, canned, dehydrated, and frozen vegetables and vegetable products. When appropriate, data are presented for both the unprepared and the prepared forms of the food.

Nutrient data for different forms of a vegetable were not necessarily derived from the same sample. That is, a single sample of snap beans was not analyzed in each of the three forms: raw, canned, and frozen. The data were obtained from many sources and may represent different growing years, growing areas, cultivars, processing techniques, lengths and conditions of storage, laboratories, and possibly different methods of analysis. Therefore, in a comparison of different forms of a vegetable, nutritional differences should not be ascribed solely to the effect of processing or preparation methods.

Several factors such as natural variation, differences in postharvest handling and storage, and variations in the processing or preparation method may cause a processed or prepared form of a vegetable to have a higher nutrient content than the unprocessed or unprepared form. The differences in nutrient content between the combined solids and liquid portion and the drained solids portion of canned vegetables may not accurately reflect the amount in the drained liquid portion for the reasons stated above.

Ascorbic acid in fresh vegetables such as cabbage, lettuce, and squash is extremely unstable and is easily oxidized, particularly after chopping, cutting, or shredding. Because the values in the database did not reflect these losses, ascorbic acid content may have been overestimated. Ascorbic acid is found in foods in the reduced form, and can be converted reversibly to dehydroascorbic acid. Both the reduced and the dehydroascorbic acid forms have vitamin activity. Dehydroascorbic acid can be oxidized to diketogulonic acid, which has no vitamin activity.

Potatoes are frequently stored for many months, which may cause a decrease in ascorbic acid content. The values in the database reflect an average of several typical storage times used commercially.

The vitamin A content of vegetables such as carrots and sweet potatoes increases as they mature. Canned and frozen forms of carrots or sweet potatoes are often more mature than fresh forms, utilize different cultivars, and thus may have higher vitamin A values. Sweet potatoes have been bred in recent years to develop cultivars with deep orange—colored flesh, and have, at the same time, increased in their vitamin A content. Data collected for the database reflect the considerable variability between different samples due to natural variation and differences in methodology.

The carbohydrate content of starchy vegetables, such as sweet corn, varies with maturity, cultivar, and length of storage. As the kernels mature, moisture decreases and the carbohydrate content increases, causing a corresponding increase in calories.

A large portion of the total carbohydrates in globe or French artichokes and Jerusalemartichokes may be inulin, a naturally occurring fructose polysaccharide, which is often measured by some analytical methods as dietary fiber. During storage, inulin is converted to available sugars (Watt and Merrill, 1963). Consequently, as the carbohydrates change with storage, the energy value also varies. The values in the tables are for the stored forms of artichokes and Jerusalem-artichokes.

Federal regulations (U.S. Food and Drug Administration—Department of Health and Human Services, 2004) allow for the addition to canned vegetables of certain calcium salts as firming agents. The standards specify how much of these salts can be added. The addition of these salts is reflected in the values in the database.

Oxalic Acid.—Oxalic acid can combine with calcium and magnesium to form highly insoluble compounds which can make these minerals unavailable to the body. However, most foods do not contain enough oxalic acid to combine with a significant amount of

calcium or magnesium from the same food or from another source. Those foods that contain high amounts of oxalic acid usually contain sufficient calcium or magnesium to bind with all the oxalic acid in that food. Therefore, oxalic acid in these foods would not interfere with the calcium and magnesium availability of other foods in the diet. A table listing the oxalic acid content of some vegetables is available on NDL's Web site (USDA-ARS, 1984).

Sodium.—Sodium values for cooked vegetables in the database are presented separately for unsalted vegetables and for cooked vegetables with salt added. Since the sodium content of tap water varies according to location (0-39 mg/100 g), the sodium value of the cooked vegetable may be underestimated if the water supply naturally contains high amounts of sodium. It is difficult to estimate the amount of salt absorbed by vegetables during cooking. Sodium content of the cooked vegetable will depend on the amount of salt used in the cooking water and can be as high as vegetables with salt added during canning. Sodium values for cooked vegetables with added salt were calculated by adding the content from approximately 1/8 of a teaspoon of salt per 100 grams of vegetables or 236 mg of sodium to the sodium naturally occurring in the cooked vegetable with no salt added. Sodium values for canned vegetables are presented, both for product with salt added and salt not added.

Certain processing methods can cause increases in the sodium content of the vegetable or vegetable product. Some processed vegetables, such as canned, frozen, or dehydrated carrots, potatoes, sweet potatoes, and tomatoes are often lye peeled. The vegetable is dipped into a hot sodium hydroxide solution, followed by a water rinse. While the rinse will remove some of the sodium absorbed during the lye peeling operation, some will remain in the finished product.

Sodium compounds such as monosodium glutamate, disodium guanylate, and disodium inosinate may be added to some processed vegetable products as flavor enhancers. Sodium compounds may be added to potatoes to prevent browning during commercial processing. Lima beans and peas are brine sorted before blanching and freezing, which can result in the vegetables picking up sodium from the brine.

Nomenclature.— To aid in identifying individual vegetables listed in the tables, the scientific name of the vegetables is included in the food description file, usually on the raw form of the vegetable. The USDA Germplasm Resources Information Network (GRIN), (USDA, 2011) was used as the basic reference for the scientific and preferred common names. Identifying vegetables by their common names is often confusing because these names are not always applied to the same food in different geographic locations. Some names of vegetables in common use or unique to one region of the country have been indicated in the common name field of the food description file. In some cases, the usual nomenclature is particularly confusing. These are further explained in the following paragraphs.

Cassava (*Manihot esculenta*) is one of the major sources of carbohydrates for human food in many parts of the world and is also known as manioc or yuca. It is extensively

cultivated in tropical areas for its starchy, tuberous root. Cassava is sometimes called yucca, though this is a different plant. The yucca (*Yucca* spp.) is more frequently grown as an ornamental plant, though the fruits, flowers and flowering stem can be eaten. However, the root contains high levels of saponins, which are toxic.

Garden cress (*Lepidium sativum*) is a cultivated plant brought originally to this country from Europe. This plant often grows wild, and is called field cress in some areas.

Endive and chicory are often confused with each other. Cultivars of endive grown in the United States have the species name *Cichorium endivia*, and are quite different in structural appearance from Witloof chicory (*Cichonium intybus*), which is also known as French or Belgian endive. Endive (*Cichonium endivia*) is always marketed in the headed form, the larger heads weighing more than a pound. The heads are low—spreading and loose—leaved. The leaves vary from deeply cut and deeply curled in some cultivars to the broad, slightly cut and curled leaves of escarole. The outer leaves are green, and the center leaves or heart and the midnibs are pale green to creamy white. Chicory is sometimes marketed as blanched heads, greens, or roots. Witloof chicory is commonly forced and can be identified by its very small, elongated, compact, well—blanched head, which resembles a small shoot and weighs about 2 ounces. Witloof chicory is also grown for greens.

The term yam is frequently used when referring to sweet potatoes in common usage and marketing. Sweet potatoes (*Ipomea batatas*) are elongated tubers with a white or orange—yellow colored flesh. The orange-yellow cultivars are commonly marketed in the United States. For the market, sweet potatoes are sometimes identified as yams. Raw, canned, and frozen sweet potatoes are sometimes identified on the label as yams. The true yam (*Dioscorea* spp.) is a tropical tuber. Yam cultivars may have white or pale—yellow flesh. In most areas of the United States, true yams are generally available only in certain specialty stores.

<u>Raw vegetables.</u>—Although nutrient data were available for several cultivars of some vegetables, the data base for any one cultivar was too small to justify giving separate entries by cultivar. Production data by cultivar were unavailable for most vegetables.

The values for raw potatoes listed in the tables were calculated from data for several cultivars and weighted as follows: Russet, 70 percent; White, 18 percent; and red, 12 percent.

<u>Prepared vegetables</u>.—Nutrient data on cooked vegetables were often unavailable or incomplete. In these cases, 'the appropriate nutrient values for the cooked form were calculated from the unprepared form of the same food. For example, nutrient data for cooked asparagus were calculated from data for raw asparagus. Appropriate true nutrient retention factors (NDL, 2007) were used to calculate the nutrient content of the cooked foods, after adjusting for changes in the moisture content of the uncooked foods. The same procedures were followed for the cooked, frozen vegetables.

Retention values are generally based on cooking methods that minimize the loss of nutrients, particularly the water soluble vitamins. Nutrient values of cooked vegetables obtained by these procedures tend to be higher than those values for the same vegetables cooked by less than optimum methods. Some conditions that affect the retention of nutrients in vegetables that are cooked include: Cooking method, size and shape of the vegetable or amount of surface area, maturity, condition of the vegetable, amount of cooking water, and length of cooking.

Nutrient values for vegetables prepared by microwave cooking would be similar to those obtained by conventional cooking methods, except where cooking times are lengthened because of the shape of the vegetable or the total amount of the vegetable that is cooked at one time. For example, one potato in a microwave oven will bake in approximately 5 minutes, while four potatoes will take four times longer. The ingredients and proportions used to calculate nutrient values for vegetable mixtures such as coleslaw, corn pudding, potato salad, spinach soufflé, and candied sweet potatoes are given in a footnote for each item. Values for each nutrient provided by the ingredients used in the recipe were totaled. Nutrient values were adjusted to account for any changes due to evaporation and heat destruction.

## References foe Notes on Foods – Vegetables and Vegetable Products

- U.S. Food and Drug Administration, Department of Health and Human Services. 2012. Food Labeling. Code of Federal Regulations, Title 21, Pt. 101. U.S. Government Printing Office website: http://www.gpo.gov/fdsys/pkg/CFR-2012-title21-vol2/pdf/CFR-2012-title21-vol2-part101.pdf (Accessed 7/11/2012).
- U.S. Food and Drug Administration, Department of Health and Human. 2009. Nutrition Information for Raw Fruits, Vegetables, and Fish. FDA Website: http://www.fda.gov/Food/LabelingNutrition/FoodLabelingGuidanceRegulatoryInformation/InformationforRestaurantsRetailEstablishments/ucm063367.htm (Accessed 7/11/2012)
- U.S. Department of Agriculture, Agricultural Research Service, National Genetic Resources Program. 2011. *Germplasm Resources Information Network (GRIN)* [Online Database]. National Germplasm Resources Laboratory, Beltsville, Maryland. http://www.ars-grin.gov/cgi-bin/npgs/html/tax\_search.pl (Accessed 7/11/2012)
- U.S. Department of Agriculture. 2007. USDA Table of Nutrient Retention Factors, Release 6. Nutrient Data Laboratory Web Site: http://www.ars.usda.gov/Services/docs.htm?docid=9448. (Accessed 7/11/2012).
- U.S. Department of Agriculture. 1984. Oxalic Acid Content of Selected Vegetables. Nutrient Data Laboratory Web Site: http://www.ars.usda.gov/Services/docs.htm?docid=9444 (Accessed 7/11/2012)

Watt, B.K., and A.L. Merrill. 1963. Composition of foods: Raw, processed, prepared. U.S. Department of Agriculture, Agriculture Handbook 8.

# **Appendix A. Abbreviations Used in Short Descriptions**

All purpose ALLPURP

Aluminum AL And & Apple APPL **Apples APPLS** Applesauce **APPLSAUC** Approximate APPROX Approximately **APPROX** Arm and blade ARM&BLD

Artificial ART
Ascorbic acid VIT C
Aspartame ASPRT

Aspartame-sweetened ASPRT-SWTND

Baby food **BABYFD** Baked BKD Barbequed **BBQ** Based **BSD** Beans **BNS** Beef BF Beverage BEV **Boiled BLD** Boneless **BNLESS Bottled BTLD Bottom** BTTM Braised **BRSD** Breakfast **BRKFST Broiled** BRLD Buttermilk **BTTRMLK** 

Calcium CA CAL Calorie, calories **CND** Canned Carbonated **CARB** Center **CNTR** Cereal CRL Cheese CHS Chicken CHICK Chocolate CHOC Choice CHOIC Cholesterol **CHOL** 

Cholesterol-free CHOL-FREE Chopped CHOPD Cinnamon CINN

Coated COATD Coconut COCNT Commercial COMM Commercially **COMMLY** Commodity CMDTY Composite **COMP** Concentrate **CONC** Concentrated CONCD Condensed COND Condiment, condiments CONDMNT

Cooked CKD
Cottonseed CTTNSD
Cream CRM
Creamed CRMD
Dark DK

Decorticated **DECORT** Dehydrated **DEHYD** Dessert, desserts DSSRT Diluted DIL **Domestic** DOM **DRND** Drained **DRSNG** Dressing Drink DRK

Drumstick DRUMSTK

English ENG
Enriched ENR
Equal EQ
Evaporated EVAP
Except XCPT
Extra EX

Flank steak FLANKSTK

Flavored FLAV
Flour FLR
Food FD
Fortified FORT

French fried FRENCH FR French fries FRENCH FR

Fresh FRSH
Frosted FRSTD
Frosting FRSTNG
Frozen FRZ
Grades GRDS
Gram GM
Green GRN

Greens GRNS Heated HTD

**HVY** Heavy Hi-meat HI-MT High HI Hour HR Hydrogenated **HYDR Imitation IMITN Immature IMMAT** Imported IMP Include, includes **INCL** Including **INCL** 

Infant formula INF FORMULA

Ingredient ING Instant **INST** Juice JUC Junior JR Kernels **KRNLS LRG** Large Lean LN Lean only LN Leavened **LVND** LT Light Liquid LIQ Low LO LOFAT Low fat

LOW ICC

Marshmallow MARSHMLLW

Mashed **MSHD** Mayonnaise **MAYO** Medium MED Mesquite **MESQ** MIN Minutes Mixed MXD Moisture **MOIST** NAT Natural New Zealand NΖ

Noncarbonated **NONCARB** Nonfat dry milk NFDM Nonfat dry milk solids **NFDMS** Nonfat milk solids **NFMS** Not Further Specified **NFS Nutrients NUTR** Nutrition **NUTR** ΟZ Ounce Pack PK PAR FR Par fried Parboiled **PARBLD** 

**PART** 

Partial

Partially PART
Partially fried PAR FR
Pasteurized PAST
Peanut PNUT
Peanuts PNUTS
Phosphate PO4
Phosphorus P

Pineapple PNAPPL
Plain PLN
Porterhouse PRTRHS

Potassium K **PDR** Powder **PDR** Powdered Precooked **PRECKD** Preheated **PREHTD** Prepared **PREP** Processed **PROC** Product code PROD CD **PROP** Propionate **PROT** Protein Pudding, puddings **PUDD** Ready-to-bake **RTB** Ready-to-cook RTC Ready-to-drink **RTD RTE** Ready-to-eat Ready-to-feed RTF **RTH** Ready-to-heat **RTS** 

Ready-to-heat RTH
Ready-to-serve RTS
Ready-to-use RTU
Reconstituted RECON
Reduced RED
Reduced-calorie RED-CAL
Refrigerated REFR
Regular REG
Reheated REHTD

Replacement REPLCMNT Restaurant-prepared REST-PREP Retail RTL

Retail RTL
Roast RST
Roasted RSTD
Round RND
Sandwich SNDWCH
Sauce SAU

Scalloped SCALLPD Scrambled SCRMBLD

Seed SD

Select SEL

Separable<sup>1</sup>

SHK&SIRL Shank and sirloin Short SHRT Shoulder SHLDR Simmered SIMMRD Skin SKN Small SML Sodium NA Solids SOL SOLN Solution SOYBN Soybean Special SPL **Species** SP Spread **SPRD** Standard STD Steamed **STMD** Stewed **STWD** Stick STK **Sticks STKS** STR Strained **SUB** Substitute Summer SMMR **SUPP** Supplement Sweet **SWT** Sweetened **SWTND** Sweetener **SWTNR** Teaspoon **TSP** 

Trimmed<sup>1</sup> Trimmed to<sup>1</sup>

Thousand

Toasted

Toddler

Uncooked **UNCKD** Uncreamed **UNCRMD** Undiluted UNDIL Unenriched **UNENR** Unheated **UNHTD** Unprepared **UNPREP** Unspecified **UNSPEC** Unsweetened UNSWTND

1000

**TSTD** 

**TODD** 

Variety, varieties VAR Vegetable, vegetables **VEG** Vitamin A VIT A Vitamin C VIT C Water H20

Whitener	WHTNR
Whole	WHL
Winter	WNTR
With	W/
Without	WO/
Yellow	YEL

<sup>&</sup>lt;sup>1</sup> Removed in short description

## **Appendix B. Other Abbreviations**

ap as purchased

ARS Agricultural Research Service
DFE Dietary Folate Equivalent

dia diameter

DRI Dietary Reference Intakes

fl oz fluid ounce

FNDDS USDA Food and Nutrient Database for Dietary Studies

g gram

INFOODS International Network of Food Data Systems

IU International Unit

kcal kilocalorie
kJ kilojoule
lb pound
mg milligram
μg, mcg microgram
ml milliliter

NDB Nutrient Databank

NDBS Nutrient Databank System NDL Nutrient Data Laboratory

NFNAP National Food and Nutrient Analysis Program

NLEA Nutrition Labeling and Education Act

oz ounce

RAE Retinol Activity Equivalent

RE Retinol Equivalents

RDA Recommended Dietary Allowances, a Dietary Reference Intake
SR USDA National Nutrient Database for Standard Reference
UL Tolerable Upper Intake Level, a Dietary Reference Intake