



# Centers for Medicare & Medicaid Services (CMS) 7500 Security Blvd Baltimore, MD 21244-1850

# HIPAA Eligibility Transaction System (HETS) Health Care Eligibility Benefit Inquiry and Response (270/271) 5010 Companion Guide

Final

Version: 5-0 June 2012

#### **Disclosure Statement**

The Centers for Medicare & Medicaid Services (CMS) is committed to maintaining the integrity and security of health care data in accordance with applicable laws and regulations. Disclosure of Medicare Beneficiary eligibility data is restricted under the provisions of the Privacy Act of 1974 and the Health Insurance Portability and Accountability Act of 1996 (HIPAA). The Provider Medicare Beneficiary eligibility transaction is to be used for conducting Medicare business only.

#### **Preface**

This Companion Guide to the v5010 ASC X12N Implementation Guides (IG)(a.k.a. TR3), adopted under HIPAA, clarifies and specifies the data content when exchanging Medicare Beneficiary eligibility data electronically with CMS utilizing the HIPAA Eligibility Transaction System (HETS) 270/271 application. Transmissions based on this Companion Guide, used in tandem with the ASC X12 270/271 and the ASC X12 999 TR3s, are compliant with both X12 syntax and the TR3. This Companion Guide is intended to convey information that is within the framework of the ASC X12 Implementation Guides adopted for use under HIPAA.



This page is intentionally left blank.

# **Table of Contents**

D	isclosu	re Statement	i
	reface.		
Ta	able of	Contents	i۷
Li	ist of T	ables	vi
Li	ist of F	igures	vi
1	Intro	oduction	. 1
	1.2 1.3	Scope	1 2 3
	1.4.4	Changes to accommodate 5010A1	
2		ing Started	
	2.2	Working with the CMS Help Desk Trading Partner Registration Certification and Testing Overview	4
3	Test	ing	. 4
4	Con	nectivity/Communications	. 5
	4.2 4.2.1 4.2.2 4.3	Process Flows	6 6 6
5	MCA	ARE Contact Information	. 8
6	Con	trol Segments/Envelopes	. 9
	6.2	Interchange Control Structure (ISA/IEA)	10
7	Paye	er Specific Business Rules and Limitations	10
	7.2 7.3 7.4 7.5 7.6 7.7 7.8 7.9	General Structural Notes	11 12 13 13 15 17 18 18
		Therapy Capitation Business Rules	

	7.12	Pulmonary Rehabilitation Services Business Rules	21
	7.13	Cardiac Rehabilitation and Intensive Cardiac Rehabilitation Services Business Rules	
	7.14	End Stage Renal Disease (ESRD) Periods Business Rules	
	7.15	Hospice Care Periods Business Rules	
	7.16	Blood Deductible Business Rules	24
	7.17	Part D Plan Enrollment Business Rules	
	7.18	MA Plan Enrollment Business Rules	
	7.19	Medicare Secondary Payer (MSP) Enrollment Business Rules	26
8	Acl	knowledgements and Error Codes	28
	8.1	TA1	28
	8.2	999	
	8.3	271	28
	8.4	Proprietary Error Message	30
9	Tra	nding Partner Agreements	31
1(	) T	Transaction Specific Information	31
	10.1	270 Eligibility Request Transaction	32
	10.1		
	10.1		
	10.1		
	10.2	271 Eligibility Response Transaction	34
A	ppend	dix A – Sample 270 Eligibility Request Transaction	61
A	ppend	dix B – Sample 271 Eligibility Response Transaction	62
Α	ppend	dix C – Acronyms	65
		dix D – Revision History	
	~~~		

# **List of Tables**

Table 1 – Standard Format of the TCP/IP Communication Transport Protocol Wrapper	
Table 2 – 270 ISA Segment Rules	
Table 3 – 270 GS Segment Rules	
Table 4 – Preferred 270 Request Transaction Delimiters	
Table 5 – HETS 270/271 Search Options	
Table 6 – Request Date Calendar	
Table 7 – AAA Error Codes	
Table 8 – Proprietary Error Messages	
Table 9 – Proprietary Error Message Codes	
Table 10 – Header and Information Source	
Table 11 – Information Receiver	
Table 12 – Subscriber	
Table 13 – Header and Information Source	
Table 14 – Information Receiver	
Table 15 – Subscriber Demographic Data	
Table 16 – Benefit Coverage Data for Mandated STCs	
Table 17 – Medicare Part A and Part B Eligibility	
Table 18 – Part A Hospital and SNF Data	
Table 19 – Home Health Data	
Table 20 – Part B Deductible Data	
Table 21 – Preventive Data	
Table 22 – Smoking/Tobacco Cessation Data	
Table 23 – Therapy Capitation Data	
Table 24 – Pulmonary Rehabilitation Services	
Table 25 – Cardiac Rehabilitation Services	
Table 26 – Intensive Cardiac Rehabilitation Services	
Table 27 – ESRD Data	
Table 28 – Hospice Data	
Table 29 – Blood Deductible Data	
Table 30 – Part D Enrollment Data	
Table 31 – MA Enrollment Data	
Table 32 – MSP Enrollment Data	
Table 33 - Acronyms	
Table 34 – Document Revision History	66
List of Figures	
Figure 1 – Process for Submitting 270 Transactions	
rigare 2 = 2. ample or 1 or /ii = continuation rianoport riotocol triappor miniminiminiminimi	O

#### 1 Introduction

# 1.1 Scope

This document defines the Medicare HIPAA compliant eligibility request sent from Medicare authorized Submitters and the corresponding response from the Medicare Health Insurance Portability and Accountability Act (HIPAA) Eligibility Transaction System (HETS) 270/271 application. To implement the HIPAA administrative simplification provisions, the 270/271 transaction set has been named under 45 CFR 162 as the Electronic Data Interchange (EDI) standard for Health Care Eligibility Benefit Inquiry/Response.

The HETS 270/271 application supports the ASC X12 270/271 version 005010X279A1 and the ASC X12 999 version 005010X231A1 TR3s that can be found at the following web site: <a href="http://www.wpc-edi.com">http://www.wpc-edi.com</a>. The 270 request and the 271 response are "paired" transactions. The 270 is an inbound eligibility request; whereas, the 271 is an outbound eligibility response.

This companion guide has two purposes. The first purpose is to educate the user on how to access the HETS 270/271 application. The second purpose is to educate the user on how to send eligibility requests and interpret responses, using the 270/271 formats, as they relate to the applicable Medicare required business rules and information.

# 1.2 Application Overview

The HETS 270/271 application provides access to Medicare Beneficiary eligibility data in a real-time environment. Providers, Clearinghouses, and/or Third Party Vendors, herein referred to as "Trading Partners", may initiate a real-time 270 eligibility request to query coverage information from Medicare on patients for whom services are scheduled or have already been delivered. In real-time mode, the Trading Partner transmits a 270 request and remains connected while the receiver processes the transaction and returns a 271 response.

The HETS 270/271 application is located at a secure CMS data center, which is available via the CMS Extranet. This extranet is a secure closed private network currently used to transmit data between CMS and their authorized contractors. Trading Partners must not send User IDs and passwords within the 270 eligibility transaction.

For a real-time 270 request, the HETS 270/271 application translates the incoming 270 request, performs validations, requests Medicare Beneficiary eligibility data from the CMS eligibility database, and creates an Eligibility Response (271), a Functional Acknowledgement (999), an Interchange Acknowledgement (TA1), or a proprietary error response.

The information included in the 271 response is not intended to provide a complete representation of all benefits, but rather to address the status of eligibility (active or inactive) and patient financial responsibility for Medicare Part A and Part B.

The data included in a 271 response file is to be considered true and accurate only at the particular time of the transaction. Questions regarding eligibility/benefit data for Medicare Part A and Part B should be directed to the appropriate regional Medicare Administrative Contractor (MAC). Eligibility/benefit questions about Medicare Advantage (MA), Part D and Medicare Secondary Payer (MSP) should be directed to the appropriate plan(s) identified in the 271 response.

#### 1.3 References

 Implementation Guides for all X12 transaction sets can be purchased from the publisher, Washington Publishing Company, at their website: <a href="http://www.wpc-edi.com">http://www.wpc-edi.com</a>

**Note:** The ASC X12 270/271 version 005010X279A1 and the ASC X12 999 version 005010X231A1 TR3s can be purchased from the publisher.

The HETS Trading Partner Agreement Form to request access to the HETS 270/271 application is available for download from the CMS HETSHelp website. Use the following link to display the "How to Get Connected – HETS 270/271" page: <a href="http://www.cms.gov/Research-Statistics-Data-and-Systems/CMS-Information-Technology/HETSHelp/HowtoGetConnectedHETS270271.html">http://www.cms.gov/Research-Statistics-Data-and-Systems/CMS-Information-Technology/HETSHelp/HowtoGetConnectedHETS270271.html</a>.

#### 1.4 Additional Information

CMS is committed to maintaining the integrity and security of health care data in accordance with applicable laws and regulations. Disclosure of Medicare Beneficiary eligibility data is restricted under the provisions of the Privacy Act of 1974 and HIPAA.

CMS implemented the HETS 270/271 application following a real-time request/response model (single response per request). The data available in this implementation allows a Provider to verify an individual's Medicare eligibility and benefits. Medicare eligibility data is only to be used for the business of Medicare; such as preparing an accurate Medicare claim or determining eligibility for specific services. Providers' authorized staff are expected to use and disclose protected health information according to the CMS regulations.

CMS monitors Medicare Beneficiary eligibility inquiries. Trading Partners identified as having aberrant behavior (e.g., high inquiry error rate or high ratio of eligibility inquires to claims submitted) may be contacted to verify and/or address improper use of the system or, when appropriate, be referred for investigation.

# 1.4.1 Authorized Purposes for Requesting Medicare Beneficiary Eligibility Information

In conjunction with the intent to provide health care services to a Medicare Beneficiary, authorized purposes include to:

- Verify eligibility, after screening the patient to determine Medicare eligibility, for Part A and/or Part B coverage
- Determine Medicare Beneficiary payment responsibility with regard to deductible/copayment
- Determine eligibility for other services, such as preventive
- Determine if Medicare is the primary or secondary payer
- Determine if the Medicare Beneficiary is in the original Medicare plan, MA plan or Part D plan
- Determine proper billing

# 1.4.2 Unauthorized Purposes for Requesting Medicare Beneficiary Eligibility Information

The following are examples of unauthorized purposes for requesting Medicare Beneficiary eligibility information:

- To determine eligibility for Medicare without first screening the patient to determine if they are Medicare eligible
- To acquire the Medicare Beneficiary's Health Insurance Claim Number (HICN)

# 1.4.3 Note to Medicare Providers/Suppliers:

The Medicare Beneficiary should be the first source of health insurance eligibility information. When scheduling a medical appointment for a Medicare Beneficiary, remind them to bring, on the day of their appointment, all health insurance cards showing their health insurance coverage. This will not only help you determine who to bill for services rendered, but also give you the proper spelling of the Medicare Beneficiary's first and last name and identify their HICN as reflected on the Medicare Health Insurance card. If the Medicare Beneficiary has Medicare coverage but does not have a Medicare Health Insurance card, encourage them to contact the Social Security Administration at 1-800-772-1213 to obtain a replacement Medicare Health Insurance card. Those beneficiaries receiving benefits from the Railroad Retirement Board (RRB) can call 1-800-808-0772 to request a replacement Medicare Health Insurance card from RRB.

It is assumed that the reader of this document is familiar with the ASC X12 270/271 TR3 and the transaction format and content rules contained within it. This Companion Guide is intended to be a complement to the TR3 and not the sole authoritative source of data.

# 1.4.4 Changes to accommodate 5010A1

For details of the changes to this Companion Guide to accommodate the 5010A1 version of the ASC X12 270/271 transaction, refer to Appendix D – Revision History.

# 2 Getting Started

# 2.1 Working with the CMS Help Desk

The Medicare Customer Assistance Regarding Eligibility (MCARE) Help Desk is available to assist with this process Monday – Friday, from 7:00 AM to 7:00 PM ET. MCARE is the single point of contact for all questions or concerns about the HETS 270/271 application. Potential Trading Partners must contact MCARE to initiate the registration process.

Please refer to <u>Section 5</u> of this Companion Guide for MCARE contact information.

## 2.2 Trading Partner Registration

To obtain access to the HETS 270/271 application via the CMS Extranet, a potential Trading Partner must access the appropriate form located on the CMS HETS Help website.

Instructions to complete the sign-up process can be found at the following link: <a href="http://www.cms.gov/Research-Statistics-Data-and-Systems/CMS-Information-Technology/HETSHelp/HowtoGetConnectedHETS270271.html">http://www.cms.gov/Research-Statistics-Data-and-Systems/CMS-Information-Technology/HETSHelp/HowtoGetConnectedHETS270271.html</a>

# 2.3 Certification and Testing Overview

Trading Partners are required to submit test transactions to ensure that their systems are HIPAA and X12 compliant. Each Trading Partner may submit up to 50 test transactions during the testing phase. Trading Partners must contact MCARE to coordinate testing procedures.

Please refer to <u>Section 5</u> of this Companion Guide for MCARE contact information.

# 3 Testing

CMS requires that all newly registered Trading Partners work with MCARE to complete basic transaction submission testing. Successful transaction submission and receipt of both valid and error responses is an indication to CMS that all systems involved can

properly submit and receive transactions. MCARE is available to assist with new Trading Partner testing Monday – Friday, from 9:00 AM to 5:00 PM ET.

Trading Partners must send all test transactions with Usage Indicator (ISA15) = "T" until approved to submit production transactions with a Usage Indicator (ISA15) = "P". The HETS 270/271 application will return a TA105 = "020" error for an Invalid Test Indicator Value if the incorrect value is included within this field.


Please refer to <u>Section 5</u> of this Companion Guide for MCARE contact information.

## 4 Connectivity/Communications

#### 4.1 Process Flows

To access the HETS 270/271 application via the CMS Extranet, potential Trading Partners need to obtain a Submitter ID through MCARE. Figure 1 illustrates the high level process for successfully registering as a Trading Partner and submitting 270 transactions:

Figure 1 – Process for Submitting 270 Transactions



#### **Step 1:** Trading Partner Registration

Complete and submit the HETS Trading Partner Agreement t Form. Refer to <u>Section</u> <u>2.2</u> of this Companion Guide for the Trading Partner registration process.

#### **Step 2:** Trading Partner Authentication

MCARE will verify the information on the Trading Partner Agreement Form and approve or deny any Submitter ID requests.

#### **Step 3:** Testing Phase

MCARE will have a Trading Partner send up to 50 test transactions and verify that all systems involved can properly submit and receive HIPAA and X12 compliant transactions. The Usage Indicator (ISA15) must be "T".

#### **Step 4:** Production Phase

Once testing is complete, a Trading Partner can begin to submit 270 transactions and receive 271 transactions in the Production environment. The Usage Indicator (ISA15) must be "P".

#### 4.2 Transmission Administrative Procedures

# 4.2.1 Schedule, Availability, and Downtime Notification

The HETS 270/271 application is available 24 hours a day, 7 days a week, with the exception of 12:00 AM – 5:00 AM Monday ET when system maintenance is performed. MCARE will notify the Trading Partners of any additional planned downtime. All current and archived downtime notifications are available via the CMS HETS Help website: <a href="http://www.cms.gov/Research-Statistics-Data-and-Systems/CMS-Information-Technology/HETSHelp/index.html">http://www.cms.gov/Research-Statistics-Data-and-Systems/CMS-Information-Technology/HETSHelp/index.html</a>.

Any unplanned downtime with the HETS 270/271 application will also be communicated to the Trading Partners via email and posted to the HETS Status website: <a href="http://www.hetsstatus.com">http://www.hetsstatus.com</a> as soon as MCARE is aware of the situation. A second follow-up email will also be sent alerting the Trading Partners when the HETS 270/271 application becomes available.

Please refer to Section 5 of this Companion Guide for MCARE contact information.

#### 4.2.2 Re-Transmission Procedure

Trading Partners may call MCARE for assistance in researching problems with their transactions. However, MCARE will not edit Trading Partner eligibility data and/or resubmit transactions for processing on behalf of a Trading Partner. The Trading Partner must correct the transaction and resubmit, following the same processes and procedures of the original file.

#### 4.3 Communication Protocol Specifications

Communications through the CMS Extranet to the HETS 270/271 application are via the TCP/IP transfer protocol. Trading Partners must initiate the TCP handshake to establish a TCP/IP socket connection at the CMS data center. Trading Partners should only request to open a TCP/IP socket connection as necessary to support their active eligibility requests.

The 270 transaction must be sent to the connected socket session immediately after Trading Partners have successfully negotiated the socket, and the 271 response will be received on the same socket connection. Trading Partners may choose to implement a client that can listen to the same socket session for a 271 response while 270 requests are being streamed. Trading Partners should monitor the TCP/IP socket connection while connected to ensure that the socket remains open and viable. Trading Partners should be able to determine if a socket has prematurely terminated for any reason.

Trading Partners should only submit one transaction concurrently per socket. Transactions process linearly; therefore, submitting more than one transaction per socket concurrently results in additional transactions queuing and delaying response time to the additional transactions.

CMS recommends that high volume Trading Partners send transactions asynchronously, that is, streaming multiple sequential requests via the single socket connection. If transactions are submitted asynchronously, Trading Partners should submit the next 270 request as soon as the response to the previous request is received. Asynchronous Trading Partners may open multiple sockets, if necessary, to support transaction volume during high volume periods.

Sending 270 requests asynchronously also improves socket efficiency. There are a finite number of available HETS 270/271 sockets, so Trading Partners should limit the number of simultaneous connections the HETS 270/271 application.

When the last requested 271 response has been received, Trading Partners should close the socket connection immediately using a TCP handshake. The HETS 270/271 application is configured to idle connections, but only after a 5-second delay to determine if additional requests will be sent. Trading Partners will greatly improve overall socket availability if they forcefully terminate all socket requests when their transactions are complete.

Each submitted transmission must contain one 270 request with only one Interchange Control Envelope, along with a transmission wrapper, around the 270 request. The purpose of the transmission wrapper is to communicate the length of the transaction message and to indicate the end of the transmission to the HETS 270/271 application.

The outbound response transaction wrapper has the same format as the inbound transmission wrapper. The 271 response to the Submitter will be returned in the same session in which the 270 request was submitted.


The standard format of the TCP/IP Communication Transport Protocol Wrapper, SOHLLLLLLLSTX<HIPAA 270 Transaction>ETX, is represented in Table 1.

Table 1 – Standard Format of the TCP/IP Communication Transport Protocol Wrapper

Element	Description	Length	Hexadecimal Value	Note(s)
SOH	Start of header	1	01	This is a required element.
LLLLLLLLL	# of bytes, including spaces, of the 270 request	10	N/A	Right justified, zero padded. This is a required element.
STX	Start of text	1	02	This is a required element.
HIPAA 270 Transaction	Eligibility request	variable	N/A	This is a required element.
ETX	End of text	1	03	This is a required element.

An illustration of the standard format of the TCP/IP Communication Transport Protocol Wrapper is represented by Figure 2.

Figure 2 – Example of TCP/IP Communication Transport Protocol Wrapper



Refer to the Extended Control Set matrix on page B.5 of the ASC X12 270/271 TR3 for additional information about SOH, STX and ETX.

#### 4.4 Security

The HETS 270/271 application is located at a secure CMS data center, which is available via the CMS Extranet. This extranet connection requires a password that is provided by the CMS-approved network reseller and features a variety of security measures to protect the integrity of the HETS 270/271 application. Additionally, the HETS 270/271 application authorizes Trading Partners based on their originating Internet Protocol (IP) address and their CMS issued HETS 270/271 Submitter ID.

All Trading Partners must assume full responsibility for the privacy and security of all Medicare Beneficiary data. Additionally, CMS holds Clearinghouse Submitters responsible for the privacy and security of eligibility transactions sent directly to them from Providers, and requires them to be able to associate each inquiry with a Provider. Provider authentication must be established by the Clearinghouse outside of the transaction.

#### 5 MCARE Contact Information

All inquiries and comments regarding Trading Partner registration, connection set-up, transaction testing, and the submission of 270/271 transactions and interpretation of their data should be directed to MCARE.

MCARE is available at 1-866-324-7315 or at <a href="MCARE@cms.hhs.gov">MCARE@cms.hhs.gov</a> Monday through Friday, from 7:00 AM to 7:00 PM ET.

**Note:** The MCARE email address is monitored during normal business hours. Emails are typically answered within one business day.

MCARE cannot assist in the resolution of benefit-related discrepancies. Questions regarding eligibility/benefit data for Medicare Part A and Part B should be directed to the appropriate regional MAC. Eligibility/benefit questions about MA, Part D and MSP should be directed to the appropriate plan(s) identified in the 271 response.

## 6 Control Segments/Envelopes

The following sections describe the HETS 270/271 transaction requirements to be used in conjunction with the requirements outlined in the TR3. Adhering to these requirements will help to ensure that transactions received by the HETS 270/271 application will pass the specified business edits.

All references to the ASC X12 270/271 TR3 assume the version referenced in <u>Section</u> 1.1 of this Companion Guide.

# 6.1 Interchange Control Structure (ISA/IEA)

Table 2 describes the values specifically required by the HETS 270/271 application within the ISA Header of the 270 request transaction. The HETS 270/271 application does not expect any custom values for the IEA segment within the 270 request. Please follow the rules as specified by the TR3.

TR3 Page #	Reference	X12 Element Name	Codes	Length	Notes/ Comments
C.4	ISA01	Authorization Information Qualifier	00	2	No authorization information must be present in ISA02
C.4	ISA03	Security Information Qualifier	00	2	N/A
C.4	ISA05	Interchange ID Qualifier	ZZ	2	N/A
C.4	ISA06	Interchange Sender ID	N/A	15	Must be Trading Partner Submitter ID assigned by CMS padded with trailing spaces to satisfy the minimum length requirements.
C.5	ISA07	Interchange ID Qualifier	ZZ	2	N/A

Table 2 – 270 ISA Segment Rules

TR3 Page #	Reference	X12 Element Name	Codes	Length	Notes/ Comments
C.5	ISA08	Interchange Receiver ID	N/A	15	Must be "CMS" padded with trailing spaces to satisfy the minimum length requirement.
C.6	ISA14	Acknowledgment Requested	0,1	1	CMS will not return the TA1 acknowledgement receipt of a real time transaction even if acknowledgment is requested.

# 6.2 Functional Group Structure (GS/GE)

Table 3 describes the values specifically required by the HETS 270/271 application within the GS Header of the 270 request transaction. Please follow the rules as specified by the TR3 for all other elements in GS Header.

The HETS 270/271 application does not expect any custom values for the GE segment within the 270 request. Please follow the rules as specified by the TR3 for the GE segment.

TR3 Page #	Reference	X12 Element Name	Codes	Length	Notes/ Comments
C.7	GS02	Application Sender's Code	N/A	8 or 10	Must be Trading Partner Submitter ID assigned by CMS
C.7	GS03	Application Receiver's Code	N/A	3	Must be "CMS"

Table 3 - 270 GS Segment Rules

# 6.3 Transaction Set Header/Trailer (ST/SE)

The HETS 270/271 application does not expect any custom values for the ST/SE segments within the 270 request. Please follow the rules as specified by the TR3.

# 7 Payer Specific Business Rules and Limitations

This section describes the business rules and limitations of the HETS 270/271 application.

All references to the ASC X12 270/271 TR3 assume the version referenced in <u>Section 1.1</u> of this Companion Guide.

#### 7.1 General Structural Notes

- Trading Partners should follow the ST/SE guidelines outlined in the 270 section of the TR3.
- Trading Partners should follow the ISA/IEA and GS/GE guidelines for HIPAA in Appendix C of the TR3 and follow the 999 and TA1 guidelines outlined in the Implementation Acknowledgement for Health Care Insurance.
- Trading Partners must follow the character set guidelines as defined in section B.1.1.2.5 of the TR3.
- CMS strongly recommends that Trading Partners use the preferred 270 request transaction delimiters in Table 4.

Character	Name	Delimiter	
* Asterisk		Data Element Separator	
Pipe		Component Element Separator	
~ Tilde		Segment Terminator	
^ Carat		Repetition Separator	

Table 4 – Preferred 270 Request Transaction Delimiters

 Each transaction must contain only one Patient Request. Each 270 request must have only one ISA/IEA, one GS/GE, one ST/SE, and a single 2100C Subscriber Loop.

#### 7.2 General Transaction Notes

- The HETS 270/271 application will return benefit data if the Medicare Beneficiary is entitled to Part A or Part B.
- The HETS 270/271 application will return a 999 error response if dependent level data is sent within a 270 request.
- The HETS 270/271 application will return a basic set of eligibility information even if no Service Type Code (STC) is included on the 270 request.
- The HETS 270/271 application will return additional eligibility information along with
  the basic set of eligibility data for certain service type codes. Refer to <u>Section 10</u> of
  this Companion Guide, for a list of data elements included within the basic set and
  the additional eligibility data elements returned on the 271 response for each
  supported STC. Only the basic set of eligibility data will be returned for valid STCs
  that are not referenced in <u>Section 10</u> of this Companion Guide.
- STCs specifically supported by the HETS 270/271 application include: 1, 14, 15, 30, 33, 35, 42, 45, 47, 86, 88, 98, AG, AL, MH and UC.

- The HETS 270/271 application will return benefit coverage status equal to "1" when the beneficiary has the applicable active Medicare enrollment for the date(s) requested for the following STCs: 1, 33, 35, 47, 86, 88, 98, AL, MH and UC.
- The HETS 270/271 application will not return STC = "47" or "88" in the "covered status" EB segment when Hospital or Part D Plan data, respectively, is returned.
- For additional information, refer to Table 17.
- The HETS 270/271 application will accept multiple STCs on a 270 request transaction.
- The HETS 270/271 application may return multiple EB loops to reflect the Medicare Beneficiary's benefit and enrollment history and/or the STCs requested in the 270 request.
- The 271 response is based upon information obtained from the CMS database at the time of inquiry and is not considered a guarantee of payment.
- The HETS 270/271 application will construct 271 responses with the preferred delimiters as noted in Table 4 of this Companion Guide.
- Trading Partners will receive a AAA error in Loop 2100A with a reject reason code of AAA03 = "42" (Unable to Respond at Current Time) when the HETS 270/271 application is unable to process a single transaction in less than 60 seconds or when other system issues are encountered.

# 7.3 Medicare Beneficiary Matching Rules

 The HETS 270/271 applies search logic that uses a combination of the following data elements: Health Insurance Claim Number (HICN), Medicare Beneficiary's Date of Birth (DOB), Medicare Beneficiary's Full Last Name, and Medicare Beneficiary's Full First Name. Table 5 describes the necessary data elements for the required primary and alternate search options supported by the HETS 270/271 application.

Search	HICN	Last Name	First Name	DOB
Primary	X	X	X	X
Alternate 1	X	X		X
Alternate 2	X	X	X	

Table 5 – HETS 270/271 Search Options

 If the Medicare Beneficiary's submitted HICN is found but is not the Medicare Beneficiary's active number, the HETS 270/271 application will cross-reference the submitted HICN to the active HICN. The 271 response will include in the 2100C Loop the inactive HICN within a REF segment, the active HICN within NM109 field, and a AAA error with a reject reason code of AAA03 = "72" (Invalid/Missing Subscriber/Insured ID). The submitter may then send a new 270 request transaction with the active HICN.

 If the search criteria do not produce a match to a Medicare Beneficiary, the HETS 270/271 application will generate the appropriate AAA03 error code in the 271 response. Refer to <u>Section 8.3</u> of this Companion Guide for additional information.

#### 7.4 Date of Service Rules

- The HETS 270/271 application will respond with the benefits provided only for the specific service date or date range contained in Loop 2100C, element DTP03 (Date Time Period) of the 270 request. If no date is contained in the 270 request, the HETS 270/271 application will respond with current eligibility information.
- CMS will verify that the requested date(s) on the 270 request are within the HETS 270/271 application's allowable date span. The allowable date span is up to 27 months in the past and up to four months in the future, based on the date the transaction was received. If requests are outside of this range, the HETS 270/271 application will return a AAA error in Loop 2100C with a reject reason code of AAA03 = "62" (Date of Service Not Within Allowable Inquiry Period).
- Table 6 illustrates the allowable request date ranges:

If the Current Month Is:	Historical Requests Are Valid Through:	Future Requests Are Valid Through:
January	October, 3 years ago	May of the current year
February	November, 3 years ago	June of the current year
March	December, 3 years ago	July of the current year
April	January, 2 years ago	August of the current year
May	February, 2 years ago	September of the current year
June	March, 2 years ago	October of the current year
July	April, 2 years ago	November of the current year
August	May, 2 years ago	December of the current year
September	June, 2 years ago	January of the following year
October	July, 2 years ago	February of the following year
November	August, 2 years ago	March of the following year
December	September, 2 years ago	April of the following year

Table 6 - Request Date Calendar

**Example:** If an eligibility request is sent on March 1, 2012, requests from December 1, 2009 through July 1, 2012 will be accepted.

# 7.5 Medicare Part A & Part B Eligibility Business Rules

 Trading Partners should review the entire 271 eligibility response to determine the appropriate eligibility status for the Medicare Beneficiary.

- To indicate periods of Medicare entitlement, the HETS 270/271 application will return Loop 2110C with element EB01 = "1" (Active Coverage) along with the Subscriber Eligibility/Benefit Date (DTP03) where DTP01 = "291" (Plan) with beginning and end dates, where appropriate, for each applicable entitlement period.
- The HETS 270/271 application will return Loop 2110C with element EB01 = "6" (Inactive) when an individual is entitled to one part of Medicare, but not the other. For example, when a Medicare Beneficiary is entitled to Part A but not Part B, the inactive EB segment would be returned for the Part B portion of the response.
- The HETS 270/271 application will return a 2110C Loop with element EB01= "6" (Inactive) for Part A and Part B without the DTP segments for either of the following reasons:
  - The Medicare Beneficiary's Part A and Part B entitlement had not yet begun as
    of the requested date(s) of service.
  - The Medicare Beneficiary's Part A and Part B entitlement has terminated prior to the requested date(s) of service.
- The HETS 270/271 application will return Loop 2110C with element EB01 = "6" (Inactive) along with a DTP segment containing beginning and end dates for the period of inactivity when an individual entitled to Medicare is ineligible for Medicare benefits over a period of time for any one the following reasons:

The Medicare Beneficiary has been classified as an illegal alien in the United States.

The Medicare Beneficiary has been deported from the United States.

The Medicare Beneficiary has been incarcerated.

**Note:** Information specifying the reason for the period of ineligibility will not be released.

- The HETS 270/271 application will return a 2110C Loop with element EB01= "6" (Inactive) and no additional data, when the Medicare Beneficiary is deceased and the Date of Death is prior to the requested date(s) of service.
- If a Medicare Beneficiary has died, but the requested date(s) of service are prior to the Date of Death, their Medicare Part A and/or Part B entitlement date(s) and other applicable eligibility data will be returned along with a separate DTP segment containing the Date of Death.
- The Insurance Type Code (EB04) will be omitted for the following reasons:
  - Requested dates are during a period of Incarceration, Deportation or Alien Status for a Beneficiary (EB04 is omitted only from the EB segment pertaining to the period of non-entitlement).

- Requested dates are after the Beneficiary's Date of Death.
- Multiple periods of a Medicare Beneficiary's inactive Medicare enrollment may be returned in a 271 response if they occur during the requested date(s) of service.
- Example segments returned in a 271 response:

#### Part A Entitlement

EB\*1\*\*30\*MA~
DTP\*307\*RD8\*CCYYMMDD-CCYYMMDD~ (DTP03 = Entitlement and Termination Dates (where applicable))

#### Part B Entitlement

EB\*1\*\*30\*MB~
DTP\*307\*RD8\*CCYYMMDD-CCYYMMDD~ (DTP03 = Entitlement and Termination Dates (where applicable))

#### Inactive Due to Date of Death

```
DTP*442*D8*CCYYMMDD~ (DTP03 = Date of Death) EB*6**30~
```

Entitled but Inactive Due to Incarceration, Deportation or Alien Status

```
EB*1**30*MA~
DTP*307*D8*CCYYMMDD~ (DTP03 = Part A Entitlement Date(s))
EB*1**30*MB~
DTP*307*D8*CCYYMMDD~ (DTP03 = Part B Entitlement Date(s))
...Benefit Information...
EB*6**30~
DTP*307*RD8*CCYYMMDD-CCYYMMDD~ (DTP03 = Inactive Date(s))
```

For additional information, refer to Table 17.

# 7.6 Part A Hospital and Skilled Nursing Facility (SNF) Spells Business Rules

- STC (Loop 2110C, Element EQ01) = "47" or "AG" must be included in the 270 request in order to receive Hospital Spell data in the 271 response.
- STC (Loop 2110C, Element EQ01) = "AG" must be included in the 270 request in order to receive SNF data in the 271 response.
- A SNF spell will always be accompanied by a prior Hospital stay.
- The dates of a Hospital/SNF spell (Loop 2110C, Element DTP01 = "435" (Admission)) will be returned as the Date of Earliest Billing Activity (DOEBA) through the Date of Latest Billing Activity (DOLBA) for the overall spell. Dates of individual Hospital/SNF stays within the complete spell will not be specified.

- All Hospital/SNF spells that fall within 60 days of the date or date range specified in the 270 request will be returned.
- If a single Hospital/SNF spell spans more than one calendar year, the HETS 270/271 application will return the daily copayment amounts associated with the beginning year of the spell.
- If there is no Hospital/SNF spell within 60 days of the requested date(s) of service, the HETS 270/271 application will return default values for Part A Spell data.
- The HETS 270/271 application will not generate a 2110 loop for future years that do not have default deductible or copayment per day values as published by CMS.
- Example 2110C loops returned in a 271 response:

# Hospital/SNF Spell

EB\*K\*\*47\*MA\*\*33\*\*\*LA\*60~ (EB10 = Part A Lifetime Days Remaining)
EB\*C\*\*47\*MA\*\*29\*150.25~ (EB07 = Part A Deductible Remaining)
DTP\*435\*RD8\*CCYYMMDD-CCYYMMDD~ (DTP03 = DOEBA-DOLBA)
EB\*F\*\*47\*MA\*\*29\*\*\*DY\*43~ (EB10 = Hospital Full Days Remaining)
DTP\*435\*RD8\*CCYYMMDD-CCYYMMDD~
EB\*B\*\*47\*MA\*\*29\*248\*\*DY\*30~ (EB07 = Copayment Amount per Day,
EB10 = Hospital Copayment Days Remaining)
DTP\*435\*RD8\*CCYYMMDD-CCYYMMDD~
EB\*F\*\*AG\*MA\*\*29\*\*\*DY\*20~ (EB10 = SNF Full Days Remaining)
DTP\*435\*RD8\*CCYYMMDD-CCYYMMDD~
EB\*B\*\*AG\*MA\*\*29\*124\*\*DY\*80~ (EB07 = Copayment Amount per Day,
EB10 = SNF Copayment Days Remaining)
DTP\*435\*RD8\*CCYYMMDD-CCYYMMDD~

#### Default Hospital/SNF Spell

EB\*K\*\*47\*MA\*\*33\*\*\*LA\*60~ (EB10 = Part A Lifetime Days Remaining)
EB\*C\*\*47\*MA\*\*29\*1100~ (EB07 = Part A Default Deductible Amount)
EB\*F\*\*47\*MA\*\*29\*\*\*DY\*60~ (EB10 = Default Hospital Full Days
Remaining)
EB\*B\*\*47\*MA\*\*29\*275\*\*DY\*30~ (EB07 = Default Copayment Amount per
Day, EB10 = Default Hospital Copayment Days Remaining)
EB\*F\*\*AG\*MA\*\*29\*\*\*DY\*20~ (EB10 = Default SNF Full Days Remaining)
EB\*B\*\*AG\*MA\*\*29\*137.5\*\*DY\*80~ (EB07 = Default Copayment Amount
per Day, EB10 = Default SNF Copayment Days Remaining)

For additional information, refer to Table 18.

#### 7.7 Home Health Periods Business Rules

- Home Health information for all periods that overlap the requested date(s) of service will only be returned on the 271 response when STC (Loop 2110C, element EQ01) = "42" is included in the 270 request.
- Insurance Type Code (EB04) of "MA" is returned if beneficiary is only Medicare Part A entitled; Insurance Type Code (EB04) of "MB" is returned if beneficiary is Medicare Part B entitled or Medicare Part A and Part B entitled.
- The DTP03 dates associated with DTP01 = "472" are the Home Health period Start and End Date(s).
- The DTP03 dates associated with DTP01 = "193" and "194" are the Home Health period DOEBA and DOLBA.
- When EB13 = "HC:G0180", the DTP03 date associated with DTP01 = "193" is the Home Health period Certification Date.
- When EB13 = "HC:G0179", the DTP03 date associated with DTP01 = "193" is the Home Health period Recertification Date.
- Home Health NPI will be returned in the 2120C loop NM109 element. The HETS 270/271 application will use multiple loops to return both the Contractor ID and the Provider ID.
- Example segments returned in a 271 response:

Home Health Periods if beneficiary is only Medicare Part A entitled

```
EB*X**42*MA**26~ (EB03 = Home Health Care)
DTP*472*RD8*CCYYMMDD-CCYYMMDD~ (DTP03 = Home Health Start and End Dates)
DTP*193*D8*CCYYMMDD~ (DTP03 = DOEBA)
DTP*194*D8*CCYYMMDD~ (DTP03 = DOLBA)
LS*2120~
NM1*PR*2*MAC*****PI*12345~ (NM109 = Contractor Number)
NM1*1P*1*****XX*1234567893~ (NM109 = Provider NPI)
LE*2120~
EB*X***MA*********HC:G0180~
DTP*193*D8*CCYYMMDD~ (Home Health Certification Start date)
EB*X***MA**********HC:G0179~
DTP*193*D8*CCYYMMDD~ (Home Health Recertification Start date)
```

Home Health Periods if beneficiary is Medicare Part B entitled or Medicare Part A and Part B entitled

```
EB*X**42*MB**26~ (EB03 = Home Health Care)
DTP*472*RD8*CCYYMMDD-CCYYMMDD~ (DTP03 = Home Health Start
```

```
and End Dates)
DTP*193*D8*CCYYMMDD~ (DTP03 = DOEBA)
DTP*194*D8*CCYYMMDD~ (DTP03 = DOLBA)
LS*2120~
NM1*PR*2*MAC*****PI*12345~ (NM109 = Contractor Number)
NM1*1P*1*****XX*1234567893~ (NM109 = Provider NPI)
LE*2120~
EB*X***MB*********HC:G0180~
DTP*193*D8*CCYYMMDD~ (Home Health Certification Start date)
EB*X***MB**********HC:G0179~
DTP*193*D8*CCYYMMDD~ (Home Health Recertification Start date)
```

For additional information, refer to Table 19.

#### 7.8 Part B Deductible Business Rules

- The dollar amount remaining for the Medicare Beneficiary's annual Part B deductible will be returned for all years within the requested Date(s) of Service, when the Medicare Beneficiary was also entitled to Part B at any time during those year(s) and when any of the following STCs are submitted on the 270 request:
  - 1, 14, 15, 30, 33, 35, 42, 45, 86, 88, 98, AL, MH, and UC
- Annual Part B deductible will not be returned when:

The Medicare Beneficiary was deceased prior to the start of that year.

The Medicare Beneficiary had an inactive period of Part B entitlement that spanned the entire calendar year.

- The HETS 270/271 application will not generate a 2110C loop for future years that do not have default deductible values as published by CMS.
- Example 2110C loop returned in a 271 response:

Part B Deductible

EB\*C\*\*96\*MB\*\*29\*0~ (EB07 = Part B Deductible Amount Remaining) DTP\*292\*RD8\*CCYY0101-CCYY1231~ (DTP03 = 01/01-12/31 of the deductible year that is represented)

For additional information, refer to Table 20.

# 7.9 Preventive Care Business Rules

Eligibility for preventive services will be returned in multiple EB Loops within a 271 response transaction when an STC of "30" is submitted for a Medicare Beneficiary that has active Part B entitlement and does not have a Date of Death on file at the time of the 270 request.

- Preventive services are described by the Healthcare Common Procedure Coding System (HCPCS). The following is a listing of the preventive categories and the associated HCPCS code(s) returned by the HETS 270/271 application:
  - Cardiovascular Disease Screening (CARD) includes codes 80061, 82465, 83718, and 84478.
  - Colorectal Cancer Screening (COLO) includes codes G0104, G0105, G0106, G0120 and G0121.
  - Fecal Occult Blood Test (FOBT) includes codes G0328 and 82270.
  - Diabetes Screening Tests (DIAB) includes codes 82947, 82950, and 82951.
  - Glaucoma Screening (GLAU) includes codes G0117 and G0118.
  - Initial Preventive Physical Examination (IPPE) includes codes G0402, G0403, G0404, and G0405.
  - Screening Mammography (MAMM) includes codes G0202 and 77057.
  - Screening Pelvic Exam (PCBE) includes code G0101.
  - Pneumococcal Vaccine (PPV) includes codes 90669, 90670 and 90732.
  - Prostate Cancer Screening (PROS) includes codes G0102 and G0103.
  - Screening Pap Test (PAPT) includes codes Q0091, P3000, G0123, G0143, G0144, G0145, G0147, and G0148.
  - Ultrasound Screening for Abdominal Aortic Aneurysm (AAA) includes code G0389.
  - Pharmacogenomic Testing for Warfarin Response (PTWR) includes code G9143.
  - Annual Wellness Visit (AWV) includes codes G0438 and G0439.
  - Screening and Behavioral Counseling to Reduce Alcohol Misuse codes are G0442 and G0443.
  - Annual Depression Screening includes code G0444.
  - Screening and Intensive Behavioral Counseling to prevent STIs includes code G0445.
  - Intensive Behavioral Therapy for Cardiovascular Disease includes code G0446.
  - Intensive Behavioral Counseling for Obesity includes code G0447.
- Preventive HCPCS codes may be returned twice in the 271 response if there are different dates for the technical and professional components of the service.
- Preventive care information displays current information only. No inference about historical eligibility can be made based on the returned next eligible dates. The next eligible date is the date on which the Medicare Beneficiary is/was eligible to receive services specified by the HCPCS.
- Example segments returned in a 271 response:

Preventive Care with the same Professional and Technical date

EB\*D\*\*\*MB\*\*\*\*\*\*\*\*\*HC|G121~ (EB13-2 = HCPCS Code) DTP\*348\*D8\*CCYYMMDD~ (DTP03 = Next Eligible Date) Preventive Care with different Professional and Technical dates for the HCPCS codes and Modifiers

```
EB*D***MB***********HC|G0103|26~ (EB13-2 = HCPCS Code, EB13-3 = HCPCS Modifier)
DTP*348*D8*20060701~ (DTP03 = Next Eligible Professional Date)
EB*D***MB*********HC|G0103|TC~ (EB13-2 = HCPCS Code, EB13-3 = HCPCS Modifier)
DTP*348*D8*20110601~ (DTP03 = Next Eligible Technical Date)
```

For additional information, refer to Table 21.

#### 7.10 Smoking / Tobacco Cessation Counseling Business Rules

- Eligibility for smoking/ tobacco cessation counseling benefits will be returned within a 271 response transaction when an STC of "30" is submitted for a Medicare Beneficiary that has active Part B entitlement and does not have a Date of Death on file at the time of the 270 request.
- Either the number of sessions remaining or next eligible date will be returned. If any sessions have been used in the applicable benefit period, the number of sessions remaining will be returned. Otherwise, the next date the Medicare Beneficiary is eligible to receive smoking/tobacco cessation counseling will be returned.
- Example segments returned in a 271 response:

Smoking/Tobacco Cessation

```
EB*D**67*MB~
DTP*348*D8*CCYYMMDD (DTP03 = Next Eligible Smoking/Tobacco
Cessation Counseling Date)
```

**OR** 

EB\*F\*\*67\*MB\*\*29\*\*\*P6\*6~ (EB10 = Number of Sessions Remaining)

For additional information, refer to Table 22.

# 7.11 Therapy Capitation Business Rules

- The dollar amount remaining for the Medicare Beneficiary's therapy capitation will be returned for all years within the requested Date(s) of Service, when the Medicare Beneficiary was also entitled to Part B at any time during those year(s) and when an STC of "30" is submitted on the 270 request.
- Therapy capitation information will not be returned when:
  - The Medicare Beneficiary was deceased prior to the start of that year.

- The Medicare Beneficiary had an inactive period of Part B entitlement that spanned the entire calendar year.
- The HETS 270/271 application will not generate an EB segment for future years that do not have default capitation values as published by CMS.
- The HETS 270/271 application will return EB03 = "AE" to represent a combined capitation limit for Physical and Speech Therapy.
- Example segments returned in a 271 response:

# **Therapy Capitation**

EB\*F\*\*AD\*MB\*\*29\*1810~ (EB07 = Therapy Capitation Amount Remaining)
DTP\*292\*RD8\*CCYY0101-CCYY1231~ (DTP03 = 01/01-12/31 of the Therapy Capitation year that is represented)

EB\*F\*\*AE\*MB\*\*29\*1810~ (EB07 = Therapy Capitation Amount Remaining)
DTP\*292\*RD8\*CCYYMMDD-CCYYMMDD~ (DTP03 = 01/01-12/31 of the Therapy Capitation year that is represented)

• For additional information, refer to Table 23.

# 7.12 Pulmonary Rehabilitation Services Business Rules

- Eligibility for Pulmonary Rehabilitation services will be returned within a 271
  response transaction when the data is available and an STC of "30" is submitted for
  a Medicare Beneficiary that has active Part B entitlement at the time of the 270
  request. Professional and/or Technical Sessions Remaining may be returned.
- Example segments returned in a 271 response:

Pulmonary Rehabilitation Services

EB\*F\*\*BF\*MB\*\*29\*\*\*CA\*72~ (EB10 = No. of PR Sessions remaining)

MSG\*Professional~

EB\*F\*\*BF\*MB\*\*29\*\*\*CA\*72~

MSG\*Technical~

For additional information, refer to Table 24.

# 7.13 Cardiac Rehabilitation and Intensive Cardiac Rehabilitation Services Business Rules

 Eligibility for Cardiac Rehabilitation and Intensive Cardiac Rehabilitation services will be returned within a 271 response transaction when the data is available and an STC of "30" is submitted for a Medicare Beneficiary that has active Part B entitlement at the time of the 270 request. Professional and/or Technical Sessions Used may be returned.

• Example segments returned in a 271 response:

Cardiac Rehabilitation Services

EB\*F\*\*BG\*MB\*\*\*\*\*99\*72~ (EB10 = No. of Cardiac Rehabilitation Sessions used)

MSG\*Professional~

EB\*F\*\*BG\*MB\*\*\*\*\*99\*72~

MSG\*Technical~

Intensive Cardiac Rehabilitation Services

EB\*F\*\*BG\*MB\*\*\*\*\*99\*72~ (EB10 = No. of Intensive Cardiac Rehab Sessions used)

MSG\*Intensive Cardiac Rehabilitation - Professional~

EB\*F\*\*BG\*MB\*\*\*\*\*99\*72~

MSG\*Intensive Cardiac Rehabilitation - Technical~

- For additional information, refer to
- Table 25 and Table 26.

#### 7.14 End Stage Renal Disease (ESRD) Periods Business Rules

- STC (Loop 2110C, element EQ01) = "14" or "15" must be included in the 270 request in order to receive ESRD dialysis method code, dialysis method start date, and kidney transplant hospital discharge date in a 271 response.
- Example segments returned in a 271 response:
  - ESRD Renal Supplies in the Home

 $EB^*D^{**}14^*MB^*$  (EB03 = 14 for Renal Supplies in the Home, EB04 = MB for Part B)

DTP\*356\*D8\*CCYYMMDD~ (DTP04 = ESRD Dialysis Method Start Date) DTP\*096\*D8\*CCYYMMDD~ (DTP04 = Kidney Transplant Hospital

Discharge Date)

ESRD – Alternative Method Dialysis

EB\*D\*\*15\*MA~ (EB03 = 15 for Alternative Method Dialysis, EB04 = MA for Part A)

DTP\*356\*D8\*CCYYMMDD~ (DTP04 = ESRD Dialysis Method Start Date) DTP\*096\*D8\*CCYYMMDD~ (DTP04 = Kidney Transplant Hospital Discharge Date)

For additional information, refer to Table 27.

#### 7.15 Hospice Care Periods Business Rules

- The Hospice section provides eligibility information when the hospice benefit is effective and when it terminates. When Hospice coverage is elected, the beneficiary waives all rights to Medicare payments for services that are related to the treatment and management of their terminal illness during any period their hospice benefit election is in effect, unless the services are provided by the designated hospice or provided by another hospice under arrangements made by the designated hospice. The one exception is for professional services of an attending physician, which may include a nurse practitioner. If the attending physician, who may be a nurse practitioner, is an employee of the designated hospice provider, they may not receive compensation from the Hospice for those services under Part B. These physician professional services are billed to Medicare Part A by the Hospice.
- Hospice information for all periods that overlap the date(s) of service requested will
  only be returned on the 271 response when STC (Loop 2110C, element EQ01) =
  "45" is included in the 270 request.
- Revocation Code will be returned in an MSG segment for the corresponding Hospice period. Revocation Code values returned by the HETS 270/271 application are:

# **Beneficiary in Hospice Care**

"0" - Not revoked, open spell

# **Beneficiary with Hospice Care Revoked**

"1" - Revoked by notice of revocation

"2" – Revoked by notice of revocation with a non-payment code of "N" and an occurrence code of "42"

"3" - Revoked by a Hospice claim with an occurrence code of "23"

Example segments returned in a 271 response:

Hospice Care with Facility information

```
EB*X**45*MA**26~ (EB03 = Hospice)
DTP*292*RD8*CCYYMMDD-CCYYMMDD~ (DTP03 = Hospice Period Dates)
MSG*Revocation Code – 0~ (MSG01 = Hospice Revocation Code)
LS*2120~
NM1*1P*2*****XX*1234567893~ (NM109 = Provider NPI)
LE*2120~
```

For additional information, refer to Table 28.

#### 7.16 Blood Deductible Business Rules

- The number of units remaining for the Medicare Beneficiary's annual blood deductible will be returned for all years within the requested Date(s) of Service, when the Medicare Beneficiary was entitled to either Medicare Part A or Part B at any time during those year(s) and when an STC of "30" is submitted on the 270 request.
- Annual blood deductible will not be returned when:

The Medicare Beneficiary was deceased prior to the start of that year.

The Medicare Beneficiary had an inactive period that spanned the entire calendar year.

- The HETS 270/271 application will not generate an EB segment for future years that do not have default deductible values as published by CMS.
- Example segments returned in a 271 response:

**Blood Deductible** 

EB\*D\*\*10\*\*\*29\*\*\*DB\*3 ~ (EB03 = Blood Charges; EB10 = Number of Units Remaining)
DTP\*292\*RD8\*CCYYMMDD-CCYYMMDD~ (DTP03 = 01/01-12/31 of the Blood Deductible year that is represented)

• For additional information, refer to Table 29.

#### 7.17 Part D Plan Enrollment Business Rules

- All Medicare Part D plans with enrollment periods that overlap the requested date(s)
  of service will be returned within the 271 response.
- Trading Partners are advised to contact the plans if there are any questions about the plan terms and conditions. In addition, indication of coverage does not imply or guarantee payment by the plan. Trading Partners should contact the plan for full benefit and billing information.
- For information on how to contact plans go to <a href="http://www.cms.gov/Research-Statistics-Data-and-Systems/Statistics-Trends-and-Reports/MCRAdvPartDEnrolData/index.html">http://www.cms.gov/Research-Statistics-Data-and-Systems/Statistics-Trends-and-Reports/MCRAdvPartDEnrolData/index.html</a> and choose "PDP Plan Directory".
- MA plans that offer Prescription Drug Coverage as a part of an HMO, PPO, POS, or Indemnity plan will be returned twice – once with the 'OT' designation to indicate Prescription Drug Coverage and once with the appropriate qualifiers for their MA Plan Type.
- MA plans that only offer Prescription Drug Coverage will be returned once, with the 'OT' designation.

Example segments returned in a 271 response:

Part D

EB\*R\*\*88\*OT~ (EB04 = OT – Prescription Drug Coverage)
REF\*18\*12345 001~ (REF02 = Contract Number followed by Plan Number)

DTP\*292\*RD8\*CCYYMMDD-CCYYMMDD~ (DTP03 = Part D Enrollment and Disenrollment Dates)

LS\*2120~

NM1\*PR\*2\*ABC DRUG COMPANY~ (NM103 = Contract Name)

N3\*PO BOX 123~ (N301 = Contract Street Address)

N4\*ANYTOWN\*MD\*99999999 (N401 = Contract City, N402 = Contract State, N403 = Contract Zip)

PER\*IC\*\*TE\*8001234567\*UR\*www.plan.com~ (PER04 = Plan Telephone Number, PER06 = Contract Website Address)
LE\*2120~

For additional information, refer to Table 30.

#### 7.18 MA Plan Enrollment Business Rules

- All Medicare Beneficiary MA plans with enrollment periods that overlap the requested date(s) of service will be returned within the 271 response.
- The HETS 270/271 application will return one of the following qualifiers within Loop 2110C, element EB04, for each MA enrollment:

HM for Health Maintenance Organization (HMO) Medicare Non-Risk

HN for HMO Medicare Risk

IN for Indemnity

PR for Preferred Provider Organization (PPO)

PS for Point of Service (POS)

The HETS 270/271 application will return only the most recent plan designation (HMO, PPO, POS, Indemnity) for an MA contract, even if the contract's plan designation has changed since the Medicare Beneficiary originally enrolled in the contract.

 MCO Bill Option Code will be returned only for Insurance Type Code values "HM", "HN", "IN", "PR" and "PS". The MCO Bill Option Codes returned by the HETS 270/271 application are:

# Beneficiary "locked in" to MCO

"A" - Fiscal Intermediary should process all claims

"B" - MCO should process only in-plan Part A claims and in-area Part B claims

"C" - MCO should process all claims

# Beneficiary NOT "locked in" to MCO

- "1" Fiscal Intermediary should process all claims
- "2" MCO should process only in-plan Part A claims and in-area Part B claims
- Trading Partners are advised to contact the plans if there are any questions about the plan terms and conditions. In addition, indication of coverage does not imply or guarantee payment by the plan. Trading Partners should contact the plan for full benefit and billing information.
- For information on how to contact plans go to <a href="http://www.cms.gov/Research-Statistics-Data-and-Systems/Statistics-Trends-and-Reports/MCRAdvPartDEnrolData/index.html">http://www.cms.gov/Research-Statistics-Data-and-Systems/Statistics-Trends-and-Reports/MCRAdvPartDEnrolData/index.html</a> and choose "MA Plan Directory".
- MA plans that offer Prescription Drug Coverage as a part of an HMO, PPO, POS, or Indemnity plan will be returned twice – once with the "OT" designation to indicate Prescription Drug Coverage and once with the appropriate qualifiers for their MA Plan Type.
- Example segments returned in a 271 response:
  - MA

EB\*R\*\*30\*HN~ (EB04 = Plan Type)
REF\*18\*12345 001~ (REF02 = Contract Number followed by Plan Number)
DTP\*290\*D8\*CCYYMMDD~ (DTP03 = MA Enrollment Date)
MSG\*MCO Bill Option Code – C~
LS\*2120~
NM1\*PRP\*2\*ABC HEALTHCARE~ (NM103 = Contract Name)
N3\*PO BOX 123~ (N301 = Contract Street Address)
N4\*ANYTOWN\*MD\*999999999 (N401 = Contract City, N402 = Contract State, N403 = Contract Zip)
PER\*IC\*\*TE\*8001234567\*UR\*www.plan.com~ (PER04 = Plan Telephone Number, PER06 = Contract Website Address)
LE\*2120~

For additional information, refer to Table 31.

# 7.19 Medicare Secondary Payer (MSP) Enrollment Business Rules

- All Medicare Beneficiary insurance coverage policies that are primary to Medicare coverage will be returned within the 271 response, provided that the enrollment period overlaps the requested date(s) of service.
- Example segments returned in a 271 response:

**MSP** 

EB\*R\*\*30\*12~(EB04 = MSP Insurance Type Code)
REF\*IG\*123456789~(REF02 = Insurance Policy Number)
DTP\*290\*D8\*CCYYMMDD~ (DTP03 = MSP Effective Date(s))
LS\*2120~
NM1\*PRP\*2\*ABC HEALTHPLAN~ (NM103 = MSP Name)
N3\*123 MAIN ST~ (N301 = MSP Street Address)
N4\*ANYTOWN\*MD\*999999999 (N401 = MSP City, N402=MSP State, N403=MSP Zip)
LE\*2120~

• For additional information, refer to

• Table 32.

#### 8 Acknowledgements and Error Codes

Only one response will be sent for each 270 request that is submitted – a TA1, a 999, a 271, or a proprietary error message. There are no CMS reports regarding the 270/271 transactions available to Trading Partners.

#### 8.1 TA1

The TA1 Interchange Acknowledgement is used by the HETS 270/271 application to communicate the rejection of a 270 request transaction based on errors encountered with X12 compliance, formatting, or CMS specific requirements of the ISA/IEA Interchange segments.

A 5010A1 TA1 may be returned if one of the following conditions exists:

- A 270 request is received and the version of the transmission cannot be determined.
- A 270 request is received and the version of the transmission is unsupported by the HETS 270/271 application. This includes previously accepted versions that are no longer supported.
- The submitter has not been authorized for the submitted X12 version.

#### 8.2 999

The 999 Implementation Acknowledgement is used by the HETS 270/271 application to communicate the rejection of a 270 request transaction based on errors encountered with X12 compliance, formatting, or CMS specific requirements within the data segments between the Functional Group Header (GS) and Functional Group Trailer (GE).

#### 8.3 271

When the 270 request complies with the X12 standard syntax requirements and all additional formatting rules as specified by this Companion Guide, then a 271 response transaction is returned to the Submitter. If no error exists, the Medicare Beneficiary eligibility data will be returned within the 271 response. Refer to Section 10.2 of this Companion Guide for more information.

The AAA error segment is utilized within the 271 response to communicate error conditions based on CMS business rules. The HETS 270/271 application will return the invalid or non-matching data element(s) from the 270 request for loop 2100C AAA error codes 15, 56, 62, 71, 72, 73 and 74. The AAA error codes are specified in Table 7.

In table 7, in the 2<sup>nd</sup> column, AAA01 Yes Condition means that the request is valid, but the transaction was rejected and AAA01 No Condition means that the request or an element in the request is not valid. In the 4<sup>th</sup> column, AAA04 Follow-up Action code R

means "Resubmission Allowed" and AAA04 Follow-up Action code C means "Please Correct and Resubmit".

Table 7 - AAA Error Codes

Loop	AAA01 Yes/ No Condition	AAA03 Reject Reason Code	AAA04 Follow-up Action Code
2100A	Yes	42 – When the system is unable to respond as a result of being unavailable. 1	R
2100A	No	79 – When 2100A NM103 or NM109 Source identification is other than "CMS".	С
2100B	No	41 – When the National Provider Identifier (NPI) located at 2100B NM109 is a valid FFS Medicare NPI and exists in HPG, but there is no current, valid relationship between the NPI and the provided HETS Submitter ID. Ensure that there is a relationship between your Submitter ID and the NPI in HPG.	С
2100B	No	43 – When the NPI located at 2100B NM109 is not a valid FFS Medicare provider or supplier or when 2100B NM101 is not equal to "IP", "FA" or "80". If you believe that the NPI is a valid FFS Medicare provider or supplier, contact your MAC for verification.	С
2100B	No	50 – When the NPI located at 2100B NM109 is a valid, FFS Medicare provider or supplier but is not currently eligible to verify Medicare eligibility in HETS. Contact MCARE for further information.	O
2100B	No	51 – When the NPI located at 2100B NM109 is not on file with HETS. Verify that the NPI is a valid FFS Medicare provider and ensure that the NPI is added to your Submitter ID via HPG.	O
2100C	15 – When the 270 2100C DMG02 element and		С
2100C	56 – When the 270 2100C DTP02 = RD8 and DTP03		С
2100C	No	62 – When the 270 2100C DTP03 element request date is more than 27 months in the past, or more than 4 months in the future.	С

 $<sup>^{1}</sup>$  If the transmission version cannot be determined or is not supported by HETS 270/271 application, the system will return a 5010A1 AAA03= 42 error.

Loop	AAA01 Yes/ No Condition	AAA03 Reject Reason Code	AAA04 Follow-up Action Code
2100C	No	71 – When the 270 2100C DMG02 element does not match the Medicare Beneficiary DOB on the database.	С
2100C	No	72 – When the 270 2100C NM109 element is an invalid length or cannot be matched to any HICN on the database.	С
2100C	No	72 – When the 270 2100C NM109 element is an inactive HICN that is cross-referenced to a new, active HICN for the same Beneficiary.	С
2100C	No	73 – When the 270 2100C NM103 element is missing or the matching algorithm of the Medicare Beneficiary Last Name on the 270 request does not match the matching algorithm of the Medicare Beneficiary Last Name in the database.	С
2100C	No	73 – When the 270 2100C NM104 element does not match the matching algorithm of the Medicare Beneficiary First Name in the database.	С

### 8.4 Proprietary Error Message

Proprietary error messages will be sent only when the ISA segment of the 270 request cannot be read, making it impossible to formulate an ISA segment for a 271 response. The proprietary message will return error codes and descriptions. Trading Partners may contact MCARE for assistance with Proprietary Errors. The format for the proprietary message is described in Table 8.

Table 8 - Proprietary Error Messages

Data Element	Description	Size	Comments
Transaction ID	Transaction ID	4	Data content will be "HETS"
Transaction Reference Number	Trace Identification Number or (ISA13)	30	
Date Stamp	System Date	8	CCYYMMDD
Time Stamp	System time	9	HHMMSSSSS
Response Code	ISA Formatting Error	2	" I" – Incoming ISA cannot be read OR "D" – Delimiter cannot be identified
Message Code	Error Code	8	Error code, refer to Table 9 of this Companion Guide
Message Text Description	Error Descriptions	500	" – Message Text Description", refer to Table 9 of this Companion Guide

Table 9 describes the Proprietary Error Message Codes.

Table 9 - Proprietary Error Message Codes

Message Code	Message Text Description
HTS00101	Transmission Wrapper SOH (hex=01) is invalid or missing
HTS00102	Transmission Wrapper STX (hex=02) is invalid or missing
HTS00103	Transmission Wrapper ETX (hex=03) is invalid or missing
HTS00104	Transmission Wrapper Length is missing or not numeric
HTS00105	Transmission Wrapper Length is greater than the Transmission Length
HTS00106	Transmission data is invalid or not ASCII
HTS00107	HIPAA 270 transaction does not start with ISA (Segment ID)
HTS00111	Transmission Inbound Message was empty
HTS00115	Interchange Error - Message specific to the condition will also be included in the error message description.
HTS00116	Syntax Error - Message specific to the condition will also be included in the error message description.
HTS00117	Transmission Error - Message specific to the condition will also be included in the error message description.

### 9 Trading Partner Agreements

The HETS 270/271 application will validate that the Clearinghouse or Provider has been established in the Trading Partner Management System (TPMS) prior to processing the 270 transaction. If the Trading Partner (ISA06) cannot be validated, the HETS 270/271 application will return a TA1 Interchange Acknowledgement.

Trading Partners may not send transactions to be executed as Usage Indicator (ISA15) = "P" until testing has been accomplished and approval to submit production transactions has been given. The HETS 270/271 application will return a TA105 = "020" error for an Invalid Test Indicator Value.

The Trading Partner Rules of Behavior are outlined within the Trading Partner Registration documentation. Please refer to Section 1.3 of this Companion Guide for links to these documents.

## 10 Transaction Specific Information

All references to the TR3 in this section assume the ASC X12 270/271 version referenced in <u>Section 1.1</u> of this Companion Guide.

• For the tables in sections 10.1 and 10.2, the "Length" column indicates field size limits of the HETS 270/271 application and may differ from the field lengths

presented in the TR3. A forward slash "/" between two numbers represents the minimum and maximum lengths for the element. For numeric fields, the minimum and maximum lengths allow for a decimal point, where applicable. Elements that include more than 1 distinct field length value will be displayed as the minimum length followed by "or" followed by the maximum length. For example, Postal Code can either be 5 digits or 9 digits; the length is displayed as "5 or 9".

• The "270 Service Type Code (EQ01)" column indicates which STC must be requested in order to receive each listed element. "All" in this column indicates that the element will be returned regardless of the STC submitted.

### 10.1 270 Eligibility Request Transaction

This section describes the values required by CMS in the 270 eligibility request transaction.

Any segments or elements not referenced in the following tables should be sent on the 270 as per the TR3.

#### 10.1.1 Information Source Level Structures

CMS will be the Information Source for all Medicare Eligibility Transactions. Trading Partners must submit the BHT03 reference identification to uniquely identify each transaction. Trading Partners must follow the specific requirements for the BHT as illustrated in Table 10.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments
64	Header	BHT02	Transaction Set Purpose Code	N/A	2	All codes are acceptable.
64	Header	BHT03	Submitter Transaction Identifier	N/A	1/50	Required for real-time inquiry.
70	2100A	NM102	Entity Type Qualifier	2	1	N/A
70	2100A	NM103	Information Source Last or Organization Name	N/A	3	"CMS"
71	2100A	NM109	Information Source Primary Identifier	N/A	3	"CMS"

Table 10 – Header and Information Source

#### 10.1.2 Information Receiver Level Structures

Clearinghouses that submit transactions on behalf of the Provider must ensure that the correct, valid, and active Medicare Provider identification is submitted as the Information Receiver. Only National Provider Identifier (NPI) numbers are accepted. Trading Partners must follow the specific requirements for the Information Receiver data as illustrated in Table 11.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments
75	2100B	NM101	Entity Identifier Code	1P, FA, or 80	2	N/A
77	2100B	NM108	Identification Code Qualifier	XX	2	N/A
78	2100B	NM109	Information Receiver Identification Number	N/A	10	The Provider's assigned Medicare NPI number.

Table 11 - Information Receiver

### 10.1.3 Subscriber Level Structures

Trading Partners must ensure that only one Medicare Beneficiary request is submitted in the Subscriber Level for each transaction. Trading Partners must follow the specific requirements for the Subscriber Level data as illustrated in Table 12.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments
93	2100C	NM103	Subscriber Last Name	N/A	1/60	Last Name is required for Medicare Beneficiary Identification using the Primary or Alternate Search options.
93	2100C	NM104	Subscriber First Name	N/A	1/35	First name is required for Medicare Beneficiary Identification only when the Beneficiary's date of birth is not submitted.

Table 12 – Subscriber

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments
94	2100C	NM107	Subscriber Name Suffix <sup>1</sup>	N/A	1/10	When the suffix is part of the Medicare Beneficiary's Last Name on the Medicare card, the suffix is required for Last Name matching.
95	2100C	NM108	Identification Code Qualifier	MI	2	N/A
96	2100C	NM109	Subscriber Primary Identifier	N/A	7/12	The HICN is required for Medicare Beneficiary Search. This element must exactly match the ID on the patient's Medicare card.
108	2100C	DMG02	Subscriber Birth Date	N/A	8	Date of Birth is required for Medicare Beneficiary Identification only when the Beneficiary's first name is not submitted.
123	2100C	DTP01	Date Time Qualifier	291	3	N/A
125	2110C	EQ01	Service Type Code	N/A	1/2	All codes are accepted. <sup>2</sup> For a complete list of codes, refer to page 126 of the TR3.
131	2110C	EQ02-1	Product or Service ID Qualifier	N/A	2	All codes are accepted.
131	2110C	EQ02-2	Procedure Code	N/A	1/48	N/A

# 10.2 271 Eligibility Response Transaction

This section describes the values returned by CMS in the 271 eligibility response transaction. The following tables describe the CMS utilization of segments and elements when there is a type of uniqueness or restriction. All other values comply with the TR3.

-

<sup>&</sup>lt;sup>1</sup> For convenience, a Medicare Beneficiary's name suffix can also be appended to the last name field in order to meet matching constraints

matching constraints.

<sup>2</sup> While all STCs will be accepted by the HETS 270/271 application, only those specified by this Companion Guide will return explicit benefit information. All other codes will return only the basic set of eligibility data.

Table 13 - Header and Information Source

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
212	Header	BHT03	Submitter Transaction Identifier	N/A	1/30	Required for real- time inquiry.	All
212	Header	BHT04	Transaction Set Creation Date	N/A	8	System Date	All
212	Header	BHT05	Transaction Set Creation Time	N/A	8	System Time Stamp	All
218	2100A	NM101	Entity Identifier Code	PR	2	N/A	All
220	2100A	NM108	Identification Code Qualifier	PI	2	N/A	All
220	2100A	NM109	Information Source Primary Identifier	N/A	3	"CMS"	All
222	2100A	PER03	Communication Number Qualifier	UR	2	N/A	All
223	2100A	PER04	Information Source Communication Number	N/A	28	http://www.cms.gov/ HETSHelp/	All
223	2100A	PER05	Communication Number Qualifier	UR	2	N/A	All
224	2100A	PER06	Information Source Communication Number	N/A	38	http://www.cms.gov/c enter/provider.asp	All

Table 14 – Information Receiver

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
234	2100B	NM108	Identification Code Qualifier	XX	2	N/A	All

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
235	2100B	NM109	Information Receiver Identification Number	N/A	10	The Provider's assigned NPI number as submitted on the 270 request.	All

Table 15 - Subscriber Demographic Data

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
248	2000C	TRN01	Trace Type Code	2	1	N/A	All
250	2100C	NM103	Subscriber Last Name <sup>1</sup>	N/A	1/40	N/A	All
250	2100C	NM104	Subscriber First Name <sup>1</sup>	N/A	1/30	N/A	All
250	2100C	NM105	Subscriber Middle Initial <sup>1</sup>	N/A	1	N/A	All
251	2100C	NM107	Subscriber Name Suffix <sup>1</sup>	N/A	1/10		All
251	2100C	NM108	Identification Code Qualifier	MI	2	N/A	All
252	2100C	NM109	Subscriber Primary Identifier	N/A	7/12	This data element is the HICN submitted on the 270 request or the active cross- referenced HICN when an inactive HICN is submitted.	All
254	2100C	REF01	Reference Identification Qualifier	Q4	2	N/A	All

<sup>&</sup>lt;sup>1</sup> If there are errors in the transaction, these data elements will be the same as the 270. If a match is found, these data elements will be the value from the CMS Eligibility Database with the exception of Subscriber Name Suffix, which will be returned only in the event of an error. If there is a valid Subscriber Name Suffix, it will be appended to the Subscriber Last Name field.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
256	2100C	REF02 <sup>1</sup>	Subscriber Supplemental Identifier	N/A	7/12	Used to communicate the submitted HICN from the 270 when a cross-referenced HICN is located	All
257	2100C	N301 <sup>2</sup>	Subscriber Address Line	N/A	1/40	Medicare Beneficiary Address Line 1	All
258	2100C	N302	Subscriber Address Line	N/A	1/40	Medicare Beneficiary Address Line 2	All
260	2100C	N401	Subscriber City Name	N/A	2/30	Medicare Beneficiary City Name	All
260	2100C	N402	Subscriber State Code	N/A	2	Medicare Beneficiary State Code	All
260	2100C	N403	Subscriber Postal Zone or Zip Code	N/A	5 or 9	Medicare Beneficiary Postal ZIP Code	All
269	2100C	DMG02	Subscriber Birth Date	N/A	8	Medicare Beneficiary Date of Birth	All
269	2100C	DMG03	Subscriber Gender Code	F, M	1	Medicare Beneficiary Gender Code <sup>3</sup>	All
283	2100C	DTP01	Date Time Qualifier	307	3	N/A	All
284	2100C	DTP02	Date Time Period Format Qualifier	D8 or RD8	2 or 3	N/A	All
284	2100C	DTP03	Date Time Period	N/A	8 or 17	Eligibility Request Start Date or Eligibility Request Start and End Dates	All
283	2100C	DTP01	Date Time Qualifier	442	3	N/A	All
284	2100C	DTP02	Date Time Period Format Qualifier	D8	2	N/A	All

<sup>&</sup>lt;sup>1</sup> REF segment in the 2100C loop is returned containing the HICN submitted on the 270 when an active/cross-referenced HICN is found and returned in the NM109. REF segment in the 2100C loop is also returned if submitted on the 270 and REF02=EJ.

The HETS 270/271 application returns only addresses that fall within the United States and its territories.

<sup>&</sup>lt;sup>3</sup> If there are errors in the transaction, this data element will be the same as the 270. If a match is found, this data element will be the value from the CMS Eligibility Database.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
284	2100C	DTP03	Eligibility or Benefit Date Time Period	N/A	8	Date of Death	All

Table 16 - Benefit Coverage Data for Mandated STCs

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	1	1	N/A	30, 1, 33, 35, 47, 86, 88, 98, AL, MH, UC
293	2110C	EB03	Service Type Code	1, 33, 35 ,47, 86, 88, 98, AL, MH, UC	17/28	If benefits for STCs "88" and "47" are returned later in the transaction, they won't be duplicated in this segment.	30
293	2110C	EB03	Service Type Code	1	17/28	N/A	1
293	2110C	EB03	Service Type Code	33	17/28	N/A	33
293	2110C	EB03	Service Type Code	35	17/28	N/A	35
293	2110C	EB03	Service Type Code	47	17/28	If this benefit is returned later in the transaction, it won't be duplicated in this segment.	47
293	2110C	EB03	Service Type Code	86	17/28	N/A	86

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
293	2110C	EB03	Service Type Code	88	17/28	If this benefit is returned later in the transaction, it won't be duplicated in this segment.	88
293	2110C	EB03	Service Type Code	98	17/28	This value will only be returned if the beneficiary has active Medicare Part B entitlement for the requested date(s).	98
293	2110C	EB03	Service Type Code	AL	17/28	N/A	AL
293	2110C	EB03	Service Type Code	МН	17/28	N/A	МН
293	2110C	EB03	Service Type Code	UC	17/28	N/A	UC

Table 17 - Medicare Part A and Part B Eligibility

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	1 or 6	1	N/A	All
293	2110C	EB03	Service Type Code	30	2	N/A	All
298	2110C	EB04	Insurance Type Code	MA or MB	2	EB04 may be omitted <sup>1</sup>	All
317	2110C	DTP01	Date Time Qualifier	291	3	N/A	All

<sup>&</sup>lt;sup>1</sup> EB04 will be omitted when requested dates are after a Beneficiary's Date of Death. When requested dates are during a period of Incarceration, Deportation or Alien Status, EB04 will be omitted only from the EB segment pertaining to the period of inactivity or ineligibility.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
318	2110C	DTP02	Date Time Period Format Qualifier	D8 or RD8	2 or 3	D8, if only Entitlement Date; RD8, if Entitlement and Termination Dates exist	All
318	2110C	DTP03 <sup>1</sup>	Eligibility or Benefit Date Time Period	N/A	8 or 17	Entitlement or Entitlement and Termination dates <sup>2</sup>	All

Table 18 – Part A Hospital and SNF Data<sup>3</sup>

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	К	1	Lifetime Reserve EB Loop	47/AG
293	2110C	EB03	Service Type Code	47	2	N/A	47/AG
298	2110C	EB04	Insurance Type Code	MA	2	N/A	47/AG
299	2110C	EB06	Time Period Qualifier	33	2	N/A	47/AG
301	2110C	EB09	Quantity Qualifier	LA	2	N/A	47/AG
302	2110C	EB10	Benefit Quantity	N/A	1/2	Lifetime Reserve Days Remaining	47/AG
291	2110C	EB01	Eligibility or Benefit Information	С	1	Part A Deductible EB Loop	47/AG
293	2110C	EB03	Service Type Code	47	2	N/A	47/AG

<sup>&</sup>lt;sup>1</sup> For inactive periods, DTP will only be included for a specific date range.

<sup>&</sup>lt;sup>2</sup> When multiple entitlements are returned, they will occur in descending order: future, current, past.

<sup>&</sup>lt;sup>3</sup> Hospital Days remaining, Hospital Copayment Days Remaining, SNF Days Remaining, SNF Copayment Days Remaining, DOEBA, and DOLBA are related to a single Inpatient Spell and NOT to the individual general benefit. DTP segments will not be returned accompanying default Part A Deductible, Hospital Days Remaining, or SNF Days Remaining data. For each Inpatient Spell, DTP segments will be returned for each occurrence of an EB segment. Part A and SNF deductible and copayment per day values will be returned for future calendar years only when CMS-published values are available.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
298	2110C	EB04	Insurance Type Code	MA	2	N/A	47/AG
299	2110C	EB06	Time Period Qualifier	29	2	N/A	47/AG
300	2110C	EB07	Benefit Amount	N/A	1/7	Deductible Amount	47/AG
317	2110C	DTP01	Date Time Qualifier	435	3	N/A	47/AG
318	2110C	DTP02	Date Time Period Format Qualifier	RD8	3	N/A	47/AG
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	17	DOEBA-DOLBA	47/AG
291	2110C	EB01	Eligibility or Benefit Information	F	1	Hospital Days Remaining EB Loop	47/AG
293	2110C	EB03	Service Type Code	47	2	N/A	47/AG
294	2110C	EB04	Insurance Type Code	MA	2	N/A	47/AG
299	2110C	EB06	Time Period Qualifier	29	2	N/A	47/AG
301	2110C	EB09	Quantity Qualifier	DY	2	N/A	47/AG
302	2110C	EB10	Benefit Quantity	N/A	1/2	Hospital Days Remaining	47/AG
291	2110C	EB01	Eligibility or Benefit Information	В	1	Hospital Copayment Days Remaining EB Loop	47/AG
293	2110C	EB03	Service Type Code	47	2	N/A	47/AG
294	2110C	EB04	Insurance Type Code	MA	2	N/A	47/AG
299	2110C	EB06	Time Period Qualifier	29	2	N/A	47/AG
300	2110C	EB07	Benefit Amount	N/A	1/5	Daily Copayment Amount	47/AG
301	2110C	EB09	Quantity Qualifier	DY	2	N/A	47/AG

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
302	2110C	EB10	Benefit Quantity	N/A	1/2	Hospital Copayment Days Remaining	47/AG
291	2110C	EB01	Eligibility or Benefit Information	F	1	SNF Days Remaining EB Loop	AG
293	2110C	EB03	Service Type Code	AG	2	N/A	AG
294	2110C	EB04	Insurance Type Code	MA	2	N/A	AG
299	2110C	EB06	Time Period Qualifier	29	2	N/A	AG
301	2110C	EB09	Quantity Qualifier	DY	2	N/A	AG
302	2110C	EB10	Benefit Quantity	N/A	1/2	SNF Days Remaining	AG
291	2110C	EB01	Eligibility or Benefit Information	В	1	SNF Copayment Days Remaining EB Loop	AG
293	2110C	EB03	Service Type Code	AG	2	N/A	AG
298	2110C	EB04	Insurance Type Code	MA	2	N/A	AG
299	2110C	EB06	Time Period Qualifier	29	2	N/A	AG
300	2110C	EB07	Benefit Amount	N/A	1/5	Daily Copayment Amount	AG
301	2110C	EB09	Quantity Qualifier	DY	2	N/A	AG
302	2110C	EB10	Benefit Quantity	N/A	1/2	SNF Copayment Days Remaining	AG

Table 19 – Home Health Data<sup>1</sup>

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)		
291	2110C	EB01	Eligibility or Benefit Information	Х	1	N/A	42		
293	2110C	EB03	Service Type Code	42	2	N/A	42		
298	2110C	EB04	Insurance Type Code	MA or MB	2	"MA" is returned if beneficiary is only Medicare Part A entitled; "MB" is returned if beneficiary is Medicare Part B entitled or Medicare Part A and Part B entitled.	42		
299	2110C	EB06	Time Period Qualifier	26	2	N/A	42		
317	2110C	DTP01	Date Time Qualifier	472, 193 or 194	3	"472" is used for Home Health Start and End Dates; "193" is used for DOEBA; "194" is used for DOLBA.	42		
318	2110C	DTP02	Date Time Period Format Qualifier	D8 or RD8	2 or 3	"RD8" is used for Start and End Dates; "D8" is used for DOEBA/DOLBA.	42		
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	8 or 17	Start Date - End Date, DOEBA, or DOLBA	42		
330	2120C	NM101	Entity Identifier Code	PR	2	N/A	42		
331	2120C	NM102	Entity Type Qualifier	2	1	N/A	42		

 $<sup>^{\</sup>rm 1}$  Home Health Data will be returned only for episodes with end dates.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
331	2120C	NM103	Benefit Related Entity Last or Organization Name	N/A	10/30	"Cahaba GBA", "National Government Services, Inc.", "National Heritage Insurance Company", "Palmetto GBA", or "United Government Services, CA"	42
332	2120C	NM108	Identification Code Qualifier	PI	2	N/A	42
333	2120C	NM109	Benefit Related Entity Identifier	N/A	5	00011, 00180, 00380, 00450, 00454, 00456, 11004, 14004, or 15004	42
330	2120C	NM101	Entity Identifier Code	1P	2	N/A	42
332	2120C	NM108	Identification Code Qualifier	XX	2	N/A	42
333	2120C	NM109	Benefit Related Entity Identifier	N/A	10	NPI	42
291	2110C	EB01	Eligibility or Benefit Information	Х	1	Home Health Certification EB Loop	42
298	2110C	EB04	Insurance Type Code	MA or MB	2	"MA" is returned if beneficiary is only Medicare Part A entitled; "MB" is returned if beneficiary is Medicare Part B entitled or Medicare Part A and Part B entitled.	42

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
299	2110C	EB13	Composite Medical Procedure Identifier	HC:G0180	8	"HC:G0180" is used to indicate Home Health Certification	42
317	2110C	DTP01	Date Time Qualifier	193	3	"193" is used for the Certification date	42
318	2110C	DTP02	Date Time Period Format Qualifier	D8	2	"D8" is used for the Certification date	42
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	8	Date of Certification	42
291	2110C	EB01	Eligibility or Benefit Information	Х	1	Home Health Recertification EB Loop	42
298	2110C	EB04	Insurance Type Code	MA or MB	2	"MA" is returned if beneficiary is only Medicare Part A entitled; "MB" is returned if beneficiary is Medicare Part B entitled or Medicare Part A and Part B entitled.	42
299	2110C	EB13	Composite Medical Procedure Identifier	HC:G0179	8	"HC:G0179" is used to indicate Home Health Recertification.	42
317	2110C	DTP01	Date Time Qualifier	193	3	"193" is used for the Recertification date	42
318	2110C	DTP02	Date Time Period Format Qualifier	D8	2	"D8" is used for the Recertification date	42
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	8	Date of Recertification	42

Table 20 – Part B Deductible Data<sup>1</sup>

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	С	1	N/A	1, 14, 15, 30, 33, 35, 42, 45, 86, 88, 98, AL, MH, UC
293	2110C	EB03	Service Type Code	96	2	N/A	1, 14, 15, 30, 33, 35, 42, 45, 86, 88, 98, AL, MH, UC
298	2110C	EB04	Insurance Type Code	МВ	2	N/A	1, 14, 15, 30, 33, 35, 42, 45, 86, 88, 98, AL, MH, UC
299	2110C	EB06	Time Period Qualifier	29	2	N/A	1, 14, 15, 30, 33, 35, 42, 45, 86, 88, 98, AL, MH, UC
300	2110C	EB07	Benefit Amount	N/A	1/5	Deductible Amount	1, 14, 15, 30, 33, 35, 42, 45, 86, 88, 98, AL, MH, UC

<sup>&</sup>lt;sup>1</sup> Part B Deductible values will be returned for future calendar years only when CMS-published values are available.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
317	2110C	DTP01	Date Time Qualifier	292	3	N/A	1, 14, 15, 30, 33, 35, 42, 45, 86, 88, 98, AL, MH, UC
318	2110C	DTP02	Date Time Period Format Qualifier	RD8	3	N/A	1, 14, 15, 30, 33, 35, 42, 45, 86, 88, 98, AL, MH, UC
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	17	CCYY0101- CCYY1231	1, 14, 15, 30, 33, 35, 42, 45, 86, 88, 98, AL, MH, UC

**Table 21 – Preventive Data** 

Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	D	1	Preventive Services EB Loop(s)	30
298	2110C	EB04	Insurance Type Code	MB	2	N/A	30
304	2110C	EB13-1	Product or Service ID Qualifier	НС	2	N/A	30
305	2110C	EB13-2	Procedure Code	N/A	5	HCPCS Code	30

Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
305	2110C	EB13-3	Procedure Modifier	26 or TC	2	HCPCS Modifier 26 (Professional Component) or TC (Technical Component) Omit EB13-3 if the dates are the same.	30
317	2110C	DTP01	Date Time Qualifier	348	3	N/A	30
318	2110C	DTP02	Date Time Period Format Qualifier	D8	2	N/A	30
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	8	Next Eligible Date	30

Table 22 - Smoking/Tobacco Cessation Data

Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01 <sup>1</sup>	Eligibility or Benefit Information	F	1	Smoking/Tobacco Cessation Sessions Remaining EB Loop	30
293	2110C	EB03	Service Type Code	67	2	N/A	30
298	2110C	EB04	Insurance Type Code	MB	2	N/A	30
299	2110C	EB06	Time Period Qualifier	29	2	N/A	30
301	2110C	EB09	Quantity Qualifier	P6	2	N/A	30
302	2110C	EB10	Benefit Quantity	N/A	1/2	Sessions remaining	30

<sup>&</sup>lt;sup>1</sup> Smoking Cessation Counseling Sessions Remaining will be returned when the Beneficiary is eligible for Smoking Cessation Counseling with no waiting period; next eligible date will not be returned.

Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01 <sup>1</sup>	Eligibility or Benefit Information	D	1	Smoking/Tobacco Cessation Next Eligible Date EB Loop	30
293	2110C	EB03	Service Type Code	67	2	N/A	30
298	2110C	EB04	Insurance Type Code	MB	2	N/A	30
317	2110C	DTP01	Date Time Qualifier	348	3	N/A	30
318	2110C	DTP02	Date Time Period Format Qualifier	D8	2	N/A	30
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	8	Next Eligible Date	30

Table 23 – Therapy Capitation Data<sup>2</sup>

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	F	1	Occupational Therapy Capitation EB Loop	30
293	2110C	EB03	Service Type Code	AD	2	N/A	30
298	2110C	EB04	Insurance Type Code	MB	2	N/A	30
299	2110C	EB06	Time Period Qualifier	29	2	N/A	30
300	2110C	EB07	Benefit Amount	N/A	1/7	Occupational Therapy Capitation Amount	30

<sup>&</sup>lt;sup>1</sup> Smoking/Tobacco Cessation Counseling Next Eligible Date will be returned when no Smoking/Tobacco Cessation Counseling sessions remain; sessions remaining will not be returned.
<sup>2</sup> Therapy Capitation values will be returned for future calendar years only when CMS-published values are available.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
317	2110C	DTP01	Date Time Qualifier	292	3	N/A	30
318	2110C	DTP02	Date Time Period Format Qualifier	RD8	3	N/A	30
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	17	CCYY0101- CCYY1231	30
291	2110C	EB01	Eligibility or Benefit Information	F	1	Physical/Speech Therapy Capitation EB Loop	30
293	2110C	EB03	Service Type Code	AE	2	N/A	30
298	2110C	EB04	Insurance Type Code	MB	2	N/A	30
299	2110C	EB06	Time Period Qualifier	29	2	N/A	30
300	2110C	EB07	Benefit Amount	N/A	1/7	Physical/Speech Therapy Capitation Amount	30
317	2110C	DTP01	Date Time Qualifier	292	3	N/A	30
318	2110C	DTP02	Date Time Period Format Qualifier	RD8	3	N/A	30
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	17	CCYY0101- CCYY1231	30

Table 24 – Pulmonary Rehabilitation Services

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	F	1	Pulmonary Rehabilitation EB Loop	30
296	2110C	EB03	Service Type Code	BF	2	N/A	30

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
298	2110C	EB04	Insurance Type Code	MB	2	N/A	30
300	2110C	EB06	Time Period Qualifier	29	2	N/A	30
301	2110C	EB09	Quantity Qualifier	CA	2	N/A	30
302	2110C	EB10	Quantity	N/A	1/2	Number of Pulmonary Rehabilitation sessions remaining	30
323	2110C	MSG01	Free-form Message Text	N/A	9 or 12	'Professional' or 'Technical'	30

**Table 25 - Cardiac Rehabilitation Services** 

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	F	1	Cardiac Rehabilitation EB Loop	30
296	2110C	EB03	Service Type Code	BG	2	N/A	30
298	2110C	EB04	Insurance Type Code	MB	2	N/A	30
301	2110C	EB09	Quantity Qualifier	99	2	N/A	30
302	2110C	EB10	Quantity	N/A	1/2	Number of Cardiac Rehabilitation sessions used	30
323	2110C	MSG01	Free-form Message Text	N/A	9 or 12	'Professional' or 'Technical'	30

Table 26 - Intensive Cardiac Rehabilitation Services

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	F	1	Intensive Cardiac Rehabilitation EB Loop	30
296	2110C	EB03	Service Type Code	BG	2	N/A	30
298	2110C	EB04	Insurance Type Code	MB	2	N/A	30
301	2110C	EB09	Quantity Qualifier	99	2	N/A	30
302	2110C	EB10	Quantity	N/A	1/2	Number of Intensive Cardiac Rehabilitation sessions used	30
323	2110C	MSG01	Free-form Message Text	N/A	44 or 47	'Intensive Cardiac Rehabilitation- Professional' or 'Intensive Cardiac Rehabilitation- Technical'	30

Table 27 - ESRD Data

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	D	1	N/A	14/15
293	2110C	EB03	Service Type Code	14 or 15	2	N/A	14/15
298	2110C	EB04	Insurance Type Code	MA or MB	2	N/A	14/15
317	2110C	DTP01	Date Time Qualifier	356	3	N/A	14/15

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
318	2110C	DTP02	Date Time Period Format Qualifier	D8	2	N/A	14/15
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	8	ESRD Effective Date	14/15
317	2110C	DTP01	Date Time Qualifier	096	3	N/A	14/15
318	2110C	DTP02	Date Time Period Format Qualifier	D8	2	N/A	14/15
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	8	Transplant Discharge Date	14/15

Table 28 – Hospice Data

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	X	1	N/A	45
292	2110C	EB03	Service Type Code	45	2	N/A	45
298	2110C	EB04	Insurance Type Code	MA	2	N/A	45
299	2110C	EB06	Time Period Qualifier	26	2	N/A	45
317	2110C	DTP01	Date Time Qualifier	292	3	N/A	45
318	2110C	DTP02	Date Time Period Format Qualifier	RD8	3	N/A	45
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	17	Start and End Dates	45

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
323	2110C	MSG01	Free-form Message Text	N/A	18	"Revocation code – <revocation code<br="">value&gt;". Code values returned are: 0, 1, 2, or 3.</revocation>	45
330	2120C	NM101	Entity Identifier Code	1P	2	N/A	45
331	2120C	NM102	Entity Type Qualifier	2	1	N/A	45
332	2120C	NM108	Identification Code Qualifier	XX	2	N/A	45
333	2120C	NM109	Benefit Related Entity Identifier	N/A	10	NPI	45

Table 29 – Blood Deductible Data<sup>1</sup>

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	D	1	N/A	30
292	2110C	EB03	Service Type Code	10	2	N/A	30
299	2110C	EB06	Time Period Qualifier	29	2	N/A	30
301	2110C	EB09	Quantity Qualifier	DB	2	N/A	30
302	2110C	EB10	Benefit Quantity	N/A	1	Number of Units	30
317	2110C	DTP01	Date Time Qualifier	292	3	N/A	30
318	2110C	DTP02	Date Time Period Format Qualifier	RD8	3	N/A	30
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	17	CCYY0101- CCYY1231	30

<sup>&</sup>lt;sup>1</sup> Blood Deductible Units will be returned for future calendar years only when CMS-published values are available.

Table 30 - Part D Enrollment Data

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	R	1	Part D Enrollment EB Loop	All
293	2110C	EB03	Service Type Code	88	2	N/A	All
298	2110C	EB04	Insurance Type Code	ОТ	2	N/A	All
315	2110C	REF01	Reference Identification Qualifier	18	2	N/A	All
316	2110C	REF02	Subscriber Eligibility or Benefit Identifier	N/A	5 or 9	Contract Number and Plan Number separated by a space. If a Plan Number is unavailable only the Contract Number will be in this element.	All
317	2110C	DTP01	Date Time Qualifier	292	3	N/A	All
318	2110C	DTP02	Date Time Period Format Qualifier	D8 or RD8	2 or 3	N/A	All
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	8 or 17	Part D Enrollment Date or Part D Enrollment and Disenrollment Dates	All
330	2120C	NM101	Entity Identifier Code	PR	2	N/A	All
331	2120C	NM102	Entity Type Qualifier	2	1	N/A	All
331	2120C	NM103	Benefit Related Entity Last or Organization Name	N/A	1/35	Plan Name	All

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
335	2120C	N301¹	Benefit Related Entity Address Line	N/A	1/55	Payer Address Line 1	All
335	2120C	N302	Benefit Related Entity Address Line	N/A	1/55	Payer Address Line 2	All
336	2120C	N401	Benefit Related Entity City Name	N/A	2/30	Payer City	All
337	2120C	N402	Benefit Related Entity State Code	N/A	2	Payer State Code	All
337	2120C	N403	Benefit Related Entity Postal Zone or Zip Code	N/A	5 or 9	Payer ZIP Code	All
340	2120C	PER01 <sup>2</sup>	Contact Function Code	IC	2	N/A	All
341	2120C	PER03 <sup>3</sup>	Communication Number Qualifier	TE	2	N/A	All
341	2120C	PER04	Benefit Related Entity Communication Number	N/A	10	Telephone Number (format AAABBBCCCC)	All
342	2120C	PER05	Communication Number Qualifier	UR	2	N/A	All
342	2120C	PER06	Benefit Related Entity Communication Number	N/A	1/50	Contract Website Address	All

<sup>&</sup>lt;sup>1</sup> The HETS 270/271 application returns only addresses that fall within the United States and its territories.
<sup>2</sup> The HETS 270/271 application does not return the PER segment when there is no Part D plan telephone number or website

address. <sup>3</sup> When the Part D plan has only a telephone number or only a website address, the HETS 270/271 application returns the telephone number or the website address data in the PER03 and PER04 elements.

Table 31 - MA Enrollment Data

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
291	2110C	EB01	Eligibility or Benefit Information	R	1	MA EB Loop	All
293	2110C	EB03	Service Type Code	30	2	N/A	All
298	2110C	EB04	Insurance Type Code	HM, HN, IN, PR, or PS	2	N/A	All
315	2110C	REF01	Reference Identification Qualifier	18	2	N/A	All
316	2110C	REF02	Subscriber Eligibility or Benefit Identifier	N/A	5 or 9	Contract Number and Plan Number separated by a space. If a Plan Number is unavailable only the Contract Number will be in this element.	All
317	2110C	DTP01	Date Time Qualifier	290	3	N/A	All
318	2110C	DTP02	Date Time Period Format Qualifier	D8 or RD8	2 or 3	N/A	All
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	8 or 17	MA Enrollment Date or MA Enrollment and Disenrollment Dates	All
323	2110C	MSG01	Free Form Message Text	N/A	1/264	"MCO Bill Option Code – (code value)". Code values returned are: A, B, C, 1 and 2.	All
330	2120C	NM101	Entity Identifier Code	PR or PRP	3	N/A	All

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
331	2120C	NM102	Entity Type Qualifier	2	1	N/A	All
331	2120C	NM103	Benefit Related Entity Last or Organization Name	N/A	1/35	Insurer Name	All
335	2120C	N301 <sup>1</sup>	Benefit Related Entity Address Line	N/A	1/55	MA Address Line 1	All
335	2120C	N302	Benefit Related Entity Address Line	N/A	1/55	MA Address Line 2	All
336	2120C	N401	Benefit Related Entity City Name	N/A	2/30	MA City	All
337	2120C	N402	Benefit Related Entity State Code	N/A	2	MA State Code	All
337	2120C	N403	Benefit Related Entity Postal Zone or Zip Code	N/A	5 or 9	MA ZIP Code	All
340	2120C	PER01 <sup>2</sup>	Contact Function Code	IC	2	N/A	All
341	2120C	PER03 <sup>3</sup>	Communication Number Qualifier	TE	2	N/A	All
341	2120C	PER04	Benefit Related Entity Communication Number	N/A	10	Telephone Number (format AAABBBCCCC)	All
342	2120C	PER05	Communication Number Qualifier	UR	2	N/A	All
342	2120C	PER06	Benefit Related Entity Communication Number	N/A	1/50	Contract Website Address	All

 $<sup>^{1}</sup>$  The HETS 270/271 application returns only addresses that fall within the United States and its territories.  $^{2}$  The HETS 270/271 application does not return the PER segment when there is no plan telephone number or website

address.

3 When the plan has only a telephone number or only a website address, the HETS 270/271 application returns the telephone number or the website address data in the PER03 and PER04 elements.

**Table 32 – MSP Enrollment Data** 

	Table 32 - MSF Ellionnent Data							
TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)	
291	2110C	EB01	Eligibility or Benefit Information	R	1	N/A	All	
293	2110C	EB03	Service Type Code	30	2	N/A	All	
298	2110C	EB04	Insurance Type Code	N/A	2	MSP Code: 12, 13, 14, 15, 16, 41, 42, 43, 47, or WC	All	
315	2110C	REF01	Reference Identification Qualifier	IG	2	N/A	All	
316	2110C	REF02	Subscriber Eligibility or Benefit Identifier	N/A	1/17	Policy Number	All	
317	2110C	DTP01	Date Time Qualifier	290	3	N/A	All	
318	2110C	DTP02	Date Time Period Format Qualifier	D8 or RD8	2 or 3	N/A	All	
318	2110C	DTP03	Eligibility or Benefit Date Time Period	N/A	8 or 17	MSP Effective Date or MSP Effective and Termination Dates	All	
330	2120C	NM101	Entity Identifier Code	PRP	3	N/A	All	
331	2120C	NM102	Entity Type Qualifier	2	1	N/A	All	
331	2120C	NM103	Benefit Related Entity Last or Organization Name	N/A	1/32	Insurer Name	All	
335	2120C	N301 <sup>1</sup>	Benefit Related Entity Address Line	N/A	1/32	MSP Address Line 1	All	
335	2120C	N302	Benefit Related Entity Address Line	N/A	1/32	MSP Address Line 2	All	
336	2120C	N401	Benefit Related Entity City Name	N/A	2/15	MSP City	All	

<sup>&</sup>lt;sup>1</sup> The HETS 270/271 application returns only addresses that fall within the United States and its territories.

TR3 Page #	Loop ID	Reference	X12 Implementation Name	Codes	Length	Notes/ Comments	270 Service Type Code (EQ01)
337	2120C	N402	Benefit Related Entity State Code	N/A	2	MSP State Code	All
337	2120C	N403	Benefit Related Entity Postal Zone or Zip Code	N/A	5 or 9	MSP ZIP Code	All

## Appendix A - Sample 270 Eligibility Request Transaction

This example includes the minimum required data elements for a HETS 270 transaction. Additional data may be provided but will not affect the 271 response.

```
□000000485□
ISA*00*
                 *00*
                               *ZZ*C123A456
                                                *ZZ*CMS
*110116*0734*^*00501*000005014*1*P*:~
GS*HS*T000000011*CMS*20110116*073411*5014*X*005010X279A1~
ST*270*00000001*005010X279A1~
BHT*0022*13*ALL*20110116*073411~
HL*1**20*1~
NM1*PR*2*CMS****PI*CMS~
HL*2*1*21*1~
NM1*80*2*TEST****XX*2223334444~
HL*3*2*22*0~
TRN*1*TEST-TEST*9TEST
NM1*IL*1*SMITH*MARY***MI*123456789A~
DMG*D8*19240901~
DTP*291*RD8*20110101-20110330~
EQ*30^AG^42^14^45~
SE*13*00000001~
GE*1*5014~
IEA*1*00005014~
```

### Appendix B - Sample 271 Eligibility Response Transaction

Not all of the information presented in this example will be present on every Medicare 271 response. This example is for illustrative purposes only and shows the various eligibility information that a 271 response may contain, including Part A, Part B, SNF, Hospital, Preventive, Smoking Cessation, Blood Deductible, Hospice, MSP, Home Health, Medicare Advantage, Part D, Inactive Periods, Rehabilitation, and Occupational, Physical, & Speech Therapies.

```
□0000003162□
                 *00*
ISA*00*
                                *ZZ*CMS
                                                   *ZZ*SUBMITTERID
*120101*0758*^*00501*1111111111*0*P*:~
GS*HB*CMS*SUBMITTERID*20120101*07580000*1*X*005010X279A1~
ST*271*0001*005010X279A1~
BHT*0022*11*TRANSA*20120101*07582355~
HL*1**20*1~
NM1*PR*2*CMS****PI*CMS~
PER*IC**UR*http://www.cms.gov/HETSHelp/*UR*http://www.cms.gov/center/provider.asp~
HL*2*1*21*1~
NM1*1P*2*IRNAME****XX*NPI~
HL*3*2*22*0~
TRN*2*TRACKNUM*ABCDEFGHIJ~
NM1*IL*1*LNAME*FNAME*MIDINIT***MI*HICN~
N3*ADDRESS LINE1*ADDRESS LINE2~
N4*CITY*ST*ZIPCODE~
DMG*D8*19200401*F~
DTP*307*D8*20120101~
EB*1**1^33^35^47^86^88^98^AL^MH^UC~
EB*1**30*MA~
DTP*291*D8*19850401~
EB*K**47*MA**33***LA*60~
EB*C**47*MA**29*1156~
EB*F**47*MA**29***DY*60~
EB*B**47*MA**29*289**DY*30~
EB*F**AG*MA**29***DY*20~
EB*B**AG*MA**29*144.5**DY*80~
EB*C**47*MA**29*0~
DTP*435*RD8*20110813-20110830~
EB*F**47*MA**29***DY*43~
DTP*435*RD8*20080813-20080830~
EB*B**47*MA**29*283**DY*30~
DTP*435*RD8*20110124-20110127~
EB*F**AG*MA**29***DY*0~
DTP*435*RD8*20100314-20100705~
EB*B**AG*MA**29*137.5**DY*5~
DTP*435*RD8*20100314-20100705~
EB*1**30*MB~
DTP*291*D8*19850401~
EB*C**96*MB**29*140~
DTP*292*RD8*20120101-20121231~
EB*D***MB*******HC | G0403~
DTP*348*D8*20090101~
EB*F**67*MB**29***P6*8~
```

```
EB*F**AD*MB**29*1880~
DTP*292*RD8*20120101-20121231~
EB*F**AE*MB**29*1880~
DTP*292*RD8*20120101-20121231~
EB*D**10***29***DB*3~
DTP*292*RD8*20110101-20111231~
EB*F**BF*MB**29***CA*36~
MSG*Professional~
EB*F**BF*MB**29***CA*36~
MSG*Technical~
EB*F**BG*MB*****99*0~
MSG*Professional~
EB*F**BG*MB****99*0~
MSG*Technical~
EB*F**BG*MB*****99*15~
MSG*Intensive Cardiac Rehabilitation - Professional~
EB*F**BG*MB****99*15~
MSG*Intensive Cardiac Rehabilitation - Technical~
EB*X**45*MA**26~
DTP*292*RD8*20100224-20100715~
MSG*Revocation Code - 1~
LS*2120~
NM1*1P*2*****XX*1234567890~
LE*2120~
EB*R**30*12~
REF*IG*POLICYNUMBER~
DTP*290*D8*19900101~
LS*2120~
NM1*PRP*2*ORGNAME~
N3*ADDRESSLINE1*ADDRESSLINE2~
N4*CITY*ST*ZIPCODE~
LE*2120~
EB*X**42*MB**26~
DTP*472*RD8*20101226-20110223~
DTP*193*D8*20101229~
DTP*194*D8*20110223~
LS*2120~
NM1*PR*2*ORGNAME****PI*CONTR~
NM1*1P*2*****XX*1234567890~
EB*X***MB*******HC | G0179~
DTP*193*D8*20101225~
EB*D**14*MB~
DTP*356*D8*20050126~
DTP*096*D8*20050828~
EB*R**30*IN~
REF*18*H0000 999~
DTP*290*D8*20110101~
MSG*MCO Bill Option Code - C~
LS*2120~
NM1*PRP*2*ORGNAME~
N3*ADDRESSLINE1*ADDRESSLINE2~
N4*CITY*ST*ZIPCODE~
PER*IC**TE* AAABBBCCCC *UR*www.website com~
LE*2120~
EB*R**88*OT~
```

```
REF*18*H0000 999~
DTP*292*D8*20110101~
LS*2120~
NM1*PRP*2*ORGNAME~
N3*ADDRESSLINE1*ADDRESSLINE2~
N4*CITY*ST*ZIPCODE~
PER*IC**TE* AAABBBCCCC *UR*www.website com~
LE*2120~
EB*6~
DTP*307*RD8*20100901-20100930~
SE*96*0001~
GE*1*1~
IEA*1*11111111~
```

# Appendix C – Acronyms

The acronyms in Table 33 are used in this document.

Table 33 - Acronyms

Acronym	Definition
ASC	Accredited Standards Committee
CMS	Centers for Medicare & Medicaid Services
DOB	Date of Birth
DOEBA	Date of Earliest Billing Activity
DOLBA	Date of Latest Billing Activity
EDI	Electronic Data Interchange
ESRD	End Stage Renal Disease
HCPCS	Healthcare Common Procedure Coding System
HETS	HIPAA Eligibility Transaction System
HICN	Health Insurance Claim Number
HIPAA	Health Insurance Portability and Accountability Act of 1996
HMO	Health Maintenance Organization
IP	Internet Protocol
MA	Medicare Advantage
MAC	Medicare Administrative Contractor
MCARE	Medicare Customer Assistance Regarding Eligibility
MSP	Medicare Secondary Payer
NPI	National Provider Identifier
POS	Point of Service
PPO	Preferred Provider Organization
RRB	Railroad Retirement Board
SNF	Skilled Nursing Facility
STC	Service Type Code
TPMS	Trading Partner Management System
TR3	ASC X12 270/271 Implementation Guide. Formally known
INJ	as the IG (Implementation Guide)

## **Appendix D – Revision History**

Table 34 provides a summary of changes made to this document.

**Table 34 – Document Revision History** 

Version	Date	Description of Changes
1-0	03/31/2009	Baseline Version
1-1	04/28/2009	R2009Q200 changes:
		Section 4.3 – Added information regarding socket connection closure after 5 seconds has elapsed since the last transaction.
		Section 7.6 and Table 16 – Updated "co-insurance" to "co-payment" for Part A Hospital and SNF.  Section 7.9 – Added HCPCS code 90669 for Pneumococcal (PPV) category.
		Section 7.13 – Added bullet item to address the change that all hospice periods that intersect the requested date(s) of service will be returned.
1-2	09/10/2009	R2009Q400 changes:
		Table 27 – Added "WC" to list of values for MSP Insurance Type Code.

Vorcion	Data	Description of Changes
Version 1-3	<b>Date</b> 11/18/2009	Description of Changes 5010 Changes:
1-3	11/10/2009	Updated all references of "004010X092A1" to "005010X279".
		Updated all IG page numbers and references.
		Updated all AAA error codes and messages.
		Updated all example segments to include EB03 = 30 when EB01 = 1 or 6.
		Replaced all references to "997" errors with "999".
		Section 1.1 – Updated link for the IG.
		Section 1.4.4 – Added section to direct users to Appendix D for a list of changes to accommodate 5010.
		Section 4.3 – Updated Figure 2 with 5010 example.
		Section 7.1 – Updated Table 4 to include the Repetition Separator; changed Sub Element Separator to
		Component Element Separator.
		Section 7.2 – Included STCs specifically supported by the HETS 270/271 application as well as those
		mandated by the IG.
		Section 7.3 – Updated to include Table 5 describing available search options.
		Section 7.4 – Updated dates in the example associated with Table 6.
		Section 7.5 – Clarified reasons when Insurance Type Code (EB04) will be omitted.
		Section 7.7 – Included new EB values; updated example segments.
		Section 7.8 – Included applicable STCs under the first bullet.
		Section 7.9 – Included applicable STC in the first bullet.
		Section 7.10 – Included applicable STC in the first bullet.
		Section 7.11 – Included applicable STC in the first bullet.
		Section 7.13 – Removed example segments for Hospice Care; Facility information will be returned with
		Hospice Care data.
		Section 7.14 – Included applicable STC in the first bullet.
		Section 7.15 – Updated example segments to include Contract Website Address.
		Section 7.16 – Updated example segments to include Contract Website Address.
		Section 8.2 – Replaced references to "997" with "999".
		Section 8.3 – Added clarification to the second paragraph regarding the return of data element(s) that cause the AAA error; updated AAA error codes and messages.
		Section 8.4 – Updated Proprietary Error Messages.
		Section 6.4 – Opdated Proprietary Error Message with TA1 Interchange Acknowledgement.
		Tables 10-29 – Replaced "X12 Element Name" header with "X12 Implementation Name"; updated all
		element names based on the Implementation Names in the IG.
		Table 12 – Updated Notes/Comments based on search option criteria; updated Length column for
		Subscriber Primary Identifier to 7/12.
		Table 13 – Added rows for elements PER03, PER04, PER05 and PER06
		Table 16 – Updated the footnote associated with Insurance Type Code (EB04) to include the reasons
		when it would be omitted.
		Table 17 – Added new table to explain how benefit coverage data will be returned for the mandated
		STCs.
		Table 19 – Updated 270 Service Type Code (EQ01) column to "42" for all elements; updated Codes and
		Notes/Comments columns for DTP01; updated Codes, Length and Notes/Comments columns for DTP02;
		Added rows for elements NM101, NM108 and NM109 elements for the NPI.
		Table 20 – Updated 270 Service Type Code (EQ01) column to "1, 14, 15, 30, 33, 35, 42, 45, 86, 88, 98,
		AL, MH, UC" for all elements.
		Table 21 – Updated 270 Service Type Code (EQ01) column to "30" for all elements.
		Table 22 – Updated 270 Service Type Code (EQ01) column to "30" for all elements.
		Table 23 – Updated 270 Service Type Code (EQ01) column to "30" for all elements.
		Table 25 – Updated 270 Service Type Code (EQ01) column to "45" for all elements; updated Codes
		column for NM108; updated Length and Notes/Comments columns for NM109.
		Table 26 – Updated 270 Service Type Code (EQ01) column to "30" for all elements.
		Table 27 – Added rows for elements PER05 and PER06.
		Table 28 – Added rows for elements PER05 and PER06.
		Appendix A – Included new 270 Sample Eligibility Request Transaction.
		Appendix B – Included new 271 Sample Eligibility Response Transaction.

Version	Date	Description of Changes
1-4	5/12/2010	Changes include:
	0, 12, 2010	Updated CMS website addresses to the new standard (cms.gov instead of cms.hhs.gov).
		Section 4.2.1 – Updated date and time for system maintenance.
		Section 7.11 – Added bullet regarding the use of EB03 = "AE"; updated example segments.
		Section 7.12 – Updated example segments with qualifier and removed message segments. Also updated
		Table 24 to include these changes.
		Table 7 – Added AAA Error Code "56".
		Table 8 – Updated length of Proprietary Error Message Text Description
		Table 9 – Updated Proprietary Error Message Codes and Descriptions.
		Table 15 – Updated Length column for elements NM103 and NM104.
		Table 23 – Updated for element EB03.
		Table 26 – Updated Codes column for element EB01.
		Added note to tables 15, 27, 28, and 29 regarding address information returned.
		Appendix B – Updated Sample 271 Eligibility Response Transaction with changes associated with
		Therapy Capitation and Blood Deductible data.
1-5	6/8/2010	Changes include:
		Table 7 – Updated with new AAA error codes and descriptions.
1-6	12/10/2010	Changes include:
		Section 5 – Updated MCARE website
		Section 7.1 – Updated 2nd bullet with correct references
		Section 7.3 – Updated 5th bullet regarding Medicare Beneficiary's gender code and search options
		Section 7.5 – Updated examples for Inactive Due to Date of Death and Entitled but Inactive Due to
		Incarceration, Deportation or Alien Status
		Section 7.6 – Updated examples with co-payment explanations
		Section 7.7 – Added bullet for Insurance Type Codes "MA" and "MB"; added example for Insurance Type
		Code "MB"
		Section 7.9 – Added HCPCS code G9143; changed Diabetes Self-Management to Diabetes Screening
		Tests; updated examples
		Section 7.13 – Added bullet for additional Hospice verbiage
		Section 7.16 – Added bullet for explanation of MCO Bill Option Code and added element to the example
		Table 7 – updated reject reason code descriptions for AAA03 = 43 and AAA03 = 73.
		Table 8 – Updated Transaction Reference Number and Response Code data elements
		Table 13 – Added rows for NM101, NM102, NM103 and NM108
		Table 17 – Removed EB02=IND and updated for benefit coverage status = "1" Table 19 – Added Insurance Type Code "MB" and Note/Comment; added row for NM102
		Tables 27 and 28 – Added footnotes for PER03 and PER04
		Table 28 – Added row for MSG01
		Appendix A 270 Example – Changed ISA06 and GS02 to "C123A456"
		Appendix A 276 Example – Changed ISA08 and GS03 to "C123A456", changed time in GS05 to
		17050000; corrected Information Source loop 2100A PER04 website address; removed "IND" from loop
		2110C EB02 in the Benefit Coverage for Mandated STCs; added MSG*MCO Bill Option Code – C~ to
		MCO 2110C loop
		Appendix C – Added ERSD to list of acronyms
2-0	03/21/2011	Changes include:
	00/21/2011	Updated all references of "005010X279" to "005010X279A1".
		Updated all references of "5010" to "5010A1".
		Removed EB02=IND from all examples.
		Section 4.3 – Updated with CMS Best Practices for HETS Connections and updated Figure 2 for 5010A1.
		Section 7.9 – Added HCPCS code 90670.
		Section 7.10 and Table 22 – Added tobacco cessation counseling.
		Table 19 – Updated values for NM103 and NM109.
2-1	06/13/2011	Changes include:
		Section 7.7 – Updated "NPI" to "Provider NPI" to be consistent with other examples throughout the
		document.
		Section 7.9 - Added HCPCS codes G0438 and G0439.

Version	Date	Description of Changes
3-0	7/18/2011	Changes include:
		Section 7 and Section 10 – Added sub-sections and corresponding tables for Pulmonary Rehabilitation,
		Cardiac Rehabilitation, and Intensive Cardiac Rehabilitation.
		Section 7.3 – Removed bullet referencing gender code.
		Table 7 – Removed AAA error code regarding gender mismatch.
		Section 7.7 and Table 19 – Added information and updated examples for Home Health Certification and
		Home Health Recertification.
		Section 7.15 and Table 28 – Updated to include Hospice Revocation Code.
4-0	10/25/2011	Changes include:
		Section 6.1 and 6.2- reworded Require to expect
		Section 7.9- Removed 90670
		Section 8.1 and section 8.3 table 7 – added 5010A1 version response.
4-1	10/27/2011	Section 7.9 Added 90670 back
4-2	01/19/2012	Changes include:
		Sections 2.1 and 5 – Updated MCARE hours of operation
		Table 6- Updated the example
		Moved Section 6.4 to Section 10.1.
		Section 7.1.2 and 7.1.3 - Updated the 271 examples.
		Moved NM101 and NM108 from table 10 to table 13.
		Section 10.1 – Updated wording
		Table 13 –Corrected lengths for Per04 and Per06
		Table 15 – Added TRN0 and corrected NM105.
		Switched table 16 and 17 to match 271 example
		Table 19 – Corrected codes for EB13
		Table 24, 25, 26 – Update EB01 and added MSG01.
	2/2/22/2	Appendix A and B -Updated 270/271 examples
5-0	6/5/2012	Changes include:
		Capitalizing 'Companion Guide' and Updating 'IG' to be 'TR3' in the entire document.
		Preface- Updated the wording
		Section 1.3, 2.2, 4.2.1, 7.17, 7.18- Updated the URL for HETSHelp
		Section 4.2.1- Updated the TPA form name
		Section 7.2 – Updated the bullet on dependent level data
		Section 7.5- Updated the example for Part A, B and Incarceration from using DTP* 291 to be DTP* 307
		Section 7.9- Added new Preventive codes G0442-G0447
		Section 8- Updated the Section title and moved the wording in 8.5 up to the beginning. Added verbiage
		for a TA1 for unsupported version.