# Pediatric Nutrition Surveillance 2010 Report

This report summarizes selected data on child health and nutrition indicators received from states, U.S. territories, and Indian Tribal Organizations that contributed to the Centers for Disease Control and Prevention's Pediatric Nutrition Surveillance System.

This report was developed by CDC's Division of Nutrition, Physical Activity, and Obesity in the National Center for Chronic Disease Prevention and Health Promotion.

# **Suggested Citation**

Dalenius K, Borland E, Smith B., Polhamus B., Grummer-Strawn L. *Pediatric Nutrition Surveillance 2010 Report.* Atlanta: U.S. Department of Health and Human Services, Centers for Disease Control and Prevention; 2012.

# **Acknowledgments**

We gratefully acknowledge and thank all contributors to the Pediatric Nutrition Surveillance Systems (PedNSS). The efforts of state, territorial, and Indian Tribal Organization surveillance coordinators; informatics staff; and local clinic staff to collect data and use nutrition surveillance systems make the national PedNSS possible.

This report is available online at http://www.cdc.gov/pednss.

#### For more information, contact

Division of Nutrition, Physical Activity, and Obesity National Center for Chronic Disease Prevention and Health Promotion Centers for Disease Control and Prevention

4770 Buford Highway NE, Mail Stop K-25 Atlanta, GA 30341-3717 800-CDC-INFO (232-4636) TTY: 888-232-6348

# Pediatric Nutrition Surveillance

The Pediatric Nutrition Surveillance System (PedNSS) is a public health surveillance system that monitors the nutritional status of low-income children in federally funded maternal and child health programs. Data on birthweight, anemia, breastfeeding, short stature, underweight, overweight, and obesity are collected for children who attend public health clinics for routine care, nutrition education, and supplemental food.

The goal of the PedNSS is to collect, analyze, and disseminate surveillance data to guide public health policy and action. PedNSS information is used to set public health priorities and to plan, implement, and evaluate nutrition programs.

Data are collected at the clinic level, aggregated at the state level, and then submitted to the Centers for Disease Control and Prevention (CDC) for analysis. A national nutrition surveillance report is produced, and an additional surveillance report is produced for each contributor. A *contributor* is defined as a state, U.S. territory, or Indian Tribal Organization (ITO).

In 2010, a total of 55 contributors, including 46 states, the District of Columbia, Puerto Rico, the U.S. Virgin Islands, and 6 ITOs, participated in the PedNSS (Figure 1). These contributors submitted data for nearly 9 million children from birth to age 4 years, which is nearly 4 million more children than in 2001. This gain is due to increases both in the number of contributors to the PedNSS and in the number of children reported by each contributor.

Figure 1. This is a map of the United States indicating contributors to PedNSS in 2010. Contributors include Alabama, Arizona, Arkansas, California, Colorado, Connecticut, Florida, Georgia, Hawaii, Idaho, Illinois, Indiana, Iowa, Kansas, Kentucky, Louisiana, Maine, Maryland, Massachusetts, Michigan, Minnesota, Mississippi, Missouri, Montana, Nebraska, Nevada, New Hampshire, New Jersey, New Mexico, New York, North Carolina, North Dakota, Ohio, Oregon, Pennsylvania, Rhode Island, South Carolina, South Dakota, Tennessee, Texas, Utah, Vermont, Virginia, Washington, West Virginia and Wisconsin. Contributors not shown on the map include the District of Columbia, Puerto Rico, the U.S. Virgin Islands, and the following Indian Tribal Organizations: Cheyenne River Sioux (SD), Inter Tribal Council of Arizona, Navajo Nation (AZ), Rosebud Sioux (SD), Standing Rock Sioux (ND), and Three Affiliated Tribes (ND).

Fluctuations in the number of contributors or the demographic characteristics of the contributors' populations can affect trends. The number of PedNSS contributors differs slightly from year to year because some contributors did not provide data every year during the 10-year period from 2001 through 2010 (see Table 1at the end of this report).

Data for the 2010 PedNSS were collected from children enrolled in federally funded programs that serve low-income children. These programs include the Special Supplemental Nutrition Program for Women, Infants, and Children (WIC) (87.5%) and other programs (12.5%), such as the Early and Periodic Screening, Diagnosis, and Treatment program and the Maternal and Child Health Bureau Title V program. This report summarizes 2010 data and highlights data trends during 2001–2010.

# **Demographic Characteristics**

Of the children in the 2010 PedNSS, 39.7% were Hispanic, 32.5% were non-Hispanic white, 19.1% were non-Hispanic black, 2.5% were Asian or Pacific Islander, 0.9% were American Indian or Alaska Native, and 5.2% were of multiple or unspecified races and ethnicities. From 2001 through 2010, the proportion of Hispanic children in the PedNSS increased from 28.5% to 39.7%. During the same period, the proportion of non-Hispanic white and non-Hispanic black children declined.

This demographic shift should be considered when interpreting PedNSS trends. Most children in the 2010 PedNSS were younger than age 2 years (55.8%); of those, 33.7% were younger than age 1 year and 22.1% were aged 12–23 months. The remaining children, 44.2%, were aged 2–4 years. The proportion of children aged 2–4 years increased slightly from 2001 (40.0%) through 2010 (44.2%), while the proportion of children younger than age 12 months decreased.

# **Pediatric Health Indicators**

# Low Birthweight

Low birthweight (<2,500 grams) is an important determinant of neonatal and postneonatal mortality. Low-birthweight infants who survive are at increased risk for health problems that include neurodevelopmental disabilities and respiratory disorders. Of the infants in the 2010 PedNSS, 9.0% had low birthweights, compared with 8.2% of all U.S. infants.

In the 2010 PedNSS, the prevalence of low birthweight was higher for black infants (13.2%) than for white (8.5%), Asian or Pacific Islander (8.9%), American Indian or Alaska Native (8.2%), or Hispanic (7.1%) infants. *Healthy People 2010* objective 16-10a proposes reducing low birthweight to no more than 5% of all live births.<sup>4</sup> The overall prevalence of low birthweight remained stable from 2001 (9.0%) through 2010 (9.0%) (Figure 2).

Figure 2. This is a line graph showing trends in the prevalence of low birthweight by race and ethnicity. Low birthweight is defined as birthweight <2,500 grams, among infants born during the reporting period. Healthy People 2010 proposes reducing low birthweight to 5% of live births. Multiple races is defined as persons who identify themselves as belonging to more than one racial group. This term was added to the PedNSS In 2004 and this report is the first to include trend data for this category. Data for this table came from 2010 National PedNSS Table 18D and is available at http://www.cdc.gov/pednss/pednss\_tables/tables\_numeric.htm.

	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010
White, Non-	8.4	8.4	8.6	8.8	9.1	8.9	8.7	8.6	8.5	8.5
Hispanic										
Black, Non-	12.7	12.6	12.9	13.1	13.6	13.5	13.4	13.1	13.2	13.2
Hispanic										
Hispanic	6.7	7.1	7.3	7.7	7.4	7.2	7.3	7.4	7.0	7.1
American Indian/	7.3	6.8	7.4	7.9	7.9	8.1	7.9	7.8	8.0	8.2
Alaska Native										
Asian/Pacific	8.3	0.8	8.3	8.4	8.5	8.3	8.1	8.3	8.3	8.9
Islander										
Multiple Races	N/A	N/A	N/A	8.8	9.6	9.3	9.3	8.9	9.2	9.2
Total	9.0	9.0	9.0	9.3	9.4	9.2	9.1	9.0	8.9	9.0

# High Birthweight

High birthweight (>4,000 grams) puts infants at increased risk for death and for birth injuries such as shoulder dystocia.<sup>5</sup> In the 2010 PedNSS, 6.3% of infants had high birthweights, compared with 8.0% in 2001. The prevalence was lower than in 2008 (7.6%), the most recent U.S. rate available.<sup>6</sup>

In 2010, the prevalence of high birthweight was higher for American Indian or Alaska Native (8.5%) infants than for white (7.5%), Hispanic (6.6%), Asian or Pacific Islander (4.5%), or black (3.9%) infants. The largest absolute decreases in high birthweight during 2001–2010 occurred among American Indian or Alaska Native (2.4%) infants.

# Breastfeeding

The nutritional, immunologic, and economic advantages of breastfeeding are well recognized. In the 2010 PedNSS, 63.2% of infants were ever breastfed, 25.1% were breastfed for at least 6 months, and 16.9% were breastfed for at least 12 months.\*

The 2010 PedNSS population failed to meet *Healthy People 2010* objectives 16-19a–16-19c, which are to increase the proportion of infants ever breastfed to 75%, the proportion of infants breastfed at 6 months to 50%, and the proportion of infants breastfed at 1 year to 25%.<sup>4</sup>

Among PedNSS contributors, Colorado, Hawaii, Idaho, Montana, the Navajo Nation, New Mexico, New York, Oregon, Texas, the U.S. Virgin Islands, Utah, Vermont, and Washington met the *Healthy People 2010* objective for ever breastfeeding, and several other contributors came close (see Table 2 at the end of this report).

Nationally representative provisional data from the 2008 National Immunization Survey (NIS) indicate that 74.6% of all U.S. infants were ever breastfed, 44.3% were breastfed for 6 months, and 23.8% were breastfed for 12 months.<sup>8</sup>

From 2001 through 2010, the absolute increase in the prevalence of breastfeeding initiation for infants in the PedNSS was 13.1%. The breastfeeding initiation rate was 50.1% in 2001. Improved breastfeeding rates were evident among all racial and ethnic groups (Figure 3). In 2010, Hispanic infants had the highest prevalence of breastfeeding initiation (76.1%), and black infants had the lowest prevalence (50.6%). Data from the NIS indicate that the proportion of infants ever breastfed in the United States increased from 70.9% in 2000 to 74.6% in 2008.

Figure 3. This is a line graph showing trends in percentage of infants ever breastfed by race and ethnicity among infants born during the reporting period. Healthy People 2010 proposes increasing the proportion of mothers who breastfeed their babies in the early postpartum period to 75%. Multiple races is defined as persons who identify themselves as belonging to more than one racial group. This term was added to the PedNSS In 2004 and this report is the first to include trend data for this category. Data for this table came from 2010 National PedNSS Table 19D and is available at http://www.cdc.gov/pednss/pednss\_tables/tables\_numeric.htm.

<sup>\*</sup> Infants born during the reporting period before their mothers were surveyed are included in the ever breastfed analysis. Only children who had turned 6 months old during the reporting period are included in the breastfed at least 6 months analysis. Only children who had turned 12 months old during the reporting period are included in the breastfed at least 12 months analysis.

	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010
White, Non-	50.6	51.0	52.6	53.8	55.4	56.6	55.9	57.7	58.5	60.2
Hispanic										
Black, Non-	36.1	40.0	41.6	42.6	46.4	47.3	46.9	49.7	48.8	50.6
Hispanic										
Hispanic	68.4	67.5	68.0	68.7	71.1	72.9	72.4	73.8	74.4	76.1
American	52.2	58.6	55.7	62.4	61.5	65.8	63.1	64.3	63.8	65.9
Indian/Alaska										
Native										
Asian/Pacific	55.3	51.0	53.6	58.8	59.4	59.7	60.4	63.5	65.4	68.1
Islander										
Multiple	N/A	N/A	N/A	50.8	57.2	58.5	58.8	59.9	58.8	60.3
Races										
Total	50.1	52.5	55.1	56.1	58.5	60.1	59.8	61.7	61.7	63.2

The proportion of infants who were breastfed for at least 6 months was 21.5% in 2001 and 25.1% in 2010, an absolute increase of 3.6%. Increases in the prevalence of infants being breastfed for at least 6 months were evident among all racial and ethnic groups. Hispanic infants had the highest prevalence of breastfeeding for at least 6 months (35.1%), and black infants had the lowest prevalence (18.0%). Data from the NIS indicate that the proportion of infants who were breastfed for at least 6 months in the United States increased from 34.2% in 2001 to 44.3% in 2008.

In 2004, the PedNSS began monitoring *exclusive breastfeeding*, defined as an infant receiving only breast milk. In 2010, a total of 28 PedNSS contributors<sup>†</sup> (51.0%) reported this supplementary data, which showed that 10.7% of infants were exclusively breastfed for at least 3 months.

Preliminary data from the NIS indicate that 35.0% of infants in the United States were exclusively breastfed for at least 3 months in 2008. Exclusive breastfeeding has a strong protective effect against lower respiratory tract infections, middle ear infections, eczema, and childhood obesity.<sup>9</sup>

#### Anemia

Anemia (low hemoglobin or low hematocrit)<sup>‡</sup> is an indicator of iron deficiency, which is associated with developmental delays and behavioral problems in children.<sup>10–12</sup> In the 2010 PedNSS, the prevalence of anemia was 14.6%. The highest prevalence was among children aged 6–23 months (18.1%) and those aged 12–17 months (18.2%). The lowest prevalence was among children aged 3–4 years (10.6%).

The overall prevalence of anemia among children in the PedNSS increased slightly, from 13.4% in 2001 to 14.6% in 2010. During this 10-year period, the overall prevalence of anemia declined to 13.0% in 2002 but increased in subsequent years.

<sup>&</sup>lt;sup>†</sup>Contributors of supplementary breastfeeding data include Arkansas, Florida, Idaho, Illinois, Indiana, Iowa, Kansas, Louisiana, Maryland, Massachusetts, Michigan, Minnesota, Missouri, Montana, New Hampshire, New York, North Dakota, Ohio, Oregon, Rhode Island, U.S. Virgin Islands, Virginia, Washington, West Virginia, Washington, West Virginia, Wisconsin, the District of Columbia, and the following ITO's: the Inter Tribal Council of Arizona and the Navajo Nation (AZ).

The prevalence of anemia varied among racial and ethnic groups in the PedNSS. In 2010, the highest prevalence was among black children (22.5%) and the lowest prevalence was among white children (11.2%). From 2001 through 2010, the largest increase in anemia was among black children (2.9%). The prevalence of anemia declined slightly among Asian or Pacific Islander children (Figure 4).

Figure 4: This is a line graph showing trends in prevalence of anemia among children aged <5 years by race and ethnicity. Anemia is defined as Hemoglobin or Hematocrit <5th percentile, CDC MMWR vol. 47 (No.RR-3), 1998. Data for this table came from 2010 National PedNSS Table 18D and is available at http://www.cdc.gov/pednss/pednss\_tables/tables\_numeric.htm.

	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010
White, Non-	10.4	10.1	10.5	10.8	10.8	11.1	11.9	11.4	11.4	11.2
Hispanic										
Black, Non-	19.6	19.1	19.1	19.4	20.0	21.0	22.8	22.6	23.1	22.5
Hispanic										
Hispanic	13.0	12.5	13.3	13.1	13.2	13.5	14.0	14.0	14.0	13.6
American	9.9	10.0	10.9	11.5	10.7	11.5	12.4	12.2	13.1	12.2
Indian/Alaska										
Native										
Asian/Pacific	12.8	12.4	12.6	12.7	12.4	12.5	13.0	13.6	13.7	13.3
Islander										
Multiple	N/A	N/A	N/A	17.3	14.0	15.0	15.7	15.3	15.1	14.7
Races										
Total	13.4	13.0	13.4	13.5	13.6	14.0	15.0	14.8	14.9	14.6

#### Short Stature

Short stature<sup>§</sup> (low length or height for a child's age) may reflect the long-term health and nutritional status of a child or a population.<sup>13</sup> Although short stature can be associated with short parental stature or low birthweight,<sup>13</sup> it also can result from growth retardation because of chronic malnutrition, recurrent illness, or both.

In the 2010 PedNSS, 5.9% of children from birth to age 4 years were of short stature, compared with 3.7% of all U.S. children of the same age.<sup>14</sup>

Compared with the general population, the prevalence of short stature was higher in the PedNSS population, which may reflect the nutritional risk of children participating in the WIC program. The prevalence of short stature in the 2010 PedNSS was above both the expected level (5%) and the *Healthy People 2010* objective 19-4 of 5% for low-income children from birth to age 4 years. Fifteen contributors achieved the *Healthy People 2010* objective of 5% in 2010 (see Table 2 at the end of this report).

<sup>§</sup> Based on sex-specific percentiles from the 2000 CDC growth chart for the United States. For children younger than age 2 years, short stature is defined as <5th percentile of length-for-age. For children aged 2-4 years, short stature is defined as <5th percentile height-for-age.

The prevalence of short stature among children in the PedNSS decreased slightly from 2001 (6.3%) through 2010 (5.9%). Some variation was evident among racial and ethnic groups. Short stature remained constant among Hispanic children and decreased among all other racial and ethnic groups (Figure 5). In 2010, the highest prevalence of short stature was among black infants younger than age 1 year (10.7%), which may reflect the high prevalence of low birthweight among this group (data not shown).

Figure 5: This is a line graph showing trends in prevalence of short stature among children aged <5 years by race and ethnicity. Short stature is defined as < 5th percentile length or height-for-age, CDC Growth Charts, 2000. Healthy PEople 2010 proposes reducing short stature among low-income children aged <5 years to 5%. Multiple races is defined as persons who identify themselves as belonging to more than one racial group. This term was added to the PedNSS In 2004 and this report is the first to include trend data for this category. Data for this table came from 2010 National PedNSS Table 18D and is available at

http://www.cdc.gov/pednss/pednss\_tables/tables\_numeric.htm.

	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010
White, Non-	6.3	6.3	6.5	6.6	6.6	6.5	6.4	6.2	6.2	6.1
Hispanic										
Black, Non-	7.5	7.0	7.1	6.9	6.9	7.1	7.0	6.6	6.6	6.3
Hispanic										
Hispanic	5.5	6.0	6.0	6.0	5.9	5.6	5.9	5.5	5.6	5.5
American	5.2	5.1	5.1	5.0	5.1	5.0	5.0	4.7	4.7	4.7
Indian/Alaska										
Native										
Asian/Pacific	7.0	6.4	6.0	6.7	6.6	6.4	6.3	6.3	6.3	6.4
Islander										
Multiple	N/A	N/A	N/A	6.2	6.5	5.9	5.9	5.7	5.6	5.6
Races										
Total	6.3	6.3	6.4	6.4	6.4	6.4	6.2	6.0	6.0	5.9

# Underweight

Data from contributors on underweight<sup>1</sup> (low weight-for-length or body mass index\*\* [BMI] for age) in children from birth to age 4 years indicate that acute malnutrition was not a public health problem in the PedNSS population. In 2010, the prevalence of underweight (4.5%) was less than the expected level (5%). The prevalence of underweight for all U.S. children in this age group was 3.4%.<sup>14</sup>

The highest prevalence of underweight in the PedNSS was among Asian or Pacific Islander (6.3%) and black (5.9%) children. Black infants younger than age 1 year had an underweight rate of 7.9%, which may reflect the high rate of low birthweight in this group. The overall prevalence of underweight among children in the PedNSS decreased from 5.4% in 2001 to 4.5% in 2010.

<sup>&</sup>lt;sup>1</sup>Based on sex-specific percentiles from the 2000 CDC growth chart for the United States. For children younger than age 2 years, underweight is defined as <5th percentile of weight-for-length. For children aged 2 years or older, underweight is defined as <5th percentile for BMI-for-age.

<sup>\*\*</sup> BMI is calculated as follows: Weight (kg) / Stature (cm) x 10,000 or Weight (lb)/ Stature (in) x703.

# Overweight and Obesity

Overweight<sup>††</sup> and obesity<sup>‡‡</sup> in young children have increased in recent decades, and the associated health consequences call for preventive efforts. <sup>15</sup> The Expert Committee on the Prevention, Assessment, and Treatment of Child and Adolescent Overweight and Obesity recommends the use of two cutoff points to screen for overweight and obesity in children aged 2 years or older. <sup>16</sup> Children with a BMI-for-age at or above the 95th percentile are considered obese, and those with a BMI-for-age in the 85th–95th percentile are considered overweight. <sup>16</sup>

In the 2010 PedNSS, the prevalence of obesity among children aged 2–4 years was 14.4%, compared with 10.4% for all U.S. children aged 2–5 years in 2007 through 2008.<sup>17</sup> In the PedNSS, the highest prevalence of obesity was among American Indian or Alaska Native (21.1%) and Hispanic (17.6%) children. The lowest prevalence was among white (12.1%), black (11.6%), and Asian or Pacific Islander (11.3%) children (Figure 6).

Figure 6: This is a vertical stacked bar graph that shows prevalence of obesity and overweight among children aged 2 to 5 years by race and ethnicity for 2010. Obesity is defined as ≥ 95th percentile BMI-for-age; overweight is defined as >85th to <95th percentile BMI-for-age, CDC Growth Charts, 2000. Multiple races is defined as persons who identify themselves as belonging to more than one racial group. This term was added to the PedNSS In 2004 and this report is the first to include trend data for this category. Data for this table came from 2010 National PedNSS Table 8D and is available at http://www.cdc.gov/pednss/pednss\_tables/tables\_numeric.htm.

	White,	Black,	Hispanic	American	Asian	Multiple	Total
	non-	non-		Indian/		Races	
	Hispanic	Hispanic		Alaska Native			
Obese	12.1	11.6	17.6	21.1	11.3	12.8	14.4
Overweight	15.7	14.1	17.4	20.1	13.6	15.7	16.1

The prevalence of obesity among children aged 2–4 years increased from 13.1% in 2001 to 14.4% in 2010 (Figure 7). During this 10-year period, obesity increased among all U.S. racial and ethnic groups except Asians or Pacific Islanders.

<sup>&</sup>lt;sup>††</sup>Based on sex-specific percentiles from the 2000 CDC growth chart for the United States. For children aged 2 years or older, overweight is defined as the 85th - 95th percentile of BMI-for-age.

<sup>&</sup>lt;sup>‡‡</sup>Based on sex-specific percentiles from the 2000 CDC growth chart for the United States. For children aged 2 years or older, obesity is defined as ≥95th percentile of BMI-for-age.

<sup>\*\*</sup> BMI is calculated as follows: Weight (kg) / Stature (cm) x 10,000 or Weight (lb)/ Stature (in) x703.

Figure 7: This is a line graph showing trends in prevalence of obesity\* among children aged 2 to 5 years by race and ethnicity. Obesity is defined as  $\geq$  95th percentile BMI-forage, CDC Growth Charts, 2000. Multiple races is defined as persons who identify themselves as belonging to more than one racial group. This term was added to the PedNSS In 2004 and this report is the first to include trend data for this category. Data for this table came from 2010 National PedNSS Table 18D and is available at http://www.cdc.gov/pednss/pednss tables/tables numeric.htm.

	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010
White, Non-	11.5	11.8	12.2	12.6	12.4	12.3	12.4	12.5	12.3	12.1
Hispanic										
Black, Non-	11.0	11.9	12.1	12.2	12.0	11.9	11.9	11.9	11.9	11.6
Hispanic										
Hispanic	17.0	19.0	18.4	18.2	18.0	18.0	18.2	17.9	17.9	17.6
American	17.1	17.5	17.7	19.0	19.0	19.4	19.5	20.2	20.7	21.1
Indian/Alaska										
Native										
Asian/Pacific	13.4	13.4	13.0	12.5	12.3	12.4	11.9	12.2	11.9	11.3
Islander										
Multiple	N/A	N/A	N/A	15.1	13.0	13.0	12.6	12.9	12.8	12.8
Races										
Total	13.1	14.3	14.7	14.8	14.7	14.8	14.9	14.6	14.7	14.4

However, overall obesity rates were stable during 2003—2009, and this trend was observed among all racial and ethnic groups except American Indians or Alaska Natives. Obesity prevalence also declined in the past year, from 14.7% in 2009 to 14.4% in 2010. The recent stability of PedNSS obesity rates has been previously reported. Although these results suggest overall progress in obesity prevention among this subset of low-income, preschool-aged children, results should be confirmed through additional research using other datasets. Factors affecting enrollment of children in public health programs that provide data to the PedNSS also need to be better understood.

Among all contributors, only Colorado, Hawaii, Idaho, New Mexico, Utah, and the U.S. Virgin Islands had a prevalence of obesity less than 12%, and 11 contributors had a prevalence of 16% or higher (Figure 8).

Figure 8: This is a map of the United States with states showing the prevalence of obesity among children aged 2 to 5 years by contributor. Obesity is defined as ≥ 95th percentile BMI-for-age, CDC Growth Charts, 2000. Five states, Colorado, Hawaii, Idaho, New Mexico, Utah and the U.S. Virgin Islands had a prevalence of obesity less than 12%. States with a prevalence of obesity from 12% up to 13.9% include the District of Columbia, Florida, Georgia, Kansas, Louisiana, Michigan, Minnesota, Mississippi, Missouri, Montana, Nebraska, Nevada, Ohio, Pennsylvania, South Carolina, Vermont, and West Virginia. Contributors with a prevalence of 14.0% to 15.9% include Alabama, Arizona, Arkansas, Connecticut, Illinois, Indiana, Maine, Maryland, New Hampshire, New York, North Carolina, North Dakota, Oregon, Rhode Island, Tennessee, Texas, Washington and Wisconsin. Contributors with a prevalence of overweight from 16% or higher include California, Massachusetts, New Jersey, South Dakota, and the following Indian Tribal Organizations and U.S. territories: Cheyenne River Sioux Tribe (SD), Inter-Tribal Council of Arizona, Navajo Nation, Rosebud Sioux (SD), Standing Rock Sioux (ND), and Three Affiliated Tribes (ND). States with no data include Alaska, and

Delaware, Oklahoma and Wyoming. Data for this map came from 2010 National PedNSS Table 6D and is available at

http://www.cdc.gov/pednss/pednss\_tables/tables\_numeric.htm.

Although the map shows no clear geographic pattern of obesity prevalence, six ITOs that participated in the PedNSS were among those contributors with the highest prevalence. No contributor had a prevalence at or less than the expected level of 5% (see Table 2 at the end of this report).

# **Pediatric Behavioral Indicators**

# **Television Viewing**

To prevent obesity and a variety of other problems during childhood, the American Academy of Pediatrics (AAP) recommends that parents limit the amount of time that children spend watching television or other media to no more than 1–2 hours per day for children aged 2 years or older. AAP also discourages exposure to any television for infants and children younger than age 2 years.<sup>19</sup>

In 2004, the PedNSS began monitoring the proportion of children from birth to age 4 years who view 2 hours or less of television (including videotapes and DVDs) per day. Mothers of children in this age range report data on their children's television viewing.

In 2010, a total of 24 PedNSS contributors (44%) reported supplementary television viewing data, which indicated that 79.2% of children aged 2–4 years viewed 2 hours or less of television per day. The proportion of children meeting the AAP's recommendation varied by race and ethnicity. Rates were lowest among black (69.9%) and American Indian or Alaska Native (77.6%) children and highest among white (85.1%) children.

# Smoking in the Household

Exposure to secondhand tobacco smoke is a risk factor associated with low birthweight, sudden infant death, poor growth, and decreased lung function in young children.<sup>20</sup> In 2004, the PedNSS began monitoring smoking in the household, defined as whether anyone in the child's household currently smokes inside the home. Mothers of children report these data.

In 2010, a total of 32 PedNSS contributors<sup>¶</sup> (58%) reported supplementary data showing that 9.4% of children were exposed to household smoke. Exposure was highest for white (17.0%) and black (9.5%) children and lowest among Asian or Pacific Islander (4.2%) children. Exposure among children younger than age 1 year was lower (8.5%) than among children from birth to age 4 years (9.4%).

<sup>&</sup>lt;sup>§§</sup> Contributors of supplementary television viewing data include Illinois, Indiana, Iowa, Kansas, Kentucky, Maryland, Michigan, Missouri, Nebraska, New Hampshire, New Jersey, New York, North Dakota, Rhode Island, South Carolina, the U.S. Virgin Islands, Utah, West Virginia, Wisconsin, the District of Columbia, and the following ITOs: the Inter Tribal Council of Arizona, the Cheyenne River Sioux Tribe (SD), the Rosebud Sioux Tribe (SD) and the Three Affiliated Tribes (ND).

Contributors of supplementary data on exposure to household smoking include Arizona, Arkansas, California, Connecticut, Illinois, Indiana, Iowa, Kansas, Kentucky, Maine, Maryland, Michigan, Missouri, Montana, Nebraska, New Hampshire, New Jersey, New York, North Dakota, Rhode Island, South Carolina, Utah, Virginia, West Virginia, Wisconsin, the District of Columbia, and the following ITOs: the Inter Tribal Council of Arizona, the Cheyenne River Sioux Tribe (SD), the Navajo Nation (AZ), the Rosebud Sioux Tribe (SD), the Standing Rock Sioux Tribe (ND) and the Three Affiliated Tribes (ND).

# **Pediatric Health Progress Review**

Few 2010 PedNSS contributors met the national objectives for breastfeeding, low birthweight, and short stature from *Healthy People 2010*. For example,

- No contributor met the objective to reduce the prevalence of low birthweight to 5%.
- Approximately 27% of contributors with good breastfeeding data quality met the
  objective to increase the proportion of infants ever breastfed to 75%; about 10% had
  rates of 70%–74.9%.
- No contributor with good breastfeeding data quality met the objective to increase the proportion of infants breastfed at 6 months to 50%; however, approximately 8% achieved rates of 40%–49.9%.
- About 28% of contributors met the objective to reduce the prevalence of short stature among low-income preschool-aged children to 5%.

Although the 2010 PedNSS data provide an op-portunity to evaluate whether states are achieving the *Healthy People 2010* objectives for children aged birth to 4 years, this evaluation must take into account that these data represent a diverse, disadvantaged, and low-income population of children.

Renewed efforts are needed to achieve the new *Healthy People 2020* objectives for low birthweight (7.8% of live births), infants ever breastfed (81.9%), infants breastfed 6 months (60.6%), infants breastfed 12 months (34.1%), and infants exclusively breastfed 3 months (46.2%).<sup>21</sup> In addition, *Healthy People 2020* includes a new objective to reduce the proportion of children aged 2–5 years who are considered obese to 9.6%.<sup>21</sup>

Advances in nutrition and health indicators were observed in the PedNSS population from 2001 through 2010 (Figure 9). The incidence of high birthweight decreased, with the greatest improvement occurring among American Indian or Alaska Native and Hispanic infants. Substantial improvements occurred in the proportion of infants ever breastfed, with the largest improvement among black infants. Overall, short stature remained stable during 2001–2010. For only the second time in 23 years, the prevalence of obesity among children aged 2–4 years declined in the PedNSS population. Obesity rates were stable during 2003–2009.

Figure 9: This Is a bar graph showing percent change in several pediatric health indicators from 2001 to 2010. The prevalence of low birthweight has not changed. The prevalence of high birthweight has seen a relative decrease of 21%. The ever breastfed rate improved by 26%; breastfed 6 months rate improved by 17%. The anemia rate has increased by 9%; short stature prevalence rates have not changed, and the obesity prevalence rate has seen a relative increase of 10%.

The 2010 PedNSS also indicated areas of concern. Although the low birthweight rate was stable during 2001–2010, it remained high. The *Healthy People 2010* objective to reduce the prevalence of low birthweight to 5%<sup>4</sup> continues to be unmet. The prevalence of anemia stayed about the same, but it remains high among all racial and ethnic groups.

Obesity is a major public health problem that has steadily increased in the United States. The proportion of children aged 2–4 years in the PedNSS who were obese

increased by 1.3 percentage points in 2010 compared with the proportion in 2001. This change is a relative increase of about 10%. Although Hispanic and American Indian or Alaska Native children had the highest prevalence of obesity, increases occurred among all racial and ethnic groups except Asians or Pacific Islanders.

Although advances have been made in breastfeeding initiation, less than one-third of contributors achieved the *Healthy People 2010* objective of 75% of infants ever being breastfed. The prevalence of breastfeeding remained lowest for black infants. In addition, no contributors achieved the *Healthy People 2010* objective of 50% of infants breastfed to 6 months.

### Recommendations

The PedNSS data indicate that national and state public health programs are needed to support the following actions:

- Prevent low birthweight by promoting preconception nutrition care and outreach activities to identify pregnancy in its early stages.
- Foster early entry into comprehensive prenatal care, including the WIC program.
- Promote and support breastfeeding initiatives in public health programs, medical care systems, work sites, and communities.
- Identify successful programs and policies to support exclusive breastfeeding, especially among populations with low prevalence.
- Promote adequate dietary iron intake and screening of children at risk for iron deficiency.
- Implement interventions in specific target areas to prevent obesity and chronic diseases that have been recommended by CDC's Division of Nutrition, Physical Activity, and Obesity, including
  - o Increasing breastfeeding initiation, duration, and exclusivity.
  - Increasing physical activity.
  - Increasing the consumption of fruits and vegetables.
  - Decreasing the consumption of sugar-sweetened beverages.
  - Reducing the consumption of high-energy-dense foods (foods high in calories per gram weight).
  - Decreasing television viewing.

# References

- 1. Mathews TJ, MacDorman MF. Infant mortality statistics from the 2005 period linked birth/infant death set. *National Vital Statistics Reports* 2008;57(2):1–32.
- 2. Institute of Medicine. *Preventing Low Birthweight*. Washington, DC: National Academy Press; 1985.
- 3. Hamilton BE, Martin JA, Ventura SJ. Births: preliminary data for 2009. *National Vital Statistics Reports* 2010;59(3):1–19. Available at http://www.cdc.gov/nchs/data/nvsr/nvsr59/nvsr59\_03.pdf.
- 4. U.S. Department of Health and Human Services. *Healthy People 2010.* Volume II. 2nd edition. Washington, DC: U.S. Government Printing Office; 2001.
- 5. Jolly MC, Sebire NJ, Harris JP, Regan L, Robinson S. Risk factors for macrosomia and its clinical consequences: a study of 350,311 pregnancies. *European Journal of Obstetrics & Gynecology and Reproductive Biology* 2003;11: 9–14.
- 6. Martin JA, Hamilton BE, Sutton PD, Ventura SJ, Mathews TJ, Nichelle JK, et al. Births: final data for 2008. *National Vital Statistics Reports* 2010;59(1):1–72. Available at http://www.cdc.gov/nchs/data/nvsr/nvsr59/nvsr59\_01.pdf.
- 7. Gartner LM, Morton J, Lawrence RA, Naylor AJ, O'Hare D, Schanler RJ. Breastfeeding and the use of human milk. *Pediatrics* 2005;115(2):496–506.
- 8. Centers for Disease Control and Prevention. *Breastfeeding Among U.S. Children Born 2000–2008*, *CDC National Immunization Survey*. Available at http://www.cdc.gov/breastfeeding/data/NIS\_data/index.htm.
- 9. Ip S, Chung M, Raman G, Chew P, Magula N, DeVine D, et al. *Breastfeeding and Maternal and Infant Health Outcomes in Developed Countries*. Rockville, MD: Agency for Healthcare Research and Quality; 2007. Evidence Report/Technology Assessment No. 153. Available at http://www.ahrq.gov/downloads/pub/evidence/pdf/brfout/brfout.pdf.
- 10. Pollitt E. Iron deficiency and cognitive function. *Annual Review of Nutrition* 1993;13:521–537.
- 11. Idjradinata P, Pollitt E. Reversal of developmental delays in iron-deficient anaemic infants treated with iron. *Lancet* 1993;341(8836):1–4.
- Centers for Disease Control and Prevention. Recommendations to prevent and control iron deficiency in the United States. MMWR Recommendations and Reports 1998;47(RR-3): 1–30.
- 13. World Health Organization Expert Committee on Physical Status. *Physical Status: The Use and Interpretation of Anthropometry.* Geneva: World Health Organization; 1996.
- 14. Mei Z, Ogden CL, Flegal KM, Grummer-Strawn LM. Comparison of the prevalence of shortness, underweight, and overweight among U.S. children aged 0 to 59 months by using the Centers for Disease Control and Prevention 2001 and the WHO 2006 growth charts. *Journal of Pediatrics* 2008;153:622 628.
- 15. Krebs NF, Jacobson MS; American Academy of Pediatrics Committee on Nutrition. Prevention of pediatric overweight and obesity. *Pediatrics* 2003;112(2):424–430.
- 16. Barlow SE; Expert Committee. Expert committee recommendations regarding the prevention, assessment, and treatment of child and adolescent overweight and obesity: summary report. *Pediatrics* 2007;120(suppl 4):S164-S192. Available at http://pediatrics.aappublications.org/cgi/content/full/120/Supplement 4/S164.

- 17. Ogden CL, Carroll MD, Curtin LR, Lamb MM, Flegal KM. Prevalence of high body mass among children and adolescents, 2007–2008. *Journal of the American Medical Association* 2010;303(3):242–249. Available at http://jama.ama-assn.org/content/303/3/242.full.
- Centers for Disease Control and Prevention. Obesity prevalence among lowincome preschool-aged children—United States, 1998–2008. Morbidity and Mortality Weekly Report 2009;58(28):769–773.
- 19. American Academy of Pediatrics, Committee on Public Education: Children, adolescents, and television. *Pediatrics* 2001;10(2):423–426.
- Centers for Disease Control and Prevention. Vital Signs: nonsmokers' exposure to secondhand smoke—United States, 1999–2008. Morbidity and Mortality Weekly Report 2010;59(35):1141–1146.
- U.S. Department of Health and Human Services, Office of Disease Prevention and Health Promotion. Healthy People 2020. Washington, DC: U.S. Government Printing Office; 2010. Available at http://www.healthypeople.gov/2020/.

#### Table 1. Contributors to the Pediatric Nutrition Surveillance System, 2001-2010

Alabama: 2003 - 2010

American Samoa: 2000-2001

Arizona: 2000 – 2010 Arkansas: 2000 – 2010 California: 2000 – 2010

Cheyenne River Sioux Tribe (SD): 2000 – 2010

Chickasaw Nation (OK): 2000 - 2005

Colorado: 2000 – 2010 Connecticut: 2001 – 2010

District of Columbia: 2000 – 2010

Florida: 2000 – 2010 Georgia: 2000 – 2010

Hawaii: 2000 – 2005, 2007 – 2010

Idaho: 2000 – 2010 Illinois: 2000 – 2010 Indiana: 2000 – 2010

Inter Tribal Council of Arizona: 2000 - 2010

Iowa: 2000 – 2010 Kansas: 2000 – 2010 Kentucky: 2000 – 2010

Louisiana: 2000 – 2004, 2007, 2009-2010

Maine: 2000 – 2005. 2009-2010 Maryland: 2000 – 2002, 2004 – 2010

Massachusetts: 2006 – 2010 Michigan: 2000 – 2010

Minnesota: 2000 - 2010

Mississippi: 2000, 2007 – 2010

Missouri: 2000 – 2010 Montana: 2003 – 2010

Navajo Nation: 2000 – 2010 Nebraska: 2000 – 2010 Nevada: 2000 – 2010

New Hampshire: 2000 – 2010 New Jersey: 2000 – 2010

New Mexico: 2000 – 2002, 2004 – 2010

New York: 2000, 2002 – 2010 North Carolina: 2000 – 2010

North Dakota: 2000 – 2005, 2007 – 2010

Ohio Child Health: 2006 – 2010

Ohio WIC: 2000 - 2010

Oregon: 2000 - 2003, 2006 - 2010

Pennsylvania: 2000 – 2010 Puerto Rico: 2002 – 2010 Rhode Island: 2006 – 2010

Rosebud Sioux Tribe (SD): 2000 – 2010

South Carolina: 2000 – 2010 South Dakota: 2000 – 2010

Standing Rock Sioux Tribe (ND): 2000 – 2006, 2008-2010

Tennessee: 2000 – 2010

Texas: 2003 – 2010

Three Affiliated Tribes (ND): 2007 - 2010

Utah: 1999 – 2005 Vermont: 2000 – 2010 Virgin Islands: 2008 – 2010

Virginia: 2003 – 2010

Washington: 1999 - 2002, 2006 - 2010

West Virginia: 2000 – 2010 Wisconsin: 2000 – 2010 Wyoming: 2001-2005

	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010
Number of Contributors	47	48	49	50	49	48	52	53	55	55
Total Unique Child Records	4.943	5.519	6.359	6.930	7.118	7.599	7.996	8.165	8.939	8.673
Submitted (x 1,000)	1,010	-,	-,	,,,,,,	.,	,,,,,,,	,,,,,,,	0,100	-,	-,

Table 2. State-specific prevalence of selected nutrition indicators for children aged <5 years, 2010 Pediatric Nutrition Surveillance System

			Ever	Breastfed		Short	
Contributors	LBW	HBW <sup>†</sup>	Breast-	6	Anemia <sup>¶</sup>	Stature**	Obesi-
Contributors	*	при			Anemia	Stature	ty <sup>††</sup>
			fed <sup>‡</sup>	Months <sup>§</sup>			•
Alabama	12.0	4.6	37.7	NA	17.7	6.1	14.1
Arizona	7.9	6.3	65.0	23.5	13.7	5.9	14.2
Arkansas	10.3	5.3	42.5	11.7	16.9	7.3	14.1
California	6.1	7.4	NA	NA	13.5	5.1	17.2
Cheyenne River Sioux (SD)	5.9	10.5	27.5	NA	11.8	1.1	19.6
Colorado	9.7	4.3	77.5	29.1	12.4	7.7	9.1
Connecticut	8.7	6.8	65.8	27.0	8.3	3.4	15.8
District of Columbia	11.2	5.3	51.0	20.2	26.7	7.6	13.7
Florida	9.8	5.8	71.8	24.0	15.8	4.3	13.4
Georgia	10.5	5.2	50.1	18.6	15.3	6.2	13.5
Hawaii	9.1	6.2	85.2	39.0	10.9	6.3	9.1
Idaho	7.4	6.7	84.5	32.2	10.5	6.5	11.4
Illinois	9.0	6.8	65.0	22.5	11.1	6.7	14.6
Indiana	8.9	6.3	65.1	21.3	14.4	5.9	14.2
Inter Tribal Council of Arizona	7.5	8.8	63.5	18.0	12.9	5.2	24.5
lowa	8.8	7.6	60.6	16.4	7.5	5.5	14.7
Kansas	8.5 9.9	6.5 6.3	67.7 38.3	17.3 13.3	10.2 12.2	6.4 5.9	13.0 15.6
Kentucky	12.1						
Louisiana Maine	12.1 NA	3.3 NA	30.4 NA	9.6 28.6	19.0 13.1	8.1 3.4	12.5 14.3
Maryland	9.9	5.9	62.3	26.0	20.0	5.6	15.7
Massachusetts	8.7	7.4	73.8	25.2	10.7	4.8	16.1
Michigan	9.0	7.4	54.9	17.8	15.6	5.2	13.3
Minnesota	7.5	9.2	74.4	30.7	10.5	4.9	12.7
Mississippi	NA	NA	NA	NA	16.0	8.5	13.7
Missouri	9.5	6.1	59.1	13.8	16.5	6.2	13.6
Montana	9.0	7.1	75.6	27.7	9.9	6.8	12.2
Navajo Nation (AZ)	7.2	6.4	80.7	34.7	5.2	5.0	18.7
Nebraska	8.2	7.0	71.6	22.0	13.2	5.9	13.8
Nevada	8.7	5.9	59.3	19.8	9.7	6.8	13.6
New Hampshire	NA	NA	71.1	22.7	13.7	5.8	14.2
New Jersey	8.6	6.1	60.6	31.3	19.9	5.6	17.3
New Mexico	9.4	4.4	75.3	NA	11.5	6.8	11.7
New York	8.8	6.6	76.9	38.2	12.3	4.3	14.5
North Carolina	9.8	6.5	61.4	22.8	13.8	5.6	15.5
North Dakota	9.1	8.0	63.4	19.8	9.6	4.7	14.1
Ohio	10.2	5.9	49.0	14.4	13.0	6.5	12.4
Oregon	7.1	9.1	91.5	42.3	13.3	5.0	15.1
Pennsylvania	10.2	6.2	47.9	16.2	20.7	6.3	12.0
Puerto Rico	NA	NA	NA	NA	5.6	10.5	18.3
Rhode Island	8.8	7.2	59.1	19.6	15.3	5.6	15.5
Rosebud Sioux (SD)	5.6	6.0	55.4	NA	26.6	8.0	21.4
South Carolina	9.9	8.0	46.4	12.8	17.0	6.0	12.8
South Dakota	7.7	8.0	63.2	21.3	8.1	5.9	16.1
Standing Rock Sioux (ND)	NA	NA	NA	NA	20.6	1.3	23.6
Tennessee	10.6	5.3	35.0	15.8	7.6	6.0	14.5
Texas	8.8	5.5	75.7	42.1	20.6	6.7	15.3
Three Affiliated Tribes (ND)	NA	NA NA	NA NA	NA 10.0	15.0	1.4	38.2
U.S. Virgin Islands	8.6	4.6	85.4	48.2	13.2	5.3	11.2
Utah	8.6	5.6	77.7	36.5	11.1	7.8	8.7
Vermont	7.2	9.9	76.2	27.9	6.7	4.9	12.2
Virginia	9.7	6.4	55.5	18.1	15.3	5.8	15.5
Washington	7.5	9.2	85.6	37.9	10.2	5.0	14.4
West Virginia	9.8	6.1	42.2	13.0	6.0	5.4	13.7
Wisconsin	8.6	7.0	68.5	26.4	10.0	5.5	14.1
National PedNSS	9.0	6.3	63.2	25.1	14.6	5.9	14.4

Abbreviations: LBW = low birthweight; HBW = high birthweight; NA = not available.

Defined as birthweight <2,500 grams.

<sup>†</sup> Defined as birthweight >4,000 grams.

<sup>‡</sup> Infants born during the reporting period are included in analysis.

<sup>§</sup> Infants who turned 6 months of age during the reporting period by/on their date of visit are included in analysis.

<sup>¶</sup> Adjusted for altitude. For children aged 6–23 months: hemoglobin (Hb) is <11.0 g/dL, or hematocrit (Hct) is <32.9%. For children aged 2–4 years: Hb is <11.1 g/dL or Hct is <33.0%.

<sup>\*\*</sup> Based on the 2000 CDC Growth Chart. Defined as <5th percentile length-for-age for children aged younger than 2 years or height-for-age for children aged 2 years or older.

<sup>††</sup> Based on the 2000 CDC Growth Chart. Defined as ≥95th percentile BMI-for-age for children aged 2 years or older