# **Label Review Manual**

# **Chapter 7:Precautionary Statements**



# I. Introduction

The precautionary statements are designed to provide the pesticide user with information regarding the toxicity, irritation and sensitization hazards associated with the use of a pesticide, as well as treatment instructions and information to reduce exposure potential. While the Precautionary Statements include Personal Protective Equipment (for uses that trigger worker protection standards), User Safety Requirements, Engineering Controls, User Safety Recommendations, Environmental Hazards, and Physical or Chemical Hazards, for the purposes of this manual, those topics are addressed in other chapters. The remaining sections (Signal Word, Child Hazard Warning, Hazards to Humans and Domestic Animals, First Aid and Personal Protective Equipment (Non-Worker Protection Standard (WPS)) are fully addressed in this chapter. Label reviewers should consult the mandatory/advisory *PR Notice 2000-5* for guidance in recommended language for precautionary statements.

# II. Background information

### A. Documents Used to Determine Precautionary Statements on Labels

The Code of Federal Regulations specifies both the acute toxicity category (40 CFR 156.62) and the Hazards to Humans and Domestic Animals statements associated with each toxicity category (40 CFR 156.70). These toxicity categories and labeling statements however are not currently being used by the Agency, because they are less detailed and provide less protection for pesticide users than other guidance. The 40 CFR 156.70(c) states that specific statements pertaining to the hazards of the product and its uses must be approved by the Agency. The labeling statements provided in the Federal Register Notice issued on 9/26/84, entitled Proposed Rule on Labeling Requirements (Volume 49, Number 188) have been used by the Agency for the past twenty years. The acute toxicity categories listed in the Proposed Rule are also being used.

# **B.** Acute Toxicity Data

The Signal Word, Hazards to Humans and Domestic Animals, Personal Protective Equipment (non-WPS) and First Aid statements are typically determined by the results of the six acute toxicity studies performed with the product formulation. The acute oral, acute dermal and acute inhalation studies evaluate systemic toxicity via the designated routes of exposure. The primary eye irritation and primary skin irritation studies measure irritation or corrosion, while the dermal sensitization study evaluates the potential for allergic contact dermatitis. With the exception of dermal sensitization, each acute study is assigned to a toxicity category based on the study results (See Table 1 below). The results of these six acute toxicity studies must be known in order for the appropriate labeling language to be determined.

Table 11 Toxicity Sategories				
Study	Category I	Category II	Category III	Category IV
Acute Oral	Up to and including 50 mg/kg	> 50 thru 500 mg/kg	> 500 thru 5000 mg/kg	> 5000 mg/kg
Acute Dermal	Up to and including 200 mg/kg	> 200 thru 2000 mg/kg	> 2000 thru 5000 mg/kg	> 5000 mg/kg
Acute Inhalation <sup>1</sup>	Up to and including 0.05 mg/liter	> 0.05 thru 0.5 mg/liter	> 0.5 thru 2 mg/liter	> 2 mg/liter
Primary Eye Irritation	Corrosive (irreversible destruction of ocular tissue) or corneal involvement or irritation persisting for more than 21 days	Corneal involvement or other eye irritation clearing in 8-21 days	Corneal involvement or other eye irritation clearing in 7 days or less	Minimal effects clearing in less than 24 hours
Primary Skin Irritation	Corrosive (tissue destruction into the dermis and/or scarring)	Severe irritation at 72 hours (severe erythema or edema)	Moderate irritation at 72 hours (moderate erythema)	Mild or slight irritation at 72 hours (no irritation or slight erythema)

**Table 1. Toxicity Categories** 

## C. Use of Reregistration Eligibility Decision (RED) Documents

During Reregistration, the RED document may also specify personal protective equipment, engineering controls and user safety recommendations. In cases where RED specifications differ from those determined by the acute toxicity categories, the most protective statements must be employed. The regulations allow use of a higher signal word for human hazard when necessary to prevent unreasonable adverse effects on man and the environment.  $(40\ CFR\ 156.64(b)(1))$ 

# III. Determining the precautionary labeling

### A. The Signal Word

- 1. When Required. A Signal Word is required for all registered pesticide products unless the pesticide product meets the criteria of Toxicity Category IV by all routes of exposure. If a signal word is used in this case, it must be "Caution".
- 2. **Determining the Signal Word.** The Signal Word is determined by the most severe toxicity category assigned to the five acute toxicity studies (see table 1) or by the presence of methanol in concentrations of 4% or more. The Signal Words and associated toxicity categories are as follows:

<sup>&</sup>lt;sup>1</sup> 4 hr exposure

Toxicity Category I DANGER
Toxicity Category II WARNING
Toxicity Category III CAUTION

Toxicity Category IV None Required

Refer to the acute toxicity data review to determine the most severe toxicity category. Also check the Confidential Statement of Formula to determine if methanol is present in concentrations of 4% or more. If so, the Signal Word, regardless of the toxicity categories noted in the acute toxicity review, is DANGER.

- 3. Location and Prominence. The Signal Word is required to appear on the front panel of the label, and must appear on a separate line from the required Child Hazard Warning statement, Keep Out of Reach of Children (KOROC). It is preferred that it appear below the KOROC statement. The Signal Word is also required on any supplemental labeling intended to accompany the product in distribution or sale. The signal word must also appear together with the heading for the human precautionary statement section of the labeling. The Agency also requests that it appear in the Precautionary Statements section immediately below the subheading "Hazards to Humans and Domestic Animals". In cases where the "First Aid" and "Hazards to Humans and Domestic Animals" statement appear on the front panel, the Agency requests that the Signal Word be placed directly below the Child Hazard Warning statement, but it does not have to be repeated after the "Hazards to Humans and Domestic Animals" statement. All required front panel warning statements shall be grouped together on the label, and shall appear with sufficient prominence relative to other front panel text and graphic material to assure that they will not be overlooked under customary conditions of purchase and use (40 CFR 156.60(b)). See Chapter 3 for the Minimum Type Size requirements for the Signal Word, Child Hazard Warning statement and the sample label format. The Signal Word must appear in all capital letters and should be oriented in the same direction as other label text.
- 4. Related Information. Because of the potential for confusion, the Agency historically has not approved labels containing the terms "caution", "warning", or "danger", except as the Signal Word for that label (e.g., "CAUTION: Wash hands before eating, or smoking" on a label with the signal of "Caution"). If the Prop 65 term conflicts with the EPA signal word, then registrants should use "Notice" or "Attention" for the Prop 65 statement so that it does not conflict with the EPA signal word. . However, registrants should use the term "notice" or "attention" instead, so that it does not conflict with the EPA required Signal Word.

### B. Poison – Skull and Crossbones Symbol

1. When Required. The word "POISON" and the skull and crossbones symbol ★ are required for products classified as toxicity category I for acute oral, acute dermal, or acute inhalation toxicity studies (40 CFR 156.64(a)(1)). It is also required if the inert, methanol, is present at 4% or more in the subject product because of the well-known possible risk of causing blindness..

Type of Product A **Product B Product C\* Product D** Product E\* Study ΙV Ι IIIAcute Oral IIIIIIAcute Dermal ΙV III IIIΙV III Acute ΙV TTT IIIIII TTT Inhalation Ι ΙΙ Ι IIIPrimary Eye III ΙV Primary Skin ΤV ΙV IIIII Special Inert, No No No No Yes\* e.g., methanol **WARNING DANGER CAUTION DANGER DANGER** CORRECT **SIGNAL** (Poison with (Poison with WORD Skull & Skull & Crossbones) Crossbones)

**Table 2. Examples of Signal Word Determination** 

2. Location and Prominence. If required, the word "POISON" and the skull and crossbones symbol must appear in immediate proximity to each other. The word "POISON" must appear in red on a background of a distinctly contrasting color. If the proposed label does not indicate these display requirements, include this requirement in your response to the registrant. In addition, the Agency requests that the "Poison" and the skull and crossbones symbol appear near the Tox.1 signal word "Danger".

# C. Child Hazard Warning Statement

1. When Required. The Child Hazard Warning statement, "Keep Out of Reach of Children" (KOROC) is required on all product labels, unless the requirement is waived. The warning statement requirement may be waived when the registrant adequately demonstrates that the likelihood of contact with children during distribution, storage or use (e.g., an MUP in some situations) is extremely remote or if the pesticide is approved for use on infants or small children.

<sup>\*</sup>Product C and Product E must also bear additional labeling (Skull & Crossbones symbol in close proximity to the word "POISON" which must appear in red on a contrasting background). Product C must bear the additional labeling as a result of the toxicity category I classification for the acute oral toxicity study. Product E must bear the additional labeling because it contains a special inert (methanol) at greater than 4%, as described in paragraph B.1. above.

- **2. Location and Prominence.** The Child Hazard Warning statement must appear on the front panel (*40 CFR 156.66*). The Child Hazard Warning must appear on a separate line above the Signal Word. Also make sure that the Child Hazard Warning statement is oriented in the same direction as other label text.
- 3. Additional Information. Based on the FIFRA unreasonable adverse effects standard, the Agency has not allowed the Precautionary Statements or the Directions for Use to contain any statement which implies that the product may be used by children. For example, draft labels of products intended to repel insects should not contain instructions such as "Do not allow use by small children without close adult supervision". Such labeling creates unacceptable risk issues, as it implies that a child can apply the product as long as an adult watches.

A modified Child Hazard Warning statement may be used for products where child contact is expected during normal use. For products requiring a modified statement, make sure that the statement is appropriate for the use pattern. Examples of appropriate statements are as follows:

"Do not allow children to apply product" or "Do not allow children to play with pet collar".

### D. Hazards to Humans and Domestic Animals Statements

- 1. When Required. Hazards to Humans and Domestic Animals statements are required when any acute toxicity study results in a product classification of toxicity category I, II, or III and/or when the dermal sensitization study result is positive. Hazards to Humans and Domestic Animals statements may specify both mandatory actions and advisory information.
- **2. Required Header.** The Hazards to Humans and Domestic Animals statements must appear under the section heading "Precautionary Statements" and below the subheading "Hazard to Humans and Domestic Animals". The Signal Word must appear before the precautionary paragraph. (40 CFR 156.70) The phrase "and Domestic Animals" may be omitted from the heading if domestic animals will not be exposed to the product. (40 CFR 156.70(a))
- 3. Location and Prominence. The Hazards to Humans and Domestic Animals section may appear on any panel. Please note, however, that these statements should not be included within the Directions For Use section. These statements should be organized so that the routes of exposure of most concern (severe routes of exposure) as supported by the toxicity category classification are listed first. This organization is strongly preferred by the Agency.

- **4. Determining the Hazards to Humans and Domestic Animals Statements for Fumigant Products.** Refer to *PR Notice 84-5*, Registration Standards or Reregistration Eligibility Decision Documents (REDs) suggested Hazards to Humans and Domestic Animals statements.
- 5. Determining the Hazards to Humans and Domestic Animals Statements for Non-Fumigant Products. Statements from the tables 3-8 can be selected based on the toxicity category assigned to each study. Statements from these tables should be combined to form a concise paragraph. Repetitious sentences should be omitted. In cases where the toxicity categories are not known, the precautionary labeling must be consistent with the signal word.
- **6. Related Information.** Hazards to Humans and Domestic Animals statements must be appropriate for all uses on the label. These statements must be consistent with each use pattern listed on the label. No statement should be used that is reasonably beyond the control of the typical applicator. Hazards to Humans and Domestic Animals statements must not require use of specialized equipment which would not be readily available to the typical user of the product.
- 7. Products that contain greater than 4% Methanol. If the product contains 4% or more of methanol, the Agency believes that in order to mitigate potential risk the following statement should be added to the label:

**Table 3. Typical Statements for Acute Oral Toxicity** 

Toxicity Category	Signal Word	Statements
I	DANGER-POISON Skull & Crossbones required	Fatal if swallowed. Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet.
II	WARNING	May be fatal if swallowed. Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet.
III	CAUTION	Harmful if swallowed. Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet.
IV	CAUTION (optional)	No statements are required. However, the registrant may choose to use category III labeling.

<sup>&</sup>quot;Methanol may cause blindness".

**Table 4. Typical Statements for Acute Dermal Toxicity** 

Toxicity Category	Signal Word	Statements
I	DANGER-POISON Skull & Crossbones required	Fatal if absorbed through skin. Do not get in eyes, on skin, or on clothing. Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet. Wear (specify appropriate protective clothing). Remove and wash contaminated clothing before reuse.
II	WARNING	May be fatal if absorbed through skin. Do not get in eyes, on skin, or on clothing. Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet. Wear (specify appropriate protective clothing). Remove and wash contaminated clothing before reuse.
III	CAUTION	Harmful if absorbed through skin. Avoid contact with skin, eyes or clothing. Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet. Remove and wash contaminated clothing before reuse. Wear (specify any appropriate protective clothing, if appropriate).
IV	CAUTION (optional)	No statements are required. However, the registrant may choose to use category III labeling.

**Table 5. Typical Statements for Acute Inhalation Toxicity** 

Toxicity Category	Signal Word	Statements
I	DANGER-POISON Skull & Crossbones required	Fatal if inhaled. Do not breathe (dust, vapor, or spray mist).* Wear (specify appropriate respiratory protection from Table 5, Chapter 10). Remove and wash contaminated clothing before reuse.
II	WARNING	May be fatal if inhaled. Do not breathe (dust, vapor or spray mist).* Wear (specify appropriate respiratory protection from Table 5, Chapter 10). Remove and wash contaminated clothing before reuse.
III	CAUTION	Harmful if inhaled. Avoid breathing (dust, vapor or spray mist).* Remove and wash contaminated clothing before reuse.
IV	CAUTION (optional)	No statements are required. However, the registrant may choose to use category III labeling.

<sup>\*</sup> Choose the word which appropriately describes the product during use.

**Table 6. Typical Statements for Primary Eye Irritation** 

Toxicity Category	Signal Word	Statements
I	DANGER	Corrosive.* Causes irreversible eye damage. Do not get in eyes or on clothing. Wear (specify appropriate protective eyewear such as goggles, face shield, or safety glasses). Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet. Remove and wash contaminated clothing before reuse.
II	WARNING	Causes substantial but temporary eye injury. Do not get in eyes or on clothing. Wear (specify appropriate protective eyewear such as goggles, face shield, or safety glasses). Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet. Remove and wash contaminated clothing before reuse.
III	CAUTION	Causes moderate eye irritation. Avoid contact with eyes or clothing. Wear (specify protective eyewear, if appropriate). Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet.
IV	CAUTION (optional)	No statements are required. However, the registrant may choose to use category III labeling.

<sup>\*</sup>The term "corrosive" is not required if corrosive effects were not observed during the study.

**Table 7. Typical Statements for Primary Skin Irritation** 

Toxicity Category	Signal Word	Statements
I	DANGER	Corrosive. Causes skin burns. Do not get in eyes, on skin, or on clothing. Wear (specify appropriate protective clothing and gloves). Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet. Remove and wash contaminated clothing before reuse.
II	WARNING	Causes skin irritation. Do not get on skin or on clothing. Wear (specify appropriate protective clothing and gloves). Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet. Remove and wash contaminated clothing before reuse.
III	CAUTION	Avoid contact with skin or clothing. Wash thoroughly with soap and water after handling and before eating, drinking, chewing gum, using tobacco or using the toilet. Wear (specify protective clothing and gloves, if appropriate).
IV	CAUTION (optional)	No statements are required. However, the registrant may choose to use category III labeling.

Table 8. Typical Statements for Dermal Sensitization\*

Study Results	Statement
Product is a sensitizer or is positive for sensitization	Prolonged or frequently repeated skin contact may cause allergic reactions in some individuals.
Product is not a sensitizer or is negative for sensitization	No labeling is required for this result.

<sup>\*</sup>A positive dermal sensitization study for a category IV product does not trigger a PPE requirement.

### E. Personal Protective Equipment (PPE)

PPE requirements are specified for uses covered under the Worker Protection Standard (WPS), but there are no regulatory requirements for non-WPS products, products used by residents, or products intended only for manufacturing use. However, to protect human health, the following guidance is offered.

- 1. For Non-WPS (Industrial/Commercial) Uses. While there are no regulatory requirements that demand PPE for non-WPS products, many states test applicators for their comprehension regarding what types of PPE are used and how to use it correctly, however, this training and testing is normally only done for users of RUPs, not unclassified pesticides. Label reviewers should ensure that adequate, understandable language regarding the types of PPE that should be worn for the product's hazards is included in any label, whether RUP or unclassified. In cases where the reviewers determine PPE would be necessary, the various PPE tables in Chapter 10 provide information about which PPE is protective in specific circumstances. If there is an applicable regulatory document which specifies PPE requirements based on concerns specific to the active ingredient then those PPE requirements must be placed on the label.
- 2. For Products used by Residents/Consumers. In order to protect human health, label reviewers should review the toxicity data and the product's uses to determine whether PPE would be necessary to meet the standards for registration. In cases where the reviewers determine PPE would be necessary, the PPE tables in Chapter 10 provide information about which PPE is protective in specific circumstances. In some cases, the PPE indicated in these tables may need to be modified; for example, to fit the consumer's ability to acquire it. For example, "shoes" may need to be substituted for "chemical resistant footwear" or "safety glasses" may need to be substituted for "protective eyewear". If there is an applicable regulatory document which specifies PPE requirements based on concerns specific to the active ingredient then those PPE requirements must be placed on the label.

#### F. First Aid Statements

- 1. When Required. A First Aid statement is required when any acute toxicity study result is classified as category I, II, or III. It is acceptable, but not required, for the registrant to include First Aid statements for products that are classified as category IV.
- **2. Appropriate Headers.** The first aid statements appear under either of the following headings: "First Aid" or "Statements of Practical Treatment". (*PR Notice 2001-1*). The heading "First Aid" is preferred by the Agency. In addition, EPA historically has not allowed the heading "Antidote" in conjunction with the first aid statements unless a specific antidote is necessary.
- 3. Location and Prominence. First Aid statements shall appear on the front panel of the label for all products classified as toxicity category I (40 CFR 156.68). The Agency may, however, permit reasonable variations in the placement of the First Aid statement as long as the reference statement, "See First Aid (or Statement of Practical Treatment) on (identify appropriate panel)" appears on the front panel, preferably near "Poison" and the skull and crossbones. First Aid statements for toxicity categories II and III classification may appear on any panel of the label. However, any time First Aid statements appear other than on the front panel, a referral statement such as, "See side/back panel for First Aid" should appear on the front panel in close proximity to the Signal Word. Furthermore, First Aid statements on the side or back panel should be grouped near the other precautionary labeling text, yet set apart or distinguishable from the other label text. First Aid statements should be organized so that the most severe routes of exposure, as demonstrated by the toxicity classification, are listed first. This organization is strongly preferred by the Agency.
- **4. Determining the First Aid Statements for Fumigant Products.** Refer to *PR Notice 84-5* and Registration Standards/REDs.
- 5. Determining the First Aid Statements for Non-Fumigant Products. Review Table 9 to determine the preferred First Aid statements for each route of exposure. Registrants should support alternative First Aid statements with medical evaluations of the product. Approval of alternative First Aid statements is guided by considerations such as those set out in the "Content and Clarity" section below. The Agency has not approved the use of salt water for emesis as a first aid technique. (*PR Notice 80-2*).
  - (a) Content and Clarity. First Aid statements should be brief, clear, simple and in straightforward language so that the average person in an emergency can easily and quickly understand the instructions. First Aid statements should apply to all ages or when necessary, include distinctions between the treatments for different ages (e.g., children vs. adults). Any reasonably competent individual should be able to perform the First Aid statements. These statements should not include procedures which

- must be performed by medical personnel or require specialized equipment. Such procedures belong under the Note to Physician heading (see section G below).
- (b) Acute Dermal and Primary Skin Irritation. Because both of these studies focus on the dermal route of exposure, any first aid statements required by the results of these two studies can be combined. Use the first aid statement required for the acute dermal toxicity study if the results of both studies place the product in the same acute toxicity category. Use the statements for the more severe acute toxicity category if the results of the studies would place the product in different acute toxicity categories.
- (c) Eye and Skin Irritation. If the product is corrosive and is in toxicity category I or II for eye or dermal irritation, then a first aid statement for ingestion may also be included. First aid statements for ingestion may be more appropriate for products with some potential for ingestion, such as liquid concentrates, but less so for products with low potential, such as aerosol sprays. For Toxicity Category I skin and eye irritants, the Agency has used the statement: "Note to Physician: Probable mucosal damage may contraindicate the use of gastric lavage." (PRN 2001-1).
- **6. Products that contain an organophosphate** (i.e., an organophosphorus ester that inhibits cholinesterase) or an **N-methyl carbamate** (i.e., an N-methyl carbamic acid ester that inhibits cholinesterase). If the product contains either chemical, the following phrase should be included in the First Aid statement (*PRN 2001-1*):

"CONTAINS AN \_\_\_\_\_ (either organophosphate or N-methyl carbamate) THAT INHIBITS CHOLINESTERASE".

**7. Products that contain zinc phosphide.** If the product contains zinc phosphide, the following First Aid statement is recommended (*PRN 2001-1*):

"If swallowed: Immediately call a Poison Control Center or doctor or transport the person to the nearest hospital. DO NOT DRINK WATER. Do not administer anything by mouth or make the person vomit unless advised to do so by a doctor".

8. Products that contain petroleum distillates. If the product contains  $\geq 10\%$  petroleum distillates, the following First Aid statement should be used (*PRN 2001-1*):

"If swallowed: Immediately call a poison control center or doctor. Do not induce vomiting unless told to do so by a poison control center or doctor. Do not give **any** liquid to the person. Do not give anything by mouth to an unconscious person".

However, if registrants have data to show there is benefit in drinking water or milk after ingesting their product(s), they may submit alternate wording via amendment.

**9. Telephone numbers.** EPA encourages, but does not require, registrants to include a company telephone number or toll-free hotline number for emergency information in the first aid section. If a number is included, confusion can be avoided by placing emergency numbers with the "First Aid" or "Hot Line Number" text. If a number is included, it should include a phrase or statement indicating the kinds of information the number should be used for and it may include hours of service. For example:

"Have the product container or label with you when calling a poison control center or doctor, or going for treatment. For emergency information on (product, usage, etc.), call (1-XXX-XXX-XXXX), Monday through Friday, 9 a.m. to 5 p.m. After 5 p.m. call your poison control center at 1-800-222-1222".

If a registrant does not have its own number, the registrant may use the National Pesticides Information Center (NPIC) 800 number (see below).

**Table 9. First Aid Statements** 

Route of Exposure and Toxicity Category	First Aid Statement	
Ingestion treatment for acute oral toxicity categories 1, 2, and 3	<ul><li>If swallowed:</li><li>Call a poison control center or doctor immediately for treatment advice.</li><li>Have person sip a glass of water if able to swallow.</li></ul>	
	<ul><li>Do not induce vomiting unless told to by a poison control center or doctor.</li><li>Do not give anything to an unconscious person.</li></ul>	
Acute oral toxicity category 4	Statement is not required. Registrants may use toxicity category 1-3 statements if they choose.	
Skin exposure treatment for acute dermal toxicity, and irritation categories 1, 2, and 3	If on skin:  - Take off contaminated clothing.  - Rinse skin immediately with plenty of water for 15-20 minutes.  - Call a poison control center or doctor for treatment advice.	
Dermal and skin irritation toxicity category 4	Statement is not required. Registrants may use toxicity category 1-3 statements if they choose.	
Inhalation treatment for acute toxicity categories 1, 2, and 3	<ul> <li>If inhaled: <ul> <li>Move person to fresh air.</li> </ul> </li> <li>If person is not breathing, call 911 or an ambulance, then give artificial respiration, preferably mouth-to-mouth if possible.</li> <li>Call a poison control center or doctor for further treatment advice.</li> </ul>	
Inhalation toxicity category 4	Statement is not required. Registrants may use toxicity category 1-3 statements if they choose.	
Eye exposure treatment for eye irritation categories 1, 2, and 3	<ul> <li>If in eyes:</li> <li>Hold eye open and rinse slowly and gently with water for 15-20 minutes. Remove contact lenses, if present, after the first 5 minutes, then continue rinsing.</li> <li>Call a poison control center or doctor for treatment advice.</li> </ul>	

Route of Exposure and Toxicity Category	First Aid Statement
Eye irritation toxicity category 4	Statement is not required. Registrants may use toxicity category 1-3 statements if they choose.
General information to include either near the first aid statement or emergency phone number	<ul> <li>Have the product container or label with you when calling a poison control center or doctor or going for treatment.</li> </ul>
	<ul> <li>For emergency information on (product, use, etc.), call the National Pesticides Information Center at 1-800-858-7378, 6:30 AM to 4:30 PM Pacific time (PT), seven days a week. During other times, call the poison control center 1-800-222-1222.</li> </ul>

**10. National Pesticides Information Center.** Regarding the General Information provided under the First Aid statements section (Table 9), the emergency phone number could be the National Pesticides Information Center's 800 number. The section could read:

"Have the product container or label with you when calling a poison control center, doctor, or going for treatment. For emergency information concerning this product, call the National Pesticides Information Center (NPIC) at 1-800-858-7378 seven days a week, 6:30 am to 4:30 pm Pacific Time (NPIC Web site: www.npic.orst.edu)".

### G. Note to Physicians

- 1. When Used. The Note to Physician is not required nor mentioned in the 40 CFR. If the label under review is for a product which is a fumigant, refer to *PR Notice* 84-5 or relevant Registration Standards or REDS for the appropriate Note to Physician. For all other products, EPA currently uses a Note to Physician as specified in the 1984 proposed rule for the following types of products:
  - (a) All products that are classified as toxicity category I.
  - (b) Products which are corrosive or classified as toxicity category I for eye or skin. These products must include the following Note to Physician: "Probable mucosal damage may contraindicate the use of gastric lavage".
  - (c) Products which contain ≥ 10% petroleum distillate should include the following Note to Physician: "Contains petroleum distillate. Vomiting may cause aspiration pneumonia".
  - (d) Products which produce physiological effects requiring specific antidotal or medical treatment such as: Cholinesterase Inhibitors (e.g., carbamates and phosphorothioates, and organophosphates); Metabolic Stimulants (e.g., dichlorphenols); Anticoagulants (e.g., warfarin).

- **2. Location and Prominence.** The Note to Physician should be located in close proximity to the First Aid statements, but should be clearly distinguished from it. In other words, it should not be placed within the First Aid statements, but should appear below the last First Aid statement.
- 3. Contents of Note. The Agency does not provide specific Notes to Physicians except for toxicity category I eye and skin irritants. However, the Agency does provide the following guidance concerning the content of Notes to Physicians. Check the label under review to make certain that it addresses the following information:
  - technical information on symptomatology;
  - use of supportive treatments to maintain life functions;
  - ▶ medicine that will counteract the specific physiological effects of the pesticide;
  - company telephone number to specific medical personnel who can provide specialized medical advice.

# IV. Labeling options

- A. Use Dilutions (Aqueous Solutions only)
  - 1. When Used. Additional Hazards to Humans and Domestic Animals and First Aid statements which correspond with the toxicity categories associated with a product's use dilution may be allowed on product labels provided the conditions below are satisfactorily addressed. Following is guidance for the submission and review of such data and for the content and placement of associated labeling.
  - 2. Data Requirements. All data and draft labeling for use dilution Hazards to Humans and Domestic Animals statements must be sent with a request for pesticide amendment. In some cases, use dilution labeling statements triggered by systemic toxicity (acute oral, dermal or inhalation toxicity) may be supported by extrapolation from the LD50/LC50 for the concentrate. At a minimum the following is required to even consider extrapolating toxicity categories. This information must be submitted by the Registrant with the extrapolation request.
    - (a) A slope calculated from at least three, and preferably more, dose levels having partial responses (i.e., a well characterized dose-response);
    - (b) Dose groups sufficiently large (>5 per group) to allow for the calculation of confidence limits that fall within the defined Toxicity Category boundaries;
    - (c) Extrapolation to higher toxicity categories will only be applied to water dilutions. It should also be determined that there are no other factors affecting the toxicity of the

- EP (e.g., inerts that enhance the absorption of the active ingredient, promote the active ingredient's toxicity, etc.). Other types of extrapolations will be done on a case by case basis.
- (d) Use dilution Hazards to Humans and Domestic Animals statements triggered by skin or eye irritation must be supported by new or cited studies. If another registered diluted product (such as a ready-to-use formulation) has acceptable data and is found similar to the concentrated product after it has been diluted, those data may also be used to support revised labeling.
- **3. Labeling Requirements.** It is not EPA's intent to allow dual sets of Hazards to Humans and Domestic Animals statements and/or First Aid statements on the label. Rather, EPA will allow certain modified statements to be added that are applicable to the most concentrated use dilution only. (40 CFR 156.68(b)) These additional statements (triggered by the toxicity category of the most concentrated use dilution) must be placed directly after the required statements for the concentrate. The following are some examples (in italics) of how use dilution labeling could appear on product labeling:

#### Hazards to Humans and Domestic Animals:

"Causes substantial but temporary eye injury. Do not get in eyes or on clothing. Wear goggles or face shield. *After product is diluted in accordance with the directions for use, goggles or face shield are not required*".

#### First Aid:

"If on skin: Wash with plenty of soap and water. Get medical attention. If product, diluted in accordance with the directions for use, gets on skin, medical attention is not required".

### **B.** Optional Labeling/Deviations

- 1. Optional Hazards to Humans and Domestic Animals Statements. Registrants may submit Hazards to Humans and Domestic Animals statements which reflect specific hazards. (40 CFR 156.70(c)) Such requests must be supported by data (or substantive justification), and should be routed to label reviewers or the Chemistry and Exposure Branch (for PPE). For example, the statements "Do not remove contact lenses, if worn. Get immediate medical attention". would not be approved by the Agency without supporting data or rationale.
- 2. Toxicity Category IV Precautionary Labeling. If the product is all toxicity category IV (non-sensitizer), precautionary labeling statements are normally not required. However, if registrants desire to place precautionary labeling on such a product they may do so. To promote labeling consistency it is recommended that the registrant use precautionary statements triggered by toxicity category III. Registrants

may propose alternate labeling which should be reviewed by precautionary labeling reviewers.

3. Identical or Substantially Similar Product Deviations. If an identical or substantially similar product is citing a product that has optional use dilution hazard statements on the label, those statements are not required on the identical or substantially similar product if the acute toxicity data results are available. Questions about the availability of the acute studies should be referred to the precautionary labeling reviewers.