

Salvage At A Glance, Part II: Non-Paper Based Archival Collections

| Material | Duiomita | Handling | Packing | Drying |
|----------|----------|-------------|---------|--------|
| Materiai | Priority | Precautions | Method | Method |

Cased Photographs

| Cased I Hotogra | | | | |
|-----------------|--|--|--|--|
| Ambrotypes, | Recovery rate is | Handle with | Pack horizontally | Air dry face |
| Pannotypes | low. Immediately dry. | care. Extremely fragile binder. Binder may be on the reverse of the glass. Glass supports. | in a padded container. | (binder side) up with case open. Never freeze. |
| Daguerreotypes | Recovery rate is low. Immediately dry. | Handle with care. Fragile surface and cover glass. | Pack horizontally in a padded container. | Air dry face up with case open. Never freeze. |
| Tintypes | Recovery rate is low. Immediately dry. | Handle with care. Fragile binder. | Horizontally. | Air dry face up with case open. Never freeze. |

Negatives

| regatives | | | | |
|--|--|--|--|---|
| Wet collodion | Recovery rate is | Handle with | Pack horizontally | Air dry emulsion |
| glass plates | low. Immediately dry. | care. Glass supports and fragile binder. | in a padded container. | side up. Never freeze. |
| Gelatin dry plate glass negatives | Freeze or dry within 48 hours. | Handle with care—glass. | If freezing, keep wet. Pack in plastic bags, verti- cally in a padded container. | Air drying pre- ferred; or thaw and air dry; freeze dry. |
| Deteriorated nitrates with soluble binders | Immediately freeze or dry. Recovery rate may be low. | Do not blot. | Pack horizontally. | Air dry; thaw and air dry; test freeze drying. |

| National Park Service | | | | rve O Gram 21/5 |
|--|--|--|---|--|
| Material | Priority | Handling Precautions | Packing Method | Drying Method |
| Deteriorated acetates | Immediately freeze or dry. Recovery rate is low. | Handle carefully—swelling of emulsion. | Pack horizontally. | Air dry; thaw and air dry; test freeze drying. |
| Polyester based film, nitrates and acetates in | Freeze or dry within 48 hours. | Do not touch emulsion with bare hands. | If freezing, keep wet. Pack in small plastic bags | Order of preference: Air dry |

inside boxes.

Thaw and air dry

Freeze dry DO NOT vacuum dry.

Transparencies

good condition

| Lantern slides | Freeze or dry | Handle with | Pack vertically | Air drying pre- |
|-----------------|------------------|------------------|------------------|------------------|
| (glass), silver | within 48 hours. | care—loose bind- | in a padded con- | ferred; thaw and |
| gelatin | | ing tapes and | tainer. | air dry. |
| | | glass. | | |

Color Transparencies

| Color Hunspure | Color Transparencies | | | | | |
|--|---|-------------------------------------|--|---|--|--|
| Additive color | Package to pre- | Handle with | Pack horizontally | Air dry. Never | | |
| transparencies (most are glass) | vent damage. Recovery rate is very poor. Immediately dry. | care—loose binding tapes and glass. | in a padded container. | freeze. | | |
| Chromogenic color transparencies, mounted color slides and sheet films | Freeze or dry within 48 hours. | Handle by mounts or edges. | If freezing, keep wet. Pack in plastic bags inside box. | Order of preference: Air dry Thaw and air dry Freeze dry DO NOT vacuum dry. | | |

Motion Pictures

| | - 0.0 | |
|------------------|--------------------|-------------------|
| Rewash and dry | If freezing, keep | Arrange with a |
| within 48 hours. | wet. Pack in plas- | film processor to |
| | tic pails or poly- | rewash and dry. |
| | propylene bins. | |
| | | |
| | | |

Microforms

| Microfilm rolls | Rewash and dry within 48 hours. | Do not remove from boxes; hold carton together with rubber bands. | If freezing, keep wet. Pack (in blocks of 5) in a polypropylene bin. | Arrange with a microfilm processor to rewash and dry. |
|--------------------------------------|---------------------------------|---|--|---|
| Aperture cards | Freeze or dry within 48 hours. | | If freezing, keep wet. Pack in plastic bags inside boxes. | Air dry or freeze, thaw, and air dry. |
| Jacketed microfilm | Freeze or dry within 48 hours. | | If freezing, keep wet. Pack in plastic bags inside boxes. | Air dry or freeze, thaw, and air dry. |
| Diazo and vesicular microfiche | Freeze or dry within 48 hours. | | Interleave between enve- lopes and pack in milk crates or polypropylene bins. | Air dry or freeze, thaw, and air dry. |

Compact Discs and CD ROMs

| Immediately dry | Do not scratch | Pack vertically | Air dry. |
|-------------------|----------------|-------------------|----------|
| discs. Dry paper | the surface. | in milk crates or | |
| enclosures within | | polypropylene | |
| 48 hours. | | bins. | |
| | | | |

Computer Media

| Tapes | Immediately rinse | Do not touch | Keep tapes wet | Air dry. |
|-------|--------------------|------------------|--------------------|----------|
| | off tapes in clean | magnetic media | in plastic bags. | |
| | water. Dry paper | with bare hands. | Pack vertically in | |
| | boxes and labels | Handle open | plastic crate. | |
| | within 48 hours. | reel tapes by | | |
| | Tapes can stay wet | hubs or reel. | | |
| | for several days. | | | |
| | DO NOT freeze. | | | |
| | | | | |

| Material | Priority | Handling Precautions | Packing Method | Drying Method |
|--------------|---|--|--|------------------|
| Floppy discs | Immediately pack and move to a loca- tion where they can be dried. DO NOT freeze. | Do not touch disk surface with bare hands. | Pack discs wet and keep them wet for transport. Pack vertically in plastic bags or tubs of cold water. | Air dry. |

Sound and Video Recordings

| Sound and | Immediately rinse | Do not touch | Keep tapes wet | Air dry. |
|---------------|----------------------|------------------|--------------------|--------------------|
| videotapes | off tapes with clean | magnetic media | in plastic bags. | |
| | water. Dry paper | with bare hands. | Pack vertically | |
| | boxes and labels | | in milk crates or | |
| | within 48 hours. | | polypropylene | |
| | Tapes can stay wet | | bins. | |
| | for several days. | | | |
| | DO NOT freeze. | | | |
| Shellac and | Immediately dry. | Discs are very | Pack vertically in | Air dry, prefer- |
| Acetate discs | Dry enclosures | fragile. Hold | rigid polyethyl- | ably with a record |
| | within 48 hours. | discs by their | ene foam-padded | cleaning machine. |
| | | edges. Avoid | boxes. | |
| | | shocks. | | |
| Vinyl discs | Dry within 48 | Hold discs by | Pack vertically in | Air dry, prefer- |
| | hours. Freezing is | their edges. | rigid polyethyl- | ably with a record |
| | untested. If it is | Avoid shocks. | ene foam-padded | cleaning machine. |
| | necessary to freeze, | | boxes. | _ |
| | keep at above | | | |
| | 0°F. Freeze or dry | | | |
| | enclosures within | | | |
| | 48 hours. | | | |

This *Conserve O Gram* was adapted from "Salvage Operations for Water Damaged Archival Collections: A Second Glance" and "Salvage at a Glance" in *WAAC Newsletter*, Vol. 19, No. 2, May 1997, by permission of the author, Betty Walsh. http://palimpsest.stanford.edu/waac/wn/wn19/wn19-2/wn19-206.html

The Conserve O Gram series is published as a reference on collections management and curatorial issues. Mention of a product, a manufacturer, or a supplier by name in this publication does not constitute an endorsement of that product or supplier by the National Park Service. Sources named are not all inclusive. It is suggested that readers also seek alternative product and vendor information in order to assess the full range of available supplies and equipment.

The series is distributed to all NPS units and is available to non-NPS institutions and interested individuals on line at http://www.cr.nps.gov/museum/publications/conserveogram/cons_toc.html. For further information and guidance concerning any of the topics or procedures addressed in the series, contact NPS Museum Management Program, 1849 C Street NW (NC 230), Washington, DC 20240; (202) 343-8142.