
## Food Safety Information



## Sausages and Food Safety

**S**ummer sausage, kielbasa, bologna, bratwurst: The list goes on and on. There are so many varieties of sausage. How long can you store them — and where? Are they fully cooked or not? The following background information will answer these questions and others. Use the chart as a guideline for safe storage.

### **Types of Sausages**

Sausages are either uncooked or ready to eat. They can be made from red meat (for example, beef, pork, lamb, or veal), poultry (turkey or chicken, for example) or a combination. Uncooked sausages include fresh (bulk, patties, or links) and smoked sausages.

To prevent foodborne illness, uncooked sausages that contain ground beef, pork, lamb or veal should be cooked to 160 °F. Uncooked sausages that contain ground turkey and chicken should be cooked to 165 °F.

Ready-to-eat sausages are dry, semi-dry, and/or cooked. Dry sausages may be smoked, unsmoked, or cooked. Semi-dry sausages are usually heated in a smokehouse to fully cook the product and partially dry it. Cooked sausages (for example, bologna, and frankfurters) are cooked and may also be smoked.

### Who inspects sausages?

USDA's Food Safety and Inspection Service (FSIS) inspects all sausages in interstate commerce and all sausages that are exported to other countries. If sausages are made in a retail establishment (such as a grocery store, meat market, or restaurant) and are sold within the State where the establishment is located, the sausage may be under the jurisdiction of that State's health or agriculture department.

### What is on the label?

The label provides consumers with information about a product at the time of sale. Labels are required to bear certain mandatory features including:

- (1) the product name;
- (2) an ingredients statement;
- (3) the name and place of business of the manufacturer, packer, or distributor;
- (4) an accurate statement of the net quantity of contents;
- (5) the inspection legend and USDA establishment number;
- (6) a safe handling statement if the product is perishable (for example, "Keep Frozen" or "Keep Refrigerated");
- (7) safe handling instructions, if the meat or poultry component of the product is not ready to eat; and
- (8) nutrition facts information. The Nutrition Facts information on the label can help consumers compare products and make more informed, healthy food choices. If sausages are made and packaged in a local store, the nutrient information on the package is voluntary or it may be at the point of purchase. The application of a "use" or "sell by" date is optional.

### What must be listed on the label of sausages that are NOT ready to eat?

The labeling for sausages under FSIS inspection that are NOT ready to eat must bear certain features such as safe handling instructions. In cases where the sausage is partially cooked or otherwise appears cooked but requires cooking by the consumer for safety, FSIS requires additional labeling features such as a prominent statement on the principal display panel, for example, "Uncooked, Ready to cook, Cook before eating, Cook and serve," or "Needs to be fully cooked."

In addition, the product should display cooking directions that are sufficient for the intended user. The manufacturer would have to validate that the cooking directions are sufficient to destroy any pathogens that could be present.

If a sausage is perishable, the label must say "Keep Refrigerated." Some federally inspected shelf-stable sausages are not ready to eat. If so, they will be labeled as above but will not have "Keep Refrigerated" on the label.

## Definition of Fresh Sausages

Fresh sausages are a coarse or finely "comminuted" (reduced to minute particles) meat food product prepared from one or more kinds of meat, or meat and meat "byproducts" (heart, kidney, or liver, for example). They may contain water not exceeding 3% of the total ingredients in the product. They are usually seasoned, frequently cured, and may contain binders and extenders (for example, wheat flour, and non-fat dry milk). They must be kept refrigerated and thoroughly cooked before eating.

## Content of Fresh Sausages

- "Fresh Pork Sausages" may not contain pork byproducts and may contain no more than 50% fat by weight.
- "Fresh Beef Sausages" may not contain beef byproducts and may contain no more than 30% fat by weight.
- "Breakfast Sausages" may contain meat and meat byproducts and no more than 50% fat by weight.
- "Whole Hog Sausage" contains meat from swine in such proportions as are normal to a single animal and no more than 50% fat by weight.
- "Italian Sausage Products" are cured or uncured sausages containing at least 85% meat, or a combination of meat and fat, with the total fat content constituting not more than 35% of the finished product. It contains salt, pepper, fennel and/or anise and no more than 3% water. Optional ingredients permitted in Italian Sausages are spices (including paprika) and flavorings, red or green peppers, onions, garlic and parsley, sugar, dextrose and corn syrup.

# Cooked and/or Smoked Sausages

Cooked and/or smoked sausages are made of one or more different kinds of chopped or ground meats which have been seasoned, cooked and/or smoked. Meat byproducts may be used. Included in this category are:

- liverwurst
- hot dogs
- bologna
- knockwurst
- cooked bratwurst
- braunschweiger
- cooked Thuringer
- cooked salami\*

\*Cooked Salami (not dry) is made from fresh meats which are cured, stuffed into casings and cooked in a smokehouse at high temperature. It may be air dried for a short time. It has a softer texture than dry and semi-dry sausages and must be refrigerated.

### **Meat Specialties**

Some meat specialties are ready-to-eat sausage-like products. These are made from comminuted meats that are seasoned and usually cooked or baked rather than smoked. They are usually sliced and served cold. Included in this category are:

- chopped ham loaf
- peppered loaf
- head cheese
- jellied corned beef
- ham and cheese loaf
- honey loaf
- old fashioned loaf
- olive loaf
- pickle and pimento loaf
- scrapple
- souse
- veal loaf

## Dry and Semi-Dry Sausages

Dry and semi-dry sausages are possibly the largest category of dried meats, particularly in the United States. These products can be fermented by bacterial growth for preservation and to produce the typical tangy flavor. Alternatively, they may be cultured with lactic acid — much as cheese, pickle, and yogurt makers do — to eliminate the fermentation phase and shorten the process. They are, with a few exceptions, cooked.

Fermentation is one of the oldest methods of preserving meats. Dry sausages — such as pepperoni, and semidry sausages such as Lebanon bologna and summer sausage, have had a good safety record for hundreds of years.

In this procedure, a mixture of curing ingredients, such as salt and sodium nitrite, and a "starter" culture of lactic acid-bacteria, is mixed with chopped and ground meat, placed in casings, fermented, and then dried by a carefully controlled, long, continuous air-drying process. The amount of acid produced during fermentation and the lack of moisture in the finished product after drying typically have been shown to cause pathogenic bacteria to die.

Dry sausages require more time to make than other types of sausages and are a more concentrated form of meat. Dried sausages range from 60% to 80% of their original weight before drying.

Semi-dry sausages are usually heated in the smokehouse to fully cook the product and partially dry it. Semi-dry sausages are semi-soft sausages with good keeping qualities due to their lactic acid fermentation and sometimes heavy application of smoke. Some are mildly seasoned, and some are quite spicy and strongly flavored.

# What are examples of dry and semi-dry sausages?

Dry sausages include:

- Sopressata (a name of a salami)
- pepperoni (not cooked, air dried)
- Genoa Salami (Italian, usually made from pork but may have a small amount of beef; it is moistened with wine or grape juice and seasoned with garlic)

#### Semi-dry sausages include:

- summer sausage
- Lebanon bologna
- Cervelat
- Thuringer

## Are any sausages shelf Stable?

Some dry sausages are shelf stable (in other words, they do not need to be refrigerated or frozen to be stored safely). Dry sausages require more production time than other types of sausage and result in a concentrated form of meat. If the product is shelf stable and ready to eat, the product is not required to have a safe handling statement, cooking directions or a "Keep Refrigerated" statement.

## Should people "at risk" eat dry sausages?

Because dry sausages are not cooked, people "at risk" (older adults, very young children, pregnant women, and those with immune systems weakened by disease or organ transplants) might want to avoid eating them. The bacterium *E. coli* O157:H7 can survive the process of dry fermenting, and in 1994, some children became ill after eating dry cured salami containing the bacteria.

After the outbreak, FSIS developed specific processing rules for making dry sausages that must be followed or the product must be heat treated. These products are included in the FSIS microbial sampling program for E. coli O157:H7, and in 1997, FSIS began to test fermented sausages for *Salmonella* and *Listeria monocytogenes*.

# Dates on Packaged Sausages

Although dating is a voluntary program and not required by the Federal government, if a date is used, it must state what the date means. The product can be used after the date, provided it was stored safely. Follow the guidelines on the following page for maximum quality in sausage products.

- "Sell-By" date tells the store how long to display the product for sale. You should buy the product before the date expires.
- "Best if Used By (or Before)" date date by which the product should be used for best flavor and quality. It is not a purchase or safety date.
- "Use-By" date the last date recommended for use of the product while at peak quality.

### **Storage**

All sausage — except dry sausage — is perishable and therefore must be kept refrigerated. For maximum quality, follow the storage times in the Sausage Storage Chart.

### SAUSAGE STORAGE CHART

- If the sausage has a "use-by" date, follow that date. It is the last date recommended for the use of the product while at peak quality. The date has been determined by the manufacturer of the product.
- If the sausage has a "sell-by" date, or no date, store it for the times recommended below.
- Freeze sausage if you can't use it within times the times recommended for refrigerator storage. Once frozen it doesn't matter if the date expires because foods kept frozen continuously are safe indefinitely.

| TYPE OF SAUSAGE                          | REFRIGERATOR -<br>UNOPENED                              | REFRIGERATOR -<br>AFTER OPENING | IN FREEZER<br>(for best quality) |
|--|---|---------------------------------|----------------------------------|
| Fresh Sausage, uncooked                  | 1 to 2 days unopened or opened                          | 1 to 2 days unopened or opened  | 1 to 2 months                    |
| Fresh Sausage, after cooking by consumer | (not applicable)  | 3 to 4 days                     | 2 to 3 months                    |
| Hard/Dry Sausage                         | Whole, 6 weeks in pantry; indefinitely in refrigerator. | 3 weeks                         | Sliced,<br>1 to 2 months         |
| Hot Dogs and other Cooked<br>Sausage     | 2 weeks   | 7 days                          | 1 to 2 months                    |
| Luncheon meat                            | 2 weeks   | 3 to 5 days                     | 1 to 2 months                    |
| Summer Sausage (Semi-dry)                | 3 months  | 3 weeks                         | 1 to 2 months                    |

## **Food Safety Questions?**

### **Call the USDA Meat & Poultry Hotline**

If you have a question about meat, poultry, or egg products, call the USDA Meat and Poultry Hotline toll free at

1-888-MPHotline (1-888-674-6854)

The hotline is open year-round

Monday through Friday from 10 a.m. to 4 p.m. ET (English

or Spanish).
Recorded food safety
messages are available 24 hours a day.
Check out the
FSIS Web site at

www.fsis.usda.gov.

Send E-mail questions to **MPHotline.fsis@usda.gov**.

### **Ask Karen!**

FSIS' automated response system can provide food safety information 24/7 and a

live chat during Hotline hours.



AskKaren.gov

PregunteleaKaren.gov

FSIS encourages the reprint and distribution of this publication for food safety purposes. However, the included image from PhotoDisc, used under license, is protected by the copyright laws of the U.S., Canada, and elsewhere, and may not be saved or downloaded except for printing of this publication.

The USDA is an equal opportunity provider and employer.

Revised May 2011