

FEDERAL REQUIREMENTS FOR ASBESTOS MANAGEMENT IN SCHOOLS

EPA Regional Asbestos Coordinators

EPA Region 1 One Congress Street Suite 1100 Boston, MA 02114

EPA Region 2 290 Broadway, 21st Floor New York, NY 10007

EPA Region 3 1650 Arch Street Philadelphia, PA 19103

EPA Region 4 61 Forsyth Street, S.W. Atlanta, GA 30303-8960

EPA Region 5 77 West Jackson Blvd. Chicago, IL 60604

EPA Region 6 1445 Ross Avenue Dallas, TX 75202

EPA Region 7 901 N. 5th Street Kansas City, KA 66101

EPA Region 8 999 - 18th Street, Suite 300 Denver, CO 80202

EPA Region 9 75 Hawthorne Street San Francisco, CA 94105

EPA Region 10 1200 Sixth Street Seattle, WA 98101 Information on Compliance with AHERA Requirements for Superintendents of Schools, Headmasters, Directors, Asbestos Inspectors & Management Planners

The Environmental Protection Agency (EPA) has developed this guidance to help Local Education Agencies (LEAs) achieve compliance with the Asbestos-Containing Materials in Schools regulation (40 CFR Part 763).

These regulations, in effect since 1986, require that public and not-for-profit non-public, elementary and secondary schools be inspected to determine the presence of asbestos-containing building materials and that asbestos management plans be developed as a result of those inspections. State requirements may vary. Contact your state agency for more information.



EPA Asbestos Line

1-800-471-7127

EPA Asbestos in Schools Website

http://www.epa.gov/asbestos/ asbestos_in_schools.html

Designated Person

The **Local Education Agency** (LEA) must designate a person (designated person) to ensure that the responsibilities of the LEA, as detailed in the regulations, are properly implemented.

- The LEA must verify that this individual has received proper training. The individual is not required to be a licensed asbestos consultant. There is no specific training course for the designated person; however, the EPA has developed a "Designated Person's Self-Study Guide" that details the required specific background knowledge the designated person must have. You can find this guide at http://www.epa.gov/asbestos/schools.html.
- The **Asbestos Management Plan** (AMP) for schools must include a true and correct statement signed by the designated person certifying that the general responsibilities of the LEA have been or will be met.
- In the event that the designated person leaves his or her position, the LEA *must ensure* that a new individual is identified and appropriately trained to serve as the designated person. The newly identified designated person must then sign the aforementioned statement of certification. The designated person must have a basic knowledge of the health effects of asbestos, the detection, identification and assessment of asbestoscontaining material, options for controlling asbestos-containing material, asbestos management programs, and relevant federal and state regulations concerning asbestos.


Reinspection

The LEA must retain the services of a licensed asbestos inspector or management planner to conduct a reinspection every **three** years subsequent to implementation of a management plan.

• Triennial reinspections must include an inspection of each area of every building that is leased, owned, or otherwise used as a school building.

Written Notification Regarding Availability of the AMP

At least once each school year, the LEA must provide written notification to parent, teacher, and employee organizations regarding the availability of the Abestos Management Plan and any response actions taken or planned.





The AMP must describe the steps taken to notify parents, teachers and employee organizations. Acceptable methods of notification include placing a notice in the school handbook, mailing a letter to each household, or placing an ad in a local paper.



Periodic Surveillance

After the AMP has been implemented, the LEA must conduct periodic surveillance in each building that it leases, owns, or otherwise uses as a school building at least once every six months.







Custodial & Maintenance Training and Short-Term Worker

All maintenance and custodial staff who may work in a building that contains asbestos-containing building materials (ACBM) must receive at least **two** hours of asbestos awareness training whether or not they are required to work with ACBM.

Maintenance and custodial staff conducting any activities that will result in the disturbance to ACBM must receive an additional fourteen hours of training.



- The LEA must ensure that new custodial and maintenance employees are trained within **sixty** days after commencement of employment.
- The LEA must ensure that short-term workers who may come in contact with asbestos (e.g. utility repair workers) are informed of the location of ACBM.



Record-Keeping Requirement

The LEA must maintain records required by the regulations to be included in the Asbestos Management Plan. This includes:

- a copy of prior inspection and/or reinspection reports;
- documentation related to the training provided to custodial and maintenance employees;
- periodic surveillance forms;
- dated statements regarding operations and maintenance activities;
- a copy of the annual notice of the management plan availability;
- a copy of all reports on response actions taken; and
- a copy of the updated management plan in each school.

Compliance/Enforcement

EPA is committed to providing assistance to LEAs to ensure compliance with regulatory requirements. While it is the goal of EPA to provide LEAs with assistance in achieving regulatory compliance voluntarily, LEAs that fail to comply with existing regulatory requirements will be subject to enforcement action. Contact your Regional Asbestos Coordinator for more information.



