



Gay and bisexual men — referred to in CDC surveillance systems as men who have sex with men (MSM)¹ — of all races continue to be the risk group most severely affected by HIV. CDC's most recent data show that between 2006 and 2009, the number of new infections that occur each year increased among young MSM — driven by an alarming 48 percent increase among young, black MSM 13 to 29 years old. These data clearly show the urgent need to expand access to proven HIV prevention programs for gay and bisexual men, and to develop new approaches to fight HIV in this population.


A Snapshot

1

- ▶ MSM account for nearly half of the 1.1 million people living with HIV in the United States (52%, or an estimated 592,100 total persons).
- ▶ MSM account for more than half of all new HIV infections in the United States each year (61%, or an estimated 29,300 infections).
- ▶ While CDC estimates that only 4 percent of men in the United States are MSM, the rate of new HIV diagnoses among MSM in the United States is more than 44 times that of other men (range: 522–989 per 100,000 MSM vs. 12 per 100,000 other men).

Estimated New HIV Infections in the U.S., 2009, for the Most-Affected Subpopulations*

Gay and bisexual men of all races and black heterosexuals account for the greatest number of new HIV infections in the United States.



*Subpopulations representing 2 percent or less of the overall U.S. epidemic are not reflected in this chart.

Source: CDC


CDC FACT SHEET

► According to the latest estimates, white MSM represent the largest number of new HIV infections (11,400) in the United States, followed closely by black MSM (10,800) and Hispanic MSM (6,000).



- ▶ The primary ages at which MSM become infected differ by race:
 - Young Black MSM: The majority of new infections among black MSM occur among young black MSM aged 13 to 29 (6,500). In fact, more new infections occur among young black MSM than white MSM aged 13 to 29 and 30 to 39 combined (6,400).
 - White MSM: New infections among white MSM occur at roughly the same levels among all age groups (aged 13-29, 30-39, and 40-49), ranging from 3,200 to 3,400 in each group.
 - Young Hispanic MSM: Among Hispanic MSM, most new infections occur in the youngest (13–29) age group (2,700), though a substantial number of new HIV infections also occur among those aged 30 to 39 (2,000).
- ► In a study of 21 major U.S. cities in 2008, MSM had high levels of HIV infection, and many of those infected with HIV did not know it.
 - Overall, one in five MSM participating in the study was infected (19 percent). While MSM of all races and ethnicities were severely affected, black MSM were particularly impacted.
 - Among those who were infected, nearly half (44 percent) were unaware of their HIV status.
 Young MSM and MSM of color were least likely to know they were infected.
- ► AIDS continues to claim the lives of too many MSM. Since the beginning of the epidemic, more than 296,000 MSM with AIDS have died.

Estimated Number of New HIV Infections among Men Who Have Sex with Men (MSM), 2009, by Race/Ethnicity and Age



†The estimate for each age range within a race/ethnicity group was calculated independently from the overall estimate for that group. Therefore, the sum of the estimates by age range may not equal CDC's official incidence estimate for a race/ethnicity group.

Complex Factors Increase Risk

- ▶ High prevalence of HIV: The existing high prevalence of HIV among gay and bisexual men means MSM face a greater risk of being exposed to infection with each sexual encounter, especially as they get older. For young black MSM, partnering with older black men (among whom HIV prevalence is high) may also lead to increased risk.
- ▶ Lack of knowledge of HIV status: Studies show that individuals who know they are infected take steps to protect their partners. Yet many MSM are unaware of their status and may unknowingly be transmitting the virus to others. Additionally, some MSM may make false assumptions or have inaccurate information about their partner's HIV status. It is critical to ensure that sexually active MSM get tested for HIV at least annually, or more frequently as needed.
- ▶ Complacency about risk: Among young MSM in particular, complacency about HIV may play a key role in HIV risk, since these men did not personally experience the severity of the early AIDS epidemic. Additional challenges for many MSM include maintaining consistently safe behaviors over time, underestimating personal risk, and the false belief that because of treatment advances, HIV is no longer a serious health threat. We must reach each generation of MSM and develop programs that can help MSM remain uninfected throughout the course of their lives.

2 JUNE 2012

CDC FACT SHEET

▶ Social discrimination and cultural issues: For some MSM, social and economic factors, including homophobia, stigma, and lack of access to health care may increase risk behaviors or be a barrier to receiving HIV prevention services.



▶ Substance abuse: Some MSM use alcohol and illegal drugs, contributing to increased risk for HIV infection and other STDs. Substance use can increase the risk for HIV transmission through risky sexual behaviors while under the influence and through sharing needles or other injection equipment.

HIV: Protect Yourself

Be smart about HIV. Here's what you can do to reduce your risk of infection:

Get the facts — Arm yourself with basic information: Are you at risk? How is HIV spread? How can you protect yourself?

Take control — You have the facts; now protect yourself and your loved ones. There are three essential ways to reduce your risk:

- 1. Don't have sex (i.e., anal, vaginal or oral)
- Only have sex (i.e., anal, vaginal or oral) if you're in a mutually monogamous relationship with a partner you know is not infected
- 3. Use a condom every time you have anal, vaginal or oral sex. (Correct and consistent use of the male latex condom is highly effective in reducing HIV transmission.)

Put yourself to the test — Knowing your HIV status is a critical step toward stopping HIV transmission, because if you know you are infected, you can take steps to protect your

partners. Also, if you are infected, the sooner you find out, the sooner you can receive life-extending treatment. In fact, CDC recommends that all adults and adolescents be tested for HIV. Because other STDs can play a role in the acquisition of HIV, knowing whether you are infected with either is critical in reducing your risk for infection.

Call 1-800-CDC-INFO or visit www.hivtest.org to find HIV and STD testing locations near you.

Start talking — Talk to everyone you know about HIV — friends and family, coworkers and neighbors, at work and at places of worship. Have ongoing and open discussions with your partners about HIV testing and risk behaviors. Talking openly about HIV can reduce the stigma that keeps too many from seeking the testing, prevention and treatment services, and support they need.

HIV doesn't have to become part of your life. Each of us can and must be part of the solution.

Visit www.actagainstaids.org for more information about HIV and what you can do to stop HIV.

If you are a member of the news media and need more information, please visit www.cdc.gov/nchhstp/Newsroom or contact the News Media Line at CDC's National Center for HIV/AIDS, Viral Hepatitis, STD, and TB Prevention (404-639-8895 or NCHHSTPMediaTeam@cdc.gov).

3 JUNE 2012