

# Prevention of Significant Deterioration and Title V Greenhouse Gas Tailoring Rule



Joseph Mangino
Operating Permits Group
Office of Air and Radiation
Office of Air Quality Planning and Standards
June 2010



#### **Overview of Presentation**

- The final Tailoring Rule
- Covered pollutants
- Phase steps to include GHG PSD coverage for large sources
- Permitting for small sources and study to assess GHG permitting in the future
- State implementation considerations
- Other topics addressed
  - Timing for permit streamlining techniques
  - Requests for higher category—specific thresholds and exemptions from applicability
  - Transitional issues including requests for grandfathering
  - PSD GHG technical information and guidance



## The Final Tailoring Rule

- Issued on May 13, 2010
- "Tailors" the requirements to focus PSD and title V permit requirements on the largest emitting facilities
- Subjects facilities responsible for nearly 70 percent of the national GHG emissions from stationary sources to CAA permitting requirements
  - This includes the nation's largest GHG emitters—power plants, refineries, and cement production facilities
  - Small farms, restaurants, and commercial facilities are shielded by this rule



#### **Pollutants Covered**

- Sets thresholds for GHG emissions, addressing emissions from six well-mixed GHGs:
  - Carbon dioxide (CO<sub>2</sub>)
  - Methane (CH<sub>4</sub>)
  - Nitrous oxide (N<sub>2</sub>O)
  - Hydrofluorocarbons (HFCs)
  - Perfluorocarbons (PFCs)
  - Sulfur hexafluoride (SF<sub>6</sub>)
- The aggregate sum of these six GHGs is the identified air pollutant in EPA's Light-Duty Vehicle Rule, and the associated Endangerment Finding and Cause or Contribute Finding
- To determine applicability, a source's GHG emissions are calculated as the sum of the six gases on a CO<sub>2</sub> equivalent (CO<sub>2</sub>e) basis and compared against the relevant threshold



## Phase-In Steps: Step 1

- January 2, 2011 to June 30, 2011
- No new permitting actions due solely to GHG emissions during this time period; only sources undertaking permitting actions anyway for other pollutants will need to address GHG
  - PSD permitting applicability:
    - Anyway sources will be subject to the PSD requirements only if they increase GHG emissions by 75,000 tpy CO<sub>2</sub>e or more
  - Title V permitting applicability:
    - Only those sources currently with title V permits will address GHGs, and only when applying for, renewing or revising their permits
- No sources will be subject to CAA permitting requirements based solely on GHG emissions
- Covers sources responsible for 65% of total national stationary source GHG emissions



## Phase-In Steps: Step 2

- July 1, 2011 to June 30, 2013
- Sources subject to GHG permitting requirements under step 1 will continue to be subject to GHG permitting requirements
- In addition, sources that emit or have the potential to emit GHGs at or above 100,000 tpy CO<sub>2</sub>e will also be subject to GHG permitting requirements as follows.
- PSD permitting applicability triggered with construction that increases emissions
  - A newly constructed source (which is not major for another pollutant) will not be subject to PSD unless it emits 100,000 tpy or more on a CO<sub>2</sub>e basis
  - A modification project at a major stationary source will not be subject to PSD unless it results in a net GHG emissions increase of 75,000 tpy or more on a CO<sub>2</sub>e basis



## Phase-In Steps: Step 2 (cont'd.)

- Title V permitting applicability
  - A GHG emission source (which is not already subject to title V) will not be subject to title V unless it emits 100,000 tpy or more on a CO<sub>2</sub>e basis.
  - These newly subject sources must apply within 1 year after becoming subject to the program, unless the permitting authority sets an earlier deadline.
  - This means that newly subject sources must apply for a title V permit on or before July 1, 2012 (which is one year from July 1, 2011).
- Covers sources responsible for nearly 70% of total national stationary source GHG emissions



## Phase-In Steps: Step 3

- The rule establishes an enforceable commitment to complete another rulemaking no later than July 1, 2012.
- We will propose or solicit comment on a possible step 3 of the phase-in plan
  - EPA will consider, during the implementation of step 2, whether it will be possible to administer GHG permitting programs for additional sources.
  - EPA will establish that step 3 would take effect on July 1, 2013 so that permitting authorities and sources can prepare for any additional GHG permitting action.
- Step 3, if different from step 2, will not require permitting of sources with GHG emissions below 50,000 tpy CO<sub>2</sub>e
- We also commit to explore a wide range of streamlining options on which we plan to take comment in the step 3 proposal
- In addition, we plan to solicit comment on a permanent exclusion of certain sources from PSD, title V or both




#### **Phase-in Steps: Further Action**

- EPA will not require permits for smaller sources until April 30, 2016 or later
- The rule establishes an enforceable commitment for EPA to complete a study within 5 years projecting the administrative burdens that remain for small sources after EPA has had time to develop (and states have had time to adopt) streamlining measures to reduce the permitting burden for such sources
- We will use this study to serve as the basis for an additional rulemaking that would take further action to address small sources, as appropriate. We are making an enforceable commitment to complete this rulemaking by April 30, 2016



#### Permitting Steps under the Tailoring Rule





#### **Newly-Subject Sources**

- The newly-subject sources in Step 2 are expected to include:
  - Large industrial sources from energy-intensive source categories that have not triggered permitting programs for their non-GHG emissions
  - The largest landfills
  - The largest coal mines or oil and gas production installations
- The title V costs for these sources will be less than \$10 million nationwide
  - Without the Tailoring Rule, there would have been millions of newly-subject sources and the costs would have been in the tens of billions of dollars
  - Title V does not trigger any new control requirements
- These sources will not trigger PSD unless they construct or modify in a way that significantly increases emissions
  - If they do trigger PSD, BACT decisions made by permitting authorities (usually state/local agencies) must take costs into account



## **State Implementation**

- Comments received from States and NACAA explained even if EPA changed the federal PSD applicability thresholds and limited the scope of EPA approval of SIPs consistent with "tailored" thresholds—state rules containing the originally approved statutory thresholds would continue to apply as matter of state law.
- Rule addresses this state law issue by adding another mechanism to implement the tailoring approach for PSD
- Definition of "subject to regulation" so that the GHGs emitted by sources that fall below the tailoring thresholds are not treated as "subject to regulation".
- To the extent state law has similar language, we think states may adopt EPA's approach by interpreting the phrase "subject to regulation" to mean the same as EPA's meaning for GHGs.



## State Implementation (cont'd)

- "Subject to regulation" approach facilitates more rapid adoption and implementation of the tailoring rule thresholds by states before January 2, 2011
  - States may be able to implement tailoring rule thresholds without the need for additional rulemaking
- EPA will also take steps to ensure that programs do not automatically apply to sources below the tailoring rule thresholds under federal law
- 60 Day Letters: EPA requests states to submit information to appropriate EPA Regional Administrator within 60 days after the date of publication of the Tailoring Rule in Federal Register
  - States should explain whether they will apply the meaning of term "subject to regulation" as established by EPA for GHGs for both PSD and Title V
  - If yes, whether state intends to do so without undertaking regulatory or legislative process
  - If state must revise its statutes or regulations to implement Tailoring Rule, provide an estimate to time needed to do so



#### Other Actions and Issues

- Timing for Permit Streamlining Techniques
  - We intend to pursue streamlining options as expeditiously as possible, beginning immediately and proceeding throughout the phase-in period, and we encourage permitting authorities to do the same.
- Requests for Higher Category-Specific Thresholds and Exemptions from Applicability
  - We are not providing exemptions from applicability determinations (major source and major modification) under title V and PSD for certain GHG emission sources, emission activities, or types of emissions at this time
- Transitional Issues including Requests for Grandfathering
  - This rule does not contain any additional exemptions or grandfathering provisions addressing the transition to PSD and title V permitting for GHGs



#### **PSD GHG Technical Information and Guidance**

#### Summer and Fall 2010:

- Initial technical data and information concerning available and emerging GHG control measures
  - GHG Mitigation Strategies Database
  - RACT/BACT/LAER Clearinghouse enhancements
  - GHG technical white papers that will provide information on control techniques and measures for the largest GHG emitting industrial sectors (e.g., power plants, industrial boilers, cement plants, refineries, iron and steel, pulp and paper and nitric acid plants)
- Before end of 2010: General guidance for applying the PSD requirements, including BACT, for GHGs and training work shops with example BACT analyses for EPA Regions and States



## Additional Questions?

- EPA point of contacts on the Tailoring Rule, its implementation and development of GHG PSD guidance and technical information
  - Juan Santiago, <u>santiago.juan@epa.gov</u>; (919) 541- 1084
  - Joseph Mangino, <u>mangino.joseph@epa.gov</u>; (919) 541-9778
- EPA's website- www.epa.gov/nsr