Recommended intervals between administration of **immune globulin preparations** and **measles-** or **varicella-containing vaccine**

Product / Indication	Dose, including mg immunoglobulin G (IgG)/kg body weight	Recommended interval before measles or varicella-containing ¹ vaccine administration
Botulinum Immune Globulin Intravenous (Human)	1.5 mL/kg (75 mg lgG/kg) IV	6 months
Tetanus IG (TIG)	250 units (10 mg IgG/kg) IM	3 months
Hepatitis A IG		
- Contact prophylaxis	0.02 mL/kg (3.3 mg IgG/kg) IM	3 months
- International travel	0.06 mL/kg (10 mg lgG/kg) IM	3 months
Hepatitis B IG (HBIG)	0.06 mL/kg (10 mg lgG/kg) IM	3 months
Rabies IG (RIG)	20 IU/kg (22 mg IgG/kg) IM	4 months
Varicella IG	125 units/10 kg (60-200 mg IgG/kg) IM, maximum 625 units	5 months
Measles prophylaxis IG		
- Standard (i.e., nonimmunocompromised) contact	0.25 mL/kg (40 mg lgG/kg) IM	5 months
- Immunocompromised contact	0.5 mL/kg (80 mg lgG/kg) IM	6 months
Blood transfusion		
- Red blood cells (RBCs), washed	10 mL/kg (negligible IgG/kg) IV	None
- RBCs, adenine-saline added	10 mL/kg (10 mg IgG/kg) IV	3 months
- Packed RBCs (hematocrit 65%) ²	10 mL/kg (60 mg IgG/kg) IV	6 months
- Whole blood (hematocrit 35%-50%) ²	10 mL/kg (80-100 mg IgG/kg) IV	6 months
- Plasma/platelet products	10 mL/kg (160 mg lgG/kg) IV	7 months
Cytomegalovirus IGIV	150 mg/kg maximum	6 months
IGIV		
- Replacement therapy for immune deficiencies ³	300-400 mg/kg IV	8 months
- Immune thrombocytopenic purpura treatment	400 mg/kg IV	8 months
- Immune thrombocytopenic purpura treatment	1,000 mg/kg IV	10 months
- Kawasaki disease	2 g/kg IV	11 months
- Postexposure varicella prophylaxis ⁴	400 mg/kg IV	8 months
Monoclonal antibody to respiratory syncytial virus F protein (Synagis™) ⁵	15 mg/kg (IM)	None

This table is not intended for determining the correct indications and dosages for using antibody-containing products. Unvaccinated persons might not be fully protected against measles during the entire recommended interval, and additional doses of IG or measles vaccine might be indicated after measles exposure. Concentrations of measles antibody in an IG preparation can vary by manufacturer's lot. Rates of antibody clearance after receipt of an IG preparation also might vary. Recommended intervals are extrapolated from an estimated half-life of 30 days for passively acquired antibody and an observed interference with the immune response to measles vaccine for 5 months after a dose of 80 mg IgG/kg.

1 Does not include zoster vaccine. Zoster vaccine may be given with antibody-containing blood products.

- 2 Assumes a serum IgG concentration of 16 mg/mL.
- 3 Measles and varicella vaccinations are recommended for children with asymptomatic or mildly symptomatic human immunodeficiency virus (HIV) infection, but are contraindicated for persons with severe immunosuppression from HIV or any other immunosuppressive disorder.
- 4 The investigational product VariZIG, similar to licensed VZIG, is a purified human IG preparation made from plasma containing high levels of anti-varicella antibodies (IgG). The interval between VariZIG and varicella vaccine (Var or MMRV) is 5 months.

5 Contains antibody only to respiratory syncytial virus