

Guidance for Industry
IMPURITIES IN NEW VETERINARY
DRUG SUBSTANCES (Revision)
VICH GL10(R)

REVISED FINAL GUIDANCE

Comments and suggestions regarding the document should be submitted to Division of Dockets Management (HFA-305), Food and Drug Administration, 5630 Fishers Lane, Rm. 1061, Rockville, MD 20852. Submit electronic comments to <http://www.regulations.gov>. All comments should be identified with the Docket No. 1999D-2215.

For questions regarding this document, contact Dennis Bensley, Center for Veterinary Medicine, (HFV-143), Food and Drug Administration, 7500 Standish Place, Rockville, MD 20855, 240-276-8268, e-mail: dennis.bensley@fda.hhs.gov.

Additional copies of this final guidance document may be requested from the Communications Staff (HFV-12), Center for Veterinary Medicine, Food and Drug Administration, 7519 Standish Place, Rockville, MD 20855, and may be viewed on the Internet at <http://www.fda.gov/AnimalVeterinary/GuidanceComplianceEnforcement/GuidanceforIndustry/default.htm>.

U.S. Department of Health and Human Services
Food and Drug Administration
Center for Veterinary Medicine
November 26, 2007



International Cooperation on Harmonisation of Technical Requirements for Registration of Veterinary Medicinal Products

VICH GL10 (QUALITY)
September 2007
Revision at Step 9

IMPURITIES IN NEW VETERINARY DRUG SUBSTANCES (REVISION)

Revised at Step 9
by the VICH Steering Committee in September 2007

This revised Guidance has been developed by the appropriate VICH Expert Working Group and is subject to consultation by the parties, in accordance with the VICH Process. At Step 9 of the Process the final draft will be recommended for adoption to the regulatory bodies of the European Union, Japan and USA.

TABLE OF CONTENTS

1. INTRODUCTION	4
2. CLASSIFICATION OF IMPURITIES	5
3. RATIONALE FOR THE REPORTING AND CONTROL OF IMPURITIES	5
3.1 Organic Impurities	5
3.2 Inorganic Impurities	6
3.3 Solvents	6
4. ANALYTICAL PROCEDURES	6
5. REPORTING IMPURITY CONTENT OF BATCHES	7
6. LISTING OF IMPURITIES IN SPECIFICATIONS	8
7. QUALIFICATION OF IMPURITIES	9
8. GLOSSARY	11
Attachment 1 - Thresholds	13
Attachment 2 - Illustration of Reporting Impurity Results for Identification and Qualification in an Application	14
Attachment 3 - Decision Tree for Identification and Qualification	15

VICH GL10(R)
Impurities in New Veterinary Drug Substances (Revision)

This guidance represents the Food and Drug Administration's (FDA's) current thinking on the subject matter. It does not create or confer any rights for or on any person and does not operate to bind FDA or the public. You can use an alternative approach if the approach satisfies the requirements of the applicable statute(s) and regulation(s). If you want to discuss an alternative approach, contact the FDA staff responsible for implementing this guidance. If you cannot identify the appropriate FDA staff, call the appropriate number listed on the title page of this guidance.

1. INTRODUCTION

This document is intended to provide guidance to registration applicants on the content and qualification of impurities in new veterinary drug substances intended to be used for new veterinary medicinal products, produced by chemical syntheses and not previously registered in a country, region, or member state. This guidance does not address new veterinary drug substances used during the clinical research stage of development. The following types of new veterinary drug substances are not covered in this guidance: biological/biotechnological, peptide, oligonucleotide, radiopharmaceutical, fermentation products and semi-synthetic products derived therefrom, herbal products, and crude products of animal or plant origin.

Impurities in new veterinary drug substances are addressed from two perspectives:

Chemistry Aspects including classification and identification of impurities, report generation, listing of impurities in specifications, and a brief discussion of analytical procedures; and

Safety Aspects including specific guidance for qualifying those impurities that were not present, or were present at substantially lower levels, in batches of a new veterinary drug substance used in safety and clinical studies.

FDA's guidance documents, including this guidance, do not establish legally enforceable responsibilities. Instead, guidances describe the Agency's current thinking on a topic and should be viewed only as recommendations, unless specific regulatory or statutory requirements are cited. The use of the word "should" in Agency guidances means that something is suggested or recommended, but not required.

Contains Non-Binding Recommendations

2. CLASSIFICATION OF IMPURITIES

Impurities can be classified into the following categories:

- Organic impurities (process- and drug-related)
- Inorganic impurities
- Residual solvents

Organic impurities can arise during the manufacturing process and/or storage of the new veterinary drug substance. They can be identified or unidentified, volatile or non-volatile, and include:

- Starting materials
- By-products
- Intermediates
- Degradation products
- Reagents, ligands and catalysts

Inorganic impurities can result from the manufacturing process. They are normally known and identified and include:

- Reagents, ligands and catalysts
- Heavy metals or other residual metals
- Inorganic salts
- Other materials (e.g., filter aids, charcoal)

Solvents are inorganic or organic liquids used as vehicles for the preparation of solutions or suspensions in the synthesis of a new veterinary drug substance. Since these are generally of known toxicity, the selection of appropriate controls is easily accomplished (see guidance VICH GL18, Residual Solvents in New Veterinary Medicinal Products, Active Substances and Excipients).

This document does not address: (1) extraneous contaminants that should not occur in new veterinary drug substances and are more appropriately addressed as Good Manufacturing Practice (GMP) issues, (2) polymorphic forms, and (3) enantiomeric impurities.

3. RATIONALE FOR THE REPORTING AND CONTROL OF IMPURITIES

3.1 Organic Impurities

The registration applicant should summarize the actual and potential impurities most likely to arise during the synthesis, purification, and storage of the new veterinary drug substance. This summary should be based on sound scientific appraisal of the chemical reactions involved in the synthesis, impurities associated with raw materials that could contribute to the impurity profile of the new veterinary drug substance, and possible degradation products. This discussion can be

Contains Non-Binding Recommendations

limited to those impurities that might reasonably be expected based on knowledge of the chemical reactions and conditions involved.

In addition, the registration applicant should summarize the laboratory studies conducted to detect impurities in the new veterinary drug substance. This summary should include test results of batches manufactured during the development process and batches from the proposed commercial process, as well as the results of stress testing (see guidance VICH GL3, Stability Testing of New Veterinary Drug Substances and Medicinal Products) used to identify potential impurities arising during storage. The impurity profile of the new veterinary drug substance batches intended for marketing should be compared with those used in development and any differences discussed.

The studies conducted to characterize the structure of actual impurities present in the new veterinary drug substance at a level greater than ($>$) the identification threshold given in Attachment 1 (e.g., calculated using the response factor of the new veterinary drug substance) should be described. Note that any impurity at a level greater than ($>$) the identification threshold in any batch manufactured by the proposed commercial process should be identified. In addition, any degradation product observed in stability studies at recommended storage conditions at a level greater than ($>$) the identification threshold should be identified. When identification of an impurity is not feasible, a summary of the laboratory studies demonstrating the unsuccessful effort should be included in the application. Where attempts have been made to identify impurities present at levels of not more than (\leq) the identification thresholds, it is useful also to report the results of these studies.

Identification of impurities present at an apparent level of not more than (\leq) the identification threshold is generally not considered necessary. However, analytical procedures should be developed for those potential impurities that are expected to be unusually potent, producing toxic or pharmacological effects at a level not more than (\leq) the identification threshold. All impurities should be qualified as described later in this guidance.

3.2 Inorganic Impurities

Inorganic impurities are normally detected and quantified using pharmacopoeial or other appropriate procedures. Carry-over of catalysts to the new veterinary drug substance should be evaluated during development. The need for inclusion or exclusion of inorganic impurities in the new veterinary drug substance specification should be discussed. Acceptance criteria should be based on pharmacopoeial standards or known safety data.

3.3 Solvents

The control of residues of the solvents used in the manufacturing process for the new veterinary drug substance should be discussed and presented (see guidance VICH GL18 for Residual Solvents).

4. ANALYTICAL PROCEDURES

The registration application should include documented evidence that the analytical procedures are validated and suitable for the detection and quantification of impurities (see guidances VICH GL1 and GL2 for Analytical Validation). Technical factors (e.g., manufacturing capability and

Contains Non-Binding Recommendations

control methodology) can be considered as part of the justification for selection of alternative thresholds based on manufacturing experience with the proposed commercial process. The use of two decimal places for thresholds does not necessarily reflect the precision of the analytical procedure used for routine quality control purposes. Thus, the use of lower precision techniques (e.g., thin-layer chromatography) can be acceptable where justified and appropriately validated. Differences in the analytical procedures used during development and those proposed for the commercial product should be discussed in the registration application.

The quantitation limit for the analytical procedure should be not more than (\leq) the reporting threshold (see Attachment 1).

Organic impurity levels can be measured by a variety of techniques, including those that compare an analytical response for an impurity to that of an appropriate reference standard or to the response of the new veterinary drug substance itself. Reference standards used in the analytical procedures for control of impurities should be evaluated and characterized according to their intended uses. The new veterinary drug substance can be used as a standard to estimate the levels of impurities. In cases where the response factors of the new veterinary drug substance and the relevant impurity are not close, this practice can still be appropriate, provided a correction factor is applied or the impurities are, in fact, being overestimated. Acceptance criteria and analytical procedures used to estimate identified or unidentified impurities can be based on analytical assumptions (e.g., equivalent detector response). These assumptions should be discussed in the registration application.

5. REPORTING IMPURITY CONTENT OF BATCHES

Analytical results should be provided in the application for all batches of the new veterinary drug substance used for clinical, safety, and stability testing, as well as for batches representative of the proposed commercial process. Quantitative results should be presented numerically as opposed to in general terms such as “complies,” “meets limit,” etc. Any impurity at a level greater than ($>$) the reporting threshold (see Attachment 1) and total impurities observed in these batches of the new veterinary drug substance should be reported with the analytical procedures indicated. Below 1.0%, the results should be reported to two decimal places (e.g., 0.06%, 0.13%); at and above 1.0%, the results should be reported to one decimal place (e.g., 1.3%). Results should be rounded using conventional rules (see Attachment 2). A tabulation (e.g., spreadsheet) of the data is recommended. Impurities should be designated by code number or by an appropriate descriptor, e.g., retention time. If a higher reporting threshold is proposed, it should be fully justified. All impurities at a level greater than ($>$) the reporting threshold should be summed and reported as total impurities.

When analytical procedures change during development, reported results should be linked to the procedure used, with appropriate validation information provided. Representative chromatograms should be provided. Chromatograms of representative batches from analytical validation studies showing separation and detectability of impurities (e.g., on spiked samples), along with any other impurity tests routinely performed, can serve as the representative impurity profiles. The applicant should ensure that complete impurity profiles (e.g., chromatograms) of individual batches are available, if requested.

Contains Non-Binding Recommendations

A tabulation should be provided that links the specific new veterinary drug substance batch to each safety study and each clinical study in which the new veterinary drug substance has been used.

For each batch of the new veterinary drug substance, the report should include:

- Batch identity and size
- Date of manufacture
- Site of manufacture
- Manufacturing process
- Impurity content, individual and total
- Use of batches
- Reference to analytical procedure used

6. LISTING OF IMPURITIES IN SPECIFICATIONS

The specification for a new veterinary drug substance should include a list of impurities. Stability studies, chemical development studies, and routine batch analyses can be used to predict those impurities likely to occur in the commercial product. The selection of impurities in the new veterinary drug substance specification should be based on the impurities found in batches manufactured by the proposed commercial process. Those individual impurities with specific acceptance criteria included in the specification for the new veterinary drug substance are referred to as "specified impurities" in this guidance. Specified impurities can be identified or unidentified.

A rationale for the inclusion or exclusion of impurities in the specification should be presented. This rationale should include a discussion of the impurity profiles observed in the safety and clinical development batches, together with a consideration of the impurity profile of batches manufactured by the proposed commercial process. Specified identified impurities should be included along with specified unidentified impurities estimated to be present at a level greater than (>) the identification threshold given in Attachment 1. For impurities known to be unusually potent or to produce toxic or unexpected pharmacological effects, the quantitation/detection limit of the analytical procedures should be commensurate with the level at which the impurities should be controlled. For unidentified impurities, the procedure used and assumptions made in establishing the level of the impurity should be clearly stated. Specified, unidentified impurities should be referred to by an appropriate qualitative analytical descriptive label (e.g., "unidentified A", "unidentified with relative retention of 0.9"). A general acceptance criterion of not more than (\leq) the identification threshold (Attachment 1) for any unspecified impurity and an acceptance criterion for total impurities should be included.

Acceptance criteria should be set no higher than the level that can be justified by safety data, and should be consistent with the level achievable by the manufacturing process and the analytical capability. Where there is no safety concern, impurity acceptance criteria should be based on data generated on batches of the new veterinary drug substance manufactured by the proposed commercial process, allowing sufficient latitude to deal with normal manufacturing and

Contains Non-Binding Recommendations

analytical variation and the stability characteristics of the new veterinary drug substance. Although normal manufacturing variations are expected, significant variation in batch-to-batch impurity levels can indicate that the manufacturing process of the new veterinary drug substance is not adequately controlled and validated (see guidance VICH GL39 on Specifications and Decision Tree #1 for establishing an acceptance criterion for a specified impurity in a new veterinary drug substance). The use of two decimal places for thresholds does not necessarily indicate the precision of the acceptance criteria for specified impurities and total impurities.

In summary, the new veterinary drug substance specification should include, where applicable, the following list of impurities:

Organic Impurities

- Each specified identified impurity
- Each specified unidentified impurity
- Any unspecified impurity with an acceptance criterion of not more than (\leq) the identification threshold
- Total impurities

Residual Solvents

Inorganic Impurities

7. QUALIFICATION OF IMPURITIES

Qualification is the process of acquiring and evaluating data that establishes the biological safety of an individual impurity or a given impurity profile at the level(s) specified. The applicant should provide a rationale for establishing impurity acceptance criteria that includes safety considerations. The level of any impurity present in a new veterinary drug substance that has been adequately tested in safety and/or clinical studies would be considered qualified. Impurities that are also significant metabolites present in animal and/or human studies are generally considered qualified. A level of a qualified impurity higher than that present in a new veterinary drug substance can also be justified based on an analysis of the actual amount of impurity administered in previous relevant safety studies.

If data are unavailable to qualify the proposed acceptance criterion of an impurity, studies to obtain such data can be appropriate when the usual qualification thresholds given in Attachment 1 are exceeded.

Higher or lower thresholds for qualification of impurities can be appropriate for some individual drugs based on scientific rationale and level of concern, including drug class effects and clinical experience. For example, qualification can be especially important when there is evidence that such impurities in certain drugs or therapeutic classes have previously been associated with adverse reactions in animals. In these instances, a lower qualification threshold can be appropriate. Conversely, a higher qualification threshold can be appropriate for individual drugs when the level of concern for safety is less than usual based on similar considerations (e.g.,

Contains Non-Binding Recommendations

animal species, drug class effects, clinical considerations). Proposals for alternative thresholds would be considered on a case-by-case basis.

The "Decision Tree for Identification and Qualification" (Attachment 3) describes considerations for the qualification of impurities when thresholds are exceeded. In some cases, decreasing the level of impurity to not more than the threshold can be simpler than providing safety data. Alternatively, adequate data could be available in the scientific literature to qualify an impurity. If neither is the case, additional safety testing should be considered. The studies considered appropriate to qualify an impurity will depend on a number of factors, including the animal species, daily dose, and route and duration of drug administration. Such studies can be conducted on the new veterinary drug substance containing the impurities to be controlled, although studies using isolated impurities can sometimes be appropriate.

Although this guidance does not address the clinical research stage of development, in the later stages of development the thresholds in this guidance can be useful in evaluating new impurities observed in the new veterinary drug substance batches prepared by the proposed commercial process. Any new impurity observed in later stages of development should be identified if its level is greater than (>) the identification threshold given in Attachment 1 (see the "Decision Tree for Identification and Qualification" in Attachment 3). Similarly, the qualification of the impurity should be considered if its level is greater than (>) the qualification threshold given in Attachment 1. Safety assessment studies to qualify an impurity should compare the new veterinary drug substance containing a representative amount of the new impurity with previously qualified material. Safety assessment studies using a sample of the isolated impurity can also be considered.

8. GLOSSARY

(The following definitions are presented for the purpose of this Revised Guidance.)

Chemical Development Studies: Studies conducted to scale-up, optimize, and validate the manufacturing process for a new veterinary drug substance.

Degradation Product: An impurity resulting from a chemical change in the drug substance brought about during its manufacture and/or storage by the effect of, for example, light, temperature, pH or water.

Enantiomeric Impurity: A compound with the same molecular formula as the new veterinary drug substance that differs in the spatial arrangement of atoms within the molecule and is a non-superimposable mirror image.

Extraneous Contaminant: An impurity arising from any source extraneous to the manufacturing process.

Herbal Products: Medicinal products containing, exclusively, plant material and/or vegetable drug preparations as active ingredients. In some traditions, materials of inorganic or animal origin can also be present.

Identified Impurity: An impurity for which a structural characterization has been achieved.

Identification Threshold: A limit above (>) which an impurity should be identified.

Impurity: Any component of the new veterinary drug substance that is not the chemical entity defined as the new veterinary drug substance.

Impurity Profile: A description of the identified and unidentified impurities present in a new veterinary drug substance.

Intermediate: A material produced during steps of the synthesis of a new veterinary drug substance that undergoes further chemical transformation before it becomes a new veterinary drug substance.

Ligand: An agent with a strong affinity to a metal ion.

New Veterinary Drug Substance: The designated therapeutic moiety that has not been previously registered in a region or member state in a veterinary medicinal product (also referred to as a new molecular entity or new chemical entity). It can be a complex, simple ester, or salt of a previously approved drug substance.

New Veterinary Medicinal Product: A pharmaceutical product type, for example, tablet, capsule, solution, cream, etc., containing a new or existing drug substance which has not previously been registered in a region or member state, and which contains a drug ingredient generally, but not necessarily, in association with excipients.

Polymorphic Forms: Different crystalline forms of the same new veterinary drug substance. These can include solvation or hydration products (also known as pseudo-polymorphs) and amorphous forms.

Contains Non-Binding Recommendations

Potential Impurity: An impurity that theoretically can arise during manufacture or storage. It may or may not actually appear in the new veterinary drug substance.

Qualification: The process of acquiring and evaluating data that establishes the biological safety of an individual impurity or a given impurity profile at the level(s) specified.

Qualification Threshold: A limit above (>) which an impurity should be qualified.

Reagent: A substance other than a starting material, intermediate, or solvent that is used in the manufacture of a new veterinary drug substance.

Reporting Threshold: A limit above (>) which an impurity should be reported. Reporting threshold is the same as reporting level in VICH GL2, Guidance on Validation of Analytical Procedures.

Solvent: An inorganic or an organic liquid used as a vehicle for the preparation of solutions or suspensions in the synthesis of a new veterinary drug substance.

Specified Impurity: An impurity that is individually listed and limited with a specific acceptance criterion in the new veterinary drug substance specification. A specified impurity can be either identified or unidentified.

Starting Material: A material used in the synthesis of a new veterinary drug substance that is incorporated as an element into the structure of an intermediate and/or of the new veterinary drug substance. Starting materials are normally commercially available and of defined chemical and physical properties and structure.

Unidentified Impurity: An impurity for which a structural characterization has not been achieved and that is defined solely by qualitative analytical properties (e.g., chromatographic retention time).

Unspecified Impurity: An impurity that is limited by a general acceptance criterion, but not individually listed with its own specific acceptance criterion, in the new veterinary drug substance specification.

Contains Non-Binding Recommendations

Attachment 1: Thresholds

New Veterinary Drug Substance

Identification ²	As per ICH* 0.20% **
Reporting ^{1,2}	As per ICH* 0.10% **
Qualification ²	0.50%

* new veterinary drug substance used in veterinary and human medicine

** new veterinary drug substance not used in human medicine

¹ Higher reporting thresholds should be scientifically justified.

² Lower thresholds can be appropriate if the impurity is unusually toxic.

Contains Non-Binding Recommendations


Attachment 2: Illustration of Reporting Impurity Results for Identification and Qualification in an Application (substances used in veterinary medicine only (see attachment 1); for substances used in human and veterinary medicine see also relevant ICH guidance)

'Raw' Result (%)	Reported Result (%)	Action	
		Identification (Threshold 0.20%)	Qualification (Threshold 0.50%)
0.166	0.17	None	None
0.1963	0.20	None	None
0.22	0.22*	Yes	None
0.649	0.65*	Yes	Yes*

* * After identification, if the response factor is determined to differ significantly from the original assumptions, it may be appropriate to re-measure the actual amount of the impurity present and re-evaluate against the qualification threshold (see Attachment 1).

Contains Non-Binding Recommendations

Attachment 3: Decision Tree for Identification and Qualification



Contains Non-Binding Recommendations

Notes on Attachment 3

- a) If considered desirable, a minimum screen (e.g., genotoxic potential), should be conducted. A study to detect point mutations and one to detect chromosomal aberrations, both in vitro, are considered an appropriate minimum screen.
- b) If general toxicity studies are desirable, one or more studies should be designed to allow comparison of unqualified to qualified material. The study duration should be based on available relevant information and performed in the species most likely to maximise the potential to detect the toxicity of an impurity. On a case-by-case basis, single-dose studies can be appropriate, especially for single-dose drugs. In general, a minimum duration of 14 days and a maximum duration of 90 days would be considered appropriate.
- c) Lower thresholds can be appropriate if the impurity is unusually toxic.
- d) For example, do known safety data for this impurity or its structural class preclude human or animal exposure at the concentration present?