FERC Staff's Responses to Discussion Questions from eTariff@FERC.gov

List of Issue Groups

Business Rules	
Attachment Related Codes	
Tariff Record Related Codes	
Type of Filing Related Questions	
eTariff Viewer	

Business Rules

	Question	Answer	Date
1	If a record change type of CHANGE is filed in a filing for record id 1234 version 2.0.0 and then is subsequently withdrawn in a later filing via a record change type of WITHDRAW, can record id 1234 version 2.0.0 be filed again at some later date? Upon processing the latter (WITHDRAW) filing, is the earlier filed record physically delete from FERC's eTariff database?	Neither the Filing Identifier (filing_id) number nor the Tariff Record's Record Version Number (record_version_num) can be reused once the filing has been accepted by the OSEC. Once the OSEC has accepted a filing, the filing is an official document with the Commission. A withdraw filing initiates a set of FERC processes. Neither the WITHDRAW filing type nor the WITHDRAW Record Change Type results in the removal of the tariff filing or the Tariff Record data being from the FERC's databases.	1/15/10
2	Under what circumstances will a filing include tariff record versions that do not contain tariff content? • Withdrawal filings? • Cancellation filings? • Motion filings? • Are there other filing types?	The Record Version Number (record_version_num) is not used in any automated fashion. It is not required for the Type of Filing (filing_type) identified as a Motion, Withdraw or Cancellation category. All other categories of Type of Filing that require Tariff Record Content Data require a Record Version Number.	12/19/08
3	For which types of filings is an associated_filing_id required in a filing? Amendment? Compliance? Motion? Withdraw? Report? Other?	The Baseline, Normal and Cancellation Type of Filing categories do not require an Associated Filing Identifier (associated_filing_id). Compliance may require an Associated Filing Identifier depending on the circumstance. All other Type of Filing categories require an Associated Filing Identifier.	12/19/08 5/25/10

	Question	Answer	Date
4	Which types of filings can BE the associated	The Commission's program specific regulations	12/19/08
	filing for a filing being filed?	and business rules specify which types of filings	5/25/10
		may be associated with which filings. For	
		example, Withdraw and Amendment Type of	
		Filings can only be associated with tariff filings	
5	In the FERC documentation there are	that the Commission has not acted upon. The referenced Amendment and Motion Type of	12/19/08
3	references to automated actions	Filing categories will in many cases automatically	1/15/10
	(amendment type filings, suspension	update the status of filings. An amendment filing	1/13/10
	motions, status_change_timeout) to update	for example will automatically change the filing	
	the status of filings and tariff records. Are	date for the proceeding after the 30 th or 60 th day	
	these things that happen automatically	which the Commission is required to act. In some	
	within FERC's tariff software? Are the	cases, the Commission may issue a notice	
	owners of the affected tariffs notified? Will	indicating that the filing has been made, but no	
	every tariff filing result in a FERC order?	explicit notification of the status tariff filing or tariff	
		record change will be issued. The filer needs to	
		be aware of the regulatory implications of its actions.	
6	Currently, there is no way for software to	Attachments are governed by the current	12/19/08
U	understand and enforce the quantity of each	Secretary's filing rules and in many cases,	12/19/00
	type of attachment that may be placed into a	multiple documents and filing types are used for	
	filing. For example, it wouldn't make sense	almost all types of documents. For example, a	
	for a filing to have two transmittal letters, but	transmittal letter may consist of a Word document	
	it would make sense for a filing to have two	with an Excel spreadsheet as an appendix. Also,	
	"Other Support not otherwise specified"	confidential information with redacted and	
	attachments. Is FERC willing to add a	unredacted copies may require the same	
	column to the attachment-reference-	attachment type be used more than once. Thus,	
	code.csv file that specifies whether multiple	designating which documents can be used	
	attachments of a particular type are allowed	multiple times is not worthwhile.	

	Question	Answer	Date
	in a filing?		
7	Can there be only one baseline filing (new_type=Y) for a tariff/database?	Yes. The Baseline Type of Filing category is a special case used to establish a new Tariff Identifier (tariff_id) for a company. Once the Tariff Identifier has been established, then all subsequent modifications to that tariff_id's database must be performed by one of the other Type of Filing categories. For example, an applicant may file in its Baseline Type of Filing filing only one record_id: the first section of its tariff. That would establish the Tariff Identifier. Subsequently, and for the first time, the applicant could file 1,000 record_ids that compose the rest of the tariff and do not yet exist in the database. This second filing must use a Type of Filing category other than Baseline.	12/19/08 1/15/10
8	Under what circumstances can a filing of refiled_type=Y be filed?	Many FERC programs' regulations require different business rules depending on whether a tariff is filed with the Commission for the first time (for example, a new company: refiled_type = N), or is simply a restatement of what the Commission has already reviewed and accepted (refiled_type = Y).	12/19/08
9	Are there rules regarding the filing of root tariff records (those without a parent) within such a filing? Or are they treated the same as tariff records that do have a parent? I suppose at the crux of this topic is the	A Tariff Identifier database can have multiple parent (root) Tariff Record Identifiers (record_ids). For example, Part 154 requires pipelines to maintain Volume No. 1 for their open access transportation and sales services, and a Volume No. 2 for their traditionally certificated services.	12/19/08

	Question	Answer	Date
	difference in FERC's eyes between a single tariff/database that contains multiple root tariff records VS multiple tariffs/databases each of which containing a single root tariff record.	Both of these Volumes can be placed in a single Tariff Identifier database under different parent Tariff Record Identifiers.	
10	How does the "Etariff Filing Rules Table" PDF relate to the type-of-filing.csv? Are these supposed to convey the same information, the former in human readable format and the latter in machine readable format? When is the next time that these resources will be updated with the latest information?	The Etariff Filing Rules Table in PDF format is the human readable format of the type-of-filing.csv and att_ref_code.csv documents. The table and related CSV files may be updated to reflect business and regulatory changes.	12/19/08 3/6 /09 5/25/10
11	The Type of Filing list posted on FERC's web site contains a lot of information that does not appear to be directly relevant to the eTariff process (e.g. amendment type, withdrawal type, refiled type). Why are these included?	The Type of Filing data shows the business rules eTariff applies to each and every Type of Filing Code (filing_type) available to applicants. The data provides information on how a tariff filing and the attached Tariff Records are processed. The information is provided to enhance applicants' tariff filing and tariff maintenance software.	12/19/08 1/15/10 5/25/10
12	If Companies A, B and C have a joint rate schedule, and Company A has agreed to be the party responsible to maintain the rate schedule, and Companies B and C have tariff records for the rate schedule which incorporates by reference Company A's rate schedule, must Companies B and C make a tariff filing to modify their tariff records when Company A makes a tariff filing affecting the joint rate	No. However, Order No. 714 did not change Companies B's or C's responsibilities for service and supporting any changes to the joint rate schedule as required by the statutes and Commission regulations.	3/6 /09

	Question	Answer	Date
	schedule?		
13	Companies A, B and C have a joint rate schedule, and Company A has filed a proposed change to that rate schedule. Companies B and C wish to file additional material to the record to support their parts of the proposed change. How can they do this?	Companies B and C can file through eTariff utilizing a REPORT filing type, such as FPA program's Type of Filing Code (filing_type) 150. When Companies B and C make such a filing, they must use Company A's Company Identifier (company_id) and Filing Identifier (filing_id) to ensure their material is properly routed to Company A's tariff filing proceeding.	3/6 /09 1/15/10
14	Companies A, B and C have a joint rate schedule, and Company B wishes to make a change to the joint rate schedule that only affects them. Can Company B make the tariff filing?	The responsibilities of Companies A, B and C with regard to filing and maintaining the joint rate schedule, and responsibilities for satisfying all other statutory and regulatory requirements related to proposed changes and compliance, are a matter of the certificate of concurrence agreement. If Companies A, B and C wish to treat Company A's joint rate schedule as a shared rate schedule (see Order No. 714 at P 65-73), the Tariff Filing XML schema will support such tariff filings. If Company B makes such a filing, it must use Company A's Company Identifier (company_id), Tariff Identifier (tariff_id) and an appropriate Filing Identifier (filing_id).	3/6 /09 1/15/10
15	Regarding the first two lines of the XML Schema, can anything be removed, edited or added to these lines without resulting in an error?	No. The first two lines of the XML Schema must be provided exactly as shown. If they are not provided exactly as shown, the OSEC cannot process the filing and it will be rejected.	1/15/10
16	My type of filing does not require all the data elements provided in the XML Schema. May I	No. Every row of information for every sequence must be provided, even if there is no information to convey.	1/15/10

	Question	Answer	Date
	omit that row of information?	If all the data elements are not provided exactly as shown, the OSEC cannot process the filing and it will be rejected.	
17	What is the proper format for data elements that are not populated?	Depending on the Type of Filing definition, different data elements need not be populated. For example, a BASELINE type of filing should not have an associated_filing_id. However, the XML Schema requires that all tariff filings provide that data element: <pre> </pre> <pre> </pre> <pre> <</pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre></pre>	1/15/10
		Please note the guidance provided at the XML Schema's note in the OSEC Implementation Guide with regard to known issues for certain XML software tools.	
18	If 0 (zero) is used to populated an XML Schema data element, will it be read by the Commission's software the same as "null"?	No. Zero and null are different. Zero is read as populating the data element. Null is read as not populating the data element.	1/15/10
19	Can the order of the XML Schema's data elements be changed?	No. The data elements must be provided in the same order as given in the XML Schema.	1/15/10
20	My filing had an ERROR and was rejected by the OSEC. May I correct the filing, use the same filing_id and resubmit it to the Commission?	Yes.	1/15/10
21	Can the clean tariff have headers and footers?	Yes. Order No. 714 removed the regulations that required some program's tariffs to include headers and footers. Headers may be included in the tariff text, or	6/25/2010

	Question	Answer	Date
		left as part of the RTF file's page definition. However, information in the headers or footers cannot be contrary to any Commission finding, such as effective date, or contrary to other meta data provided by the company, such as section titles.	
22	Must the tariff or rate schedule have a table of contents?	If the Commission's regulations or order requires a table of content for a tariff, rate schedule or any other tariff document, it must be included.	6/25/2010
23	Can a company continue use of the old designation system?	Yes. However, if a company chooses to use its old system, it still must abide by the general rule that the designations must be unique so as not to create confusion. <i>See</i> RP10-563-000.	6/25/2010
24	Order No. 714 permits companies sharing joint tariffs to incorporate a tariff by reference. Joint tariffs are most common in the FPA program. May other programs incorporate tariffs by reference?	Yes, Order No. 714's findings apply to all the tariff programs, not just the Part 35 program.	6/25/2010
25	As a non-designated party to a joint tariff, what should be included on the tariff section incorporating the designated filer's tariff?	Generally, the non-designated tariff section should have an informative section title, the name of the designated party, tariff and, as necessary, section title, and any other information or limitations applicable to the tariff and non-designated party. See Portland General Electric Company for an example of a designated party filing, and Puget Sound Energy, Inc. for an example of a non-designated filing, especially the accepted tariff sheet.	6/25/2010
26	Company A's paper version of the OATT was maintain and filed with the Commission under a Service Company B designation. That OATT	This is similar to a Joint tariff situation. Yes, Company A can provide a single tariff record incorporating Company C's OATT by reference in the baseline	6/25/2010

	Question	Answer	Date
	will now be in another Company C's tariff. Can Company A's Order No. 714 baseline tariff filing incorporate Company C's OATT by reference?	filing. The Transmittal Letter of Company A must clearly explain that Company C will be the location of the OATT in place of what used to be Service Company B's tariff, and confirm that no other significant changes are in the baselined Company C incorporated tariff.	
27	Company A's paper rate schedule is identical to Company B's paper rate schedule. Can Company A incorporate Company B's rate schedule as part of its Order No. 714 compliance filing?	If the rate schedules are clearly marked as a joint tariff and are identical in all respects, Company A can incorporate Company B's rate schedule provided the appropriate letters of concurrence are provided. The Transmittal Letter must clearly state the nature of the incorporation by reference. See also answers to Qu. 12 and 14 above. Any proposals to change the rate schedule or only incorporate parts of the rate schedule by reference imply that the rate schedules, or their application, are not identical. In that case, Company A needs to make a normal/statutory filing either before or after the baseline filing with its proposal for incorporation by reference.	6/25/2010
28	In a contested proceeding before an ALJ, the parties wish to file a settlement with the ALJ. Can eTariff be used to file the Settlement?	Technically, eTariff can be used to file Settlements. However, parties should follow the instructions of the ALJ. Any Settlement that claims to have real tariff records as part of the Settlement and is not filed through eTariff must be followed up with an eTariff Compliance filing to enter the tariff records into the	6/25/2010

	Question	Answer	Date
		eTariff data base.	
29	A Settlement contains tariff records. Can eTariff	Any filing that contains real tariff records must be filed	6/25/2010
	be used to file the Settlement?	in eTariff.	
30	A Settlement contains tariff records and provides	When an applicant does not know or have a proposed	6/25/2010
	that the agreed upon tariff records will go into	effective date, the Tariff Record Proposed Effective	<u>10/4/2011</u>
	effect upon Commission approval. What date	Date should be populated with 12/31/9998. Note	
	should be used to populate the Tariff Record	special case when establishing a new Tariff Identifier:	
	Proposed Effective Date?	Tariff Record Related Codes, Qu. 32.	
31	The ISO has, under one of its tariffs, tariff	eFiling provides functionality to add co-applicants to	1/27/2011
	documents of its members. As the eTariff XML	an eTariff filing. eFiling's instructions are located at	
	schema only contains the Company Identifier of	https://ferconline.ferc.gov/efiling-help.asp.	
	the owner of the Tariff Identifier, how can the		
	other party to the shared tariff be made a co-		
	applicant to the proceeding?		
32	My Transmittal Letter requested that several	Since Order No. 703, eFiled material is not read by	1/27/2011
	names be added to the Commission maintained	staff to transcribe names to the Commission service	
	service list in my proceeding. However, only the	list. Populating the Commission's service list is	
	name on the service list is the one associated	performed by the applicant as part of the eFiling	
	with the Company Profile. Why are the names	process. eFiling's instructions on how to add names to	
	in the Transmittal Letter not on the service list?	the Commission's service list are located at	
		https://ferconline.ferc.gov/efiling-help.asp. If a party	
		wishes to add more names to the Commission's service	
		list, they may do so by using the electronic	
		Documentless Intervention function. Those	
		instructions are available at	
		https://ferconline.ferc.gov/efiling-	
		help.asp#intervention.	
33	I ZIPped my XML tariff filing using Apple's OS	Apple's OS X's embedded compression software is	4/18/11
	X's embedded compression software. However,	known to include a sub-folder and a file in that sub	

Question	Answer	Date
upon making the filing with the Commission, I	folder that is usually hidden from OS X users. The	
received and error message that the eTariff Zip	subfolder contains another file with the identical name	
file contains more that one file. I looked at the	as the file at the parent level, but whose content is	
file and I do not see anything other than the	different. eFiling screens ZIP files to ensure that only	
XML file. What is happening?	one file is included, and that the file is an XML file.	
	The subfolder is considered by eFiling as a second file.	
	eTariff filers should not use compression software that	
	uses proprietary formats.	

Attachment Related Codes

	Question	Answer	Date
1	Is FERC willing to add the valid file extensions for each type of file identified in the attachment-content-type.csv file? This would enable software to automatically identify the attachment type based on the file's extension. In the event that the file extension is not unique to an attachment type, software could present users with a short list of file types from which they could choose.	The extension information is now provided in the att_content_type_code.csv file.	12/19/08 1/15/10
2	The "Record Content Type Code" file (record-content-type-code.csv) provides a "security_level" column but no "record_content_type_code" column. The "security_level" column should be changed to "record_content_type_code," right?	This error has been corrected.	12/19/08
3	Concerning the various software packages used for Attachments: how best can the acceptable software versions be determined? If software versions are too new will this create problems in the upload of the electronic tariff package?	The Secretary of the Commission determines which electronic document formats may be electronically filed with the Commission. OSEC posts this information on the www.ferc.gov web site, and OSEC is delegated the responsibility of maintaining the Attachment Content Type Codes (att_content_type_code).	12/19/08
4	The Attachment Reference Code list posted on FERC's site contains a cross-reference to Filing Type. Will this list be	The Attachment Reference Codes for Transmittal Letter, Tariff, Marked Tariff and Other have been normalized across Types of Filings as of 12/7/2009.	12/19/08 1/15/10

	Question	Answer	Date
	normalized across Filing Types?		
5	RTF was chosen as one of the "standards". Was SGML (Standard Generalized Markup Language) considered?	RTF was one of two Record Binary Data (record_binary_data) versions of software recommended to the Commission by NAESB and accepted by Order No. 714. As noted by Order No. 714, the standards are the result of a consensus after a long process starting in 2001.	12/19/08
6	Since Office 2007/Word 2007 supports many more features than RTF, is there any guideline on how to translate these features to RTF?	Microsoft provides compatibility documentation for various versions of Word with RTF entitled Rich Text Format (RTF) Specification. There are no OSEC guidelines at this time. Each company needs to asses the use of its word processing capabilities with respect to creation of RTF files. Our guidance would be that tariff provisions should not use complex formats. A reasonable test is to view the document after it has been saved in RTF.	12/19/08 5/25/10
7	A Word 2007 DOCX saved as a RTF may expand tremendously. There may be a problem with size of files once translated to RTF from DOCX. E.g. I saved a 10mb DOCX as a RTF and it became 243 MB. However zipping that same file it became 23 MB while the DOCX zipped yielded 8MB (a resulting 3x difference).	Each company needs to asses the use of its word processing capabilities with respect to creation of RTF files. Our guidance would be that tariff provisions should not use complex formats. There is a 10MB limit to the Record Binary Data (record_binary_data). Tariff creation software should be chosen and configured to conform to the technological limits of RTF and the <i>OSEC Implementation Guidelines</i> . See also the response to Question 12 below.	12/19/08 4/18/11
8	A map/line drawing/diagram greatly increased the size of the RTF versions of the Record	Maps/line drawings/diagrams in JPG format can significantly increase the RTF file size. Try converting	5/25/10 4/18/11

	Question	Answer	Date
	Binary Data file. What are the alternatives means of creating this data?	from JPG to GIF format, and saving in grey scale. An alternative is to file the Maps/line drawings/diagrams as a separate tariff section in PDF format.	
9	My eTariff filing was rejected by the Commission as it failed to include a Clean Tariff. However, the att_ref_code.csv table indicates that a Clean Tariff is not required. Why was my filing rejected?	See also the response to Question 12 below. Order No. 714 did not change the documentation requirements for a complete tariff filing. The convention for eTariff filings permits the Clean Tariff to be part of the Transmittal Letter or attached as a separate document. The flexibility eTariff provides users to satisfy the attachment requirement does not change the requirement that the documentation must be provided. Note that the OSEC and the Commission have the ability to change the eTariff attachment filing requirements to mandate the attachment of a separate Clean Tariff document as a means of ensuring the regulatory requirement is satisfied.	5/25/10
10	My formula rates tariff sheets are creating large tariff sections when converted into RTF files. What can I do?	Many formula rate paper tariff sheets were constructed by printing directly from the spreadsheet software or copying spreadsheets into a word processor and saving in the native file format before printing. RTF is capable of receiving some forms of embedded objects and rendering tables. However RTF is not as efficient as native file formats for tables and styles. When converting formula rate tariff sheets to RTF, review the tariff sheets to ensure that the existing tariff	6/10/10 4/18/11

	Question	Answer	Date
		sheets are compliant with the minimum font size required by the Commission's regulations (10 point font: sec. 385.2003(a)(4) (2010)).	
		Review whether a table structure is required, or whether columns or tabs will suffice.	
		Review whether tables contain unnecessary rows or columns.	
		Consider converting the formula rate into a plain-text	
		format to remove most table and style codes. For	
		example, Excel provides Save As MS –DOS text format.	
		For an example of this technique for rendering large rate	
		designs, see http://www.ferc.gov/industries/gas/gen-	
		info/rate-filings/rate_fnl.pdf.	
		See also the response to Question 12 below.	
11	Can I leave active hyper-links in my tariff sections?	No. Leaving hyper-links in a tariff creates a security risk for both FERC and site that the link is directed.	6/10/10
12	My Microsoft Word file has graphics in it, and	Yes. However, it should only be done with great caution	4/18/11
	RTF conversion file size is large. Can I set	and some companies may limit access to the necessary	
	some default in Word to reduce the file size?	files to IT support personnel only. The Microsoft	
		information and instructions are located here:	
1.5		http://support.microsoft.com/kb/224663	
13	How can I improve the attachment descriptions	eLibrary prominently displays the hyperlinked	5/25/11
	that appear in eLibrary?	Attachment Document File Name as the lead item,	
		followed by the Attachment Description. As a result,	
		many applicants believe that the Attachment Document	

Question	Answer	Date
	File Name is the attachment's description. However, it	
	is not. Further, many applicants who try to name their	
	attachment file names with complete descriptions	
	quickly run into the 60-character limit for the	
	Attachment Document File Name data element. The	
	effective available Attachment Document File Name	
	character limit is really about 55, as the remaining	
	characters must be reserved for the extension ("dot" and	
	the extension characters).	
	eLibrary's description of the attachment follows the	
	hyperlinked Attachment Document File Name.	
	Applicants should use the Attachment Description to	
	pass the attachment's description to eLibrary. The	
	Attachment Description data element has an 80 character	
	limit. Many applicants do not change their software's	
	default Attachment Description of "Other", and thereby	
	miss an opportunity to provide eLibrary and the public a	
	more informative description of the attachment's	
	content.	

Tariff Record Related Codes

	Question	Answer	Date
1	Discuss "PRO FORMA" record change type relative to version numbers. It seems that "PRO FORMA" tariff records will "use up" a version. Could PRO FORMA tariff record versions use version numbers in the 1000's, for example, so that they do not collide with the natural progression of version numbers? Are there any tariff record filing rules that are relaxed for records filed with a "PRO FORMA" change type?	Order No. 714 gave applicants some discretion in creating Record Version Number (record_version_num) entries, and the application of such discretion to Pro Forma Tariff Records would be reasonable. As applicants usually file Pro Forma tariff sections as part of a request for a full review of the proposed tariff changes, all the Tariff Record Content Data should be filed for each Pro Forma Tariff Record.	12/19/08
2	Tariff Record Proposed Effective Date: this XML field is marked as required in the "OSEC Implementation Guide," however, it wouldn't be needed for a withdrawal filing, for example. Is this right? Aside from withdrawal filings, are there other types of filings for which Tariff Record Proposed Effective Date would not be required?	Currently, there is no Withdraw category Type of Filing Code (filing_type) that requires a Tariff Record Proposed Effective Date (proposed_effective_date) to implement the Commission's regulatory business rules. However, that may not be the case in the future.	12/19/08
3	When filing a tariff record with multiple options, do all tariff records in the filing have to have the same number of options? For example, if	The Commission's normal business practice, and adopted in the OSEC Implementation Guide, is to accept one option in its entirety, reject the others, and require a compliance filing to include proposals in other options	12/19/08

Question	Answer	Date
tariff record #12 was being filed with	where accepted. Given this business practice, applicants	
option codes "A" and "B," would tariff		
record #23 also need to be filed as	complete sets to reduce the likelihood of a subsequent	
an option "A" and an option "B" even	compliance filing or the number of Tariff Records that	
if only one version of record #23 was	must be included in a subsequent compliance filing.	
desired?		

Under eTariff, when filing a new version of a given tariff record, in addition to the content of the record being updated, the organization of tariff can also be changed. Specifically, the "Tariff Record Collation Value" and the "Tariff Record Parent Identifier" can also be changed. I present here an example filing scenario followed by some questions.

Scenario

Given the following tariff records which represent only a portion of the overall tariff:

```
#17 v0.0.0 General Terms & Conditions
|
+---#1120 v3.0.0 Gas Quality
```

Record id 17 is the "General Terms & Conditions" section. Record id 1120 is the "Gas Quality" section, which has some history as it is on version 3.0.0. Record 1120 is a child of record 17.

Filing scenario: Two new sections are being added: "Rate Guarantees" and "Issue Resolution Response". Like "Gas Quality," these sections speak to "Pipeline Performance." As such, a new section called "Pipeline Performance" will also be added. Its parent will be "General Terms & Conditions" (record 17). "Gas Quality," "Rate Guarantees," and "Issue Resolution Response" will all be children of "Pipeline Performance". Therefore, the new structure of the tariff will be as follows:

```
#17 v0.0.0 General Terms & Conditions
|
+---#???? v?.?.? Pipeline Performance
```

	Question	Answer	Date					
	+#???? v?.?.? Gas Quality +#9217 v0.0.0 Rate Guarantees							
	+#9218 v0.0.0 Issue Resolutio	n Response						
	There are 3 ways to file these change presented below:	s to the tariff that all have roughly the same results. They a	re .					
	 (1) File 3 new records for "Pipeline Performance," "Rate Guarantees," and "Issue Resolution." File "Gas Quality" as v4.0.0. of record id 1120 and change its parent to be the "Pipeline Performance" record. (2) File v4.0.0 of record id 1120 changing it over to be the "Pipeline Performance" record, which obviates the need to change its parent. In addition, file 3 new records for "Gas Quality," "Rate Guarantees," and "Issue Resolution." (3) Cancel record id 1120. In addition, file 4 new records for "Pipeline Performance," "Gas Quality," "Rate Guarantees," and "Issue Resolution." 							
4a		Some of this data is available from the Commission's FASTR data, available at http://www.ferc.gov/industries/gas/gen-info/fastr/htmlall/index.asp. Every Volume No. 1 with a revision above "Original" constitutes a reorganized tariff. Adding sections to existing tariffs most frequently is associated with the Commission imposing new tariff requirements.	12/19/08					
4b	For FERC: What is the preferred filing method (1, 2, or 3) for such a filing?	All the proposed filing methods require the use of a Tariff Record Collation Value (collation_value) to organize the Tariff Records in the proposed fashion. Filing method 1 is preferred: retain the use of Tariff Record No. 1120, and relocate its position in the tariff through a new Tariff Record Collation Value. This method preserves the history of Tariff Record No. 1120.	12/19/08					

	Question	Answer	Date
5	How are the energy companies to use the parent relationship in a sheet-based tariff to meet the needs of the eTariff process and FERC's eTariff Viewer?	At NAESB's public web site is a Draft Implementation Guide 01/25/08 (Redline) (http://www.naesb.org/pdf3/etariff012308a2.doc). It has an extensive set of Use Case Descriptions starting at approximately page 44. The Use Cases show examples of how to use the Tariff Record Identifier (record_id) and Tariff Record Parent Identifier (record_parent_id) that will be used by the FERC's eTariff Viewer to show the structure of the Tariff Records in the Table of Contents pane.	12/19/08 10/8/10
6	Should the Title Sheet of Volume X be the parent and all the tariff sheets in Volume X be its children?	This suggestion would work. See response to Business Rules, Question No. 9.	12/19/08
7	Would this solution cause problems in generating the Table of Contents?	No.	12/19/08
8	These questions all relate to filings ha records.	ving associated filings and tariff records having associated t	ariff
8a	When a filing has an associated filing, is it necessarily true that every tariff record contained within will be associated with the same filing?	The Associated Filing Identifier (associated_filing_id) is the Filing Identifier (filing_id) for the previous Tariff Filing to which the subject Tariff Filing or Tariff Record pertains. The Filing Data's Associated Filing Identifier does not necessarily determine the appropriate Tariff Record Content Data's Associated Filing Identifier. See 8(d) for examples.	12/19/08
8b	When a tariff record being filed is associated with a previously filed tariff record, the Associated Filing Identifier, Associated Record Identifier, and Associated Option Code work together to uniquely	True.	12/19/08

	Question	Answer	Date
	identify the associated record. True?		
8c	When a tariff record being filed is associated with a previously filed tariff record, must the filing within which it is being filed also be associated with a previously filed filing? Must they be the same filing?	No.	12/19/08
8d	Can you provide an example where the Associated Fling ID at the Filing level would differ from the Associated Filing ID at the Tariff record level?	Example A: A COMPLIANCE Type of Filing that CHANGEs Tariff Records from a NORMAL Type of Filing category filing (e.g., RP01-234-000) and Tariff Records from two subsequent and associated AMENDMENT Type of Filing category filings (RP01-234-001 and RP01-234-002). Example B: A Compliance Type of Filing that CHANGEs a Tariff Record from a NORMAL Associated Filing, which would have the association data, and introduces a NEW Tariff Record, which would have no association data. Example C: A Motion Type of Filing that moves into effect suspended Tariff Records from a NORMAL and its AMENDMENT Tariff Filings.	12/19/08
8e	Could there be multiple Associated Filing IDs at the Tariff record level?	Multiple Tariff Records can have different Associated Filing IDs, but any given Tariff Record Identifier can have no more than one Associated Filing ID.	12/19/08
9	Under what circumstances will a filing include tariff records that do not contain tariff content such that fields record_content_type_code,	The MOTION, WITHDRAW and CANCELLATION Type of Filing categories (filing_type) do not require content for the record_content_type_code, record_binary_data, and record_plain_text fields. Further, regardless of the Type	12/19/08 10/8/10

	Question	Answer	Date
	record_binary_data, and record_plain_text will be blank. >Withdrawal filings? >Cancellation filings? >Motion filings? Are there other filing types?	of Filing, Tariff Records with a Record Change Type (record_change_type) populated with CANCEL or WITHDRAW do not require content for the record_content_type_code, record_binary_data, and record_plain_text fields. In addition, no tariff text may be required for some tariff	
		organization. For example, a parent record may only have text in the Record Content Description and/or Tariff Record Title.	
10	Could record binary data in .rtf format contain a page break? For instance, because there appears to be no limitation of content on a tariff sheet, one could presumably have the content run over to the next sheet but continue to name that Sheet No. 200, thus one would need to have a break to make it work.	Yes. The eTariff software system will not be altering any of the binary content of the tariff record. If the material is retrieved as an rtf file, then the page break codes should show up as they were entered. However, in a web page viewer, or any other conversion to other formats, page breaks may or may not be recognized.	12/19/08
11	Consider the following scenario: (A) An eTariff record is filed with FERC. (B) FERC accepts the changes subject to conditions. (C) The record is filed again in a compliance filing (like today's Substitute tariff sheets) with the same effective date as in (A) above. Is it necessary that the two filed	Yes, the Record Effective Priority Order (priority_order) is required: Tariff status is largely controlled by dates (think of the statutory clock and notice periods as examples). The problem becomes what happens for the same tariff record of a single date with multiple tariff record changes hitting on the same date. 1) Two tariff record changes: In this scenario, which is the same as in the question for date 1/1/2020, the "substitute" record is likely to take precedence over the "original" record, and the objective is to show as "effective" the substitute record for the whole day.	3/6 /09

	Question			A	Answer		Date
	records (in (A) and (C) above) have						
	different Record Effective Priority	Section Status	Revision	Priority	Order Disposition	Tariff Record	
	Order values?	Section 156 Section 156	6.0.0 6.1.0	500 520	Minimal Suspension Accepted	Superceded Effective	
		,	nplex iss	ues. Su	plistic, and there ppose the examp		
		Section Section 156 Section 156	Revision 6.0.0 7.0.0	Priority 500 600	Order Disposition Minimal Suspension Accepted	Tariff Record Status Superceded Effective	
			_		cord text was requinpliance filing wo	•	
		Section Section 156 Section 156 Section 156	Revision 6.0.0 6.1.0 7.0.0	Priority 500 520 600	Order Disposition Minimal Suspension Accepted Accepted	Tariff Record Status Superceded Superceded Effective	
			ected the		cord text was requ xt of 7.0.0, then th	•	
		Section Section 156 Section 156 Section 156	Revision 6.0.0 7.0.0 7.1.0	Priority 500 600 620	Order Disposition Minimal Suspension Accepted Accepted	Tariff Record Status Superceded Superceded Effective	
12	What are the status conditions for			-	er time and in acco		3/6 /09
	Natural Gas Act (natural gas	variety of statutory, regulatory and business rules. The					
	pipeline) tariff records?		combination of the meta data required by the XML schema and the business rules permit at least the				
					-	ast the	
		rollowing	tariii rec	อาด ราสเป	us conditions:		

	Question	Answer	Date
13	What are the status conditions for Federal Power Act (public utility) tariff records?	Pending Accepted Effective Suspended Superceded Rejected Withdrawn Overtaken by events Pro Forma Status conditions vary over time and in accordance with a variety of statutory, regulatory and business rules. The combination of the meta data required by the XML schema and the business rules permit at least the following tariff record status conditions: Pending Pending (tolled) Accepted Effective Suspended Superceded Rejected Withdrawn Overtaken by events	3/6/09
14	What are the status conditions for Interstate Commerce Act (oil pipeline) tariff records?	Pro Forma Status conditions vary over time and in accordance with a variety of statutory, regulatory and business rules. The combination of the meta data required by the XML schema and the business rules permit at least the following tariff record status conditions: Conditionally Accepted	3/6 /09

	Question	Answer	Date
15	What are the status conditions for Part 284 program (NGPA intrastate and NGA Hinshaw gas pipelines) tariff records?	Conditionally Effective Accepted Effective Suspended Superceded Rejected Withdrawn Overtaken by events Pro Forma Status conditions vary over time and in accordance with a variety of statutory, regulatory and business rules. The combination of the meta data required by the XML schema and the business rules permit at least the following tariff record status conditions: Conditionally Accepted Conditionally Effective Accepted Effective Superceded Rejected Withdrawn Overtaken by events Pro Forma	3/6 /09
16	What are the status conditions for Power Administration tariff records?	Status conditions vary over time and in accordance with a variety of statutory, regulatory and business rules. The combination of the meta data required by the XML schema and the business rules permit at least the following tariff record status conditions: Conditionally Accepted Conditionally Effective	3/6 /09

	Question	Answer	Date
		Accepted Effective Superceded Rejected Withdrawn Overtaken by events Pro forma	
17	What is the tariff record status condition of "Overtaken by events"?	The tariff record status condition of "Overtaken by events" indicates the disposition of a tariff record whose status before the Commission is moot because it has been overtaken by some other filing. Currently, if an applicant files a correction to an initial filing's tariff record or a correction to a compliance filing's tariff record, the applicant should indicate that the underlying record is withdrawn. If it fails to do so, the Commission should reject the tariff record as moot. In eTariff, AMENDMENTS to a NORMAL/STATUTORY or another AMENDMENT, or COMPLIANCE to a COMPLIANCE Type of Filing should target the underlying tariff record utilizing the associated date elements: Associated Filing Identifier, Associated Record Identifier and Associated Option Code. Upon OSEC acceptance of the later tariff filing, the associated tariff record's status will convert to "Overtaken by events" without further action by the applicant or the Commission.	3/6 /09 1/15/10 5/25/10 1/27/11
18	What is the FPA program's tariff record status condition of "Pending (tolled)"?	The "Pending (tolled)" status condition indicates that the Commission has issued an order finding a NORMAL/STATUTORY FPA program type of filing (a filing type for which there is a statutory time the	3/6 /09 1/15/10 5/25/10

	Question	Answer	Date
		Commission must act) tariff filing deficient and cannot be processed. The statutory time for the Commission to act is no longer applicable. The tariff filing and tariff records will remain in this status until (a) an AMENDMENT type of filing is filed, which will reset the filing date for the statutory clock to the date of the AMENDMENT filing; (b) the Commission rejects the tariff record; or (c) the filing is withdrawn.	
19	What is the difference between the tariff record status conditions of "Accepted" and "Effective"?	The tariff record status condition of "Accepted" indicates that the tariff record has been accepted by the Commission or pursuant to some other statutory or business rule, and may become effective some date in the future. The tariff record status condition of "Effective" indicates that the tariff record has been Accepted and is in effect.	3/6 /09
20	What is the tariff record status condition of "Conditionally Accepted"?	Certain programs' statutory, regulatory or business rules permit a tariff record to become effective before Commission action is required. Conditionally Accepted indicates a tariff record change is proposed to be effective on a specified future date.	3/6 /09
21	What is the tariff record status condition of "Conditionally Effective"?	Certain programs' statutory, regulatory or business rules permit a tariff record to become effective before Commission action is required. The tariff record status condition of "Conditionally Effective" indicates that the tariff record is effective, but that final Commission action is still pending.	3/6 /09
22	NGA section 7 certificate filings commonly contain "Pro Forma" tariff records. Are NGA section 7 certificate filings' "Pro Forma" tariff	Not at this time. If the Commission decides to require NGA section 7 certificate filings to be filed utilizing the eTariff gateway of eFiling, that requirement will be the subject of a separate Notice and/or rulemaking.	3/6 /09

	Question	Answer	Date
23	records required to be filed utilizing eTariff. If a Conditionally Accepted or	All NGA section 4 compliance filings to Commission orders on NGA section 7 certificate filings must utilized eTariff. These compliance filings may contain Pro Forma, New or Changed tariff records. No. The status of the tariff record that was superceded	3/6 /09
23	Conditionally Effective tariff record is Suspended or Rejected, must the applicant refile the tariff record that was formerly effective?	by the Conditionally Accepted or Conditionally Effective tariff record will revert to tariff record status of Effective.	
24	Can the Associated Filing Identifier (associated_filing_id) reference a Filing Identifier (filing_id) other than the filer's?	No. The Associated Filing Identifier (associated_filing_id) must reference only Filing Identifiers (filing_id) made by the filer as identified by the Company Identifier (company_id).	3/6 /09
25	Can the Associated Record Identifier (associated_record_id) reference a Tariff Record Identifier (record_id) of another Company Identifier (company_id) or Tariff Identifier (tariff_id)?	No. The Associated Record Identifier (associated_record_id) must reference only a Tariff Record Identifier (record_id) that exists in the Tariff Filing's Tariff Identifier (tariff_id) for the of the Tariff Filing's Company Identifier (company_id).	3/6 /09
26	In a situation of multiple option sets – Options A, B and C, and a new Tariff Record Identifier (record_id) is being created, what should the different option sets' Record Change Type (record_change_type) contain?	There must be at least one Record Change Type (record_change_type) of NEW in the first option the proposed new Tariff Record Identifier (record_id) appears. Thereafter and within the tariff filing's option sets, Tariff Record Identifier (record_id) of either NEW or CHANGE are acceptable. Acceptable examples for a new Tariff Record Identifier (record_id) of "1234": Example 1: Option Record Change Type	5/25/10

	Question	Answer	Date
		A NEW	
		B CHANGE	
		C CHANGE	
		Example 2:	
		Option Record Change Type	
		A NEW	
		B NEW	
		C CHANGE	
		Example 3:	
		Option Record Change Type	
		A null	
		B NEW C CHANGE	
27	For tariff records with a Record		5/25/10
27		Yes. There can be multiple PRO FORMA option sets.	5/25/10
	Change Type (record_change_type) of PRO FORMA, must the Option	However, PRO FORMA option sets should avoid Option Code (option_code) "A", as that code designates the	
	Code (option_code) be populated?	applicant's primary real (as opposed to pro forma) tariff	
	Code (option_code) be populated?	change proposal.	
28	I found a mistake in a tariff record in	If the pending tariff filing is a Normal/Statutory filing, then	6/10/10
20	a tariff filing that is still pending	file an Amendment category type of filing; or if the	0/10/10
	before the Commission. How do I	pending tariff filing is a Compliance filing, then file a	
	correct the tariff record?	Compliance category type of filing. The corrected tariff	
		records should contain all the associated tariff record	
		information (associated_filing_id, associated_record_id,	
		and associated_option_code) to properly target the	
		incorrect tariff record. Providing the associated tariff	
		record information informs the Commission that the	
		targeted tariff record is replaced. The Commission will	

	Question	Answer	Date
		reflect the targeted tariff record's status as OBE (Overtaken By Events).	
29	I found a mistake in tariff record 123 in a tariff filing that is still pending before the Commission. Tariff record 123 had several child records with Record Change Type NEW. I filed a single tariff record consisting of (a) a correction to tariff record 123 with a Record Change Type WITHDRAW to withdraw the record or (b) an associated tariff record 567 with tariff record 123 to OBE tariff record 123. Now all the child records with Record Change Type NEW to tariff record 123 are no longer visible in the Public Tariff Viewer and appear to have been either (a) withdrawn or (b) OBE. What happened?	Any proposal to withdraw or OBE a pending tariff record with pending child records, regardless of whether the child records are in the proceeding or another proceeding, will be deemed either withdrawn or OBE, as there is no longer a parent record for the child records to attach. All tariff records must have a parent to provide the tariff with structure and continuity. Tariff records cannot "float" in a tariff, and must be "anchored." Another analog to visualize the situation: imagine a NEW section to an outline, and the section has several subsections. If the highest level of the section is removed, all the subsections will be removed at the same time.	6/25/2010
30	My filing was rejected by the Commission as it failed an eTariff validation test. I corrected the error. However, the filing was rejected again as it failed another test not previously identified. How can this happen?	Many of the Secretary's validation tests are complex, requiring use of several data elements from the XML file and comparing to several other data elements in the Commission's eTariff data base. If the expected data from the XML filing are not available or unexpected, the validation test results will find that there was an error and reject the filing. The complex validation tests will not run. Once the filing has been refiled with the previously noted errors corrected, then the complex tests can run. The result of those complex tests can be other error	1/27/2011

	Question	Answer	Date
		messages and rejection of the filing. It is always a good idea to first test your XML filing in the Sandbox to ensure the filing will pass all validation tests.	
31	I tried to upload my test tariff filing into the Sandbox, but I received an error message that the site is unavailable, that I do not have rights to the site, or nothing happens. What is wrong with your Sandbox site?	In most instances the problem is with the user's internet browser's security settings with regard to access to and use of an FTP site. Either use your browser's HELP feature to research the appropriate settings or discuss your requirement to access the Sandbox's FTP site with your IT personnel.	5/25/11
		Frequently, browser settings permitting access to the Sandbox are lost when browsers are upgraded. If you formerly had access to the Commission's Sandbox but have lost access, check your FTP security settings.	
<u>32</u>	A new company is creating a new	Baseline tariff filings with "to be determined" proposed	10/4/11
	tariff, but does not know when it will	effective dates of 12/31/9998 need to include at least one	
	go into service. What Tariff Record	tariff record with a Tariff Record Proposed Effective Date	
	Proposed Effective Dates should the	in the near future – date of filing is acceptable. The	
	Baseline filing contain?	reason is that the earliest Tariff Record Proposed	
		Effective Date in a Baseline filing becomes the	
		establishment date for the Tariff Identifier. No Tariff	
		Record can have an effective date that predates the Tariff	
		Identifier's establishment date. Therefore, if a Tariff Identifier has an establishment date of 12/31/9998, once	
		the company goes into service and informs the	
		Commission of its in-service date, it will not be able to	
		provide a Tariff Record Proposed Effective Date earlier	
		than 12/31/9998. The company will have to file a	
		Cancellation of the Tariff Identifier with the 12/31/9998	
		establishment date and file a new Baseline filing to create	

Question	Answer	Date
	a new Tariff Identifier with the in-service date.	

Type of Filing Related Questions

	Question	Answer	Date
1	Can a column be added to the 'Type of Filing' csv that provides a shorter name for each type of filing? From a software display standpoint, the description column provided is too long for some display scenarios.	There does not appear to be any benefit to providing another column with essentially identical information. The names for each Type of Filing can be discussed at a technical conference to be held later.	12/19/08
2	Is the Tariff Record key = Tariff record Identifier + Option Code + Tariff Record Effective Date Record + Effective Priority Order as shown on page 11 of the NAESB Implementation Guide? And Is the Tariff Filing key = Company Identifier + Filing Identifier + Tariff Identifier as shown on page 11 of the NAESB Implementation Guide?	Unique identifier keys will likely be data base specific. A "Tariff Record key" is not a required XML filing package data element.	12/19/08
3	Is the Associated Filing Identifier required for every COMPLIANCE type of filing?	 No. Many COMPLIANCE type of filings will be required for which there is no Associated Filing Identifier. For example: Compliance tariff filings pursuant to a Commission rule making; During the transition from paper tariff filings to eTariff filings, all compliance filings referencing paper tariff filings. 	3/6 /09

	Question	Answer	Date
4	I forgot to include an attachment in a tariff filing.	File the omitted attachment using a Report category	5/25/10
	How do I correct this mistake?	Type of Filing. This Type of Filing requires the	
		Associated Filing Identifier at the filing level.	
5	I made a mistake with a tariff record in a COMPLIANCE Type of Filing. How do I correct this mistake?	Use a COMPLIANCE Type of Filing to correct a tariff record. Including the Associated Filing Identifier at the filing level to ensure proper docketing and posting in eLibrary. Include the Associated Filing Identifier, Associated Record Identifier, and Associated Option Code at the tariff record level to reflect the fact that the	5/25/10
		note that AMENDMENT Type of Filings ARE NOT used to correct COMPLIANCE Type of Filings.	
6	I made a mistake on my COMPLIANCE	The COMPLIANCE filing will have to be withdrawn	5/25/10
	category Type of Filing – it should have been a NORMAL/STATUTORY filing. How do I correct this mistake?	using a WITHDRAW filing, and refiled using a NORMAL/STATUTORY filing code.	10/8/10
7	I am making a Compliance filing to a proceeding that predates the Baseline filing of my company. How do I ensure that the old docket number will be assigned to this Compliance filing?	The Commission has converted, for tariff filings, to automatic docketing. Compliance filings that are to tariff filings that predate a company's Baseline filing will lack the Filing Identifier necessary to populate the eTariff XML schema. The Commission will issue Compliance filings that lack an Associated Filing Identifier a new docket number. The Commission, in its January 21, 2010 order, advised applicants in this situation to put the source docket number in the Filing Title/Description.	6/10/10
8	I wish to extend the date by which the	File an AMENDMENT filing with at least one tariff	10/8/10
	Commission must act on a	record. As with any statutory type of filing, the new	
	NORMAL/STATUTORY, AMENDMENT,	statutory period depends on the proposed effective	

	Question	Answer	Date
	BASELINE/NEW or CANCELLATION filing. How do I do it?	date(s) in the AMENDMENT filing.	
9	Must a motion to extend the date by which the Commission may act be filed through eTariff?	Yes. See Order No. 714 at P 83.	10/8/10 10/4/11
		Such a filing should use an AMENDMENT category	
		Type of Filing Code, as such a motion is a proposal to	
		amend the proceeding' action dates. The company has	
		a choice as to how long the Commission action date	
		may be extended:	
		A) A simple statutory extension (30 or 60 days): Refile	
		any tariff record from the underlying filing with the	
		same proposed effective date (Tariff Record Proposed	
		Effective Date) and content, but increase the Record	
		Effective Priority Order and Record version number,	
		and populate the associated tariff record information to	
		OBE the underlying and duplicative record;	
		B) To extend the Commission action date to a given	
		date beyond the statutory date (beyond the 30 or 60	
		days): Refile any tariff record from the underlying	
		filing with the proposed effective date and content, but	
		increase the Record Version Number, and populate the	
		associated tariff record information to OBE the	
		underlying and duplicative record. The proposed	
		effective date should be the day after the company	
		wishes the Commission to act. If the company wishes to maintain the proposed effective date(s) of the	
		underlying filing, the tariff record in the amendment	
		filing should not have the associated tariff record	
		information.	
		C) To extend the Commission action date indefinitely:	

	Question	Answer	Date
		Refile any tariff record from the underlying filing with a well into the future proposed effective date and content, but increase the Record Version Number, and populate	
		the associated tariff record information to OBE the underlying and duplicative record. The proposed	
		effective date should be the day after the company	
		wishes the Commission to act. If the company wishes	
		to maintain the proposed effective date(s) of the underlying filing, the tariff record in the amendment	
		filing should not have the associated tariff record	
		information. When the company decides to restart the	
		proceeding, it should file another motion through the	
		AMENDMENT category Type of Filing Code with another tariff record, and populate the associated tariff	
		record information to OBE the underlying and	
		duplicative record with the indefinite date.	
10	I need to motion suspended tariff records into	File all the records that the company wishes to move	4/18/11
	effect. However, there have been intervening	into effect (both changed and unchanged) using a	
	changes. How do this?	COMPLIANCE filing. The Tariff Record Proposed	
		Effective Date for each of the record should conform	
		with the motion filing rules.	
11	Should my MOTION category filing's tariff	No. MOTION category filings' tariff records should	5/25/11
	records contain tariff text or modified Record	not contain tariff text or a revised Record Version	
	Version Number?	Number, as the applicant is not supposed to be	
		proposing any change to the suspended tariff records'	
		tariff text. A Motion filing is only for the purpose of	
		changing a proposed effective date for a suspended	
		tariff record.	

eTariff Viewer

	Question	Answer	Date
1	In the OSEC Implementation Guide under Tariff	Tariff Record Title (record_title) will definitely	12/19/08
	Record Content Data Tariff Record Title	be used in an automated table of contents.	1/15/10
	(record_title) and Record Content Description	How the Record Content Description	10/8/10
	(record_content_desc), it states that "this field may	(record_content_desc) will be displayed has	10/4/11
	be used in a database generated Table of	not be determined. At the April 28, 2009	
	Contents." Can FERC commit that these are the	technical conference, Record Content	
	fields they will use in an automated table of	Description, Tariff Record Title and Record	
	contents?	Version Number, in this arrangement, were	
		identified as the data elements to be used.	
		Commission orders commonly refer to this	
		set of data elements as the "section title."	
2	If leading spaces are placed in Tariff Record Title	Leading spaces will likely be removed for the	2/9 /09
	(record_title), Record Content Description	eTariff Viewer's display. ETariff will not	
	(record_content_description), Record Version	modify the data submitted to the	
	Number (record_version_num) or Record Narrative	Commission, including leading spaces.	
	Name (record_narrative_name), how will the		
	spaces appear in the eTariff Viewer?		
3	When a tariff filing is made, how long does it take for	The new tariff records should appear within a few	10//8/10
	the new tariff records to appear in the eTariff Viewer?	minutes of the Secretary accepting the tariff filing	
		for filing before the Commission.	
4	When the Commission acts on a tariff filing, how long	There may be up to a 5-day delay between the	10/8/10
	does it take for the Commission's actions to be reflected	time the Commission order issues and the time	
	in the eTariff Viewer?	the actions are reflected in the eTariff Viewer.	
5	My RTF tariff text does not appear the same as the	There are many reasons why the RTF	10/8/10
	Clean Tariff I provided as an attachment. Why are they	representation of the tariff text in the eTariff	

	Question	Answer	Date
	different?	Viewer does not match the Clean Tariff. Users	
		should be aware that the Commission did not	
		promise it could render tariff material in the	
		eTariff Viewer with the same fidelity intended by	
		the applicant. The Clean Tariff requirement is the	
		applicant's rendition of its tariff.	
		Reasons for the lack of fidelity include one or	
		more of the following possible explanations:	
		Creating the tariff document in a format	
		other than RTF and converting to RTF	
		(note Discussion items above regarding	
		incompatibilities between Microsoft Word	
		formats and RTF);	
		Creating the tariff document in a format	
		other than RTF, creating the Clean Tariff	
		document from that document, then	
		converting to RTF, instead of creating the	
		Clean Tariff document from the RTF	
		document.	
		➤ Use of conversion software (including	
		word processing conversions, binary64	
		conversions and XML generators) that do	
		not recognize the same character sets or features. These conversion issues can be	
		located with the tariff creators or with	
		FERC.	
6	I have lost access to the company's tariff data base and I	The eTariff Viewer provides a feature that	4/18/11
	need to restore it to continue making filings. How can I	permits any person to download in an XML	
	do that?	format enough of the tariff to continue business.	

	Question	Answer	Date
		The instructions on how to use this feature are	
		located under Help on the eTariff Viewer home	
		page.	
7	I have lost access to the company's past XML and	No. The Commission does not retain a copy of	4/18/11
	ZIPped eTariff filings. Can I obtain a copy from the	the XML or ZIPped tariff filings. All the material	
	Commission?	from these tariff filings, including the meta data,	
		are available on eLibrary.	