LC BSR for Textual Monographs Based on the PCC BIBCO Standard Record for Textual Monographs Metadata Application Profile

Note on application: This MAP applies to printed textual monographs and microform reproductions of printed textual monographs. It does **not** apply to rare books that will be cataloged according to DCRM(B) (a separate BSR for rare books is forthcoming). Books with non-Latin scripts should also follow the PCC Guidelines for Multiple Character Sets.

Other Cataloging Streams: This document applies to LC original cataloging; it does not apply to minimal level or 'lccopycat'

REMINDER: This MAP represents a 'floor' record, catalogers may, at their discretion, add additional elements when warranted.

Key:

M: Mandatory for all records
A: Mandatory if applicable

Element	Labels and notes	Use
	Leader	•
06	Type of record "a" or "t"	M
07	Bibliographic level "m"	M
17	Encoding level "blank" upon completion	M
	For LC: also use "8" at CIP galley stage	
18	Descriptive cataloging form "a"	M
	007 Variable Control Fields-Physical Description Fixed Field	
007/00	Category of material.	A
	For LC: most likely value "h" for microform	
007/01	Specific material designation	A
007/02-	For LC: catalogers may code these positions with the fill character or with the	A
12	appropriate values	
	008 Variable Control Fields-Fixed-Length Data Elements: Books	
	For LC: code all appropriate positions as for traditional full-level cataloging,	M
	including those not mandatory under the PCC BSR. Code subject-oriented fixed field	
	values according to the guidelines in SHM Appendix F.	
	Variable data fields	
010	\$a Library of Congress Control Number (LCCN)	M
	For LC:	A
	\$z Cancelled Library of Congress Control Number	
020	International Standard Book Number ISBN \$a	A
041	Language code	A
	For LC: at least subfields \$a (for multilingual works) and \$h (for translations) if	
	readily available	
042	Authentication code "pcc"	M

Element	Labels and notes	Use
043	For LC : Assign if readily ascertainable following the instructions in SHM Appendix E.	A
050	Classification number For LC: Assign at least one call number from the Library of Congress Classification system; include alternate class numbers where appropriate (analytics in certain collected sets and bibliographies classed in Z), and additional 050 fields as outlined in the CSM F memos.	M
051	For LC: Apply as appropriate	
082	For LC: Assign as appropriate	A
100-130	Main entry—personal name; corporate body; meeting name; uniform title	A
240	Uniform title Supply if known or can be easily inferred from the item being cataloged.	A
245	Title and statement of responsibility	
	\$a Title proper	M
	\$n, \$p, \$b, \$c In cases of multiple parallel titles, MINIMALLY include the first parallel title and any English parallel title	A
	\$h (for microforms)	M
246	Varying form of title: \$a, \$n, \$p Assess each item or collection and assign titles that cover variations deemed important to assist users. The importance of varying title information is intended to reflect individual cataloger judgment and/or local policy. Code the 246 for parallel title as 246:31; all other varying titles may be coded as 246:1# by default, or with the appropriate MARC 21 indicators	A
250	Edition statement	A
260	Publication, distribution, etc. (imprint)	
	\$a Place of publication, etc. Supply if readily available; otherwise, use [S.l.]; only the first-named place of publication as found on the resource is required for items with only one publisher that has multiple places; do not include for an unpublished item	A
	\$b Name of publisher, etc. Supply if readily available; otherwise, use [s.n.]; do not include for an unpublished item	A
	\$c Date of publication, etc.	M
300	Physical description	
	\$a Extent	M
	\$b Other physical details	A
	For LC: \$c Dimensions	M
490	Series statement Transcribe here the form of the series statement as it appears on the prescribed source in the item For LC: For LC original records, code all series statements with first indicator 0 (Series not traced)	A

Element	Labels and notes	Use
500	Source of title proper (if other than the chief source)	A
501	"With" note	A
502	Dissertation note	Α
504	For LC:	A
	Bibliography note	
505	Formatted contents note	Α
	Supply as appropriate for compilations, or for multi-part items with separate titles.	
533	Reproduction note	A
	For LC: use for microform reproductions	-
546	Language note	A
	Give the language(s) of the described materials if not apparent from the rest of the	
	description. Also describe alphabets, scripts, or other symbol systems appearing in the	
CVV	item.	1
6XX	Subject and Form/Genre access fields	A
	For LC: Use judgment in assessing each item. As appropriate, assign a complement	
	of headings from LCSH that provides access to at least the primary/essential subject	
	and/or form of the work at the appropriate level of specificity. Additional guidance for LC:	
	Multiple headings may be applied when needed in LCSH to represent a compound or	
	multi-element topic, when reciprocal headings are used, or when a standard array is	
	prescribed.	
700-751	Added entry fields	A
700 751	Use judgment in assessing each item. Assign a complement of added entries that	11
	covers the significant relationships associated with the work, expression, or	
	manifestation of which the item is a part. The inclusion and importance of added	
	entries are intended to reflect individual cataloger's judgment and/or local policy, in	
	the context of shared cataloging.	
	Additional guidance for LC:	
	Use the following guidelines for relationships that may be less obvious:	
	Corporate bodies: Assign added entries for corporate bodies that bear significant	
	responsibility for the work.	
	Related works: Assign added entries for a work to which the work being cataloged is	
	closely related (AACR2 21.30G), e.g., when cataloging adaptations (AACR2 21.10),	
	revisions (AACR2 21.12), or supplements (AACR2 21.28A1).	
	Analytical added entries: Assign an analytical added entry under the heading for a	
	work contained within an item being cataloged, e.g., when cataloging commentaries	
	with text (AACR2 21.12) or collections covered by AACR2 21.7B, 21.7C, and 25.7.	
8XX	Note: It is not necessary to justify added entries with notes, etc.	Δ
8XX	Note: It is not necessary to justify added entries with notes, etc. Series added entry	A
8XX	Note: It is not necessary to justify added entries with notes, etc. Series added entry If cataloger judgment of local cataloging policy is to trace a series, include in this field	A
8XX	Note: It is not necessary to justify added entries with notes, etc. Series added entry If cataloger judgment of local cataloging policy is to trace a series, include in this field the authorized form of the series as established in the LC Name Authority File	A
8XX	Note: It is not necessary to justify added entries with notes, etc. Series added entry If cataloger judgment of local cataloging policy is to trace a series, include in this field	A