Bid List No. 0120

SPECIFICATION

Property No. 230685

Blanket, Offset, Group 85

General Requirements

Shall be a conventional offset blanket with a quick-release surface. Shall be suitable for use with oil-base and quickset offset inks using a variety of commercial grade offset printing papers. Shall be suitable for use on a Miehle Super 60 sheet-fed press operating at 4,000 to 6,000 impressions per hour. Holes for mounting bars will be punched by GPO.

Size: 1194 mm around x 1511 mm across the cylinder (47" x

59-1/2")

Ply and Type: 3-ply conventional

Thickness: $1.68 \text{ mm} \pm 0.05 \text{ mm} (0.066" \pm 0.002")$

Bars: None

Punch: None

Sample Requirement: One blanket

Qualified Products List:

Reeves Brothers, Inc. - 578-SR

Rapidtec - Colormaster Blue Sinclair and Valentine - David M Group II Green

Coatings, Inc. - No. 400

D.Y.C. Supply - No. K300 Dayco: No 8