Bid List No. 0125

SPECIFICATION

Property No. 209490

Blanket, 4-ply conventional

General Requirements

Shall be best quality 4-ply conventional, offset sheet-fed blankets with a quick release surface. Shall be suitable for use on a Harris L-125-C offset sheet-fed press using not more than 10% isopropyl alcohol and alcohol substitutes in dampening system. Ink used will be oil based; quick set offset ink printing of a wide variety of commercial grades, offset printing papers. Holes for mounting bars will be punched by GPO.

| Size: | 25-1/2" across cylinder (648 mm) 24-3/4" around cylinder (629 mm) |
|------------|--|
| Ply: | 4-ply conventional |
| Thickness: | 0.075" <u>+</u> 0.002" (1.91 mm <u>+</u> 0.05 mm) |
| Sample: | Request a sample of two of each size is supplied. |
| | |

Qualified Products List

| Reeves Brothers Inc | Vulcan 578-SR |
|----------------------------|------------------------|
| Rapidtec, Inc | Colormaster Blue 4-ply |
| Sinclair and Valentine Inc | David M Group II Green |
| Coatings Inc - | Number 400 |
| D.Y.L. Supply Corp - | Number K-400 |
| Dayco Corporation - | Number 8212 Blue 4-ply |