

Bid List No. 0390

SPECIFICATION

Property No. 140996

Strippable Masking Film

Thickness	shall average 0.0060 inch (0.152 mm). A tolerance of plus 0 and minus 0.0005 inch (0.0127 mm) shall be permitted.
Light Transmission	Shall not exceed 0.1 percent at wavelengths below 540 manometers and 4.5 percent at wavelengths from 540 to 700 manometers, as measures spectrophotometrically. Use ASTM Method E308.
Color	shall match the attached sample.
General Appearance	Sheets shall lie flat with no visible curl, wrinkle, or waviness, and shall be uniformly clear of imperfections of manufacture.
Size and Trim	Paper shall be furnished in the following size: 46 x 60 inches (1168-x 1524 mm). Paper shall be trimmed square on four sides with clean smooth edges. A tolerance of \pm 1/16 inch (1.6 mm) shall be allowed. Paper shall be considered square if the variation between the diagnosis of the sheet does not exceed 1/16 inch (1.6 mm).
Performance	Product shall be so dimensionally stable as to permit exact reproduction of photographic negatives after a time interval of 48 hours.
Testing	shall be conducted in accordance with the Technical Association of the Pulp and Paper Industry (TAPPI) testing standards.