# BID LIST NO. 0408

# **SPECIFICATION**

## Hi Speed Floor Finisher

#### Property No. 175269

This product must be a type of polymer or copolymer which is compatible for use, that is, bonds with a floor sealer of the same brand and can be buffed at speeds of 2000 RPM to give the floor a high gloss wet look. The buffing machine used is the Pioneer "2100" Superbuffer. When the finisher is rebuffed in a dry condition it must be capable of regaining its loss of gloss (or wet look)>

In addition the product should have the following characteristics:

pH 9.0 + 0.5 undiluted

Solids 15 - 20%

Water Content 80 - 85%

Taber Abraser Test must resist complete removal when combined with the same

brand sealer and subjected to 200 revolutions of the abrading machine using the CS-17 abrading wheel with a 500-gram weight.

### Sample Requirement

A one-gallon sample is required for a lab and performance test. MSDS required.

### **Qualified Products**

Pioneer Eclipse Corp.: Total Eclipse

Sunshine Chemical Specialties, Inc.: Rock Hard National Chemical Laboratories of PA, Inc.: DR-18 MPC Concept 1000 Thermal Plastic Floor Finish

Stott Professional Floor Finish

Daycon: Ultra-glaze Thermoplastic Floor Finish

American Supply: Detergent Resistant Metal Interlock Scrubbable Floor Finish

Acme Paper and Supply Co.: Ultra-Shine Floor Finish and Protector Puritan Churchill Chemical Co.: Dazzle High Solids Floor Finish

Puritan Churchill Chemical Co.: LEGENDARY
Puritan Churchill Chemical Co.: Imperium
National Laboratories: High Gloss Floor Finish
Troy Chemical Co.: Troy 1003 Buffable Floor Finish

National Sanitary Supply Co.: Ultra-Hi Fisher, Lang & Co.: TP One Thousand

Intex Products, Inc.: Intex 8907 Huntington Labs, Inc.: Easy 20

Triple S: Miraquest Wet Look High Speed Floor Finish

Rite Chem Super Shine

Masterpiece High Gloss Floor Finish - Washington paper and Chemical