## **SPECIFICATION**

## Paper, Tympan, Untreated USE BID LIST 661

Stock: Recovered fiber, in any percentage, is permitted, provided that the requirements of this Standard are met.

Tearing Strength: Average, each direction, not less

A tolerance of  $\pm$  0.008 mm (0.0003") shall be allowed. Paper shall not vary more than 0.005 mm (0.0002") from one edge to the other.

Curl: Paper shall lie flat with either no tendency or curl or with a curl which can be overcome under reasonable working conditions.

Size and Trim: Sheets: Paper shall be 1066 mm x 1371 mm (42 x 54 inches) and shall be flat, trimmed square on four sides with clean, smooth edges, and evenly jogged. A tolerance of + 2.0 mm (1/16 inch) shall be allowed.

Grain: Shall be parallel to the long dimension.

General Appearance: Match the attached sample.

Use Information: This paragraph is informational only and is not exclusively definitive of the end use. For use as a

packing paper around press cylinders.

Testing and References: Testing shall be conducted in accordance with the Technical Association of the Pulp and

Paper Industry (TAPPI) testing standards. These Standards may be obtained from TAPPI,

PO Box 105113, Atlanta, GA 30348.

Sample Requirements: Ten sample sheets, 215 mm x 279 mm (8-1/2 x 11 inches).