### **SPECIFICATION**

### **PROPERTY NO. 137995**

## **ANTI SKINNING SPRAY**

#### **GENERAL REQUIREMENTS**

This item shall be an aerosol unit containing a suitable antioxidant such as butylated hydroxytoluene or clove that will eliminate press wash ups during the shut down periods. When sprayed on ink rollers, the product shall prevent sheet-fed offset and letter press inks from drying on rollers for periods up to eight (8) hours. The product should have o objectional odor or solvents detrimental to rollers or other press parts. The product must not change the color of viscosity of inks during normal use.

### **Specific Requirements**

When applied to a non-absorbent substrate such as lithocoated stock, black sheet-fed offset ink shall be wet to the touch, 24 hours after spraying.

The product can not contain methylene chloride.

#### Packaging

The anti-skinning spray shall be packaged in 14-18 ounce (net weight) pressurized cans.

# Sample Requirements

A one can sample of this product is required for testing to determine suitability for use at the GPO. A Material Safety Data Sheet must be submitted with the sample.

### **Qualified Products**

Anchor Lith Kem/Ko
Midland Color Co. (Braznell Co.)
William Recht Co.
Borden Chemical
Sprayway, Inc. (Meeks Printing)
Spray, Inc. (Wash.Printing Supplies)
Printing Development Inc.
Terand Industires, Inc.

Inkote Product #7044 Econ-O-Mist No Skin Press Life SP-10 #950 Anti Skin Spray #950 Anti Skin Spray Non Skin Spray U-561 Terand Non-Skinning Agent