SPECIFICATION

Tape, Heat Sealing, Plastic Banding (Postal Card)

Property No. 253472

The clear banding plastic film is to be used for banding postal cards in a "cut and pack" system which cuts, bundles and packages the printed postal cards.

The film can be made of such plastics as polyester, cellophane, polypropylene etc., with a coating of heat activated adhesive. In the case of polypropylene the plastic can be made to bond unto itself without an adhesive coating. The heat activated adhesive is to be activated in the temperature range of 275 $^{\circ}$ to 350 $^{\circ}$ F (133 $^{\circ}$ - 177 $^{\circ}$ C).

Physical Characteristics	
Width of Film	1.5" (38.1 mm)
Thickness of Film	.0015" to .0020" (.0381 to .0508 MM)
Diameter of Core	3.0" (76.2 mm)
Diameter of Roll	9.5" (241.3 mm)
Color of Tape	clear

Sample Requirement

One roll

Qualified Products

Flexel - 116HB-20