## BID LIST NO. 0800

## **SPECIFICATION**

## Property No. 252981

Paper Tape, Pressure Sensitive Adhesive

Stock: 100% unbleached sulphate pulp.

**Note:** reclaimed fiber, in any percentage is permitted, provided the requirements of this standard are met.

Basis weight: 24 x 36 - 500 Pounds (base stock without adhesive)-- 80

Metric equivalent  $(g/m^2)$ ------130 A tolerance of  $\pm$  5% shall be allowed.

Tear (of product): Average, cross direction, not less than (grams)------125

Metric equivalent (mN)-----1225

Adhesive: Shall be easy release suitable for adhering tightly to corrugated containers and paper products. Note, there is; no backing sheet for the adhesive. The backside of the tape should be coated with a wax, silicone or plastic material for easy release from the roll itself.

Roll construction: Shall be tightly wound at even tension with the adhesive on the inside.

Roll size: Diameter shall be 16 inches (406 mm) maximum. Core shall be 3 inches (76 mm). A tolerance of  $\pm$  1/4 inch (6 mm) shall e allowed on the core. Roll width shall be 2 inches. (51 mm). A tolerance of  $\pm$  1/16 inch (1.59 mm) shall be allowed on the width.

Sample Requirement: Each bidder shall submit a sample roll of tape to show the quality of the material and construction of the product he proposes to furnish.

Testing and Reference: Paper testing shall be conducted in accordance with applicable Technical Association of the Pulp and Paper Industry (TAPPI) testing standards unless otherwise specified. These standards may be obtained from TAPPI, PO Box 105113, Atlanta, GA 30348.

Acceptable Product

Manufacturer: Beltline Brand #539 of Anchor Tape Company Supplier: Fiber Products Company, Baltimore, MD