

**BID LIST NO. 0801**

**SPECIFICATION**

**Property No. 253715**

Tape, Carton Sealing

General Requirements

The product is to be a biaxially oriented polypropylene tape with a rubber based pressure sensitive adhesive. The adhesive must be specially formulated to adhere to fiberboard surfaces immediately with no dwell time. It is to be water and moisture resistant.

The adhesive should not ooze or seep around the edges. The tape should have good roll stability over a year's period in normal storage.

Specific Requirements

Tensile Strength.....	5.25 kN/m (30 lbs./in width)
Stretch at break.....	160%
Total Thickness.....	0.066 mm (0.026")
Color.....	Tan
Width.....	51.0 mm (2")
Length of Roll.....	54.8 m (60 yards)
Diameter of Roll.....	76.0 mm (3")
Adhesion to Steel.....	0.55 kN/m (50 oz/in)

Test methods used are from the Pressure Sensitive Test Council.

Sample Requirements

A one-roll sample of tape is required for testing purposes.