

Bid List 0818

SPECIFICATION

Thread, Blue, Four Cord Cotton for U.S. Passports
Property No. 290025

General Requirements

Stock shall be pure, long staple, sound cotton fiber, lint free and having a heavy bookbinding finish. It must loop properly and be suitable for use on the UNO passport line on cushion or "King" base tubes. The finish is to be glaze for smooth running and have no knots or thick splices that would cause interruptions in production.

Specific Requirements

Color.....American and Efird C-7 Wedgewood Blue or equal. (PMS-285).
Ticket Number.....20
Ply or cord.....4
Yarn Number.....26
Breaking Strength.....4.7 pounds minimum
Percent sizing.....6.0% minimum
Twist.....left
Yards per pound.....5400 minimum (10,900 m/kg)
Yard per tube.....6000 (5486 m)

Sample Requirement

Bidders must submit a sample tube for a performance test on the passport assembly line.

Qualified Products List

American Efird Mills, Inc. - Penninsular KNTL