## Chapter 26

## **Germaneness of Amendments**

## A. GENERALLY

- § 1. Introduction
- § 2. Germaneness Defined; Factors To Be Considered
- § 3. Proposition to Which Amendment Must Be Germane
- § 4. Tests of Germaneness
- § 5. Subject Matter
- § 6. —Committee Jurisdiction
- § 7. Fundamental Purpose
- § 8. Accomplishing Result of Bill by Different Method
- § 9. —Individual Proposition or Class Not Germane to Another
- § 10. —General Amendments to Specific or Limited Propositions
- § 11. Specific Amendments to General Propositions
- § 12. Adding to Two or More Propositions
- § 13. Appropriation Bills

## B. APPLICATION OF RULE TO PARTICULAR FORMS OF AMENDMENT

- § 14. In General
- § 15. Amendments to Particular Portion of Bill
- § 16. Adding New Section or Title
- § 17. Striking Text
- § 18. Substitute Amendments
- § 19. Committee Amendments
- § 20. Recommittals; Instructions to Committees

## C. AMENDMENTS IMPOSING QUALIFICATIONS OR LIMITATIONS

- § 21. In General; Exceptions or Exemptions
- § 22. Conditions or Qualifications
- § 23. Restrictions or Limitations
- § 24. Discretionary Powers
- § 25. Use of Funds
- § 26. Postponing Effectiveness Pending Contingency

## D. RELATION TO EXISTING LAW

- § 27. Amendments to Bills Amending Existing Law
- § 28. Amendments to Bills Repealing Existing Law
- § 29. Amendments to Bills Incorporating Other Laws by Reference
- § 30. Amendments to Bills Continuing or Extending Existing Laws
- §31. Amendments Changing Law to Bills Not Changing That Law

## E. HOUSE-SENATE RELATIONS

- § 32. Senate Germaneness Rules
- § 33. Motions to Instruct Conferees
- § 34. Senate Provisions in Conference Reports and in Amendments in Disagreement
- § 35. Amendments to Senate Amendments
  - F. PROCEDURAL MATTERS; POINTS OF ORDER
- § 36. In General

#### **Research References**

5 Hinds §§ 5801-5924 8 Cannon §§ 2908-3064 Deschler-Brown Ch 28 Manual §§ 467, 928-940, 1089

## A. Generally

## § 1. Introduction

#### **Evolution of Rule**

The House adopted its first germaneness rule in 1789, amended it in 1822, and has retained the rule in every subsequent Congress. Clause 7 of rule XVI states that no motion or proposition on a "subject different from that under consideration shall be admitted under color of amendment." *Manual* § 928.

It is a fundamental rule of the House that a germane relationship must exist between an amendment and the matter sought to be amended. No such rule existed under the practice of the early common law or under the rules of Parliament. It was not until 1883 that the British Parliament adopted a rule requiring "relevancy" of amendments. Erskine-May, 9th ed., p 325. Most State legislatures now also have germaneness requirements.

Before the advent of a germaneness requirement, a legislative assembly could by an amendment change the entire character of any bill or other pending proposition. It might entirely displace the original subject under consideration, and in its stead adopt one wholly foreign to it, both in form and in substance. 5 Hinds § 5825; Deschler-Brown Ch 28 §§ 1, 17.2; 105-2, Dec. 19, 1998, p 28102. Thus, the purpose of the rule is to maintain an orderly legislative process, and to prevent hasty and ill-considered legislation. It prevents the presentation to the House of propositions that might not reasonably be anticipated, and for which it might not be properly prepared. 8 Cannon § 2993.

## **Application of Rule Limited to Amendments**

The germaneness rule applies to amendments and not to the relationship between the various propositions set forth within the bill itself. 5 Hinds § 6929; Deschler-Brown Ch 28 § 1. A bill may be composed in the first instance to embrace different subjects. The germaneness rule may preclude the introduction of a new subject by way of amendment during consideration of the bill. 5 Hinds § 5825. For example, a point of order will not lie against an appropriation in a general appropriation bill because it is not germane to the rest of the bill. Deschler-Brown Ch 28 § 17.1.

A point of order will not lie against a special order of business reported from the Committee on Rules "self-executing" the adoption in the House or in the Committee of the Whole of a nongermane amendment to a measure because the amendment is not separately before the House during consideration of the special order of business. *Manual* § 928. For a discussion of the germaneness of amendments to special orders of business reported from the Committee on Rules, see § 3, infra.

## **Application Before Adoption of Rules**

The germaneness requirement has been held applicable in the House even before the adoption of the rules, under a theory of general parliamentary law based upon precedent. *Manual* § 60.

## § 2. Germaneness Defined; Factors To Be Considered

#### In General

For an amendment to be germane, it must be one that would appropriately be considered in connection with the bill. 8 Cannon § 2993. The concept implies more than the mere "relevance" of one subject to another. The fact that two subjects are related does not necessarily render each of them germane to the other. 8 Cannon §§ 2970, 2971, 2995; Deschler-Brown Ch 28 § 3.57. The germaneness of an amendment may depend on the rel-

ative scope of the amendment compared with that of the proposition sought to be amended. A proposition of narrow or limited scope may not be amended by a proposition of a more general nature, even though both propositions may be related to each other. § 10, infra. For example, to a bill authorizing emergency loans to livestock producers, an amendment changing the word "livestock" to "agricultural" was held to broaden the class of producers covered by the bill and, therefore, to be not germane. Deschler-Brown Ch 28 § 9.27.

## **Factors Considered in Determining Germaneness**

In evaluating an amendment to determine its germaneness, the Chair considers the relationship of the amendment to the pending text, as perfected. The Chair considers the relationship between the amendment and an existing statute that the pending bill seeks to amend only if the existing statute is so comprehensively amended by the pending bill as to render amendable all its provisions. *Manual* § 939; 8 Cannon § 2942; Deschler-Brown Ch 28 § 12.10. The Chair considers the relationship of the amendment to the text to which it is offered and does not generally rely on language in accompanying reports not contained in the pending text. Deschler-Brown Ch 28 § 2.3.

The stage of the reading in the House or Committee of the Whole also must be considered when evaluating the germaneness of a particular amendment. An amendment that might be considered germane if offered at the end of the reading of the bill for amendment may not be germane if offered during the reading, before all the provisions of the bill are open to consideration. Deschler-Brown Ch 28 § 18.1; § 3, infra.

The germaneness of an amendment is not to be judged by the apparent motives of the Member offering it. Deschler-Brown Ch 28 § 46.1. In ruling on germaneness, the Chair does not determine the legal effect of the bill, law, or amendment in question. The Chair rules only on whether the amendment addresses a "subject different" from that under consideration. Deschler-Brown Ch 28 §§ 35.64-35.66.

The title or heading of a bill is not controlling (although it may be informative) in evaluating the germaneness of amendments offered to propositions in the bill. The scope of a measure is determined by its provisions and not by the phraseology of its formal title. Deschler-Brown Ch 28 § 2.4. Thus, the heading of a portion of a bill as "Miscellaneous" will not alone permit amendments to that portion that are not germane to its actual content; but the provisions under such a heading may be sufficiently diverse to permit an amendment to be tested, in effect, by its germaneness to the bill as

a whole rather than merely that portion. *Manual* § 929; Deschler-Brown Ch 28 § 2.5.

# § 3. Proposition to Which Amendment Must Be Germane Generally

The germaneness of an amendment is based on its relationship to the particular portion of the bill then open for amendment. The amendment should be germane to the particular paragraph, section, or title to which it is offered and not anticipate the subject matter of other portions not yet read or portions that have been passed in the reading. *Manual* § 929; 5 Hinds §§ 5811-5820; 8 Cannon § 2922; Deschler-Brown Ch 28 § 2. For example, the test of germaneness of an amendment offered to a title of a bill being read for amendment by titles is its relationship to the pending title as perfected and not to the particular section within that title addressed by the amendment. *Manual* § 929.

The germaneness of an amendment inserting a new portion is based on the relationship of the amendment to the portions of the bill that have been read. For example, the germaneness of an amendment adding a new title to the end of the bill is based on the relationship of the amendment to the entire bill. *Manual* § 929. Similarly, an amendment inserting a new section need not necessarily be germane to the preceding section of the bill, it being sufficient that the amendment be germane to the sections of the bill read to that point. By the same reasoning, an amendment in the form of a new paragraph need not be germane to the paragraph immediately preceding or following it. *Manual* § 929; 8 Cannon §§ 2932-2935.

#### **Amendments to Pending Amendments**

The test of germaneness of an amendment to a pending amendment is its relationship to the pending amendment and not to the bill to which that pending amendment has been offered. Deschler-Brown Ch 28 § 2.24. It follows that the test of germaneness of a substitute for a pending amendment is the relationship between the substitute and the amendment and not between the substitute and the pending bill. Deschler-Brown Ch 28 § 2.17. Similarly, the test of germaneness of an amendment to an amendment in the nature of a substitute is the relationship between those two propositions, and not between the amendment and the pending bill. Deschler-Brown Ch 28 § 21.23.

#### **Consideration of Entire Bill**

An amendment might be germane at the end of the reading of the bill for amendment, even though it would not have been germane if offered during the reading. Where a bill is, by unanimous consent, considered as read and open to amendment at any point, the test of germaneness of an amendment thereto is its relationship to the entire bill and not just its relationship to the particular section to which offered. *Manual* § 929; Deschler-Brown Ch 28 §§ 2.6, 2.31, 19.21. An amendment that adds a new portion at the end of the bill is evaluated by the relationship of the amendment to the entire bill. *Manual* § 929.

The test of germaneness in the case of a motion to recommit with instructions is the relationship of the instructions to the perfected bill taken as a whole and not merely their relationship to the separate portion of the bill specifically proposed to be amended in the instructions. *Manual* § 929.

#### **Effect of Prior Amendments**

In evaluating the germaneness of an amendment, the Chair considers the relationship of the amendment to the bill as modified by the adoption of any prior amendment and is not bound solely by the provisions of the original text. Thus, a perfecting amendment may be ruled out as not germane where it pertains to text that has been stricken from the bill. *Manual* § 929; Deschler-Brown Ch 28 §§ 2.9, 2.13, 35.32.

#### **Effect of Pendency of Motion to Strike**

A perfecting amendment to a title in a bill may be offered while there is pending a motion to strike the title. Such an amendment is to the pending text and not to the motion to strike; and thus the amendment is required to be germane to the text to which offered rather than the motion to strike. *Manual* § 929.

## Amendments to Special Orders of Business Reported from the Committee on Rules

An amendment offered to a special order of business reported from the Committee on Rules (for example, waiving germaneness points of order against a specified amendment to be offered) must be germane to that resolution. A special order of business reported from the Committee on Rules providing for the consideration of a bill relating to a certain subject may be amended neither by an amendment that would substitute the consideration of a different proposition nor an amendment that would permit the additional consideration of a nongermane amendment to the bill. *Manual* § 928.

## § 4. Tests of Germaneness

## Generally; Nonexclusiveness of Tests

Various tests may be invoked to determine the germaneness of an amendment. These tests are not mutually exclusive. *Manual* § 935. The Chair, in evaluating germaneness, first must understand the nature and scope of the pending portion of the proposition being amended and then the relationship of the offered amendment to that pending text. The Chair follows the most appropriate line of precedent in rendering a ruling.

An amendment may satisfy one of the tests and yet be ruled out because of its failure to satisfy another. An amendment may thus be subject to a germaneness point of order, even though it is in some sense related to the pending proposition.

This principle is illustrated in the following precedents:

#### **Held Not Germane**

Text	Amendment
Excluding a Member-elect	Expelling the Member-elect (5 Hinds § 5924)
Expelling a Member	Censuring the Member (6 Cannon § 236)
Relating to interstate commerce	Relating to foreign commerce (8 Cannon § 2918)
Proposing a committee investigation	Requesting a committee report (5 Hinds § 5887)
Assigning clerks to committees	Assigning clerks to Members (5 Hinds § 5901)
Erecting a building for a mint	Changing coinage laws (5 Hinds § 5884)
Raising price of agricultural products by creation of corporation	Raising price by cooperative marketing (8 Cannon § 2912)
Repealing a specific mortgage refinancing program	Regulating financial sector employee compensation. (112-1, Mar. 10, 2011, p)
Increasing food supplies by educational and demonstrational methods	Increasing food supplies by sale of fertilizer (8 Cannon § 2980)

## Text Amendment

Enforcing State liquor laws. . . . Enforcing State firearm laws (*Manual* § 932)

## § 5. — Subject Matter

Clause 7 of rule XVI precludes amendments "on a subject different from that under consideration." This test of germaneness implies more than mere "relevance." The test is whether or not a new subject is introduced by the amendment. An amendment relating to a subject to which there is no reference in the pending text may be subject to a point of order that it is not germane to the bill. *Manual* § 932; Deschler-Brown Ch 28 § 3; see also § 2, supra.

This principle is illustrated in the following precedents:

## **Held Germane**

A mandmant

Amendment
Changing route (5 Hinds § 5909)
Specifying time of report (5 Hinds § 5915)
Creating one board with authorization to discharge the duties of both boards (8 Cannon § 3064)
Fixing new date for adjournment (5 Hinds § 5920)
Providing an educational test for immigrants (5 Hinds § 5873)
Removing fence of Botanic Garden (5 Hinds § 5914)
Appropriating funds for an investigation incident thereto (8 Cannon § 3060)
Providing that the vessels be constructed in government plants (8 Cannon § 3063)

#### **Text**

#### Amendment

Revising food safety laws and providing new regulatory authorities. . . .

Addressing the interrelation of House committees and imposing requirements for filing and content of committee reports. . . .

Ameliorating procedures relating to mortgage foreclosure under the National Housing Act. . . .

Addressing certain sections of the Clean Air Act with respect to the impact of shortages of energy resources on standards imposed under that Act. . . .

Prescribing the functions of a new Federal Energy Administration and conferring wide discretionary powers on its Administrator. . . .

Requiring a general study of factors affecting domestic production of automobiles

Providing for the preemptive purchase of food related to such authorities (111-1, July 30, 2009, p \_\_\_\_)

Addressing the content of reports from the Committee on Appropriations and the jurisdictional responsibilities of that committee and legislative committees (Deschler-Brown Ch 28 § 35.89)

Placing a moratorium on foreclosures of mortgages in economically depressed areas (Deschler-Brown Ch 28 § 3.36)

Addressing another section of that Act suspending for a temporary period the authority of the EPA Administrator to control automobile emissions (*Manual* § 932)

Directing the Administrator to issue preliminary summer guidelines for citizen fuel use (Deschler-Brown Ch 28 § 33.15)

Requiring a study of a particular factor—currency exchange rates—affecting that production (Deschler-Brown Ch 28 § 10.6)

## **Held Not Germane**

## **Text**

## Amendment

Admitting religious refugees. . . . Admitting political refugees (8 Can-

non § 3047)

Limiting immigration. . . . Disseminating information to attract a better class of immigrants (8 Cannon

§ 3048)

#### Text

#### Amendment

Prohibiting mailing of revolvers. . . .

advertising revolvers (8 Cannon § 3052)

Prohibiting mailing of publications

Authorizing arbitration of claims against the government. . . .

Appropriating funds to pay claims so arbitrated (8 Cannon § 3057)

Eliminating wage discrimination based on the sex of the employee. . . .

Eliminating discrimination based on race (Deschler-Brown Ch 28 § 3.18)

Providing for comprehensive reform of immigration laws. . . .

Increasing the number of law enforcement officials, including U.S. Marshalls (whose responsibilities go beyond enforcement of immigration laws) (109-2, Sept. 21, 2006, p 18861)

Authorizing the use of American civilians to operate an early-warning system in the Sinai. . . .

Requiring that the U.S. contribution to the U.N. peace-keeping forces in the Middle East be proportionately reduced (Deschler-Brown Ch 28 § 3.47)

Establishing a cotton research program and promoting the marketing of cotton. . . .

Providing for research with respect to training and utilization of displaced farm labor in the cotton industry (Deschler-Brown Ch 28 § 3.5)

Extending the phased subsidization of certain categories of nonprofit mail. . . .

Establishing a new class of mail and postal rate therefor (Deschler-Brown Ch 28 § 9.54)

Reducing tax liabilities of individuals and businesses by providing diverse tax credits within the Internal Revenue Code. . . . Providing rebates to recipients under retirement and survivor benefit programs (Deschler-Brown Ch 28 § 35.52)

Governing the political activities of Federal employees and containing certain restrictions on Federal employment relative to such activities. . . .

Prohibiting any employment or compensation, from whatever source, for candidates for office (Deschler-Brown Ch 28 § 9.50)

Addressing access to committee hearings and meetings. . . .

Addressing committee staffing (Deschler-Brown Ch 28 § 35.91)

#### **Text**

#### Amendment

Addressing the administrative structure of a new department. . . .

Prohibiting the department from withholding funds to carry out certain objectives (Deschler-Brown Ch 28 § 34.25)

Providing for the settlement of tribal claims. . . .

Setting new fuel procurement objectives for Federal agencies (110-2, June 25, 2008, p 13755)

During consideration of one of two reconciliation bills reported by the Committee on the Budget. . . .

Changing prospectively and indirectly the other reconciliation bill not then pending before the House (*Manual* § 932)

Reauthorizing the National Sea Grant College Program. . . .

Amending existing law to provide for automatic continuation of appropriations in the absence of timely enactment of a regular appropriation bill (Manual § 932)

Opposing concessional loans to a country and outlining principles governing the conduct of industrial cooperation projects of U.S. nationals in that country. . . .

Waiving other provisions of law by requiring changes in tariff schedules to achieve overall trade reciprocity between that country and the United States (*Manual* § 932)

Authorizing the deployment of troops to implement a peace agreement. . . .

Expressing support for the armed forces in carrying out such mission (*Manual* § 932)

Addressing enforcement of State liquor laws. . . .

Addressing enforcement of State firearm laws (*Manual* § 932)

## **Proposals Relating to Studies**

To a proposal authorizing a program to be undertaken, an amendment providing for a study to determine the feasibility of undertaking such a program may be germane. Deschler-Brown Ch 28 § 30.37 (in effect overturning 8 Cannon § 2989). Conversely, an amendment requiring certain action is not germane to a proposal that would merely require a study. Accordingly, to a proposition establishing a commission to study a matter, an amendment directing an official to undertake and accomplish that matter is not germane. Deschler-Brown Ch 28 § 3.69. However, if an amendment to a proposal to study a matter merely requires the submission of proposed legislation to im-

plement the study, the amendment may be germane. Deschler-Brown Ch 28 § 3.14.

## § 6. — Committee Jurisdiction

## Generally

Committee jurisdiction over the subject of an amendment is a relevant test to be applied in determining the germaneness of that amendment. *Manual* § 934; Deschler-Brown Ch 28 § 4. Thus, to a bill providing agricultural price supports to stimulate domestic production, an amendment repealing price control for all commodities (within the jurisdiction of the Committee on Banking and Currency) would not be germane. *Manual* § 934. Similarly, an amendment changing the statement of policy contained in a bill is not germane if its effect is to fundamentally change the purpose of the bill and to emphasize a subject within the jurisdiction of another committee. Deschler-Brown Ch 28 § 4.11. Likewise, an amendment conferring authority on an executive official not mentioned in the pending proposition is not germane where the subject of that authority is not within the jurisdiction represented in the pending proposition. *Manual* § 934.

The chair of the Committee of the Whole may determine the germaneness of an amendment based upon the discernible committee jurisdictions as to subject matter without infringing upon the Speaker's prerogatives under rule XII to determine committee jurisdiction over introduced legislation. Deschler-Brown Ch 28 § 4.71. The fact that the amendment is contained in a motion to recommit the bill with instructions does not dispense with the requirement that the subject matter of the amendment be within the jurisdiction represented in the pending text. *Manual* § 930.

However, the fact that the subject matter of an amendment lies within the jurisdiction of a committee other than that having jurisdiction over the introduced bill does not necessarily dictate the conclusion that the amendment is not germane. Committee jurisdiction is but one of the tests of germaneness. In ruling on the question, the Chair must take into consideration other factors, including the fact that the introduced bill may have been broadened or narrowed by amendment. *Manual* § 929. Where the bill is amended in Committee of the Whole to include matters within the jurisdiction of other committees, further similar amendments may be germane. Deschler-Brown Ch 28 § 4.54. The Chair also may take into account the fact that the portion of the bill being amended itself contains language related to the amendment that is not within the jurisdiction of the committee reporting the bill. *Manual* § 934. An amendment in the nature of a substitute may be in order even though an incidental portion of the amendment, if consid-

ered separately, might be within the jurisdiction of another committee. Deschler-Brown Ch 28 § 30.36.

Committee jurisdiction over the subject of an amendment is most relevant where the pending text is entirely within one committee's jurisdiction and where the amendment falls within another committee's purview. Deschler-Brown Ch 28 § 4.99. Thus, committee jurisdiction is a relevant test where an authorization bill that is solely within one committee's jurisdiction is proposed to be amended by permanent changes of laws within another committee's jurisdiction. Deschler-Brown Ch 28 § 24.1. Committee jurisdiction over the subject of an amendment may not be the most apt test of germaneness where the proposition being amended contains provisions so comprehensive as to overlap several committees' jurisdictions. *Manual* § 934.

This principle is illustrated in the following precedents:

#### **Held Not Germane**

### Text

## A bill reported from the Committee on International Relations (now Foreign Affairs) dealing with humanitarian and evacuation assistance in South Vietnam. . . .

A bill reported from the Committee on Armed Services containing diverse provisions relating to national defense policy, military procurement, and personnel. . . .

A bill within the jurisdiction of the Committee on Armed Services and the Committee on Foreign Affairs regarding the redeployment of U.S. troops and related diplomatic issues. . . .

A bill reported from the Committee on Merchant Marine and Fisheries authorizing various activities of the Coast Guard. . . .

#### Amendment

Providing for payment of costs of settlement of evacuees in the U.S., a matter within the jurisdiction of the Committee on the Judiciary (Deschler-Brown Ch 28 § 4.52)

Requiring reports on the Soviet Union's compliance with its arms control commitments, a matter within the jurisdiction of the Committee on Foreign Affairs (Deschler-Brown Ch 28 § 4.26)

Proposing revisions to the Foreign Intelligence Surveillance Act, an act within the jurisdiction of the Committee on the Judiciary and the Permanent Select Committee on Intelligence (110-1, July 12, 2007, p 18844)

Urging cooperation of other nations as to certain Coast Guard and military operations, a matter within the jurisdiction of the Committee on Foreign Affairs (Deschler-Brown Ch 28 § 4.46)

## **Text**

## Amendment

A bill reported from the Committee on Natural Resources providing for a study of two rivers for inclusion in the National Wild and Scenic Rivers System. . . .

A bill reported from the Committee on Public Works and Transportation amending the Federal Water Pollution Control Act. . . .

A bill authorizing environmental research and development activities of an agency for two years. . . .

A bill relating to intelligence activities of the executive branch. . . .

A bill reported from the Committee on Science and Technology (now Science, Space, and Technology) authorizing environmental *research and development activities* of an agency for two years. . . .

A bill reported from the Committee on Interior and Insular Affairs designating certain wilderness areas in Oregon. . . .

A bill reported from the Committee on Agriculture providing a one-year price support for milk. . . .

Providing for comprehensive energy legislation within the jurisdiction of seven different committees (110-2, Sept. 10, 2008, p 18417)

Amending the Clean Air Act (a statute within the jurisdiction of the Committee on Energy and Commerce) to regulate "acid rain" (Deschler-Brown Ch 28 § 4.3)

Adding permanent regulatory authority by amending a law not within the jurisdiction of the committee reporting the bill (Deschler-Brown Ch 28 § 4.1)

Effecting a change in the rules of the House by directing a committee to impose an oath of secrecy on its members and staff (*Manual* § 934)

Expressing the sense of Congress as to the agency's *regulatory and enforcement activity*—a matter within the jurisdiction of another committee (Deschler-Brown Ch 28 § 4.2)

Providing unemployment and retraining entitlement payments to persons affected by such wilderness designations, a matter falling within the jurisdiction of other committees (Deschler-Brown Ch 28 § 4.8)

Relating to tariff duties on imported dairy products, a matter within the jurisdiction of the Committee on Ways and Means (Deschler-Brown Ch 28 § 4.74)

#### **Text**

#### Amendment

A bill reported from the Committee on Public Works and Transportation relating to grants to State and local governments for local public works construction projects. . . .

A bill reported from the Committee on Ways and Means providing taxes and tax incentives to conserve energy. . . .

A bill reported from the Committee on Interstate and Foreign Commerce to conserve energy resources by regulating the production, allocation and use of those resources. . . .

A bill reported by the Committee on Ways and Means dealing only with import duties and quotas on sugar. . . .

A bill reported from the Committee on International Relations (now Foreign Affairs) providing foreign economic assistance. . . .

A bill reported from the Committee on Energy and Commerce relating to mentally ill individuals. . . .

Providing grants to such governments to assist them in providing public services, a program within the jurisdiction of the Committee on Government Operations (Deschler-Brown Ch 28 § 4.99)

Precluding the purchase of fuel-inefficient automobiles by the government, a subject within the jurisdiction of the Committee on Government Operations (Deschler-Brown Ch 28 § 4.21)

Reducing energy consumption by the Federal government by a reduced work-week for Federal civilian employees, a matter within the jurisdiction of the Committee on Post Office and Civil Service (Deschler-Brown Ch 28 § 4.13)

Eliminating all price support payments for sugar, a matter within the jurisdiction of the Committee on Agriculture (Deschler-Brown Ch 28 § 4.73)

Providing foreign *and domestic* economic assistance, a matter within the jurisdiction of the Committee on Banking (Deschler-Brown Ch 28 § 3.46)

Prohibiting certain uses of general revenue-sharing funds (a matter within the jurisdiction of another committee) in certain areas (Deschler-Brown Ch 28 § 4.104)

## **Text**

#### Amendment

A bill reported from the Committee on Education and Labor (now Education and the Workforce) authorizing a variety of civilian national service programs. . . .

A bill reauthorizing programs administered by two agencies within one committee's jurisdiction. . . .

A bill reported by the Committee on Transportation and Infrastructure reforming and privatizing Amtrak. . . .

A concurrent resolution expressing a sense of Congress with respect to the availability of public funds for expenses incurred in the evaluation of a problem. . . .

A bill reported from the Committee on Government Reform and Oversight proposing to alter responsibilities of executive branch agencies under an existing law. . . .

A resolution authorizing the deployment of troops to implement a peace agreement, within the jurisdiction of the Committee on International Relations. . . .

A bill comprehensively amending agricultural law and addressing some laws outside the jurisdiction of the Committee on Agriculture. . . .

Establishing a contingent military service obligation (a matter within the jurisdiction of the Committee on Armed Services) (Manual § 934)

Providing for authority that is more general in scope, affecting agencies within the jurisdiction of other committees (*Manual* § 934)

Rescinding previously appropriated funds for certain administrative expenses, a matter within the jurisdiction of the Committee on Appropriations (*Manual* § 934)

Addressing legislative responses to that problem, within the jurisdiction of other committees (*Manual* § 934)

Proposing to extend the application of that law to entities of the legislative branch, a matter within the jurisdiction of the Committee on House Administration (*Manual* § 934)

Expressing support for the armed forces carrying out such mission, within the jurisdiction of both the Committees on Armed Services and International Relations (Manual § 934)

Proposing to extend an existing dairy compact and create three new dairy compacts, within the jurisdiction of the Committee on the Judiciary (Manual § 934)

## § 7. — Fundamental Purpose

Another test used by the Chair in determining germaneness is one in which the fundamental purpose of the bill is compared with the fundamental purpose of the amendment. *Manual* § 933. If the purpose or objective of an amendment is unrelated to that of the bill to which it is offered, the amendment may be held not germane. 8 Cannon § 2911; Deschler-Brown Ch 28 § 4.10. This test is particularly applicable to an amendment in the nature of a substitute. Deschler-Brown Ch 28 § 5. If the purpose of a highway bill is to connect points A and B, an amendment specifying a different *route* between A and B would reflect the same fundamental purpose. However, an amendment connecting A and D would have a different purpose and would not be germane. 5 Hinds § 5909.

An amendment changing the statement of policy contained in a bill is not germane if its effect is to fundamentally change the purpose of the bill. Deschler-Brown Ch 28 § 4.11. An amendment changing the law with respect to the operations of one agency is not germane to a bill relating to the operations of a different agency. Deschler-Brown Ch 28 § 5.24.

In determining the fundamental purpose of a bill or an amendment offered thereto, the Chair may examine the broad scope of the bill and the stated purpose of the amendment and need not be bound by ancillary purposes that are merely suggested by the amendment. *Manual* § 933; Deschler-Brown Ch 28 § 5.12. An amendment in the form of a new title may be germane to a bill as a whole where that bill contains additional provisions not necessarily confined to the primary purpose, so long as the amendment falls within the overall parameters of the bill. Deschler-Brown Ch 28 § 5.20.

This principle is illustrated in the following precedents:

#### **Held Germane**

## Text

## Authorizing funds to provide humanitarian and evacuation assistance and authorizing the use of United States troops to provide that assistance. . . .

Enforcing the right to vote as guaranteed by the 15th amendment to the Constitution. . . .

## **Amendment**

Authorizing funds for military aid to a foreign country to be used by that country to further the fundamental purpose of the bill (Deschler-Brown Ch 28 § 5.23)

Protecting freedom of speech and other first amendment rights whose abridgment might affect the exercise of voting rights (Deschler-Brown Ch 28 § 5.3)

## **Text**

#### Amendment

Enforcing constitutional voting rights by requiring preservation of Federal election returns. . . .

Criminalizing use of a firearm during the commission of a felony that may be prosecuted in a Federal court. . . .

Providing an omnibus surface transportation authorization for highwayrelated projects as well as roadways. . . .

Authorizing the construction of a trans-Alaska oil-gas pipeline pursuant to procedural safeguards promulgated by the Secretary of the Interior. . . .

Freezing the obligation of funds for fiscal year 1996 for missile defense until the Secretary of Defense rendered a specified readiness certification. . . .

Providing for court appointment of voting referees to insure protection of voters' rights (Deschler-Brown Ch 28 § 5.2)

Criminalizing carrying of a firearm during the commission of a felony that may be prosecuted in either a State or Federal court (Deschler-Brown Ch 28 § 12.10)

Authorizing funds for certain highway projects that would incidentally permit completion of a related flood control project (Deschler-Brown Ch 28 § 5.12)

Containing similar procedures and including the condition that all participants be assured rights against discrimination as set forth in the Civil Rights Act (Deschler-Brown Ch 28 § 5.1)

Permitting an increase in the obligation of such funds on the basis of legislative findings concerning readiness, as each proposition addressed the relationship between 1996 funding levels for missile defense and readiness (*Manual* § 933)

## **Held Not Germane**

## Text

## Amendment

Proposing a constitutional amendment relating to the election of the President and Vice President by popular vote rather than through the electoral college process. . . .

Proposing an apportionment of Representatives and concerning the size of congressional districts (Deschler-Brown Ch 28 § 8.12)

## **Text**

#### Amendment

Authorizing military	assistance	pro-	Aut
grams to foreign natio	ons		U.N
			Δαε

Authorizing a contribution to the U.N. International Atomic Energy Agency (Deschler-Brown Ch 28 § 42.52)

Authorizing law enforcement agency grants to purchase photographic and fingerprint equipment for law enforcement purposes. . . .

Providing for the purchase of bullet-proof vests (Deschler-Brown Ch 28 § 3.78)

Extending the advisory and informational authority of the Council on Wage and Price Stability to encourage *voluntary programs* to resist inflation. . . .

Authorizing the President to issue *orders and regulations* stabilizing economic transfers, including wages and prices (Deschler-Brown Ch 28 § 6.20)

Establishing a new office within a government department. . . .

Abolishing the department (Deschler-Brown Ch 28 § 4.109)

Enabling agencies of the government to formulate policies relating to energy conservation. . . . Prohibiting certain uses of fuel (for school busing) and imposing criminal penalties for such use (Deschler-Brown Ch 28 § 5.15)

Extending various laws relating to higher education. . . .

Imposing restrictions on preschool, elementary, and secondary education policy (Deschler-Brown Ch 28 § 35.58)

Providing funding for urban highway transportation systems. . . .

Broadening the bill to include rail transportation (Deschler-Brown Ch 28 § 4.62)

Requiring registration and public disclosure by lobbyists but not regulating or prohibiting their activities. . . . Regulating their activities by placing a ceiling on their monetary contributions to Federal officials and prohibiting lobbying within certain areas (Deschler-Brown Ch 28 § 5.31)

Relating to the minting and issuance of public currency. . . .

Providing for a commemorative coin intended for private circulation (Deschler-Brown Ch 28 § 5.27)

Impeaching the President. . . .

Censuring the President (Manual § 933)

#### **Text**

#### Amendment

Authorizing a State attorney general to bring a civil action in Federal court against a person who has violated a State law regulating intoxicating liquor. . . .

Authorizing a State attorney general to bring a civil action in Federal court against a person who has violated a State law regulating intoxicating liquor. . . .

Singling out certain violations of liquor laws on the basis of their regard for any and all firearms issues (*Manual* § 933)

Creating new Federal laws to regulate intoxicating liquor (*Manual* § 933)

## §8. — Accomplishing Result of Bill by Different Method

In order to be germane, an amendment must not only have the same end as the matter sought to be amended, but also must contemplate a method of achieving that end that is closely allied to the method encompassed in the bill or other matter sought to be amended. Manual § 933; Deschler-Brown Ch 28 § 6.4. Under this principle, when a proposition to accomplish a certain purpose by one method is pending, an amendment seeking to achieve the same purpose by another closely related method is germane. Deschler-Brown Ch 28 § 5.14. For example, if the purpose of a bill is to support the health of school children by mandating oranges in a school lunch program, an amendment providing free vitamin C supplements may be germane. Likewise, a proposition to accomplish a certain result by two alternative methods may be amended by language proposing to accomplish that result by a third, closely related method. Deschler-Brown Ch 28 § 6.8. However, an amendment to accomplish a similar purpose by an unrelated method, not contemplated by the bill, is not germane. Deschler-Brown Ch 28 § 6.4.

This principle is illustrated in the following precedents:

## **Held Germane**

#### **Text**

#### Amendment

Accomplishing a result through regulation by an executive branch agency. . . .

Achieving the same result through the use of another governmental entity (Deschler-Brown Ch 28 § 6.8)

#### **Text**

#### Amendment

Conducting a broad range of programs involving energy sources, including environmental research related to the development of energy sources. . . .

Providing loan guarantee programs for all States and subdivisions. . . .

Subjecting employers who fail to apprise their workers of health risks to penalties under certain laws and regulations. . . .

Freezing the obligation of funds for fiscal year 1996 for missile defense until the Secretary of Defense rendered a specified readiness certification. . . .

Authorizing the Council on Environmental Quality to evaluate environmental effects of energy technology (Deschler-Brown Ch 28 § 6.9)

Providing direct loans (and limiting them to New York) (Deschler-Brown Ch 28 § 6.4)

Subjecting employers to penalties prescribed in the amendment (*Manual* § 933)

Permitting an increase in the obligation of such funds on the basis of legislative findings concerning readiness, as each proposition addressed the relationship between 1996 funding levels for missile defense and readiness (*Manual* § 933)

#### **Held Not Germane**

#### **Text**

#### Amendment

Conserving energy through the imposition of civil penalties on manufacturers of low-miles-per-gallon automobiles. . . .

Establishing an independent agency within the executive branch to accomplish a particular purpose. . . .

Authorizing the Attorney General to participate in litigation based on discrimination in public facilities. . . .

Conserving energy through tax rebates to purchasers of high-miles-pergallon automobiles (Deschler-Brown Ch 28 § 6.12)

Emphasizing committee oversight and authorizing committees to order the agency to take certain actions (Deschler-Brown Ch 28 § 6.36)

Establishing a Community Relations Service to assist in resolving disputes arising from discriminatory practices (Deschler-Brown Ch 28 § 9.11) nants. . . .

## **Held Not Germane—Continued**

#### **Text**

## Authorizing the promulgation of national drinking water standards to protect public health from contami-

Controlling crime through research and training. . . .

Extending unemployment compensation benefits during a period of economic recession. . . .

Promoting technological advancement by fostering Federal research and development. . . .

Providing financial assistance to domestic agriculture through a system of price support payments. . . .

Addressing substance abuse through prevention and treatment. . . .

Impeaching the President. . . .

Authorizing a State attorney general to bring a civil action in Federal court against a person who has violated a State law regulating intoxicating liquor. . . .

Authorizing a State attorney general to bring a civil action in Federal court against a person who has violated a State law regulating intoxicating liquor. . . .

#### Amendment

Requiring the negotiation and enforcement of international agreements to accomplish that purpose (Deschler-Brown Ch 28 § 6.25)

Controlling crime through regulation of the sale of firearms (Deschler-Brown Ch 28 § 6.6)

Stimulating economic growth by tax incentives and regulatory reform (Manual § 933)

Promoting same by changes in tax and antitrust laws (Manual § 933)

Protecting domestic agriculture by restricting imports in competition therewith (Deschler-Brown Ch 28 § 6.18)

Imposing civil penalties on drug dealers (*Manual* § 933)

Censuring the President (Manual § 933)

Singling out certain violations of liquor laws on the basis of their regard for any and all firearms issues (*Manual* § 933)

Creating new Federal laws to regulate intoxicating liquor (*Manual* § 933)

## §9. —Individual Proposition or Class Not Germane to Another

One individual proposition is not germane to another individual proposition. *Manual* § 936; 8 Cannon §§ 2951-2953, 2963-2966; Deschler-Brown Ch 28 §§ 8.23, 8.33. Thus, in theory, a bill regulating the transportation of apples could not be amended by language regulating the transportation of

oranges. However, if an individual proposition is rendered general in its scope by amendment, it is then subject to further amendment by propositions of the same class. 8 Cannon § 3003.

An individual proposition is not germane to another individual proposition merely because they are related. Thus, to a bill amending one subsection of law dealing with one prohibited type of activity, an amendment to another subsection dealing with a related but separate prohibited type of activity is not germane. Deschler-Brown Ch 28 § 8.7.

Where a bill covers two or more subjects within a readily definable class, it is not germane to add subjects outside of that class by way of amendment. Deschler-Brown Ch 28 § 3.80. Likewise, to a bill pertaining to several functions within an identifiable class of activity, an amendment adding a function outside that class would not be germane. *Manual* § 936.

To a bill dealing with relief for one class, an amendment seeking to include another class is not germane. Deschler-Brown Ch 28 § 13.19. Thus, to a bill providing financial relief for one class—agricultural producers—an amendment was held not germane where it extended such relief to another class, commercial fishermen, particularly where relief to the latter class was within the jurisdiction of another committee. Deschler-Brown Ch 28 § 4.70.

To a bill extending certain provisions to specified categories within a certain class of employees, an amendment extending those provisions to an additional category of employees within that same class is germane. Deschler-Brown Ch 28 § 12.1. However, such an amendment is not germane if it brings other classes of employees within the scope of the bill. Deschler-Brown Ch 28 § 13.1.

This principle is illustrated in the following precedents:

Toyt

### **Held Not Germane**

A mandmant

Text	Amenument
Providing for the relief of one individual	Providing for similar relief of another (5 Hinds §§ 5826-5929)
Exterminating the boll weevil	Including the gypsy moth (5 Hinds § 5832)
Providing a clerk for a committee	Providing a clerk for another committee (5 Hinds § 5833)
Providing for an additional judge in one territory	Providing additional judges in other territories (5 Hinds § 5830)

Text	Amendment
Providing relief for dependents of persons in the Army	Extending benefits to dependents in the National Guard (8 Cannon § 2953)
Pensioning veterans of Indian wars	Pensioning veterans of Mexican wars (8 Cannon § 2960)
Appropriating funds for only one year (and containing no provisions extending beyond that year)	Extending the appropriation to another year ( <i>Manual</i> § 936; 8 Cannon § 2913)
Relating to congressional actions on the budget	Repealing the Impoundment Control Act, thereby addressing Presidential authority to rescind or defer (Desch- ler-Brown Ch 28 § 4.89)
Siting a certain type of repository for a specified kind of nuclear waste	Prohibiting the construction at another site of another type of repository for another kind of nuclear waste ( <i>Manual</i> § 936)
Disposing of tin from the national stockpile	Disposing of silver from the national stockpile (Deschler-Brown Ch 28 § 8.33)
Providing financial assistance to the States for construction of public school facilities	Providing loans to assist in the construction of private schools (Deschler-Brown Ch 28 § 8.39)
Settling a particular railway labor dispute	Settling another dispute between a different railroad company and its employees (Deschler-Brown Ch 28 § 8.34)
Prohibiting a certain type of activity	Including another class of prohibited activities (Deschler-Brown Ch 28 § 8.7)
Designing certain coins	Specifying the metal content of other coins (Deschler-Brown Ch 28 § 8.35)
Regulating poll-closing time in Presidential <i>general</i> elections	Extending the provisions to Presidential <i>primary</i> elections (Deschler-Brown Ch 28 § 8.13)

#### **Text**

#### Amendment

Relating	to	the	civil	service	sy	stem
for Feder	al	civili	an en	ployees		

Including other classes of employees (postal and District of Columbia employees) (Deschler-Brown Ch 28 § 8.4)

Providing a cost-of-living adjustment for foreign service retirees. . . .

Providing a comparable adjustment in annuities for Federal civil service employees (Deschler-Brown Ch 28 § 8.6)

Determining the equitability of Federal pay practices under statutory systems applicable to agencies of the executive branch. . . .

Extending the determination of fairness to pay practices in the legislative branch (Deschler-Brown Ch 28 § 13.8)

Providing for payment from the Senate contingent fund of certain travel expenses incurred by Senate employees. . . .

Providing additional travel allowances, payable from the House contingent fund, to Members of the House (Deschler-Brown Ch 28 § 13.7)

Authorizing grants to States for purchase of one class of equipment (photographic and fingerprinting equipment) for law enforcement purposes. . . .

Including assistance for the purchase of a different class of equipment (bulletproof vests) (Deschler-Brown Ch 28 § 8.37)

Addressing violent crimes. . . .

Addressing nonviolent crimes, such as crimes of fraud and deception or crimes against the environment (*Manual* § 936)

Naming a facility after a specific person. . . .

Substituting the name of a different person (8 Cannon § 2955) where it could not be shown that the amendment merely intended a return to the facility's existing designation (105-2, Feb. 4, 1998, pp 784, 790)

Addressing whether public funds should be available for specified endeavors of one group. . . .

Addressing the same question for unrelated endeavors of another group (*Manual* § 936)

#### **Text**

#### Amendment

Extending the application of that law

Altering responsibilities of executive branch agencies under an existing law. . . .

to entities of the legislative branch

§ 936)

(Manual § 936) Extending the authorization or appropriation for another year (Manual

Appropriating or authorizing appropriations for a single year and containing no provisions beyond that year. . . .

Constitutional amendment on flag desecration. . . .

Constitutional amendment on a Balanced Federal Budget or on the Social Security Trust Fund (109-1, June 22, 2005, p 13539)

## § 10. — General Amendments to Specific or Limited Propositions

A specific proposition may not be amended by a proposition more general in scope. *Manual* § 937; 5 Hinds § 5843; 8 Cannon § § 2997, 2998; Deschler-Brown Ch 28 § 9. Thus, an amendment applicable to fruits of all kinds would not be germane to a bill dealing only with apples. An amendment applicable to all departments and agencies is not germane to a bill limited in its application to certain departments and agencies. Deschler-Brown Ch 28 § 9.22. Even an amendment that merely strikes words from a bill may be ruled out if the amendment has the effect of broadening the scope of the bill. § 17, infra.

A substitute for an amendment must be confined in scope to the subject of the amendment. Deschler-Brown Ch 28 § 9.42. Thus, an amendment rewriting an entire concurrent resolution on the budget was held not germane to a perfecting amendment that proposed certain changes in figures for one of the years covered by the resolution. Deschler-Brown Ch 28 § 9.38.

This principle is illustrated in the following precedents:

#### **Held Not Germane**

#### **Text** Amendment

Admitting a Territory. . . . Admitting several Territories (5 Hinds § 5837) Relating to all corporations in inter-Relating to all corporations (5 Hinds state commerce. . . . § 5842)

## Text

#### Applying proposition to one bureau Applying proposition to the Navy of the Navy Department. . . . Department as a whole (8 Cannon § 2997) Prohibiting Prohibiting speculation in cotton, speculation in cotwheat, and corn (8 Cannon § 3001) ton. . . . Designating a single National His-Altering regulations for all Historic toric Trail. . . . Trails (110-2, July 10, 2008, p

14584)

Amending a law in one par- Repealiticular... Cannon

Authorizing loans to farmers in certain areas. . . .

Terminating a specific mortgage refinancing program. . . .

Authorizing foreign economic assistance to *certain qualifying nations*. . . .

Restricting the use of funds for military operations in South Vietnam. . . .

Amending the Constitution to prohibit the U.S. or any State from denying persons 18 years of age or older the right to vote. . . .

Criminalizing obstruction of court orders relating to desegregation of public schools. . . .

Relating to *official conduct* of Federal employees. . . .

Repealing the law (5 Hinds § 5924; 8 Cannon § 2949)

Amendment

Authorizing loans without geographical restriction (8 Cannon § 3235)

Authorizing a study of mortgages generally (112-1, Mar. 10, 2011, p

Requiring reports on human rights violations by *all foreign countries* (Deschler-Brown Ch 28 § 35.58)

Extending that restriction to other countries in Indochina (Deschler-Brown Ch 28 § 9.48)

Requiring the U.S. and all States to treat persons 18 years and older as having reached the age of legal majority for all purposes under the law (Manual § 937)

Extending criminalization to all court orders (Deschler-Brown Ch 28 § 9.12)

Relating to any criminal conduct of those officials (Deschler-Brown Ch 28 § 9.49)

schools). . . .

## **Held Not Germane—Continued**

## Text

# Extending the benefits of a Federal program to one class (public

Amending existing law to promote economic development through financial assistance to local communities. . . .

Addressing mental health. . . .

Suspending temporarily certain requirements of the Clean Air Act. . . .

Authorizing activities of certain government agencies for a temporary period. . . .

Appropriating or authorizing funds for only one year. . . .

Amending an existing law to authorize a program. . . .

Striking from a bill one activity from those covered by the law being amended. . . .

Continuing funding within one executive department. . . .

Relating to one aspect of Federal spending (U.S. contributions to an international financial institution). . . .

#### Amendment

Extending the benefits to a broader category—all nonprofit institutions in depressed areas (Deschler-Brown Ch 28 § 39.18)

Requiring a study of the impact of *all* Federal, State, and local laws and regulations on employment opportunities (Deschler-Brown Ch 28 § 9.35)

Addressing a variety of public health programs (Deschler-Brown Ch 28 § 4.104)

Suspending temporarily other requirements of all other environmental protection laws (Deschler-Brown Ch 28 § 4.5)

Permanently changing existing law to cover a broader range of government activities (*Manual* § 937)

Extending the appropriation or authorization to another year (Deschler-Brown Ch 28 § 9.2)

Restricting authorizations under that or any other act (Manual § 937)

Striking an entire subsection of the bill, thereby eliminating the applicability of existing law to a number of activities (*Manual* § 937)

Addressing funding for other departments or addressing the compensation of all Federal employees (*Manual* § 937)

Relating to the entire Federal budget, mandating that total outlays not exceed receipts (Deschler-Brown Ch 28 § 35.48)

#### **Text**

#### Amendment

Appropriating	funds	tor	a	program
for one fiscal	year			

Prohibiting the use of funds appropriated for a fiscal year for a specified purpose. . . .

Proposing a temporary change in law. . . .

Amending an authority of an agency under an existing law. . . .

Establishing an office in the Department of the Interior to manage biological information. . . .

Waiving a requirement in existing law that an authorization be enacted before the obligation of certain funds. . . .

Relating only to a certain appropriation account in a bill. . . .

Raising an employment ceiling for one year. . . .

Authorizing Federal funds for qualifying State national service programs. . . .

Addressing particular educational requirements imposed on educational agencies. . . .

Relating to eligibility for funding in any fiscal year (Deschler-Brown Ch 28 § 15.24)

Prohibiting the use of funds appropriated for that or any prior fiscal year for an unrelated purpose (Deschler-Brown Ch 28 § 9.20)

Proposing permanent changes in that law (Manual § 937)

Expressing the sense of Congress on regulatory agencies generally (*Manual* § 937)

Addressing requirements of compensation for constitutional takings by other regulatory agencies (*Manual* § 937)

Enacting by reference bills containing not only that authorization but also other policy matters (*Manual* § 937)

Relating not only to that account but also to funds in other acts (*Manual* § 937)

Addressing in permanent law a hiring preference system for such employees (*Manual* § 937)

Conditioning a portion of such funding on the enactment of State laws immunizing volunteers in nonprofit or public programs, generally, from certain legal liabilities (*Manual* § 937)

Addressing any requirements imposed on educational agencies by the underlying bill (*Manual* § 937)

#### **Text**

#### **Amendment**

Reauthorizing programs administered by the Economic Development Administration and the Appalachian Regional Commission. . . .

Waiving any Federal regulation that would interfere with economic development (*Manual* § 937)

Prohibiting a certain class of abortion procedures. . . .

Prohibiting any or all abortion procedures (*Manual* § 937)

Addressing a class of imported goods (those produced by forced labor). . . .

Addressing all imported goods from one specified country (Manual § 937)

## § 11. — Specific Amendments to General Propositions

A general proposition may be amended by a specific proposition or one more limited in nature if within the same class. *Manual* § 938; 8 Cannon §§ 3002, 3009, 3012; Deschler-Brown Ch 28 § 10. Thus, a bill regulating the transportation of fruits of all kinds could be amended by language applicable specifically to oranges. Where a bill seeks to accomplish a general purpose by diverse methods, an amendment that adds a specific method to accomplish that result may be germane. Deschler-Brown Ch 28 § 6.47. Thus, to a bill authorizing a broad program of research and development, an amendment directing specific emphasis during the administration of that program was held germane. Deschler-Brown Ch 28 § 10.9.

To a proposition conferring a broad range of authority to accomplish a particular result, an amendment granting specific authority to achieve that result is germane. Deschler-Brown Ch 28 § 10.10.

An amendment defining a term in a bill may be germane so long as it relates to the bill (but may not rely on a relationship to a law being amended by the bill in aspects not the subject of the bill). Thus, to a bill clarifying the definition of persons or institutions under certain civil rights statutes, an amendment providing that the term "person" for the purpose of the bill shall include unborn children was held germane. Deschler-Brown Ch 28 § 10.1.

This principle is illustrated in the following precedents:

## **Held Germane**

Text	Amendment
Appropriating a lump sum for rivers and harbors	Designating specific projects on which a lump sum should be expended (8 Cannon §§ 3004, 3008)
Providing for a decennial census of the entire population of the United States	Relating to the alien population of the United States (8 Cannon § 3005)
Authorizing a commission to report on the public domain	Specifying a report on a designated area of the public domain (8 Cannon § 3007)
Establishing an executive agency and conferring broad authority thereon	Directing that agency to conduct a study of a subject within the scope of that authority (Deschler-Brown Ch 28 § 42.27)
Conferring wide discretionary powers upon an energy administrator	Directing the administrator to issue preliminary summer guidelines for citizen fuel use (Deschler-Brown Ch 28 § 33.15)
Authorizing the Federal Energy Administrator to restrict exports of certain energy resources	Directing that official to prohibit the exportation of petroleum products for use in military operations in Indochina (Deschler-Brown Ch 28 § 33.12)
Directing the President to require all government agencies to use economy-model motor vehicles	Limiting the number of "fuel-inefficient" passenger motor vehicles that the government could purchase (Deschler-Brown Ch 28 § 10.11)
Seeking to accomplish a general purpose (support of the arts and humanities) by diverse methods	Authorizing the employment of un- employed artists through the National Endowment for the Arts (Deschler- Brown Ch 28 § 6.47)
Addressing a range of criminal prohibitions	Addressing another criminal prohibition within that range (Manual § 938)
Addressing violent crimes	Addressing violent crimes involving the environment (Manual § 938)

## § 12. — Adding to Two or More Propositions

A measure containing two or more diverse propositions within the same class may be amended by an amendment adding a third proposition on the same subject. *Manual* § 938; 8 Cannon § 3016; Deschler-Brown Ch 28 § 11. For example, a bill regulating the transportation of apples and oranges could be amended by language extending the bill to bananas. To a bill bringing two new categories within the coverage of existing law, an amendment to include a third category of the same class may be germane. Deschler-Brown Ch 28 § 11.16. Likewise, where a bill contains several unrelated titles on a general subject, an amendment adding a further title within that general subject is germane. *Manual* § 929. Where a bill defines several unlawful acts, an amendment proposing to include another unlawful act of the same class is germane. Deschler-Brown Ch 28 § 11.21.

On the other hand, where a bill covers two or more subjects within a readily definable class, it is not germane to add subjects outside of that class by way of amendment. *Manual* § 938. Thus, to a bill authorizing the Secretary of the Treasury to strike two types of national medals honoring the bicentennial, an amendment permitting private mints to strike State medals was held not germane. 92-2, Feb. 2, 1972, pp 2180-82.

To a bill containing definitions of several of the terms used therein, an amendment may be germane that modifies one of the definitions and adds another (Deschler-Brown Ch 28 § 30.34) or that further defines other terms used in the bill (Deschler-Brown Ch 28 § 11.2).

This principle is illustrated in the following precedents:

**Text** 

## **Held Germane**

Amendment

#### Admitting several Territories into the Admitting another Territory (5 Hinds Union. . . . § 5838) Constructing buildings in two cit-Constructing similar buildings in sevies. . . . eral other cities (5 Hinds § 5840) Providing a number of restrictions on Adding another restriction (8 Cannon § 3010) an expenditure. . . . Providing for a number of Army Providing for an additional camp (8 Cannon § 3012) camps. . . . Authorizing payment to several em-Authorizing payment to another employees for injuries. . . . ployee for such injuries (8 Cannon § 3015)

## Text

#### Amendment

Collecting statistics on agriculture, manufacture, and mining. . . .

Relating to motor trucks and passenger-carrying automobiles. . . .

Setting forth diverse findings and purposes related to a general subject. . . .

Prohibiting indirect assistance to several foreign countries. . . .

Relating to diverse political rights of the people of the District of Columbia. . . .

Funding several departments and agencies. . . .

Extending coverage of gun control laws to rifles, shotguns, and ammunition. . . .

Criminalizing a number of activities in the field of interstate consumer credit transactions. . . .

Extending the coverage of the Flammable Fabrics Act to include wearing apparel and household furnishings. . . .

Reducing tax liabilities in several diverse ways—including tax credits. . . .

Providing farm programs for dairy products, wool, feed grains, cotton and wheat. . . .

Addressing violent crimes. . . .

Collecting statistics on insurance (8 Cannon § 3016)

Relating also to motorcycles and trailers (7 Cannon § 1415)

Setting forth a further finding or purpose related to that subject (Deschler-Brown Ch 28 § 11.23)

Including additional countries within that prohibition (Deschler-Brown Ch 28 § 12.9)

Conferring upon that electorate the additional right of electing a non-voting Delegate to the Senate (Deschler-Brown Ch 28 § 11.25)

Funding subway construction in the District of Columbia (*Manual* § 938)

Relating to registration of firearms by the purchasers thereof (Deschler-Brown Ch 28 § 11.36)

Criminalizing a further activity, "loansharking" (Deschler-Brown Ch 28 § 11.15)

Extending such coverage further to include children's toys (Deschler-Brown Ch 28 § 11.16)

Adding an additional tax credit (Deschler-Brown Ch 28 § 11.34)

Adding a new program for poultry and eggs (Deschler-Brown Ch 28 § 11.28)

Addressing violent crimes involving the environment (*Manual* § 938)

## § 13. Appropriation Bills

An amendment offered to a general appropriation bill must be germane to the part of the bill that is under consideration. Deschler-Brown Ch 28 § 15. An amendment offered to an appropriation bill is judged by the general tests of germaneness that are set forth elsewhere in this chapter. § 4, supra; § 25, infra. Although general appropriation bills are normally read by paragraph, an amendment that increases an appropriation by transferring amounts from an account in another paragraph is normally offered under the protection of clause 2(f) of rule XXI. Therefore, in modern practice, the germaneness rule does not preclude such a transfer amendment. *Manual* § 929.

Subject to clause 2(c) of rule XXI (requiring that limitation amendments to general appropriation bills be offered at the end of the reading of the bill for amendment), an amendment limiting the use of funds by a particular agency funded in a general appropriation bill may be germane to the paragraph carrying the funds or to any general provisions portion of the bill affecting that agency or all agencies funded by the bill. However, an amendment limiting funds in a general appropriation bill for activities prescribed by laws unrelated to the functions of departments and agencies addressed by the bill was held not germane. *Manual* § 929.

Germaneness is an express requirement of any amendment sought to be introduced pursuant to the Holman rule, which permits legislative matter in general appropriation bills under certain circumstances. *Manual* § 1062; see APPROPRIATIONS.

This principle is illustrated in the following precedents:

#### **Held Germane**

## Text Amendment

Appropriating certain funds and permitting them to remain available beyond the fiscal year covered by the bill. . . .

Appropriating funds for foreign assistance programs. . . .

Appropriating funds for the Department of Agriculture and including a specific allocation of funds for animal disease and pest control. . . .

Placing certain restrictions on their use, to become effective after the expiration of the fiscal year (Deschler-Brown Ch 28 § 15.27)

Denying funds therein to pay arrearages or dues of members of the United Nations (Deschler-Brown Ch 28 § 15.8)

Limiting funds in the Act for chemical pesticides where their use would be prohibited by State or local law (Deschler-Brown Ch 28 § 15.7)

#### **Text**

#### Amendment

Appropriating funds for the Depart- Limiting funds in the Act for financment of Defense. . . .

ing of certain military operations (Deschler-Brown Ch 28 § 15.27)

#### **Held Not Germane**

#### **Text**

#### Amendment

Prohibiting aid to one nation unless a certain condition is met. . . .

Prohibiting aid to another nation pending certain actions, and referring to funds in other Acts (Deschler-Brown Ch 28 § 15.15)

Continuing appropriations pending enactment of regular appropriation bills and curtailing certain government expenditures. . . .

Requiring an agency to report to each Member the total Federal expenditures in the congressional district represented by each Member and directing the Members to take certain steps to effect a reduction in expenditures (Deschler-Brown Ch 28 § 15.48)

Continuing appropriations for certain departments and agencies for one month. . . .

Restricting the total administrative budget expenditures for the fiscal year and thus affecting funds not continued by the bill (Deschler-Brown Ch 28 § 15.17)

Providing supplemental appropriations for certain specified departments of government. . . .

Affecting appropriations for virtually all departments and agencies of government (Deschler-Brown Ch 28 § 15.14)

Continuing the availability of appropriated funds and also imposing diverse legislative conditions on the availability of appropriations. . . .

Changing permanent law as to the eligibility of certain recipients (Deschler-Brown Ch 28 § 15.26)

Appropriating funds for an agency for one year. . . .

Changing the appropriation figure but also adding language having the effect of permanent law (Deschler-Brown Ch 28 § 27.24)

#### **Text**

#### Amendment

Appropriating funds for a certain purpose for one government agency. . . .

Appropriating funds for another government agency for the same general (Deschler-Brown Ch 28 purpose § 15.37)

departments and agencies. . . .

Providing appropriations for certain Limiting funds therein to activities prescribed by laws unrelated to the functions of departments and agencies addressed by the bill (Manual § 929)

## B. Application of Rule to Particular Forms of Amendment

## § 14. In General

The rule requiring germaneness of amendments has been applied to many forms of propositions having amendatory effect, including an amendment to a particular part of a bill (§ 15, infra), amendments to amendments (8 Cannon § 2924), and motions to recommit with instructions (§ 20, infra). The rule applies to amendments recommended by committee as well as to amendments offered from the floor. § 19, infra.

The form in which an amendment is offered may affect the determination of whether the amendment is germane. Thus, whether an amendment adds a new title to a bill or adds language to an existing title may affect the determination of whether the amendment is germane. § 16, infra.

#### § 15. Amendments to Particular Portion of Bill

An amendment must be germane to the particular portion of the bill that is open to amendment; that is, an amendment must be germane to the pending paragraph, section, or title. Manual § 929; Deschler-Brown Ch 28 § 18. The Chair will evaluate the germaneness of an amendment by comparing the amendment to the pending portion of the bill without considering the bill as a whole. Deschler-Brown Ch 28 § 18.3.

The test of germaneness of an amendment is its relationship to the pending portion of the bill, as amended to that point. Manual § 929. For this reason, an amendment inserting a new section may be ruled out because it is not germane to the bill as read to that point. However, a similar amendment may be allowed subsequently when the scope of the bill has been broadened by additional sections passed in the reading or adoption of additional amendments. Deschler-Brown Ch 28 § 18.1. An amendment that would be germane if offered when the bill is first taken up may not be germane to the bill, as modified, after portions of the bill have been stricken by amendment. 8 Cannon § 2910.

# § 16. Adding New Section or Title

An amendment in the form of a new title, section, or paragraph need not necessarily be germane to the title, section, or paragraph immediately preceding it. The Chair will evaluate the relationship of the amendment to as much of the bill as has been read. 8 Cannon §§ 2932, 2935; Deschler-Brown Ch 28 § 19. If an amendment is offered at the conclusion of the reading, the Chair will evaluate the relationship of the amendment to the bill as a whole, as perfected. *Manual* § 929; Deschler-Brown Ch 28 § 19.3. For this reason, an amendment that might not be germane when offered to a particular title of a bill may be considered germane if offered as a new title. Deschler-Brown Ch 28 § 18.7. This test is applied even though the amendment in effect modifies (albeit indirectly) a provision previously read and passed. Deschler-Brown Ch 28 § 19.11.

In determining the application of this test, the Chair must take into account whether the text is being read by titles, sections, or paragraphs. Thus, the test of the germaneness of an amendment in the form of a new section to a title of a bill being read by *titles* is the relationship between the amendment and the pending title. Deschler-Brown Ch 28 § 3.11.

# § 17. Striking Text

An amendment striking language from a bill may not be germane if the result of the amendment extends the scope of the provisions of the bill to subjects other than those originally presented. 8 Cannon § 2920. Deschler-Brown Ch 28 § 20. A pro forma amendment merely to "strike the last word" to secure time for debate in the Committee of the Whole is germane. *Manual* § 928.

#### § 18. Substitute Amendments

The test of the germaneness of a substitute amendment is its relationship to the amendment to which it is offered and not its relationship to the underlying bill. *Manual* § 929; Deschler-Brown Ch 28 § 21. A substitute must be confined in scope to the subject of the amendment and must relate to the same portion of the bill being addressed by the amendment. Deschler-Brown Ch 28 §§ 9.42, 21. Thus, for an amendment establishing a termi-

nation date for the Federal Energy Administration, a substitute not dealing with the date of termination, but providing instead a reorganization plan for that agency, was ruled out as not germane. Deschler-Brown Ch 28 § 21.1.

However, for an amendment changing certain language in a pending section, a substitute changing that text and also adding language in the section may be germane if it has the effect of dealing with the same subject in a related and more limited way. Deschler-Brown Ch 28 § 32.16.

# § 19. Committee Amendments

The rule of germaneness applies to committee amendments as well as to those offered by individual Members. 5 Hinds § 5806; Deschler-Brown Ch 28 § 22. A committee amendment that is not germane to the bill as introduced may require a waiver in the rule providing for the consideration of the underlying bill. Deschler-Brown Ch 28 § 45.2.

# § 20. Recommittals; Instructions to Committees

The germaneness rule applies to instructions in a motion to recommit a bill to a committee. It is not in order to propose as part of a motion to recommit any proposition that would not have been germane if proposed as an amendment to the bill on the floor. *Manual* §§ 929, 930; 5 Hinds §§ 5529-5541; 8 Cannon §§ 2708-2712. In one instance, for example, during consideration of a bill authorizing military expenditures, a motion to recommit with instructions was ruled not germane because it contained provisions seeking to prescribe foreign policy objectives. Deschler-Brown Ch 28 § 23.3.

The test of germaneness in the case of a motion to recommit with instructions is the relationship of the instructions to the bill taken as a whole as perfected (and not merely to the separate portion of the bill specifically proposed to be amended in the instructions). *Manual* § 930. This is so even where the instructions do not propose a direct amendment to the bill but merely contain general instructions to the committee to pursue an unrelated approach or to instruct the committee not to report the bill back to the House until an unrelated contingency occurs. 8 Cannon § 2704; Deschler-Brown Ch 28 § 23.9.

A point of order against a motion to recommit with instructions has been entertained before completion of the reading of such motion where the matter contained in the instructions has been ruled not germane when offered as an amendment in the Committee of the Whole (Deschler-Brown Ch 28 § 23.3) or after a non-germane portion of the instructions has been read (*Manual* § 628).

# C. Amendments Imposing Qualifications or Limitations

# § 21. In General; Exceptions or Exemptions

As pointed out earlier in this chapter, a general subject may be amended by a specific proposition of the same class. § 11, supra. Under an extension of this principle, an amendment that makes a specific exception to or exemption from a general proposition is germane. 8 Cannon § 3028; Deschler-Brown Ch 28 § 29. Thus, to a section dealing with a designated class, an amendment exempting from the provisions of the section a certain portion of that class may be germane. 8 Cannon § 3026. Provisions restricting authority may be modified by amendments providing exceptions to those restrictions. 8 Cannon § 3024.

This principle is illustrated in the following precedents:

# **Held Germane**

Text	Amendment			
Deporting aliens	Exempting a portion of such aliens from deportation (8 Cannon § 3029)			
Prohibiting courts from issuing injunctions in labor disputes	Excepting all labor disputes affecting public utilities (8 Cannon § 3024)			
Prohibiting an administrator from setting ceiling prices above a certain level for domestic crude oil	Exempting new crude petroleum sold by producers of less than 30,000 bar- rels per day (Deschler-Brown Ch 28 § 29.13)			
Limiting discretionary powers conferred in a bill	Providing an exception from that limitation (Deschler-Brown Ch 28 § 35.13)			
Requiring NLRB certification of employee elections of unions as bargaining agents only where there has been a secret ballot	Excepting an employer that has undermined the election or is otherwise estopped from challenging it (Deschler-Brown Ch 28 § 35.24)			
Denying benefits to recipients failing to meet a certain qualification	Denying the same benefits to some recipients but excepting others (Deschler-Brown Ch 28 § 29.11)			

# § 22. Conditions or Qualifications

A condition or qualification sought to be added by way of amendment must be germane to the provisions of the bill. *Manual* § 940; Deschler-

Brown Ch 28 § 30. An amendment is not germane if it makes the effectiveness of a bill contingent upon an unrelated event or determination. Deschler-Brown Ch 28 § 31.22. Thus, an amendment making the implementation of a funding program contingent upon compliance with unrelated legislation is not germane. Deschler-Brown Ch 28 § 30.23. For discussion of postponements pending contingencies, see § 26, infra.

On the other hand, an amendment imposing a condition may be in order if it imposes a prerequisite that comes within the general subject covered by the bill. For example, where a bill provided a comprehensive grant program that included within its scope the welfare of law enforcement officers, an amendment requiring States to enact a law enforcement officers' grievance system as a prerequisite to receiving grants under the bill was held to come within the general subject of law enforcement improvement covered by the bill and was held germane. Deschler-Brown Ch 28 § 30.30.

Assistance to a particular class of recipient covered by a bill may not by amendment be conditioned on actions or inaction by another class of recipient or agent not covered by the bill. Deschler-Brown Ch 28 § 30.29. For example, an amendment conditioning the availability to certain recipients of funds in an authorization bill upon their compliance with Federal law *not otherwise applicable to those recipients* and within the jurisdiction of other House committees may be ruled out as not germane. Deschler-Brown Ch 28 § 34.37.

This principle is illustrated in the following precedents:

**Text** 

# **Held Germane**

Amendment

Authorizing funds for a variety of programs that satisfy several stated requirements, in order to accomplish a general purpose	Conditioning the availability of those funds upon implementation of another program related to that general purpose (Deschler-Brown Ch 28 § 30.30)
Providing for scholarships	Providing requirements for eligibility for such scholarships (Deschler-Brown Ch 28 § 30.11)
Authorizing funds for military pro- curement and construction	Barring use of the funds in military operations in North Vietnam (Deschler-Brown Ch 28 § 30.6)

# Text Amendment

Authorizing the insurance of ves- Denying such insurance to vessels sels. . . . charging exorbitant rates (8 Cannon § 3023) Authorizing an agency to undertake Allowing Congress to disapprove certain activities. . . . regulations issued pursuant thereto (Deschler-Brown Ch 28 § 33.11) Requiring certain intelligence infor-Imposing relevant conditions of secube given rity on the handling of such informamation to to the House. . . . tion in committee (Manual § 940)

# § 23. Restrictions or Limitations

Restrictions and limitations sought to be added to a bill by way of amendment must be germane to the provisions of the bill. *Manual* § 940; Deschler-Brown Ch 28 § 32. Thus, to a bill amending a statute, an amendment prohibiting assistance under that Act or under any other Act for a particular purpose, and affecting laws not being amended by the bill, may be ruled out as not germane. Deschler-Brown Ch 28 § 35.62.

This principle is illustrated in the following precedents:

#### **Held Germane**

Text	Amendment			
Authorizing change in railroad rates	Excluding rate increases (8 Cannon § 3022)			
Authorizing aid to shipping	Limiting such aid to ships equipped with life-saving devices (8 Cannon § 3027)			
Authorizing use of oil-burning engines on ships	Prohibiting use of such engines if constructed outside of the United States (8 Cannon § 3032)			
Furnishing medical services and facilities	Prohibiting the use of such services to perform certain abortions (Deschler-Brown Ch 28 § 32.7)			
Providing unlimited terms of service for judges	Restricting terms to four years (8 Cannon § 3031)			

#### **Text**

#### Amendment

Transferring specified property solely for the purpose of providing shelter to the homeless and protecting the public health. . . .

Requiring reversion of the property if not used for that charitable purpose as defined under a provision of the Internal Revenue Code (Deschler-Brown Ch 28 § 32.12)

Providing Federal funds to States for certain purposes. . . .

Restricting payment of those funds to States that enact certain laws relating to the activities being funded (*Manual* § 940)

# **Held Not Germane**

#### Text

#### Amendment

Repairing naval vessels. . . .

Prohibiting such repairs in navy yards (in order to make them at less expense elsewhere) by restricting funds in portions of the bill not open to amendment (8 Cannon § 3034)

# § 24. — Discretionary Powers

To a proposition conferring discretionary authority, an amendment limiting or restricting the exercise of that authority is germane. 8 Cannon § 3022; Deschler-Brown Ch 28 § 33. Such an amendment may be germane, even though it incorporates as a term of measurement a qualification or condition applicable to entities beyond the scope of the bill. Deschler-Brown Ch 28 § 33.23. For example, to a proposition that the Administrator of Veterans' Affairs be authorized to establish a maximum interest rate for loans, an amendment stating that "the rate fixed shall not be higher than the FHA rate" was held germane. Deschler-Brown Ch 28 § 33.28.

Although a proposition reorganizing existing discretionary agency authority may be amended by imposing limitations on the exercise of those functions, an amendment directly changing policies in the substantive law to be administered by that agency is not germane. Deschler-Brown Ch 28 § 33.13.

This principle is illustrated in the following precedents:

# Held Germane

# **Text**

#### Amendment

Authorizing funds for the National Aeronautics and Space Administration. . . .

Conferring authority on the President to establish rules for ordering priorities among petroleum users and requiring that vital services in the areas of education and transportation shall receive priority. . . .

Prescribing the functions of a new Federal Energy Administration by conferring wide discretionary powers on the administrator. . . .

Prescribing the functions of a new Federal Energy Administration. . . .

Authorizing an agency to undertake certain activities. . . .

Continuing U.S. participation under the International Development Association Act. . . .

Containing diverse provisions relating to authorities of the Department of Defense. . . .

Prohibiting contracts for "support" services except where certain cost comparisons were made (Deschler-Brown Ch 28 § 33.27)

Restricting that regulatory authority by requiring that petroleum products allocated for public school transportation be used only between the student's home and the school closest thereto (Deschler-Brown Ch 28 § 33.9)

Limiting the authority of the administrator in setting prices for propane gas by requiring an equitable allocation of production costs (Deschler-Brown Ch 28 § 33.17)

Prohibiting the promulgation of petroleum rationing rules without prior approval by Congress (Deschler-Brown Ch 28 § 33.16)

Providing that regulations issued pursuant to that authority may be disapproved by Congress (Deschler-Brown Ch 28 § 33.11)

Directing opposition in that forum to loans to nations not party to a nuclear nonproliferation treaty (Deschler-Brown Ch 28 § 33.29)

Precluding the use of certain land for deployment of a weapons system pending a study (Deschler-Brown Ch 28 § 11.17)

# § 25. — Use of Funds

Amendments that merely place restrictions on the use of funds that are authorized or referred to in the bill are generally upheld as germane. Deschler-Brown Ch 28 § 34. An amendment seeking to restrict the use of funds

must be limited to the subject matter and scope of the provisions sought to be amended. Manual § 940. The amendment must be confined to the agencies, authorities, and funds addressed by the bill and may not be more comprehensive in scope. Deschler-Brown Ch 28 § 32.6. A limiting amendment may be held not germane if it places restrictions on funds authorized or appropriated in other bills. Deschler-Brown Ch 28 § 31.30. To be germane, the amendment restricting the use of funds must relate solely to those funds and may not apply to another related category of funds. Deschler-Brown Ch 28 § 34.23.

An amendment limiting the use of funds by a particular agency funded in a general appropriation bill may be germane at more than one place in the bill. Subject to clauses 2(c) and (d) of rule XXI, the amendment may be offered when the paragraph carrying such funds is pending, or to an appropriate "general provision" portion of the bill affecting that agency or all agencies funded by the bill. Deschler-Brown Ch 28 § 15.1.

This principle is illustrated in the following precedents:

#### **Held Germane**

#### Authorizing supplemental appropria-Prohibiting use of those funds to tions for military procurement, develcarry out military operations in North Vietnam (Deschler-Brown Ch 28 opment, and construction. . . . § 34.10)

Appropriating funds for an additional Washington airport. . . .

**Text** 

Authorizing an investigation and incidental travel to be undertaken by a committee of the House. . . .

Authorizing appropriations to enter into contracts for the development of synthetic fuels. . . .

Authorizing appropriations for contributions to the United Nations Environmental Fund. . . .

Amendment

Limiting the amount to be used for the construction of an access road (Deschler-Brown Ch 28 § 34.32)

Restricting use of the funds permitted in such travel (Deschler-Brown Ch 28 § 34.5)

Prohibiting use of the funds to enter into contracts with any major oil company (Deschler-Brown Ch 28 § 34.28)

Prohibiting use of those funds to assist in the reconstruction of North Vietnam (93-1, May 15, 1973, pp 15747, 15752)

#### **Text**

#### Amendment

Authorizing appropriations for the National Science Foundation. . . .

Prohibiting use of those funds for research on a live human fetus outside the womb (93-1, June 22, 1973, p 20946)

Establishing a rural electrification and telephone revolving fund for insured and guaranteed loans. . . .

Providing that no such funds be used outside the United States or its possessions (93-1, Apr. 4, 1973 p 10395)

Continuing U.S. participation under the International Development Association Act. . . .

Prohibiting use of U.S. contributions as loans for the purchase of nuclear weapons or materials (Deschler-Brown Ch 28 § 32.5)

Restricting the availability of funds to a certain category of recipients. . . .

Restricting further the availability of those funds to a subcategory of the same recipients (Deschler-Brown Ch 28 § 34.4)

Providing assistance for mass transportation programs and permitting certain school systems to be eligible applicants for school bus subsidies. . . .

Prohibiting use of funds to implement programs intended to overcome racial imbalance in school systems (Deschler-Brown Ch 28 § 34.20)

Authorizing funds and limited use of troops for a specific purpose. . . .

Denying funds for deployment of troops beyond a certain period of time (Deschler-Brown Ch 28 § 34.13)

Providing Federal funds to States for certain purposes. . . .

Restricting payment of those funds to States that enact certain laws relating to the activities being funded (*Manual* § 940)

#### **Held Not Germane**

# Text

#### Amendment

Changing a dollar amount in operating expenses for an agency. . . .

Prohibiting a certain activity and the use of any funds therefor (*Manual* § 940)

#### **Text**

#### Amendment

Establishing a new Department of Education and addressing only the administrative structure of the department. . . .

Approving an increase in the U.S. quota to the International Monetary Fund and authorizing dealing in gold in connection therewith. . . .

Striking a provision prohibiting the use of funds in the bill for a designated oil land lease in California. . . .

Providing general appropriations. . . .

Prohibiting the use of funds to compel the transportation of students or teachers with the goal of establishing racial or ethnic balance (Deschler-Brown Ch 28 § 34.38)

Prohibiting the alienation of gold to *any* international organization or its agents, or to *any* person or organization acting for certain purchasers (Deschler-Brown Ch 28 § 32.6)

Prohibiting use of funds in the bill or in any other act for that lease and other California leases (Deschler-Brown Ch 28 § 15.21)

Limiting funds therein to activities prescribed by laws unrelated to the functions of departments and agencies addressed by the bill (*Manual* § 940)

# § 26. Postponing Effectiveness Pending Contingency

Amendments that merely postpone the effective date of the legislation to a date certain without stating a condition have been held germane. Thus, to a title of a bill establishing procedures permitting either House of Congress to disapprove an impoundment of appropriated funds by the President, an amendment delaying the effective date of that title to a day certain was held germane. *Manual* § 940. Similarly, to an amendment abolishing the Federal Energy Administration on a date certain and transferring some of its functions to other agencies at that time, an amendment delaying the termination date of that agency for one year was held germane. Deschler-Brown Ch 28 § 32.10.

An amendment may make the effectiveness of a bill subject to a condition if that condition is related to the provisions of the bill. Deschler-Brown Ch 28 § 31.33. An amendment delaying operation of a proposed amendment pending a determination of a fact is germane when the fact to be determined relates solely to the subject matter of the bill. 8 Cannon § 3029; Deschler-Brown Ch 28 § 31.18. However, an amendment is not germane if it delays

the effectiveness of a bill contingent upon actions not involved in the administration of the affected program and that extend in scope beyond the authorities contained in the bill. Deschler-Brown Ch 28 § 31.1.

An amendment delaying the operation of proposed legislation pending an unrelated contingency is not germane. *Manual* § 940; 8 Cannon § 3037; Deschler-Brown Ch 28 § 31. Thus, an amendment making the implementation of Federal legislation contingent upon the enactment of unrelated State legislation is not germane. Deschler-Brown Ch 28 § 31.5. It is not germane for an amendment to render a measure contingent upon an unrelated congressional action. For example, to a bill authorizing appropriations for radio broadcasting to Cuba, an amendment prohibiting use of those funds until Congress considered a constitutional amendment mandating a balanced budget was ruled out as nongermane, imposing an unrelated contingency requiring separate congressional action on another subject. Deschler-Brown Ch 28 § 31.39. Likewise, an amendment to an appropriation bill delaying the availability of the appropriation pending an unrelated contingency—the enactment of certain revenue legislation—was held not germane. Deschler-Brown Ch 28 § 31.8.

An amendment may subject the operation of the bill to an external benchmark, so long as it does not constitute an unrelated condition. For example, an abstract fiscal standard may be used as the measure of availability of funding provided by the bill, or as the measure of applicability of a fiscal or budgetary feature of the bill. Deschler-Brown Ch 28 § 34.1.

This principle is illustrated in the following precedents:

#### **Held Germane**

Text	Amendment			
Authorizing funds for elementary and secondary education	Prohibiting use of those funds "so long as the present Commissioner of Education occupies that office" (Deschler-Brown Ch 28 § 31.42)			
Funding cost-of-living salary increase for Members	Restricting availability of those funds during months in which there is ar increase in the public debt (Deschler- Brown Ch 28 § 34.1)			

#### **Text**

#### Amendment

Authorizing appropriations for humanitarian and evacuation assistance to war refugees in South Vietnam. . . .

Making that authorization contingent on a report to Congress on the costs of a portion of the evacuation program (Deschler-Brown Ch 28 § 34.12)

Delaying that assistance until that nation's former ambassador testified before a House committee (Deschler-Brown Ch 28 § 31.33)

# **Held Not Germane**

#### **Text**

#### Amendment

Extending funding for housing and urban renewal. . . .

Making such funding contingent on enactment of legislation raising additional revenue (Deschler-Brown Ch 28 § 31.11)

Appropriating funds for emergency fuel assistance. . . .

Making such funding contingent on enactment of an oil windfall profit tax (Deschler-Brown Ch 28 § 31.8)

Authorizing funds for one Federal agency. . . .

Making such funding contingent on appropriations for another Federal agency (110-1, May 2, 2007, p 11094)

Authorizing funds for construction of atomic energy facilities. . . .

Making such project contingent upon the enactment of Federal or State fair-housing measures (Deschler-Brown Ch 28 § 31.5)

Authorizing appropriations for the Arms Control and Disarmament Agency. . . .

Making such authorization contingent on the Soviet Union ceasing "to supply military articles to our enemy in Vietnam" (Deschler-Brown Ch 28 § 31.32)

Authorizing funds for foreign assistance. . .

Making aid to a nation contingent upon the enactment of tax reform measures by that nation (Deschler-Brown Ch 28 § 31.37)

# Text

#### Amendment

Authorizing military assistance to Israel and funds for the United Nations Emergency Force in the Middle East. . . .

Authorizing the development of certain military missile systems. . . .

Rescinding an agency's funds for motor vehicle seat belt and passive restraint research and education. . . .

Making such funds to Israel contingent on Presidential certification of the existence of a designated level of energy supplies for the U.S. (Deschler-Brown Ch 28 § 31.22)

Making expenditures contingent on the impact of U.S. grain sales on Soviet military preparedness (Deschler-Brown Ch 28 § 31.24)

Conditioning the availability of *all* funds pending State compliance with Federal standards for *mandatory seat belt use* (Deschler-Brown Ch 28 § 15.19)

# D. Relation to Existing Law

# § 27. Amendments to Bills Amending Existing Law

The germaneness rule may provide the basis for a point of order against an amendment that is offered to a bill amending existing law. A germaneness point of order may be sustained where the proposed amendment relates to the existing law rather than to the pending bill. *Manual* § 939; 8 Cannon §§ 2916, 3045; Deschler-Brown Ch 28 § 35. Unless a bill so extensively amends existing law as to open up the entire law to amendment, the germaneness of an amendment to the bill depends upon its relationship to the subject of the bill and not to the entire law being amended. Deschler-Brown Ch 28 § 35.95. A bill amending several sections of one title of the U.S. Code does not necessarily bring the entire title under consideration so as to permit an amendment to any portion thereof. Deschler-Brown Ch 28 § 35.

Where a bill amends existing law in one narrow particular, an amendment proposing to modify such existing law in other particulars will generally be ruled out as not germane. Deschler-Brown Ch 28 § 35.65. Likewise, if a bill amending existing law relates to a single subject or has a single purpose, an amendment is not germane that proposes to modify the law further in a manner not related to the purpose of the bill. Deschler-Brown Ch 28 §§ 35.51, 41.4. Where a proposition narrowly amends one section of

existing law by changing a specific program therein, that section of law is not open to a further amendment that would enlarge the scope of the pending proposition. 92-1, Dec. 8, 1971, p 45536.

To a proposition modifying a limited portion of existing law, an amendment further modifying that portion may be germane. Deschler-Brown Ch 28 § 35.19. Such an amendment may add exceptions or definitions modifying the proposition if related to the same subject. Deschler-Brown Ch 28 § 35.24. However, an amendment repealing the law is not germane. Deschler-Brown Ch 28 § 36.1.

This principle is illustrated in the following precedents:

#### **Held Not Germane**

# Text Amendment

Amending a section of title 5 of the U.S. Code granting certain rights to employees of executive agencies. . . .

Amending a portion of an existing law to extend the authorization for U.S. contributions to the International Monetary Fund. . . .

**Text** 

Extending those rights to legislative branch employees as defined in a different section of that title (Deschler-Brown Ch 28 § 35.95)

Amending another section of that law mandating that the total budget outlays of the Federal government shall not exceed its receipts (Deschler-Brown Ch 28 § 35.48)

Amendment

# § 28. Amendments to Bills Repealing Existing Law

Where a bill repealing several sections of an existing law is pending, an amendment proposing to repeal the entire law may be germane. Where the bill seeks to repeal only one provision of an existing law, an amendment modifying that provision (rather than repealing it) also may be germane. Deschler-Brown Ch 28 § 37. On the other hand, to a bill repealing one narrow subsection of existing law, an amendment proposing a comprehensive revision of the whole law is not germane. Deschler-Brown Ch 28 § 37.7.

This principle is illustrated in the following precedents:

# **Held Not Germane**

Repealing	Chinese	Exclusion	Relating	to	immigration	generally
Acts			(Deschler-Brown Ch 28 § 37.6)			

# Text

#### Amendment

Repealing a narrow provision of an existing Act. . . .

Expressing congressional policy as to the pending bill *and* to the administration of the whole Act (Deschler-Brown Ch 28 § 37.9)

Repealing a narrow subsection of law relating to the order of induction of selective service registrants. . . .

Placing restrictions on the assignment of personnel to Vietnam without their consent (Deschler-Brown Ch 28 § 37.8)

# § 29. Amendments to Bills Incorporating Other Laws by Reference

A general rule of germaneness is that an amendment to a law in the jurisdiction of one committee is not germane to a bill in the jurisdiction of another committee. See § 6, supra. However, where the pending bill incorporates by reference provisions of a law from another committee and conditions the effectiveness of the bill upon actions taken pursuant to a section of that law, an amendment to alter that section of the law may be germane. Deschler-Brown Ch 28 § 4.100. Furthermore, a bill incorporating by reference procedural requirements contained in other Acts may be broad enough to permit an amendment similarly referring to, but not directly amending, other statutes and intending to accomplish the result sought to be effected by the portion of the bill to which offered. For example, to a bill including requirements for certification of Federal land use activities as compatible with approved State management programs and incorporating by reference certain statutory provisions, an amendment applying the procedures contained in those statutes to approval of such Federal land use programs in lieu of the certification procedures in the bill was held germane. Deschler-Brown Ch 28 § 4.100. On the other hand, to a bill citing but not amending a law on one subject, an amendment incorporating that law by reference to broaden its application to the subject of the bill is not germane. Deschler-Brown Ch 28 § 41.21.

# **Effect of Disclaimers**

Ordinarily, the inclusion of language in a bill "disclaiming" any substantive effect of the bill on other provisions of law would not render germane amendments that do in fact affect that law. However, where disclaimer language in a bill is accompanied by other provisions changing a category

of law cited in the disclaimer, an amendment further addressing the relationship between the bill and laws cited in the disclaimer may be germane. Deschler-Brown Ch 28 § 42.54.

# § 30. Amendments to Bills Continuing or Extending Existing Laws

A bill extending an existing law may open up the law being extended to germane amendments. Deschler-Brown Ch 28 § 39. A bill continuing and reenacting an existing law may be amended by a proposition modifying in a germane manner the provisions of the law being extended. Deschler-Brown Ch 28 § 39.28. To a bill extending an existing law in modified form, an amendment proposing further modification of the law is germane. Deschler-Brown Ch 28 § 39.19. However, while a bill "extending existing law" may open up the law being extended to germane amendments, a proposition that merely extends an official's authority under that law does not necessarily open up the entire law to amendment. Deschler-Brown Ch 28 § 39.27.

This principle is illustrated in the following precedents:

# **Held Germane**

#### **Text** Amendment Continuing for one year the Mexican Requiring a determination that reafarm labor program. . . . sonable efforts have been made to hire domestic workers (Deschler-Brown Ch 28 § 39.14) Amending and extending the Elemen-Providing that no funds in the Act be and Secondary Education used for the transportation of students tary Act. . . . or teachers "in order to meet provisions of" the Civil Rights Act of 1964 (Deschler-Brown § 39.19) Restricting the method of submitting Reenacting a law to extend the existence of the Federal Energy Adminisenergy action proposals to Congress tration, including the authority to (Deschler-Brown Ch 28 § 39.30) conduct energy programs. . . . Extending the existence of the Fed-Requiring that agency to promulgate eral Energy Administration and auregulations to assure that the agency hearings be conducted in certain thorizing appropriations for that agenareas (Deschler-Brown Ch су. . . . § 39.31)

# **Held Not Germane**

# Text Amendment

Extending the authority of the Administrator of Veterans' Affairs to establish a maximum interest rate for insured loans to veterans. . . .

Altering provisions of existing law and modifying the authority of the administrator to manage the loan program (Deschler-Brown Ch 28 § 39.27)

Providing for a temporary extension of certain intelligence laws. . . .

Altering provisions of those laws on a permanent basis (110-2, Feb. 13, 2008, p 2116)

Extending the school milk program and making "preschool programs operated as part of the school system" eligible for benefits. . . .

Extending further such benefits to programs operated by nonprofit institutions in depressed areas (Deschler-Brown Ch 28 § 39.18)

# § 31. Amendments Changing Law to Bills Not Changing That Law Generally

An amendment that amends a law not contemplated in the bill under consideration and not related to the text before the House is subject to a germaneness point of order. Thus, to a bill amending one law, an amendment changing the provisions of another law is not germane. Deschler-Brown Ch 28 § 42. Likewise, to a bill making appropriations for the current fiscal year, an amendment permanently changing existing law is not germane and thus is not in order, even though it tends to reduce expenditures for that year. Deschler-Brown Ch 28 § 42.57. The number and variety of laws being amended by the underlying text may also affect the germaneness of an amendment changing an additional law. *Manual* § 939.

The germaneness of an amendment may be affected by the adoption of other amendments that broaden the scope of the pending bill. For example, where a bill authorizing foreign military assistance was broadened by amendment to address permanent law relating to economic relations with foreign nations, an amendment to remove military and economic trade sanctions against Rhodesia was held germane to the bill as a whole in its perfected form. 95-2, Aug. 2, 1978, p 23938.

This principle is illustrated in the following precedents:

# **Held Not Germane**

#### **Text**

#### Amendment

Reorganizing existing discretionary governmental authority and vesting it in a new agency. . . .

Consolidating certain functions under a new agency and limiting its policymaking authority to that contained in existing law. . . .

Providing in part for increased salaries for Members of Congress and legislative employees. . . .

Amending the Fair Labor Standards Act with respect to the effect of imports on the domestic labor market. . . .

Establishing a Federal Energy Administration but not amending existing laws relating to energy conservation policy. . . .

Regulating the importation of liquefied natural gas, but not directly amending the Natural Gas Act. . . .

Amending certain Acts to provide for market adjustment and price support programs for wheat and feed grains. . . .

Changing for one year an existing law establishing price supports for several agricultural commodities. . . .

Amending several provisions of an existing law. . . .

Directly changing policies in the substantive law to be administered by that agency (Deschler-Brown Ch 28 § 42.23)

Prescribing new policy by amending a law not amended by the bill (Deschler-Brown Ch 28 § 42.24)

Relating to audits of financial transactions of the House and the Architect of the Capitol under another law (Deschler-Brown Ch 28 § 42.45)

Amending the Tariff Act of 1930 with respect to the importation of merchandise from Communist nations (Deschler-Brown Ch 28 § 42.2)

Repealing the Emergency Daylight Saving Time Energy Conservation Act (Deschler-Brown Ch 28 § 42.21)

Amending the Natural Gas Act to prohibit the FPC from regulating the price of natural gas at the well-head (Deschler-Brown Ch 28 § 42.20)

Amending another Act to direct the President to conduct an investigation into imports of specified agricultural products (Deschler-Brown Ch 28 § 42.11)

Waiving the provisions of another law relating to price supports for another agricultural commodity (Deschler-Brown Ch 28 § 42.17)

Repealing a section of another law (Manual § 939)

# Waivers or Repeals

An amendment repealing existing law has been held not germane to a bill not amending that law. Deschler-Brown Ch 28 § 42.21. An amendment may be subject to a point of order on the basis that it contains the language "notwithstanding any other provision of law" if it has the effect of waiving a statute not amended by the bill. Deschler-Brown Ch 28 § 42.17. In one such instance, the Chair noted that the waivers in the bill were waivers of a narrow class of existing laws, whereas the amendment waived various unspecified laws not within the scope of the pending measure. Deschler-Brown Ch 28 § 42.18.

# E. House-Senate Relations

# § 32. Senate Germaneness Rules

In contrast to House practice, there is no general Senate rule prohibiting nongermane amendments. However, questions of germaneness of amendments to general appropriation bills are submitted to the Senate without debate under Senate rule XVI. The Chair does not rule on the question. Another rule prohibits nongermane amendments to bills after cloture has been invoked. See clause 2 of Senate rule XXII. In addition, pursuant to unanimous-consent agreements, the Senate sometimes prohibits nongermane amendments to particular bills, or may prohibit a certain class of nongermane amendments to a bill. Deschler-Brown Ch 28 § 25; see also S. Doc. 101-28. Under section 305 of the Budget Act, amendments offered in the Senate to a concurrent resolution on the budget must be germane; and under section 310, a similar restriction applies to amendments to budget reconciliation bills. *Manual* § 1127.

#### § 33. Motions to Instruct Conferees

The rule that amendments must be germane applies to amendments to a motion to instruct conferees. 8 Cannon §§ 3230, 3235; Deschler-Brown Ch 28 § 28. The test of an amendment to a motion to instruct conferees is the relationship of the amendment to the subject matter of the House and Senate versions of the bill (*Manual* § 930) and not to the original motion to instruct.

Where an amendment in the nature of a substitute has been proposed by one House for the entire bill passed by the other House, provisions in either the bill or the substitute may be addressed in motions to instruct conferees. 8 Cannon § 3230.

# § 34. Senate Provisions in Conference Reports and in Amendments in Disagreement

Formerly, a Senate amendment was not subject to the point of order that it was not germane to the House bill. 8 Cannon § 3425. Today, under changes in the rules enacted in 1972, points of order may be made against nongermane Senate matter in a conference report or in a proposal to concur in a Senate amendment (with or without amendment). If sustained, separate votes may be demanded on portions of Senate amendments and conference reports containing language that would not have been germane if offered in the House. Clause 10 of rule XXII; *Manual* § 1089.

Clause 10 of rule XXII permits points of order against language in a conference report that was originally in the Senate bill or amendment and that would not have been germane if offered to the House-passed version, and permits a separate motion to reject such portion of the conference report if found nongermane. For purposes of that rule, the House-passed version, against which the Senate provisions are compared, is that version finally committed to conference, taking into consideration all amendments adopted by the House, including House amendments to Senate amendments. Deschler-Brown Ch 28 § 27.

Pursuant to clause 10 of rule XXII, where the Speaker sustains a point of order that a portion of a conference report containing a Senate amendment is not germane to the House bill, a motion to reject that portion of the conference report is in order and is subject to 40 minutes of debate. Deschler-Brown Ch 28 § 26.29.

The Member representing the conference committee recognized in opposition to a motion to reject a nongermane Senate provision pursuant to clause 10 of rule XXII, and not the proponent of the motion, has the right to close debate thereon. *Manual* § 1090. After the 40 minutes of debate permitted by that rule, it is then in order, following the disposition of the motion to reject, to make further points of order and motions to reject. If any such motion is adopted, the conference report shall be considered as rejected and the pending question shall be, in the case of a House bill with a Senate amendment, whether the House will recede from disagreement to the Senate amendment and concur therein with an amendment consisting of the portion of the conference report not rejected. Deschler-Brown Ch 28 § 26.31.

Clause 10 of rule XXII also permits points of order against nongermane Senate matter in motions to concur or concur with amendment in Senate amendments, the stage of disagreement having been reached. If such a point of order is sustained, a separate motion to reject such nongermane matter is permitted. *Manual* §§ 931, 1089. Clause 10 is not applicable to a provi-

sion contained in a motion to recede and concur with an amendment that is not contained in any form in the Senate version, the only requirement in such circumstances being that the motion as a whole be germane to the Senate amendment as a whole under the House germaneness rule. Deschler-Brown Ch 28 § 27.12.

This principle is illustrated in the following precedents:

# **Held Not Germane**

#### **House Bill**

#### **Senate Amendment**

Prohibiting the availability of any

Continuing the operations of an executive department for one year. . . .

funds appropriated for foreign military base agreements absent congressional approval (93-1, Sept. 11, 1973, pp 29243-46)

Exempting from tariff duty certain equipment and repairs for vessels operated by the United States. . . .

Extending benefits under the unemployment compensation program (Deschler-Brown Ch 28 § 26.30)

Requiring that a percentage of U.S. oil imports be carried on U.S. flag vessels. . . .

Relating to the construction of vessels with certain anti-pollution requirements (Deschler-Brown Ch 28 § 26.29)

Containing several diverse amendments to the Internal Revenue Code to provide individual and business tax credits. . . .

Authorizing appropriations for special payments to social security recipients (Deschler-Brown Ch 28 § 26.27)

Improving automotive fuel efficiency by imposing fuel economy standards upon manufacturers. . . .

Providing loan guarantees for automotive research and development (Deschler-Brown Ch 28 § 26.15)

# § 35. Amendments to Senate Amendments

An amendment offered in the House to a Senate amendment must ordinarily be germane to the particular Senate amendment to which it is offered, it not being sufficient that the amendment be germane to the provisions of the bill if the Senate amendment merely inserts new matter and does not strike House provisions. 5 Hinds § 6188; 8 Cannon § 2936; *Manual* § 931. Thus, during consideration of a Senate amendment reported in disagreement by conferees, a proposal to amend must be germane to the Senate amendment. Deschler-Brown Ch 28 § 27.35. Although a Senate amendment proposing legislation on a general appropriation bill is subject to an amendment

of a similar character in the House, the requirement remains that the House amendment be germane to the Senate amendment. Deschler-Brown Ch 28 § 27.

The test of the germaneness of an amendment to an amendment contained in a motion to concur in a Senate amendment is the relationship between the offered amendment and the motion, and not the relationship between that amendment and the Senate amendment to which the motion has been offered. Deschler-Brown Ch 28 § 27.6.

The test of germaneness of an amendment in the nature of a substitute to a Senate amendment—proposed in a motion to concur therein with an amendment—is the relationship between the proposed amendment in its entirety and the Senate amendment in its entirety (and not the relationship between any one provision of the amendment and any one provision of the Senate amendment). Deschler-Brown Ch 28 §§ 27.11, 27.12.

The rule of germaneness applies to motions to recede and concur in a Senate amendment with an amendment. Such a motion must be germane to the Senate amendment. Deschler-Brown Ch 28 § 27. However, where a Senate amendment proposes only to strike language in a House bill, the test of the germaneness of a motion to recede and concur with an amendment is the relationship between the language in the motion and the provisions in the House bill proposed to be stricken by the Senate amendment. *Manual* § 931.

These principles are illustrated in the following precedents:

#### **Held Germane**

#### **Senate Amendment**

# Appropriating funds for a Senate office building extension, providing a funding ceiling on such extension, and providing for the transfer of personnel and equipment to such exten-

sion. . . .

Containing diverse provisions relating to the organization and administration of the Federal courts, including appointment of additional district and circuit judges. . . .

#### **House Amendment**

Reducing the appropriation and the funding ceiling, and providing that such extension upon completion meet certain personnel needs (96-1, Aug. 2, 1979, p 22007)

Containing comparable provisions and in addition permitting courts of appeals of a certain size to establish administrative units (Deschler-Brown Ch 28 § 27.12)

#### **Senate Amendment**

#### **House Amendment**

Appropriating funds for termination of the civil supersonic aircraft. . . .

Appropriating funds for termination of payment of the airlines' contribution to development costs (92-1, July 29, 1971, p 28053)

#### **Held Not Germane**

# **Senate Amendment**

# **House Amendment**

Prohibiting use of specified funds as compensation for certain former employees. . . .

Prohibiting use of funds in a general appropriation bill for only one basing mode for the MX missile. . . .

Providing for payment, from the Senate contingent fund, of certain additional travel expenses incurred by Senate employees. . . .

Striking a provision in a general appropriation bill that precluded the use of funds therein by the Environmental Protection Agency to control air pollution by regulating parking facilities. . . .

Appropriating funds for asbestos hazards abatement in schools. . . .

Enlarging the class of persons ineligible for such compensation (Deschler-Brown Ch 28 § 27.34)

Authorizing appropriations for research and development of another weapons system (Deschler-Brown Ch 28 § 27.19)

Providing additional travel allowances to Members of the House from the House contingent fund (Deschler-Brown Ch 28 § 27.35)

Prohibiting use of those EPA funds temporarily to implement any plan requiring the review of *any* indirect sources of air pollution (Deschler-Brown Ch 28 § 27.14)

Earmarking funds for the refinancing of a recycling program of a specified city (Deschler-Brown Ch 28 § 27.1)

# F. Procedural Matters; Points of Order

# § 36. In General

A point of order against an amendment to a proposition on germaneness grounds is generally treated the same way as other points of order. As noted earlier, the rule is not self-enforcing, and requires a Member to raise the point of order at the appropriate time. Deschler-Brown Ch 28 § 44. The pro-

ponent of the amendment bears the burden of proof that the amendment is germane to the underlying matter. 8 Cannon § 2995.

For more on points of order, including timeliness and debate thereon, see POINTS OF ORDER; PARLIAMENTARY INQUIRIES. For a discussion of special order of business resolutions, which may waive the germaneness rule or otherwise alter the normal tests of germaneness, see SPECIAL ORDERS OF BUSINESS.