

Common ADA Problems at Newly Constructed Lodging Facilities

Introduction

Hotels, motels, inns, and other places of lodging designed and constructed after January 26, 1993 must comply with the Americans with Disabilities Act (ADA). To comply with the ADA and to make it possible for persons with disabilities to use lodging facilities like everyone else, lodging facilities must meet specific requirements set out in Justice Department regulations, 28 C.F.R. pt. 36. These regulations include detailed architectural requirements known as the ADA Standards for Accessible Design (ADA Standards), 28 C.F.R. pt. 36, Appendix A. The ADA Standards are designed to make lodging facilities usable by persons with a wide variety of disabilities, including persons who are blind or who have low vision, persons who are deaf or hard of hearing, persons with mobility impairments who use wheelchairs, canes, crutches, or walkers, and persons with other disabilities or with combinations of disabilities.

The Justice Department is the government agency responsible for enforcing the ADA at lodging facilities. As part of ADA enforcement efforts, the Department has conducted numerous on-site investigations of hotels, motels, inns, and other places of lodging. During these investigations, the Department has observed certain common ADA problems at newly constructed lodging facilities. This publication describes those problems so that owners, franchisors, architects, and building contractors can avoid these common ADA mistakes and comply with the law when designing and constructing new facilities. This document is not intended to be comprehensive or exhaustive. Any failure to comply with the ADA Standards violates the ADA.

For additional information about the design and construction requirements of the ADA, contact the Department of Justice ADA Information Line. This free service provides answers to general and technical questions about ADA requirements and is a source for free ADA materials including the ADA Standards for Accessible Design, "Five Steps to Make New Lodging Facilities Comply with the ADA," and "ADA Checklist for Newly Constructed Lodging Facilities," and "Common ADA Errors and **Omissions in New Construction** and Alterations." You may reach the ADA Information Line at: 800-514-0301 (voice) or 800-514-0383 (TTY). ADA information is also available on the Department's ADA Home Page on the World Wide Web at (http://www.usdoj.gov/crt/ada/ adahom1.htm).

Reproduction of this document is encouraged. 11/99


Doors and doorways into and within <u>all</u> guestrooms and suites, including bathroom doors and doorways, do not allow 32 inches of clear opening width.


Result:

Requirements:

Doors and doorways into and within guestrooms and suites and, in particular, bathroom doors and doorways within these spaces are too narrow to allow persons who use wheelchairs, crutches, walkers, and other mobility aids to pass through them. As a result, persons with disabilities are excluded from accommodations when accessible guestrooms are sold out and also are unable to visit other guests in their rooms. All doors and doorways (except shallow closets) into and within all guestrooms and suites (including guestroom bathrooms, kitchens, and connecting room doors) shall provide 32 inches of clear opening width measured when a hinged door is open 90 degrees or a sliding door is fully opened.

ADA Standards 9.4; 4.13.5.





Measuring Clear Width

Accessible guestrooms are not dispersed among the various classes of rooms available at a lodging facility and do not provide people with disabilities the same range of amenities available to others.

Result:

Requirements:

Persons with disabilities who desire or may need different classes of accessible guestrooms are denied the range of lodging options that other guests without disabilities can take for granted (<u>e.g.</u>, rooms with one or two beds, suites). In order to provide persons with disabilities the same range of options that are available to other persons at the facility, lodging facilities must disperse accessible guestrooms/suites among the various classes of guestrooms/ suites available at the facility. Factors to be considered in dispersing accessible guestrooms among different classes of rooms include room size, cost, amenities provided (e.g., smoking and nonsmoking rooms, suites, kitchenettes, rooms with preferred views, connecting rooms), and the number of beds provided. ADA Standards 9.1.4.

Accessible Guestroom Choices	Â
Rooms with One Bed	\checkmark
Rooms with Two Beds	\checkmark
Suites	✓
Smoking and Nonsmoking Rooms	\checkmark

27 max

685

(a)

lav

Common Problem:

In hotels, motels, or other lodging facilities of 50 or more sleeping rooms, no rooms with roll-in showers are provided, or the roll-in showers that are provided lack a permanently attached fold-down seat.

Result:

30 min

36 min

716


side

Requirements:

Some people with mobility impairments, such as persons who use wheelchairs, walkers, crutches, and other mobility aids, must use a roll-in shower or a shower with a fold-down seat in order to shower. When a roll-in shower is not

> provided or when the roll-in shower lacks a folding seat, these guests may not be able to shower or may resort to using guestroom furniture in the shower.

Lodging facilities must provide a specific number of accessible guest rooms based on the table provided below. Bathing facilities in these rooms must comply with the Standards. In addition, in lodging facilities with more than 50 guestrooms or suites, the facility must provide a specified number of accessible guestrooms that have a roll-in shower with a permanently attached fold-down seat. The roll-in shower in these rooms must comply with specific requirements contained in Figure 57 of the Standards, shown on this page. ADA Standards 9.1.2; 9.2; 4.21; Figure 57(a) or (b).



60 min

1220

Fig. 57 Roll-in Shower with Folding Seat

<u>Required Accessible Guestrooms</u>
1
2
4 (1 with roll-in shower)
5 (1 with roll-in shower)
7 (2 with roll-in showers)
8 (2 with roll-in showers)
10 (3 with roll-in showers)
12 (4 with roll-in showers)
13 (4 with roll-in showers)
2% of all rooms (plus 1 room with a
roll-in shower for each 100 rooms)
20 plus 1 for each 100 over 1000
(plus 1 room with a roll-in shower
for each 100 rooms)

Accessible guestrooms and suites (and an additional number of rooms specifically for individuals who are deaf or hard of hearing) are not equipped with visual alarms and other visual notification devices.

Result:

Requirements:

People who are deaf or hard of hearing cannot hear fire alarms, ringing telephones, knocking at doors or ringing doorbells. Consequently, when accessible guestrooms and other guestrooms do not have visual fire alarms and visual notification devices, people who are deaf or hard of hearing have no notice of fires or other life-threatening emergencies and have no means of knowing when the telephone is ringing, when someone is knocking on the door, or when someone is ringing the doorbell.

All accessible guestrooms and a
specific number of additional
guestrooms for use by persons
who are deaf or hard of hearing
must be equipped with visual fire
alarm strobes that are connected
to the building's fire alarm system
and visual notification devices to
alert guests who are deaf or hard
of hearing to telephone calls and
to persons knocking on the door
and/or ringing the doorbell. While
visual alarms must be connected
to the fire alarm system,
notification devices (for doors and
telephones) may be provided in
kits available at the lodging
facility's registration desk. In
addition to accessible guestrooms,
lodging facilities must provide
additional guestrooms for persons
who are deaf or hard of hearing
following the table on this page.
ADA Standards 9.1.3; 9.2.2 (8);
9.3; 9.3.2.


<u>Total Guestrooms</u>	<u>Guestrooms for Use by Persons</u> <u>Who Are Deaf or Hard of Hearing</u> *
1 to 25	1
26 to 50	2
51 to 75	3
76 to 100	4
101 to 150	5
151 to 200	6
201 to 300	7
301 to 400	8
401 to 500	9
501 to 1000	2% of all rooms
1001 and over	20 plus 1 for each
	100 over 1000
-	s who are deaf or hard of hearing ition to accessible guestrooms.

The shape of the hardware on accessible doors, and on faucets, fixed lamps, drapery controls, and heating and air conditioning controls in spaces required to be accessible requires tight grasping, pinching, and twisting of the wrist.


Result:

Requirements:

Persons who have the use of only one hand or who have limited use of hands, wrists, or arms are unable to open doors to get into rooms, lock doors for security, use sinks or showers to wash, adjust draperies for privacy, turn on lamps, or adjust heating or air conditioning levels for comfort.



Handles, pulls, latches, locks, and other operating devices on accessible doors; faucets; fixed lamps; and drapery, heating, and air conditioning controls shall have a shape that is easy to grasp with one hand and does not require tight grasping, tight pinching, or twisting of the wrist to operate. Lever-operated mechanisms, push-type mechanisms, and U-shaped handles are acceptable designs. ADA Standards 4.13.9; 9.2.2(3); 9.2.2(5).




single-lever handle that is easy to reach and operable with one hand

For permanent rooms and spaces, identification signage is mounted in the wrong location and cannot be read by persons who are blind or have low vision.

Result:

Blind persons and persons with low vision will have difficulty locating rooms. If Braille and raised letter signs are mounted on doors instead of walls, blind persons and persons with low vision may be hurt by someone who is pushing a door open while they are trying to read a sign or they may not be able to find the sign.




Requirements:

Signs that are provided for all permanent rooms and spaces in the lodging facility must be mounted on the wall (not the door) adjacent to the latch side of the door and centered 60 inches above the floor so that they can be easily located by persons who are blind or who have low vision. Signs must include the same information in Braille, with raised lettering that forms a high contrast with the background of the sign. Signs should not be made of reflective materials such as brass, silver, gold, glass, or mirrored surfaces unless there is an additional properly located sign that complies with the Standards. ADA Standards 4.1.3(16)(a); 4.30.4; 4.30.5.

Both the exterior pedestrian routes (e.g., sidewalks, walkways and plazas) on a site that people use to travel from public transportation stops, from accessible parking spaces, from passenger loading zones, and from public streets and sidewalks to the accessible entrance(s), and the interior routes (e.g., hallways and corridors) throughout the lodging facility, are not usable by persons who use wheelchairs or other mobility aids, or who are unable to climb steps or stairs.

Result:

Because people who use wheelchairs, walkers, scooters or other mobility aids cannot climb steps or negotiate curbs, people



with disabilities are often unable to travel safely into the lodging facility from public transportation, parking lots, passenger drop-off areas, and public streets and sidewalks without using a vehicular way. Once inside the lodging facility, people with disabilities cannot get through the facility to the guestrooms,

conference rooms, toilet rooms, restaurants, or other various accessible elements and spaces.

At least one route that is a minimum of 36 inches wide without steps, stairs, or other abrupt level changes must be provided

Requirements:

At least one route that is a minimum of 36 inches wide without steps, stairs, or other abrupt level changes must be provided within the boundary of the lodging facility's property from an accessible entrance to the building to public transportation stops, accessible parking spaces, accessible passenger pick-up/ drop-off areas, if provided, and public streets or sidewalks. Once inside the facility, an accessible route must be provided between an accessible entrance, lobby and the various accessible elements and spaces in the lodging facility. ADA Standards 4.1.2 (1); 4.1.3(1); 4.3.




In areas inside and outside the lodging facility where people are expected to walk, objects protrude too far from the side, from posts, or hang down too low from overhead.

Result:

Requirements:

People who are blind or who have low vision can be seriously injured when they are unable to detect an object in their path by using the sweep of their cane.





All objects that protrude from surfaces or posts and all overhanging objects in areas where people walk shall comply with the following requirements:

Objects mounted on walls at a height above 27 inches and below 80 inches (e.g., fire extinguishers, telephones) shall protrude no more than 4 inches into walks, halls, corridors, passageways, aisles, or any other areas where a person walks.

Free-standing objects mounted on posts or pylons may not project more than 12 inches into walks, halls, corridors, passageways, aisles, or any other area where a person walks at heights between 27 inches and 80 inches above the ground or finished floor.

Stairways and escalators with undersides that are not enclosed and all objects hanging above walks, hallways, corridors, passageways, aisles, and lobbies cannot hang down below a height of 80 inches above the ground or finished floor, unless there is a cane-detectible barrier that would alert a person who is blind or who has low vision to the hazard. ADA Standards 4.1.2(3); 4.1.3(2); 4.4.


Lodging facilities with more than two floors of occupiable space -including any basement levels -- do not have full-size passenger elevators available for use by guests.

Result:

Requirements:

People with disabilities who are unable to use stairs and steps cannot gain access to floors above and below the ground level and, in many instances, do not have access to the amenities provided in the lodging facility. At least one passenger elevator must serve each level of a facility that has more than two floors of occupiable space, including basement levels. If a facility has less than 3,000 square feet per floor, an elevator exemption applies. All passenger elevators must meet the requirements of the Standards.


ADA Standards 4.1.3(5); 4.10.



There are an insufficient number of accessible parking spaces provided, including van-accessible parking spaces, in the proper locations.

Result:

Persons with disabilities are unable to park their vehicles and do not have convenient access to



the lodging facility. Persons who use vans equipped with a wheelchair lift have inadequate space to lower the lift and exit the vehicle.

<u>Total Spaces in</u>	<u>Required Number of Accessible</u>
Parking Lot	Parking Spaces
1 to 25	1 van space
26 to 50	1 standard space + 1 van space
51 to 75	2 standard spaces + 1 van space
76 to 100	3 standard spaces + 1 van space
101 to 150	4 standard spaces + 1 van space
151 to 200	5 standard spaces + 1 van space
201 to 300	6 standard spaces + 1 van space
301 to 400	7 standard spaces + 1 van space
401 to 500	7 standard spaces + 2 van spaces
501 to 1000	2 % of total spaces; 1 in every 8
	accessible spaces must be van-
	accessible
1001 and over	20 + 1 extra space for each hundred
	spaces over 1000; 1 in every 8
	accessible spaces must be
	van-accessible

Requirements:

When a lodging facility offers "self-parking," it must have the proper number of standard accessible parking spaces and van-accessible parking spaces as shown in the table below. Standard accessible parking spaces must be at least 8 feet wide and have or share an access aisle that is at least 5 feet wide. Van-accessible spaces must be at least 8 feet wide and have or share an access aisle that is at least 8 feet wide. The vertical clearance for van accessible parking spaces shall be at least 98 inches. The surface of all standard accessible parking spaces and all van-accessible parking spaces should be level (i.e., no greater than 1:50 or 2%). Accessible parking spaces should be dispersed so that some of those spaces are the nearest to the lobby and others are the nearest spaces to accessible entrances that serve accessible guestrooms. All accessible spaces in a parking garage may be grouped on one level of the structure. All accessible parking spaces must have signs with the international symbol of accessibility that are mounted high enough so that they are not obscured by parked cars. ADA Standards 4.1.2 (5); 4.6.2; 4.6.3; 4.6.4.