

Authorized <u>GOGGLES</u>	Unit of Issue	Manufacturer's Part Number	NSN
ESS Profile NVG Goggle Kit, Foliage Green 504, NSLIN HA4064	1 each	EP01FG1-MSB	4240-01-540-5585
ESS Profile NVG Goggle Kit, Black, NSLIN HA4064	1 each	EP01BK1-TSB	4240-01-504-6222
ESS Profile NVG Goggle Kit, Desert Tan, NSLIN HA4064	1 each	EP01DT1-MSB	4240-01-504-5727
Replacement Frame, Foliage Green 504, ESS Profile NVG	1 each	740-0464	4240-01-587-7565
Replacement Frame, Black, ESS Profile NVG	1 each	740-0465	4240-01-586-7520
Replacement Lens, Clear, ESS Profile NVG	1 each	740-0113	4240-01-587-8420
Replacement Lens, Gray, ESS Profile NVG	1 each	740-0119	4240-01-587-7640
Replacement Lenses, Clear, ESS Profile NVG	Package of 50	PR1C-50	4240-01-504-5641
Replacement Lenses, Gray, ESS Profile NVG	Package of 50	PR1Y-50	4240-01-504-6143
Anti-Fog Cloths, ESS Profile NVG	Package of 25	740-0209	4240-01-525-5107
U-Rx Prescription Lens Carrier, Compatible with ESS Profile NVG Goggle, ESS Crossbow Spectacle and Oakley SI Ballistics M Frame 2.0 Spectacle	1 Each	740-0411	<b>6540-01-584-0170</b>
U-Rx Prescription Lens Carriers, Compatible with ESS Profile NVG Goggle, ESS Crossbow Spectacle and Oakley SI Ballistics M Frame 2.0 Spectacle	Package of 25	740-0444	<b>6540-01-584-0176</b>



The ESS Profile NVG protective Goggle consists of an injection molded rubber frame (one size) with interchangeable polycarbonate lenses. The frame is lined with a foam backing for improved comfort where it contacts the face. Foam covered venting around the periphery provides ventilation while keeping sand/dust out. The ESS Profile NVG Goggle weighs 4.4 ounces. All lenses have been treated with a hard-coat on the exterior surface to reduce scratching and an anti-fog coating on the interior surface to reduce fogging. The anti-reflective sleeve reduces glint when the goggle is not in use. The ESS Profile NVG provides ballistic-fragmentation protection, and meets all ANSI Z87.1-2003 optical and safety requirements. The lens material blocks 99.9% of all UVA and UVB light. An optional prescription lens carrier is available for those who require corrective lenses.

**WARNING:** Use of prescription lens configurations not listed on the Authorized Protective Eyewear List (APEL) for a specific APEL spectacle or goggle may result in serious injury. We strongly recommend that Soldiers use Army optometry clinics to obtain prescription (Rx) correction for APEL products approved for this purpose. Rx correction is available through garrison and deployed optometry clinics at no cost to the Soldier. All APEL approved Rx configurations have been subjected to ballistic fragmentation testing for safety. Offers by vendors for unapproved Rx products via vendor website and/or through conferences should be avoided, as these items may not be safe or operationally suitable for use in a field environment.