Authorized GOGGLES	Unit of Issue	Manufacturer's Part Number	NSN
Revision Desert Locust Goggle Kit, Foliage Green, NSLIN HA4078	1 each	4-0309-9510	4240-01-547-6218
Revision Desert Locust Goggle Kit, Tan 499, NSLIN HA4078	1 each	4-0309-9524	4240-01-592-8619
Revision Desert Locust Goggle Kit, Black, NSLIN HA4078	1 each	4-0309-9500	4240-01-547-6227
Replacement Frame, Foliage Green 504, Revision Desert Locust	1 each	4-0647-9200	4240-01-587-8475
Replacement Frame, Tan 499, Revision Desert Locust	1 each	4-0647-9400	4240-01-592-8625
Replacement Frame, Black, Revision Desert Locust	1 each	4-0647-9100	4240-01-587-8477
Replacement Lens, Clear, Revision Desert Locust	1 each	4-0331-9101	4240-01-588-3259
Replacement Lens, Gray, Revision Desert Locust	1 each	4-0331-9202	4240-01-588-3254
Replacement Lenses, Clear, Revision Desert Locust	Package of 10	4-0331-9100	4240-01-547-6568
Replacement Lenses, Gray, Revision Desert Locust	Package of 10	4-0331-9200	4240-01-547-6567
Anti-Fog Cloths, Revision Desert Locust	Package of 10	4-0330-9001	4240-01-571-3625
Prescription Carrier Insert with goggle connector (fits the Desert Locust Goggle, when used with goggle connector, and fits the Revision Sawfly Spectacle)	Package of 10	4-0133-9100	6540-01-527-4056



The Revision Desert Locust protective goggle consists of an injection molded rubber frame (one size) with interchangeable polycarbonate lenses. The face seal likewise consists of injection molded rubber for a low profile fit against the face and to facilitate ease of cleaning/sanitation. Foam covered venting around the periphery provides ventilation while keeping sand/dust out. The Revision Desert Locust Goggle's weighs 4.3 ounces. All lenses have been treated with a combination anti-scratch/ anti-fog coating to minimize scratching and fogging. The anti-reflective sleeve reduces glint when the goggle is not in use The Desert Locust provides ballistic-fragmentation protection, and meets ANSI Z87.1-2003 optical and safety requirements. The lens material blocks 99.9% of all UVA and UVB light. An optional prescription lens carrier is available for those who require corrective lenses.

WARNING: Use of prescription lens configurations not listed on the Authorized Protective Eyewear List (APEL) for a specific APEL spectacle or goggle may result in serious injury. We strongly recommend that Soldiers use Army optometry clinics to obtain prescription (Rx) correction for APEL products approved for this purpose. Rx correction is available through garrison and deployed optometry clinics at no cost to the Soldier. All APEL approved Rx configurations have been subjected to ballistic fragmentation testing for safety. Offers by vendors for unapproved Rx products via vendor website and/or through conferences should be avoided, as these items may not be safe or operationally suitable for use in a field environment.